



Specialists in Explosives, Blasting and Vibration  
Consulting Engineers

Blast Impact Analysis  
Proposed West Carleton Quarry Extension Quarry  
Part of Lot 15, Concession 11, former geographic township of  
Huntley, City of Ottawa

**Submitted to:**

Thomas Cavanagh Construction Limited  
9094 Cavanagh Road  
Ashton, Ontario  
K0A 1B0

**Prepared by:**

Mark Morelli, B.Eng.  
Explotech Engineering Ltd.

Rob Cyr, P. Eng.  
Explotech Engineering Ltd.



**August 12, 2021**



## **EXECUTIVE SUMMARY**

ExploTech Engineering Ltd. was retained in November 2020 to provide a Blast Impact Analysis for the proposed Cavanagh West Carleton Quarry Extension operation located on Part of Lot 15, Concession 11, former geographic township of Huntley, City of Ottawa.

Vibration levels assessed in this report are based on the Ministry of the Environment, Conservation and Parks Model Municipal Noise Control By-law (NPC 119) with regard to guidelines for blasting in Mines and Quarries. We have assessed the area surrounding the proposed license area with regard to potential damage from blasting operations and compliance with the aforementioned by-law document. In addition, we have reviewed blast and vibration reports collected at the existing licenced quarry for the 2017 - 2020 blasting campaigns.

We have inspected the site and reviewed the available site plans. ExploTech Engineering Ltd. is of the opinion that the planned mineral extraction extension on the site can be carried out safely and within Ministry of the Environment, Conservation and Parks guidelines as set out in NPC 119 of the By-Law.

Recommendations are included in this report for blasting operations to be carried out in a safe and productive manner and to suitably manage and mitigate the possibility of damage to any buildings, wells, structures or residences surrounding the property.



## TABLE OF CONTENTS

INTRODUCTION .....	3
EXISTING CONDITIONS .....	4
PROPOSED MINERAL EXTRACTION.....	6
BLAST VIBRATION AND OVERPRESSURE LIMITS.....	7
BLAST MECHANICS AND DERIVATIVES .....	8
VIBRATION AND OVERPRESSURE THEORY .....	9
GROUND VIBRATION AND OVERPRESSURE ATTENUATION STUDY.....	10
VIBRATION LEVELS AT THE NEAREST SENSITIVE RECEPTOR .....	11
OVERPRESSURE LEVELS AT THE NEAREST SENSITIVE RECEPTOR .....	14
ADDITIONAL CONSIDERATIONS OUTSIDE OF THE BLAST IMPACT	
ANALYSIS SCOPE.....	16
FLYROCK .....	16
THEORETICAL HORIZONTAL FLYROCK CALCULATIONS .....	16
RESIDENTIAL WATER WELLS .....	20
REVIEW OF HISTORICAL WEST CARLETON QUARRY DATA .....	22
RECOMMENDATIONS .....	23
CONCLUSION .....	25

APPENDIX A – SEQUENCE OF OPERATIONS PLAN  
SENSITIVE RECEPTOR OVERVIEWS

APPENDIX B – METEOROLOGICAL CONDITIONS

APPENDIX C – ATTENUATION RESULTS  
– HISTORICAL BLAST SUMMARY DATA 2017 – 2020 (individual  
blast record data is kept on-file at Cavanagh)

APPENDIX D – CURRICULUM VITAE OF REPORT WRITERS

APPENDIX E – BLASTING TERMS & DEFINITIONS  
REFERENCES



## **INTRODUCTION**

The proposed West Carleton Quarry Extension operation is located on the West side of the existing licensed and operating West Carleton Quarry (Licence 4085). The legal description for the subject property is Part of Lot 15, Concession 11, former geographic township of Huntley, City of Ottawa.

This Blast Impact Analysis is based on the Ministry of the Environment, Conservation and Parks (MECP) Model Municipal Noise Control By-law (NPC 119) with regard to guidelines for blasting in mines and quarries. We have additionally assessed the area surrounding the proposed license with regard to potential damage from blasting operations.

Given that quarry operations are currently underway on the adjacent Cavanagh licenced property and all blasts conducted are monitored for ground vibrations and overpressure, site-specific blast monitoring data is available for the area. The site specific data has been incorporated into this assessment. It is a recommendation of this report that a vibration monitoring program be continued on this site, including within the proposed West Carleton Quarry Extension lands, and that the program be maintained for the duration of all blasting activities to permit timely adjustment to blast parameters as required.

While not specifically required as part of the required scope of the Blast Impact Analysis under the Aggregate Resources Act, this report reviews the topics of flyrock and residential water wells. Details related to residential water wells are addressed in the hydrogeological report prepared by Golder Associates while specific flyrock control is addressed at the operational level by Cavanagh given significant influences related to blast design, geology and field accuracy.

Recommendations are included in this report for blasting operations to be carried out in a safe and productive manner and to suitably manage and mitigate the possibility of damage to any buildings, wells, structures or residences surrounding the property.



## **EXISTING CONDITIONS**

The existing licensed area for the West Carleton Quarry (Licence 4085) is described as Lot 14 and part of lot 15, Concession 11, former geographic township of Huntley, City of Ottawa. This property is bound by March Road to the North, Upper Dwyer Hill Road to the East and vacant forested lands to the South and West. The lands surrounding the licence are sparsely populated with the areas of closest and densest development lying immediately to the North / Northwest.

The licenced area for the proposed West Carleton Quarry Extension lands encompasses a total area of approximately 18.2HA. The associated extraction area is approximately 16.5HA when allowing for setbacks and sterilized areas.

The proposed West Carleton Quarry Extension is located immediately West of the existing licence Lot 14 and part of lot 15, Concession 11, former geographic township of Huntley, City of Ottawa. The extension lands are bound by vacant lands to the West and South, the existing West Carleton Quarry to the East, and March Road to the North with properties located along Burnt Lands Road to the Northwest. The closest sensitive receptors surrounding the proposed limit of extraction are listed in Table 1 below as well as in the Sensitive Receptor Overview contained in Appendix A:

<b>Sensitive Receptor Address</b>	<b>Sensitive Receptor or Non Sensitive Receptor</b>	<b>Distance to Receptor (m)</b>	<b>Direction from Extraction Limits</b>
1616 Burnt Lands Road	Sensitive	135	Northwest
1644 Burnt Lands Road	Sensitive	305	Northwest
1654 Burnt Lands Road	Sensitive	385	Northwest
1674 Burnt Lands Road	Sensitive	480	Northwest
1692 Burnt Lands Road	Sensitive	585	Northwest
1720 Burnt Lands Road	Sensitive	705	Northwest
1730 Burnt Lands Road	Sensitive	820	Northwest
4061 March Road	Sensitive	420	North
4512 March Road	Sensitive	1255	West
1331 Upper Dwyer Hill Road	Sensitive	1375	East
1486 Upper Dwyer Hill Road	Sensitive	1550	Northeast
1550 Upper Dwyer Hill Road	Sensitive	1080	Northeast
1661 Upper Dwyer Hill Road	Sensitive	975	North
1350 Golden Line Road	Sensitive	1435	Southwest



Sensitive Receptor Address	Sensitive Receptor or Non Sensitive Receptor	Distance to Receptor (m)	Direction from Extraction Limits
1491 Golden Line Road	Sensitive	1270	Southwest
1509 Golden Line Road	Sensitive	1260	Southwest

**Table 1: Closest Sensitive Receptors**



## **PROPOSED MINERAL EXTRACTION**

As per the November 2020 Extraction Plan (Refer to Appendix A), the proposed initial quarry operations will commence on the Northeast face or Southeast face of the proposed extension licence extraction limit and will retreat Southwesterly and Northwesterly respectively across the extension lands. This will eliminate the need for a sinking cut and provide the maximum distance separation to neighbouring receptors. It is a recommendation of this report to initiate extraction operations at the Southeast corner of the extension extraction limits and retreat in an echelon pattern towards the Northwest corner to both direct all overpressures away from sensitive receptors along March Road and provide the maximum distance separation to neighbouring receptors for the initial operations. Alternatively, in the event that the rock in the existing licence adjacent the Southeast face has not been extracted prior to entering into the proposed licence, a slot could be advanced starting near the Southeast corner of the Northwest face, retreating in a Southwest direction before turning the face 90 degrees and retreat northwesterly as shown on the operational plan attached in Appendix A.

Bedrock will be extracted to a final floor elevation of 107masl. Given existing topography of approximately 153masl, it is anticipated that the extraction will take place in up to 5 benches. The approximate floor elevations for each respective bench is anticipated to be 142masl, 134masl, 125masl, 116masl and 107masl, respectively.

As quarry operations migrate across the property, the closest sensitive receptors to the required blasting operations will vary. While recommended initial mineral extraction in the proposed licence area will occur approximately 725m from the closest sensitive receptors to the blast location, the quarry face along the Northwest limits of extraction will come within 135m of the closest property located on Burnt Lands Road, namely 1616 Burnt Lands Road (Refer to Table 1 above).

Current practice at the Cavanagh West Carleton Quarry operation employs 101mm diameter blast holes with a typical load per delay of between 65Kg - 100kg based on an 8m – 10m bench height. While current practices would be acceptable for the initial blasting in the extension area, calculations contained within this report suggest modifications to current blast designs will be necessary as operations progress towards adjacent receptors. Fortunately, given advanced initial separation distances between blasting operations and neighbouring receptors, there exists ample opportunity for data collection and analysis prior to any required blasting in closer proximity to the adjacent homes.



## **BLAST VIBRATION AND OVERPRESSURE LIMITS**

The Ontario MECP guidelines for blasting in quarries are among the most stringent in North America.

Studies by the U.S. Bureau of Mines have shown that normal temperature and humidity changes can cause more damage to residences than blast vibrations and overpressure in the range permitted by the MECP. The limits suggested by the MECP are as follows.

**Vibration**\_\_\_\_\_ 12.5mm/s                      Peak Particle Velocity (PPV)

**Overpressure**\_\_\_\_\_ 128dB                      Peak Sound Pressure Level (PSPL)

The above guidelines apply when blasts are being monitored. Cautionary levels are slightly lower and apply when blasts are not monitored on a routine basis. It is a recommendation of this report that all blasts at the operation be monitored to quantify and record ground vibration and overpressure levels employing a minimum of two (2) digital seismographs, one installed at the closest receptor behind the blast, or closer, and one installed at the closest receptor in front of the blast, or closer.





## **BLAST MECHANICS AND DERIVATIVES**

The detonation of explosives within a blast hole results in the development of very high gas and shock pressures. This energy is transmitted to the surrounding rock mass, crushing the rock immediately surrounding the borehole (approximately 1 borehole radius) and permanently distorts the rock to several borehole diameters (5-25, depending on the rock type, prevalence of joint sets, etc).

The intensity of this stress wave decays quickly so that there is no further permanent deformation of the rock mass. The remaining energy from the detonation travels through the unbroken material in the form of a pressure wave or shock front which, although it causes no plastic deformation of the rock mass, is transmitted in the form of vibrations.

Particle velocity is the descriptor of choice when dealing with vibrations because of its superior correlation with the appearance of cosmetic cracking. As such, for the purposes this report, ground vibration units have been listed in mm/s.

In addition to the ground vibrations, overpressure, or air vibrations, are generated through the direct action of the explosive venting through cracks in the rock or through the indirect action of the rock movement. In either case, the result is a pressure wave which travels through the air, measured in linear decibels (or dBL) for the purposes of this report.



## **VIBRATION AND OVERPRESSURE THEORY**

Transmission and decay of vibrations and overpressure can be estimated by the development of attenuation relations. These relations utilize empirical data relating measured velocities at specific separation distances from the vibration source to predict particle velocities at variable distances from the source. While the resultant prediction equations are reliable, divergence of data occurs as a result of a wide variety of variables, most notably site-specific geological conditions and blast geometry and design for ground vibrations and local prevailing climatic conditions for overpressure.

In order to circumvent this scatter and improve confidence in forecast vibration levels, probabilistic and statistical modeling is employed to increase conservatism built into prediction models, usually by the application of 95% confidence lines to attenuation data.

The attenuation relations are not designed to conclusively predict vibration levels at a specific location as a result of a specific blast design, application of this probabilistic model creates confidence that for any given scaled distance, 95% of the resultant velocities will fall below the calculated 95% regression line.

While the data still provides insight into probable vibration intensities, attenuation relations for overpressure tends to be less reliable and precise than results for ground vibrations. This is due primarily to wider variations in variables outside of the influence of the blast design which impact propagation of the vibrations. Atmospheric factors such as temperature gradients and prevailing winds (refer to Appendix B) as well as local topography can all serve to significantly alter overpressure attenuation characteristics.

Our experience and analysis demonstrates that blast overpressure is greatest when blasting towards receptors, and blast vibrations are greatest when retreating towards the receptors.



## **GROUND VIBRATION AND OVERPRESSURE ATTENUATION STUDY**

A comprehensive network of seismographs was installed by Explotech to measure ground vibration and air overpressure intensities for three (3) blasts conducted in April 2021 and July 2021 at the existing West Carleton Quarry in Ottawa, Ontario. Monitor locations were established in linear arrays emanating from the blast site to assess the rate of decay of the ground vibration and overpressure. All ground vibration data was plotted using square root scaling from blast vibration data collected (refer to Appendix C). Overpressure data was plotted employing cube root scaling (refer to Appendix C).

It should again be noted that given the high dependence on local environmental conditions, overpressure prediction is far less reliable as a means of blast control.

# EXPLOTECH

## VIBRATION LEVELS AT THE NEAREST SENSITIVE RECEPTOR

The most commonly used formula for predicting PPV is known as the Bureau of Mines (BOM) prediction formula or Propagation Law. We have used this formula to predict the PPV's at the closest house for the initial operations.

$$PPV = k \left( \frac{d}{\sqrt{w}} \right)^e$$

Where, PPV = the predicted peak particle velocity (mm/s)

K, e = site factors

d = distance from receptor (m)

w = maximum explosive charge per delay (kg)

The value of K and e are variable and influenced by many factors (i.e. rock type, geology, thickness of overburden, etc.). As such, these site factors are developed empirically through the measurement of vibration characteristics at the specific operations of interested.

Based on the vibration data collected from the April 2021 and July 2021 attenuation study, the values for “e” and “K” have been established at -1.683 and 3507.6 respectively for receptors falling behind the blast at the West Carleton Quarry site.

For a distance of 725m (the standoff distance to the closest sensitive receptor behind the blast for the initial blasting, namely 1616 Burnt Lands Road) and a maximum explosive load per delay of 80kg (101mm diameter hole, 10m deep, 2m surface collar and 1 hole per delay), we can calculate the maximum PPV as follows:

$$PPV = 3507.6 \left( \frac{725}{\sqrt{80}} \right)^{-1.683} = 2.15 \text{ mm/s}$$

The calculated PPV based on the blast discussed above would be 2.15mm/s.

As discussed in previous sections, the MECP guideline for blast-induced vibration is 12.5 mm/s (0.5 in/s). The calculated 95% predicted PPV (based on the standoff distance to the closest sensitive receptor for the initial blasting) would be 2.15mm/s, below the MECP guideline limit. It is understood that as separation distance to receptors decreases, adjustments to blast designs may be necessary to maintain compliance with the guideline limits.

Similarly, the above equation used to calculate PPV can be reformatted to find an approximation of the distance at which a vibration velocity of 12.5mm/s would occur at a receptor behind the blast if all blasting parameters are kept the same as used in the example above:

$$12.5 = 3507.6 \left( \frac{d}{\sqrt{80}} \right)^{-1.683} = 254.77m$$

The above result suggests that design modifications to the above preliminary design would be required once blasting operations encroach to within 255m of sensitive receptors surrounding the quarry extraction operations. Fortunately, vibration data will be continually collected and analyzed as part of the Compliance Monitoring Program as the sensitive receptors are approached in order to confirm the requirement for any design modifications. An abundance of design modifications are available which would readily maintain vibration intensities below guideline limits.

Given the separation distances that will be involved at the West Carleton Quarry Extension, Table 2 below provides initial guidance on maximum loads per delay based on various separation distances. The following maximum loads per delay were derived from the equation developed through the April 2021 and July 2021 attenuation study and are based on a maximum intensity of 12.5mm/s:

<b>TABLE 2</b> <b>Maximum Loads per Delay to Maintain 12.5mm/s at Various Separation Distances</b>	
<b>Separation distance between sensitive receptor and closest borehole (meters)</b>	<b>Maximum recommended explosive load per delay (Kilograms)</b>
500	308
450	249
400	197
350	150
300	110
250	77
200	49
150	27
135	23

# EXPLOTECH

It is noteworthy that the above values are typically conservative and are intended as a guideline only as the ground vibration attenuation equation is based on a calculated 95% regression line. Actual loads employed shall be based on the results of the monitoring program in place and adjusted as necessary.

The closest separation distance between a sensitive receptor and any blast over the life of the license is 135m. While blasting at this separation distance is feasible from a technical perspective, given current blasting technology and techniques, market economics will dictate the feasibility of extracting rock at lesser separation distances. Monitoring and changes in blasting designs will be required in order to confirm all blasts are within MECP guidelines when blasting comes closer to adjacent sensitive receptors.

## OVERPRESSURE LEVELS AT THE NEAREST SENSITIVE RECEPTOR

It is unusual for overpressure to reach damaging levels, and when it does, the evidence is immediate and obvious in the form of broken windows in the area. However, overpressure remains of interest due to its ability to travel further distances as well as cause audible sounds and excitation in windows and walls.

Air overpressure decays in a known manner in a uniform atmosphere, however, a uniform atmosphere is not a normal condition. As such, air overpressure attenuation is far more variable due to its intimate relationship with environmental influences. Air vibrations decay slower than ground vibrations with an average decay rate of 6dB for every doubling of distance.

Air overpressure levels are analyzed using cube root scaling based on the following equation:

$$P = k \left( \frac{d}{\sqrt[3]{w}} \right)^e$$

Where, P = the peak overpressure level (psi – imperial, Pa, dB - metric)  
K, e = site factors  
d = distance from receptor (ft – imperial, m - metric)  
w = maximum explosive charge per delay (lbs – imperial, kg - metric)

The value of K and e are variable and are influenced by many factors (i.e. rock type, geology, thickness of overburden, environmental conditions at the time of a blast, etc.). As such, these site factors are developed empirically through the measurement of overpressure characteristics at the specific operations of interest.

Based on the overpressure data collected from the April 2021 and July 2021 attenuation study, the values for “e” and “K” have been established at -0.102 and 224.3 respectively for receptors falling in front of the blast at the West Carleton Quarry site.

As discussed in previous sections, the MECP guideline for blast-induced overpressure is 128dB. For a distance of 1100m (i.e. the standoff distance to the closest sensitive receptor in front of the blast for the initial blasting, namely 1550 Upper Dwyer Hill Road) and a maximum explosive load of 80kg (101mm diameter hole, 10m deep, 2m surface collar and 1 hole per delay), we can

# EXPLOTECH

calculate the maximum overpressure at the nearest receptor in front of the blast as follows:

$$P = 224.3 \left( \frac{1100}{\sqrt[3]{80}} \right)^{-0.102} = 127.44 \text{dB(L)}$$

We reiterate that air overpressure attenuation is far more variable due to its intimate relationship with environmental influences and as such, the equation employed is less reliable than that developed for ground vibration. Overpressure monitoring performed on site shall be used to guide blast design as it pertains to the control of blast overpressures. As demonstrated in Appendix B, prevailing winds during quarry operational periods are predominantly out of the South and West, a condition which will assist in attenuating overpressures at the receptors in front of the blasting throughout the phasing of the extension licence.

Given the intimate correlation between overpressure and environmental conditions as stated previously, care must be taken to avoid blasting on days when weather patterns are less favourable. Extraction directions have been selected so as to minimize overpressure impacts on adjacent receptors. Table 3 below can be used as an initial guide showing maximum loads per delay based on various separation distances for receptors in front of the blast face. The following maximum loads per delay are derived from the air overpressure equation above and are based on a peak overpressure level of 128dB(L):

<b>TABLE 3</b> <b>Maximum Loads per Delay to Maintain 128dB(L) at Various Separation Distances for Receptors in Front of the Face</b>	
<b>Separation distance between sensitive receptor and closest blasthole (meters)</b>	<b>Maximum recommended explosive load per delay (Kilograms)</b>
1100	91
1000	68
900	49
800	35
700	23
600	14
500	8

We note that the above values are conservative and are intended as a guideline only as the air overpressure attenuation equation is based on a calculated 95% regression line. Actual loads employed shall be based on the results of the monitoring program in place.





## **ADDITIONAL CONSIDERATIONS OUTSIDE OF THE BLAST IMPACT ANALYSIS SCOPE**

The following headings are addressed for general information purposes and are not strictly required as part of the scope of the Blast Impact Analysis as required under the ARA to ensure compliance with MECP NPC-119 guidelines. The hydrogeological study prepared by Golder Associates as part of the licence application will address residential water wells in detail. Flyrock control is addressed at the operational level given significant influences related to blast design, geology and field accuracy which render concrete recommendations related to control inappropriate at the licencing phase.

### **FLYROCK**

Flyrock is the term used to define rocks which are propelled from the blast area by the force of the explosion. This action is a predictable and necessary component of a blast and requires that every blast have an exclusion zone established within which no persons or property which may be harmed are permitted.

Government regulations strictly prohibit the ejection of flyrock off of a quarry property. The regulations regarding flyrock are enforced by the Ministries of Natural Resources and Forestry, Environment, Conservation and Parks and Labour. In the event of an incident where flyrock does leave a site, the punitive measures include suspension / revocation of licences and fines to both the blaster and quarry owner / operator. Fortunately, flyrock incidents are extremely rare due to the prevalence of professionally designed and implemented blasting programs as well as rigorous prosecution of such events. It is in the best interest of all, stakeholders and non-stakeholders, to ensure that dangerous flyrock does not occur. Through proper blast planning and design, it is possible to control and mitigate the possibility for flyrock.

### **THEORETICAL HORIZONTAL FLYROCK CALCULATIONS**

Flyrock occurs when explosives in a hole are poorly confined by the stemming or rock mass and the high pressure gas breaks out of confinement and launches rock fragments into the air. The three primary sources of fly rock are as follows:

- **Face burst:** Lack of confinement by the rock mass in front of the blast hole results in fly rock in front of the face.

# EXPLOTECH

- **Cratering:** Insufficient stemming height or weakened collar rock results in a crater being formed around the hole collar with rock projected in any direction.
- **Stemming Ejection:** Poor stemming practice can result in a high angle throw of the stemming material and loose rocks in the blasthole wall and collar.

The horizontal distance flyrock can be thrown ( $L_H$ ) from a blast hole is determined using the expression:

$$L_H = \frac{V_o^2 \sin 2\theta_0}{g} \quad [1]$$

where:

$V_o$  = launch velocity (m/s)

$\theta_0$  = launch angle (degrees)

$g$  = gravitational constant (9.8 m/s<sup>2</sup>)

The theoretical maximum horizontal distance fly rock will travel occurs when  $\theta_0 = 45$  degrees, thereby yielding the equation:

$$L_{H \max} = \frac{V_o^2}{g} \quad [2]$$

The normal range of launch velocity for blasting is between 10m/s - 30m/s. To calculate the launch velocity of a blast the following formula is used:

$$V_o = k \left( \frac{\sqrt{m}}{B} \right)^{1.3} \quad [3]$$

where:

$k$  = a constant

$m$  = charge mass per meter (kg/m)

$B$  = burden (m)

# EXPLOTECH

By combining equations 2 and 3 and taking into account the different sources of fly rock, the following equations can be used to calculate the maximum fly rock thrown from a blast:

Face burst: 
$$L_{H \max} = \frac{k^2}{g} * \left( \frac{\sqrt{m}}{B} \right)^{2.6}$$

Cratering: 
$$L_{H \max} = \frac{k^2}{g} * \left( \frac{\sqrt{m}}{SH} \right)^{2.6}$$

Stemming Ejection: 
$$L_{H \max} = \frac{k^2}{g} * \left( \frac{\sqrt{m}}{SH} \right)^{2.6} \sin 2\theta$$

where:  $\theta$  = drill hole angle  
 $L_{h\max}$  = maximum flyrock throw (m)  
 $m$  = charge mass per meter (kg/m)  
 $B$  = burden (m)  
 $SH$  = stemming height (m)  
 $g$  = gravitational constant  
 $k$  = a constant

For flyrock calculation purposes, we have applied the current blasting parameters used in the West Carleton Quarry which utilize 101mm (4") diameter holes on a 3.0m x 3.0m (10'x 10') pattern, with total depths of up to 10m (33') and a collar length of 2m (6.5').

The range for the constant  $k$  is 13.5 for soft rocks and 27 for hard rocks. Given the proposed licence area is predominantly limestone, we have applied a  $k$  value of 21. The explosive density is assigned to be 1.2 g/cc for emulsion products and the drill hole angles are assumed to be 90 degrees (i.e. vertical).

Based on a free face blast, maximum anticipated horizontal flyrock projection distances are calculated as follows in Table 4:

<b>Table 4 – Maximum Flyrock Horizontal</b>		
<b>Collar Lengths</b> (m)	<b>Maximum Throw Face Burst</b> (m)	<b>Maximum Throw Cratering and Stemming Ejection</b> (m)
1.5	48	302
2.0	48	143
2.5	48	80
3.0	48	50
3.5	48	33

Different collar lengths are displayed in the table above to account for over or under loaded holes. As demonstrated with these various collar lengths, any deviation, no matter how slight, can greatly affect these maximum values. The current proposed initial blasting parameters have the potential to send flyrock 143m assuming all holes achieve the designed collar lengths of 2.0m. Blast mats or sand can be placed on top of the shot to further reduce the distance for potential flyrock.

Through proper blast design and diligence in inspecting the geology before every blast, flyrock can readily be maintained within the quarry limits. It may be necessary to increase collars and adjust designs accordingly when blasting along the perimeter to accommodate the reduced distance to receptors and to ensure flyrock remains within the property limit. The operational plan for the quarry has been designed to retreat towards the closest receptors thereby projecting flyrock and overpressures away from the receptors.



## **RESIDENTIAL WATER WELLS**

Possible impacts to the water quality and production capacity of groundwater supply wells is a common concern for residents near blasting operations. Complaints related to changes in water quality often include the appearance of turbidity, water discolouration and changes in water. Complaints regarding water production most often involve loss of quantity production, air in water and damage to well screens and casings. A review of research and common causes of these problems indicates that most of these concerns are not related to blasting and can be shown to be the direct impact of environmental factors and poor well construction and maintenance.

There is an intuitive belief that blasting operations have dramatic and disastrous impacts on residential water wells for large distances around such operations. However, there is no scientific basis for such claims. Outside of the immediate radius of approximately 20-25 blasthole diameters from a loaded hole, there is no permanent ground displacement. As such, barring blasting activity within several meters of an existing well, the probability of damage to residential wells is essentially non-existent.

Despite the scientific support for the above conclusion, numerous studies have been performed to verify the validity of this statement. These studies have investigated the effects of blasting on varied well configurations and in varied geological mediums to ensure results could be readily extrapolated to all blasting operations. The conclusion of these studies has confirmed that with the exception of possible temporary increases in turbidity, blasting operations did not result in any permanent impact on wells outside of the immediate blast zone of the blast until vibrations levels reached exceedingly high intensities. Applying universally accepted threshold levels for ground vibrations eliminates the possibility for any long term adverse effects on wells in the vicinity of blasting operations.

In a study by Froedge (1983), blast vibration levels of up to 32.3mm/s were recorded at the bottom of a shallow well located at a distance of 60 meters (200 feet) from an open pit blast. There was no report of visible damage to the well nor was there any change in the water pumping flow rate. This study concluded that the commonly accepted limit of 50mm/s PPV level is adequate to protect wells from any damage. We reiterate, the current guideline limit for vibrations from quarry and mining operations is 12.5mm/s.

# EXPLOTECH

Rose et al. (1991) studied the effect of blasting in close proximity to water wells near an open pit mine in Nevada, USA. Blasts of up to 70 kilograms of explosives per delay period were detonated at a distance of 75 meters (245 feet) from a deep water well. There was no reported visible damage to the well. Fluctuations in water level and flow rate were evident immediately after the blast. However, the well water level and flow rate quickly stabilized.

The U.S. Bureau of Mines conducted a study (Robertson et al., 1990) to determine the changes in well capacity and water quality. This involved pumping from wells before and after nearby blasting. One experiment with a well in sandstone showed no change in well capacity after blasts induced PPV's at the surface of 84mm/s and there was no change in water level after PPV's of 141mm/s, well above the current guideline limit of 12.5mm/s.

Matheson et al. (1997) brought together available information on the most common complaints, the possible causes of the complaints and the relation between blasting and the complaint causes. This study yet again reaffirmed the fact that the attribution of well problems to blast sources are unfounded.

The MECP vibration limit of 12.5mm/s effectively excludes any possibility of damage to residential water wells. Based on available research and our extensive experience in Ontario quarry blasting, blasting at the West Carleton Quarry will induce no permanent adverse impacts on the residential water wells on properties surrounding the site.



## **REVIEW OF HISTORICAL WEST CARLETON QUARRY DATA**

A vibration and overpressure monitoring program has been in place for all blasts conducted at the Cavanagh West Carleton Quarry in recent years. As part of this analysis, Cavanagh has provided copies of vibration data summaries collected from 2017 – 2020. For continuity, summaries of the historical data collected and supplied by Cavanagh are included in Appendix C to this report.

### **2017 – 2020 DATA**

Vibration monitoring conducted from 2017 – 2020 has included the installation of seismographs at the following locations:

- 1331 Dwyer Hill Road
- 1550 Dwyer Hill Road
- 3950 March Road

All vibration monitoring was performed by either the blasting contractor or the quarry owner. A review of the data supplied confirms that for 2017 through 2020 inclusive, all blasts were compliant with the MECP guideline limit of 12.5mm/s set for ground vibration and 128dB(L) set for overpressure.

Based on the reviewed blast reports, the maximum blast related ground vibration during the 2017 – 2020 period was a reading of 5.27mm/s registered on April 2, 2020, at 1550 Dwyer Hill Road at a separation distance of 875.4m. The maximum overpressure was a reading of 127.7dB(L) registered on August 10, 2017 at 1331 Dwyer Hill Road at a separation distance of 1617.3m.



## **RECOMMENDATIONS**

It is recommended that the following conditions be applied for all blasting operations at the proposed Cavanagh – West Carleton Quarry Extension areas:

1. All blasts shall be monitored for both ground vibration and overpressure at the closest privately owned sensitive receptors adjacent the site, or closer, with a minimum of two (2) instruments – one installed in front of the blast and one installed behind the blast.
2. In order to safeguard the structural integrity of non-sensitive receptors, we recommend that vibrations at these properties be maintained below 50mm/s (>40Hz) in accordance with research performed by the United States Bureau of Mines (USBM RI8507).
3. The guideline limits for vibration and overpressure shall adhere to standards as outlined in the MECP Model Municipal Noise Control By-law publication NPC 119 (1978) or any such document, regulation or guideline which supersedes this standard.
4. In the event of an exceedance of NPC 119 limits or any such document, regulation or guideline which supersedes this standard, blast designs and protocol shall be reviewed prior to any subsequent blasts and revised accordingly in order to return the operations to compliant levels.
5. Orientation of the aggregate extraction operation will be designed and maintained so that the direction of the overpressure propagation will be away from structures as much as possible.
6. Blast designs shall be continually reviewed with respect to fragmentation, ground vibration and overpressure. Blast designs shall be modified as required to ensure compliance with current applicable guidelines and regulations.
7. Blasting procedures such as drilling and loading shall be reviewed on a yearly basis and modified as required to ensure compliance with industry standards.
8. Detailed blast records shall be maintained in accordance with current industry best practices.





The blast parameters described within this report are supported by the modeling in the attached appendices. As the quarry progresses and as site-specific data is collected from the on-going operation, the blast parameters can be refined, as necessary, to ensure continual compliance with MECP Guidelines.




## **CONCLUSION**

The blast parameters described within this report will provide a good basis for the initial blasting operations at this location. As site specific blast vibration and overpressure data becomes available, it will be possible to refine these parameters on an on-going basis.


Blasting operations required for operations at the proposed Cavanagh – West Carleton Quarry Extension site can be carried out safely and within governing guidelines set by the Ministry of the Environment, Conservations and Parks.

Modern blasting techniques will permit blasting to take place with explosives charges below allowable charge weights ensuring that blast vibrations and overpressure will remain minimal at the nearest receptors.


# Appendix A




OPERATIONS PLAN  
SCALE 1:2,000



SCALE 1:12,000 m  
VERT. 1:1,000 m  
A-A' SECTION



TYPICAL BERM DETAIL  
SCALE 1:1



SCALE 1:12,000 m  
VERT. 1:1,000 m  
B-B' SECTION



**ALMONTE QUARRY**  
PART OF LOT 15, CONCESSION 11  
FORMER GEOGRAPHIC TOWNSHIP OF HUNTLEY,  
CITY OF OTTAWA

APPLICANT:  
THOMAS CAVANAGH CONSTRUCTION LIMITED  
9094 CAVANAGH ROAD  
ASHTON, ONTARIO  
K0A 1B0

QUARRY LICENSE NO. \_\_\_\_\_

- NOTE(S)**
- LICENCED AREA, ALMONTE QUARRY 18.2 HECTARES.
  - AREA OF OPERATION, ALMONTE QUARRY 15.5 HECTARES.
  - THIS SITE PLAN IS PREPARED FOR SUBMISSION TO THE MINISTRY OF NATURAL RESOURCES AND FORESTRY IN CONJUNCTION WITH AN APPLICATION FOR A CLASS 'A' CATEGORY 2 QUARRY BELOW WATER UNDER THE AGGREGATE RESOURCES ACT AND REGULATIONS.
  - THIS PLAN WAS PREPARED USING PHOTOGRAMMETRIC METHODS FROM AERIAL PHOTOGRAPHS.
  - LOT, CONCESSION AND BOUNDARY LINES ON THIS PLAN ARE APPROXIMATE.
  - THIS IS NOT A LEGAL SURVEY DRAWING IN ACCORDANCE WITH THE PROVINCE OF ONTARIO SURVEYORS ACT 1987. THIS DRAWING WAS PRODUCED USING STANDARD PHOTOGRAMMETRIC PRACTICES.

- LEGEND**
- BOUNDARY OF AREA TO BE LICENCED
  - LIMIT OF EXTRACTION
  - 120-METRE SURROUND
  - ▲ BOREHOLE / MONITORING WELL
  - ▲ PRIVATE WELL (AS PER MINISTRY OF ENVIRONMENT, CONSERVATION AND PARKS WATER WELL INFORMATION SYSTEM)
  - CON 12, LOT 15  
CON 12, LOT 14  
LOTS AND CONCESSION LINES
  - ◇ BUILDING: S-SILO, H-HOUSE, G-GARAGE, B-BARN, S-SHED, O-OFFICE, SC-SCALE HOUSE, A-AUTO
  - PAGE WIRE FENCE/GATE
  - UTILITY POLE
  - ROADSIDE DITCH
  - WOODED AREA
  - CONTOURS/INDEX CONTOURS
  - ▲ A-A' CROSS-SECTIONS
  - ▲ PRIMARY ENTRANCE
  - ▲ PRIMARY EXIT
  - ▲ GENERAL DIRECTION OF EXCAVATION
  - X EL. 107.00 PROPOSED QUARRY FLOOR SPOT ELEVATION, mASL

- REFERENCE(S)**
- KEY PLAN: Service Layer Credits: Sources: Esri, HERE, DeLorme, Intermap, increment P Corp., NRCAN, Esri, Japan, METI, Esri China (Hong Kong), Esri (Thailand), TomTom, Mapbox, OpenStreetMap contributors, and the GIS User Community.
  - LAND INFORMATION ONTARIO (LIO) DATA PRODUCED BY COLDER ASSOCIATES LTD. UNDER LICENSE FROM ONTARIO MINISTRY OF NATURAL RESOURCES, © QUEEN'S PRINTER 2018
  - CITY OF OTTAWA 2012 TOPO LIDAR TILES
  - PROJECTION: TRANSVERSE MERCATOR, DATUM: NAD 83, COORDINATE SYSTEM: MTM ZONE 9, VERTICAL DATUM: CGVD28.

CLIENT  
THOMAS CAVANAGH CONSTRUCTION LIMITED

PROJECT  
ALMONTE QUARRY EXTENSION

TITLE  
OPERATIONS PLAN

APPLICANT	THOMAS CAVANAGH CONSTRUCTION LIMITED	YYYY-MM-DD	2020-10-06
DESIGNED	---	---	---
PREPARED	JM	---	---
REVIEWED	---	---	---
APPROVED	---	---	---

PROJECT NO. 1899975 CONTROL 0009 REV A FIGURE 3 OF 4

SIGNATURE OF APPLICANT/LICENSEE	DATE
PREPARED UNDER THE DIRECTION OF: JAIME OKTOBIE	DATE

**THOMAS CAVANAGH CONSTRUCTION LIMITED**

AMENDMENTS	DATE	APPROVAL DATE

SITE PLANS APPROVED BY THE MINISTRY OF NATURAL RESOURCES AND FORESTRY.

SIGNATURE	DATE
-----------	------

**DRAFT**

0 100 200  
12,000 METRES



1661 Upper Dwyer Hill Road



1550 Upper Dwyer Hill Road



1720 Burnt Lands Road



1692 Burnt Lands Road



1674 Burnt Lands Road



1644 Burnt Lands Road



1654 Burnt Lands Road



1616 Burnt Lands Road



4061 March Road



1486 Upper Dwyer Hill Road



1331 Upper Dwyer Hill Road



4512 March Road



1509 Golden Line Road



1491 Golden Line Road



1350 Golden Line Road



Image © 2021 Maxar Technologies  
© 2021 Google

Google Earth



Carroll Site Rd

1730 Burnt Lands Road

1720 Burnt Lands Road

1692 Burnt Lands Road

1674 Burnt Lands Road

1654 Burnt Lands Road

1644 Burnt Lands Road

1616 Burnt Lands Road

4061 March Road

March Rd

Image © 2021 Maxar Technologies  
© 2021 Google

Google Earth

# Appendix B



## West Carleton (Almonte) Quarry Extension

### PREVAILING METEOROLOGICAL CONDITIONS

Medians provided by Environment Canada  
Canadian Climate Normals 1981-2010

Date	Wind Direction	Max Hourly Wind Velocity Km/h	Temperature (Deg Celsius)
January	SW	48	-11.5
February	NW	40	-9.5
March	SW	45	-3.3
April	SW	53	5.6
May	NW	47	12.9
June	SW	40	18.1
July	NW	34	20.7
August	SE	32	19.4
September	SW	35	14.5
October	SW	39	7.8
November	SW	48	0.8
December	SW	42	-6.8




# Appendix C

Regression Line For WEST CARLETON ALMONTE REGRESSION - GROUND VIBRATIONS.SDF

95% Line Equation:  $V = 3507.6 * (SD)^{-1.683}$


Coefficient of Determination = 0.956 Standard Deviation = 0.094



# Regression Line For WEST CARLETON ALMONTE REGRESSION - AIR OVERPRESSURE.SDF

95% Line Equation:  $V = 224.3 * (SD)^{-0.102}$

Coefficient of Determination = 0.710 Standard Deviation = 0.016



**Date/Time** Long at 12:45:08 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE22087 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.2 Volts  
**Unit Calibration** April 16, 2020 by InstanTel  
**File Name** X087IXCR.F80

### Notes

**Location:** 9-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 09:29:36  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 114.0 dB(L) at 1.749 sec  
**ZC Freq** 3.4 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	3.810	3.810	3.683	mm/s
ZC Freq	23	24	30	Hz
Time (Rel. to Trig)	0.359	0.229	0.171	sec
Peak Acceleration	0.119	0.093	0.106	g
Peak Displacement	0.020	0.017	0.017	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 4.538 mm/s at 0.229 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 12:45:09 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE15861 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.2 Volts  
**Unit Calibration** January 25, 2021 by InstanTel  
**File Name** Q861IXCR.F90

### Notes

**Location:** 3-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 09:46:21  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 124.9 dB(L) at 1.856 sec  
**ZC Freq** 2.7 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	17.65	13.59	23.88	mm/s
ZC Freq	30	73	34	Hz
Time (Rel. to Trig)	0.195	0.346	0.189	sec
Peak Acceleration	0.384	0.544	0.530	g
Peak Displacement	0.087	0.058	0.110	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 24.75 mm/s at 0.190 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 10.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 12:45:15 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE19649 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** September 4, 2020 by InstanTel  
**File Name** U649IXCR.FF0

### Notes

**Location:** 5-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes


Combo Mode April 7, 2021 09:41:06  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 120.4 dB(L) at 2.096 sec  
**ZC Freq** 3.2 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	15.62	10.79	16.76	mm/s
ZC Freq	34	47	37	Hz
Time (Rel. to Trig)	0.406	0.229	0.289	sec
Peak Acceleration	0.358	0.331	0.437	g
Peak Displacement	0.067	0.034	0.084	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 17.65 mm/s at 0.189 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 5.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:45:20 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE22084 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.4 Volts  
**Unit Calibration** April 16, 2020 by InstanTel  
**File Name** X084IXCR.FK0

### Notes

**Location:** 8-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 09:23:21  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 115.6 dB(L) at 1.300 sec  
**ZC Freq** 4.3 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	5.080	2.540	5.715	mm/s
ZC Freq	28	37	28	Hz
Time (Rel. to Trig)	0.326	0.164	0.231	sec
Peak Acceleration	0.106	0.080	0.133	g
Peak Displacement	0.027	0.020	0.029	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 5.760 mm/s at 0.231 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:45:23 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE21252 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** December 31, 2020 by InstanTel  
**File Name** W252IXCR.FNO

### Notes

**Location:** 10-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 09:33:45  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 114.4 dB(L) at 1.867 sec  
**ZC Freq** 3.4 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	2.921	2.413	3.302	mm/s
ZC Freq	24	26	26	Hz
Time (Rel. to Trig)	0.419	0.366	0.311	sec
Peak Acceleration	0.053	0.080	0.080	g
Peak Displacement	0.018	0.017	0.022	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 4.074 mm/s at 0.315 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check



**Date/Time** Vert at 12:45:24 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE20051 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** February 26, 2021 by InstanTel  
**File Name** V051IXCR.F00

### Notes

**Location:** 6-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 09:12:15  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 119.9 dB(L) at 0.872 sec  
**ZC Freq** 4.1 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	4.699	8.001	6.985	mm/s
ZC Freq	26	32	24	Hz
Time (Rel. to Trig)	0.324	0.195	0.346	sec
Peak Acceleration	0.106	0.239	0.146	g
Peak Displacement	0.028	0.034	0.038	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 9.617 mm/s at 0.195 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:45:24 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE21128 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** January 25, 2021 by InstanTel  
**File Name** W128IXCR.FOO

### Notes

**Location:** 7-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 09:17:08  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 118.3 dB(L) at 2.298 sec  
**ZC Freq** 2.8 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	6.985	5.715	9.144	mm/s
ZC Freq	28	22	30	Hz
Time (Rel. to Trig)	0.328	0.196	0.189	sec
Peak Acceleration	0.146	0.172	0.172	g
Peak Displacement	0.047	0.033	0.048	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 9.532 mm/s at 0.190 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 5.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 12:45:42 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415  
**Operator/Setup:** Operator/2halfF.mmb

**Serial Number** UM10656 V 10-90 Micromate ISEE  
**Battery Level** 3.8 Volts  
**Unit Calibration** March 16, 2021 by InstanTel  
**File Name** UM10656\_20210407124542.IDFW

**Post Event Notes**  
 Location is 2.5-B

**Notes**

Location: 2.5-F  
 Client: M8415A - Cavanagh  
 User Name: Explotech Engineering Ltd.  
 General: Coupled to Ground

**Extended Notes**



Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 125.4 dB(L) at 0.330 sec  
**ZC Freq** 43 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	34.49	47.42	49.56	mm/s
ZC Freq	43	28	51	Hz
Time (Rel. to Trig)	0.272	0.322	0.271	sec
Peak Acceleration	1.919	3.092	3.024	g
Peak Displacement	0.141	0.373	0.177	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 56.14 mm/s at 0.271 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 20.00 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:45:48 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE15860 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.2 Volts  
**Unit Calibration** May 8, 2020 by InstanTel  
**File Name** Q860IXCR.GC0

### Notes

**Location:** 2-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 08:18:47  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 129.7 dB(L) at 0.367 sec  
**ZC Freq** 7.8 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	36.07	38.99	69.85	mm/s
ZC Freq	30	57	39	Hz
Time (Rel. to Trig)	0.338	0.351	0.329	sec
Peak Acceleration	1.206	1.723	1.975	g
Peak Displacement	0.280	0.131	0.238	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 70.24 mm/s at 0.329 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 20.00 mm/s/div Mic: 20.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:44 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE15860 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** May 8, 2020 by InstanTel  
**File Name** Q860IXEJ.XW0

### Notes

**Location:** 2-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 09:02:22  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 130.9 dB(L) at 0.328 sec  
**ZC Freq** 9.7 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	39.24	34.92	72.01	mm/s
ZC Freq	43	47	43	Hz
Time (Rel. to Trig)	0.210	0.188	0.373	sec
Peak Acceleration	1.286	1.339	2.373	g
Peak Displacement	0.189	0.148	0.243	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 74.45 mm/s at 0.372 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 20.00 mm/s/div Mic: 20.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 11:58:44 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE15861 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** January 25, 2021 by InstanTel  
**File Name** Q861IXEJ.XW0

### Notes

**Location:** 3-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 08:55:16  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 125.6 dB(L) at 1.662 sec  
**ZC Freq** 2.7 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	13.72	15.75	24.26	mm/s
ZC Freq	24	39	28	Hz
Time (Rel. to Trig)	0.313	0.333	0.127	sec
Peak Acceleration	0.318	0.544	0.544	g
Peak Displacement	0.072	0.051	0.166	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 24.78 mm/s at 0.127 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 10.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:45 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE21128 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** January 25, 2021 by InstanTel  
**File Name** W128IXEJ.XX0

### Notes

**Location:** 7-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 08:17:56  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 119.2 dB(L) at 2.073 sec  
**ZC Freq** 2.6 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	11.05	7.874	10.54	mm/s
ZC Freq	24	32	21	Hz
Time (Rel. to Trig)	0.299	0.409	0.313	sec
Peak Acceleration	0.199	0.186	0.186	g
Peak Displacement	0.068	0.049	0.078	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 14.47 mm/s at 0.316 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 5.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:45 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE21252 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** December 31, 2020 by InstanTel  
**File Name** W252IXEJ.XX0

### Notes

**Location:** 10-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 08:43:02  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 114.4 dB(L) at 2.801 sec  
**ZC Freq** 2.7 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	2.159	2.286	2.540	mm/s
ZC Freq	30	19	23	Hz
Time (Rel. to Trig)	0.444	0.369	0.297	sec
Peak Acceleration	0.053	0.066	0.066	g
Peak Displacement	0.012	0.013	0.016	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 2.935 mm/s at 0.444 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check



**Date/Time** Long at 11:58:45 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE22084 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** April 16, 2020 by InstanTel  
**File Name** X084IXEJ.XX0

### Notes

**Location:** 8-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 08:27:23  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 116.3 dB(L) at 1.224 sec  
**ZC Freq** 6.2 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	3.556	4.064	4.445	mm/s
ZC Freq	27	32	22	Hz
Time (Rel. to Trig)	0.443	0.209	0.292	sec
Peak Acceleration	0.066	0.106	0.066	g
Peak Displacement	0.019	0.021	0.030	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 5.414 mm/s at 0.294 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:45 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE22087 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.2 Volts  
**Unit Calibration** April 16, 2020 by InstanTel  
**File Name** X087IXEJ.XX0

### Notes

**Location:** 9-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 08:36:04  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 115.4 dB(L) at 1.417 sec  
**ZC Freq** 6.2 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	2.667	3.302	3.937	mm/s
ZC Freq	32	34	32	Hz
Time (Rel. to Trig)	0.358	0.381	0.455	sec
Peak Acceleration	0.080	0.080	0.080	g
Peak Displacement	0.020	0.014	0.019	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 4.366 mm/s at 0.455 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:46 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE20051 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** February 26, 2021 by InstanTel  
**File Name** V051IXEJ.XY0

### Notes

**Location:** 6-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 08:51:35  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 120.1 dB(L) at 1.975 sec  
**ZC Freq** 2.8 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	7.239	6.731	9.017	mm/s
ZC Freq	28	26	20	Hz
Time (Rel. to Trig)	0.271	0.383	0.311	sec
Peak Acceleration	0.133	0.159	0.119	g
Peak Displacement	0.036	0.040	0.062	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 9.386 mm/s at 0.310 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 11:58:47 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE17375 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.4 Volts  
**Unit Calibration** May 29, 2020 by InstanTel  
**File Name** S375IXEJ.XZ0

### Notes

**Location:** 4-B  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 07:58:52  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 123.7 dB(L) at 1.748 sec  
**ZC Freq** 2.8 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	24.00	15.87	28.70	mm/s
ZC Freq	39	30	30	Hz
Time (Rel. to Trig)	0.328	0.304	0.379	sec
Peak Acceleration	0.663	0.371	0.663	g
Peak Displacement	0.098	0.078	0.148	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 30.58 mm/s at 0.316 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 10.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 10:15:01 July 23, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 31.75 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BA20200 V 10.72-8.17 BlastMate III  
**Battery Level** 6.3 Volts  
**Unit Calibration** August 21, 2020 by InstanTel  
**File Name** V200J2UP.T10

**Notes**

**Location:** B3  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to ground



**Extended Notes**

Combo Mode July 23, 2021 07:44:50  
 Unit is installed using industry standard practices for the West Carleton Quarry extension attenuation study.

	Tran	Vert	Long	
PPV	20.03	18.03	13.64	mm/s
ZC Freq	32	51	47	Hz
Time (Rel. to Trig)	0.386	0.276	0.270	sec
Peak Acceleration	0.482	0.575	0.399	g
Peak Displacement	0.193	0.271	0.064	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 24.35 mm/s at 0.385 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 5.000 mm/s/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 10:15:23 July 23, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE5717 V 10.72-4.32 MiniMate Plus  
**Battery Level** 6.5 Volts  
**Unit Calibration** August 18, 2020 by InstanTel  
**File Name** G717J2UP.TN0

### Notes

**Location:** B1  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to ground



### Extended Notes

Unit is setup behind the blast for attenuation study for the West Carleton Quarry Extension using standard practice methods.

	Tran	Vert	Long	
PPV	41.02	33.27	71.12	mm/s
ZC Freq	85	57	>100	Hz
Time (Rel. to Trig)	0.415	0.244	0.245	sec
Peak Acceleration	3.579	2.002	5.581	g
Peak Displacement	0.073	0.110	0.115	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.5	7.4	7.3	Hz
Overswing Ratio	4.3	4.7	4.5	

Peak Vector Sum 77.18 mm/s at 0.245 sec

### USBM RI8507 And OSMRE



Sensor Check

**Date/Time** Long at 10:15:39 July 23, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE20061 V 10.72-8.17 MiniMate Plus/8  
**Battery Level** 6.4 Volts  
**Unit Calibration** August 17, 2020 by InstanTel  
**File Name** V061J2UP.U30

### Notes

**Location:** B5  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to ground



### Extended Notes

Combo Mode July 23, 2021 07:57:24  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry Extension using standard practice methods.

	Tran	Vert	Long	
PPV	9.906	7.366	10.29	mm/s
ZC Freq	34	47	34	Hz
Time (Rel. to Trig)	0.488	0.297	0.321	sec
Peak Acceleration	0.305	0.239	0.239	g
Peak Displacement	0.039	0.028	0.040	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 11.23 mm/s at 0.488 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 5.000 mm/s/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 10:15:40 July 23, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE8899 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** August 7, 2020 by InstanTel  
**File Name** J899J2UP.U40

### Notes

**Location:** B2  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to ground



### Extended Notes

Combo Mode July 23, 2021 07:30:33  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry Extensions using standard practice methods.

	Tran	Vert	Long	
PPV	14.60	22.10	13.84	mm/s
ZC Freq	28	43	30	Hz
Time (Rel. to Trig)	0.398	0.337	0.401	sec
Peak Acceleration	0.398	0.650	0.305	g
Peak Displacement	0.074	0.080	0.082	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 25.66 mm/s at 0.338 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 5.000 mm/s/div  
**Trigger =**

Sensor Check



**Date/Time** Long at 10:15:42 July 23, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 31.75 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE20939 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** July 21, 2021 by InstanTel  
**File Name** V939J2UP.U60

### Notes

**Location:** B7  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd  
**General** Coupled to ground



### Extended Notes

Combo Mode July 23, 2021 08:07:47  
 Geophone is coupled to ground using industry standard practices for the West Carleton Quarry extension attenuation analysis.

	Tran	Vert	Long	
PPV	4.254	4.223	4.397	mm/s
ZC Freq	57	47	43	Hz
Time (Rel. to Trig)	0.331	0.334	0.209	sec
Peak Acceleration	0.136	0.128	0.124	g
Peak Displacement	0.013	0.014	0.016	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 5.203 mm/s at 0.331 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 1.000 mm/s/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:44:45 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE10846 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.4 Volts  
**Unit Calibration** May 11, 2020 by InstanTel  
**File Name** L846IXCR.EL0

### Notes

**Location:** 3-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 10:28:07  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 146.9 dB(L) at 0.516 sec  
**ZC Freq** 34 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	5.969	12.45	14.10	mm/s
ZC Freq	30	39	43	Hz
Time (Rel. to Trig)	0.216	0.398	0.194	sec
Peak Acceleration	0.172	0.384	0.371	g
Peak Displacement	0.026	0.048	0.050	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 16.97 mm/s at 0.194 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 5.000 mm/s/div Mic: 100.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:45:03 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE10735 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** March 26, 2021 by InstanTel  
**File Name** L735IXCR.F30

**Notes**

Location: 2-F  
 Client: M8415A - Cavanagh  
 User Name: Explotech Engineering Ltd.  
 General: Coupled to Ground

**Extended Notes**



Combo Mode April 7, 2021 10:26:27  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 146.2 dB(L) at 0.379 sec  
**ZC Freq** 34 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	5.461	5.334	12.83	mm/s
ZC Freq	47	51	34	Hz
Time (Rel. to Trig)	0.189	0.189	0.184	sec
Peak Acceleration	0.225	0.212	0.703	g
Peak Displacement	0.024	0.024	0.051	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 12.83 mm/s at 0.184 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 5.000 mm/s/div Mic: 100.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:45:06 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE15256 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** March 30, 2021 by InstanTel  
**File Name** Q256IXCR.F60

### Notes

**Location:** 7-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 10:43:55  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 136.3 dB(L) at 1.398 sec  
**ZC Freq** 28 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	1.397	2.032	1.651	mm/s
ZC Freq	30	26	23	Hz
Time (Rel. to Trig)	0.443	0.107	0.287	sec
Peak Acceleration	0.040	0.040	0.053	g
Peak Displacement	0.010	0.014	0.010	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 2.129 mm/s at 0.107 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 50.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:45:34 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE15257 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** March 30, 2021 by InstanTel  
**File Name** Q257IXCR.FY0

### Notes

**Location:** 6-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 10:42:22  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 139.6 dB(L) at 1.191 sec  
**ZC Freq** 32 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	2.413	8.509	2.667	mm/s
ZC Freq	39	28	37	Hz
Time (Rel. to Trig)	0.392	0.602	0.184	sec
Peak Acceleration	0.053	0.159	0.066	g
Peak Displacement	0.015	0.048	0.011	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 8.564 mm/s at 0.602 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 50.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:45:36 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415  
**Operator/Setup:** Operator/8F.MMB

**Serial Number** UM11714 V 10-89 Micromate ISEE  
**Battery Level** 3.8 Volts  
**Unit Calibration** May 6, 2020 by InstanTel  
**File Name** UM11714\_20210407124536.IDFW

**Notes**

**Location:** 8-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to Ground

**Extended Notes**



Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 133.2 dB(L) at 1.667 sec  
**ZC Freq** 34 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	1.411	1.679	1.482	mm/s
ZC Freq	23	32	28	Hz
Time (Rel. to Trig)	0.348	0.426	0.546	sec
Peak Acceleration	0.049	0.064	0.057	g
Peak Displacement	0.009	0.012	0.011	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 1.772 mm/s at 0.552 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 50.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:45:41 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE14197 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** May 29, 2020 by InstanTel  
**File Name** P197IXCR.G50

### Notes

**Location:** 4-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 10:34:17  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 144.7 dB(L) at 0.651 sec  
**ZC Freq** 37 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	2.921	7.239	9.144	mm/s
ZC Freq	47	47	39	Hz
Time (Rel. to Trig)	0.309	0.288	0.194	sec
Peak Acceleration	0.106	0.239	0.212	g
Peak Displacement	0.019	0.025	0.033	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 9.223 mm/s at 0.194 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 5.000 mm/s/div Mic: 100.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 12:45:50 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415  
**Operator/Setup:** Operator/micromate front.mmb

**Serial Number** UM13270 V 10-90 Micromate ISEE  
**Battery Level** 3.8 Volts  
**Unit Calibration** February 18, 2021 by InstanTel  
**File Name** UM13270\_20210407124550.IDFW

**Notes**

**Location:** 9-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to Ground

**Extended Notes**



Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 131.1 dB(L) at 1.761 sec  
**ZC Freq** 32 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	1.174	1.781	1.103	mm/s
ZC Freq	26	28	24	Hz
Time (Rel. to Trig)	0.081	0.451	0.046	sec
Peak Acceleration	0.021	0.032	0.029	g
Peak Displacement	0.008	0.012	0.007	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 1.948 mm/s at 0.450 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 20.00 pa.(L)/div  
**Trigger =**

Sensor Check



**Date/Time** Long at 12:45:58 April 7, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE15255 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** March 30, 2021 by InstanTel  
**File Name** Q255IXCR.GM0

### Notes

**Location:** 5-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 7, 2021 10:35:51  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 141.3 dB(L) at 0.921 sec  
**ZC Freq** 34 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	3.175	3.937	4.064	mm/s
ZC Freq	30	30	37	Hz
Time (Rel. to Trig)	0.408	0.554	0.185	sec
Peak Acceleration	0.066	0.133	0.106	g
Peak Displacement	0.016	0.020	0.016	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 4.706 mm/s at 0.185 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 100.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:43 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE10846 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.4 Volts  
**Unit Calibration** May 11, 2020 by InstanTel  
**File Name** L846IXEJ.XV0

### Notes

**Location:** 3-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 10:03:32  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 137.2 dB(L) at 0.549 sec  
**ZC Freq** 13 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	4.572	12.57	24.89	mm/s
ZC Freq	47	39	47	Hz
Time (Rel. to Trig)	0.240	0.271	0.239	sec
Peak Acceleration	0.225	0.451	0.650	g
Peak Displacement	0.017	0.051	0.075	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 27.35 mm/s at 0.239 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 10.000 mm/s/div Mic: 50.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:44 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE15255 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.2 Volts  
**Unit Calibration** March 30, 2021 by InstanTel  
**File Name** Q255IXEJ.XW0

### Notes

**Location:** 5-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 09:54:33  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 131.5 dB(L) at 0.958 sec  
**ZC Freq** 11 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	3.429	4.318	6.096	mm/s
ZC Freq	26	34	39	Hz
Time (Rel. to Trig)	0.310	0.372	0.229	sec
Peak Acceleration	0.093	0.119	0.159	g
Peak Displacement	0.019	0.020	0.023	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 6.515 mm/s at 0.229 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 20.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:44 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE15257 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** March 30, 2021 by InstanTel  
**File Name** Q257IXEJ.XW0

### Notes

**Location:** 6-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 09:50:31  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 129.9 dB(L) at 1.230 sec  
**ZC Freq** 9.5 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	2.540	7.493	2.286	mm/s
ZC Freq	30	26	43	Hz
Time (Rel. to Trig)	0.287	0.361	0.227	sec
Peak Acceleration	0.066	0.146	0.106	g
Peak Displacement	0.011	0.045	0.009	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 7.782 mm/s at 0.361 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 20.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:45 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE14197 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** May 29, 2020 by InstanTel  
**File Name** P197IXEJ.XX0

### Notes

**Location:** 4-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 09:59:13  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 135.5 dB(L) at 0.685 sec  
**ZC Freq** 13 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
<b>PPV</b>	3.683	9.398	13.46	mm/s
<b>ZC Freq</b>	32	43	22	Hz
<b>Time (Rel. to Trig)</b>	0.300	0.281	0.237	sec
<b>Peak Acceleration</b>	0.093	0.278	0.451	g
<b>Peak Displacement</b>	0.017	0.037	0.068	mm
<b>Sensor Check</b>	Disabled	Disabled	Disabled	
<b>Frequency</b>	***	***	***	Hz
<b>Overswing Ratio</b>	***	***	***	

**Peak Vector Sum** 14.23 mm/s at 0.237 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 5.000 mm/s/div Mic: 50.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:45 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE15256 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** March 30, 2021 by InstanTel  
**File Name** Q256IXEJ.XX0

### Notes

**Location:** 7-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General** Coupled to Ground

### Extended Notes



Combo Mode April 8, 2021 09:45:31  
 Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 127.4 dB(L) at 1.412 sec  
**ZC Freq** 11 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	1.524	1.651	1.651	mm/s
ZC Freq	32	30	28	Hz
Time (Rel. to Trig)	0.239	0.271	0.278	sec
Peak Acceleration	0.053	0.066	0.053	g
Peak Displacement	0.012	0.012	0.009	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 2.136 mm/s at 0.257 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 20.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:49 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415  
**Operator/Setup:** Operator/10F.MMB

**Serial Number** UM10656 V 10-90 Micromate ISEE  
**Battery Level** 3.8 Volts  
**Unit Calibration** March 16, 2021 by InstanTel  
**File Name** UM10656\_20210408115849.IDFW

### Notes

**Location:** 10-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to Ground

### Extended Notes



Unit is setup in front of the blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 116.5 dB(L) at 2.634 sec  
**ZC Freq** 15 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
<b>PPV</b>	0.780	1.308	1.103	mm/s
<b>ZC Freq</b>	19	27	26	Hz
<b>Time (Rel. to Trig)</b>	0.082	0.230	0.231	sec
<b>Peak Acceleration</b>	0.026	0.030	0.020	g
<b>Peak Displacement</b>	0.006	0.009	0.007	mm
<b>Sensor Check</b>	Disabled	Disabled	Disabled	
<b>Frequency</b>	***	***	***	Hz
<b>Overswing Ratio</b>	***	***	***	

**Peak Vector Sum** 1.782 mm/s at 0.230 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 5.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 11:58:49 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415  
**Operator/Setup:** Operator/8F.MMB

**Serial Number** UM11714 V 10-89 Micromate ISEE  
**Battery Level** 3.8 Volts  
**Unit Calibration** May 6, 2020 by InstanTel  
**File Name** UM11714\_20210408115849.IDFW

### Notes

**Location:** 8-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to Ground

### Extended Notes



Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 124.6 dB(L) at 1.674 sec  
**ZC Freq** 23 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	1.190	2.554	1.356	mm/s
ZC Freq	20	28	28	Hz
Time (Rel. to Trig)	0.373	0.285	0.149	sec
Peak Acceleration	0.038	0.095	0.065	g
Peak Displacement	0.010	0.015	0.007	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 2.568 mm/s at 0.285 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check



**Date/Time** Vert at 11:58:49 April 8, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415  
**Operator/Setup:** Operator/micromate front.mmb

**Serial Number** UM13270 V 10-90 Micromate ISEE  
**Battery Level** 3.8 Volts  
**Unit Calibration** February 18, 2021 by InstanTel  
**File Name** UM13270\_20210408115849.IDFW

### Notes

**Location:** 9-F  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to Ground

### Extended Notes



Unit is setup in front of blast for attenuation study for the West Carleton Quarry extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 124.3 dB(L) at 1.784 sec  
**ZC Freq** 23 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	1.025	2.262	1.592	mm/s
ZC Freq	21	28	30	Hz
Time (Rel. to Trig)	0.317	0.229	0.205	sec
Peak Acceleration	0.039	0.049	0.073	g
Peak Displacement	0.007	0.013	0.008	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

**Peak Vector Sum** 2.289 mm/s at 0.229 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 10:15:35 July 23, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415

**Serial Number** BE9330 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** July 23, 2020 by InstanTel  
**File Name** K330J2UP.TZ0

### Notes

**Location:** F2  
**Client:** M8415A - Cavanagh  
**User Name:** Explotech Engineering Ltd.  
**General:** Coupled to ground

### Extended Notes



Combo Mode July 23, 2021 08:57:40  
 Unit is setup behind the blast for attenuation study for the West Carleton Quarry Extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 137.4 dB(L) at 0.520 sec  
**ZC Freq** 32 Hz  
**Channel Test** Disabled

	Tran	Vert	Long	
PPV	4.064	3.302	3.683	mm/s
ZC Freq	57	43	57	Hz
Time (Rel. to Trig)	0.324	0.490	0.122	sec
Peak Acceleration	0.172	0.119	0.133	g
Peak Displacement	0.012	0.011	0.011	mm
Sensor Check	Disabled	Disabled	Disabled	
Frequency	***	***	***	Hz
Overswing Ratio	***	***	***	

Peak Vector Sum 4.239 mm/s at 0.324 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 50.00 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 10:15:47 July 23, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415  
**Operator/Setup:** AMA/M8415A - Front .nsb

**Serial Number** MP13282 V 10-73 Minimate Pro 4  
**Battery Level** 4.1 Volts  
**Unit Calibration** Uninitialized  
**Geo1 Calibration** SE12641, March 3, 2021 by InstanTEL  
**Mic Calibration** SL12571, March 18, 2021 by InstanTEL  
**File Name** MP13282\_20210723101547.IDFW

**Notes**

Location: F6  
 Client: M8415A - Cavanagh  
 User Name: Explotech Engineering Ltd.  
 General: Coupled to ground

**Extended Notes**



Unit is setup in front of the blast for attenuation study for the West Carleton Quarry Extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 120.8 dB(L) at 1.313 sec  
**ZC Freq** 6.8 Hz  
**Channel Test** Passed (Freq = 20.4 Hz Amp = 1622 mv )

	Tran	Vert	Long	
<b>PPV</b>	1.056	0.985	0.686	mm/s
<b>ZC Freq</b>	39	39	39	Hz
<b>Time (Rel. to Trig)</b>	0.272	0.002	0.270	sec
<b>Peak Acceleration</b>	0.026	0.035	0.019	g
<b>Peak Displacement</b>	0.032	0.004	0.003	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
<b>Frequency</b>	7.6	7.4	7.3	Hz
<b>Overswing Ratio</b>	3.6	3.7	3.8	

**Peak Vector Sum** 1.240 mm/s at 0.272 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div    **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 5.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 10:15:47 July 23, 2021  
**Trigger Source** Geo: 0.750 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps  
**Job Number:** 8415  
**Operator/Setup:** Operator 1/M8415A - Pro .nsb

**Serial Number** MP13427 V 10-72 Minimate Pro 4 XM  
**Battery Level** 4.1 Volts  
**Unit Calibration** October 30, 2020 by InstanTel  
**Geo1 Calibration** SE12643, November 9, 2020 by InstanTel  
**Mic Calibration** SL12601, March 18, 2021 by InstanTel  
**File Name** MP13427\_20210723101547.IDFW

**Notes**

Location: F7  
 Client: M8415A - Cavanagh  
 User Name: Explotech Engineering Ltd.  
 General: Coupled to ground

**Extended Notes**



Unit is setup in front of the blast for attenuation study for the West Carleton Quarry Extension using standard practice methods.

**Microphone** Linear Weighting  
**PSPL** 117.5 dB(L) at 1.580 sec  
**ZC Freq** 6.9 Hz  
**Channel Test** Passed (Freq = 20.4 Hz Amp = 1676 mv )

	Tran	Vert	Long	
<b>PPV</b>	1.702	1.545	1.836	mm/s
<b>ZC Freq</b>	27	24	24	Hz
<b>Time (Rel. to Trig)</b>	0.434	0.381	0.368	sec
<b>Peak Acceleration</b>	0.028	0.022	0.028	g
<b>Peak Displacement</b>	0.017	0.010	0.014	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
<b>Frequency</b>	7.3	7.6	7.7	Hz
<b>Overswing Ratio</b>	4.0	3.5	3.5	

**Peak Vector Sum** 2.279 mm/s at 0.368 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div    **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 5.000 pa.(L)/div  
**Trigger =**

Sensor Check

## BLAST REPORT SUMMARY

Blast#	Date	Time	Weather	Wind	Wind	Max Kg	Hole Dia.	# Of	# Of	Ave Hole	Total	Location	Monitor 1			Monitor 2			Monitor 2				
				From	Velocity	/Delay	(in.)	Rows	Holes	Depth	Tons		(mm/s)	(dbl.)	Distance	Location	(mm/s)	(dbl.)	Distance	Location	(mm/s)	(dbl.)	Distance
17001	Jun 9/17	12:30	Cloudy	NE	20-30	75.3	3.5	7	127	9.45	32380.2	1331 Dwire Hill	1.6	113.0	1198.2	1550 Dwire Hill	DNT	DNT	1344.5	3950 March	DNT	DNT	1344.5
17002	Jun 20/17	12:00	Clear	S	20-35	73.90	3.5	8	108	9.14	???	1331 Dwire Hill	DNT	DNT	1236.0	1550 Dwire Hill	1.53	111.0	1318.3	3950 March	1.53	111.0	1318.3
17003	Jul 31/17	10:00	Cloudy	SSW	0-5	91.4	4	6	60	9.14	17706.3	1331 Dwire Hill	DNT	DNT	1463.3	1550 Dwire Hill	2.73	114	826.92	3950 March	1.426	116	1097.28
17004	Aug 01/17	12:00	Clear	WSW	0-5	175.1	4	5	112	16.46	66103.2	1331 Dwire Hill	1.5	116.0	1576.7	1550 Dwire Hill	3.49	119	885.75	3950 March	2.416	113	1135.08
17005	Aug 10/17	13:07	Cloudy	SSW	15-25	173.8	4	5	115	16.76	66125.2	1331 Dwire Hill	4.5	127.7	1617.3	1550 Dwire Hill	1.81	119	860.15	3950 March	0.58	124	1093.93
17006	Sep 13/17	12:50	Clear	SW	0.00	144.70	3.75	5	125	16.61	55166.2	1331 Dwire Hill	3.5	116.0	1662.4	1550 Dwire Hill	4.11	122	???	3950 March	0.52	117	1103.07
17007	Sep 25/16	15:00	Clear	SSW	10-May	79	3.5	6	180	10.06	49593.8	1331 Dwire Hill	DNT	DNT	1459.7	1550 Dwire Hill	2.93	112	767.79	3950 March	0.31	113	1033.58
17008	Oct 04/17	13:00	Part Cloud	WSW	15-25	77.30	3.5	6	180	10.06	49593.8	1331 Dwire Hill	DNT	DNT	1499.6	1550 Dwire Hill	2.37	110.0	742.8	3950 March	0.25	115.0	995.5
18001	Mar 14/18	14:45	Heavy Snow	NE	0-5	91.60	4	5	112	3.66	9745.8	1331 Dwire Hill	DNT	DNT	1351.8	1550 Dwire Hill	1.29	108	990.9				
18002	Mar 16/18	10:20	Part Cloud	NE	35-50	29.40	4	4	63	3.66	5738.1	1331 Dwire Hill	DNT	DNT	1380.4	1550 Dwire Hill	0.22	119.0	969.6				
18003	Apr 2/18	16:30	Cloudy	NNE	0-5	36.50	4	4	86	3.96	8091.0	1331 Dwire Hill	DNT	DNT	1422.5	1550 Dwire Hill	0.22	119.0	1004.0				
18004	Apr 3/18	10:15	Cloudy	NNE	0-5	31.60	4	8	79	3.96	7005.6	1331 Dwire Hill	DNT	DNT	1434.7	1550 Dwire Hill	DNT	DNT	929.6				
18005	May 22/18	13:00	Light Rain	WSW	0-5	182.80	4	4	84	17.22	51872.2	1331 Dwire Hill	1.5	117.0	1647.8	1550 Dwire Hill	4.1	116.0	926.0	3950 March	1.82	113.0	1161.3
18006	May 29/18	17:00	Hazy Hot & Humid	S	0-5	189.10	4	8	94	17.83	60102.8	1331 Dwire Hill	1.9	115.0	1669.1	1550 Dwire Hill	5.15	116.0	949.2				
18007	Jun 1/18	12:00	Hazy Hot & Humid	S	0-1	21.30	3.5	15	182	3.44	15609.8	1331 Dwire Hill	DNT	DNT	1393.6	1550 Dwire Hill	DNT	DNT	1139.7				
18008	Jun 1/18	14:30	Light Rain	S	0-3	140.40	4	5	97	17.68	46752.0	1331 Dwire Hill	DNT	DNT	1669.1	1550 Dwire Hill	3.58	115.0	936.7				
18009	Sep 7/18	12:04	Clear	W	0-5	77.80	3.75	6	112	9.75	29777.6	1331 Dwire Hill	DNT	DNT	1454.5	1550 Dwire Hill	4.56	116.0	668.7				
18010	Sep 11/18	11:30	Overcast	N	0-2	77.40	3.75	5	129	9.75	34343.8	1331 Dwire Hill	2.6	93.0	1477.7	1550 Dwire Hill	4.51	117.0	670.6				
18011	Sep 13/18	12:17	Clear	E	3-6	79.20	3.75	4	191	9.75	59272.3	1331 Dwire Hill	2.4	105.0	1472.8	1550 Dwire Hill	3.34	114.0	634.3				
18012	Oct 15/18	11:00	Light Rain	NE	2-12	77.93	3.5	4	120	10.06	35514.4	1331 Dwire Hill	0.1	105.0	1548.0	1550 Dwire Hill	0.13	111.0	764.0				
18013	Oct 26/18	10:15	Partly cloudy	NW	4-6	75.70	4	5	150	10.06	40272.8	1331 Dwire Hill	2.1	110.0	1505.7	1550 Dwire Hill	2.74	115.0	680.3				
18014	Nov 2/18	13:15	Light Rain	N	0-5	77.90	4	6	109	9.14	35740.4	1331 Dwire Hill	DNT	DNT	1237.5	1550 Dwire Hill	DNT	DNT	1346.3				
18015	Nov 9/18	13:40	Heavy Snow	NE	10-15	95.80	4	5	95	9.14	31149.8	1331 Dwire Hill	***1.606	108.4	1199.7	1550 Dwire Hill	DNT	DNT	1336.6				
18016	Dec 1/18	10:05	Clear	SSW	2-14	83.50	4	7	89	9.45	29474.5	1331 Dwire Hill	DNT	114.0	1172.3	1550 Dwire Hill	DNT	DNT	1355.5				
18016	Dec 4/18	13:30	Part Cloud	N	5-10	82.20	4	5	106	9.45	34221.2	1331 Dwire Hill	0.2	118.0	1210.7	1550 Dwire Hill	2.3	114.0	1372.5				
19001	Apr 12/19	10:50	Cloudy	S	10-15	163.10	4	5	75	17.53	43992.4	1331 Dwire Hill	DNT	DNT	1618.2	1550 Dwire Hill	DNT	DNT	830.3				
19002	Apr 15/19	11:00	Light Rain	N	0-5	163.50	4	5	75	17.53	43992.4	1331 Dwire Hill	DNT	DNT	1680.1	1550 Dwire Hill	4.62	106.0	902.5				
19003	Apr 17/19	11:00	Clear	S	0-5	182.50	4	5	45	18.44	26450.1	1331 Dwire Hill	DNT	DNT	1663.3	1550 Dwire Hill	3.37	117.0	882.7				
19004	Jul 26/19	10:14	Clear	S	0-1	91.40	4	5	179	9.60	59906.1	1331 Dwire Hill	1.5	96.0	1571.6	1550 Dwire Hill	3.06	118.0	776.3				
19005	Jul 30/19	12:36	Light Rain	W	2-5	91.50	4	5	180	9.75	62955.5	1331 Dwire Hill	1.4	115.0	1592.3	1550 Dwire Hill	4.18	97.0	789.1				
19006	Sep 6/19	10:29	Clear	ESE	4-8	164.00	4	6	77	17.68	48812.4	1331 Dwire Hill	1.6	94.0	1677.3	1550 Dwire Hill	2.91	117.0	919.6				
19007	Sep 9/19	10:49	Clear	W	0-3	155.50	4	6	78	17.62	58459.1	1331 Dwire Hill	1.4	94.0	1699.6	1550 Dwire Hill	3.61	114.0	929.3				
19008	Sep 11/19	12:59	Clear	W	2-4	159.80	4	4	38	17.98	24504.4	1331 Dwire Hill	2.9	99.0	1737.1	1550 Dwire Hill	1.18	122.0	981.5				
19009	Oct 7/19	10:50	Cloudy	W	5-10	82.10	4	5	110	9.14	36068.2	1331 Dwire Hill	***4.239	97.5	1210.7	1550 Dwire Hill	***0.925	114.2	1372.5				
19010	Oct 10/19	10:43	Clear	E	3-7	87.20	4	5	115	9.14	37707.7	1331 Dwire Hill	DNT	DNT	1231.4	1550 Dwire Hill	3.28	88.0	1377.7				
19011	Oct 15/19	10:25	Clear	W	3-7	82.70	4	4	113	8.84	27272.1	1331 Dwire Hill	2.0	117.0	1240.8	1550 Dwire Hill	1.21	94.0	1407.6				
19012	Nov 13/19	12:15	Clear	N	8-14	69.40	3.5	7	136	9.45	31294.1	1331 Dwire Hill	1.4	117.0	1266.4	1550 Dwire Hill	1.28	94.0	1428.0				
19013	Nov 20/19	15:56	Partly cloudy	N	1-3	72.40	3.5	8	115	9.45	26435.1	1331 Dwire Hill	1.9	98.0	1277.7	1550 Dwire Hill	1.83	109.0	1439.0				
19014	Nov 21/19	16:00	Partly cloudy	S	2-5	68.10	3.5	7	97	9.45	22823.4	1331 Dwire Hill	1.7	108.0	1283.8	1550 Dwire Hill	1.28	106.0	1405.4				
19015	Dec 2/19	11:33	Partly cloudy	NE	20-30	65.60	4	4	81	9.45	18117.5	1331 Dwire Hill	1.0	99.0	1298.1	1550 Dwire Hill	1.73	108.0	1432.6				
19016	Dec 4/19	13:59	Light Snow	SW	2-5	66.10	3.5	5	57	9.14	12979.0	1331 Dwire Hill	1.9	104.0	1303.0	1550 Dwire Hill	DNT	DNT	1424.6				
19017	Dec 10/19	9:31	Partly cloudy	N	4-9	56.80	3.5	5	56	9.14	12751.3	1331 Dwire Hill	0.2	113.0	1286.9	1550 Dwire Hill	1.88	88.0	1390.5				
19018	Dec 13/19	9:59	Partly cloudy	SW	5-7	64.80	3.5	6	72	9.14	16394.6	1331 Dwire Hill	1.4	88.0	1289.0	1550 Dwire Hill	0.22	111.0	1363.7				
20-001	Apr 1/20	9:00	Clear	E	2-5	69.30	3.5	7	55	8.53	13729.1	1331 Dwire Hill	DNT	DNT	1620.0	1550 Dwire Hill	3.23	104.0	811.4				
20-002	Apr 2/20	10:12	Clear	NW	5-9	138.70	3.25	3	69	17.98	29555.8	1331 Dwire Hill	0.2	121.0	1693.2	1550 Dwire Hill	5.27	119.0	875.4				
20-003	Apr 6/20	10:27	Clear	S	0-3	139.90	3.5	3	73	17.98	32451.0	1331 Dwire Hill	0.2	115.0	1661.2	1550 Dwire Hill	3.07	120.0	843.7				
20-004	Apr 8/20	12:30	Cloudy	SE	3-10	175.20	4	3	73	17.98	34499.9	1331 Dwire Hill	DNT	DNT	1669.4	1550 Dwire Hill	4.97	113.0	846.1				
20-005	Sep 22/20	10:31	Clear	S	4-9	169.80	4	4	61	18.59	37410.1	1331 Dwire Hill	0.3	119.0	1690.4	1550 Dwire Hill	1.38	119.0	911.7				
20-006	Sep 25/20	11:31	Cloudy	S	3-6	140.40	3.5	5	66	18.44	30307.3	1331 Dwire Hill	DNT	DNT	1715.1	1550 Dwire Hill	1.50	115.0	924.2				
20-007	Sep 28/20	11:33	Clear	S	25-30	137.50	3.5	3	84	17.98	36273.2	1331 Dwire Hill	DNT	DNT	1676.4	1550 Dwire Hill	2.80	117.0	845.5				
20-008	Oct 28/20	13:17	Partly cloudy	SW	7-9	71.50	3.5	9	117	9.45	27529.3	1331 Dwire Hill	1.7	112.0	1320.1	1550 Dwire Hill	0.55	116.0	1419.2				
20-009	Oct 30/20	12:16	Clear	NW	3-6	78.00	3.5	5	126	9.75	30603.3	1331 Dwire Hill	0.3	111.0	1297.2	1550 Dwire Hill	DNT	DNT	1309.7				
20-010	Nov 2/20	10:58	Cloudy	NW	25-31	72.90	3.5	9	108	9.45	25411.7	1331 Dwire Hill	1.4	115.0	1306.4	1550 Dwire Hill	DNT	DNT	1371.9				
20-011	Nov 9/20	10:30	Clear	S	3-5	75.60	3.5	5	120	9.45	28235.3	1331 Dwire Hill	2.0	109.0	1339.9	1550 Dwire Hill	DNT	DNT	1351.2				

\*\*\* Corrected vibration information. Blast report contained incorrect vibration data, further review of the forwarded seismograph event reports confirmed correct vibrations

Executed by Explotech for the purpose of West Carleton Quarry Extension

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2017-01

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 06/09/2017 12:30

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location:

**SEISMOGRAPH 1 - SEISMOGRAPH 1**

Data Type: Seismic Record    Seismograph Type: instancel

Date: 06/09/17    Trigger Level: 1.23 mm/s    Off dB    Transverse: 0.635 mm/s    28.0 Hz

Time: 12:30    Calibration Date: 03/06/17    Vertical: 1.397 mm/s    21.0 Hz

Distance From Blast: 1,198.17 m    Calibration Signal:    Longitudinal: 1.397 mm/s    21.0 Hz

Direction From Blast: ENE    Geophone Min. Freq.: --- Hz    PPV: --- mm/s    --- Hz

Readout:    Mic. Min. Freq.: --- Hz    Acoustic: 113 dB

Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: 1.555 mm/s

Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: William Coleman, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: No Trigger    Seismograph Type: instancel

Date: 06/09/17    Trigger Level: 1.23 mm/s    Off dB    Transverse: --- mm/s    --- Hz

Time: 12:30    Calibration Date: 03/06/17    Vertical: --- mm/s    --- Hz

Distance From Blast: 1,344.47 m    Calibration Signal:    Longitudinal: --- mm/s    --- Hz

Direction From Blast: N    Geophone Min. Freq.: --- Hz    PPV: --- mm/s    --- Hz

Readout:    Mic. Min. Freq.: --- Hz    Acoustic: --- dB

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: --- mm/s

Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: William Coleman, Austin Powder

No Trigger

Event Report: Monitor Log - Minimate Blaster # BE15020-Compliance

Start Time	End Time	Status
-----	-----	SERIAL NUMBER: BE15020
May 31 /17 11:26:04		Start Monitoring Trigger Level: Geo: 1.70 mm/s
May 31 /17 11:55:04	May 31 /17 11:55:09	Event recorded. Trigger Level Long: 1.70 mm/s
May 31 /17 11:55:23	May 31 /17 12:28:36	No events recorded. (Keyboard Exit) Geo: 1.70 mm/s
Jun 9 /17 11:34:55	Jun 9 /17 12:45:03	No events recorded. (Keyboard Exit) Geo: 1.70 mm/s

1550 Dwyer,

Hill Rd.

**Date/Time** Vert at 12:29:02 June 9, 2017  
**Trigger Source** Geo: 1.230 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** March 6, 2017 by Instantel  
**File Name** Q589GXFU.OE0  
**Post Event Notes**  
 set up at 1331 Dwire Hill rd, geo spiked and wieght bagged.

**Notes**



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 112.6 dB(L) at 2.983 sec  
**ZC Freq** 13 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 517 mv )

	Tran	Vert	Long	
PPV	0.635	1.397	1.397	mm/s
ZC Freq	28	21	21	Hz
Time (Rel. to Trig)	-0.141	0.172	0.161	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.006	0.013	0.013	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.8	7.9	7.8	Hz
Overswing Ratio	3.4	3.4	3.6	

**Peak Vector Sum** 1.555 mm/s at 0.170 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2017-02

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 06/20/2017 12:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location:

**SEISMOGRAPH 1 - SEISMOGRAPH 1**

Data Type: No Trigger      Seismograph Type: instancel  
Date: 06/20/17      Trigger Level: 1.23 mm/s      Off dB      Transverse: --- mm/s      --- Hz  
Time: 12:30      Calibration Date: 03/06/17      Vertical: --- mm/s      --- Hz  
Distance From Blast: 1,235.96 m      Calibration Signal:      Longitudinal: --- mm/s      --- Hz  
Direction From Blast: ENE      Geophone Min. Freq.: --- Hz      PPV: --- mm/s      --- Hz  
Readout:      Mic. Min. Freq.: --- Hz      Acoustic: --- dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.      Vector Sum: --- mm/s  
Lat./Long.: 45° 15' 27.900" N      76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Cliffton, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record      Seismograph Type: instancel  
Date: 06/20/17      Trigger Level: 1.23 mm/s      Off dB      Transverse: 1.016 mm/s      28.0 Hz  
Time: 12:30      Calibration Date: 03/06/17      Vertical: 1.016 mm/s      47.0 Hz  
Distance From Blast: 1,318.26 m      Calibration Signal:      Longitudinal: 1.27 mm/s      27.0 Hz  
Direction From Blast: N      Geophone Min. Freq.: --- Hz      PPV: --- mm/s      --- Hz  
Readout: Printed Copy      Mic. Min. Freq.: --- Hz      Acoustic: 111 dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.      Vector Sum: 1.529 mm/s  
Lat./Long.: 45° 15' 59.300" N      76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Cliffton, Austin Powder

**Date/Time** Long at 12:00:54 June 20, 2017  
**Trigger Source** Geo: 1.200 mm/s  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** March 6, 2017 by InstanTel  
**File Name** Q020GY06.PIO

2

**Notes**

Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 110.9 dB(L) at 3.440 sec  
**ZC Freq** 10 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 511 mv )

	Tran	Vert	Long	
PPV	1.016	1.016	1.270	mm/s
ZC Freq	28	47	27	Hz
Time (Rel. to Trig)	0.506	-0.141	0.516	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.006	0.004	0.008	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.3	7.6	7.4	Hz
Overswing Ratio	3.9	3.5	3.7	

Peak Vector Sum 1.529 mm/s at 0.534 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

3

No Trigger

Event Report: Monitor Log - MiniMate Plus # BE19637-Compliance

Start Time	End Time	Status
		SERIAL NUMBER: BE19637
Jun 9 /17 11:38:05	Jun 9 /17 12:47:26	No events recorded. (Keyboard Exit) Geo: 1.70 mm/s
Jun 12 /17 13:03:53	Jun 12 /17 14:32:51	No events recorded. (Keyboard Exit) Geo: 1.70 mm/s
Jun 14 /17 12:45:53		Start Monitoring Trigger Level: Geo: 1.70 mm/s
Jun 14 /17 13:46:47	Jun 14 /17 13:46:53	Event recorded. Trigger Level Vert: 1.70 mm/s
Jun 14 /17 13:47:06	Jun 14 /17 14:08:23	No events recorded. (Keyboard Exit) Geo: 1.70 mm/s
Jun 19 /17 11:45:10		Start Monitoring Trigger Level: Geo: 1.70 mm/s
Jun 19 /17 12:28:36	Jun 19 /17 12:28:41	Event recorded. Trigger Level Vert: 1.70 mm/s
Jun 19 /17 12:28:55	Jun 19 /17 12:51:59	No events recorded. (Keyboard Exit) Geo: 1.70 mm/s
Jun 20 /17 11:00:37	Jun 20 /17 12:22:43	No events recorded. (Keyboard Exit) Geo: 1.70 mm/s



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2017-03

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 07/31/2017 10:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location:

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL				
Date:	07/31/17	Trigger Level:	1.23 mm/s	Off dB	Transverse:	2.413 mm/s	30.0 Hz
Time:	10:00	Calibration Date:	03/06/17		Vertical:	2.159 mm/s	47.0 Hz
Distance From Blast:	826.92 m	Calibration Signal:			Longitudinal:	2.286 mm/s	21.0 Hz
Direction From Blast:	NE	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	114 dB	
Location:	Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.				Vector Sum:	2.73 mm/s	
Lat./Long.:	45° 15' 59.300" N		76° 7' 28.700" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Wyatt Cliffton, Austin Powder						

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type:	No Trigger	Seismograph Type:	instanTEL				
Date:	07/31/17	Trigger Level:	1.23 mm/s	Off dB	Transverse:	--- mm/s	--- Hz
Time:	10:00	Calibration Date:	03/06/17		Vertical:	--- mm/s	--- Hz
Distance From Blast:	1,463.34 m	Calibration Signal:			Longitudinal:	--- mm/s	--- Hz
Direction From Blast:	E	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:		Mic. Min. Freq.:	2.0 Hz		Acoustic:	--- dB	
Location:	Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.				Vector Sum:	--- mm/s	
Lat./Long.:	45° 15' 27.900" N		76° 6' 50.100" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Wyatt Cliffton, Austin Powder						

**SEISMOGRAPH 3 - 3950 MARCH RD**

Data Type:	Seismic Record	Seismograph Type:	InstanTEL				
Date:	07/31/17	Trigger Level:	--- mm/s	--- dB	Transverse:	0.635 mm/s	26.0 Hz
Time:	10:00	Calibration Date:	03/06/17		Vertical:	0.635 mm/s	34.0 Hz
Distance From Blast:	1,097.28 m	Calibration Signal:			Longitudinal:	1.397 mm/s	18.0 Hz
Direction From Blast:	NNE	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	116 dB	
Location:	Set up in Driveway of 3950 march Rd. Geo spiked and wqeight bagged.				Vector Sum:	1.426 mm/s	
Lat./Long.:	45° 16' 10.000" N		76° 7' 28.000" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Wyatt Cliffton, Austin Powder						

No Trigger

Event Report: Monitor Log - MiniMate Plus # BE19637-Compliance

Start Time	End Time	Status
-----	-----	SERIAL NUMBER: BE19637
Jul 26 /17 12:14:13		Start Monitoring Trigger Level: Geo: 1.70 mm/s Mic: 114.0 dB(L)
Jul 26 /17 13:41:50	Jul 26 /17 13:42:06	Event recorded. Trigger Level Vert: 1.70 mm/s
Jul 26 /17 13:42:20		Start Monitoring Trigger Level: Geo: 1.70 mm/s Mic: 114.0 dB(L)
Jul 26 /17 13:43:08	Jul 26 /17 13:43:25	Event recorded. Trigger Level MicL: 114.0 dB(L)
Jul 26 /17 13:43:38	Jul 26 /17 14:37:00	No events recorded. (Keyboard Exit) Geo: 1.70 mm/s Mic: 114.0 dB(L)
Jul 31 /17 09:15:19	Jul 31 /17 10:44:14	No events recorded. (Keyboard Exit) Geo: 1.70 mm/s Mic: 114.0 dB(L)

**Date/Time** Long at 10:02:29 July 31, 2017  
**Trigger Source** Geo: 1.230 mm/s, Mic: 114.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 16.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** March 6, 2017 by InstanTel  
**File Name** Q589H03Y.K50

**Notes**

**Post Event Notes**  
 Set up in driveway of 3950 march Rd, geo spiked and weight bagged.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 116.1 dB(L) at 3.417 sec  
**ZC Freq** 12 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 482 mv )

	Tran	Vert	Long	
PPV	0.635	0.635	1.397	mm/s
ZC Freq	26	34	18	Hz
Time (Rel. to Trig)	-0.195	-0.245	0.141	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.005	0.005	0.014	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.8	7.9	7.8	Hz
Overswing Ratio	3.4	3.4	3.6	

**Peak Vector Sum** 1.426 mm/s at 0.143 sec

**USBM RI8507 And OSMRE**



**Date/Time** Vert at 10:02:15 July 31, 2017  
**Trigger Source** Geo: 1.200 mm/s, Mic: 103.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 15.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** March 6, 2017 by Instantel  
**File Name** Q020H03Y.JR0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 set up in driveway of 1550 Dwire Hill rd. Geo spiked and weight bagged.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 113.8 dB(L) at 2.198 sec  
**ZC Freq** 7.9 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 517 mv)

	Tran	Vert	Long	
PPV	2.413	2.159	2.286	mm/s
ZC Freq	30	47	21	Hz
Time (Rel. to Trig)	0.758	0.165	0.609	sec
Peak Acceleration	0.053	0.080	0.053	g
Peak Displacement	0.013	0.011	0.018	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.3	7.5	7.6	Hz
Overswing Ratio	3.9	3.6	3.6	

Peak Vector Sum 2.730 mm/s at 0.612 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**AUSTIN POWDER LTD.**  
**BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2017-04

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 08/01/2017 12:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location:

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instancel  
Date: 08/01/17 Trigger Level: 1.23 mm/s Off dB Transverse: 1.27 mm/s 16.0 Hz  
Time: 12:02 Calibration Date: 03/06/17 Vertical: 1.016 mm/s 18.0 Hz  
Distance From Blast: 1,576.73 m Calibration Signal: Longitudinal: 0.99 mm/s 27.0 Hz  
Direction From Blast: E Geophone Min. Freq.: 2.0 Hz PPV: --- mm/s --- Hz  
Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 116 dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged. Vector Sum: 1.54 mm/s  
Lat./Long.: 45° 15' 27.900" N 76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Cliffton, Austin Powder

**SEISMOGRAPH 2 - 3950 MARCH RD**

Data Type: Seismic Record Seismograph Type: Instantell  
Date: 08/01/17 Trigger Level: 1.70 mm/s 113.00 dB Transverse: 2.032 mm/s 18.0 Hz  
Time: 12:02 Calibration Date: 03/06/17 Vertical: 1.27 mm/s 20.0 Hz  
Distance From Blast: 1,135.08 m Calibration Signal: Longitudinal: 1.778 mm/s 18.0 Hz  
Direction From Blast: NNE Geophone Min. Freq.: 2.0 Hz PPV: --- mm/s --- Hz  
Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 113 dB  
Location: Set up in Driveway of 3950 march Rd. Geo spiked and wqeight bagged. Vector Sum: 2.416 mm/s  
Lat./Long.: 45° 16' 10.000" N 76° 7' 28.000" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm:

**SEISMOGRAPH 3 - 1550 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instancel  
Date: 08/01/17 Trigger Level: 1.23 mm/s Off dB Transverse: 2.667 mm/s 21.0 Hz  
Time: 12:02 Calibration Date: 03/06/17 Vertical: 1.651 mm/s 37.0 Hz  
Distance From Blast: 885.75 m Calibration Signal: Longitudinal: 3.429 mm/s 24.0 Hz  
Direction From Blast: NE Geophone Min. Freq.: 2.0 Hz PPV: --- mm/s --- Hz  
Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 119 dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged. Vector Sum: 3.49 mm/s  
Lat./Long.: 45° 15' 59.300" N 76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Cliffton, Austin Powder



Date/Time Vert at 12:02:46 August 1, 2017  
 Trigger Source Geo: 1.200 mm/s, Mic: 103.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 15.0 sec at 1024 sps

Serial Number BE15020 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.3 Volts  
 Unit Calibration March 6, 2017 by InstanTel  
 File Name Q020H05Y.SMO  
 Post Event Notes  
 Set up in driveway of 1550 Dwire Hill Rd, geo spiked and weight bagged.



Notes  
 Location:  
 Client:  
 User Name:  
 General:

Extended Notes

Microphone Linear Weighting  
 PSPL 118.6 dB(L) at 2.979 sec  
 ZC Freq 8.3 Hz  
 Channel Test Passed (Freq = 20.5 Hz Amp = 447 mv )

	Tran	Vert	Long	
PPV	2.667	1.651	3.429	mm/s
ZC Freq	21	37	24	Hz
Time (Rel. to Trig)	0.217	0.376	0.670	sec
Peak Acceleration	0.053	0.053	0.066	g
Peak Displacement	0.024	0.009	0.030	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.2	7.5	7.6	Hz
Overswing Ratio	3.9	3.5	3.7	

Peak Vector Sum 3.490 mm/s at 0.652 sec



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger = Sensor Check

Date/Time Tran at 12:03:02 August 1, 2017  
 Trigger Source Geo: 1.230 mm/s, Mic: 114.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 16.0 sec at 1024 sps

Serial Number BE15589 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.4 Volts  
 Unit Calibration March 6, 2017 by InstanTel  
 File Name Q589H05Y.T20  
 Post Event Notes  
 Set up in driveway at 1331 Drire Hill Rd. Geo spiked and weight bagged.

Notes



Extended Notes

Microphone Linear Weighting  
 PSPL 116.3 dB(L) at 3.115 sec  
 ZC Freq 24 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 438 mv)

	Tran	Vert	Long	
PPV	1.270	1.016	0.889	mm/s
ZC Freq	16	18	27	Hz
Time (Rel. to Trig)	0.000	0.107	-0.081	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.012	0.009	0.009	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.8	7.9	7.8	Hz
Overswing Ratio	3.4	3.3	3.5	

Peak Vector Sum 1.540 mm/s at 0.112 sec

USBM RI8507 And OSMRE



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

Date/Time Long at 12:02:38 August 1, 2017  
 Trigger Source Geo: 1.700 mm/s, Mic: 114.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 15.0 sec at 1024 sps

Serial Number BE19637 V 10.72-8.17 MiniMate Plus  
 Battery Level 6.5 Volts  
 Unit Calibration September 9, 2016 by InstanTel  
 File Name U637H05Y.SE0

Notes



Post Event Notes  
 Set up in driveway of 3950 March Rd. Geo spiked and weight bagged.

Microphone Linear Weighting  
 PSPL 112.8 dB(L) at 2.441 sec  
 ZC Freq 24 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 546 mv)

	Tran	Vert	Long	
PPV	2.032	1.270	1.778	mm/s
ZC Freq	18	20	18	Hz
Time (Rel. to Trig)	0.098	-0.022	0.001	sec
Peak Acceleration	0.040	0.027	0.027	g
Peak Displacement	0.017	0.016	0.022	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.4	7.4	7.5	Hz
Overswing Ratio	3.7	3.6	3.7	

Peak Vector Sum 2.416 mm/s at 0.100 sec

USBM R18507 And OSMRE



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger = [Symbol]

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2017-05

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 08/10/2017 13:07

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North Deep

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL				
Date:	08/10/17	Trigger Level:	1.23 mm/s	Off dB	Transverse:	1.297 mm/s	17.0 Hz
Time:	13:04	Calibration Date:	03/06/17		Vertical:	1.524 mm/s	15.0 Hz
Distance From Blast:	860.15 m	Calibration Signal:			Longitudinal:	1.27 mm/s	18.0 Hz
Direction From Blast:	NE	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	119 dB	
Location:	Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.				Vector Sum:	1.805 mm/s	
Lat./Long.:	45° 15' 59.300" N		76° 7' 28.700" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Wyatt Cliffton, Austin Powder						

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL				
Date:	08/10/17	Trigger Level:	1.23 mm/s	Off dB	Transverse:	4.191 mm/s	18.0 Hz
Time:	13:03	Calibration Date:	03/06/17		Vertical:	2.54 mm/s	43.0 Hz
Distance From Blast:	1,617.27 m	Calibration Signal:			Longitudinal:	3.937 mm/s	19.0 Hz
Direction From Blast:	ESE	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	128 dB	
Location:	Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.				Vector Sum:	4.49 mm/s	
Lat./Long.:	45° 15' 27.900" N		76° 6' 50.100" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Wyatt Cliffton, Austin Powder						

**SEISMOGRAPH 3 - 3950 MARCH RD**

Data Type:	Seismic Record	Seismograph Type:	InstanTEll				
Date:	08/10/17	Trigger Level:	1.70 mm/s	113.00 dB	Transverse:	0.508 mm/s	9.7 Hz
Time:	13:03	Calibration Date:	03/06/17		Vertical:	0.254 mm/s	57.0 Hz
Distance From Blast:	1,093.93 m	Calibration Signal:			Longitudinal:	0.381 mm/s	12.0 Hz
Direction From Blast:	NE	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	124 dB	
Location:	Set up in Driveway of 3950 march Rd. Geo spiked and wqeight bagged.				Vector Sum:	0.582 mm/s	
Lat./Long.:	45° 16' 10.000" N		76° 7' 28.000" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Wyatt Cliffton, Austin Powder						

# Event Report

**Date/Time** MicL at 13:03:53 August 10, 2017  
**Trigger Source** Geo: 1.700 mm/s, Mic: 114.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 15.0 sec at 1024 sps



**Serial Number** BE19637 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.4 Volts  
**Unit Calibration** September 9, 2016 by InstanTel  
**File Name** U637HOMP.MHO  
**Post Event Notes**  
 Set up in Driveway of 3950 March Rd. Geo spiked and weight bagged.

**Notes**

**Microphone** Linear Weighting  
**PSPL** 124.0 dB(L) at 0.011 sec  
**ZC Freq** 7.5 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 583 mv)

	Tran	Vert	Long	
PPV	0.508	0.254	0.381	mm/s
ZC Freq	9.7	57	12	Hz
Time (Rel. to Trig)	0.582	-0.226	-0.203	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.009	0.003	0.009	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.4	7.3	7.5	Hz
Overswing Ratio	3.7	3.7	3.7	

Peak Vector Sum 0.582 mm/s at 0.809 sec



Date/Time Tran at 13:04:29 August 10, 2017  
 Trigger Source Geo: 1.000 mm/s, Mic: 110.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 6.0 sec at 1024 sps

Serial Number BE15589 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.4 Volts  
 Unit Calibration March 6, 2017 by InstanTel  
 File Name Q589HOMP.NH0  
 Post Event Notes  
 Set up at gate of 1550 Drire Hill Rd. Geo spiked and weight bagged.



Notes

Extended Notes

Microphone Linear Weighting  
 PSPL 119.0 dB(L) at 3.855 sec  
 ZC Freq 6.4 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 495 mv)

	Tran	Vert	Long	
PPV	1.397	1.524	1.270	mm/s
ZC Freq	17	15	18	Hz
Time (Rel. to Trig)	0.040	5.573	0.032	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.017	0.016	0.014	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.9	7.8	7.7	Hz
Overswing Ratio	3.4	3.3	3.6	

Peak Vector Sum 1.805 mm/s at 0.040 sec



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger = <math>\blacktriangleleft</math>

Sensor Check

# Event Report

**Date/Time** Vert at 13:03:58 August 10, 2017  
**Trigger Source** Geo: 1.000 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** March 6, 2017 by InstanTel  
**File Name** Q020HOMP.MMO  
**Post Event Notes**  
 Set up in driveway of 1331 Drire Hill Rd

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 127.7 dB(L) at 2.273 sec  
**ZC Freq** 7.5 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 539 mv)

	Tran	Vert	Long	
PPV	4.191	2.540	3.937	mm/s
ZC Freq	18	43	19	Hz
Time (Rel. to Trig)	0.506	0.396	0.734	sec
Peak Acceleration	0.093	0.080	0.066	g
Peak Displacement	0.037	0.014	0.041	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.2	7.5	7.4	Hz
Overswing Ratio	3.9	3.5	3.6	

Peak Vector Sum 4.490 mm/s at 0.488 sec

**USBM RI8507 And OSMRE**





**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2017-06

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 09/13/2017 12:50

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location:

**SEISMOGRAPH 1 - 1331 UPPER DWYERHILL RD**

Data Type:	Seismic Record	Seismograph Type:	Instantel				
Date:	09/13/17	Trigger Level:	1.23 mm/s	---	dB	Transverse:	1.397 mm/s 20.0 Hz
Time:	12:46	Calibration Date:	03/06/17			Vertical:	1.27 mm/s 23.0 Hz
Distance From Blast:	1,662.38 m	Calibration Signal:				Longitudinal:	1.016 mm/s 24.0 Hz
Direction From Blast:	ESE	Geophone Min. Freq.:	---	Hz		PPV:	---
Readout:	Printed Copy	Mic. Min. Freq.:	---	Hz		Acoustic:	116 dB
Location:	1331 Upper DwyerHill Rd					Vector Sum:	1.529 mm/s
U.T.M.:	18N 412595 mE 5012191 mN						
Reader and Firm:	Dave Klingspor, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:							

**SEISMOGRAPH 2 - 1550 UPPER DWYERHILL RD**

Data Type:	Seismic Record	Seismograph Type:	Instantel				
Date:	09/13/17	Trigger Level:	1.23 mm/s	112.00	dB	Transverse:	2.413 mm/s 16.0 Hz
Time:	12:49	Calibration Date:	03/06/17			Vertical:	1.905 mm/s 51.0 Hz
Distance From Blast:	30,479.70 m	Calibration Signal:				Longitudinal:	3.683 mm/s 23.0 Hz
Direction From Blast:	SE	Geophone Min. Freq.:	---	Hz		PPV:	---
Readout:	Printed Copy	Mic. Min. Freq.:	---	Hz		Acoustic:	122 dB
Location:	1550 Upper DwyerHill Rd					Vector Sum:	4.107 mm/s
U.T.M.:	18N 5013178 mE 411774 mN						
Reader and Firm:	Dave Klingspor, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:							

**SEISMOGRAPH 3 - 3950 MARCH RD**

Data Type:	Seismic Record	Seismograph Type:	Instantel					
Date:	09/13/17	Trigger Level:	---	mm/s	---	dB	Transverse:	0.127 mm/s 0.0 Hz
Time:	12:49	Calibration Date:	09/09/16			Vertical:	0.381 mm/s 14.0 Hz	
Distance From Blast:	1,103.07 m	Calibration Signal:				Longitudinal:	0.508 mm/s 9.1 Hz	
Direction From Blast:	NE	Geophone Min. Freq.:	---	Hz		PPV:	---	
Readout:	Printed Copy	Mic. Min. Freq.:	---	Hz		Acoustic:	117 dB	
Location:	3950 March Rd					Vector Sum:	0.524 mm/s	
U.T.M.:	18N 411792 mE 5013511 mN							
Reader and Firm:	Dave Klingspor, AUSTIN POWDER							
Analyst and Firm:								
Installer and Firm:								



**Date/Time** MicL at 12:49:42 PM September 13, 2017  
**Trigger Source** Geo: 1.700 mm/s, Mic: 114.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE19637 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** September 9, 2016 by InstanTel  
**File Name** \_\_TEMP.EVT



**Notes**

**Microphone** Linear Weighting  
**PSPL** 117.2 dB(L) at 0.013 sec  
**ZC Freq** 7.3 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 493 mv)

	Tran	Vert	Long	
PPV	0.127	0.381	0.508	mm/s
ZC Freq	>100	14	9.1	Hz
Time (Rel. to Trig)	-0.249	-0.034	0.508	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.000	0.007	0.009	mm
<b>Sensor Check</b>	Check	Passed	Passed	
Frequency	18.6	7.4	7.7	Hz
Overswing Ratio	2.8	3.7	3.6	

**Peak Vector Sum** 0.524 mm/s at 0.508 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

Date/Time Tran at 12:46:46 PM September 13, 2017  
 Trigger Source Geo: 1.230 mm/s  
 Range Geo: 254.0 mm/s  
 Record Time 6.0 sec at 1024 sps

Serial Number BE15589 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.3 Volts  
 Unit Calibration March 6, 2017 by InstanTel  
 File Name \_TEMP.EVT

**Notes**



**Extended Notes**

Microphone Linear Weighting  
 PSPL 115.6 dB(L) at 4.152 sec  
 ZC Freq 9.0 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 510 mv)

	Tran	Vert	Long	
PPV	1.397	1.270	1.016	mm/s
ZC Freq	20	23	24	Hz
Time (Rel. to Trig)	0.531	0.211	0.164	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.015	0.010	0.013	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.9	7.8	Hz
Overswing Ratio	3.4	3.4	3.6	

Peak Vector Sum 1.529 mm/s at 0.338 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =  $\blacktriangleleft$   $\blacktriangleright$

Sensor Check

**Date/Time** Vert at 12:49:11 PM September 13, 2017  
**Trigger Source** Geo: 1.230 mm/s, Mic: 112.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** March 6, 2017 by InstanTel  
**File Name** \_\_TEMP.EVT

**Notes**

Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 122.3 dB(L) at 2.174 sec  
**ZC Freq** 7.1 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 494 mv )

	Tran	Vert	Long	
PPV	2.413	1.905	3.683	mm/s
ZC Freq	16	51	23	Hz
Time (Rel. to Trig)	0.643	0.549	0.638	sec
Peak Acceleration	0.040	0.066	0.066	g
Peak Displacement	0.026	0.009	0.024	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.3	7.5	7.5	Hz
Overswing Ratio	3.8	3.6	3.6	

Peak Vector Sum 4.107 mm/s at 0.638 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2017-07

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 09/25/2017 15:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: March Rd Lower Bench

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL				
Date:	09/25/17	Trigger Level:	1.23 mm/s	Off dB	Transverse:	2.794 mm/s	32.0 Hz
Time:	15:00	Calibration Date:	03/06/17		Vertical:	1.905 mm/s	43.0 Hz
Distance From Blast:	767.79 m	Calibration Signal:			Longitudinal:	1.524 mm/s	34.0 Hz
Direction From Blast:	NE	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	112 dB	
Location:	Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.				Vector Sum:	2.927 mm/s	
Lat./Long.:	45° 15' 59.300" N		76° 7' 28.700" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Wyatt Clifton, Austin Powder						

**SEISMOGRAPH 2 - 3950 MARCH RD**

Data Type:	Seismic Record	Seismograph Type:	InstanTEll				
Date:	09/25/17	Trigger Level:	1.70 mm/s	113.00 dB	Transverse:	0.254 mm/s	--- Hz
Time:	15:00	Calibration Date:	03/06/17		Vertical:	0.127 mm/s	--- Hz
Distance From Blast:	1,033.58 m	Calibration Signal:			Longitudinal:	0.254 mm/s	--- Hz
Direction From Blast:	NNE	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	113 dB	
Location:	Set up in Driveway of 3950 march Rd. Geo spiked and wqeight bagged.				Vector Sum:	0.311 mm/s	
Lat./Long.:	45° 16' 10.000" N		76° 7' 28.000" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Wyatt Clifton, Austin Powder						

**SEISMOGRAPH 3 - 1331 DWIRE HILL RD**

Data Type:	No Trigger	Seismograph Type:	instanTEL				
Date:	09/25/17	Trigger Level:	1.23 mm/s	Off dB	Transverse:	--- mm/s	--- Hz
Time:	15:00	Calibration Date:	03/06/17		Vertical:	--- mm/s	--- Hz
Distance From Blast:	1,459.69 m	Calibration Signal:			Longitudinal:	--- mm/s	--- Hz
Direction From Blast:	ESE	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:		Mic. Min. Freq.:	2.0 Hz		Acoustic:	--- dB	
Location:	Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.				Vector Sum:	--- mm/s	
Lat./Long.:	45° 15' 27.900" N		76° 6' 50.100" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Wyatt Clifton, Austin Powder						

False Trigger

Event Report: Monitor Log - Minimate Blaster # BE15589-Compliance

Start Time	End Time	Status
		SERIAL NUMBER: BE15589
Sep 14 /17 13:22:19	Sep 14 /17 15:10:54	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s
Sep 15 /17 11:32:11	Sep 15 /17 13:34:53	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s
Sep 18 /17 12:11:11		Start Monitoring Trigger Level: Geo: 1.23 mm/s
Sep 18 /17 12:57:16	Sep 18 /17 12:57:22	Event recorded. Trigger Level Tran: 1.23 mm/s
Sep 18 /17 12:57:36	Sep 18 /17 13:25:17	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s
Sep 19 /17 11:16:20		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 110.0 dB(L)
Sep 19 /17 12:02:42	Sep 19 /17 12:02:48	Event recorded. Trigger Level Tran: 1.23 mm/s
Sep 19 /17 12:03:01	Sep 19 /17 12:17:43	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 110.0 dB(L)
Sep 25 /17 14:11:50		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 110.0 dB(L)
Sep 25 /17 14:11:55	Sep 25 /17 14:12:01	Event recorded. Trigger Level Vert: 1.23 mm/s
Sep 25 /17 14:12:14		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 110.0 dB(L)
Sep 25 /17 14:45:38	Sep 25 /17 14:45:44	Event recorded. Trigger Level Vert: 1.23 mm/s
Sep 25 /17 14:45:58		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 110.0 dB(L)
Sep 25 /17 15:18:54	Sep 25 /17 15:19:00	Event recorded. Trigger Level Vert: 1.23 mm/s
Sep 25 /17 15:19:13	Sep 25 /17 15:22:11	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 110.0 dB(L)

Date/Time MicL at 15:01:01 September 25, 2017  
 Trigger Source Geo: 1.700 mm/s, Mic: 110.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 5.0 sec at 1024 sps



Serial Number BE19637 V 10.72-8.17 MiniMate Plus  
 Battery Level 6.5 Volts  
 Unit Calibration September 21, 2017 by InstanTel  
 File Name U637H301.PP0  
 Post Event Notes  
 Set up 3950 March Rd. Geo spiked and weight bagged.

Notes

Microphone Linear Weighting  
 PSPL 113.1 dB(L) at 0.006 sec  
 ZC Freq 11 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 472 mv)

	Tran	Vert	Long	
PPV	0.254	0.127	0.254	mm/s
ZC Freq	>100	>100	>100	Hz
Time (Rel. to Trig)	-0.093	-0.235	-0.132	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.000	0.000	0.000	mm
Sensor Check	Passed	Passed	Check	
Frequency	7.5	7.4	8.5	Hz
Overswing Ratio	3.6	3.6	3.4	
Peak Vector Sum	0.311 mm/s at -0.034 sec			

USBM RI8507 And OSMRE



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =  $\blacktriangleleft$

Sensor Check

Date/Time Tran at 15:00:18 September 25, 2017  
 Trigger Source Geo: 1.230 mm/s, Mic: 112.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 6.0 sec at 1024 sps

Serial Number BE15020 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.2 Volts  
 Unit Calibration March 6, 2017 by InstanTel  
 File Name Q020H301.O10  
 Post Event Notes  
 Set up at 1550 Dwire Hill Rd. Geo spiked and weight bagged.

Notes

Location:  
 Client:  
 User Name:  
 General:



Extended Notes

Microphone Linear Weighting  
 PSPL 111.8 dB(L) at 2.123 sec  
 ZC Freq 7.4 Hz  
 Channel Test Passed (Freq = 20.5 Hz Amp = 503 mv )

	Tran	Vert	Long	
PPV	2.794	1.905	1.524	mm/s
ZC Freq	32	43	34	Hz
Time (Rel. to Trig)	0.290	0.109	0.191	sec
Peak Acceleration	0.066	0.066	0.040	g
Peak Displacement	0.019	0.008	0.012	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.2	7.5	7.4	Hz
Overswing Ratio	3.9	3.5	3.6	

Peak Vector Sum 2.927 mm/s at 0.830 sec

USBM RI8507 And OSMRE



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger = <--->

Sensor Check

**AUSTIN POWDER LTD.**  
**BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2018-08

Blast Type: Stone Quarry/Stone Mine - Development/  
Site Development

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 10/04/2017 13:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: Lower level, near scale  
house.

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instancel  
Date: 10/04/17      Trigger Level: 1.23 mm/s      Off dB      Transverse: --- mm/s      --- Hz  
Time: 13:00      Calibration Date: 03/06/17      Vertical: --- mm/s      --- Hz  
Distance From Blast: 1,499.62 m      Calibration Signal:      Longitudinal: --- mm/s      --- Hz  
Direction From Blast: ESE      Geophone Min. Freq.: 2.0 Hz      PPV: --- mm/s      --- Hz  
Readout:      Mic. Min. Freq.: 2.0 Hz      Acoustic: --- dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.      Vector Sum: --- mm/s  
Lat./Long.: 45° 15' 27.900" N      76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record      Seismograph Type: instancel  
Date: 10/04/17      Trigger Level: 1.23 mm/s      Off dB      Transverse: 1.905 mm/s      37.0 Hz  
Time: 13:00      Calibration Date: 03/06/17      Vertical: 1.397 mm/s      51.0 Hz  
Distance From Blast: 742.80 m      Calibration Signal:      Longitudinal: 2.159 mm/s      32.0 Hz  
Direction From Blast: NE      Geophone Min. Freq.: 2.0 Hz      PPV: --- mm/s      --- Hz  
Readout: Printed Copy      Mic. Min. Freq.: 2.0 Hz      Acoustic: 110 dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.      Vector Sum: 2.366 mm/s  
Lat./Long.: 45° 15' 59.300" N      76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**SEISMOGRAPH 3 - 3950 MARCH RD**

Data Type: Seismic Record      Seismograph Type: Instancell  
Date: 10/04/17      Trigger Level: 1.70 mm/s      113.00 dB      Transverse: 0.127 mm/s      --- Hz  
Time: 13:00      Calibration Date: 03/06/17      Vertical: 0.127 mm/s      --- Hz  
Distance From Blast: 995.48 m      Calibration Signal:      Longitudinal: 0.254 mm/s      --- Hz  
Direction From Blast: NNE      Geophone Min. Freq.: 2.0 Hz      PPV: --- mm/s      --- Hz  
Readout: Printed Copy      Mic. Min. Freq.: 2.0 Hz      Acoustic: 115 dB  
Location: Set up in Driveway of 3950 march Rd. Geo spiked and wqeight bagged.      Vector Sum: 0.254 mm/s  
Lat./Long.: 45° 16' 10.000" N      76° 7' 28.000" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder



No Trigger

Event Report: Monitor Log - Minimate Blaster # BE15589-Compliance

Start Time	End Time	Status
		SERIAL NUMBER: BE15589
Oct 4 /17 12:15:46		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 110.0 dB(L)
Oct 4 /17 12:15:48	Oct 4 /17 12:15:54	Event recorded. Trigger Level Vert: 1.23 mm/s
Oct 4 /17 12:16:08		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 110.0 dB(L)
Oct 4 /17 12:52:41	Oct 4 /17 12:52:47	Event recorded. Trigger Level Vert: 1.23 mm/s
Oct 4 /17 12:53:01		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 110.0 dB(L)
Oct 4 /17 13:17:07	Oct 4 /17 13:17:13	Event recorded. Trigger Level Vert: 1.23 mm/s
Oct 4 /17 13:17:27	Oct 4 /17 13:22:31	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 110.0 dB(L)

Date/Time MicL at 13:01:05 October 4, 2017  
 Trigger Source Geo: 1.700 mm/s, Mic: 110.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 5.0 sec at 1024 sps

Serial Number BE19637 V 10.72-8.17 MiniMate Plus  
 Battery Level 6.4 Volts  
 Unit Calibration September 21, 2017 by InstanTel  
 File Name U637H3GK.5T0

Notes



Post Event Notes  
 Set up at 3950 March Road in driveway. geo spiked and weight bagged.

Microphone Linear Weighting  
 PSPL 115.0 dB(L) at 2.025 sec  
 ZC Freq 7.5 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 582 mv)

	Tran	Vert	Long	
PPV	0.127	0.127	0.254	mm/s
ZC Freq	>100	>100	>100	Hz
Time (Rel. to Trig)	-0.249	-0.248	2.868	sec
Peak Acceleration	0.013	0.013	0.013	g
Peak Displacement	0.000	0.000	0.000	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.6	7.4	7.6	Hz
Overswing Ratio	3.6	3.6	3.7	

Peak Vector Sum 0.254 mm/s at 2.868 sec

USBM R18507 And OSMRE



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

Date/Time Tran at 12:59:06 October 4, 2017  
 Trigger Source Geo: 1.230 mm/s, Mic: 112.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 6.0 sec at 1024 sps

Serial Number BE15020 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.2 Volts  
 Unit Calibration March 6, 2017 by InstanTel  
 File Name Q020H3GK.210  
 Post Event Notes  
 Set up at 1550 Drire Hill Rd. Geo spiked and weight bagged.

Notes  
 Location:  
 Client:  
 User Name:  
 General:



Extended Notes

Microphone Linear Weighting  
 PSPL 110.2 dB(L) at 1.917 sec  
 ZC Freq 23 Hz  
 Channel Test Passed (Freq = 20.5 Hz Amp = 596 mv )

	Tran	Vert	Long	
PPV	1.905	1.397	2.159	mm/s
ZC Freq	37	51	32	Hz
Time (Rel. to Trig)	0.443	0.513	0.647	sec
Peak Acceleration	0.040	0.053	0.053	g
Peak Displacement	0.012	0.009	0.013	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.4	7.6	7.5	Hz
Overswing Ratio	4.0	3.6	3.7	

Peak Vector Sum 2.366 mm/s at 0.648 sec

USBM RI8507 And OSMRE



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-01

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 03/14/2018 14:45

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location:

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 03/14/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: 0.726 mm/s    28.0 Hz  
Time: 14:31    Calibration Date: 09/21/17    Vertical: 0.381 mm/s    51.0 Hz  
Distance From Blast: 990.90 m    Calibration Signal:    Longitudinal: 1.27 mm/s    27.0 Hz  
Direction From Blast: NNE    Geophone Min. Freq.: 2.0 Hz    PPV: --- mm/s    --- Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 108 dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on snowy wet ground.    Vector Sum: 1.291 mm/s  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger    Seismograph Type: instancel  
Date: 03/14/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: --- mm/s    --- Hz  
Time: 14:31    Calibration Date: 10/27/17    Vertical: --- mm/s    --- Hz  
Distance From Blast: 1,351.79 m    Calibration Signal:    Longitudinal: --- mm/s    --- Hz  
Direction From Blast: E    Geophone Min. Freq.: 2.0 Hz    PPV: --- mm/s    --- Hz  
Readout:    Mic. Min. Freq.: 2.0 Hz    Acoustic: --- dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: --- mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

No Trigger  
Set up at end of driveway of 1331 Dwire Hill Rd  
Wiegth bagged on wet ground

Event Report: Monitor Log - Minimate Blaster # BE15589-Compliance

Start Time	End Time	Status
-----	-----	SERIAL NUMBER: BE15589
Mar 13 /18 13:50:42		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 13 /18 13:50:46	Mar 13 /18 13:50:51	Event recorded. (Keyboard Exit) Trigger Level Vert: 1.23 mm/s
Mar 14 /18 13:36:41		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 14 /18 13:55:24	Mar 14 /18 13:55:29	Event recorded. Trigger Level Tran: 1.23 mm/s
Mar 14 /18 13:55:42		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 14 /18 14:19:40	Mar 14 /18 14:19:45	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 14 /18 14:19:59	Mar 14 /18 14:48:53	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 119.0 dB(L)

**Date/Time** Long at 14:31:34 March 14, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19637 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.4 Volts  
**Unit Calibration** September 21, 2017 by InstanTel  
**File Name** U637HBQT.OM0

**Notes**

**Post Event Notes**



Set up at end of driveway of 1550 Dwire Hill Rd. Geo spiked and weight bagged on snowy, wet ground.

**Microphone** Linear Weighting  
**PSPL** 108.4 dB(L) at 2.856 sec  
**ZC Freq** 3.5 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 769 mv )

	Tran	Vert	Long	
PPV	0.762	0.381	1.270	mm/s
ZC Freq	28	51	27	Hz
Time (Rel. to Trig)	-0.126	-0.235	0.000	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.005	0.003	0.007	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.4	7.4	7.8	Hz
Overswing Ratio	3.9	3.9	3.8	

**Peak Vector Sum** 1.391 mm/s at 0.000 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2018-02

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 03/16/2018 10:20

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: West Wall, short bench

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: False Trigger    Seismograph Type: instancel  
Date: 03/16/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: 0.127 mm/s    --- Hz  
Time: 10:05    Calibration Date: 09/21/17    Vertical: 0.127 mm/s    --- Hz  
Distance From Blast: 969.57 m    Calibration Signal:    Longitudinal: 0.127 mm/s    --- Hz  
Direction From Blast: NNE    Geophone Min. Freq.: 2.0 Hz    PPV: --- mm/s    --- Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 119 dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on snowy wet ground. False Trigger, triggered 15mins before blast.    Vector Sum: 0.22 mm/s  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger    Seismograph Type: instancel  
Date: 03/16/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: --- mm/s    --- Hz  
Time: 10:20    Calibration Date: 10/27/17    Vertical: --- mm/s    --- Hz  
Distance From Blast: 1,380.44 m    Calibration Signal:    Longitudinal: --- mm/s    --- Hz  
Direction From Blast: E    Geophone Min. Freq.: 2.0 Hz    PPV: --- mm/s    --- Hz  
Readout:    Mic. Min. Freq.: 2.0 Hz    Acoustic: --- dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: --- mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

No Trigger  
False Trigger, very windy cold day.  
Wiegth bagged on wet ground

Event Report: Monitor Log - MiniMate Plus # BE19637-Compliance

Start Time	End Time	Status
		SERIAL NUMBER: BE19637
Mar 15 /18 11:12:26	Mar 15 /18 12:28:07	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 09:17:47		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 09:20:26	Mar 16 /18 09:20:31	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 16 /18 09:20:45		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 09:22:34	Mar 16 /18 09:22:39	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 16 /18 09:22:53		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 09:46:02	Mar 16 /18 09:46:07	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 16 /18 09:46:21		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 09:48:29	Mar 16 /18 09:48:34	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 16 /18 09:48:48		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 09:49:37	Mar 16 /18 09:49:42	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 16 /18 09:49:55		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 09:56:08	Mar 16 /18 09:56:13	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 16 /18 09:56:26		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 09:57:03	Mar 16 /18 09:57:08	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 16 /18 09:57:22		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 10:00:47	Mar 16 /18 10:00:53	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 16 /18 10:01:06		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 10:02:29	Mar 16 /18 10:02:34	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 16 /18 10:02:47		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Mar 16 /18 10:04:26	Mar 16 /18 10:04:31	Event recorded. Trigger Level MicL: 119.0 dB(L)
Mar 16 /18 10:04:45	Mar 16 /18 10:35:39	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 119.0 dB(L)



Date/Time MicL at 10:05:29 March 16, 2018  
Trigger Source Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
Range Geo: 254.0 mm/s  
Record Time 5.0 sec at 1024 sps

Serial Number BE15589 V 10.72-1.1 Minimate Blaster  
Battery Level 6.3 Volts  
Unit Calibration October 27, 2017 by Instantel  
File Name Q589HBU6.P50

Notes

Post Event Notes

Set up on roadside of 1550 Dwire Hill Rd  
False Trigger, set up on roadside, possible snow plow, very cold and windy day.



Extended Notes

Microphone Linear Weighting  
PSPL 119.3 dB(L) at 0.001 sec  
ZC Freq 6.6 Hz  
Channel Test Passed (Freq = 20.1 Hz Amp = 740 mv )

	Tran	Vert	Long	
PPV	0.127	0.127	0.127	mm/s
ZC Freq	>100	>100	>100	Hz
Time (Rel. to Trig)	-0.234	-0.083	-0.247	sec
Peak Acceleration	0.027	0.027	0.013	g
Peak Displacement	0.000	0.000	0.000	mm
Sensor Check	Check	Passed	Passed	
Frequency	9.9	7.9	7.8	Hz
Overswing Ratio	4.9	3.6	3.9	

Peak Vector Sum 0.220 mm/s at -0.063 sec

USBM RI8507 And OSMRE



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
Trigger = >-----<

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-03

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 04/02/2018 16:30

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: Lower Bench

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instancel

Date: 04/02/18 Trigger Level: 1.23 mm/s Off dB Transverse: 0.127 mm/s --- Hz

Time: 16:19 Calibration Date: 09/21/17 Vertical: 0.127 mm/s --- Hz

Distance From Blast: 1,004.01 m Calibration Signal: Longitudinal: 0.127 mm/s --- Hz

Direction From Blast: NNE Geophone Min. Freq.: 2.0 Hz PPV: --- mm/s --- Hz

Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 119 dB

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on frozen ground. Vector Sum: 0.22 mm/s

Lat./Long.: 45° 15' 59.300" N 76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Wyatt Clifton, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger Seismograph Type: instancel

Date: 04/02/18 Trigger Level: 1.23 mm/s Off dB Transverse: --- mm/s --- Hz

Time: 16:30 Calibration Date: 10/27/17 Vertical: --- mm/s --- Hz

Distance From Blast: 1,422.50 m Calibration Signal: Longitudinal: --- mm/s --- Hz

Direction From Blast: E Geophone Min. Freq.: 2.0 Hz PPV: --- mm/s --- Hz

Readout: Mic. Min. Freq.: 2.0 Hz Acoustic: --- dB

Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged. frozen ground. Vector Sum: --- mm/s

Lat./Long.: 45° 15' 27.900" N 76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Wyatt Clifton, Austin Powder

No Trigger  
Set up at 1331 Drire Hill rd  
Wieght bagged on frozen ground, near Rd

Event Report: Monitor Log - MiniMate Plus # BE19637-Compliance

Start Time	End Time	Status
-----	-----	SERIAL NUMBER: BE19637
Apr 2 /18 12:09:54		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Apr 2 /18 12:28:33	Apr 2 /18 12:28:38	Event recorded. Trigger Level Tran: 1.23 mm/s
Apr 2 /18 12:28:51	Apr 2 /18 12:39:54	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 119.0 dB(L)
Apr 2 /18 15:37:51	Apr 2 /18 16:46:58	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 119.0 dB(L)
Apr 3 /18 09:35:55	Apr 3 /18 10:37:25	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 119.0 dB(L)

**Date/Time** MicL at 16:29:45 April 2, 2018  
**Trigger Source** Geo: 1.100 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19638 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.2 Volts  
**Unit Calibration** February 5, 2018 by Instantel  
**File Name** U638HCQ5.TLO

**Notes**  
Location:  
Client:  
User Name:  
General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 119.4 dB(L) at 0.118 sec  
**ZC Freq** 26 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 717 mv )

	Tran	Vert	Long	
PPV	0.127	0.127	0.127	mm/s
ZC Freq	>100	>100	N/A	Hz
Time (Rel. to Trig)	0.020	-0.188	-0.250	sec
Peak Acceleration	0.013	0.013	0.013	g
Peak Displacement	0.000	0.000	0.000	mm
Sensor Check	Check	Passed	Passed	
Frequency	44.5	7.6	7.5	Hz
Overswing Ratio	2.0	3.7	3.9	

**Peak Vector Sum** 0.220 mm/s at 2.789 sec  
N/A: Not Applicable

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**AUSTIN POWDER LTD.**  
**BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-04

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 04/03/2018 10:15

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: Lower Bench

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instancel  
Date: 04/03/18      Trigger Level: 1.23 mm/s      Off dB      Transverse: --- mm/s      --- Hz  
Time: 10:15      Calibration Date: 09/21/17      Vertical: --- mm/s      --- Hz  
Distance From Blast: 929.64 m      Calibration Signal:      Longitudinal: --- mm/s      --- Hz  
Direction From Blast: NNE      Geophone Min. Freq.: 2.0 Hz      PPV: --- mm/s      --- Hz  
Readout:      Mic. Min. Freq.: 2.0 Hz      Acoustic: --- dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on frozen ground.      Vector Sum: --- mm/s  
Lat./Long.: 45° 15' 59.300" N      76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instancel  
Date: 04/03/18      Trigger Level: 1.23 mm/s      Off dB      Transverse: --- mm/s      --- Hz  
Time: 10:15      Calibration Date: 10/27/17      Vertical: --- mm/s      --- Hz  
Distance From Blast: 1,434.69 m      Calibration Signal:      Longitudinal: --- mm/s      --- Hz  
Direction From Blast: E      Geophone Min. Freq.: 2.0 Hz      PPV: --- mm/s      --- Hz  
Readout:      Mic. Min. Freq.: 2.0 Hz      Acoustic: --- dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged. frozen ground.      Vector Sum: --- mm/s  
Lat./Long.: 45° 15' 27.900" N      76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2018-05

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 05/22/2018 13:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North Wall

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instancel  
Date: 05/22/18 Trigger Level: 1.23 mm/s Off dB Transverse: 3.556 mm/s 16.0 Hz  
Time: 12:56 Calibration Date: 09/21/17 Vertical: 1.397 mm/s 20.0 Hz  
Distance From Blast: 925.98 m Calibration Signal: Longitudinal: 3.683 mm/s 22.0 Hz  
Direction From Blast: NE Geophone Min. Freq.: 2.0 Hz PPV: --- mm/s --- Hz  
Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 116 dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on frozen ground. Vector Sum: 4.113 mm/s  
Lat./Long.: 45° 15' 59.300" N 76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instancel  
Date: 05/22/18 Trigger Level: 1.23 mm/s Off dB Transverse: 1.397 mm/s 21.0 Hz  
Time: 12:58 Calibration Date: 10/27/17 Vertical: 1.016 mm/s 27.0 Hz  
Distance From Blast: 1,647.75 m Calibration Signal: Longitudinal: 1.143 mm/s 15.0 Hz  
Direction From Blast: E Geophone Min. Freq.: 2.0 Hz PPV: --- mm/s --- Hz  
Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 117 dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged. frozen ground. Vector Sum: 1.454 mm/s  
Lat./Long.: 45° 15' 27.900" N 76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**SEISMOGRAPH 3 - 3950 MARCH RD**

Data Type: Seismic Record Seismograph Type: Instantell  
Date: 05/22/18 Trigger Level: 1.70 mm/s 113.00 dB Transverse: 1.524 mm/s 11.0 Hz  
Time: 12:52 Calibration Date: 09/21/17 Vertical: 1.016 mm/s 16.0 Hz  
Distance From Blast: 1,161.29 m Calibration Signal: Longitudinal: 1.651 mm/s 17.0 Hz  
Direction From Blast: NE Geophone Min. Freq.: 2.0 Hz PPV: --- mm/s --- Hz  
Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 113 dB  
Location: Set up in Driveway of 3950 march Rd. Geo spiked and wqeight bagged. Vector Sum: 1.823 mm/s  
Lat./Long.: 45° 16' 10.000" N 76° 7' 28.000" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**Date/Time** Tran at 12:58:16 May 22, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** October 27, 2017 by InstanTel  
**File Name** Q589HFAH.D40

**Post Event Notes**

Set up at end of driveway of 1331 Dwire Hill rd. Geo spiked and weight bagged.

**Notes**



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 116.9 dB(L) at 3.958 sec  
**ZC Freq** 12 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 582 mv )

	Tran	Vert	Long	
PPV	1.397	1.016	1.143	mm/s
ZC Freq	21	27	15	Hz
Time (Rel. to Trig)	0.002	-0.106	0.188	sec
Peak Acceleration	0.027	0.040	0.027	g
Peak Displacement	0.011	0.007	0.013	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.9	7.8	Hz
Overswing Ratio	3.5	3.4	3.6	

**Peak Vector Sum** 1.454 mm/s at 0.002 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:56:42 May 22, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** March 19, 2018 by InstanTel  
**File Name** Q020HFAH.AIO

**Notes**

Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**

Set up in front yard of 1550 Dwire Hill Rd. Geo spiked and weight bagged on wet lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 116.1 dB(L) at 2.240 sec  
**ZC Freq** 9.1 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 576 mv)

	Tran	Vert	Long	
PPV	3.556	1.397	3.683	mm/s
ZC Freq	16	20	22	Hz
Time (Rel. to Trig)	0.730	0.479	0.693	sec
Peak Acceleration	0.040	0.040	0.066	g
Peak Displacement	0.035	0.015	0.025	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.2	7.5	7.3	Hz
Overswing Ratio	3.9	3.6	3.8	

Peak Vector Sum 4.113 mm/s at 0.694 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check



**Date/Time** Tran at 12:52:55 May 22, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19637 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.4 Volts  
**Unit Calibration** September 21, 2017 by InstanTel  
**File Name** U637HFAH.470

**Notes**



**Post Event Notes**  
 Set up at end of driveway of 3950 March Rd. Geo spiked and weight bagged on thick ditch grass.

**Microphone** Linear Weighting  
**PSPL** 113.3 dB(L) at 2.806 sec  
**ZC Freq** 9.0 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 534 mv )

	Tran	Vert	Long	
PPV	1.524	1.016	1.651	mm/s
ZC Freq	11	16	17	Hz
Time (Rel. to Trig)	0.290	0.071	0.351	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.019	0.016	0.014	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.6	7.4	7.5	Hz
Overswing Ratio	3.6	3.7	3.7	

**Peak Vector Sum** 1.823 mm/s at 0.353 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

# AUSTIN POWDER LTD.

## BLAST REPORT



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2018-06

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: <sup>28</sup>05/29/2018 17:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West High Wall

### SEISMOGRAPH 1 - 1550 DWIRE HILL RD

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 05/29/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: 3.048 mm/s    18.0 Hz  
Time: 17:11    Calibration Date: 09/21/17    Vertical: 2.286 mm/s    28.0 Hz  
Distance From Blast: 949.15 m    Calibration Signal:    Longitudinal: 4.826 mm/s    20.0 Hz  
Direction From Blast: NE    Geophone Min. Freq.: 2.0 Hz    PPV: --- mm/s    --- Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 116 dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on frozen ground.    Vector Sum: 5.145 mm/s  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

### SEISMOGRAPH 2 - 1331 DWIRE HILL RD

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 05/29/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: 1.524 mm/s    20.0 Hz  
Time: 17:13    Calibration Date: 10/27/17    Vertical: 1.524 mm/s    28.0 Hz  
Distance From Blast: 1,669.08 m    Calibration Signal:    Longitudinal: 1.016 mm/s    21.0 Hz  
Direction From Blast: E    Geophone Min. Freq.: 2.0 Hz    PPV: --- mm/s    --- Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 115 dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged. frozen ground.    Vector Sum: 1.871 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**Date/Time** Long at 17:11:39 May 28, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** March 19, 2018 by InstanTel  
**File Name** Q020HFLX.3F0

**Notes**

Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**

Set up in front yard of 1550 Dwire Hill Rd. Geo spiked and weight bagged on normal lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 116.3 dB(L) at 2.201 sec  
**ZC Freq** 8.3 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 569 mv )

	Tran	Vert	Long	
PPV	3.048	2.286	4.826	mm/s
ZC Freq	18	28	20	Hz
Time (Rel. to Trig)	0.693	0.223	0.347	sec
Peak Acceleration	0.040	0.040	0.066	g
Peak Displacement	0.026	0.016	0.040	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.2	7.6	7.5	Hz
Overswing Ratio	3.9	3.5	3.6	

Peak Vector Sum 5.145 mm/s at 0.321 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**Date/Time** Vert at 17:13:23 May 28, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** October 27, 2017 by InstanTel  
**File Name** Q589HFLX.6B0

**Notes**

**Post Event Notes**  
 Set up at end of driveway of 1331 Dwire Hill rd. Geo spiked and weight bagged on mossy gravel.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 115.2 dB(L) at 4.212 sec  
**ZC Freq** 6.6 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 541 mv )

	Tran	Vert	Long	
PPV	1.524	1.524	1.016	mm/s
ZC Freq	20	28	21	Hz
Time (Rel. to Trig)	0.113	0.002	0.137	sec
Peak Acceleration	0.027	0.040	0.027	g
Peak Displacement	0.016	0.010	0.009	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.9	7.8	Hz
Overswing Ratio	3.4	3.3	3.6	

Peak Vector Sum 1.871 mm/s at 0.316 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-07

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 06/01/2018 12:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: Lower level

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instantel  
Date: 06/01/18      Trigger Level: 1.23 mm/s      Off dB      Transverse: --- mm/s      --- Hz  
Time: 12:00      Calibration Date: 09/21/17      Vertical: --- mm/s      --- Hz  
Distance From Blast: 1,139.65 m      Calibration Signal:      Longitudinal: --- mm/s      --- Hz  
Direction From Blast: NNE      Geophone Min. Freq.: 2.0 Hz      PPV: --- mm/s      --- Hz  
Readout:      Mic. Min. Freq.: 2.0 Hz      Acoustic: --- dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on frozen ground.      Vector Sum: --- mm/s  
Lat./Long.: 45° 15' 59.300" N      76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instantel  
Date: 06/01/18      Trigger Level: 1.23 mm/s      Off dB      Transverse: --- mm/s      --- Hz  
Time: 12:00      Calibration Date: 10/27/17      Vertical: --- mm/s      --- Hz  
Distance From Blast: 1,393.55 m      Calibration Signal:      Longitudinal: --- mm/s      --- Hz  
Direction From Blast: E      Geophone Min. Freq.: 2.0 Hz      PPV: --- mm/s      --- Hz  
Readout:      Mic. Min. Freq.: 2.0 Hz      Acoustic: --- dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged. frozen ground.      Vector Sum: --- mm/s  
Lat./Long.: 45° 15' 27.900" N      76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder



# AUSTIN POWDER LTD. BLAST REPORT



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-08

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 06/01/2018 14:30

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Wall

## SEISMOGRAPH 1 - 1550 DWIRE HILL RD

Data Type: Seismic Record    Seismograph Type: instantel

Date: 06/01/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: 2.413 mm/s    20.0 Hz

Time: 14:28    Calibration Date: 09/21/17    Vertical: 1.778 mm/s    20.0 Hz

Distance From Blast: 936.65 m    Calibration Signal:    Longitudinal: 3.175 mm/s    18.0 Hz

Direction From Blast: NE    Geophone Min. Freq.: 2.0 Hz    PPV: --- mm/s    --- Hz

Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 115 dB

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on frozen ground.    Vector Sum: 3.579 mm/s

Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm:

## SEISMOGRAPH 2 - 1331 DWIRE HILL RD

Data Type: No Trigger    Seismograph Type: instantel

Date: 06/01/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: --- mm/s    --- Hz

Time: 14:30    Calibration Date: 10/27/17    Vertical: --- mm/s    --- Hz

Distance From Blast: 1,669.08 m    Calibration Signal:    Longitudinal: --- mm/s    --- Hz

Direction From Blast: E    Geophone Min. Freq.: 2.0 Hz    PPV: --- mm/s    --- Hz

Readout:    Mic. Min. Freq.: 2.0 Hz    Acoustic: --- dB

Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged. frozen ground.    Vector Sum: --- mm/s

Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Wyatt Clifton, Austin Powder

**Date/Time** Long at 14:28:08 June 1, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** March 19, 2018 by InstanTel  
**File Name** Q020HFT4.6W0  
**Post Event Notes**  
 Set up at end of driveway of 1550 Dwire Hill Rd.

**Notes**

Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 114.6 dB(L) at 2.358 sec  
**ZC Freq** 9.1 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 585 mv )

	Tran	Vert	Long	
PPV	2.413	1.778	3.175	mm/s
ZC Freq	20	20	18	Hz
Time (Rel. to Trig)	0.171	0.305	0.544	sec
Peak Acceleration	0.053	0.040	0.053	g
Peak Displacement	0.020	0.014	0.027	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
<b>Frequency</b>	7.3	7.5	7.4	Hz
<b>Overswing Ratio</b>	3.9	3.5	3.7	

Peak Vector Sum 3.579 mm/s at 0.544 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger = <--->

Sensor Check

**False Trigger's**  
**Set up at end of driveway of 1331 Dwire Hill Rd.**

**Event Report: Monitor Log - Minimate Blaster # BE15589-Compliance**

Start Time	End Time	Status
		SERIAL NUMBER: BE15589
Jun 1 /18 10:34:40		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 10:34:44	Jun 1 /18 10:34:49	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 10:35:02		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 10:39:23	Jun 1 /18 10:39:28	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 10:39:41		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 11:12:45	Jun 1 /18 11:12:50	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 11:13:04		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 11:16:33	Jun 1 /18 11:16:38	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 11:16:52		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 11:17:40	Jun 1 /18 11:17:45	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 11:17:59		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 11:36:20	Jun 1 /18 11:36:26	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 11:36:39		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 12:45:48	Jun 1 /18 12:45:53	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 12:46:07		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 13:35:08	Jun 1 /18 13:35:13	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 13:35:27		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 13:45:14	Jun 1 /18 13:45:19	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 13:45:33		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 13:48:42	Jun 1 /18 13:48:47	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 13:49:01		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 13:55:03	Jun 1 /18 13:55:08	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 13:55:22		Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 119.0 dB(L)
Jun 1 /18 14:50:30	Jun 1 /18 14:50:35	Event recorded. Trigger Level Vert: 1.23 mm/s
Jun 1 /18 14:50:48	Jun 1 /18 14:50:51	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 119.0 dB(L)



**AUSTIN POWDER LTD.**  
**BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-09

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 09/07/2018 12:04

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: Near Scale House

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 09/07/18                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 4.445 mm/s    21.0 Hz  
Time: 12:03                        Calibration Date: 10/10/17                    Vertical: 1.524 mm/s    30.0 Hz  
Distance From Blast: 668.73 m    Calibration Signal:                    Longitudinal: 2.54 mm/s    32.0 Hz  
Direction From Blast: NE            Geophone Min. Freq.: 2.0 Hz                    PPV: --- mm/s    --- Hz  
Readout: Printed Copy            Mic. Min. Freq.: 2.0 Hz                    Acoustic: 116 dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on frozen ground.                    Vector Sum: 4.561 mm/s  
Lat./Long.: 45° 15' 59.300" N                    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm:

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger            Seismograph Type: instancel  
Date: 09/07/18                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: --- mm/s    --- Hz  
Time: 12:00                        Calibration Date: 10/27/17                    Vertical: --- mm/s    --- Hz  
Distance From Blast: 1,454.51 m    Calibration Signal:                    Longitudinal: --- mm/s    --- Hz  
Direction From Blast: ESE            Geophone Min. Freq.: 2.0 Hz                    PPV: --- mm/s    --- Hz  
Readout:                            Mic. Min. Freq.: 2.0 Hz                    Acoustic: --- dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged. frozen ground.                    Vector Sum: --- mm/s  
Lat./Long.: 45° 15' 27.900" N                    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Patrick Garlic, Austin Powder

**Date/Time** Tran at 12:03:16 September 7, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** March 19, 2018 by InstanTel  
**File Name** Q020HKUE.TGO  
**Post Event Notes**  
 Set up beside driveway of 1550 Dwire Hill Rd. Geo spiked and weight bagged on nice lawn.

**Notes**

Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 116.4 dB(L) at 2.079 sec  
**ZC Freq** 7.3 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 503 mv )

	Tran	Vert	Long	
PPV	4.445	1.524	2.540	mm/s
ZC Freq	21	30	32	Hz
Time (Rel. to Trig)	0.742	0.616	0.323	sec
Peak Acceleration	0.066	0.040	0.053	g
Peak Displacement	0.031	0.007	0.020	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.3	7.5	7.4	Hz
Overswing Ratio	4.0	3.6	3.8	

**Peak Vector Sum** 4.561 mm/s at 0.744 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

No Trigger  
Set up at 1331 Dwire Hill Rd. Geo spiked and weight bagged.

Event Report: Monitor Log - Minimate Blaster # BE15589-Compliance

Start Time	End Time	Status
Sep 7 /18 11:12:13	Sep 7 /18 12:23:32	SERIAL NUMBER: BE15589 No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 119.0 dB(L)



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-10

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 09/11/2018 11:30

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North Wall

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL				
Date:	09/11/18	Trigger Level:	1.23 mm/s	Off dB	Transverse:	3.683 mm/s	20.0 Hz
Time:	11:34	Calibration Date:	10/10/17		Vertical:	1.651 mm/s	37.0 Hz
Distance From Blast:	670.56 m	Calibration Signal:			Longitudinal:	2.921 mm/s	20.0 Hz
Direction From Blast:	NE	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	117 dB	
Location:	Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on lawn.				Vector Sum:	4.512 mm/s	
Lat./Long.:	45° 15' 59.300" N		76° 7' 28.700" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Patrick Garlic, Austin Powder						

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL				
Date:	09/11/18	Trigger Level:	1.23 mm/s	Off dB	Transverse:	2.023 mm/s	16.0 Hz
Time:	11:29	Calibration Date:	10/27/17		Vertical:	1.397 mm/s	16.0 Hz
Distance From Blast:	1,477.67 m	Calibration Signal:			Longitudinal:	1.651 mm/s	16.0 Hz
Direction From Blast:	ESE	Geophone Min. Freq.:	2.0 Hz		PPV:	--- mm/s	--- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	93 dB	
Location:	Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.				Vector Sum:	2.572 mm/s	
Lat./Long.:	45° 15' 27.900" N		76° 6' 50.100" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Patrick Garlic, Austin Powder						

# Event Report

**Date/Time** Tran at 11:29:08 September 11, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** October 27, 2017 by InstanTel  
**File Name** Q589HL1R.WK0

**Notes**

**Post Event Notes**  
 Set up in flower bed at end of driveway of 1331 Dwire Hill Rd. Geo spiked and weight bagged on soft, lose, soil.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 93.98 dB(L) at -0.231 sec  
**ZC Freq** 64 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 588 mv )

	Tran	Vert	Long	
PPV	2.032	1.397	1.651	mm/s
ZC Freq	16	16	16	Hz
Time (Rel. to Trig)	0.739	0.128	0.708	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.021	0.013	0.016	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.9	7.8	Hz
Overswing Ratio	3.5	3.4	3.6	

Peak Vector Sum 2.572 mm/s at 0.708 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

Date/Time Tran at 11:34:57 September 11, 2018  
 Trigger Source Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 6.0 sec at 1024 sps

Serial Number BE15020 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.2 Volts  
 Unit Calibration March 19, 2018 by Instantel  
 File Name Q020HL1S.690

Notes  
 Location:  
 Client:  
 User Name:  
 General:

Post Event Notes  
 Set up at end of driveway of 1550 Dwire Hill Rd. Geo spiked and weight bagged on lawn.



Extended Notes

Microphone Linear Weighting  
 PSPL 116.6 dB(L) at 2.187 sec  
 ZC Freq 21 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 632 mv)

	Tran	Vert	Long	
PPV	3.683	1.651	2.921	mm/s
ZC Freq	20	37	20	Hz
Time (Rel. to Trig)	0.604	0.579	0.670	sec
Peak Acceleration	0.053	0.040	0.053	g
Peak Displacement	0.034	0.010	0.021	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.6	7.5	7.6	Hz
Overswing Ratio	3.9	3.6	3.7	

Peak Vector Sum 4.512 mm/s at 0.672 sec

USBM RI8507 And OSMRE



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-11

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 09/13/2018 12:17

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North East Wall

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 09/13/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: 2.413 mm/s    24.0 Hz  
Time: 12:14    Calibration Date: 10/10/17    Vertical: 1.397 mm/s    51.0 Hz  
Distance From Blast: 634.29 m    Calibration Signal:    Longitudinal: 3.175 mm/s    28.0 Hz  
Direction From Blast: NE    Geophone Min. Freq.: 2.0 Hz    PPV: --- mm/s    --- Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 114 dB  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on lawn.    Vector Sum: 3.336 mm/s  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Wyatt Clifton, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 09/13/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: 1.143 mm/s    30.0 Hz  
Time: 12:13    Calibration Date: 10/27/17    Vertical: 2.286 mm/s    28.0 Hz  
Distance From Blast: 1,472.79 m    Calibration Signal:    Longitudinal: 1.143 mm/s    24.0 Hz  
Direction From Blast: ESE    Geophone Min. Freq.: 2.0 Hz    PPV: --- mm/s    --- Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 105 dB  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: 2.376 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Patrick Garlic, Austin Powder

**Date/Time** Vert at 12:13:56 September 13, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** October 27, 2017 by InstanTel  
**File Name** Q589HL5J.B80

**Notes**

**Post Event Notes**  
 Set up at 1331 Dwire Hill Rd. Geo spiked and weight bagged in flower bed at end of driveway.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 104.9 dB(L) at 3.948 sec  
**ZC Freq** 6.5 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 532 mv )

	Tran	Vert	Long	
PPV	1.143	2.286	1.143	mm/s
ZC Freq	30	28	24	Hz
Time (Rel. to Trig)	0.093	0.242	0.268	sec
Peak Acceleration	0.027	0.040	0.027	g
Peak Displacement	0.008	0.013	0.009	mm
<b>Sensor Check</b>	Check	Passed	Passed	
Frequency	9.8	7.9	7.7	Hz
Overswing Ratio	4.0	3.4	3.6	

**Peak Vector Sum** 2.376 mm/s at 0.242 sec

**USBM R18507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check



**Date/Time** Vert at 12:14:54 September 13, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** March 19, 2018 by InstanTel  
**File Name** Q020HL5J.CU0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up at 1550 Dwire Hill Rd. Geo spiked and weight bagged at end of driveway.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 113.5 dB(L) at 1.881 sec  
**ZC Freq** 8.4 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 544 mv)

	Tran	Vert	Long	
PPV	2.413	1.397	3.175	mm/s
ZC Freq	24	51	28	Hz
Time (Rel. to Trig)	0.135	0.000	0.261	sec
Peak Acceleration	0.053	0.053	0.080	g
Peak Displacement	0.022	0.009	0.018	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
<b>Frequency</b>	7.4	7.4	7.4	Hz
<b>Overswing Ratio</b>	3.8	3.6	3.7	

**Peak Vector Sum** 3.336 mm/s at 0.261 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-12

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 10/15/2018 11:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Wall

**SEISMOGRAPH 1 - 1550 DWYER HILL RD**

Data Type: Seismic Record Seismograph Type: Instantel

Date: 10/15/18 Trigger Level: 0.07 in/s 114.00 dB Transverse: 0.085 in/s 22.0 Hz

Time: 10:59 Calibration Date: 08/01/18 Vertical: 0.05 in/s 43.0 Hz

Distance From Blast: 2,507.00 ft Calibration Signal: Longitudinal: 0.125 in/s 32.0 Hz

Direction From Blast: NE Geophone Min. Freq.: --- Hz

Readout: Printed Copy Mic. Min. Freq.: --- Hz Acoustic: 111 dB --- Hz

Location: 1550 Dwyer Hill Rd, Set Up In Yard, Geo Spiked and Weight Bagged on Lawn Vector Sum: 0.128 in/s

Lat./Long.: 45° 15' 59.300" N 76° 7' 28.700" W

Reader and Firm: Matt Gordon, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Patrick Garlick / Austin Powder

**SEISMOGRAPH 2 - 1331 DWYER HILL RD**

Data Type: Seismic Record Seismograph Type: Instantel

Date: 10/15/18 Trigger Level: 0.07 in/s 114.00 dB Transverse: 0.03 in/s 34.0 Hz

Time: 10:59 Calibration Date: 03/19/18 Vertical: 0.05 in/s 34.0 Hz

Distance From Blast: 5,079.00 ft Calibration Signal: Longitudinal: 0.03 in/s 34.0 Hz

Direction From Blast: ESE Geophone Min. Freq.: --- Hz

Readout: Printed Copy Mic. Min. Freq.: --- Hz Acoustic: 105 dB --- Hz

Location: 1331 Dwyer Hill Rd Set up In Yard, Geo Spiked and Weight Bagged Vector Sum: 0.058 in/s

Lat./Long.: 45° 15' 27.900" N 76° 6' 50.100" W

Reader and Firm: Matt Gordon, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Patrick Garlick / Austin Powder

**Date/Time** Long at 10:59:16 October 15, 2018  
**Trigger Source** Geo: 1.700 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19636 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** August 1, 2018 by InstanTel  
**File Name** U636HMSP.6S0

**Post Event Notes**  
 1550 Dwyer Hill Rd  
 Set Up In Yard  
 Geo Spiked and Weight Bagged On Damp Lawn



**Notes**

**Microphone** Linear Weighting  
**PSPL** 111.5 dB(L) at 2.221 sec  
**ZC Freq** 27 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 645 mv)

	Tran	Vert	Long	
PPV	2.159	1.270	3.175	mm/s
ZC Freq	22	43	32	Hz
Time (Rel. to Trig)	0.981	0.191	0.108	sec
Peak Acceleration	0.040	0.040	0.066	g
Peak Displacement	0.018	0.005	0.016	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.5	7.3	7.5	Hz
Overswing Ratio	3.8	3.8	3.9	

Peak Vector Sum 3.248 mm/s at 0.109 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div    **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 10:59:41 October 15, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** March 19, 2018 by InstanTel  
**File Name** Q020HMSP.7H0  
**Post Event Notes**  
 1331 Dwyer Hill Rd  
 Set Up In Yard  
 Geo Spiked and Weight Bagged On Damp Lawn

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 105.5 dB(L) at 3.417 sec  
**ZC Freq** 18 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 657 mv )

	Tran	Vert	Long	
PPV	0.762	1.270	0.762	mm/s
ZC Freq	34	34	34	Hz
Time (Rel. to Trig)	-0.082	0.000	-0.146	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.004	0.007	0.005	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.2	7.4	7.4	Hz
Overswing Ratio	4.1	3.7	3.8	

**Peak Vector Sum** 1.470 mm/s at 0.000 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark  
ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-13

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 10/26/2018 10:15

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: S.E Wall

**SEISMOGRAPH 1 - 1550 DWYER HILL RD**

Data Type:	Seismic Record	Seismograph Type:	Instantel			
Date:	10/26/18	Trigger Level:	1.70 mm/s	114.00 dB	Transverse:	1.905 mm/s 20.0 Hz
Time:	12:15	Calibration Date:	08/01/18		Vertical:	1.397 mm/s 47.0 Hz
Distance From Blast:	680.31 m	Calibration Signal:			Longitudinal:	2.54 mm/s 23.0 Hz
Direction From Blast:	NE	Geophone Min. Freq.:	---	Hz	Acoustic:	115 dB --- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	---	Hz	Vector Sum:	2.739 mm/s
Location:	1550 Dwyer Hill Rd, Set Up In Yard, Geo Spiked and Weight Bagged on Lawn					
Lat./Long.:	45° 15' 59.300" N		76° 7' 28.700" W			
Reader and Firm:	Matt Gordon, AUSTIN POWDER					
Analyst and Firm:						
Installer and Firm:	Patrick Garlick / Austin Powder					

**SEISMOGRAPH 2 - 1331 DWYER HILL RD**

Data Type:	Seismic Record	Seismograph Type:	Instantel			
Date:	10/26/18	Trigger Level:	1.70 mm/s	114.00 dB	Transverse:	0.889 mm/s 22.0 Hz
Time:	12:15	Calibration Date:	10/16/18		Vertical:	1.905 mm/s 24.0 Hz
Distance From Blast:	1,505.71 m	Calibration Signal:			Longitudinal:	0.762 mm/s 27.0 Hz
Direction From Blast:	ESE	Geophone Min. Freq.:	---	Hz	Acoustic:	110 dB --- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	---	Hz	Vector Sum:	2.08 mm/s
Location:	1331 Dwyer Hill Rd Set up In Yard, Geo Spiked and Weight Bagged					
Lat./Long.:	45° 15' 27.900" N		76° 6' 50.100" W			
Reader and Firm:	Matt Gordon, AUSTIN POWDER					
Analyst and Firm:						
Installer and Firm:	Patrick Garlick / Austin Powder					

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-14

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION

(THO1100-002)

Date/Time: 11/02/2018 13:15

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South East Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instancel  
Date: 11/02/18      Trigger Level: 1.23 mm/s      Off dB  
Time: 13:15      Calibration Date: 10/16/18  
Distance From Blast: 1,237.49 m      Calibration Signal:  
Direction From Blast: ENE      Geophone Min. Freq.: 2.0 Hz  
Readout:      Mic. Min. Freq.: 2.0 Hz  
Location: Set up in driveway of 1331 Dwire Hill Rd, geo spiked and wieght bagged.  
Lat./Long.: 45° 15' 27.900" N      76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: William Coleman, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instancel  
Date: 11/02/18      Trigger Level: 1.23 mm/s      Off dB  
Time: 13:15      Calibration Date: 09/27/18  
Distance From Blast: 1,346.30 m      Calibration Signal:  
Direction From Blast: N      Geophone Min. Freq.: 2.0 Hz  
Readout:      Mic. Min. Freq.: 2.0 Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on lawn.  
Lat./Long.: 45° 15' 59.300" N      76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Patrick Garlic, Austin Powder

**AUSTIN POWDER LTD.  
BLAST REPORT**



Blast No.: 2018-15

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 11/09/2018 13:40

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 11/09/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: 38.71 mm/s    30.0 Hz  
Time: 13:40    Calibration Date: 10/16/18    Vertical: 16.129 mm/s    37.0 Hz  
Distance From Blast: 1,199.69 m    Calibration Signal:    Longitudinal: 29.032 mm/s    23.0 Hz  
Direction From Blast: ENE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 108 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: 40.792 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Patrick Garlic, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: No Trigger    Seismograph Type: instancel  
Date: 11/09/18    Trigger Level: 1.23 mm/s    Off dB  
Time: 13:40    Calibration Date: 09/27/18  
Distance From Blast: 1,336.55 m    Calibration Signal:  
Direction From Blast: N    Geophone Min. Freq.: 2.0 Hz  
Readout:    Mic. Min. Freq.: 2.0 Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on lawn.  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Patrick Garlic, Austin Powder

**Date/Time** Tran at 13:40:08 November 9, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** March 19, 2018 by InstanTel  
**File Name** Q020HO37.AW0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:



**Post Event Notes**  
 Set up in backyard of 1331 Dwire Hill Rd. Geo spiked and weight bagged on wet Lawn.

**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 108.4 dB(L) at 3.358 sec  
**ZC Freq** 8.0 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 769 mv )

	Tran	Vert	Long	
PPV	1.524	0.635	1.143	mm/s
ZC Freq	30	37	23	Hz
Time (Rel. to Trig)	0.021	0.061	0.063	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.010	0.003	0.009	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.3	7.5	7.4	Hz
Overswing Ratio	4.1	3.7	4.0	

Peak Vector Sum 1.606 mm/s at 0.021 sec





No Trigger  
Set up on front lawn of 1550 Dwire Hill Rd.

Event Report: Monitor Log - Minimate Blaster # BE15589-Compliance

Start Time	End Time	Status
Nov 9 /18 12:59:08		SERIAL NUMBER: BE15589
Nov 9 /18 13:17:45	Nov 9 /18 13:17:50	Start Monitoring Trigger Level: Geo: 1.23 mm/s Mic: 110.0 dB(L)
Nov 9 /18 13:18:04	Nov 9 /18 14:03:29	Event recorded. Trigger Level MicL: 110.0 dB(L)
		No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 110.0 dB(L)

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2018-16

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 12/01/2018 10:05

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South Wall

**SEISMOGRAPH 1 - 1331 DWYER HILL RD**

Data Type: Seismic Record    Seismograph Type: Instantel

Date: 12/01/18

Trigger Level: 1.70 mm/s    114.00 dB

Transverse: 1.905 mm/s    23.0 Hz

Time: 10:05

Calibration Date: 10/16/18

Vertical: 1.397 mm/s    37.0 Hz

Distance From Blast: 1,172.26 m

Calibration Signal:

Longitudinal: 1.778 mm/s    28.0 Hz

Direction From Blast: ENE

Geophone Min. Freq.: --- Hz

Readout: Printed Copy

Mic. Min. Freq.: --- Hz

Acoustic: 114 dB    --- Hz

Location: 1331 Dwyer Hill Rd Set up In Yard, Geo Spiked and Weight Bagged

Vector Sum: --- mm/s

Lat./Long.: 45° 15' 27.900" N

76° 6' 50.100" W

Reader and Firm: Matt Gordon, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Matt Gordon / Austin Powder

**SEISMOGRAPH 2 - 1550 DWYER HILL RD**

Data Type: No Trigger    Seismograph Type: Instantel

Date: 12/01/18

Trigger Level: 1.70 mm/s    114.00 dB

Time: 10:05

Calibration Date: 08/01/18

Distance From Blast: 1,355.45 m

Calibration Signal:

Direction From Blast: N

Geophone Min. Freq.: --- Hz

Readout:

Mic. Min. Freq.: --- Hz

Location: 1550 Dwyer Hill Rd, Set Up In Yard, Geo Spiked and Weight Bagged on Lawn

Lat./Long.: 45° 15' 59.300" N

76° 7' 28.700" W

Reader and Firm: Matt Gordon, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Matt Gordon / Austin Powder

**AUSTIN POWDER LTD.**  
**BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2018-17

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 12/04/2018 13:30

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 12/04/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: 0.127 mm/s    --- Hz  
Time: 13:00    Calibration Date: 10/16/18    Vertical: 0.127 mm/s    --- Hz  
Distance From Blast: 1,210.67 m    Calibration Signal:    Longitudinal: 0.127 mm/s    --- Hz  
Direction From Blast: ENE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 118 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. snow covered lawn.    Vector Sum: 0.22 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm:

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 12/04/18    Trigger Level: 1.23 mm/s    Off dB    Transverse: 1.778 mm/s    15.0 Hz  
Time: 13:29    Calibration Date: 09/27/18    Vertical: 0.762 mm/s    --- Hz  
Distance From Blast: 1,372.51 m    Calibration Signal:    Longitudinal: 1.651 mm/s    13.0 Hz  
Direction From Blast: N    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 114 dB    --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on snow covered lawn.    Vector Sum: 2.261 mm/s  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Patrick Garlic, Austin Powder

**Date/Time** MicL at 13:30:07 December 4, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** October 16, 2018 by InstanTel  
**File Name** Q589HPDH.I70

**Post Event Notes**  
 Set up in back yard of 1330 Dwire Hill Rd. Geo spiked and wright bagged on snow covered lawn.

**Notes**



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 117.5 dB(L) at 0.014 sec  
**ZC Freq** 11 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 778 mv )

	Tran	Vert	Long	
PPV	0.127	0.127	0.127	mm/s
ZC Freq	>100	>100	>100	Hz
Time (Rel. to Trig)	-0.238	-0.128	-0.230	sec
Peak Acceleration	0.013	0.027	0.013	g
Peak Displacement	0.000	0.000	0.000	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.9	7.7	Hz
Overswing Ratio	3.7	3.6	3.9	

Peak Vector Sum 0.220 mm/s at 0.838 sec

**USBM R18507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Tran at 13:29:08 December 4, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** March 19, 2018 by InstanTel  
**File Name** Q020HPDH.GK0  
**Post Event Notes**

Set up in front yard of 1550 Dwire Hill Rd. Geo spiked and weight bagged on snow covered lawn.

**Notes**

Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 114.2 dB(L) at 3.313 sec  
**ZC Freq** 8.0 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 741 mv )

	Tran	Vert	Long	
PPV	1.778	0.762	1.651	mm/s
ZC Freq	15	N/A	13	Hz
Time (Rel. to Trig)	0.675	-0.247	0.724	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.021	0.007	0.020	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.2	7.5	7.4	Hz
Overswing Ratio	4.2	3.8	4.1	

**Peak Vector Sum** 2.261 mm/s at 0.722 sec  
 N/A: Not Applicable

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-01

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 04/12/2019 10:50

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location:

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instancel  
Date: 04/12/19      Trigger Level: 1.23 mm/s      Off dB  
Time: 10:50      Calibration Date: 09/27/18

Distance From Blast: 830.28 m      Calibration Signal:  
Direction From Blast: NE      Geophone Min. Freq.: 2.0 Hz  
Readout:      Mic. Min. Freq.: 2.0 Hz

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet covered lawn.

Lat./Long.: 45° 15' 59.300" N      76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Patrick Garlic, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instancel  
Date: 04/12/19      Trigger Level: 1.23 mm/s      Off dB  
Time: 10:50      Calibration Date: 10/16/18

Distance From Blast: 1,618.18 m      Calibration Signal:  
Direction From Blast: ESE      Geophone Min. Freq.: 2.0 Hz  
Readout:      Mic. Min. Freq.: 2.0 Hz

Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.

Lat./Long.: 45° 15' 27.900" N      76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Patrick Garlic, Austin Powder

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-02

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 04/15/2019 11:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location:

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instantel

Date: 04/15/19 Trigger Level: 1.23 mm/s Off dB Transverse: 2.921 mm/s 13.0 Hz

Time: 11:00 Calibration Date: 09/27/18 Vertical: 4.429 mm/s 19.0 Hz

Distance From Blast: 902.51 m Calibration Signal: Longitudinal: 4.064 mm/s 18.0 Hz

Direction From Blast: NE Geophone Min. Freq.: 2.0 Hz

Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 106 dB --- Hz

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet covered lawn. Vector Sum: 4.618 mm/s

Lat./Long.: 45° 15' 59.300" N 76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger Seismograph Type: instantel

Date: 04/15/19 Trigger Level: 1.23 mm/s Off dB

Time: 11:00 Calibration Date: 10/16/18

Distance From Blast: 1,680.06 m Calibration Signal:

Direction From Blast: E Geophone Min. Freq.: 2.0 Hz

Readout: Mic. Min. Freq.: 2.0 Hz

Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.

Lat./Long.: 45° 15' 27.900" N 76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Long at 11:00:46 April 15, 2018  
**Trigger Source** Geo: 1.230 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q020HDDT.9A0

**Notes**

Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**

Set up in front yard of 1550 Dwire Hill Rd. Geo spiked and weight bagged on super saturated lawn. Yard flooded.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 106.0 dB(L) at 2.240 sec  
**ZC Freq** 19 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 756 mv )

	Tran	Vert	Long	
PPV	2.921	3.429	4.064	mm/s
ZC Freq	13	19	18	Hz
Time (Rel. to Trig)	0.361	0.471	0.415	sec
Peak Acceleration	0.053	0.053	0.053	g
Peak Displacement	0.038	0.028	0.035	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.2	7.6	7.5	Hz
Overswing Ratio	4.1	3.6	3.9	

Peak Vector Sum 4.618 mm/s at 0.417 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check



No Trigger  
Set up at 1331 Dwire Hill Rd.

Event Report: Monitor Log - Minimate Blaster # BE15589-Compliance

Start Time	End Time	Status
-----	-----	SERIAL NUMBER: BE15589
Apr 12 /19 10:10:25	Apr 12 /19 11:12:31	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 118.0 dB(L)
Apr 15 /19 10:20:47	Apr 15 /19 11:29:28	No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 118.0 dB(L)



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-03

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 04/17/2019 11:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instancel

Date: 04/17/19 Trigger Level: 1.23 mm/s Off dB

Time: 10:56 Calibration Date: 09/27/18 Transverse: 2.413 mm/s 14.0 Hz

Distance From Blast: 882.70 m Calibration Signal: Vertical: 1.905 mm/s 39.0 Hz

Direction From Blast: NE Geophone Min. Freq.: 2.0 Hz Longitudinal: 3.302 mm/s 24.0 Hz

Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 117 dB --- Hz

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet covered lawn. Vector Sum: 3.372 mm/s

Lat./Long.: 45° 15' 59.300" N 76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger Seismograph Type: instancel

Date: 04/17/19 Trigger Level: 1.23 mm/s Off dB

Time: 11:00 Calibration Date: 10/16/18

Distance From Blast: 1,663.29 m Calibration Signal:

Direction From Blast: ESE Geophone Min. Freq.: 2.0 Hz

Readout: Mic. Min. Freq.: 2.0 Hz

Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.

Lat./Long.: 45° 15' 27.900" N 76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

Date/Time Vert at 10:56:20 April 17, 2019  
 Trigger Source Geo: 1.230 mm/s, Mic: 118.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 5.0 sec at 1024 sps

Serial Number BE15589 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.4 Volts  
 Unit Calibration October 16, 2018 by InstanTel  
 File Name Q589HW9F.PWO

Post Event Notes

Set up at 1550 Dwire Hill Rd. Geo spiked and weight bagged on saturated lawn.

Notes



Extended Notes

Microphone Linear Weighting  
 PSPL 116.7 dB(L) at 2.257 sec  
 ZC Freq 18 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 616 mv)

	Tran	Vert	Long	
PPV	2.413	1.905	3.302	mm/s
ZC Freq	14	39	24	Hz
Time (Rel. to Trig)	1.118	0.251	0.383	sec
Peak Acceleration	0.040	0.040	0.053	g
Peak Displacement	0.027	0.009	0.028	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.9	7.8	Hz
Overswing Ratio	3.6	3.5	3.8	

Peak Vector Sum 3.372 mm/s at 0.383 sec

USBM RI8507 And OSMRE



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger = <--->

Sensor Check

No Trigger  
Set up at 1331 Dwire Hill Rd.

Event Report: Monitor Log - Minimate Blaster # BE15020-Compliance

Start Time	End Time	Status
Apr 17 /19 10:23:43	Apr 17 /19 11:39:53	SERIAL NUMBER: BE15020 No events recorded. (Keyboard Exit) Geo: 1.23 mm/s Mic: 110.0 dB(L)

**AUSTIN POWDER LTD.  
BLAST REPORT**



Blast No.: 2019-04

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 07/26/2019 10:14

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North Wall

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 07/26/19    Trigger Level: 1.23 mm/s    Off dB    Transverse: 2.921 mm/s    18.0 Hz  
Time: 10:14    Calibration Date: 09/27/18    Vertical: 1.651 mm/s    47.0 Hz  
Distance From Blast: 776.33 m    Calibration Signal:    Longitudinal: 2.54 mm/s    32.0 Hz  
Direction From Blast: NE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 118 dB    --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet covered lawn.    Vector Sum: 3.064 mm/s  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 07/26/19    Trigger Level: 1.23 mm/s    Off dB    Transverse: 1.016 mm/s    15.0 Hz  
Time: 10:14    Calibration Date: 10/16/18    Vertical: 1.397 mm/s    26.0 Hz  
Distance From Blast: 1,571.55 m    Calibration Signal:    Longitudinal: 1.016 mm/s    13.0 Hz  
Direction From Blast: ESE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 96 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.    Vector Sum: 1.454 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Austin Harrison, Austin Powder

**Date/Time** Tran at 10:14:08 July 26, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q02011EK.FK0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up in back yard of 1331 Dwire Hill Rd, geo spiked and weight bagged on lawn.



### Extended Notes

**Microphone** Linear Weighting  
**PSPL** 95.92 dB(L) at 3.518 sec  
**ZC Freq** 18 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 440 mv )

	Tran	Vert	Long	
PPV	1.016	1.397	1.016	mm/s
ZC Freq	15	26	13	Hz
Time (Rel. to Trig)	0.003	0.432	0.155	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.012	0.009	0.010	mm
Sensor Check	Check	Passed	Passed	
Frequency	8.2	7.4	7.7	Hz
Overswing Ratio	3.3	3.7	3.5	

Peak Vector Sum 1.454 mm/s at 0.432 sec

### USBM RI8507 And OSMRE



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Vert at 10:14:33 July 26, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 118.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** October 16, 2018 by InstanTel  
**File Name** Q58911EK.G90  
**Post Event Notes**

Set up at 1550 Dwire Hill Rd. Geo spiked and wight bagged on lawn.

**Notes**



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 118.3 dB(L) at 1.895 sec  
**ZC Freq** 4.9 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 530 mv )

	Tran	Vert	Long	
PPV	2.921	1.651	2.540	mm/s
ZC Freq	18	47	32	Hz
Time (Rel. to Trig)	0.831	0.294	0.860	sec
Peak Acceleration	0.053	0.053	0.053	g
Peak Displacement	0.029	0.009	0.012	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.8	7.9	7.8	Hz
Overswing Ratio	3.4	3.4	3.6	

Peak Vector Sum 3.064 mm/s at 0.831 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-05

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 07/30/2019 12:36

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL					
Date:	07/30/19	Trigger Level:	1.23 mm/s	Off dB	Transverse:	4.064 mm/s	16.0 Hz	
Time:	12:36	Calibration Date:	09/27/18		Vertical:	1.651 mm/s	28.0 Hz	
Distance From Blast:	789.13 m	Calibration Signal:			Longitudinal:	2.413 mm/s	23.0 Hz	
Direction From Blast:	NE	Geophone Min. Freq.:	2.0 Hz		Acoustic:	97 dB	--- Hz	
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Vector Sum:	4.178 mm/s		
Location:	Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet covered lawn.							
Lat./Long.:	45° 15' 59.300" N		76° 7' 28.700" W					
Reader and Firm:	William Coleman, AUSTIN POWDER							
Analyst and Firm:								
Installer and Firm:	Ross Scott, Austin Powder							

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL					
Date:	07/30/19	Trigger Level:	1.23 mm/s	Off dB	Transverse:	1.27 mm/s	20.0 Hz	
Time:	12:36	Calibration Date:	10/16/18		Vertical:	1.016 mm/s	26.0 Hz	
Distance From Blast:	1,592.28 m	Calibration Signal:			Longitudinal:	0.508 mm/s	32.0 Hz	
Direction From Blast:	ESE	Geophone Min. Freq.:	2.0 Hz		Acoustic:	115 dB	--- Hz	
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Vector Sum:	1.442 mm/s		
Location:	Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.							
Lat./Long.:	45° 15' 27.900" N		76° 6' 50.100" W					
Reader and Firm:	William Coleman, AUSTIN POWDER							
Analyst and Firm:								
Installer and Firm:	Ross Scott, Austin Powder							



**Date/Time** Tran at 12:36:25 July 30, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q02011M5.OP0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up at 1550 Dwire Hill Rd. Geo spiked and weight bagged onfront lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 97.50 dB(L) at 1.822 sec  
**ZC Freq** 17 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 561 mv )

	Tran	Vert	Long	
PPV	4.064	1.651	2.413	mm/s
ZC Freq	16	28	23	Hz
Time (Rel. to Trig)	0.635	0.504	0.699	sec
Peak Acceleration	0.066	0.053	0.040	g
Peak Displacement	0.043	0.010	0.016	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.8	7.4	7.5	Hz
Overswing Ratio	3.4	3.7	3.5	

**Peak Vector Sum** 4.178 mm/s at 0.635 sec

**USBM R18507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

Date/Time Vert at 12:36:58 July 30, 2019  
 Trigger Source Geo: 0.930 mm/s, Mic: 118.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 6.0 sec at 1024 sps

Serial Number BE15589 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.4 Volts  
 Unit Calibration October 16, 2018 by InstanTel  
 File Name Q58911M5.PM0  
 Post Event Notes  
 Set up at 1331 Dwire Hill rd. Geo spiked and weight bagged on roadside near fence.

Notes



Extended Notes

Microphone Linear Weighting  
 PSPL 114.8 dB(L) at 3.694 sec  
 ZC Freq 8.8 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 542 mv )

	Tran	Vert	Long	
PPV	1.270	1.016	0.508	mm/s
ZC Freq	20	26	32	Hz
Time (Rel. to Trig)	0.202	0.014	0.339	sec
Peak Acceleration	0.027	0.040	0.027	g
Peak Displacement	0.010	0.007	0.003	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.9	7.9	Hz
Overswing Ratio	3.5	3.3	3.5	

Peak Vector Sum 1.442 mm/s at 0.428 sec

USBM RI8507 And OSMRE



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-06

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 09/06/2019 10:29

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 09/06/19    Trigger Level: 1.23 mm/s    Off dB    Transverse: 0.635 mm/s    13.0 Hz  
Time: 10:29    Calibration Date: 03/21/19    Vertical: 1.78 mm/s    18.0 Hz  
Distance From Blast: 919.58 m    Calibration Signal:    Longitudinal: 2.667 mm/s    20.0 Hz  
Direction From Blast: NE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 117 dB    --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet covered lawn.    Vector Sum: 2.907 mm/s  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm:

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 09/06/19    Trigger Level: 1.23 mm/s    Off dB    Transverse: 1.016 mm/s    19.0 Hz  
Time: 10:29    Calibration Date: 10/16/18    Vertical: 1.143 mm/s    21.0 Hz  
Distance From Blast: 1,677.31 m    Calibration Signal:    Longitudinal: 1.016 mm/s    17.0 Hz  
Direction From Blast: E    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 94 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.    Vector Sum: 1.581 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Vert at 10:29:48 September 6, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 118.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** October 16, 2018 by InstanTel  
**File Name** Q589I3KD.500

**Notes**

**Post Event Notes**  
 Set up at 1550 Dwire Hill Rd. Geo spiked and weight bagged on front lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 117.2 dB(L) at 2.151 sec  
**ZC Freq** 6.2 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 595 mv )

	Tran	Vert	Long	
PPV	0.635	1.778	2.667	mm/s
ZC Freq	13	18	20	Hz
Time (Rel. to Trig)	0.532	0.632	0.684	sec
Peak Acceleration	0.013	0.027	0.040	g
Peak Displacement	0.008	0.015	0.021	mm
<b>Sensor Check</b>	Check	Passed	Passed	
Frequency	14.0	7.9	8.1	Hz
Overswing Ratio	2.2	3.4	3.6	

**Peak Vector Sum** 2.907 mm/s at 0.634 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**Date/Time** Long at 10:29:14 September 6, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q020I3KD.4Q0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up at 1331 Dwire Hill Rd. Geo spiked and weight bagged on shoulder of driveway.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 93.98 dB(L) at 4.393 sec  
**ZC Freq** 16 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 617 mv)

	Tran	Vert	Long	
PPV	1.016	1.143	1.016	mm/s
ZC Freq	19	21	17	Hz
Time (Rel. to Trig)	0.054	0.450	0.682	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.010	0.010	0.010	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.6	7.4	7.6	Hz
Overswing Ratio	3.6	3.8	3.6	

Peak Vector Sum 1.581 mm/s at 0.451 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



Blast No.: 2019-07

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 09/09/2019 10:49

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 09/09/19    Trigger Level: 1.23 mm/s    Off dB    Transverse: 3.302 mm/s    15.0 Hz  
Time: 10:49    Calibration Date: 03/21/19    Vertical: 1.905 mm/s    18.0 Hz  
Distance From Blast: 929.34 m    Calibration Signal:    Longitudinal: 2.667 mm/s    17.0 Hz  
Direction From Blast: NE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 114 dB    --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet covered lawn.    Vector Sum: 3.606 mm/s  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 09/09/19    Trigger Level: 1.23 mm/s    Off dB    Transverse: 1.143 mm/s    17.0 Hz  
Time: 10:48    Calibration Date: 10/16/18    Vertical: 1.016 mm/s    28.0 Hz  
Distance From Blast: 1,699.56 m    Calibration Signal:    Longitudinal: 0.762 mm/s    14.0 Hz  
Direction From Blast: E    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 94 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.    Vector Sum: 1.426 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm:

**Date/Time** Vert at 10:48:51 September 9, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q02013PY.1F0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up on 1331 Dwire Hill Rd. Geo spiked and weight bagged at end of driveway.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 93.98 dB(L) at 4.461 sec  
**ZC Freq** 23 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 570 mv )

	Tran	Vert	Long	
PPV	1.143	1.016	0.762	mm/s
ZC Freq	17	28	14	Hz
Time (Rel. to Trig)	0.406	0.001	0.521	sec
Peak Acceleration	0.027	0.040	0.027	g
Peak Displacement	0.012	0.011	0.010	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.4	7.4	Hz
Overswing Ratio	3.6	3.9	3.6	

**Peak Vector Sum** 1.426 mm/s at 0.410 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 10:49:30 September 9, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 118.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** October 16, 2018 by Instantel  
**File Name** Q589I3PY.210

**Notes**

**Post Event Notes**  
 Set up in front lawn of 1550 Dwire Hill Rd. Geo spiked and weight bagged on moist lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 114.4 dB(L) at 2.360 sec  
**ZC Freq** 16 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 583 mv )

	Tran	Vert	Long	
PPV	3.302	1.905	2.667	mm/s
ZC Freq	15	18	17	Hz
Time (Rel. to Trig)	0.721	0.985	0.283	sec
Peak Acceleration	0.040	0.040	0.053	g
Peak Displacement	0.034	0.017	0.026	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.9	7.9	7.8	Hz
Overswing Ratio	3.5	3.5	3.7	

Peak Vector Sum 3.606 mm/s at 0.989 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check





**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-08

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 09/11/2019 12:59

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL				
Date:	09/11/19	Trigger Level:	1.23 mm/s	Off dB	Transverse:	0.635 mm/s	28.0 Hz
Time:	12:59	Calibration Date:	03/21/19		Vertical:	1.143 mm/s	24.0 Hz
Distance From Blast:	981.46 m	Calibration Signal:			Longitudinal:	0.635 mm/s	26.0 Hz
Direction From Blast:	NE	Geophone Min. Freq.:	2.0 Hz		Acoustic:	122 dB	--- Hz
Readout:	Display Only	Mic. Min. Freq.:	2.0 Hz		Vector Sum:	1.178 mm/s	
Location:	Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet covered lawn.						
Lat./Long.:	45° 15' 59.300" N		76° 7' 28.700" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:							

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL				
Date:	09/11/19	Trigger Level:	1.23 mm/s	Off dB	Transverse:	2.667 mm/s	17.0 Hz
Time:	12:59	Calibration Date:	10/16/18		Vertical:	0.889 mm/s	32.0 Hz
Distance From Blast:	1,737.06 m	Calibration Signal:			Longitudinal:	2.921 mm/s	22.0 Hz
Direction From Blast:	E	Geophone Min. Freq.:	2.0 Hz		Acoustic:	99 dB	--- Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Vector Sum:	2.9 mm/s	
Location:	Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.						
Lat./Long.:	45° 15' 27.900" N		76° 6' 50.100" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Joel McNamee, Austin Powder						

**Date/Time** Vert at 12:59:20 September 11, 2019  
**Trigger Source** Geo: 1.030 mm/s, Mic: 118.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE19637 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** September 25, 2018 by InstanTel  
**File Name** U63713TT.EW0

**Notes**



**Post Event Notes**  
 Set up at 1550 Dwire Hill Rd. Geo spiked and weight bagged on front lawn.

**Microphone** Linear Weighting  
**PSPL** 121.5 dB(L) at 4.151 sec  
**ZC Freq** 5.9 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 605 mv )

	Tran	Vert	Long	
PPV	0.635	1.143	0.635	mm/s
ZC Freq	28	24	26	Hz
Time (Rel. to Trig)	-0.146	0.002	0.189	sec
Peak Acceleration	0.027	0.027	0.013	g
Peak Displacement	0.004	0.008	0.006	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.8	7.6	7.7	Hz
Overswing Ratio	3.4	3.7	3.6	

**Peak Vector Sum** 1.178 mm/s at 0.003 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:59:09 September 11, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q020I3TT.ELO

**Notes**

Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**

Set up in driveway of 1331 Dwire Hill rd. Geo spiked and weight bagged on packed gravel.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 98.84 dB(L) at 2.540 sec  
**ZC Freq** 6.0 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 568 mv)

	Tran	Vert	Long	
PPV	2.667	0.889	2.921	mm/s
ZC Freq	17	32	22	Hz
Time (Rel. to Trig)	0.578	0.121	0.514	sec
Peak Acceleration	0.040	0.027	0.040	g
Peak Displacement	0.026	0.007	0.021	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.9	7.4	7.7	Hz
Overswing Ratio	3.4	3.8	3.5	

Peak Vector Sum 2.976 mm/s at 0.514 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-09

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 10/07/2019 10:50

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instancel

Date: 10/07/19 Trigger Level: 1.23 mm/s Off dB Transverse: 106.451 mm/s 17.0 Hz

Time: 10:49 Calibration Date: 10/16/18 Vertical: 77.419 mm/s 18.0 Hz

Distance From Blast: 1,210.67 m Calibration Signal: Longitudinal: 74.193 mm/s 16.0 Hz

Direction From Blast: ENE Geophone Min. Freq.: 2.0 Hz

Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 97 dB --- Hz

Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght Vector Sum: 107.671 mm/s  
bagged. wet lawn.

Lat./Long.: 45° 15' 27.900" N 76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instancel

Date: 10/07/19 Trigger Level: 1.23 mm/s Off dB Transverse: 3.226 mm/s --- Hz

Time: 10:51 Calibration Date: 03/21/19 Vertical: 16.129 mm/s 18.0 Hz

Distance From Blast: 1,372.51 m Calibration Signal: Longitudinal: 22.581 mm/s 22.0 Hz

Direction From Blast: N Geophone Min. Freq.: 2.0 Hz

Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 114 dB --- Hz

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght Vector Sum: 23.495 mm/s  
bagged on wet covered lawn.

Lat./Long.: 45° 15' 59.300" N 76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Tran at 10:49:32 October 7, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q020I55S.QK0

**Notes**

Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**

Set up in driveway of 1331 Dwire Hill Rd. Geo spiked and weight bagged on lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 97.50 dB(L) at 2.903 sec  
**ZC Freq** 28 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 589 mv)

	Tran	Vert	Long	
PPV	4.191	3.048	2.921	mm/s
ZC Freq	17	18	16	Hz
Time (Rel. to Trig)	0.530	0.397	0.481	sec
Peak Acceleration	0.053	0.040	0.040	g
Peak Displacement	0.038	0.027	0.029	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.4	7.5	Hz
Overswing Ratio	3.6	3.9	3.5	

Peak Vector Sum 4.239 mm/s at 0.532 sec

**USBM R18507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 10:51:01 October 7, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 118.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** October 16, 2018 by InstanTel  
**File Name** Q589I55S.T10

**Notes**

**Post Event Notes**  
 Set up in front yard of 1550 Dwire Hill Rd. Geo spiked and weight bagged on wet lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 114.2 dB(L) at 3.010 sec  
**ZC Freq** 21 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 586 mv )

	Tran	Vert	Long	
PPV	0.127	0.635	0.889	mm/s
ZC Freq	N/A	18	22	Hz
Time (Rel. to Trig)	-0.250	-0.124	0.000	sec
Peak Acceleration	0.013	0.013	0.027	g
Peak Displacement	0.000	0.006	0.009	mm
<b>Sensor Check</b>	Check	Passed	Passed	
<b>Frequency</b>	113.8	7.9	7.9	Hz
<b>Overswing Ratio</b>	0.0	3.5	3.7	

**Peak Vector Sum** 0.925 mm/s at 0.098 sec  
 N/A: Not Applicable

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

**Sensor Check**

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-10

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 10/10/2019 10:43

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Wall

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instancel

Date: 10/10/19      Trigger Level: 1.23 mm/s      Off dB

Time: 10:43      Calibration Date: 09/20/19

Distance From Blast: 1,231.39 m      Calibration Signal:

Direction From Blast: ENE      Geophone Min. Freq.: 2.0 Hz

Readout:      Mic. Min. Freq.: 2.0 Hz

Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.

Lat./Long.: 45° 15' 27.900" N      76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm:

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record      Seismograph Type: instancel

Date: 10/10/19      Trigger Level: 1.23 mm/s      Off dB      Transverse: 2.794 mm/s      17.0 Hz

Time: 10:42      Calibration Date: 03/21/19      Vertical: 1.524 mm/s      16.0 Hz

Distance From Blast: 1,377.70 m      Calibration Signal:      Longitudinal: 2.794 mm/s      20.0 Hz

Direction From Blast: N      Geophone Min. Freq.: 2.0 Hz

Readout: Printed Copy      Mic. Min. Freq.: 2.0 Hz      Acoustic: 88 dB      --- Hz

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet lawn.      Vector Sum: 3.277 mm/s

Lat./Long.: 45° 15' 59.300" N      76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Tran at 10:42:23 October 10, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q02015BC.EN0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up in at end of driveway of 1550 Dwire Hill Rd. Geo spiked and weight bagged near gate.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** <88 dB(L)  
**ZC Freq** 23 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 639 mv )

	Tran	Vert	Long	
PPV	2.794	1.524	2.794	mm/s
ZC Freq	17	16	20	Hz
Time (Rel. to Trig)	0.584	0.337	0.487	sec
Peak Acceleration	0.040	0.040	0.040	g
Peak Displacement	0.028	0.014	0.022	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.8	7.4	7.7	Hz
Overswing Ratio	3.6	3.9	3.6	

Peak Vector Sum 3.277 mm/s at 0.582 sec  
 N/A: Not Applicable

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger = <math>\blacktriangleleft \blacktriangleright</math>

Sensor Check



No Trigger  
1331 Dwire Hill Rd.

Event Report: Monitor Log - MiniMate Plus # BE19637-Compliance

Start Time	End Time	Status
-----	-----	SERIAL NUMBER: BE19637
Oct 10 /19 10:18:35	Oct 10 /19 11:05:36	No events recorded. (Keyboard Exit) Geo: 1.70 mm/s Mic: 121.9 dB(L)

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2019-11

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 10/15/2019 10:25

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instancel  
Date: 10/15/19 Trigger Level: 1.23 mm/s Off dB Transverse: 1.524 mm/s 24.0 Hz  
Time: 10:25 Calibration Date: 09/20/19 Vertical: 0.762 mm/s 39.0 Hz  
Distance From Blast: 1,240.84 m Calibration Signal: Longitudinal: 1.905 mm/s 26.0 Hz  
Direction From Blast: ENE Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 117 dB --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn. Vector Sum: 2.048 mm/s  
Lat./Long.: 45° 15' 27.900" N 76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instancel  
Date: 10/15/19 Trigger Level: 1.23 mm/s Off dB Transverse: 1.016 mm/s 17.0 Hz  
Time: 10:23 Calibration Date: 03/21/19 Vertical: 0.508 mm/s 30.0 Hz  
Distance From Blast: 1,407.57 m Calibration Signal: Longitudinal: 0.889 mm/s 27.0 Hz  
Direction From Blast: N Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 94 dB --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet lawn. Vector Sum: 1.205 mm/s  
Lat./Long.: 45° 15' 59.300" N 76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Long at 10:23:21 October 15, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q02015KK.UX0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up at 1550 Dwire Hill rd. Geo spiked and weight bagged on front lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 93.98 dB(L) at 3.307 sec  
**ZC Freq** 12 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 617 mv )

	Tran	Vert	Long	
PPV	1.016	0.508	0.889	mm/s
ZC Freq	17	30	27	Hz
Time (Rel. to Trig)	0.113	-0.078	0.000	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.010	0.003	0.008	mm
<b>Sensor Check</b>	Check	Passed	Passed	
Frequency	8.5	7.5	7.5	Hz
Overswing Ratio	3.3	3.9	3.6	

Peak Vector Sum 1.205 mm/s at 0.113 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**Date/Time** Long at 10:25:54 October 15, 2019  
**Trigger Source** Geo: 1.700 mm/s, Mic: 121.9 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19637 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** September 25, 2019 by InstanTel  
**File Name** U63715KK.Z60

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up at 1331 Dwire Hill Rd. Geo spiked and weight bagged on lawn beside house.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 116.9 dB(L) at 3.004 sec  
**ZC Freq** 11 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 691 mv )

	Tran	Vert	Long	
PPV	1.524	0.762	1.905	mm/s
ZC Freq	24	39	26	Hz
Time (Rel. to Trig)	-0.093	0.166	0.175	sec
Peak Acceleration	0.040	0.027	0.040	g
Peak Displacement	0.011	0.003	0.011	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.5	7.5	7.5	Hz
Overswing Ratio	3.6	3.8	3.8	

**Peak Vector Sum** 2.048 mm/s at 0.192 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-12

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 11/13/2019 12:15

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 11/13/19                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 0.254 mm/s    --- Hz  
Time: 12:14                        Calibration Date: 03/21/19                    Vertical: 1.016 mm/s    39.0 Hz  
Distance From Blast: 1,427.99 m    Calibration Signal:                    Longitudinal: 1.27 mm/s    19.0 Hz  
Direction From Blast: N                    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy            Mic. Min. Freq.: 2.0 Hz                    Acoustic: 94 dB    --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet lawn.                    Vector Sum: 1.283 mm/s  
Lat./Long.: 45° 15' 59.300" N                    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm:

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 11/13/19                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 0.889 mm/s    37.0 Hz  
Time: 12:15                        Calibration Date: 09/20/19                    Vertical: 0.762 mm/s    47.0 Hz  
Distance From Blast: 1,266.44 m    Calibration Signal:                    Longitudinal: 1.27 mm/s    39.0 Hz  
Direction From Blast: ENE                    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy            Mic. Min. Freq.: 2.0 Hz                    Acoustic: 117 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.                    Vector Sum: 1.35 mm/s  
Lat./Long.: 45° 15' 27.900" N                    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Vert at 12:14:01 November 13, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q020I72F.BD0

**Notes**

Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**

Set up in front yard of 1550 Dwire Hille Rd. Geo spiked and weight bagged on frozen ground.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 93.98 dB(L) at 3.667 sec  
**ZC Freq** 18 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 758 mv )

	Tran	Vert	Long	
PPV	0.254	1.016	1.270	mm/s
ZC Freq	>100	39	19	Hz
Time (Rel. to Trig)	-0.103	0.002	0.627	sec
Peak Acceleration	0.013	0.027	0.027	g
Peak Displacement	0.000	0.005	0.010	mm
<b>Sensor Check</b>	Check	Passed	Passed	
Frequency	2.3	7.3	7.5	Hz
Overswing Ratio	1.0	4.1	3.8	

**Peak Vector Sum** 1.283 mm/s at 0.627 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Long at 12:15:19 November 13, 2019  
**Trigger Source** Geo: 1.230 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** October 23, 2019 by InstanTel  
**File Name** Q589I72F.DJ0

**Notes**

**Post Event Notes**  
 Set up in yard of 1331 Dwire Hill Rd. Geo spiked and weight bagged on frozen ground.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 116.7 dB(L) at 2.725 sec  
**ZC Freq** 11 Hz  
**Channel Test** Passed (Freq = 19.7 Hz Amp = 739 mv )

	Tran	Vert	Long	
PPV	0.889	0.762	1.270	mm/s
ZC Freq	37	47	39	Hz
Time (Rel. to Trig)	-0.007	-0.056	0.000	sec
Peak Acceleration	0.027	0.027	0.040	g
Peak Displacement	0.004	0.003	0.005	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.5	7.9	7.8	Hz
Overswing Ratio	4.8	3.6	3.8	

Peak Vector Sum 1.350 mm/s at 0.001 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



Blast No.: 2019-13

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 11/20/2019 15:56

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instantel  
Date: 11/20/19    Trigger Level: 1.23 mm/s    Off dB    Transverse: 1.524 mm/s    27.0 Hz  
Time: 15:56    Calibration Date: 09/20/19    Vertical: 0.508 mm/s    73.0 Hz  
Distance From Blast: 1,277.72 m    Calibration Signal:    Longitudinal: 1.397 mm/s    43.0 Hz  
Direction From Blast: ENE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 98 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.    Vector Sum: 1.943 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm:

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instantel  
Date: 11/20/19    Trigger Level: 1.23 mm/s    Off dB    Transverse: 1.778 mm/s    17.0 Hz  
Time: 15:55    Calibration Date: 03/21/19    Vertical: 1.016 mm/s    37.0 Hz  
Distance From Blast: 1,438.96 m    Calibration Signal:    Longitudinal: 1.27 mm/s    21.0 Hz  
Direction From Blast: N    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 109 dB    --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet lawn.    Vector Sum: 1.892 mm/s  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder



**Date/Time** Long at 15:56:12 November 20, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q02017FO.900

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up in yard of 1331 Dwire Hill Rd. Geo spiked and weight bagged on snow covered lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 97.50 dB(L) at 3.075 sec  
**ZC Freq** 19 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 766 mv )

	Tran	Vert	Long	
PPV	1.524	0.508	1.397	mm/s
ZC Freq	27	73	43	Hz
Time (Rel. to Trig)	0.361	-0.086	0.111	sec
Peak Acceleration	0.040	0.027	0.040	g
Peak Displacement	0.010	0.002	0.006	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.4	7.7	Hz
Overswing Ratio	3.7	4.0	3.7	

Peak Vector Sum 1.943 mm/s at 0.361 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =  $\blacktriangleleft$   $\blacktriangleright$

Sensor Check

**Date/Time** Tran at 15:55:55 November 20, 2019  
**Trigger Source** Geo: 1.200 mm/s, Mic: 116.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19637 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** September 25, 2019 by Instantel  
**File Name** U63717FO.970

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up in front yard of 1550 Dwire Hill Rd. Geo spiked and weight bagged on snow covered lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 109.2 dB(L) at 3.754 sec  
**ZC Freq** 9.7 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 660 mv )

	Tran	Vert	Long	
PPV	1.778	1.016	1.270	mm/s
ZC Freq	17	37	21	Hz
Time (Rel. to Trig)	0.545	0.015	0.728	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.017	0.007	0.011	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.6	7.6	7.6	Hz
Overswing Ratio	3.7	3.9	3.8	

Peak Vector Sum 1.892 mm/s at 0.728 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-14

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 11/21/2019 16:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 11/21/19                      Trigger Level: 1.23 mm/s    Off dB                      Transverse: 1.651 mm/s    20.0 Hz  
Time: 15:58                          Calibration Date: 09/20/19                      Vertical: 0.508 mm/s    34.0 Hz  
Distance From Blast: 1,283.82 m    Calibration Signal:                      Longitudinal: 0.889 mm/s    28.0 Hz  
Direction From Blast: ENE                      Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy                      Mic. Min. Freq.: 2.0 Hz                      Acoustic: 108 dB                      --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.                      Vector Sum: 1.694 mm/s  
Lat./Long.: 45° 15' 27.900" N                      76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 11/21/19                      Trigger Level: 1.23 mm/s    Off dB                      Transverse: 1.016 mm/s    21.0 Hz  
Time: 15:59                          Calibration Date: 03/21/19                      Vertical: 0.508 mm/s    28.0 Hz  
Distance From Blast: 1,405.43 m    Calibration Signal:                      Longitudinal: 1.143 mm/s    21.0 Hz  
Direction From Blast: N                          Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy                      Mic. Min. Freq.: 2.0 Hz                      Acoustic: 106 dB                      --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet lawn.                      Vector Sum: 1.276 mm/s  
Lat./Long.: 45° 15' 59.300" N                      76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Long at 15:59:59 November 21, 2019  
**Trigger Source** Geo: 1.100 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19636 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** July 31, 2019 by InstanTel  
**File Name** U63617HJ.3Z0

**Post Event Notes**

Set up in front yard of 1550 Dwire Hill Rd. Geo spiked and weight bagged on wet lawn.



**Notes**

**Microphone** Linear Weighting  
**PSPL** 106.5 dB(L) at 2.619 sec  
**ZC Freq** 6.3 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 691 mv )

	Tran	Vert	Long	
PPV	1.016	0.508	1.143	mm/s
ZC Freq	21	28	21	Hz
Time (Rel. to Trig)	-0.169	-0.135	0.000	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.008	0.005	0.009	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.6	7.4	7.5	Hz
Overswing Ratio	3.8	3.9	3.9	

Peak Vector Sum 1.276 mm/s at -0.173 sec

**USBM R18507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Tran at 16:58:02 November 21, 2019  
**Trigger Source** Geo: 1.100 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19638 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.2 Volts  
**Unit Calibration** March 27, 2019 by InstanTel  
**File Name** U638I7HL.SQ0  
**Post Event Notes**  
 Geo spiked and weight bagged at end of driveway of 1331 Dwire Hill Rd.

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 107.5 dB(L) at 3.499 sec  
**ZC Freq** 8.8 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 647 mv )

	Tran	Vert	Long	
PPV	1.651	0.508	0.889	mm/s
ZC Freq	20	34	28	Hz
Time (Rel. to Trig)	0.031	0.198	-0.102	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.013	0.003	0.007	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.4	7.5	7.4	Hz
Overswing Ratio	3.8	3.7	3.9	

Peak Vector Sum 1.694 mm/s at 0.031 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger = ▶ ◀

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-15

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 12/02/2019 11:33

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 12/02/19                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 0.889 mm/s    26.0 Hz  
Time: 11:34                        Calibration Date: 09/20/19                    Vertical: 0.381 mm/s    --- Hz  
Distance From Blast: 1,298.14 m    Calibration Signal:                    Longitudinal: 0.508 mm/s    34.0 Hz  
Direction From Blast: ENE            Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy            Mic. Min. Freq.: 2.0 Hz                    Acoustic: 99 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. wet lawn.                    Vector Sum: 0.976 mm/s  
Lat./Long.: 45° 15' 27.900" N                    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 12/02/19                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 1.651 mm/s    18.0 Hz  
Time: 11:36                        Calibration Date: 03/21/19                    Vertical: 0.635 mm/s    39.0 Hz  
Distance From Blast: 1,432.56 m    Calibration Signal:                    Longitudinal: 0.635 mm/s    30.0 Hz  
Direction From Blast: N                Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy            Mic. Min. Freq.: 2.0 Hz                    Acoustic: 108 dB    --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on wet lawn.                    Vector Sum: 1.727 mm/s  
Lat./Long.: 45° 15' 59.300" N                    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Tran at 11:34:52 December 2, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q020181K.640

**Notes**

Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**

Set up at 1331 Dwire Hill Rd. Geo spiked and weight bagged in yard on lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** <88 dB(L)  
**ZC Freq** >100 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 673 mv )

	Tran	Vert	Long	
PPV	0.889	0.381	0.508	mm/s
ZC Freq	26	>100	34	Hz
Time (Rel. to Trig)	0.000	-0.183	-0.166	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.007	0.001	0.003	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.6	7.4	7.5	Hz
Overswing Ratio	3.8	4.0	3.8	

**Peak Vector Sum** 0.976 mm/s at 0.220 sec  
 N/A: Not Applicable

**USBM R18507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**Date/Time** Tran at 11:36:41 December 2, 2019  
**Trigger Source** Geo: 1.230 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** October 23, 2019 by InstanTel  
**File Name** Q589I81K.950

**Notes**

**Post Event Notes**

Set up at 1550 Dwire Hill Rd. Geo spiked and weight bagged on front lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 107.5 dB(L) at 3.729 sec  
**ZC Freq** 3.6 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 742 mv )

	Tran	Vert	Long	
PPV	1.651	0.635	0.635	mm/s
ZC Freq	18	39	30	Hz
Time (Rel. to Trig)	0.205	-0.094	-0.126	sec
Peak Acceleration	0.027	0.013	0.027	g
Peak Displacement	0.014	0.004	0.005	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.8	7.9	8.1	Hz
Overswing Ratio	4.6	3.6	3.8	

**Peak Vector Sum** 1.727 mm/s at 0.205 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check



**AUSTIN POWDER LTD.  
BLAST REPORT**



Blast No.: 2019-16

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 12/04/2019 13:59

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 12/04/19                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 1.905 mm/s    18.0 Hz  
Time: 13:59                      Calibration Date: 09/20/19                    Vertical: 0.635 mm/s    26.0 Hz  
Distance From Blast: 1,303.02 m    Calibration Signal:                    Longitudinal: 1.143 mm/s    20.0 Hz  
Direction From Blast: ENE            Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy            Mic. Min. Freq.: 2.0 Hz                    Acoustic: 104 dB            --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. snow covered lawn.                    Vector Sum: 1.926 mm/s  
Lat./Long.: 45° 15' 27.900" N                    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: No Trigger            Seismograph Type: instancel  
Date: 12/04/19                    Trigger Level: 1.23 mm/s    Off dB  
Time: 14:00                      Calibration Date: 03/21/19  
Distance From Blast: 1,424.64 m    Calibration Signal:  
Direction From Blast: N            Geophone Min. Freq.: 2.0 Hz  
Readout:                            Mic. Min. Freq.: 2.0 Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on snow covered lawn.  
Lat./Long.: 45° 15' 59.300" N                    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Tran at 13:59:15 December 4, 2019  
**Trigger Source** Geo: 1.100 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 7.0 sec at 1024 sps

**Serial Number** BE19636 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.2 Volts  
**Unit Calibration** July 31, 2019 by InstanTel  
**File Name** U636I85G.6R0

**Notes**



**Post Event Notes**  
 Set up at 1330 Dwire Hill Rd. Geo spiked and weight bagged on snow covered lawn.

**Microphone** Linear Weighting  
**PSPL** 104.2 dB(L) at 3.412 sec  
**ZC Freq** 15 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 684 mv )

	Tran	Vert	Long	
PPV	1.905	0.635	1.143	mm/s
ZC Freq	18	26	20	Hz
Time (Rel. to Trig)	0.335	0.660	0.390	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.017	0.005	0.010	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.8	7.4	7.5	Hz
Overswing Ratio	3.7	3.9	3.9	

Peak Vector Sum 1.926 mm/s at 0.200 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

No Trigger  
1550 Dwire Hill Rd

Event Report: Monitor Log - MiniMate Plus # BE19637-Compliance

Start Time	End Time	Status
-----	-----	SERIAL NUMBER: BE19637
Dec 4 /19 09:47:26		Start Monitoring Trigger Level: Geo: 1.20 mm/s Mic: 116.0 dB(L)
Dec 4 /19 10:30:30	Dec 4 /19 10:30:36	Event recorded. Trigger Level MicL: 116.0 dB(L)
Dec 4 /19 10:30:49	Dec 4 /19 10:50:34	No events recorded. (Keyboard Exit) Geo: 1.20 mm/s Mic: 116.0 dB(L)
Dec 4 /19 13:09:52	Dec 4 /19 14:16:19	No events recorded. (Keyboard Exit) Geo: 1.20 mm/s Mic: 116.0 dB(L)



**AUSTIN POWDER LTD.**  
**BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-17

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 12/10/2019 09:31

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel

Date: 12/10/19                      Trigger Level: 1.23 mm/s    Off dB                      Transverse: 0.127 mm/s    --- Hz

Time: 09:32                          Calibration Date: 09/20/19                      Vertical: 0.127 mm/s    --- Hz

Distance From Blast: 1,286.87 m    Calibration Signal:                      Longitudinal: 0.127 mm/s    --- Hz

Direction From Blast: ENE              Geophone Min. Freq.: 2.0 Hz

Readout: Printed Copy              Mic. Min. Freq.: 2.0 Hz                      Acoustic: 113 dB    --- Hz

Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. snow covered lawn.                      Vector Sum: 0.22 mm/s

Lat./Long.: 45° 15' 27.900" N                      76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel

Date: 12/10/19                      Trigger Level: 1.23 mm/s    Off dB                      Transverse: 1.651 mm/s    20.0 Hz

Time: 09:30                          Calibration Date: 03/21/19                      Vertical: 0.508 mm/s    26.0 Hz

Distance From Blast: 1,390.50 m    Calibration Signal:                      Longitudinal: 0.889 mm/s    14.0 Hz

Direction From Blast: N                  Geophone Min. Freq.: 2.0 Hz

Readout: Printed Copy              Mic. Min. Freq.: 2.0 Hz                      Acoustic: 88 dB    --- Hz

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on snow covered lawn.                      Vector Sum: 1.875 mm/s

Lat./Long.: 45° 15' 59.300" N                      76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Tran at 09:30:19 December 10, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q02018G7.QJ0

**Notes**

Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**

Set up in front yard of 1550 Dwire Hill Rd. Geo spiked and weight bagged on wet lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** <88 dB(L)  
**ZC Freq** >100 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 656 mv)

	Tran	Vert	Long	
PPV	1.651	0.508	0.889	mm/s
ZC Freq	20	26	14	Hz
Time (Rel. to Trig)	0.130	0.176	0.136	sec
Peak Acceleration	0.080	0.013	0.027	g
Peak Displacement	0.027	0.004	0.011	mm
Sensor Check	Check	Passed	Passed	
Frequency	13.7	7.3	7.5	Hz
Overswing Ratio	6.7	4.0	3.7	

**Peak Vector Sum** 1.875 mm/s at 0.136 sec  
**N/A: Not Applicable**

**USBM R18507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

Date/Time MicL at 09:32:24 December 10, 2019  
 Trigger Source Geo: 1.230 mm/s, Mic: 110.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 5.0 sec at 1024 sps

Serial Number BE15589 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.4 Volts  
 Unit Calibration October 23, 2019 by InstanTel  
 File Name Q589I8G7.U00

Notes

Post Event Notes  
 Set up in backyard of 1331 Dwire Hill Rd. Geo spiked and weight bagged on wet lawn.



Extended Notes

Microphone Linear Weighting  
 PSPL 113.3 dB(L) at 0.051 sec  
 ZC Freq 14 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 703 mv )

	Tran	Vert	Long	
PPV	0.127	0.127	0.127	mm/s
ZC Freq	>100	>100	>100	Hz
Time (Rel. to Trig)	-0.241	-0.212	-0.236	sec
Peak Acceleration	0.013	0.013	0.013	g
Peak Displacement	0.000	0.000	0.000	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.5	7.9	7.9	Hz
Overswing Ratio	4.8	3.6	3.8	

Peak Vector Sum 0.220 mm/s at 0.321 sec

USBM RI8507 And OSMRE



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2019-18

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 12/13/2019 09:59

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instantel  
Date: 12/13/19                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 0.127 mm/s    --- Hz  
Time: 09:59                    Calibration Date: 03/21/19                    Vertical: 0.127 mm/s    --- Hz  
Distance From Blast: 1,363.68 m    Calibration Signal:                    Longitudinal: 0.127 mm/s    --- Hz  
Direction From Blast: NNE                    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy                    Mic. Min. Freq.: 2.0 Hz                    Acoustic: 111 dB    --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged on snow covered lawn.                    Vector Sum: 0.22 mm/s  
Lat./Long.: 45° 15' 59.300" N                    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instantel  
Date: 12/13/19                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 1.27 mm/s    21.0 Hz  
Time: 09:57                    Calibration Date: 09/20/19                    Vertical: 0.635 mm/s    30.0 Hz  
Distance From Blast: 1,289.00 m    Calibration Signal:                    Longitudinal: 0.762 mm/s    23.0 Hz  
Direction From Blast: ENE                    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy                    Mic. Min. Freq.: 2.0 Hz                    Acoustic: 88 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged. snow covered lawn.                    Vector Sum: 1.426 mm/s  
Lat./Long.: 45° 15' 27.900" N                    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** MicL at 09:59:27 December 13, 2019  
**Trigger Source** Geo: 1.230 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** October 23, 2019 by Instantel  
**File Name** Q589I8LT.330

**Notes**



**Post Event Notes**  
 Set up at 1331 Dwire Hill Rd. Geo spiked and weight bagged on frozen lawn.

**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 110.6 dB(L) at 0.001 sec  
**ZC Freq** 8.5 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 691 mv )

	Tran	Vert	Long	
PPV	0.127	0.127	0.127	mm/s
ZC Freq	>100	>100	>100	Hz
Time (Rel. to Trig)	-0.248	-0.240	-0.249	sec
Peak Acceleration	0.027	0.013	0.027	g
Peak Displacement	0.000	0.000	0.000	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.4	7.9	7.9	Hz
Overswing Ratio	4.8	3.6	3.8	

Peak Vector Sum 0.220 mm/s at 0.123 sec



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =  $\blacktriangleleft$   $\blacktriangleright$

Sensor Check



**Date/Time** Tran at 09:57:17 December 13, 2019  
**Trigger Source** Geo: 0.930 mm/s, Mic: 119.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 6.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.1 Volts  
**Unit Calibration** April 1, 2019 by InstanTel  
**File Name** Q020I8LS.ZH0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up at 1550 Dwire Hill Rd. Geo spiked and weight bagged on frozen lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** <88 dB(L)  
**ZC Freq** >100 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 712 mv )

	Tran	Vert	Long	
PPV	1.270	0.635	0.762	mm/s
ZC Freq	21	30	23	Hz
Time (Rel. to Trig)	0.218	0.218	0.322	sec
Peak Acceleration	0.027	0.027	0.013	g
Peak Displacement	0.010	0.004	0.006	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.6	7.4	7.5	Hz
Overswing Ratio	3.8	4.0	3.7	

**Peak Vector Sum** 1.426 mm/s at 0.218 sec  
**N/A:** Not Applicable

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2020-01

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 04/01/2020 09:00

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North Wall

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record Seismograph Type: instantel

Date: 04/01/20 Trigger Level: 1.23 mm/s Off dB Transverse: 2.032 mm/s 22.0 Hz

Time: 09:00 Calibration Date: 09/23/19 Vertical: 1.524 mm/s 43.0 Hz

Distance From Blast: 811.38 m Calibration Signal: Longitudinal: 2.794 mm/s 26.0 Hz

Direction From Blast: NE Geophone Min. Freq.: 2.0 Hz

Readout: Printed Copy Mic. Min. Freq.: 2.0 Hz Acoustic: 104 dB --- Hz

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged. Vector Sum: 3.228 mm/s

Lat./Long.: 45° 15' 59.300" N 76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger Seismograph Type: instantel

Date: 04/01/20 Trigger Level: 1.23 mm/s Off dB

Time: 09:00 Calibration Date: 09/20/19

Distance From Blast: 1,620.01 m Calibration Signal:

Direction From Blast: ESE Geophone Min. Freq.: 2.0 Hz

Readout: Mic. Min. Freq.: 2.0 Hz

Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.

Lat./Long.: 45° 15' 27.900" N 76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Joel McNamee, Austin Powder

**Date/Time** Vert at 09:00:47 April 1, 2020  
**Trigger Source** Geo: 1.200 mm/s, Mic: 116.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19637 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** September 25, 2019 by Instantel  
**File Name** U637IE9F.PB0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up at 1550 Drire Hill Rd. Geo spiked and weight bagged on wet lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 104.2 dB(L) at 2.300 sec  
**ZC Freq** 2.6 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 648 mv )

	Tran	Vert	Long	
PPV	2.032	1.524	2.794	mm/s
ZC Freq	22	43	26	Hz
Time (Rel. to Trig)	0.329	0.021	0.417	sec
Peak Acceleration	0.040	0.040	0.053	g
Peak Displacement	0.017	0.007	0.018	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.7	7.6	7.6	Hz
Overswing Ratio	3.6	3.9	3.8	

Peak Vector Sum 3.228 mm/s at 0.419 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2020-02

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 04/02/2020 10:12

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Wall

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL					
Date:	04/02/20	Trigger Level:	1.23 mm/s	Off dB	Transverse:	3.556 mm/s	17.0 Hz	
Time:	10:11	Calibration Date:	09/23/19		Vertical:	1.905 mm/s	34.0 Hz	
Distance From Blast:	875.39 m	Calibration Signal:			Longitudinal:	5.08 mm/s	24.0 Hz	
Direction From Blast:	NE	Geophone Min. Freq.:	2.0 Hz		Acoustic:	119 dB	---	Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Vector Sum:	5.27 mm/s		
Location:	Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.							
Lat./Long.:	45° 15' 59.300" N		76° 7' 28.700" W					
Reader and Firm:	William Coleman, AUSTIN POWDER							
Analyst and Firm:								
Installer and Firm:	Joel McNamee, Austin Powder							

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instanTEL					
Date:	04/02/20	Trigger Level:	1.23 mm/s	Off dB	Transverse:	0.127 mm/s	---	Hz
Time:	10:12	Calibration Date:	09/20/19		Vertical:	0.127 mm/s	---	Hz
Distance From Blast:	1,693.16 m	Calibration Signal:			Longitudinal:	0.127 mm/s	---	Hz
Direction From Blast:	ESE	Geophone Min. Freq.:	2.0 Hz		Acoustic:	121 dB	---	Hz
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Vector Sum:	0.22 mm/s		
Location:	Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.							
Lat./Long.:	45° 15' 27.900" N		76° 6' 50.100" W					
Reader and Firm:	William Coleman, AUSTIN POWDER							
Analyst and Firm:								
Installer and Firm:	Joel McNamee, Austin Powder							

**Date/Time** MicL at 10:12:16 April 2, 2020  
**Trigger Source** Geo: 1.230 mm/s, Mic: 110.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** October 23, 2019 by InstanTel  
**File Name** Q589IEBD.OGO

**Notes**

**Post Event Notes**  
 Set up at 1331 Dwire Hill Rd. Geo spiked and weight bagged on Wet gravel.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 121.3 dB(L) at 0.201 sec  
**ZC Freq** 13 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 662 mv )

	Tran	Vert	Long	
PPV	0.127	0.127	0.127	mm/s
ZC Freq	>100	>100	>100	Hz
Time (Rel. to Trig)	-0.245	-0.167	-0.247	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.000	0.000	0.000	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.5	7.9	7.9	Hz
Overswing Ratio	4.8	3.6	3.8	

**Peak Vector Sum** 0.220 mm/s at 0.782 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

Date/Time Vert at 10:11:50 April 2, 2020  
 Trigger Source Geo: 1.200 mm/s, Mic: 116.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 5.0 sec at 1024 sps

Serial Number BE19637 V 10.72-8.17 MiniMate Plus  
 Battery Level 6.3 Volts  
 Unit Calibration September 25, 2019 by InstanTel  
 File Name U637IEBD.NQ0

Post Event Notes  
 Set up at 1551 Dwire Hill Rd. Geo spiked and weight bagged on wet lawn.

Notes

Location:  
 Client:  
 User Name:  
 General:



Extended Notes

Microphone Linear Weighting  
 PSPL 119.4 dB(L) at 2.353 sec  
 ZC Freq 5.6 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 609 mv )

	Tran	Vert	Long	
PPV	3.556	1.905	5.080	mm/s
ZC Freq	17	34	24	Hz
Time (Rel. to Trig)	0.862	0.248	0.445	sec
Peak Acceleration	0.053	0.053	0.080	g
Peak Displacement	0.030	0.008	0.036	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.6	7.6	7.6	Hz
Overswing Ratio	3.6	3.8	3.8	

Peak Vector Sum 5.270 mm/s at 0.445 sec

USBM RI8507 And OSMRE



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check



# AUSTIN POWDER LTD. BLAST REPORT



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2020-03

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONSTRUCTION  
(THO1100-002)

Date/Time: 04/06/2020 10:27

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Wall

## SEISMOGRAPH 1 - 1550 DWIRE HILL RD

Data Type:	Seismic Record	Seismograph Type:	instanTEL						
Date:	04/06/20	Trigger Level:	1.23 mm/s	Off dB	Transverse:	2.667 mm/s	15.0 Hz		
Time:	10:27	Calibration Date:	09/23/19		Vertical:	1.27 mm/s	39.0 Hz		
Distance From Blast:	843.69 m	Calibration Signal:			Longitudinal:	3.048 mm/s	26.0 Hz		
Direction From Blast:	NE	Geophone Min. Freq.:	2.0 Hz		Acoustic:	120 dB	---	Hz	
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Vector Sum:	3.069 mm/s			
Location:	Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.								
Lat./Long.:	45° 15' 59.300" N		76° 7' 28.700" W						
Reader and Firm:	William Coleman, AUSTIN POWDER								
Analyst and Firm:									
Installer and Firm:	Austin Harrison, Austin Powder								

## SEISMOGRAPH 2 - 1331 DWIRE HILL RD

Data Type:	Seismic Record	Seismograph Type:	instanTEL						
Date:	04/06/20	Trigger Level:	1.23 mm/s	Off dB	Transverse:	0.127 mm/s	---	Hz	
Time:	10:27	Calibration Date:	09/20/19		Vertical:	0.127 mm/s	---	Hz	
Distance From Blast:	1,661.16 m	Calibration Signal:			Longitudinal:	0.127 mm/s	---	Hz	
Direction From Blast:	ESE	Geophone Min. Freq.:	2.0 Hz		Acoustic:	115 dB	---	Hz	
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Vector Sum:	0.22 mm/s			
Location:	Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.								
Lat./Long.:	45° 15' 27.900" N		76° 6' 50.100" W						
Reader and Firm:	William Coleman, AUSTIN POWDER								
Analyst and Firm:									
Installer and Firm:	Austin Harrison, Austin Powder								

Date/Time Vert at 10:27:25 April 6, 2020  
 Trigger Source Geo: 1.200 mm/s, Mic: 116.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 5.0 sec at 1024 sps

Serial Number BE19637 V 10.72-8.17 MiniMate Plus  
 Battery Level 6.3 Volts  
 Unit Calibration September 25, 2019 by InstanTel  
 File Name U637IEIT.1P0

Post Event Notes  
 Set up on front lawn of 1550 Dwire Hill Rd. Geo spiked and weight bagged on saturated lawn.

Notes

Location:  
 Client:  
 User Name:  
 General:



Extended Notes

Microphone Linear Weighting  
 PSPL 120.5 dB(L) at 2.131 sec  
 ZC Freq 20 Hz  
 Channel Test Passed (Freq = 20.5 Hz Amp = 637 mv)

	Tran	Vert	Long	
PPV	2.667	1.270	3.048	mm/s
ZC Freq	15	39	26	Hz
Time (Rel. to Trig)	1.143	0.364	0.422	sec
Peak Acceleration	0.027	0.040	0.053	g
Peak Displacement	0.032	0.008	0.020	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.7	7.5	7.6	Hz
Overswing Ratio	3.6	3.8	3.7	

Peak Vector Sum 3.069 mm/s at 0.422 sec

USBM RI8507 And OSMRE



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check



Date/Time MicL at 10:27:58 April 6, 2020  
 Trigger Source Geo: 1.230 mm/s, Mic: 110.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 5.0 sec at 1024 sps

Serial Number BE15589 V 10.72-1.1 Minimate Blaster  
 Battery Level 6.4 Volts  
 Unit Calibration October 23, 2019 by Instantel  
 File Name Q589IEIT.2M0

Post Event Notes  
 Set up at end of driveway of 1331 Dwire Hill Rd. Geo spiked and weight bagged on wet grass.

Notes



Extended Notes

Microphone Linear Weighting  
 PSPL 114.8 dB(L) at 0.006 sec  
 ZC Freq 13 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 594 mv )

	Tran	Vert	Long	
PPV	0.127	0.127	0.127	mm/s
ZC Freq	N/A	>100	N/A	Hz
Time (Rel. to Trig)	-0.250	-0.232	-0.250	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.000	0.000	0.000	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.4	7.9	7.8	Hz
Overswing Ratio	4.8	3.5	3.7	

Peak Vector Sum 0.220 mm/s at 0.213 sec  
 N/A: Not Applicable

USBM R18507 And OSMRE



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check



# AUSTIN POWDER LTD. BLAST REPORT



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2020-04

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONST.-W. CARLTON  
(THO1100-002)

Date/Time: 04/08/2020 12:30

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Corner

## SEISMOGRAPH 1 - 1550 DWIRE HILL RD

Data Type: Seismic Record    Seismograph Type: instantel

Date: 04/08/20    Trigger Level: 1.23 mm/s    Off dB    Transverse: 4.572 mm/s    16.0 Hz

Time: 12:30    Calibration Date: 09/23/19    Vertical: 1.778 mm/s    57.0 Hz

Distance From Blast: 846.12 m    Calibration Signal:    Longitudinal: 2.921 mm/s    19.0 Hz

Direction From Blast: NE    Geophone Min. Freq.: 2.0 Hz

Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 113 dB    --- Hz

Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: 4.968 mm/s

Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Austin Harrison, Austin Powder

## SEISMOGRAPH 2 - 1331 DWIRE HILL RD

Data Type: No Trigger    Seismograph Type: instantel

Date: 04/08/20    Trigger Level: 1.23 mm/s    Off dB

Time: 12:30    Calibration Date: 09/20/19

Distance From Blast: 1,669.39 m    Calibration Signal:

Direction From Blast: ESE    Geophone Min. Freq.: 2.0 Hz

Readout:    Mic. Min. Freq.: 2.0 Hz

Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.

Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W

Reader and Firm: William Coleman, AUSTIN POWDER

Analyst and Firm:

Installer and Firm: Austin Harrison, Austin Powder

Date/Time Vert at 12:30:04 April 8, 2020  
 Trigger Source Geo: 1.100 mm/s, Mic: 110.0 dB(L)  
 Range Geo: 254.0 mm/s  
 Record Time 7.0 sec at 1024 sps

Serial Number BE19636 V 10.72-8.17 MiniMate Plus  
 Battery Level 6.4 Volts  
 Unit Calibration July 31, 2019 by Instantel  
 File Name U636IEMO.240

Notes



Post Event Notes  
 Set up in front yard of 1550 Dwire Hill Rd. Geo spiked and weight bagged on wet lawn.

Microphone Linear Weighting  
 PSPL 113.1 dB(L) at 2.476 sec  
 ZC Freq 14 Hz  
 Channel Test Passed (Freq = 20.1 Hz Amp = 632 mv )

	Tran	Vert	Long	
PPV	4.572	1.778	2.921	mm/s
ZC Freq	16	57	19	Hz
Time (Rel. to Trig)	0.948	0.218	0.467	sec
Peak Acceleration	0.053	0.066	0.053	g
Peak Displacement	0.048	0.013	0.024	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.4	7.4	7.4	Hz
Overswing Ratio	3.8	3.8	3.9	

Peak Vector Sum 4.968 mm/s at 0.951 sec

USBM RI8507 And OSMRE



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

No Trigger  
1331 Dwire Hill Rd

Event Report: Monitor Log - MiniMate Plus # BE19637-Compliance

Start Time	End Time	Status
Apr 8 /20 11:55:30	Apr 8 /20 12:42:29	SERIAL NUMBER: BE19637 No events recorded. (Keyboard Exit) Geo: 1.20 mm/s Mic: 116.0 dB(L)



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2020-05

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONST.-W. CARLTON  
(THO1100-002)

Date/Time: 09/22/2020 10:31

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instantel				
Date:	09/22/20	Trigger Level:	1.23 mm/s	Off dB	Transverse:	1.397 mm/s	19.0 Hz
Time:	10:31	Calibration Date:	04/17/20		Vertical:	1.016 mm/s	27.0 Hz
Distance From Blast:	911.66 m	Calibration Signal:			Longitudinal:	2.286 mm/s	20.0 Hz
Direction From Blast:	NE	Geophone Min. Freq.:	2.0 Hz				
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	119 dB	--- Hz
Location:	Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.				Vector Sum:	1.376 mm/s	
Lat./Long.:	45° 15' 59.300" N		76° 7' 28.700" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:	Cory Bragan, Austin Powder						

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type:	Seismic Record	Seismograph Type:	instantel				
Date:	09/22/20	Trigger Level:	1.23 mm/s	Off dB	Transverse:	0.127 mm/s	--- Hz
Time:	10:31	Calibration Date:	10/23/19		Vertical:	0.254 mm/s	--- Hz
Distance From Blast:	1,690.42 m	Calibration Signal:			Longitudinal:	0.127 mm/s	--- Hz
Direction From Blast:	E	Geophone Min. Freq.:	2.0 Hz				
Readout:	Printed Copy	Mic. Min. Freq.:	2.0 Hz		Acoustic:	119 dB	--- Hz
Location:	Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.				Vector Sum:	0.284 mm/s	
Lat./Long.:	45° 15' 27.900" N		76° 6' 50.100" W				
Reader and Firm:	William Coleman, AUSTIN POWDER						
Analyst and Firm:							
Installer and Firm:							

**Date/Time** MicL at 10:31:46 September 22, 2020  
**Trigger Source** Geo: 1.000 mm/s, Mic: 115.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 12.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.3 Volts  
**Unit Calibration** October 23, 2019 by Instantel  
**File Name** Q589IN7R.WY0

**Post Event Notes**

Set up at end of driveway of 1331 Dwire Hill Rd. Geo spiked and weight bagged on packed gravel.

**Notes**

Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 118.5 dB(L) at 0.008 sec  
**ZC Freq** 13 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 623 mv)

	Tran	Vert	Long	
PPV	0.127	0.254	0.127	mm/s
ZC Freq	>100	>100	>100	Hz
Time (Rel. to Trig)	-0.201	0.108	-0.243	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.000	0.000	0.000	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.5	7.9	7.9	Hz
Overswing Ratio	4.8	3.5	3.7	

**Peak Vector Sum** 0.284 mm/s at 0.108 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2020-06

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONST.-W. CARLTON  
(THO1100-002)

Date/Time: 09/25/2020 11:31

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instantel  
Date: 09/25/20                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 1.397 mm/s    16.0 Hz  
Time: 11:31                        Calibration Date: 04/17/20                    Vertical: 1.016 mm/s    57.0 Hz  
Distance From Blast: 924.15 m    Calibration Signal:                    Longitudinal: 1.016 mm/s    39.0 Hz  
Direction From Blast: NE            Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy            Mic. Min. Freq.: 2.0 Hz                    Acoustic: 115 dB            --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.                    Vector Sum: 1.497 mm/s  
Lat./Long.: 45° 15' 59.300" N                    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Cory Bragan, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger            Seismograph Type: instantel  
Date: 09/25/20                    Trigger Level: 1.23 mm/s    Off dB  
Time: 11:31                        Calibration Date: 10/23/19  
Distance From Blast: 1,715.11 m    Calibration Signal:  
Direction From Blast: ESE            Geophone Min. Freq.: 2.0 Hz  
Readout:                            Mic. Min. Freq.: 2.0 Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.  
Lat./Long.: 45° 15' 27.900" N                    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Cory Bragan, Austin Powder

**Date/Time** Vert at 11:31:03 September 25, 2020  
**Trigger Source** Geo: 1.000 mm/s, Mic: 115.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 12.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** October 23, 2019 by InstanTel  
**File Name** Q589INDE.NR0  
**Post Event Notes**

Geo spiked and weight bagged in front yard of 1550 Dwire Hill Rd.

**Notes**



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 114.6 dB(L) at 1.921 sec  
**ZC Freq** 13 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 599 mv)

	Tran	Vert	Long	
PPV	1.397	1.016	1.016	mm/s
ZC Freq	16	57	39	Hz
Time (Rel. to Trig)	0.168	0.000	0.009	sec
Peak Acceleration	0.027	0.040	0.027	g
Peak Displacement	0.013	0.004	0.005	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.5	8.1	7.8	Hz
Overswing Ratio	4.8	3.4	3.7	

**Peak Vector Sum** 1.497 mm/s at 0.302 sec

**USBM R18507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check



No Trigger.

Event Report: Monitor Log - Minimate Blaster # BE15020-Compliance

Start Time	End Time	Status
----- Sep 25 /20 08:58:47	----- Sep 25 /20 11:54:59	SERIAL NUMBER: BE15020 No events recorded. (Keyboard Exit) Geo: 1.000 mm/s Mic: 113.0 dB(L)

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2020-07

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONST.-W. CARLTON  
(THO1100-002)

Date/Time: 09/28/2020 11:33

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: North West Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 09/28/20    Trigger Level: 1.23 mm/s    Off dB    Transverse: 2.794 mm/s    14.0 Hz  
Time: 11:33    Calibration Date: 10/23/19    Vertical: 1.143 mm/s    47.0 Hz  
Distance From Blast: 845.52 m    Calibration Signal:    Longitudinal: 2.159 mm/s    26.0 Hz  
Direction From Blast: NE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 117 dB    --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: 2.797 mm/s  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Robert Turton, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: No Trigger    Seismograph Type: instancel  
Date: 09/28/20    Trigger Level: 1.23 mm/s    Off dB  
Time: 11:33    Calibration Date: 04/17/20  
Distance From Blast: 1,676.40 m    Calibration Signal:  
Direction From Blast: ESE    Geophone Min. Freq.: 2.0 Hz  
Readout:    Mic. Min. Freq.: 2.0 Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Rob Turton, Austin Powder

**Date/Time** Vert at 11:33:19 September 28, 2020  
**Trigger Source** Geo: 1.000 mm/s, Mic: 115.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 12.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** October 23, 2019 by Instantel  
**File Name** Q589INIY.RJ0

**Post Event Notes**  
 Set up in front yard of 1550 Dwire Hill Rd. Geo siked and weight bagged on front lawn.

**Notes**



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 117.1 dB(L) at 2.380 sec  
**ZC Freq** 8.3 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 562 mv )

	Tran	Vert	Long	
PPV	2.794	1.143	2.159	mm/s
ZC Freq	14	47	26	Hz
Time (Rel. to Trig)	0.867	0.001	0.585	sec
Peak Acceleration	0.040	0.040	0.053	g
Peak Displacement	0.035	0.008	0.016	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.6	7.9	7.8	Hz
Overswing Ratio	4.7	3.4	3.6	

Peak Vector Sum 2.797 mm/s at 0.867 sec

**USBM R18507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

No Trigger.

Event Report: Monitor Log - Minimate Blaster # BE15020-Compliance

Start Time	End Time	Status
-----	-----	SERIAL NUMBER: BE15020
Sep 25 /20 08:58:47	Sep 25 /20 11:54:59	No events recorded. (Keyboard Exit) Geo: 1.000 mm/s Mic: 113.0 dB(L)
Sep 28 /20 10:31:55	Sep 28 /20 12:05:49	No events recorded. (Keyboard Exit) Geo: 1.000 mm/s Mic: 113.0 dB(L)

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2020-08

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONST.-W. CARLTON  
(THO1100-002)

Date/Time: 10/28/2020 13:17

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1550 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instantel  
Date: 10/28/20                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 0.381 mm/s    19.0 Hz  
Time: 13:18                    Calibration Date: 04/17/20                    Vertical: 0.381 mm/s    27.0 Hz  
Distance From Blast: 1,419.15 m    Calibration Signal:                    Longitudinal: 0.381 mm/s    17.0 Hz  
Direction From Blast: NNE                    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy                    Mic. Min. Freq.: 2.0 Hz                    Acoustic: 116 dB                    --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.                    Vector Sum: 0.554 mm/s  
Lat./Long.: 45° 15' 59.300" N                    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: William Coleman, Austin Powder

**SEISMOGRAPH 2 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instantel  
Date: 10/28/20                    Trigger Level: 1.23 mm/s    Off dB                    Transverse: 1.397 mm/s    15.0 Hz  
Time: 13:17                    Calibration Date: 04/17/20                    Vertical: 0.635 mm/s    47.0 Hz  
Distance From Blast: 1,320.09 m    Calibration Signal:                    Longitudinal: 0.762 mm/s    20.0 Hz  
Direction From Blast: ENE                    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy                    Mic. Min. Freq.: 2.0 Hz                    Acoustic: 112 dB                    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.                    Vector Sum: 1.67 mm/s  
Lat./Long.: 45° 15' 27.900" N                    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: William Coleman, Austin Powder

**Date/Time** Tran at 13:17:33 October 28, 2020  
**Trigger Source** Geo: 1.000 mm/s, Mic: 109.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 12.0 sec at 1024 sps

**Serial Number** BE19638 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.2 Volts  
**Unit Calibration** February 7, 2020 by InstanTel  
**File Name** U638IP2N.L90

**Notes**

Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**

Set up at driveway of 1331 Dwire Hill Rd. Geo spiked and weight bagged on soggy ground.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 112.0 dB(L) at 2.874 sec  
**ZC Freq** 13 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 633 mv)

	Tran	Vert	Long	
PPV	1.397	0.635	0.762	mm/s
ZC Freq	15	47	20	Hz
Time (Rel. to Trig)	0.109	-0.076	0.556	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.016	0.003	0.009	mm
Sensor Check	Check	Passed	Passed	
Frequency	7.7	7.6	7.6	Hz
Overswing Ratio	3.6	3.6	3.8	

**Peak Vector Sum** 1.670 mm/s at 0.558 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**Date/Time** MicL at 13:18:19 October 28, 2020  
**Trigger Source** Geo: 1.000 mm/s, Mic: 113.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 12.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** April 17, 2020 by InstanTel  
**File Name** Q020IP2N.MJO

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 geo spiked and weight bagged in front of 1550 Dwire Hill Rd, on wet lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 116.3 dB(L) at 0.105 sec  
**ZC Freq** 12 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 651 mv)

	Tran	Vert	Long	
PPV	0.381	0.381	0.381	mm/s
ZC Freq	19	27	17	Hz
Time (Rel. to Trig)	1.374	1.493	0.293	sec
Peak Acceleration	0.013	0.027	0.013	g
Peak Displacement	0.004	0.003	0.006	mm
Sensor Check	Check	Passed	Check	
Frequency	14.4	7.4	7.8	Hz
Overswing Ratio	7.0	4.0	3.7	

Peak Vector Sum 0.554 mm/s at 1.443 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2020-09

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONST.-W. CARLTON  
(THO1100-002)

Date/Time: 10/30/2020 12:16

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 10/30/20    Trigger Level: 1.23 mm/s    Off dB    Transverse: 0.127 mm/s    --- Hz  
Time: 12:16    Calibration Date: 04/17/20    Vertical: 0.254 mm/s    --- Hz  
Distance From Blast: 1,297.23 m    Calibration Signal:    Longitudinal: 0.127 mm/s    --- Hz  
Direction From Blast: ENE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 111 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: 0.254 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Matt Gordon, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: No Trigger    Seismograph Type: instancel  
Date: 10/30/20    Trigger Level: 1.23 mm/s    Off dB  
Time: 12:16    Calibration Date: 04/17/20  
Distance From Blast: 1,309.73 m    Calibration Signal:  
Direction From Blast: NNE    Geophone Min. Freq.: 2.0 Hz  
Readout:    Mic. Min. Freq.: 2.0 Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Matt Gordon, Austin Powder



# Event Report

**Date/Time** MicL at 12:16:23 October 30, 2020  
**Trigger Source** Geo: 1.700 mm/s, Mic: 108.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19637 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.2 Volts  
**Unit Calibration** September 26, 2020 by InstanTel  
**File Name** U637IP6A.3B0

**Post Event Notes**  
 1331 Dwire Hill Rd. Set up on lawn near house.

**Notes**

Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 110.9 dB(L) at 0.005 sec  
**ZC Freq** 11 Hz  
**Channel Test** Passed (Freq = 20.5 Hz Amp = 723 mv )

	Tran	Vert	Long	
PPV	0.127	0.254	0.127	mm/s
ZC Freq	>100	>100	>100	Hz
Time (Rel. to Trig)	-0.115	0.550	-0.225	sec
Peak Acceleration	0.027	0.027	0.013	g
Peak Displacement	0.000	0.000	0.000	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.6	7.4	7.6	Hz
Overswing Ratio	3.8	3.8	3.9	

Peak Vector Sum 0.254 mm/s at 0.550 sec

**USBM R18507 And OSMRE**



**Time Scale:** 0.20 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

No Trigger

Event Report: Monitor Log - Minimate Blaster # BE15020-Compliance

Start Time	End Time	Status
Oct 30 /20 11:21:48	Oct 30 /20 12:41:12	SERIAL NUMBER: BE15020 No events recorded. (Keyboard Exit) Geo: 1.000 mm/s Mic: 113.0 dB(L)

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2020-10

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONST.-W. CARLTON  
(THO1100-002)

Date/Time: 11/02/2020 10:58

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instancel  
Date: 11/02/20    Trigger Level: 1.23 mm/s    Off dB    Transverse: 1.27 mm/s    28.0 Hz  
Time: 10:58    Calibration Date: 04/17/20    Vertical: 0.762 mm/s    47.0 Hz  
Distance From Blast: 1,306.37 m    Calibration Signal:    Longitudinal: 0.762 mm/s    28.0 Hz  
Direction From Blast: ENE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 115 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: 1.368 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Matt Gordon, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: No Trigger    Seismograph Type: instancel  
Date: 11/02/20    Trigger Level: 1.23 mm/s    Off dB  
Time: 10:58    Calibration Date: 04/17/20  
Distance From Blast: 1,371.90 m    Calibration Signal:  
Direction From Blast: NNE    Geophone Min. Freq.: 2.0 Hz  
Readout:    Mic. Min. Freq.: 2.0 Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Matt Gordon, Austin Powder

## Wind Triggers

### Event Report: Monitor Log - Minimate Blaster # BE15589-Compliance

Start Time	End Time	Status
		SERIAL NUMBER: BE15589
Nov 2 /20 11:01:44		Start Monitoring Trigger Level: Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 11:02:59	Nov 2 /20 11:03:04	Event recorded. Trigger Level MicL: 115.0 dB(L)
Nov 2 /20 11:03:18		Start Monitoring Trigger Level: Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 11:04:40	Nov 2 /20 11:04:45	Event recorded. Trigger Level MicL: 115.0 dB(L)
Nov 2 /20 11:04:59		Start Monitoring Trigger Level: Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 11:18:51	Nov 2 /20 11:18:56	Event recorded. Trigger Level MicL: 115.0 dB(L)
Nov 2 /20 11:19:09		Start Monitoring Trigger Level: Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 11:36:55	Nov 2 /20 11:37:00	Event recorded. Trigger Level MicL: 115.0 dB(L)
Nov 2 /20 11:37:13		Start Monitoring Trigger Level: Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 11:50:59	Nov 2 /20 11:51:04	Event recorded. Trigger Level MicL: 115.0 dB(L)
Nov 2 /20 11:51:17		Start Monitoring Trigger Level: Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 11:51:35	Nov 2 /20 11:51:40	Event recorded. Trigger Level MicL: 115.0 dB(L)
Nov 2 /20 11:51:54		Start Monitoring Trigger Level: Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 11:59:33	Nov 2 /20 11:59:38	Event recorded. Trigger Level MicL: 115.0 dB(L)
Nov 2 /20 11:59:51		Start Monitoring Trigger Level: Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 12:03:24	Nov 2 /20 12:03:29	Event recorded. Trigger Level MicL: 115.0 dB(L)
Nov 2 /20 12:03:43		Start Monitoring Trigger Level: Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 12:15:32	Nov 2 /20 12:15:37	Event recorded. Trigger Level MicL: 115.0 dB(L)
Nov 2 /20 12:15:51	Nov 2 /20 12:16:44	No events recorded. (Keyboard Exit) Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 12:36:03		Start Monitoring Trigger Level: Geo: 1.000 mm/s Mic: 115.0 dB(L)
Nov 2 /20 15:12:15	Nov 2 /20 15:12:20	Event recorded. Trigger Level Long: 1.000 mm/s
Nov 2 /20 15:12:33	Nov 2 /20 15:26:39	No events recorded. (Keyboard Exit) Geo: 1.000 mm/s Mic: 115.0 dB(L)

**Date/Time** Tran at 10:58:32 November 2, 2020  
**Trigger Source** Geo: 1.000 mm/s, Mic: 113.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 12.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.4 Volts  
**Unit Calibration** April 17, 2020 by InstanTel  
**File Name** Q020IPBQ.HK0

**Notes**

Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**

Set up in yard of 1331 Dwire Hill Rd. Geo spiked and weight bagged on lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 115.4 dB(L) at 2.858 sec  
**ZC Freq** 12 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 672 mv )

	Tran	Vert	Long	
PPV	1.270	0.762	0.762	mm/s
ZC Freq	28	47	28	Hz
Time (Rel. to Trig)	0.078	-0.103	0.038	sec
Peak Acceleration	0.027	0.027	0.027	g
Peak Displacement	0.007	0.003	0.004	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.7	7.4	7.4	Hz
Overswing Ratio	3.6	4.0	3.7	

Peak Vector Sum 1.368 mm/s at 0.078 sec

**USBM RI8507 And OSMRE**



**Time Scale:** 0.50 sec/div **Amplitude Scale:** Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
**Trigger =**

Sensor Check

**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G 1- K0

Blast No.: 2020-11

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONST.-W. CARLTON  
(THO1100-002)

Date/Time: 11/09/2020 10:30

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: Seismic Record    Seismograph Type: instantel  
Date: 11/09/20    Trigger Level: 1.23 mm/s    Off dB    Transverse: 1.27 mm/s    43.0 Hz  
Time: 10:35    Calibration Date: 04/17/20    Vertical: 0.762 mm/s    51.0 Hz  
Distance From Blast: 1,339.90 m    Calibration Signal:    Longitudinal: 1.524 mm/s    39.0 Hz  
Direction From Blast: ENE    Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy    Mic. Min. Freq.: 2.0 Hz    Acoustic: 109 dB    --- Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.    Vector Sum: 2.048 mm/s  
Lat./Long.: 45° 15' 27.900" N    76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Robert Turton, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: No Trigger    Seismograph Type: instantel  
Date: 11/09/20    Trigger Level: 1.23 mm/s    Off dB  
Time: 11:35    Calibration Date: 04/17/20  
Distance From Blast: 1,351.18 m    Calibration Signal:  
Direction From Blast: NNE    Geophone Min. Freq.: 2.0 Hz  
Readout:    Mic. Min. Freq.: 2.0 Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.  
Lat./Long.: 45° 15' 59.300" N    76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Robert Turton, Austin Powder

**Date/Time** Long at 10:35:15 November 9, 2020  
**Trigger Source** Geo: 1.000 mm/s, Mic: 113.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 12.0 sec at 1024 sps

**Serial Number** BE15020 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.5 Volts  
**Unit Calibration** April 17, 2020 by InstanTel  
**File Name** Q020IPOO.2R0

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:

**Post Event Notes**  
 Set up at 1331 Dwire Hill Rd. Geo spiked and weight bagged on lawn.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 109.2 dB(L) at 3.195 sec  
**ZC Freq** 6.4 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 610 mv )

	Tran	Vert	Long	
PPV	1.270	0.762	1.524	mm/s
ZC Freq	43	51	39	Hz
Time (Rel. to Trig)	0.151	0.081	0.108	sec
Peak Acceleration	0.040	0.027	0.053	g
Peak Displacement	0.007	0.003	0.007	mm
<b>Sensor Check</b>	Passed	Passed	Passed	
Frequency	7.7	7.3	7.5	Hz
Overswing Ratio	3.6	3.9	3.6	

Peak Vector Sum 2.048 mm/s at 0.151 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.50 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check

**Date/Time** MicL at 11:29:13 November 9, 2020  
**Trigger Source** Geo: 1.700 mm/s, Mic: 108.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE19637 V 10.72-8.17 MiniMate Plus  
**Battery Level** 6.3 Volts  
**Unit Calibration** September 26, 2020 by InstanTel  
**File Name** U637IPOQ.KP0  
**Post Event Notes**  
 Probably false trigger. 1550 Dwire Hill Rd, on front lawn.

**Notes**  
 Location:  
 Client:  
 User Name:  
 General:



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 108.4 dB(L) at 0.000 sec  
**ZC Freq** 7.4 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 653 mv)

	Tran	Vert	Long	
PPV	0.381	0.381	0.381	mm/s
ZC Freq	51	73	47	Hz
Time (Rel. to Trig)	1.279	0.767	0.733	sec
Peak Acceleration	0.013	0.027	0.027	g
Peak Displacement	0.001	0.002	0.002	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.4	7.4	7.5	Hz
Overswing Ratio	3.8	3.7	3.8	

Peak Vector Sum 0.475 mm/s at 1.229 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
 Trigger =

Sensor Check



**AUSTIN POWDER LTD.  
BLAST REPORT**



330-Lanark

ON, Lanark, Canada K0G I- K0

Blast No.: 2020-12

Blast Type: Stone Quarry/Stone Mine - Production

Customer: THOMAS CAVANAGH  
CONST.-W. CARLTON  
(THO1100-002)

Date/Time: 12/16/2020 10:34

Pit/Permit: WEST CARLETON QUARRY / ARA-4085

Location: South West Corner

**SEISMOGRAPH 1 - 1331 DWIRE HILL RD**

Data Type: No Trigger      Seismograph Type: instancel  
Date: 12/16/20      Trigger Level: 1.23 mm/s      Off dB  
Time: 10:25      Calibration Date: 04/17/20  
Distance From Blast: 1,321.31 m      Calibration Signal:  
Direction From Blast: ENE      Geophone Min. Freq.: 2.0 Hz  
Readout:      Mic. Min. Freq.: 2.0 Hz  
Location: Set up in back yard of 1331 Dwire Hill Rd, geo spiked and wieght bagged.  
Lat./Long.: 45° 15' 27.900" N      76° 6' 50.100" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Andrew Tysick, Austin Powder

**SEISMOGRAPH 2 - 1550 DWIRE HILL RD**

Data Type: Seismic Record      Seismograph Type: instancel  
Date: 12/16/20      Trigger Level: 1.23 mm/s      Off dB      Transverse: 29.032 mm/s      17.0 Hz  
Time: 10:25      Calibration Date: 04/17/20      Vertical: 9.677 mm/s      64.0 Hz  
Distance From Blast: 1,376.78 m      Calibration Signal:      Longitudinal: 19.355 mm/s      22.0 Hz  
Direction From Blast: NNE      Geophone Min. Freq.: 2.0 Hz  
Readout: Printed Copy      Mic. Min. Freq.: 2.0 Hz      Acoustic: 108 dB      --- Hz  
Location: Set up in driveway of 1550 Dwire Hill Rd, geo spiked and wieght bagged.      Vector Sum: 29.921 mm/s  
Lat./Long.: 45° 15' 59.300" N      76° 7' 28.700" W  
Reader and Firm: William Coleman, AUSTIN POWDER  
Analyst and Firm:  
Installer and Firm: Andrew Tysick, Austin Powder

**Date/Time** Tran at 10:25:37 December 16, 2020  
**Trigger Source** Geo: 1.000 mm/s, Mic: 115.0 dB(L)  
**Range** Geo: 254.0 mm/s  
**Record Time** 5.0 sec at 1024 sps

**Serial Number** BE15589 V 10.72-1.1 Minimate Blaster  
**Battery Level** 6.2 Volts  
**Unit Calibration** October 28, 2020 by Instantel  
**File Name** Q589IRL6.AP0

**Notes**

**Post Event Notes**  
Geo spiked and weight bagged on frozen front lawn of 1550 Dwire Hill Rd.



**Extended Notes**

**Microphone** Linear Weighting  
**PSPL** 108.4 dB(L) at 3.616 sec  
**ZC Freq** 3.3 Hz  
**Channel Test** Passed (Freq = 20.1 Hz Amp = 583 mv )

	Tran	Vert	Long	
PPV	1.143	0.381	0.762	mm/s
ZC Freq	17	64	22	Hz
Time (Rel. to Trig)	0.003	-0.235	-0.008	sec
Peak Acceleration	0.013	0.013	0.027	g
Peak Displacement	0.011	0.003	0.006	mm
Sensor Check	Passed	Passed	Passed	
Frequency	7.5	7.5	7.3	Hz
Overswing Ratio	4.0	4.1	4.5	

Peak Vector Sum 1.178 mm/s at 0.003 sec

**USBM RI8507 And OSMRE**



Time Scale: 0.20 sec/div Amplitude Scale: Geo: 2.000 mm/s/div Mic: 10.000 pa.(L)/div  
Trigger = <math>\blacktriangleleft \text{---} \text{---} \blacktriangleright</math>

Sensor Check

No Trigger

Event Report: Monitor Log - Minimate Blaster # BE15020-Compliance

Start Time	End Time	Status
Dec 16 /20 09:21:51	Dec 16 /20 10:43:02	SERIAL NUMBER: BE15020 No events recorded. (Keyboard Exit) Geo: 1.000 mm/s Mic: 113.0 dB(L)

# Appendix D

# EXPLOTECH

Specialists in Explosives, Blasting and Vibration  
Consulting Engineers

**Robert J. Cyr, P. Eng.**  
Principal, Explotech Engineering Ltd.

## EDUCATION

Bachelor of Applied Science,  
Civil Engineering, Queen's University

## PROFESSIONAL AFFILIATIONS

Association of Professional Engineers of Ontario (APEO)  
Association of Professional Engineers and Geoscientists of BC (APEG)  
Association of Professional Engineers, Geologists and Geophysicists of Alberta  
Association of Professional Engineers and Geoscientists of New Brunswick  
Association of Professional Engineers of Nova Scotia  
Association of Professional Engineers and Geoscientists Manitoba  
Professional Engineers and Geoscientists Newfoundland and Labrador  
International Society of Explosives Engineers (ISEE)  
Aggregate Producers Association of Ontario (APAO)  
Surface Blaster Ontario Licence 450109

## SUMMARY OF EXPERIENCE

Over thirty years experience in many facets of the construction and mining industry has provided the expertise and experience required to efficiently and accurately address a comprehensive range of engineering and construction conditions. Sound technical training is reinforced by formidable practical experience providing the tools necessary for accurate, comprehensive analysis and application of feasible solutions. Recent focus on vibration analysis, blast monitoring, blast design, damage complaint investigation for explosives consumers and specialized consulting to various consulting engineering firms.

## PROFESSIONAL RECORD

2001 – Present	-Principal, Explotech Engineering Ltd.
1996 – 2001	-Leo Alarie & Sons Limited - Project Engineer/Manager
1993 – 1996	-Rideau Oxford Developments Inc. – Project Manager
1982 – 1993:	-Alphe Cyr Ltd. – Project Coordinator/Manager

---

**EXPLOTECH ENGINEERING LTD.**

**Ottawa ♦ Sudbury ♦ Toronto ♦ Halifax**

**WWW.EXPLOTECH.COM**

**1-866-EXPLOTECH**



Specialists in Explosives, Blasting and Vibration  
Consulting Engineers

Mitch Malcomson, P.Eng.

Explotech Engineering Ltd.

## EDUCATION

Bachelor of Engineering,  
Civil Engineering with Concentration in Business Management,  
Carleton University

## PROFESSIONAL AFFILIATIONS

Association of Professional Engineers of Ontario (APEO)  
International Society of Explosives Engineers (ISEE)

## SUMMARY OF EXPERIENCE

A Civil Engineer and Project Organizer for Explotech Engineering Ltd. Mitch holds a Bachelor of Engineering degree from Carleton University in Civil Engineering with a Concentration in Business Management. Mitch has strong analytical, technical, business and leadership skills. Recent projects have focused on vibration analysis and the drilling and blasting portions of mining, quarrying and construction projects across Canada.

## PROFESSIONAL RECORD

2008 – Present - Engineer / Project Manager, Explotech Engineering Ltd.



Specialists in Explosives, Blasting and Vibration  
Consulting Engineers

Mark Morelli, B.Eng.

Explotech Engineering Ltd.

## EDUCATION

Bachelor of Engineering,  
Civil Engineering, Carleton University

## PROFESSIONAL AFFILIATIONS

International Society of Explosives Engineers (ISEE)

## SUMMARY OF EXPERIENCE

A technician working for Explotech Engineering Ltd., Mark holds a Bachelor of Engineering degree in Civil Engineering and has strong technical, leadership, interpersonal, communication, and presentation skills. Recent focus on blast monitoring, data management, scheduling, job estimations, vibration analysis, damage complaint investigation and attenuation analysis.

## PROFESSIONAL RECORD

- 2006 – Present - Technician, Explotech Engineering Ltd.
- 2003 – 2004 - Labourer, Hydracorp Canada Ltd.
- 2002 – 2003 - Labourer, Quad Construction

# Appendix E





## Blasting Terminology

ANFO:	Ammonium Nitrate and Fuel Oil – explosive product
ANFO WR:	Water resistant ANFO
Blast Pattern:	Array of blast holes
Body hole:	Those blast holes behind the first row of holes (Face Holes)
Burden:	Distance between the blast hole and a free face
Column:	That portion of the blast hole above the required grade
Column Load:	The portion of the explosive loaded above grade
Collar:	That portion of the blast hole above the explosive column, filled with inert material, preferably clean crushed stone
Face Hole:	The blast holes nearest the free face
Overpressure:	A compressional wave in air caused by the direct action of the unconfined explosive or the direct action of confining material subjected to explosive loading.
Peak Particle Velocity:	The rate of change of amplitude, usually measured in mm/s or in/s. This is the velocity or excitation of the particles in the ground resulting from vibratory motion.
Scaled distance:	An equation relating separation distance between a blast and receptor to the energy (usually expressed as explosive weight) released at any given instant in time.
Sensitive Receptor:	Sensitive land use may include recreational uses which are deemed by the municipality or provincial agency to be sensitive; and/or any building or associated amenity area (i.e. may be indoor or outdoor space) which is not directly associated with the industrial use, where humans or the natural environment may be adversely affected by emissions generated by the operation of a nearby industrial facility. For example, the building or amenity area may be associated with residences, senior citizen homes, schools,

# EXPLOTECH

day care facilities, hospitals, churches and other similar institutional uses, or campgrounds.

Spacing:	Distance between blast holes
Stemming:	Inert material, preferably clean crushed stone applied into the blast hole from the surface of the rock to the surface of the explosive in the blast hole.
Sub-grade:	That portion of the blast hole drilled and loaded below the required grade
Toe Load:	The portion of explosive loaded below grade



## References

Building Research Establishment, (1990), *"Damage to Structures From Ground-Borne Vibration"*, BRE Digest 353, Gaston, Watford, U.K.

Crum S. V., Siskind D. E., Pierce W. E., Radcliffe K. S., (1995) *"Ground Vibrations and Airblasts Monitored in Swedesburg, Pennsylvania, From Blasting at McCoy Quarry"*, Contract Research Rept. By the United States Bureau of Mines for the Pennsylvania Department of Environmental Resources, 120 pp.

Dowding C.H., (1985), *"Blast Vibration, Monitoring and Control"*, Prentice-Hall Canada Inc., 297 pp.

Dowding C.H., (1996), *"Construction Vibrations"*, Prentice-Hall, Upper Saddle, N.J., USA, 610 pp.

Du Pont Company, (1980), *"Blaster's Handbook"* Wilmington, Delaware, United States of America

Fletcher L.R., D'Andrea D.V., (1986) *"Control of Flyrock in Blasting"*, Proceedings of the Twelfth Annual Conference on Explosives and Blasting Technique, International Society of Explosives Engineers

Froedge D. T., (1983) *"Blasting Effects on Water Wells"*, Proceedings of the Ninth Annual Conference on Explosives and Blasting Technique, International Society of Explosives Engineers

Kopp J.W., (1994) *"Observation of Flyrock at Several Mines and Quarries"*, Proceedings of the Twentieth Annual Conference on Explosives and Blasting Technique, International Society of Explosives Engineers

Matheson G. M., Miller D. K., (1997) *"Blasting Vibration Damage to Water Supply, Well Water Quality and Quantity"*, Proceedings of the Twenty-Third Conference on Explosives and Blasting Technique, International Society of Explosive Engineers

Moore A.J., Richards A.B., (2005), *"Golden Pike Cut-Back Flyrock Control and Calibration of a Predictive Model"*, Terrock Consulting Engineers, Eltham, Victoria, Australia.

# EXPLOTECH

Nicholls H., Johnson C., Duvall W., (1970), "*Blasting Vibrations and their Effects on Structures*", United States Department of the Interior, Bureau of Mines, Bulletin 656

Oriard L.L., (1989) "*The Scale of Effects in Evaluating Vibration Damage Potential*" Fifteenth Conference on Explosives and Blasting Technique, International Society of Explosive Engineers

Oriard L.L., (2002) "*Explosives Engineering, Construction Vibrations and Geology*" International Society of Explosive Engineers, Cleveland, Ohio, United States of America

Robertson D. A., Gould J. A., Straw J. A., Dayton M. A., (1980) "*Survey of Blasting Effects on Ground Water Supplies in Appalachia*", United States Department of the Interior, Bureau of Mines, Contract No. J-0285029

Rose R., Bowles B., Bender W. L., (1991) "*Results of Blasting in Close Proximity to Water Wells at the Sleeper Mine*", Proceedings of the Seventeenth Annual Conference on Explosives and Blasting Technique, International Society of Explosive Engineers

Roth J., (1979) "*A Model for Determination of Flyrock Range as a Function of Shot Conditions*", United States Department of the Interior, Bureau of Mines, Report OFR 77-81

Siskind D.E., Stagg M.S., Kopp J.W., Dowding C.H., (1980), "*Structural Response and Damage Produced by Ground Vibration from Surface Mine Blasting*", United States Bureau of Mines RI 8507.

White, T.J., Farnfield, R.A., Kelly, M., (1993), "*The Effect of Low Level Blast Vibrations and the Environment on a Domestic Building*", Proceedings of the Ninth Annual Symposium on Explosives and Blasting Research, International Society of Explosives Engineers.

Wright D.G., Hopky G. E., (1998) "*Guidelines for the Use of Explosives In or Near Canadian Fisheries Waters*", Canadian Technical Report of Fisheries and Aquatic Sciences 2107