



McKINLEY
ENVIRONMENTAL
SOLUTIONS

Combined Environmental Impact Statement &
Tree Conservation Report (Revised)
Kanata Golf and Country Club Redevelopment
7000 Campeau Drive, Ottawa



May 2020

EXECUTIVE SUMMARY	1
1.0 INTRODUCTION	4
1.1 Reading the Tree Conservation Report (TCR).....	4
1.2 Scoping the Environmental Impact Statement	4
1.3 Site Overview and Background (TCR).....	5
1.4 Description of Undertaking (TCR).....	7
1.5 Agency Consultation	11
1.6 Regulatory Requirements (TCR).....	12
2.0 METHODOLOGY	13
2.0.1 Vegetation Survey and Tree Inventory Methodology (TCR).....	13
2.0.2 Significant Woodlot Assessment Methodology (TCR)	15
2.0.3 Environmental Impact Statement Methodology.....	16
3.0 EXISTING CONDITIONS	19
3.1 Geological Conditions	19
3.2 Vegetation Communities (TCR).....	20
3.2.1 Golf Course.....	28
3.2.2 Landscaping Features (TCR).....	28
3.2.3 Tree Stands and Large Trees (TCR).....	28
3.2.4 Forest and Thicket Communities (TCR).....	34
3.3 Significant Woodlot Assessment (TCR).....	39
3.3.1 Significant Woodlot Assessment – Woodlot Sizes (TCR)	40
3.3.2 Significant Woodlot Assessment – Woodlot Ages (TCR).....	43
3.3.3 Significant Woodlot Assessment – NHRM Criteria and Ecosystem Services (TCR)	48
3.3.4 Significant Woodlot Assessment – Summary (TCR).....	51
3.4 Watercourses and Fish Habitat	52
3.4.1 Stormwater Infiltration Swales	52
3.4.2 Stormwater Ponds	54
3.4.3 Fish Habitat.....	54
3.5 Adjacent Lands and Significant Features	55

3.6	Wildlife and Significant Wildlife Habitat	56
3.7	Species at Risk	60
3.7.1	Blanding's Turtle and Snapping Turtle	60
3.7.2	Eastern Whip Poor Will and Common Nighthawk	62
3.7.3	Butternut Trees (TCR).....	65
3.7.4	Bat Species at Risk	67
3.7.5	Additional Species at Risk.....	70
3.8	Linkages	74
4.0	DESCRIPTION OF ENVIRONMENTAL IMPACTS AND MITIGATION	75
4.1	Terrestrial Habitat and Tree Removal (TCR)	75
4.1.1	Significant Woodlot Impacts and Tree Retention (TCR).....	75
4.1.2	Tree Preservation Mitigation Measures (TCR)	81
4.1.3	Grading Impacts, Transplanting, and Replanting (TCR)	82
4.2	Watercourses and Aquatic Habitats.....	84
4.2.1	Removal of Stormwater Swales and Ponds	84
4.2.2	Servicing and Stormwater Management	84
4.2.3	Sediment and Erosion Controls	85
4.3	Adjacent Lands and Significant Features	86
4.4	Species at Risk and Wildlife	87
4.4.1	Butternut Tree Regulatory Requirements (TCR)	87
4.4.2	Wildlife Construction Stage Mitigation - Terrestrial.....	88
4.4.3	Wildlife Construction Stage Mitigation - Aquatic.....	90
5.0	CUMULATIVE EFFECTS	91
6.0	MONITORING	92
7.0	CLOSURE	93
8.0	REFERENCES.....	94

LIST OF FIGURES

Land Use Concept Plan (May 14, 2020)

Draft Plan of Subdivision (April 2020)

Figure 1: Site Overview

Figure 2: Vegetation Mapping Overview

Figure 3: Vegetation Mapping – Section 1

Figure 4: Vegetation Mapping – Section 2

Figure 5: Vegetation Mapping – Section 3

Figure 6: Vegetation Mapping – Section 4

Figure 7: Vegetation Mapping – Section 5

Figure 8: Vegetation Mapping – Section 6

Figure 9: Forest ELC Communities – Woodlot Sizes

Figure 10: Forest Patches ≥ 0.8 Hectares

Figure 11: Significant Woodlots (Woodlots ≥ 0.8 ha and 60 Years Old)

Figure 12: Bird Survey Points

Figure 13: Whip Poor Will Survey Points

Figure 14: Butternut Locations

Figure 15: Bat Maternity Roost Assessment

Drawing 1: Existing Conditions – Forest and Significant Woodlots

Drawing 2: Post Development Conditions – Forest and Significant Woodlots

Appendix A – Site Photographs

Appendix B – Master Plant List

Appendix C – Bird and Wildlife Species Lists

Appendix D – Significant Woodlot Assessment Terms of Reference

Appendix E – OMNRF Potential Species at Risk List for the Geographic Township of March

Appendix F – Butternut Health Assessment (Fleguel 2019)

EXECUTIVE SUMMARY

McKinley Environmental Solutions (MES) and Muncaster Environmental Planning (MEP) were retained by Minto Communities on behalf of Clublink Corporation ULC to prepare a Combined Environmental Impact Statement (EIS) and Tree Conservation Report (TCR) to support the proposed redevelopment of the Kanata Golf and Country Club property (the Site). Clublink, in partnership with Minto Communities and Richcraft Homes, proposes to redevelop the Site to accommodate a residential subdivision. The Site occurs within the developed urban portion of Kanata (Ottawa) and is predominantly surrounded by existing developed residential homes and/or roads on all sides. The Site is approximately 71 ha in size and is irregularly shaped.

The Site has been operated as a golf and country club for several decades and is predominantly an artificial landscape which has been maintained to provide golfing facilities. The Site includes four (4) existing buildings. The majority of the surface area of the Site includes the golf course playing surfaces (e.g. manicured lawns). The Site also includes a variety of native and non-native landscaping features, including many deciduous and coniferous planted trees and tree stands. Natural vegetation communities primarily consist of patches of native deciduous forest and deciduous thickets, which are present principally around the edges of the Site. There are five (5) forest patches that are ≥ 0.8 ha in size, with the largest being approximately 1.59 ha. Of these, only three (3) appear to have significant forest cover that is ≥ 60 years of age. Therefore, there are three (3) forest patches which qualify as Significant Woodlots under the amended City of Ottawa criteria for the urban area.

There are no natural watercourses or wetland habitats within the Site. Two (2) stormwater management ponds are located within the Site. Six (6) stormwater conveyance/infiltration swales are also present within the Site, all of which are fed either by outlet pipes from the adjacent developed subdivisions or by surface run-off from the golf course. Although small patches of wetland vegetation have developed within some of the stormwater swales, none of these are natural features, and none are large enough to qualify as wetlands.

Butternut Trees (endangered) were noted within the Site. A Butternut Health Assessment (BHA) has been completed to assess the condition of the Butternut Trees. Regulatory requirements related to impacts to the Butternut Trees and their habitat will be addressed as required by the Ontario Endangered Species Act. No other significant Species at Risk (SAR) concerns were noted for the Site.

The Site is proposed to be redeveloped to include approximately 630 single detached homes, 478 townhomes, and 436 medium density units for a total of approximately 1,544 units. The two (2) existing stormwater management ponds and the existing stormwater management swales are to be

decommissioned. Stormwater servicing will be provided by four (4) new stormwater management blocks, which collectively will occupy approximately 7.31 ha. The Site will also receive municipal sewer and water.

The redevelopment will include a 3.53 ha Neighborhood Park and a 1.62 ha Woodland Park. The redevelopment will also include two (2) parkettes (0.4 ha and 0.4 ha in size). The portion of Significant Woodlot D that overlaps the Neighborhood Park is proposed to be retained within the Neighborhood Park. The portion of Significant Woodlot E that overlaps the Woodland Park is proposed to be retained within the Woodland Park. Within each park, new trees will be planted adjacent to the retained portions of the Significant Woodlots (in areas that currently lack forest cover), in order to augment the features and functions of the retained portions of the Significant Woodlots. The Land Use Concept Plan includes an additional 5.19 ha of open space blocks, which will provide additional opportunities for tree retention and tree planting. All existing trees within the open space blocks will be retained wherever feasible, and new trees will be planted within any portions of the open space blocks that do not currently have forest coverage. Following completion of the redevelopment, each of the open space blocks are intended to be fully forested. Notably, a portion of Significant Woodlot C will be retained within the open space blocks. New trees will be planted within the open space block surrounding Significant Woodlot C (in areas that currently lack tree cover), thereby augmenting the features and functions of the retained portion of Significant Woodlot C.

The combined size of the three (3) Significant Woodlots prior to development is approximately 3.86 ha. Following the redevelopment, the combined size of the three (3) Significant Woodlots is anticipated to be similar (approximately 3.77 ha). As described above, the post development Significant Woodlots will include a combination of retained trees and new tree plantings to augment their features and functions. Significant Woodlot C (1.0 ha pre-development, 1.15 ha post development) and Significant Woodlot E (1.27 ha pre-development, 1.62 ha post development) are anticipated to expand in size. Significant Woodlot D (1.59 ha pre-development, 1.0 ha post development) is anticipated to be reduced in size. Notably, all three (3) Significant Woodlots are anticipated to be ≥ 0.8 ha in size following development, and therefore will continue to qualify as Significant Woodlots under the amended City of Ottawa criteria for the urban area.

In addition, a network of trails has been identified to connect the parkland, open space blocks, and stormwater management blocks. The retained portions of the Significant Woodlots within both the Neighborhood Park and the Woodland Park will include walking trails and other recreational amenities. The trail network and the recreational amenities within the retained portions of the Significant Woodlots are intended to preserve and enhance their recreational and aesthetic values.

The tree retention/tree planting within the park and open space blocks, as well as the trail system and recreational amenities, is anticipated to be sufficient to preserve the significant features and functions of the three (3) Significant Woodlots.

The Land Use Concept Plan includes minimum 3 m wide landscaped buffers around the Site edges adjacent to existing residential properties. The combined size of the minimum 3 m wide landscaped buffers is 1.65 ha. Many of the Site edges are currently occupied by planted trees, tree stands, or forest patches, and therefore the minimum 3 m wide landscaped buffers will provide additional opportunities for tree retention along the Site edges, including protection of the critical root zones. New trees will be planted within the minimum 3 m wide landscaped buffers both where tree removal is required to accommodate grading, and also where there is currently insufficient tree coverage at the edge of the Site. Once the redevelopment is complete, the minimum 3 m property buffers will be fully treed with retained and/or planted trees. Lastly, new trees and landscaping features will be planted within the stormwater management blocks.

Provided that the regulatory, mitigation, and avoidance measures outlined in this report are implemented appropriately, the redevelopment is not anticipated to have a significant negative effect on the natural features and functions.

1.0 INTRODUCTION

1.1 Reading the Tree Conservation Report (TCR)

This report is presented as a Combined Environmental Impact Statement (EIS) and Tree Conservation Report (TCR). Readers who are principally interested in the TCR may choose to read only those portions of the report where the section headings are marked **(TCR)**. This includes Sections 1.3, 1.4, 1.6, 2.0.1, 2.0.2, 3.2, 3.3, 3.7.3, 4.1, 4.4.1, and Appendix D. Readers who are interested in the EIS should read the entire report, as information included in the TCR sections is not reiterated.

1.2 Scoping the Environmental Impact Statement

This EIS was undertaken following the City of Ottawa's Environmental Impact Statement Guidelines. Following the City guidelines, the Environmental Impact Statement (EIS) includes the following:

- Documentation of existing natural features on and around the Site;
- Identification of potential environmental impacts of the project;
- Recommendations for ways to avoid and reduce any negative impacts; and
- Proposal of ways to enhance natural features and functions.

This EIS was prepared with guidance from the *Natural Heritage Reference Manual* (OMNRF 2010). The major objective of this EIS is to assess whether the proposed project will negatively affect the significant features and functions of the Site, and to ensure that impacts will be minimized through mitigation measures.

1.3 Site Overview and Background (TCR)

The Site addressed by this Combined EIS and TCR encompasses the Kanata Golf and Country Club property, which is proposed to be redeveloped jointly by Minto Communities, Richcraft Homes and Clublink, in order to accommodate a residential subdivision (discussed below). The Site is approximately 71 ha in size and is irregularly shaped (Refer to Figure 1). The municipal address of the Site is 7000 Campeau Drive. The Site occurs within the developed urban portion of Kanata (Ottawa) and is predominantly surrounded by existing developed residential homes and/or roads on all sides.

The Site has been operated as a golf and country club for several decades and is predominantly an artificial landscape which has been maintained to provide golfing facilities. The Site includes four (4) existing buildings. These include two (2) vehicle maintenance/workshop buildings, the clubhouse/restaurant, and a small storage shed. The majority of the surface area of the Site includes the golf course playing surfaces (e.g. manicured lawns). The Site also includes a variety of native and non-native landscaping features, including many deciduous and coniferous planted trees and tree stands. Natural vegetation communities primarily consist of patches of native deciduous forest and deciduous thickets, which are present principally around the edges of the Site. There are five (5) forest patches that are ≥ 0.8 ha in size, with the largest being approximately 1.59 ha. Of these, only three (3) appear to have significant forest cover that is ≥ 60 years of age. Therefore, there are three (3) forest patches which qualify as Significant Woodlots under the amended City of Ottawa criteria for the urban area (discussed in greater detail in Section 3.3).

There are no natural watercourses or wetland habitats within the Site. Two (2) Stormwater Management (SWM) ponds are located within the Site (referred to as the Northern and Southern SWM Ponds). Six (6) stormwater conveyance/infiltration swales are also present within the Site, all of which are fed either by outlet pipes from the adjacent developed subdivisions or by surface run-off from the golf course. Although small patches of wetland vegetation have developed within some of the stormwater swales, none of these are natural features, and none are large enough to qualify as wetlands.

Butternut Trees (endangered) were noted within the Site. As discussed in Sections 1.6 and 3.7.3, a Butternut Health Assessment (BHA) has been completed to assess the condition of the Butternut Trees (Appendix F). Regulatory requirements under the Ontario Endangered Species Act to address impacts to Butternut Trees and their habitat are discussed below in Section 1.6. No other significant Species at Risk (SAR) concerns were noted for the Site.

FIGURE 1: SITE OVERVIEW

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate.

1.4 Description of Undertaking (TCR)

The Land Use Concept Plan (May 14th, 2020) and the Draft Plan of Subdivision (April 2020) are included below. As noted above, the Site as a whole is approximately 71 ha in size. The Site is proposed to be redeveloped to include approximately 630 single detached homes, 478 townhomes, and 436 medium density units for a total of approximately 1,544 units. The two (2) existing stormwater management ponds and the existing stormwater management swales are to be decommissioned. Stormwater servicing will be provided by four (4) new stormwater management blocks, which collectively will occupy approximately 7.31 ha. The Site will also receive municipal sewer and water.

The redevelopment will include a 3.53 ha Neighborhood Park and a 1.62 ha Woodland Park. The redevelopment will also include two (2) parkettes (0.4 ha and 0.4 ha in size). The portion of Significant Woodlot D that overlaps the Neighborhood Park is proposed to be retained within the Neighborhood Park. The portion of Significant Woodlot E that overlaps the Woodland Park is proposed to be retained within the Woodland Park. Within each park, new trees will be planted adjacent to the retained portions of the Significant Woodlots (in areas that currently lack forest cover), in order to augment the features and functions of the retained portions of the Significant Woodlots. The Land Use Concept Plan includes an additional 5.19 ha of open space blocks, which will provide additional opportunities for tree retention and tree planting. All existing trees within the open space blocks will be retained wherever feasible, and new trees will be planted within any portions of the open space blocks that do not currently have forest coverage. Following completion of the redevelopment, each of the open space blocks are intended to be fully forested. Notably, a portion of Significant Woodlot C will be retained within the open space blocks. New trees will be planted within the open space block surrounding Significant Woodlot C (in areas that currently lack tree cover), thereby augmenting the features and functions of the retained portion of Significant Woodlot C.

The combined size of the three (3) Significant Woodlots prior to development is approximately 3.86 ha. Following the redevelopment, the combined size of the three (3) Significant Woodlots is anticipated to be similar (approximately 3.77 ha). As described above, the post development Significant Woodlots will include a combination of retained trees and new tree plantings to augment their features and functions. Significant Woodlot C (1.0 ha pre-development, 1.15 ha post development) and Significant Woodlot E (1.27 ha pre-development, 1.62 ha post development) are anticipated to expand in size. Significant Woodlot D (1.59 ha pre-development, 1.0 ha post development) is anticipated to be reduced in size. Notably, all three (3) Significant Woodlots are



anticipated to be ≥ 0.8 ha in size following development, and therefore will continue to qualify as Significant Woodlots under the amended City of Ottawa criteria for the urban area.

In addition, a network of trails has been identified to connect the parkland, open space blocks, and stormwater management blocks. The retained portions of the Significant Woodlots within both the Neighborhood Park and the Woodland Park will include walking trails and other recreational amenities. The trail network and the recreational amenities within the retained portions of the Significant Woodlots are intended to preserve and enhance their recreational and aesthetic values. The tree retention/tree planting within the park and open space blocks, as well as the trail system and recreational amenities, is anticipated to be sufficient to preserve the significant features and functions of the three (3) Significant Woodlots. Refer to Section 4.1.1 for further details regarding tree retention.

The Land Use Concept Plan includes minimum 3 m wide landscaped buffers around the Site edges adjacent to existing residential properties. The combined size of the minimum 3 m wide landscaped buffers is 1.65 ha. Many of the Site edges are currently occupied by planted trees, tree stands, or forest patches, and therefore the minimum 3 m wide landscaped buffers will provide additional opportunities for tree retention along the Site edges, including protection of the critical root zones. New trees will be planted within the minimum 3 m wide landscaped buffers both where tree removal is required to accommodate grading, and also where there is currently insufficient tree coverage at the edge of the Site. Once the redevelopment is complete, the minimum 3 m property buffers will be fully treed with retained and/or planted trees. Lastly, new trees and landscaping features will be planted within the stormwater management blocks.

Legend


- Single Detached
- Front Drive Towns
- Back-to-Back Towns
- Stacked Town Block
- Medium Density Block
- SWM
- Parkland
- Open Space
- Residential Buffer



scale | 1:6000

SUBJECT TO THE CONDITIONS, IF ANY, SET FORTH IN OUR LETTER DATED 2010-03-20. THIS DRAFT PLAN IS APPROVED BY THE CITY OF OTTAWA UNDER SECTION 51 OF THE PLANNING ACT. THIS PLAN IS DATED 2010-03-20.

STANTEC GEOMATICS, MANAGER DEVELOPMENT REVIEW-WEST PLANNING, INFRASTRUCTURE AND ECONOMIC DEVELOPMENT DEPARTMENT, CITY OF OTTAWA



DRAFT PLAN OF SUBDIVISION OF
BLOCK 69
REGISTERED PLAN 4M-510,
REGISTERED PLAN 126 AND 132
REGISTERED PLAN 4M-651,
PART OF BLOCKS 184 AND 192,
ALL OF BLOCKS 183, 185 AND 186
REGISTERED PLAN 4M-652,
BLOCK 160
REGISTERED PLAN 4M-739,
BLOCK 76
REGISTERED PLAN 4M-741,
PART OF BLOCK 76
REGISTERED PLAN 4M-828,
PART OF BLOCK 1
REGISTERED PLAN 4M-881,
PART OF BLOCK 56 AND
ALL OF BLOCK 55
REGISTERED PLAN 4M-883,
PART OF LOTS 5 AND 6 AND
PART OF THE ROAD ALLOWANCE
BETWEEN LOTS 5 AND 6
(CLOSED BY BY-LAW 1048 (1852228))
CONCESSION 3
 (GEOGRAPHIC TOWNSHIP OF MARCHE)
CITY OF OTTAWA

Scale: 1:1000
 METRIC CONVERSION
 DISTANCES AND COORDINATES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048

REMARKS NOTE
 REMARKS ARE COMPILED FROM OFFICE RECORDS.

LEGEND:

#	DENOTES	RN BLOCK 0411
•	DENOTES	RN BLOCK 0412
•	DENOTES	RN BLOCK 0413
•	DENOTES	CONTR

INFORMATION: REQUIRED UNDER SECTION 51(1) OF THE PLANNING ACT R.S.O. 1990

- SEE PLAN
- SEE PLAN
- SEE PROPOSED LAND USE SCHEDULE (ABOVE)
- SEE PLAN
- SEE PLAN
- SEE PLAN
- CITY WATER AVAILABLE
- SEE SOIL REPORT
- SEE TOPOGRAPHICAL INFORMATION
- ALL CITY SERVICES AVAILABLE
- SUBJECT TO ASSESSMENTS PER INST. NO. S-17607362, LT568249, LT569968, LT436339, LT568246, LT568250, LT568251, LT568272, LT1014950, LT567253, LT568447, LT12658304, LT599218, LT599219, LT1011768, LT866335, LT924341, MH1493, TOGETHER WITH LT10220195

SURVEYOR'S CERTIFICATE
 I HEREBY CERTIFY THAT THE BOUNDARIES OF THE SUBJECT LOTS AND THEIR RELATIONSHIP TO ADJOINING LOTS HAVE BEEN ACCURATELY AND CORRECTLY SHOWN.

DATE: _____ SURVEYOR: BRIAN J. WESTER, CHARTERED LAND SURVEYOR

1.5 Agency Consultation

The proponent has discussed the current redevelopment proposal with the City, and the Mississippi Valley Conservation Authority (MVCA) was circulated as part of the development application review. The Ontario Ministry of Natural Resources and Forestry (OMNRF) provided a potential Species at Risk (SAR) list for the Geographic Township of March (Appendix E). Responsibility for the administration of the Ontario Endangered Species Act (ESA) has recently been transitioned from the OMNRF to the Ontario Ministry of Environment, Conservation, and Parks (OMEC). As noted below, it is anticipated that additional review/consultation with the OMEC will be required to address requirements under the Ontario ESA with respect to the presence of Butternut Trees (endangered).

1.6 Regulatory Requirements (TCR)

As discussed in greater detail in the following sections, the following natural heritage related approvals are anticipated to be required:

- **Ontario Endangered Species Act (ESA):** Butternut Trees (endangered) were noted within the Site. The rules and regulations of the Ontario Endangered Species Act (ESA) require the completion of a Butternut Health Assessment (BHA) in order to assess the health status of the Butternut Trees and subsequent regulatory requirements under the Ontario ESA (OMECP 2019). The BHA was completed in June 2019 (Appendix F). Due to the presence of Category 3 trees, it is anticipated that the redevelopment will require authorization through obtainment of an Overall Benefit Permit under Clause 17(2)(C) of the Ontario ESA. The Ontario ESA review and permitting process was initiated in January 2020 through the submission of the Information Gathering Form to the Ontario Ministry of Environment, Conservation, and Parks (OMECP). No other significant Species at Risk (SAR) issues were identified for the Site.
- **Ontario Regulation 153/06:** Ontario Regulation 153/06 regulates activities that would alter shorelines, watercourses, and wetlands. As discussed below, there are no natural watercourses and/or wetlands present within the Site or in the immediately surrounding area. The two (2) existing stormwater management ponds and the stormwater management swales are artificial features that are entirely fed by outlet pipes from the surrounding subdivisions and overland flow from the golf course. There is no upstream or downstream connection to natural watercourses or wetlands. As such, a Headwaters Drainage Assessment (HDA) is not anticipated to be required to support the MVCA project review.
- **Fisheries Act:** Fisheries and Oceans Canada does not require projects that take place within artificial stormwater management ponds to be submitted for review under the Fisheries Act (FOC 2019). Therefore, a review under the Fisheries Act is not required to support the decommissioning of the existing stormwater management ponds and swales. Fish and wildlife salvage requirements during dewatering are discussed in Section 4.4.3.
- **Tree Removal Permit:** If applicable, the City of Ottawa may require obtainment of a Tree Removal Permit under the Urban Tree Conservation By-law No. 2009-200 prior to the commencement of tree clearing.

2.0 METHODOLOGY

2.0.1 Vegetation Survey and Tree Inventory Methodology (TCR)

A three (3) season plant inventory was undertaken to document the occurrence of plants, create a master plant list, and to identify and delineate plant communities. Site visits to inventory plants and measure tree sizes were completed by Dr. McKinley on May 8th, May 24th, June 2nd, June 13th, and September 17th 2018.

The majority of the surface area of the Site includes the golf course playing surfaces (e.g. manicured lawns). The Site also includes a variety of native and non-native landscaping features, including many deciduous and coniferous trees and tree stands. Natural vegetation communities primarily consist of patches of native deciduous forest and deciduous thickets, which are present principally around the edges of the Site. Because the Site includes a mixture of natural forest/thickets, landscaping features, and many small tree stands, several survey methods were employed.

Forest patches and thickets were classified according to the vegetation communities identified in the Ecological Land Classification (ELC) manual (OMNRF 1998; Lee 2008). Tree measurements were completed in areas of continuous tree cover by undertaking TCR sampling plots. Plots were measured 5 m by 10 m to give a total survey area of 50 m² (for each plot). Plots were distributed evenly within the forested portions of the Site to achieve the desired density of 1 plot per hectare of forest (minimum). A total of twenty one (21) plots were undertaken throughout the forested areas of the Site. The number of plots undertaken in each vegetation community is listed below in Tables A & B (Section 3.2). Trees within each plot that were 10 cm diameter at breast height (dbh) or greater in size were measured with the use of a D-tape, which is a calibrated dbh tape.

In addition to the forest and thicket communities, the Site includes a comparatively large number of native and non-native landscaping features, including both deciduous and coniferous stems. For the purposes of this Combined Environmental Impact Statement and Tree Conservation Report, landscaping features, individual trees, and tree stands were surveyed and are described in detail where stands of trees occur with approximately ten (10) or more stems and/or where individual trees ≥ 50 cm dbh occurred. Smaller tree stands (<10 stems) and individual trees with a dbh <50 cm were not documented in detail throughout the Site, although the presence of landscaping features is described in general terms. In order to provide an inventory of large trees, both planted and naturally occurring trees ≥ 50 cm dbh were documented whenever they were encountered. Trees ≥ 50 cm dbh are described below and are shown in Figures 3 to 8. Trees occurring individually and in small stands were measured with the use of a D-tape, which is a calibrated dbh tape.

The following terms are used throughout this report:

- Diameter at Breast Height (dbh) means the measurement of the trunk of a tree at a height of 120 cm above grade for trees 15 cm diameter or greater, and at a height of 30 cm above grade for trees less than 15 cm diameter.
- The Critical Root Zone (CRZ) is 10 centimeters from the trunk of the tree for every centimeter of trunk dbh. The CRZ is calculated as $dbh \times 10$ cm.

Following the identification and classification of the forest communities within the Site, the total size of forest within the Site was measured using Geographic Information System (GIS) software. As described below in Section 4.1.1, the anticipated loss of forest cover was quantified by comparing the pre-development forest cover to the anticipated extent of forest cover following completion of the redevelopment. Further detail is provided below in Section 4.1.1.

2.0.2 Significant Woodlot Assessment Methodology (TCR)

The City of Ottawa guidelines for Significant Woodlot evaluation require preparation of an Individual Terms of Reference when evaluating potential Significant Woodlots within the urban area (City of Ottawa 2019b). An Individual Terms of Reference has been prepared to support the evaluation of the potential Significant Woodlots within the Site (Refer to Appendix D). The evaluation methodology has also been summarized below.

The City of Ottawa Official Plan (Section 2.4.2), as amended by Official Plan Amendment 179, defines Significant Woodlots in the urban area as any forested area ≥ 0.8 ha in size supporting woodland 40 years of age or older at the time of evaluation. However, the age criteria has recently been revised to include woodlots 60 years of age or older, as a result of a recent Local Planning Appeal Tribunal (LPAT) decision. The Site occurs within the urban area of the City of Ottawa, and therefore the recently amended urban area criteria apply.

In order to evaluate the potential presence of Significant Woodlots, vegetation communities within the Site were first inventoried and classified according to the vegetation communities identified in the Ecological Land Classification (ELC) manual (OMNRF 1998; Lee 2008) (described above). Once the presence of forest communities within the Site was identified, the size of each forest patch was measured using Geographic Information System (GIS) software. Forest patches ≥ 0.8 ha in size were identified (Refer to Section 3.3.1 and Figures 9 & 10). As discussed in Section 3.3.1, a total of five (5) forest patches that are ≥ 0.8 ha in size were identified within the Site, with the largest being approximately 1.59 ha.

Historic air photos made available by the City of Ottawa (2019a) and NRCAN (2019) were then utilized to determine the likely age of forest within each of the forest patches ≥ 0.8 ha in size. As discussed in Section 3.3.2, air photos from 1976 and July 1959 were utilized to evaluate forest age. The historic air photos from 1976 are approximately 44 years old, whereas the historic air photo from July 1959 is approximately 61 years old and most closely matches the 60 year age criteria. Of the five (5) forest patches ≥ 0.8 ha in size, three (3) appear to include significant forest cover that is ≥ 60 years of age (Refer to Section 3.3.2 and Figure 11). Therefore, there are three (3) forest patches within the Site which qualify as Significant Woodlots under the amended City of Ottawa criteria for the urban area. The significant features and functions of the three (3) Significant Woodlots were further evaluated and discussed by reviewing the *Natural Heritage Reference Manual* criteria (OMNRF 2010).

2.0.3 Environmental Impact Statement Methodology

The presence of natural heritage features was assessed by completing the following:

- Site surveys to describe vegetation communities and inventory trees (see above);
- Completion of a Significant Woodlot assessment (see above and Appendix D);
- Site surveys to assess the potential for the habitat of Species at Risk (SAR), wetlands, fish habitat, significant wildlife habitat features, and other significant habitat features to be present;
- Examination of aerial imagery to evaluate landscape features;
- Natural Heritage Information Center (NHIC) database review;
- Obtainment of an updated potential Species at Risk (SAR) List for the Geographic Township of March from the Ontario Ministry of Natural Resources and Forestry (OMNRF);
- Review of Official Plan designations; and
- Review of the background geotechnical report (Paterson 2019).

Detailed surveys to assess natural heritage features were completed as follows:

- **Plant Inventory, Large Tree Inventory and Ecological Land Classification:** See description above.
- **Breeding Bird Survey:** In order to assess the potential presence of avian Species at Risk (SAR) including Bobolink (threatened), Eastern Meadowlark (threatened), Wood Thrush (special concern), Eastern Wood Pewee (special concern), Barn Swallow (threatened), Chimney Swift (threatened), and Bank Swallow (threatened), a breeding bird survey was undertaken following the OMNRF *Wildlife Monitoring Programs and Inventory Techniques - Technical Manual* (Konze & McLaren 1998) Breeding Bird Survey (BBS) method. As discussed below in Section 3.7, due to the absence of potentially suitable habitat, none of these species were anticipated to be likely to occur within the Site. The survey included completion of three (3) site surveys in May and June 2018. The timing and methodology of the surveys followed the requirements outlined in the OMNRF *Survey Methodology under the Endangered Species Act: Dolichonyx oryzivorus (Bobolink)* (OMNRF 2011a). As part of the survey, all interior and exterior surfaces of buildings within the Site were searched to confirm the presence/absence of Barn Swallow nests. Breeding bird surveys were completed in the early morning during suitable weather conditions on May 24th (20 °C), June 2nd (24 °C), and June 13th (21 °C), 2018. Bird survey points are shown below in Figure 12.
- **Marsh Monitoring Program – Amphibian Call Counts:** The two (2) stormwater ponds and the stormwater swales that are present within the Site were surveyed to evaluate the potential presence of breeding amphibians. Amphibian breeding habitat was surveyed according to the *Marsh Monitoring Program – Amphibian Call Counts Method* (Konze and McLaren 1998). This method included three (3) night time surveys in April, May, and June 2018 to survey for

amphibian breeding activity by listening for frog calls. Surveys were completed after sunset on April 26th, May 24th, and June 25th, 2018. Survey conditions and results are presented in detail in Table C.

- **Blanding's Turtle and Snapping Turtle:** A basking survey was completed to survey the two (2) stormwater ponds and the hydrated portions of the stormwater swales, in order to evaluate the potential presence of Blanding's Turtle (threatened) and Snapping Turtle (special concern). Surveys were undertaken following the OMNRF *Occurrence Survey Protocol for Blanding's Turtle in Ontario* (OMNRF 2013). Per the OMNRF protocol, five (5) survey visits were completed between late April and mid-June 2018. Although not required by the survey protocol, an additional sixth survey visit was completed in September 2018 in order to evaluate the potential presence of turtles prior to the overwintering season. Surveys were completed on April 30th, May 8th, May 24th, June 2nd, June 13th, and September 17th, 2018. Survey conditions and results are presented in detail in Table D.
- **Eastern Whip Poor Will and Common Nighthawk:** Surveys for Eastern Whip Poor Will and Common Nighthawk were undertaken following the OMNRF *Draft Survey Protocol for Eastern Whip Poor Will* (OMNRF 2014f). The protocol necessitates that three (3) Whip Poor Will call surveys must be undertaken after dusk (one week before or after the full moon), from mid-May until end of June. Surveys were completed on May 24th, May 31st, and June 25th, 2018. Survey conditions and results are presented in detail in Table E. The survey protocol functions by listening for Eastern Whip Poor Will calls from fixed survey points. The survey protocol instructs the surveyor to: "*Examine aerial imagery or a map, and set up a survey route(s) along existing roads (when possible) or trails within or adjacent to the project area so that the route passes within 300 m of all typical habitat...Eastern Whip-poor-will can be heard for 300 m but may be heard up to 500 m under extremely good conditions...*" (OMNRF 2014f, pg. 7). As instructed by the survey protocol, the survey points were selected both within and adjacent to the Site, utilizing existing roads where required. Some of the survey points were positioned outside of the Site limits in order to provide efficient coverage of the Site, ensuring that all areas of the Site fall within 300 m of one (or more) of the survey points. Whip Poor Will call survey points are shown in Figure 13.
- **Butternut Trees:** During the vegetation surveys and tree inventory, several Butternut Trees were found within the Site. The rules and regulations of the Ontario Endangered Species Act (ESA) require the completion of a Butternut Health Assessment (BHA) in order to assess the health status of the Butternut Trees and subsequent regulatory requirements under the Ontario ESA (OMECP 2019). A BHA was completed in June 2019. Refer to Appendix F for additional detail regarding the BHA methodology.
- **Bat Maternity Roost Assessment (Little Brown Bat, Northern Long Eared Bat, Tricolored Bat, Eastern Small Footed Myotis):** The OMNRF (2011b) guidelines for bat surveying are outlined in the *Bats and Bat Habitats: Guidelines for Wind Power Projects*. These guidelines state that

deciduous and mixed forest habitats have the potential to provide maternity roosting sites. Per the OMNRF guidelines, the potential for qualifying forest areas to provide maternity roosting habitat is assessed by completing a bat snag/cavity survey during the leaf-off period. The surveying protocol states that a minimum of 10x 0.05 ha plots must be surveyed for any qualifying forest area <10 ha in size. All forest patches within the Site are <10 ha in size, and therefore each qualifying forest patch within the Site required completion of a minimum of 10x 0.05 ha plots (surveying an area 0.5 ha in size). Due to the requirement to complete 10x 0.05 ha plots, forest patches must be a minimum of 0.5 ha in size in order to complete the survey. All forest patches within the Site which are ≥ 0.5 ha in size were surveyed for the presence of cavity trees/snags on January 10th, 2020. Conditions during the survey included cloudy skies, temperatures of -4 °C, and full snow coverage throughout the Site. Given the comparatively small size of forest patches within the Site (the largest being approximately 1.59 ha in size), it was determined that it would be more efficient to search the entirety of each feature for cavity trees/snags, rather than identifying plots. As such, the entirety of each forest patch within the Site ≥ 0.5 ha in size was surveyed as part of the bat maternity roost assessment. Survey results are presented in detail in Table F. The qualifying forest patches that were assessed during the survey are shown in Figure 15. No caves, bedrock fissures, mining shafts, abandoned buildings, or other features which may function as bat hibernacula habitat were noted within the Site. During the January 10th, 2020 survey, all buildings within the Site were examined to determine if any included significant exterior openings which may allow bats to enter. As discussed below in Section 3.7.4, all buildings within the Site were found to be in good condition and well maintained. The buildings are continuously occupied/utilized year round, and no evidence of significant exterior openings was noted. As such, the buildings within the Site are unlikely to function as bat hibernacula sites.

- **Aquatic Habitat and Fish Habitat Assessment:** As discussed below in Section 3.4, there are no natural wetlands or watercourses within the Site. The two (2) existing stormwater management ponds and the stormwater management swales are artificial features that are entirely fed by outlet pipes from the surrounding subdivisions and overland flow from the golf course. There is no upstream or downstream connection to natural watercourses or wetlands. As such, a Headwaters Drainage Assessment (HDA) is not anticipated to be required to support the Mississippi Valley Conservation Authority (MVCA) project review. Due to the fact that stormwater ponds are not regulated by the Fisheries Act, a fish habitat assessment was not deemed to be required. Requirements for fish and wildlife salvage during dewatering are discussed in Section 4.4.3.

3.0 EXISTING CONDITIONS

3.1 Geological Conditions

Paterson Group (2019) note that the Site is predominately flat. The Site is predominantly well drained, although some areas of the golf course are prone to seasonal shallow ponding. Surface conditions generally consist of topsoil overlying a firm to very stiff silty clay deposit. The silty clay deposit is generally underlain by a glacial till deposit. Bedrock outcrops and shallow bedrock were noted in several locations throughout the Site. The overburden thickness to bedrock varies between 0 m and 20 m (Paterson Group 2019).

3.2 Vegetation Communities (TCR)

The Site is predominantly an artificial landscape dominated by manicured lawns (e.g. the golf course) and planted landscaping features, which include a mix of native and non-native trees, including many large trees and both deciduous and coniferous plantings. Natural vegetation communities primarily consist of patches of native deciduous forest and deciduous thickets, which are present principally around the edges of the Site.

For the purposes of this Combined EIS and TCR, landscaping features, individual trees, and tree stands were surveyed and are described in detail where stands of trees occur with approximately ten (10) or more stems and/or where individual trees ≥ 50 cm dbh occurred. Smaller tree stands (<10 stems) and individual trees with a dbh <50 cm were not documented in detail throughout the Site, although the presence of landscaping features is described in general terms. In order to provide an inventory of large trees, both planted and naturally occurring trees ≥ 50 cm dbh were documented whenever they were encountered. Trees ≥ 50 cm dbh are described below and are shown in Figures 3 to 8. Any forest or thickets communities were classified according to Ecological Land Classification criteria. Vegetation features found within the Site include the following:

- The Golf Course;
- Landscaping Features (Individual Trees and Small Stands);
- Tree Stands and Large Trees;
- Dry-Fresh Sugar Maple - Basswood Deciduous Forest (Community A);
- Deciduous Shrub Thicket (Community B);
- Fresh-Moist Poplar Deciduous Forest (Community C);
- Dry-Fresh Sugar Maple – Black Cherry Deciduous Forest (Community D);
- Dry-Fresh Sugar Maple – Ironwood Deciduous Forest (Community E);
- Fresh-Moist White Spruce - Hardwood Mixed Forest (Community F);
- Dry-Fresh White Ash – Hardwood Deciduous Forest (Community G); and
- Silver Maple Mineral Deciduous Swamp (Community H).

Due to the large size of the Site and its layout, it was necessary to present vegetation community mapping over multiple figures, each of which shows a section of the Site. Figure 2 divides the Site into six (6) mapping sections. Figures 3 to 8 show vegetation communities within each section of the Site. Appendix A includes photos of the vegetation communities. Appendix B includes a list of plant species noted during the vegetation surveys. Each of the vegetation communities is described in greater detail below.

FIGURE 2: VEGETATION MAPPING OVERVIEW

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



— Site Limits **— Section Boundary**

Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate.

FIGURE 3: VEGETATION MAPPING – SECTION 1

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Please Note:
This is not a
legal land
survey. All
dimensions
and locations
are shown as
approximate.



FIGURE 4: VEGETATION MAPPING – SECTION 2

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate.



FIGURE 5: VEGETATION MAPPING – SECTION 3

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Deciduous Shrub Thicket (Community B)

SECTION 2

Dry-Fresh Sugar Maple – Basswood Deciduous Forest (Community A)

Dry-Fresh Sugar Maple – Ironwood Deciduous Forest (Community E)

SECTION 3

SECTION 5

Deciduous Shrub Thicket (Community B)

SECTION 4


Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate.



FIGURE 6: VEGETATION MAPPING – SECTION 4

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate.





FIGURE 7: VEGETATION MAPPING – SECTION 5

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate.




FIGURE 8: VEGETATION MAPPING – SECTION 6

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate.

3.2.1 Golf Course

The golf course includes golf greens, fairways, tee boxes, and other golf course features. The majority of the golf course consists of manicured lawn dominated by domestic grasses. Due to ongoing landscaping and maintenance as part of the golf course operation, shrubs, tree stems, and herbaceous groundcover generally do not occur within the golf course, except where planted as landscaping features. Weedy species are generally absent as a result of landscaping activities, although a few White Clover, Red Clover, Dandelion and Common Plantain are present among the grasses.

3.2.2 Landscaping Features (TCR)

Planted tree stands with approximately ten (10) or more stems are described below. As noted above, landscaping features that consist of smaller planted tree stands (<10 stems) and individual planted trees with a diameter at breast height (dbh) <50 cm were not documented in detail throughout the Site. In general, planted trees include a mixture of Red Pine, White Pine, Scots Pine, White Spruce, Norway Spruce, Sugar Maple, Silver Maple, Honey Locust, Bur Oak and Horse Chestnuts (planted in a few locations), varying in size between approximately 10 cm and 40 cm dbh. Several planted gardens with domestic flowers and shrubs are also present in various locations throughout the Site.

3.2.3 Tree Stands and Large Trees (TCR)

The following is a list of tree stands with approximately ten (10) or more stems and individual trees ≥ 50 cm dbh in size. Features which are described below as 'overgrown' include trees that are overgrown with Deciduous Shrub Thickets. Throughout the Site, the Deciduous Shrub Thickets have similar shrub and groundcover composition as described below for Community B. Tree Stands and Large Trees are listed below, and are numbered in Figures 3 to 8:

- **Feature #1:** Feature #1 is a 67 cm dbh Butternut.
- **Feature #2:** Feature #2 is a 57 cm dbh Bur Oak.
- **Feature #3:** Feature #3 is a stand of Norway Spruce and White Spruce which are between approximately 10 cm to 25 cm dbh in size.
- **Feature #4:** Feature #4 is a stand of Manitoba Maples with a dbh between approximately 10 cm to 40 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (see Community B below).
- **Feature #5:** Feature #5 is a stand of White Spruce, Norway Spruce, Sugar Maple and White Pine which are between approximately 10 cm and 25 cm dbh.
- **Feature #6:** Feature #6 includes a 48 cm and a 47 cm dbh Bitternut Hickory, which are overgrown with Deciduous Shrub Thicket (see Community B below).
- **Feature #7:** Feature #7 includes a 54 cm and a 71 cm dbh Bur Oak.

- **Feature #8:** Feature #8 is a 57 cm dbh Bur Oak.
- **Feature #9:** Feature #9 is a stand of Trembling Aspen up to 20 cm dbh, which is overgrown with Deciduous Shrub Thicket (see Community B below).
- **Feature #10:** Feature #10 is a row of approximately twenty (20) White Pine, which vary between approximately 30 cm to 50 cm dbh.
- **Feature #11:** Feature #11 includes a 48 cm and a 64 cm dbh Bur Oak.
- **Feature #12:** Feature #12 is a stand of Ironwood and Bur Oak growing around a bedrock outcrop. Trees within the stand vary between approximately 10 cm and 30 cm dbh,
- **Feature #13:** Feature #13 is a Weeping Willow with a dbh of over 1 m.
- **Feature #14:** Feature #14 is a Deciduous Shrub Thicket dominated by Staghorn Sumac (see Community B below).
- **Feature #15:** Feature #15 is an 84 cm dbh Bur Oak.
- **Feature #16:** Feature #16 is a 96 cm dbh Bur Oak.
- **Feature #17:** Feature #17 is a stand of Norway Spruce and Silver Maple, which vary between approximately 10 cm and 30 cm dbh.
- **Feature #18:** Feature #18 is a stand of approximately twenty (20) White Pine, which vary between approximately 30 cm and 71 cm dbh. The base of the trees is overgrown with Deciduous Shrub Thicket.
- **Feature #19:** Feature #19 is a stand of White Spruce, Norway Spruce, and Bur Oak which vary between approximately 10 cm and 30 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (see Community B, below).
- **Feature #20:** Feature #20 is an 84 cm dbh Bur Oak.
- **Feature #21:** Feature #21 is a stand of White Cedar that vary between approximately 10 cm and 20 cm dbh.
- **Feature #22:** Feature #22 includes approximately seven (7) White Pine and four (4) White Spruce. One (1) White Spruce is 54 cm dbh in size, whereas the other trees vary between approximately 10 cm and 30 cm dbh.
- **Feature #23:** Feature #23 is a stand of approximately eight (8) White Pine and two (2) Red Pine that vary between approximately 40 cm and 60 cm dbh.
- **Feature #24:** Feature #24 is a mixed stand of Basswood, White Spruce, Manitoba Maple, American Elm and Black Cherry, with stems varying between approximately 10 cm and 30 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #25:** Feature #25 is a Deciduous Shrub Thicket (Community B, see below).
- **Feature #26:** Feature #26 is a 57 cm dbh American Elm.
- **Feature #27:** Feature #27 is a stand of Basswood, Bur Oak, and Sugar Maple which vary between approximately 10 cm and 25 cm dbh.
- **Feature #28:** Feature #28 is a 97 cm dbh Bur Oak.

- **Feature #29:** Feature #29 is a 74 cm dbh Sugar Maple.
- **Feature #30:** Feature #30 is a 56 cm dbh American Elm.
- **Feature #31:** Feature #31 includes a 47 cm dbh Sugar Maple and a 65 cm dbh Basswood.
- **Feature #32:** Feature #32 is a 102 cm dbh Silver Maple.
- **Feature #33:** Feature #33 includes a 50 cm and a 48 cm dbh Honey Locust.
- **Feature #34:** Feature #34 includes a line of Basswood which are between approximately 40 cm and 60 cm dbh in size. The tree stand is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #35:** Feature #35 is a stand of Manitoba Maple up to 20 cm dbh in size, which is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #36:** Feature #36 includes a 53 cm, 48 cm and 54 cm dbh White Pine and White Cedars between approximately 10 cm and 20 cm dbh.
- **Feature #37:** Feature #37 is a stand of White Spruce and White Pine between approximately 30 cm and 40 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #38:** Feature #38 is a dying 68 cm dbh White Ash.
- **Feature #39:** Feature #39 is a stand of dead White Ash between approximately 10 cm and 20 cm dbh.
- **Feature #40:** Feature #40 includes six (6) Red Pine and five (5) White Pine between approximately 20 cm and 40 cm dbh.
- **Feature #41:** Feature #41 is an 84 cm dbh Bitternut Hickory.
- **Feature #42:** Feature #42 is a stand of White Pine between approximately 40 cm and 60 cm dbh.
- **Feature #43:** Feature #43 is a stand of Trembling Aspen and dead/dying White Ash between approximately 10 cm and 30 cm dbh. Sugar Maple and American Elm are also present. The stand is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #44:** Feature #44 is a stand of Sugar Maple and Domestic Apple with a dbh between approximately 10 cm and 20 cm.
- **Feature #45:** Feature #45 is a stand of Red Pine and White Pine with a dbh between approximately 10 cm and 30 cm.
- **Feature #46:** Feature #46 is a stand of White Pine and Sugar Maple between approximately 30 cm and 60 cm dbh.
- **Feature #47:** Feature #47 is a stand of Trembling Aspen, Sugar Maple, American Elm, White Ash, and Basswood between approximately 10 cm and 25 cm dbh.
- **Feature #48:** Feature #48 is a stand of White Pine and Sugar Maple between approximately 40 cm and 60 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #49:** Feature #49 is a 76 cm dbh American Elm.

- **Feature #50:** Feature #50 is an 86 cm dbh Bitternut Hickory.
- **Feature #51:** Feature #51 is a 76 cm dbh White Pine.
- **Feature #52:** Feature #52 is a 79 cm dbh Sugar Maple.
- **Feature #53:** Feature #53 is a stand of Red Pine and White Spruce between approximately 20 cm and 30 cm dbh.
- **Feature #54:** Feature #54 is a 63 cm dbh Silver Maple.
- **Feature #55:** Feature #55 is a stand of White Pines between approximately 40 cm and 60 cm dbh. The base of the trees is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #56:** Feature #56 is a stand of Ironwood, White Ash, and Sugar Maple between approximately 10 cm and 30 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #57:** Feature #57 includes a 94 cm and 76 cm dbh Bur Oak.
- **Feature #58:** Feature #58 is a 77 cm dbh Bur Oak.
- **Feature #59:** Feature #59 is a stand of Red Oak, Sugar Maple, Basswood, and White Ash between approximately 10 cm and 45 cm dbh.
- **Feature #60:** Feature #60 is a stand of Red Pines between approximately 10 cm and 20 cm dbh.
- **Feature #61:** Feature #61 is a stand of Sugar Maples between approximately 20 cm and 40 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #62:** Feature #62 includes White Pine, Red Pine, Norway Spruce, and White Spruce between approximately 20 cm and 40 cm dbh, which are planted along the edge of the golf course at the property boundary.
- **Feature #63:** Feature #63 is a 92 cm dbh Sugar Maple.
- **Feature #64:** Feature #64 includes a stand of White Pines less than 20 cm dbh.
- **Feature #65:** Feature #65 is a Sugar Maple with a dbh of over 1 m.
- **Feature #66:** Feature #66 is a row of large Sugar Maple and Red Oak, which are between approximately 40 cm and 60 cm dbh in size.
- **Feature #67:** Feature #67 is a stand of Sugar Maples approximately 20 cm to 40 cm dbh in size. One (1) large Sugar Maple has a dbh of over 1 m.
- **Feature #68:** Feature #68 includes a 94 cm and a 73 cm dbh Sugar Maple.
- **Feature #69:** Feature #69 includes a 46 cm and 52 cm Bur Oak and an 85 cm dbh Red Oak.
- **Feature #70:** Feature #70 is a stand of Red Pine, White Pine, Norway Spruce and White Spruce planted along the edge of the golf course at the property boundary. Trees vary between approximately 20 cm and 30 cm dbh.
- **Feature #71:** Feature #71 is a stand of Trembling Aspen, White Birch, Sugar Maple, White Spruce, American Elm and dead White Ash growing along the edge of the golf course at the property boundary. Trees vary between approximately 10 cm and 40 cm dbh.

- **Feature #72:** Feature #72 includes a 72 cm dbh Sugar Maple and a Sugar Maple with a dbh of over 1 m.
- **Feature #73:** Feature #73 is a stand of White Spruce between approximately 40 cm and 60 cm dbh.
- **Feature #74:** Feature #74 includes several stands of White Spruce, Norway Spruce, Red Pine and White Pine, which are planted in several locations within the golf course and along the property line. Trees vary between approximately 20 cm and 60 cm dbh.
- **Feature #75:** Feature #75 includes three (3) Sugar Maples, each of which have a dbh of over 1 m.
- **Feature #76:** Feature #76 is a stand of Sugar Maple, Basswood and Ironwood between approximately 10 cm and 40 cm dbh.
- **Feature #77:** Feature #77 is a Sugar Maple with a dbh of over 1 m.
- **Feature #78:** Feature #78 includes a 68 cm and a 90 cm dbh Bur Oak
- **Feature #79:** Feature #79 includes a 76 cm Bur Oak, a Bur Oak with a dbh of over 1 m, two (2) Silver Maples with a dbh of over 1 m, and two (2) Silver Maples with multiple stems measuring 71 cm, 38 cm, 37 cm, 35 cm, and 43 cm dbh.
- **Feature #80:** Feature #80 includes a stand of Sugar Maples between approximately 10 cm and 40 cm dbh in size. An 84 cm dbh Sugar Maple is present within the stand.
- **Feature #81:** Feature #81 is a stand of Sugar Maples, White Cedar, and White Spruce between approximately 20 cm and 40 cm dbh.
- **Feature #82:** Feature #82 is a Sugar Maple with a dbh of over 1 m.
- **Feature #83:** Feature #83 includes a 71 cm dbh Silver Maple and a Silver Maple with a dbh of over 1 m.
- **Feature #84:** Feature #84 includes several stands of planted White Spruce, Norway Spruce, Sugar Maple, Red Pine, White Pine, Scots Pine, and White Cedar between approximately 20 cm and 60 cm dbh. The tree stands are planted in several clusters around the golf course in Section 6.
- **Feature #85:** Feature #85 is a stand of White Spruce and White Pine between approximately 20 cm and 40 cm dbh.
- **Feature #86:** Feature #86 includes a stand of young Bur Oak, Trembling Aspen, Basswood and White Ash between approximately 10 cm and 30 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #87:** Feature #87 includes a stand of White Cedar, Trembling Aspen, Ironwood, American Elm and Staghorn Sumac between approximately 10 cm and 40 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (Community B, see below).
- **Feature #88:** Feature #88 is a stand of White Spruce and White Pine planted adjacent to the parking lot. Trees vary in size between approximately 20 cm and 40 cm dbh.

- **Feature #89:** Feature #89 includes a row of planted Silver Maples adjacent to the parking lot. Trees vary in size between approximately 20 cm and 40 cm dbh.
- **Feature #90:** Feature #90 includes Silver Maples, Sugar Maples, White Pine, Norway Spruce and White Spruce planted around the clubhouse. Trees vary in size between approximately 20 cm and 40 cm dbh.
- **Feature #91:** Feature #91 is a 58 cm dbh Butternut.
- **Feature #92:** Feature #92 is a large multi-stemmed Basswood. The tree has four (4) stems which vary in size between approximately 60 cm and 90 cm dbh.
- **Feature #93:** Feature #93 includes three (3) large Bur Oaks and three (3) large Sugar Maples, each between approximately 60 cm and 90 cm dbh.
- **Feature #94:** Feature #94 is a 76 cm dbh Basswood.

3.2.4 Forest and Thicket Communities (TCR)

Tree inventory plots were completed in all forested communities. The number of plots and the tree size measurements are summarized below in Tables A & B. The following forest and thicket communities were identified within the Site:

- **Dry-Fresh Sugar Maple - Basswood Deciduous Forest (Community A):** Community A is dominated by Sugar Maple. Basswood, American Elm, White Ash, Black Cherry, Butternut, Largetooth Aspen, American Beech, Trembling Aspen, Bur Oak and White Birch also occur. Most of the Community A forest patches are moderately aged, with the majority of trees between approximately 10 cm and 40 cm dbh. Shrub cover includes Common Buckthorn, Tartarian Honeysuckle, Lilac, Wild Red Raspberry, Red Osier Dogwood, Alternate Leaved Dogwood, Domestic Apple, and Riverbank Grape, all of which were principally found growing around the forest edges and within openings. Within the forest interior, shrub cover is generally sparse, with Riverbank Grape and Prickly Gooseberry occurring sporadically. Groundcover includes a typical mixture of deciduous forest species including Bracken Fern, Spinulose Wood Fern, Downy Yellow Violet, White Baneberry, Wild Sarsaparilla, Trout Lily, Day Lily, False Solomon's Seal, White Trillium, Virginia Creeper, and Common Blue Violet. Forest openings were generally dominated by Deciduous Shrub Thickets, with a similar composition as described below (Community B).
- **Deciduous Shrub Thicket (Community B):** Deciduous Shrub Thickets are found throughout the Site in several locations. The large thickets found in Section 3 are growing around several large bedrock outcrops. The shrub thickets are dominated by deciduous shrubs, with Common Buckthorn and Staghorn Sumac being the most common shrubs in most areas. However, Lilac, Glossy Buckthorn, Tartarian Honeysuckle, Choke Cherry, Alternate Leaved Dogwood, Red Osier Dogwood, Wild Red Raspberry, Domestic Apple, Riverbank Grape, and Purple Flowering Raspberry are also abundant throughout the Site. Trees found within the shrub thickets include young stems (generally 10 cm to 30 cm dbh) of many of the deciduous and coniferous trees that are planted and/or occur naturally throughout the Site. Groundcover includes a mixture of native and non-native weedy species including Brome Grass, Meadow Grass, Timothy, Garlic Mustard, Common Ragweed, Canada Anemone, Common Burdock, Common Milkweed, Yellow Rocket, Canada Thistle, Bull Thistle, Queen Anne's Lace, Philadelphia Fleabane, Common Strawberry, Ox-eye Daisy, Common Buttercup, Canada Goldenrod, New England Aster, Small White Aster, Dandelion, Red Clover, White Clover, Common Mullein, Virginia Creeper, and Tufted Vetch. Thick colonies of the highly invasive Dog Strangling Vine are present in some areas.
- **Fresh-Moist Poplar Deciduous Forest (Community C):** Community C is dominated by Large Tooth Aspen, with Sugar Maple, White Ash, American Elm and Bur Oak well represented. Butternut are also present within Community C. The forest is moderately aged, with the majority of trees between approximately 10 cm and 40 cm dbh. Shrub cover includes Common

Buckthorn, Tartarian Honeysuckle, Lilac, Wild Red Raspberry, Red Osier Dogwood, Alternate Leaved Dogwood, Domestic Apple, and Riverbank Grape, all of which were principally found growing around the forest edges and within openings. Within the forest interior, shrub cover is generally sparse, with Riverbank Grape, Virginia Creeper and Skunk Currant occurring sporadically. Groundcover included Jack in the Pulpit, White Baneberry, Lady Fern, Woolly Sweet Cicely, White Trillium, and Trout Lily.

- **Dry-Fresh Sugar Maple – Black Cherry Deciduous Forest (Community D):** Community D differs from Community A primarily due to the fact that Sugar Maple is comparatively less dominant in Community D. Black Cherry, Basswood, and White Ash account for a higher proportion of trees within Community D (compared to Community A). The forest is relatively young, with the majority of trees between approximately 10 cm and 30 cm dbh. Shrub and groundcover within Community D is similar as described above for Community A.
- **Dry-Fresh Sugar Maple – Ironwood Deciduous Forest (Community E):** Community E differs from Community A primarily due to the fact that Sugar Maple and Ironwood are co-dominant. Basswood, White Ash, and Red Oak are also well represented. White Pine, White Birch, Bitternut Hickory and Black Cherry occur within Community E, but are relatively scarce. Most Community E forest patches are moderately aged, with the majority of trees between approximately 10 cm and 40 cm dbh. Shrub and groundcover within Community E is similar as described above for Community A.
- **Fresh-Moist White Spruce – Hardwood Mixed Forest (Community F):** Community F includes two (2) small patches of Mixed Forest that are found in Section 5. The Mixed Forest is dominated by White Spruce, with Sugar Maple and American Elm well represented. White Cedar, White Ash, Trembling Aspen and Black Cherry are also present. Notably, several large Butternut Trees are present in the eastern portion of Community F. The White Spruce, White Cedar and Butternut Trees range from approximately 20 cm to 50 cm dbh, and are comparatively larger than the other tree species. This suggests that the coniferous stems and Butternut may be older plantings, around which younger hardwood stems have recently grown. Shrub cover includes Common Buckthorn, Purple Flowering Raspberry, Riverbank Grape and Skunk Currant. Groundcover includes Sensitive Fern, White Baneberry, Wild Sarsaparilla, Virginia Creeper, and Common Blue Violet.
- **Dry-Fresh White Ash – Hardwood Deciduous Forest (Community G):** Community G is dominated by dead/dying White Ash trees with American Elm, Sugar Maple, and other hardwoods also being present. The forest is moderately aged, with the majority of trees between approximately 10 cm and 40 cm dbh. Shrub and groundcover within Community G reflects the highly disturbed and degraded condition of the forest, and is dominated by invasive Garlic Mustard and Common Buckthorn.

- **Silver Maple Mineral Deciduous Swamp (Community H):** Community H is a small area of Silver Maple Swamp that is present around the Stormwater Infiltration Swale in Section 5. Community H is dominated by Silver Maples, although Weeping Willow and Red Maple are also present. Shrub cover is generally sparse. Groundcover surrounding the Silver Maples and along the edges of the Stormwater Infiltration Swale includes Common Cattail, Purple Loosestrife, Reed Canary Grass, Spotted Touch Me Not, various sedges, and Sensitive Fern.

Table A: Forest Communities (Part 1)

Common Name	Scientific Name	Average DBH	DBH Standard Deviation	% Occupancy	Estimated Stems Per Hectare*
Dry-Fresh Sugar Maple - Basswood Deciduous Forest (Community A - 8 Plots)					
Sugar Maple	<i>Acer saccharum</i>	21	8	50%	1325
Basswood	<i>Tilia americana</i>	23	11	17%	450
American Elm	<i>Ulmus americana</i>	24	8	7%	175
White Ash	<i>Fraxinus americana</i>	22	10	6%	150
Black Cherry	<i>Prunus serotina</i>	23	7	6%	150
Butternut	<i>Juglans cinerea</i>	31	15	5%	125
Largetooth Aspen	<i>Populus grandidentata</i>	22	8	3%	75
American Beech	<i>Fagus grandifolia</i>	16	7	3%	75
Trembling Aspen	<i>Populus tremuloides</i>	17	10	2%	50
Bur Oak	<i>Quercus macrocarpa</i>	19	1	2%	50
White Birch	<i>Betula papyrifera</i>	40	1	2%	50
Fresh-Moist Poplar Deciduous Forest (Community C - 1 Plot)					
Largetooth Aspen	<i>Populus grandidentata</i>	29	10	45%	1800
Sugar Maple	<i>Acer saccharum</i>	14	2	15%	600
White Ash	<i>Fraxinus americana</i>	12	3	15%	600
American Elm	<i>Ulmus americana</i>	29	17	10%	400
Bur Oak	<i>Quercus macrocarpa</i>	15	6	10%	400
Butternut	<i>Juglans cinerea</i>	25	N/A	5%	200
Dry-Fresh Sugar Maple - Black Cherry Deciduous Forest (Community D - 2 Plots)					
Sugar Maple	<i>Acer saccharum</i>	19	6	38%	800
Black Cherry	<i>Prunus serotina</i>	23	4	29%	600
White Ash	<i>Fraxinus americana</i>	24	9	24%	500
Basswood	<i>Tilia americana</i>	23	13	10%	200

N/A Values in the DBH Standard Deviation are due to only one tree of that species being observed within the sample plot. Zero values are due to all trees of that species being the same size.

**Trees >50 cm were measured and are described in the text (above). However, they are not included in the tables, as they disproportionately affect the average tree size.

Please note: The combined % Occupancy for all tree species may not total 100%, due to rounding of the individual values for each species.

Table B: Forest Communities (Part 2)

Common Name	Scientific Name	Average DBH	DBH Standard Deviation	% Occupancy	Estimated Stems Per Hectare*
Dry-Fresh Sugar Maple - Ironwood Deciduous Forest (Community E - 6 Plots)					
Ironwood	<i>Ostrya virginiana</i>	15	3	35%	867
Sugar Maple	<i>Acer saccharum</i>	22	11	33%	833
Basswood	<i>Tilia americana</i>	26	12	13%	333
White Ash	<i>Fraxinus americana</i>	18	8	5%	133
Red Oak	<i>Quercus rubra</i>	29	15	5%	133
White Pine	<i>Pinus strobus</i>	33	9	4%	100
White Birch	<i>Betula papyrifera</i>	29	2	3%	67
Black Cherry	<i>Prunus serotina</i>	19	N/A	1%	33
Fresh-Moist White Spruce - Hardwood Mixed Forest (Community F - 2 Plots)					
White Spruce	<i>Picea glauca</i>	29	12	37%	1000
Sugar Maple	<i>Acer saccharum</i>	14	5	19%	500
American Elm	<i>Ulmus americana</i>	14	4	11%	300
White Cedar	<i>Thuja occidentalis</i>	28	13	7%	200
White Ash	<i>Fraxinus americana</i>	17	2	7%	200
Trembling Aspen	<i>Populus tremuloides</i>	15	5	7%	200
Butternut	<i>Juglans cinerea</i>	30	15	7%	200
Black Cherry	<i>Prunus serotina</i>	18	N/A	4%	100
Dry-Fresh White Ash - Hardwood Deciduous Forest (Community G - 1 Plot)					
White Ash	<i>Fraxinus americana</i>	24	9	54%	1400
American Elm	<i>Ulmus americana</i>	17	8	23%	600
Sugar Maple	<i>Acer saccharum</i>	15	5	23%	600
Silver Maple Mineral Deciduous Swamp (Community H - 1 Plot)					
Silver Maple	<i>Acer saccharinum</i>	27	15	100%	1400

N/A Values in the DBH Standard Deviation are due to only one tree of that species being observed within the sample plot. Zero values are due to all trees of that species being the same size.

**Trees >50 cm were measured and are described in the text (above). However, they are not included in the tables, as they disproportionately affect the average tree size.

Please note: The combined % Occupancy for all tree species may not total 100%, due to rounding of the individual values for each species.

3.3 Significant Woodlot Assessment (TCR)

The City of Ottawa guidelines for Significant Woodlot evaluation require preparation of an Individual Terms of Reference when evaluating potential Significant Woodlots within the urban area (City of Ottawa 2019b). An Individual Terms of Reference has been prepared to support the evaluation of the potential Significant Woodlots within the Site (Refer to Appendix D). The evaluation methodology has also been summarized above in Section 2.0.2.

The City of Ottawa Official Plan (Section 2.4.2), as amended by Official Plan Amendment 179, defines Significant Woodlots in the urban area as any forested area ≥ 0.8 ha in size supporting woodland 40 years of age or older at the time of evaluation. However, the age criteria has recently been revised to include woodlots 60 years of age or older, as a result of a recent Local Planning Appeal Tribunal (LPAT) decision. The Site occurs within the urban area of the City of Ottawa, and therefore the recently amended urban area criteria apply.


3.3.1 Significant Woodlot Assessment – Woodlot Sizes (TCR)

In order to evaluate the potential presence of Significant Woodlots, vegetation communities within the Site were first inventoried and classified according to the vegetation communities identified in the Ecological Land Classification (ELC) manual (OMNRF 1998; Lee 2008) (described above). The size of each forest patch within the Site is shown below in Figure 9. As shown in Figure 9, the majority of forest patches within the Site are small and fragmented. A total of five (5) forest patches that are ≥ 0.8 ha in size were identified within the Site, with the largest being approximately 1.59 ha. Forest patches ≥ 0.8 ha in size are shown in Figure 10. The five (5) forest patches ≥ 0.8 ha in size have been labelled as Woodlots A to E. These include the following:

- **Woodlot A:** Woodlot A is approximately 1.1 ha in size and is classified entirely as Dry-Fresh Sugar Maple – Ironwood Deciduous Forest (Community E).
- **Woodlot B:** Woodlot B is approximately 1.0 ha in size and is classified entirely as Dry-Fresh Sugar Maple – Basswood Deciduous Forest (Community A).
- **Woodlot C:** Woodlot C is approximately 1.0 ha in size and is classified entirely as Dry-Fresh Sugar Maple – Ironwood Deciduous Forest (Community E).
- **Woodlot D:** Woodlot D is approximately 1.59 ha in size and includes Dry-Fresh Sugar Maple – Basswood Deciduous Forest (Community A), Dry-Fresh White Ash – Hardwood Deciduous Forest (Community G), and Silver Maple Deciduous Swamp (Community H).
- **Woodlot E:** Woodlot E is approximately 1.27 ha in size and is classified entirely as Dry-Fresh Sugar Maple – Basswood Deciduous Forest (Community A).

FIGURE 9: FOREST ELC COMMUNITIES – WOODLOT SIZES

Kanata Golf and Country Club Redevelopment
Combined Environmental Impact Statement and Tree Conservation Report (Revised)




— Site Limits

Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate. Only Ecological Land Classification (ELC) Forest Communities are shown. Thicket communities and tree stands are shown on Figures 3 to 8. Refer to Figures 3 to 8 for forest community ELC labels.

FIGURE 10: FOREST PATCHES ≥ 0.8 HECTARES

Kanata Golf and Country Club Redevelopment
Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate. Only Ecological Land Classification (ELC) Forest Communities are shown. Thicket communities and tree stands are shown on Figures 3 to 8.

3.3.2 Significant Woodlot Assessment – Woodlot Ages (TCR)

Historic air photos made available by the City of Ottawa (2019a) and NRCAN (2019) were utilized to determine the likely age of forest within each of the forest patches ≥ 0.8 ha in size. The historic air photos from 1976 are approximately 44 years old, whereas the historic air photo from July 1959 is approximately 61 years old and most closely matches the 60 year age criteria. The historic air photos are shown below.

Although isolated trees and shrubs appear to be present in 1976, the majority of the area that is currently occupied by Woodlot A and Woodlot B is devoid of tree and shrub cover in 1976. It should be noted that a road is present in the vicinity of Woodlot A in the 1976 air photo. A small area north of the road (within Woodlot A) appears to have tree cover in 1976 (see below). However, the road was removed during the golf course development (after 1976), at which time the tree stand that occurred north of the road was also cleared. Conditions visible in the 1976 air photo suggest that the majority of trees within Woodlot A and Woodlot B are less than approximately 40 years of age, and hence do not meet the 60 year age criteria. Trees older than 40 years of age within Woodlot A and Woodlot B are likely to be limited to a few isolated stems.

In 1976 and also in July 1959, tree and/or shrub cover is visible throughout the majority of the area that is currently occupied by Woodlot C and Woodlot D. This suggests that the majority of trees within Woodlot C and Woodlot D are older than 60 years of age. In 1976, very young tree and/or shrub cover is visible in the area that is currently occupied by the southern portion of Woodlot E. The area that is currently occupied by the northern portion of Woodlot E appears largely devoid of tree and shrub cover in 1976. In July 1959, tree and shrub cover is again visible in the area that is currently occupied by the southern portion of Woodlot E, whereas the northern portion of Woodlot E appears largely devoid of tree and shrub cover. This suggests that trees in the southern portion of Woodlot E are older than 60 years of age, whereas trees in the northern portion of Woodlot E are likely younger than 40 years of age.


Of the five (5) forest patches ≥ 0.8 ha in size, three (3) appear to include significant forest cover that is ≥ 60 years of age (Woodlots C, D and E). Therefore, there are three (3) forest patches within the Site which qualify as Significant Woodlots under the amended City of Ottawa criteria for the urban area. Woodlots C, D and E are shown below in Figure 11.



Historic Air Photograph 1: Historic Air Photo from 1976 (Site limits shown in red). Note that although isolated trees and shrubs appear to be present in 1976, the majority of the area that is currently occupied by Woodlot A and Woodlot B is devoid of tree and shrub cover in 1976. This suggests that the majority of trees within Woodlot A and Woodlot B are less than approximately 40 years old. The road and the small tree stand that are visible in the northern part of Woodlot A were removed during the golf course development (after 1976) (Photo from City of Ottawa 2019a).




Historic Air Photograph 2: Historic Air Photo from 1976 (Site limits shown in red). Note that tree and/or shrub cover is visible throughout the majority of the area that is currently occupied by Woodlot C and Woodlot D. This suggests that the majority of trees within Woodlot C and Woodlot D are older than 40 years (refer to the July 1959 air photo below). Very young tree and/or shrub cover is visible in the area that is currently occupied by the southern portion of Woodlot E. The area that is currently occupied by the northern portion of Woodlot E appears largely devoid of tree and shrub cover. This suggests that trees in the southern portion of Woodlot E are older than 40 years of age (refer to the July 1959 air photo below), whereas trees in the northern portion of Woodlot E are likely younger than 40 years of age (Photo from City of Ottawa 2019a).



Historic Air Photograph 3: Historic Air Photo from July 1959. Note that tree and/or shrub cover is visible throughout the majority of the area that is currently occupied by Woodlot C and Woodlot D. This suggests that the majority of trees within Woodlot C and Woodlot D are older than 60 years. Tree and/or shrub cover is visible in the area that is currently occupied by the southern portion of Woodlot E. The area that is currently occupied by the northern portion of Woodlot E appears largely devoid of tree and shrub cover. This suggests that trees in the southern portion of Woodlot E are older than 60 years of age, whereas trees in the northern portion of Woodlot E are likely younger than 40 years of age (Photo from NRCAN 2019).

FIGURE 11: SIGNIFICANT WOODLOTS

Kanata Golf and Country Club Redevelopment
Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate. Significant Woodlots are shown to include Ecological Land Classification (ELC) Forest Communities ≥ 60 years of age and ≥ 0.8 ha in size (City of Ottawa - Urban Area Criteria).

3.3.3 Significant Woodlot Assessment – NHRM Criteria and Ecosystem Services (TCR)

The following is a summary of the *Natural Heritage Reference Manual* (NHRM) Significant Woodlot criteria for the three (3) Significant Woodlots that are found within the Site (OMNRF 2010):

- **Woodland Size Criteria** – The Site is within the Ottawa West Minor Watershed, which has approximately 38% forest cover (City of Ottawa 2011). In planning areas with 30-60% forest cover, woodlots 60 ha or larger would qualify under the size criteria. Woodlots C, D and E are approximately 1.0, 1.59 and 1.27 ha in size (respectively). Although the sizes of Woodlots C, D and E are sufficient for these features to qualify under the amended City of Ottawa criteria for the urban area (≥ 0.8 ha), they are much too small to qualify under the NHRM woodland size criteria.
- **Interior Forest Habitat** – Forested areas 100 m from an opening that is 20 m or greater in size are considered interior forest habitat. Woodlots C, D, and E each occur as relatively thin stands that are present along the edges of the Site. The largest of these features (Woodlot D) is approximately 1.59 ha in size. All three Significant Woodlots occur with houses on one side and the golf course on the other. There are no portions of the Significant Woodlots that occur more than 100 m from an opening, and therefore no interior forest habitat is present.
- **Proximity to Other Woodlands/Habitats** – Woodlots within 30 m of another significant feature meet this criteria. As discussed above, the Site is surrounded by existing developed residential properties and/or roads on all sides. Woodlots C, D and E all occur between the existing golf course and existing developed residential homes. As such, there are no other woodland and/or significant habitats in close proximity.
- **Water Protection** – As discussed below in Section 3.4, the only water features found within the Site include artificial stormwater management ponds and stormwater swales. All of the stormwater management features are fed either by outlet pipes from the adjacent subdivisions and/or by surface runoff from the golf course. There is no direct connection to any natural watercourses or wetlands. Although stormwater management swales pass through Woodlots D and E, the woodlots do not provide a significant water protection function, due to the absence of natural wetlands and watercourses.
- **Linkages** – As noted above, Woodlots C, D and E all occur between existing residential homes and the golf course. The Site in general is surrounded by existing developed residential properties and/or roads on all sides. As such, Woodlots C, D, and E are not likely to provide a significant linkage function.
- **Woodlot Diversity** – As described above, the plant diversity within Woodlots C, D and E is comparatively low, and the features are dominated by relatively young to moderately aged secondary regrowth forest. Due to their proximity to existing development and landscaping

features, there is relatively low native plant diversity and invasive species are comparatively highly represented. Woodlots C, D and E were not found to contain exceptional plant diversity, and no regionally rare forest plant species were noted.

- **Uncommon Characteristics** – Uncommon forest types, environmental features, or plant communities may contribute to woodlot significance. Also, forest stands older than 100 years would be considered significant. As discussed above in Section 3.3.2, historic air photos indicate that portions of Woodlots C, D and E are older than approximately 60 years of age. However, trees visible in the July 1959 and 1976 historic air photos appear relatively young, which suggests that trees within the woodlots are only likely to be marginally older than 60 years of age (on average). Woodlots C, D and E do not appear to be older than 100 years of age. Woodlots C, D and E are each comprised of common forest types that are relatively abundant as secondary regrowth throughout the region. As such, Woodlots C, D and E do not qualify under the Uncommon Characteristics criteria.
- **Economic and Social** – Woodlots which contribute special economic or social functions can qualify under this criteria. Woodlots C, D and E occur within the City of Ottawa urban area. Within the urban area, the City of Ottawa automatically recognizes woodlots ≥ 0.8 ha in size and over 60 years of age as qualifying under the social criteria. The social functions provided by Woodlots C, D, and E primarily relate to their position within a golf course and country club property. Within this context, they contribute to the general ability of the Site to provide opportunities for recreation (e.g. sporting activities), they provide aesthetic value, and they provide opportunities for passive recreational enjoyment. Woodlots C and D do not currently have formal or informal trail systems. A portion of the golf course pathway system, which includes a pedestrian bridge, passes through Woodlot E. Woodlots C, D and E all occur adjacent to existing residential properties, and therefore they provide aesthetic value for adjacent residents.

The City of Ottawa guidelines for Significant Woodlot evaluation require an assessment of the ecosystem services provided by potential Significant Woodlots (City of Ottawa 2019b). The NHRM criteria discussed above, while not labelled as 'ecosystem services', address the same natural heritage values as described in the City of Ottawa guidelines (e.g. water protection, social value, biodiversity, etc.) (City of Ottawa 2019b). The list of ecosystem services discussed in the City of Ottawa guidelines includes urban air quality (City of Ottawa 2019b). This is not addressed in the NHRM criteria. The *Results of the National Capital Air Quality Mapping Pilot Project* indicate that the City of Ottawa's air quality is within the Canadian and World Health Organization standards most of the time (City of Ottawa 2009). The City of Ottawa (2009) pilot project also noted that the results of the study were not sufficiently detailed to pinpoint air quality hotspots within the City. The City of Ottawa (2009) pilot project further notes that urban air quality is influenced by a wide variety of

factors (e.g. industrial output, transportation activity, home heating, weather patterns, climate, etc.), of which tree coverage is unlikely to be the most significant. As discussed above, the Site is within the Ottawa West Minor Watershed, which has approximately 38% forest cover (City of Ottawa 2011). The Ottawa West Minor Watershed is approximately 31,700 ha in size with approximately 12,046 ha of forest cover (38%) (City of Ottawa 2011). The forest patches within the Site are very small within the context of the subwatershed (the largest forest patch within the Site being approximately 1.59 ha in size). As such, the potential loss of forest cover associated with the redevelopment, and by extension the potential impact on air quality, is insignificant within the context of the subwatershed.

3.3.4 Significant Woodlot Assessment – Summary (TCR)

In summary, the City of Ottawa Significant Woodlot criteria for the urban area defines Significant Woodlots as forest patches that are ≥ 0.8 ha in size and 40 years of age or older at the time of evaluation. However, the age criteria has recently been revised to include woodlots 60 years of age or older, as a result of a recent Local Planning Appeal Tribunal (LPAT) decision. There are five (5) forest patches within the Site which are ≥ 0.8 ha in size. Of these, three (3) had significant shrub and/or tree coverage in the July 1959 historic air photo. There are therefore three (3) Significant Woodlots within the Site (Woodlots C, D and E).

Woodlots C, D and E are comparatively small secondary growth features that are partially degraded due to their presence adjacent to a golf course and existing residential development. As discussed above, the woodlots do not qualify as Significant Woodlots under any of the *Natural Heritage Reference Manual (NHRM)* Significant Woodlot criteria, with the exception of the social criteria (OMNRF 2010). Therefore, although Woodlots C, D and E have the potential to qualify as Significant Woodlots under the social criteria, they provide comparatively little ecological value and are not recommended to be retained for conservation purposes. Instead, retention and/or mitigation of impacts to Woodlots C, D and E should focus on preserving and/or replacing their social value. Potential impacts to Woodlots C, D and E, along with the proposed extent of tree retention, are discussed in greater detail in Section 4.1.1. Measures to preserve the social functions provided by Woodlots C, D and E are also discussed in Section 4.1.1.

3.4 Watercourses and Fish Habitat

3.4.1 Stormwater Infiltration Swales

There are six (6) stormwater infiltration/conveyance swales within the Site. All of the stormwater infiltration/conveyance swales were observed to be fed either by outlet pipes from the adjacent residential subdivisions and/or by surface runoff from the golf course. None of the stormwater swales are directly connected to any downstream natural features. Photographs of the stormwater swales, including the outlet pipes that feed them, are included in Appendix A.

Of the six (6) swales, only the swale in the southwest corner of the Site and the swale that connects to the northern stormwater management pond were observed to have significant standing water during the Site surveying. The swale in the southwest corner of the Site occurs in a broad ravine, which is present north of the existing clubhouse. A bridge passes over the ravine, connecting the clubhouse to the adjacent golf course. The swale passes through Woodlot E, and was observed to be hydrated in the spring and early summer, with surface water up to approximately 50 cm deep. The feature was observed to be dry by late summer. The swale does not appear to have an outlet, and water that is fed into the swale from the adjacent subdivision either evaporates or infiltrates.

The swale that connects to the northern stormwater management pond was also observed to be hydrated in the spring and early summer. Surface water depths up to approximately 50 cm were observed. The swale passes through Woodlot D and is fed by an outlet pipe from the adjacent subdivision. Water within the swale outlets to the adjacent northern stormwater management pond.

The remaining four (4) swales were predominantly dry throughout the surveying period. Within the dry swales, vegetation included Common Cattail and Reed Canary Grass. In the two (2) hydrated swales, vegetation included Common Cattail, Purple Loosestrife, Reed Canary Grass, Spotted Touch Me Not, various sedges, and Sensitive Fern. All of the stormwater management swales are artificial features that are fed either by outlet pipes from the adjacent subdivisions and/or by surface runoff from the golf course. They are too small and artificial in origin to be considered wetlands and have no open upstream or downstream connection to potential natural fish habitat. As such, none of the stormwater swales are considered significant features.

It should be noted that the minimum patch size for potentially suitable vegetation communities to qualify as wetlands under the Ecological Land Classification and Ontario Wetland Evaluation System is 0.5 ha (OMNRF 1998; OMNRF 2014g). The two (2) hydrated swales are each approximately 0.1 ha in size, and hence are too small to qualify as wetlands. The Mississippi Valley Conservation Authority (MVCA) was circulated as part of the development application review process. In their review

comments, the MVCA confirmed that their mapping does not show the presence of any wetlands within the Site, and also that the MVCA has no concerns with respect to wetland features.



McKINLEY ENVIRONMENTAL SOLUTIONS

613-620-2255

mckinleyenvironmental@gmail.com

www.mckinleyenvironmental.com

3.4.2 Stormwater Ponds

Photographs of the stormwater management ponds are included in Appendix A. Two (2) stormwater management ponds are located within the Site, both of which are artificial features. The stormwater management ponds predominantly consist of open water, with limited vegetation found growing around the edges. The majority of the pond edges appear to be regularly mowed, thereby limiting the growth of wetland plants. Small patches of wetland vegetation are found along the pond edges, including Yellow Iris, Narrow Leaved Cattail, Common Cattail, and Purple Loosestrife.

3.4.3 Fish Habitat

As discussed above in Section 2.0.3, fish sampling was not deemed to be required, due to the absence of natural wetland and watercourse features. However, the presence of fish within the stormwater management ponds was visually assessed by observing fish from the surface. Invasive Goldfish (*Carassius auratus*) and invasive Common Carp (*Cyprinus carpio*) were both observed to be present within the stormwater management ponds. In addition, unidentified minnows were observed, some of which may include individuals of native species. As discussed below in Section 4.4.3, a fish and wildlife salvage plan will be required to relocate fish and other wildlife during the dewatering of the stormwater management ponds. The fish and wildlife salvage plan will be required to include contingencies for the disposal of invasive species (e.g. Goldfish and Common Carp).

Fisheries and Oceans Canada does not require projects that take place within artificial stormwater management ponds to be submitted for review under the Fisheries Act (FOC 2019). Therefore, a review under the Fisheries Act is not required to support the decommissioning of the existing stormwater management ponds and swales.

3.5 Adjacent Lands and Significant Features

Within the Site, there are no features that are shown as Provincially Significant Wetlands (PSWs), Areas of Natural and Scientific Interest (ANSI), and/or features that are shown as part of the City of Ottawa Natural Heritage System (City of Ottawa 2014; OMNRF 2019). The only significant natural heritage features found within the Site are the Significant Woodlots, which are discussed above in Section 3.3.

There are several natural heritage features and urban parks located in the region surrounding the Site. The Beaver Pond and the surrounding forest/buffer lands are located approximately 450 m north of the Site, and are separated from the Site by existing residential homes and Walden Drive. The Kimmins Court Park is located approximately 800 m northeast of the Site and is also separated from the Site by existing houses. As shown in Figure 1, Bill Teron Park is located south of the Site and is separated from the Site by Campeau Drive, which is a multilane roadway that is sufficiently wide as to limit significant direct ecological connectivity between Bill Teron Park and the Site. Robert Gray Park is located approximately 400 m southeast of the Site and is also separated from the Site by Campeau Drive and existing high density developments. Due to the existing development surrounding the Site (including Walden Drive and Campeau Drive), there is no direct connection between the Site and the Beaver Pond, Kimmins Court Park, Bill Teron Park, and Robert Gray Park. Due to the separation distance between the Site and the adjacent natural heritage features/urban parks, as well as the presence of existing development surrounding the Site, the proposed redevelopment is unlikely to directly impact the Beaver Pond, Kimmins Court Park, Bill Teron Park, and Robert Gray Park. The potential for wildlife to move between the nearby natural heritage features/urban parks and the Site is discussed below in Section 3.8.

Walden Park (130 Walden Drive) is located immediately adjacent to the Site (located adjacent to the northwest corner of the Site) (Refer to Figure 1). The trees that occur at the edge of Walden Park adjacent to the Site were investigated on January 10th, 2020, and it was found that the forest at the edge of Walden Park predominantly consists of recent regrowth, with the majority of trees ≤ 25 cm diameter at breast height (dbh) in size. Photograph #118 in Appendix A shows the trees at the edge of Walden Park. The critical root zone of trees is generally accepted to be 10 cm for every centimeter of trunk dbh. Given that the majority of trees at the edge of Walden Park have a dbh of ≤ 25 cm, their critical root zone is ≤ 2.5 m. The proposed minimum 3 m wide landscaped buffer that is shown at the edge of Walden Park is therefore anticipated to be sufficient to protect the critical root zone of the edge trees.

3.6 Wildlife and Significant Wildlife Habitat

Wildlife and bird species noted during surveys of the Site are listed in Appendix C. Surveying results for Species at Risk (SAR) are discussed below in Section 3.7. The habitat of SAR is considered Significant Wildlife Habitat (SWH). As described below in Section 3.7, no wildlife SAR were noted within the Site.

Breeding bird survey points are shown in Figure 12. A total of forty (40) bird species were noted within the Site during the breeding bird survey. All of the bird species noted within the Site are relatively common species that are frequently found in urban and suburban areas in the Ottawa region. The stormwater management ponds were observed to attract Red Winged Blackbird, Mallard, Great Blue Heron, Canada Goose, Cackling Goose, Black Crowned Night Heron, Double Crested Cormorant, and Swamp Sparrow. The remaining species listed in Appendix C were observed within the forest and thicket patches throughout the Site. No interior forest breeding species, nor avian SAR, were observed within the Site.

Mammals observed within the Site included Common Raccoon, Eastern Grey Squirrel, Red Squirrel, Eastern Cottontail, and Eastern Chipmunk. In addition to the targeted wildlife surveys described in Section 2.0.3, additional field surveying was completed throughout the Site on January 10th, 2020. During the January 10th, 2020 site visit, snow was present throughout the Site, and observations were made of mammal tracks and signs. Mammal tracks noted during the site visit included Common Raccoon, Eastern Cottontail, Red Squirrel, Eastern Grey Squirrel, and Eastern Chipmunk. During the various wildlife surveys, Red Fox, White Tailed Deer, Striped Skunk, and Coyotes were not encountered within the Site. However, each of these species are relatively common in the suburban areas of Ottawa, and the presence of White Tailed Deer has been reported by local residents. As such, it can be assumed that White Tailed Deer, Red Fox, Striped Skunk, and Coyotes may be observed within the Site sporadically. In order for a Site to qualify as SWH for White Tailed Deer (e.g. a winter deer yard), the Site must include contiguous forest greater than 100 ha in size (OMNRF 2014b). The Site does not contain sufficient forest for it to be possible for it to qualify as a winter deer yard. The transient presence of Red Fox, White Tailed Deer, Striped Skunk, and/or Coyote is not sufficient for the Site to qualify as SWH under any of the other SWH categories (OMNRF 2014b).

The amphibian breeding survey results are summarized below in Table C. Amphibian surveys included the hydrated stormwater swales and the stormwater management (SWM) ponds. As noted in Table C, the only amphibians that were found within the Site were American Bullfrogs and Green Frogs. Both species were observed calling in the SWM ponds. The maximum extent of calling was observed on June 25th, when five (5) Green Frogs and two (2) American Bullfrogs were heard calling

in the Northern SWM Pond, and three (3) Green Frogs and two (2) American Bullfrogs were heard calling in the Southern SWM Pond. The density of amphibian calling activity was very low in comparison to natural wetlands that are typically identified as SWH due to amphibian breeding. Although American Bullfrogs were observed calling in low densities, breeding activity was not directly observed, and no egg masses and/or tadpoles were noted. As such, breeding activity could not be confirmed. The *Significant Wildlife Habitat Mitigation Support Tool* (OMNRF 2014b, pg. 510) describes American Bullfrog breeding habitat as "...deep, permanent pools and ponds as well as lakes, preferably with abundant emergent plants for foraging and cover/protection." As described above in Section 3.4.2, the majority of the stormwater pond edges appear to be regularly mowed, thereby limiting the growth of wetland plants. Small patches of wetland vegetation are found along the pond edges, however, the majority of the shoreline of both ponds is devoid of emergent vegetation. Photographs of the shoreline of the ponds are included in Appendix A. The absence of emergent vegetation, the low density of American Bullfrog calling, and the artificial and highly disturbed nature of the ponds, suggests that it is unlikely that the features provide significant American Bullfrog breeding habitat functionality. As such, the stormwater management ponds should not qualify as SWH for breeding amphibians.


No reptile species (e.g. no snakes or turtles) were observed within the Site, despite completing detailed basking surveys for turtles (discussed below). Notably, no snakes were observed anywhere within the Site. This suggests that it is unlikely that any snake hibernacula features occur within the Site, as snakes are typically abundant in the spring adjacent to hibernacula features. No stick nests, migratory bird stopover points, wetlands, heron rookeries, caves, bedrock fissures, snake hibernacula, or any other features which may qualify as SWH were noted within the Site (OMNRF 2014b).

TABLE C: AMPHIBIAN SURVEY RESULTS					
Survey Date	Temperature	Conditions	Start Time	Amphibian Calls	Other Species
April 26th, 2018	11°C	Clear Skies	8:30 PM	None within Site. Large chorus of Spring Peepers south of Campeau Drive.	None
May 24th, 2018	19°C	Clear Skies	9:00 PM	No Calling Activity. Green Frogs and American Bullfrogs observed in both SWM ponds.	None
June 25th, 2018	18°C	Clear Skies	9:45 PM	North SWM Pond - 5x Green Frogs and 2 x American Bullfrogs. South SWM Pond - 3x Green Frogs and 2x American Bullfrogs.	None

FIGURE 12: BIRD SURVEY POINTS

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



— - Site Limits B2 - Bird Survey Points

Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate.

3.7 Species at Risk

3.7.1 Blanding's Turtle and Snapping Turtle

The *General Habitat Description for Blanding's Turtles* (OMNRF 2014a) recognizes areas of suitable habitat that occur within 2 km of a known Blanding's Turtle sighting as habitat for the species. A population of Blanding's Turtles is known to reside within the Kizell Provincially Significant Wetland Complex and the South March Highlands Provincially Significant Wetland Complex. Portions of both wetland complexes are located north and northwest of the Site, within 2 km of the northern part of the Site. However, the Site is entirely separated from these wetlands by existing residential development. The existing residential development that lies between the Site and the Kizell Provincially Significant Wetland and the South March Highlands Provincially Significant Wetland is sufficiently dense that it is highly unlikely that a Blanding's Turtle could leave the wetlands and successfully travel to the Site.

As noted above in Section 3.4, there are no natural wetland or watercourse features found within the Site. The stormwater swales and stormwater ponds are artificial features with very limited areas of wetland vegetation. Due to their sparse wetland vegetation and their highly artificial and disturbed nature, it is unlikely that the stormwater swales and stormwater ponds are capable of providing suitable habitat for Blanding's Turtle.

However, in an abundance of caution, a basking survey was undertaken within the Site in order to verify if any turtle species are present. The survey results are summarized below in Table D. The survey included the standard five (5) visits required by the OMNRF survey protocol, as well as an additional sixth visit, which was completed in September 2018 to address the potential that turtles may be present prior to the overwintering season. No turtles of any species were observed within the Site during the surveys. This suggests that it is unlikely that any turtles are present within the Site. Blanding's Turtle and Snapping Turtle are therefore unlikely to be a concern for the proposed redevelopment.

TABLE D: BLANDING'S TURTLE SURVEY RESULTS

Survey Date	Start Temperature	End Temperature	Conditions	Start Time	Turtle Sightings
April 30th, 2018	19°C	19°C	Full Sun	3:00 PM	None
May 8th, 2018	21°C	20°C	Full Sun	3:15 PM	None
May 24th, 2018	16°C	20°C	Full Sun	8:30 AM	None
June 2nd, 2018	24°C	24°C	Full Sun	3:30 PM	None
June 13th, 2018	21°C	21°C	Partly Cloudy	1:00 PM	None
September 17th, 2018	24°C	22°C	Full Sun	1:00 PM	None

3.7.2 Eastern Whip Poor Will and Common Nighthawk

The *General Habitat Description for the Eastern Whip Poor Will* (OMNRF 2014e) describes Whip Poor Will breeding habitat as "...open and half treed areas (which) often exhibit a scattered distribution of treed and open space...". Suitable breeding habitats generally consist of a 'mosaic' of open, half treed, and closed conditions (Garlapow 2007). On average, it is estimated that Eastern Whip Poor Will require a minimum of 9 ha of suitable habitat in order to form a breeding territory (OMNRF 2014e). As noted above, the Site generally does not provide the 'mosaic' of open and closed space preferred by Eastern Whip Poor Will. Common Nighthawk can be found nesting in open areas with little ground vegetation such as alvars, shorelines, quarries, rock barrens, and recent burns (SARO 2020). Although they are sometimes found in orchards, urban parks, and along gravel roads, Common Nighthawk more frequently nest in natural areas (SARO 2020).

Eastern Whip Poor Will call surveys were completed to survey the Site for Eastern Whip Poor Will and Common Nighthawk. Eastern Whip Poor Will call survey sites are shown below in Figure 13. The survey results are summarized below in Table E. As outlined below, no evidence of Eastern Whip Poor Will and Common Nighthawk calling was noted during the survey. Eastern Whip Poor Will and Common Nighthawk are therefore unlikely to be a significant concern for the proposed redevelopment.

TABLE E: WHIP POOR WILL SURVEY RESULTS						
Survey Date	Temperature	Conditions	Wind Speed	Start Time	WPWI Calls	Other Species
May 24th, 2018	19°C	100% Clear	10 kph	9:00 PM	None	WPW 4 - Killdeer
May 31st, 2018	25°C	60% Clear	11 kph	10:00 PM	None	WPW 3 - Green Frogs
June 25th, 2018	18°C	100% Clear	10 kph	9:45 PM	None	WPW 2 - Green Frogs and American Bullfrogs WPW 3 - Green Frogs and American Bullfrogs

FIGURE 13: WPWI SURVEY POINTS

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



 - Site Limits  - Whip Poor Will Survey Points

Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate.

3.7.3 Butternut Trees (TCR)

During the vegetation surveys, Butternut Trees were noted in several locations throughout the Site, including in Vegetation Communities A, C and F. The rules and regulations of the Ontario Endangered Species Act (ESA) require the completion of a Butternut Health Assessment (BHA) in order to assess the health status of the Butternut Trees and subsequent regulatory requirements under the Ontario ESA (OMECP 2019). A BHA was completed in June 2019 (Appendix F). The BHA documented the presence of twenty three (23) Category 2 (retainable) Butternut Trees and eleven (11) Category 3 (archiveable) Butternut Trees within the Site. Butternut Tree locations are shown below in Figure 14. Note that no Butternut Trees were encountered in the northern part of the Site. As such, Figure 14 has been zoomed in to show only the southern portion of the Site where Butternuts occur. Potential impacts on Butternut Trees and their habitat, as well as regulatory requirements for Butternut Trees, are summarized below in Section 4.4.1.


FIGURE 14: BUTTERNUT LOCATIONS

Kanata Golf and Country Club Redevelopment

Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate. The northern part of the Site is not shown on this figure, as no Butternut Trees were found within the Site beyond the area displayed.



3.7.4 Bat Species at Risk

Little Brown Bat, Northern Long Eared Bat, Tricolored Bat, and Eastern Small Footed Myotis are all bat species which are listed as endangered in Ontario. All four (4) species have the potential to occur within the Ottawa area (SARO 2020). It should be noted that no bats were observed foraging within the Site during the Amphibian Call Count Survey and the Eastern Whip Poor Will Call Survey, both of which were completed at night.

The OMNRF (2011b) guidelines for bat surveying are outlined in the *Bats and Bat Habitats: Guidelines for Wind Power Projects*. These guidelines state that deciduous and mixed forest habitats have the potential to provide maternity roosting sites. As described above in Section 2.0.3, all qualifying forest patches ≥ 0.5 ha in size within the Site were surveyed for the potential presence of maternity roosting habitat. As shown below in Figure 15, a total of eight (8) qualifying forest patches ≥ 0.5 ha in size occur within the Site. Per the OMNRF (2011b) guidelines, the potential presence of maternity roosting habitat is assessed by determining the density of cavity trees and snags. Each of the qualifying forest patches was surveyed for cavity trees and snags on January 10th, 2020. The survey results are summarized below in Table F. A total of twenty (20) cavity trees were noted throughout the Site, while no snags were found. Photographs of the cavity trees are included in Appendix A. As shown in Table F, the highest density of cavity trees found within the Site was 4.0 cavity trees per hectare. The OMNRF (2011b) guidelines state that in order for a forest patch to qualify as potential bat maternity roost habitat, the density of cavity trees/snags must be ≥ 10 trees/snags per hectare. Therefore, none of the forest patches within the Site contain sufficiently dense stands of cavity trees/snags to qualify as potential maternity roost habitat. It should be noted that the golf course conducts regular landscaping maintenance throughout the Site, during which unsightly trees (e.g. dead or decaying trees that may include cavities) are frequently removed. The ongoing landscaping and maintenance activities of the golf course likely reduce the potential for high density stands of cavity trees and snags within the Site.


No caves, bedrock fissures, mining shafts, abandoned buildings, or other features which may function as bat hibernacula habitat were noted within the Site. During the January 10th, 2020 survey, all buildings within the Site were examined to determine if any included significant exterior openings which may allow bats to enter. All buildings within the Site were found to be in good condition and well maintained. The buildings are continuously occupied/utilized year round, and no evidence of significant exterior openings was noted. As such, the buildings within the Site are unlikely to function as bat hibernacula sites.

The Site is therefore unlikely to provide significant bat maternity roosting and/or hibernacula habitat.

TABLE F: BAT MATERNITY ROOST ASSESSMENT SURVEY RESULTS				
Woodlot/Tree Stand*	Cavity Trees**	Snags	Feature Size	Cavity Trees Per Hectare
Tree Stand A	#1 - dead Sugar Maple - 25 cm #2 - dead Sugar Maple - 25 cm	0	0.58 ha	3.4
Tree Stand B	#3 - double stem Sugar Maple - 33 cm, 32 cm	0	0.58 ha	1.7
Tree Stand C	#4 - Butternut #23 - 71 cm	0	0.52 ha	1.9
Woodlot A	#6 - dead Sugar Maple - 42 cm #7 - Sugar Maple - 63 cm #8 - dead White Ash - 58 cm #9 - Sugar Maple - 69 cm	0	1.1 ha	3.6
Woodlot B	#5 - Bitternut Hickory (Feature #41) - 84 cm	0	1.0 ha	1.0
Woodlot C	#10 - Sugar Maple - 49 cm #11 - Red Oak (Feature #66) - 82 cm #12 - Sugar Maple - 83 cm #13 - Sugar Maple (Feature #63) - 96 cm	0	1.0 ha	4.0
Woodlot D	#19 - Sugar Maple (Feature #82) - >1 m #20 - Silver Maple - 85 cm	0	1.59 ha	1.3
Woodlot E	#14 - Basswood - 50 cm #15 - Sugar Maple - >1 m #16 - Butternut - 48 cm #17 - Basswood - 44 cm #18 - Sugar Maple - 72 cm	0	1.27 ha	3.9
*As described in Section 2.0.3, only forest patches ≥ 0.5 ha in size required assessment as potential bat maternity roosting habitat.				
**All tree sizes represent diameter at breast height.				

FIGURE 15: BAT MATERNITY ROOST ASSESSMENT

Kanata Golf and Country Club Redevelopment Combined Environmental Impact Statement and Tree Conservation Report (Revised)



Please Note: This is not a legal land survey. All dimensions and locations are shown as approximate. As described in Section 2.0.3 of the Combined EIS and TCR, only forest patches ≥ 0.5 ha in size required assessment as potential bat maternity roosting habitat. All forest patches ≥ 0.5 ha in size are shown. Refer to Figures 3 to 8 for Ecological Land Classification (ELC) forest community labels.

—— - Site Limits

 - Cavity Tree

3.7.5 Additional Species at Risk

The Natural Heritage Information Center (NHIC) records for the nine (9) grids that include and surround the Site were reviewed. This included an area 3 km x 3 km in size and all published Species at Risk (SAR) records were noted (OMNRF 2019). The Ontario Ministry of Natural Resources and Forestry (OMNRF) provided a potential Species at Risk (SAR) list for the Geographic Township of March (Appendix E). In addition to Blanding's Turtle, Snapping Turtle, Eastern Whip Poor Will, Common Nighthawk, Butternut Trees, Eastern Small Footed Myotis, Little Brown Bat, Northern Long Eared Bat, and Tricolored Bat (discussed above), the following SAR were identified as potentially occurring within the vicinity:

- American Eel – Endangered
- Lake Sturgeon – Threatened
- Hickorynut - Endangered
- American Ginseng - Endangered
- Bank Swallow – Threatened
- Barn Swallow – Threatened
- Chimney Swift – Threatened
- Bobolink and Eastern Meadowlark - Threatened
- Least Bittern - Threatened
- Loggerhead Shrike – Endangered
- Rusty Patched Bumblebee – Endangered
- Transverse Lady Beetle - Endangered
- Bald Eagle – Special Concern
- Black Tern – Special Concern
- Horned Grebe – Special Concern
- Canada Warbler – Special Concern
- Eastern Wood Pewee – Special Concern
- Wood Thrush – Special Concern
- Peregrine Falcon – Special Concern
- Rusty Blackbird – Special Concern
- Eastern Musk Turtle – Special Concern
- Northern Map Turtle – Special Concern
- River Redhorse – Special Concern
- Silver Lamprey – Special Concern
- Monarch – Special Concern

The potential for these species to occur within the Site is discussed below:

- **American Eel and Lake Sturgeon:** American Eel and Lake Sturgeon are fish species that are found in association with the Ottawa River (SARO 2020). As described above in Section 3.4, there are no natural wetlands or watercourses within the Site. Therefore, American Eel and Lake Sturgeon are unlikely to be a significant concern for the proposed redevelopment.
- **Hickorynut:** Hickorynut is a freshwater mussel found in association with the Ottawa River (SARO 2020). As described above in Section 3.4, there are no natural wetlands or watercourses within the Site. Therefore, Hickorynut is unlikely to be a significant concern for the proposed redevelopment.
- **American Ginseng:** American Ginseng are found in association with mature Deciduous Forests (SARO 2020). As noted above in Section 3.2, there are several Deciduous Forest vegetation communities within the Site. It should be noted that American Ginseng are exceedingly rare and prone to overharvesting, and are typically only found in Ontario in relatively remote and/or undisturbed forest areas. The forested habitats within the Site are present within an urban area, and are subject to frequent recreational usage. As such, it is relatively unlikely that American Ginseng would be found within the Site. No evidence of American Ginseng was noted within the Site during the plant surveys.
- **Bank Swallows:** Bank Swallows nest in natural and artificial sand and silt deposits with vertical faces (SARO 2020). There are no significant sand or silt deposits with vertical faces within the Site. No Bank Swallows were noted during the breeding bird survey. Bank Swallows are therefore unlikely to be a significant concern for the proposed redevelopment.
- **Barn Swallow and Chimney Swift:** Barn Swallows are found nesting in many anthropogenic structures including old barns, sheds, under bridges, and in large culverts (SARO 2020). Chimney Swifts are found nesting in uncapped stone chimneys (SARO 2020). No Barn Swallows or Chimney Swifts were seen foraging within the Site during the May and June breeding bird surveys. No evidence of Barn Swallow or Chimney Swift nesting was noted within the Site, and therefore neither species is anticipated to be a significant concern for the proposed redevelopment. Four (4) buildings are found within the Site. Building locations are shown in Figure 1. Photographs of the buildings are included in Appendix A. Buildings within the Site include the following:
 - **Building #1:** Building #1 is a maintenance building with metal siding, a metal roof and limited exterior overhangs. The only exterior opening is the garage roll-door, which is closed on a nightly basis. No evidence of Barn Swallow nesting was noted.
 - **Building #2:** Building #2 is also a maintenance building with metal siding, a metal roof and limited exterior overhangs. The only exterior opening is the garage roll-door, which is closed on a nightly basis. No evidence of Barn Swallow nesting was noted.

- **Building #3:** Building #3 is the pro-shop and clubhouse, which includes a restaurant. Building #3 has numerous overhangs and a patio. However, the building is well maintained and no evidence of Barn Swallow nesting was noted. Building #3 does not have any chimneys.
- **Building #4:** Building #4 is a small metal supply shed with limited exterior overhangs. No exterior openings were noted. No evidence of Barn Swallow nesting was noted.
- **Bobolink and Eastern Meadowlark:** Bobolink and Eastern Meadowlark can both be found nesting in graminoid dominated fields including natural prairies, fallow agricultural fields, hayfields, and pastures (SARO 2020). The open areas of the Site are dominated by manicured lawn (e.g. the golf course) which do not provide potentially suitable habitat for Bobolink and Eastern Meadowlark. No occurrences of Bobolink and/or Eastern Meadowlark were noted during the breeding bird survey. Bobolink and Eastern Meadowlark are therefore unlikely to be a significant concern for the proposed redevelopment.
- **Least Bittern:** Least Bittern breed in open marshes and wetlands. As described above in Section 3.4, the stormwater management ponds do not provide any significant areas of marsh habitat, and emergent vegetation within the ponds is limited to small patches around the pond edges. The extent of habitat provided by the stormwater management ponds is likely insufficient to support Least Bittern, and no evidence of Least Bittern was noted within the Site during the breeding bird surveys. Least Bittern are therefore unlikely to be a significant concern for the proposed redevelopment.
- **Loggerhead Shrike:** Loggerhead Shrike are found nesting in large pastures and grasslands with scattered low trees and thorny shrubs. They also nest and forage in alvars (SARO 2020). As discussed above in Section 3.2, the Site does not provide open pasture, alvar, and/or grassland habitat that is large enough to support Loggerhead Shrike. Therefore, Loggerhead Shrike are not likely to be a significant concern for the proposed redevelopment.
- **Rusty Patched Bumblebee and Transverse Lady Beetle:** Rusty Patched Bumblebee is exceedingly rare in Ontario and the only sightings in the province since 2002 have been at the Pinery Provincial Park on Lake Huron (SARO 2020). There have been no records of Transverse Lady Beetle in Ontario since 1990 (SARO 2020). As such, Rusty Patched Bumblebee and Transverse Lady Beetle are unlikely to be a significant concern for the proposed redevelopment.
- **Bald Eagle:** Bald Eagles are a species of Special Concern, and therefore their habitat is not protected by the Ontario Endangered Species Act (ESA). Bald Eagles are primarily found nesting adjacent to large lakes and rivers (e.g. the Ottawa River) (SARO 2020). Due to the absence of large bodies of water in the vicinity of the Site, Bald Eagles are unlikely to be present. As such, Bald Eagles are unlikely to be a significant concern for the proposed redevelopment.
- **Black Tern and Horned Grebe:** Black Terns build their nests in shallow marshes (SARO 2020). Horned Grebe build their nests in marshes, ponds, and shallow bays (SARO 2020). The wetland

vegetation found around the edges of the stormwater management ponds is much too small for Black Terns and/or Horned Grebes to nest. Therefore, Black Terns and Horned Grebes are unlikely to be a significant concern for the proposed redevelopment.

- **Canada Warbler, Eastern Wood Pewee, and Wood Thrush:** Canada Warbler, Eastern Wood Pewee, and Wood Thrush can all be found nesting in deciduous and mixed forests, although Eastern Wood Pewee and Wood Thrush are typically only found breeding in interior forest areas (SARO 2020). As discussed above in Section 3.3.3, there are no areas of interior forest habitat within the Site. No occurrences of Canada Warbler, Eastern Wood Pewee and/or Wood Thrush were documented during the breeding bird survey. As such, Canada Warbler, Eastern Wood Pewee, and Wood Thrush are unlikely to be a significant concern for the proposed redevelopment.
- **Peregrine Falcon:** Peregrine Falcons nest on steep cliff edges and at the top of tall buildings in urban areas (SARO 2020). There are no potentially suitable nest sites for Peregrine Falcons within the Site, and therefore they are unlikely to be a significant concern for the proposed redevelopment.
- **Rusty Blackbird:** Rusty Blackbirds breed in coniferous forest near wetlands (SARO 2020). As discussed above in Section 3.2, there are no areas of coniferous forest within the Site that are large enough to potentially support Rusty Blackbird. No evidence of Rusty Blackbird was noted during the breeding bird surveys, and therefore Rusty Blackbird are unlikely to be a significant concern for the proposed redevelopment.
- **Eastern Musk Turtle, Northern Map Turtle, River Redhorse, Silver Lamprey:** Eastern Musk Turtle, Northern Map Turtle, River Redhorse, and Silver Lamprey are all species of special concern, and therefore their habitat is not regulated under the Ontario ESA. All four (4) species are primarily riverine species (SARO 2020). Most sightings of these species in the region are associated with the Ottawa River and its major tributaries (SARO 2020). As described above in Section 3.4, there are no natural wetlands or watercourse habitats within the Site. Therefore, Eastern Musk Turtle, Northern Map Turtle, River Redhorse, and Silver Lamprey are unlikely to be a significant concern for the proposed redevelopment.
- **Monarch Butterfly:** Monarch Butterflies are found in association with their Milkweed host plants (SARO 2020). Occurrences of Common Milkweed within the Site were limited to the Deciduous Shrub Thicket (Community B). However, the density of Common Milkweed was not high, and no Monarch Butterflies were noted within the Site during surveying. It should be noted that Monarch Butterflies are a species of special concern, and therefore their habitat is not protected under the Ontario ESA. The wildlife and Species at Risk mitigation measures discussed in Section 4.4.2 will help to mitigate any potential impacts to individual Monarch Butterflies at the construction stage.

3.8 Linkages

As described above in Section 3.5, the Site is predominantly surrounded by existing developed residential properties and/or roads. The Beaver Pond and the surrounding forest/buffer lands are located approximately 450 m north of the Site, and are separated from the Site by existing residential homes and Walden Drive. There is no direct connection between the Site and the natural features surrounding the Beaver Pond. However, from both the northeast corner of the Site and the northwest corner of the Site, there are narrow corridors which could theoretically allow the movement of some urban adapted wildlife species. From the northwest corner of the Site, there is limited connectivity through Walden Park. However, the frontage of Walden Park along Walden Drive is entirely developed, with the exception of a narrow (approximately 20 m wide) undeveloped area immediately west of 144 Walden Drive. In order for wildlife to reach the northwest corner of the Site when travelling from the Beaver Pond, they would be required to cross over Walden Drive and then pass through the narrow approximately 20 m wide opening west of 144 Walden Drive. From the northeast corner of the Site, there is an approximately 40 m to 50 m wide area consisting of manicured lawn, a small playground, and a soccer field, which is surrounded by landscaping features and adjacent residential homes. The manicured lawn/recreational areas extend for approximately 300 m north of the northeast corner of the Site, before reaching the nearest area of contiguous tree cover. In order for wildlife to reach the northeast corner of the Site when travelling from the Beaver Pond, they would be required to cross Walden Drive and to pass through the highly disturbed and open corridor of manicured lawn/recreational areas, which is approximately 300 m long. Both routes provide very limited opportunities for wildlife movement, which only common urban species that are tolerant of disturbance/human activity would be likely to utilize.

As described above in Sections 3.2 and 3.4, the Site itself does not include any features which would provide a natural corridor function (e.g. watercourses, ravines, etc.). The forest within the Site occurs in discontinuous patches which are separated from one another by highly exposed areas of manicured lawn (e.g. the golf course). Again, this offers limited opportunities for wildlife movement, which only common urban species that are tolerant of disturbance/human activity would be likely to utilize. The Bill Teron Park is separated from the Site by Campeau Drive (a multi-lane road), which represents a significant barrier to wildlife movement for many species.

The existing barriers to wildlife movement both north and south of the Site (e.g. existing residential development, Walden Drive, Campeau Drive, etc.), the narrow and highly disturbed nature of the potential corridors to the northeast and northwest of the Site (varying between 20 m and 50 m wide), as well as the general lack of contiguous natural features throughout the Site, are such that the Site is unlikely to provide a significant wildlife movement function.

4.0 DESCRIPTION OF ENVIRONMENTAL IMPACTS AND MITIGATION

4.1 Terrestrial Habitat and Tree Removal (TCR)

4.1.1 Significant Woodlot Impacts and Tree Retention (TCR)

As described above in Section 3.3.4, there are three (3) woodlots within the Site that qualify as Significant Woodlots under the City of Ottawa criteria for the urban area (Significant Woodlots C, D and E). Significant Woodlots C, D and E are comparatively small secondary growth features that are partially degraded due to their presence adjacent to a golf course and existing residential development. As discussed in Section 3.3.3, the woodlots do not qualify as Significant Woodlots under any of the *Natural Heritage Reference Manual (NHRM)* Significant Woodlot criteria, with the exception of the social criteria (OMNRF 2010). Therefore, although Significant Woodlots C, D and E have the potential to qualify as Significant Woodlots under the social criteria, they provide comparatively little ecological value and are not recommended to be retained for conservation purposes. Instead, retention and/or mitigation of impacts to Significant Woodlots C, D and E should focus on preserving and/or replacing their social value.

In addition to preserving portions of the Significant Woodlots, additional forest patches, landscaping features, and tree stands will be preserved. Drawings showing the pre-development and post development forest and Significant Woodlot conditions are included below. The following is a summary of the recommended tree retention measures:

- The portion of Significant Woodlot D that overlaps the Neighborhood Park is proposed to be retained within the Neighborhood Park. The portion of Significant Woodlot E that overlaps the Woodland Park is proposed to be retained within the Woodland Park. Within each park, new trees will be planted adjacent to the retained portions of the Significant Woodlots (in areas that currently lack forest cover), in order to augment the features and functions of the retained portions of the Significant Woodlots;
- The Land Use Concept Plan includes an additional 5.19 ha of open space blocks, which will provide additional opportunities for tree retention and tree planting. All existing trees within the open space blocks will be retained wherever feasible, and new trees will be planted within any portions of the open space blocks that do not currently have forest coverage. Following completion of the redevelopment, each of the open space blocks are intended to be fully forested. Notably, a portion of Significant Woodlot C will be retained within the open space blocks. New trees will be planted within the open space block surrounding Significant Woodlot C (in areas that currently lack tree cover), thereby augmenting the features and functions of the retained portion of Significant Woodlot C;

- The portions of Significant Woodlots C, D, and E which do not fall within the parks/open space blocks cannot be retained due to grading and road elevation requirements. For each of the three (3) Significant Woodlots, the potential to expand the park and open space blocks to retain additional areas of the Significant Woodlots was investigated. In each case, it was determined that additional areas of the Significant Woodlots could not be retained without major changes to the road and development layout. This is due to the adjacent road elevation and grading requirements;
- As described below in Section 4.1.3, if grading requirements result in the removal of trees at the edges of the parks and/or the open space blocks, new trees will be planted at the edges of those features, in order to replace any trees lost due to grading requirements;
- The Land Use Concept Plan includes minimum 3 m wide landscaped buffers around the Site edges adjacent to existing residential properties. The combined size of the minimum 3 m wide landscaped buffers is 1.65 ha. Many of the Site edges are currently occupied by planted trees, tree stands, or forest patches, and therefore the minimum 3 m wide landscaped buffers will provide additional opportunities for tree retention along the Site edges, including protection of the critical root zones. New trees will be planted within the minimum 3 m wide landscaped buffers both where tree removal is required to accommodate grading, and also where there is currently insufficient tree coverage at the edge of the Site. Once the redevelopment is complete, the minimum 3 m property buffers will be fully treed with retained and/or planted trees;
- New trees and landscaping features will be planted within the stormwater management blocks; and
- A network of trails has been identified to connect the parkland, open space blocks, and stormwater management blocks. The retained portions of the Significant Woodlots within both the Neighborhood Park and the Woodland Park will include walking trails and other recreational amenities. The trail network and the recreational amenities within the retained portions of the Significant Woodlots are intended to preserve and enhance their recreational and aesthetic values.

The social functions provided by Significant Woodlots C, D, and E primarily relate to their position within a golf course and country club property. Within this context, the woodlots contribute to the general ability of the Site to provide opportunities for recreation (e.g. sporting activities), they provide aesthetic value, and they provide opportunities for passive recreational enjoyment. The Land Use Concept Plan provides significant opportunities for recreational and aesthetic enjoyment of the Site following the redevelopment. Opportunities for recreational and aesthetic enjoyment of the Site are provided by the Neighborhood Park (3.53 ha), the Woodland Park (1.62 ha), the two (2) parkettes (0.4 ha and 0.40 ha), the open space blocks (5.19 ha), the stormwater management blocks (7.31 ha), and the minimum 3 m wide property buffers (1.65 ha). As described above, portions of all



three (3) Significant Woodlots will be retained within the Site. The functions of the Significant Woodlots will be augmented by planting new trees within adjacent areas of the parks and open space blocks that currently lack tree cover.

The combined size of the three (3) Significant Woodlots prior to development is approximately 3.86 ha. Following the redevelopment, the combined size of the three (3) Significant Woodlots is anticipated to be similar (approximately 3.77 ha). As described above, the post development Significant Woodlots will include a combination of retained trees and new tree plantings to augment their features and functions. Significant Woodlot C (1.0 ha pre-development, 1.15 ha post development) and Significant Woodlot E (1.27 ha pre-development, 1.62 ha post development) are anticipated to expand in size. Significant Woodlot D (1.59 ha pre-development, 1.0 ha post development) is anticipated to be reduced in size. Notably, all three (3) Significant Woodlots are anticipated to be ≥ 0.8 ha in size following development, and therefore will continue to qualify as Significant Woodlots under the amended City of Ottawa criteria for the urban area.

In addition, a network of trails has been identified to connect the parkland, open space blocks, and stormwater management blocks. The retained portions of the Significant Woodlots within both the Neighborhood Park and the Woodland Park will include walking trails and other recreational amenities. The trail network and the recreational amenities within the retained portions of the Significant Woodlots are intended to preserve and enhance their recreational and aesthetic values. The tree retention/tree planting within the park and open space blocks, as well as the trail system and recreational amenities, is anticipated to be sufficient to preserve the significant features and functions of the three (3) Significant Woodlots.



The anticipated extent of post development forest cover within the Site is shown below. Following the identification and classification of the forest communities within the Site, the total size of forest within the Site was measured using Geographic Information System (GIS) software. Under existing conditions, the Site features approximately 10.02 ha of forest cover. This includes the three (3) Significant Woodlots, as well as smaller forest stands that do not qualify as Significant Woodlots (discussed above in Section 3.2.4). Similar to the pre-development conditions, the post development forest cover will include the three (3) Significant Woodlots, as well as other smaller forest stands. As described above, post development forest cover within the Site will include both retained forest and newly planted trees. As shown below, the entirety of the open space blocks, the minimum 3 m property buffers, the Woodland Park, and the southern portion of the Neighborhood Park are shown to include forest cover following completion of the redevelopment (this includes newly planted trees in areas that do not currently include forest cover). Taking into account the areas of forest retention and tree planting, the post development forest cover within the Site will be

approximately 7.64 ha. The redevelopment of the Site will hence result in a reduction in the extent of forest cover of approximately 24%. However, as described above, the combined size of the three (3) Significant Woodlots will be similar post development to existing conditions. As such, the overall reduction in forest cover throughout the Site is due primarily to the loss of smaller forest stands. As described above in Section 3.3, the smaller forest stands do not qualify as significant natural heritage features, and therefore their removal is not anticipated to significantly impact the natural features and functions of the Site.



NOTE:
REFER TO FIGURES 3 TO 8 OF THE COMBINED ENVIRONMENTAL
IMPACT STATEMENT AND TREE CONSERVATION REPORT FOR
ECOLOGICAL LAND CLASSIFICATION FOREST COMMUNITY LABELS



LEGEND

-  SIGNIFICANT WOODLOTS
-  OTHER FOREST PATCHES



**EXISTING CONDITIONS
FOREST AND SIGNIFICANT WOODLOTS**

SCALE: 1:3000
DATE: MARCH 2020
DRAWING No. 1



NOTE:
REFER TO FIGURES 3 TO 8 OF THE COMBINED ENVIRONMENTAL
IMPACT STATEMENT AND TREE CONSERVATION REPORT FOR
ECOLOGICAL LAND CLASSIFICATION FOREST COMMUNITY LABELS

THE 3m WIDE LANDSCAPED BUFFERS ARE NOT QUANTIFIED ON
THIS DRAWING DUE TO THE DRAWING SCALE. THE 3m WIDE
LANDSCAPED BUFFERS HAVE A COMBINED AREA OF 1.65 Ha

LEGEND

- FORESTED PORTION OF PARKS
- FORESTED PORTIONS OF OPEN SPACE BLOCKS
- NON-RETAINED PORTIONS OF SIGNIFICANT WOODLOTS
- OTHER NON-RETAINED FOREST PATCHES



**POST DEVELOPMENT CONDITIONS
FOREST AND SIGNIFICANT WOODLOTS**

SCALE: 1:3000
DATE: MARCH 2020
DRAWING No. 2

4.1.2 Tree Preservation Mitigation Measures (TCR)

The following tree mitigation measures should be implemented to help protect and preserve retained trees:

- Wherever feasible, exclude Site grading and excavation activities from designated areas of tree retention;
- Mark the edge of the tree clearing area to ensure only designated trees are removed. Protect the critical root zone (CRZ) of retained trees, where the CRZ is established as being 10 cm from the trunk of a tree for every centimeter of trunk dbh. The CRZ is calculated as dbh x 10 cm;
- When trees to be removed overlap with the CRZ of trees to be retained, cut roots at the edge of the CRZ and grind down stumps after tree removal. Do not pull out stumps. Ensure there is not root pulling or disturbance of the ground within the CRZ;
- If roots must be cut, roots 20 mm or larger should be cut at right angles with clean, sharp horticultural tools without tearing, crushing, or pulling;
- Do not place any material or equipment within the CRZ of any tree;
- Do not attach any signs, notices, or posters to any tree;
- Do not damage the root system, trunk, or branches of any retained tree. Branches that extend into the work area are to be pruned by a qualified arborist before site alteration begins, wherever required in order to avoid damage to the trees; and
- Ensure that exhaust fumes from all equipment are directed away from any tree canopy.

During tree clearing operations, trees will be selectively removed that occur within one tree length of the development and which appear to be hazardous and/or in significant decline. In addition, any trees with a significant lean towards the development will be evaluated to determine if they need to be selectively removed.

4.1.3 Grading Impacts, Transplanting, and Replanting (TCR)

Requirements for tree planting and transplanting include the following:

- In order to mitigate the loss of woody vegetation from Site clearing, individual trees, tree stands, and shrubs will be replanted selectively between lots, at the back and front of lots, and along roadways. The individual trees, tree stands, and shrubs planted between lots, at the back and front of lots, and along roadways will mitigate the loss of the landscaping features that are currently present throughout the Site;
- In addition, there are four (4) new stormwater management blocks, which collectively will occupy approximately 7.31 ha. Tree retention within the stormwater management blocks is not likely to be feasible, due to the required excavation and grade changes. However, it is recommended that tree coverage within the Site should be enhanced by adding new plantings/landscaping features within the stormwater management blocks as part of the Site redevelopment. New plantings within the stormwater management blocks will mitigate the loss of the landscaping features that are currently present throughout the Site;
- New trees will also be planted at the edges of the Neighborhood Park, the Woodland Park, and the open space blocks, both where there is currently insufficient tree coverage, and also in any locations where tree removal is required in order to accommodate grading (discussed above in Section 4.1.1). Ultimately, the southern portion of the Neighborhood Park, the Woodland Park, and the open space blocks are intended to be fully forested following the redevelopment (through a combination of retained and planted trees);
- As described above in Section 4.1.1, the minimum 3 m wide landscaped buffers will provide opportunities for tree retention, and existing trees within the minimum 3 m wide landscaped buffers will be retained wherever feasible. New trees will be planted within the minimum 3 m wide landscaped buffers both where tree removal is required to accommodate grading, and also where there is currently insufficient tree coverage at the edge of the Site. Ultimately, the minimum 3 m wide landscaped buffers are intended to be fully forested following the redevelopment (through a combination of retained and planted trees);
- The planting locations and specific planting requirements will be confirmed by a detailed Landscaping Plan. Plantings should emphasize the use of native trees and shrubs, which may include those identified in Appendix B. Planting of Ash trees should be avoided due to the high likelihood that any planted Ash trees will become infested with Emerald Ash Borer; and
- Where feasible, suitably sized trees will be transplanted from later stages of the redevelopment into the earlier stages, in order to assist with landscaping requirements. In particular, transplanting will emphasize moving trees from the later phases into the stormwater management blocks that are first constructed. During detailed design, trees will be selected for transplanting. Trees selected for transplanting will predominantly include the existing

landscaping features within the Site, which are described above in Section 3.2.2. These may include a mixture of the existing planted Red Pine, White Pine, White Spruce, Sugar Maple, Silver Maple, Honey Locust, Bur Oak and Horse Chestnuts that exist as landscaping features throughout the Site. The existing landscaping features generally vary in size between approximately 10 cm and 40 cm diameter at breast height (dbh).

4.2 Watercourses and Aquatic Habitats

4.2.1 Removal of Stormwater Swales and Ponds

As discussed above in Section 3.4, there are no natural watercourses or wetland habitats within the Site. There are two (2) stormwater management ponds and six (6) stormwater infiltration/conveyance swales within the Site. As described above in Section 3.4, all of the existing stormwater management features are artificial features with little habitat value. All of the existing stormwater management features are fed by outlet pipes from the adjacent subdivisions and/or by surface runoff from the golf course. There is no direct upstream or downstream connection to natural watercourses or wetlands. The existing stormwater management features will be decommissioned during Site redevelopment. Due to their artificial and degraded condition, removal of the existing stormwater management features is not considered a significant impact to the natural features and functions of the Site. It should be noted that the limited ecological functions provided by the existing stormwater management ponds are likely to be replaced (or exceeded) by the installation of four (4) new stormwater management ponds as part of the redevelopment (discussed below). Similar to the existing ponds, the new stormwater management ponds will also be artificially constructed features, and are likely to provide similar ecological functions as the existing ponds.

4.2.2 Servicing and Stormwater Management

Stormwater servicing will be provided by four (4) new stormwater management blocks, which collectively will occupy approximately 7.31 ha. The four (4) new stormwater management blocks account for approximately 10.3% of the surface area of the Site. The new stormwater management ponds are designed to outlet to buried servicing pipes (e.g. existing sewers), which will convey water to the Beaver Pond. The Beaver Pond is located approximately 450 m north of the proposed redevelopment. The Beaver Pond is a licensed inline stormwater management facility, which outlets to the Kizell Drain. The Kizell Drain is a tributary of Watt's Creek. Watt's Creek ultimately flows to Shirley's Bay along the Ottawa River. The Site will also receive municipal sewer and water. The stormwater management and servicing studies will consider Low Impact Development (LID) options, in order to mitigate potential impacts to the water balance of the Site.

4.2.3 Sediment and Erosion Controls

Due to the fact that the existing stormwater management features are scheduled to be decommissioned, sediment and erosion controls are not required to protect these features during redevelopment. However, during construction existing conveyance systems along Knudson Drive, Campeau Drive and other surrounding roads could be exposed to significant sediment loading. Although construction is only a temporary situation, a sediment and erosion control plan will be required to ensure the existing conveyance systems are not negatively impacted by sediment and erosion.

The sediment and erosion control plan will include the following:

- Groundwater in trenches (if present) will be pumped into a filter mechanism, such as a trap made up of geotextile filters and straw, prior to release to the environment;
- Bulkhead barriers will be installed at the nearest downstream manhole in each sewer which connects to an existing downstream sewer (e.g. existing sewers along Knudson Drive, Campeau Drive, and other roads, if required). These bulkheads will trap any sediment carrying flows, thus preventing any construction-related contamination of existing sewers;
- Seepage barriers will be constructed in any temporary drainage ditches;
- Construction vehicles will leave the Site at designated locations. Exits will consist of a bed of granular material, in order to minimize the tracking of mud off-site;
- Any stockpiled material will be properly managed to prevent those materials from entering the sewer systems; and
- Until landscaped areas are sodded or until streets are asphalted and curbed, all catch basins and manholes will be constructed with a geotextile filter sock located between the structure frame and cover.

4.3 Adjacent Lands and Significant Features

As described above in Section 3.5, there is no direct connection between the Site and the Beaver Pond, Kimmins Court Park, Bill Teron Park, and Robert Gray Park. Due to the separation distance between the Site and the adjacent natural heritage features/urban parks, as well as the presence of existing development surrounding the Site, the proposed redevelopment is unlikely to directly impact the Beaver Pond, Kimmins Court Park, Bill Teron Park, and Robert Gray Park.

Walden Park (130 Walden Drive) is located immediately adjacent to the Site (located adjacent to the northwest corner of the Site) (Refer to Figure 1). The trees that occur at the edge of Walden Park adjacent to the Site were investigated on January 10th, 2020, and it was found that the forest at the edge of Walden Park predominantly consists of recent regrowth, with the majority of trees ≤ 25 cm diameter at breast height (dbh) in size. Photograph #118 in Appendix A shows the trees at the edge of Walden Park. The critical root zone of trees is generally accepted to be 10 cm for every centimeter of trunk dbh. Given that the majority of trees at the edge of Walden Park have a dbh of ≤ 25 cm, their critical root zone is ≤ 2.5 m. The proposed minimum 3 m wide landscaped buffer that is shown at the edge of Walden Park is therefore anticipated to be sufficient to protect the critical root zone of the edge trees. Mitigation measures to protect retained trees and trees that occur on properties adjacent to the Site are discussed above in Section 4.1.2.

4.4 Species at Risk and Wildlife

4.4.1 Butternut Tree Regulatory Requirements (TCR)

As discussed above in Section 3.7.3, the rules and regulations of the Ontario Endangered Species Act (ESA) require the completion of a Butternut Health Assessment (BHA) in order to assess the health status of Butternut Trees and subsequent regulatory requirements under the Ontario ESA (OMECP 2019). A BHA was completed in June 2019 (Appendix F). The BHA documented the presence of twenty three (23) Category 2 (retainable) Butternut Trees and eleven (11) Category 3 (archiveable) Butternut Trees within the Site. The rules and regulations of the Ontario ESA establish a 25 m buffer zone surrounding Category 2 and 3 Butternut Trees. Activities that may negatively affect a Butternut Tree are considered an 'impact' to that tree if they take place within 25 m of the tree (OMECP 2019). Butternut habitat is defined as the area within 50 m of a Category 2 or 3 Butternut Tree. It is anticipated that the redevelopment will result in the removal and/or impacts to multiple Category 2 and 3 Butternut Trees, as well as the removal of Butternut habitat. However, it should be noted that the open space block located east of the Neighborhood Park includes seven (7) of the eleven (11) Category 3 trees. As such, the potential exists for up to seven (7) of the Category 3 Butternut Trees to be retained within the open space block located east of the Neighborhood Park. Additional opportunities to retain individual Category 2 Butternut Trees within the Woodland Park and within the open space blocks have been noted.

Due to the anticipated impacts to Butternut Trees and their habitat, it is anticipated that an Overall Benefit Permit under Clause 17(2)(c) of the Ontario ESA will be required to support the redevelopment. The Ontario ESA review and permitting process was initiated in January 2020 through the submission of the Information Gathering Form to the Ontario Ministry of Environment, Conservation, and Parks (OMECP). During the Overall Benefit Permit review and approval process, potential impacts to Butternut Trees and their habitat will be documented in greater detail, and opportunities for retention and/or protection of Butternut Trees will be further investigated. Where feasible, the Category 2 and 3 Butternut Trees that occur within the Woodland Park and the open space blocks will be retained.

4.4.2 Wildlife Construction Stage Mitigation - Terrestrial

Potential impacts to wildlife at the construction stage may include the following:

- Removal of habitat features and displacement of wildlife from existing habitat areas;
- Potential injury or mortality of adults in terrestrial habitats due to vehicle impacts, during excavations, or during land clearing; and
- Interruption of movement to essential foraging, breeding, or overwintering areas due to site hoarding or sediment and erosion control fencing.

Mitigation for Species at Risk (SAR) and wildlife during construction is summarized here. These recommendations include provisions from the City of Ottawa (2015) *Protocol for Wildlife Protection During Construction*:

- **Pre-Stressing:** Prior to vegetation removal, the area should be pre-stressed by traversing the Site with a loud noise such as an excavator horn. This will encourage wildlife to leave the area;
- **Tree Clearing Direction:** Trees should be cleared towards the retained open space blocks and/or areas of tree retention within the park blocks, in order to provide an opportunity for wildlife to leave the work area;
- **Temporary Exclusion Fencing:** Due to the absence of wetland and/or watercourse features, temporary wildlife exclusion fencing at the construction stage should not be required. Following decommissioning of the stormwater management ponds (discussed below), the risk of frogs and other wildlife entering the Site is anticipated to be negligible;
- **Sweeps:** Prior to vegetation clearing, preconstruction sweeps of vegetated areas will be undertaken by a designated staff member. A designated staff member will be required to conduct daily sweeps each morning prior to the commencement of work to ensure that wildlife have not entered the work area;
- **Vehicle Operation:** Vehicles and equipment are to be operated on Construction Travelways (e.g. roads within the Site) at a speed at which drivers are able to identify wildlife and stop safely to avoid collisions with wildlife;
- **Species at Risk Encounters:** If Species at Risk (SAR) are encountered in the work area, construction in the vicinity must be stopped immediately and measures must be taken to ensure the SAR is not harmed. The project biologist and the Ontario Ministry of Environment, Conservation, and Parks (OMECP) must be contacted to discuss how to proceed prior to the recommencement of work;
- **General Provisions:** General provisions for Site management include the following:
 - Do not harm, feed, or unnecessarily harass wildlife;
 - Drive slowly and avoid hitting wildlife;

- Keep the Site tidy and free of garbage and food wastes. Secure all garbage in appropriate sealed containers;
- Ensure proper Site drainage so that standing water does not accumulate on Site. This will reduce the likelihood that wildlife may enter the Site;
- Any stockpiles should be properly secured with silt fencing to prevent wildlife from accessing areas of loose fill; and
- **Timing Windows:** The core migratory bird nesting season is defined as April 15th to August 15th each year. Initial vegetation clearing should be undertaken outside of this period. If tree clearing must occur during the core migratory bird nesting season, the tree clearing area must first be surveyed by a Qualified Biologist, in order to verify the absence of nesting migratory birds.

4.4.3 Wildlife Construction Stage Mitigation - Aquatic

In addition to those mitigation measures outlined above, the following requirements apply during the dewatering and decommissioning of the two (2) stormwater management ponds and any of the stormwater management swales that are hydrated at the time of decommissioning:

- **Dewatering:** All dewatering operations must be supervised by a Qualified Biologist, who must be present during dewatering to relocate fish and other wildlife. Full time supervision by a Qualified Biologist is necessary during initial water draw down;
- **Permits:** Prior to the decommissioning of the existing stormwater management features, a *Wildlife Scientific Collector's Authorization* and *License to Collect Fish for Scientific Purposes* must be obtained from the Ontario Ministry of Natural Resources and Forestry (OMNRF). Relocation sites and detailed fish and wildlife salvage procedures will be identified during the fish and wildlife relocation permit application process;
- **Fish and Wildlife Salvage:** A salvage plan must be in place that will allow for relocation of any fish and other wildlife found within dewatering work areas. In accordance with the dewatering arrangement, the water level in any dewatering work areas must be drawn down to permit the safe removal of fish and wildlife. All removal activities will be undertaken before the area is completely dry, in order to avoid aquatic animals being exposed to dry conditions. During water draw down, a mesh net will be in place around any dewatering pumps to ensure that fish will not become entangled in the pumps; and
- **Timing Windows:** The stormwater management ponds and stormwater management swales are not directly connected to any adjacent natural watercourses and/or wetlands. Therefore, timing windows for sensitive in-water work should not apply to the decommissioning of the stormwater management features.

5.0 CUMULATIVE EFFECTS

Cumulative effects were considered in the design of the mitigation measures outlined in Section 4.0. As described above, the redevelopment of the Site is not anticipated to significantly contribute to the cumulative loss of wetland and/or significant wildlife habitat. The Site is within the Ottawa West Minor Watershed, which has approximately 38% forest cover (City of Ottawa 2011). The Ottawa West Minor Watershed is approximately 31,700 ha in size with approximately 12,046 ha of forest cover (38%) (City of Ottawa 2011). Forest cover within the Site occurs in relatively small and fragmented patches, the largest of which is approximately 1.59 ha in size. As described above in Section 4.1.1, the pre-development forest cover within the Site is approximately 10.02 ha. The post development forest cover within the Site is anticipated to be approximately 7.64 ha (this includes both retained trees and newly planted trees). The anticipated loss of forest cover that will result from the redevelopment is approximately 2.38 ha (24%). Given that the Ottawa West Minor Watershed has approximately 12,046 ha of forest, the loss of 2.38 ha of forest cover associated with the redevelopment will not contribute significantly to the cumulative loss of forest in the region. The potential for the Site redevelopment to contribute to the cumulative loss of local forest cover is addressed by the tree retention, tree planting, and mitigation measures described above in Section 4.1.

The only Species at Risk (SAR) documented within the Site are Butternut Trees. As described above in Section 4.4.1, it is anticipated that an Overall Benefit Permit under Clause 17(2)(c) of the Ontario Endangered Species Act (ESA) will be required to support the redevelopment. The Ontario ESA Overall Benefit Permit process requires that proponents either mitigate all impacts to a species, or that they provide an overall benefit to the species, both of which imply no net loss of habitat functionality. Measures to compensate for impacts to Butternut Trees and their habitat are anticipated to be required to fulfill the requirements of the Overall Benefit Permit process. The Ontario ESA review and permitting process was initiated in January 2020 through the submission of the Information Gathering Form to the Ontario Ministry of Environment, Conservation, and Parks (OMECIP). Compensation requirements will be determined in consultation with the OMECIP as part of the Overall Benefit Permit process.

6.0 MONITORING

Construction stage monitoring requirements are outlined in Section 4.4.2 and 4.4.3 (above). Construction stage monitoring will include pre-construction sweeps to inspect vegetation prior to clearing, daily sweeps by construction staff, and full-time supervision by a Qualified Biologist during dewatering.


Monitoring requirements related to Butternut Trees will be determined in consultation with the Ontario Ministry of Environment, Conservation, and Parks (OMEC) as part of the Ontario Endangered Species Act Overall Benefit Permit review and approval process.

7.0 CLOSURE

Provided that the regulatory, mitigation, and avoidance measures outlined in this report are implemented appropriately, the redevelopment of the Site is not anticipated to have a significant negative effect on the natural features and functions.

We trust that the above information is sufficient; should you have any questions or require further information, please do not hesitate to contact the undersigned, at your convenience.

Sincerely,



Dr. Andrew McKinley, EP, RP Bio.
Senior Biologist, McKinley Environmental Solutions

A handwritten signature in black ink that reads "Bernie Muncaster".

Bernie Muncaster, M. Sc.
Principal, Muncaster Environmental Planning Inc.

8.0 REFERENCES

Please note: The Ontario Ministry of Natural Resources and Forestry (OMNRF) has recently transitioned responsibility for the Ontario Endangered Species Act to the Ontario Ministry of Environment, Conservation and Parks (OMECP). References which continued to be published at the time of report preparation with the OMNRF listed as the author, are attributed to the OMNRF throughout this report. Websites and other references that have recently been relabeled to reference OMECP as the author are instead attributed to OMECP throughout this report.

City of Ottawa (2009) Results of the National Capital Air Quality Mapping Pilot Project.

City of Ottawa (2011) Characterization of Ottawa's Watersheds: An Environmental Foundation Document with Supporting Information Base.

City of Ottawa (2014) Natural Heritage System Overlay (West). Official Plan Schedule L3.

City of Ottawa (2015) Protocol for Wildlife Protection During Construction.

City of Ottawa (2019a) Geo-Ottawa Municipal Mapping Site. <<http://maps.ottawa.ca/geottawa/>> (Accessed January 4th, 2019)

City of Ottawa (2019b) Significant Woodlands: Guidelines for Identification, Evaluation, and Impact Assessment.

Fisheries and Oceans Canada (FOC) (2019) Project Activities and Waterbodies Where Review Isn't Required. <<http://www.dfo-mpo.gc.ca/pnw-ppe/activities-activites-eng.html>> (Accessed January 4th, 2019).

Garlapow, R.M. (2007) Whip-poor-will Prey Availability and Foraging Habitat: Implications for Management in Pitch Pine / Scrub Oak Barrens Habitats. Master Dissertation, Univ. of Massachusetts, Amherst, Massachusetts.

Konze, K. and McLaren, M. (1998) Wildlife Monitoring Programs and Inventory Techniques for Ontario. NEST Technical Manual TM-009.

Lee, Harold (2008) Southern Ecological Land Classification Ecosystem Catalogue (2008 version).

Natural Resources Canada (NRCAN) (2019) Earth Observation Data Management System. <https://www.eodms-sgdot.nrcan-rncan.gc.ca/index_en.jsp> (Accessed July 20th, 2019).

Ontario Ministry of Environment, Conservation and Parks (OMECOP) (2019) Butternut Trees On Your Property. <<https://www.ontario.ca/page/butternut-trees-your-property>> (Accessed January 4th, 2019).

Ontario Ministry of Natural Resources and Forestry (OMNRF) (1998) Ecological Land Classification for Southern Ontario: First Approximation and its Applications.

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2010) OMNRF Natural Heritage Reference Manual for Natural Heritage Policies of the Provincial Policy Statement, 2005, Second Edition.

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2011a) Survey Methodology under the Endangered Species Act: *Dolichonyx oryzivorus* (Bobolink).

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2011b) Bats and Bat Habitats: Guidelines for Wind Power Projects.

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2013) Occurrence Survey Protocol for Blanding's Turtle in Ontario.

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2014a) General Habitat Description for Blanding's Turtle.

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2014b) Significant Wildlife Habitat Mitigation Support Tool.

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2014c) General Habitat Description for Bobolink.

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2014d) General Habitat Description for Eastern Meadowlark.

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2014e) General Habitat Description for the Eastern Whip Poor Will.

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2014f) Draft Survey Protocol for Eastern Whip Poor Will.

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2014g) Ontario Wetland Evaluation System – Southern Manual (3rd Edition, Version 3.3).

Ontario Ministry of Natural Resources and Forestry (OMNRF) (2019) Natural Heritage Information Center. <http://www.gisapplication.lrc.gov.on.ca/mamnh/Index.html?site=MNR_NHLUPS_NaturalHeritage&viewer=NaturalHeritage&locale=en-US> (Accessed January 4th, 2019).

Paterson Group (2019) Geotechnical Investigation – Proposed Residential Development, Kanata Lakes Golf and Country Club, 7000 Campeau Drive, Ottawa, Ontario. Report Number PG4135-2.

Species at Risk Ontario (SARO) (2020) Species at Risk Ontario. <<http://www.ontario.ca/environment-and-energy/species-risk-ontario-list>> (Accessed March 4th, 2020).

APPENDIX A

Site Photographs

Golf Course (Refer to Section 3.2.1)



Photograph 1: The golf course within Section 1 (May 24th, 2018).



Photograph 2: The golf course within Section 6 (May 24th, 2018).

Landscaping Features (Refer to Section 3.2.2)



Photograph 3: Example of typical tree plantings within Section 1. Plantings of small groups of trees and individual trees are present throughout the Site (June 2nd, 2018).

Tree Stands and Large Trees (Refer to Section 3.2.3)



Photograph 4: Feature #2 is a 57 cm dbh Bur Oak (June 2nd, 2018).



Photograph 5: Feature #3 is a stand of Norway Spruce and White Spruce which are between approximately 10 cm to 25 cm dbh in size (June 2nd, 2018).



Photograph 6: Feature #4 is a stand of Manitoba Maples with a dbh between approximately 10 cm to 40 cm. The stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 7: Feature #5 is a stand of White Spruce, Norway Spruce, Sugar Maple and White Pine which are between approximately 10 cm and 25 cm dbh (June 2nd, 2018).



Photograph 8: Feature #6 includes a 48 cm and a 47 cm dbh Bitternut Hickory, which are overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 9: Feature #7 includes a 54 cm and a 71 cm dbh Bur Oak (June 2nd, 2018).



Photograph 10: Feature #8 is a 57 cm dbh Bur Oak (far left) (June 2nd, 2018).



Photograph 11: Feature #9 is a stand of Trembling Aspen up to 20 cm dbh, which is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 12: Feature #10 is a row of approximately twenty (20) White Pine, which vary between approximately 30 cm to 50 cm dbh (June 2nd, 2018).



Photograph 13: Feature #11 includes a 48 cm and a 64 cm dbh Bur Oak (June 2nd, 2018).



Photograph 14: Feature #12 is a stand of Ironwood and Bur Oak growing around a bedrock outcrop. Trees within the stand vary between approximately 10 cm and 30 cm dbh (June 2nd, 2018).



Photograph 15: Feature #13 is a Weeping Willow with a dbh of over 1 m (June 2nd, 2018).



Photograph 16: Feature #14 is a Deciduous Shrub Thicket dominated by Staghorn Sumac (June 2nd, 2018).



Photograph 17: Feature #15 is an 84 cm dbh Bur Oak (June 2nd, 2018).



Photograph 18: Feature #16 is a 96 cm dbh Bur Oak (June 2nd, 2018).



Photograph 19: Feature #17 is a stand of Norway Spruce and Silver Maple, which vary between approximately 10 cm and 30 cm dbh (June 2nd, 2018).



Photograph 20: Feature #18 is a stand of approximately twenty (20) White Pine, which vary between approximately 30 cm and 71 cm dbh. The base of the trees is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 21: Feature #19 is a stand of White Spruce, Norway Spruce, and Bur Oak which vary between approximately 10 cm and 30 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 22: Feature #20 is an 84 cm dbh Bur Oak (June 2nd, 2018).



Photograph 23: Feature #21 is a stand of White Cedar that vary between approximately 10 cm and 20 cm dbh (June 2nd, 2018).



Photograph 24: Feature #22 includes approximately seven (7) White Pine and four (4) White Spruce. One (1) White Spruce is 54 cm dbh in size, whereas the other trees vary between approximately 10 cm and 30 cm dbh (June 2nd, 2018).



Photograph 25: Feature #23 is a stand of approximately eight (8) White Pine and two (2) Red Pine that vary between approximately 40 cm and 60 cm dbh (June 2nd, 2018).



Photograph 26: Feature #24 is a mixed stand of Basswood, White Spruce, Manitoba Maple, American Elm and Black Cherry, with stems varying between approximately 10 cm and 30 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 27: Feature #25 is a Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 28: Feature #26 is a 57 cm dbh American Elm (June 2nd, 2018).



Photograph 29: Feature #27 is a stand of Basswood, Bur Oak, and Sugar Maple which vary between approximately 10 cm and 25 cm dbh (June 2nd, 2018).



Photograph 30: Feature #28 is a 97 cm dbh Bur Oak (June 2nd, 2018).



Photograph 31: Feature #29 is a 74 cm dbh Sugar Maple (June 2nd, 2018).



Photograph 32: Feature #30 is a 56 cm dbh American Elm (June 2nd, 2018).



Photograph 33: Feature #31 includes a 47 cm dbh Sugar Maple and a 65 cm dbh Basswood (June 2nd, 2018).



Photograph 34: Feature #32 is a 102 cm dbh Silver Maple (June 2nd, 2018).



Photograph 35: Feature #33 includes a 50 cm and a 48 cm dbh Honey Locust (June 2nd, 2018).



Photograph 36: Feature #34 includes a line of Basswood which are between approximately 40 cm and 60 cm dbh in size. The tree stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 37: Feature #35 is a stand of Manitoba Maple up to 20 cm dbh in size, which is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 38: Feature #36 includes a 53 cm, 48 cm and 54 cm dbh White Pine, and White Cedars between approximately 10 cm and 20 cm dbh (June 2nd, 2018).



Photograph 39: Feature #37 is a stand of White Spruce and White Pine between approximately 30 cm and 40 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 40: Feature #38 is a dying 68 cm dbh White Ash (June 2nd, 2018).



Photograph 41: Feature #39 is a stand of dead White Ash between approximately 10 cm and 20 cm dbh (June 2nd, 2018).



Photograph 42: Feature #40 includes six (6) Red Pine and five (5) White Pine between approximately 20 cm and 40 cm dbh (June 2nd, 2018).



Photograph 43: Feature #41 is an 84 cm dbh Bitternut Hickory (June 2nd, 2018).



Photograph 44: Feature #42 is a stand of White Pine between approximately 40 cm and 60 cm dbh (June 2nd, 2018).



Photograph 45: Feature #43 is a stand of Trembling Aspen and dead/dying White Ash between approximately 10 cm and 30 cm dbh. Sugar Maple and American Elm are also present. The stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 46: Feature #44 is a stand of Sugar Maple and Domestic Apple with a dbh between approximately 10 cm and 20 cm (June 2nd, 2018).



Photograph 47: Feature #45 is a stand of Red Pine and White Pine with a dbh between approximately 10 cm and 30 cm (June 2nd, 2018).



Photograph 48: Feature #46 is a stand of White Pine and Sugar Maple between approximately 30 cm and 60 cm dbh (June 2nd, 2018).



Photograph 49: Feature #47 is a stand of Trembling Aspen, Sugar Maple, American Elm, White Ash, and Basswood between approximately 10 cm and 25 cm dbh (June 2nd, 2018).



Photograph 50: Feature #48 is a stand of White Pine and Sugar Maple between approximately 40 cm and 60 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 51: Feature #49 is a 76 cm dbh American Elm (June 2nd, 2018).



Photograph 52: Feature #51 is a 76 cm dbh White Pine (June 2nd, 2018).



Photograph 53: Feature #52 is a 79 cm dbh Sugar Maple (June 2nd, 2018).



Photograph 54: Feature #53 is a stand of Red Pine and White Spruce between approximately 20 cm and 30 cm dbh (June 2nd, 2018).



Photograph 55: Feature #54 is a 63 cm dbh Silver Maple (June 2nd, 2018).



Photograph 56: Feature #55 is a stand of White Pines between approximately 40 cm and 60 cm dbh. The base of the trees is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 57: Feature #56 is a stand of Ironwood, White Ash, and Sugar Maple between approximately 10 cm and 30 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 58: Feature #57 includes a 94 cm and 76 cm dbh Bur Oak (June 2nd, 2018).



Photograph 59: Feature #58 is a 77 cm dbh Bur Oak (June 2nd, 2018).



Photograph 60: Feature #59 is a stand of Red Oak, Sugar Maple, Basswood, and White Ash between approximately 10 cm and 45 cm dbh (June 2nd, 2018).



Photograph 61: Feature #60 is a stand of Red Pines between approximately 10 cm and 20 cm dbh (June 2nd, 2018).



Photograph 62: Feature #61 is a stand of Sugar Maples between approximately 20 cm and 40 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 63: Feature #62 includes White Pine, Red Pine, Norway Spruce, and White Spruce between approximately 20 cm and 40 cm dbh, which are planted along the edge of the golf course at the property boundary (June 2nd, 2018).



Photograph 64: Feature #63 is a 92 cm dbh Sugar Maple (left) (June 2nd, 2018).



Photograph 65: Feature #64 includes a stand of White Pines less than 20 cm dbh (June 2nd, 2018).



Photograph 66: Feature #65 is a Sugar Maple with a dbh of over 1 m (June 2nd, 2018).



Photograph 67: Feature #66 is a row of large Sugar Maple and Red Oak, which are between approximately 40 cm and 60 cm dbh in size (June 2nd, 2018).



Photograph 68: Feature #67 is a stand of Sugar Maples approximately 20 cm to 40 cm dbh in size. One (1) large Sugar Maple has a dbh of over 1 m (June 2nd, 2018).



Photograph 69: Feature #68 includes a 94 cm and a 73 cm dbh Sugar Maple (June 2nd, 2018).



Photograph 70: Feature #69 includes a 46 cm and 52 cm Bur Oak and an 85 cm dbh Red Oak (background, center) (June 2nd, 2018).



Photograph 71: Feature #70 is a stand of Red Pine, White Pine, Norway Spruce and White Spruce planted along the edge of the golf course at the property boundary. Trees vary between approximately 20 cm and 30 cm dbh (June 2nd, 2018).



Photograph 72: Feature #71 is a stand of Trembling Aspen, White Birch, Sugar Maple, White Spruce, American Elm and dead White Ash growing along the edge of the golf course at the property boundary. Trees vary between approximately 10 cm and 40 cm dbh (June 13th, 2018).



Photograph 73: Feature #72 includes a 72 cm dbh Sugar Maple and a Sugar Maple with a dbh of over 1 m (June 2nd, 2018).



Photograph 74: Feature #73 is a stand of White Spruce between approximately 40 cm and 60 cm dbh (June 2nd, 2018).



Photograph 75: Feature #74 includes several stands of White Spruce, Norway Spruce, Red Pine and White Pine, which are planted in several locations within the golf course and along the property line in the northern part of Section #5. Trees vary between approximately 20 cm and 60 cm dbh (June 2nd, 2018).



Photograph 76: Feature #75 includes three (3) Sugar Maples, each of which have a dbh of over 1 m (June 2nd, 2018).



Photograph 77: Feature #77 is a Sugar Maple with a dbh of over 1 m (June 2nd, 2018).



Photograph 78: Feature #78 includes a 68 cm and a 90 cm dbh Bur Oak (June 2nd, 2018).



Photograph 79: Feature #79 includes a 76 cm Bur Oak, a Bur Oak with a dbh of over 1 m, two (2) Silver Maples with a dbh of over 1 m, and two (2) Silver Maples with multiple stems measuring 71 cm, 38 cm, 37 cm, 35 cm, and 43 cm dbh (June 2nd, 2018).



Photograph 80: Feature #80 includes a stand of Sugar Maples between approximately 10 cm and 40 cm dbh in size. An 84 cm dbh Sugar Maple is present within the stand (center) (June 2nd, 2018).



Photograph 81: Feature #81 is a stand of Sugar Maples, White Cedar, and White Spruce between approximately 20 cm and 40 cm dbh (June 2nd, 2018).



Photograph 82: Feature #83 includes a 71 cm dbh Silver Maple and a Silver Maple with a dbh of over 1 m (June 2nd, 2018).



Photograph 83: Feature #84 includes several stands of planted White Spruce, Norway Spruce, Sugar Maple, Red Pine, White Pine, Scots Pine, and White Cedar between approximately 20 cm and 60 cm dbh. The tree stands are planted in several clusters around the golf course in Section #6 (June 2nd, 2018).



Photograph 84: Feature #84 includes several stands of planted White Spruce, Norway Spruce, Sugar Maple, Red Pine, White Pine, Scots Pine, and White Cedar between approximately 20 cm and 60 cm dbh. The tree stands are planted in several clusters around the golf course in Section #6 (June 2nd, 2018).



Photograph 85: Feature #85 is a stand of White Spruce and White Pine between approximately 20 cm and 40 cm dbh (June 2nd, 2018).



Photograph 86: Feature #86 includes a stand of young Bur Oak, Trembling Aspen, Basswood and White Ash between approximately 10 cm and 30 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 87: Feature #87 includes a stand of White Cedar, Trembling Aspen, Ironwood, American Elm and Staghorn Sumac between approximately 10 cm and 40 cm dbh. The stand is overgrown with Deciduous Shrub Thicket (June 2nd, 2018).



Photograph 88: Feature #88 is a stand of White Spruce and White Pine planted adjacent to the parking lot. Trees vary in size between approximately 20 cm and 40 cm dbh (June 2nd, 2018).



Photograph 89: Feature #89 includes a row of planted Silver Maples adjacent to the parking lot. Trees vary in size between approximately 20 cm and 40 cm dbh (June 2nd, 2018).



Photograph 90: Feature #90 includes Silver Maples, Sugar Maples, White Pine, Norway Spruce and White Spruce planted around the clubhouse. Trees vary in size between approximately 20 cm and 40 cm dbh (June 2nd, 2018).



Photograph 91: Feature #93 includes three (3) large Bur Oaks and three (3) large Sugar Maples, each between approximately 60 cm and 90 cm dbh (June 2nd, 2018).



Photograph 92: Feature #94 is a 76 cm dbh Basswood (June 13th, 2018).

Forest and Thicket Communities (Refer to Section 3.2.4)



Photograph 93: Dry-Fresh Sugar Maple – Basswood Deciduous Forest (Community A) within Section #1 (June 2nd, 2018).



Photograph 94: Dry-Fresh Sugar Maple – Basswood Deciduous Forest (Community A) within Section #1 (June 2nd, 2018).



Photograph 95: Dry-Fresh Sugar Maple – Basswood Deciduous Forest (Community A) within Section #3 (June 2nd, 2018).



Photograph 96: Dry-Fresh Sugar Maple – Basswood Deciduous Forest (Community A) within Section #5 (June 2nd, 2018).



Photograph 97: Deciduous Shrub Thicket (Community B) within Section #3 (June 2nd, 2018).



Photograph 98: Deciduous Shrub Thicket (Community B) within Section #6 (June 2nd, 2018).



Photograph 99: Fresh-Moist Poplar Deciduous Forest (Community C) within Section #1 (June 2nd, 2018).



Photograph 100: Dry-Fresh Sugar Maple – Black Cherry Deciduous Forest (Community D) within Section #2 (June 2nd, 2018).



Photograph 101: Dry-Fresh Sugar Maple – Ironwood Deciduous Forest (Community E) within Section #3 (June 2nd, 2018).



Photograph 102: Dry-Fresh Sugar Maple – Ironwood Deciduous Forest (Community E) within Section #3 (June 2nd, 2018).



Photograph 103: Dry-Fresh Sugar Maple – Ironwood Deciduous Forest (Community E) within Section #3 (September 17th, 2018).



Photograph 104: Fresh-Moist White Spruce – Hardwood Mixed Forest (Community F) within Section #5 (June 13th, 2018).



Photograph 105: Dry-Fresh White Ash – Hardwood Deciduous Forest (Community G) within Section #5 (June 13th, 2018).



Photograph 106: Silver Maple Mineral Deciduous Swamp (Community H) within Section #5 (June 13th, 2018).



Photograph 107: Silver Maple Mineral Deciduous Swamp (Community H) within Section #5 (September 17th, 2018).

Stormwater Infiltration Swales (Refer to Section 3.4.1)



Photograph 108: Stormwater Infiltration Swale within Section #5. The Stormwater Infiltration Swale is fed by a pipe from the adjacent subdivision, and the swale outlets to the Northern Stormwater Management Pond (May 24th, 2018).



Photograph 109: Pipe from the adjacent subdivision that feeds water into the Stormwater Infiltration Swale within Section #5 (May 24th, 2018).



Photograph 110: Stormwater Infiltration Swale within Section #6, located north of the clubhouse. The Stormwater Infiltration Swale is fed by a pipe from the adjacent subdivision. The Section #6 Stormwater Infiltration Swale has no outlet, and standing water infiltrates/evaporates (May 24th, 2018).



Photograph 111: Pipe from the adjacent subdivision that feeds water into the Stormwater Infiltration Swale within Section #6 (located north of the clubhouse) (May 24th, 2018).



Photograph 112: Dry Stormwater Infiltration Swale within the southern part of Section #3 – no surface water observed (May 24th, 2018).



Photograph 113: Dry Stormwater Infiltration Swale within the northern part of Section #3 – no surface water observed (September 17th, 2018).

Stormwater Ponds (Refer to Section 3.4.2)



Photograph 114: Looking east across the Southern Stormwater Pond (April 30th, 2018).



Photograph 115: Looking east across the Southern Stormwater Pond (September 17th, 2018).



Photograph 116: Looking east across the Northern Stormwater Pond (May 8th, 2018).



Photograph 117: Looking west across the Northern Stormwater Pond (June 13th, 2018).

Adjacent Lands and Significant Features (Refer to Section 3.5)



Photograph 118: Looking northwest from the Site boundary at the edge of Walden Park. Note that the edge trees within Walden Park predominantly consist of recent regrowth (up to 25 cm dbh) (January 10th, 2020).

Wildlife and Significant Wildlife Habitat (Refer to Section 3.6)



Photograph 119: American Bullfrog observed within the Southern Stormwater Pond (May 24th, 2018).



Photograph 120: Green Frog observed within the Northern Stormwater Pond (June 2nd, 2018).

Butternut Trees (Refer to Section 3.7.3)



Photograph 121: Example of a 67 cm dbh Butternut (Feature #1) found within the Site (May 24th, 2018)

Bat Species at Risk – Cavity Trees (Refer to Section 3.7.4)



Photograph 122: Cavity Tree #1 (dead Sugar Maple) (January 10th, 2020).



Photograph 123: Cavity Tree #2 (dead Sugar Maple) (January 10th, 2020).



Photograph 124: Cavity Tree #3 (double stem Sugar Maple) (January 10th, 2020).



Photograph 125: Cavity Tree #4 (Butternut #23) (January 10th, 2020).



Photograph 126: Cavity Tree #5 (Bitternut Hickory – Feature #41) (January 10th, 2020).



Photograph 127: Cavity Tree #6 (dead Sugar Maple) (January 10th, 2020).



Photograph 128: Cavity Tree #7 (Sugar Maple) (January 10th, 2020).



Photograph 129: Cavity Tree #8 (dead White Ash) (January 10th, 2020).



Photograph 130: Cavity Tree #9 (Sugar Maple) (January 10th, 2020).



Photograph 131: Cavity Tree #10 (Sugar Maple) (January 10th, 2020).



Photograph 132: Cavity Tree #11 (Red Oak - Feature #66) (January 10th, 2020).



Photograph 133: Cavity Tree #12 (Sugar Maple) (January 10th, 2020).



Photograph 134: Cavity Tree #13 (Sugar Maple – Feature #63) (January 10th, 2020).



Photograph 135: Cavity Tree #14 (Basswood) (January 10th, 2020).



Photograph 136: Cavity Tree #15 (Sugar Maple) (January 10th, 2020).



Photograph 137: Cavity Tree #16 (Butternut) (January 10th, 2020).



Photograph 138: Cavity Tree #17 (Basswood) (January 10th, 2020).



Photograph 139: Cavity Tree #18 (Sugar Maple) (January 10th, 2020).



Photograph 140: Cavity Tree #19 (Sugar Maple – Feature #82) (January 10th, 2020).



Photograph 141: Cavity Tree #20 (Silver Maple) (January 10th, 2020).

Additional Species at Risk (Refer to Section 3.7.5)



Photograph 142: Looking east at Building #1. The garage door is closed on a nightly basis. No significant exterior openings were noted (January 10th, 2020).



Photograph 143: Looking west at Building #1. No significant exterior openings were noted (January 10th, 2020).



Photograph 144: Looking north at Building #2. The garage door is closed on a nightly basis. No significant exterior openings were noted (May 24th, 2018).



Photograph 145: Looking southwest at Building #3. No significant exterior openings were noted (January 10th, 2020).



Photograph 146: Looking south at Building #3. No significant exterior openings were noted (January 10th, 2020).



Photograph 147: Looking west at Building #4. No significant exterior openings were noted (May 24th, 2018).

APPENDIX B

Master Plant List



McKINLEY ENVIRONMENTAL SOLUTIONS

613-620-2255

mckinleyenvironmental@gmail.com

www.mckinleyenvironmental.com

TABLE A: VEGETATION

Common Name	Scientific Name	Provincial S rank	Brunton Significance Ranking for the City of Ottawa (Brunton, 2005)	Vegetation Type
Yellow Iris	<i>Iris pseudacorus</i>	SNA	Rare (Planted)	Aquatic
Narrowleaf Cattail	<i>Typha angustifolia</i>	SNA	Common	Aquatic
Common Cattail	<i>Typha latifolia</i>	S5	Common	Aquatic
Lady Fern	<i>Athyrium filix-femina</i>	S5	Common	Fern
Spinulose Wood Fern	<i>Dryopteris carthusiana</i>	S5	Common	Fern
Sensitive Fern	<i>Onoclea sensibilis</i>	S5	Common	Fern
Bracken fern	<i>Pteridium aquilinum</i>	S5	Common	Fern
Brome Grass	<i>Bromus sp.</i>		n/a	Grass
Reed Canary Grass	<i>Phalaris arundinacea</i>	SE5	Common (locally abundant introduction)	Grass
Timothy	<i>Phleum pratense</i>	SNA	Common	Grass
Downy Yellow Violet	<i>Viola pubescens</i>	S5	Common	Herbaceous
White Baneberry	<i>Actaea pachypoda</i>	S5	Common	Herbaceous
Garlic-mustard	<i>Alliaria petiolata</i>	SNA	Common	Herbaceous
Common Ragweed	<i>Ambrosia artemisiifolia</i>	S5	Common	Herbaceous
Canada Anemone	<i>Anemone canadensis</i>	S5	Common	Herbaceous
Wild Sarsaparilla	<i>Aralia nudicaulis</i>	S5	Common	Herbaceous
Common Burdock	<i>Arctium minus</i>	SNA	Common	Herbaceous
Jack in the Pulpit	<i>Arisaema triphyllum</i>	S5	Common	Herbaceous
Common Milkweed	<i>Asclepias syriaca</i>	S5	Common	Herbaceous
Yellow Rocket	<i>Barbarea vulgaris</i>	SNA	Common	Herbaceous
Canada Thistle	<i>Cirsium arvense</i>	S5	Common	Herbaceous
Bull Thistle	<i>Cirsium vulgare</i>	SNA	Common	Herbaceous
Queen Anne's Lace	<i>Daucus carota</i>	SNA	Common	Herbaceous
Philadelphia Fleabane	<i>Erigeron philadelphicus</i>	S5	Common	Herbaceous
Trout Lily	<i>Erythronium americanum</i>	S5	Common	Herbaceous
Common Strawberry	<i>Fragaria virginiana</i>	S5	Common	Herbaceous
Day Lily	<i>Hemerocallis fulva</i>	SNA	Common	Herbaceous
Spotted Touch Me Not	<i>Impatiens capensis</i>	S5	Common	Herbaceous

Ox-eye Daisy	Leucanthemum vulgare	SNA	Common	Herbaceous
Purple Loosestrife	Lythrum salicaria	SNA	Common (invasive)	Herbaceous
False Solomon's Seal	Maianthemum racemosum	S5	Common	Herbaceous
Woolly Sweet Cicely	Osmorhiza claytoni	S5	Common	Herbaceous
Wild Parsnip	Pastinaca sativa	SNA	Common	Herbaceous
Common Plantain	Plantago major	S5	Common	Herbaceous
Common Buttercup	Ranunculus acris	SNA	Common	Herbaceous
Canada Goldenrod	Solidago canadensis	S5	Common	Herbaceous
New England Aster	Symphotrichum novae-angliae	S5	Common	Herbaceous
Small White Aster	Symphotrichum sp.	S5	n/a	Herbaceous
Dandelion	Taraxacum officinale	SNA	Common	Herbaceous
Red Clover	Trifolium pratense	SNA	Common	Herbaceous
White Clover	Trifolium repens	SNA	Common	Herbaceous
White Trillium	Trillium grandiflorum	S5	Common	Herbaceous
Common Mullein	Verbascum thapsus	SNA	Common	Herbaceous
Tufted Vetch	Vicia Cracca	SNA	Common	Herbaceous
Common Blue Violet	Viola sororia	S5	Common	Herbaceous
Alternate Leaved Dogwood	Cornus alternifolia	S5	Common	Shrub
Red Osier Dogwood	Cornus sericea (stolonifesa)	S5	Common	Shrub
Glossy Buckthorn	Frangula alnus	SNA	Common (aggressive invasive)	Shrub
Tartarian honeysuckle	Lonicera tatarica	SNA	Common (aggressive invasive)	Shrub
Choke Cherry	Prunus virginiana	S5	Common	Shrub
Common Buckthorn	Rhamnus cathartica	SNA	Common (aggressive invasive)	Shrub
Prickly Gooseberry	Ribes cynosbati	S5	Common	Shrub
Skunk Currant	Ribes glandulosum	S5	Common	Shrub
Wild Red Raspberry	Rubus idaeus	S5	Common	Shrub
Purple Flowering Raspberry	Rubus odoratus	S5	Common	Shrub
Lilac	Syringa vulgaris	SNA	Common	Shrub
Manitoba Maple	Acer negundo	S5	Common	Tree
Red Maple	Acer rubrum	S5	Common	Tree
Silver Maple	Acer saccharinum	S5	Common	Tree
Sugar Maple	Acer saccharum	S5	Common	Tree

Horse Chestnut	Aesculus hippocastanum	SNA	Rare (Planted)	Tree
White Birch	Betula papyrifera	S5	Common	Tree
Bitternut Hickory	Carya cordiformis	S5	Common	Tree
American Beech	Fagus grandifolia	S4	Common	Tree
Black Ash	Fraxinas nigra	S5	Common	Tree
White Ash	Fraxinus americana	S5	Common	Tree
Green Ash	Fraxinus pennsylvanica	S5	Common	Tree
Honey Locust	Gleditsia triacanthos	S2	n/a	Tree
Butternut	Juglans cinerea	S3	Endangered	Tree
Domestic Apple	Malus sylvestris	n/a	Common	Tree
Ironwood	Ostrya Virginiana	S5	Common	Tree
Norwegian Spruce	Picea abies	SNA	n/a	Tree
White Spruce	Picea glauca	S5	Common	Tree
Red Pine	Pinus resinosa	S5	Common	Tree
Eastern White Pine	Pinus strobus	S5	Common	Tree
Scots Pine	Pinus sylvestris	SNA	Rare (frequently planted)	Tree
Large Tooth Aspen	Populus grandidentata	S5	Common	Tree
Trembling Aspen	Populus tremuloides	S5	Common	Tree
Black Cherry	Prunus serotina	S5	Common	Tree
Bur Oak	Quercus macrocarpa	S5	Common	Tree
Red Oak	Quercus rubra	S5	Common	Tree
Staghorn Sumac	Rhus hirta	S5	Common	Tree
Weeping Willow	Salix alba	SNA	Uncommon	Tree
Crack Willow	Salix fragilis	SNA	Common (invasive)	Tree
White Cedar	Thuja occidentalis	S5	Common	Tree
American Basswood	Tilia americana	S5	Common	Tree
American or White Elm	Ulmus americana	S5	Common	Tree
Virginia Creeper	Parthenocissus vitacea	S5	Common	Vine
Dog Strangling Vine	Vincetoxicum rossicum	SNA	Uncommon (locally abundant invasive)	Vine
Riverbank Grape	Vitis riparia	S5	Common	Vine

Provincial ranks (assigned by NHIC)

S5 = Very common within the province with > 1000 occurrences, populations or records

S4 = Common within the province with 21 - 1000 occurrences, populations or records

S3 = Rare within the province with 6 - 20 occurrences, populations or records

SNA = Ranking not available

SE5 = Very common exotic with > 1000 occurrences, populations or records within the province

S? = Unranked, or if followed by a ranking, temporarily assigned (eg. S4?)

APPENDIX C

Bird and Wildlife Sightings



TABLE B: BIRDS

Common Name	Scientific Name
Red-winged Blackbird	<i>Agelaius phoeniceus</i>
Mallard	<i>Anas fulvigula</i>
Great Blue Heron	<i>Ardea herodias</i>
Cedar Waxwing	<i>Bombycilla cedrorum</i>
Canada Goose	<i>Branta canadensis</i>
Cackling Goose	<i>Branta hutchinsii</i>
Northern Cardinal	<i>Cardinalis cardinalis</i>
Killdeer	<i>Charadrius vociferus</i>
Black-billed Cuckoo	<i>Coccyzus erythrophthalmus</i>
Northern Flicker	<i>Colaptes auratus</i>
Rock Pigeon	<i>Columba livia</i>
American Crow	<i>Corvus brachyrhynchos</i>
Blue Jay	<i>Cyanocitta cristata</i>
Pileated Woodpecker	<i>Dryocopus pileatus</i>
Gray Catbird	<i>Dumetella carolinensis</i>
Alder Flycatcher	<i>Empidonax alnorum</i>
Common Yellowthroat	<i>Geothlypis trichas</i>
Baltimore Oriole	<i>Icterus galbula</i>
Ring-billed Gull	<i>Larus delawarensis</i>
Swamp Sparrow	<i>Melospiza georgiana</i>
Song Sparrow	<i>Melospiza melodia</i>
Great Crested Flycatcher	<i>Myiarchus crinitus</i>
Black-Crowned Night-Heron	<i>Nycticorax nycticorax</i>
House Sparrow	<i>Passer domesticus</i>
Double-crested Cormorant	<i>Phalacrocorax auritus</i>
Downy Woodpecker	<i>Picoides pubescens</i>
Hairy Woodpecker	<i>Picoides villosus</i>

Black-capped Chickadee	Poecile atricapilla
Common Grackle	Quiscalus quiscula
Eastern Phoebe	Sayornis phoebe
Yellow-rumped Warbler	Setophaga coronata
Yellow Warbler	Setophaga petechia
American Redstart	Setophaga ruticilla
White-breasted Nuthatch	Sitta carolinensis
American Goldfinch	Spinus tristis
Chipping Sparrow	Spizella passerina
European Starling	Sturnus vulgaris
American Robin	Turdus migratorius
Red-eyed Vireo	Vireo olivaceus
Mourning Dove	Zenaida macroura

TABLE C: OTHER WILDLIFE

Common Name	Scientific Name
Common Raccoon	Procyon lotor
Eastern Grey Squirrel	Sciurus carolinensis
Red Squirrel	Sciurus vulgaris
Eastern Cottontail	Sylvilagus floridanus
Eastern Chipmunk	Tamias striatus
American Bullfrog	Lithobates catesbeianus
Green Frog	Lithobates clamitans

APPENDIX D

Significant Woodlot Assessment Terms of Reference





Minto Communities
180 Kent Street, Suite 200
Ottawa, ON, K1P 0B6

January 10th, 2019

Attn: Beth Henderson, Senior Land Development Manager

RE: Individual Terms of Reference – Significant Woodlot Assessment
Kanata Golf and Country Club Redevelopment

1.0 SITE OVERVIEW AND BACKGROUND

McKinley Environmental Solutions (MES) and Muncaster Environmental Planning (MEP) were retained by Minto Communities on behalf of Clublink Corporation ULC to prepare a Combined Environmental Impact Statement (EIS) and Tree Conservation Report (TCR) to support the proposed redevelopment of the Kanata Golf and Country Club property (the Site). The Site occurs within the developed urban portion of Kanata (Ottawa) and is predominantly surrounded by existing developed residential homes and/or roads on all sides. The Site is approximately 71 ha in size and is irregularly shaped. The Site has been operated as a golf and country club for several decades and is predominantly an artificial landscape which has been maintained to provide golfing facilities. The majority of the surface area of the Site includes manicured golf greens and fairways (e.g. manicured lawns). The Site also includes a variety of native and non-native landscaping features, including many deciduous and coniferous planted trees and tree stands. Natural vegetation communities primarily consist of patches of native deciduous forest and deciduous thickets, which are present principally around the edges of the Site. There are no natural watercourses or wetland habitats within the Site. Two (2) Stormwater Management (SWM) ponds are located within the Site (referred to as the Northern and Southern SWM Ponds). Six (6) stormwater conveyance/infiltration swales are also present within the Site, all of which are fed either by outlet pipes from the adjacent developed subdivisions or by surface run-off from the golf greens. As discussed in greater detail in the Combined EIS and TCR, Butternut Trees (endangered) are known to occur within the Site. No other significant Species at Risk (SAR) concerns have been noted for the Site, however, the Combined EIS and TCR methodology includes detailed surveying for a variety of SAR (see below).

McKINLEY ENVIRONMENTAL SOLUTIONS

613-620-2255

mckinleyenvironmental@gmail.com

www.mckinleyenvironmental.com

2.0 DESCRIPTION OF UNDERTAKING

The Site is proposed to be redeveloped to include approximately 545 single detached homes, 586 townhomes, and 371 medium density units for a total of approximately 1,502 units. The two (2) existing stormwater management ponds and the existing stormwater management swales are to be decommissioned. Stormwater servicing will be provided by five (5) new stormwater management blocks, which collectively will occupy approximately 8.02 ha. The Site will also receive municipal sewer and water.

3.0 ASSESSMENT METHODS

The City of Ottawa guidelines for Significant Woodlot evaluation require preparation of an Individual Terms of Reference when evaluating potential Significant Woodlots within the urban area. This Individual Terms of Reference has been prepared to support the evaluation of the potential Significant Woodlots within the Site. Ultimately, the detailed assessment methodology and assessment results will be integrated within the Combined EIS and TCR.

The assessment methods to inventory trees and classify plant communities within the Site will include the following:

- Completion of a three (3) season plant inventory to document the occurrence of plants, create a master plant list, and identify and delineate plant communities;
- Classification of forest patches and thickets according to the vegetation communities identified in the Ecological Land Classification (ELC) manual (OMNRF 1998; Lee 2008);
- Completion of a tree inventory including identification of tree species and tree size measurements using tree sampling plots at a minimum density of 1 plot per hectare of forest;
- Inventory of landscaping features, individual trees, and tree stands where stands of trees occur with approximately ten (10) or more stems and/or where individual trees ≥ 50 cm diameter at breast height (dbh) occur;
- Due to the large number of landscaping features within the Site, smaller tree stands (<10 stems) and individual trees with a dbh <50 cm will be described in general terms, but will not be documented in detail; and
- Documentation of trees ≥ 50 cm dbh wherever they occur within the Site.

The City of Ottawa Official Plan (Section 2.4.2), as amended by Official Plan Amendment 179, defines Significant Woodlots in the urban area as any forested area ≥ 0.8 ha in size supporting woodland 40 years of age or older at the time of evaluation. However, the age criteria has recently been revised to include woodlots 60 years of age or older, as a result of a recent Local Planning Appeal Tribunal (LPAT) decision. The Site occurs within the urban area of the City of Ottawa, and therefore the recently

amended urban area criteria apply. The assessment methods to evaluate the potential presence of Significant Woodlots within the Site, and to describe their significant features and functions, will include the following:

- In order to evaluate the potential presence of Significant Woodlots, vegetation communities within the Site will first be inventoried and classified according to the vegetation communities described in the Ecological Land Classification (ELC) manual (described above);
- Once the presence of forest communities within the Site has been identified, the size of each forest patch will be measured using GIS software. Forest patches ≥ 0.8 ha in size will be identified and mapped;
- Historic air photos made available by the City of Ottawa and Natural Resources Canada will then be utilized to determine the likely age of forest within each of the forest patches ≥ 0.8 ha in size. Air photos from 1959 will be utilized to identify woodlots that are 60 years of age or greater; and
- The significant features and functions of any potential Significant Woodlots that qualify under the age and size criteria will further be evaluated and discussed by reviewing the *Natural Heritage Reference Manual* criteria (OMNRF 2010).

Additional surveying that will be completed to support the Combined EIS and TCR, as well as the Significant Woodlot assessment, includes the following:

- Site surveys to assess the potential for the habitat of Species at Risk (SAR), wetlands, fish habitat, significant wildlife habitat features, and other significant habitat features to be present;
- Examination of aerial imagery to evaluate landscape features;
- Natural Heritage Information Center (NHIC) database review;
- Obtainment of an updated Potential Species at Risk (SAR) List for the Geographic Township of March from the Ontario Ministry of Natural Resources and Forestry (OMNRF);
- Review of Official Plan designations;
- Review of the background geotechnical report;
- Completion of a Breeding Bird Survey for several avian Species at Risk (SAR), an Amphibian Call Count survey for breeding amphibians, a Basking Survey for Blanding's Turtle (threatened) and Snapping Turtle (special concern), an Eastern Whip Poor Will (threatened) and Common Nighthawk (special concern) Call Survey, a Butternut Health Assessment (BHA) to document the occurrence and health of Butternut Trees, and an assessment of the potential for Bat Maternity Roosting. All SAR and wildlife surveys will be completed following recognized Ontario Ministry of Natural Resources and Forestry (OMNRF) protocols; and
- Detailed aquatic habitat, fish surveys, and/or a Headwaters Drainage Assessment were not deemed to be required, due to the absence of natural wetland and watercourse features.

4.0 ANTICIPATED TREE RETENTION AND MITIGATION

Tree retention and mitigation recommendations are expected to include the following:

- Three (3) major park blocks are identified in the Land Use Concept Plan, which collectively provide 4.36 ha of parkland;
- Notably, park block 75 overlaps a portion of potential Significant Woodlot D, thereby providing an opportunity for portions of the feature and its significant functions to be retained. Within the park design, it is recommended that retention of overlapping portions of the potential Significant Woodlot should be prioritized. Wherever feasible, the portions of potential Significant Woodlot D that overlap park block 75 should be retained;
- Park blocks 74 and 76 do not overlap the potential Significant Woodlots. However, existing tree coverage should also be retained within the park design for park blocks 74 and 76, wherever possible;
- The Land Use Concept Plan includes an additional 5.36 ha of open space blocks, which will provide additional opportunities for tree retention. Notably, open space block 87 will preserve a portion of potential Significant Woodlot C, whereas open space blocks 88 and 91 will preserve a portion of potential Significant Woodlot E. Existing tree coverage will be retained within the open space blocks wherever feasible;
- The Land Use Concept Plan includes 3 m wide landscaped buffers around the Site edges adjacent to existing residential properties. The combined size of the 3 m wide landscaped buffers is 1.7 ha. Many of the Site edges are currently occupied by planted trees, tree stands, or forest patches, and therefore the 3 m wide landscaped buffers will provide additional opportunities for tree retention along the Site edges, including protection of the critical root zones. Existing tree coverage will be retained within the 3 m wide landscaped property buffers wherever feasible;
- There are five (5) new stormwater management blocks, which collectively will occupy approximately 8.02 ha. Tree retention within the stormwater management blocks is not likely to be feasible, due to the required excavation and grade changes. However, it is recommended that tree coverage within the Site should be enhanced by adding new plantings/landscaping features within the stormwater management blocks as part of the Site redevelopment;
- A network of trails has been identified to connect the parkland, open space blocks, and stormwater management blocks. The trails will enhance access to these features, thereby enhancing their ability to provide recreational and aesthetic value;
- The Combined EIS and TCR will include detailed Tree Preservation and Mitigation Measures;
- The Combined EIS and TCR will also include recommendations for tree planting;
- A detailed Landscaping Plan will be prepared to provide planting details (under separate cover);

- The Combined EIS and TCR will describe any regulatory requirements with respect to potential impacts on Butternut Trees (endangered), as well as any other requirements related to the Ontario Endangered Species Act; and
- The Combined EIS and TCR will include detailed Wildlife Construction Stage mitigation measures.



5.0 CLOSURE


The City of Ottawa guidelines for Significant Woodlot evaluation require preparation of an Individual Terms of Reference when evaluating potential Significant Woodlots within the urban area. This Individual Terms of Reference has been prepared to support the evaluation of the potential Significant Woodlots within the Site. Ultimately, the detailed assessment methodology and assessment results will be integrated within the Combined EIS and TCR. Refer to the completed Combined EIS and TCR report for the full Significant Woodlot assessment and conclusions.

We trust that the above information is sufficient; should you have any questions or require further information, please do not hesitate to contact the undersigned, at your convenience.

Sincerely,



Dr. Andrew McKinley, EP, RP Bio.
Senior Biologist, McKinley Environmental Solutions



Bernie Muncaster, M. Sc.
Principal, Muncaster Environmental Planning Inc.

APPENDIX E

Ontario Ministry of Natural Resources and Forestry (OMNRF) Potential Species at Risk List for the Geographic Township of March

LONGUEUIL	MARCH	MARLBOROUGH
American Eel	American Eel	American Ginseng
American Ginseng	American Ginseng	Bald Eagle
Bank Swallow	Bald Eagle	Bank Swallow
Barn Swallow	Bank Swallow	Barn Swallow
Black Tern	Barn Swallow	Black Tern
Blanding's Turtle	Black Tern	Blanding's Turtle
Bobolink	Blanding's Turtle	Bobolink
Butternut	Bobolink	Bogbean Buckmoth
Canada Warbler	Butternut	Bridle Shiner
Channel Darter	Canada Warbler	Butternut
Chimney Swift	Chimney Swift	Chimney Swift
Common Nighthawk	Eastern Meadowlark	Common Nighthawk
Cutlip Minnow	Eastern Musk Turtle	Eastern Meadowlark
Eastern Meadowlark	Eastern Small-footed Myotis	Eastern Musk Turtle
Eastern Musk Turtle	Eastern Whip-poor-will	Eastern Prairie Fringed Orchid
Eastern Ribbonsnake	Eastern Wood-pewee	Eastern Small-footed Myotis
Eastern Small-footed Myotis	Hickorynut	Eastern Whip-poor-will
Eastern Wood Pewee	Horned Grebe	Eastern Wood-pewee
Evening Grosbeak	Lake Sturgeon	Grasshopper Sparrow
Golden Eagle	Least Bittern	King Rail
Hickorynut	Little Brown Myotis	Least Bittern
Lake Sturgeon	Loggerhead Shrike	Little Brown Myotis
Least Bittern	Monarch	Loggerhead Shrike
Little Brown Myotis	Northern Map Turtle	Monarch
Monarch	Northern Myotis	Northern Map Turtle
Northern Map Turtle	Peregrine Falcon	Northern Myotis
Northern Myotis	River Redhorse	Red-headed Woodpecker
River Redhorse	Rusty Blackbird	Snapping Turtle
Rusty Blackbird	Rusty-patched Bumble Bee	Spotted Turtle
Short-eared Owl	Silver Lamprey	Tri-colored Bat
Silver Lamprey	Snapping Turtle	Wood Thrush
Snapping Turtle	Transverse Lady Beetle	Yellow Rail
Spotted Turtle	Tri-colored Bat	
Tri-colored Bat	Wood Thrush	
West Virginia White	Yellow-banded Bumblebee	
Whip poor will		
Wood Thrush		

APPENDIX F

Butternut Health Assessment (Rose Fleguel 2019)



Rosemary Fleguel
405 Latourell Rd.
Mountain, ON
K0E 1S0

Beth Henderson, Senior Land Development Manager
Minto Communities – Canada
200-180 Kent St.
Ottawa, ON
K1P 0B6

June 13, 2019

RE: Kanata Golf & Country Club
BHA Report Number: 002-002
Date(s) of Butternut health assessment: June 7, 8 and 12, 2019

Dear Beth,

This letter is in regard to my assessment of the Butternut trees on the above noted property. Please read this report carefully as it contains important information about the Endangered Species Act, 2007 (ESA).

Best regards,

Rosemary Fleguel
Designated Butternut Health Assessor #002
rosefleguel@gmail.com
613 858 3678

Enclosures:

1. Information from the Ministry of Natural Resources and Forestry about Butternut and the *Endangered Species Act, 2007*
2. Butternut Health Assessor's Report
3. Scanned copied data forms – originals to MECP
4. Electronic and printed copies of the Excel data spreadsheet (BHA Tree Analysis)

Ministry of Natural
Resources and Forestry

Ministère des Richesses
naturelles et des Forêts

Species At Risk
P.O. Box 7000, 300 Water Street
Peterborough ON K9J 8M5

Espèces en péril
C.P. 7000, 300, rue Water
Peterborough ON K9J 8M5



The enclosed Butternut Health Assessor's Report documents the results of the Butternut health assessment that was conducted by the designated Butternut Health Assessor (BHA) identified in the top section of the report. If there are other Butternut trees (of any size or age) at the site that may be affected by the activity and they are not identified in the enclosed BHA Report, they too must be assessed by a designated BHA.

Butternut is listed as an endangered species on the Species at Risk in Ontario List, and as such, it is protected under the *Endangered Species Act, 2007* (ESA) from being killed, harmed, or removed. If you are planning to undertake an activity that may affect Butternut, you may be eligible to follow the requirements set out in section 23.7 of Ontario Regulation 242/08 under the ESA, or you may need to seek an authorization under the ESA (e.g., a permit).

Please visit e-laws at the link provided below for the legal requirements of eligible activities under section 23.7 of Ontario Regulation 242/08 and conditions that must be fulfilled. Information about Butternut is also available at: <http://www.ontario.ca/environment-and-energy/butternut-trees-your-property>.

If you are eligible to kill, harm or take Butternut under section 23.7 of the regulation, your first step is to submit the BHA Report and the original data forms enclosed in this package to the local Ministry of Natural Resources and Forestry (MNR) District Manager. Note that MNR cannot accept photocopies or scanned electronic copies of the data forms.

Note regarding changes:

If the enclosed BHA Report does not identify which Butternut tree(s) are proposed to be killed, harmed, or taken in Table 1 (i.e., if "unknown" is indicated in the second last column of Table 1), or, if the information in the last two columns of Table 1 has changed since the date this BHA Report was produced, **do not make any edits to the BHA Report**. Instead, please attach a cover letter that identifies which Butternut tree(s) are proposed to be killed, harmed, or taken (by referencing the tree identification numbers) when you submit the enclosed BHA Report to the local MNR District Manager.

The BHA Report must be submitted at least 30 days prior to registering an eligible activity to kill, harm, or remove a Butternut tree. During this 30 day period, no Butternut trees (of any category) may be killed, harmed, or removed, and MNR may contact you for an opportunity to examine the trees. If MNR chooses to examine the trees, a representative of MNR will contact you using the information you supplied when you submitted the BHA Report.

If you are eligible to follow the rules in regulation under section 23.7, you may register your activity using the “Notice of Butternut Impact” form on the [MNRF Registry](#) **after the 30 day period has elapsed.**

If you are **not** eligible to follow the rules in regulation under section 23.7, please contact the local MNRF district office to determine whether you will need to seek an authorization (e.g., a permit). A link to the directory of MNRF offices is provided below.

Note that municipal by-laws and legislation other than the ESA may also be applicable to the removal or harming of trees.

Please retain this information and a copy of the BHA Report (including copies of all data forms) for your records, along with any other documentation you may receive from MNRF should an examination of the trees occur. If you have any questions, please contact your local MNRF district office.

Links:

Endangered Species Act, 2007:

http://www.e-laws.gov.on.ca/html/statutes/english/elaws_statutes_07e06_e.htm

Ontario Regulation 242/08 (refer to section 23.7):

http://www.e-laws.gov.on.ca/html/regs/english/elaws_regs_080242_e.htm

MNRF Office Locations:

<https://www.ontario.ca/government/ministry-natural-resources-and-forestry-regional-and-district-offices>

Butternut Health Assessor's Report Number: 002-002

Rosemary Fleguel
 Designated BHA #002
 405 Latourell Rd.
 Mountain, ON
 K0E 1S0
 613 858 3667
 rosefleguel@hotmail.com

Beth Henderson, Senior Land Development Manager
 Minto Communities – Canada
 200-180 Kent St.
 Ottawa, ON
 K1P 0B6
 613 782 2311
 bhenderson@minto.com

Site location: Kanata Golf & Country Club

Date(s) of Butternut health assessment: June 7, 8 and 12, 2019)

Date BHA Report prepared: June 13, 2019

Map datum used: NAD83 WGS84¹

Total number of trees assessed in this BHA Report: 46

The assessed trees were numbered on site using white paint or white flagging with black marker. The numbers at the site correspond to the tree numbers referenced in this report.

This BHA Report includes the following tables:

- Table 1: Butternut Trees Assessed
- Table 2: Trees Determined by BHA to be Butternut Hybrids
- Table 3: Summary of Assessment Results

Table 1: Butternut Trees Assessed

Tree #	UTM coordinates	Category ¹ (1, 2, or 3 ²)	dbh ³ (cm)	Cultivated? (Y/N)	Proposed to be: (enter one: unknown ⁴ , killed, harmed or taken)	If tree is proposed to be killed, harmed, or taken, indicate reason tree is proposed to be killed, harmed or taken:
--------	-----------------	---	-----------------------	----------------------	---	---

¹ The extent to which the tree is affected by Butternut Canker is presented in the Excel document titled, "BHA Tree Analysis" that accompanies this BHA Report.

² Category 3 trees are not eligible to be killed, harmed or taken under section 23.7 of Ontario Regulation 242/08.

³ dbh: diameter at breast height, rounded to nearest cm (if tree is shorter than breast height, enter zero)

⁴ In this column, "unknown" indicates that at the time of assessment, there are no proposals to kill, harm or take this tree that are known to the BHA.

Tree #	UTM coordinates	Category ¹ (1, 2, or 3 ²)	dbh ³ (cm)	Cultivated? (Y/N)	Proposed to be: (enter one: unknown ⁴ , killed, harmed or taken)	If tree is proposed to be killed, harmed, or taken, indicate reason tree is proposed to be killed, harmed or taken:
1	E0428261 N5018398	1	46	n	unknown	
2	E0428244 N5018371	3	88	N	unknown	
3	E0428238 M5018400	1	27	N	unknown	
4	E0428239 N5018399	1	27	N	unknown	
5	E0428253 N5018394	1	22	N	unknown	
6	E0428266 N5018453	2	57	N	unknown	
7	E0428167 N5019144	2	8	N	unknown	
8	E0428307 N5018900	2	40	N	unknown	
9	E0428298 N5018672	2	6	N	unknown	
10	E0428426 N5018545	2	6	N	unknown	
11	E0428422 N5018505	2	20	N	unknown	
12	E0428781 N5018999	3	56	N	unknown	
13	E0428790 N5018990	3	22	N	unknown	
14	E0428784 N5019013	3	27	N	unknown	
15	E0428771 N5018999	3	35	N	unknown	
16	E0428768 N5019004	3	26	N	unknown	
17	E0428767 N5019019	3	39	N	unknown	
18	E0428764 N5019019	1	37	N	unknown	
19	E0428768 N5019017	3	40	N	unknown	
20	E0428672 N5018945	2	2	N	unknown	
21	E0429167 N5018963	1	7	N	unknown	
22	E0429152 N5018995	2	29	N	unknown	
23	E0429149 N5019004	2	71	N	unknown	
24	E0429150 N5018005	2	29	N	unknown	

Tree #	UTM coordinates	Category ¹ (1, 2, or 3 ²)	dbh ³ (cm)	Cultivated? (Y/N)	Proposed to be: (enter one: unknown ⁴ , killed, harmed or taken)	If tree is proposed to be killed, harmed, or taken, indicate reason tree is proposed to be killed, harmed or taken:
25	E0429147 N5018995	2	32	N	unknown	
26	E0429131 N5018990	2	32	N	unknown	
27	E0429129 N5018991	1	21	N	unknown	
28	E0429128 N5019000	2	36	N	unknown	
29	E0429142 N5019009	2	31	N	unknown	
30	E0428977 N5018593	2	69	N	unknown	
31	E0429257 N5018659	2	66	N	unknown	
32	E0428968 N5018534	1	40	N	unknown	
33	E0428961 N5018525	3	50	N	Unknown	
34	E0429157 N5018701	3	47	N	unknown	
35	E0429157 N5018700	3	50	N	unknown	
36	E0429166 N5018701	1	26	N	unknown	
37	E0429168 N5018710	1	20	N	unknown	
38	E0429174 N5018708	1	37	N	unknown	
39	E0429183 N5018698	1	21	N	unknown	
40	E0429184 N5018696	2	16	N	unknown	
41	E0428971 N5018607	2	55	N	unknown	
42	E0428908 N5018583	2	26	N	unknown	
43	E0428901 N5018575	2	29	N	unknown	
44	E0428880 N5018585	2	32	N	unknown	
45	E0428881 N5018589	2	61	N	unknown	
46	E0428873 N5018598	2	0	N	unknown	

Table 2: Trees Determined by BHA to be Butternut Hybrids

Tree #	UTM coordinates	Method used (genetic testing or field identification):

Table 3: Summary of Assessment Results

Result:	Total #:	Important information for persons planning activities that may affect Butternut:
Category 1	12	<ul style="list-style-type: none"> A Category 1 tree is one that is affected by butternut canker to such an advanced degree that retaining the tree would not support the protection or recovery of butternut in the area in which the tree is located; and is considered “non-retainable”. During the 30 day period that follows your submission of this BHA Report to the MNR District Manager, no Butternut trees (of Category 1, 2, or 3) may be killed, harmed, or taken, and MNR may contact you for an opportunity to examine the trees. Category 1 trees may be killed, harmed or taken after the 30 day period that follows submission of this BHA Report to the MNR District Manager, unless the results of an MNR examination indicate that the assessment has not been conducted in accordance with the document entitled “Butternut Assessment Guidelines: Assessment of Butternut Tree Health for the Purposes of the <i>Endangered Species Act, 2007</i>”.
Category 2	23	<ul style="list-style-type: none"> A Category 2 tree is one that is not affected by Butternut Canker, or is affected by Butternut Canker but the degree to which it is affected is not too advanced and retaining the tree could support the protection or recovery of butternut in the area in which the tree is located, and is considered “retainable”. During the 30 day period that follows your submission of this BHA Report to the MNR District Manager, no Butternut trees (of Category 1, 2, or 3) may be killed, harmed, or taken, and MNR may contact you for an opportunity to examine the trees. Activities that may kill, harm or take up to a maximum of ten (10) Category 2 trees may be eligible to follow the rules in section 23.7 of Ontario Regulation 242/08, in accordance with the conditions and requirements set out in the regulation. Refer to e-Laws for the legal requirements of eligible activities under section 23.7 of Ontario Regulation 242/08 and conditions that must be fulfilled: http://www.e-laws.gov.on.ca/html/reg/english/elaws_regs_080242_e.htm Activities that may kill, harm or take more than ten (10) Category 2 trees are not eligible to follow the rules in section 23.7 of Ontario Regulation 242/08. Contact the local MNR district office for information on how to seek an ESA authorization (e.g., a permit) or consider an alternative that would be eligible for the regulation.
Category 3	11	<ul style="list-style-type: none"> A Category 3 tree is one that may be useful in determining sources of resistance to Butternut Canker, and is considered “archivable”. Category 3 trees are not eligible to be killed, harmed or taken under section 23.7 of Ontario Regulation 242/08. Contact the local MNR district office for information on how to seek an ESA authorization, or consider an alternative that will avoid killing, harming or taking any Category 3 trees.
Cultivated	0	<ul style="list-style-type: none"> An activity that involves killing, harming, or taking a cultivated Butternut tree that was not required to be planted to fulfill a condition of an ESA permit or a condition of a regulation, may be eligible for the exemption provided by subsection 23.7 (11) of O. Reg. 242/08.

Result:	Total #:	Important information for persons planning activities that may affect Butternut:
		<ul style="list-style-type: none"> • Prior to undertaking the activity, the owner or occupier of the land on which the Butternut is located (or person acting on their behalf) will need to determine whether the exemption for cultivated trees is applicable by determining whether or not the tree was cultivated as a result of the requirements for an exemption under O. Reg. 242/08 or a condition of a permit issued under the ESA. This information can be accessed by contacting the local MNRF district office. • The owner or occupier of the land on which the Butternut is located (or person acting on their behalf) is encouraged to append the details regarding whether the tree was planted to satisfy a requirement (e.g., the permit number or registration number) to this BHA Report for their records.
Hybrid	0	<ul style="list-style-type: none"> • Hybrid Butternut trees are not protected under the ESA, but their removal may be subject to municipal by-laws and other legislation.

Butternut Health Assessor's Comments:

This concludes the summary of the BHA Report. A complete BHA Report must also include:

1. All original (hard copy) data forms (i.e., all completed sets of Form 1 and Form 2), and
2. Electronic and printed copies of the Excel data analysis spreadsheet.

BHA Tree Analysis (version: December 2013)

This table is to be completed by a designated Butternut Health Assessor (BHA).

BHA Report #	002-002	Assessment Date(s)	June 7, 8 and 12, 2019	Total # Butternut Trees in BHA Report	46
BHA ID #	2	BHA Name	Rosemary Fleguel		
Landowner / Client Name		Minto Canada Inc.			
Property Location		Kanata Golf & Country Club			

input field data										automatic calculations from field data						Categories:										
Tree #	Live Crown %	Tree dbh (cm)	# bole cankers				# root flare (RF) cankers		Y or N <40 m from cankered tree?	Circ. (cm) = Pi x dbh	total bole canker width (sooty x 2.5 + open x 5)	total RF canker width (sooty x 2.5 + open x 5)	bole canker % of circ.	RF canker % of circ.	total bole & root canker % of 2xCirc	LC% >= 50 & BC% = 0	LC% >70 & BRC % <20	LC% >70 & BC % <20	Preliminary tree call	FINAL TREE CALL a Cat 2, dbh>20cm <40m from a Cat 1						
			sooty (S) (will be assigned 2.5 cm per canker)		open (O) (will be assigned 5 cm per canker)		RF S	RF O													Circ (cm)	BC (cm)	RC (cm)	BC%	RC%	BRC%
			S <2 m	S >2 m	O <2 m	O >2 m																				
1	40	46							144.4	0.0	0.0	0.0	0.0	0.0	1	1	1	1	1							
2	90	88	3	0	1	0	3	5	y	276.3	12.5	32.5	4.5	11.8	8.1	1	2	2	2	3						
3	80	27	3	2	2	1	0	4	y	84.78	27.5	20.0	32.4	23.6	28.0	1	1	1	1	1						
4	0	27								84.78	0.0	0.0	0.0	0.0	0.0	1	1	1	1	1						
5	0	22								69.08	0.0	0.0	0.0	0.0	0.0	1	1	1	1	1						
6	90	57	4	0	2	1	1	11	n	179	25.0	57.5	14.0	32.1	23.0	1	1	2	2	2						
7	95	8	0	0	0	0	0	0		25.12	0.0	0.0	0.0	0.0	0.0	2	2	2	2	2						
8	95	40	0	0	0	0	0	0	n	125.6	0.0	0.0	0.0	0.0	0.0	2	2	2	2	2						
9	95	6	0	0	0	0	0	0		18.84	0.0	0.0	0.0	0.0	0.0	2	2	2	2	2						
10	100	6	0	0	0	0	0	0		18.84	0.0	0.0	0.0	0.0	0.0	2	2	2	2	2						
11	100	20	0	0	0	0	0	1	n	62.8	0.0	5.0	0.0	8.0	4.0	2	2	2	2	2						
12	95	56	1	0	0	0	2	3	y	175.8	2.5	20.0	1.4	11.4	6.4	1	2	2	2	3						
13	90	22	5	1	1	0	0	0	y	69.08	20.0	0.0	29.0	0.0	14.5	1	2	1	2	3						
14	100	27	0	0	0	0	2	0	y	84.78	0.0	5.0	0.0	5.9	2.9	2	2	2	2	3						
15	85	35	3	4	0	0	0	6	y	109.9	17.5	30.0	15.9	27.3	21.6	1	1	2	2	3						
16	90	26	0	0	0	0	0	0	y	81.64	0.0	0.0	0.0	0.0	0.0	2	2	2	2	3						
17	85	39	2	0	2	0	2	3	y	122.5	15.0	20.0	12.2	16.3	14.3	1	2	2	2	3						
18	85	37	7	1	3	1	2	3	n	116.2	40.0	20.0	34.4	17.2	25.8	1	1	1	1	1						
19	95	40	0	0	0	0	1	0	y	125.6	0.0	2.5	0.0	2.0	1.0	2	2	2	2	3						
20	100	2	0	0	0	0	0	0		6.28	0.0	0.0	0.0	0.0	0.0	2	2	2	2	2						
21	90	7	2	1	0	0	1	0		21.98	7.5	2.5	34.1	11.4	22.7	1	1	1	1	1						
22	95	29	0	0	1	0	0	1	n	91.06	5.0	5.0	5.5	5.5	5.5	1	2	2	2	2						
23	90	71	4	1	0	0	1	0	n	222.9	12.5	2.5	5.6	1.1	3.4	1	2	2	2	2						
24	95	29	2	0	1	0	2	0	n	91.06	10.0	5.0	11.0	5.5	8.2	1	2	2	2	2						
25	95	32	0	0	0	0	1	0	n	100.5	0.0	2.5	0.0	2.5	1.2	2	2	2	2	2						
26	85	32	5	0	1	0	2	1	n	100.5	17.5	10.0	17.4	10.0	13.7	1	2	2	2	2						
27	80	21	0	0	5	1	0	0	n	65.94	30.0	0.0	45.5	0.0	22.7	1	1	1	1	1						
28	95	36	4	0	0	0	0	0	n	113	10.0	0.0	8.8	0.0	4.4	1	2	2	2	2						
29	95	31	1	1	0	0	1	1	n	97.34	5.0	7.5	5.1	7.7	6.4	1	2	2	2	2						
30	90	69	0	0	0	0	0	0	n	216.7	0.0	0.0	0.0	0.0	0.0	2	2	2	2	2						
31	95	66	1	1	1	0	4	0	n	207.2	10.0	10.0	4.8	4.8	4.8	1	2	2	2	2						

32	10	40								125.6	0.0	0.0	0.0	0.0	0.0	1	1	1	1	1	
33	80	50	0	0	0	0	3	0	y	157	0.0	7.5	0.0	4.8	2.4	2	2	2	2	3	
34	80	47	5	4	2	1	1	1	y	147.6	37.5	7.5	25.4	5.1	15.2	1	2	1	2	3	
35	85	50	2	0	1	1	1	1	y	157	15.0	7.5	9.6	4.8	7.2	1	2	2	2	3	
36	20	26								81.64	0.0	0.0	0.0	0.0	0.0	1	1	1	1	1	
37	0	20								62.8	0.0	0.0	0.0	0.0	0.0	1	1	1	1	1	
38	30	37								116.2	0.0	0.0	0.0	0.0	0.0	1	1	1	1	1	
39	90	21	1	0	3	0	1	2		65.94	17.5	12.5	26.5	19.0	22.7	1	1	1	1	1	
40	90	16	2	0	0	1	0	1		50.24	10.0	5.0	19.9	10.0	14.9	1	2	2	2	2	
41	95	55	3	0	1	0	1	5	n	172.7	12.5	27.5	7.2	15.9	11.6	1	2	2	2	2	
42	85	26	0	0	0	0	0	0	n	81.64	0.0	0.0	0.0	0.0	0.0	2	2	2	2	2	
43	90	29	0	0	0	0	0	0	n	91.06	0.0	0.0	0.0	0.0	0.0	2	2	2	2	2	
44	90	32	0	0	1	0	0	2	n	100.5	5.0	10.0	5.0	10.0	7.5	1	2	2	2	2	
45	95	61	1	0	0	0	1	1	n	191.5	2.5	7.5	1.3	3.9	2.6	1	2	2	2	2	
46	100	1	0	0	0	0	0	0		3.14	0.0	0.0	0.0	0.0	0.0	2	2	2	2	2	
47										0	0.0	0.0	#####	#####	#####	####	###	###	##	#	#DIV/0!
48										0	0.0	0.0	#####	#####	#####	####	###	###	##	#	#DIV/0!
49										0	0.0	0.0	#####	#####	#####	####	###	###	##	#	#DIV/0!
50										0	0.0	0.0	#####	#####	#####	####	###	###	##	#	#DIV/0!
51										0	0.0	0.0	#####	#####	#####	####	###	###	##	#	#DIV/0!
52										0	0.0	0.0	#####	#####	#####	####	###	###	##	#	#DIV/0!

Butternut Data Collection Form 1 - 2010 Edition

Surveyor ID or BHA #

(PLEASE USE BLOCK LETTERS)

Date (dd/mm/yyyy) - -

Shaded fields are mandatory for Butternut Health Assessments

Surveyor Contact

First Last

Email

Telephone () - Telephone Other ()

Property Owner

(check if same as surveyor)

First Last

or Company

Email

Telephone () - Telephone Other ()

Property Owner's Mailing address

Address Postal Code Prov.

City

Tree Location (if different from mailing address)

Address/(911#)

Township Lot Con

City

Directions

- Yes No Can Share Location Information with other Butternut Recovery Organizations?
- Yes No Site visits OK? (prior arrangements will always be made for a site visit)

Butternut Trees Tally by Diameter Class

(Do a dot tally in blank space; write total# in box for each)

Tree Condition	< 3 cm	3-15 cm	16-30cm	>30 cm
Vigorous: > 50% Live Crown Minor or no cankers	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Poor Vigor: <50% Live Crown or >50% Live Crown + heavily cankered stem	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Dead	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Overall Property Description (area(s) containing Butternut)

Rolling Upland Bottomland

Valley Slope Variable

Tableland Unknown

Vegetation Community/ies

Open Fencerow

Shrubland Roadside

DeciduousForest Quarry

ConiferForest UrbanYard

MixedForest UrbanPark

Other

Historically, do some trees produce seeds? Y N Unknown

Estimated area containing butternut for properties > 1 acre (0.4 hectares): Acres Hectares

Tree #2 DBHs = 47cm, 50cm, 55cm.
 Wb at E 0428552 N 5018960
 E 0428757 N 5019513 - off property ~ 5m
 Tree #23 DBHs = 52cm, 48cm

Soil Drainage

Well Drained

Moderately Drained

Poorly Drained

Unknown

Soil Texture

Clay Sand

Clay Loam Variable

Loam Unknown

Loamy Sand

Soil Depth

> 1metre

30 - 99cm

< 30cm

Variable

Unknown

Please enter matching numerical page link code on forms 1 and 2

Page Link

(Contact Information follows all applicable privacy policies and guidelines)

Please return forms to:
 Forest Gene Conservation Association
 275 County Rd 44
 Kemptville, ON, K0G 1J0
 www.fgca.net

49731



Butternut Data Collection FORM 2 (2010 Edition)

(PLEASE USE BLOCK LETTERS)

Fill when Form 1 indicates canker is well established. The information on Form 2 must be filled out for all trees when doing a Butternut Health Assessment.

Shaded fields are mandatory for Butternut Health Assessments

Site Code(A,B,...Z, AA...)

Surveyor ID or BHA # 002

Date (dd/mm/yyyy)

07 - 06 - 2019

Surveyor Last Name

Tree ID Numbering: 1,2,3,...Starting from 1 for each site

Tree # Zone Easting Northing
1 18 428261 5018398

Crown Class 40 Live Crown % Main Stem Length(m) Below crown Seed Signs
 Twig Dieback Branch Dieback Defoliation Discolouration
 2 #Stems
 46 DBH(cm)
 Butternut Origin: Natural Planted Unknown
 Signs: Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty
 Root =<2m >2m

Metres from badly cankered tree
 < 40 > 40 None Found
 Competing Species

Tree # Zone Easting Northing
2 18 428244 5018371

Crown Class 90 Live Crown % 14 Main Stem Length(m) Below crown Seed Signs
 Twig Dieback Branch Dieback Defoliation Discolouration
 3 #Stems
 88 DBH(cm)
 Butternut Origin: Natural Planted Unknown
 Signs: Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty
 Root =<2m >2m

Metres from badly cankered tree
 < 40 > 40 None Found
 Competing Species

Tree # Zone Easting Northing
3 18 428238 5018400

Crown Class 80 Live Crown % 10 Main Stem Length(m) Below crown Seed Signs
 Twig Dieback Branch Dieback Defoliation Discolouration
 1 #Stems
 27 DBH(cm)
 Butternut Origin: Natural Planted Unknown
 Signs: Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty
 Root =<2m >2m

Metres from badly cankered tree
 < 40 > 40 None Found
 Competing Species

Tree # Zone Easting Northing
4 18 428239 5018399

Crown Class 0 Live Crown % Main Stem Length(m) Below crown Seed Signs
 Twig Dieback Branch Dieback Defoliation Discolouration
 1 #Stems
 27 DBH(cm)
 Butternut Origin: Natural Planted Unknown
 Signs: Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty
 Root =<2m >2m

Metres from badly cankered tree
 < 40 > 40 None Found
 Competing Species

Tree # Zone Easting Northing
5 18 428253 5018394

Crown Class 0 Live Crown % Main Stem Length(m) Below crown Seed Signs
 Twig Dieback Branch Dieback Defoliation Discolouration
 1 #Stems
 22 DBH(cm)
 Butternut Origin: Natural Planted Unknown
 Signs: Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty
 Root =<2m >2m

Metres from badly cankered tree
 < 40 > 40 None Found
 Competing Species

Very healthy young Bn but storm broke crown off

Please enter matching page link code on forms 1 and 2

Page Link

428261

(Contact Information follows all applicable privacy policies and guidelines)

Please return forms to:
 Forest Gene Conservation Association
 Suite 233, 266 Charlotte St.
 Peterborough, ON, K9J 2V4
 www.fgca.net

49731

Butternut Data Collection FORM 2 (2010 Edition)

(PLEASE USE BLOCK LETTERS)

Fill when Form 1 indicates canker is well established. The information on Form 2 must be filled out for all trees when doing a Butternut Health Assessment.

Shaded fields are mandatory for Butternut Health Assessments

Site Code(A,B,...Z, AA...)

Surveyor ID or BHA # **002**

Date (dd/mm/yyyy) **07 - 06 - 2019**

Surveyor Last Name

Tree ID Numbering: 1,2,3,...Starting from 1 for each site

Tree # **6** Zone **18** Easting **428266** Northing **5018453**

Crown Class **90** Live Crown % **14** Main Stem Length(m) Below crown **14** Seed Signs
 Twig Dieback **2** #Stems Male Flowers
 Branch Dieback **2** #Stems Natural Female Flowers
 Defoliation **57** DBH(cm) Planted Seed Set
 Discolouration **57** DBH(cm) Unknown None

Assess below live crown
 #Epic-Live #Epic-Dead
 Bark Type =<2m **2** # Callused Wounds >2m **1**
 #Open #Sooty Root **1** **1**

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

2

Tree # **7** Zone **18** Easting **428167** Northing **5019144**

Crown Class **95** Live Crown % **2** Main Stem Length(m) Below crown **2** Seed Signs
 Twig Dieback **1** #Stems Male Flowers
 Branch Dieback **1** #Stems Natural Female Flowers
 Defoliation **8** DBH(cm) Planted Seed Set
 Discolouration **8** DBH(cm) Unknown None

Assess below live crown
 #Epic-Live #Epic-Dead
 Bark Type =<2m **0** # Callused Wounds >2m **0**
 #Open #Sooty Root **0** **0**

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

2

Tree # **8** Zone **18** Easting **428307** Northing **5018900**

Crown Class **95** Live Crown % **10** Main Stem Length(m) Below crown **10** Seed Signs
 Twig Dieback **1** #Stems Male Flowers
 Branch Dieback **1** #Stems Natural Female Flowers
 Defoliation **40** DBH(cm) Planted Seed Set
 Discolouration **40** DBH(cm) Unknown None

Assess below live crown
 #Epic-Live #Epic-Dead
 Bark Type =<2m **0** # Callused Wounds >2m **0**
 #Open #Sooty Root **0** **0**

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

2

Tree # **9** Zone **18** Easting **428298** Northing **5018672**

Crown Class **95** Live Crown % **1** Main Stem Length(m) Below crown **1** Seed Signs
 Twig Dieback **9** #Stems Male Flowers
 Branch Dieback **9** #Stems Natural Female Flowers
 Defoliation **6** DBH(cm) Planted Seed Set
 Discolouration **6** DBH(cm) Unknown None

Assess below live crown
 #Epic-Live #Epic-Dead
 Bark Type =<2m **0** # Callused Wounds >2m **0**
 #Open #Sooty Root **0** **0**

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

2

Tree # **10** Zone **18** Easting **428426** Northing **5018545**

Crown Class **100** Live Crown % **2** Main Stem Length(m) Below crown **2** Seed Signs
 Twig Dieback **1** #Stems Male Flowers
 Branch Dieback **1** #Stems Natural Female Flowers
 Defoliation **6** DBH(cm) Planted Seed Set
 Discolouration **6** DBH(cm) Unknown None

Assess below live crown
 #Epic-Live #Epic-Dead
 Bark Type =<2m **0** # Callused Wounds >2m **0**
 #Open #Sooty Root **0** **0**

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

2

All coppice coming out of old cut stump. Assessed the dominant stem

Please enter matching page link code on forms 1 and 2

Page Link

428261

(Contact Information follows all applicable privacy policies and guidelines)

Please return forms to:
 Forest Gene Conservation Association
 Suite 233, 266 Charlotte St.
 Peterborough, ON, K9J 2V4
 www.fgca.net

49731



Butternut Data Collection FORM 2 (2010 Edition)

(PLEASE USE BLOCK LETTERS)

Fill when Form 1 indicates canker is well established. The information on Form 2 must be filled out for all trees when doing a Butternut Health Assessment.

Shaded fields are mandatory for Butternut Health Assessments

Site Code(A,B,...Z, AA...)

Surveyor ID or BHA # 002

Date (dd/mm/yyyy) 08 - 06 - 2019

Surveyor Last Name

Tree ID Numbering: 1,2,3,...Starting from 1 for each site

Tree # Zone Easting Northing
11 18 428422 5018505

Crown Class 100 Live Crown % 2 Main Stem Length(m) Below crown 2
 Twig Dieback Branch Dieback 1 #Stems Defoliation Discolouration 20 DBH(cm)
 Butternut Origin Natural Planted Unknown
 Seed Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty Root =<2m >2m

Metres from badly cankered tree < 40 > 40 None Found
 Competing Species

Tree # Zone Easting Northing
12 18 428781 5018999

Crown Class 95 Live Crown % 5 Main Stem Length(m) Below crown 5
 Twig Dieback Branch Dieback 1 #Stems Defoliation Discolouration 56 DBH(cm)
 Butternut Origin Natural Planted Unknown
 Seed Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty Root =<2m >2m

Metres from badly cankered tree < 40 > 40 None Found
 Competing Species

Tree # Zone Easting Northing
13 18 428790 5018990

Crown Class 90 Live Crown % 3 Main Stem Length(m) Below crown 3
 Twig Dieback Branch Dieback 1 #Stems Defoliation Discolouration 22 DBH(cm)
 Butternut Origin Natural Planted Unknown
 Seed Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty Root =<2m >2m

Metres from badly cankered tree < 40 > 40 None Found
 Competing Species

Tree # Zone Easting Northing
14 18 428784 5019013

Crown Class 100 Live Crown % 3 Main Stem Length(m) Below crown 3
 Twig Dieback Branch Dieback 1 #Stems Defoliation Discolouration 27 DBH(cm)
 Butternut Origin Natural Planted Unknown
 Seed Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty Root =<2m >2m

Metres from badly cankered tree < 40 > 40 None Found
 Competing Species

Storm damage injury in crown but healing + healthy

Tree # Zone Easting Northing
15 18 428771 5018999

Crown Class 85 Live Crown % 8 Main Stem Length(m) Below crown 8
 Twig Dieback Branch Dieback 1 #Stems Defoliation Discolouration 35 DBH(cm)
 Butternut Origin Natural Planted Unknown
 Seed Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty Root =<2m >2m

Metres from badly cankered tree < 40 > 40 None Found
 Competing Species

Please enter matching page link code on forms 1 and 2

Page Link 428261

(Contact Information follows all applicable privacy policies and guidelines)

Please return forms to:
 Forest Gene Conservation Association
 Suite 233, 266 Charlotte St.
 Peterborough, ON, K9J 2V4
 www.fgca.net

49731

Butternut Data Collection FORM 2 (2010 Edition)

(PLEASE USE BLOCK LETTERS)

Fill when Form 1 indicates canker is well established. The information on Form 2 must be filled out for all trees when doing a Butternut Health Assessment.

Shaded fields are mandatory for Butternut Health Assessments

Site Code(A,B,...Z, AA...)

Surveyor ID or BHA # 002

Date (dd/mm/yyyy)

08 - 06 - 2019

Surveyor Last Name

Tree ID Numbering: 1,2,3,...Starting from 1 for each site

Tree # Zone Easting Northing
16 18 428768 5019004

Crown Class 90 Live Crown % 3 Main Stem Length(m) Below crown 3
 Twig Dieback Branch Dieback Defoliation Discolouration
 1 #Stems
 26 DBH(cm)
 Butternut Origin: Natural Planted Unknown
 Signs: Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty
 Root =<2m >2m
 0 0
 0 0
 0 0

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # Zone Easting Northing
17 18 428767 5019019

Crown Class 85 Live Crown % 6 Main Stem Length(m) Below crown 6
 Twig Dieback Branch Dieback Defoliation Discolouration
 1 #Stems
 39 DBH(cm)
 Butternut Origin: Natural Planted Unknown
 Signs: Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty
 Root =<2m >2m
 6 3
 2 2
 5 0

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # Zone Easting Northing
18 18 428764 5019019

Crown Class 85 Live Crown % 3 Main Stem Length(m) Below crown 3
 Twig Dieback Branch Dieback Defoliation Discolouration
 1 #Stems
 37 DBH(cm)
 Butternut Origin: Natural Planted Unknown
 Signs: Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty
 Root =<2m >2m
 3 2
 3 7
 10 1

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # Zone Easting Northing
19 18 428768 5019017

Crown Class 95 Live Crown % 7 Main Stem Length(m) Below crown 7
 Twig Dieback Branch Dieback Defoliation Discolouration
 1 #Stems
 40 DBH(cm)
 Butternut Origin: Natural Planted Unknown
 Signs: Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty
 Root =<2m >2m
 0 1
 0 0
 1 0

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # Zone Easting Northing
20 18 428672 5018945

Crown Class 100 Live Crown % 1 Main Stem Length(m) Below crown 1
 Twig Dieback Branch Dieback Defoliation Discolouration
 1 #Stems
 2 DBH(cm)
 Butternut Origin: Natural Planted Unknown
 Signs: Male Flowers Female Flowers Seed Set None

Assess below live crown
 #Epic-Live #Epic-Dead Bark Type # Callused Wounds
 #Open #Sooty
 Root =<2m >2m
 0 0
 0 0
 0 0

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Please enter matching page link code on forms 1 and 2

Page Link 428261

(Contact Information follows all applicable privacy policies and guidelines)

Please return forms to:
 Forest Gene Conservation Association
 Suite 233, 266 Charlotte St.
 Peterborough, ON, K9J 2V4
 www.fgca.net

49731



Butternut Data Collection FORM 2 (2010 Edition)

(PLEASE USE BLOCK LETTERS)

Fill when Form 1 indicates canker is well established. The information on Form 2 must be filled out for all trees when doing a Butternut Health Assessment.

Shaded fields are mandatory for Butternut Health Assessments

Site Code(A,B,...Z, AA...)

Surveyor ID or BHA # **002**

Date (dd/mm/yyyy)

08 - 06 - 2019

Surveyor Last Name

Tree ID Numbering: 1,2,3,...Starting from 1 for each site

Tree # **21** Zone **18** Easting **429167** Northing **5018963**

Crown Class **90** Live Crown % **4** Main Stem Length(m) Below crown **4** Seed Signs Male Flowers Female Flowers Seed Set None

Butternut Origin Natural Planted Unknown Twig Dieback Branch Dieback Defoliation Discolouration #Stems **1** DBH(cm) **7**

Assess below live crown

#Epic-Live	#Open	#Sooty
<input type="checkbox"/>	Root	0 1
#Epic-Dead	=<2m	0 2
Bark Type	>2m	0 1
7 # Callused Wounds		

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # **22** Zone **18** Easting **429152** Northing **5018995**

Crown Class **95** Live Crown % **8** Main Stem Length(m) Below crown **8** Seed Signs Male Flowers Female Flowers Seed Set None

Butternut Origin Natural Planted Unknown Twig Dieback Branch Dieback Defoliation Discolouration #Stems **1** DBH(cm) **29**

Assess below live crown

#Epic-Live	#Open	#Sooty
<input type="checkbox"/>	Root	1 0
#Epic-Dead	=<2m	1 0
Bark Type	>2m	0 0
2 # Callused Wounds		

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # **23** Zone **18** Easting **429149** Northing **5019004**

Crown Class **90** Live Crown % **8** Main Stem Length(m) Below crown **8** Seed Signs Male Flowers Female Flowers Seed Set None

Butternut Origin Natural Planted Unknown Twig Dieback Branch Dieback Defoliation Discolouration #Stems **2** DBH(cm) **71**

Assess below live crown

#Epic-Live	#Open	#Sooty
<input type="checkbox"/>	Root	0 1
#Epic-Dead	=<2m	0 4
Bark Type	>2m	0 1
3 # Callused Wounds		

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # **24** Zone **18** Easting **429150** Northing **5018005**

Crown Class **95** Live Crown % **10** Main Stem Length(m) Below crown **10** Seed Signs Male Flowers Female Flowers Seed Set None

Butternut Origin Natural Planted Unknown Twig Dieback Branch Dieback Defoliation Discolouration #Stems **1** DBH(cm) **29**

Assess below live crown

#Epic-Live	#Open	#Sooty
<input type="checkbox"/>	Root	0 2
#Epic-Dead	=<2m	1 2
Bark Type	>2m	0 0
1 # Callused Wounds		

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # **25** Zone **18** Easting **429147** Northing **5018995**

Crown Class **95** Live Crown % **5** Main Stem Length(m) Below crown **5** Seed Signs Male Flowers Female Flowers Seed Set None

Butternut Origin Natural Planted Unknown Twig Dieback Branch Dieback Defoliation Discolouration #Stems **1** DBH(cm) **32**

Assess below live crown

#Epic-Live	#Open	#Sooty
<input type="checkbox"/>	Root	0 1
#Epic-Dead	=<2m	0 0
Bark Type	>2m	0 0
0 # Callused Wounds		

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Please enter matching page link code on forms 1 and 2

Page Link **428261**

(Contact Information follows all applicable privacy policies and guidelines)

Please return forms to:
Forest Gene Conservation Association
Suite 233, 266 Charlotte St.
Peterborough, ON, K9J 2V4
www.fgca.net

49731



Butternut Data Collection FORM 2 (2010 Edition)

(PLEASE USE BLOCK LETTERS)

Fill when Form 1 indicates canker is well established. The information on Form 2 must be filled out for all trees when doing a Butternut Health Assessment.

Shaded fields are mandatory for Butternut Health Assessments

Site Code(A,B,...Z, AA...) Surveyor ID or BHA #

Date (dd/mm/yyyy)

Surveyor Last Name

Tree ID Numbering: 1,2,3,...Starting from 1 for each site

Tree # Zone Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown Seed Signs Butternut Origin

Assess below live crown #Epic-Live #Epic-Dead Bark Type # Callused Wounds

Metres from badly cankered tree < 40 > 40 None Found Competing Species

Tree # Zone Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown Seed Signs Butternut Origin

Assess below live crown #Epic-Live #Epic-Dead Bark Type # Callused Wounds

Metres from badly cankered tree < 40 > 40 None Found Competing Species

None of the open 'cankers' are active. - not heavily cankered

Tree # Zone Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown Seed Signs Butternut Origin

Assess below live crown #Epic-Live #Epic-Dead Bark Type # Callused Wounds

Metres from badly cankered tree < 40 > 40 None Found Competing Species

Tree # Zone Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown Seed Signs Butternut Origin

Assess below live crown #Epic-Live #Epic-Dead Bark Type # Callused Wounds

Metres from badly cankered tree < 40 > 40 None Found Competing Species

Tree # Zone Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown Seed Signs Butternut Origin

Assess below live crown #Epic-Live #Epic-Dead Bark Type # Callused Wounds

Metres from badly cankered tree < 40 > 40 None Found Competing Species

Hollow old Bn

Please enter matching page link code on forms 1 and 2

Page Link

(Contact Information follows all applicable privacy policies and guidelines)

Please return forms to: Forest Gene Conservation Association Suite 233, 266 Charlotte St. Peterborough, ON, K9J 2V4 www.fgca.net

49731



3025 4394
1369

Butternut Data Collection FORM 2 (2010 Edition)

(PLEASE USE
BLOCK LETTERS)

Fill when Form 1 indicates canker is well established. The information on Form 2 must be filled out for all trees when doing a Butternut Health Assessment.

Shaded fields are mandatory for Butternut Health Assessments

Site Code(A,B,...Z, AA...)

Surveyor ID or BHA # 002

Date (dd/mm/yyyy) 12 - 06 - 2019

Surveyor Last Name

Tree ID Numbering: 1,2,3,...Starting from 1 for each site

Tree # Zone Easting Northing
31 18 429257 5018659

Crown Class 95 Live Crown % 2 Main Stem Length(m) Below crown Seed Signs
 Twig Dieback 2 #Stems
 Branch Dieback 2
 Defoliation
 Discolouration 66 DBH(cm)
Butternut Origin Natural Planted Unknown
Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
#Epic-Live #Open #Sooty
#Epic-Dead Root 0 4
Bark Type =<2m 1 1
2 # Callused Wounds >2m 0 1

Metres from badly cankered tree < 40 > 40 None Found
Competing Species

DBH - 55cm and 37cm. Did not mark - on south side of cart path near Knudson Dr

Tree # Zone Easting Northing
32 18 428968 5018534

Crown Class 10 Live Crown % Main Stem Length(m) Below crown Seed Signs
 Twig Dieback 2 #Stems
 Branch Dieback 2
 Defoliation
 Discolouration 40 DBH(cm)
Butternut Origin Natural Planted Unknown
Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
#Epic-Live #Open #Sooty
#Epic-Dead Root
Bark Type =<2m
 # Callused Wounds >2m

Metres from badly cankered tree < 40 > 40 None Found
Competing Species

Tree # Zone Easting Northing
33 18 428961 5018525

Crown Class 80 Live Crown % 4 Main Stem Length(m) Below crown Seed Signs
 Twig Dieback 1 #Stems
 Branch Dieback 1
 Defoliation
 Discolouration 50 DBH(cm)
Butternut Origin Natural Planted Unknown
Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
#Epic-Live #Open #Sooty
#Epic-Dead Root 0 3
Bark Type =<2m 0 0
1 # Callused Wounds >2m 0 0

Metres from badly cankered tree < 40 > 40 None Found
Competing Species

Not marked with paint - unsure if it is on property

Tree # Zone Easting Northing
34 18 429157 5018701

Crown Class 80 Live Crown % 8 Main Stem Length(m) Below crown Seed Signs
 Twig Dieback #Stems
 Branch Dieback
 Defoliation
 Discolouration 47 DBH(cm)
Butternut Origin Natural Planted Unknown
Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
#Epic-Live #Open #Sooty
#Epic-Dead Root 1 1
Bark Type =<2m 2 5
11 # Callused Wounds >2m 1 4

Metres from badly cankered tree < 40 > 40 None Found
Competing Species

Tree # Zone Easting Northing
35 18 429157 5018700

Crown Class 85 Live Crown % 6 Main Stem Length(m) Below crown Seed Signs
 Twig Dieback 1 #Stems
 Branch Dieback 1
 Defoliation
 Discolouration 50 DBH(cm)
Butternut Origin Natural Planted Unknown
Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
#Epic-Live #Open #Sooty
#Epic-Dead Root 1 1
Bark Type =<2m 1 2
7 # Callused Wounds >2m 1 0

Metres from badly cankered tree < 40 > 40 None Found
Competing Species

Please enter matching page link code on forms 1 and 2

Page Link 429261

(Contact Information follows all applicable privacy policies and guidelines)

Please return forms to:
Forest Gene Conservation Association
Suite 233, 266 Charlotte St.
Peterborough, ON, K9J 2V4
www.fgca.net

49731



Butternut Data Collection FORM 2 (2010 Edition)

(PLEASE USE BLOCK LETTERS)

Fill when Form 1 indicates canker is well established. The information on Form 2 must be filled out for all trees when doing a Butternut Health Assessment.

Shaded fields are mandatory for Butternut Health Assessments

Site Code(A,B,...Z, AA...) Surveyor ID or BHA #

Date (dd/mm/yyyy) 12 - 06 - 2019

Surveyor Last Name

Tree ID Numbering: 1,2,3,...Starting from 1 for each site

Tree # Zone Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown Seed Signs Butternut Origin

Assess below live crown #Epic-Live #Epic-Dead Bark Type # Callused Wounds

Metres from badly cankered tree < 40 > 40 None Found Competing Species

Tree # Zone Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown Seed Signs Butternut Origin

Assess below live crown #Epic-Live #Epic-Dead Bark Type # Callused Wounds

Metres from badly cankered tree < 40 > 40 None Found Competing Species

Tree # Zone Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown Seed Signs Butternut Origin

Assess below live crown #Epic-Live #Epic-Dead Bark Type # Callused Wounds

Metres from badly cankered tree < 40 > 40 None Found Competing Species

Tree # Zone Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown Seed Signs Butternut Origin

Assess below live crown #Epic-Live #Epic-Dead Bark Type # Callused Wounds

Metres from badly cankered tree < 40 > 40 None Found Competing Species

Tree # Zone Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown Seed Signs Butternut Origin

Assess below live crown #Epic-Live #Epic-Dead Bark Type # Callused Wounds

Metres from badly cankered tree < 40 > 40 None Found Competing Species

Please enter matching page link code on forms 1 and 2

Page Link 429261

Contact Information follows all applicable privacy policies and guidelines

Please return forms to: Forest Gene Conservation Association Suite 233, 266 Charlotte St. Peterborough, ON, K9J 2V4 www.fgca.net

49731



Butternut Data Collection FORM 2 (2010 Edition)

(PLEASE USE BLOCK LETTERS)

Fill when Form 1 indicates canker is well established. The information on Form 2 must be filled out for all trees when doing a Butternut Health Assessment.

Shaded fields are mandatory for Butternut Health Assessments

Site Code(A,B,...Z, AA...) **Surveyor ID or BHA #** 002

Date (dd/mm/yyyy)
12 - 06 - 2019

Surveyor Last Name

Tree ID Numbering: 1,2,3,...Starting from 1 for each site

Tree # 4118 Zone 428971 Easting 5018607 Northing

2 Crown Class 95 Live Crown % .4 Main Stem Length(m) Below crown Seed Signs

Twig Dieback 1 #Stems **Butternut Origin** Natural Planted Unknown Male Flowers Female Flowers Seed Set None

Branch Dieback Defoliation Discolouration 55 DBH(cm)

Assess below live crown

#Epic-Live	#Open	#Sooty
<input type="checkbox"/>	Root 5	1
#Epic-Dead	=<2m 1	3
Bark Type	>2m 0	0
# Callused Wounds		
3		

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # 4218 Zone 428908 Easting 5018583 Northing

2 Crown Class 85 Live Crown % 2 Main Stem Length(m) Below crown Seed Signs

Twig Dieback 1 #Stems **Butternut Origin** Natural Planted Unknown Male Flowers Female Flowers Seed Set None

Branch Dieback Defoliation Discolouration 26 DBH(cm)

Assess below live crown

#Epic-Live	#Open	#Sooty
<input type="checkbox"/>	Root 0	0
#Epic-Dead	=<2m 0	0
Bark Type	>2m 0	0
# Callused Wounds		
1		

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # 4318 Zone 428901 Easting 5018575 Northing

2 Crown Class 90 Live Crown % 5 Main Stem Length(m) Below crown Seed Signs

Twig Dieback 2 #Stems **Butternut Origin** Natural Planted Unknown Male Flowers Female Flowers Seed Set None

Branch Dieback Defoliation Discolouration 29 DBH(cm)

Assess below live crown

#Epic-Live	#Open	#Sooty
<input type="checkbox"/>	Root 0	0
#Epic-Dead	=<2m 0	0
Bark Type	>2m 0	0
# Callused Wounds		
0		

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # 4418 Zone 428880 Easting 5018585 Northing

2 Crown Class 90 Live Crown % 4 Main Stem Length(m) Below crown Seed Signs

Twig Dieback 1 #Stems **Butternut Origin** Natural Planted Unknown Male Flowers Female Flowers Seed Set None

Branch Dieback Defoliation Discolouration 32 DBH(cm)

Assess below live crown

#Epic-Live	#Open	#Sooty
<input type="checkbox"/>	Root 2	0
#Epic-Dead	=<2m 1	0
Bark Type	>2m 0	0
# Callused Wounds		
3		

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # 4518 Zone 428881 Easting 5018589 Northing

2 Crown Class 95 Live Crown % 5 Main Stem Length(m) Below crown Seed Signs

Twig Dieback 1 #Stems **Butternut Origin** Natural Planted Unknown Male Flowers Female Flowers Seed Set None

Branch Dieback Defoliation Discolouration 61 DBH(cm)

Assess below live crown

#Epic-Live	#Open	#Sooty
<input type="checkbox"/>	Root 1	1
#Epic-Dead	=<2m 0	1
Bark Type	>2m 0	0
# Callused Wounds		
12		

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Please enter matching page link code on forms 1 and 2

Page Link 429261

(Contact Information follows all applicable privacy policies and guidelines)

Please return forms to:
 Forest Gene Conservation Association
 Suite 233, 266 Charlotte St.
 Peterborough, ON, K9J 2V4
 www.fgca.net

49731



Butternut Data Collection FORM 2 (2010 Edition)

(PLEASE USE BLOCK LETTERS)

Fill when Form 1 indicates canker is well established. The information on Form 2 must be filled out for all trees when doing a Butternut Health Assessment.

Shaded fields are mandatory for Butternut Health Assessments

Site Code(A,B,...Z, AA...)

Surveyor ID or BHA # 002

Date (dd/mm/yyyy) 12-06-2019

Surveyor Last Name

Tree ID Numbering: 1,2,3,...Starting from 1 for each site

Tree # 46 Zone 18 Easting 428873 Northing 5018598

Crown Class 100 Live Crown % 0 Main Stem Length(m) Below crown 0
Twig Dieback Branch Dieback Defoliation Discolouration
Butternut Origin Natural Planted Unknown
Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
#Epic-Live #Epic-Dead Bark Type # Callused Wounds
#Open #Sooty Root =<2m >2m

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

New seedling

Tree # 1 Zone 1 Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown
Twig Dieback Branch Dieback Defoliation Discolouration
Butternut Origin Natural Planted Unknown
Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
#Epic-Live #Epic-Dead Bark Type # Callused Wounds
#Open #Sooty Root =<2m >2m

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # 1 Zone 1 Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown
Twig Dieback Branch Dieback Defoliation Discolouration
Butternut Origin Natural Planted Unknown
Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
#Epic-Live #Epic-Dead Bark Type # Callused Wounds
#Open #Sooty Root =<2m >2m

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # 1 Zone 1 Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown
Twig Dieback Branch Dieback Defoliation Discolouration
Butternut Origin Natural Planted Unknown
Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
#Epic-Live #Epic-Dead Bark Type # Callused Wounds
#Open #Sooty Root =<2m >2m

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Tree # 1 Zone 1 Easting Northing

Crown Class Live Crown % Main Stem Length(m) Below crown
Twig Dieback Branch Dieback Defoliation Discolouration
Butternut Origin Natural Planted Unknown
Signs Male Flowers Female Flowers Seed Set None

Assess below live crown
#Epic-Live #Epic-Dead Bark Type # Callused Wounds
#Open #Sooty Root =<2m >2m

Metres from badly cankered tree < 40 > 40 None Found

Competing Species

Please enter matching page link code on forms 1 and 2

Page Link 429261

(Contact Information follows all applicable privacy policies and guidelines)

Please return forms to: Forest Gene Conservation Association Suite 233, 266 Charlotte St. Peterborough, ON, K9J 2V4 www.fgca.net

49731

