

REPORT
PROJECT: 134569-6.04-01

ENVIRONMENTAL NOISE IMPACT ASSESSMENT SOUTH KEYS PHASE 1

Table of Contents

1	Introduction	1
2	Background	2
2.1	Noise Sources.....	2
2.2	Sound Level Limits for Road & Rail Traffic.....	2
2.2.1	Indoor sound level criterion – ventilation and warning clause requirements	2
2.2.2	Outdoor sound level criterion	3
2.2.3	Indoor Sound Level Criterion – Building Components.....	3
2.3	Sound Level Limits for Aircraft Noise.....	3
3	Roadway Noise	4
3.1	Road & Rail Traffic Data	4
3.2	Calculation Methods	5
4	Abatement Measures	6
4.1	Indoor Sound Levels	6
4.2	Outdoor Living Area	6
4.3	Building Components.....	7
4.4	Aircraft Sound Levels.....	7
5	Summary of Attenuation Measures	8
5.1	Warning Clauses.....	8
5.2	Ventilation Requirements and Building Components	8
5.3	Noise Barrier	8
6	Conclusion	9
7	Professional Authorization	9

List of Tables

Table 3.1	Traffic and Road Data Summary
Table 3.2	Unattenuated Noise Levels at Building Face (Indoor)
Table 3.3	Unattenuated Noise Levels at OLA

List of Appendices

- Appendix A – Trillium Line Extension EA Extracts
- Appendix B – Noise Calculations
- Appendix C – Architectural Drawings
- Appendix D – STC Calculations

List of Figures

- Figure 1 – Location Plan
- Noise Plan – Drawing No. 134569-N1

1 Introduction


This Environmental Noise Impact Assessment (ENIA) has been prepared in support of combined Zoning By-law Amendment (ZBLA) and Site Plan Control (SPC) applications for a proposed high-rise residential development at 2200 Bank Street within the South Keys Shopping Centre in Ottawa, referred to as 'South Keys Phase 1'. Ultimately, four phases are planned to occupy the subject lands, however the scope of this study was limited to Phase 1, as the subsequent phases are still highly-conceptual in nature and will be reviewed as part of separate Site Plan Control (SPC) applications, as required. This study evaluated the expected transportation-related noise levels within the development and recommended any warning clauses and associated noise abatement measures required in the Tenancy Agreement for each dwelling unit included in Phase 1.

The proposed development consists of a 20-storey tower and 9-storey podium atop a 2-storey, above-grade garage.

Phase 1 is generally bound by a large-format retail establishment to the north, existing surface parking to the east, a cinema to the south and the Transitway/Trillium Line Extension to the west.

The site location and its surrounding context are shown in **Figure 1** below.

Figure 1 – Site Location



2 Background

2.1 Noise Sources

The study area is primarily subjected to roadway noise from the existing Bus Rapid Transit (BRT) corridor. There are no other collector or higher-order roadways within close enough proximity to generate noise sources of any significance within the site.

Aircraft noise from the Ottawa International Airport impacts the whole site, as it is located entirely within the Airport Vicinity Development Zone (AVDZ) identified on Schedule C14 of the 2022 Official Plan. As such, consideration will be given to aircraft noise in this study.

In accordance with the City of Ottawa Environmental Noise Control (ENC) Guidelines (January 2016), rail lines within 500 metres of the site must be taken into consideration in the noise analysis. A review of the study area indicates that the Trillium Line Extension Light Rail Transit (LRT) corridor is presently under construction immediately west and parallel to the existing BRT line.

2.2 Sound Level Limits for Road & Rail Traffic

Sound level criteria for road traffic were extracted from the ENC Guidelines. Noise levels are expressed in the form Leq (T) which refers to a weighted level of a steady sound carrying the same total energy in the time period T (in hours) as the observed fluctuation sound.

2.2.1 Indoor sound level criterion – ventilation and warning clause requirements

The recommended indoor sound level criteria from Table 2.2b of the ENC Guidelines are as follows:

- Bedrooms – 23:00 to 07:00 – 40 dBA Leq (8 hours)
- Living Room – 07:00 to 23:00 – 45 dBA Leq (16 hours)

The sound levels are based on the windows and doors to an indoor space being closed.

As discussed previously, the proposed development consists of a 20-storey tower and a 9-storey podium joined by a two-storey, above-grade parking podium. For the purpose of assessing the most significant indoor noise in this study, the outdoor noise levels for the 20-Storey Tower are observed at 58.5 metres above, while critical noise associated with the 9-storey podium was calculated at 25.5 metres above the ground level. These receiver heights were determined by reviewing the living room and bedroom window locations for the upper-floor dwelling units from architectural drawings provided by the proponent, and were analysed to determine noise impacts with respect to the adjacent transportation network.

As per NPC-300 C7.1.3, if the daytime outdoor sound levels exceed 65 dBA at the living room window or if the nighttime sound levels exceed 60 dBA at the bedroom window, then the building must be compliant with the Ontario Building Code. Should the outdoor sound levels exceed this criteria, then the building component (walls, windows, etc.) must be designed to achieve indoor sound level criteria.

As per NPC-300 C7.1.2.1 and C7.1.2.2, when the outdoor noise levels are greater than 55 dBA and less than or equal to 65 dBA at the living room window and/or greater than 50 dBA and less than or equal to 60 dBA at the bedroom window, then a warning clause is compulsory. This warning clause specifies that forced air heating with a provision for central air conditioning is required. Should the outdoor sound levels exceed the criteria, central air conditioning is mandatory, and a warning clause is required.

2.2.2 Outdoor sound level criterion

As per Table 2.2a of the ENC Guidelines, the sound level criteria for the outdoor living area (OLA) during the daytime (i.e. 07:00 and 23:00 hours) is 55 dBA Leq (16). Sound levels for the OLA are calculated 3 metres from the building face at the centre of the unit, or in the middle of the OLA at a height of 1.5 metres above the ground/elevated terrace.

If the Leq sound level is less than or equal to the above criteria, then no further action is required by the developer. If the sound level exceeds the criteria by less than 5 dBA then the developer may, with City approval, either provide a warning clause to prospective tenants or install physical attenuation. For sound levels greater than 5 dBA above the criteria control measures are required to reduce the noise levels as close to 55 dBA as technically, economically and administratively possible. Should the sound levels with the barrier in place exceed 55 dBA a warning clause is also required.

2.2.3 Indoor Sound Level Criterion – Building Components

As per NPC-300 C7.1.3 when the outdoor sound levels are less than or equal to 65 dBA at the living room window and/or less than or equal to 60 dBA at the bedroom level then the building must be compliant with the Ontario Building Code. Should the outdoor sound levels exceed these criteria, then the building component (walls, windows etc.) must be designed to achieve indoor sound level criteria.

2.3 Sound Level Limits for Aircraft Noise

Aircraft noise impact assessment is based on the Noise Exposure Forecast (NEF) and Noise Exposure Projection (NEP) methods approved by Transport Canada. The noise contours were used to define the Airport Operating Influence Zone (AOIZ) and Airport Vicinity Development Zone (AVDZ) which is shown on Schedule C14 of the 2022 Official Plan.

No new noise sensitive developments are permitted within the AOIZ. Noise sensitive development is permitted within the AVDZ and outside of the AOIZ subject to a noise study or under the Prescribed Measures for Aircraft Noise in Part 6 of the ENC Guidelines. Indoor and outdoor sound level limits for aircraft noise is included in Table 4.2a of the ENC Guidelines.

3 Roadway Noise

3.1 Road & Rail Traffic Data

Based on the configuration of the road and rail transportation network with respect to the proposed development, it is assumed that the major sources of transportation noise impacting the site will originate from the existing Bus Rapid Transit (BRT) and the future Trillium Line Extension.

Bus Rapid Transit (BRT) Corridor

The dedicated Bus Rapid Transit corridor, also referred to as the Transitway, exists immediately west of the subject site. Based on discussions with City staff, it is understood that the existing BRT line will continue to operate between the Hunt Club Road Transitway Loop and Hurdman Station once the Trillium Line Extension is open for full revenue service.

Appropriate traffic inputs parameters for the BRT line were conservatively determined based on a review of current OC Transpo schedules for South Keys Station which indicate that the station typically serves approximately 760 buses during a typical weekday. This figure was rounded up to 800 buses per day to account for 'deadhead' (i.e. out-of-service) buses travelling through the station. The daytime and nighttime splits were determined based on a review of OC Transpo routes serving South Keys Station and found to be consistent with the proportions used in the Trillium Line Extension EA Study, as discussed below.

Trillium Line Extension

The Trillium Line Extension is part of Ottawa's Light Rail Transit (LRT) Stage 2 and involves the expansion of the north-south transit line from its current terminus at Greenboro Station further south to the future Limebank Station in Riverside South. The Trillium Line Extension, slated to open for full revenue service in early 2024, will serve South Keys Station adjacent to the subject site and will be located just west of the existing BRT corridor.

Consistent with the Noise, Vibration & Air Quality Report O-Train Extension Environmental Assessment (January 2016), the noise impacts of the Trillium Line Extension were modelled using a 4-car SRT (Scarborough Rapid Transit) vehicle with an assumed operating speed of 70km/h and 2031 projected volumes. Daytime and nighttime splits were based on a review of train schedules obtained from OC Transpo as part of the EA study. Relevant extracts from the Trillium Line EA Study are included in **Appendix A**.

Table 3.1 below summarizes the traffic, road and rail parameters are used to assess the noise levels.

TABLE 3.1 – TRAFFIC AND ROAD DATA SUMMARY

	BUS RAPID TRANSIT (BRT) CORRIDOR	TRILLIUM LINE EXTENSION
Annual Average Daily Traffic (AADT)	800 buses	432 trains ¹
Posted Speed Limit (km/h)	80	70
% Medium Trucks	-	-
% Heavy Trucks	-	-
% Daytime Traffic	89%	89%

Notes: ¹ 216 trains per direction as projected in Trillium Line Extension EA study under 2031 conditions.

It should be noted that Dazé Street, which is identified in the Transportation Master Plan (TMP) as a collector road, is separated from the subject site by a significant distance of at least 105 metres. As such, the transportation-related noise impacts from this road were not considered in the analysis for this study.

3.2 Calculation Methods

Roadway noise was calculated using the STAMSON 5.04 computer program from the Ontario Ministry of the Environment. In the STAMSON program, both the LRT and BRT lines were simulated with custom noise sources.

Unattenuated daytime and nighttime noise levels at the building face, calculated to determine indoor sound levels, are presented in **Table 3.2** below. Parameters used for calculating the noise levels, including the perpendicular distance from the source to receiver and the roadway segment angles are also indicated. The noise impacts associated with LRT were modelled separately for northbound and southbound directions and then combined, consistent with the Trillium Line Extension EA Study.

As indicated on **Noise Plan – Drawing No. 135639-N1**, there are two outdoor living areas (OLAs), referred to as the 3rd Floor Terrace (Shared Amenity Area #1) and the 10th Floor Terrace (Shared Amenity Area #2). An analysis of the 3rd Floor Terrace is presented in **Table 3.3** below. The noise level for the 3rd Floor Terrace was evaluated at location ‘P1’ on the Noise Plan in accordance with the ENC Guidelines which indicate that the midpoint should be used to assess this type of shared amenity area. The balconies associated with each unit have depths of less than 4 metres and are therefore not defined as ‘outdoor living areas’ in the ENC Guidelines.

STAMSON noise calculations conducted for this study are included in **Appendix B**.

TABLE 3.2 – UNATTENUATED NOISE LEVELS AT BUILDING FACE (INDOOR)

LOCATION	ROADWAY	SOURCE RECEIVER DISTANCE (m)	NOISE ANGLES		NOISE (dBA)	
			LEFT	RIGHT	DAYTIME	NIGHTTIME
West Façade 20-Storey Tower	LRT NB	44.8	-90	90	69.81	63.74
	LRT SB	55.8	-90	90		
	BRT	21.8	-90	90		
North Façade 20-Storey Tower	LRT NB	45.8	0	90	66.61	60.55
	LRT SB	56.8	0	90		
	BRT	22.8	0	90		
North Façade, Midpoint 20-Storey Tower	LRT NB	66.2	0	90	63.91	57.84
	LRT SB	77.2	0	90		
	BRT	43.2	0	90		
Northeast Façade 20-Storey Tower	LRT NB	87.8	0	90	62.19	56.13
	LRT SB	98.8	0	90		
	BRT	64.8	0	90		
South Façade 20 Storey Tower	LRT NB	47.5	-90	0	66.30	60.24
	LRT SB	59.0	-90	0		
	BRT	24.5	-90	0		
West Façade Midpoint 9-Storey Podium	LRT NB	74.4	-90	45	65.02	58.96
	LRT SB	85.9	-90	45		
	BRT	50.3	-90	45		
Southwest Corner 9-Storey Podium	LRT NB	74.4	-90	65	65.62	59.56
	LRT SB	85.9	-90	65		
	BRT	50.3	-90	65		
South Façade 9-Storey Podium	LRT NB	75.4	-90	0	63.18	57.11
	LRT SB	86.9	-90	0		
	BRT	51.3	-90	0		
South Façade Midpoint 9-Storey Podium	LRT NB	82.4	-90	0	62.64	56.57
	LRT SB	93.9	-90	0		
	BRT	58.3	-90	0		
Southeast Corner 9-Storey Podium	LRT NB	89.9	-90	0	62.16	56.09
	LRT SB	100.9	-90	0		
	BRT	65.3	-90	0		

As indicated in **Table 3.2** above, the daytime noise exceeds 55 dBA at numerous locations.

TABLE 3.3 – UNATTENUATED NOISE LEVELS AT OLA

LOCATION	ROADWAY	SOURCE RECEIVER DISTANCE (M)	ANGLES		DAYTIME
			LEFT	RIGHT	NOISE (dBA)
3 rd Floor Terrace Shared Amenity Area #1 (P1)	LRT NB	54.5	-90	75	59.51
	LRT SB	66.0	-90	75	
	BRT	30.5	-90	75	
10 th Floor Terrace Shared Amenity Area #2 (P2)	LRT NB	84.5	-40	10	52.16
	LRT SB	96.0	-40	10	
	BRT	60.5	-40	10	

As indicated in **Table 3.3** above, the daytime noise levels for the 3rd Floor Terrace exceed 55 dBA but remain below 60 dBA, therefore it is proposed that a warning clause Type 'A' be included on the Tenancy Agreements for all dwelling units in lieu of a noise barrier.

Noise levels at Location P2 were calculated for the 10th Floor Terrace. Given that this smaller amenity area is further set back from the LRT/BRT lines in comparison with the 3rd Floor Terrace and is partially screened by the proposed 20-Storey Tower, the noise levels at P2 are anticipated to remain below 55 dBA.

4 Abatement Measures

4.1 Indoor Sound Levels

As identified in **Table 3.2** above, the dwelling units on the north, south and west facades of the 20-Storey Tower or the west façade of the 9-Storey Podium have direct exposure to noise from the existing LRT and BRT lines and are expected to exceed 65 dBA (daytime) or 60 dBA (nighttime). As such, mandatory central air conditioning, a review of building components are required, as well as a Type 'D' warning clause on the Tenancy Agreement for each dwelling unit along with an exterior wall occupying these facades.

For dwelling units on the south façade of the 9-storey podium, which will be indirectly exposed to noise from the existing BRT and future LRT lines and are significantly set back farther from these noise sources than the 20-storey tower, daytime noise levels were determined to be less than 65 dBA but still are still expected to exceed 55 dBA (or nighttime noise level is less than 60 dBA but exceeds 50 dBA). As such, an alternative means of ventilation is required, as well as a Type 'C' warning clause in the Tenancy Agreement for each north- or south-facing unit. Alternative means of ventilation usually consist of a forced air heating system with ducts sized for future installation of central air conditioning.

4.2 Outdoor Living Area

As discussed previously, given that the noise levels within Amenity Area #1 are anticipated to remain below above 55 dBA but below 60 dBA, warning clause Type 'A' is proposed in lieu of a physical abatement measures.

4.3 Building Components

An analysis of the required building components for dwelling units expected to experience noise levels at the building face is typically required when noise levels are either 65 dBA (daytime) or 60 dBA (nighttime). In this circumstance, the results presented in **Table 3.2** above indicate that daytime noise levels along the western building façade will exceed the 65 dBA threshold (69.81 dBA), while the nighttime noise levels were found to exceed the 60 dBA threshold (63.74 dBA). As such, an assessment of building components was conducted under both daytime and nighttime conditions. This method was developed by the National Research Council (NRC), and involves a review of architectural plans to determine appropriate design assumptions (i.e. window/floor area ratios) in order to calculate the STC rating for windows and glazed doors.

Exterior walls were assumed to have an STC rating of 50, which is a conservative value for a pre-cast concrete wall designed to accommodate Ottawa winters from the Ontario Building Code. With the exterior walls in place, the amount of sound energy absorbed by the windows is calculated in order to determine the STC rating required to meet the sound criteria. All rooms were assumed to have an intermediate, absorptive interior rather than a hard or very absorptive interior, as would be expected for a residential unit. As indicated in **Table 4.1** below, the maximum required STC rating for the largest west-facing windows and glazed doors was calculated to be 35. This rating was conservatively based on the expected noise levels for the top-floor, single-level dwelling units with the highest exposure to the existing BRT and future LRT lines.

Preliminary plan and profile architectural drawings are provided in **Appendix C**, while STC calculations for the proposed development are included in **Appendix D**.

TABLE 4.1: SOUND TRANSMISSION CLASS (STC) RATINGS

DWELLING UNIT		LEVEL	ROOM TYPE	REQUIRED STC RATING FOR WINDOWS & GLAZED DOORS
20 Storey Tower	West Façade	20 th Floor	Living Room	35
			Bedroom	34

4.4 Aircraft Sound Levels

As stated in Section 2.1, the subject site is entirely located within the Airport Vicinity Development Zone (AVDZ). The site is, however, outside of the 25 NEF/NEP contour line so the building components and ventilation requirements, presented in Part 6: Prescribed Measures for Aircraft Noise of the ENC Guidelines, do not apply. A warning clause is required for the residential units inside the AVDZ, which in this case applies to all dwelling units proposed within the South Keys Phase 1 development.

The warning clause for aircraft noise is as follows:

“Purchasers/tenants are advised that due to the proximity of the Ottawa Macdonald-Cartier International Airport, noise from the airport and individual aircraft may at times interfere with outdoor or indoor activities”.

5 Summary of Attenuation Measures

5.1 Warning Clauses

A clause regarding noise must appear on the Tenancy Agreement for the dwelling units indicated on the **Noise Plan - Drawing No. 134569-N1**:

Type 'A'	Shared Amenity Area #1 (3 rd Floor Terrace) – All Units
Type 'C'	9-Storey Podium – South Façade
Type 'D'	20-Storey Tower – North, South & West Façades 9-Storey Podium – West Façade

Aircraft Warning South Keys Phase 1 – All dwelling units

The following warning clauses are taken from Section C8.1 of NPC-300 Guidelines.

Type A	“Purchasers/tenants are advised that sound levels due to BRT and LRT traffic may occasionally interfere with some activities of the dwelling occupants as the sound levels exceed the sound level limits of the Municipality and the Ministry of the Environment’s noise criteria.”
Type C	“This dwelling unit has been designed with the provision for adding central air conditioning at the occupant’s discretion. Installation of central air conditioning by the occupant in low and medium density developments will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the Municipality and the Ministry of the Environment.”
Type D	“This dwelling unit has been supplied with a central air conditioning system which will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the Municipality and the Ministry of the Environment.”

The aircraft warning clause was provided previously in Section 4.4.

5.2 Ventilation Requirements and Building Components

All dwelling units with a Type ‘C’ warning clause listed in Section 5.1 require a forced air heating system sized to accommodate a central air conditioning system.

All dwelling units with a Type ‘D’ warning clause require mandatory central air conditioning and an acoustical review of building components.

5.3 Noise Barrier

Based on the foregoing analysis, it is not anticipated that any noise barriers will be required to accommodate the proposed development.

6 Conclusion


This report outlines the impact of transportation-related noise on the proposed development, located at 2200 Bank Street, within the South Keys Shopping Centre in Ottawa. Based on the analysis conducted for this study, it is expected that noise levels will remain within the standards established by the City of Ottawa and Ministry of the Environment, Conservation and Parks (MECP), with the exception of select units identified on **Noise Plan Drawing No. 134569-N1**. For these dwelling units, appropriate warning clauses and associated noise abatement measures must be provided on the Tenancy Agreement. Sound Transmission Class (STC) ratings for windows and glazed doors are provided for dwelling units with the highest exposure to the LRT and BRT corridors. Since the subject site is located entirely within the Airport Vicinity Development Zone (AVDZ), a warning clause will be required in the Tenancy Agreement for each dwelling unit.

7 Professional Authorization

Prepared by:



Ben Pascolo-Neveu, P. Eng.



SHARED AMENITY AREA #2
(10th Floor Terrace)

SHARED AMENITY AREA #1
(3rd Floor Terrace)

LEGEND:

- ▲ OUTDOOR LIVING AREA (OLA) NOISE RECEPTOR
- INDOOR NOISE RECEPTOR
- A C D WARNING CLAUSE

CIVIL ENGINEER
ARCADIS (IBI GROUP)
 333 Preston Street, Suite 400
 Ottawa, ON K1S 5N4
 Tel: (613) 225-1311



Appendix A –
Trillium Line Extension EA Extracts

Lance Erion

From: Yousfani, Asad <Asad.Yousfani@ottawa.ca>
Sent: Monday, April 04, 2016 10:08 AM
To: Lance Erion
Cc: Kaufman, Cathlyn; Jim Burghout; Terry Brule
Subject: FW: BRRT

Hi Lance,

I've received the following information from Frank for you to update the noise study.

Thanks,

Asad

From: McKinney, Frank
Sent: Monday, April 04, 2016 9:39 AM
To: Yousfani, Asad
Subject: FW: BRRT

Hi Asad, as requested by IBI at Friday's meeting:

As per p. 5 of Appendix F, the vehicle type, volume and speed assumptions were as follows:

"The ENCG accepts noise models based on the Ontario Road Noise Analysis Method for Environment and Transportation (ORNAMENT), including the computerized version, STAMSON (MOE 1996). These models have built-in sound power data for road vehicles; however, they do not specify values specifically for buses. Based on ENCG section 2.4.1, transitway buses should be classified as "medium trucks" for modeling purposes using STAMSON. However, the buses operating on the BRT are 60 foot articulating buses, with three axles and a weight over 18,000 kg. Based on the MOE "STAMSON Version 4.1 User's Guide", a vehicle with three or more axles and a weight greater than 12,000 kg should be considered as a "heavy truck" for modelling. Therefore, the proposed BRT buses were modelled as "heavy trucks". A summary of the model inputs is presented below in Table 3.

Table 3: Traffic Inputs for Surface Transportation Corridor Modelling

	Dedicated BRT Sections of Project	Transit Street without Proposed BRT	Transit Street with Median BRT
AADT	600	14000	14600
Speed Limit	80 km/h	60 km/h	60 km/h
Day / Night Split	74% / 26%	92% / 8%	91% / 9%
% Medium / % Heavy of Total Traffic	0% / 100%	7% / 5%	7% / 8%

Frank

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

TABLE 5: AADT TRAFFIC AND RAIL VOLUMES (EXISTING AND FUTURE)

Road Segment	AADT		Speed (km/h)
	Existing (2015)	Projected (2031)	
Bayview Road	5,518	6,731	50
Gladstone Avenue	4,758	5,804	40
Highway 417 (/direction)	93,000	11,3450	100
Preston Street	19,976	24,369	50
Airport Parkway	24,879	33,359	80
Airport Parkway (SB Walkley Exit)	5,891	7,899	80
Walkley Road	21,390	26,093	50
Huntclub Road	28,986	35,360	60
Flannery Drive	9,648	11,769	40
O-Train LRT	180	216	70
VIA Rail	14	20	150

Transportation noise calculations have been based on the Ontario Road Noise Analysis Method for Environmental and Transportation (ORNAMENT), and calculated using the MOECC approved software STAMSON (5.04). This method calculates noise levels based on: (i) AADT volumes, posted speed limits, and vehicle mix data for roadways, representing the source; and (ii) source-receiver distance, exposure angles and intermediate ground surface characteristics, and source-receiver ground elevation, as characterizing the path of noise. This method was developed by the MOECC and satisfies City of Ottawa requirements. Unless otherwise specified in Table 5, AADT volumes on surrounding streets were considered to be split 92% daytime, and 8% nighttime, for each roadway segment, as well as a vehicle mix of 7% and 5% for medium and heavy trucks, respectively. Speed limits used in the calculations are presented in Table 5.

The O-Train was modelled in STAMSON as a 4-car SRT (Scarborough Rapid Transit) vehicle; operating at an assumed speed of 70 km/h. Daytime and nighttime split is based on current train schedules obtained from OC Transpo.

Appendix B –
STAMSON Noise Calculations

Indoor Noise at Building Face

Filename: 20toww.te Time Period: Day/Night 16/8 hours
Description: 20 Storey Tower West Facade indoor

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 44.80 / 44.80 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 2: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT NB (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 55.80 / 55.80 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):
Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 21.80 / 21.80 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Results segment # 1: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 54.19 + 0.00) = 54.19 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	58.95	-4.75	0.00	0.00	0.00	0.00	54.19

Segment Leq : 54.19 dBA

Results segment # 2: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 53.24 + 0.00) = 53.24 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	58.95	-5.71	0.00	0.00	0.00	0.00	53.24

Segment Leq : 53.24 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 69.59 + 0.00) = 69.59 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	71.21	-1.62	0.00	0.00	0.00	0.00	69.59

Segment Leq : 69.59 dBA

Total Leq All Segments: 69.81 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 48.17 + 0.00) = 48.17 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	52.93	-4.75	0.00	0.00	0.00	0.00	48.17

Segment Leq : 48.17 dBA

Results segment # 2: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 47.22 + 0.00) = 47.22 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	52.93	-5.71	0.00	0.00	0.00	0.00	47.22

Segment Leq : 47.22 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 63.52 + 0.00) = 63.52 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	65.14	-1.62	0.00	0.00	0.00	0.00	63.52

Segment Leq : 63.52 dBA

Total Leq All Segments: 63.74 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 69.81
(NIGHT): 63.74

Filename: 20town.te Time Period: Day/Night 16/8 hours
Description: 20 Storey Tower North Facade indoor

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 45.80 / 45.80 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 2: LRT SB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT SB (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 56.80 / 56.80 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):
Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 22.80 / 22.80 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Results segment # 1: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 51.09 + 0.00) = 51.09 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	58.95	-4.85	-3.01	0.00	0.00	0.00	51.09

Segment Leq : 51.09 dBA

Results segment # 2: LRT SB (day)

Source height = 0.50 m

RT/Custom (0.00 + 50.15 + 0.00) = 50.15 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	58.95	-5.78	-3.01	0.00	0.00	0.00	50.15

Segment Leq : 50.15 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 66.38 + 0.00) = 66.38 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	71.21	-1.82	-3.01	0.00	0.00	0.00	66.38

Segment Leq : 66.38 dBA

Total Leq All Segments: 66.61 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 45.07 + 0.00) = 45.07 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	52.93	-4.85	-3.01	0.00	0.00	0.00	45.07

Segment Leq : 45.07 dBA

Results segment # 2: LRT SB (night)

Source height = 0.50 m

RT/Custom (0.00 + 44.13 + 0.00) = 44.13 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	52.93	-5.78	-3.01	0.00	0.00	0.00	44.13

Segment Leq : 44.13 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 60.32 + 0.00) = 60.32 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	65.14	-1.82	-3.01	0.00	0.00	0.00	60.32

Segment Leq : 60.32 dBA

Total Leq All Segments: 60.55 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 66.61
(NIGHT): 60.55

Filename: 20townmp.te Time Period: Day/Night 16/8 hours
Description: 20 Storey Tower North Facade Midpoint indoor

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 66.20 / 66.20 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 2: LRT SB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT SB (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 77.20 / 77.20 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):
Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 43.20 / 43.20 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Results segment # 1: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 49.49 + 0.00) = 49.49 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	58.95	-6.45	-3.01	0.00	0.00	0.00	49.49

Segment Leq : 49.49 dBA

Results segment # 2: LRT SB (day)

Source height = 0.50 m

RT/Custom (0.00 + 48.82 + 0.00) = 48.82 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	58.95	-7.12	-3.01	0.00	0.00	0.00	48.82

Segment Leq : 48.82 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 63.61 + 0.00) = 63.61 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	71.21	-4.59	-3.01	0.00	0.00	0.00	63.61

Segment Leq : 63.61 dBA

Total Leq All Segments: 63.91 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 43.47 + 0.00) = 43.47 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	52.93	-6.45	-3.01	0.00	0.00	0.00	43.47

Segment Leq : 43.47 dBA

Results segment # 2: LRT SB (night)

Source height = 0.50 m

RT/Custom (0.00 + 42.80 + 0.00) = 42.80 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	52.93	-7.12	-3.01	0.00	0.00	0.00	42.80

Segment Leq : 42.80 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 57.54 + 0.00) = 57.54 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	65.14	-4.59	-3.01	0.00	0.00	0.00	57.54

Segment Leq : 57.54 dBA

Total Leq All Segments: 57.84 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 63.91
(NIGHT): 57.84

Filename: 20towne.te Time Period: Day/Night 16/8 hours
Description: 20 Storey Tower Northeast Corner indoor

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 87.80 / 87.80 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 2: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT NB (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 98.80 / 98.80 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):
Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 64.80 / 64.80 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Results segment # 1: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 48.26 + 0.00) = 48.26 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	58.95	-7.67	-3.01	0.00	0.00	0.00	48.26

Segment Leq : 48.26 dBA

Results segment # 2: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 47.75 + 0.00) = 47.75 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	58.95	-8.19	-3.01	0.00	0.00	0.00	47.75

Segment Leq : 47.75 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 61.85 + 0.00) = 61.85 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	71.21	-6.35	-3.01	0.00	0.00	0.00	61.85

Segment Leq : 61.85 dBA

Total Leq All Segments: 62.19 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 42.24 + 0.00) = 42.24 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	52.93	-7.67	-3.01	0.00	0.00	0.00	42.24

Segment Leq : 42.24 dBA

Results segment # 2: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 41.73 + 0.00) = 41.73 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	52.93	-8.19	-3.01	0.00	0.00	0.00	41.73

Segment Leq : 41.73 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 55.78 + 0.00) = 55.78 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	90	0.00	65.14	-6.35	-3.01	0.00	0.00	0.00	55.78

Segment Leq : 55.78 dBA

Total Leq All Segments: 56.13 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 62.19
(NIGHT): 56.13

Filename: 20tows.te Time Period: Day/Night 16/8 hours
Description: 20 Storey Tower South Facade indoor

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:

Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 47.50 / 47.50 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 2: LRT SB (day/night)

1 - 4-car SRT:

Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT SB (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 59.00 / 59.00 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):

Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 24.50 / 24.50 m
Receiver height : 58.50 / 58.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Results segment # 1: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 50.93 + 0.00) = 50.93 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	58.95	-5.01	-3.01	0.00	0.00	0.00	50.93

Segment Leq : 50.93 dBA

Results segment # 2: LRT SB (day)

Source height = 0.50 m

RT/Custom (0.00 + 49.99 + 0.00) = 49.99 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	58.95	-5.95	-3.01	0.00	0.00	0.00	49.99

Segment Leq : 49.99 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 66.07 + 0.00) = 66.07 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	71.21	-2.13	-3.01	0.00	0.00	0.00	66.07

Segment Leq : 66.07 dBA

Total Leq All Segments: 66.30 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 44.91 + 0.00) = 44.91 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	52.93	-5.01	-3.01	0.00	0.00	0.00	44.91

Segment Leq : 44.91 dBA

Results segment # 2: LRT SB (night)

Source height = 0.50 m

RT/Custom (0.00 + 43.97 + 0.00) = 43.97 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	52.93	-5.95	-3.01	0.00	0.00	0.00	43.97

Segment Leq : 43.97 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 60.00 + 0.00) = 60.00 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	65.14	-2.13	-3.01	0.00	0.00	0.00	60.00

Segment Leq : 60.00 dBA

Total Leq All Segments: 60.24 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 66.30
(NIGHT): 60.24

Filename: 9podWmp.te Time Period: Day/Night 16/8 hours
Description: 9 Storey Podium West Facade indoor

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : -90.00 deg 45.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 74.40 / 74.40 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 2: LRT SB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT SB (day/night)

Angle1 Angle2 : -90.00 deg 45.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 85.90 / 85.90 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):
Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : -90.00 deg 45.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 50.30 / 50.30 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Results segment # 1: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 50.74 + 0.00) = 50.74 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	45	0.00	58.95	-6.95	-1.25	0.00	0.00	0.00	50.74

Segment Leq : 50.74 dBA

Results segment # 2: LRT SB (day)

Source height = 0.50 m

RT/Custom (0.00 + 50.12 + 0.00) = 50.12 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	45	0.00	58.95	-7.58	-1.25	0.00	0.00	0.00	50.12

Segment Leq : 50.12 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 64.71 + 0.00) = 64.71 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	45	0.00	71.21	-5.25	-1.25	0.00	0.00	0.00	64.71

Segment Leq : 64.71 dBA

Total Leq All Segments: 65.02 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 44.72 + 0.00) = 44.72 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	45	0.00	52.93	-6.95	-1.25	0.00	0.00	0.00	44.72

Segment Leq : 44.72 dBA

Results segment # 2: LRT SB (night)

Source height = 0.50 m

RT/Custom (0.00 + 44.10 + 0.00) = 44.10 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	45	0.00	52.93	-7.58	-1.25	0.00	0.00	0.00	44.10

Segment Leq : 44.10 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 58.64 + 0.00) = 58.64 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	45	0.00	65.14	-5.25	-1.25	0.00	0.00	0.00	58.64

Segment Leq : 58.64 dBA

Total Leq All Segments: 58.96 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 65.02
(NIGHT): 58.96

Filename: 9podsw.te Time Period: Day/Night 16/8 hours
Description: 9 Storey Podium Southwest Corner indoor

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : -90.00 deg 65.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 74.40 / 74.40 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 2: LRT SB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT SB (day/night)

Angle1 Angle2 : -90.00 deg 65.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 85.90 / 85.90 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):
Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : -90.00 deg 65.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 50.30 / 50.30 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Results segment # 1: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 51.34 + 0.00) = 51.34 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	65	0.00	58.95	-6.95	-0.65	0.00	0.00	0.00	51.34

Segment Leq : 51.34 dBA

Results segment # 2: LRT SB (day)

Source height = 0.50 m

RT/Custom (0.00 + 50.72 + 0.00) = 50.72 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	65	0.00	58.95	-7.58	-0.65	0.00	0.00	0.00	50.72

Segment Leq : 50.72 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 65.31 + 0.00) = 65.31 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	65	0.00	71.21	-5.25	-0.65	0.00	0.00	0.00	65.31

Segment Leq : 65.31 dBA

Total Leq All Segments: 65.62 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 45.32 + 0.00) = 45.32 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	65	0.00	52.93	-6.95	-0.65	0.00	0.00	0.00	45.32

Segment Leq : 45.32 dBA

Results segment # 2: LRT SB (night)

Source height = 0.50 m

RT/Custom (0.00 + 44.70 + 0.00) = 44.70 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	65	0.00	52.93	-7.58	-0.65	0.00	0.00	0.00	44.70

Segment Leq : 44.70 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 59.24 + 0.00) = 59.24 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	65	0.00	65.14	-5.25	-0.65	0.00	0.00	0.00	59.24

Segment Leq : 59.24 dBA

Total Leq All Segments: 59.56 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 65.62
(NIGHT): 59.56

Filename: 9pods.te Time Period: Day/Night 16/8 hours
Description: 9 Storey Podium South Facade indoor

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 75.40 / 75.40 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 2: LRT SB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT SB (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 86.90 / 86.90 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):
Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 51.30 / 51.30 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Results segment # 1: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 48.92 + 0.00) = 48.92 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	58.95	-7.01	-3.01	0.00	0.00	0.00	48.92

Segment Leq : 48.92 dBA

Results segment # 2: LRT SB (day)

Source height = 0.50 m

RT/Custom (0.00 + 48.31 + 0.00) = 48.31 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	58.95	-7.63	-3.01	0.00	0.00	0.00	48.31

Segment Leq : 48.31 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 62.86 + 0.00) = 62.86 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	71.21	-5.34	-3.01	0.00	0.00	0.00	62.86

Segment Leq : 62.86 dBA

Total Leq All Segments: 63.18 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 42.90 + 0.00) = 42.90 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	52.93	-7.01	-3.01	0.00	0.00	0.00	42.90

Segment Leq : 42.90 dBA

Results segment # 2: LRT SB (night)

Source height = 0.50 m

RT/Custom (0.00 + 42.29 + 0.00) = 42.29 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	52.93	-7.63	-3.01	0.00	0.00	0.00	42.29

Segment Leq : 42.29 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 56.79 + 0.00) = 56.79 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	65.14	-5.34	-3.01	0.00	0.00	0.00	56.79

Segment Leq : 56.79 dBA

Total Leq All Segments: 57.11 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 63.18
(NIGHT): 57.11

Filename: 9podsmpte Time Period: Day/Night 16/8 hours
Description: 9 Storey Podium South Midpoint indoor

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 82.40 / 82.40 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 2: LRT SB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT SB (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 93.90 / 93.90 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):
Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 58.30 / 58.30 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Results segment # 1: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 48.54 + 0.00) = 48.54 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	58.95	-7.40	-3.01	0.00	0.00	0.00	48.54

Segment Leq : 48.54 dBA

Results segment # 2: LRT SB (day)

Source height = 0.50 m

RT/Custom (0.00 + 47.97 + 0.00) = 47.97 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	58.95	-7.97	-3.01	0.00	0.00	0.00	47.97

Segment Leq : 47.97 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 62.31 + 0.00) = 62.31 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	71.21	-5.90	-3.01	0.00	0.00	0.00	62.31

Segment Leq : 62.31 dBA

Total Leq All Segments: 62.64 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 42.52 + 0.00) = 42.52 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	52.93	-7.40	-3.01	0.00	0.00	0.00	42.52

Segment Leq : 42.52 dBA

Results segment # 2: LRT SB (night)

Source height = 0.50 m

RT/Custom (0.00 + 41.95 + 0.00) = 41.95 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	52.93	-7.97	-3.01	0.00	0.00	0.00	41.95

Segment Leq : 41.95 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 56.24 + 0.00) = 56.24 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	65.14	-5.90	-3.01	0.00	0.00	0.00	56.24

Segment Leq : 56.24 dBA

Total Leq All Segments: 56.57 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 62.64
(NIGHT): 56.57

Filename: 9podse.te Time Period: Day/Night 16/8 hours
Description: 9 Storey Podium Southeast Corner indoor

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:

Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 89.90 / 89.90 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 2: LRT SB (day/night)

1 - 4-car SRT:

Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT SB (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 100.90 / 100.90 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):

Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 65.30 / 65.30 m
Receiver height : 25.50 / 25.50 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00

Results segment # 1: LRT NB (day)

Source height = 0.50 m

RT/Custom (0.00 + 48.16 + 0.00) = 48.16 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	58.95	-7.78	-3.01	0.00	0.00	0.00	48.16

Segment Leq : 48.16 dBA

Results segment # 2: LRT SB (day)

Source height = 0.50 m

RT/Custom (0.00 + 47.66 + 0.00) = 47.66 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	58.95	-8.28	-3.01	0.00	0.00	0.00	47.66

Segment Leq : 47.66 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 61.82 + 0.00) = 61.82 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	71.21	-6.39	-3.01	0.00	0.00	0.00	61.82

Segment Leq : 61.82 dBA

Total Leq All Segments: 62.16 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

RT/Custom (0.00 + 42.14 + 0.00) = 42.14 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	52.93	-7.78	-3.01	0.00	0.00	0.00	42.14

Segment Leq : 42.14 dBA

Results segment # 2: LRT SB (night)

Source height = 0.50 m

RT/Custom (0.00 + 41.64 + 0.00) = 41.64 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	52.93	-8.28	-3.01	0.00	0.00	0.00	41.64

Segment Leq : 41.64 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 55.75 + 0.00) = 55.75 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	0	0.00	65.14	-6.39	-3.01	0.00	0.00	0.00	55.75

Segment Leq : 55.75 dBA

Total Leq All Segments: 56.09 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 62.16
(NIGHT): 56.09

Outdoor Living Area (OLA)

Filename: amenity1.te Time Period: Day/Night 16/8 hours
Description: Shared Amenity Area #1 P1 - OLA

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : -90.00 deg 75.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 54.50 / 54.50 m
Receiver height : 1.50 / 58.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 75.00 deg
Barrier height : 6.00 m
Barrier receiver distance : 17.50 / 17.50 m
Source elevation : 90.00 m
Receiver elevation : 93.50 m
Barrier elevation : 87.50 m
Reference angle : 0.00

RT/Custom data, segment # 2: LRT SB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT SB (day/night)

Angle1 Angle2 : -90.00 deg 75.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 66.00 / 66.00 m
Receiver height : 1.50 / 58.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 75.00 deg
Barrier height : 6.00 m
Barrier receiver distance : 17.50 / 17.50 m
Source elevation : 90.00 m
Receiver elevation : 93.50 m
Barrier elevation : 87.50 m
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):
Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : -90.00 deg 75.00 deg

```

Wood depth           :      0      (No woods.)
No of house rows    :      0 / 0
Surface             :      1      (Absorptive ground surface)
Receiver source distance : 30.50 / 30.50 m
Receiver height     :      1.50 / 58.50 m
Topography          :      2      (Flat/gentle slope; with barrier)
Barrier angle1      : -90.00 deg  Angle2 : 75.00 deg
Barrier height      :      6.00 m
Barrier receiver distance : 17.50 / 17.50 m
Source elevation    :      90.00 m
Receiver elevation  :      93.50 m
Barrier elevation   :      87.50 m
Reference angle     :      0.00

```

Results segment # 1: LRT NB (day)

Source height = 0.50 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          0.50 !          1.50 !          6.06 !          93.56

```

RT/Custom (0.00 + 48.06 + 0.00) = 48.06 dBA

```

-----
Angle1 Angle2  Alpha RefLeq  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
  -90    75    0.33  58.95  -7.45  -1.05  0.00  0.00  -5.00  45.45*
  -90    75    0.66  58.95  -9.30  -1.58  0.00  0.00  0.00  48.06
-----

```

* Bright Zone !

Segment Leq : 48.06 dBA

Results segment # 2: LRT SB (day)

Source height = 0.50 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          0.50 !          1.50 !          6.31 !          93.81

```

RT/Custom (0.00 + 46.68 + 0.00) = 46.68 dBA

```

-----
Angle1 Angle2  Alpha RefLeq  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
  -90    75    0.33  58.95  -8.56  -1.05  0.00  0.00  -4.87  44.47*
  -90    75    0.66  58.95 -10.68  -1.58  0.00  0.00  0.00  46.68
-----

```

* Bright Zone !

Segment Leq : 46.68 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
0.50	1.50	4.92	92.42

RT/Custom (0.00 + 58.94 + 0.00) = 58.94 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	75	0.33	71.21	-4.10	-1.05	0.00	0.00	-7.13	58.94

Segment Leq : 58.94 dBA

Total Leq All Segments: 59.51 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
0.50	58.50	44.75	132.25

RT/Custom (0.00 + 46.94 + 0.00) = 46.94 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	75	0.00	52.93	-5.60	-0.38	0.00	0.00	-0.00	46.94*
-90	75	0.00	52.93	-5.60	-0.38	0.00	0.00	0.00	46.94

* Bright Zone !

Segment Leq : 46.94 dBA

Results segment # 2: LRT SB (night)

Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
0.50	58.50	48.19	135.69

RT/Custom (0.00 + 46.11 + 0.00) = 46.11 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	75	0.00	52.93	-6.43	-0.38	0.00	0.00	-0.00	46.11*
-90	75	0.00	52.93	-6.43	-0.38	0.00	0.00	0.00	46.11

* Bright Zone !

Segment Leq : 46.11 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

Barrier height for grazing incidence

Source ! Receiver ! Barrier ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
0.50 ! 58.50 ! 29.21 ! 116.71

RT/Custom (0.00 + 61.68 + 0.00) = 61.68 dBA

Angle1 Angle2 Alpha RefLeq D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq

-90 75 0.00 65.14 -3.08 -0.38 0.00 0.00 -0.01 61.68*
-90 75 0.00 65.14 -3.08 -0.38 0.00 0.00 0.00 61.68

* Bright Zone !

Segment Leq : 61.68 dBA

Total Leq All Segments: 61.94 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 59.51
(NIGHT): 61.94

Filename: amenity2.te Time Period: Day/Night 16/8 hours
Description: Shared Amenity Area #2 P2 - OLA

RT/Custom data, segment # 1: LRT NB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 1: LRT NB (day/night)

Angle1 Angle2 : -40.00 deg 10.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 84.50 / 84.50 m
Receiver height : 1.50 / 58.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -40.00 deg Angle2 : 10.00 deg
Barrier height : 27.00 m
Barrier receiver distance : 6.00 / 6.00 m
Source elevation : 90.00 m
Receiver elevation : 114.50 m
Barrier elevation : 87.50 m
Reference angle : 0.00

RT/Custom data, segment # 2: LRT SB (day/night)

1 - 4-car SRT:
Traffic volume : 192/24 veh/TimePeriod
Speed : 70 km/h

Data for Segment # 2: LRT SB (day/night)

Angle1 Angle2 : -40.00 deg 10.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 96.00 / 96.00 m
Receiver height : 1.50 / 58.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -40.00 deg Angle2 : 10.00 deg
Barrier height : 27.00 m
Barrier receiver distance : 6.00 / 6.00 m
Source elevation : 90.00 m
Receiver elevation : 114.50 m
Barrier elevation : 87.50 m
Reference angle : 0.00

RT/Custom data, segment # 3: BRT (day/night)

1 - Custom (87.0 dBA):
Traffic volume : 712/88 veh/TimePeriod
Speed : 80 km/h

Data for Segment # 3: BRT (day/night)

Angle1 Angle2 : -40.00 deg 10.00 deg

```

Wood depth           :      0      (No woods.)
No of house rows    :      0 / 0
Surface             :      1      (Absorptive ground surface)
Receiver source distance : 60.50 / 60.50 m
Receiver height     :      1.50 / 58.50 m
Topography          :      2      (Flat/gentle slope; with barrier)
Barrier angle1      : -40.00 deg  Angle2 : 10.00 deg
Barrier height      :      27.00 m
Barrier receiver distance : 6.00 / 6.00 m
Source elevation    :      90.00 m
Receiver elevation  :     114.50 m
Barrier elevation   :      87.50 m
Reference angle     :      0.00

```

Results segment # 1: LRT NB (day)

Source height = 0.50 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          0.50 !          1.50 !          26.69 !          114.19

```

RT/Custom (0.00 + 40.51 + 0.00) = 40.51 dBA

```

-----
Angle1 Angle2  Alpha RefLeq  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
   -40    10    0.00  58.95  -7.51  -5.56   0.00   0.00  -5.37  40.51
-----

```

Segment Leq : 40.51 dBA

Results segment # 2: LRT SB (day)

Source height = 0.50 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          0.50 !          1.50 !          26.91 !          114.41

```

RT/Custom (0.00 + 40.29 + 0.00) = 40.29 dBA

```

-----
Angle1 Angle2  Alpha RefLeq  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
   -40    10    0.00  58.95  -8.06  -5.56   0.00   0.00  -5.03  40.29
-----

```

Segment Leq : 40.29 dBA

Results segment # 3: BRT (day)

Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
0.50	1.50	25.97	113.47

RT/Custom (0.00 + 51.54 + 0.00) = 51.54 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-40	10	0.00	71.21	-6.06	-5.56	0.00	0.00	-8.06	51.54

Segment Leq : 51.54 dBA

Total Leq All Segments: 52.16 dBA

Results segment # 1: LRT NB (night)

Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
0.50	58.50	79.64	167.14

RT/Custom (0.00 + 39.86 + 0.00) = 39.86 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-40	10	0.00	52.93	-7.51	-5.56	0.00	0.00	0.00	39.86*
-40	10	0.00	52.93	-7.51	-5.56	0.00	0.00	0.00	39.86

* Bright Zone !

Segment Leq : 39.86 dBA

Results segment # 2: LRT SB (night)

Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
0.50	58.50	80.34	167.84

RT/Custom (0.00 + 39.30 + 0.00) = 39.30 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-40	10	0.00	52.93	-8.06	-5.56	0.00	0.00	0.00	39.30*
-40	10	0.00	52.93	-8.06	-5.56	0.00	0.00	0.00	39.30

* Bright Zone !

Segment Leq : 39.30 dBA

Results segment # 3: BRT (night)

Source height = 0.50 m

Barrier height for grazing incidence

Source ! Receiver ! Barrier ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
0.50 ! 58.50 ! 77.32 ! 164.82

RT/Custom (0.00 + 53.52 + 0.00) = 53.52 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-40	10	0.00	65.14	-6.06	-5.56	0.00	0.00	0.00	53.52*
-40	10	0.00	65.14	-6.06	-5.56	0.00	0.00	0.00	53.52

* Bright Zone !

Segment Leq : 53.52 dBA

Total Leq All Segments: 53.86 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 52.16
(NIGHT): 53.86


Appendix C –
Architectural Drawings

IT IS THE RESPONSIBILITY OF THE APPROPRIATE CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS ON SITE AND TO REPORT ALL ERRORS AND/OR OMISSIONS TO THE ARCHITECT.
 ALL CONTRACTORS MUST COMPLY WITH ALL PERTINENT CODES AND BY-LAWS.
 THIS DRAWING MAY NOT BE USED FOR CONSTRUCTION UNTIL SIGNED BY THE ARCHITECT.
 DO NOT SCALE DRAWINGS.
 COPYRIGHT RESERVED.


WITHOUT PREJUDICE




L8-9 PLAN



L10 PLAN




L11-20 PLAN



MAIN ROOF

No.	DESCRIPTION	DD.MM.YY
REVISIONS:		

ARCHITECT SEAL: _____ NORTH ARROW:  TRUE NORTH

CLIENT:  SMARTCENTRES


ARCHITECT:  rla/architecture
 56 Beech Street, Ottawa, Ontario K1S 3J6
 t.613.724.9932 f.613.724.1209 www.rodericklathey.ca

PROJECT TITLE: Ottawa, ON
 SmartCentres South Keys

SHEET TITLE: FLOOR PLANS

DRAWN: Author	CHECKED: Checker
SCALE: 1 : 250	SHEET No: A-102
PROJECT No: 2030	

PAPER SIZE: ISO Full Base B1 (707.00 x 1000.00mm) D07-1023-1082




EAST ELEVATION



NORTH ELEVATION



SOUTH ELEVATION



WEST ELEVATION

IT IS THE RESPONSIBILITY OF THE APPROPRIATE CONTRACTOR TO CHECK AND VERIFY ALL DIMENSIONS ON SITE AND TO REPORT ALL ERRORS AND/OR OMISSIONS TO THE ARCHITECT.
ALL CONTRACTORS MUST COMPLY WITH ALL PERTINENT CODES AND BY-LAWS.
THIS DRAWING MAY NOT BE USED FOR CONSTRUCTION UNTIL SIGNED BY THE ARCHITECT.
DO NOT SCALE DRAWINGS.
COPYRIGHT RESERVED.

WITHOUT PREJUDICE

No.	DESCRIPTION	DD.MM.YY
REVISIONS:		
ARCHITECT SEAL:	NORTH ARROW:	

CLIENT:



SMARTCENTRES

ARCHITECT:

rla/architecture
56 Beech Street, Ottawa, Ontario K1S 3J6
t.613.724.9932 f.613.724.1209 www.rodericklathey.ca

PROJECT TITLE:

Ottawa, ON

SmartCentres South Keys

SHEET TITLE:

BUILDING ELEVATIONS

DRAWN:	CHECKED:
Author	Checker

SCALE:	SHEET No.:
1 : 250	A-200

PROJECT No.:	
2030	

PLOT DATE: 2023-10-11 10:15:50 AM # 18595

PAPER SIZE: ISO Full Base 61 (707.0x 1000.0mm) 001-12-21-1082

Appendix D –
Sound Transmission Class (STC)
Calculations

Bedroom - West Façade of 3-Bedroom Corner Unit (20th Floor of 20-Storey Tower)

Reverse Evaluation of Sound Transmission Class (STC) for Building Components

1.0	Free field sound level	<u>63.74</u> dBA	Noise source
	Correction for reflections	<u>3</u> dBA	Rail
	Outdoor sound level	66.74 dBA	Indoor Quarters
	Indoor sound level (Night time)	<u>35</u> dBA	Sleeping
	Required Noise Reduction (NR)	<u>31.74</u> dB	Subtract indoor from outdoor sound level
2.0	Sound angle of incidence	0 to 90 degrees	C ₁ Correction from Table 7.7
			<u>0</u> dB
			Sum <u>31.74</u> dB

	Component:	Wall	STC	<u>50</u> dB
3.0	Noise spectrum type	D - Mixed Road Traffic, Distant Aircraft	C ₄ from Table 7.10	<u>7</u> dB
	Component category	d. Sealed thick window, or exterior wall, or roof/ceiling	Correction	<u>-7</u> dB
4.0	Room floor area	<u>95.9</u> m ²	15.64129 % of floor area	
	Component Area	<u>15</u> m ²		
	Room absorption category	Intermediate	C ₃ from Table 7.9	<u>-5</u> dB
			Correction	<u>5</u> dB
5.0	Noise reduction if only this component transmits sound			<u>48</u> dB
6.0	Required noise reduction (from Step 1)			<u>32</u> dB
7.0	Term C ₂ : Subtract the Required NR from the Noise Reduction for this component			<u>16</u> dB
8.0	Determine from Table 7.8 the corresponding value of total transmitted sound energy			<u>5</u> %

	Component:	Window	After step 2	<u>31.74</u> dB
9.0	Transmits	95 % of total sound energy	C ₂ from Table 7.8	<u>0</u> dB
10.0	Room floor area	<u>95.9</u> m ²	25.02607 % of floor area	
	Component Area	<u>24</u> m ²		
	Room absorption category	Intermediate	C ₃ from Table 7.9	<u>-5</u> dB
11.0	Noise spectrum type	D - Mixed Road Traffic, Distant Aircraft	C ₄ from Table 7.10	<u>7</u> dB
	Component category	d. Sealed thick window, or exterior wall, or roof/ceiling		
			STC=NR+C ₁ +C ₂ +C ₃ +C ₄	Required STC <u>34</u>

Tables from Environmental Noise Assessment in Land Use Planning, dated 1999, published by the MOE

Living/Dining Room - West Façade of 3-Bedroom Corner Unit (20th Floor of 20-Storey Tower)

Reverse Evaluation of Sound Transmission Class (STC) for Building Components

1.0	Free field sound level	<u>69.81</u> dBA	Noise source
	Correction for reflections	<u>3</u> dBA	Rail
	Outdoor sound level	<u>72.81</u> dBA	Indoor Quarters
	Indoor sound level (Daytime)	<u>40</u> dBA	Living
	Required Noise Reduction (NR)	<u>32.81</u> dB	Subtract indoor from outdoor sound level
2.0	Sound angle of incidence	0 to 90 degrees	C ₁ Correction from Table 7.7
			<u>0</u> dB
			Sum <u>32.81</u> dB

	Component:	Wall	STC	<u>50</u> dB
3.0	Noise spectrum type	D - Mixed Road Traffic, Distant Aircraft	C ₄ from Table 7.10	<u>7</u> dB
	Component category	d. Sealed thick window, or exterior wall, or roof/ceiling	Correction	<u>-7</u> dB
4.0	Room floor area	<u>95.9</u> m ²	15.64129 % of floor area	
	Component Area	<u>15</u> m ²		
	Room absorption category	Intermediate	C ₃ from Table 7.9	<u>-5</u> dB
			Correction	<u>5</u> dB
5.0	Noise reduction if only this component transmits sound			<u>48</u> dB
6.0	Required noise reduction (from Step 1)			<u>33</u> dB
7.0	Term C ₂ : Subtract the Required NR from the Noise Reduction for this component			<u>15</u> dB
8.0	Determine from Table 7.8 the corresponding value of total transmitted sound energy			<u>5</u> %

	Component:	Window	After step 2	<u>32.81</u> dB
9.0	Transmits	95 % of total sound energy	C ₂ from Table 7.8	<u>0</u> dB
10.0	Room floor area	<u>95.9</u> m ²	25.02607 % of floor area	
	Component Area	<u>24</u> m ²		
	Room absorption category	Intermediate	C ₃ from Table 7.9	<u>-5</u> dB
11.0	Noise spectrum type	D - Mixed Road Traffic, Distant Aircraft	C ₄ from Table 7.10	<u>7</u> dB
	Component category	d. Sealed thick window, or exterior wall, or roof/ceiling		
			STC=NR+C ₁ +C ₂ +C ₃ +C ₄	Required STC <u>35</u>

Tables from Environmental Noise Assessment in Land Use Planning, dated 1999, published by the MOE