

1039 Terry Fox Drive 5331 Fernbank Road (117198)
 Summary of Hydraulic Grade Line (HGL) Elevations



MH ID	Obvert Elevation (m)	T/G Elevation (m)	HGL Elevation ¹ (m)	MIN USF (m)	Surcharge (m)	Clearance from T/G (m)	HGL in Stress Test ¹ (m)
MH200	95.67	97.45	95.50	95.97	0.00	1.95	95.51
MH201	95.50	97.73	95.48	95.80	0.00	2.25	95.49
MH202	95.36	97.50	95.42	95.72	0.06	2.08	95.43
MH203	95.25	97.50	95.36	95.66	0.11	2.14	95.37
MH204	95.22	97.44	95.35	95.65	0.13	2.09	95.35
MH205	95.18	97.31	95.32	95.62	0.14	1.99	95.33
MH206	95.09	97.35	95.27	95.57	0.18	2.08	95.27
MH207	95.02	97.39	95.20	95.50	0.18	2.19	95.20
MH208	94.97	97.04	95.14	95.44	0.17	1.90	95.14
MH209	94.92	96.76	95.10	95.40	0.18	1.66	95.10
MH210	95.38	97.43	95.44	95.74	0.06	1.99	95.44
MH211	95.47	97.81	95.45	95.77	0.00	2.36	95.45
MH212	95.63	98.20	95.48	95.93	0.00	2.72	95.48
MH213	95.71	98.30	95.56	96.01	0.00	2.74	95.57
MH214	95.60	98.05	95.32	95.90	0.00	2.73	95.32
MH215	95.54	98.09	95.31	95.84	0.00	2.78	95.31
MH216	95.46	97.95	95.29	95.76	0.00	2.66	95.29
MH217	95.34	98.02	95.27	95.64	0.00	2.75	95.27
MH218	95.23	97.78	95.25	95.55	0.02	2.53	95.25
MH219	95.21	97.74	95.24	95.54	0.03	2.50	95.24
MH220	95.13	97.88	95.21	95.51	0.08	2.67	95.21
MH221	95.08	97.87	95.19	95.49	0.11	2.68	95.20
MH222	95.04	97.60	95.18	95.48	0.14	2.42	95.18
MH223	95.28	97.90	95.27	95.58	0.00	2.63	95.27
MH224	95.19	97.83	95.27	95.57	0.08	2.56	95.27
MH225	95.11	97.44	95.24	95.54	0.13	2.20	95.24

¹ 3-hour Chicago Storm; Fixed outfall (100yr HGL in MH1013 = 95.05).