



Engineers, Planners & Landscape Architects

Engineering

Land/Site
Development

Municipal
Infrastructure

Environmental/
Water Resources

Traffic/
Transportation

Recreational

Planning

Land/Site
Development

Planning Application
Management

Municipal Planning
Urban Design

Expert Witness
(OLT)

Wireless Industry

Landscape Architecture

Streetscapes & Public
Amenities

Open Space, Parks &
Recreation

Community &
Residential

Commercial &
Institutional

Environmental
Restoration

Proposed Residential Development 249-255 Richmond Road & 372 Tweedsmuir Avenue Transportation Impact Assessment

Engineering excellence.

Planning progress.

Liveable landscapes.

Proposed Residential Development
249-255 Richmond Road & 372 Tweedsmuir Avenue
Transportation Impact Assessment

Prepared By:

NOVATECH

Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario
K2M 1P6

October 26, 2021

Revised: March 25, 2022

Revised: April 18, 2023

Revised: July 31, 2025

Novatech File: 121193

Ref: R-2021-124

July 31, 2025

City of Ottawa
Planning and Growth Management Department
110 Laurier Ave. W. 4th Floor
Ottawa, ON K1P 1J1

Attention: Mr. Wally Dubyk
Project Manager, Infrastructure Approvals

Dear Mr. Dubyk:

Reference: 249-255 Richmond Road & 372 Tweedsmuir Avenue
Revised Transportation Impact Assessment
Novatech File No.: 121193

We are pleased to submit the following revised Transportation Impact Assessment Report in support of Zoning By-law Amendment and Site Plan Control applications for the above noted properties, for your review and signoff. The structure and format of this report is in accordance with the City of Ottawa Transportation Impact Assessment Guidelines (2017).

The original TIA in support of this development was submitted in October 2021, followed by two revised TIAs in March 2022 and April 2023. This revised TIA has been prepared to reflect changes in the site plan.

If you have any questions or comments regarding this report, please feel free to contact Brad Byvelds or the undersigned.

Yours truly,

NOVATECH



Mohammed Talha, M. Eng.
Engineering Intern | Transportation

Table of Contents

1.0 SCREENING	1
1.1 Introduction	1
1.2 Proposed Development	1
1.3 Screening Form	2
2.0 SCOPING	2
2.1 Existing Conditions	2
2.1.1 Roadways	2
2.1.2 Study Area Intersections	3
2.1.3 Driveways	4
2.1.4 Pedestrian and Cycling Facilities	4
2.1.5 Area Traffic Management	4
2.1.6 Transit	5
2.1.7 Existing Traffic Volumes	7
2.1.8 Collision Records	8
2.2 Planned Conditions	9
2.2.1 Transportation Projects	9
2.2.2 Other Area Developments	12
2.3 Study Area and Time Periods	12
2.4 Exemptions Review	13
3.0 FORECASTING	13
3.1 Development Generated Travel Demand	13
3.1.1 Trip Generation	13
3.1.2 Trip Distribution	18
3.2 Background Traffic	18
3.2.1 Other Area Developments	18
3.2.2 General Background Growth Rate	19
4.0 ANALYSIS	20
4.1 Development Design	20
4.1.1 Design for Sustainable Modes	20
4.2 Parking	23
4.3 Boundary Streets	23
4.3.1 Pedestrian Level of Service (PLOS)	23
4.3.2 Bicycle Level of Service (BLOS)	24
4.3.3 Transit Level of Service (TLOS)	24
4.3.4 Truck Level of Service (TkLOS)	24
4.3.5 Segment MMLOS Summary	25
4.4 Access Intersections	25
4.5 Transportation Demand Management	26
4.5.1 Context for TDM	26
4.5.2 Need and Opportunity	27
4.5.3 TDM Program	27
5.0 CONCLUSIONS AND RECOMMENDATIONS	27

Figures

Figure 1: Study Area	1
Figure 2: OC Transpo Bus Stop Locations	6
Figure 3: Existing Traffic Volumes	7
Figure 4: LRT Phase 2 - Confederation Line Extension West	11

Figure 5: 2026 Background Traffic Volumes	19
Figure 6: 2031 Background Traffic Volumes	20
Figure 7: Existing Pavement Markings and Signage Drawing	22

Tables

Table 1: OC Transpo Route Information	6
Table 2: Collision History Summary	8
Table 3: TIA Exemptions	13
Table 4: Person Trips Generated by Existing Development	14
Table 5: Existing Development – Peak Hour Person Trips	14
Table 6: Trips Generated by Proposed Residential Development	15
Table 7: TRANS and TOD Mode Share Comparison	15
Table 8: Proposed Residential Development – Peak Period Person Trips	15
Table 9: Proposed Residential Development – Peak Hour Person Trips	16
Table 10: Trips Generated by Proposed Commercial Development	16
Table 11: Proposed Commercial Development – Peak Hour Person Trips	17
Table 12: Net Person Trip Generation	17
Table 13: Minimum Parking Requirements	23
Table 14: PLOS Segment Table	24
Table 15: BLOS Segment Analysis	24
Table 16: TLOS Segment Analysis	24
Table 17: TkLOS Segment Analysis	25
Table 18: Segment MMLOS Summary	25

Appendices

Appendix A: Site Plan
Appendix B: TIA Screening Form
Appendix C: OC Transpo Maps
Appendix D: Traffic Count Data
Appendix E: Collision Records
Appendix F: Other Area Developments
Appendix G: TDM Checklists

EXECUTIVE SUMMARY

This Transportation Impact Assessment (TIA) has been prepared in support of Zoning By-law Amendment and Site Plan Control applications for the subject property at 249-255 Richmond Road and 372 Tweedsmuir Avenue located in Ward 15, Kitchissippi, in Ottawa. Currently, the site has an area of approximately 0.22 hectares (0.54 acres) and is occupied by a commercial retail building, a restaurant, and a single-family dwelling.

The subject site is surrounded by the following:

- Residential properties to the north;
- Existing commercial developments and Tweedsmuir Avenue to the east;
- Gas station, existing residential properties and Richmond Road to the south;
- Existing commercial developments and Athlone Avenue to the west.

The subject site is designated as 'Corridor – Mainstreet' (Richmond Road) on Schedule B2 of the City of Ottawa's Official Plan. The implemented zoning for the property is part of the Mixed Use/Commercial Zones, and more specifically the 'Traditional Mainstreet' zone (TM), which allows for a broad range of uses including retail, service commercial, office, residential and institutional uses, including mixed-use buildings but excluding auto-related uses.

The proposed development will replace the existing commercial retail building, restaurant, and single residential unit with a nine-storey condo building containing 127 dwelling units, approximately 394 square metres of retail space and 212 square metres of restaurant space. The development is anticipated to be constructed in a single phase with full occupancy in the year 2026. Access will be provided via the existing commercial driveway to Tweedsmuir Avenue. An existing residential driveway to Tweedsmuir Avenue will be removed, as well as two existing driveways to Richmond Road. The development has proposed 77 underground vehicle parking spaces. Additionally, 2 bicycle parking spaces will be provided at-grade near the Richmond Road building entrance, 30 will be provided within the building lobby and 128 will be provided within the underground parking garage. In total, 160 bicycle parking spaces will be provided.

The study area for this report includes the boundary street Richmond Road, and the study area intersections at Richmond Road/Athlone Avenue, Richmond Road/Tweedsmuir Avenue, and Richmond Road/McRae Avenue.

The selected time periods for the analysis are the weekday AM and PM peak hours, as they represent the 'worst case' combination of site-generated traffic and adjacent street traffic. The proposed development is expected to be completed with full occupancy by the year 2026. As such, this TIA considers the weekday AM and PM peak hours for the buildout year 2026 and horizon year 2031.

The conclusions and recommendations of this TIA can be summarized as follows:

Development Design

- Sidewalk connections will be provided between the building entrance and Richmond Road and Tweedsmuir Avenue.
- Sidewalks will be depressed and continuous across the parking garage access in accordance with City standards.

- Two bicycle parking spaces will be provided at-grade near the Richmond Road building entrance, 30 spaces will be provided within the building lobby, and 128 will be provided within the underground parking garage. In total, 160 bicycle parking spaces will be provided.
- All required Transportation Demand Management (TDM)-supportive design and infrastructure measures in the checklist are met.
- Garbage bins will be wheeled up the parking ramp for curbside private pick-up on Tweedsmuir Avenue. The fire route for the development is curbside along Richmond Road and Tweedsmuir Avenue.
- Loading operations for the residential function of the building will take place along Tweedsmuir Avenue adjacent to the east entrance. A holding room is provided adjacent to the east entrance to facilitate a shorter unloading time, hold furniture etc. which limits the amount of time that the unloading vehicles is parked on Tweedsmuir Avenue. Loading for the commercial developments will occur on-street along Richmond Road.
- No changes to the existing signage are proposed along the subject site's frontage.

Parking

- The proposed vehicular parking spaces adhere to the requirements of the City's *Zoning By-law* (ZBL).
- Relief from the ZBL Exception 2900 is being sought for the minimum number of bicycle parking spaces that are required. A total of 160 bicycle parking spaces are proposed for the development, equating to a rate of approximately 1.25 spaces per unit.

Boundary Street Design

- Richmond Road and Tweedsmuir Avenue have been evaluated using the targets set for arterial and local roadways within 600m of a rapid transit stop.
- The target pedestrian level of service (PLOS) is not achieved on either Richmond Road or Tweedsmuir Avenue. To achieve the target PLOS A along Richmond Road, either a reduction in the posted speed or Annual Average Daily Traffic (AADT) volumes is required. To achieve the target PLOS A along Tweedsmuir Avenue, a 2m sidewalk and boulevard greater than 0.5m is required. The proposed development will provide a 2.0m sidewalk adjacent to the curb with planters behind the sidewalk.
- The target bicycle level of service (BLOS) is not achieved on either Richmond Road or Tweedsmuir Avenue. To achieve the target BLOS C along Richmond Road, bike lanes are required. To achieve the target BLOS D along Tweedsmuir Avenue, a reduction in the operating speed is required. This is identified for the City's consideration.
- The target transit level of service (TLOS) is not achieved on Richmond Road. To achieve the target TLOS D along Richmond Road, a reduction in parking/driveway friction is required.
- The target truck level of service (TkLOS) target of E is met on Richmond Road due to lanes that measure more than 3.7m.

Access Intersections

- The width of the proposed access adheres to the requirements of the City's *Private Approach By-law* (PABL) and ZBL.
- The location of the proposed access adheres to the requirements of the PABL.
- A maximum grade of 5% will be provided for a distance of 13.2m behind the sidewalk and 8.7m within the private property. As the proposed grading meets the TAC

recommendations, and adequate sightlines for pedestrians crossing the access will be maintained, a waiver to Section 25 (1)(u) of the PABL is recommended.

- For drivers exiting the property, adequate sightlines turning left and right out of the proposed access can also be provided, as long as any proposed trees and shrubs are trimmed and maintained.

Transportation Demand Management

- The following measures will be implemented upon completion of the proposed development:
 - Display local area maps with walking/cycling access routes and key destinations at major entrances;
 - Display relevant transit schedules and route maps at entrances;
 - Provide real-time arrival information display at entrances;
 - Offer PRESTO cards preloaded with one monthly transit pass on residence purchase/ move-in, to encourage residents to use resident;
 - Unbundle parking cost from purchase price (condominium);
 - Unbundle parking cost from monthly rent (multi-family);
 - Provide a multimodal travel option information package to new residents;

Based on the foregoing, the proposed development is recommended from a transportation perspective.

1.0 SCREENING

1.1 Introduction


This Transportation Impact Assessment (TIA) has been prepared in support of Zoning By-law Amendment and Site Plan Control applications for the subject property at 249-255 Richmond Road and 372 Tweedsmuir Avenue located in Ward 15, Kitchissippi, in Ottawa. Currently, the site has an area of approximately 0.22 hectares (0.54 acres) and is occupied by a commercial retail building, a restaurant, and a single-family dwelling.

The subject site is surrounded by the following:

- Residential properties to the north;
- Existing commercial developments and Tweedsmuir Avenue to the east;
- Gas station, existing residential properties and Richmond Road to the south;
- Existing commercial developments and Athlone Avenue to the west.

A view of the subject site and study area is provided in **Figure 1**.

Figure 1: Study Area



1.2 Proposed Development

The subject site is designated as 'Corridor – Mainstreet' (Richmond Road) on Schedule B2 of the City of Ottawa's Official Plan. The implemented zoning for the property is part of the Mixed Use/Commercial Zones, and more specifically the 'Traditional Mainstreet' zone (TM), which

allows for a broad range of uses including retail, service commercial, office, residential and institutional uses, including mixed-use buildings but excluding auto-related uses.

The proposed development will replace the existing commercial retail building, restaurant, and single residential unit with a nine-storey condo building containing 127 dwelling units, approximately 394 square metres of retail space and 212 square metres of restaurant space. The development is anticipated to be constructed in a single phase with full occupancy in the year 2026. Access will be provided via the existing commercial driveway to Tweedsmuir Avenue. An existing residential driveway to Tweedsmuir Avenue will be removed, as well as two existing driveways to Richmond Road. The development has proposed 77 underground vehicle parking spaces. Additionally, 2 bicycle parking spaces will be provided at-grade near the Richmond Road building entrance, 30 will be provided within the building lobby and 128 will be provided within the underground parking garage. In total, 160 bicycle parking spaces will be provided.

A copy of the site plan is included in **Appendix A**.

1.3 Screening Form

The City's 2017 *TIA Guidelines* identify three triggers for completing a TIA report, including trip generation, location, and safety. The criteria for each trigger are outlined in the City's TIA Screening Form. The trigger results are as follows:

- Trip Generation Trigger – The net traffic generated by the site development is anticipated to generate marginally over 60 person trips/peak hour; after discussion with City staff, it has been determined that further assessment is **not required** based on this trigger.
- Location Triggers – The proposed development is located within a 'Design Priority Area and/or Transit-Oriented Development Zone;' further assessment is **required** based on this trigger.
- Safety Triggers – The proposed development does not flag any safety triggers; further assessment is **not required** based on this trigger.

A copy of the TIA Screening Form is included in **Appendix B**.

2.0 SCOPING

2.1 Existing Conditions

2.1.1 Roadways

All roadways within the study area fall under the jurisdiction of the City of Ottawa.

Richmond Road is an arterial roadway that runs on an east-west alignment between Baseline Road and Island Park Drive. East of Island Park Drive, Richmond Road continues as Wellington Street and West of Baseline Road, Richmond Road continues as Robertson Road. Within the study area, Richmond Road has a two-lane undivided urban cross-section, sidewalks on both sides of the roadway, and a regulatory speed limit of 50 km/h under the Highway Traffic Act. Richmond Road is classified as a full-load truck route within the study area. On-street parking is

permitted on both sides of the road with a maximum 90-minute time restriction between 7:00AM and 7:00PM. The City of Ottawa's Official Plan does not identify any ROW protection on Richmond Road adjacent to the site.

Athlone Avenue is a local roadway that runs on a north-south alignment between Scott Street and south of Wesley Avenue. North of Richmond Road, Athlone Avenue has a two-lane undivided urban cross-section, sidewalks on the west side of the roadway. South of Richmond Road, it has a two-lane undivided rural cross section and has an unposted regulatory speed limit of 50 km/h under the Highway Traffic Act. Within the study area, Athlone Avenue is not classified as a truck route and prohibits trucks from entering the road. On-street parking is permitted on the east side of the road, with a maximum 60-minute time restriction between 7:00AM and 7:00PM on weekdays.

Tweedsmuir Avenue is a local roadway that runs on a north-south alignment between Scott Street and Currell Avenue. Within the study area, Tweedsmuir Avenue has a two-lane undivided urban cross-section, sidewalks on the eastern side of the roadway, and an unposted regulatory speed limit of 50 km/h under the Highway Traffic Act. Tweedsmuir Avenue is not classified as a truck route and prohibits trucks from entering the road. On-street parking is permitted only on the western side of the road.

McRae Avenue is a local roadway that runs on a north-south alignment between Scott Street and Richmond Road. Within the study area, McRae Avenue typically has a two-lane undivided urban cross-section, sidewalks on both sides of the roadway, and an unposted regulatory speed limit of 50 km/h under the Highway Traffic Act. McRae Avenue is classified as a restricted load truck route. On-street parking is not permitted on both sides of the road.

2.1.2 Study Area Intersections

Richmond Road/Athlone Avenue

- Unsignalized (two-way stop-controlled) four-legged intersection
- All Approaches: one shared left turn/through/right turn lane
- Additional Information: an intersection pedestrian signal is provided on the west approach and standard pedestrian crossings on the north and south approaches



Richmond Road/Tweedsmuir Avenue

- Unsignalized (two-way stop-controlled) four-legged intersection
- All Approaches: one shared left turn/through/right turn lane
- Additional Information: standard pedestrian crossings on the north and south approaches



Richmond Road/McRae Road

- Signalized four-legged intersection
- North Approach: one shared left turn/through/right turn lane
- South/East/West Approaches: one left turn lane and one shared through/right turn lane
- Additional Information: standard pedestrian crossings on all approaches

**2.1.3 Driveways**

In accordance with the City's *2017 TIA Guidelines*, a review of driveways on the boundary streets within 200m of the proposed development is provided as follows:

Richmond Road, North Side:

- One driveway to businesses at 205 Richmond Road
- Two driveways to a car dealership at 225 Richmond Road
- One driveway to businesses at 277 Richmond Road

Richmond Road, South Side:

- Two driveways to a gas station at 256 Richmond Road
- One driveway to a business at 274 Richmond Road
- One driveway to a bank at 288 Richmond Road

Tweedsmuir Avenue, North of Richmond Road:

- One driveway to businesses at the car dealership.
- 15 and 21 driveways to residences on the east and west sides of the roadway, respectively.

2.1.4 Pedestrian and Cycling Facilities

Concrete and/or unit paver sidewalks are provided on both sides of Richmond Road, McRae Avenue, and on one side of Tweedsmuir Avenue and Athlone Avenue north of Richmond Road.

Within the study area, Richmond Road is classified as a suggested bicycle route. Athlone Avenue, Tweedsmuir Avenue, and McRae Road do not have any cycling infrastructure (mixed traffic).

2.1.5 Area Traffic Management

The following Transportation Management Implementation Plan was developed by the City of Ottawa and will have an impact on the proposed development:

- *Richmond Road/Westboro Transportation Management Implementation Plan*: this long-term plan identifies a set of programs, policies, and infrastructure improvements that promote a shift to more sustainable modes of transport.

In addition, the following has been completed as part of the area traffic management:

- Richmond Road eastbound has lane hatch markings on the curb at the intersection with Athlone Avenue and Tweedsmuir Avenue to prevent drivers from using it as a turn lane.
- No Heavy Trucks (Rb-62) signs are implemented on Athlone Avenue and Tweedsmuir Avenue north of Richmond Road.

- Athlone Avenue north of Richmond Road has a playground ahead (Wc-3) sign in advance of the pedestrian connection to Lion's Park.
- Tweedsmuir Avenue, south of Richmond Road, has a speed bump, mid-block and intersection narrowings.
- Tweedsmuir Avenue, north of Richmond Road has flex stakes along with Traffic Calmed Neighbourhood signage.

2.1.6 Transit

The Westboro Transit Station (a future Light Rail Transit station) is currently operating using temporary bus platforms on Scott Street at Athlone Avenue and Tweedsmuir Avenue, at a walking distance of approximately 300m from the subject site. This station currently services bus routes 57, 60, 61, 62, 63, 66, 67, 73, 74, 75, 81, 82, 87, 256, 261, 262, 263, 265, 266, 275, 277, and 279.

There are several other bus stops within 400 m of the subject site. A summary of the closest bus stops and routes along Richmond Road is provided as follows:

Richmond Road/Kirkwood Avenue

- Stop #2389: Services bus routes 11, 81
- Stop #6929: Services bus routes 51, 81
- Stop #6930: Services bus route 51

Richmond Road/McRae Avenue

- Stop #4863: Services bus route 11
- Stop #2356: Services bus routes 11, 81
- Stop #7377: Services bus routes 81

Richmond Road/Eden Avenue

- Stop #4864: Services bus route 11

Richmond Road/Edgewood Avenue

- Stop #4865: Services bus route 11

Richmond Road/Churchill Avenue

- Stop #4870: Services bus route 11
- Stop #4876: Services bus routes 11

Location of these transit stops are shown in **Figure 2**. A summary of the various routes which serve the study area is included in **Table 1**. OC Transpo maps for the routes outlined above and a portion of the OC Transpo System Map are included in **Appendix C**.

Figure 2: OC Transpo Bus Stop Locations




Table 1: OC Transpo Route Information

Route	From ↔ To	Frequency
11	Waller ↔ Bayshore	15–30 minutes headway depending on peak/off-peak hours, 7 days a week, all day service
51	Tunney's Pasture ↔ Britannia	30-minute headways, 7 days a week, all day service
57	Tunney's Pasture & N Rideau ↔ Carling Campus	15-minutes headway for buses starting from Bayshore Station and Tunney's Pasture Station, 15–30 minutes headway for buses starting from Carling Campus depending on peak/off-peak hours, 7 days a week, all day service
60	Cope / Terry Fox ↔ Tunney's Pasture	30-minutes headway, Mon-Fri, all day service
61	Stittsville ↔ Tunney's Pasture	15-30 minutes headway for buses starting from Terry Fox and Tunney's Pasture, 30-minutes headway for buses starting from Cardelrec-Goulbourn Complex, 7 days a week, all day service
62	Stittsville ↔ Tunney's Pasture	30-minutes headway, 7 days a week, all day service
63	Briarbrook ↔ Tunney's Pasture	15-30 minutes headway depending on peak/off-peak hours, 7 days a week, all day service
66	Innovation ↔ Tunney's Pasture	30-minutes headway, Mon-Fri, peak periods only
67	Terry Fox / Tunney's Pasture ↔ Cope	30-minutes headway, 7 days a week, all day service
73	Tunney's Pasture ↔ Fallowfield / Limebank	30-minutes headway, Mon-Fri, all day service
74	Tunney's Pasture ↔ Limebank	15-minutes headway, 7 days a week, all day service
75	Cambrian ↔ Tunney's Pasture	7-15 minutes headway, 7 days a week, all day service
81	Tunney's Pasture ↔ Bayshore	30-minutes headway, 7 days a week, all day service

Route	From ↔ To	Frequency
82	Tunney's Pasture / Lincoln Fields ↔ Baseline	30 minutes headway, 7 days per week, all day service
87	Tunney's Pasture ↔ Baseline	15 minutes headway, 7 days per week, all day service
256	Tunney's Pasture ↔ Bridlewood	30 minutes headway, Mon-Fri, peak periods only
261	Kimpton ↔ Tunney's Pasture	45-55 minutes headway, Mon-Fri, peak periods only
262	Tunney's Pasture ↔ West Ridge	30-50 minutes headway, Mon-Fri, peak periods only
263	Tunney's Pasture ↔ Richmond	60 minutes headway, Mon-Fri, peak periods only
265	Tunney's Pasture ↔ Terry Fox	30 minutes headway, Mon-Fri, peak periods only
266	Springbrook ↔ Tunney's Pasture	40-60 minutes headway, Mon-Fri, peak periods only
275	Half Moon Bay ↔ Tunney's Pasture	30 minutes headway, Mon-Fri, peak periods only
277	Tunney's Pasture ↔ Nepean Woods	30 minutes headway, Mon-Fri, peak periods only
279	Manotick ↔ Tunney's Pasture	60 minutes headway, Mon-Fri, peak periods only


2.1.7 Existing Traffic Volumes

Weekday traffic counts completed by the City of Ottawa were used to determine the existing pedestrian, cyclist, and vehicular traffic volumes at the study area intersections. The traffic counts were completed on the following dates:

- Richmond Road/Athlone Avenue July 18, 2019
- Richmond Road/McRae Avenue January 23, 2020

It is noted that the city does not have any traffic counts at the Richmond Road/Tweedsmuir Avenue intersection. Through traffic volumes along Richmond Road have been estimated based on the January 2020 traffic count at Richmond Road/Athlone Avenue. Traffic count data is included in **Appendix D**. Traffic volumes within the study area are shown in **Figure 3**.

Figure 3: Existing Traffic Volumes



2.1.8 Collision Records

Historical collision data from the last five years was obtained from the City's Public Works and Service Department for the study area intersections. Copies of the collision summary reports are included in **Appendix E**.

The collision data has been evaluated to determine if there are any identifiable collision patterns, which are defined in the 2017 TIA Guidelines as 'more than six collisions in five years' for any one movement. The number of collisions at each intersection from January 1, 2015, to December 31, 2019, is summarized in **Table 2**.

Table 2: Collision History Summary

Intersection/Road Segment	Impact Types					Total
	Angle	Rear-end	Sideswipe	Turning	SMV ¹ /Other	
Richmond Road/Athlone Avenue	5	1	1	-	1	8
Richmond Road/Tweedsmuir Avenue	4	1	-	1	1	7
Richmond Road/McRae Avenue	2	6	1	1	4	14
Richmond Road btwn Athlone Avenue and Tweedsmuir Avenue	4	-	1	-	1	6
Richmond Rd btwn Tweedsmuir Avenue and McRae Avenue	-	-	-	-	2	2

1. SMV: Single Motor Vehicle

Richmond Road/Athlone Avenue

A total of 8 collisions were reported at this intersection over the last five years, of which there were one rear-end impact, one sideswipe impact, five angle impacts, and one single-vehicle/other impacts. Only one of the collisions at this location caused injuries, but none caused fatalities. None of the collisions involved cyclists, and none involved a pedestrian.

Of the eight collisions at this location, six of them occurred during clear conditions where weather was not a factor. Additionally, of the eight collisions, four of them occurred during daylight hours.

As there are less than 6 collisions of any specific impact type, there are no identifiable collision patterns at the intersection of Richmond Road and Athlone Avenue.

Richmond Road/Tweedsmuir Avenue

A total of 7 collisions were reported at this intersection over the last five years, of which there were one rear-end impact, one turning movement impact, four angle impacts, and one single-vehicle/other impacts. Three of the collisions caused injuries, but none caused fatalities. One of the collisions involved cyclists, and none involved a pedestrian.

Of the seven collisions at this location, four of them occurred during clear conditions where weather was not a factor. Additionally, of the seven collisions, four of them occurred during daylight hours.

As there are less than 6 collisions of any specific impact type, there are no identifiable collision patterns at the intersection of Richmond Road and Tweedsmuir Avenue.

Richmond Road/McRae Avenue

A total of 14 collisions were reported at this intersection over the last five years, of which there were six rear-end impacts, one sideswipe impact, one turning movement impact, two angle impacts, and four single-vehicle/other impacts. Four of the collisions caused injuries, but none caused fatalities. None of the collisions involved cyclists, and three involved a pedestrian.

Of the 14 collisions at this location, eleven of them occurred during clear conditions where weather was not a factor. Additionally, of the 14 collisions, twelve of them occurred during daylight hours.

Of the six rear-end collisions, three involved westbound vehicles, two involved eastbound vehicles, and one involved southbound vehicle. All of the rear-end impacts were a result of vehicles following too close, speeding too fast for conditions, or lost control.

As there are less than 6 collisions of any other specific impact type, there are no other identifiable collision patterns at the Richmond Road segment between Richmond Road and McRae Avenue.

Richmond Road between Athlone Avenue and Tweedsmuir Avenue

A total of 6 collisions were reported at this intersection over the last five years, of which there were four angle impacts, one sideswipe impacts, and one single-vehicle/other impacts. Two of the collisions caused injuries, but none caused fatalities. One of the collisions involved cyclists, and none involved a pedestrian. All of the collisions occurred during clear environment and four of the collisions occurred during daylight hours.

As there are less than 6 collisions of any specific impact type, there are no identifiable collision patterns at the Richmond Road segment between Athlone Avenue and Tweedsmuir Avenue.

Richmond Road between Tweedsmuir Avenue and McRae Avenue

A total of 2 collisions were reported at this intersection over the last five years, of which both were four single-vehicle/other impacts. One of the collisions caused injuries, but none caused fatalities. None of the collisions involved cyclists, and none involved a pedestrian.

As there are less than 6 collisions of any specific impact type, there are no identifiable collision patterns at the Richmond Road segment between Tweedsmuir Avenue and McRae Avenue.

2.2 Planned Conditions

2.2.1 Transportation Projects

Context from 2013 TMP

As identified in the 2013 TMP, the 2031 Affordable Rapid Transit and Transit Priority (RTTP) Networks identify the implementation of transit signal priority and queue jump lanes at select intersections along Richmond Road, Wellington Street West, and Somerset Street. In addition, the affordable RTTP Network identifies the extension of Light Rail Transit (LRT) to the east, west, and south (Phase 2).

Context from Draft 2025 TMP Capital Infrastructure Plan (CIP)

Within the 2025 Draft 2025 TMP CIP, the Needs Based Transit Network Map, and the Priority Transit Network Map identify transit priority corridor along Richmond Road which may include dedicated bus lanes, queue jump lanes at intersections, transit priority signals, and changes to bus stop configurations. The locations and timelines for these improvements are currently not identified in the Draft TMP.

Active Transportation Projects New TMP Part -1

Within the City of Ottawa Transportation Master Plan's Active Transportation Projects, no planned projects are identified within the study area.

Integrated Renewal of Athlone, Lincoln, Edgewood and Eden Avenues (Planning Phase)

As part of the integrated renewal project, the city plans to do a full road reconstruction and street redesign to implement the 30kmph per the local residential street policy. The limits of the project include Athlone Avenue between Scott Street and Byron Avenue, Edgewood Avenue, Lincoln Avenue between Churchill Avenue North and Edgewood Avenue, and Eden Avenue between Lincoln Avenue and Richmond Road. The project is anticipated to start construction in fall 2027.


Integrated Renewal: Winona, Wilmont, Elmgrove and Picton

The City of Ottawa plans to replace watermains, and sanitary sewers on Wilmont Avenue along with other works on Winona, Elmgrove and Picton Avenue. As part of the renewal, the roads will be fully reconstructed with new asphalt, catch basins, concrete curbs and sidewalks. The project is also proposed to incorporate several new traffic calming features such as mid-block narrowings, speed humps and raised crosswalks to achieve an operating speed of 30 kmph.

LRT Phase 2

Construction for Phase 2 of the LRT (i.e. the Confederation Line Extension West) began in 2019 and is anticipated to be completed in 2027. This project involves extending the western LRT terminus from Tunney's Pasture Station to both Moodie Station and Algonquin College. As part of this project, the Westboro Transit Station will be converted to Westboro LRT Station. Assuming the same frequency as the existing Confederation Line, trains serving Westboro Station will operate on five-minute headways (i.e. 12 trains per hour). The proposed Confederation Line Extension West extension is shown in **Figure 4**.

Figure 4: LRT Phase 2 - Confederation Line Extension West



2.2.2 Other Area Developments

The Ottawa Development Application search tool allows review of any applications that have been submitted to the City of Ottawa. Upon examining the applications, the following developments are proposed in close proximity to the study area of 255 Richmond Road:

- *114 Richmond Road*: nine storey addition consisting of an apartment building with 161 units, and reprogramming of the convent to include two restaurants, 5 residential units and amenity space.
- *175 Richmond Road*: nine-storey mixed-use building to accommodate commercial uses on the main floors and residential uses above. There are 241 residential units proposed and approximately 675 m² of retail commercial along Richmond Road.
- *319-327 Richmond Road*: a nine-storey mixed-use building with 1738m² space on ground floor for commercial units and approximately 184 dwelling units on the upper storeys.
- *70 Richmond*: nine-storey mixed-use building with 60 residential units and a retail use at grade.
- *316-332 Clifton Road*: low-rise planned unit development consisting of 29 dwelling units, comprising of townhouses and back-to-back townhouses and an internal private road.
- *398-406 Roosevelt Avenue*: redevelopment of the site for a six-storey residential building with 61 dwelling units.
- *349 Danforth Avenue*: three-storey mixed-use building with 13 residential units and 2 commercial, ground-floor units.
- *335 Roosevelt Avenue*: two high-rise residential buildings with common underground parking lot with a total of 312 units and with 275 parking spaces.
- *397-399 Winston Avenue*: seven-storey mixed use development with a commercial use on the ground floor and 42 residential units above and two levels of underground parking with 18 parking spaces.
- *320 McRae Avenue, 1976 Scott Street, and 315 Tweedsmuir Avenue*: mixed-use development with 297 residential units and 14,440ft² of retail land uses. This development was recently constructed.
- *403 Richmond Road and 389 Roosevelt Avenue*: nine-storey mixed-use building with 141 residential units and 5,283ft² of ground floor commercial space.
- *2050 Scott St, 2046 Scott St, 301 Ashton Ave, 299 Ashton Ave, 295 Ashton Ave*: thirty-storey residential building on a 3- and 6-storey podiums with approximately 353 units and 233m² of ground commercial/office.
- *2026 Scott St, 2020 Scott St, 2006 Scott St, 318 Athlone Ave, and 314 Athlone Ave*: forty-storey towers with a total of 856 dwelling units and approximately 3,207ft² of ground-floor commercial space.
- *1950 Scott St, 314 Clifton Rd, and 312 Clifton Rd*: twenty-two storey residential tower with a total of 244 dwellings and approximately 2,098ft² of ground-floor commercial space.

2.3 Study Area and Time Periods

The study area for this report includes the boundary street Richmond Road, and the study area intersections at Richmond Road/Athlone Avenue, Richmond Road/Tweedsmuir Avenue, and Richmond Road/McRae Avenue.

The selected time periods for the analysis are the weekday AM and PM peak hours, as they represent the 'worst case' combination of site-generated traffic and adjacent street traffic. The

proposed development is expected to be completed with full occupancy by the year 2026. As such, this TIA considers the weekday AM and PM peak hours for the buildout year 2026 and horizon year 2031.

2.4 Exemptions Review

This section reviews possible exemptions from the TIA, as outlined in the *2017 TIA Guidelines*. The applicable exemptions for the site are shown in **Table 3**.

Table 3: TIA Exemptions

Module	Element	Exemption Criteria	Status
Design Review Component			
4.1 Development Design	4.1.2 Circulation and Access	Only required for site plans	Not Exempt
	4.1.3 New Street Networks	Only required for plans of subdivision	Exempt
4.2 Parking	4.2.1 Parking Supply	Only required for site plans	Not Exempt
	4.2.2 Spillover Parking	Only required for site plans where parking supply is 15% below unconstrained demand	Exempt
Network Impact Component			
4.5 Transportation Demand Management	<i>All elements</i>	Not required for site plans expected to have fewer than 60 employees and/or students on location at any given time	Not Exempt
4.6 Neighbourhood Traffic Management	4.6.1 Adjacent Neighbourhoods	Only required when the development relies on local or collector streets for access and total volumes exceed ATM capacity thresholds	Exempt
4.8 Network Concept	<i>All elements</i>	Only required when proposed development generates more than 200 person-trips during the peak hour in excess of the equivalent volume permitted by the established zoning	Exempt

As confirmed by City staff, the TIA report is limited to the Design Review components, as well as Module 4.5 (Transportation Demand Management).

3.0 FORECASTING

3.1 Development Generated Travel Demand

3.1.1 Trip Generation

Existing Trip Generation

Currently, the subject site is occupied by a retail building, and a high turnover restaurant, with a total gross floor area of approximately 11,000 square feet (approximated using aerial photography). Trips generated by the existing development has been estimated using the rates outlined in the *ITE Trip Generation Manual, 11th Edition* for the Shopping Centre (Land Use 820)

and High-Turnover Restaurant (Land Use 932) land uses. Note that the High-Turnover Restaurant use has only been considered in the PM peak hour, as it is not open during the AM peak hour. The person trips generated by the existing development are summarized in **Table 4**.

Table 4: Person Trips Generated by Existing Development

Land Use	ITE Code	GFA	AM Peak Hour (PPH) ¹			PM Peak Hour (PPH) ¹		
			In	Out	Total	In	Out	Total
Shopping Centre	820	7,000 ft ²	5	3	8	14	17	31
High-Turnover Restaurant	932	4,000 ft ²	-	-	0	28	18	46
Total			5	3	8	42	35	77

1. PPH = Persons Trips per Hour - Calculated using an ITE Trip to Person Trip factor of 1.28, consistent with the 2017 TIA Guidelines

The modal shares for the existing retail development are assumed to be consistent with the modal shares outlined in the *2020 TRANS Trip Generation Manual*, specific to the Ottawa West Area region. The assumed modal shares have been taken as the average of the TRANS AM and PM peak hour modal shares. As the modal shares presented in the 2020 TRANS report do not include restaurants, the modal shares for the existing restaurant have been estimated based on the 2011 TRANS O-D Survey Report. The modal share values applied to the existing restaurant development are based on all observed trips within the Ottawa West Area during the AM peak hour and PM peak hour. A full breakdown of the existing trips by modal share is shown in **Table 5**.

Table 5: Existing Development – Peak Hour Person Trips

Travel Mode	Mode Share	AM Peak Hour			PM Peak Hour		
		In	Out	Total	In	Out	Total
Shopping Centre Person Trips		5	3	8	14	17	31
Auto Driver	50%	3	2	5	7	9	16
Auto Passenger	15%	1	0	1	2	2	4
Transit	10%	0	0	0	1	2	3
Cyclist	5%	0	0	0	1	1	2
Pedestrian	20%	1	1	2	3	3	6
Restaurant Person Trips		0	0	0	28	18	46
Auto Driver	35%	-	-	0	10	6	16
Auto Passenger	10%	-	-	0	3	2	5
Transit	5%	-	-	0	1	1	2
Cyclist	5%	-	-	0	1	1	2
Pedestrian	45%	-	-	0	13	8	21

From the previous tables, the existing development is estimated to generate 8 person trips (including 5 vehicle trips) during the AM peak hour, and 77 person trips (including 32 vehicle trips) during the PM peak hour.

Proposed Residential Trip Generation

The proposed redevelopment will include 127 residential units. Trips generated by the proposed residential units during the AM and PM peak period have been estimated using the recommended rates from the *2020 TRANS Trip Generation Manual*. The trip generation rates are taken from Table 3 and correspond to High-Rise Residential in the Ottawa West Area. The directional split

between inbound and outbound trips are based on the blended splits presented in Table 9 of the report.

The estimated number of trips generated by the proposed residential units is shown in **Table 6**.

Table 6: Trips Generated by Proposed Residential Development

Land Use	TRANS Rate	Units	AM Peak Period (PPP) ¹			PM Peak Period (PPP) ¹		
			In	Out	Total	In	Out	Total
High-Rise Residential, Ottawa West	AM: 0.80 PM: 0.90	127 units	31	70	101	66	48	114

1. PPP = Person Trips per Period

The *2020 TRANS Trip Generation Manual* provides modal shares for residential developments within the Ottawa West Area. However, developments within 600m of rapid transit stations can be considered as Transit Oriented Developments (TOD). In TOD zones, the transit share is assumed to increase significantly compared to any TRANS O-D District. A summary of the TRANS residential mode shares, TOD mode shares, and assumed residential mode shares is provided in **Table 7**.

Table 7: TRANS and TOD Mode Share Comparison

	Auto Driver	Auto Passenger	Transit	Cycling	Walking
TRANS	30%	10%	35%	5%	20%
TOD	15%	5%	65%	5%	10%
Proposed	25%	10%	40%	5%	20%

The proposed residential modal shares reflect a 5% reduction in auto trips compared to the Ottawa Inner Area to account for the development's proximity to the Westboro Transit Station. A full breakdown of the projected person trips by modal share is shown in **Table 8**.

Table 8: Proposed Residential Development – Peak Period Person Trips

Travel Mode	Mode Share	AM Peak Period			PM Peak Period		
		In	Out	Total	In	Out	Total
Residential Person Trips		31	70	101	66	48	114
Auto Driver	25%	8	17	25	17	12	29
Auto Passenger	10%	3	7	10	7	5	12
Transit	40%	13	28	41	26	19	45
Cyclist	5%	2	3	5	3	2	5
Pedestrian	20%	6	14	20	13	10	23

Table 4 of the *2020 TRANS Trip Generation Manual* includes adjustment factors to convert the estimated number of trips generated for each mode from peak period to peak hour. A breakdown of the peak hour trips by mode is shown in **Table 9**.

Table 9: Proposed Residential Development – Peak Hour Person Trips

Travel Mode	Adjustment Factor		AM Peak Period			PM Peak Period		
	AM	PM	In	Out	Total	In	Out	Total
Residential Person Trips			16	36	52	30	22	52
Auto Driver	0.48	0.44	4	8	12	7	5	12
Auto Passenger	0.48	0.44	1	3	4	3	2	5
Transit	0.55	0.47	7	15	22	12	9	21
Cyclist	0.58	0.48	1	2	3	1	1	2
Pedestrian	0.58	0.52	3	8	11	7	5	12

From the previous tables, the proposed residential uses are estimated to generate 52 person trips (including 12 vehicle trips) during the AM peak hour, and 52 person trips (including 12 vehicle trips) during the PM peak hour.

Proposed Commercial Trip Generation

The proposed redevelopment will also include two retail units with a combined gross floor area of approximately 4,240 square feet and a restaurant with a gross floor area of approximately 2,282 square feet. Consistent with the existing development, trips generated by the commercial uses have been calculated using the Shopping Centre (LU 820) and High-Turnover Sit-Down Restaurant (LU 932) land uses in the *ITE Trip Generation Manual, 11th Edition*. The proposed restaurant is conservatively assumed to operate during both peak hours.

The estimated number of trips generated by the proposed commercial development is shown in **Table 10**.

Table 10: Trips Generated by Proposed Commercial Development

Land Use	ITE Code	GFA	AM Peak Hour (PPH)			PM Peak Hour (PPH)		
			In	Out	Total	In	Out	Total
Shopping Centre	820	4,240 ft ²	3	3	6	9	9	18
High-Turnover Restaurant	932	2,282 ft ²	15	13	28	17	10	27
Total			18	16	34	26	19	45

The modal shares for the proposed commercial development are anticipated to be consistent with the modal shares outlined for the existing commercial developments.

A full breakdown of the projected person trips by modal share is shown in **Table 11**.

Table 11: Proposed Commercial Development – Peak Hour Person Trips

Travel Mode		Mode Share	AM Peak Hour			PM Peak Hour		
			In	Out	Total	In	Out	Total
Shopping Centre Person Trips			3	3	6	9	9	18
Auto Driver	50%		2	2	4	5	5	10
Auto Passenger	15%		0	0	0	1	1	2
Transit	10%		0	0	0	1	1	2
Cyclist	5%		0	0	0	0	0	0
Pedestrian	20%		1	1	2	2	2	4
Restaurant Person Trips			15	13	28	17	10	27
Auto Driver	35%		5	4	9	6	4	10
Auto Passenger	10%		1	1	2	2	1	3
Transit	5%		1	1	2	1	1	2
Cyclist	5%		1	1	2	1	0	1
Pedestrian	45%		7	6	13	7	4	11

Based on the previous table, the proposed commercial uses are projected to generate 34 person trips during the AM peak period and 45 person trips during the PM peak period. Of the trips generated, 13 and 20 are expected to be vehicle trips during the AM and PM peak periods, respectively.

Net Trip Generation

A full breakdown of the net person trips generated by modal share is shown in **Table 12**.

Table 12: Net Person Trip Generation

Travel Mode	AM Peak Hour			PM Peak Hour		
	In	Out	Total	In	Out	Total
<i>Existing Development</i>						
Auto Driver	3	2	5	17	15	32
Auto Passenger	1	0	1	5	4	9
Transit	0	0	0	2	3	5
Cyclist	0	0	0	2	2	4
Pedestrian	1	1	2	16	11	27
Total	5	3	8	42	35	77
<i>Proposed Development</i>						
Auto Driver	11	14	25	18	14	32
Auto Passenger	2	4	6	6	4	10
Transit	8	16	24	14	11	25
Cyclist	2	3	5	2	1	3
Pedestrian	11	15	26	16	11	27
Total	34	52	86	56	41	97
<i>Net Trips</i>						
Auto Driver	8	12	20	1	-1	0
Auto Passenger	1	4	5	1	0	1
Transit	8	16	24	12	8	20
Cyclist	2	3	5	0	-1	-1
Pedestrian	10	14	24	0	0	0
Total	29	49	78	14	6	20

Based on the previous table, the vehicle trip generation for the proposed development is expected to increase by 20 vehicle trips during the AM peak hours and is anticipated to decrease by 0 vehicle trips during the PM peak hour. The proposed development is expected to generate an additional 24 and 20 transit trips during the AM and PM peak hours, respectively, compared to the existing development.

3.1.2 Trip Distribution

For this report, trip distribution assumptions have not been included.

3.2 Background Traffic

3.2.1 Other Area Developments

A description of the other study area developments is included in section 2.2

A review of traffic studies for the following study area developments suggests that the traffic generated by these developments is expected to have a negligible impact on the adjacent roadways:

- *114 Richmond Road*: nine storey addition consisting of an apartment building with 161 units, and reprogramming of the convent to include two restaurants, 5 residential units and amenity space.
- *70 Richmond*: nine-storey mixed-use building with 60 residential units and a retail use at grade.
- *316-332 Clifton Road*: low-rise planned unit development consisting of 29 dwelling units, comprising of townhouses and back-to-back townhouses and an internal private road.
- *398-406 Roosevelt Avenue*: redevelopment of the site for a six-storey residential building with 61 dwelling units.
- *349 Danforth Avenue*: three-storey mixed-use building with 13 residential units and 2 commercial, ground-floor units.
- *397-399 Winston Avenue*: seven-storey mixed use development with a commercial use on the ground floor and 42 residential units above and two levels of underground parking with 18 parking spaces.
- *1950 Scott St, 314 Clifton Rd, and 312 Clifton Rd*: twenty-two storey residential tower with a total of 244 dwellings and approximately 2,098ft² of ground-floor commercial space.

The projected traffic volumes generated by the following developments have been added to the background traffic at all relevant intersections within the study area:

- *175 Richmond Road*: nine-storey mixed-use building to accommodate commercial uses on the main floors and residential uses above. There are 241 residential units proposed and approximately 675 m² of retail commercial along Richmond Road.
- *335 Roosevelt Avenue*: two high-rise residential buildings with common underground parking lot with a total of 312 units and with 275 parking spaces.
- *319-327 Richmond Road*: a nine-storey mixed-use building with 1738m² space on ground floor for commercial units and approximately 184 dwelling units on the upper storeys.
- *320 McRae Avenue, 1976 Scott Street, and 315 Tweedsmuir Avenue*: mixed-use development with 297 residential units and 14,440ft² of retail land uses. This development was recently constructed.

- *403 Richmond Road and 389 Roosevelt Avenue*: nine-storey mixed-use building with 141 residential units and 5,283ft² of ground floor commercial space.
- *2050 Scott St, 2046 Scott St, 301 Ashton Ave, 299 Ashton Ave, 295 Ashton Ave*: thirty-storey residential building on a 3- and 6-storey podiums with approximately 353 units and 233m² of ground commercial/office.
- *2026 Scott St, 2020 Scott St, 2006 Scott St, 318 Athlone Ave, and 314 Athlone Ave*: forty-storey towers with a total of 856 dwelling units and approximately 3,207ft² of ground-floor commercial space.

Excerpts of the transportation studies in support of the above developments area included in **Appendix F**.

3.2.2 General Background Growth Rate

A rate of background growth has been established through a review of the city of Ottawa's Strategic Long-Range Model (comparing snapshots of 2011 and 2031 AM peak volumes) from the Richmond Road corridor. On the roadways within and around the study area, the snapshots suggest a growth rate between -1% and +2% per annum.

A background growth rate of 1% per annum has been conservatively applied to through traffic along Richmond Road based on the snapshots from the City's Strategic Long-Range Model.

The background traffic volumes in 2026 and 2031 are shown in **Figure 5** and **Figure 6** respectively.

Figure 5: 2026 Background Traffic Volumes





Figure 6: 2031 Background Traffic Volumes



4.0 ANALYSIS

4.1 Development Design

4.1.1 Design for Sustainable Modes

Sidewalk connections will be provided between the building entrance and Richmond Road and Tweedsmuir Avenue. Sidewalks will be depressed and continuous across the parking garage access in accordance with City standards.

Two bicycle parking spaces will be provided at-grade near the Richmond Road building entrance, 30 spaces will be provided within the building lobby, and 128 will be provided within the underground parking garage. In total, 160 bicycle parking spaces will be provided. Further review of the number of bicycle parking spaces is included in Section 4.2.

OC Transpo guidelines recommend that all developments within the vicinity of a bus route should have at least one bus stop within a walking distance of 400m, roughly a five-minute walk. All of the transit stops outlined in Section 2.1.6 are within the 400m distance. The closest bus stops to the subject site along Richmond Road provide service to routes 11, 51, and 81.

A review of the *Transportation Demand Management (TDM)-Supportive Development Design and Infrastructure Checklist* has been conducted. A copy of the TDM checklist is included in **Appendix G**. All required TDM-supportive design and infrastructure measures in the TDM checklist are met. In addition to the required measures, the proposed development also meets the following 'basic' or 'better' measures as defined on the *TDM-Supportive Development Design and Infrastructure Checklist*:

- Locate building close to the street, and do not locate parking areas between the street and building entrances.
- Locate building entrances in order to minimize walking distances to sidewalks and transit stops/stations.
- Locate building doors and windows to ensure visibility of pedestrians from the building, for their security and comfort.


- Provide safe, direct and attractive walking routes from building entrances to nearby transit stops.
- Ensure that walking routes to transit stops are secure, visible, lighted, shaded and wind-protected wherever possible.
- Provide lighting, landscaping and benches along walking and cycling routes between building entrances and streets, sidewalks and trails.

Garbage bins will be wheeled up the parking ramp for curbside private pick-up on Tweedsmuir Avenue. The fire route for the development is curbside along Richmond Road and Tweedsmuir Avenue.

Loading operations for the residential function of the building will take place along Tweedsmuir Avenue adjacent to the east entrance. A holding room is provided adjacent to the east entrance to facilitate a shorter unloading time, hold furniture etc. which limits the amount of time that the unloading vehicles is parked on Tweedsmuir Avenue. Loading for the commercial developments will occur on-street along Richmond Road.

An existing pavement markings and signage figure, which also includes the proposed site plan and both sides of Richmond Road, Tweedsmuir Avenue, and Athlone Avenue in the immediate vicinity of the subject site, is shown in **Figure 7**. No changes to the existing signage are proposed along the subject site's frontage.

M:\2021\121193\CAD\Design\Figures\Traffic\121193-PV\MK-X2.dwg, P\MK, Mar 18, 2022 - 11:29am, jaudia



4.2 Parking

The subject site is located in Area B of Schedule 1 and Area Y of Schedule 1A of the City of Ottawa's Zoning By-Law (ZBL) and is located within 600m of a rapid transit station. Sections 101, 102, 103, and 111 of the ZBL summarize the minimum vehicle parking space rates, maximum vehicle parking space rates, and minimum bicycle parking space rates for various land uses. The parking space requirements for the proposed development are summarized in **Table 13**.

Table 13: Minimum Parking Requirements

Land Use	Rate	Units/GFA	Required
<i>Minimum Vehicle Parking</i>			
Residential	Resident: 0.5 per dwelling, after the first 12 units	127 units	58
	Visitor: 0.1 per dwelling, after the first 12 units		12
Commercial	Retail: No parking required when GFA < 500 m ²	394 m ²	0
	Restaurant: No parking required when GFA < 350 m ²	212 m ²	0
		Minimum Provided	70
			77
<i>Maximum Vehicle Parking</i>			
Residential	Resident + Visitor: 1.75 per dwelling	127 units	222
Commercial	Retail: 1 per 250 m ² GFA	394 m ²	2
		Maximum Provided	203
			77
<i>Minimum Bicycle Parking</i>			
Residential	Resident: 1.75 per dwelling ¹	127 units	222
Commercial	Retail & Restaurant: 1 per 250 m ² GFA	606 m ²	2
		Minimum Provided	224
			160

1. Per ZBL Exception 2900

Based on the previous tables, the amount of vehicle parking provided meets the requirements of the City of Ottawa ZBL.

Relief from the ZBL Exception 2900 is being sought for the minimum number of bicycle parking spaces that are required. A total of 160 bicycle parking spaces are proposed for the development, equating to a rate of approximately 1.25 spaces per unit.

4.3 Boundary Streets

This section provides a review of the boundary streets, Richmond Road and Tweedsmuir Avenue using complete streets principles. The Multi-Modal Level of Service (MMLOS) guidelines produced by IBI Group in October 2015 have been used to evaluate the LOS of boundary roadways for each mode of transportation.

Both roadways are located within 600m of the Westboro Transit Station. Richmond Road is classified as an arterial roadway and Tweedsmuir Avenue is classified as a local roadway.

4.3.1 Pedestrian Level of Service (PLOS)

Exhibit 4 of the MMLOS guidelines has been used to evaluate the segment PLOS of Richmond Road and Tweedsmuir Avenue. Exhibit 22 of the MMLOS guidelines suggests a target PLOS A

for all roadways within 600m of a rapid transit station. The results of the segment PLOS analysis are summarized in **Table 14**.

Table 14: PLOS Segment Table

Sidewalk Width	Boulevard Width	Avg. Daily Curb Lane Traffic Volume	Presence of On-Street Parking	Operating Speed ¹	PLOS
Richmond Road (north curb)					
> 2.0m	> 2.0m	> 3,000 vpd	Yes	60 km/h	B
Richmond Road (south curb)					
> 2.0m	0.5 to 2.0m	> 3,000 vpd	Yes	60 km/h	C
Tweedsmuir Avenue (east curb)					
> 2.0m	> 2.0m	< 3,000 vpd	No	60 km/h	A
Tweedsmuir Avenue (west curb)					
No sidewalk		< 3,000 vpd	Yes	60 km/h	F

1. Operating speed taken as the speed limit plus 10 km/h.

4.3.2 Bicycle Level of Service (BLOS)

Exhibit 11 of the MMLOS guidelines has been used to evaluate the segment BLOS of Richmond Road and Tweedsmuir Avenue. Exhibit 22 of the MMLOS guidelines suggests a target BLOS C for Richmond Road and BLOS D for Tweedsmuir Avenue. The results of the segment BLOS analysis are summarized in **Table 15**.

Table 15: BLOS Segment Analysis

Road Class	Bike Route	Type of Bikeway	Travel Lanes	Operating Speed	BLOS
Richmond Road					
Arterial	Suggested	Mixed Traffic	2	60 km/h	F
Tweedsmuir Avenue					
Local	No Class	Mixed Traffic	2	60 km/h	F

4.3.3 Transit Level of Service (TLOS)

Exhibit 15 of the MMLOS guidelines has been used to evaluate the segment TLOS of Richmond Road. Exhibit 22 of the MMLOS guidelines suggests a target TLOS D for arterial roadways along a transit priority corridor (isolated measures). Since Tweedsmuir Avenue does not provide transit service, the transit level of service (TLOS) has not been evaluated. The results of the segment TLOS analysis are summarized in **Table 16**.

Table 16: TLOS Segment Analysis

Facility Type	Exposure to Congestion Delay, Friction, and Incidents			TLOS
	Congestion	Friction	Incident Potential	
Richmond Road				
Mixed Traffic – Frequent Parking/Driveway Friction	Yes	High	High	F

4.3.4 Truck Level of Service (TkLOS)

Exhibit 20 of the MMLOS guidelines has been used to evaluate the segment TkLOS of Richmond Road and Tweedsmuir Avenue. Exhibit 22 of the MMLOS guidelines suggests a target TkLOS D

for Richmond Road and no target for Tweedsmuir Avenue. The results of the segment TkLOS analysis are summarized in **Table 17**.

Table 17: TkLOS Segment Analysis

Curb Lane Width	Number of Travel Lanes Per Direction	TkLOS
Richmond Road		
> 3.7m	1	B
Tweedsmuir Avenue		
> 3.7m	1	B

4.3.5 Segment MMLOS Summary

A summary of the results of the segment MMLOS analysis for the boundary roads is provided in **Table 18**.

Table 18: Segment MMLOS Summary

Segment	PLOS	BLOS	TLOS	TkLOS
Richmond Road	C	F	F	B
Target	A	C	D	E
Tweedsmuir Avenue	F	F	-	B
Target	A	B	D	N/A

The target **PLOS** is not achieved in either segment. To achieve the target PLOS A along Richmond Road, either a reduction in the posted speed or Annual Average Daily Traffic (AADT) volumes is required. To achieve the target PLOS A along Tweedsmuir Avenue, a 2m sidewalk and boulevard greater than 0.5m is required. The proposed development will provide a 2.0m sidewalk adjacent to the curb on Tweedsmuir Avenue with planters behind the sidewalk.

The target **BLOS** is not achieved in either segment. To achieve the target BLOS D along Tweedsmuir Avenue, a reduction in the operating speed is required. To achieve the target BLOS C along Richmond Road, bike lanes are required. This is identified for the City's consideration.

The target **TLOS** is not achieved on the Richmond Road Segment. To achieve the target TLOS D along Richmond Road, a reduction in parking/driveway friction is required.

The target **TkLOS** is met on Richmond Road due to lanes that measure more than 3.7 metres.

4.4 Access Intersections

The proposed redevelopment will be served by a two-way underground parking garage access along Tweedsmuir Avenue. The proposed underground parking ramp will have a width of approximately 6.0m and will be located approximately 25m from the Richmond Road right-of-way limit and 14m from the northern property line.

Section 25 (1)(c) of the Private Approach By-law (PABL) states that two-way accesses to have a width no greater than 9m, as measured at the street line. Furthermore, the City of Ottawa's ZBL identifies a minimum width of 6.0m and maximum width of 6.7m for a two-way driveway leading to an underground parking garage with more than 50 spaces. The width of the proposed driveway adheres to the requirements of the PABL and ZBL.

Section 25 (1)(m)(ii) of the PABL states where a property abuts an arterial roadway and has less than 100 parking spaces, that the distance between private approach and nearest intersecting street line be 18 metres. Section 25 (1)(p) of the PABL identifies a minimum spacing requirement of 3.0m between the nearest limit of a private approach and the property line, as measured at the street line. The location of the proposed driveway adheres to section 25 (1)(m)(ii) and 25 (1)(p) of the PABL.

Section 25 (1)(u) of the PABL identifies a maximum grade of 2% for a distance of 9m within the property, where the access leads to 50 or more parking spaces. A distance of 8.2m with a grade of 1.0% from garage door to property line and a grade of 1.4% sloping towards the roadway will be provided between the back of sidewalk and the garage door. At the garage door, the slope transitions to a 5% grade in the direction of the property for approximately 5.0m, before transitioning to a 13% grade. Within the first 9m of the property line the proposed grades are 1.0% for approximately 3.7m, and 5% for approximately 5.0m. By limiting the maximum grade to 5% for the first 9m and including a 1.4% slope for approximately 8.2m between the garage door and the back of sidewalk, it is anticipated that drivers exiting the subject site will have adequate sightlines to pedestrians walking along Tweedsmuir Avenue.

Further, the Transportation Association of Canada (TAC)'s *Geometric Design Guidelines for Canadian Roads* identifies a maximum recommended downgrade of 7% for low volume driveways on local roadways in Section 8.9.11. Based on the proposed grading identified above, a maximum grade of 5% will be provided for a distance of 13.2m behind the sidewalk and 8.7m within the private property. As the proposed grading meets the TAC recommendations, a waiver to the requirement of Section 25 (1)(u) of the PABL is recommended.

Tables 9.9.4 and 9.9.6 of the *Geometric Design Guide* identifies minimum stopping sight distance (SSD) and intersection sight distance (ISD) requirements, based on the roadway grade and design speed (taken as the speed limit plus 10 km/h). Assuming level grade and a design speed of 60 km/h, the SSD requirement is 85m and the ISD requirements are 130m for left turning vehicles and 110m for right turning vehicles. As Tweedsmuir Avenue is a straight roadway, adequate SSD can be provided at the proposed access. Based on the landscape plan, short shrubs and honey locust trees with a high canopy are proposed on either side of the access. Adequate sightlines for drivers turning left and right out of the proposed access can also be provided, as long as any proposed trees and shrubs are trimmed and maintained.

4.5 Transportation Demand Management

4.5.1 Context for TDM

The proposed development consists of a total of 127 residential units. The unit breakdown is summarized as follows:

- Studio: 9 units;
- One Bedroom: 61 units;
- One Bedroom and Den: 21 units;
- Two Bedroom: 36 units.

4.5.2 Need and Opportunity

As the proposed development is located within a TOD zone, the Ottawa West modal shares presented in the 2020 TRANS Trip Generation Manual have been adjusted to reflect a slightly higher transit mode share. The assumed modal shares for the development decrease the auto modal share from 30% (Ottawa West) to 25%. Should the development only meet the TRANS modal shares, the development is anticipated to generate an additional two and five vehicle trips two-way during the AM and PM peak hours respectively. However, as the proposed development is located in close proximity to the future Westboro LRT station and the development will provide a suite of TDM measures described in the following section, the development is anticipated to meet the target modal shares.

4.5.3 TDM Program

A review of the Transportation Demand Management (TDM) – Measures Checklist has been conducted. A copy of the TDM checklist is included in **Appendix G**.

The following measures will be implemented upon completion of the proposed development:

- Display local area maps with walking/cycling access routes and key destinations at major entrances (multi-family, condominium);
- Display relevant transit schedules and route maps at entrances (multi-family, condominium);
- Provide real-time arrival information display at entrances (multi-family, condominium);
- Offer PRESTO cards preloaded with one monthly transit pass on residence purchase/move-in, to encourage residents to use resident;
- Unbundle parking cost from purchase price (condominium);
- Unbundle parking cost from monthly rent (multi-family);
- Provide a multimodal travel option information package to new residents.

5.0 CONCLUSIONS AND RECOMMENDATIONS

Based on the foregoing, the conclusions and recommendations of this TIA can be summarized as follows:

Development Design

- Sidewalk connections will be provided between the building entrance and Richmond Road and Tweedsmuir Avenue.
- Sidewalks will be depressed and continuous across the parking garage access in accordance with City standards.
- Two bicycle parking spaces will be provided at-grade near the Richmond Road building entrance, 30 spaces will be provided within the building lobby, and 128 will be provided within the underground parking garage. In total, 160 bicycle parking spaces will be provided.
- All required Transportation Demand Management (TDM)-supportive design and infrastructure measures in the checklist are met.
- Garbage bins will be wheeled up the parking ramp for curbside private pick-up on Tweedsmuir Avenue. The fire route for the development is curbside along Richmond Road and Tweedsmuir Avenue.

- Loading operations for the residential function of the building will take place along Tweedsmuir Avenue adjacent to the east entrance. A holding room is provided adjacent to the east entrance to facilitate a shorter unloading time, hold furniture etc. which limits the amount of time that the unloading vehicles is parked on Tweedsmuir Avenue. Loading for the commercial developments will occur on-street along Richmond Road.
- No changes to the existing signage are proposed along the subject site's frontage.

Parking

- The proposed vehicular parking spaces adhere to the requirements of the City's *Zoning By-law* (ZBL).
- Relief from the ZBL Exception 2900 is being sought for the minimum number of bicycle parking spaces that are required. A total of 160 bicycle parking spaces are proposed for the development, equating to a rate of approximately 1.25 spaces per unit.

Boundary Street Design

- Richmond Road and Tweedsmuir Avenue have been evaluated using the targets set for arterial and local roadways within 600m of a rapid transit stop.
- The target pedestrian level of service (PLOS) is not achieved on either Richmond Road or Tweedsmuir Avenue. To achieve the target PLOS A along Richmond Road, either a reduction in the posted speed or Annual Average Daily Traffic (AADT) volumes is required. To achieve the target PLOS A along Tweedsmuir Avenue, a 2m sidewalk and boulevard greater than 0.5m is required. The proposed development will provide a 2.0m sidewalk adjacent to the curb with planters behind the sidewalk.
- The target bicycle level of service (BLOS) is not achieved on either Richmond Road or Tweedsmuir Avenue. To achieve the target BLOS C along Richmond Road, bike lanes are required. To achieve the target BLOS D along Tweedsmuir Avenue, a reduction in the operating speed is required. This is identified for the City's consideration.
- The target transit level of service (TLOS) is not achieved on Richmond Road. To achieve the target TLOS D along Richmond Road, a reduction in parking/driveway friction is required.
- The target truck level of service (TkLOS) target of E is met on Richmond Road due to lanes that measure more than 3.7m.

Access Intersections

- The width of the proposed access adheres to the requirements of the City's *Private Approach By-law* (PABL) and ZBL.
- The location of the proposed access adheres to the requirements of the PABL.
- A maximum grade of 5% will be provided for a distance of 13.2m behind the sidewalk and 8.7m within the private property. As the proposed grading meets the TAC recommendations, and adequate sightlines for pedestrians crossing the access will be maintained, a waiver to Section 25 (1)(u) of the PABL is recommended.
- For drivers exiting the property, adequate sightlines turning left and right out of the proposed access can also be provided, as long as any proposed trees and shrubs are trimmed and maintained.

Transportation Demand Management

- The following measures will be implemented upon completion of the proposed development:

- Display local area maps with walking/cycling access routes and key destinations at major entrances;
- Display relevant transit schedules and route maps at entrances;
- Provide real-time arrival information display at entrances;
- Offer PRESTO cards preloaded with one monthly transit pass on residence purchase/ move-in, to encourage residents to use resident;
- Unbundle parking cost from purchase price (condominium);
- Unbundle parking cost from purchase price (multi-family);
- Provide a multimodal travel option information package to new residents;

Based on the foregoing, the proposed development is recommended from a transportation perspective.

NOVATECH

Prepared by:



Mohammed Talha, M. Eng.
Engineering Intern | Transportation

Reviewed by:



Brad Byvelds, P. Eng.
Senior Project Manager | Transportation

Appendix A: Site Plan



AVERAGE GRADE CALCULATION	
67.20	
67.30	
65.65	
65.55	
66.65	
65.98	
67.45	
TOTAL: 66.54	

MATERIAL LEGEND:	
	TYP. BALLASTED ROOF
	TERRACE ROOF (PAVERS)
	BALCONIES
	PLANTERS

UNIT DISTRIBUTION SUMMARY				
Level	Name	Count	Area	
Level 1	One Bedroom	4	247.83 m²	
Level 1	One Bedroom (BF)	1	62.80 m²	
		5	310.62 m²	
Level 2	One Bedroom	8	508.47 m²	
Level 2	Studio	1	52.64 m²	
Level 2	Two Bedroom	3	301.49 m²	
		12	662.60 m²	
Level 3	One Bedroom	10	633.82 m²	
Level 3	One Bedroom + Den	4	318.80 m²	
Level 3	Studio	1	42.38 m²	
Level 3	Two Bedroom	4	383.75 m²	
		19	1378.55 m²	
Level 4	One Bedroom	10	639.32 m²	
Level 4	One Bedroom + Den	4	318.80 m²	
Level 4	Studio	1	42.44 m²	
Level 4	Two Bedroom	4	385.27 m²	
		19	1385.85 m²	
Level 5	One Bedroom	6	384.39 m²	
Level 5	One Bedroom + Den	4	318.80 m²	
Level 5	Studio	1	42.44 m²	
Level 5	Two Bedroom	6	561.11 m²	
		17	1306.75 m²	
Level 6	One Bedroom	8	508.25 m²	
Level 6	One Bedroom + Den	4	318.80 m²	
Level 6	Studio	1	42.38 m²	
Level 6	Two Bedroom	4	374.70 m²	
		17	1244.13 m²	
Level 7	One Bedroom	4	258.14 m²	
Level 7	One Bedroom + Den	4	318.80 m²	
Level 7	Studio	1	42.38 m²	
Level 7	Two Bedroom	6	584.97 m²	
		15	1214.29 m²	
Level 8	One Bedroom	5	366.75 m²	
Level 8	One Bedroom + Den	1	81.03 m²	
Level 8	Studio	1	39.19 m²	
Level 8	Two Bedroom	5	487.01 m²	
		12	973.97 m²	
Level 9	One Bedroom	5	368.96 m²	
Level 9	Studio	1	39.21 m²	
Level 9	Two Bedroom	5	505.72 m²	
		11	913.90 m²	
Grand total:		127	9560.67 m²	

ZONING INFORMATION

ZONE DESIGNATION

TM H(15)

ZONING REQUIREMENTS

NOTE:	
MIN. LOT WIDTH REQUIRED:	NO MINIMUM
LOT WIDTH PROVIDED (NORTH PROPERTY LINE):	48.8M
LOT WIDTH PROVIDED (SOUTH PROPERTY LINE):	49.6M
MIN. LOT AREA REQUIRED (M²):	NO MINIMUM
LOT AREA PROVIDED:	2181.2M²
MAX BUILDING HEIGHT:	15.0M
BUILDING HEIGHT FROM AVG GRADE:	31.0M
AVERAGE GRADE:	66.37m (GEODETIC)
MAX FRONT YARD SETBACK:	2M
FRONT YARD SETBACK (RETAIL) (VARIES AT GRADE):	0M
FRONT YARD SETBACK (RESIDENTIAL):	2M
MIN. REAR YARD SETBACK:	7.5M
REAR YARD SETBACK (FORMER R4 ZONE):	1.2M
REAR YARD SETBACK (AMENITY AREAS):	0.07M
REAR YARD SETBACK (BUILDING ABOVE GRADE):	7.5M
MAX INTERIOR SIDE YARD SETBACK:	3M
INTERIOR SIDE YARD SETBACK (FORMER R4 ZONE):	7.5M
INTERIOR SIDE YARD SETBACK (TM ZONE):	0.135M
MIN. CORNER YARD SETBACK (EAST):	1.2M
MIN. CORNER YARD SETBACK (ABOVE 15M):	3M
CORNER YARD SETBACK (EAST) PROVIDED:	2M
CORNER YARD SETBACK (ABOVE 15M) PROVIDED:	2.5M
MIN. DRIVEWAY AISLE WIDTH:	6.7M
DRIVEWAY AISLE WIDTH:	6M

DEVELOPMENT INFORMATION

PROPOSED:

GROUND FLOOR G.F.A. RETAIL:	611.10M²
GROSS CONSTRUCTED AREA (EXCLUDED BELOW GRADE / MPH / TERRACES):	12756.44M²
GROSS CONSTRUCTED AREA MECH. PENTHOUSE:	221.03M²
GROSS CONSTRUCTED AREA P1:	2090.37M²
GROSS CONSTRUCTED AREA P2:	2090.37M²
PROPOSED # UNIT (RETAIL):	3 UNITS
PROPOSED # UNITS (RESIDENTIAL):	127 UNITS

PARKING REQUIREMENTS

MIN. RESIDENT PARKING STALLS REQUIRED:	0.5
(STALLS) SWELLING UNIT AFTER FIRST 12 UNITS:	
MIN. VISITOR PARKING STALLS REQUIRED:	0.1
(STALLS) SWELLING UNIT AFTER FIRST 12 UNITS:	
MIN. REQUIRED PARKING STALLS @ (127-12 = 115 X 0.5):	58
MIN. REQUIRED VISITOR PARKING STALLS @ (127-12 = 115 X 0.1 - 10%):	12
TOTAL PARKING REQUIRED:	70


PROPOSED PARKING

DRIVE AISLE WIDTH (RETAIL AND VISITOR PARKING SHARED):	6.0M
PINCH POINT IN GARAGE:	
PROPOSED RETAIL PARKING:	
PROPOSED RESIDENTIAL PARKING:	65
PROPOSED VISITOR PARKING:	12
TOTAL OF PROPOSED PARKING (P1, P2):	77
ACCESSIBLE:	1
CONFORMING STALLS (2.4 X 5.2m):	38
CONFORMING SHORT CAR STALLS (2.4 X 4.6m MIN.):	32
PROPOSED BICYCLE PARKING	
REQUIRED RETAIL BICYCLE PARKING:	2
REQUIRED RESIDENTIAL BICYCLE PARKING (@ 1.75/UNIT):	222
SUB-TOTAL OF REQUIRED BICYCLE PARKING:	224
PROVIDED RESIDENTIAL BICYCLE PARKING (@ 1.25 / UNIT):	158
PROVIDED RETAIL BICYCLE PARKING:	2
TOTAL BICYCLE PARKING PROVIDED:	160
BICYCLE PARKING PROVIDED (UNDERGROUND):	128
BICYCLE PARKING PROVIDED (LOBBY):	30
BICYCLE PARKING PROVIDED (EXTERIOR):	2
BICYCLE PARKING PROVIDED (TOTAL):	160


AMENITY AREA CALCULATIONS - PROPOSED

NOTE: CALCULATIONS DONE IN ACCORDANCE WITH CITY OF OTTAWA BY-LAW 2008-250, SECTION 137 - AMENITY AREA	
RESIDENTIAL TOTAL REQUIRED AMENITY AREA (MIN.):	762.0M²
(127 UNITS @ 6.0M²/UNIT)	
COMMUNAL AREA (MIN.):	381.0M²
(50% OF REQ'D TOTAL AMENITY AREA)	
TOTAL RESIDENTIAL AMENITY AREA REQUIRED:	762M²
TOTAL AMENITY AREA PROVIDED:	
BALCONY AREA (104 UNITS):	937.01M²
INDOOR AMENITY AREA (COMMUNAL):	323.46M²
OUTDOOR AMENITY AREA (COMMUNAL):	288.51M²
TOTAL RESIDENTIAL AMENITY AREA PROVIDED:	1,524.98M²
LANDSCAPED AREA REQUIRED:	NON MINIMUM
LANDSCAPED AREA PROVIDED:	400.00M²
MINIMUM WIDTH OF LANDSCAPE AREA ABUTTING A RESIDENTIAL ZONE:	1.0M WITH FENCE
WIDTH OF LANDSCAPE AREA PROVIDED ABUTTING RESIDENTIAL ZONE (FORMER R4 REAR YARD):	7.4M WITH FENCE
WIDTH OF LANDSCAPE AREA PROVIDED ABUTTING RESIDENTIAL ZONE (FORMER R4 SIDE YARD):	1.2M
WIDTH OF LANDSCAPE AREA PROVIDED ABUTTING RESIDENTIAL ZONE (TM ZONE REAR YARD):	0.070M
WIDTH OF LANDSCAPE AREA PROVIDED ABUTTING RESIDENTIAL ZONE (TM ZONE ABOVE GARAGE RAMP):	7.4M

BICYCLE PARKING TYPES



VEHICLE PARKING TYPES



NOTE: TYPICAL CONFORMING STALLS HIGHLIGHTED IN YELLOW ON PLANS. REMAINING STALLS ARE NON-CONFORMING.




3019 Carling Ave, Suite 201B,
Ottawa, K2K 2A3

- ALL SITE INFORMATION TAKEN FROM PLAN OF SURVEY AS PREPARED BY FARLEY, SMITH, AND DENIS OLS, DATED SEPTEMBER 10, 2020. PART OF LOT 4 AND ALL OF LOTS 5, 6 & 42, REGISTERED PLAN 263, CITY OF OTTAWA.
- REFER TO LANDSCAPE PLANS FOR SIDEWALK, DEMARCATION OF PEDESTRIAN CLEARWAY, PAVING, AND PLANTING STRATEGIES ALL BUILDING SETBACKS AND STEPBACKS TO CONFORM TO THE ZONING AND HEIGHT SCHEDULE ATTACHED TO SITE PLAN SHEET A01.00
- PERMITTED PROJECTION DECORATIVE CORNICE DETAIL OMITTED FROM SITE PLAN FOR CLARITY
- PROJECTING CANOPIES @ GROUND LEVEL SUBJECT TO EASEMENT.

No.	DESCRIPTION	DATE	CHD
16	Updated Site Plan	2025-07-30	
15	Revised Parking - P1, P2	2025-07-14	
14	Issued to Consultants	2025-06-06	
13	Full Arch. Set	2025-04-17	
12	Schematic Design	2025-04-09	
11	Revised as per City Comments R2	2024-03-05	
10	Revised as per City Comments R2	2023-11-14	
9	Revised as per City Comments	2023-08-28	
8	Revised for Zoning Amendment	2023-04-14	
7	Revised for Zoning Amendment	2023-04-04	
6	Revised for Zoning Amendment	2023-04-03	

REVISIONS		
CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND REPORT ANY OMISSIONS OR DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.		
DO NOT SCALE THE DRAWINGS		
THIS DRAWING SHALL NOT BE USED FOR CONSTRUCTION PURPOSES UNTIL SIGNED BY THE ARCHITECT		
DATE	03/05/2024	
DRAWN	SH	
DATE	03/05/2024	
CHECKED	VPC	
DATE PRINTED	2025-07-30 5:32:29 PM	



249, 255 Richmond Road, 372
Tweedsmuir Avenue
Ottawa, ON

DWG. TITLE
Site Plan

SCALE
As indicated

PROJ. NO.
2219

DWG. NO.
A01.00

1. ALL SITE INFORMATION TAKEN FROM PLAN OF SURVEY AS PREPARED BY FARLEY, SMITH, AND DENIS OLS, DATED SEPTEMBER 10, 2011. PART OF LOT 20, & ALL OF LOTS 5, 6 & 42, REGISTERED PLAN 263, CITY OF OTTAWA.
2. REFER TO LANDSCAPE PLANS FOR SIDEWALK, DEMARCATION OF PEDESTRIAN CLEARWAY, PAVING, AND PLANTING STRATEGIES
3. ALL BUILDING SETBACKS AND TERRACES TO CONFORM TO THE SETBACKS AND HEIGHTS BY-LAW ATTACHED TO SITE PLAN SHEET A01.00
4. PERMITTED PROJECTION OF DECORATIVE CORNICE DETAIL OMITTED FROM SITE PLAN FOR CLARITY
5. PROJECTING CANOPIES AT GROUND LEVEL SUBJECT TO EASEMENT.

16	Updated Site Plan	2025-07-30
14	Issued to Consultants	2025-05-06
13	Full Arch. Set	2025-04-17
12	Schematic Design	2025-04-09
11	Issued for Zoning Amendment	2025-03-31
10	Setback & Height Review	2025-03-18
8	Issued for Draft Review	2025-02-12
7	Issued for SPA	2024-03-05
5	Revised as per City Comments	2023-08-28
3	Re-Issued for Zoning Amendment	2023-04-14
2	Re-Issued for Zoning Amendment	2023-04-04
1	Issued for Zoning Amendment	2023-04-03

REVISIONS

CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND REPORT ANY OMISSIONS OR DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.

DO NOT SCALE THE DRAWINGS

THIS DRAWING SHALL NOT BE USED FOR CONSTRUCTION PURPOSES UNTIL SIGNED BY THE ARCHITECT.

DATE	03/24/2024
DRAWN	SH
DATE	03/24/2024
CHECKED	VPC
DATE PRINTED	2025-07-30 5:32:31

VINCENT P.
COLIZZA
ARCHITECT
INCORPORATED

☐ ☐ ☐ ☐ ☐

249, 255 Richmond Road, 372
Tweedsmuir Avenue
Ottawa, ON

DWG. TITLE


Level 01 Floor Plan

SCALE	As indicated
-------	--------------

DWG. NO.


PROJ. NO.	2219
-----------	------

A10.03




1 Level 1
1 : 100

BICYCLE PARKING TYPES



VEHICLE PARKING TYPES



*NOTE: TYPICAL CONFORMING STALLS HIGHLIGHTED IN YELLOW ON PLANS. REMAINING STALLS ARE NON-CONFORMING.

Level 1 Area Summary					
Level	Name	Number	Area Designation	Area (Sqm)	Area (Sqft)
Level 1	Amenity	108	Amenity	91.40 m²	983.78 ft²
Level 1	E-Commerce	111-A	Amenity	18.17 m²	195.63 ft²
Level 1	Entrance Area Amenity	111	Amenity	130.75 m²	1407.34 ft²
Level 1	Fitness Center	150	Amenity	62.16 m²	669.07 ft²
Amenity: 4				302.48 m²	3255.83 ft²
Level 1	Corridor	100C-A	Corridors	141.84 m²	1526.76 ft²
Level 1	Corridor	100C-B	Corridors	19.28 m²	207.55 ft²
Corridors: 2				161.12 m²	1734.31 ft²
Level 1	Outdoor Amenity	100	Outdoor Amenity	150.55 m²	1620.48 ft²
Level 1	Outdoor Amenity	106	Outdoor Amenity	110.18 m²	1185.94 ft²
Outdoor Amenity: 2				260.72 m²	2806.42 ft²
Level 1	Balcony	129O	Outdoor Private Amenity	3.66 m²	39.37 ft²
Level 1	Balcony	131O	Outdoor Private Amenity	4.01 m²	43.13 ft²
Level 1	Balcony	132O	Outdoor Private Amenity	3.78 m²	40.73 ft²
Level 1	Balcony	133O	Outdoor Private Amenity	4.45 m²	47.93 ft²
Level 1	Terrace	151-O	Outdoor Private Amenity	13.95 m²	150.20 ft²
Outdoor Private Amenity: 5				29.86 m²	321.36 ft²
Level 1	Restaurant	101	Retail	211.97 m²	2281.58 ft²
Level 1	Retail	103	Retail	197.28 m²	2123.48 ft²
Level 1	Retail	104	Retail	196.96 m²	2120.04 ft²
Retail: 3				606.20 m²	6525.10 ft²
Level 1	One Bedroom	129	Unit	65.59 m²	706.00 ft²
Level 1	One Bedroom	131	Unit	56.01 m²	602.90 ft²
Level 1	One Bedroom	132	Unit	54.99 m²	591.87 ft²
Level 1	One Bedroom	133	Unit	71.24 m²	766.80 ft²
Level 1	One Bedroom (BF)	151	Unit	62.80 m²	675.94 ft²
Unit: 5				310.62 m²	3343.50 ft²

Appendix B: TIA Screening Form

City of Ottawa 2017 TIA Guidelines Screening Form

1. Description of Proposed Development

Municipal Address	249-255 Richmond Road & 372 Tweedsmuir Avenue
Description of Location	Approximately 0.54 acres in area, located north of Richmond Road and west of Tweedsmuir Avenue
Land Use Classification	High-Rise Residential with Ground-Floor Retail
Development Size (units)	127 dwellings
Development Size (m ²)	606 m² (6,523 ft²) of retail or restaurant space
Number of Accesses and Locations	One proposed access to Tweedsmuir Avenue
Phase of Development	1
Buildout Year	2026

If available, please attach a sketch of the development or site plan to this form.

2. Trip Generation Trigger

Considering the Development's Land Use type and Size (as filled out in the previous section), please refer to the Trip Generation Trigger checks below.

Land Use Type	Minimum Development Size
Single-family homes	40 units
Townhomes or apartments	90 units
Office	3,500 m ²
Industrial	5,000 m ²
Fast-food restaurant or coffee shop	100 m ²
Destination retail	1,000 m ²
Gas station or convenience market	75 m ²

** If the development has a land use type other than what is presented in the table above, estimates of person-trip generation may be made based on average trip generation characteristics represented in the current edition of the Institute of Transportation Engineers (ITE) Trip Generation Manual.*

If the proposed development size is greater than the sizes identified above, the Trip Generation Trigger is satisfied.

3. Location Triggers

	Yes	No
Does the development propose a new driveway to a boundary street that is designated as part of the City's Transit Priority, Rapid Transit or Spine Bicycle Networks?		✓
Is the development in a Design Priority Area (DPA) or Transit-oriented Development (TOD) zone?*	✓	

*DPA and TOD are identified in the City of Ottawa Official Plan (DPA in Section 2.5.1 and Schedules A and B; TOD in Annex 6). See Chapter 4 for a list of City of Ottawa Planning and Engineering documents that support the completion of TIA).

If any of the above questions were answered with 'Yes,' the Location Trigger is satisfied.

4. Safety Triggers

	Yes	No
Are posted speed limits on a boundary street are 80 km/hr or greater?		✓
Are there any horizontal/vertical curvatures on a boundary street limiting sight lines at a proposed driveway?		✓
Is the proposed driveway within the area of influence of an adjacent traffic signal or roundabout (i.e. within 300 m of intersection in rural conditions, or within 150 m of intersection in urban/suburban conditions)?		✓
Is the proposed driveway within auxiliary lanes of an intersection?		✓
Does the proposed driveway make use of an existing median break that serves an existing site?		✓
Is there is a documented history of traffic operations or safety concerns on the boundary streets within 500 m of the development?		✓
Does the development include a drive-thru facility?		✓

If any of the above questions were answered with 'Yes,' the Safety Trigger is satisfied.

5. Summary

	Yes	No
Does the development satisfy the Trip Generation Trigger?		✓
Does the development satisfy the Location Trigger?	✓	
Does the development satisfy the Safety Trigger?		✓

If none of the triggers are satisfied, the TIA Study is complete. If one or more of the triggers is satisfied, the TIA Study must continue into the next stage (Screening and Scoping).

Appendix C: OC Transpo Maps



Fréquent


WALLER BAYSHORE

7 days a week / 7 jours par semaine

All day service

Service toute la journée

WALLER



Transitway & Station



Shopping Centre / Centre commercial

04.2025

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.

Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com





51


BRITANNIA TUNNEY'S PASTURE

Local

7 days a week / 7 jours par semaine

All day service

Service toute la journée



Station



Shopping Centre / Centre commercial

04.2025

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com



Fréquent

**CARLING CAMPUS
COMPLEXE CARLING
BAYSHORE**

TUNNEY'S PASTURE

7 days a week / 7 jours par semaine

All day and limited overnight service


Service toute la journée et limité la nuit



**TUNNEY'S
PASTURE**



BAYSHORE



Transitway & Station



Shopping Centre / Centre commercial

04.2025



When O-Train Line 1 is not running overnight, Route 57 will be extended downtown to Rideau Station. / Lorsque la Ligne 1 de l'O-Train ne circule pas la nuit, le circuit 57 sera prolongée au centre-ville jusqu'à la station Rideau.

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com



60

COPE

TERRY FOX TUNNEY'S PASTURE

Local


Monday to Friday / Lundi au vendredi

All day service

Service toute la journée

**TUNNEY'S
PASTURE**

1
**Tunney's
Pasture**



TERRY FOX

COPE



Station



Transitway



Peak Periods Only / Périodes de pointe seulement



Park & Ride / Parc relais



Shopping Centre / Centre commercial

04/2025

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com



STITTSVILLE TERRY FOX


TUNNEY'S PASTURE

Fréquent

7 days a week / 7 jours par semaine

All day and limited overnight service

Service toute la journée et limité la nuit



05/2025

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com



62


STITTSVILLE TUNNEY'S PASTURE

Fréquent


7 days a week / 7 jours par semaine

All day service

Service toute la journée




Transitway & Station



Weekday southbound trips before noon and weekday northbound trips between noon and 8 p.m. travel via Iber and Abbott E.

Trajets en semaine vers le sud en avant midi et trajets en semaine vers le nord entre midi et 20 h via Iber et Abbott E.



Saturday and Sunday / Samedi et dimanche



Shopping Centre / Centre commercial



Park & Ride / Parc relais

04/2025

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com




BRIARBROOK INNOVATION TUNNEY'S PASTURE

Fréquent

7 days a week / 7 jours par semaine

All day and limited overnight service

Service toute la journée et limité la nuit



2024

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.

Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com



66


INNOVATION TUNNEY'S PASTURE

Local

Monday to Friday / Lundi au vendredi

Peak periods only

Périodes de pointe seulement



Transitway & Station

04/2025



Shopping Centre / Centre commercial



Park & Ride / Parc relais

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com



67

COPE

TERRY FOX TUNNEY'S PASTURE

Local

7 days a week / 7 jours par semaine

All day service


Service toute la journée

**TUNNEY'S
PASTURE**

**Tunney's
Pasture**



TERRY FOX



Transitway & Station



Peak Periods Only / Périodes de pointe seulement



Park & Ride / Parc relais

2025.04

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com



73


TUNNEY'S PASTURE FALLOWFIELD LIMEBANK

Local

Monday to Friday / Lundi au vendredi

All day service

Service toute la journée



Transitway & Station



Peak Periods / Périodes de pointe



Park & Ride / Parc relais



Shopping Centre / Centre commercial

05.2025

2025.05

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com




Fréquent

TUNNEY'S PASTURE LIMEBANK

7 days a week / 7 jours par semaine

All day service

Service toute la journée



Transitway & Station



Park & Ride / Parc relais



Shopping Centre / Centre commercial

05.2025

2025.05

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com



Fréquent

CAMBRIAN


TUNNEY'S PASTURE

7 days a week / 7 jours par semaine

All day and overnight service
Service toute la journée et la nuit



TUNNEY'S PASTURE



CAMBRIAN

04.2025



When O-Train Line 1 is not running overnight, Route 75 will be extended downtown to Rideau Station. / Lorsque la Ligne 1 de l'O-Train ne circule pas la nuit, le circuit 75 sera prolongée au centre-ville jusqu'à la station Rideau.

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com



81


TUNNEY'S PASTURE BAYSHORE

Local

7 days a week / 7 jours par semaine

All day service

Service toute la journée



2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.

Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com





82

TUNNEY'S PASTURE LINCOLN FIELDS

BASELINE

Local

7 days a week / 7 jours par semaine

All day service


Service toute la journée

**TUNNEY'S
PASTURE**

 **1**
**Tunney's
Pasture**

**LINCOLN
FIELDS**

BASELINE



Transitway & Station
(Peak periods / périodes de pointe)



Peak periods / périodes de pointe



Park & Ride / Parc relais



Shopping Centre / Centre commercial

04/2025

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com



Fréquent

TUNNEY'S PASTURE BASELINE


7 days a week / 7 jours par semaine

All day service

Service toute la journée



**TUNNEY'S
PASTURE**



BASELINE



Transitway & Station



Park & Ride / Parc relais



Shopping Centre / Centre commercial

04.2025

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com



256


TUNNEY'S PASTURE BRIDLEWOOD

Connexion

Monday to Friday / Lundi au vendredi

Peak periods only

Périodes de pointe seulement



Transitway & Station



Limited stops: Off only in AM / No stop in PM
Arrêts limités : débarquement en AM seulement / aucun arrêt en PM



AM: Off only - PM: Full Service
AM : débarquement seul. - PM : service complet

2024.04

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com



261

KIMPTON


TUNNEY'S PASTURE

Connexion

Monday to Friday / Lundi au vendredi

Peak periods only

Périodes de pointe seulement



Transitway & Station

04.2025



AM Peak Only / Pointe seulement



Limited stops: Off only in AM / No stop in PM
Arrêts limités : débarquement en AM seul. / aucun arrêt en PM



AM: Off only - PM: Full Service
AM : débarquement seul. - PM : service complet

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com



262

FERNBANK

TUNNEY'S PASTURE

Connexion

Monday to Friday / Lundi au vendredi


Peak periods only

Périodes de pointe seulement

AM



TUNNEY'S PASTURE



PM



FERNBANK



Transitway & Station

04.2025



AM Peak Only / Pointe seulement



Limited stops: Off only in AM / No stop in PM
Arrêts limités : débarquement en AM seul. / aucun arrêt en PM



AM: Off only - PM: Full Service
AM : débarquement seul. - PM : service complet



Park & Ride / Parc relais

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com



263


TUNNEY'S PASTURE RICHMOND

Connexion

Monday to Friday / Lundi au vendredi

Peak periods only

Périodes de pointe seulement



2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com



266


SPRINGBROOK TUNNEY'S PASTURE

Connexion

Monday to Friday / Lundi au vendredi

Peak periods only

Périodes de pointe seulement



Transitway & Station

04.2025



AM Peak Only / Pointe seulement



Limited stops: Off only in AM / No stop in PM
Arrêts limités : débarquement en AM seul. /
aucun arrêt en PM



AM: Off only - PM: Full Service
AM : débarquement seul. - PM : service complet



Shopping Centre / Centre commercial

2024

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com



275


Connexion

HALF MOON BAY TUNNEY'S PASTURE

Monday to Friday / Lundi au vendredi

Peak periods only

Périodes de pointe seulement



Transitway & Station



Limited stops: Off only in AM / No stop in PM
Arrêts limités : débarquement en AM seulement / aucun arrêt en PM



Park & Ride / Parc relais



Shopping Centre / Centre commercial

04.2025

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com




277

Connexion

NEPEAN WOODS TUNNEY'S PASTURE

Monday to Friday / Lundi au vendredi
Peak periods only
Périodes de pointe seulement



Transitway & Station



Limited stops: Off only in AM / No stop in PM
Arrêts limités: débarquement en AM seul. / aucun arrêt en PM



Park & Ride / Parc relais

04.2025

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com



279

Connexion


MANOTICK

TUNNEY'S PASTURE

Monday to Friday / Lundi au vendredi

Peak periods only

Périodes de pointe seulement



2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**

Transpo

octranspo.com

Appendix D: Traffic Count Data

Survey Date: Thursday, July 18, 2019

Start Time: 07:00


WO No:

38412

Device:

Miovision

Full Study Diagram



Survey Date: Thursday, July 18, 2019

WO No:


38412

Start Time: 07:00

Device:

Miovision

Full Study Peak Hour Diagram



Turning Movement Count - Peak Hour Diagram


ATHLONE AVE @ RICHMOND RD

Survey Date: Thursday, July 18, 2019

Start Time: 07:00

WO No: 38412

Device: Miovision



Turning Movement Count - Peak Hour Diagram


ATHLONE AVE @ RICHMOND RD

Survey Date: Thursday, July 18, 2019

Start Time: 07:00

WO No: 38412

Device: Miovision



Turning Movement Count - Peak Hour Diagram


ATHLONE AVE @ RICHMOND RD

Survey Date: Thursday, July 18, 2019

Start Time: 07:00

WO No: 38412

Device: Miovision





Transportation Services - Traffic Services

Turning Movement Count - Study Results

ATHLONE AVE @ RICHMOND RD

Survey Date: Thursday, July 18, 2019

WO No: 38412

Start Time: 07:00

Device: Miovision

Full Study Summary (8 HR Standard)

Survey Date: Thursday, July 18, 2019

Total Observed U-Turns

Northbound: 0 Southbound: 0
Eastbound: 2 Westbound: 0

AADT Factor

.90

ATHLONE AVE

RICHMOND RD

Period	Northbound					Southbound					Eastbound					Westbound					STR TOT	Grand Total
	LT	ST	RT	NB TOT		LT	ST	RT	SB TOT	STR TOT	LT	ST	RT	EB TOT		LT	ST	RT	WB TOT			
07:00 08:00	3	4	9	16		4	6	9	19	35	15	350	3	368		4	195	6	205		573	608
08:00 09:00	5	5	7	17		7	0	15	22	39	15	410	3	428		5	253	12	270		698	737
09:00 10:00	1	3	4	8		4	2	12	18	26	18	370	10	398		5	304	7	316		714	740
11:30 12:30	6	2	10	18		11	8	18	37	55	21	404	12	437		12	412	27	451		888	943
12:30 13:30	7	5	10	22		6	3	14	23	45	13	393	13	419		5	414	17	436		855	900
15:00 16:00	2	1	11	14		8	5	21	34	48	11	379	12	402		7	535	9	551		953	1001
16:00 17:00	10	1	14	25		8	5	14	27	52	9	384	10	403		14	573	13	600		1003	1055
17:00 18:00	5	6	13	24		5	9	27	41	65	15	439	10	464		7	541	18	566		1030	1095
Sub Total	39	27	78	144		53	38	130	221	365	117	3129	73	3319		59	3227	109	3395		6714	7079
U Turns	0			0		0			0	0	2			2		0			0		2	2
Total	39	27	78	144		53	38	130	221	365	119	3129	73	3321		59	3227	109	3395		6716	7081
EQ 12Hr	54	38	108	200		74	53	181	308	508	165	4349	101	4615		82	4486	152	4720		9335	9843
Note: These values are calculated by multiplying the totals by the appropriate expansion factor.																			1.39			
AVG 12Hr	49	34	97	180		67	48	163	278	458	148	3914	91	4153		74	4037	137	4248		8401	8859
Note: These volumes are calculated by multiplying the Equivalent 12 hr. totals by the AADT factor.																			.90			
AVG 24Hr	64	45	127	236		88	63	214	365	601	194	5127	119	5440		97	5288	179	5564		11004	11605

Note: These volumes are calculated by multiplying the Average Daily 12 hr. totals by 12 to 24 expansion factor.

1.31

Note: U-Turns provided for approach totals. Refer to 'U-Turn' Report for specific breakdown.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

ATHLONE AVE @ RICHMOND RD

Survey Date: Thursday, July 18, 2019

WO No: 38412

Start Time: 07:00

Device: Miovision

Full Study 15 Minute Increments

ATHLONE AVE

RICHMOND RD

Northbound

Southbound

Eastbound

Westbound

Time Period	LT	ST	RT	N TOT	LT	ST	RT	S TOT	STR TOT	LT	ST	RT	E TOT	LT	ST	RT	W TOT	STR TOT	Grand Total	
07:00	07:15	1	0	1	2	2	2	1	5	7	4	60	1	65	1	38	0	39	104	111
07:15	07:30	1	2	3	6	0	2	3	5	11	6	79	0	85	0	52	0	52	137	148
07:30	07:45	1	2	2	5	1	0	3	4	9	3	86	2	91	2	46	0	48	139	148
07:45	08:00	0	0	3	3	1	2	2	5	8	3	125	0	128	1	59	6	66	194	202
08:00	08:15	2	1	1	4	3	0	2	5	9	2	100	1	103	2	55	2	59	162	171
08:15	08:30	2	2	1	5	0	0	2	2	7	1	102	0	103	1	61	2	64	167	174
08:30	08:45	1	0	2	3	4	0	4	8	11	5	110	1	116	1	66	4	71	187	198
08:45	09:00	0	2	3	5	0	0	7	7	12	7	98	1	106	1	71	4	76	182	194
09:00	09:15	1	0	1	2	1	0	2	3	5	4	102	3	109	2	67	4	73	182	187
09:15	09:30	0	1	1	2	0	0	4	4	6	5	98	4	107	0	74	0	74	181	187
09:30	09:45	0	1	1	2	1	1	2	4	6	5	79	2	86	3	76	1	80	166	172
09:45	10:00	0	1	1	2	2	1	4	7	9	4	91	1	96	0	87	2	89	185	194
11:30	11:45	0	0	5	5	2	2	1	5	10	4	98	0	102	3	107	4	114	216	226
11:45	12:00	2	1	3	6	5	2	5	12	18	8	106	6	120	3	92	9	104	224	242
12:00	12:15	1	1	2	4	3	1	4	8	12	1	88	3	92	2	101	5	108	200	212
12:15	12:30	3	0	0	3	1	3	8	12	15	8	112	3	123	4	112	9	125	248	263
12:30	12:45	2	1	5	8	2	1	6	9	17	6	103	4	113	1	94	6	101	214	231
12:45	13:00	2	1	1	4	0	1	2	3	7	4	75	4	83	2	114	4	120	203	210
13:00	13:15	3	1	4	8	1	0	5	6	14	2	109	1	112	1	113	2	116	228	242
13:15	13:30	0	2	0	2	3	1	1	5	7	2	106	4	112	1	93	5	99	211	218
15:00	15:15	1	0	3	4	5	0	4	9	13	4	98	3	105	0	124	0	124	229	242
15:15	15:30	0	0	3	3	0	1	4	5	8	3	105	2	110	3	133	2	138	248	256
15:30	15:45	1	0	2	3	1	1	7	9	12	1	95	0	96	3	131	4	138	234	246
15:45	16:00	0	1	3	4	2	3	6	11	15	3	81	7	91	1	147	3	151	242	257
16:00	16:15	2	0	6	8	1	1	1	3	11	5	98	3	106	2	143	1	146	252	263
16:15	16:30	3	1	5	9	3	2	5	10	19	3	107	2	112	2	152	7	161	273	292
16:30	16:45	2	0	2	4	2	1	4	7	11	1	101	2	104	5	159	3	167	271	282
16:45	17:00	3	0	1	4	2	1	4	7	11	0	78	3	81	5	119	2	126	207	218
17:00	17:15	2	3	2	7	3	3	8	14	21	5	105	1	111	1	126	8	135	246	267
17:15	17:30	3	1	4	8	0	3	4	7	15	3	122	2	127	1	144	4	149	276	291
17:30	17:45	0	2	4	6	1	2	7	10	16	4	105	3	112	2	144	1	147	259	275
17:45	18:00	0	0	3	3	1	1	8	10	13	3	107	4	114	3	127	5	135	249	262
Total:		39	27	78	144	53	38	130	221	365	119	3129	73	3321	59	3227	109	3395	365	7,081

Note: U-Turns are included in Totals.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

ATHLONE AVE @ RICHMOND RD

Survey Date: Thursday, July 18, 2019

WO No: 38412

Start Time: 07:00

Device: Miovision

Full Study Cyclist Volume

		ATHLONE AVE			RICHMOND RD			Grand Total
Time Period		Northbound	Southbound	Street Total	Eastbound	Westbound	Street Total	
07:00	07:15	0	0	0	2	0	2	2
07:15	07:30	1	0	1	2	2	4	5
07:30	07:45	0	0	0	5	1	6	6
07:45	08:00	2	1	3	5	5	10	13
08:00	08:15	4	1	5	5	4	9	14
08:15	08:30	7	0	7	4	5	9	16
08:30	08:45	0	0	0	6	4	10	10
08:45	09:00	2	0	2	9	3	12	14
09:00	09:15	0	1	1	4	0	4	5
09:15	09:30	0	1	1	3	3	6	7
09:30	09:45	2	0	2	1	4	5	7
09:45	10:00	0	1	1	3	9	12	13
11:30	11:45	2	2	4	7	7	14	18
11:45	12:00	1	0	1	3	1	4	5
12:00	12:15	0	3	3	7	4	11	14
12:15	12:30	2	0	2	5	2	7	9
12:30	12:45	0	0	0	5	12	17	17
12:45	13:00	0	4	4	5	7	12	16
13:00	13:15	0	1	1	5	3	8	9
13:15	13:30	0	1	1	2	1	3	4
15:00	15:15	0	2	2	4	7	11	13
15:15	15:30	0	1	1	3	6	9	10
15:30	15:45	3	1	4	4	6	10	14
15:45	16:00	0	1	1	8	6	14	15
16:00	16:15	2	1	3	3	6	9	12
16:15	16:30	2	2	4	5	10	15	19
16:30	16:45	2	3	5	13	6	19	24
16:45	17:00	0	2	2	4	6	10	12
17:00	17:15	1	1	2	4	3	7	9
17:15	17:30	1	8	9	12	4	16	25
17:30	17:45	2	2	4	8	5	13	17
17:45	18:00	1	4	5	11	6	17	22
Total		37	44	81	167	148	315	396



Transportation Services - Traffic Services

Turning Movement Count - Study Results

ATHLONE AVE @ RICHMOND RD

Survey Date: Thursday, July 18, 2019

WO No: 38412

Start Time: 07:00

Device: Miovision

Full Study Pedestrian Volume

ATHLONE AVE

RICHMOND RD

Time Period	NB Approach (E or W Crossing)	SB Approach (E or W Crossing)	Total	EB Approach (N or S Crossing)	WB Approach (N or S Crossing)	Total	Grand Total
07:00 07:15	4	6	10	5	0	5	15
07:15 07:30	7	5	12	5	2	7	19
07:30 07:45	12	0	12	9	2	11	23
07:45 08:00	9	12	21	6	0	6	27
08:00 08:15	8	11	19	11	0	11	30
08:15 08:30	15	9	24	16	0	16	40
08:30 08:45	20	6	26	9	0	9	35
08:45 09:00	9	11	20	9	1	10	30
09:00 09:15	13	12	25	7	0	7	32
09:15 09:30	16	13	29	11	0	11	40
09:30 09:45	9	10	19	8	0	8	27
09:45 10:00	21	17	38	7	0	7	45
11:30 11:45	32	31	63	11	2	13	76
11:45 12:00	25	27	52	18	1	19	71
12:00 12:15	49	39	88	24	1	25	113
12:15 12:30	54	42	96	24	2	26	122
12:30 12:45	32	45	77	16	3	19	96
12:45 13:00	39	40	79	28	4	32	111
13:00 13:15	32	29	61	19	1	20	81
13:15 13:30	29	34	63	17	0	17	80
15:00 15:15	25	14	39	13	1	14	53
15:15 15:30	16	23	39	16	2	18	57
15:30 15:45	10	17	27	9	0	9	36
15:45 16:00	17	22	39	16	0	16	55
16:00 16:15	21	31	52	16	1	17	69
16:15 16:30	10	23	33	11	0	11	44
16:30 16:45	23	31	54	20	0	20	74
16:45 17:00	18	32	50	21	0	21	71
17:00 17:15	22	35	57	32	0	32	89
17:15 17:30	24	30	54	19	0	19	73
17:30 17:45	29	35	64	25	0	25	89
17:45 18:00	16	34	50	17	0	17	67
Total	666	726	1392	475	23	498	1890



Transportation Services - Traffic Services

Turning Movement Count - Study Results

ATHLONE AVE @ RICHMOND RD

Survey Date: Thursday, July 18, 2019

WO No: 38412

Start Time: 07:00

Device: Miovision

Full Study Heavy Vehicles

ATHLONE AVE

RICHMOND RD

Northbound

Southbound

Eastbound

Westbound

Time Period	LT	ST	RT	N TOT	LT	ST	RT	S TOT	STR TOT	LT	ST	RT	E TOT	LT	ST	RT	W TOT	STR TOT	Grand Total
07:00 07:15	0	0	0	0	0	0	0	0	0	0	5	0	5	0	4	0	4	9	9
07:15 07:30	0	0	0	0	0	0	0	0	0	0	6	0	6	0	1	0	1	7	7
07:30 07:45	0	0	0	0	0	0	0	0	0	0	1	0	1	0	4	0	4	5	5
07:45 08:00	0	0	0	0	0	0	0	0	0	0	5	0	5	0	1	0	1	6	6
08:00 08:15	0	0	0	0	0	0	0	0	0	0	4	0	4	0	3	0	3	7	7
08:15 08:30	0	0	0	0	0	0	0	0	0	0	5	0	5	0	4	0	4	9	9
08:30 08:45	0	0	0	0	0	0	0	0	0	0	4	0	4	0	5	0	5	9	9
08:45 09:00	0	0	0	0	0	0	1	1	1	0	6	0	6	0	4	0	4	10	11
09:00 09:15	0	0	0	0	0	0	0	0	0	0	5	0	5	0	3	0	3	8	8
09:15 09:30	0	0	0	0	0	0	0	0	0	0	5	0	5	0	6	0	6	11	11
09:30 09:45	0	0	0	0	0	0	0	0	0	0	4	0	4	0	7	0	7	11	11
09:45 10:00	0	0	0	0	0	0	0	0	0	1	3	0	4	0	7	0	7	11	11
11:30 11:45	0	0	0	0	0	0	0	0	0	0	3	0	3	0	1	0	1	4	4
11:45 12:00	0	0	0	0	0	0	0	0	0	0	3	0	3	0	2	0	2	5	5
12:00 12:15	0	0	0	0	0	0	0	0	0	0	3	1	4	0	5	0	5	9	9
12:15 12:30	0	0	0	0	0	0	0	0	0	0	4	0	4	0	1	0	1	5	5
12:30 12:45	0	0	0	0	0	0	0	0	0	0	2	0	2	0	5	0	5	7	7
12:45 13:00	0	0	0	0	0	0	0	0	0	0	4	1	5	0	4	0	4	9	9
13:00 13:15	0	0	0	0	0	0	0	0	0	0	2	0	2	0	4	0	4	6	6
13:15 13:30	0	0	0	0	0	0	0	0	0	0	4	0	4	0	2	0	2	6	6
15:00 15:15	0	0	0	0	0	0	0	0	0	0	3	0	3	0	0	0	0	3	3
15:15 15:30	0	0	0	0	0	0	0	0	0	0	2	0	2	0	3	0	3	5	5
15:30 15:45	0	0	0	0	0	0	0	0	0	0	2	0	2	0	1	0	1	3	3
15:45 16:00	0	0	0	0	0	0	0	0	0	0	2	0	2	0	2	0	2	4	4
16:00 16:15	0	0	0	0	0	0	0	0	0	0	3	0	3	0	5	0	5	8	8
16:15 16:30	0	0	0	0	0	0	0	0	0	0	1	0	1	0	3	0	3	4	4
16:30 16:45	0	0	0	0	0	0	2	2	2	0	0	0	0	0	2	0	2	2	4
16:45 17:00	0	0	0	0	0	0	0	0	0	0	2	0	2	0	1	0	1	3	3
17:00 17:15	0	0	0	0	0	0	0	0	0	0	4	0	4	0	1	0	1	5	5
17:15 17:30	0	0	0	0	0	0	0	0	0	0	3	0	3	0	1	0	1	4	4
17:30 17:45	0	0	0	0	0	0	0	0	0	0	1	0	1	0	5	0	5	6	6
17:45 18:00	0	0	0	0	0	0	0	0	0	0	1	0	1	0	0	0	0	1	1
Total: None	0	0	0	0	0	0	3	3	3	1	102	2	105	0	97	0	97	202	205



Transportation Services - Traffic Services

Turning Movement Count - Study Results

ATHLONE AVE @ RICHMOND RD

Survey Date: Thursday, July 18, 2019

WO No: 38412

Start Time: 07:00

Device: Miovision

Full Study 15 Minute U-Turn Total

ATHLONE AVE

RICHMOND RD

Time Period		Northbound U-Turn Total	Southbound U-Turn Total	Eastbound U-Turn Total	Westbound U-Turn Total	Total
07:00	07:15	0	0	1	0	1
07:15	07:30	0	0	0	0	0
07:30	07:45	0	0	0	0	0
07:45	08:00	0	0	0	0	0
08:00	08:15	0	0	0	0	0
08:15	08:30	0	0	0	0	0
08:30	08:45	0	0	0	0	0
08:45	09:00	0	0	0	0	0
09:00	09:15	0	0	0	0	0
09:15	09:30	0	0	0	0	0
09:30	09:45	0	0	0	0	0
09:45	10:00	0	0	0	0	0
11:30	11:45	0	0	0	0	0
11:45	12:00	0	0	0	0	0
12:00	12:15	0	0	0	0	0
12:15	12:30	0	0	0	0	0
12:30	12:45	0	0	1	0	1
12:45	13:00	0	0	0	0	0
13:00	13:15	0	0	0	0	0
13:15	13:30	0	0	0	0	0
15:00	15:15	0	0	0	0	0
15:15	15:30	0	0	0	0	0
15:30	15:45	0	0	0	0	0
15:45	16:00	0	0	0	0	0
16:00	16:15	0	0	0	0	0
16:15	16:30	0	0	0	0	0
16:30	16:45	0	0	0	0	0
16:45	17:00	0	0	0	0	0
17:00	17:15	0	0	0	0	0
17:15	17:30	0	0	0	0	0
17:30	17:45	0	0	0	0	0
17:45	18:00	0	0	0	0	0
Total		0	0	2	0	2


Survey Date: Thursday, January 23, 2020

Start Time: 07:00

WO No: 39388

Device: Miovision

Full Study Diagram



5472206 - THU JAN 23, 2020 - 8HRS - LORETTA


Survey Date: Thursday, January 23, 2020

WO No: 39388

Start Time: 07:00

Device: Miovision

Full Study Peak Hour Diagram



5472206 - THU JAN 23, 2020 - 8HRS - LORETTA



MCRAE AVE @ RICHMOND RD

Device: Miovision



Turning Movement Count - Peak Hour Diagram


MCRAE AVE @ RICHMOND RD

Survey Date: Thursday, January 23, 2020

Start Time: 07:00

WO No: 39388

Device: Miovision





Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram


MCRAE AVE @ RICHMOND RD

Survey Date: Thursday, January 23, 2020

Start Time: 07:00

WO No: 39388

Device: Miovision



Comments 5472206 - THU JAN 23, 2020 - 8HRS - LORETTA



Transportation Services - Traffic Services

Turning Movement Count - Study Results

MCRAE AVE @ RICHMOND RD

Survey Date: Thursday, January 23, 2020

WO No: 39388

Start Time: 07:00

Device: Miovision

Full Study Summary (8 HR Standard)

Survey Date: Thursday, January 23, 2020

Total Observed U-Turns

AADT Factor

Northbound: 0 Southbound: 0

1.00

Eastbound: 0 Westbound: 1

MCRAE AVE

RICHMOND RD

		Northbound				Southbound				Eastbound				Westbound						Grand Total	
Period		LT	ST	RT	NB TOT	LT	ST	RT	SB TOT	STR TOT	LT	ST	RT	EB TOT	LT	ST	RT	WB TOT	STR TOT		
07:00	08:00	4	4	11	19	63	8	29	100	119	74	293	14	381	7	169	60	236	617	736	
08:00	09:00	13	11	13	37	76	11	40	127	164	98	333	28	459	9	249	93	351	810	974	
09:00	10:00	31	21	12	64	50	25	56	131	195	59	291	39	389	14	216	72	302	691	886	
11:30	12:30	47	47	36	130	62	34	77	173	303	46	298	61	405	27	328	59	414	819	1122	
12:30	13:30	48	44	35	127	59	43	73	175	302	57	274	63	394	21	355	80	456	850	1152	
15:00	16:00	59	45	36	140	98	45	84	227	367	49	300	49	398	32	383	68	483	881	1248	
16:00	17:00	53	48	45	146	95	40	123	258	404	62	267	64	393	39	452	114	605	998	1402	
17:00	18:00	62	49	56	167	106	64	110	280	447	68	277	73	418	58	415	86	559	977	1424	
Sub Total		317	269	244	830	609	270	592	1471	2301	513	2333	391	3237	207	2567	632	3406	6643	8944	
U Turns		0			0	0			0	0	0			0	1			1	1	1	
Total		317	269	244	830	609	270	592	1471	2301	513	2333	391	3237	208	2567	632	3407	6644	8945	
EQ 12Hr		441	374	339	1154	847	375	823	2045	3199	713	3243	543	4499	289	3568	878	4735	9234	12433	
Note: These values are calculated by multiplying the totals by the appropriate expansion factor.															1.39						
AVG 12Hr		441	374	339	1154	847	375	823	2045	3199	713	3243	543	4499	289	3568	878	4735	9234	12433	
Note: These volumes are calculated by multiplying the Equivalent 12 hr. totals by the AADT factor.															1.00						
AVG 24Hr		578	490	444	1512	1110	491	1078	2679	4191	934	4248	711	5893	379	4674	1150	6203	12096	16287	

Note: These volumes are calculated by multiplying the Average Daily 12 hr. totals by 12 to 24 expansion factor.

1.31

Note: U-Turns provided for approach totals. Refer to 'U-Turn' Report for specific breakdown.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

MCRAE AVE @ RICHMOND RD

Survey Date: Thursday, January 23, 2020

WO No: 39388

Start Time: 07:00

Device: Miovision

Full Study 15 Minute Increments

MCRAE AVE

RICHMOND RD

Northbound

Southbound

Eastbound

Westbound

Time Period	LT	ST	RT	N TOT	LT	ST	RT	S TOT	STR TOT	LT	ST	RT	E TOT	LT	ST	RT	W TOT	STR TOT	Grand Total	
07:00	07:15	0	2	4	6	16	1	4	21	27	13	61	0	74	2	41	7	50	124	151
07:15	07:30	1	1	2	4	14	2	3	19	23	19	71	5	95	2	42	18	62	157	180
07:30	07:45	1	1	0	2	15	2	11	28	30	19	77	2	98	2	31	12	45	143	173
07:45	08:00	2	0	5	7	18	3	11	32	39	23	84	7	114	1	55	23	79	193	232
08:00	08:15	3	2	3	8	21	1	10	32	40	17	88	3	108	4	56	25	85	193	233
08:15	08:30	2	3	5	10	14	1	8	23	33	22	87	11	120	1	65	24	90	210	243
08:30	08:45	4	2	2	8	29	2	11	42	50	22	82	4	108	2	62	24	88	196	246
08:45	09:00	4	4	3	11	12	7	11	30	41	37	76	10	123	2	66	20	88	211	252
09:00	09:15	5	6	1	12	17	6	18	41	53	18	88	7	113	4	54	22	80	193	246
09:15	09:30	7	4	1	12	11	5	7	23	35	19	69	12	100	1	53	13	67	167	202
09:30	09:45	9	6	5	20	12	6	19	37	57	7	66	10	83	6	60	19	85	168	225
09:45	10:00	10	5	5	20	10	8	12	30	50	15	68	10	93	3	49	18	70	163	213
11:30	11:45	14	8	10	32	14	14	19	47	79	12	72	20	104	3	79	18	100	204	283
11:45	12:00	8	9	10	27	11	6	19	36	63	8	92	11	111	2	90	13	105	216	279
12:00	12:15	12	15	7	34	19	5	15	39	73	12	70	14	96	12	85	17	114	210	283
12:15	12:30	13	15	9	37	18	9	24	51	88	14	64	16	94	10	74	11	95	189	277
12:30	12:45	8	10	7	25	11	11	24	46	71	19	53	19	91	5	84	24	113	204	275
12:45	13:00	15	14	7	36	12	13	13	38	74	15	71	13	99	9	92	14	115	214	288
13:00	13:15	10	12	11	33	18	7	14	39	72	8	74	19	101	5	87	24	116	217	289
13:15	13:30	15	8	10	33	18	12	22	52	85	15	76	12	103	3	92	18	113	216	301
15:00	15:15	14	6	8	28	27	12	16	55	83	14	82	12	108	8	95	13	116	224	307
15:15	15:30	22	11	10	43	20	15	18	53	96	9	82	13	104	7	81	12	100	204	300
15:30	15:45	13	17	11	41	21	7	29	57	98	12	65	7	84	5	102	14	121	205	303
15:45	16:00	10	11	7	28	30	11	21	62	90	14	71	17	102	12	105	29	146	248	338
16:00	16:15	7	12	13	32	30	9	25	64	96	18	56	8	82	12	99	32	143	225	321
16:15	16:30	12	11	12	35	20	13	30	63	98	15	74	20	109	11	131	30	172	281	379
16:30	16:45	19	13	11	43	23	9	35	67	110	16	76	16	108	9	113	29	151	259	369
16:45	17:00	15	12	9	36	22	9	33	64	100	13	61	20	94	7	109	23	139	233	333
17:00	17:15	17	9	13	39	36	18	29	83	122	25	75	24	124	22	109	23	154	278	400
17:15	17:30	14	11	14	39	28	20	28	76	115	7	52	17	76	8	110	20	138	214	329
17:30	17:45	9	14	17	40	20	13	19	52	92	15	68	13	96	18	105	23	146	242	334
17:45	18:00	22	15	12	49	22	13	34	69	118	21	82	19	122	10	91	20	121	243	361
Total:		317	269	244	830	609	270	592	1471	2301	513	2333	391	3237	208	2567	632	3407	2301	8,945

Note: U-Turns are included in Totals.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

MCRAE AVE @ RICHMOND RD

Survey Date: Thursday, January 23, 2020

WO No: 39388

Start Time: 07:00

Device: Miovision

Full Study Cyclist Volume

		MCRAE AVE			RICHMOND RD			Grand Total
Time Period		Northbound	Southbound	Street Total	Eastbound	Westbound	Street Total	
07:00	07:15	0	0	0	0	0	0	0
07:15	07:30	0	0	0	2	0	2	2
07:30	07:45	0	0	0	0	0	0	0
07:45	08:00	0	0	0	2	0	2	2
08:00	08:15	0	0	0	1	2	3	3
08:15	08:30	0	0	0	0	0	0	0
08:30	08:45	0	0	0	3	1	4	4
08:45	09:00	0	0	0	1	0	1	1
09:00	09:15	0	0	0	2	0	2	2
09:15	09:30	0	0	0	0	1	1	1
09:30	09:45	0	0	0	1	1	2	2
09:45	10:00	0	0	0	0	1	1	1
11:30	11:45	0	0	0	0	0	0	0
11:45	12:00	0	0	0	0	0	0	0
12:00	12:15	0	0	0	0	0	0	0
12:15	12:30	0	0	0	1	0	1	1
12:30	12:45	1	0	1	0	0	0	1
12:45	13:00	0	0	0	2	0	2	2
13:00	13:15	0	1	1	1	0	1	2
13:15	13:30	0	0	0	0	0	0	0
15:00	15:15	0	0	0	1	0	1	1
15:15	15:30	0	0	0	1	0	1	1
15:30	15:45	0	0	0	1	2	3	3
15:45	16:00	0	0	0	1	0	1	1
16:00	16:15	2	0	2	0	0	0	2
16:15	16:30	0	0	0	0	2	2	2
16:30	16:45	0	2	2	1	1	2	4
16:45	17:00	2	1	3	4	1	5	8
17:00	17:15	0	0	0	0	3	3	3
17:15	17:30	0	0	0	0	0	0	0
17:30	17:45	0	2	2	0	0	0	2
17:45	18:00	0	0	0	0	0	0	0
Total		5	6	11	25	15	40	51



Transportation Services - Traffic Services

Turning Movement Count - Study Results

MCRAE AVE @ RICHMOND RD

Survey Date: Thursday, January 23, 2020

WO No: 39388

Start Time: 07:00

Device: Miovision

Full Study Pedestrian Volume

MCRAE AVE

RICHMOND RD

Time Period	NB Approach (E or W Crossing)	SB Approach (E or W Crossing)	Total	EB Approach (N or S Crossing)	WB Approach (N or S Crossing)	Total	Grand Total
07:00 07:15	7	3	10	2	0	2	12
07:15 07:30	6	5	11	1	4	5	16
07:30 07:45	7	8	15	2	5	7	22
07:45 08:00	29	11	40	5	11	16	56
08:00 08:15	9	1	10	4	8	12	22
08:15 08:30	12	7	19	4	5	9	28
08:30 08:45	18	14	32	6	11	17	49
08:45 09:00	5	4	9	2	3	5	14
09:00 09:15	5	9	14	0	6	6	20
09:15 09:30	13	11	24	6	11	17	41
09:30 09:45	14	6	20	4	14	18	38
09:45 10:00	12	7	19	4	9	13	32
11:30 11:45	25	10	35	3	29	32	67
11:45 12:00	12	18	30	4	19	23	53
12:00 12:15	35	20	55	11	35	46	101
12:15 12:30	30	21	51	5	23	28	79
12:30 12:45	36	22	58	23	24	47	105
12:45 13:00	24	28	52	13	27	40	92
13:00 13:15	21	17	38	6	22	28	66
13:15 13:30	32	17	49	6	33	39	88
15:00 15:15	28	17	45	12	20	32	77
15:15 15:30	22	13	35	8	21	29	64
15:30 15:45	42	26	68	12	26	38	106
15:45 16:00	37	27	64	11	27	38	102
16:00 16:15	41	20	61	26	27	53	114
16:15 16:30	39	16	55	12	23	35	90
16:30 16:45	46	20	66	23	19	42	108
16:45 17:00	35	29	64	10	31	41	105
17:00 17:15	32	26	58	15	35	50	108
17:15 17:30	25	19	44	13	32	45	89
17:30 17:45	31	38	69	29	31	60	129
17:45 18:00	42	26	68	18	29	47	115
Total	772	516	1288	300	620	920	2208

5472206 - THU JAN 23, 2020 - 8HRS - LORETTA



Transportation Services - Traffic Services

Turning Movement Count - Study Results

MCRAE AVE @ RICHMOND RD

Survey Date: Thursday, January 23, 2020

WO No: 39388

Start Time: 07:00

Device: Miovision

Full Study Heavy Vehicles

MCRAE AVE

RICHMOND RD

Northbound

Southbound

Eastbound

Westbound

Time Period		Northbound			N TOT	Southbound			S TOT	STR TOT	Eastbound			E TOT	Westbound			W TOT	STR TOT	Grand Total
		LT	ST	RT		LT	ST	RT			LT	ST	RT		LT	ST	RT			
07:00	07:15	0	0	0	0	2	0	0	2	2	1	2	0	3	1	1	0	2	5	7
07:15	07:30	0	0	0	0	0	0	1	1	1	0	3	1	4	0	3	1	4	8	9
07:30	07:45	0	0	0	0	1	0	0	1	1	0	3	0	3	1	3	2	6	9	10
07:45	08:00	0	0	0	0	1	0	1	2	2	0	3	0	3	0	2	1	3	6	8
08:00	08:15	0	0	0	0	3	0	1	4	4	0	4	0	4	0	6	1	7	11	15
08:15	08:30	0	0	0	0	3	0	1	4	4	1	6	0	7	0	5	2	7	14	18
08:30	08:45	0	0	0	0	3	0	0	3	3	0	7	1	8	1	4	2	7	15	18
08:45	09:00	0	0	0	0	1	0	1	2	2	1	1	0	2	0	4	4	8	10	12
09:00	09:15	0	0	0	0	2	0	1	3	3	1	3	0	4	0	4	3	7	11	14
09:15	09:30	1	0	0	1	2	0	0	2	3	1	4	0	5	0	3	0	3	8	11
09:30	09:45	0	0	0	0	3	0	0	3	3	0	5	2	7	0	4	2	6	13	16
09:45	10:00	1	0	0	1	0	0	2	2	3	1	6	1	8	0	1	3	4	12	15
11:30	11:45	0	0	0	0	1	1	0	2	2	0	1	0	1	0	5	1	6	7	9
11:45	12:00	0	0	0	0	1	0	1	2	2	0	3	0	3	0	2	2	4	7	9
12:00	12:15	0	0	0	0	3	1	0	4	4	1	5	0	6	1	4	1	6	12	16
12:15	12:30	0	0	0	0	0	0	0	0	0	0	4	0	4	0	3	1	4	8	8
12:30	12:45	1	0	1	2	3	0	1	4	6	0	3	1	4	0	5	2	7	11	17
12:45	13:00	0	1	1	2	1	1	0	2	4	0	2	1	3	1	4	2	7	10	14
13:00	13:15	0	0	0	0	4	0	0	4	4	0	4	0	4	0	2	2	4	8	12
13:15	13:30	0	0	0	0	1	0	0	1	1	0	1	0	1	1	4	1	6	7	8
15:00	15:15	0	0	0	0	2	0	0	2	2	0	4	0	4	0	4	2	6	10	12
15:15	15:30	0	0	1	1	1	0	0	1	2	0	2	0	2	0	2	0	2	4	6
15:30	15:45	0	0	0	0	1	0	0	1	1	0	1	0	1	1	0	2	3	4	5
15:45	16:00	0	0	0	0	2	0	0	2	2	0	1	0	1	1	3	0	4	5	7
16:00	16:15	0	1	0	1	2	0	0	2	3	0	2	0	2	0	2	4	6	8	11
16:15	16:30	0	0	0	0	1	0	0	1	1	0	2	0	2	0	2	0	2	4	5
16:30	16:45	0	0	0	0	1	0	0	1	1	0	1	0	1	0	0	1	1	2	3
16:45	17:00	0	0	0	0	2	0	1	3	3	0	1	0	1	0	0	1	1	2	5
17:00	17:15	0	0	0	0	1	0	0	1	1	0	3	0	3	0	3	2	5	8	9
17:15	17:30	0	0	0	0	1	0	0	1	1	0	0	0	0	0	1	0	1	1	2
17:30	17:45	0	0	0	0	1	0	0	1	1	0	2	0	2	2	0	1	3	5	6
17:45	18:00	0	0	0	0	1	0	0	1	1	0	1	0	1	0	1	0	1	2	3
Total:	None	3	2	3	8	51	3	11	65	73	7	90	7	104	10	87	46	143	247	320



Transportation Services - Traffic Services

Turning Movement Count - Study Results

MCRAE AVE @ RICHMOND RD

Survey Date: Thursday, January 23, 2020

WO No: 39388

Start Time: 07:00

Device: Miovision

Full Study 15 Minute U-Turn Total

MCRAE AVE

RICHMOND RD

Time Period		Northbound U-Turn Total	Southbound U-Turn Total	Eastbound U-Turn Total	Westbound U-Turn Total	Total
07:00	07:15	0	0	0	0	0
07:15	07:30	0	0	0	0	0
07:30	07:45	0	0	0	0	0
07:45	08:00	0	0	0	0	0
08:00	08:15	0	0	0	0	0
08:15	08:30	0	0	0	0	0
08:30	08:45	0	0	0	0	0
08:45	09:00	0	0	0	0	0
09:00	09:15	0	0	0	0	0
09:15	09:30	0	0	0	0	0
09:30	09:45	0	0	0	0	0
09:45	10:00	0	0	0	0	0
11:30	11:45	0	0	0	0	0
11:45	12:00	0	0	0	0	0
12:00	12:15	0	0	0	0	0
12:15	12:30	0	0	0	0	0
12:30	12:45	0	0	0	0	0
12:45	13:00	0	0	0	0	0
13:00	13:15	0	0	0	1	1
13:15	13:30	0	0	0	0	0
15:00	15:15	0	0	0	0	0
15:15	15:30	0	0	0	0	0
15:30	15:45	0	0	0	0	0
15:45	16:00	0	0	0	0	0
16:00	16:15	0	0	0	0	0
16:15	16:30	0	0	0	0	0
16:30	16:45	0	0	0	0	0
16:45	17:00	0	0	0	0	0
17:00	17:15	0	0	0	0	0
17:15	17:30	0	0	0	0	0
17:30	17:45	0	0	0	0	0
17:45	18:00	0	0	0	0	0
Total		0	0	0	1	1

Appendix E: Collision Records



Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2015 To: December 31, 2019

Location: ATHLONE AVE @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 8

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2015-Mar-28, Sat,11:02	Clear	Angle	P.D. only	Dry	South	Going ahead	Pick-up truck	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2015-Sep-16, Wed,15:32	Clear	Angle	P.D. only	Dry	South	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2015-Nov-20, Fri,17:57	Clear	Rear end	P.D. only	Dry	West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
					West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2018-Feb-17, Sat,21:15	Clear	Angle	Non-fatal injury	Dry	South	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2018-Jul-09, Mon,12:20	Clear	Sideswipe	P.D. only	Dry	West	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2018-Aug-28, Tue,19:26	Clear	Angle	P.D. only	Dry	South	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Turning right	Automobile, station wagon	Other motor vehicle	
2019-Feb-03, Sun,17:12	Snow	SMV unattended vehicle	P.D. only	Loose snow	East	Going ahead	Municipal transit bus	Unattended vehicle	0
2019-Nov-01, Fri,19:19	Rain	Angle	P.D. only	Wet	South	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	

Location: MCRAE AVE @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 14

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2015-Aug-29, Sat,08:15	Clear	Rear end	P.D. only	Dry	East	Going ahead	Pick-up truck	Other motor vehicle	0
					East	Stopped	Pick-up truck	Other motor vehicle	
2015-Dec-12, Sat,08:55	Clear	Angle	P.D. only	Dry	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					South	Going ahead	Pick-up truck	Other motor vehicle	



Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2015 **To:** December 31, 2019

Location: MCRAE AVE @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 14

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2017-Jan-30, Mon,13:48	Clear	SMV other	Non-fatal injury	Dry	West	Turning left	Automobile, station wagon	Pedestrian	1
2017-Jul-15, Sat,13:28	Clear	SMV other	Non-fatal injury	Dry	West	Turning left	Automobile, station wagon	Pedestrian	1
2017-Dec-23, Sat,15:30	Snow	Rear end	P.D. only	Loose snow	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2018-Feb-16, Fri,13:02	Clear	SMV other	Non-fatal injury	Wet	West	Turning left	Automobile, station wagon	Pedestrian	1
2018-Mar-11, Sun,16:28	Clear	Angle	P.D. only	Dry	South	Reversing	Automobile, station wagon	Other motor vehicle	0
					East	Turning left	Automobile, station wagon	Other motor vehicle	
2018-Apr-06, Fri,12:32	Clear	Rear end	P.D. only	Dry	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2018-Apr-12, Thu,08:30	Freezing Rain	Rear end	P.D. only	Wet	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	
2018-Jun-27, Wed,17:01	Clear	Sideswipe	P.D. only	Dry	West	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2018-Nov-22, Thu,19:35	Clear	Turning movement	Non-fatal injury	Dry	East	Making "U" turn	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Pick-up truck	Other motor vehicle	
2019-Jan-12, Sat,10:00	Clear	Rear end	P.D. only	Packed snow	South	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					South	Stopped	Automobile, station wagon	Other motor vehicle	
					South	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Jan-19, Sat,16:30	Snow	Rear end	P.D. only	Loose snow	West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Feb-16, Sat,15:34	Clear	SMV unattended vehicle	P.D. only	Dry	East	Turning right	Truck and trailer	Unattended vehicle	0



Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2015 **To:** December 31, 2019

Location: RICHMOND RD @ TWEEDSMUIR AVE

Traffic Control: Stop sign

Total Collisions: 7

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2015-Mar-03, Tue,18:55	Snow	Angle	P.D. only	Packed snow	South	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2015-Jun-10, Wed,12:17	Clear	Turning movement	Non-fatal injury	Dry	West	Going ahead	Bicycle	Other motor vehicle	0
					West	Turning right	Automobile, station wagon	Cyclist	
2015-Aug-22, Sat,14:58	Rain	SMV other	Non-fatal injury	Wet	West	Going ahead	Motorcycle	Skidding/sliding	0
2017-Sep-16, Sat,18:42	Clear	Angle	P.D. only	Dry	South	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Jul-16, Tue,21:21	Clear	Angle	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Nov-15, Fri,13:30	Unknown	Rear end	P.D. only	Wet	West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Unknown	Other motor vehicle	
2019-Dec-29, Sun,03:11	Clear	Angle	Non-fatal injury	Wet	North	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	

Location: RICHMOND RD btwn ATHLONE AVE & TWEEDSMUIR AVE

Traffic Control: No control

Total Collisions: 6

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2015-May-21, Thu,16:45	Clear	Angle	P.D. only	Dry	North	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Turning left	Pick-up truck	Other motor vehicle	
2015-May-22, Fri,12:55	Clear	Other	P.D. only	Dry	West	Reversing	Automobile, station wagon	Other motor vehicle	0
					East	Slowing or stopping	Pick-up truck	Other motor vehicle	
2015-Oct-30, Fri,19:40	Clear	Angle	P.D. only	Dry	North	Turning right	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	



Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2015 **To:** December 31, 2019

Location: RICHMOND RD btwn ATHLONE AVE & TWEEDSMUIR AVE

Traffic Control: No control

Total Collisions: 6

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2016-Apr-28, Thu,19:30	Clear	Sideswipe	Non-fatal injury	Dry	East	Stopped	Automobile, station wagon	Cyclist	0
					East	Going ahead	Bicycle	Other motor vehicle	
2019-Jun-02, Sun,19:30	Clear	Angle	P.D. only	Dry	North	Turning right	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Jul-24, Wed,18:08	Clear	Angle	Non-fatal injury	Dry	North	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Motorcycle	Other motor vehicle	


Location: RICHMOND RD btwn TWEEDSMUIR AVE & MCRAE AVE

Traffic Control: No control

Total Collisions: 2

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2015-Sep-14, Mon,09:24	Clear	SMV unattended vehicle	Non-fatal injury	Dry	East	Going ahead	Passenger van	Unattended vehicle	0
2017-Jan-16, Mon,00:00	Clear	SMV unattended vehicle	P.D. only	Dry	Unknown	Unknown	Unknown	Unattended vehicle	0

Appendix F: Other Area Developments



NOVATECH
ENGINEERING
CONSULTANTS LTD.

ENGINEERS & PLANNERS
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada
K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Email: novainfo@novatech-eng.com

LEGEND

- Unsignalized Intersection
- Signalized Intersection
- xx VPH AM Peak Hour
- (xx) VPH PM Peak Hour

175 RICHMOND ROAD

PROPOSED SITE TRAFFIC

SEP 2011

111130

FIGURE 9

Figure 13: New Site Generation Auto Volumes





Figure 10: Site Generated Traffic



1 Screening

This study has been prepared according to the City of Ottawa's 2017 Transportation Impact Assessment (TIA) Guidelines. Accordingly, a Step 1 Screening Form has been prepared and is included as Appendix A, along with the Certification Form for TIA Study PM. As shown in the Screening Form, a TIA is required including the Design Review Component and the Network Impact Component.

2 Existing and Planned Conditions

2.1 Proposed Development

The proposed development, located at 381 Churchill Avenue, 380 Winona Avenue, 319, 325, and 327 Richmond Road, is currently zoned as part Traditional Mainstreet (TM H15), part General Mixed Use (GM1), and part Residential Fourth Density (R4). The existing land uses include a car garage and maintenance shop, two small retail stores and a residential apartment with six units. TOD principles apply to the proposed development Study Area.

The proposed development is a nine-storey building with 184 apartment units, 1738 square metres of retail space, 130 vehicle parking spots, and 99 bicycle parking spaces. The site is proposed to have two accesses; one of which is a full movement access on Churchill Avenue approximately 65 metres north of the Churchill Avenue / Richmond Road intersection (measured from access centreline to intersection centre). The second access is located on Winona Avenue approximately 50 metres north of the Winona Avenue / Richmond Road intersection (measured from access centreline to intersection centre) and is a loading entrance with access solely to loading aisles. The anticipated full build-out and occupancy horizon is 2022. Figure 1 illustrates the Study Area context. Figure 2 illustrates the proposed site plan of the development.

Figure 1: Area Context Plan





Figure 13: New Site Generation Auto Volumes



6 Background Network Travel Demands

6.1 Transportation Network Plans

The transportation network plans were discussed in Section 2.3.1. Both TOD policies and the opening of the Westboro LRT station and Dominion LRT station have been accounted for within the modal share assumptions. No road improvements are noted for this area with the exception of future road sewer, and water work along Winona Avenue.

1 Screening

This study has been prepared according to the City of Ottawa's 2017 Transportation Impact Assessment (TIA) Guidelines. Accordingly, a Step 1 Screening Form has been prepared and is included as Appendix A, along with the Certification Form for TIA Study PM. As shown in the Screening Form, a TIA is required including the Design Review component and the Network Impact Component. This study has been prepared to support a site plan application for 320 McRae Avenue.

2 Existing and Planned Conditions

2.1 Proposed Development

The proposed development located at 320 McRae Avenue is currently a mix of residential and commercial buildings. The site is in an area that is zoned as part Traditional Mainstreet (TM 2489 S382-h), part Parks and Open Space (O 1) and part General Mixed Zone (GM2490 H (15) h). The proposed development is within 400 metres of the future Westboro LRT Station to be built by 2025 and therefore TOD principles apply to the applicable future horizons.

The proposed development is made up of a four-storey commercial / residential tower, and a commercial / residential tower with both a 26-storey and a six-storey component. The development is expected to have 882 square metres (9,494 square feet) of commercial space, 307 apartment units, 11 townhouse units, 185 underground automobile parking spaces and 163 bicycle parking spaces. Of the 163 bicycle spaces, 123 will be underground and due to space restrictions, 15 bicycle parking spaces will be slightly off the property and 25 will be in the loading area. The site is proposed to have two full-movement accesses, one approximately 40 metres, curb to curb, south of Scott Street on Tweedsmuir Avenue (Site Access #1) and the second approximately 120 metres, curb to curb, south of Scott Street on McRae Avenue (Site Access #2). Site Access #2 is a loading access and is intended for truck use only. A drop-off area is located on McRae Avenue, approximately 23 metres, curb to curb, south of Scott Street. The anticipated full build-out and occupancy horizon is 2022. Figure 1 illustrates the Study Area Context. Figure 2 illustrates the proposed concept plan.

Figure 1: Area Context Plan




Figure 13: New 2022 Site Generation Auto Volumes





Figure 14: New 2027 Site Generation Auto Volumes




6 Background Network Travel Demands

6.1 Transportation Network Plans

The transportation network plans were discussed in Section 2.3.1. The opening of the Westboro LRT station and Dominion LRT station, isolated measure transit priority along Richmond Road and TOD policies have been accounted for within the modal share assumptions. No road improvements within the study horizons are noted for this area.

The additional connectivity provided by future bicycle spine routes along Scott Street and Richmond Road as part of the City of Ottawa ultimate cycling plan will improve the active mode network.

Figure 7: Site Generated Traffic Volumes



2.5 Access Design

The proposed development will be served by two full movement accesses, one along Roosevelt Avenue and the other along Wilmont Avenue. The two buildings and the underground parking garage will be constructed in two phases; however, the garages will be connected internally once the construction is completed.

Roosevelt Avenue at the north end will be extended to form a cul-de-sac and will provide connectivity to the multi-use pathway. Winston Avenue will also be extended at the north end such that it forms a cul-de-sac between the two proposed buildings and will be used as pickup and drop off location.

1. Step 1 - Screening Form

With respect to the City of Ottawa's 2017 Transportation Impact Assessment (TIA) Guidelines, the proposed development (described below in Section 2.1) triggered the trip generation, location, and the safety criteria outlined in the City's TIA Step 1 – Screening form. Given these three (3) triggers were met, a formal TIA (i.e. completed Steps 1-5) must accompany the subject development application.

2. Step 2 - Scoping

2.1 Existing and Planned Conditions

Description of Proposed Development

The subject site is municipally known as 403 Richmond Road and 389 Roosevelt Avenue, and is currently bound by Richmond Road to the south, Roosevelt Avenue to the west, commercial/residential land uses to the east and residential land uses to the north. Based on the available/provided information, the subject site is currently occupied by a funeral home (403 Richmond Road) and a single family home (389 Roosevelt Avenue) and is planned to be replaced by a 9 storey mix-used building with 141 residential units, a 10th floor amenity space and 5,283 ft² of ground floor commercial space. The development will be constructed in a single phase, with an estimated build-out year of 2025.

The latest Concept Plan depicts that the development will have one vehicular full-movement access point utilizing the existing driveway connection at Roosevelt Avenue, which is to the west of the site. All parking will be provided in an underground parking facility with access/egress located on the back side of the building. There will be no vehicular access point from Richmond Road (i.e. the existing driveway connection to Richmond Road will be closed).

Pedestrians will have direct access to existing sidewalks along both Roosevelt Avenue and Richmond Road, which connects with a well-developed surrounding pedestrian network. Cyclists will be able to use the dedicated cycling network along Scott Street to the north, or Byron Avenue to the south to access the City's established off-road cycling network. The surrounding active transportation network also provides convenient access to/from the public transit via the existing BRT Dominion station, as well as local bus service along Richmond Road and Churchill Avenue.

The local context of the subject development site is provided in the following **Figure 1**, and the proposed Concept Plan is provided in the subsequent **Figure 2**.





Figure 14: 'New' Projected Site-Generated Traffic



1.0 SCREENING

1.1 Introduction

This Transportation Impact Assessment (TIA) has been prepared in support of a Site Plan application for a proposed development at 2006 Scott Street, 2020 Scott Street, 2026 Scott Street, 314 Athlone Avenue, 316 Athlone Avenue, and 318 Athlone Avenue.

The subject site is surrounded by the following:

- Scott Street and the OC Transpo East-West Transitway to the north;
- Ashton Avenue, Lion's Park, and residential properties fronting Athlone Avenue to the south;
- Athlone Avenue and residential uses to the east; and
- Various existing low-rise retail uses along Scott Street to the west. A residential development is proposed at 2050 Scott Street, directly abutting the subject site to the west.

A view of the subject site is provided in **Figure 1**.

The property at 2026 Scott Street is currently occupied by the Granite Curling Club, which will be relocated to 2740 Queensview Drive. The site is currently served by an existing full-movement access to Scott Street and a rear access at the eastern terminus of Ashton Avenue.

The property at 2020 Scott Street was previously occupied by a used car dealer, with access to Scott Street. The property at 2006 Scott Street was previously occupied by a retail store, with access to Scott Street. The property at 314 Athlone Avenue is currently being used as an office space, while the properties at 316 and 318 Athlone Avenue are residential homes. All existing buildings on-site will be demolished as part of this application.

1.2 Proposed Development

The subject site is designated as 'Corridor – Mainstreet' (Scott Street) in Schedule B2 of the City of Ottawa's Official Plan and zoned as 'Traditional Mainstreet' (TM[2829]). The original TIA in support of a Zoning By-Law Amendment application for this development was submitted in April 2022 and resubmitted in September 2022 (City Application No. D02-02-22-0037).

The proposed development consists of two 40-storey towers with a total of 856 dwelling units and approximately 3,207 ft² of ground-floor commercial space. Phase 1 of the development includes the East Building, which consists of 392 dwellings and 1,287 ft² of commercial space. Phase 2 of the development includes the West Building, which consists of 464 dwellings and 1,920 ft² of commercial space. An underground parking garage with a total of 373 parking spaces will be provided beneath the entire development. The development will be accessed via one full-movement driveway to Athlone Avenue, which will be the only access constructed as part of Phase 1. One full-movement driveway to Scott Street will be constructed as part of Phase 2. The parking garage will be constructed in two phases, but the two phases will not be separated once complete (i.e. vehicles will be able to access any parking area from either driveway). Buildout of Phase 1 is anticipated to occur in 2026 and buildout of Phase 2 is anticipated to occur in 2029.

A copy of the site plan is included in **Appendix A**. A site context plan, which includes the site plan and shows all details of the roadway network immediately surrounding the site, is included in **Figure 2**.

Figure 8: Proposed Site-Generated Traffic Volumes (2026)




Figure 9: Proposed Site-Generated Traffic Volumes (2031)




Figure 10: Net Site-Generated Traffic Volumes (2026)





Figure 11: Net Site-Generated Traffic Volumes (2031)



TIA STRATEGY REPORT

The following Strategy Report has been prepared in support of a Site Plan Application (SPA) for the proposed residential development located at 2050 Scott Street. This document follows the TIA process, as outlined in the City Transportation Impact Assessment (TIA) Guidelines (2017). City comments and responses have been included as Appendix A.

1. Screening Form

The completed Screening Form for the proposed residential development at 2050 Scott Street confirmed the need for a TIA in support of the proposed development based on the Trip Generation, Location and Safety triggers. The proposed development consists of approximately 355 residential units; is located in a Design Priority Area (DPA) and Transit Oriented Development (TOD) area; and has a proposed driveway within the influence area of an adjacent traffic signal. The Screening Form is provided in Appendix B.

2. Scoping Report

2.1. Existing and Planned Conditions


2.1.1. PROPOSED DEVELOPMENT

It is our understanding that the proponent is proposing to construct a residential development located at 2050 Scott Street. A single-phased project is proposed with assumed buildout year of 2021. The development will consist of a 30-storey residential building on a 3- and 6-storey podiums with approximately 353 units and 233 m² of ground commercial/office. The taller portion of the building is located closer to Scott Street while the 3- and 6-storey podiums extend towards Ashton Avenue. Vehicle access is proposed at Scott Street via a single all movement driveway. An underground parking lot with 210 vehicle spaces and 292 bicycle spaces are proposed. The site is located between 2 different land zonings, TM[103] fronting Scott Street and R4G on the south portion of the parcel towards Ashton Avenue. This TIA is in support of a Zoning By-Law Amendment (ZBLA) and Site Plan Application (SPA) to vary the height schedule from 6-storeys (18 meters) to 30-storeys within the TM zoning and from 4-storeys (11 meters) to 6-storeys within the R4 zoning. Height step-backs (staggering) are proposed to assist in the transition from low-rise to mid- and high-rise from south to north. The site is currently occupied by a mechanic garage, a hot tub retailer and 3 residential houses. The local context of the site is provided as **Figure 1** and the proposed Site Plan is provided as **Figure 2**.

Figure 1: Local Context



Figure 9: 'New' Site-Generated Traffic




3.2. Background Network Travel Demands

3.2.1. TRANSPORTATION NETWORK PLANS

As mentioned in Section 2.1.3 Planned Conditions, 210 to 225 buses will be detoured on to Scott Street for the AM and PM peak periods respectively as part of the Stage 2 LRT West Extension construction. These buses were layered on to the study area intersections for the duration of anticipated construction (2021 to 2025) and are exhibited in **Figure 10**. Note that as part of the bus detours, Churchill/Scott intersection will be upgraded to a signalized intersection.

Figure 10: Buses Detoured on Scott Street



3.2.2. BACKGROUND GROWTH & OTHER DEVELOPMENTS

The emphasis in the City's recent Official Plan and Transportation Master Plan is to place priority on transit, encourage intensification around transit stations, encourage mixed-use developments and provide "complete streets" that better accommodate the active transportation needs of its residents and reduce the use of the private auto. Given the location of the site near future Confederation Line LRT Extension and future Scott Street 'Complete Street' plan, the trips generated from this development as well as nearby developments will likely choose alternate modes of transportation over driving. It is expected to see a decrease in vehicle traffic along Scott Street in the future as the public transportation network near the site becomes mature and alternate modes of transportation become more desirable (see map of anticipated background growth attached as Appendix F). As such, the background vehicle traffic volumes for horizon year 2026 is assumed to be the same as year 2021.

The projected vehicle volumes from the planned area developments as discussed in Section 2.1.3. 'Planned Conditions – Other Area Developments' were added to the study area intersections and are shown in **Figure 11**. The volumes from the other area development along with detoured buses were layered onto the existing traffic volumes for the future interim analysis volumes. Since the bus detour are anticipated between 2021 and 2025, they have been removed from 2026

Appendix G: TDM Checklists

TDM-Supportive Development Design and Infrastructure Checklist: *Non-Residential Developments (office, institutional, retail or industrial)*

Legend	
REQUIRED	The Official Plan or Zoning By-law provides related guidance that must be followed
BASIC	The measure is generally feasible and effective, and in most cases would benefit the development and its users
BETTER	The measure could maximize support for users of sustainable modes, and optimize development performance

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
1. WALKING & CYCLING: ROUTES		
1.1 Building location & access points		
BASIC	1.1.1 Locate building close to the street, and do not locate parking areas between the street and building entrances	☒
BASIC	1.1.2 Locate building entrances in order to minimize walking distances to sidewalks and transit stops/stations	☒
BASIC	1.1.3 Locate building doors and windows to ensure visibility of pedestrians from the building, for their security and comfort	☒
1.2 Facilities for walking & cycling		
REQUIRED	1.2.1 Provide convenient, direct access to stations or major stops along rapid transit routes within 600 metres; minimize walking distances from buildings to rapid transit; provide pedestrian-friendly, weather-protected (where possible) environment between rapid transit accesses and building entrances; ensure quality linkages from sidewalks through building entrances to integrated stops/stations (<i>see Official Plan policy 4.3.3</i>)	☒
REQUIRED	1.2.2 Provide safe, direct and attractive pedestrian access from public sidewalks to building entrances through such measures as: reducing distances between public sidewalks and major building entrances; providing walkways from public streets to major building entrances; within a site, providing walkways along the front of adjoining buildings, between adjacent buildings, and connecting areas where people may congregate, such as courtyards and transit stops; and providing weather protection through canopies, colonnades, and other design elements wherever possible (<i>see Official Plan policy 4.3.12</i>)	☒

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
REQUIRED	1.2.3 Provide sidewalks of smooth, well-drained walking surfaces of contrasting materials or treatments to differentiate pedestrian areas from vehicle areas, and provide marked pedestrian crosswalks at intersection sidewalks (<i>see Official Plan policy 4.3.10</i>)	☒
REQUIRED	1.2.4 Make sidewalks and open space areas easily accessible through features such as gradual grade transition, depressed curbs at street corners and convenient access to extra-wide parking spaces and ramps (<i>see Official Plan policy 4.3.10</i>)	☒
REQUIRED	1.2.5 Include adequately spaced inter-block/street cycling and pedestrian connections to facilitate travel by active transportation. Provide links to the existing or planned network of public sidewalks, multi-use pathways and on-road cycle routes. Where public sidewalks and multi-use pathways intersect with roads, consider providing traffic control devices to give priority to cyclists and pedestrians (<i>see Official Plan policy 4.3.11</i>)	☒
BASIC	1.2.6 Provide safe, direct and attractive walking routes from building entrances to nearby transit stops	☒
BASIC	1.2.7 Ensure that walking routes to transit stops are secure, visible, lighted, shaded and wind-protected wherever possible	☒
BASIC	1.2.8 Design roads used for access or circulation by cyclists using a target operating speed of no more than 30 km/h, or provide a separated cycling facility	☐
1.3 Amenities for walking & cycling		
BASIC	1.3.1 Provide lighting, landscaping and benches along walking and cycling routes between building entrances and streets, sidewalks and trails	☐
BASIC	1.3.2 Provide wayfinding signage for site access (where required, e.g. when multiple buildings or entrances exist) and egress (where warranted, such as when directions to reach transit stops/stations, trails or other common destinations are not obvious)	☐

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
2. WALKING & CYCLING: END-OF-TRIP FACILITIES		
2.1 Bicycle parking		
REQUIRED	2.1.1 Provide bicycle parking in highly visible and lighted areas, sheltered from the weather wherever possible (<i>see Official Plan policy 4.3.6</i>)	☒
REQUIRED	2.1.2 Provide the number of bicycle parking spaces specified for various land uses in different parts of Ottawa; provide convenient access to main entrances or well-used areas (<i>see Zoning By-law Section 111</i>)	☒
REQUIRED	2.1.3 Ensure that bicycle parking spaces and access aisles meet minimum dimensions; that no more than 50% of spaces are vertical spaces; and that parking racks are securely anchored (<i>see Zoning By-law Section 111</i>)	☒
BASIC	2.1.4 Provide bicycle parking spaces equivalent to the expected number of commuter cyclists (assuming the cycling mode share target is met), plus the expected peak number of customer/visitor cyclists	☐
BETTER	2.1.5 Provide bicycle parking spaces equivalent to the expected number of commuter and customer/visitor cyclists, plus an additional buffer (e.g. 25 percent extra) to encourage other cyclists and ensure adequate capacity in peak cycling season	☐
2.2 Secure bicycle parking		
REQUIRED	2.2.1 Where more than 50 bicycle parking spaces are provided for a single office building, locate at least 25% of spaces within a building/structure, a secure area (e.g. supervised parking lot or enclosure) or bicycle lockers (<i>see Zoning By-law Section 111</i>)	☒
BETTER	2.2.2 Provide secure bicycle parking spaces equivalent to the expected number of commuter cyclists (assuming the cycling mode share target is met)	☐
2.3 Shower & change facilities		
BASIC	2.3.1 Provide shower and change facilities for the use of active commuters	☐
BETTER	2.3.2 In addition to shower and change facilities, provide dedicated lockers, grooming stations, drying racks and laundry facilities for the use of active commuters	☐
2.4 Bicycle repair station		
BETTER	2.4.1 Provide a permanent bike repair station, with commonly used tools and an air pump, adjacent to the main bicycle parking area (or secure bicycle parking area, if provided)	☐

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
3. TRANSIT		
3.1 Customer amenities		
BASIC	3.1.1 Provide shelters, lighting and benches at any on-site transit stops	☐
BASIC	3.1.2 Where the site abuts an off-site transit stop and insufficient space exists for a transit shelter in the public right-of-way, protect land for a shelter and/or install a shelter	☐
BETTER	3.1.3 Provide a secure and comfortable interior waiting area by integrating any on-site transit stops into the building	☐
4. RIDESHARING		
4.1 Pick-up & drop-off facilities		
BASIC	4.1.1 Provide a designated area for carpool drivers (plus taxis and ride-hailing services) to drop off or pick up passengers without using fire lanes or other no-stopping zones	☐
4.2 Carpool parking		
BASIC	4.2.1 Provide signed parking spaces for carpools in a priority location close to a major building entrance, sufficient in number to accommodate the mode share target for carpools	☐
BETTER	4.2.2 At large developments, provide spaces for carpools in a separate, access-controlled parking area to simplify enforcement	☐
5. CARSHARING & BIKESHARING		
5.1 Carshare parking spaces		
BETTER	5.1.1 Provide carshare parking spaces in permitted non-residential zones, occupying either required or provided parking spaces (<i>see Zoning By-law Section 94</i>)	☐
5.2 Bikeshare station location		
BETTER	5.2.1 Provide a designated bikeshare station area near a major building entrance, preferably lighted and sheltered with a direct walkway connection	☐

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
6. PARKING		
6.1 Number of parking spaces		
REQUIRED	6.1.1 Do not provide more parking than permitted by zoning, nor less than required by zoning, unless a variance is being applied for	☒
BASIC	6.1.2 Provide parking for long-term and short-term users that is consistent with mode share targets, considering the potential for visitors to use off-site public parking	☐
BASIC	6.1.3 Where a site features more than one use, provide shared parking and reduce the cumulative number of parking spaces accordingly (<i>see Zoning By-law Section 104</i>)	☐
BETTER	6.1.4 Reduce the minimum number of parking spaces required by zoning by one space for each 13 square metres of gross floor area provided as shower rooms, change rooms, locker rooms and other facilities for cyclists in conjunction with bicycle parking (<i>see Zoning By-law Section 111</i>)	☐
6.2 Separate long-term & short-term parking areas		
BETTER	6.2.1 Separate short-term and long-term parking areas using signage or physical barriers, to permit access controls and simplify enforcement (i.e. to discourage employees from parking in visitor spaces, and vice versa)	☐
7. OTHER		
7.1 On-site amenities to minimize off-site trips		
BETTER	7.1.1 Provide on-site amenities to minimize mid-day or mid-commute errands	☐

TDM-Supportive Development Design and Infrastructure Checklist: *Residential Developments (multi-family or condominium)*

Legend	
REQUIRED	The Official Plan or Zoning By-law provides related guidance that must be followed
BASIC	The measure is generally feasible and effective, and in most cases would benefit the development and its users
BETTER	The measure could maximize support for users of sustainable modes, and optimize development performance

TDM-supportive design & infrastructure measures: <i>Residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
1. WALKING & CYCLING: ROUTES		
1.1 Building location & access points		
BASIC	1.1.1 Locate building close to the street, and do not locate parking areas between the street and building entrances	☒
BASIC	1.1.2 Locate building entrances in order to minimize walking distances to sidewalks and transit stops/stations	☒
BASIC	1.1.3 Locate building doors and windows to ensure visibility of pedestrians from the building, for their security and comfort	☒
1.2 Facilities for walking & cycling		
REQUIRED	1.2.1 Provide convenient, direct access to stations or major stops along rapid transit routes within 600 metres; minimize walking distances from buildings to rapid transit; provide pedestrian-friendly, weather-protected (where possible) environment between rapid transit accesses and building entrances; ensure quality linkages from sidewalks through building entrances to integrated stops/stations (<i>see Official Plan policy 4.3.3</i>)	☒
REQUIRED	1.2.2 Provide safe, direct and attractive pedestrian access from public sidewalks to building entrances through such measures as: reducing distances between public sidewalks and major building entrances; providing walkways from public streets to major building entrances; within a site, providing walkways along the front of adjoining buildings, between adjacent buildings, and connecting areas where people may congregate, such as courtyards and transit stops; and providing weather protection through canopies, colonnades, and other design elements wherever possible (<i>see Official Plan policy 4.3.12</i>)	☒

TDM-supportive design & infrastructure measures: <i>Residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
REQUIRED	1.2.3 Provide sidewalks of smooth, well-drained walking surfaces of contrasting materials or treatments to differentiate pedestrian areas from vehicle areas, and provide marked pedestrian crosswalks at intersection sidewalks (<i>see Official Plan policy 4.3.10</i>)	☒
REQUIRED	1.2.4 Make sidewalks and open space areas easily accessible through features such as gradual grade transition, depressed curbs at street corners and convenient access to extra-wide parking spaces and ramps (<i>see Official Plan policy 4.3.10</i>)	☒
REQUIRED	1.2.5 Include adequately spaced inter-block/street cycling and pedestrian connections to facilitate travel by active transportation. Provide links to the existing or planned network of public sidewalks, multi-use pathways and on-road cycle routes. Where public sidewalks and multi-use pathways intersect with roads, consider providing traffic control devices to give priority to cyclists and pedestrians (<i>see Official Plan policy 4.3.11</i>)	☒
BASIC	1.2.6 Provide safe, direct and attractive walking routes from building entrances to nearby transit stops	☒
BASIC	1.2.7 Ensure that walking routes to transit stops are secure, visible, lighted, shaded and wind-protected wherever possible	☒
BASIC	1.2.8 Design roads used for access or circulation by cyclists using a target operating speed of no more than 30 km/h, or provide a separated cycling facility	☐
1.3 Amenities for walking & cycling		
BASIC	1.3.1 Provide lighting, landscaping and benches along walking and cycling routes between building entrances and streets, sidewalks and trails	☒
BASIC	1.3.2 Provide wayfinding signage for site access (where required, e.g. when multiple buildings or entrances exist) and egress (where warranted, such as when directions to reach transit stops/stations, trails or other common destinations are not obvious)	☐

TDM-supportive design & infrastructure measures: <i>Residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
2. WALKING & CYCLING: END-OF-TRIP FACILITIES		
2.1 Bicycle parking		
REQUIRED	2.1.1 Provide bicycle parking in highly visible and lighted areas, sheltered from the weather wherever possible (<i>see Official Plan policy 4.3.6</i>)	☒
REQUIRED	2.1.2 Provide the number of bicycle parking spaces specified for various land uses in different parts of Ottawa; provide convenient access to main entrances or well-used areas (<i>see Zoning By-law Section 111</i>)	☒
REQUIRED	2.1.3 Ensure that bicycle parking spaces and access aisles meet minimum dimensions; that no more than 50% of spaces are vertical spaces; and that parking racks are securely anchored (<i>see Zoning By-law Section 111</i>)	☒
BASIC	2.1.4 Provide bicycle parking spaces equivalent to the expected number of resident-owned bicycles, plus the expected peak number of visitor cyclists	☐
2.2 Secure bicycle parking		
REQUIRED	2.2.1 Where more than 50 bicycle parking spaces are provided for a single residential building, locate at least 25% of spaces within a building/structure, a secure area (e.g. supervised parking lot or enclosure) or bicycle lockers (<i>see Zoning By-law Section 111</i>)	☒
BETTER	2.2.2 Provide secure bicycle parking spaces equivalent to at least the number of units at condominiums or multi-family residential developments	☐
2.3 Bicycle repair station		
BETTER	2.3.1 Provide a permanent bike repair station, with commonly used tools and an air pump, adjacent to the main bicycle parking area (or secure bicycle parking area, if provided)	☐
3. TRANSIT		
3.1 Customer amenities		
BASIC	3.1.1 Provide shelters, lighting and benches at any on-site transit stops	☐
BASIC	3.1.2 Where the site abuts an off-site transit stop and insufficient space exists for a transit shelter in the public right-of-way, protect land for a shelter and/or install a shelter	☐
BETTER	3.1.3 Provide a secure and comfortable interior waiting area by integrating any on-site transit stops into the building	☐

TDM-supportive design & infrastructure measures: <i>Residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
4. RIDESHARING		
4.1 Pick-up & drop-off facilities		
BASIC	4.1.1 Provide a designated area for carpool drivers (plus taxis and ride-hailing services) to drop off or pick up passengers without using fire lanes or other no-stopping zones	☐
5. CARSHARING & BIKESHARING		
5.1 Carshare parking spaces		
BETTER	5.1.1 Provide up to three carshare parking spaces in an R3, R4 or R5 Zone for specified residential uses (see <i>Zoning By-law Section 94</i>)	☐
5.2 Bikeshare station location		
BETTER	5.2.1 Provide a designated bikeshare station area near a major building entrance, preferably lighted and sheltered with a direct walkway connection	☐
6. PARKING		
6.1 Number of parking spaces		
REQUIRED	6.1.1 Do not provide more parking than permitted by zoning, nor less than required by zoning, unless a variance is being applied for	☒
BASIC	6.1.2 Provide parking for long-term and short-term users that is consistent with mode share targets, considering the potential for visitors to use off-site public parking	☐
BASIC	6.1.3 Where a site features more than one use, provide shared parking and reduce the cumulative number of parking spaces accordingly (see <i>Zoning By-law Section 104</i>)	☐
BETTER	6.1.4 Reduce the minimum number of parking spaces required by zoning by one space for each 13 square metres of gross floor area provided as shower rooms, change rooms, locker rooms and other facilities for cyclists in conjunction with bicycle parking (see <i>Zoning By-law Section 111</i>)	☐
6.2 Separate long-term & short-term parking areas		
BETTER	6.2.1 Provide separate areas for short-term and long-term parking (using signage or physical barriers) to permit access controls and simplify enforcement (i.e. to discourage residents from parking in visitor spaces, and vice versa)	☐

TDM Measures Checklist:
Residential Developments (multi-family, condominium or subdivision)

Legend	
BASIC	The measure is generally feasible and effective, and in most cases would benefit the development and its users
BETTER	The measure could maximize support for users of sustainable modes, and optimize development performance
★	The measure is one of the most dependably effective tools to encourage the use of sustainable modes

TDM measures: <i>Residential developments</i>		Check if proposed & add descriptions
1. TDM PROGRAM MANAGEMENT		
1.1 Program coordinator		
BASIC ★	1.1.1 Designate an internal coordinator, or contract with an external coordinator	☐
1.2 Travel surveys		
BETTER	1.2.1 Conduct periodic surveys to identify travel-related behaviours, attitudes, challenges and solutions, and to track progress	☐
2. WALKING AND CYCLING		
2.1 Information on walking/cycling routes & destinations		
BASIC	2.1.1 Display local area maps with walking/cycling access routes and key destinations at major entrances (<i>multi-family, condominium</i>)	☒
2.2 Bicycle skills training		
BETTER	2.2.1 Offer on-site cycling courses for residents, or subsidize off-site courses	☐

TDM measures: <i>Residential developments</i>		Check if proposed & add descriptions
3. TRANSIT		
3.1 Transit information		
BASIC	3.1.1 Display relevant transit schedules and route maps at entrances (<i>multi-family, condominium</i>)	☒
BETTER	3.1.2 Provide real-time arrival information display at entrances (<i>multi-family, condominium</i>)	☒
3.2 Transit fare incentives		
BASIC ★	3.2.1 Offer PRESTO cards preloaded with one monthly transit pass on residence purchase/move-in, to encourage residents to use transit	☒
BETTER	3.2.2 Offer at least one year of free monthly transit passes on residence purchase/move-in	☐
3.3 Enhanced public transit service		
BETTER ★	3.3.1 Contract with OC Transpo to provide early transit services until regular services are warranted by occupancy levels (<i>subdivision</i>)	☐
3.4 Private transit service		
BETTER	3.4.1 Provide shuttle service for seniors homes or lifestyle communities (e.g. scheduled mall or supermarket runs)	☐
4. CARSHARING & BIKESHARING		
4.1 Bikeshare stations & memberships		
BETTER	4.1.1 Contract with provider to install on-site bikeshare station (<i>multi-family</i>)	☐
BETTER	4.1.2 Provide residents with bikeshare memberships, either free or subsidized (<i>multi-family</i>)	☐
4.2 Carshare vehicles & memberships		
BETTER	4.2.1 Contract with provider to install on-site carshare vehicles and promote their use by residents	☐
BETTER	4.2.2 Provide residents with carshare memberships, either free or subsidized	☐
5. PARKING		
5.1 Priced parking		
BASIC ★	5.1.1 Unbundle parking cost from purchase price (<i>condominium</i>)	☒
BASIC ★	5.1.2 Unbundle parking cost from monthly rent (<i>multi-family</i>)	☒

TDM measures: <i>Residential developments</i>		Check if proposed & add descriptions
6. TDM MARKETING & COMMUNICATIONS		
6.1 Multimodal travel information		
BASIC ★	6.1.1 Provide a multimodal travel option information package to new residents	☒
6.2 Personalized trip planning		
BETTER ★	6.2.1 Offer personalized trip planning to new residents	☐