

Geotechnical Investigation

Proposed Multi-Storey Building Complex

1009 Trim Road
Ottawa, Ontario

Prepared for Trim Road 1 Limited Partnership
c/o Vuze Construction

Report PG5336-1 Revision 5 dated September 22, 2025

Table of Contents

	PAGE
1.0 Introduction	1
2.0 Proposed Development.....	1
3.0 Method of Investigation	2
3.1 Field Investigation	2
3.2 Field Survey	3
3.3 Laboratory Testing	3
3.4 Analytical Testing	4
4.0 Observations	5
4.1 Surface Conditions	5
4.2 Subsurface Profile	5
4.3 Groundwater	6
5.0 Discussion	7
5.1 Geotechnical Assessment.....	7
5.2 Site Grading and Preparation.....	7
5.3 Foundation Design	8
5.4 Design for Earthquakes.....	10
5.5 Basement Slab	11
5.6 Basement Wall	12
5.7 Pavement Structure	13
6.0 Design and Construction Precautions	15
6.1 Foundation Drainage and Backfill	15
6.2 Protection of Footings Against Frost Action	16
6.3 Retaining Wall Design	17
6.4 Excavation Side Slopes	18
6.5 Pipe Bedding and Backfill	20
6.6 Groundwater Control.....	21
6.7 Winter Construction.....	22
6.8 Corrosion Potential and Sulphate.....	23
6.9 Landslide Hazard Assessment.....	23
7.0 Recommendations	24
8.0 Statement of Limitations.....	25

Appendices

Appendix 1	Soil Profile and Test Data Sheets Symbols and Terms Analytical Testing Results Soil Profile by Others
Appendix 2	Figure 1 – Key Plan Drawing PG5336-1 – Test Hole Location Plan
Appendix 3	Landslide Hazard Assessment Addendum

1.0 Introduction

Paterson Group (Paterson) was commissioned by Trim Road 1 Limited Partnership, care of Vuze Construction to carry out a geotechnical investigation for the proposed multi-storey building complex to be located at 1009 Trim Road, in the City of Ottawa (refer to Figure 1 - Key Plan in Appendix 2 of this report).

The objective of the geotechnical investigation was to:

- Determine the subsoil and groundwater conditions at this site by means of a test hole program.
- Provide geotechnical recommendations pertaining to the design of the proposed development including construction considerations which may affect the design.

The following report has been prepared specifically and solely for the aforementioned project which is described herein. It contains our findings and includes geotechnical recommendations pertaining to the design and construction of the subject development as they are understood at the time of writing this report.

Investigating the presence or potential presence of contamination on the subject site was not part of the scope of work of the present investigation. Therefore, the present report does not address environmental issues.

2.0 Proposed Development

Based on available drawings, the proposed complex will consist of four high rise residential buildings. It is understood that each tower will be constructed over a common podium consisting of an underground parking structure extending 3 levels under finished grade along Trim Road. The podium levels of Residential Tower B2 and B3 will be connected by a 1-storey podium level that will be constructed within the area between the two buildings. The development will also include associated asphalt covered parking areas, access lanes and landscaped areas. It is further anticipated that the site will be municipally serviced.

3.0 Method of Investigation

3.1 Field Investigation

Field Program

The field program for the current investigation was carried out on June 29 to July 2, 2020, and consisted of a total of 4 boreholes drilled and sampled to a maximum depth of 15.9 m below the existing grade. A dynamic cone penetration test (DCPT) was carried out at two boreholes (BH 3 and BH 4) to determine inferred bedrock depth which ranged from 34.0 to 41.8 m below the existing grade. A previous field program was carried out by others in 2016. At that time a total of 6 boreholes and 4 test pits were advanced to a maximum depth of 47.9 m below the existing grade. These locations of these test holes are illustrated on Drawing PG5336- 1 - Test Hole Location Plan included in Appendix 2.

The borehole locations for the current investigation were determined in the field by Paterson personnel taking into consideration existing borehole coverage and existing site features. The locations of the boreholes are illustrated on Drawing PG5336-1 - Test Hole Location Plan included in Appendix 2.

The boreholes were put down using a track-mounted auger drill rig operated by a two-person crew. All fieldwork was conducted under the full-time supervision of personnel from Paterson's geotechnical division under the direction of a senior engineer. The testing procedure for boreholes consisted of augering to the required depths and at the selected locations and sampling the overburden.

Sampling and In Situ Testing

Soil samples from the boreholes were recovered from the auger flights or a 50 mm diameter split-spoon sampler. All soil samples were classified on site, placed in sealed plastic bags and transported to the laboratory for further review. The depths at which the auger and split spoon samples were recovered from the test holes are presented as AU and SS, respectively, on the Soil Profile and Test Data sheets presented in Appendix 1.

Standard Penetration Testing (SPT) was conducted in conjunction with the recovery of the split-spoon samples. The SPT results are recorded as "N" values on the Soil Profile and Test Data sheets. The "N" value is the number of blows required to drive the split-spoon sampler 300 mm into the soil after a 150 mm initial penetration using a 63.5 kg hammer falling from a height of 760 mm.

The overburden thickness was evaluated by a dynamic cone penetration test (DCPT) completed at each borehole completed during the current field program. The DCPT consists of driving a steel drill rod, equipped with a 50 mm diameter cone at the tip, using a 63.5 kg hammer falling from a height of 760 mm. The number of blows required to drive the cone into the soil is recorded for each 300 mm increment.

Undrained shear strength testing was carried out at regular depth intervals in cohesive soils. This testing was done in general accordance with ASTM D2573-08 - Standard Test Method for Field Vane Shear Test in Cohesive Soil. Reference should be made to the Soil Profile and Test Data Sheets provided in Appendix 1.

The subsurface conditions observed in the test holes were recorded in detail in the field. The soil profiles are presented on the Soil Profile and Test Data sheets in Appendix 1 of this report.

Sample Storage

All samples from the investigation were stored in the laboratory for a period of one month after issuance of the initial report. The samples were then discarded unless directed otherwise.

3.2 Field Survey

The test hole locations were selected by Paterson to provide general coverage of the proposed development taking into consideration existing site features and underground utilities. The test hole locations and ground surface elevations at each test hole location were surveyed by Paterson personnel. The ground surface elevations at the borehole locations were referenced to a geodetic datum. The test hole locations are presented on Drawing PG5336-1 - Test Hole Location Plan in Appendix 2.

3.3 Laboratory Testing

Soil samples were recovered from the subject site and visually examined in our laboratory to review the results of the field logging. All samples will be stored in the laboratory for a period of one month after the issuance of this report. They will then be discarded unless we are otherwise directed.

3.4 Analytical Testing

One (1) soil sample was submitted for analytical testing to assess the corrosion potential for exposed ferrous metals and the potential of sulphate attacks against subsurface concrete structures. The sample was submitted to determine the concentration of sulphate and chloride, the resistivity, and the pH of the samples. The results are presented in Appendix 1 and are discussed further in Section 6.7.

4.0 Observations

4.1 Surface Conditions

The majority of the subject site is gravel covered with large boulders. Small to medium sized trees are present on the property boundaries of the subject site that border Trim Road and Inlet Private. The southern portion of the site is relatively flat and slightly above grade from Inlet Private. The site slopes towards the Ottawa river to the north, following Trim Road. An approximately 2 m high pile of boulders was observed at the northwestern portion of the site. The ground surface within the subject site slopes down gradually towards the northern portion of the site. The northern portion of the site is wet land from the Ottawa River. The site is bordered to the north by the Ottawa River, to the east by vacant treed land, to the west by Tweddle Road, and to the south by Trim Road.

4.2 Subsurface Profile

Overburden

Generally, the subsurface profile at the test hole locations consists of topsoil underlain by a fill consisting of silty sand mixed with clay and/or gravel. Fill consisting of boulders and blast rock were also noted on site. A very stiff brown silty clay deposit was encountered under the fill layer. The brown silty clay was underlain by a stiff grey silty clay layer. Practical refusal to DCPT was encountered in BH3 and BH4 between 34.0 and 41.8 m below existing grade.

Reference should be made to the Soil Profile and Test Data sheets in Appendix 1 for details of the soil profiles encountered at each test hole location.

Bedrock

Based on available geological mapping, the subject site is located in an area where the bedrock consists of interbedded limestone and dolomite of the Gull River formation. The overburden drift thickness is estimated to be between 20 to 35 m.

4.3 Groundwater

The groundwater level readings are presented in Table 1. It is important to note that groundwater level readings from piezometers and monitoring wells could be influenced by surface water infiltrating the backfilled boreholes within low permeability soils, such as at the subject site. Groundwater conditions can also be estimated based on the observed colour, moisture levels and consistency of the recovered soil samples. Based on Paterson's review of the recovered soil samples, the long-term groundwater level is expected to be at a depth ranging between 4 to 5 m below existing ground surface.

Table 1 – Summary of Groundwater Levels				
Test Hole Number	Ground Surface Elevation (m)	Measured Groundwater Levels		Dated Recorded
		Depth (m)	Elevation (m)	
BH 1-20	46.87	4.72	42.15	July 17, 2020
BH 2-20	47.73	4.51	43.22	July 17, 2020
BH 3-20	49.31	4.93	44.38	July 17, 2020
MW 16-1	47.30	3.29	44.01	July 17, 2020
		1.50	45.80	April 7, 2016
MW 16-2	47.20	2.83	44.37	July 17, 2020
		5.50	41.70	April 7, 2016
MW 16-3	48.80	4.10	44.70	July 17, 2020
		5.02	43.78	April 7, 2016
MW 16-4	47.10	2.83	44.27	July 17, 2020
		2.00	45.10	April 7, 2016
MW 16-5	43.60	4.80	38.80	April 7, 2016
MW 16-6	43.00	1.10	41.90	July 17, 2020
		0.70	42.30	April 7, 2016
Notes: The ground surface elevations at the borehole locations are referenced to a geodetic datum. - “**” indicates monitoring well installed within borehole.				

5.0 Discussion

5.1 Geotechnical Assessment

From a geotechnical perspective, the subject site is suitable for the proposed high-rise buildings. It is expected that the proposed high-rise buildings will be founded on end bearing piled foundations extending to the bedrock surface. It is also expected that the underground parking structure beyond the towers' extent will be founded on conventional spread footings placed on an undisturbed, very stiff to stiff silty clay bearing surface.

A control joint between the piled foundation and the underground parking foundation can be considered to avoid differential settlement. The structural design will dictate if this is required.

Permissible Grade Raise

Due to the presence of a silty clay layer, the subject site is subjected to a permissible grade restriction. Our permissible grade raise recommendations are discussed in Subsection 5.3.

5.2 Site Grading and Preparation

Stripping Depth

Topsoil and fill, such as those containing organic or deleterious materials, should be stripped from under any buildings and other settlement sensitive structures.

Fill Placement

Fill used for grading purposes beneath the proposed buildings should consist of clean imported granular fill, such as Ontario Provincial Standard Specifications (OPSS) Granular A or Granular B Type II. The fill should be tested and approved prior to delivery to the site. It should be placed in lifts no greater than 300 mm in thickness and compacted using suitable compaction equipment for the specified lift thickness. Fill placed beneath the building areas should be compacted to at least 98% of its standard Proctor maximum dry density (SPMDD).

Non-specified existing fill along with site-excavated soil can be used as general landscaping fill where settlement of the ground surface is of minor concern. These materials should be spread in thin lifts and be compacted at minimum by the tracks of the spreading equipment to minimize voids. If these materials are to be used to build up the subgrade level for areas to be paved, they should be compacted in thin lifts to a minimum density of 95% of their respective SPMDD. Non-specified existing fill and site-excavated soils are not suitable for placement as backfill against foundation walls due to the frost heave potential of the site excavated soils below settlement sensitive areas, such as concrete sidewalks and exterior concrete entrance areas.

Fill used for grading beneath the base and subbase layers of paved areas should consist, unless otherwise specified, of clean imported granular fill, such as OPSS Granular A, Granular B Type II or select subgrade material. This material should be tested and approved prior to delivery to the site. The fill should be placed in lifts no greater than 300 mm thick and compacted using suitable compaction equipment for the lift thickness. Fill placed beneath the paved areas should be compacted to at least 95% of its SPMDD.

5.3 Foundation Design

Conventional Shallow Footings

Strip footings, up to 3 m wide, and pad footings, up to 5 m wide, placed over an undisturbed, very stiff brown silty clay bearing surface can be designed using bearing resistance value at serviceability limit states (SLS) of **200 kPa** and a factored bearing resistance value at ultimate limit states (ULS) of **300 kPa**. A geotechnical resistance factor of 0.5 was applied to the reported bearing resistance values at ULS.

Strip footings, up to 3 m wide, and pad footings, up to 5 m wide, placed over an undisturbed, stiff grey silty clay bearing surface can be designed using bearing resistance value at serviceability limit states (SLS) of **150 kPa** and a factored bearing resistance value at ultimate limit states (ULS) of **250 kPa**. A geotechnical resistance factor of 0.5 was applied to the reported bearing resistance values at ULS.

An undisturbed soil bearing surface consists of one from which all topsoil and deleterious materials, such as loose, frozen or disturbed soil, have been removed prior to the placement of concrete for footings.

For the parking garage, the bearing resistance value given for footings at SLS will be subjected to potential post construction total and differential settlements of 20 and 10 mm, respectively.

Footings on Lean Concrete

Where the underside of footings is located within the existing fill layer, consideration should be given to lower the footings to a native bearing surface.

Alternatively, footings can be placed over lean concrete in-filled trenches extending from design underside of footing level to the native bearing surface. The bearing surface should be reviewed and approved by the geotechnical consultant at the time of excavation. The near vertical, zero entry trench should extend at least 300 mm beyond the outside face of the footing and be in-filled with minimum 15 MPa lean concrete. It should be noted that the zero-entry trenches would be excavated through silty sand and therefore, the sidewalls could become unstable. Precautions should be taken during construction to ensure personnel and equipment are kept away from the top of the trenches (see Subsection 6.3).

Lateral Support

The bearing medium under footing-supported structures is required to be provided with adequate lateral support with respect to excavations and different foundation levels. Above the groundwater level, adequate lateral support is provided to a stiff silty clay when a plane extending down and out from the bottom edge of the footing at a minimum of 1H:1V passes only through in situ soil or engineered fill.

Piled Foundation

It is expected that the buildings will be constructed over concrete filled steel pipe piles driven to refusal on the bedrock surface.

For deep foundations, concrete-filled steel pipe piles are generally utilized in the Ottawa area. Applicable pile resistance at SLS values and factored pile resistance at ULS values are given in Table 2. A resistance factor of 0.4 has been incorporated into the factored ULS values. Note that these are all geotechnical axial resistance values.

The geotechnical pile resistance values were estimated using the Hiley dynamic formula, to be confirmed during pile installation with a program of dynamic monitoring. For this project, the dynamic monitoring of two (2) to four (4) piles would be recommended. This is considered to be the minimum monitoring program, as the piles under shear walls may be required to be driven using the maximum recommended driving energy to achieve the greatest factored resistance at ULS values. Re-striking of all piles at least once will also be required after at least 48 hours have elapsed since initial driving.

Table 2 – Pile Foundation Design Data					
Pile Outside Diameter (mm)	Pile Wall Thickness (mm)	Geotechnical Axial Resistance		Final Set (blows/12mm)	Transferred Hammer Energy (kJ)
		SLS (kN)	Factored at ULS (kN)		
245	9	925	1110	6	27
245	11	1050	1260	6	31
245	13	1200	1440	6	35

Permissible Grade Raise Restrictions

Based on the results of our field investigation, a permissible grade raise restriction for the subject site of **2.0 m** can be used for design purposes. If higher than permissible grade raises are required, preloading with or without a surcharge, lightweight fill, and/or other measures should be investigated to reduce the risks of unacceptable long-term post construction total and differential settlements.

5.4 Design for Earthquakes

The subject site can be taken as seismic site response **Class D** as defined in Table 4.1.8.4.A of the Ontario Building Code (OBC) 2024 for foundations considered at this site.

Further to the above, it should be noted that liquefaction potential is assessed as part of the seismic design considerations. The silty clay deposit encountered at the subject site has been encountered during numerous geotechnical investigations completed by Paterson across the greater Ottawa area. Based on our experience, and supported by multiple laboratory testing results, this material would typically be considered highly plastic with a plasticity index (PI) greater than 20. Figure 6.15 of the Canadian Foundation Manual (2006) provides criteria for liquefaction assessment of fine-grained soils from Bray et al. (2004) as shown in Figure 1 below.




Figure 1 – Bray et al. (2004) criteria for liquefaction assessment of fine-grained soils

Based on the Atterberg Limits testing results conducted on the representative soils samples at the subject site resulting in Plasticity Index (PI) above 20 in conjunction with the site-specific shear wave velocity test results, the underlying soils at the subject site not considered susceptible to liquefaction or subsequent ‘earth flows’ from a geotechnical perspective.

5.5 Basement Slab

With the removal of all topsoil and deleterious fill, such as those containing organic materials, within the footprint of the proposed building, the in-situ soil or engineered fill surface will be considered to be an acceptable subgrade on which to commence backfilling for floor slab construction.

Any soft areas should be removed and backfilled with appropriate backfill material prior to placing any fill. OPSS Granular B Type II compacted to a minimum of 98% of the material’s SPMDD are recommended for backfilling below the floor slab.

It is expected that the basement area for the proposed building will be mostly parking, and the recommended pavement structure noted in Subsection 5.7 will be applicable. However, if storage or other uses of the lower level are proposed where a concrete floor slab will be used, it is recommended that the upper 200 mm of sub-slab fill consist of OPSS Granular A crushed stone compacted to 98% of the materials SPMDD.

A sub-slab drainage system, consisting of lines of perforated drainage pipe subdrains connected to a positive outlet, should be provided under the lowest level floor slab where a basement level is provided. The spacing of the sub-slab drainage pipes should be advised by Paterson during the design phase and once the footing and sump pit locations are known. The footprint would be confirmed at the time of construction once groundwater infiltration can be best assessed, if any. This is discussed further in Subsection 6.1.

5.6 Basement Wall

There are several combinations of backfill materials and retained soils that could be applicable for the basement walls of the subject structure. However, the conditions can be well-represented by assuming the retained material has an angle of internal friction of 30 degrees and a bulk (drained) unit weight of 20 kN/m³.

Where undrained conditions are anticipated (i.e. below the groundwater level), the applicable effective (undrained) unit weight of the retained material can be taken as 13 kN/m³, where applicable. A hydrostatic pressure should be added to the total static earth pressure when using the effective unit weight.

Lateral Earth Pressures

The static horizontal earth pressure (P_o) can be calculated using a triangular earth pressure distribution equal to $K_o \cdot \gamma \cdot H$ where:

K_o = at-rest earth pressure coefficient of the applicable retained soil (0.5)

γ = unit weight of fill of the applicable retained soil (kN/m³)

H = height of the wall (m)

An additional pressure having a magnitude equal to $K_o \cdot q$ and acting on the entire height of the wall should be added to the above diagram for any surcharge loading, q (kPa), that may be placed at ground surface adjacent to the wall.

The surcharge pressure will only be applicable for static analyses and should not be used in conjunction with the seismic loading case. Actual earth pressures could be higher than the “at-rest” case if care is not exercised during the compaction of the backfill materials to maintain a minimum separation of 0.3 m from the walls with the compaction equipment.

Seismic Earth Pressures

The total seismic force (P_{AE}) includes both the earth force component (P_o) and the seismic component (ΔP_{AE}).

The seismic earth force (ΔP_{AE}) can be calculated using $0.375 \cdot a_c \cdot \gamma \cdot H^2 / g$ where:

$$a_c = (1.45 - a_{max}/g) a_{max}$$

γ = unit weight of fill of the applicable retained soil (kN/m³)

H = height of the wall (m)

g = gravity, 9.81 m/s²

The peak ground acceleration, (a_{max}), specific for the site is 0.405 g according to OBC 2024. Note that the vertical seismic coefficient is assumed to be zero.

The earth force component (P_o) under seismic conditions can be calculated using $P_o = 0.5 K_o \gamma H^2$, where $K_o = 0.5$ for the soil conditions noted above.

The total earth force (P_{AE}) is considered to act at a height, h (m), from the base of the wall, where:

$$h = \{P_o \cdot (H/3) + \Delta P_{AE} \cdot (0.6 \cdot H)\} / P_{AE}$$

The earth forces calculated are unfactored. For the ULS case, the earth loads should be factored as live loads, as per OBC 2024.

5.7 Pavement Structure

The recommended pavement structures for the subject site are shown in Table 3, Table 4 and Table 5.

Table 3 – Recommended Pavement Structure – Car Only Parking Areas	
Thickness (mm)	Material Description
50	Wear Course - HL 3 or Superpave 12.5 Asphaltic Concrete
150	BASE - OPSS Granular A Crushed Stone
300	SUBBASE - OPSS Granular B Type II
SUBGRADE - Either fill, in situ soil or OPSS Granular B Type I or II material placed over in situ soil.	

Table 4 – Recommended Pavement Structure – Access Lanes and Ramp	
Thickness (mm)	Material Description
40	Wear Course - HL-3 or Superpave 12.5 Asphaltic Concrete
50	Binder Course - HL-8 or Superpave 19.0 Asphaltic Concrete
150	BASE - OPSS Granular A Crushed Stone
450	SUBBASE - OPSS Granular B Type II
SUBGRADE - Either fill, in situ soil, or OPSS Granular B Type I or II material placed over in situ soil.	

Table 5 – Recommended Rigid Pavement Structure – Lower Parking Level	
Thickness (mm)	Material Description
Specified by Others	32 MPa Concrete
300	BASE - OPSS Granular A Crushed Stone
SUBGRADE - Either fill, in situ soil, or OPSS Granular B Type I or II material placed over in situ soil.	

Minimum Performance Graded (PG) 58-34 asphalt cement should be used for this project. If soft spots develop in the subgrade during compaction or due to construction traffic, the affected areas should be excavated and replaced with OPSS Granular B Type I or Type II material.

The pavement granular base and subbase should be placed in maximum 300 mm thick lifts and compacted to a minimum of 99% of the material's SPMD using suitable compaction equipment.

Pavement Structure Drainage

Satisfactory performance of the pavement structure is largely dependent on keeping the contact zone between the subgrade material and the base stone in a dry condition. Failure to provide adequate drainage under conditions of heavy wheel loading can result in the fine subgrade soil being pumped into the voids in the stone subbase, thereby reducing its load carrying capacity.

Where silty clay is anticipated at subgrade level, consideration should be given to installing subdrains during the pavement construction. The sub-drain inverts should be approximately 300 mm below subgrade level and run longitudinal along the curblines. The subgrade surface should be crowned to promote water flow to the drainage lines.

6.0 Design and Construction Precautions

6.1 Foundation Drainage and Backfill

Foundation Drainage/Flood Proofing

Based on the available information, the lower parking level will be located below the 100-year flood level. To limit long-term groundwater infiltration, it is recommended that a flood proofing system be designed for the proposed building. The system should consist of a water suppression system to lessen the infiltration volumes and manage discharge. Also, a perimeter foundation drainage system will be required as a secondary system to account for any groundwater which breaches the primary groundwater infiltration control system.

The groundwater infiltration control system should extend above the 100-year flood level and the following is suggested for preliminary design purposes:

- ☐ Pour a concrete mud slab at the base of the excavation to create a horizontal hydraulic barrier. Typically, the minimum thickness of the concrete mud slab is 150 mm.
- ☐ Place a composite drainage layer, such as Delta Drain 6000 or equivalent, over the foundation wall (as a secondary system). The composite drainage layer should extend from finished grade to underside of footing level.
- ☐ Place a suitable waterproofing membrane on the drainage layer, such as a bentomat liner system or equivalent. The membrane liner should extend down to footing level. The membrane liner should tie into the concrete mud slab.
- ☐ Pour foundation wall against the composite drainage system.

It is recommended that the composite drainage system (such as Delta Drain 6000 or equivalent) extend down to the footing level. It is recommended that 150 mm diameter sleeves at 3-6 m centres be cast in the footing or at the foundation wall/footing interface to allow the infiltration of water to flow to the interior perimeter drainage pipe. The perimeter drainage pipe and underfloor drainage system should direct water to sump pit(s) within the lower basement area.

It is important to note that the building's sump pit and elevator pit be considered for waterproofing in a similar fashion. A detail can be provided by Paterson once the design drawings are available for the elevator and sump pits.

Underfloor Drainage

It is anticipated that underfloor drainage will be required to control water infiltration. For design purposes, we recommend that 150 mm diameter perforated pipes be placed at 6 m centres. The spacing of the underfloor drainage system should be confirmed at the time of completing the excavation when water infiltration can be better assessed.

Foundation Backfill

Backfill against the exterior sides of the foundation walls should consist of free draining non frost susceptible granular materials compacted in lifts as per Subsection 5.2 for areas where frost susceptible structures, such as the site access lane, are to be located. A frost taper should also be provided at the transition between the building face and the native, silty clay subgrade for the access lane.

The greater part of the site excavated materials will be frost susceptible and, as such, are acceptable for foundation wall backfill within landscaped finished areas only.

6.2 Protection of Footings Against Frost Action

Perimeter footings of heated structures are required to be insulated against the deleterious effects of frost action. A minimum 1.5 m thick soil cover (or equivalent) should be provided in this regard.

A minimum of 2.1 m thick soil cover (or equivalent) should be provided for exterior unheated footings, not thermally connected to a heated space, such as exterior columns and/or wing walls.

The parking garage may require protection against frost action depending on the founding depth. Unheated structures, such as the access ramp wall footings, may be required to be insulated against the deleterious effect of frost action. A minimum of 2.1 m of soil cover alone, or a minimum of 0.6 m of soil cover, in conjunction with foundation insulation, should be provided.

It has been our experience that insufficient soil cover is typically provided to footings located in areas where minimal soil cover is available, such as entrance ramps to underground parking garages. Paterson requests permission to review design drawings prior to construction to ensure proper frost protection is provided.

6.3 Retaining Wall Design

It is expected that retaining walls will be required to grade the property. Retaining walls higher than 1.0 m should be designed by a professional engineer. The bearing resistance values provided in Section 5.3 are applicable to the proposed retaining walls.

The soil parameters presented in Tables 6 should be used for the design of the retaining walls. The design should also include a global stability analysis of the system.

Global stability analysis should include static and seismic analysis of the system and present the minimum factor of safety. The system should be design for a factor of safety of 1.5 under static conditions and 1.1 for seismic conditions.

Backfill Material

The retaining wall should be backfilled with free-draining granular backfill materials and incorporate longitudinal drains and weep holes to provide positive drainage of the backfill. For the purpose of this report, it is recommended that the wall be backfilled with either OPSS Granular B Type II or Granular A materials. The backfill should be placed within a wedge-shaped zone defined by a line drawn up and back from the back edge of the base block of the wall at an inclination of 1H:1V or a minimum of 1 m behind the back of the blocks. All material should be compacted to a minimum of 98% of the material's SPMDD.

Based on the proposed preliminary landscaping plans provided, the proposed grades within multiple areas adjacent to the retaining walls exceed our permissible grade raise recommendations. Where significant grade raise exceedances have occurred, lightweight fill (LWF), such as expanded polystyrene (EPS) geofoam blocks, is recommended for specific areas adjacent to the proposed retaining walls. The designer is to consider the maximum grade raise and provide equivalent LWF backfill to mitigate possible differential settlement.

Lateral Earth Pressures

It is recommended that a minimum of 1 m of the backfill material to consist of clean imported engineered crushed stone such as OPSS Granular A or Granular B Type II. The soil parameters presented in Table 6 should be used for the design of the retaining wall.

Table 6 – Geotechnical Parameters for Backfill and Bedding Materials							
Material Description	Unit Weight (kN/m ³)		Friction Angle (°) ϕ'	Friction Factor, $\tan \delta$	Earth Pressure Coefficients		
	Drained γ_{dr}	Effective γ'			Active K_a	At-Rest K_o	Passive K_p
OPSS Granular A (Crushed Stone)	22	13.7	36	0.6	0.26	0.41	3.85
OPSS Granular B Type II (Crushed Stone)	22	13.7	36	0.6	0.26	0.41	3.85
OPSS Granular B Type I (Sand-Gravel)	21	13	32	0.52	0.31	0.47	3.25
Notes: 1. Properties for fill materials are for condition of 98% of standard Proctor maximum dry density. 2. The earth pressure coefficients provided are for horizontal backfill profile. 3. For soil above the groundwater level the “drained” unit weight should be used and below groundwater level the “effective” unit weight should be used.							

Retaining Wall Types

Where the retaining wall is to be higher than 1 m and or support a roadway or slope consideration can be given to using large precast concrete segmental block retaining wall system, such as Redi-Rock and Stone Strong. Quality precast products are designed to resist large load under gravity and may not require as much excavation or reinforcement. Typical products vary in size from 0.6 to over 2.4 m in depth depending on the total height of the wall. The size of these supporting structures should be considered when drafting site plans and grading plans, especially where they will be located between structures.

6.4 Excavation Side Slopes

The side slopes of excavations in the soil and fill overburden materials should either be cut back at acceptable slopes or should be retained by shoring systems from the start of the excavation until the structure is backfilled. It is assumed that sufficient room will be available for the greater part of the excavations to be undertaken by open-cut methods (i.e. unsupported excavations).

Unsupported Excavations

The excavation side slopes above the groundwater level extending to a maximum depth of 3 m should be excavated at 1H:1V or shallower. The shallower slope is required for excavation below groundwater level. The subsurface soils are considered to be a Type 2 and Type 3 soil according to the Occupational Health and Safety Act and Regulations for Construction Projects.

Excavated soil should not be stockpiled directly at the top of excavations and heavy equipment should be kept away from the excavation sides.

Slopes in excess of 3 m in height should be periodically inspected by the geotechnical consultant in order to detect if the slopes are exhibiting signs of distress.

A trench box is recommended to protect personnel working in trenches with steep or vertical sides. Services are expected to be installed by “cut and cover” methods and excavations should not remain open for extended periods of time.

Temporary Shoring

Temporary shoring may be considered to retain the overburden soil to complete the required excavations where insufficient room is available for open cut methods. The shoring requirements designed by a structural engineer specializing in those works, or Paterson, will depend on the depth of the excavation, the proximity of the adjacent structures and the elevation of the adjacent building foundations and underground services. The design and implementation of these temporary systems will be the responsibility of the excavation contractor and their design team.

Inspections and approval of the temporary system will also be the responsibility of the designer. Geotechnical information provided below is to assist the designer in completing a suitable and safe shoring system. The designer should take into account the impact of a significant precipitation event and designate design measures to ensure that a precipitation will not negatively impact the shoring system, or soils supported by the system.

Any changes to the approved shoring design system should be reported immediately to the owner’s structural design prior to implementation.

The temporary system could consist of soldier pile and lagging system or interlocking steel sheet piling. Any additional loading due to street traffic, construction equipment, adjacent structures, and facilities, etc., should be included to the earth pressures described below.

These systems could be cantilevered, anchored, or braced. Given the sandy nature of the soils present throughout the subject site, the designer should consider provisions to mitigate the potential for excessive losses of retained soil during the lagging installation process if consideration is given to using a soldier pile and lagging system.

Generally, it is expected that the shoring systems will be provided with tie-back rock anchors to ensure their stability. The shoring system is recommended to be adequately supported to resist toe failure and inspected to ensure that the sheet piles extend well below the excavation base.

It should be noted if consideration is being given to utilizing a raker style support for the shoring system that lateral movements can occur, and the structural engineer should ensure that the design selected minimizes these movements to tolerable levels.

The earth pressures acting on the shoring system may be calculated using the parameters provided in Table 7.

Table 7 - Soil Parameters for Calculating Earth Pressures Acting on Shoring System	
Parameter	Value
Active Earth Pressure Coefficient (K_a)	0.33
Passive Earth Pressure Coefficient (K_p)	3
At-Rest Earth Pressure Coefficient (K_o)	0.5
Unit Weight (γ), kN/m ³	20
Submerged Unit Weight (γ'), kN/m ³	13

The active earth pressure should be calculated where wall movements are permissible while the at-rest pressure should be calculated if no movement is permissible. The dry unit weight should be calculated above the groundwater level while the effective unit weight should be calculated below the groundwater level.

The hydrostatic groundwater pressure should be included to the earth pressure distribution wherever the effective unit weight is calculated for earth pressures. If the groundwater level is lowered, the dry unit weight for the soil should be calculated full weight, with no hydrostatic groundwater pressure component.

For design purposes, the minimum factor of safety of 1.5 should be calculated.

6.5 Pipe Bedding and Backfill

Bedding and backfill materials should be in accordance with the most recent Material Specifications and Standard Detail Drawings from the Department of Public Works and Services, Infrastructure Services Branch of the City of Ottawa.

At least 150 mm of OPSS Granular A crushed stone should be used for pipe bedding for sewer and water pipes. The bedding should extend to the spring line of the pipe. Cover material, from the spring line to at least 300 mm above the obvert of the pipe, should consist of OPSS Granular A (concrete or PSM PVC pipes) or sand (concrete pipe). The bedding and cover materials should be placed in maximum 225 mm thick lifts compacted to 95% of the material's SPMDD.

Where hard surface areas are considered above the trench backfill, the trench backfill material within the frost zone (about 1.8 m below finished grade) should consist of the soils exposed at the trench walls to minimize differential frost heaving. The trench backfill should be placed in maximum 300 mm thick loose lifts and compacted to a minimum of 95% of the SPMDD.

To reduce long-term lowering of the groundwater level at this site, clay seals should be provided in the service trenches where a clay subgrade is encountered. The seals should be at least 1.5 m long and should extend from trench wall to trench wall. Generally, the seals should extend from the frost line and fully penetrate the bedding, subbedding and cover material. The barriers should consist of relatively dry and compactable brown silty clay placed in maximum 225 mm thick loose layers and compacted to a minimum of 95% of the material's SPMDD. The clay seals should be placed at the site boundaries and at strategic locations at no more than 60 m intervals in the service trenches.

6.6 Groundwater Control

It is anticipated that groundwater infiltration into the excavations should be low through the sides of the excavation and controllable using open sumps. Pumping from open sumps should be sufficient to control the groundwater influx through the sides of shallow excavations. The contractor should be prepared to direct water away from all bearing surfaces and subgrades, regardless of the source, to prevent disturbance to the founding medium.

Groundwater Control for Building Construction

A temporary Ministry of Environment, Conservation and Parks (MECP) permit to take water (PTTW) may be required if more than 400,000 L/day of ground and/or surface water are to be pumped during the construction phase. At least 4 to 5 months should be allowed for completion of the application and issuance of the permit by the MECP.

For typical ground or surface water volumes being pumped during the construction phase, typically between 50,000 to 400,000 L/day, it is required to register on the Environmental Activity and Sector Registry (EASR). A minimum of two to four weeks should be allotted for completion of the EASR registration and the Water Taking and Discharge Plan to be prepared by a Qualified Person as stipulated under O.Reg. 63/16.

Long-term Groundwater Control

Our recommendations for the proposed building's long-term groundwater control are presented in Subsection 6.1. Any groundwater which encounters the building's perimeter groundwater infiltration control system will be directed to the proposed building's sump pit. It is expected that groundwater flow will be low (i.e. less than 25,000 L/day with peak periods noted after rain events). It is anticipated that the groundwater flow will be controllable using conventional open sumps.

Impacts on Neighboring Structures

Based on observations, the long-term groundwater level is anticipated at depths below 4-5 m. A local groundwater lowering is anticipated under short-term conditions due to construction of the proposed building. The extent of any significant groundwater lowering should occur within a limited range of the subject site due to the minimal temporary groundwater lowering.

The neighboring structures are expected to be founded within the brown silty clay crust bearing surface. No issues are expected, with respect to groundwater lowering, that would cause long term damage to adjacent structures surrounding the proposed building.

6.7 Winter Construction

The subsurface soil conditions contain frost susceptible materials. In the presence of water and freezing conditions, ice could form within the soil mass. Heaving and settlement upon thawing could occur.

In the event of construction during below zero temperatures, the founding stratum should be protected from freezing temperatures by the installation of straw, propane heaters and tarpaulins or other suitable means.

The base of the excavations should be insulated from sub-zero temperatures immediately upon exposure and until such time as heat is adequately supplied to the building and the footings are protected with sufficient soil cover to prevent freezing at founding level.

The trench excavations should be constructed to avoid the introduction of frozen materials, snow or ice into the trenches. As well, pavement construction is difficult during winter. The subgrade consists of frost susceptible soils which will experience total and differential frost heaving during construction.

Also, the introduction of frost, snow or ice into the pavement materials or fill used to backfill the lower basement level, which is difficult to avoid during winter conditions, will greatly negatively affect the performance of the fill and impact construction schedules.

6.8 Corrosion Potential and Sulphate

The results of analytical testing show that the sulphate content is less than 0.1%. This result is indicative that Type 10 Portland cement (normal cement) would be appropriate for this site. The chloride content and the pH of the sample indicate that they are not significant factors in creating a corrosive environment for exposed ferrous metals at this site, whereas the resistivity is indicative of an aggressive to highly aggressive corrosive environment.

6.9 Landslide Hazard Assessment

Paterson reviewed the landslide hazard assessment addendum prepared by McQuarrie Geotechnical Consultants Limited dated July 6, 2023.

The report recommended that a river expert be retained to assess the existing bank and provide guidance on the potential for fluvial erosion and mitigation measures. It also advised to use of a temporary shoring system to facilitate the excavation for the underground parking structure, along with recommendations for temporary open-cut excavations to reduce the risk of localized failures that could progress into larger retrogressive failures. In addition, the report included recommendations for temporary slope monitoring during construction using inclinometers, as well as considerations for long-term monitoring through LiDAR surveys and change-detection analysis.

Based on our review of the report, Paterson is satisfied with the findings and concur with the conclusions presented in the report.

Reference should be made to the full report presented in Appendix 3.

7.0 Recommendations

It is recommended that the following be carried out by Paterson once preliminary and future details of the proposed development have been prepared:

- Review preliminary and detailed grading, servicing and structural plan(s) from a geotechnical perspective.
- Review of the geotechnical aspects of the excavation contractor's shoring design, prior to construction, if applicable.
- Review of architectural plans pertaining to foundation and underfloor drainage systems and waterproofing details for elevator shafts and pools.
- Complete detailed retaining wall structural and geotechnical design.

A material testing and observation services program is a requirement for the provided foundation design data to be applicable. The following aspects of the program should be performed by Paterson:

- ☐ Observation of all bearing surfaces prior to the placement of concrete.
- ☐ Inspection of all foundation drainage and groundwater infiltration control systems.
- ☐ Sampling and testing of the concrete and fill materials used.
- ☐ Observation of the placement of the foundation insulation, if applicable.
- ☐ Periodic observation of the condition of unsupported excavation side slopes in excess of 3 m in height, if applicable.
- ☐ Observation of all subgrades prior to backfilling.
- ☐ Field density tests to determine the level of compaction achieved.
- ☐ Sampling and testing of the bituminous concrete including mix design reviews.

A report confirming the work has been conducted in general accordance with the recommendations could be issued, upon request, following the completion of a satisfactory materials testing and observation program by Paterson.

All excess soil must be handled as per *Ontario Regulation 406/19: On-Site and Excess Soil Management*.

8.0 Statement of Limitations

The recommendations provided are in accordance with the present understanding of the project. Paterson requests permission to review the recommendations when the drawings and specifications are completed.

A soils investigation is a limited sampling of a site. Should any conditions at the site be encountered which differ from those at the test locations, Paterson requests immediate notification to permit reassessment of our recommendations.


The recommendations provided herein should only be used by the design professionals associated with this project. They are not intended for contractors bidding on or undertaking the work. The latter should evaluate the factual information provided in this report and determine the suitability and completeness for their intended construction schedule and methods. Additional testing may be required for their purposes.

The present report applies only to the project described in this document. Use of this report for purposes other than those described herein or by person(s) other than Trim Road 1 Limited Partnership and Vuze Construction, or their agents, is not authorized without review by Paterson for the applicability of our recommendations to the alternative use of the report.

Paterson Group Inc.



Pratheep Thirumoolan, M.Eng.



Joey R. Villeneuve, M.A.Sc., P.Eng, ing.

Report Distribution:

- ☐ Vuze Construction
- ☐ Trim Road 1 Limited Partnership (1 email copy)
- ☐ Paterson Group (1 copy)

APPENDIX 1

SOIL PROFILE AND TEST DATA SHEETS

SYMBOLS AND TERMS

ANALYTICAL TESTING RESULTS

SOIL PROFILE BY OTHERS

DATUM Geodetic

REMARKS

BORINGS BY Track-Mount Power Auger


DATE June 29, 2020

FILE NO.

PG5336

HOLE NO.

BH 1-20



DATUM Geodetic

REMARKS

BORINGS BY Track-Mount Power Auger


DATE June 30, 2020

FILE NO.

PG5336

HOLE NO.

BH 2-20



DATUM Geodetic

REMARKS

BORINGS BY Track-Mount Power Auger


DATE July 2, 2020

FILE NO.

PG5336

HOLE NO.

BH 3-20



SOIL PROFILE AND TEST DATA

Geotechnical Investigation
Prop. Multi-Storey Building Complex - 1009 Trim Road
Ottawa, Ontario

DATUM Geodetic

REMARKS

BORINGS BY Track-Mount Power Auger

DATE July 2, 2020

FILE NO.
PG5336

HOLE NO.
BH 3-20

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction		
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %						
								20	40	60	80			
GROUND SURFACE						17	32.31							
						18	31.31							
						19	30.31							
						20	29.31							
						21	28.31							
						22	27.31							
						23	26.31							
						24	25.31							
						25	24.31							
						26	23.31							
						27	22.31							
						28	21.31							
						29	20.31							
						30	19.31							
						31	18.31							
						32	17.31							
						33	16.31							
						34	15.31							

Shear Strength (kPa)

▲ Undisturbed △ Remoulded

Depth (m)	Undisturbed Shear Strength (kPa)	Remoulded Shear Strength (kPa)
32	55	75
33	65	85
34	95	100

SOIL PROFILE AND TEST DATA

Geotechnical Investigation
Prop. Multi-Storey Building Complex - 1009 Trim Road
Ottawa, Ontario

DATUM Geodetic


REMARKS

BORINGS BY Track-Mount Power Auger

DATE July 2, 2020

FILE NO.
PG5336

HOLE NO.
BH 3-20



DATUM Geodetic

REMARKS

BORINGS BY Track-Mount Power Auger


DATE June 30, 2020

FILE NO.

PG5336

HOLE NO.

BH 4-20



SOIL PROFILE AND TEST DATA

Geotechnical Investigation
Prop. Multi-Storey Building Complex - 1009 Trim Road
Ottawa, Ontario

DATUM Geodetic

REMARKS

BORINGS BY Track-Mount Power Auger

DATE June 30, 2020

FILE NO.
PG5336

HOLE NO.
BH 4-20

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone					Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %						
								20	40	60	80			
GROUND SURFACE						17	31.90							
						18	30.90							
						19	29.90							
						20	28.90							
						21	27.90							
						22	26.90							
						23	25.90							
						24	24.90							
						25	23.90							
						26	22.90							
						27	21.90							
						28	20.90							
						29	19.90							
						30	18.90							
						31	17.90							
						32	16.90							
						33	15.90							
						34	14.90							
								20	40	60	80	100		
								Shear Strength (kPa)						
								▲ Undisturbed △ Remoulded						

SOIL PROFILE AND TEST DATA

Geotechnical Investigation

**Prop. Multi-Storey Building Complex - 1009 Trim Road
Ottawa, Ontario**

DATUM	Geodetic
-------	----------

FILE NO.

PG5336

REMARKS

HOLE NO.

BH 4-20

BORINGS BY Track-Mount Power Auger

DATE June 30, 2020

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction		
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %						
GROUND SURFACE								20	40	60	80			
						34	14.90							
						35	13.90							
						36	12.90							
						37	11.90							
						38	10.90							
						39	9.90							
						40	8.90							
						41	7.90							
End of Borehole												101		
Practical DCPT refusal at 41.78m depth.														

SYMBOLS AND TERMS

SOIL DESCRIPTION

Behavioural properties, such as structure and strength, take precedence over particle gradation in describing soils. Terminology describing soil structure are as follows:

Desiccated	-	having visible signs of weathering by oxidation of clay minerals, shrinkage cracks, etc.
Fissured	-	having cracks, and hence a blocky structure.
Varved	-	composed of regular alternating layers of silt and clay.
Stratified	-	composed of alternating layers of different soil types, e.g. silt and sand or silt and clay.
Well-Graded	-	Having wide range in grain sizes and substantial amounts of all intermediate particle sizes (see Grain Size Distribution).
Uniformly-Graded	-	Predominantly of one grain size (see Grain Size Distribution).

The standard terminology to describe the relative strength of cohesionless soils is the compactness condition, usually inferred from the results of the Standard Penetration Test (SPT) 'N' value. The SPT N value is the number of blows of a 63.5 kg hammer, falling 760 mm, required to drive a 51 mm O.D. split spoon sampler 300 mm into the soil after an initial penetration of 150 mm. An SPT N value of "P" denotes that the split-spoon sampler was pushed 300 mm into the soil without the use of a falling hammer.

Compactness Condition	'N' Value	Relative Density %
Very Loose	<4	<15
Loose	4-10	15-35
Compact	10-30	35-65
Dense	30-50	65-85
Very Dense	>50	>85

The standard terminology to describe the strength of cohesive soils is the consistency, which is based on the undisturbed undrained shear strength as measured by the in situ or laboratory shear vane tests, unconfined compression tests, or occasionally by the Standard Penetration Test (SPT). Note that the typical correlations of undrained shear strength to SPT N value (tabulated below) tend to underestimate the consistency for sensitive silty clays, so Paterson reviews the applicable split spoon samples in the laboratory to provide a more representative consistency value based on tactile examination.

Consistency	Undrained Shear Strength (kPa)	'N' Value
Very Soft	<12	<2
Soft	12-25	2-4
Firm	25-50	4-8
Stiff	50-100	8-15
Very Stiff	100-200	15-30
Hard	>200	>30

SYMBOLS AND TERMS (continued)

SOIL DESCRIPTION (continued)

Cohesive soils can also be classified according to their “sensitivity”. The sensitivity, S_t , is the ratio between the undisturbed undrained shear strength and the remoulded undrained shear strength of the soil. The classes of sensitivity may be defined as follows:

Low Sensitivity:	$S_t < 2$
Medium Sensitivity:	$2 < S_t < 4$
Sensitive:	$4 < S_t < 8$
Extra Sensitive:	$8 < S_t < 16$
Quick Clay:	$S_t > 16$

ROCK DESCRIPTION

The structural description of the bedrock mass is based on the Rock Quality Designation (RQD).

The RQD classification is based on a modified core recovery percentage in which all pieces of sound core over 100 mm long are counted as recovery. The smaller pieces are considered to be a result of closely-spaced discontinuities (resulting from shearing, jointing, faulting, or weathering) in the rock mass and are not counted. RQD is ideally determined from NQ or larger size core. However, it can be used on smaller core sizes, such as BQ, if the bulk of the fractures caused by drilling stresses (called “mechanical breaks”) are easily distinguishable from the normal in situ fractures.

RQD %	ROCK QUALITY
90-100	Excellent, intact, very sound
75-90	Good, massive, moderately jointed or sound
50-75	Fair, blocky and seamy, fractured
25-50	Poor, shattered and very seamy or blocky, severely fractured
0-25	Very poor, crushed, very severely fractured

SAMPLE TYPES

SS	-	Split spoon sample (obtained in conjunction with the performing of the Standard Penetration Test (SPT))
TW	-	Thin wall tube or Shelby tube, generally recovered using a piston sampler
G	-	"Grab" sample from test pit or surface materials
AU	-	Auger sample or bulk sample
WS	-	Wash sample
RC	-	Rock core sample (Core bit size BQ, NQ, HQ, etc.). Rock core samples are obtained with the use of standard diamond drilling bits.

SYMBOLS AND TERMS (continued)

PLASTICITY LIMITS AND GRAIN SIZE DISTRIBUTION

WC%	-	Natural water content or water content of sample, %
LL	-	Liquid Limit, % (water content above which soil behaves as a liquid)
PL	-	Plastic Limit, % (water content above which soil behaves plastically)
PI	-	Plasticity Index, % (difference between LL and PL)
Dxx	-	Grain size at which xx% of the soil, by weight, is of finer grain sizes These grain size descriptions are not used below 0.075 mm grain size
D10	-	Grain size at which 10% of the soil is finer (effective grain size)
D60	-	Grain size at which 60% of the soil is finer
Cc	-	Concavity coefficient = $(D_{30})^2 / (D_{10} \times D_{60})$
Cu	-	Uniformity coefficient = D_{60} / D_{10}

Cc and Cu are used to assess the grading of sands and gravels:

Well-graded gravels have: $1 < Cc < 3$ and $Cu > 4$

Well-graded sands have: $1 < Cc < 3$ and $Cu > 6$

Sands and gravels not meeting the above requirements are poorly-graded or uniformly-graded.

Cc and Cu are not applicable for the description of soils with more than 10% silt and clay
(more than 10% finer than 0.075 mm or the #200 sieve)

CONSOLIDATION TEST


p'_o	-	Present effective overburden pressure at sample depth
p'_c	-	Preconsolidation pressure of (maximum past pressure on) sample
Ccr	-	Recompression index (in effect at pressures below p'_c)
Cc	-	Compression index (in effect at pressures above p'_c)
OC Ratio		Overconsolidation ratio = p'_c / p'_o
Void Ratio		Initial sample void ratio = volume of voids / volume of solids
Wo	-	Initial water content (at start of consolidation test)

PERMEABILITY TEST

k	-	Coefficient of permeability or hydraulic conductivity is a measure of the ability of water to flow through the sample. The value of k is measured at a specified unit weight for (remoulded) cohesionless soil samples, because its value will vary with the unit weight or density of the sample during the test.
---	---	--

SYMBOLS AND TERMS (continued)


STRATA PLOT




Topsoil




Asphalt




Fill




Peat




Sand




Silty Sand




Silt




Sandy Silt



Clay




Silty Clay




Clayey Silty Sand



Glacial Till




Shale




Bedrock

MONITORING WELL AND PIEZOMETER CONSTRUCTION

MONITORING WELL CONSTRUCTION



PIEZOMETER CONSTRUCTION



Certificate of Analysis

Report Date: 13-Jul-2020

Client: Paterson Group Consulting Engineers

Order Date: 7-Jul-2020

Client PO: 29948

Project Description: PG5336

Client ID:	BH4-SS8B	-	-	-
Sample Date:	29-Jun-20 12:00	-	-	-
Sample ID:	2028144-01	-	-	-
MDL/Units	Soil	-	-	-

Physical Characteristics

% Solids	0.1 % by Wt.	73.0	-	-	-
----------	--------------	------	---	---	---

General Inorganics

pH	0.05 pH Units	7.44	-	-	-
Resistivity	0.10 Ohm.m	45.0	-	-	-

Anions

Chloride	5 ug/g dry	32	-	-	-
Sulphate	5 ug/g dry	38	-	-	-

LOG OF BOREHOLE MW16-1

Project: Geotechnical Investigation

Client: Grandmaître Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 5038380 E 462237

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm


Core Diameter: 76 mm

Project No.: 161-03361-00

Date Started: 3/24/2016

Supervisor:

Reviewer:



Continued Next Page

GROUNDWATER ELEVATIONS

GRAPH
NOTES

+ 3, × 3: Numbers refer to Sensitivity

○ $\epsilon=3\%$ Strain at Failure

Sheet No. 1 of 5

Shallow/ Single Installation Deep/Dual Installation

LOG OF BOREHOLE MW16-1

Project: Geotechnical Investigation

Client: Grandmaître Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 5038380 E 462237

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm


Core Diameter: 76 mm

Project No.: 161-03361-00

Date Started: 3/24/2016

Supervisor:

Reviewer:



Continued Next Page

GROUNDWATER ELEVATIONS

GRAPH
NOTES

$+^3, \times^3$: Numbers refer to Sensitivity

○ $\epsilon=3\%$ Strain at Failure

Sheet No. 2 of 5

Shallow/ Single Installation   Deep/Dual Installation  

LOG OF BOREHOLE MW16-1



LOG OF BOREHOLE MW16-2

Project: Geotechnical Investigation

Client: Grandmaître Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 462330 E 5038430

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm

Core Diameter:

Project No.: 161-03361-00

Date Started: 3/22/2016

Supervisor:

Reviewer:

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC LIMIT W _p	NATURAL MOISTURE CONTENT W	LIQUID LIMIT W _L	POCKET PEN. (C _u) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)			
(m)	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			SHEAR STRENGTH (kPa)											WATER CONTENT (%)		
ELEV								○ UNCONFINED + FIELD VANE & Sensitivity											○ 25 50 75		
DEPTH								● QUICK TRIAXIAL × LAB VANE													
47.2							20	40	60	80	100										
0.0	CRUSHED SAND AND GRAVEL trace to some silt, trace to some clay, grey, compact to very dense (FILL)		1	SS	12																
			2	SS	50/ 150 mm																
			3	SS	11																
	- grey																				
44.5			4A	SS	11																
44.3	GRAVEL: black, mosit (FILL)		4B																		
2.9	SILTY CLAY: grey brown, firm to very stiff, moist to wet, (WEATHERED CRUST)																				
			5	SS	12																
			6	SS	10																
			7	SS	16																
			8	SS	6																
			9	SS	21																
			10	SS	12																
39.5																					
7.6	SILTY CLAY: grey, wet, stiff		11	SS	2																

Continued Next Page

GROUNDWATER ELEVATIONS

GRAPH NOTES

+ 3, × 3: Numbers refer to Sensitivity

○ s=3% Strain at Failure

Sheet No. 1 of 4

Shallow/ Single Installation Deep/Dual Installation



LOG OF BOREHOLE MW16-2

Project: Geotechnical Investigation

Client: Grandmaître Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 462330 E 5038430

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm

Core Diameter:

Project No.: 161-03361-00

Date Started: 3/22/2016

Supervisor:

Reviewer:

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC NATURAL LIQUID LIMIT MOISTURE CONTENT			POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			SHEAR STRENGTH (kPa)		W _p	W	W _L			
	SILTY CLAY (Inferred based on DCPT results)(Continued)							○ UNCONFINED ● QUICK TRIAXIAL	+ FIELD VANE & Sensitivity × LAB VANE						GR SA SI CL
							27								
							26								
							25								
							24								
							23								
							22								
							21								
							20								
							19								
							18								

Continued Next Page

GROUNDWATER ELEVATIONS

GRAPH
NOTES

+ 3 , × 3 : Numbers refer
to Sensitivity

○ $\epsilon=3\%$ Strain at Failure

Sheet No. 3 of 4

Shallow/ Single Installation Deep/Dual Installation

WSP SOIL LOG - OTTAWA GEOTECHNICAL BH LOGS - 1009 TRIM ROAD, OTTAWA, ONTARIO, GPJ SPL GDT 5/5/16



LOG OF BOREHOLE MW16-2

Project: Geotechnical Investigation

Client: Grandmaitre Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 462330 E 5038430

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm

Core Diameter:

Project No.: 161-03361-00

Date Started: 3/22/2016

Supervisor:

Reviewer:

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC NATURAL LIQUID LIMIT			POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			SHEAR STRENGTH (kPa)		W _p	W	W _L			
								20 40 60 80 100							GR SA SI CL
	SILTY CLAY (Inferred based on DCPT results)(Continued)						17								
							16								
							15								
							14								
13.3															
33.9	END OF BOREHOLE 1) Augering 14.9 m below the existing ground surface, switch to DCPT. 2) Borehole dry at completion of augering. 3) DCPT refusal at 33.9 m below the existing ground surface. 4) 31 mm monitoring well installed at 6.1 m below the existing ground surface. 5) Date Groundwater Depth 4/7/2016 5.5 m														

GROUNDWATER ELEVATIONS

GRAPH NOTES

+ 3, × 3: Numbers refer to Sensitivity

○ ε=3% Strain at Failure

Sheet No. 4 of 4

Shallow/ Single Installation ▽ ▽ Deep/Dual Installation ▽ ▽

WSP SOIL LOG - OTTAWA GEOTECHNICAL BH LOGS - 1009 TRIM ROAD, OTTAWA, ONTARIO, GPJ SPL GDT 5/5/16



LOG OF BOREHOLE MW16-3

Project: Geotechnical Investigation

Client: Grandmaître Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 462249 E 5038342

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm














Core Diameter:

Project No.: 161-03361-00

Date Started: 3/22/2016

Supervisor:

Reviewer:

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC NATURAL LIQUID LIMIT MOISTURE CONTENT			POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)																				
(m)	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			SHEAR STRENGTH (kPa)					WATER CONTENT (%)																									
ELEV DEPTH								20 40 60 80 100	25 50 75 100 125	25 50 75	○ UNCONFINED ● QUICK TRIAXIAL	+ FIELD VANE & Sensitivity × LAB VANE	W _p W W _L																									
48.8 0.0	CRUSHED SAND AND GRAVEL trace to some silt, trace to some clay, grey, compact to very dense (FILL)		1	SS	14		48																															
			2	SS													47																					
			3	SS	6																							46										
			4	SS	15																																	
45.7 3.1	SILTY CLAY: grey, moist, firm to stiff		5	SS	9	44																																
			6	SS	8												43																					
44.8 4.0			SILTY CLAY: grey, moist, firm to stiff		7																							SS	7	42								
	8	SS			4	41																																
	9	SS			3												40																					
	VANE																											39										
41.5 7.3	END OF BOREHOLE 1) Borehole terminated at 7.62 m below the existing ground surface. 2) Borehole dry at the completion of augering. 3) 31 mm monitoring well installed at 6.1 m below the existing ground surface. 4) Date Groundwater Depth 4/7/2016 5.02 m																																					

GROUNDWATER ELEVATIONS

GRAPH NOTES

+ 3, × 3: Numbers refer to Sensitivity

○ s=3% Strain at Failure

Sheet No. 1 of 1

Shallow/ Single Installation ▽ ▽ ▽ Deep/Dual Installation ▽ ▽ ▽

WSP SOIL LOG - OTTAWA GEOTECHNICAL BH LOGS - 1009 TRIM ROAD, OTTAWA, ONTARIO, GPJ SPL GDT 5/5/16



LOG OF BOREHOLE MW16-4

Project: Geotechnical Investigation

Client: Grandmaître Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 462344 E 5038407

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm


Core Diameter:

Project No.: 161-03361-00

Date Started: 3/22/2016

Supervisor:

Reviewer:





LOG OF BOREHOLE MW16-5

Project: Geotechnical Investigation

Client: Grandmaître Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 462379 E 5038450

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm

Core Diameter:

Project No.: 161-03361-00

Date Started: 3/22/2016

Supervisor:

Reviewer:

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT					PLASTIC NATURAL LIQUID LIMIT			POCKET PEN. (Cu) (kPa)	NATURAL UNIT WT (kN/m³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)
(m)	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			20	40	60	80	100	W _p	W	W _L			
43.6																		
0.0	SILTY CLAY brown-grey, moist, soft to firm (FILL)		1	SS	2									○				
			2	SS	6									○				
42.1																		
1.5	SILTY CLAY some organic deposits, brown-grey, moist, stiff		3	SS	5									○				
41.3			4A	SS	21									○				
2.4	SILTY SAND grey-brown, moist		4B		21									○				
41.0			4C		21									○				
2.6	SILTY CLAY: grey brown, wet, stiff to very stiff (WEATHERED CRUST)																	
			5	SS	15									○				
			6	SS	5										○			
39.1																		
4.6	SILTY CLAY: grey, wet, stiff		7	SS	2										○			
			8	SS	1										○			
37.5																		
6.1	END OF BOREHOLE 1) Borehole terminated at 6.1 m below the existing ground surface. 2) 31 mm monitoring well installed at 6.1 m below the existing ground surface. 3) Date Groundwater Depth 4/7/2016 4.8 m																	

GROUNDWATER ELEVATIONS

GRAPH NOTES

+ 3, × 3: Numbers refer to Sensitivity

○ s=3% Strain at Failure

Sheet No. 1 of 1

Shallow/ Single Installation ▽ ▽ Deep/Dual Installation ▽ ▽

WSP SOIL LOG - OTTAWA GEOTECHNICAL BH LOGS - 1009 TRIM ROAD, OTTAWA, ONTARIO, GPJ SPL GDT 5/5/16



LOG OF BOREHOLE MW16-6

Project: Geotechnical Investigation

Client: Grandmaître Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 462225 E 5038410

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm


Core Diameter:

Project No.: 161-03361-00

Date Started: 3/23/2016

Supervisor:

Reviewer:



Continued Next Page

GROUNDWATER ELEVATIONS

GRAPH NOTES

+ 3, x 3: Numbers refer to Sensitivity

○ s=3% Strain at Failure

Sheet No. 1 of 5

Shallow/ Single Installation Deep/Dual Installation

LOG OF BOREHOLE MW16-6

Project: Geotechnical Investigation

Client: Grandmaître Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 462225 E 5038410

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm


Core Diameter:

Project No.: 161-03361-00

Date Started: 3/23/2016

Supervisor:

Reviewer:



Continued Next Page

GROUNDWATER ELEVATIONS

GRAPH
NOTES

+ 3, × 3: Numbers refer to Sensitivity

○ $\epsilon=3\%$ Strain at Failure

Sheet No. 2 of 5

Shallow/ Single Installation Deep/Dual Installation

Shallow/ Single Installation   Deep/Dual Installation  



LOG OF BOREHOLE MW16-6

Project: Geotechnical Investigation

Client: Grandmaître Family

Project Location: Part Lot 30, Concession 1, Parts 1 & 2, Cumberland, ON

Datum: Approximate

BH Location: See borehole location plan N 462225 E 5038410

DRILLING DATA

Rig Type:

Method: Hollow Stem Auger

Borehole Diameter: 203 mm

Core Diameter:

Project No.: 161-03361-00

Date Started: 3/23/2016

Supervisor:

Reviewer:

SOIL PROFILE			SAMPLES			GROUND WATER CONDITIONS	ELEVATION	DYNAMIC CONE PENETRATION RESISTANCE PLOT		PLASTIC LIMIT w _p	NATURAL MOISTURE CONTENT w	LIQUID LIMIT w _L	POCKET PEN. (C _u) (kPa)	NATURAL UNIT WT (kN/m ³)	REMARKS AND GRAIN SIZE DISTRIBUTION (%)
(m) ELEV DEPTH	DESCRIPTION	STRATA PLOT	NUMBER	TYPE	"N" BLOWS 0.3 m			SHEAR STRENGTH (kPa)							
								20 40 60 80 100							
								25 50 75 100 125							
2.7															
40.3	END OF BOREHOLE 1) End of augering at 15.2 m below the existing ground surface. Switch to DCPT. 2) Seepage noted at the bottom of borehole upon completion of augering. 3) DCPT refusal at 40.3 m below the existing ground surface. 4) 31 mm monitoring well installed at 6.1 m below the existing ground surface. 5) Date Groundwater Depth 4/7/2016 0.7 m														

GROUNDWATER ELEVATIONS

GRAPH
NOTES

+ 3, × 3: Numbers refer to Sensitivity

○ ε=3% Strain at Failure

Sheet No. 5 of 5

Shallow/ Single Installation ▽ ▽ Deep/Dual Installation ▽ ▽

WSP SOIL LOG - OTTAWA GEOTECHNICAL BH LOGS - 1009 TRIM ROAD, OTTAWA, ONTARIO, GPJ SPL GDT 5/5/16

Appendix B: Test-pit Logs

TEST PIT NUMBER (ELEVATION)	DEPTH (METRES)	DESCRIPTION
TP 16-1 (44.4 m)	0.0 – 1.2	Crushed Sand and Gravel, black, moist (FILL)
	1.2 – 1.8	Silty Clay some sand, trace to some gravel, dark brown, moist (Fill)
	1.8 – 4.0	Silt Clay, trace roots and organics, brown-grey, moist (WEATHERED CRUST)
	4.0 – 6.7	Silty Clay, grey, moist
	6.7	End of Test Pit



TEST PIT NUMBER (ELEVATION)	DEPTH (METRES)	DESCRIPTION
TP 16-2 (45.7 m)	0.0 – 2.1	Silty Sand and Crushed Gravel with boulders/cobbles, trace to some clay, brown, moist (FILL)
	2.1 – 3.4	Silty Clay mixed with organic deposits, brown, moist
	3.4 – 6.7	Silty Clay. grey-brown, moist (WEATHERED CRUST)
	6.7	End of Test Pit
		


TEST PIT NUMBER (ELEVATION)	DEPTH (METRES)	DESCRIPTION
TP 16-3 (45.9 m)	0.0 – 0.9	Crushed Sand and Gravel, with boulders/cobbles, grey, moist (FILL)
	0.9 - 2.6	Silty Clay, trace sand, trace to some gravel, brown, moist (FILL) - Roots 1.7 m in depth
	2.6 – 4.3	Silty Clay, some gravel, trace to some roots and organic material, grey-brown, moist
	4.3 – 7.3	Silty Clay, grey-brown, moist (Weathered Crust) End of Test Pit
		
		

TEST PIT NUMBER (ELEVATION)	DEPTH (METRES)	DESCRIPTION		
TP 16-4 (47.3 m)	0.0 – 1.8 1.8 – 4.0 4.0 – 6.4 6.4 – 7.3 7.3	Crushed Sand and Gravel with boulders/cobbles, grey, moist (FILL) Silty Sand and Gravel, some clay to clayey, brown, moist (FILL) Silty Clay, trace to some gravel, trace roots, grey-brown, moist (FILL) Organic Soil mixed with roots, black, moist End of Test Pit		
Sample 1	Depth 0 – 0.6 m	<u>% Gravel</u> 84	<u>% Sand</u> 15	<u>% Fines</u> 1
				
				

APPENDIX 2

FIGURE 1 – KEY PLAN

DRAWING PG5336-1 – TEST HOLE LOCATION PLAN



7	UPDATED TO LATEST CONCEPTUAL PLAN	2805/2025	PT
6	UPDATED TO LATEST CONCEPTUAL PLAN	10/02/2024	JV
5	UPDATED TO LATEST CONCEPTUAL PLAN	10/12/2021	JV
4	SLOPE STABILITY INFORMATION ADDED	08/19/2020	RG
3	UPDATED TO LATEST CONCEPTUAL PLAN	08/18/2020	RG
NO.	REVISIONS	DATE	INITIAL

STARWOOD GROUP INC.
GEOTECHNICAL INVESTIGATION
PROPOSED MULTI-STOREY BUILDING COMPLEX
1009 TRIM ROAD

OTTAWA,
Title:

ONTARIO

TEST HOLE LOCATION PLAN

Scale:	1:750	Date:	04/2020
Drawn by:	RCG	Report No.:	PG5336-1
Checked by:	RG	Dwg. No.:	PG5336-1
Approved by:	DJG	Revision No.:	7

p:\autocad\drawings\geotechnical\pg5336\pg5336-1 (hlp rev7).dwg

APPENDIX 3

LANDSLIDE HAZARD ASSESSMENT ADDENDUM

July 6, 2023

File: 125-1

Starwood Group Inc.
c/o Paterson Group Inc.
9 Auriga Drive
Ottawa, Ontario K2E 7T9

**1015 TWEDDLE ROAD, OTTAWA, ONTARIO
LANDSLIDE HAZARD ASSESSMENT
ADDENDUM**

This report is an addendum to the Landslide Hazard Assessment dated February 8, 2021 and addresses the changes to the landslide hazards and risks associated with the addition of a fourth tower to the proposed development.

This report is subject to the attached Statement of General Conditions. These conditions should be clearly understood while reading or interpreting this report.

1 INTRODUCTION & BACKGROUND

McQuarrie Geotechnical summarized the results of a landslide hazard and partial risks analysis in a report dated February 8, 2021. The development plans were amended by adding a fourth residential tower. The purpose of this addendum is to update and expand the landslide risk assessment in light of the addition of the fourth tower. Specifically, the addendum includes:

- i. more details regarding the individual risk assessment;
- ii. analysis of the societal or group risk; and
- iii. mitigation options to reduce the risk “as low as reasonably practicable” (ALARP).

2 PROPOSED DEVELOPMENT

The proposed development by Starwood Group includes four multi-storey residential towers connected by two levels of underground parking that will extend beyond the footprints of each tower and cover a majority of the site. The towers will range from 24 to 32 storeys high for a total of 1,006 one and two bedroom units. The final grade of the main floor is 52.40 m and the lower parking grade will be at 44.90 m elevation.

The existing grade along the south property line is approximately 50.0 m elevation; therefore, the temporary cutslope will be roughly 6.0 m deep, allowing for the depth of the pile caps. The existing grades across the site are highly variable but the parkade will generally result in removal of roughly 2 m of fill, on average. Final grades on the north side of the parkade are expected to be between 45.5 and 47 m elevation (LRL Associates, 2015), requiring landscaping fill outside of the building area ranging from 0 to 2 m thick.

3 RISK ANALYSIS METHODOLOGY

The probability of a landslide was estimated based on the ratio of bank affected by past landslides divided by the total length of bank comprised of sensitive clay. This analysis assumes that all slope and soil parameters are equal throughout the hazard area. Soil type or geology, and terrain conditions were considered in a secondary manner by:

- i. only including the terrain mapped as sensitive clay or silt on the surficial geology maps;
- ii. only including the terrain on the southwest (Ontario) side of the Ottawa River valley;
- iii. only including the active bank of the Ottawa River and the lowermost bank of the proto-Ottawa River.

The older/upper terrace banks of the proto-Ottawa River were excluded because they are higher and have been deeply incised by tributary gullies. These gully banks are more prone to landslides but are not representative of the landslide probability at the subject property because of the vastly different terrain conditions. Similarly, the landslide frequency on the Quebec side of the Ottawa River is higher, mainly due to steeper terrain and many more tributary streams and rivers with deeper banks. Without factoring in the terrain conditions at each of the landslide locations, including the landslides on the Quebec side within the study would result in a bimodal relationship, with a much higher landslide probability on the Quebec side. So while bank height was not a direct factor in the probability analysis, it was considered and included indirectly by being selective of the area used to determine the probability.

Landslides along the upper proto-river terraces would be a factor if analyzing the probability of the subject property being impacted by a landslide initiating along the upper terrace. However, the upper terrace is located at least 1 km south of the subject property; therefore, any landslide would have to travel that far across gentle terrain including single-family residential developments, commercial developments, and the new light rail transit system. The probability of such a landslide reaching the subject property without warning is considered extremely remote.

In a multivariable risk analysis, this base probability would be adjusted using several other parameters. For landslides in sensitive clays, the other parameters would include bank height (as a direct factor), slope angle, and the presence of active toe erosion. Soil strength parameters would also be factored into the probability calculation by considering clay sensitivity, liquidity index, and remoulded shear strength. Unfortunately, such a detailed analysis is impossible without knowing the terrain and soil conditions at each of the past landslides within the study area. Such information is not available; therefore, instead of directly including these factors in the quantitative analysis, the base landslide probability was adjusted higher or lower using judgement by considering the soil strength and slope parameters at the

Tweddle Road site. These other critical factors affecting the landslide probability are described in Section 9 of the original report, and outlined below in Section 4.

4 LANDSLIDE HAZARD ASSESSMENT

4.1 Geology

Landslides in the sensitive clays in the Ottawa area have been found to occur more commonly where a surficial sand layer overlies the clay (Unit 2 on GSC OF352). The project site is mapped as clay without a surficial sand layer (Unit 1), as verified by the bore hole data from site. The base probability of landslide occurrence already takes into consideration the geology by differentiating Unit 1 from Unit 2. Only the Unit 1 polygons were included in the analysis.

4.2 Bank Height & Angle

Higher banks are associated with a much greater landslide occurrence. Various studies referenced in the original report found:

- banks less than 6 m high are rarely associated with landslides;
- modelling shows banks must be at least 10 m high to trigger an earth flow;
- higher banks are associated with larger earth flows.

For retrogressive flow slides, the bank height must be high enough to allow the initial slide debris to exit the depletion zone in order to create the over-steepened headscarp to allow retrogression (unless the bank is actively subject to toe erosion, as discussed below).

The upper slope along the south side of the property was originally between 3 and 5 m high, but has been supported for several decades by fill placed across the site. The local slope hazard maps for Ottawa did not even classify the subject property as being on a slope¹. This fill will be excavated as part of the underground parkade but the cutslope will ultimately be fully supported by the parkade structure. The temporary excavation will be 5 to 6 m high and will create a short-term risk that should be mitigated. Mitigation measures should focus on maintaining the lateral support to the slope during construction by shoring or other means.

The north embankment above the river will be 3 to 4 m high but most of the fillslope has existed for decades without any instability. The excavation for the parkade will unload most of the property with the increased load limited to the exterior landscaping beyond the parkade footprint.

¹ Klugman, M.A. and Chung, P. 1976. Slope stability study of the Regional Municipality of Ottawa-Carleton, Ontario Canada. Ontario Geological Survey Miscellaneous Paper MP68.

The permanent slope conditions both to the north and south should result in a much lower landslide probability than the base probability provided the temporary cutslopes are suitably shored or buttressed to prevent the development of any planes of weakness.

4.3 River Bank Erosion

A majority of the landslides in sensitive clays in Canada are triggered (or at least partly caused) by toe erosion. After a landslide has occurred, further erosion can remove the debris accumulation, creating conditions for retrogression.

Petrie Island is in a depositional environment and Tweddle Road further obstructs the river flow and any fluvial erosion along the north side of the subject property. This slope has not eroded in several decades if not longer; therefore, the landslide probability should be much less than the base probability.

4.4 Undrained Shear Strength, Clay Sensitivity & Liquidity Index

Earth flows occur where the remoulded shear strength is 1 kPa or less, the liquidity index is greater than 1.2 to 2.0, and the sensitivity is greater than 16 to 30. Earth spreads may occur where the remoulded shear strength is as high as 1.6 or perhaps even 2.0 kPa.

The site investigations at the project site found:

- The lowest remoulded shear strengths in the test holes by Paterson Group are typically 7 to 10 kPa, while WSP's test holes found remoulded strengths between 3 and 8 kPa. No remoulded strengths were found to be 2 kPa or less.
- The sensitivities found in the test holes by Paterson Group are typically 10 or less. WSP's test holes measured sensitivities typically between 10 and 12 but as high as 16.
- WSP measured liquidity indices between 0.66 and 1.62.

The sensitivities and liquidity indices are at the low end of the range associated with landslides in sensitive clays, while the remoulded strengths are much too high for an earth spread, let alone an earth flow. Based on these soil strength parameters, the landslide probability at this site should be significantly less than the base probability.

4.5 Earthquakes

Some of the landslides in the Ottawa area were very likely triggered by large earthquakes. However, the earthquake hazard is ubiquitous wherever the sensitive clay is located. For the most part, the seismically-induced landslide hazard should be affected by the same parameters that create the static landslide hazard (i.e. the same soil and slope conditions described above). Slopes that are marginally stable

under static conditions are more likely to fail during an earthquake than slopes with a higher static factor of safety.

At Tweddle Road, the pseudo-static slope stability analysis determined the factor of safety under seismic conditions to be greater than 1.1 when subject to the 1:2,475 year earthquake. The application of limit equilibrium analysis to landslides in sensitive clay has been questioned by some researchers; however, it is still often used to analyze the initiating failure that triggers an earth flow. The stable factor of safety is consistent with both the terrain and soil conditions described above. Even under seismic conditions, the landslide probability should be less than the base probability.

5 RISK ANALYSIS

5.1 Individual Risk

The risk calculation estimates the probability of death to an individual using the following formula:

$$PDI = P(H) \times P(S:H) \times P(T:S) \times V(L:T)$$

where:

PDI is the annual probability of death to a specific individual.

$P(H)$ is the annual probability of a landslide occurrence.

$P(S:H)$ is the probability of spatial interaction with subject property.

$P(T:S)$ is the probability of temporal interaction, which is separated into $P(T_R:S)$ the probability of someone being in the home at the time of the landslide (i.e. percentage of the day someone is in their home), and $P(T_W:S)$ the probability of insufficient warning to allow the occupant to escape.

$V(L:T)$ is the vulnerability, specifically the probability of fatality to persons in the building impacted by the landslide.

The values applied in the risk analysis must be reasonable and based on estimates while avoiding inherent and repeated conservatism. To quote Strouth and McDougall ²:

Engineers are trained to incorporate conservatism into their design assumptions. However, risk is overestimated when this conservative attitude is applied, perhaps unknowingly and to a number of different inputs, in a risk analysis. Inflated risk estimates are inappropriate for risk evaluation.

² Strouth, A. & McDougall, S. (2022a). Individual risk evaluation for landslides: key details. Landslides 19: 977-991. <http://dx.doi.org/10.1007/s10346-020-01547-8>.

Analysts should assess and present uncertainties transparently, while using best estimates for risk evaluation.

The base probability, as explained in Section 3, considered the southeast bank of the Ottawa River from Lower Allumette Lake to the east end of the mapping project downstream of Hawkesbury. Of this more than 240 km of bank, approximately 112 km is mapped as Unit 1 (clay) and less than 2.8 km is mapped as a landslide or crosses a landslide. This accounts for 7 or 8 landslides ranging in width from 100 m to 1,100 m, but more typically 300 to 500 m wide. The percentage of the river bank comprised of Unit 1 that has been directly affected by landslides is 2.5%.

Since some of these landslides were undoubtedly caused by the large earthquake 4550 years BP, the geologic record extends at least that far back and the landslides can be assumed to have occurred over at least that time period, resulting in an annual probability of a large landslide no greater than 1 in 182,000. If the landslide inventory is assumed to represent the full 8000 years of the clay deposit, the probability of a landslide occurring at this site would be estimated to be 1 in 320,000 per annum.

The resulting range of probabilities (1 in 182,000 to 1 in 320,000) is due to the unknown timeframe of the landslide record. Specifically, over what period can landslide scars still be delineated? The original surficial geology maps are from 1976, predating LiDAR; however, most of the study area used to estimate the landslide probability is also included in the recent mapping using LiDAR (GSC OF8600). With the added detail of LiDAR, the landslide record likely extends back the full 8,000 years, justifying a base probability of 1 in 320,000 per annum.

Since the probability already considers the width of the landslides, spatial interaction based on landslide width has already been factored ($P(H) \times P(S_W:H)$). Spatial interaction based on landslide length must still be considered. If a landslide occurs along the existing river bank or youngest of the proto-river banks along the south property line, the landslide is assumed to definitely affect the subject property, yielding a probability of spatial interaction $P(S_L:H)$ of 1.0. The steep bank along the next proto-river bank is at least 1 km south, far beyond the potential earth flow runoff; therefore, such landslides were not considered in the risk analysis ($P(S_L:H) = 0$).

The probability of a landslide occurring at this site ($P(H) \times P(S_W:H)$) should be adjusted based on the hazard criteria, as discussed in Section 4. The factors critical to landslides in sensitive clay are: clay sensitivity, liquidity index, remoulded strength, bank height and angle, and active toe erosion (or loss of toe support by other means). In the absence of studies specifically relating landslide probability to each factor, adjustments must be based on professional judgement. The conditions at the subject property are positive with respect to all of these factors. None of the studies indicate any measureable hazard where the bank height is less than 6 m, there is no toe erosion, the remoulded strength is above 2 kPa, and the sensitivity is less than

10. Based on the actual site conditions, the estimated landslide probability at this specific site should be adjusted much lower than the base probability. At most, the probability would range between 1:320,000 and 1:500,000 per annum.

The probability of temporal interaction is based on an individual spending 12 hours per day inside their home on weekdays and 16 hours per day on weekends, averaging to $P(T_R:S) = 0.55$.

The probability of no warning ($P(T_W:S)$) is more complex. Some earth flows have occurred with merely a few hours of warning; however, most investigations of sensitive clay landslides in Canada and Norway describe ample warning signs. Most of the devastating landslides in sensitive clay are preceded by one or more precursor landslides and extensive river erosion, such as the Saint Jude landslide in 2010 and the Saint-Luc-de-Vincennes landslide in 2016. The area of the 1993 South Nation Landslide was evacuated years prior to the landslide due to evidence of pending failure.³ The June 2022 earth flow in Saguenay, Quebec required evacuation of more than 50 homes. Several homes were lost in the landslide but no one was killed.

The deadliest landslide in Quebec history was the 1971 Saint-Jean-Vianney Landslide where 31 people died and 40 homes were destroyed. The landslide assessment⁴ describes large tension cracks developing over a few weeks prior to the landslide, some houses settling 15 to 20 cm, and even cows refusing to go into the fields near the landslide. The main landslide movement began more than 3 hours prior to destruction of the first home. Despite the death toll, many people obviously evacuated the 40 homes as well as the surrounding area. The death toll is most likely due to a lack of knowledge at that time as to the potential for such a large, catastrophic and retrogressive landslide in sensitive clays.

Governments are far more aware of the landslide hazards today than in 1971, as evident by the significant reduction in deaths in the more recent landslides. Even without a formal emergency management system that includes evacuation alerts and evacuation orders, signs of a pending landslide would likely be readily noticed.

The Tweddle Road development will create a large, relatively rigid structure comprising the reinforced concrete parkade and four towers founded on piles. Although the piles cannot be designed to fully resist the landslide movement, they should resist movement enough to form large tension cracks between the foundation walls and the adjacent unreinforced ground. The most likely scenario is that precursor ground movement should be obvious in the hard landscaping and roadways, allowing ample warning to evacuate the buildings. A formal evacuation

³ S.G. Evans and G.R. Brooks. 2011. An earthflow in sensitive Champlain Sea sediments at Lemieux, Ontario, June 20, 1993, and its impact on the South Nation River. *Canadian Geotechnical Journal*. **31**(3): 384-394. <https://doi.org/10.1139/t94-046>

⁴ F. Tavenas, J.-Y. Chagnon, and P. La Rochelle. 2011. The Saint-Jean-Vianney Landslide: Observations and Eyewitnesses Accounts. *Canadian Geotechnical Journal*. **8**(3): 463-478. <https://doi.org/10.1139/t71-048>

system managed by either the regional or provincial government could result in a $P(T_W:S)$ possibly as low as zero. In the absence of such a system, and allowing for less warning from some landslides, a reasonable value for $P(T_W:S)$ is estimated to be 0.3 (30% of residents fail to evacuate).

For comparison, PDI is also calculated for a $P(T_W:S)$ of 1.0, which assumes there is no warning. Since most of the recent landslides provided at least some warning and most residents were able to evacuate even without a government managed alert system, a $P(T_W:S)$ of 1.0 is not considered reasonable. However, the calculation is provided as a worst-case scenario merely to demonstrate the effect on PDI.

Vulnerability is equally challenging to estimate. The structure is larger and much more rigid than single-family houses. Considering the bank height and the potential magnitude of a landslide, the probability of any of the towers collapsing is considered to be quite low. However, as a worst-case scenario, this analysis applied FEMA's HAZUS natural hazard analysis tool for a building collapse due to an earthquake, which estimates the number of casualties to be 10% of the occupants.

The above values result in a PDI between 1:19 million to 1:30 million.

$PDI = P(H) \times P(S:H) \times P(T:S) \times V(L:T)$				
$P(H) \times P(S:H)$	$P(T_R:S)$	$P(T_W:S)$	$V(L:T)$	PDI
1 : 320,000	0.55	0.30	0.10	1 : 19,000,000
1 : 500,000	0.55	0.30	0.10	1 : 30,000,000

Even if a landslide occurs without warning and no residents are able to evacuate prior to the landslide, the PDI would be less than 1 in 5 million per annum.

$PDI = P(H) \times P(S:H) \times P(T:S) \times V(L:T)$				
$P(H) \times P(S:H)$	$P(T_R:S)$	$P(T_W:S)$	$V(L:T)$	PDI
1 : 320,000	0.55	1.0	0.10	1 : 5,800,000
1 : 500,000	0.55	1.0	0.10	1 : 9,000,000

Regardless, the PDI is several orders of magnitude less than the normal tolerable threshold of 1:10,000 and 1.5 to 2 orders of magnitude less than the more stringent threshold of 1:100,000 used for new structures by the District of North Vancouver. The PDI for this development meets all tolerable risk standards for individual risk.

PDI is the annual probability of death to a specific individual, usually the person most exposed to the hazard. Because PDI is the risk to a specific individual, it does not consider the number of people exposed or threatened by the hazard. Therefore, the increased density of the proposed development from three towers to four towers does not increase the individual risk or PDI.

5.2 Societal or Group Risk

When large groups of people are exposed to a potential landslide, societal or group risk analysis is more applicable. The differences between individual and societal risk analyses are explained by Strouth and McDougall (2022)⁵:

“In short, individual risk tolerance thresholds are unrelated to, and need to be defined independently from, societal risk tolerance thresholds and reference lines. Individual and societal risk tolerance thresholds originated from different places and have different meanings. Societal risk tolerance thresholds refer to the probability of ‘N’ fatalities out of a larger population. They do not consider risk to any specific individual. The tolerable probability of one or more fatalities on a societal risk tool is not equivalent to an individual risk threshold.”

Societal risk estimates are based on F-N curves that plot the estimated number of fatalities versus the probability of landslide occurrence. When multiple landslide scenarios exist, each is plotted individually to create a series of points. Different landslide scenarios could include different magnitudes of landslides or different structures where the probability of spatial interaction or the vulnerability differ. However, in this situation, only one landslide hazard was considered and all of the occupants of the four towers were considered to be equally exposed.

Using the same variables as described for individual risks in Section 4.1, the probability of a landslide occurrence at this property is estimated to be no greater than 1:320,000 and more likely 1:500,000 per annum.

Based on the total number of units being 1,006 and an average occupancy of roughly 1.5 people per unit, a total building population of 1,500 was assumed. Accordingly, a reasonable estimate of the number of deaths based on the same variables used in the PDI calculation would be 25.

$N_{fatalities} = P(T_R:S) \times P(T_W:S) \times V(L:T) \times N_{exposed}$				
$P(T_R:S)$	$P(T_W:S)$	$V(L:T)$	$N_{exposed}$	$N_{fatalities}$
0.55	0.3	0.10	1,500	25

In the unlikely event that a landslide occurs without warning and no residents are able to evacuate prior to the landslide, the number of deaths would be 83.

$N_{fatalities} = P(T_R:S) \times P(T_W:S) \times V(L:T) \times N_{exposed}$				
$P(T_R:S)$	$P(T_W:S)$	$V(L:T)$	$N_{exposed}$	$N_{fatalities}$
0.55	1.0	0.10	1,500	83

⁵ Strouth, A., McDougall, S. Individual Risk Evaluation For Landslides: Key Details. *Landslides* 19, 977–991 (2022). <https://doi.org/10.1007/S10346-021-01838-8>

Both of these points are plotted on the F-N graph on Figure 1. Despite the vastly different estimates on probability and number of deaths, the two points still plot in the middle of the ALARP zone, which demonstrates the broad range of risks represented by this zone.




Figure 1: Societal Risk Frequency of Landslide vs Number of Fatalities

6 RISK MITIGATION

A large majority of sites selected for a detailed quantitative risk assessment invariably results in the societal risk plotting within the ALARP zone; the question is then, how much mitigation is necessary to be considered ALARP?⁶ The ALARP zone is generally acceptable for development, provided reasonable measures are taken to reduce the risks. However, the costs of the risk reduction measures must be proportionate to the benefits in risk reduction.

6.1 Hazard Avoidance

Avoidance is not a practical mitigation method at this particular site considering the prevalence of the sensitive clay deposit in the Ottawa area. When the site characteristics (i.e. low bank height, lack of river erosion) and soil characteristics (high remoulded strength, low sensitivity) are taken into account, this site has a lower probability of being impacted by a landslide than much of the Ottawa area, particularly for river front property. The regional slope stability map for Ottawa-Carleton identifies this property as being practically the most stable along the Ottawa River east of Ottawa⁷ (see Figure 2 of the original report). In this context, the property is relatively favourable and does not warrant avoidance.

6.2 Erosion Mitigation

Given the low probability of a landslide at this site, the most effective means of mitigating the landslide risks would be to prevent any reduction in slope stability resulting from the development. Most importantly, fluvial erosion must be prevented. Without erosion, the river bank is so short that a landslide initiating along the north side of the development is highly unlikely. Therefore, the first mitigation measure would be for a river processes expert to assess the foreshore slope to determine if erosion protection measures are needed and, if so, to design such measures.

6.3 Cutslope Stabilization

Stability of the slope along the south side of the property must be maintained during construction. The proposed cutslope should be designed and supported by shoring to prevent even a small failure that could initiate a larger retrogressive failure.

If an open cutslope is planned, even for a short period of time while shoring is installed, it must proceed sequentially. This could be achieved by initially excavating the cutslope no steeper than 2H:1V, then sequentially excavating panels 3 to 5 m

⁶ Strouth, A., McDougall, S. Societal risk evaluation for landslides: historical synthesis and proposed tools. *Landslides* **18**, 1071–1085 (2021). <https://doi.org/10.1007/s10346-020-01547-8>

⁷ Klugman, M.A. and Chung, P. 1976. Slope stability study of the Regional Municipality of Ottawa-Carleton, Ontario Canada. Ontario Geological Survey Miscellaneous Paper MP68.

wide. Each panel must be fully supported and braced before proceeding with the adjacent panel, and no more than 20% of the panels should be unsupported at any one time. Shoring and bracing prevents the short-term loss of lateral support to the clay cutslope and, therefore, mitigates the landslide hazard along the south bank.

6.4 Increase Lateral Support

This south slope will be supported permanently by the parkade foundation wall. Walls are typically designed for active earth pressure conditions, which allows for minor movement of the wall. To mitigate the landslide risk, the south parkade wall should be design to support at-rest earth pressures, which are higher than active earth pressures. This mitigation measure increases the lateral support provided by the structure and should prevent any movement of the ground behind the wall.

6.5 Monitoring During Construction

Monitoring is the most common method of risk mitigation for landslides in sensitive clay and would be particularly effective in the short-term, during construction. Specifically, 4 or 5 slope inclinometers should be installed near the crest of the excavation and monitored regularly during construction to confirm that no ground movement occurs behind the south parkade wall. If more than 2 to 3 mm of movement occurs at depth (ignoring ice lensing in the upper 2 m), additional shoring support is recommended. The objective of cutslope monitoring would be to prevent the development of conditions that could lead to a landslide, thereby reducing the probability of a landslide.

6.6 Measures Not Considered Practicable

Other than the measures described above, mitigation options for landslides in sensitive clay are limited. The potential magnitude and depth preclude any structural means of stabilization. Increasing the pile size to stabilize the landslide is impossible because the potential depth and magnitude of the landslide would create bending moments that exceed the capacity of even large diameter steel pipe piles filled with concrete. Tie-back anchors to increase the lateral resistance are not an option because of the depth to bedrock, till, or any layer suitable to achieve pullout resistance.

If the river bank was higher, a toe buttress could be effective. However, the foreshore slope is so short and gentle that a toe buttress would be beneficial only to remediate river erosion. Therefore, the need for a toe buttress should be determined from the fluvial erosion assessment.

Long-term monitoring of landslide-prone areas has become the most common mitigation measure for sensitive clay landslides. However, the challenge with long-term monitoring is determining who is responsible for obtaining the information and

who analyzes the results. At this particular site, with such a low probability of a landslide, there are many areas along the Ottawa River valley that would benefit much more from a monitoring program. With increased development in the area, a broad-based monitoring program using annual LiDAR surveys and change detection analysis will eventually become more viable and should be considered. The objective of long-term monitoring would be to allow evacuation of the area, thereby reducing the probability of no warning to zero. If $P(T_W:S) = 0$, there should be zero deaths.

6.7 Conclusion

The combination of recommended mitigation measures:


- i. preventing erosion of the north bank,
- ii. shoring and short-term monitoring of the south cutslope, and
- iii. increasing the lateral resistance of the south parkade wall,

is considered an effective, reasonable and practicable, approach proportionate to the benefits in risk reduction. The risk reduction associated with these measures cannot be accurately quantified; however, by preventing any movement in the slopes both during construction and in the long-term, it is difficult to foresee how an earth flow or spread could possibly occur. The mitigated probability of a landslide occurrence is estimated to be reduced by 50%, reducing the estimated probability to the order of 1 in 10^6 per annum. With these measures, the risk can be considered to be “as low as reasonably practicable.”

CLOSING

Please contact me if you have any questions regarding this assessment or its conclusions.

McQuarrie Geotechnical Consultants Ltd.
EGBC Permit #1001716



Eric J. McQuarrie, P.Eng., P.Geo. (BC)