

**McINTOSH
PERRY**



Wall Sound and Lighting– Proposed Warehouse Development

210/220 Maple Creek Court, City of Ottawa

Site Servicing and Stormwater Management Report

Prepared for:

BBS Construction
1805 Woodward Drive
Ottawa, ON
K2C 0P9

Prepared by:

McIntosh Perry
115 Walgreen Road
Carp, ON
K0A 1L0

REV05: September 25th, 2020

CP-15-0429

www.mcintoshperry.com

TABLE OF CONTENTS

1.0 PROJECT DESCRIPTION	1
1.1 Purpose	1
1.2 Site Description	1
2.0 BACKGROUND STUDIES	2
3.0 PRE-CONSULTATION SUMMARY	2
4.0 EXISTING SERVICES	3
5.0 SERVICING PLAN	3
5.1 Water Servicing	3
5.2 Sanitary Servicing	3
5.3 Storm Servicing	4
6.0 STORMWATER MANAGEMENT	5
6.1 Design Methodology	5
6.2 Site Drainage	6
6.2.1 Pre-Development Drainage	6
6.2.2 Post-Development Drainage	6
6.3 Quantity Control	7
6.4 Quality Control	7
6.4.1 Soakaway Pit	8
6.4.2 Temperature Mitigation Measures	8
6.4.3 Maintenance Design Parameters	9
7.0 SEDIMENT AND EROSION CONTROL	9
8.0 SUMMARY	10
9.0 RECOMMENDATION	11

List of Figures

FIGURE 1: KEY MAP: 210/220 MAPLE CREEK COURT, OTTAWA..... 1

List of Tables

TABLE 1: PRE-DEVELOPMENT DRAINAGE SUMMARY 6

TABLE 2: POST-DEVELOPMENT RUNOFF CALCULATIONS..... 6

List of Appendices

APPENDIX A: CITY OF OTTAWA PRE-CONSULTATION NOTES

APPENDIX B: WATER DEMANDS AND FIRE CALCULATIONS

APPENDIX C: SEPTIC DESIGN BY PATERSON GROUP

APPENDIX D: PRE-DEVELOPMENT PLAN

APPENDIX E: POST-DEVELOPMENT PLAN

APPENDIX F: STORMWATER CALCULATIONS

APPENDIX G: CITY OF OTTAWA DESIGN CHECKLIST

1.0 PROJECT DESCRIPTION

1.1 Purpose

This report will address the servicing (water, sanitary, and storm) and stormwater management requirements associated with the proposed development located at 210/220 Maple Creek Court within the City of Ottawa.

1.2 Site Description

The property is located at 210/220 Maple Creek Court within the approved Reis Road Industrial Park. It is described as Parts 4 & 5, Plan 27R-17169 geographic Township of Huntley, City of Ottawa. The land in question covers approximately 3.47 ha and is located at the end of the cul-de-sac on Maple Creek Court.

The existing site is currently undeveloped and is made up of gravel and grass areas with low lying vegetation. There are no buildings or infrastructure located on or under the existing site.

The proposed development consists of four (4) warehouse buildings approximately 1,865 m² in size. The proposed development will be completed in phases. Parking and drive aisles will be provided throughout the site with landscaping located around the perimeter of the site.



Figure 1: Key Map: 210/220 Maple Creek Court, Ottawa

2.0 BACKGROUND STUDIES

Background studies that have been completed for the site include review of the City of Ottawa as-built drawings, Reis Road Industrial Park Design Guidelines, a topographical survey of the site, A Phase I Environmental Site Assessment, a geotechnical report, a hydrogeological assessment and an environmental impact statement.

As-built drawings of the existing services within the vicinity of the site were reviewed in order to determine proper servicing and stormwater management schemes for the site.

The original Reis Road Industrial Park Design Guidelines were reviewed for the specific design criteria.

A topographic survey of the site was completed by McIntosh Perry Survey Inc. (MPSI) dated November 2nd, 2016, and can be found under separate cover.

The following reports have previously been completed and are available under separate cover:

- Phase I Environmental Site Assessment completed by Pinchin dated October 7th, 2014.
- Geotechnical Investigation completed by Paterson Group dated January 3, 2018.
- Hydrogeological Assessment completed by Paterson Group dated January, 2017.
- Environmental Impact Statement completed by McIntosh Perry dated January 20th, 2017

3.0 PRE-CONSULTATION SUMMARY

City of Ottawa Staff have been pre-consulted regarding this proposed development in person on June 16th, 2016. Specific design parameters to be incorporated within this design include the following:

- Pre-development and post-development flows shall be calculated using a time of concentration (Tc) of 20 minutes and 10 minutes, respectively.
- Control 5 through 100-year post-development as outlined in the approved Reis Road Industrial Park Guidelines.
 - Sites in this subdivision can be developed without a requirement for on-site SWM as long as the combined C-value does not exceed 0.775
 - It is important to note that the subdivision design used constant C-values, while the City of Ottawa Sewer Design Guidelines (SDG) now stipulate a 25% increase during the 100-year event. Accordingly, future designs are to use the City's 100-year runoff coefficients when determining the combined C-value for the site.
- Quality control is required to be provided to an enhanced level, 80% TSS as per discussions with the MVCA.

Correspondence with the City can be found in Appendix 'A'.

4.0 EXISTING SERVICES

No underground water, storm or sanitary mains exist within Maple Creek Court. There is currently a roadside ditch within Maple Creek Court. The roadside ditches within the vicinity of the site direct storm flows towards the northwest away from the proposed site. There is an existing low spot along the center of the property frontage.

Hydro, cable and Bell are available to service the site from Maple Creek Court.

5.0 SERVICING PLAN

The proposed site will be serviced with a new well and septic system that will provide the proposed development with water and sanitary services. Stormwater runoff will sheet flow to the clear stone media storage located at the front of the site.

Hydro, Bell, and cable will be provided via an underground trench. All utilities will be provided from Maple Creek Court.

All servicing requirements shall be approved by the City of Ottawa or the relevant utilities, as applicable.

5.1 Water Servicing

An existing well will provide the domestic water supply for the phase 1 and 2 buildings. A new well will be drilled on site to provide the proposed phase 3 and 4 buildings with domestic water supply. As per the findings of the *Hydrogeological Assessment Report*, dated January 2017, the drilled well can provide sufficient quantity and quality of water for proposed site needs. The report also finds the proposed development will not adversely affect groundwater.

Neither the existing nor the proposed well will provide the required fire protection for the site. Fire protection will be provided on site via an underground fire tank protection system which will be located in the northwest corner of the site, on the south side of the site entrance. The tank system will hold 50,000 UK Gallons and will be equipped with all of the required connections as well as a dry hydrant system on the outside of the buildings. Correspondence with Ottawa Fire Services and calculations are available in Appendix 'B'.

5.2 Sanitary Servicing

The proposed septic system has been designed by Paterson Group and is found under separate cover. The design flow for the proposed development was calculated as 9,900 L/day based on the Ontario Building Code (OBC) for a warehouse without showers. (See Appendix 'C' for more information). The septic design has been completed and will be submitted to the Ottawa Septic System Office by Paterson Group. For further design information pertaining to the on-site sewage disposal system, please refer to Paterson's design drawing in Appendix 'C'.

5.3 Storm Servicing

A new sewer system will be extended from the existing ditch within Maple Creek Court. The new pipe network will collect storm flows and restrict runoff prior to leaving the site. Site runoff within the development will sheet flow across grassed, landscaped and paved surfaces to the proposed underground storm network.

Runoff from the proposed site will be collected and directed towards a Stormceptor at the front of the subject property. Catchbasins and landscape catchbasins are proposed throughout the subject property conveying flow to the Stormceptor. There is also a clear stone media gallery proposed where the majority of the stormwater runoff from the site will be conveyed through, where the water will be stored promoting infiltration. Once the clear stone media gallery is saturated, runoff will flow toward the proposed Stormceptor unit. The Stormceptor unit, which will remove 80% of the total suspended solids, will convey runoff to the roadside ditches present within the Maple Creek Court right-of-way. The storm sewers will range from 200 mm to 675 mm in diameter throughout the subject property.

The storm sewers will be sized for the 5-year flow without any restriction and the 100-year flow for the three loading dock drainage areas (B6,B7,B8). A storm sewer design sheet was created using the rational method and City of Ottawa 5/100-year storm event.

The storm design sheet calculates the proper sizing of the storm pipes within the development. Drainage area information, along with respective pipe slopes and other necessary information was utilized to evaluate the performance of the storm sewer network. The time of concentration calculated for the storm sewer system is based on a 10 minute inlet time at the uppermost sewer run. Within the design sheet, pipe capacities and associated full flow velocities have been calculated. The design flow (peak flow) was checked against the theoretical capacity to ensure that each storm sewer pipe can convey the 5-year unrestricted flow with the 100-year flow for the three loading dock drainage areas.

See CP-15-0429 - POST and Storm Sewer Design Sheet in Appendix 'F' of this report for more details. The Stormwater Management design for the subject property will be outlined in Section 6.0.

6.0 STORMWATER MANAGEMENT

Stormwater management for the development area will be maintained through positive drainage away from the proposed buildings and into the proposed storm pipe network. Restricted runoff from the clear stone media gallery will then be directed to the existing roadside ditch along Maple Creek Court. This SWM plan will protect the receiving waterways from excessive erosion by implementing velocity and quality control strategies. The storm runoff will enter the pipe system through landscape catchbasins (LSCB), catchbasins (CB's) and catchbasin manholes (CBMH's) located throughout the site. The quantitative and qualitative properties of the storm runoff for both the pre- and post-development flows are further detailed below.

In summary, the following design criteria have been employed in developing the stormwater management design for the site as directed by the MVCA and City:

Quality Control

- The site has been designed to achieve an 80% total suspended solids removal (enhanced level) using a proposed oil/grit separator.

Quantity Control

- No quantity control is required for the site. Subject property has been accounted for within the downstream storm system.

6.1 Design Methodology

Runoff calculations in this report are derived using the Rational Method, given as:

$$Q=2.78 CIA (L/s)$$

C=Runoff coefficient

I=Rainfall intensity in mm/hr.

A=Drainage area in hectares

It is recognized that the rational method tends to overestimate runoff rates. As a by-product of using extremely conservative prediction method, any facilities that are sized using these results are expected to function as intended in real world conditions.

In conjunction with the City of Ottawa Sewer Design Guidelines the following runoff coefficients were used to develop a balanced 'C' for each drainage area:

Building roofs, Asphalt, Concrete	0.90
Grass, undeveloped areas	0.20
Gravel	0.60

As per the City of Ottawa Sewer Design Guidelines, the 5-year balanced 'C' value must be increased by 25% for a 100-year storm event to a maximum of 1.0.

As per the pre-consultation meeting with the City of Ottawa the time of concentration (Tc) used for pre-development and post-development flows shall be calculated using a time of concentration (Tc) of 20 minutes and 10 minutes, respectively.

6.2 Site Drainage

6.2.1 Pre-Development Drainage

The existing site has been demonstrated as drainage areas A1-A3. Drawing CP-15-0429 PRE (Appendix 'D') indicates the limits of these drainage areas.

Table 1: Pre-Development Drainage Summary

Basin	Drainage Area (ha)	Runoff Coefficient (C) 5-yr	Runoff Coefficient (C) 100-yr	5-Year Flow Rate (l/s)	100-Year Flow Rate (l/s)
A1	0.92	0.20	0.25	35.9	76.6
A2	1.24	0.26	0.32	62.7	131.8
A3	1.30	0.20	0.25	50.6	108.0
Total	3.45	0.22	0.26	149.2	316.4

6.2.2 Post-Development Drainage

The proposed site has been demonstrated as drainage areas B1-B10. Drawing CP-15-0429 Post (Appendix 'E') indicates the limits of these drainage areas.

Table 2: Post-Development Runoff Calculations

Basin	Drainage Area (ha)	Runoff Coefficient (C) 5-yr	Runoff Coefficient (C) 100-yr	5-Year Flow Rate (l/s)	100-Year Flow Rate (l/s)
B1	0.51	0.66	0.74	65.4	125.2
B2	0.72	0.73	0.81	102.0	193.2
B3	0.58	0.52	0.59	59.2	114.7
B4	0.23	0.81	0.91	36.9	70.8
B5	0.36	0.57	0.65	40.2	78.3
B6	0.11	0.90	1.00	20.0	37.9
B7	0.05	0.90	1.00	9.6	18.3
B8	0.09	0.87	0.97	15.4	29.3
B9	0.38	0.59	0.67	43.5	84.3
B10	0.41	0.20	0.25	14.7	37.4
Total	3.45	0.60	0.68	409.7	789.3

(See Appendix 'F' for Calculations)

6.3 Quantity Control

The allowable runoff rate from sites within the Reis Road Industrial Park is governed by the design assumptions used in the approved Engineering Report contained in Schedule 'H' of the subdivision agreement. If the resulting runoff from the proposed site will be less than the allowable rate, no on-site SWM will be required. The design of the internal drainage for the subdivision was based on site developments that would be 50% building (C=1.0), 25% parking (C=0.9) and 25% undeveloped (C=0.2).

The design assumptions have been interpreted by the City of Ottawa, that sites in this subdivision can be developed without a requirement for on-site SWM as long as the combined C-value does not exceed 0.775. As detailed within Appendix 'D' the proposed development will have a C-value of 0.68.

After discussing with City staff, the stormwater management criteria for the site, no stormwater management quantity control is required for this site as the site C-value does not warrant SWM as per the excerpt provided by the City (See Appendix 'A' for City correspondence).

In the event that there is a rainfall above the 100-year storm event, or a blockage within the storm network, an emergency overland flow route has been provided such that the storm water runoff will be conveyed towards the north and south corners of the site away from the buildings. An elevation difference of 1.07 m has been provided from the lowest finished floor (115.20) of the building to the overland flow route elevation (114.00).

6.4 Quality Control

The Mississippi Valley Conservation Authority (MVCA) was contacted in order to identify the quality control requirements. An enhanced level of protection which involves a quality control of 80% Total Suspended Solids (TSS) removal is required for the site. Details can be found in Appendix 'A'.

The grass swales between the buildings have been designed to have shallow slopes ($\leq 4\%$) & to have a length greater than 40 m, however the depth of flow will not be controlled. Each swale has a tributary drainage area less than 1 ha. The grass within the swales will be kept at a length greater than 75 mm to enhance the filtration of suspended soils. The rear portion of the site will remain vegetated and will act as a large vegetated filter strip. The filter strip has an existing slope of 0.4%, has a length of 30 m and is 10 m wide in the flow direction (towards the south). Perennial rye grass shall be planted within the swales as it is a very fast germinating grass that spreads well under full sun conditions. The outlet for this area will be the south corner of the property as in pre-development conditions.

A Stormceptor (STC) will provide the required 80% TSS removal before stormwater runoff enters the clear stone media trench. The clear stone media trench is designed to provide temperature mitigation benefits by retaining water to allow heat transfer from the water to the clear stone. Further information regarding the function of the soakaway pit is available in Section 6.4.1.

The development of this lot will employ Best Management Practices (BMP's) wherever possible. The intent of implementing stormwater BMP's is to ensure that water quality and quantity concerns are addressed at all stages of development. BMP's at this site will be implemented at the lot level. Lot level BMP's typically include minimizing ground slopes and maximizing landscaped areas which are being implemented on this development.

In addition, the Carp River Watershed/Subwatershed study indicates Subwatershed priorities for Huntley Creek infiltration target of 104mm/yr infiltration for moderate recharge areas. This is further detailed below.

6.4.1 Soakaway Pit

A soakaway pit has been designed in accordance with MECP 'Stormwater Management Planning and Design Manual', Section 4.5.5. The soakaway pit will accept runoff from drainage areas B2 through B9.

As per the Carp River Watershed / Subwatershed Study, 104mm/yr is required to be infiltrated. Therefore, taking the development area of 3.45ha by the required infiltration, 2,075m³/year is required to be infiltrated. 2017 Annual Rainfall data has been taken and derived from the Canada Weather Stats website. Storm events between the 6mm and 10mm were considered, which gives a total number of 22 events in 2017 with an average precipitation depth of 7.75mm yielding a total of volume of runoff of 4,312m³/yr to infiltrate (which exceeds the required volume noted above).

The ponding area has been designed to contain and infiltrate flows from a 10mm storm event. Taking the product of areas B2-B9 by the 10mm storm event, a volume of 252.90m³ is required to be held within the ponding area. A percolation rate of 50mm/hr with an applied safety factor of 2 has been used for the site. The average retention time is 44 hours for a 10mm event. In the instance of a storm event exceeding the 10mm event, runoff from the soakaway pit will overflow to the outlet pipe. Refer to Appendix 'F' for calculations.

6.4.2 Temperature Mitigation Measures

The MVCA references the requirements for temperature mitigation measures for Huntley Creek as it has been designated as a "cool-water fish habitat". It is expected that stormwater measures designed to promote infiltration would aid in addressing these targets. The site is primarily impervious area underlain by glacial till, so infiltration measures will be limited as BMPs for temperature mitigation. The building rooftop has been proposed with light-coloured (high albedo) material to reduce radiant heat transfer to stormwater runoff from roof areas.

The majority of heat transfer from paved surfaces occurs during the first flush (considered as the initial 10 mm of the design event). Due to site constraints within phase one, the clear stone trench will retain 80% of the 10 mm rain event. For calculations on the volume of runoff from the 10 mm rain event, please refer to Appendix 'F'. It is expected that the retention of 80% of the first flush runoff volume and the high albedo roof material will provide sufficient temperature mitigation to satisfy the ecological balance within the cool-water fish habitat of Huntley Creek.

6.4.3 Maintenance Design Parameters

Operation and maintenance is required to ensure effective operation, longevity and aesthetic functioning of the SWMP and may include: sediment removal, trash removal, maintenance of vegetation and inspection of the inlet(s) and outlet(s).

Estimates of the longevity of infiltration SWMPs are based on professional opinion. Equation 7.1 and Table 7.4 from the MOE Stormwater Management Planning and Design Manual may be used as guidance for estimating longevity (based on monitoring results in literature and the native soil permeability). Recognizing the subjectiveness of Equation 7.1, there needs to be flexibility in assessing the lifespan of infiltration SWMPs based on site-specific information. As the majority of the site is made up of the proposed roof the runoff entering the SWM Area will have limited opportunity for carrying sediments to the infiltration structure.

Our recommendation for the SWM Area is to have annual inspections completed for the Clear Stone Media Trench including a CCTV of the pipe network within the SWM area. The inspection should note any sediment build-up, standing water or any trash within the structure. Based on the reviews maintenance will be required to ensure the SWM Area is functioning as designed.

7.0 SEDIMENT AND EROSION CONTROL

The site-grading contractor is responsible for ensuring sediment control structures are installed in accordance with the Site Grading and Drainage Plan as indicated. Silt fences shall be installed on site before construction or earth-moving operations begin, as shown on the site plan. Each phase of the development will erect silt fences around the perimeter of the development area. Mud mats for the two private entrances shall be present while construction is underway.

Geosock is to be installed under the grates of all existing structures along the frontage of the site and any new structures immediately upon its installation. The Geosock is to be removed only after all areas have been paved. Care shall be taken at the removal stage to ensure that any silt that has accumulated is properly handled and disposed of. Removal of silt fences without prior removal of the sediments shall not be permitted.

At the discretion of the project manager, municipal staff or conservation authority, additional silt control devices shall be installed at designated locations.

8.0 SUMMARY


- Four (4) new $\pm 1,865$ m² warehouse buildings will be constructed on the site located at 210/220 Maple Creek Court.
- A new septic system will be installed on-site and has been designed by Paterson Group. This design has been added to this report in Appendix C for reference purposes only.
- An existing as well as a new drilled well onsite will service the development with domestic water supply.
- A new storm network will be installed onsite and will discharge to the clear stone media area.
- As discussed with the City of Ottawa staff, stormwater management is not required for this site as the combined C-value is below the 0.775 threshold.
- Stormwater quality treatment will be designed to remove 80% TSS per Mississippi Valley Conservation Authority requirements.

9.0 RECOMMENDATION

Based on the information presented within this report dated September 25th, 2020 we recommend that the City approve this Servicing and Stormwater Management Report in support of the proposed development located at 210/220 Maple Creek Court.

The sediment and erosion control plan outlined in Section 7.0 and detailed in the Grading and Drainage Plan notes are to be implemented by the contractor.

This report is respectfully being submitted for approval.



Ryan Kennedy, P. Eng.
Practice Area Lead, Land Development
(613) 836-2184 Ext.2243
R.Kennedy@mcintoshperry.com

APPENDIX A: CITY OF OTTAWA PRE-CONSULTATION NOTES

Jonathan Jonker

From: Hall, Kevin <Kevin.Hall@ottawa.ca>
Sent: December 1, 2016 3:06 PM
To: Jonathan Jonker
Subject: RE: 210/220 Maple Creek Court - SWM Confirmation

Follow Up Flag: Follow up
Flag Status: Flagged

Jonathan

Yes those are still the requirements.

Kevin Hall, C.E.T.

Project Manager, Infrastructure Approvals
Development Review - Rural Services
Gestionnaire de projet, Approbation des demandes d'infrastructure
Examen des demandes d'aménagement (Services ruraux)
City of Ottawa | Ville d'Ottawa
613.580.2424 ext./poste 27824
ottawa.ca/planning / ottawa.ca/urbanisme

From: Jonathan Jonker [mailto:j.jonker@mcintoshperry.com]
Sent: Thursday, December 01, 2016 2:50 PM
To: Hall, Kevin
Subject: 210/220 Maple Creek Court - SWM Confirmation

Good Afternoon Kevin,

We are working with BBS to complete the submittal package for this site. As per the Reis Road Industrial Park Guidelines, we have determined that the site will have a combined C value of 0.66 for the 5-year and 0.74 for the 100-year. As per the engineering report for the subdivision and previous designs within the park, the site will not require on-site SWM controls.

We will provide our calculations to prove the combined runoff coefficients are below the 0.775 values. Can you please confirm that this is still the design criteria for the subdivision?

We have contacted the MVCA and they have stipulated that an enhanced level of treatment is required for the site, we will ensure this is provided through the site design.

Thank you very much,

Jonathan Jonker, C.E.T. 
Designer / Inspector | Land Development
115 Walgreen Road, RR 3, Carp, ON K0A 1L0
T. 613.836.2184 (2252) | F. 613.836.3742 | C. 613.868.6484

Stormwater Management – The allowable runoff rate from sites within the Reis Industrial Park is governed by the design assumptions used in the approved Engineering Report contained in Schedule “H” of the subdivision agreement. If the resulting runoff from the proposed site will be less than the allowable rate, no on-site SWM will be required. The design parameters used in the approved subdivision Engineering Report are as follows:

- The design of the internal drainage for the subdivision was based on site developments that would be: 50% building (C=1.0), 25% parking (C=0.9) and 25% undeveloped (C=0.2). By my interpretation of design assumptions in the subdivision Engineering Report, sites in this subdivision can be developed without a requirement for on-site SWM as long as the combined C-value does not exceed 0.775.

It is important to note that the subdivision design used constant C-values, while the City of Ottawa Sewer Design Guidelines now stipulate a 25% increase during the 100-year event. Accordingly, I would ask that you use the City’s 100-year runoff coefficients when determining the combined C-value for the site. If this is below 0.775, no on-site SWM will be required. If SWM is required, the allowable release will be based on the 5-year flow, with a C-value of 0.775

Jonathan Jonker

From: Myra Van Die <MVandie@mvc.on.ca>
Sent: September 30, 2015 10:56 AM
To: Curtis Melanson
Cc: Craig Cunningham
Subject: RE: 210 Maple Creek Court

Hi Curtis,

MVCA's quality control recommendations for the site are listed below:

- Huntley Creek is located to the south east of the site. An enhanced level of quality treatment is recommended for Huntley Creek based on the targets from the Carp River Watershed Subwatershed Study.
- The Carp Road Corridor CDP indicates the site is located within an area of high groundwater recharge. Given this, it is recommended stormwater techniques to infiltrate runoff be considered. Where infiltration measures receives primarily roof and pervious area runoff, the techniques can be employed without pre-treatment. Credit Valley Conservation has the following Design Guide available at: <http://www.creditvalleyca.ca/low-impact-development/low-impact-development-support/stormwater-management-lid-guidance-documents/low-impact-development-stormwater-management-planning-and-design-guide/> that may be of assistance.
- The Carp River Watershed Study identifies Huntley Creek as a cold water system and includes infiltration and runoff temperature targets. It is expected that stormwater measures designed to promote infiltration would aid in addressing these targets.

Please contact me should you have any questions.

Regards,

Myra Van Die, P.Eng. | Water Resources Engineer
Mississippi Valley Conservation Authority

From: Curtis Melanson [mailto:c.melanson@mcintoshperry.com]
Sent: September-21-15 1:35 PM
To: Craig Cunningham
Cc: Myra Van Die
Subject: 210 Maple Creek Court

Hi Craig,

We have a client who is looking to develop approximately 50,000 ft² of warehouse space at 210 Maple Creek Court in the Reis Industrial Park. Please see the attached concept plans for the site. They have not identified which concept they will be moving forward with.

Please note that we recognize there are a number of items missing including the septic/well/SWM locations.

We have not had a pre-consultation meeting with the City but are anticipating quantity control requirements. Can you please review and let us know what the quality control requirements for the site would be?

Thanks,

APPENDIX B: WATER DEMANDS AND FIRE CALCULATIONS

Project: 210/220 MAPLE CREEK COURT
 Project No.: CP-15-0429
 Designed By: JMJ
 Checked By: CJM
 Date: January 20, 2017

Ontario 2006 Building Code Compendium (Div. B - Part 3)

Water Supply for Fire-Fighting - Store/Office & Warehouse Building

Building is classified as Group : F2 (from table 3.2.2.55)
 Building is of noncombustible construction or of heavy timber construction conforming to Article 3.1.4.6. Floor assemblies are fire separations but with no fire-resistance rating. Roof assemblies, mezzanines, loadbearing walls,

From Div. B A-3.2.5.7. of the Ontario Building Code - 3. Building On-Site Water Supply:

(a) $Q = K \times V \times Stot$

where:

Q = minimum supply of water in litres
 K = water supply coefficient from Table 1
 V = total building volume in cubic metres
 Stot = total of spatial coefficient values from the property line exposures on all sides as obtained from the formula:
 Stot = 1.0 + [Sside1+Sside2+Sside3+...etc.]

K	27	(from Table 1 pg A-31) (Worst case occupancy {E / F2} 'K' value used)			
V	17,058	(Total building volume in cu.m.)			From Figure 1 (A-32)
Stot	1.0	(From figure 1 pg A-32)	→	Snorth	13.825 m 0.0
Q =	460,577.71 L			Seast	129.1 m 0.0
				Ssouth	34.07 m 0.0
				Swest	20.57 m 0.0

From Table 2: Required Minimum Water Supply Flow Rate (L/s)

9000 L/min (if Q >270,000 L)
 2378 GPM

*approximate distances



Project: Wall Sound and Lighting
210/220 Maple Creek Court
Ottawa, ON
Re: Fire Fighting Storage Tank Calculations

1. Building Occupancy

From Table 3.1.2.1. Volume 1 of the National Building Code – Major Occupancy Classification:

- Group F Division 2

2. Buildings Requiring On-Site Water Supply

From Div. B A-3.2.5.7. Volume 2 of the National Building Code – 3. “Buildings Requiring On-Site Water Supply”

- $Q = K * V * S_{tot}$ Where:
K = 27 (from Table 1 pg A-30)
V = 17,058 m³
(NOTE: The volume was calculated using total final volume of the Phase 1 building)
S_{tot} = 1.00 (from Figure 1 pg A-32)
- Therefore, $Q = (27) * (17,058 \text{ m}^3) * (1.00) = \underline{460,566 \text{ L}}$ (~ 121,669 gal)

3. Minimum Required Water Supply

From Div. B A-3.2.5.7., Table 2, Volume 2 of the National Building Code – Required Minimum Water Supply Flow Rate (L/min)

- 9,000 L/min (if $Q > 270,000 \text{ L}$)
From 3. (c) 9000 L/min for 30 min = 270,000 L (~71,326 gal)

Due to the excessive amount of water required from the equation above, the minimum supply required for 30 minutes will be used for this site. Therefore, the proposed underground fire protection tanks will be 5 – 45460.9 L (10,000 gal) tanks.

(MPCE File # CP-15-0429)

APPENDIX C: SEPTIC DESIGN BY PATERSON GROUP

CONSTRUCTION & DESIGN NOTES

1) ESTIMATE OF DAILY SEWAGE FLOW (Q)

Building No.	Unit No.	Office Space (m ²)			Warehouse (m ²)			Total
		Office	Warehouse	Total	Office	Warehouse	Total	
1	1	92	827	919	742	450	1192	
2	2	92	827	919	742	450	1192	
Total		184	1654	3500	1484	900	2384	
PHASE 1 - TDDSSF								2700
3	1	92	827	919	742	450	1192	
4	2	92	827	919	742	450	1192	
Total		184	1654	3500	1484	900	2384	
PHASE 2 - TDDSSF								2400
5	1	92	827	919	742	450	1192	
6	2	92	827	919	742	450	1192	
Total		184	1654	3500	1484	900	2384	
PHASE 3 - TDDSSF								2400
7	1	92	827	919	742	450	1192	
8	2	92	827	919	742	450	1192	
Total		184	1654	3500	1484	900	2384	
PHASE 4 - TDDSSF								2400

ESTIMATED DAILY SEWAGE FLOW FOR PHASE 1 = 268 L
 DESIGN DAILY SEWAGE FLOW FOR PHASE 1 = 2700 L
 THE PROPOSED DEVELOPMENT WILL BE CONSTRUCTED IN 4 PHASES.
 ESTIMATED SEWAGE FLOW FOR THE BUILT-OUT DEVELOPMENT = 9300 L
 DESIGN DAILY SEWAGE FLOW FOR BUILT-OUT DEVELOPMENT = 9300 L
 THE DESIGN NOTES AND GUIDELINES BELOW HAVE BEEN PROVIDED FOR THE PHASE 1 SEWAGE SYSTEM PERMIT. THE SYSTEM SHALL BE EXTENDED FOR EACH OF THE SUBSEQUENT PHASES.

2) SOIL CONDITIONS

SOILS INFORMATION GATHERED BY PATERSON GROUP INC. ON NOVEMBER 14, 2016

BH #	ELEV.	DEPTH	SOIL TYPE	REMARKS
04-30	114.99	0.00-0.30	TOPSOIL	
0304-09	114.99	0.30-0.60	GLACIAL TILL: RED-BROWN SILTY FINE SAND	
069-4-82	114.99	0.60-1.82	SOME GRAVEL & COBBLES GLACIAL TILL: BROWN SILTY FINE SAND, SOME GRAVEL, COBBLES & BOULDERS, TRACE CLAY	
04-08	114.99	0.00-0.08	TOPSOIL	
098-4-31	114.99	0.08-4.31	GLACIAL TILL: RED-BROWN SILTY FINE SAND	
5.31	114.99	5.31	PRACTICAL REFUSAL	

GWL @ 2.64 m DEPTH

3) TANKAGE

GENERAL REQUIREMENTS

- ALL TANKS SHALL BE PRECAST CONCRETE TANKS CONFORMING TO CSA-896-10.
- THE ACTUAL TANK CONFIGURATION MAY DIFFER FROM THAT SHOWN PROVIDED THE MINIMUM SPECIFIED WORKING CAPACITY OF THE TANK MEETS THE DESIGN REQUIREMENTS.
- ALL SEPTIC TANKS MUST BE CSA OR CSA CERTIFIED AND SHALL BE DESIGNED TO WITHSTAND ALL APPLICABLE LOADS.
- TANKS SHALL BE BEDDED ON A LAYER OF OPSS GRANULAR A COMPACTED TO AT LEAST 85% OF ITS SPMD.
- TANKS SHALL BE CONNECTED TO 100mm Ø SCH 40 PVC SEWER PIPE WITH WATER TIGHT CONNECTIONS.
- BACKFILL TANKS USING OPSS GRANULAR B TYPE 1 BACKFILL OR CLEAN SAND FILL. PLACE BACKFILL IN UNIFORM LAYERS NOT EXCEEDING 100mm THICKNESS AND COMPACT TO AT LEAST 85% OF ITS SPMD.
- FINAL GRADING SHALL BE SHAPED TO ENSURE THAT SURFACE WATER IS DIRECTED AWAY FROM ALL TANKS.
- WORK AREAS SHALL BE COVERED WITH A LAYER OF TOPSOIL OF AT LEAST 100mm IN THICKNESS.

SEPTIC TANK

- MINIMUM WORKING CAPACITY OF TANK REQUIRED = 30 x 8,100 L, A 9,000 L PRECAST TWO-COMPARTMENT CONCRETE SEPTIC TANK SHALL BE INSTALLED.
- A POLYLOCK PL-420 EFFLUENT FILTER WITH A PIPE SUPPORT SHALL BE INSTALLED IN THE SEPTIC TANK.
- THE EFFLUENT FILTER SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S GUIDELINES AND CENTERED OVER THE ACCESS OPENING.
- THE ACCESS OPENING OVER THE TANK OPENINGS (2) SHALL EXTEND TO THE GROUND SURFACE. INSTALL POLY RISERS AND COVERS TO SUIT.
- RISERS SHALL EXTEND TO AT LEAST 50mm ABOVE FINISHED GRADE.

PUMP STATION

- THE PUMP STATION SHALL CONSIST OF A 1,350 L MIN. SINGLE COMPARTMENT TANK.
- THE PUMP STATION SHALL BE LOCATED IN SERIES AND DOWNSTREAM FROM THE SEPTIC TANK.
- TANKS SHALL BE CONNECTED USING 100mm Ø SCH 40 PVC SEWER PIPE WITH WATER TIGHT CONNECTIONS.
- THE ACCESS OPENING OVER THE PUMP SYSTEM SHALL EXTEND TO THE GROUND SURFACE. INSTALL POLY RISERS AND COVERS TO SUIT.
- RISERS SHALL EXTEND TO AT LEAST 50mm ABOVE FINISHED GRADE.
- THE PUMP CHAMBER SHALL BE EQUIPPED WITH A FLOAT OPERATED EFFLUENT PUMP (MVERS MESH OR EQUIVALENT) OPERATED BY AN ON DEMAND CONTROL PANEL AND A HIGH WATER ALARM WITH AUDIBLE AND VISUAL WARNING CAPABILITIES.
- CONTROL PANEL TO BE MOUNTED ON SIDE OF BUILDING.
- THE RECOMMENDED PUMP DUTY CYCLE IS 30%.
- INSTALL RECOMMENDED FITTINGS FROM NEW PUMP AND CONNECT TO 50mm Ø SCH 40 PVC FORCE MAIN.
- PUMP DISCHARGE ASSEMBLY SHALL BE CONFIGURED SUCH THAT THE PUMP CAN BE EASILY REMOVED FROM THE GROUND SURFACE.
- FORCE MAIN TO BE PROVIDED WITH AT LEAST 1.5 m OF SOIL COVER AND OVERLAIN WITH 50mm THICK BY 600mm WIDE INSULATION BOARDS.
- ALL PIPING CONNECTIONS TO BE QUALIFIED.
- ALL ELECTRICAL WORKS MUST BE CARRIED OUT BY A QUALIFIED ELECTRICAL CONTRACTOR IN ACCORDANCE TO THE LATEST CODES, BYLAW AND REGULATIONS.
- CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN ALL NECESSARY ELECTRICAL PERMITS AND COORDINATE ALL ELECTRICAL INSPECTIONS.

4) LEACHING BED SIZING

- LENGTH OF PIPE REQUIRED = $Q / (2000) = 27000 / 200 = 135m$
- USE RUNS OF 13.5m EACH RUN
- TOTAL LENGTH OF DISTRIBUTION PIPES PROVIDED = 108m
- TOTAL BED AND MANTLE AREA = 930m²
- HYDRAULIC LOADING RATE = 5.1 L/m²

5) DISPOSAL FIELD CONSTRUCTION GUIDELINES

- A FILL BASED ABSORPTION TRENCH STYLE LEACHING BED SHALL BE INSTALLED.
- THE SUBGRADE SURFACE FOR THE BED AND MANTLE AREAS SHOULD BE PREPARED BY REMOVING ALL EXISTING TOPSOIL AND SUBCAVING TO AT LEAST ELEVATION 113.80m.
- WHERE REQUIRED, THE SPECIFIED CONTACT LEVEL SHALL BE ESTABLISHED WITH SELECT SAND FILL.
- THE SUBGRADE SHALL BE SCARIFIED UNDER DRY CONDITIONS.
- A MINIMUM THICKNESS OF 0.9m OF IMPORTED SAND FILL HAVING A PERCOLATION RATE OF NOT GREATER THAN 60mm/hr SHALL BE PROVIDED BELOW THE BASE OF THE TRENCHES.
- LEACHING BED SAND FILL SHALL BE UNIFORM SAND WITH GRADING LIMITS SIMILAR TO 100% PASSING 13.2mm SIEVE, LESS THAN 5% PASSING 0.075mm SIEVE AND HAVING A PERCOLATION RATE OF 6.0mm/hr. LEACHING BED FILL SHALL BE PRE-APPROVED BY THE CONSULTANT.
- THE DISTRIBUTION PIPES SHOULD CONSIST OF 100mm Ø PERFORATED SEPTIC PIPE WHICH SHOULD BE EMBEDDED IN A 300mm THICK 100mm MIN. WIDE LAYER OF WASHED SEPTIC STONE.
- AT THE HEADERS AND ELEVATION 114.85m AT THE FOOTER.
- THE SIDES OF EACH TANK SHALL BE INTERCONNECTED WITH A SOLID FOOTER PIPE.
- THE CLEAR STONE LAYER SHOULD BE COVERED WITH A NON-WOVEN GEOTEXTILE FABRIC.
- THE CLEAR STONE LAYER SHOULD BE BACKFILLED WITH PERMEABLE SAND FOLLOWED BY APPROXIMATELY 50mm OF SANDY TOPSOIL.
- THE TOTAL THICKNESS OF THE COVER OVER THE BASE OF THE TRENCHES SHOULD BE WITHIN THE RANGE OF 0.6m TO 0.9m.
- THE SIDES OF THE BED SHOULD BE SLOPED IN THE RANGE OF 4H:1V OR SHALLOWER.
- THE SAND AREA OUTSIDE OF LIMITS OF THE DISTRIBUTION PIPES SHALL CONSIST OF A MINIMUM THICKNESS OF 300mm OF UNIFORM SAND HAVING A PERCOLATION RATE OF NOT GREATER THAN 8 mm/hr.
- THE BED AREA SHOULD BE VEGETATED AS SOON AS POSSIBLE.

6) MINIMUM CLEARANCE DISTANCES FROM DISTRIBUTION PIPES



- 6.0m FROM ANY PROPERTY LINE
- 6.0m FROM ANY STRUCTURE
- 18.0m FROM ANY DRILLED WELL

7) MINIMUM CLEARANCE DISTANCES FROM TANKS

- 3.0m FROM ANY PROPERTY LINE
- 1.5m FROM ANY STRUCTURE
- 15.0m FROM ANY DRILLED WELL

GENERAL NOTES FOR SEWAGE SYSTEMS:

- SEWAGE SYSTEM CONTRACTOR SHALL BE QUALIFIED AND REGISTERED UNDER PART 9 OF THE ONTARIO BUILDING CODE.
- ALL WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE LATEST BYLAW, CODES AND REGULATIONS.
- CONTRACTOR SHALL REVIEW DRAWINGS IN DETAIL AND SHALL INFORM THE CONSULTANT OF ANY ERRORS AND/OR OMISSION ON DESIGN DRAWINGS IMMEDIATELY.
- CONTRACTOR SHALL VISIT THE SITE AND REVIEW ALL DOCUMENTATION TO BECOME FAMILIAR WITH THE SITE AREA AND SUBSURFACE SOIL CONDITIONS TO DETERMINE SUITABLE METHODS OF CONSTRUCTION.
- CONTRACTOR SHALL BE RESPONSIBLE FOR LAYOUT AND GRADING FOR SEWAGE SYSTEMS AS DETAILLED ON DESIGN DRAWINGS.
- THE CONTRACTOR IS RESPONSIBLE TO LOCATE AND PROTECT ALL EXISTING UNDERGROUND SERVICES.
- THE CONTRACTOR SHALL COORDINATE ALL WORK WITH THE PROJECT MANAGER.
- THE WORK AREAS SHALL BE PROTECTED DURING CONSTRUCTION WORK.
- THE CONTRACTOR IS RESPONSIBLE FOR DAMAGE TO PROPERTY AND STRUCTURES AND SHALL REPAIR AT OWN EXPENSE.
- ALL MATERIALS AND CONSTRUCTION METHODS SHALL CONFORM TO OBC, OPSS AND CITY OF OTTAWA STANDARDS AND SPECIFICATIONS.
- THE CONTRACTOR SHALL CONTROL WATER RUN OFF FROM THE SITE IN ACCORDANCE WITH STANDARD SEDIMENT CONTROL MEASURES.
- EXCESS AND/OR UNSUITABLE SITE EXCAVATED SOIL SHALL BE REMOVED FROM THE SEWAGE SYSTEM AREA AND DISPOSED OF AS DIRECTED BY THE CONSULTANT AT NO ADDITIONAL COST TO THE OWNER.
- THE CONTRACTOR IS RESPONSIBLE TO SUPPLY ALL MATERIALS AND LABOUR NECESSARY TO MAKE THE SEWAGE SYSTEM FULLY FUNCTIONAL AND AS INTENDED BY DESIGN.
- THE CONTRACTOR SHALL SUPPLY AND HAVE INSTALLED BY A QUALIFIED PERSON ALL ELECTRICAL COMPONENTS NECESSARY TO MAKE THE PUMPING SYSTEM FUNCTIONAL AND CONFORM TO THE PERTINENT REGULATIONS.




LEGEND:

- 114.10 GROUND SURFACE ELEVATION (m)
- 114.20 PROPOSED SITE GRADING (m) (REFER TO SITE GRADING AND SERVING PLAN)
- 113.80 PROPOSED GROUND SURFACE ELEV. OVER SEWAGE SYSTEM COMPONENTS (m)
- 113.7 GROUNDWATER ELEV. (m) - NOV. 14, 2016
- 110.9 PRACTICAL REFUSAL TO DCP/ELEVATION (m)
- DRILLED WELL LOCATION
- F.F. FINISHED FLOOR LEVEL
- STORM SEWER LINE
- LIMIT OF PHASE 1 WORK AREA

REFERENCES:

BASE PLAN AND EXISTING TOPOGRAPHIC INFORMATION PROVIDED BY OTHERS
 THIS PLAN PROVIDES DETAILS OF THE PROPOSED SEWAGE SYSTEM. REFER TO DRAWINGS C101 AND C102 BY MCFOSH PERRY FOR DETAILS OF THE PROPOSED SITE GRADING AND SERVING.

TYPICAL FORECMAIN TRENCH DETAIL
 SCALE - N.T.S.



2434894 ONTARIO INC.
 C/O BBS CONSTRUCTION (ONTARIO) INC.



PROPOSED WAREHOUSE DEVELOPMENT
 210 & 220 MAPLE CREEK COURT
 OTTAWA, ONTARIO

SEWAGE SYSTEM LAYOUT PLAN & DETAILS

PROJECT NO.	DRAWING NO.	REVISION NO.
PH3158	SS1	0

APPENDIX D: PRE-DEVELOPEMENT PLAN

FILENAME: I:\01 Project - Proposals\2015\0429 BBS_Site Plan_210 Maple Creek Court\015 - Drawings\DCP-15-0429 - PRESENTATION.dwg
 LAST SAVE: Monday, December 02, 2019 1:45:42 PM
 LAST PLOTTED: Monday, December 02, 2019 1:45:42 PM



LEGEND

AREA	A1	2.10	AREA SIZE (HECTARES)	
		ha		
		0.20		5-YR RUNOFF COEFFICIENT
		0.25		

No.	Revision/Issue	Date
04	REVISED PER CITY COMMENTS	DEC 4, 2019
03	ISSUED FOR CITY REVIEW	FEB 5, 2018
02	REVISED PER CITY COMMENTS	JAN 26, 2018
01	ISSUED FOR SITE PLAN CONTROL	JAN 20, 2017

Check and verify all dimensions before proceeding with the work. Do not scale drawings

McINTOSH PERRY
 115 Walgreen Road, RR3, Carp, ON K0A 1L0
 Tel: 613-836-2184 Fax: 613-836-3742
 www.mcintoshperry.com

	Stamp:




Client:
BBS CONSTRUCTION (ONTARIO) LTD.
 1805 WOODWARD DRIVE P: 613-226-8830
 OTTAWA ON, K2C 0P9 F: 613-226-7709

Project:
 210/220 MAPLE CREEK COURT
**WALL SOUND
 PROPOSED WAREHOUSE DEVELOPMENT**
 OTTAWA ONTARIO

Drawing Title:
PRE-DEVELOPMENT DRAINAGE PLAN

Scale: N.T.S.	Project Number: CP-15-0429
Drawn by: SVL/PGK	Drawing Number: PRE
Checked By: RPK/CJM	
Designed By: SVL/PGK	SHEET 1 of 1
Date: NOV 25, 2016	


APPENDIX E: POST-DEVELOPMENT PLAN



No.	Revision/Issue	Date
04	REVISED PER CITY COMMENTS	DEC 4, 2019
03	ISSUED FOR CITY REVIEW	FEB 5, 2018
02	REVISED PER CITY COMMENTS	JAN 26, 2018
01	ISSUED FOR SITE PLAN CONTROL	JAN 20, 2017

Check and verify all dimensions before proceeding with the work. Do not scale drawings.

McINTOSH PERRY
 115 Walgreen Road, RR3, Carp, ON K0A 1L0
 Tel: 613-836-2184 Fax: 613-836-3742
 www.mcintoshperry.com



Client:
BBS CONSTRUCTION (ONTARIO) LTD.
 1805 WOODWARD DRIVE P: 613-226-8830
 OTTAWA ON, K2C 0P9 F: 613-226-7709

Project:
 210/220 MAPLE CREEK COURT
**WALL SOUND
 PROPOSED WAREHOUSE DEVELOPMENT**
 OTTAWA ONTARIO

Drawing Title:
POST-DEVELOPMENT DRAINAGE PLAN

Scale: N.T.S.	Project Number: CP-15-0429
Drawn by: SVL/PKG	
Checked by: RPK/CJM	
Designed by: SVL/PKG	Drawing Number:
Date: NOV 25, 2016	SHEET 1 of 1

POST

FILENAME: I:\01 Project - Proposals\2015\Indy\CP-15-0429 BBS_Site Plan_210 Maple Creek Court\015 - Drawings\015-0429 PRESENTATION.dwg
 LAST SAVE: Monday, December 02, 2019 1:51:45 PM
 LAST PLOTTED: Monday, December 02, 2019 1:51:45 PM
 PLOTTED BY: SVL

APPENDIX F: STORMWATER CALCULATIONS

AVERAGE PRE-DEVELOPMENT RUNOFF COEFFICIENT CALCULATIONS

Area A1		210 MAPLE CREEK - NORTH SIDE			
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
GRAVEL	0.60	0.75	0.0	0.0	0.0
GRASS	0.20	0.25	9183.0	1836.6	2295.8
Avg C	0.20	0.25			

Area A2		220 MAPLE CREEK - SOUTH SIDE			
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
GRAVEL	0.60	0.75	1816.3	1089.8	1362.2
GRASS	0.20	0.25	10538.7	2107.7	2634.7
Avg C	0.26	0.32			

Area A3		220 MAPLE CREEK - SOUTH SIDE			
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
GRAVEL	0.60	0.75	0.0	0.0	0.0
GRASS	0.20	0.25	12955.0	2591.0	3238.8
Avg C	0.20	0.25			

AVERAGE POST-DEVELOPMENT RUNOFF COEFFICIENT CALCULATIONS

Area B1		NORTH WEST CORNER OF DEVELOPMENT AREA			
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
ASPHALT	0.90	1.00	2766.0	2489.4	2766.0
BUILDING	0.90	1.00	217.4	195.7	217.4
CONCRETE	0.90	1.00	318.4	286.5	318.4
GRASS	0.20	0.25	1771.9	354.4	443.0
Avg C	0.66	0.74			

Area B2		SOUTH WEST CORNER OF DEVELOPMENT AREA			
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
ASPHALT	0.90	1.00	2598.4	2338.6	2598.4
BUILDING	0.90	1.00	2783.1	2504.8	2783.1
GRASS	0.20	0.25	1769.7	353.9	442.4
Avg C	0.73	0.81			

Area B3		SOUTH SIDE OF PROPERTY DEVELOPMENT			
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
ASPHALT	0.90	1.00	1717.7	1546.0	1717.7
BUILDING	0.90	1.00	926.7	834.0	926.7
GRASS	0.20	0.25	3186.8	637.4	796.7
Avg C	0.52	0.59			

Area B4		CENTRAL AREA OF BUILDINGS			
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
ASPHALT	0.90	1.00	1688.5	1519.6	1688.5
CONCRETE	0.90	1.00	348.5	313.7	348.5
GRASS	0.20	0.25	295.0	59.0	73.8
Avg C	0.81	0.91			

Area B5		BETWEEN BUILDINGS			
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
ASPHALT	0.90	1.00	1421.1	1278.9	1421.1
BUILDING	0.90	1.00	487.7	438.9	487.7
GRASS	0.20	0.25	1702.5	340.5	425.6
Avg C	0.57	0.65			

Area B6		PHASE 4 BUILDING AREA			
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
ASPHALT	0.90	1.00	430.5	387.5	430.5
BUILDING	0.90	1.00	706.8	636.1	706.8
Avg C	0.90	1.00			

Area B7		SOUTHEAST HALF OF PHASE 3 BUILDING			
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
ASPHALT	0.90	1.00	207.1	186.4	207.1
BUILDING	0.90	1.00	340.7	306.6	340.7
Avg C	0.90	1.00			

Area B8					
NORTHEAST HALF OF PHASE 3 BUILDING					
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
ASPHALT	0.90	1.00	249.6	224.6	249.6
BUILDING	0.90	1.00	620.7	558.6	620.7
GRASS	0.20	0.25	36.9	7.4	9.2
Avg C	0.87	0.97			

Area B9					
NORTH EAST CORNER OF DEVELOPMENT AREA					
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
ASPHALT/BUILDING	0.90	1.00	2114.4	1903.0	2114.4
GRASS	0.20	0.25	1657.4	331.5	414.3
Avg C	0.59	0.67			

Area B10					
SOUTH EAST SIDE OF DEVELOPMENT AREA					
Type	C (5-yr)	C (100-yr)	Area (m ²)	Product (5-yr)	Product (100-yr)
GRASS	0.20	0.25	4127.8	825.6	1031.9
Avg C	0.20	0.25			

Time of concentration (min.)	25mm EVENT (mm/hr)	5-Year (mm/hr)	100-Year (mm/hr)	
20.00	15.4	70.3	120.0	PRE-DEVELOPMENT
10.00	32.0	104.2	178.6	POST-DEVELOPMENT

PRE-DEVELOPMENT RUNOFF COEFFICIENT CALCULATIONS

Basin	Drainage Area (ha)	Balanced Runoff Coefficient (C) 5-yr	Balanced Runoff Coefficient (C) 100-yr	5-Year Flow Rate (l/s)	100-Year Flow Rate (l/s)
A1	0.92	0.20	0.25	35.9	76.6
A2	1.24	0.26	0.32	62.7	131.8
A3	1.30	0.20	0.25	50.6	108.0
Total	3.45	0.22	0.26	149.2	316.4

POST-DEVELOPMENT RUNOFF COEFFICIENT CALCULATIONS

Basin	Drainage Area (ha)	Balanced Runoff Coefficient (C) 5-yr	Balanced Runoff Coefficient (C) 100-yr	5-Year Flow Rate (l/s)	100-Year Flow Rate (l/s)
B1	0.51	0.66	0.74	97.0	186.4
B2	0.72	0.73	0.81	151.2	287.5
B3	0.58	0.52	0.59	87.8	170.8
B4	0.23	0.81	0.91	54.7	105.3
B5	0.36	0.57	0.65	59.6	116.5
B6	0.11	0.90	1.00	29.6	56.5
B7	0.05	0.90	1.00	14.3	27.2
B8	0.09	0.87	0.97	22.9	43.7
B9	0.38	0.59	0.67	64.5	125.4
B10	0.41	0.20	0.25	23.9	51.2
Total	3.45	0.61	0.68	605.5	1170.5

QUALITY CONTROL CALCULATIONS (MOECC EQUATION 4.9)

Basin	Drainage Area (ha)	Balanced Runoff Coefficient (C)	5-Year Flow Rate (l/s)
B1	0.51	0.66	29.8
B2	0.72	0.73	46.4
B3	0.58	0.52	26.9
B4	0.23	0.81	16.8
B5	0.36	0.57	18.3
B6	0.11	0.90	9.1
B7	0.05	0.90	4.4
B8	0.09	0.87	7.0
B9	0.38	0.59	19.8
B10	0.41	0.20	7.3
Total	3.45	0.61	185.8

STORM SEWER DESIGN SHEET

PROJECT: Maple Creek Court
 LOCATION: Ottawa
 CLIENT: BBS Construction
 PAGE: 3 OF 3



LOCATION				CONTRIBUTING AREA (ha)								RATIONAL DESIGN FLOW										SEWER DATA								
1	2	3	4	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32
STREET	AREA ID	FROM MH	TO MH	C-VALUE	AREA	INDIV AC	CUMUL AC	INLET (min)	TIME IN PIPE	TOTAL (min)	i (5) (mm/hr)	i (10) (mm/hr)	i (100) (mm/hr)	5yr PEAK FLOW (L/s)	10yr PEAK FLOW (L/s)	100yr PEAK FLOW (L/s)	FIXED FLOW (L/s)	DESIGN FLOW (L/s)	CAPACITY (L/s)	LENGTH (m)	PIPE SIZE (mm)			SLOPE (%)	VELOCITY (m/s)	AVAIL CAP (5yr/100YR)				
																					DIA	W	H			(L/s)	(%)			
	B9	LCSB#11	CBMH#10	0.59	0.38	0.22	0.22	10.00	0.19	10.19	104.19	122.14	178.56	64.46				64.46	74.70	16.63	250					1.45	1.474	10.25	13.72%	
	B6	CBMH#10	CBMH#7	1.00	0.11		0.22	10.19	0.16	10.34	103.21	120.98	176.86	63.85				56.45	120.31	162.91	9.29	450				0.30	0.992	42.61	26.15%	
	B8	CB#9	CBMH#8	0.97	0.09			10.00	0.15	10.15	104.19	122.14	178.56					43.68	43.68	78.14	9.46	300				0.60	1.071	34.46	44.10%	
	B7	CBMH#8	CBMH#7	1.00	0.05			10.15	0.81	10.95	103.42	121.23	177.22					70.87	70.87	122.70	52.01	375				0.45	1.076	51.83	42.24%	
	B5	CBMH#7	LSCB#6	0.57	0.36	0.21	0.43	10.95	0.37	11.32	99.42	116.52	170.30	118.39				127.33	245.72	283.76	27.89	525				0.40	1.270	38.03	13.40%	
		LSCB#6	LSCB#5			0.00	0.43	11.32	0.31	11.63	97.71	114.50	167.34	116.36				127.33	243.69	283.76	23.49	525				0.40	1.270	40.07	14.12%	
	B4	LSCB#5	LSCB#4	0.81	0.23	0.19	0.62	11.63	0.32	11.95	96.32	112.87	164.94	165.28				127.33	292.61	347.53	29.99	525				0.60	1.555	54.92	15.80%	
		LSCB#4	CBMH#3		0.06	0.03	0.65	11.95	0.45	12.40	94.92	111.22	162.51	171.11				127.33	298.44	350.85	32.72	600				0.30	1.202	52.41	14.94%	
	B3	CBMH#3	CBMH#2	0.52	0.52	0.27	0.92	12.40	1.27	13.68	93.01	108.98	159.22	238.02				127.33	365.35	480.32	99.47	675				0.30	1.300	114.97	23.94%	
	B2	CBMH#2	LSCB#1	0.73	0.72	0.52	1.44	13.68	0.43	14.11	88.09	103.18	150.72	353.26				127.33	480.59	636.13	36.34	750				0.30	1.395	155.54	24.45%	
	B1	LSCB#12	TEE	0.66	0.51	0.33	0.33	10.00	0.06	10.06	104.19	122.14	178.56	97.00					97.00	133.02	2.88	450				0.20	0.810	36.02	27.08%	
		LSCB#1	STC			0.00	1.78	18.31	0.04	18.35	74.19	86.84	126.74	366.58				127.33	493.91	1,780.41	9.00	750				2.35	3.904	1286.50	72.26%	
		STC	Ex. DITCH			0.00	1.78	18.35	0.09	18.44	74.09	86.73	126.57	366.11				127.33	493.44	636.13	7.70	750				0.30	1.395	142.69	22.43%	

Definitions:
 Q = 2.78CIA, where:
 Q = Peak Flow in Litres per Second (L/s)
 A = Area in Hectares (ha)
 i = Rainfall intensity in millimeters per hour (mm/hr)
 [i = 998.071 / (TC+6.053)^0.814] 5 YEAR
 [i = 1174.184 / (TC+6.014)^0.816] 10 YEAR
 [i = 1735.688 / (TC+6.014)^0.820] 100 YEAR

Notes:
 1. Mannings coefficient (n) = 0.013
 2. Areas B6/B7/B8 are accounted for by the 100-year flow

Designed: SVL/PGK
 Checked: RPK
 Project No.: CP-15-0429

No.	Revision	Date
1.	ISSUED FOR SITE PLAN CONTROL	20/01/2017
2.	REVISED PER CITY COMMENTS	26/01/2018
3.	ISSUED FOR CITY REVIEW	05/02/2018
4.	REVISED PER CITY COMMENTS	21/06/2019

Date: 2019-12-02
 Sheet No: 3 of 3

SOAKAWAY PIT SIZING

Soakaway Pit Sizing as per TRCA/CVC LID Planning and Design Guide (2010)

Maximum allowable depth:

Equation;

$$d_{r\ max} = \frac{i \times t_s}{V_r}$$

where;

i = infiltration rate for native soils (mm/hr)

t_s = time to drain (24 to 48 hours)

V_r = void space ratio for aggregate used

d_{r max} = maximum stone reservoir depth (mm)

Value
30 mm/hr
48 hours
0.40

$$d_{r\ max} = \underline{\underline{3.60\ m}}$$

Minimum Footprint Surface Area:

Equation;

$$A_{f\ min} = \frac{WQV}{(d_r \times V_r)}$$

where;

WQV = water quality volume (m³)

d_r = stone reservoir depth (m)

V_r = void space ratio for aggregate used

A_f = Footprint surface area (m²)

Value	
120.75 m ³	As per Table 3.2 MOE Stormwater Management Planning and Design Manual (2003)
2.75 m	
0.40	

$$A_{f\ min} = \underline{\underline{109.77\ m^2}}$$

Stone Reservoir Depth (d_r)

Top of Trench (Maximum):	113.85 m
Bottom of Trench (Maximum):	111.10 m
Depth of Sand Filter :	0 m
Depth of Infiltration Trench :	2.75 m

SOAKAWAY PIT INFILTRATION CALCULATION

Volume Required to be Infiltrated

Required Infiltration Rate:	104 mm/yr	(Moderate Recharge Area per Figure 9.3 - Carp River Watershed / Subwatershed Study)
Site Area:	3.45 ha	
Required Infiltration:	3,588 m ³ /yr	(Required Infiltration X Site Area)
Post-Dev Pervious Area:	1.45 ha	
Infiltration in Pervious Area:	1,513 m ³ /yr	
Infiltration needed in Basin:	2,075 m ³ /yr	

Annual Rainfall Data (Up to 10mm Storm Event)

Number of events/yr 6mm<x<10mm:	22
Average Days Between Events:	13.9
Average Depth 6mm<x<10mm:	7.75 mm
Area B1-B9:	25,290 m ²
Cummulative Rainfall Depth 6mm<x<10mm:	170.5 mm
Volume of Runoff per year to Infiltrated:	4,312 m ³ /yr

Requried Storage Volume (10mm Event)

Required Storage Volume:	252.90 m ³	Infiltration Bed Area x 10mm
Assumed Porosity (n):	40%	
Clearstone Volume:	632.24 m ³	Storage Volume/n

Infiltration Trench Volume

Depth:	2.75 m
Area:	229.91 m ²
Volume:	632.24 m ³

Infiltration Rate Through Soil

Percolation Rate:	50.0 mm/hr	
Percolation Rate:	25.0 mm/hr	Applied Safety Factor of 2
Infiltration Rate:	1.60 L/s	Percolation Rate x Area of Trench

Retention Time Average (8 mm event)

Volume of Water during the 12mm event:	196.00 m ³	
Volume of Pit Occupied:	435.54 m ³	
Depth:	1.89 m	
Time:	34 hr	Volume / Infiltration Rate
	1.4 days	

Retention Time (10 mm event)

Volume of Water:	252.90 m ³	
Time:	44 hr	Volume / Infiltration Rate
	1.8 days	

Sean Leflar

From: Brandon O'Leary <Brandon.OLeary@forterrabp.com>
Sent: January 4, 2018 1:52 PM
To: Sean Leflar
Subject: RE: 210/220 Maple Creek Court, Carp, ON - Quality Treatment Unit Sizing
Attachments: 010418 Stormceptor STC Sizing Report, 210-220 Maple Creek Crt, Carp, McIntosh Perry, Sean Leflar.pdf

Hello Sean,

Attached is the requested Stormceptor STC sizing report. Based on the site parameters that you have provided below, a STC-4000 is required. The cost of this unit is \$41,870. The treatment flow rate for this unit is 50 L/s, the oil capacity is 3360 L, the sediment capacity is 3038 L, and the total volume of the unit is 20,255 L.

If you have any questions, please feel free to contact me.

Regards

Brandon O'Leary, EIT, B.A.Sc.
Stormwater Specialist
Cambridge Plant
Cell (905) 630-0359



Stormceptor

Protecting the water for future generations

From: Sean Leflar [mailto:s.leflar@mcintoshperry.com]
Sent: Thursday, January 04, 2018 11:48 AM
To: Brandon O'Leary <Brandon.OLeary@forterrabp.com>
Subject: 210/220 Maple Creek Court, Carp, ON - Quality Treatment Unit Sizing

Good Afternoon,

I originally sent this email to Hal Stratford on December 20th and got a automatic reply that he was retiring that week. I did not know if the request got passed down . If you already have received this request, please disregard this email. If not, I would appreciate your assistance.

We are working on a development located at 210/220 Maple Creek Court that is going to require stormwater quality control. The Mississippi Valley Conservation Authority has stipulated 80% TSS removal, there is limited room on the site during phase 1 of the construction for treatment using natural features therefore we will need a Quality treatment unit. Please find below site parameters for the sizing of the unit.

OSR Unit: Areas B1-9

Site Parameters:

Location: 210/220 Maple Creek Court, Carp, ON
Total Site Area: ±3.12 ha
% Impervious: 49%

Need 80% TSS

Site Flows:

Flow (100yr Storm) = 745.8 L/s

Flow (5yr Storm) = 387.3 L/s

C Value = 0.62

We Will Require:

- The units treatment flow rate
- Oil Capacity
- Sediment Capacity
- Total Holding Capacity
- Cost Estimate

If you require clarification or any additional information, please feel free to get in contact.

Thank you,

Sean Leflar,

Civil Engineering Technologist | Land Development

115 Walgreen Road, R.R. 3, Carp, ON K0A 1L0

T. 613.836.2184 (ext 2252) | F. 613.836.3742

s.leflar@mcintoshperry.com | www.mcintoshperry.com

McINTOSH PERRY

Confidentiality Notice – If this email was not intended for you, please delete it. Click [here](#) to read all of the legal language around this concept.

Detailed Stormceptor Sizing Report – 210/220 Maple Creek Crt.

Project Information & Location			
Project Name	210/220 Maple Creek Crt,	Project Number	5738
City	Carp	State/ Province	Ontario
Country	Canada	Date	1/4/2018
Designer Information		EOR Information (optional)	
Name	Brandon O'Leary	Name	Sean Leflar
Company	Forterra	Company	McIntosh Perry
Phone #	905-630-0359	Phone #	
Email	brandon.oleary@forterrabp.com	Email	

Stormwater Treatment Recommendation

The recommended Stormceptor Model(s) which achieve or exceed the user defined water quality objective for each site within the project are listed in the below Sizing Summary table.

Site Name	210/220 Maple Creek Crt.
Recommended Stormceptor Model	STC 4000
Target TSS Removal (%)	80.0
TSS Removal (%) Provided	80
PSD	Fine Distribution
Rainfall Station	OTTAWA MACDONALD-CARTIER INT'L A

The recommended Stormceptor model achieves the water quality objectives based on the selected inputs, historical rainfall records and selected particle size distribution.

Stormceptor Sizing Summary		
Stormceptor Model	% TSS Removal Provided	% Runoff Volume Captured Provided
STC 300	57	62
STC 750	69	79
STC 1000	70	79
STC 1500	71	79
STC 2000	75	88
STC 3000	76	88
STC 4000	80	93
STC 5000	81	93
STC 6000	83	96
STC 9000	87	98
STC 10000	87	98
STC 14000	89	99
StormceptorMAX	Custom	Custom

Stormceptor

The Stormceptor oil and sediment separator is sized to treat stormwater runoff by removing pollutants through gravity separation and flotation. Stormceptor’s patented design generates positive TSS removal for each rainfall event, including large storms. Significant levels of pollutants such as heavy metals, free oils and nutrients are prevented from entering natural water resources and the re-suspension of previously captured sediment (scour) does not occur.

Stormceptor provides a high level of TSS removal for small frequent storm events that represent the majority of annual rainfall volume and pollutant load. Positive treatment continues for large infrequent events, however, such events have little impact on the average annual TSS removal as they represent a small percentage of the total runoff volume and pollutant load.

Design Methodology

Stormceptor is sized using PCSWMM for Stormceptor, a continuous simulation model based on US EPA SWMM. The program calculates hydrology using local historical rainfall data and specified site parameters. With US EPA SWMM’s precision, every Stormceptor unit is designed to achieve a defined water quality objective. The TSS removal data presented follows US EPA guidelines to reduce the average annual TSS load. The Stormceptor’s unit process for TSS removal is settling. The settling model calculates TSS removal by analyzing:

- Site parameters
- Continuous historical rainfall data, including duration, distribution, peaks & inter-event dry periods
- Particle size distribution, and associated settling velocities (Stokes Law, corrected for drag)
- TSS load
- Detention time of the system

Hydrology Analysis	
PCSWMM for Stormceptor calculates annual hydrology with the US EPA SWMM and local continuous historical rainfall data. Performance calculations of Stormceptor are based on the average annual removal of TSS for the selected site parameters. The Stormceptor is engineered to capture sediment particles by treating the required average annual runoff volume, ensuring positive removal efficiency is maintained during each rainfall event, and preventing negative removal efficiency (scour). Smaller recurring storms account for the majority of rainfall events and average annual runoff volume, as observed in the historical rainfall data analyses presented in this section.	

Rainfall Station			
State/Province	Ontario	Total Number of Rainfall Events	4819
Rainfall Station Name	OTTAWA MACDONALD-CARTIER INT'L A	Total Rainfall (mm)	20978.1
Station ID #	6000	Average Annual Rainfall (mm)	567.0
Coordinates	45°19'N, 75°40'W	Total Evaporation (mm)	1727.3
Elevation (ft)	370	Total Infiltration (mm)	10672.2
Years of Rainfall Data	37	Total Rainfall that is Runoff (mm)	8578.6

Notes	
<ul style="list-style-type: none"> • Stormceptor performance estimates are based on simulations using PCSWMM for Stormceptor, which uses the EPA Rainfall and Runoff modules. • Design estimates listed are only representative of specific project requirements based on total suspended solids (TSS) removal defined by the selected PSD, and based on stable site conditions only, after construction is completed. • For submerged applications or sites specific to spill control, please contact your local Stormceptor representative for further design assistance. 	

Drainage Area	
Total Area (ha)	3.12
Imperviousness %	49

Up Stream Storage	
Storage (ha-m)	Discharge (cms)
0.000	0.000

Water Quality Objective	
TSS Removal (%)	80.0
Runoff Volume Capture (%)	90.00
Oil Spill Capture Volume (L)	
Peak Conveyed Flow Rate (L/s)	745.80
Water Quality Flow Rate (L/s)	387.30

Up Stream Flow Diversion	
Max. Flow to Stormceptor (cms)	0.00000

Design Details	
Stormceptor Inlet Invert Elev (m)	
Stormceptor Outlet Invert Elev (m)	
Stormceptor Rim Elev (m)	
Normal Water Level Elevation (m)	
Pipe Diameter (mm)	
Pipe Material	
Multiple Inlets (Y/N)	No
Grate Inlet (Y/N)	No

Particle Size Distribution (PSD)		
<p>Removing the smallest fraction of particulates from runoff ensures the majority of pollutants, such as metals, hydrocarbons and nutrients are captured. The table below identifies the Particle Size Distribution (PSD) that was selected to define TSS removal for the Stormceptor design.</p>		
Fine Distribution		
Particle Diameter (microns)	Distribution %	Specific Gravity
20.0	20.0	1.30
60.0	20.0	1.80
150.0	20.0	2.20
400.0	20.0	2.65
2000.0	20.0	2.65

Site Name	210/220 Maple Creek Crt.
------------------	--------------------------

Site Details

Drainage Area	
Total Area (ha)	3.12
Imperviousness %	49

Surface Characteristics	
Width (m)	353.00
Slope %	2
Impervious Depression Storage (mm)	1.57
Pervious Depression Storage (mm)	4.67
Impervious Manning's n	0.015
Pervious Manning's n	0.25

Maintenance Frequency	
Maintenance Frequency (months) >	12

Infiltration Parameters	
Horton's equation is used to estimate infiltration	
Max. Infiltration Rate (mm/hr)	76.2
Min. Infiltration Rate (mm/hr)	13.2
Decay Rate (1/sec)	0.00115
Regeneration Rate (1/sec)	0.01

Evaporation	
Daily Evaporation Rate (mm/day)	2.54

Dry Weather Flow	
Dry Weather Flow (Ips)	0

Winter Months	
Winter Infiltration	0

TSS Loading Parameters

TSS Loading Function	Build Up/ Wash-off
----------------------	--------------------


Buildup/Wash-off Parameters	
Target Event Mean Conc. (EMC) mg/L	125
Exponential Buildup Power	0.40
Exponential Washoff Exponent	0.20

TSS Availability Parameters	
Availability Constant A	0.057
Availability Factor B	0.04
Availability Exponent C	1.10
Min. Particle Size Affected by Availability (micron)	400


Cumulative Runoff Volume by Runoff Rate			
Runoff Rate (L/s)	Runoff Volume (m³)	Volume Over (m³)	Cumulative Runoff Volume (%)
1	36291	233571	13.4
4	105156	164736	39.0
9	166581	103358	61.7
16	205981	63888	76.3
25	228882	40997	84.8
36	242613	27247	89.9
49	251759	18105	93.3
64	257716	12143	95.5
81	261724	8136	97.0
100	264449	5409	98.0
121	266271	3587	98.7
144	267642	2215	99.2
169	268574	1284	99.5
196	269131	727	99.7
225	269492	365	99.9
256	269687	171	99.9
289	269792	65	100.0

Cumulative Runoff Volume by Runoff Rate

For area: 3.12(ha), imperviousness: 49.0%, rainfall station: OTTAWA MACDONALD-CARTIER INT'L A



Rainfall Event Analysis				
Rainfall Depth (mm)	No. of Events	Percentage of Total Events (%)	Total Volume (mm)	Percentage of Annual Volume (%)
6.35	3843	79.7	5885	28.1
12.70	520	10.8	4643	22.1
19.05	225	4.7	3470	16.5
25.40	98	2.0	2144	10.2
31.75	58	1.2	1639	7.8
38.10	32	0.7	1118	5.3
44.45	24	0.5	996	4.7
50.80	9	0.2	416	2.0
57.15	5	0.1	272	1.3
63.50	1	0.0	63	0.3
69.85	1	0.0	64	0.3
76.20	1	0.0	76	0.4
82.55	0	0.0	0	0.0
88.90	1	0.0	84	0.4
95.25	0	0.0	0	0.0
101.60	0	0.0	0	0.0
107.95	0	0.0	0	0.0
114.30	1	0.0	109	0.5
120.65	0	0.0	0	0.0
127.00	0	0.0	0	0.0



For Stormceptor Specifications and Drawings Please Visit:
<http://www.imbriumsystems.com/technical-specifications>

APPENDIX G: CITY OF OTTAWA DESIGN CHECKLIST

City of Ottawa

4. Development Servicing Study Checklist

The following section describes the checklist of the required content of servicing studies. It is expected that the proponent will address each one of the following items for the study to be deemed complete and ready for review by City of Ottawa Infrastructure Approvals staff.

The level of required detail in the Servicing Study will increase depending on the type of application. For example, for Official Plan amendments and re-zoning applications, the main issues will be to determine the capacity requirements for the proposed change in land use and confirm this against the existing capacity constraint, and to define the solutions, phasing of works and the financing of works to address the capacity constraint. For subdivisions and site plans, the above will be required with additional detailed information supporting the servicing within the development boundary.

4.1 General Content

Criteria	Location (if applicable)
<input type="checkbox"/> Executive Summary (for larger reports only).	N/A
<input type="checkbox"/> Date and revision number of the report.	On Cover
<input type="checkbox"/> Location map and plan showing municipal address, boundary, and layout of proposed development.	Appendix 'E'
<input type="checkbox"/> Plan showing the site and location of all existing services.	Site Servicing and Utility Plan
<input type="checkbox"/> Development statistics, land use, density, adherence to zoning and official plan, and reference to applicable subwatershed and watershed plans that provide context to which individual developments must adhere.	1.1 Purpose 1.2 Site Description 6.0 Stormwater Management
<input type="checkbox"/> Summary of Pre-consultation Meetings with City and other approval agencies.	Appendix 'A'
<input type="checkbox"/> Reference and confirm conformance to higher level studies and reports (Master Servicing Studies, Environmental Assessments, Community Design Plans), or in the case where it is not in conformance, the proponent must provide justification and develop a defensible design criteria.	1.1 Purpose 1.2 Site Description 6.0 Stormwater Management

<input type="checkbox"/> Statement of objectives and servicing criteria.	3.0 Pre-Consultation Summary
<input type="checkbox"/> Identification of existing and proposed infrastructure available in the immediate area.	N/A
<input type="checkbox"/> Identification of Environmentally Significant Areas, watercourses and Municipal Drains potentially impacted by the proposed development (Reference can be made to the Natural Heritage Studies, if available).	Lot Grading, Drainage Plan, Sediment and Erosion Control Plan
<input type="checkbox"/> Concept level master grading plan to confirm existing and proposed grades in the development. This is required to confirm the feasibility of proposed stormwater management and drainage, soil removal and fill constraints, and potential impacts to neighbouring properties. This is also required to confirm that the proposed grading will not impede existing major system flow paths.	Lot Grading, Drainage Plan, Sediment and Erosion Control Plan
<input type="checkbox"/> Identification of potential impacts of proposed piped services on private services (such as wells and septic fields on adjacent lands) and mitigation required to address potential impacts.	N/A
<input type="checkbox"/> Proposed phasing of the development, if applicable.	N/A
<input type="checkbox"/> Reference to geotechnical studies and recommendations concerning servicing.	See Geotech
<input type="checkbox"/> All preliminary and formal site plan submissions should have the following information: <ul style="list-style-type: none"> ○ Metric scale ○ North arrow (including construction North) ○ Key plan ○ Name and contact information of applicant and property owner ○ Property limits including bearings and dimensions ○ Existing and proposed structures and parking areas ○ Easements, road widening and rights-of-way ○ Adjacent street names 	Lot Grading, Drainage Plan, Sediment and Erosion Control Plan

4.2 Development Servicing Report: Water

Criteria	Location (if applicable)
<input type="checkbox"/> Confirm consistency with Master Servicing Study, if available	N/A
<input type="checkbox"/> Availability of public infrastructure to service proposed development	N/A
<input type="checkbox"/> Identification of system constraints	N/A
<input type="checkbox"/> Identify boundary conditions	N/A
<input type="checkbox"/> Confirmation of adequate domestic supply and pressure	N/A
<input type="checkbox"/> Confirmation of adequate fire flow protection and confirmation that fire flow is calculated as per the Fire Underwriter's Survey. Output should show available fire flow at locations throughout the development.	Appendix 'B'
<input type="checkbox"/> Provide a check of high pressures. If pressure is found to be high, an assessment is required to confirm the application of pressure reducing valves.	N/A
<input type="checkbox"/> Definition of phasing constraints. Hydraulic modeling is required to confirm servicing for all defined phases of the project including the ultimate design	N/A
<input type="checkbox"/> Address reliability requirements such as appropriate location of shut-off valves	N/A
<input type="checkbox"/> Check on the necessity of a pressure zone boundary modification.	N/A
<input type="checkbox"/> Reference to water supply analysis to show that major infrastructure is capable of delivering sufficient water for the proposed land use. This includes data that shows that the expected demands under average day, peak hour and fire flow conditions provide water within the required pressure range	N/A

<input type="checkbox"/> Description of the proposed water distribution network, including locations of proposed connections to the existing system, provisions for necessary looping, and appurtenances (valves, pressure reducing valves, valve chambers, and fire hydrants) including special metering provisions.	N/A
<input type="checkbox"/> Description of off-site required feeder mains, booster pumping stations, and other water infrastructure that will be ultimately required to service proposed development, including financing, interim facilities, and timing of implementation.	N/A
<input type="checkbox"/> Confirmation that water demands are calculated based on the City of Ottawa Design Guidelines.	Appendix 'B'
<input type="checkbox"/> Provision of a model schematic showing the boundary conditions locations, streets, parcels, and building locations for reference.	N/A

4.3 Development Servicing Report: Wastewater

Criteria	Location (if applicable)
<input type="checkbox"/> Summary of proposed design criteria (Note: Wet-weather flow criteria should not deviate from the City of Ottawa Sewer Design Guidelines. Monitored flow data from relatively new infrastructure cannot be used to justify capacity requirements for proposed infrastructure).	N/A
<input type="checkbox"/> Confirm consistency with Master Servicing Study and/or justifications for deviations.	N/A
<input type="checkbox"/> Consideration of local conditions that may contribute to extraneous flows that are higher than the recommended flows in the guidelines. This includes groundwater and soil conditions, and age and condition of sewers.	N/A
<input type="checkbox"/> Description of existing sanitary sewer available for discharge of wastewater from proposed development.	5.2 Sanitary Servicing

<input type="checkbox"/> Verify available capacity in downstream sanitary sewer and/or identification of upgrades necessary to service the proposed development. (Reference can be made to previously completed Master Servicing Study if applicable)	N/A
<input type="checkbox"/> Calculations related to dry-weather and wet-weather flow rates from the development in standard MOE sanitary sewer design table (Appendix 'C') format.	N/A
<input type="checkbox"/> Description of proposed sewer network including sewers, pumping stations, and forcemains.	5.2 Sanitary Servicing
<input type="checkbox"/> Discussion of previously identified environmental constraints and impact on servicing (environmental constraints are related to limitations imposed on the development in order to preserve the physical condition of watercourses, vegetation, soil cover, as well as protecting against water quantity and quality).	N/A
<input type="checkbox"/> Pumping stations: impacts of proposed development on existing pumping stations or requirements for new pumping station to service development.	N/A
<input type="checkbox"/> Forcemain capacity in terms of operational redundancy, surge pressure and maximum flow velocity.	N/A
<input type="checkbox"/> Identification and implementation of the emergency overflow from sanitary pumping stations in relation to the hydraulic grade line to protect against basement flooding.	N/A
<input type="checkbox"/> Special considerations such as contamination, corrosive environment etc.	N/A

4.4 Development Servicing Report: Stormwater Checklist

Criteria	Location (if applicable)
<input type="checkbox"/> Description of drainage outlets and downstream constraints including legality of outlets (i.e. municipal drain, right-of-way, watercourse, or private property)	6.0 Stormwater Management
<input type="checkbox"/> Analysis of available capacity in existing public infrastructure.	N/A
<input type="checkbox"/> A drawing showing the subject lands, its surroundings, the receiving watercourse, existing drainage patterns, and proposed drainage pattern.	Pre- and Post-Development Plans
<input type="checkbox"/> Water quantity control objective (e.g. controlling post-development peak flows to pre-development level for storm events ranging from the 2 or 5 year event (dependent on the receiving sewer design) to 100 year return period); if other objectives are being applied, a rationale must be included with reference to hydrologic analyses of the potentially affected subwatersheds, taking into account long-term cumulative effects.	6.0 Stormwater Management
<input type="checkbox"/> Water Quality control objective (basic, normal or enhanced level of protection based on the sensitivities of the receiving watercourse) and storage requirements.	6.0 Stormwater Management
<input type="checkbox"/> Description of the stormwater management concept with facility locations and descriptions with references and supporting information.	6.0 Stormwater Management
<input type="checkbox"/> Set-back from private sewage disposal systems.	N/A
<input type="checkbox"/> Watercourse and hazard lands setbacks.	N/A
<input type="checkbox"/> Record of pre-consultation with the Ontario Ministry of Environment and the Conservation Authority that has jurisdiction on the affected watershed.	N/A
<input type="checkbox"/> Confirm consistency with sub-watershed and Master Servicing Study, if applicable study exists.	N/A

<input type="checkbox"/> Storage requirements (complete with calculations) and conveyance capacity for minor events (1:5 year return period) and major events (1:100 year return period).	Appendix 'F'
<input type="checkbox"/> Identification of watercourses within the proposed development and how watercourses will be protected, or, if necessary, altered by the proposed development with applicable approvals.	Sediment and Erosion Control Plan
<input type="checkbox"/> Calculate pre and post development peak flow rates including a description of existing site conditions and proposed impervious areas and drainage catchments in comparison to existing conditions.	6.0 Stormwater Management, Appendix 'F'
<input type="checkbox"/> Any proposed diversion of drainage catchment areas from one outlet to another.	6.0 Stormwater Management
<input type="checkbox"/> Proposed minor and major systems including locations and sizes of stormwater trunk sewers, and stormwater management facilities.	6.0 Stormwater Management
<input type="checkbox"/> If quantity control is not proposed, demonstration that downstream system has adequate capacity for the post-development flows up to and including the 100 year return period storm event.	Appendix 'A'
<input type="checkbox"/> Identification of potential impacts to receiving watercourses	N/A
<input type="checkbox"/> Identification of municipal drains and related approval requirements.	N/A
<input type="checkbox"/> Descriptions of how the conveyance and storage capacity will be achieved for the development.	6.0 Stormwater Management
<input type="checkbox"/> 100 year flood levels and major flow routing to protect proposed development from flooding for establishing minimum building elevations (MBE) and overall grading.	Lot Grading, Drainage Plan & sediment Control Plan
<input type="checkbox"/> Inclusion of hydraulic analysis including hydraulic grade line elevations.	N/A

<input type="checkbox"/> Description of approach to erosion and sediment control during construction for the protection of receiving watercourse or drainage corridors.	7.0 Sediment and Erosion Control
<input type="checkbox"/> Identification of floodplains – proponent to obtain relevant floodplain information from the appropriate Conservation Authority. The proponent may be required to delineate floodplain elevations to the satisfaction of the Conservation Authority if such information is not available or if information does not match current conditions.	N/A
<input type="checkbox"/> Identification of fill constraints related to floodplain and geotechnical investigation.	N/A

4.5 Approval and Permit Requirements: Checklist

The Servicing Study shall provide a list of applicable permits and regulatory approvals necessary for the proposed development as well as the relevant issues affecting each approval. The approval and permitting shall include but not be limited to the following:

Criteria	Location (if applicable)
<input type="checkbox"/> Conservation Authority as the designated approval agency for modification of floodplain, potential impact on fish habitat, proposed works in or adjacent to a watercourse, cut/fill permits and Approval under Lakes and Rivers Improvement Act. The Conservation Authority is not the approval authority for the Lakes and Rivers Improvement Act. Where there are Conservation Authority regulations in place, approval under the Lakes and Rivers Improvement Act is not required, except in cases of dams as defined in the Act.	N/A
<input type="checkbox"/> Application for Certificate of Approval (CofA) under the Ontario Water Resources Act.	N/A
<input type="checkbox"/> Changes to Municipal Drains.	N/A
<input type="checkbox"/> Other permits (National Capital Commission, Parks Canada, Public Works and Government Services Canada, Ministry of Transportation etc.)	N/A

4.6 Conclusion Checklist

Criteria	Location (if applicable)
<input type="checkbox"/> Clearly stated conclusions and recommendations	8.0 Summary 9.0 Recommendations
<input type="checkbox"/> Comments received from review agencies including the City of Ottawa and information on how the comments were addressed. Final sign-off from the responsible reviewing agency.	All are stamped
<input type="checkbox"/> All draft and final reports shall be signed and stamped by a professional Engineer registered in Ontario	All are stamped