



**Site Servicing & Stormwater Management Report
IBPS Temple – 6688 Franktown Road, Ottawa, ON.**

Client:
GRC Architects

Project Number:
OTT-22027645-A0

Application Stage:
Site Plan Control

Prepared By: Aaditya Jariwala, M.Eng, P.Eng.

EXP Services Inc.
100-2650 Queensview Drive
Ottawa, ON K2B 8H6

Date Submitted:
December 18, 2024
Revised: June 6, 2025

Site Servicing & Stormwater Management Report IBPS Temple – 6688 Franktown Road, Ottawa, ON.

Client:

GRC Architects
47 Clerance Street, Suite 401
Ottawa, ON K1N 9K1

Submitted for:

Site Plan Control Application

Project Name:

IBPS Temple

Project Number:

OTT-22027645-A0

Prepared By:

EXP
2650 Queensview Drive
Ottawa, ON K2B 8H8
t: +1.613.688.1899
f: +1.613.225.7337

Prepared by:

Aaditya Jariwala, M.Eng, P.Eng.
Project Manager
Infrastructure Services

Date Submitted:

December 18, 2024
Revised: June 6, 2025

Legal Notification

This report was prepared by **EXP** Services Inc. for the account of GRC Architects. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. **EXP** Services Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this project.

Table of Contents

1	Introduction	1
2	Existing Conditions.....	1
3	References	1
4	Pre-Consultation / Permits / Approvals	2
5	Watermain Design	2
5.1	Existing Water Servicing	2
5.2	Required Fire Flow	2
5.3	Proposed Domestic Water Demands	3
5.4	Proposed Water Servicing Design	4
6	Sanitary Sewer Design.....	4
6.1	Peak Design Flow	4
7	Stormwater Management.....	5
7.1	Storm Design Criteria	5
7.2	Pre-Development Conditions	6
7.3	Allowable Release Rate	6
7.4	Post-Development Stormwater Management Design	6
8	Erosion and Sediment Control.....	8
9	Conclusions.....	8

List of Appendices

Appendix A – Figures

Appendix B – Water Servicing

Appendix C – Stormwater Management Design Sheet

Appendix D – Sewage Flows and Storage Volume Calculations Sheet

Appendix E – Additional Information

Appendix F – Drawings

1 Introduction

EXP Services Inc. (EXP) was retained by GRC Architects on behalf of International Buddhist Progress Society (IBPS) to provide Site Servicing and Stormwater Management report for Fo Guang Shan Temple of Ottawa located in Ottawa, ON.

The property located at 6688 Franktown Road is approx. 39.87 hectares. and located just outside the village of Richmond in the City of Ottawa. The property is surrounded by farm lands along the north-east and south-west property lines, a residential development on the south-east corner and Franktown road along the frontage of the property. Refer to **Figure A1** in **Appendix A** for the site location.

The proposed Fo Guang Shan Temple is intended to be developed in two phases. Under phase one, a small temple building with approx. 360m² footprint was constructed in 2020 along with a septic system, private water well, 10,000 Gallon underground water tank for fire fighting and a gravel access road. The current site plan control application is for the phase two development where a new temple building with approx. 1400 m² footprint along with stormwater management infrastructure, extension of the ex. septic system, new water well, asphalt parking lots and asphalt driveways are intended to be added. The subject development will be concentrated in approx. 3.2 hectares of the property near Franktown road, while the remainder of the property will remain as forested/vegetated lands.

This servicing and stormwater management design report will address the Servicing requirements for the proposed phase two development including the domestic and fire water, sanitary and storm servicing. The report will also cover the storm water management requirements and proposed methods to meet those requirements.

2 Existing Conditions

There is an existing temple building constructed under phase one along with a septic system, water well, underground water tank for fire fighting, an existing electrical transformer, asphalt parking lot, concrete patio and a gravel access road. The remainder of the site is forested or vegetated.

The topography of the site is fairly flat, with some depressed areas within the property. The topography is assumed to be gradually sloping to the northeast towards Franktown Road.

There is a municipal 200mm dia. sanitary force main within the Franktown Road ROW. No other known municipal infrastructure is present within the City ROW near the subject property. The stormwater runoff from the subject property is currently carried by the existing roadside ditch along Franktown Road.

3 References

Various documents were referred to in preparing the current report including:

- Sewer Design Guidelines, Second Edition, Document SDG002, October 2012, City of Ottawa (Guidelines) including:
 - Technical Bulletin ISDTB-2012-4 (20 June 2012)
 - Technical Bulletin ISDTB-2014-01 (05 February 2014)
 - Technical Bulletin PIEDTB-2016-01 (September 6, 2016)

- Technical Bulletin ISDTB-2018-01 (21 March 2018)
- Technical Bulletin ISDTB-2018-04 (27 June 2018)
- Technical Bulletin ISDTB-2019-02 (08 July 2019)
- Ottawa Design Guidelines – Water Distribution, July 2010 (WDG001), including:
 - Technical Bulletin ISDTB-2014-02 (May 27, 2014)
 - Technical Bulletin ISTB-2018-02 (21 March 2018)
 - Technical Bulletin ISTB-2021-03 (18 August, 2021)
- Ontario Ministry of Transportation (MTO) Drainage Manual, 1995-1997
- Stormwater Management Planning and Design Manual, Ontario Ministry of the Environment and Climate Change, March 2003 (SMPDM).
- Design Guidelines for Drinking-Water Systems, Ontario Ministry of the Environment and Climate Change, 2008 (GDWS).
- Fire Underwriters Survey, Water Supply for Public Fire Protection (FUS), 2020
- Ontario Building Code 2012, Ministry of Municipal Affairs and Housing
- Servicing and Stormwater Management Report prepared by McIntosh Perry dated, July 30, 2018
- Geotechnical Report prepared by McIntosh Perry dated July 2018.
- Hydrogeological Study prepared by McIntosh Perry dated July 2018.

4 Pre-Consultation / Permits / Approvals

A pre-consultation meeting was held with the City prior to design commencement for phase 1. The notes from this meeting outlined the submission requirements and provided information to assist with the development proposal. Please refer to the meeting notes included in **Appendix E**.

Since the stormwater flows from the proposed development will discharge to the road side ditch which ultimately outlets into Jock River to the east, a direct submission to MECP for an Environmental Compliance Approval (ECA) application will be required. Additionally, an ECA application for the on-site private septic system will be required. The preparations for these ECA application are currently underway and will be submitted to MECP directly once completed.

5 Watermain Design

5.1 Existing Water Servicing

The existing temple building is serviced by a 64mm dia. watermain from a private water well. The well yield was noted as 92 L/min (1.53 L/sec) during a 6-hour pump test.

Additionally, there is an existing 10,000 Gallons underground water tank for fire fighting purposes.

5.2 Required Fire Flow

Since the new building will have a greater area and volume, the required fire flow demands were calculated for the new building only.

The required fire flow for the proposed building was estimated based on OBC Div B A-3.2.5.7. The following equation was used.

$$Q = K \times V \times S_{\text{tot}}$$

where:

Q = Minimum supply of water in liters

K = water supply coefficient from Table 1 OBC Div B A-3.2.5.7.

V = total building volume in cubic meters

S_{tot} = total of spatial coefficient values from property line exposures on all sides as obtained from the formula:

$$S_{\text{tot}} = 1.0 + [S_{\text{side1}} + S_{\text{side2}} + S_{\text{side3}} + \dots \text{etc.}]$$

Spatial coefficients are a function of exposure distance and can be found in Figure 1 OBC Div B A-3.2.5.7.

The required minimum water supply flow rate is a function of Q and is given in Table 2 OBC Div B A-3.2.5.7. Table 5.1 below summarizes the parameters used for estimating the Required Fire Flows (RFF) based on the Ontario Building Code (OBC) and the latest City of Ottawa Technical Bulletins.

Table 5.1: Summary of Design Parameters Used in Calculating Required Fire Flows (RFF) Using OBC

Item	Design Value
Floors Above Grade	1 floor
Sprinklered	No
North Exposure Distance, Spatial Coefficient	>10.0m, 0.0
East Exposure Distance, Spatial Coefficient	>10.0m, 0.0
South Exposure Distance, Spatial Coefficient	>10.0m, 0.0
West Exposure Distance, Spatial Coefficient	>10.0, 0.0
S _{tot}	1.0
V(m ³)	1397 m ² x 3.0m = 4191.0m ³
K	Based on Non-Combustible Construction and Occupancy Group A, Division 2 C, K=16
Q	67,056.00 L
Required Minimum Water Supply Flow Rate (L/min)	2700 L/min (45 L/sec) (if Q ≤ 108,000 L)

The estimated required fire flows (RFF) based on the OBC method is 67,056.00 L at a supply rate of 45.0 L/sec for the proposed temple building.

5.3 Proposed Domestic Water Demands

Domestic water demands were calculated for the residential occupancy and institutional occupancy. For the residential occupancy, six (6) – one bedroom units were considered. For the institutional occupancy, gross hectare area of the proposed development limit (3.25 ha) was considered.

Domestic demands for institutional development of 28,000 L/ha/day and residential demands of 280 L/person/day were used based on City of Ottawa WDG001. Additionally, even though the proposed

development will be serviced by a private well, for the conservative demands calculation, peaking factors of 9.5 and 14.3 were used for the residential demands and 1.5 and 2.7 were used for the institutional demands for max. day and peak hour demands, respectively. With the above noted considerations, the total average day demand, max day demand and peak hour demands were calculated as 1.07 L/sec, 1.77 L/sec and 3.12 L/sec, respectively. Refer to **Table B1** in **Appendix B** for detailed information.

5.4 Proposed Water Servicing Design

The existing building is serviced by an existing private water well. Based on the Hydrogeological assessment study and site servicing and storm water management report prepared by McIntosh Perry during the phase 1 site plan application, the existing water well can sufficiently service the existing building and new building. The pump rate for the existing well during 6-hour pumping test was noted as 92 L/min.

Based on the revised Hydrogeological Assessment study dated, June 6, 2025; prepared by EGIS stated that the existing well should be sufficient to service the new water demands based on the previous pump test and the observed drawdown. Therefore, A new 100mm dia. water service is proposed for the new building to feed from the existing well. Friction loss of 2.6 psi is anticipated over a length of 142 m with ground elevation difference of 1.02m (102.0m new bldg. FFE – 100.18m ex. well ground elevation).

Additionally, mechanical engineer will have to provide booster pumps to ensure that the serviceability within the building remains between the range of 40psi and 80psi for water service.

For fire fighting purposes, 67,056L of water at 2,700 L/min rate is required. A 10,000 Gallon capacity water tank was installed during phase 1 construction. EXP had reached out to the City fire department staff to review the site specific fire fighting infrastructure requirements. Based on their input, the existing 10,000 Gallon fire water storage tank is sufficient to provide required fire flow for the new and existing building. Additionally, the staff had advised EXP to install a new dry hydrant to feed from the existing fire water tank, which is shown on the site servicing plan C100. Refer to the correspondence with the City fire department staff included in **Appendix B**.

6 Sanitary Sewer Design

6.1 Peak Design Flow

Peak sanitary design flows were estimated for the existing building and proposed building using the events list and expected attendees received from the client. Residential demands were also calculated for the six (6) – one bedroom units in the new temple building. Please refer to the table included in **Appendix D** for peak daily sewage flows and max. storage calculations.

Based on this events list, an average number of attendees was calculated as 97 persons. There were two events on the list which had 1000 attendees and one event with 5000 attendees. which were excluded from the demand calculations. The existing septic system was designed to treat 10,000 L/day for sewage flows (Refer to septic application included in **Appendix E**), which equates to approx. 277 persons, considering 36 L/person/day of sanitary demands. Therefore, to maintain the efficiency of the septic system and health of the bacterial community within the existing biofilter by providing regular and sufficient sewage flows to the existing septic system; a new holding tank is proposed to be added. Which will hold the additional sewage greater than 10,000 L/day temporarily from the proposed development. With addition of the new sewage holding tank, the existing septic system will be able to accommodate six (6) proposed residential units and up to 1,000 attendees as per the sequencing provided by the owners in the events list by the client. The detailed calculation of sewage flows, sequencing of the events, attendance during each event and sewage holding tank volume can be found in **Appendix D**.

The owners will arrange temporary mobile toilets during infrequent large gatherings with attendance in exceedance of 1,000 people.

Design Flows

Design flows are calculated using the sewage demands for residential and institutional occupancies as per OBC 2012 tables 8.2.1.3 (A) and 8.2.1.3 (B), respectively.

Sewage design flows for Assembly: 36 L/person/day

Max. Attendance: 1000 people

Residential Bedrooms: 6

Sewage Flows from Residential Occupancy: 3,000 L/day

Peak Design Flow: = (36L/person/day)(1,000 persons)(1/86400) + (3,000 L/day)(1/86400)
= **0.44 L/s or 39,000 L/day**

As per the previous site servicing and stormwater management report prepared by McIntosh Perry, the septic system and septic bed installed during phase 1 construction were designed for sewage flows of 9,999 L/day.

As noted above, the existing system can accommodate sewage flows from up to 277 occupants. Majority of the events on the events list provided by the client have attendance less than 97. Only three events during the year will have 1000-5000 attendees. To maintain the efficiency of the biofilter by ensuring regular and consistent sewage load, a new 50,000 L holding tank is proposed to be added. With this holding tank, sewage flows from max. 1000 attendees will be accommodated. The existing septic system treatment units and septic bed sizes will remain as-is.

Previously designed septic system prepared by McIntosh Perry is included in **Appendix E** and on drawing C100 as well as C101 for information.

The existing temple building is serviced by a 100mm dia. gravity sanitary sewer discharging into the anaerobic digester. The proposed building will be serviced by a 200mm dia. sanitary sewer at 0.6% having a full flow capacity of 25.8 L/sec and will discharge into a new sewage holding tank. The holding tank will be equipped with two sewage grinder pumps sized to pump at the maximum rate of 10,000 L/day. The holding tank will also be equipped with two agitators to avoid solids from settling at the tank bottom. The electric panel for the holding tank will be mounted in the building and will have alarms set at 70% and 100% capacities based on the tank level floats. The holding tank will be connected to the existing anaerobic digester. The existing building sanitary service will be re-routed to the proposed sewage holding tank as well. Size and location of the new holding tank are shown on drawing C101 – Septic System Plan. The existing septic system includes an anaerobic digester followed by Waterloo biofilter tanks followed by a pump tank. The sewage from the holding tank will flow through the septic system in above mentioned order in a loop and then finally be pumped to the existing raised bed Type A septic bed at the previously design rate of 10,000 L/day.

Since the daily design sewage flow under phase 2 development will exceed 10,000 L/day, an ECA application will be required for the proposed septic system and will be submitted for a direct review to MECP.

7 Stormwater Management

7.1 Storm Design Criteria

The storm sewer system was designed in conformance with the City of Ottawa Sewer Design Guidelines (October 2012) and MECP SMPDM (March 2003). The stormwater management design criteria for the proposed development are as follows:

- Post-development peak run-off for each storm events up to and including 100-year storm event to match pre-development run-off.
- Maximum allowable ponding depth is 300 mm for surface ponding and 150mm for roof ponding.
- Minimum freeboard of 300mm between the 100-year overland spill elevation and finished floor elevation. Minimum freeboard of 150mm between the 100-year overland spill elevation and lowest grades against the building foundation.
- Quality control criteria of 80% TSS removal (Enhanced level treatment) as noted by RVCA in the pre-consultation meeting notes.

7.2 Pre-Development Conditions

The subject site was a forested/vegetated parcel before the phase 1 development. During the phase 1 development, a new temple building was added along with asphalt parking lot and concrete patio. To determine the post-development allowable release rates from the subject site, pre-development landcovers before phase 1 development were used to calculate pre-development runoff coefficient. Refer to topographic survey plan prepared by McIntosh Perry dated, February 21, 2018 included in **Appendix F**.

7.3 Allowable Release Rate

To calculate allowable release rates, pre-development average run-off coefficient was calculated for the 3.25 ha of development area. An average time of concentration was also calculated. With the pre-development average runoff coefficient of 0.25 and time of concentration of 34.88 mins; pre-development runoff rates during 2-year, 5-year and 100-year storm events were estimated using rational method.

Therefore, the allowable release rates from the subject development (phase 1 and phase 2) were calculated as 82.76 L/sec, 111.36 L/sec and 236.92 L/sec during 2-year, 5-year and 100-year storm events, respectively. Refer to **Table C1 – Table C3** in **Appendix C** for detailed calculations.

7.4 Post-Development Stormwater Management Design

In post-development conditions the existing temple building constructed under phase 1 development along with the proposed temple building, asphalt areas and landscaping within the 3.25 ha development area were considered. Using the area-weighted average method, post-development average run-off coefficients were calculated. The proposed stormwater management and drainage strategy includes sheet drainage, low slope-flat bottom vegetated swales and ditches, culverts and an extended detention dry pond equipped with a sediment forebay. Based on the proposed storm drainage strategy, the development area was divided into two post-development catchment areas A1 and A2.

Drainage area A1 consists of 1.76 ha of the site on western portion of the development with a calculated average runoff coefficient of 0.52. Area A2 consists of 1.49 ha of the site on eastern portion of the development and includes the existing temple building and surrounding areas developed during phase 1 construction. Average runoff coefficient for catchment A2 was calculated as 0.57. The total post-development average runoff coefficient for the proposed 3.25ha development was calculated as 0.55. Increase in the post-development runoff coefficient is due to increase in the impervious areas such as asphalt driveways and parking lots, building roof, concrete etc.

With a time of concentration of 10mins and calculated runoff coefficients, post-development runoff rates were estimated using rational method. Post development uncontrolled runoff during 2-year, 5-year and 100-year storm events were estimated at 380.03 L/sec, 515.55 L/sec and 1104.39 L/sec, respectively. Required

storage volumes during each storm events were estimated using the Modified Rational Method. Which were estimated at 211.1 m³, 289.7 m³ and 618.4 m³ during 2-year, 5-year and 100-year storm events, respectively. These estimates were based on the allowable release rates specified in **Section 7.3** above.

A detailed stormwater management pond sizing and pond outlet structure design was carried out as per MECP SMPDM. In the Geotech investigation report prepared by McIntosh Perry dated July 2018, groundwater elevation at the site was noted to be between 1.0m-1.5m below ground surface. Due to site constraints such as high groundwater table and flat topography, a dry pond was chosen as the proposed SWM facility for achieving the quantity and quality control criteria for the proposed development.

With a drainage area of 3.25 ha and 52% imperviousness, water quality volume requirement was calculated at 110.8 m³/ha. This equates to a total water quality volume of 360 m³. This volume calculation was based on a normal protection level (70% TSS removal). Additionally, extended detention volume of 130 m³ was calculated based on 40 m³/ha. For a dry pond, extended detention volume is included in the water quality volume. With the estimated quality and quantity control volumes, the proposed dry pond was designed to have a maximum depth of 1.0m with 4:1 side slopes. Additionally, a sediment forebay was designed to provide initial treatment to the stormwater runoff from the subject development. The total designed stormwater storage volume is 1,037 m³ out of which 134 m³ will be provided in the sediment forebay and 903 m³ will be provided in the dry pond. Refer to Civil drawings for further details.

With the target drawdown time/detention time of minimum 24hours, the stormwater management pond outlet structure was designed. The outlet structure will be a pre-cast or a cast-in-place concrete weir wall with a 75mm square orifice for quality control and a rectangular 0.5m wide weir for quantity control. With 75mm square orifice, the calculated drawdown time during water quality flow rate was estimated at 27 hours. The quantity control weir will restrict the peak flow rates during WQF, 2-year, 5-year and 100-year storm events to 15.03 L/sec, 82.76 L/sec, 108.19 L/sec and 230 L/sec, utilizing storage volume of 376 m³, 458 m³, 504 m³ and 707 m³, respectively. During 100year + 20% storm events (check for climate change), expected peak flowrate will be 284.30 L/sec and utilized storage will be 811 m³. The proposed stormwater management pond will outlet into the road side ditch along Franktown Road and eventually flow to Jock River towards the east.

In addition to extended detention dry-pond, low slope flat bottom vegetated ditches were also designed as per MECP design guidelines to further improve the quality of stormwater and promote infiltration and TSS removal by maintaining flow velocities less than 0.5 m/sec. The proposed ditches will have bottom width of 0.8m and depth of 0.5m with min. 3:1 side slopes. The average longitudinal slopes were kept less than 1.0% with majority of the ditch sections at 0.5%. Based on various literature review on TSS removal efficiency of a vegetated swale, a conservative 50% TSS removal was assumed for the proposed design. Therefore, the effective TSS removal from the proposed vegetated ditches and extended detentions dry pond will be 85%. Additionally, to prevent re-suspension of the settled sediments in the dry-pond, appropriate vegetation will be planted within the dry-pond as per the landscape plan.

Refer to **Table C4 to C14** in **Appendix C** for detailed stormwater management design calculations. **Table C15** and **C16** provides detailed ditch capacity and flow velocity calculations.

With the above presented stormwater management design and supporting calculations, stormwater management quantity and quality criteria set for the subject site (phase 1 and 2 development) can be met successfully.

8 Erosion and Sediment Control

During all construction activities, erosion and sedimentation shall be controlled by the following techniques:

- Extent of exposed soils shall be limited at any given time;
- Exposed areas shall be re-vegetated as soon as possible;
- Minimize the area to be cleared and disruption of adjacent areas;
- Visual inspection shall be completed daily on sediment control barriers and any damage will be repaired immediately. Care will be taken to prevent damage during construction operations;
- In some cases, barriers may be removed temporarily to accommodate the construction operations. The affected barriers will be reinstated at night when construction is completed;
- Sediment control devices will be cleaned of accumulated silt as required. The deposits will be disposed of as per the requirements of the contract;
- During construction, if the engineer believes that additional prevention methods are required to control erosion and sedimentation, the contractor will install additional silt fences or other methods as required to the satisfaction of the engineer; and,
- Construction and maintenance requirements for erosion and sediment controls are to comply with Ontario Provincial Standard Specification (OPSS) 805.


9 Conclusions

This report addresses the site servicing and stormwater management requirements for the site plan control application for the proposed development. Based on the analysis provided in this report, the conclusions are as follows:

- Proposed phase 2 development will be serviced by the existing water well for domestic demands. The existing 10m000 Gallon fire water storage tank has sufficient capacity to service both building for fire demands as confirmed by the City fire department staff.
- The proposed building will be serviced by a 200mm diameter sanitary sewer, which will discharge into a new sewage holding tank. The existing building 100mm dia. sanitary service will re-routed and connected to the new holding tank as well. The holding tank will discharge to the existing aerobic digester that was installed during phase 1 construction. It is understood that the existing septic system has a treatment capacity of 9,999 L/day. Pump rate from the new holding to the ex. Septic system will be controlled to 10,000 L/day. Therefore, the daily sewage volume treated by the ex. Septic system will remain the same. No additional changes are proposed to the existing septic treatment units and septic bed.
- Stormwater Management criteria for the proposed development will be achieved by restricting the post-development stormwater discharge rates up to and including the 100-year to the allowable release rates.
- Additionally, quality control criteria of 80% TSS removal will be achieved by low slope and flat bottom vegetated ditches as well as the proposed extended detention dry pond. The anticipated TSS removal efficiency of the proposed stormwater management system will be 85%.
- Temporary erosion and sediment control measures for the subject site have been identified.

Appendix A – Figures

Figure A1
Site Location Plan



Google Earth

Image © 2024 Airbus

Appendix B – Water Servicing

TABLE B1
Water Demand Chart

Junction Number (Building)	No. of Units										Total Pop	Residential Demands					Commercial/Institutional						Total Demands in (L/sec)			
	Singles/Semis/Towns				Apartments							Avg Day Demand (L/day)	Max Day Peaking Factor	Max Hour Peaking Factor	Max Day Demand (L/day)	Peak Hourly Demand (L/day)	Area (ha)	Avg Demand (L/day)	Peaking Factors (x Avg Day)		Max Day Demand (L/day)	Peak Hour Demand (L/day)	Avg Day (L/s)	Max Day (L/s)	Peak Hour (L/s)	
	Single Family	Semi	Duplex	Townh ome	Bach elor	1- Bed Apt	2-Bed Apt	3-Bed Apt	4-Bed Apt	Avg Apt.									Max Day	Peak Hour						
6688 Franktown Road					6						6.0	1,680	9.50	14.30	15,960	24,024	3.25	91,000	1.5	2.7	136500.0	245700.0	1.073	1.765	3.122	
Totals =					6						8.4	1,680			15,960	24,024	3.3				136,500	245,700	1.073	1.765	3.122	

Unit Densities

Persons/Unit

Singles3.4

Semi-Detached2.7

Duplex2.3

Townhome2.7

Bachelor Apt Unit1.4

1-Bed Apt Unit1.4

2-Bed Apt Unit2.1

3-Bed Apt Unit3.1

4-Bed Apt Unit4.1

Avg. Apt Unit1.8

Residential

Residential Consumption (L/pers/day) =280

Max Day Peaking Factor (* avg day) =2.5

Peak Hour Factor (* avg day) =5.5

Industrial/Commercial/Institutional Water Consumption

Light Industrial (L/gross ha/day) =35,000

Heavy Industrial (L/gross ha/day) =55,000

Commer/Instit (L/gross ha/day) =28,000

Max Day Peaking Factor (* avg day) =1.5

Peak Hour Factor (* avg day) =2.7

Based on MECP-GDWS Table 3-3. Less than 500 persons

9.50

14.30

Project:

IBPS Temple

Designed:

Aaditya Jariwala, M.Eng., P.Eng

Checked:

Alam Ansari, M.Sc., P.Eng

File Reference:

22027645 - Water - Demand Chart.xlsx

Location:

6688 Franktown Road, Ottawa, ON.

Page No:

1 of 1

From: Evans, Allan <Allan.Evans@ottawa.ca>
Sent: Monday, April 28, 2025 1:02 PM
To: Aaditya Jariwala
Cc: Alex Leung; Caelan Mitchell; Alam Ansari; Morgan, Brian; Whittaker, Damien
Subject: RE: IBPS Temple - 6688 Franktown Road.
Attachments: [Rural Water Technical Drawings.pdf](#)





CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Hi everyone- thanks for the chat today. Here are my summary points:

- Eliminate 3 additional water storage tanks proposed – existing water storage is sufficient
- Add remote hydrant system roughly as shown below
 - o Pipe diameter to be determined (min 6”) based upon engineering calculations/fireflow
 - o Due to high water table, fire hydrants will require sealed weep holes to prevent water infiltration and subsequent freezing in winter
 - This also means when tested after install and any time used on site that they will have to be pumped dry (there are agencies that do this)
 - o Note that remote fire hydrants have a specific paint pattern and placement location (near the water tank, but not too close)
- Ensure fire route maintains all OBC requirements

Happy to discuss further as needed.





Allan Evans

Fire Protection Engineer / Ingénieur de Protection d'Incendies
Prevention Division / Prévention des Incendies

Ottawa Fire Services / Service des Incendies d'Ottawa

1445 Carling Avenue / 1445 Avenue Carling

Ottawa, ON K1Z 7L9

Allan.Evans@Ottawa.ca

☎ (613) 913-2747 | ☎ (613) 580-2424 x24119 | 📠 (613) 580-2866 | 📧 Mail Code: 25-102 |

[Book time with Evans, Allan](#)



An internationally accredited agency 2019-2024



OTTAWA FIRE SERVICES

SERVICE DES INCENDIES D'OTTAWA

Protecting Our Nation's Capital With Honour

Protéger notre capitale nationale avec honneur

Classified as City of Ottawa - Internal / Ville d'Ottawa - classé interne

From: Aaditya Jariwala <Aaditya.Jariwala@exp.com>

Sent: April 25, 2025 1:51 PM

To: Evans, Allan <Allan.Evans@ottawa.ca>

Cc: Alex Leung <aleung@provencherroy.ca>; Caelan Mitchell <cmitchell@provencherroy.ca>; Alam Ansari <alam.ansari@exp.com>; Morgan, Brian <Brian.Morgan@ottawa.ca>; Whittaker, Damien <Damien.Whittaker@ottawa.ca>

Subject: RE: IBPS Temple - 6688 Franktown Road.

CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.

ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.

Ok thank you, will send an invite for Monday noon shortly.

Aaditya Jariwala, M.Eng, P.Eng.

EXP | Project Manager

t : +1.613.688.1899, 63240 | m : +1.613.816.5961 | e : aaditya.jariwala@exp.com

exp.com | legal disclaimer

keep it green, read from the screen

Classified as City of Ottawa - Internal / Ville d'Ottawa - classé interne

From: Evans, Allan <Allan.Evans@ottawa.ca>

Sent: Friday, April 25, 2025 1:49 PM

To: Aaditya Jariwala <Aaditya.Jariwala@exp.com>

Cc: Alex Leung <aleung@provencherroy.ca>; Caelan Mitchell <cmitchell@provencherroy.ca>; Alam Ansari <alam.ansari@exp.com>; Morgan, Brian <Brian.Morgan@ottawa.ca>; Whittaker, Damien <Damien.Whittaker@ottawa.ca>

Subject: RE: IBPS Temple - 6688 Franktown Road.



CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Let's do Monday at noon – I need to discuss some items with the sector chief about this site and make sure he and I are on the same page.

Brian and/or Damien are welcome to attend.

A

Allan Evans

Fire Protection Engineer / Ingénieur de Protection d'Incendies

Prevention Division / Prévention des Incendies

Ottawa Fire Services / Service des Incendies d'Ottawa

1445 Carling Avenue / 1445 Avenue Carling

Ottawa, ON K1Z 7L9

Allan.Evans@Ottawa.ca

☎ (613) 913-2747 | ☎ (613) 580-2424 x24119 | 📠 (613) 580-2866 | 📧 Mail Code: 25-102 |

[Book time with Evans, Allan](#)



An internationally accredited agency 2019-2024



OTTAWA FIRE SERVICES

SERVICE DES INCENDIES D'OTTAWA

Protecting Our Nation's Capital With Honour

Protéger notre capitale nationale avec honneur

Classified as City of Ottawa - Internal / Ville d'Ottawa - classé interne

From: Aaditya Jariwala <Aaditya.Jariwala@exp.com>

Sent: April 25, 2025 1:25 PM

To: Evans, Allan <Allan.Evans@ottawa.ca>

Cc: Alex Leung <aleung@provencherroy.ca>; Caelan Mitchell <cmitchell@provencherroy.ca>; Alam Ansari <alam.ansari@exp.com>; Morgan, Brian <Brian.Morgan@ottawa.ca>
Subject: RE: IBPS Temple - 6688 Franktown Road.

CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.

ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.

Hi Allan,

I can meet today between 3PM – 4PM or anytime on Monday. Let me know. If any of the discussions are related to architectural and building code then I would have to confirm their availability as well.

Let me know,

Aaditya Jariwala, M.Eng, P.Eng.

EXP | Project Manager

t : +1.613.688.1899, 63240 | m : +1.613.816.5961 | e : aaditya.jariwala@exp.com

exp.com | legal disclaimer

keep it green, read from the screen

Classified as City of Ottawa - Internal / Ville d'Ottawa - classé interne

From: Evans, Allan <Allan.Evans@ottawa.ca>

Sent: Friday, April 25, 2025 12:31 PM

To: Aaditya Jariwala <Aaditya.Jariwala@exp.com>

Cc: Alex Leung <aleung@provencherroy.ca>; Caelan Mitchell <cmitchell@provencherroy.ca>; Alam Ansari <alam.ansari@exp.com>; Morgan, Brian <Brian.Morgan@ottawa.ca>

Subject: RE: IBPS Temple - 6688 Franktown Road.



CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

This proposal does not work for us for location and how you are implying we would operate at this location. I think a Teams meeting to clarify some outstanding issues would be the best way to simply and move forward here. Please let me know what works for you next week – I'm available most days 9:00-2:30 but I do have other meetings schedule already.

Regards,

Allan Evans

Fire Protection Engineer / Ingénieur de Protection d'Incendies
Prevention Division / Prévention des Incendies

Ottawa Fire Services / Service des Incendies d'Ottawa

1445 Carling Avenue / 1445 Avenue Carling

Ottawa, ON K1Z 7L9

Allan.Evans@Ottawa.ca

☎ (613) 913-2747 | ☎ (613) 580-2424 x24119 | 📠 (613) 580-2866 | 📧 Mail Code: 25-102 |

[Book time with Evans, Allan](#)



An internationally accredited agency 2019-2024



OTTAWA FIRE SERVICES

SERVICE DES INCENDIES D'OTTAWA

Protecting Our Nation's Capital With Honour

Protéger notre capitale nationale avec honneur

Classified as City of Ottawa - Internal / Ville d'Ottawa - classé interne

From: Aaditya Jariwala <Aaditya.Jariwala@exp.com>

Sent: April 25, 2025 10:13 AM

To: Evans, Allan <Allan.Evans@ottawa.ca>

Cc: Alex Leung <aleung@provencherroy.ca>; Caelan Mitchell <cmitchell@provencherroy.ca>; Alam Ansari <alam.ansari@exp.com>; Morgan, Brian <Brian.Morgan@ottawa.ca>

Subject: RE: IBPS Temple - 6688 Franktown Road.

Importance: High

CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.

ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.

Hi Allan,

See attached plan showing the location of new tanks as well as the existing tank. Answers to your comments are provided in **Red** below.

Aaditya Jariwala, M.Eng, P.Eng.

EXP | Project Manager

t : +1.613.688.1899, 63240 | m : +1.613.816.5961 | e : aaditya.jariwala@exp.com

exp.com | [legal disclaimer](#)

keep it green, read from the screen

Classified as City of Ottawa - Internal / Ville d'Ottawa - classé interne

From: Evans, Allan <Allan.Evans@ottawa.ca>

Sent: Wednesday, April 16, 2025 1:10 PM

To: Aaditya Jariwala <Aaditya.Jariwala@exp.com>


Cc: Alex Leung <aleung@provencherroy.ca>; Caelan Mitchell <cmitchell@provencherroy.ca>; Alam Ansari <alam.ansari@exp.com>; Morgan, Brian <Brian.Morgan@ottawa.ca>

Subject: RE: IBPS Temple - 6688 Franktown Road.



CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Hi Aaditya – OFS does not provide fire route letters, I provide fire route comments back to planning. As long as the fire route design meets OBC requirements, there typically is only limited comments around specific access requirements for OFS as appropriate – especially in rural settings. One thing I did bring up was the overhead canopy as shown below. There is a requirement that the overhead clearance (if the fire route continues underneath) of 5m. If it is not to be part of the fire route, we would request a height signage be installed on both sides of the canopy. Additionally please show that there is a code compliant turnaround within 90m of a dead-end if the fire route does not go underneath.



3.2.5.6. Access Route Design

1) A portion of a roadway or yard provided as a required access route for fire department use shall

- a) have a clear width not less than 6 m, unless it can be shown that lesser widths are satisfactory,
- b) have a centre-line radius not less than 12 m,
- c) have an overhead clearance not less than 5 m,
- d) have a change of gradient not more than 1 in 12.5 over a minimum distance of 15 m,
- e) be designed to support the expected loads imposed by firefighting equipment and be surfaced with concrete, asphalt or other material designed to permit accessibility under all climatic conditions,
- f) have turnaround facilities for any dead-end portion of the access route more than 90 m long, and
- g) be connected with a public thoroughfare.

(See Note A-3.2.5.6.(1).)

2) For buildings conforming to Article 3.2.2.51. or 3.2.2.60., no portion of the access route described in Sentence 3.2.2.10.(3) shall be more than 20 m below the uppermost floor level.

In your Servicing Report you mention 3 new tanks x 10000. I have a few questions around this.

- 1) Location – are you proposing to add to existing tank, or is it at the location shown below circled in red? **See attached plan showing location of new and existing tanks.**
- 2) According to the OBC calculation you provided, the new building required 67060 L, yet you propose 113562L in additional storage on top of the existing storage – why? Is there a sprinkler system? Some other reason? **No, the new or existing buildings are not sprinklered. We had provided additional storage for redundancy purposes until we had a contact from the City regrading this matter. We will remove one of the three tanks. So it will be 2x 10,000 Gal new tanks and 1x10,000 Gal existing tank on site.**

- 3) Can you please provide distance from the primary entrance of the new building to the proposed location of tanks and the existing tank (travel path, not straight line). **Shown on the attached plan.**




Table 5.1: Summary of Design Parameters Used in Calculating Required Fire Flows (RFF) Using OBC

Item	Design Value
Floors Above Grade	1 floor
Sprinklered	No
North Exposure Distance, Spatial Coefficient	>10.0m, 0.0
East Exposure Distance, Spatial Coefficient	>10.0m, 0.0
South Exposure Distance, Spatial Coefficient	>10.0m, 0.0
West Exposure Distance, Spatial Coefficient	>10.0, 0.0
S_{tot}	1.0
$V(m^3)$	$1397 m^2 \times 3.0m = 4191.0m^3$
K	Based on Non-Combustible Construction and Occupancy Group A, Division 2 C, K=16
Q	67,056.00 L
Required Minimum Water Supply Flow Rate (L/min)	2700 L/min (45 L/sec) (if $Q \leq 108,000$ L)

The estimated required fire flows (RFF) based on the OBC method is 45.0 L/sec for the proposed temple building.

Table J.2 – Applied Criteria

OBC Flow Rates (L/min)	Storage (Q)	Detail
2700, 3600 or 4500	$Q - 57000$	OBC method to be used for all fire flows < 9000 L/min
5400 or 6300	Q	OBC method to be used for all fire flows < 9000 L/min
9000	Special Evaluation	Applicant to provide calculations for OBC, FUS and National Fire Protection Association (NFPA) 1142 (possibility of two draft points required)
Sprinkler System	Special Evaluation	Applicant to provide calculations for OBC and NFPA 13.

OFS is capable of flowing approximately 4500 L/min from a single draft point. For OBC flow rates ≤ 4500 L/min, a reduction in storage volume will be applied ($1,900$ L/min \times 30 min = 57000 L) to Q to the minimum permissible storage volume of 38000 L.

Allan Evans

Fire Protection Engineer / Ingénieur de Protection d'Incendies
Prevention Division / Prévention des Incendies
Ottawa Fire Services / Service des Incendies d'Ottawa
1445 Carling Avenue / 1445 Avenue Carling
Ottawa, ON K1Z 7L9
Allan.Evans@Ottawa.ca

☎ (613) 913-2747 | ☎ (613) 580-2424 x24119 | ☎ (613) 580-2866 | ✉ Mail Code: 25-102 |

[Book time with Evans, Allan](#)



An internationally accredited agency 2019-2024



OTTAWA FIRE SERVICES
SERVICE DES INCENDIES D'OTTAWA

Protecting Our Nation's Capital With Honour
Protéger notre capitale nationale avec honneur

Classified as City of Ottawa - Internal / Ville d'Ottawa - classé interne

From: Aaditya Jariwala <Aaditya.Jariwala@exp.com>

Sent: April 16, 2025 10:40 AM

To: Evans, Allan <Allan.Evans@ottawa.ca>

Cc: Alex Leung <aleung@provencherroy.ca>; Caelan Mitchell <cmitchell@provencherroy.ca>; Alam Ansari <alam.ansari@exp.com>

Subject: IBPS Temple - 6688 Franktown Road.

Importance: High

CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.

ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.

Good morning Allan,

I am reaching out regarding the proposed development at 6688 Franktown Road in Ottawa. We had submitted to the City for SPA. In the first round of review comments, City advised us to reach out to you and get your approval letter on the fire route and on-site water storage volume for fire fighting purposes. The site is in rural area and has no access to municipal watermain. Therefore, the property will be serviced by on-site underground water storage tanks for fire demands. There is an existing temple building on-site and an existing 10,000 USGAL storage tank. As part of the proposed development, a new bigger temple building will be added along with 3 additional underground water storage tanks. The calculated volume of water for fire fighting purposes for the new building per OBC 2012 is 2700 L/min (67,056 L). With the 3 new 10,000 USGAL storage tanks each and 1 existing 10,000 USGAL tank, the total onsite storage volume for fire fighting purposes will be 151416.47 L.

See attached excerpt from our site servicing and stormwater management report. I have also attached the site plan showing the proposed fire route.

Can you please review and advise if you need any further information or clarification?

Looking forward to hearing back from you.

Best regards,



Aaditya Jariwala, M.Eng, P.Eng.

EXP | Project Manager

t : +1.613.688.1899, 63240 | m : +1.613.816.5961 | e : aaditya.jariwala@exp.com

2650 Queensview Drive

Suite 100

Ottawa, ON K2B 8H6

CANADA

exp.com | legal disclaimer

keep it green, read from the screen

,

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

,

,

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

,

,

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

,

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

,

Appendix C – Stormwater Management Design Sheet

TABLE C1
CALCULATION OF AVERAGE RUNOFF COEFFICIENTS FOR PRE-DEVELOPMENT CONDITONS

Area No.	Roof Areas		Asphalt Areas		Gravel		Grassed Areas		Sum AC	Total Area (m ²)	C _{AVG}
	C=0.90		C=0.90		C=0.70		C=0.20				
	Area (m ²)	A * C	Area (m ²)	A * C	Area (m ²)	A * C	Area (m ²)	A * C			
E1	0	0	0	0	3394	2376	29303.020	5860.604	8236.502	32697.160	0.25
Site									8236.502	32697.160	0.25

TABLE C2
CALCULATION OF CATCHMENT TIME OF CONCENTRATION FOR PRE-DEVELOPMENT CONDITIONS

Catchment No.	Area (ha)	High Elev (m)	Low Elev (m)	Flow Path Length (m)	Indiv Slope	Avg. C	Time of Conc. Tc (mins)	Description
E1	3.2697	100.60	99.98	109.4	0.6	0.25	34.88	See Note 2
Notes 1) For Catchments with Runoff Coefficient less than C=0.40, Time of Concentration Based on Federal Aviation Formula (Airport Method), from MTO Drainage Manual Equation 8.16, where: $T_c = 3.26 * (1.1 - C) * L^{0.5} / S_w^{0.33}$ 2) For Catchments with Runoff Coefficient greater than C=0.40, Time of Concentration Based on Bransby Williams Equation, from MTO Drainage Manual Equation 8.15, where: $T_c = 0.057 * L / (S_w^{0.2} * A^{0.1})$								

TABLE C3
CALCULATION OF PEAK RUNOFF FOR PRE-DEVELOPMENT CONDITONS

Area No	Outlet Location	Area (ha)	Time of Conc, Tc (min)	Storm = 2 yr			Storm = 5 yr			Storm = 100 yr		
				I ₂ (mm/hr)	Cavg	Q ₂ (L/sec)	I ₅ (mm/hr)	Cavg	Q ₅ (L/sec)	I ₁₀₀ (mm/hr)	Cavg	Q ₁₀₀ (L/sec)
E1	Franktown Road	3.2697	34.88	36.14	0.25	82.76	48.63	0.25	111.36	82.78	0.31	236.92
Total				82.76			111.36			236.92		
<u>Notes</u>												
1) Intensity, $I = 732.951/(Tc+6.199)^{0.810}$ (2-year)												
2) Intensity, $I = 998.071/(Tc+6.053)^{0.814}$ (5-year)												
3) Intensity, $I = 1735.688/(Tc+6.014)^{0.820}$ (100-year)												
4) Cavg for 100-year is increased by 25% to a maximum of 1.0												
5) The standard minimum Time of Concentraion of 10 minutes was used, rather then the calaculted time, since calaculted time was less than 10 minutes.												

TABLE C4
AVERAGE RUNOFF COEFFICIENTS FOR POST-DEVELOPMENT CONDITIONS

$C_{ASPH/CONC} = 0.90$ $C_{ROOF} = 0.90$ $C_{SLA} = 0.20$ $C_{GRAVEL} = 0.70$												
Area No.	Asphalt & Conc Areas (m ²)	A * C _{ASPH}	Roof Areas (m ²)	A * C _{ROOF}	Soft Landscaped Areas (m ²)	A * C _{SLA}	Gravel Areas (m ²)	A * C _{GRAVEL}	Sum AC	Total Area (m ²)	C _{AVG} (see note)	Comment
A1	6095.4	5485.8	511.9	460.7	8821	1764.3	2171.3	1519.9	9230.7	17600	0.52	West portion of the site
A2	6613.0	5951.7	1233.4	1110.0	6888	1377.6	183.8	128.7	8567.9	14918	0.57	East portion of the site
Totals									17799	32518	0.55	
Notes: Areas for each land-use are taken from CAD												

TABLE C5
SUMMARY OF POST-DEVELOPMENT PEAK FLOWS (Uncontrolled and Controlled)

Area No	Area (ha)	Time of Conc, Tc (min)	Storm = WQF				Storm = 2 yr				Storm = 5 yr				Storm = 100 yr				Storm = 100 yr+20%				Comments
			C _{AVG}	I ₅ (mm/hr)	Q (L/sec)	Q _{CAP} (L/sec)	C _{AVG}	I ₅ (mm/hr)	Q (L/sec)	Q _{CAP} (L/sec)	C _{AVG}	I ₅ (mm/hr)	Q (L/sec)	Q _{CAP} (L/sec)	C _{AVG}	I ₅ (mm/hr)	Q (L/sec)	Q _{CAP} (L/sec)	C _{AVG}	I ₅ (mm/hr)	Q (L/sec)	Q _{CAP} (L/sec)	
A1	1.7600	10	0.52	28.45	73.01	15.03	0.52	76.81	197.09	82.76	0.52	104.19	267.37	108.19	0.66	178.56	572.76	230.00	0.66	214.27	687.31	284.30	West portion of the site
A2	1.4918	10	0.57	30.60	72.88		0.57	76.81	182.94		0.57	104.19	248.17		0.72	178.56	531.63		0.72	214.27	637.96		East portion of the site
Total	3.2518				145.89	15.03			380.03	82.76			515.55	108.19			1104.39	230.00			1325.27	284.30	
Allowable Release Rates						82.76				82.76				111.36				236.92				236.92	

Notes

1) Intensity, $I = 43C + 5.9$ (Water Quality Flowrate based on MECP SMPDM)

2) Intensity, $I = 732.951/(T_c + 6.199)^{0.810}$ (2-year)

3) Intensity, $I = 998.071/(T_c + 6.053)^{0.814}$ (5-year)

4) Intensity, $I = 1735.688 / (T_c + 6.014)^{0.820}$ (100-year)

5) C_{avg} for 100-year is increased by 25% to a maximum of 1.0

6) Time of Concentration, $T_c =$ 10 mins

7) Controlled release rate is indicated by,

<div>Area No: A1, A2</div> <div>C_{AVG} = 0.55 (2-yr)</div> <div>C_{AVG} = 0.55 (5-yr)</div> <div>C_{AVG} = 0.68 (100-yr, Max 1.0)</div> <div>Time Interval = 5.00 (mins)</div> <div>Drainage Area = 3.2518 (hectares)</div>																Actual Release Rate (L/sec) = 230.00 Percentage of Actual Rate (City of Ottawa requirement) = 100% (Set to 50% when U/G storage used) Release Rate Used for Estimation of 100-year Storage (L/sec) = 230.00							Intensity Incr (%) = 20% Use 20% for Climate Change		
Duration (mins)	Release Rate = 82.76 (L/sec) Return Period = 2 (years) IDF Parameters, A = 733.0 , B = 0.810 (I = A/(T _c +C) , C = 6.199					Release Rate = 108.19 (L/sec) Return Period = 5 (years) IDF Parameters, A = 998.1 , B = 0.814 (I = A/(T _c +C) , C = 6.053					Release Rate = 230.00 (L/sec) Return Period = 100 (years) IDF Parameters, A = 1735.7 , B = 0.820 (I = A/(T _c +C) , C = 6.014					Release Rate = 284.30 (L/sec) Return Period = 100+20% (years) IDF Parameters, A = 1735.7 , B = 0.820 (I = A/(T _c +C) , C = 6.014									
	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m³)	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m³)	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m³)	Rainfall Intensity, I (mm/hr)	Peak Flow (L/sec)	Release Rate (L/sec)	Storage Rate (L/sec)	Storage (m³)					
0	167.2	827.4	82.8	744.7	0.0	230.5	1140.4	108.2	1032.2	0.0	398.6	2465.5	230.0	2235.5	0.0	478.3	2958.6	284.3	2674.3	0.0					
5	103.6	512.5	82.8	429.7	128.9	141.2	698.6	108.2	590.4	177.1	242.7	1501.1	230.0	1271.1	381.3	291.2	1801.4	284.3	1517.1	455.1					
10	76.8	380.0	82.8	297.3	178.4	104.2	515.5	108.2	407.4	244.4	178.6	1104.4	230.0	874.4	524.6	214.3	1325.3	284.3	1041.0	624.6					
15	61.8	305.6	82.8	222.9	200.6	83.6	413.4	108.2	305.3	274.7	142.9	883.8	230.0	653.8	588.4	171.5	1060.6	284.3	776.3	698.6					
20	52.0	257.5	82.8	174.7	209.6	70.3	347.6	108.2	239.4	287.3	120.0	741.9	230.0	511.9	614.3	143.9	890.3	284.3	606.0	727.2					
25	45.2	223.5	82.8	140.7	211.1	60.9	301.3	108.2	193.1	289.7	103.8	642.3	230.0	412.3	618.4	124.6	770.8	284.3	486.5	729.7					
30	40.0	198.1	82.8	115.4	207.7	53.9	266.8	108.2	158.6	285.6	91.9	568.2	230.0	338.2	608.8	110.2	681.8	284.3	397.5	715.6					
35	36.1	178.4	82.8	95.7	200.9	48.5	240.1	108.2	131.9	276.9	82.6	510.8	230.0	280.8	589.6	99.1	612.9	284.3	328.6	690.1					
40	32.9	162.6	82.8	79.9	191.6	44.2	218.6	108.2	110.4	265.0	75.1	464.8	230.0	234.8	563.5	90.2	557.7	284.3	273.4	656.2					
45	30.2	149.6	82.8	66.9	180.5	40.6	201.0	108.2	92.8	250.7	69.1	427.1	230.0	197.1	532.1	82.9	512.5	284.3	228.2	616.1					
50	28.0	138.7	82.8	56.0	168.0	37.7	186.3	108.2	78.1	234.4	64.0	395.6	230.0	165.6	496.7	76.7	474.7	284.3	190.4	571.1					
55	26.2	129.5	82.8	46.7	154.2	35.1	173.8	108.2	65.6	216.5	59.6	368.8	230.0	138.8	458.0	71.5	442.5	284.3	158.2	522.2					
60	24.6	121.5	82.8	38.8	139.5	32.9	163.0	108.2	54.8	197.3	55.9	345.7	230.0	115.7	416.6	67.1	414.9	284.3	130.6	470.0					
65	23.2	114.6	82.8	31.8	124.0	31.0	153.6	108.2	45.4	177.1	52.6	325.6	230.0	95.6	372.9	63.2	390.7	284.3	106.4	415.1					
70	21.9	108.4	82.8	25.7	107.8	29.4	145.3	108.2	37.1	156.0	49.8	308.0	230.0	78.0	327.4	59.7	369.5	284.3	85.2	358.0					
75	20.8	103.0	82.8	20.2	91.0	27.9	138.0	108.2	29.8	134.1	47.3	292.3	230.0	62.3	280.2	56.7	350.7	284.3	66.4	29					

TABLE C7
Stage-Storage Data of SWM Facility

	Elev	Incr. Elev	Total Depth Above NWL	End Area	Volume
	(m)	(m)	(m)	(m2)	(m3)
Active Storage (Dry Pond)					
Top of Pond	100.44	0.24	1.04	2097	903
Interim	100.20	0.20	0.80	1379	498
Interim	100.00	0.20	0.60	716	299
Interim	99.80	0.20	0.40	618	166
Interim	99.60	0.20	0.20	521	52
Bottom	99.40	0.00	0.00	0	0
Sediment Forebay/Ditch					
Top of Forebay Berm	100.17	0.50	1.00	465	134
Interm	99.67	0.50	0.50	87	27
Bottom of sediment forebay	99.17	0.00	0.00	2	0
Maximum Active Storage =					903
Forebay Storage =					134
Total Pond Storage (Pond + Ditch + Sediment Forebay) =					1,037
Forebay Area as percent of total area =					15%

Chart C8: Stage-Storage Curve of SWM Facility




TABLE C9
Storage-Outflow Data of SWM Facility

811	100-year +20% Storm Volume (Forecasted from stage storage)
100.394	100-year+20% Storm Elev. (Forecasted based on design outflow from Table D6)
707	100-year Storm Volume (Forecasted from stage storage)
100.336	100-year Storm Elev. (Forecasted based on design outflow from Table D6)
504	5 -year Storm Volume (Forecasted from stage storage)
100.204	5-year Storm Elev. (Forecasted based on design outflow from Table D6)
458	2 -year Storm Volume (Forecasted from stage storage)
100.177	2-year Storm Elev. (Forecasted based on design outflow from Table D6)
376	Water Quality Volume (Forecasted from stage storage)
100.104	Water Quality Volume Elev. (Forecasted based on design outflow from Table D6)

1		2	
Vertical Rectangular Orifice		Broad-Crested Weir	
Width (m)	0.075	Length (m)	0.50
Height (m)	0.08	Height (m)	0.34
Area (m2):	0.00563	Area (m2):	0.17000
Coeff, C:	0.61	Coeff, C:	1.837
Orifice Inv:	99.50 m	Weir Inv:	100.10 m
Orifice Cen:	99.538 m		

WSE Elev	Comments	Quantity Volume (Note 1)	Head (Note 4)	Outflow	Head, H	Outflow	Total Flow	Storage
(m)		(m3)	(m)	(L/sec)	(m)	(L/sec)	(L/sec)	(m3)
100.44	Top of Pond	902.91	0.903	14.44	0.3400	312.2900	326.73	902.910
100.40		822.61	0.863	14.12	0.3000	275.5500	289.67	822.610
100.35		731.09	0.813	13.70	0.2500	229.6250	243.32	731.090
100.30		647.10	0.763	13.27	0.2000	183.7000	196.97	647.100
100.25		569.47	0.713	12.83	0.1500	137.7750	150.60	569.470
100.20		497.69	0.663	12.37	0.1000	91.8500	104.22	497.690
100.15		412.41	0.613	11.89	0.0500	45.9250	57.82	412.410
100.10		373.42	0.563	11.40			11.40	373.420
100.05		335.71	0.513	10.88			10.88	335.710
100.00		299.26	0.463	10.34			10.34	299.260
99.95		264.07	0.413	9.76			9.76	264.070
99.90		230.11	0.363	9.15			9.15	230.110
99.85		197.39	0.313	8.50			8.50	197.390
99.80		165.90	0.263	7.79			7.79	165.900
99.75		135.62	0.213	7.01			7.01	135.620
99.70		106.56	0.163	6.13			6.13	106.560
99.65		78.71	0.113	5.10			5.10	78.710
99.60		52.06	0.063	3.80			3.80	52.060
99.55		27.50	0.013	1.70			1.70	27.500
99.50		10.05						10.050
99.45		2.07						2.070
99.40	Bottom of Pond							

NOTES:
1) Quantity Storage values based on pond geometry and stage-storage data at 0.05m increments
2) Top of Pond = 100.44 m
3) WSE Interval = 0.050 m

Chart D10: Storage-Outflow Curves of SWM Facility




TABLE C11
SUMMARY OF WATER QUALITY VOLUMES OF SWM FACILITY

Item	Units	Pond 1		Comment
		Required	Provided	
Facility type		Extended Detention Dry Pond		
Drainage Area to Facility, A	ha	3.25		
Percent Imperviousness	%	52%		
Water Quality Volume Requirements, WQVV	m3/ha	110.8		Based on MOE Table 3.2
Extended Detention Volume Requirements	m3/ha	40.0		Based on 40 m3/ha
Extended Detention Volume Requirements	m3/ha	27.7		Based on 25% of WQCV
Extended Detention Volume Requirements	m3/ha	40.0		Maximum of 40 m3/h or 25% of WQCV
Permanent Pool Volume Requirements	m3/ha	0.0		WQCV - 40m3/ha for Wet Ponds, 0 for Dry Ponds
Permanent Pool Volume Req'd	m3	0	27	(WQCV - 40m3/ha) * A
Water Quality Volume Requirements	m3	360	605	Water Quality Volume = WQCV * A. Provided Volume Based on Permanent Pool + Extended Detention Volume
Extended Detention Volume, EDV	m3	130	605	Based on: 40m3/ha * A OR 25%*WQCV*A
Flood (or Quantity) Control Volume	m3	707	903	Based on City of Ottawa 100-year storm event
Extended Detention + Flood Control Vol		837	903	Extended Detention Is Included in Flood Control Volume for Wet Ponds
Forebay Volume	m3	0	134	Based on 20% of the Permanent Pool Volume per MOE, 0 for drypond
Main Cell Volume	m3	0	1037	Main Cell Volume = Permanent Pool - Forebay Volume

WATER QUALITY REQUIREMENTS FOR DRY PONDS BASED ON MOE REQUIREMENTS (From Table 3.2)

Protection Level	TSS Removal Target (%)	Drainage Area %IMP	Storage Required (m3/ha)	Stormwater Management Plan Type
Normal	70%	0	55	Dry Pond. Same Level of Protection as Wet Pond
		35	90	
		55	110	
		70	130	
		85	150	
		100	170	
Note: Storage Requirements for 0% and 100% are extrapolated				

TABLE C12**Area-Depth Data of SWM Facility**

Elev (m)	Depth of Ponding (m)	End Area (m ²)	Comments
100.44	1.04	2,097	Top of Pond
100.10	0.70	1,158	Interim
99.60	0.20	600	Interim
99.40			Bottom
Slope coefficient from the area-depth linear regression, C2 =			2762.0
Intercept from the area-depth linear regression, C3 =			377.3

TABLE C13
Drawdown Data of SWM Facility

Top of Pond Elev (m) =	100.44	<u>Comments</u>
Bottom of Pond Elev (m) =	99.40	
WQCV (m3) =	360	Water Quality Control Volume Based on MOE Criteria(Table 3.2)
WQCE (m) =	100.03	
WCD (m) =	0.63	
Orifice Type =	Vertical Rectangular Orifice	LOWER ORIFICE
Orifice Area (m2) =	0.0056	
Orifice Invert Elev (m) =	99.50	
Orifice Centroid Elev (m) =	99.538	
Orifice Discharge Coefficient =	0.61	
Weir Type =	Broad-Crested Weir	UPPER ORIFICE
Weir Area (m2) =	0.1700	
Weir Invert Elev (m) =	100.10	
Weir Width (m) =	0.50	
Weir Side Slopes (Z) =	1.00	
Weir Discharge Coefficient =	1.84	
C2 =	2,762	Slope coefficient from the area-depth linear regression
C3 =	377	
		Intercept from the area-depth linear regression

WSE Elev (m)	Active Storage Above NWL			Quality Orifice (Lower)			Quantity Orifice (Upper)			Drawdown Time		Outflow (L/sec)	Comments
	VOLUME (m3)	AREA (m2)	TOTAL DEPTH ABOVE NWL (m)	Height (m)	Area (m2)	Indiv Drawdown Time (hrs)	Height (m)	Area (m2)	Indiv Drawdown Time (hrs)	HOURS	DAYS		
100.44	903	2,097	0.94	0.94	0.0056	43.0	0.34	0.170	0.48	26.19	1.09	289.665	Top of Pond
100.40	823	1,914	0.90	0.90	0.0056	40.8	0.30	0.170	0.42	26.13	1.09	243.325	
100.35	731	1,746	0.85	0.85	0.0056	38.1	0.25	0.170	0.36	26.07	1.09	196.972	
100.30	647	1,613	0.80	0.80	0.0056	35.5	0.20	0.170	0.30	26.01	1.08	150.604	
100.25	569	1,492	0.75	0.75	0.0056	33.0	0.15	0.170	0.24	25.95	1.08	104.221	
100.20	498	1,379	0.70	0.70	0.0056	30.5	0.10	0.170	0.18	25.88	1.08	57.820	
100.15	412	1,258	0.65	0.65	0.0056	28.1	0.05	0.170	0.11	25.82	1.08	11.399	
100.10	373	1,158	0.60	0.60	0.0056	25.7		0.170		25.71	1.07	10.880	
100.05	336	1,067	0.55	0.55	0.0056	23.4		0.170		23.40	0.98	10.336	
100.00	299	986	0.50	0.50	0.0056	21.2		0.170		21.15	0.88	9.761	
99.95	264	912	0.45	0.45	0.0056	19.0		0.170		18.97	0.79	9.151	
99.90	230	846	0.40	0.40	0.0056	16.9		0.170		16.85	0.70	8.496	
99.85	197	791	0.35	0.35	0.0056	14.8		0.170		14.79	0.62	7.787	
99.80	166	742	0.30	0.30	0.0056	12.8		0.170		12.80	0.53	7.006	
99.75	136	701	0.25	0.25	0.0056	10.9		0.170		10.87	0.45	6.127	
99.70	107	665	0.20	0.20	0.0056	9.0		0.170		8.99	0.37	5.098	
99.65	79	632	0.15	0.15	0.0056	7.1		0.170		7.15	0.30	3.800	
99.60	52	600	0.10	0.10	0.0056	5.3		0.170		5.32	0.22	1.699	
99.55	28	534	0.05	0.05	0.0056	3.4		0.170		3.40	0.14		
99.50	10	304			0.0056			0.170					
99.45	2	144			0.0056			0.170					
99.40		60			0.0056			0.170					Bottom of Pond

NOTES:

- 2) Top of Pond = 100.44 m
3) WSE Interval = 0.05 m

Elev of WQ Volume =	100.034
Depth of WQ Volume =	0.634
Drawdown for WQ Volume =	27

$$t = \frac{0.66 C_2 h^{1.5} + 2 C_3 h^{0.5}}{2.75 A_o}$$

where:

- t = Drawdown time (seconds)
C2 = Slope coefficient from the area-depth linear regression
C3 = Intercept from the area-depth linear regression
Ao = Cross-sectional area of the orifice (m2)
h = Maximum water Elevation above the orifice

Equation 4.11 Drawdown Time.
(Page 4-58 MOE Stormwater Management
Planning and Design Manual)

TABLE C14
SEDIMENT REMOVAL FREQUENCY

SWM Facility Type	<u>Extended Detention Dry Pond</u>
Upstream Drainage Area (ha)	<u>3.251796</u>
Imperviousness (%)	<u>51.7</u>
Required Water Quality Vol (m3/ha)	<u>110.8</u>
Sediment Removal Frequency (years)	<u>33</u> (from Figure 6.1 Below based on WQV)

Figure 6.3: Storage Volume vs. Removal Frequency – for 70% Impervious Catchments




Table C15 - Full Flow Capacity of Channel-1

Channel Name:	Channel East		
Channel Type:	Trapezoidal		
Bottom Width, B =	0.8	m	
Side Slope (left) Z:1	3.0		
Side Slope (right) Z:1	3.0		
Max Depth, y	0.67	m	
			Flow Depth During WQF
			0.16 m
$T = B + Y*(Z_1 + Z_2)$	4.820	m	1.772 m
$A = Y/2*(B + T)$	1.8827	m ²	0.208332 m ²
$P = B + 2*Y*\sqrt{1+Z^2}$	5.0375	m	1.8246 m
$R = A/P$	0.37374	m	0.11418 m
Manning N,	0.050	dimensionless	(kentucky bluegrass, mowed 0.10 to 0.15m high)
	low		(depth of flow > 0.2m)
Longitudinal Slope	0.0050	m/m	
Full Flow Capacity	1381.5	L/sec	Water Quality Flow (WQF)
Full Flow Velocity	0.7	m/sec	WQF Velocity
			69.3 L/sec
			0.33 m/sec





Table C16 - Full Flow Capacity of Channel-2

Channel Name:	Channel West		
Channel Type:	Trapezoidal		
Bottom Width, B =	0.8	m	
Side Slope (left) Z:1	3.0		
Side Slope (right) Z:1	3.0		
Max Depth, y	0.50	m	
			Flow Depth During WQF
			0.17
			m
$T = B + Y*(Z_1 + Z_2)$	3.800	m	1.802
$A = Y/2*(B + T)$	1.15	m ²	0.217267
$P = B + 2*Y*\sqrt{1+Z^2}$	3.9623	m	1.8562
$R = A/P$	0.29024	m	0.11705
Manning N,	0.050	dimensionless	(kentucky bluegrass, mowed 0.10 to 0.15m high)
	low		(depth of flow > 0.2m)
Longitudinal Slope	0.0050	m/m	
Full Flow Capacity	712.9	L/sec	Water Quality Flow (WQF)
Full Flow Velocity	0.6	m/sec	73.5
			WQF Velocity
			0.34
			m/sec



Appendix D – Sewage Flows and Storage Volume Calculations Sheet

Week	Day	Peak	Peak Attendance	Residential	Sewage Flows	Residential	Total Sewage	Sewage Volume	Daily Treatment	Sewage Storage	
		Attendance	Used for Septic Design								
Week 1	Monday	0	0	6	0	3000.0	3000.0	0	3000.0	0	
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Sunday	200	200	6	7200	3000.0	10200.0	0.0	10000.0	200.0	
Week 2	Monday	0	0	6	0	3000.0	3000.0	200.0	3200.0	0.0	
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Saturday	130	130	6	4680	3000.0	7680.0	0.0	7680.0	0.0	
	Sunday	330	330	6	11880	3000.0	14880.0	0.0	10000.0	4880.0	
Week 3	Monday	0	0	6	0	3000.0	3000.0	4880.0	7880.0	0.0	
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Saturday	300	300	6	10800	3000.0	13800.0	0.0	10000.0	3800.0	
	Sunday	80	80	6	2880	3000.0	5880.0	3800.0	9680.0	0.0	
Week 4	Monday	0	0	6	0	3000.0	3000.0	0.0	3000.0	0.0	
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Saturday	100	100	6	3600	3000.0	6600.0	0.0	6600.0	0.0	
	Sunday	360	360	6	12960	3000.0	15960.0	0.0	10000.0	5960.0	
Week 5	Monday	0	0	6	0	3000.0	3000.0	5960.0	8960.0	0.0	
	Tuesday	30	30	6	1080	3000.0	4080.0	0.0	4080.0	0.0	
	Wednesday	30	30	6	1080	3000.0	4080.0	0.0	4080.0	0.0	
	Thursday	30	30	6	1080	3000.0	4080.0	0.0	4080.0	0.0	
	Friday	30	30	6	1080	3000.0	4080.0	0.0	4080.0	0.0	
	Saturday	30	30	6	1080	3000.0	4080.0	0.0	4080.0	0.0	
	Sunday	200	200	6	7200	3000.0	10200.0	0.0	10000.0	200.0	
Week 6	Monday	0	0	6	0	3000.0	3000.0	200.0	3200.0	0.0	
	Tuesday	30	30	6	1080	3000.0	4080.0	0.0	4080.0	0.0	
	Wednesday	30	30	6	1080	3000.0	4080.0	0.0	4080.0	0.0	
	Thursday	30	30	6	1080	3000.0	4080.0	0.0	4080.0	0.0	
	Friday	30	30	6	1080	3000.0	4080.0	0.0	4080.0	0.0	
	Saturday	500	500	6	18000	3000.0	21000.0	0.0	10000.0	11000.0	
	Sunday	5000	1000	6	36000	3000.0	39000.0	11000.0	10000.0	40000.0	
Week 7	Monday	0	0	6	0	3000.0	3000.0	40000.0	10000.0	33000.0	
	Tuesday	30	30	6	1080	3000.0	4080.0	33000.0	10000.0	27080.0	
	Wednesday	30	30	6	1080	3000.0	4080.0	27080.0	10000.0	21160.0	
	Thursday	30	30	6	1080	3000.0	4080.0	21160.0	10000.0	15240.0	
	Friday	30	30	6	1080	3000.0	4080.0	15240.0	10000.0	9320.0	
	Saturday	30	30	6	1080	3000.0	4080.0	9320.0	10000.0	3400.0	
	Sunday	350	350	6	12600	3000.0	15600.0	3400.0	10000.0	9000.0	
Week 8	Monday	0	0	6	0	3000.0	3000.0	9000.0	10000.0	2000.0	
	Tuesday	35	35	6	1260	3000.0	4260.0	2000.0	6260.0	0.0	
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0	
Week 9	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0	
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0	

Week 19	Monday	0	0	6	0	3000.0	3000.0	29000.0	10000.0	22000.0
	Tuesday	35	35	6	1260	3000.0	4260.0	22000.0	10000.0	16260.0
	Wednesday	35	35	6	1260	3000.0	4260.0	16260.0	10000.0	10520.0
	Thursday	35	35	6	1260	3000.0	4260.0	10520.0	10000.0	4780.0
	Friday	35	35	6	1260	3000.0	4260.0	4780.0	9040.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
Week 20	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
Week 21	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Sunday	1000	1000	6	36000	3000.0	39000.0	0.0	10000.0	29000.0
Week 22	Monday	0	0	6	0	3000.0	3000.0	29000.0	10000.0	22000.0
	Tuesday	35	35	6	1260	3000.0	4260.0	22000.0	10000.0	16260.0
	Wednesday	35	35	6	1260	3000.0	4260.0	16260.0	10000.0	10520.0
	Thursday	35	35	6	1260	3000.0	4260.0	10520.0	10000.0	4780.0
	Friday	35	35	6	1260	3000.0	4260.0	4780.0	9040.0	0.0
	Saturday	100	100	6	3600	3000.0	6600.0	0.0	6600.0	0.0
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
Week 23	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
Week 24	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
Week 25	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	300	300	6	10800	3000.0	13800.0	0.0	10000.0	3800.0
	Sunday	560	560	6	20160	3000.0	23160.0	3800.0	10000.0	16960.0
Week 26	Monday	335	335	6	12060	3000.0	15060.0	16960.0	10000.0	22020.0
	Tuesday	335	335	6	12060	3000.0	15060.0	22020.0	10000.0	27080.0
	Wednesday	335	335	6	12060	3000.0	15060.0	27080.0	10000.0	32140.0
	Thursday	335	335	6	12060	3000.0	15060.0	32140.0	10000.0	37200.0
	Friday	35	35	6	1260	3000.0	4260.0	37200.0	10000.0	31460.0
	Saturday	35	35	6	1260	3000.0	4260.0	31460.0	10000.0	25720.0
	Sunday	260	260	6	9360	3000.0	12360.0	25720.0	10000.0	28080.0
Week 27	Monday	185	185	6	6660	3000.0	9660.0	28080.0	10000.0	27740.0
	Tuesday	185	185	6	6660	3000.0	9660.0	27740.0	10000.0	27400.0
	Wednesday	185	185	6	6660	3000.0	9660.0	27400.0	10000.0	27060.0
	Thursday	185	185	6	6660	3000.0	9660.0	27060.0	10000.0	26720.0
	Friday	185	185	6	6660	3000.0	9660.0	26720.0	10000.0	26380.0
	Saturday	35	35	6	1260	3000.0	4260.0	26380.0	10000.0	20640.0
	Sunday	360	360	6	12960	3000.0	15960.0	20640.0	10000.0	26600.0
Week 28	Monday	100	100	6	3600	3000.0	6600.0	26600.0	10000.0	23200.0
	Tuesday	100	100	6	3600	3000.0	6600.0	23200.0	10000.0	19800.0

Week 29	Wednesday	100	100	6	3600	3000.0	6600.0	19800.0	10000.0	16400.0
	Thursday	100	100	6	3600	3000.0	6600.0	16400.0	10000.0	13000.0
	Friday	100	100	6	3600	3000.0	6600.0	13000.0	10000.0	9600.0
	Saturday	35	35	6	1260	3000.0	4260.0	9600.0	10000.0	3860.0
	Sunday	260	260	6	9360	3000.0	12360.0	3860.0	10000.0	6220.0
	Monday	0	0	6	0	3000.0	3000.0	6220.0	9220.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
Week 30	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	235	235	6	8460	3000.0	11460.0	0.0	10000.0	1460.0
	Sunday	460	460	6	16560	3000.0	19560.0	1460.0	10000.0	11020.0
	Monday	0	0	6	0	3000.0	3000.0	11020.0	10000.0	4020.0
	Tuesday	35	35	6	1260	3000.0	4260.0	4020.0	8280.0	0.0
Week 31	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	235	235	6	8460	3000.0	11460.0	0.0	10000.0	1460.0
	Sunday	460	460	6	16560	3000.0	19560.0	1460.0	10000.0	11020.0
	Monday	235	235	6	8460	3000.0	11460.0	11020.0	10000.0	12480.0
	Tuesday	235	235	6	8460	3000.0	11460.0	12480.0	10000.0	13940.0
Week 32	Wednesday	235	235	6	8460	3000.0	11460.0	13940.0	10000.0	15400.0
	Thursday	235	235	6	8460	3000.0	11460.0	15400.0	10000.0	16860.0
	Friday	235	235	6	8460	3000.0	11460.0	16860.0	10000.0	18320.0
	Saturday	35	35	6	1260	3000.0	4260.0	18320.0	10000.0	12580.0
	Sunday	260	260	6	9360	3000.0	12360.0	12580.0	10000.0	14940.0
	Monday	0	0	6	0	3000.0	3000.0	14940.0	10000.0	7940.0
	Tuesday	35	35	6	1260	3000.0	4260.0	7940.0	10000.0	2200.0
Week 33	Wednesday	35	35	6	1260	3000.0	4260.0	2200.0	6460.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
Week 34	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
Week 35	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	100	100	6	3600	3000.0	6600.0	0.0	6600.0	0.0
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
Week 36	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
Week 37	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0

Week	Day	Week 37		Week 38		Week 39		Week 40		Week 41		Week 42		Week 43		Week 44		Week 45		Week 46	
		Start	End	Start	End	Start	End	Start	End	Start	End	Start	End	Start	End	Start	End	Start	End	Start	End
Week 38	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0											
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0											
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
Week 39	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0											
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0											
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
Week 40	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0											
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0											
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
Week 41	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0											
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0											
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
Week 42	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0											
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0											
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
Week 43	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Saturday	185	185	6	6660	3000.0	9660.0	0.0	9660.0	0.0											
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0											
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0											
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
Week 44	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Sunday	185	185	6	6660	3000.0	9660.0	0.0	9660.0	0.0											
	Monday	0	0	6	0	3000.0	3000.0	0.0	3000.0	0.0											
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
Week 45	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0											
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0											
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
Week 46	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0											
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0											
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0											

Week	Day	Week 1		Week 2		Week 3		Week 4		Total
		Actual	Target	Actual	Target	Actual	Target	Actual	Target	
Week 47	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
Week 48	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
Week 49	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
Week 50	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
Week 51	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
Week 52	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
	Monday	0	0	6	0	3000.0	3000.0	2360.0	5360.0	0.0
	Tuesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Wednesday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Thursday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Friday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Saturday	35	35	6	1260	3000.0	4260.0	0.0	4260.0	0.0
	Sunday	260	260	6	9360	3000.0	12360.0	0.0	10000.0	2360.0
		97	86		3111.4		6111.4			4000.0</

Appendix E – Additional Information

Requirements

The following is to be brought to a Client Service Centre:

- 1) Application form for Site Plan Control: Application for New Development, Manager Approval, Public Consultation which can be found at:
http://app06.ottawa.ca/online_services/forms/ds/site_plan_control_en.pdf
- 2) Application Fee Of \$23,483.66
 - \$21,508.66 for Site Plan Application Type
 - \$ 1,000 for Engineering Design Review and Inspection Fee (unless you think should be more)
 - \$975 Conservation Authority Fee
- 3) Plans
 - Street level visualization of the proposed development (.jpg or .pdf format) - optional
 - Survey Plan (2 copies)
 - Site Plan (10 copies)
 - Landscape Plan (10 copies) – prepared by a Landscape Architect
 - Architectural Elevation Drawings – including dimensions & materials (3 copies)
 - Grade Control and Drainage Plan (5 copies)
 - Site Servicing Plan (5 copies)
 - Stormwater Management Plan (5 copies)
 - Erosion and Sediment Control Plan (5 copies)

All plans and drawings must be produced on A1-sized paper and folded to 21.6 cm x 27.9 cm (8½" x 11"). A scale of 1:200 is recommended for the Site and Landscape Plans.

Studies

- Planning Rationale including Design Statement and Integrated Environmental Review Statement (3 copies)
 - Minimum Distance Separation (MDS) (3 copies) – for institutional uses a review of a 2km radius is required.
 - Geotechnical Study (3 copies)
 - Hydrogeological and Terrain Analysis (3 copies)
 - Reasonable Use Assessment (if flows will exceed 10,000 L/d (3 copies)
 - Stormwater Management Brief (3 copies)
 - Environmental Impact Statement (3 copies)
 - Tree Conservation Report (3 copies)
 - Transportation Impact Brief (3 copies)
- 4) Electronic copies of all required studies and plans must be supplied on a Compact Disk on memory stick in Adobe .pdf format. These documents will be made publicly available on the City's Development Application Search Tool.

Comments

- 1) For more details on Development Applications can refer to links [Development application review process](#), [Guide to Preparing studies and Plans](#).
- 2) Recommend that you contact the Ward Councillor, who is Scott Moffatt (scott.moffatt@ottawa.ca or 613-580-2491), neighbours who may be impacted by the

development and the following Community groups, before submitting an application (as they will be circulated when the application is provided):

Country Club Village Community Association

Attn: Denyse MacKenzie

Phone Day: 613-253-0026

denysmackenzie@xplornet.ca

6 Links Drive South

Ashton, Ontario

K0A 1B0

Richmond Village Association

Attn: John Shearer

Phone Day: 613-838-4830

johnshearer@richmondvillage.ca; davidproulx@richmondvillage.ca

208 Cedarstone Street

Richmond, Ontario


K0A 2Z0

- 3) Comments from Rideau Valley Conservation Authority (RVCA):
 - There is a ditch running along the front of the property, identified as a watercourse, tributary to the Jack River. Development is to be setback 30 metres from the watercourse. Any new crossings/relocation of culverts will be subject to a permit from the RVCA.
 - Additionally, Stormwater Management will need to demonstrate that water quality protection is maintain 80% TSS removal.
 - If the site is to be on Private Services, it may be subject to review and permitting through the Ottawa Septic Office (or MOE based on sizing)
 - Stormwater will need to be controlled post to pre for the 5 year and 100 year events.
 - the proponent will need to provide 80% TSS removal for the proposal.
 - For private on-site wastewater systems, the flows for this type of development often exceed 10,000 L/day and therefore may require approval from Ministry of the Environment and Climate Change (MOECC). If flows are less than 10,000 L per day, the Ottawa Septic System Office (OSSO) would be involved with the review through the RVCA. A permit from the OSSO or an Environmental Compliance Approval (ECA) from MOECC is normally a requirement before completion granting Site Plan Approval, to show that the proposed on-site system is consistent with the site plan.
- 4) Franktown Road is an arterial road. Per the City's OP a right-of-way protection of 30m is required; i.e. 15m from the existing centreline of the road to the property line.
- 5) The site access should be designed and implemented in accordance to the City's Private Approach By-law.
- 6) Depending on the interface between the Entrance Landscape Courtyard and Franktown Road Right of Way, may want to consider a landscaped buffer between the courtyard and the front property line. The design will need to take into consideration that there is a ditch.
- 7) If you have any questions regarding the Transportation Impact Brief, please feel free to contact Amira directly @ amira.shehata@ottawa.ca, 613-580-2424 x 27737.
- 8) Planning Rationale:

- Reference to policies of the Official Plan, particularly policies 3.7.2 – General Rural Area, 3.2 – Natural Environment, 4.6.4 - Scenic Entry Route, and 4.7.5 Protection of Groundwater Resources
 - References to Zoning By-law, particularly Rural Exceptions (Section 240) for RI[643r] and RI[644r], Rural Institutional Zone (Sec 223-224), Rural Countryside Zone (Section 227-228), Accessory uses, Buildings and Structures (Section 55), Place of Worship (Section 96), parking, Queuing and Loading Provisions (Section 100-114)
- 9) Hydrogeological:
- Must address the fact that the subject site is within a Wellhead Protection Area
 - Will need to drill well and test it as per MOECC guidelines as a minimum (more testing may be required depending on the scope of the project—this should be discussed with the City prior to starting the hydrogeological investigation).
 - Will need to determine how MOECC defines what the City calls an accessory rooming house and what criteria to apply for the Drinking Water System.
 - Will need to include a reasonable use assessment if flows exceed 10,000 L/d.
 - Will want to start discussions with MOECC as soon as possible because it can take up to a year for their approval.
- 10) Require Permit To Take Water if any water taking exceeds 50,000 litres per day.
- 11) Not sure if MOECC will need to approve stormwater but most likely will need to approve the sewage system (if the flows >10,000 L/d). Registration with either the MOECC or the City's Health Dept. will be required depending on the category of the Drinking Water System.
- 12) Site Plan:
- To show fire route
- 13) Environmental Impact Statement (EIS)
- The property is indicated in Schedule L2 as part of our Natural Heritage System due to the significant woodlands which triggers an EIS along with the potential for Endangered and Threatened Species Habitat.
 - The EIS is to conform with the Council-approved guidelines which are available here: http://documents.ottawa.ca/sites/documents.ottawa.ca/files/documents/eis_guidelines2015_en.pdf
 - Consultation with the Ministry of Natural Resources and Forestry very important to ensure all endangered and threatened species are considered and some of these have very particular survey requirements, for example the Whip-poor-will.
 - Should start before the end of June due to seasonal studies being required.
 - The EIS will need to demonstrate that their project will not have a significant negative impact on the significant woodlands and that any endangered and/or threatened species habitat present is protected as per MNRF requirements.
- 14) Tree Conservation Report (TCR) is required to demonstrate how trees will be retained and incorporated into the landscaping.
- could be combined with the EIS to simplify the coordination between the EIS and TCR reports.
- 15) The error in the zoning by-law for exception 643r has been corrected with the removal of the 'h'.
- 16) It appears that no development buildings are in the area of Archaeological Potential so an Archaeological Resource Assessment will not be required.
- 17) Will there be a connection between this property and the residential property in the northeast corner from the 6688 Franktown?

18) Design has changed significantly from the Concept Plan provided with the rezoning application, from the pre-consult in June 2005, and the downscaling noted in May of 2016..

- Appears to be more hardscape and less features protected.
- More parking (200 spaces)
- Slightly larger building
- Less uses? (previously proposed classroom, gift shop, office, main hall, conference room, storage, rooming house, pagoda
- Private Approach - will it conform to the Private Approach By-law?
- sculptures





Ottawa Septic Bureau des systèmes
System Office septiques d'Ottawa

3889 Rideau Valley Drive Box 599 Manotick, ON K4M 1A5

Phone: 613-692-3571 1-800-267-3504 Fax: 613-692-1507

Email: 'septic@rvca.ca'

Address of property: 6688 Frankton Township: OSG HUN-GLO-FIT-CUM-NEP-GOU-RID-KAN

Contact for pickup: International Buddhist Phone# / Email: (1) bigferg.li 2 bigpro.ca

INFORMATION FOR OWNER/APPLICANT

Attached is your Sewage System Permit. A minimum of two inspections are required before your proposed sewage system can be approved for use (additional inspections may be required for clay soils/bedrock and/or re-inspections). Inspections must be requested in writing. Please see attached:

- Inspection fax request form (all inspections MUST be requested in writing)
- As-built components and drawing form
- Copy of the approved application and schedule pages
- Approved Part 8 permit (applicant copy – YELLOW)(city copy#2 – PINK ** Agent Deliver Direct To City**)

PLEASE NOTE

- A permit is valid for 12 months from the original date of issuance noted in "permit date". If lapsed, it may be renewed only once for a period of 12 months from the date of expiry.

- No person shall make a material change or cause a material change to be made to a plan, specification, document or other information on the basis of which a permit was issued without notifying, filing details with and obtaining the authorization of the Chief Building Official. (Building Code Act 1992, c.23, s.8(12))

Sewage System Permit Construction Requirements

1. Clay Soils/Bedrock only (if required per issued Approval)

In clay soils/bedrock, a site preparation inspection is required. The total contact area must be properly prepared. Scarification must be done under dry conditions prior to importing leaching bed fill.

2. Installation Inspection – 2nd inspection

When the sewage system is substantially completed (i.e., before the final fill is placed over the septic tank and leaching bed system) an installation inspection is required. Prior to any inspection request, the following must be submitted:

- "as-built components" and "as-built drawings" — see attached form
- "engineer letter" — if the system is engineered
- grain size analysis and weight bills for all Filter Media types of septic systems
- Weight bills for washed septic stone, where applicable
- Maintenance/service contract for treatment unit installed

3. Final Grading Inspection – 3rd inspection

When construction of the sewage system is complete, a final grading inspection is required. Before a Certificate of Completion can be issued, the following must be complete:

- The leaching bed and septic tank must be covered with sand fill and topsoil and graded accordingly
- All conditions of the Sewage System Permit & comments on the installation inspection report must be met
- The depth of cover & material type must be identified by inspection pipes or holes placed over trenches at 4 corners of bed
- The 4 corners of the bed must be staked

May 2016



SEPTIC APPLICATION
18-548
REQUIRED FOR ALL
INQUIRIES

Inspection Request Form

Complete and fax to: 613-692-1507 or e-mail: septic@rvca.ca

Section A. Property and General Information			
Date Submitted		Septic File Number:	
Civic Address			
Former Township	<input type="checkbox"/> Osgoode <input type="checkbox"/> Cumberland <input type="checkbox"/> Goulbourn <input type="checkbox"/> Torbolton <input type="checkbox"/> Nepean		
	<input type="checkbox"/> Huntley <input type="checkbox"/> Rideau <input type="checkbox"/> Gloucester <input type="checkbox"/> Fitzroy <input type="checkbox"/> Kanata <input type="checkbox"/> Ottawa		
Property Owner			

Section B. Requestor Information			
Name of Requestor		Phone Number:	
E-mail		Fax Number:	
I am the (check one)	<input type="checkbox"/> Installer <input type="checkbox"/> Engineer <input type="checkbox"/> Property Owner		

Section C. I am Requesting the following:		
<input type="checkbox"/> 1 st - Subgrade (If required - check one): <input type="checkbox"/> Scarification <input type="checkbox"/> Clay Seal <input type="checkbox"/> Subgrade	<input type="checkbox"/> 2 nd - Installation Inspection (Check all that apply) Refer to attached: <input type="checkbox"/> As-Built Components Page <input type="checkbox"/> As-Built Drawing <input type="checkbox"/> Engineers Letter <input type="checkbox"/> Filter Media Bills <input type="checkbox"/> Grain Size Analysis <input type="checkbox"/> Maintenance Agreement <input type="checkbox"/> ESA Permit Number: <input type="text"/>	<input type="checkbox"/> 3 rd - Final Grade Inspection Note: Topsoil must be applied unless winter conditions exist at Director's discretion All deficiencies must be addressed from installation report
Notes/Comments		

Section D. Re-inspection			
<input type="checkbox"/> Re-inspection - 1 st call	<input type="checkbox"/> Re-inspection Request - 2 nd call		
	Note: Re-inspection fee applies on requests for same deficiency - Please provide payment information below		
	Card Type:	<input type="checkbox"/> Mastercard	<input type="checkbox"/> Visa
	Card Number:		Expiry:
	Cardholder Name:		
Notes/Comments			

Please Note:

- 3-5 business day turn around for inspections
- OSSO file will be given to inspector upon receipt of this request form
- PRIORITY will be given to requests that have septic file/permit numbers

AS-BUILT COMPONENTS

(required prior to installation inspection)

SEPTIC PERMIT NO.

SEPTIC APPLICATION

18-548

REQUIRED FOR ALL PROPERTIES

Elevations of installed system must be supplied with this report (in reference to the TBM).

Exact size and location of all structures, well(s) and system(s) and its components must be shown (including neighbouring lots).

Septic/Holding Tank: _____ L

Manufacturer: _____

☐ concrete ☐ plastic ☐ other

Filter: ☐ no ☐ yes _____ make

Treatment: Make _____

Unit: Model _____

Diameter of pipes _____ mm/inches

Make of pipes: _____

Ends: ☐ capped ☐ interconnected

Number of runs: _____ m

Length of runs: _____ m

Stone area _____ m²

Filter media:

Amount Purchased: _____ kg

Date Purchased: _____

Supplier: _____

Grain/size analysis by: _____

Analysis dated: _____

Stone:

Amount Purchased: _____ kg

Date Purchased: _____

Supplier: _____

Name of owner: _____

Installer: _____

Installer Signature: _____

License Number: _____

Date of Installation: _____

Pump Systems:

ESA Permit #: _____

Volume discharge rates: _____ /15min

Alarm location: _____

Dimension of Pump Chamber: _____

Height of Float Switch: _____

Grease Interceptor:


☐ no ☐ yes Size: _____

Location: _____

*** Grain Size Analysis and weight bills must be supplied with this report.**

All rights reserved. No part of this work may be reproduced or used in any form without the prior written permission of the copyright holder.

NOTE: All as-built drawings must be cross-referenced to the house in two (2) locations.



NOTE:

Drilled well • 15 metres to septic tank
• 15 – 18 metres to distribution pipes

Dug well • 15 metres septic tank
• 30 – 33 metres to distribution pipes

AS-BUILT DRAWING

SEPTIC APPLICATION
18-548
REQUIRED FOR ALL
INQUIRIES

N

Scale: 1 = 1 metre

SEPTIC PERMIT NO.


Application for a Permit to Construct or Demolish

This form is authorized under subsection 8(1.1) of the Building Code Act, 1992

For use by Principal Authority			
Application number:		Permit number (if different):	
Date received:		Roll number:	
OTTAWA SEPTIC SYSTEM OFFICE			
Application submitted to: _____ (Name of municipality, upper-tier municipality, board of health or conservation authority)			
A. Project information			
Building number, street name 6688 Franktown Road		Unit number	Lot/con. Part Lot 19, Con 3
Municipality Ottawa, Geographic Township of Goulbourn	Postal code K0A 2Z0	Plan number/other description	
Project value est. \$		Area of work (m ²) ~924 sq.m	
B. Purpose of application			
<input checked="" type="radio"/> New construction	<input type="radio"/> Addition to an existing building	<input type="radio"/> Alteration/repair	<input type="radio"/> Demolition
Proposed use of building Assembly/Place of Worship		Current use of building N/A	
Description of proposed work Proposed development of a Class 4 leaching bed with a level IV treatment unit, and 'Type A' dispersal bed for the future development of a place of worship. Leaching bed designed, as per this application, is intended to service the interim facility. Some components of the system which are expected to form part of a larger approval for the final build out of the development (to be approved by MECP) have been oversized for this reason.			
C. Applicant			
Applicant is:		Owner or <input checked="" type="radio"/> Authorized agent of owner	
Last name Leblanc	First name Patrick	Corporation or partnership McIntosh Perry Consulting Engineers	
Street address 115 Walgreen Road, R.R. #3		Unit number	Lot/con.
Municipality Carp	Postal code K0A 1L0	Province Ontario	E-mail p.leblanc@mcintoshperry.com
Telephone number (613) 714-4586	Fax (613) 836-3742	Cell number (613) 229-5863	
D. Owner (if different from applicant)			
Last name		First name	Corporation or partnership International Buddhist Progress Society of Ottawa-Carleton
Street address 1950 Scott Street		Unit number	Lot/con.
Municipality City of Ottawa	Postal code K1Z 8L8	Province Ontario	E-mail bingfeng.li@bingpro.ca
Telephone number (613) 759-8111	Fax ()	Cell number ()	

Application for a Permit to Construct or Demolish – Effective January 1, 2014


OSSO version June 2014

E. Builder (optional)				
Last name		First name	Corporation or partnership (if applicable)	
Street address			Unit number	Lot/con.
Municipality	Postal code	Province	E-mail	
Telephone number ()	Fax ()		Cell number ()	
F. Tarion Warranty Corporation (Ontario New Home Warranty Program)				
i. Is proposed construction for a new home as defined in the <i>Ontario New Home Warranties Plan Act</i> ? If no, go to section G.			Yes	No <input checked="" type="checkbox"/>
ii. Is registration required under the <i>Ontario New Home Warranties Plan Act</i> ?			Yes	No <input checked="" type="checkbox"/>
iii. If yes to (ii) provide registration number(s): _____				
G. Required Schedules				
i) Attach Schedule 1 for each individual who reviews and takes responsibility for design activities.				
ii) Attach Schedule 2 where application is to construct on-site, install or repair a sewage system.				
H. Completeness and compliance with applicable law				
i) This application meets all the requirements of clauses 1.3.1.3 (5) (a) to (d) of Division C of the Building Code (the application is made in the correct form and by the owner or authorized agent, all applicable fields have been completed on the application and required schedules, and all required schedules are submitted).			Yes <input checked="" type="checkbox"/>	No
Payment has been made of all fees that are required, under the applicable by-law, resolution or regulation made under clause 7(1)(c) of the <i>Building Code Act, 1992</i> , to be paid when the application is made.			Yes <input checked="" type="checkbox"/>	No
ii) This application is accompanied by the plans and specifications prescribed by the applicable by-law, resolution or regulation made under clause 7(1)(b) of the <i>Building Code Act, 1992</i> .			Yes <input checked="" type="checkbox"/>	No
iii) This application is accompanied by the information and documents prescribed by the applicable by-law, resolution or regulation made under clause 7(1)(b) of the <i>Building Code Act, 1992</i> which enable the chief building official to determine whether the proposed building, construction or demolition will contravene any applicable law.			Yes <input checked="" type="checkbox"/>	No
iv) The proposed building, construction or demolition will not contravene any applicable law.			Yes <input checked="" type="checkbox"/>	No
I. Declaration of applicant				
I, <u>Patrick Leblanc</u> declare that:				
(print name)				
1. The information contained in this application, attached schedules, attached plans and specifications, and other attached documentation is true to the best of my knowledge.				
2. If the owner is a corporation or partnership, I have the authority to bind the corporation or partnership.				
Date April 23, 2019		Signature of applicant 		

Personal information contained in this form and schedules is collected under the authority of subsection 8(1.1) of the *Building Code Act, 1992*, and will be used in the administration and enforcement of the *Building Code Act, 1992*. Questions about the collection of personal information may be addressed to: a) the Chief Building Official of the municipality or upper-tier municipality to which this application is being made, or, b) the inspector having the powers and duties of a chief building official in relation to sewage systems or plumbing for an upper-tier municipality, board of health or conservation authority to whom this application is made, or, c) Director, Building and Development Branch, Ministry of Municipal Affairs and Housing 777 Bay St., 2nd Floor. Toronto, M5G 2E5 (416) 585-6666.

Schedule 1: Designer Information

Use one form for each individual who reviews and takes responsibility for design activities with respect to the project.

A. Project Information			
Building number, street name 6688 Franktown Road		Unit no.	Lot/con. Part Lot 19, Con 3
Municipality City of Ottawa, Geographic Township of Goulbourn	Postal code K0A 2Z0	Plan number/ other description	
B. Individual who reviews and takes responsibility for design activities			
Name Patrick Leblanc		Firm McIntosh Perry Consulting Engineers	
Street address 115 Walgreen Road, R.R. #3		Unit no.	Lot/con.
Municipality Carp	Postal code K0A 1L0	Province Ontario	E-mail p.leblanc@mcintoshperry.com
Telephone number (613) 714-4586	Fax number (613) 836-3742	Cell number (613) 229-5863	
C. Design activities undertaken by individual identified in Section B. [Building Code Table 3.5.2.1. of Division C]			
House Small Buildings Large Buildings Complex Buildings	HVAC – House Building Services Detection, Lighting and Power Fire Protection	Building Structural Plumbing – House Plumbing – All Buildings <u>On-site Sewage Systems</u>	
Description of designer's work Proposed development of a Class 4 leaching bed with a Level IV treatment unit, and 'Type A' dispersal bed for the interim facility which will consist of a place of worship.			
D. Declaration of Designer			
I, <u>Patrick Leblanc</u> declare that (choose one as appropriate): (print name)			
I review and take responsibility for the design work on behalf of a firm registered under subsection 3.2.4. of Division C, of the Building Code. I am qualified, and the firm is registered, in the appropriate classes/categories. Individual BCIN: _____ Firm BCIN: _____			
I review and take responsibility for the design and am qualified in the appropriate category as an "other designer" under subsection 3.2.5. of Division C, of the Building Code. Individual BCIN: _____ Basis for exemption from registration: _____			
The design work is exempt from the registration and qualification requirements of the Building Code. Basis for exemption from registration and qualification: <u>P.Eng. (Licence #100141438)</u>			
I certify that: 1. The information contained in this schedule is true to the best of my knowledge. 2. I have submitted this application with the knowledge and consent of the firm.			
Date April 23, 2019		Signature of Designer 	

NOTE:


- For the purposes of this form, "individual" means the "person" referred to in Clause 3.2.4.7(1) (c) of Division C, Article 3.2.5.1. of Division C, and all other persons who are exempt from qualification under Subsections 3.2.4. and 3.2.5. of Division C.
- Schedule 1 is not required to be completed by a holder of a license, temporary license, or a certificate of practice, issued by the Ontario Association of Architects. Schedule 1 is also not required to be completed by a holder of a license to practise, a limited license to practise, or a certificate of authorization, issued by the Association of Professional Engineers of Ontario.

Schedule 2: Sewage System Installer Information

A. Project Information			
Building number, street name		6688 Franktown Road	
Municipality	Ottawa, Geographic Township of Goulbourn	Postal code	K0A 2Z0
Unit number		Lot/con.	
		Part Lot 19, Con 3	
B. Sewage system installer			
Is the installer of the sewage system engaged in the business of constructing on-site, installing, repairing, servicing, cleaning or emptying sewage systems, in accordance with Building Code Article 3.3.1.1, Division C?			
Yes (Continue to Section C)		No (Continue to Section E)	
		X Installer unknown at time of application (Continue to Section E)	
C. Registered installer information (where answer to B is "Yes")			
Name		BCIN	
Street address		Unit number	Lot/con.
Municipality	Postal code	Province	E-mail
Telephone number ()	Fax ()	Cell number ()	
D. Qualified supervisor information (where answer to section B is "Yes")			
Name of qualified supervisor(s)		Building Code Identification Number (BCIN)	
E. Declaration of Applicant:			
<p>Patrick Leblanc</p> <p>I _____ declare that:</p> <p style="text-align: center;">(print name)</p> <p>I am the applicant for the permit to construct the sewage system. If the installer is unknown at time of application, I shall submit a new Schedule 2 prior to construction when the installer is known;</p> <p><u>OR</u></p> <p>I am the holder of the permit to construct the sewage system, and am submitting a new Schedule 2, now that the installer is known.</p> <p>I certify that:</p> <ol style="list-style-type: none"> The information contained in this schedule is true to the best of my knowledge. If the owner is a corporation or partnership, I have the authority to bind the corporation or partnership. <div style="display: flex; justify-content: space-between; margin-top: 20px;"> <div>Date April 23, 2019</div> <div>Signature of applicant </div> </div>			



Schedule 4
Proposed Services
Complete Sections 1 thru 7



1. Engineered

- ☒ Yes
☐ No

2. Water supply

- ☒ Proposed
☐ Existing

3. Type of work proposed

- ☒ New Installation
☐ Replacement
☐ Alteration

4. Type of Well

- ☐ Dug/bored/Sandpoint well
☒ Drilled well
☐ Municipal
☐ Other

5. Residential Sewage Design Flow Info.

Bedrooms _____

House (floor area) _____ m²

People _____

Total Fixture Units _____ (Schedule 8)

Residential Flow _____ L/day

6. Sewage Design Flow Other Occupancies

Design Flow 9,999 _____ L/day

Detailed sewage flow calculations:

Assembly Hall, Kitchen Facilities Provided: 36L/day/seat or person

Assume Max Occupancy in one day is 277 People

Flow (Q) = (36L/day/Person) * (277 People) = 9,972 L/day

7. Type of System

- ☒ Treatment Unit Waterloo Biofilter Baskets (2x)
☐ Class 2 – Leaching Pit
☐ Class 3 – Cesspool
☐ Class 4 – Shallow Buried Trench

☐ Class 4 – Trench (Schedule 9)

- ☐ Fully raised
☐ Partially raised
☐ In-ground

☐ Class 4 – Filter Media (Schedule 10)

- ☐ Fully raised
☐ Partially raised
☐ In-ground

☐ Class 4 – BMEC Area Bed (Schedule 11)

- ☐ Fully raised
☐ Partially raised
☐ In-ground

☒ Class 4 – “Type A” Dispersal (Schedule 13)

- ☒ Fully raised
☐ Partially raised
☐ In-ground


☐ Class 4 – “Type B” Dispersal (Schedule 14)

- ☐ Fully raised
☐ Partially raised
☐ In-ground

☐ Class 5 – Holding Tank (9000L min)

☐ Tank/Treatment Unit/Pump Chamber ONLY

☐ Effluent Filter/Risers ONLY



Schedule 5
Sewage System Details

Do Not Complete
Permit No. _____
Revision No. _____
Date _____
18-548
SEPTIC APPLICATION
REQUIRED FOR ALL
INQUIRIES

Type of System Class 4 Fully Raised Type A Dispersal Bed System (Schedule 4)
Septic/Holding Tank Size: 19,998 (min) Litres Make: MacGregor Concrete Products
Septic Tank Effluent Filter Make: Polylok PL-625 or Equivalent Model: MAC-23000-1P

Treatment Unit – Make & Model Waterloo Biofilter (2x Biofilter Medium Filled Baskets)

Number of Units: 1

Other: _____

Refer to Typical Drawing # E

Pump(s) required yes

Mantle Information:

Pump Rate as per Waterloo

Native or imported = 15m in S-E direction(s)

Note: Alarm required for all
pumping systems

Slope subgrade N/A % slope
_____ direction(s)

Site to be Scarified (If clay) YES / (NO)
Clay Seal Required (If bedrock) YES / (NO)

☐ Trench

Distribution Pipe Length _____ m

Loading Area _____ m²

Type of Chamber _____

Length of Chamber _____ m

☐ BMEC Area Bed

☒ Type A

☐ Type B

Stone _____ m²

Sand _____ m²

Pipe _____ m

Linear Loading _____ L/m²

☐ Shallow Buried Trench

Pipe Length _____ m

☐ Filter Media Bed

Stone _____ m²

Extended Base _____ m²

Pipe _____ m

Weight of Filter Media _____ Kg

Loading Area _____ m²

☐ Tank/Treatment Unit/Pump Chamber Replacement ONLY

☐ Effluent Filter & Riser ONLY

Construction Notes:

All tanks, piping and connections below original grade shall be sealed to prevent groundwater infiltration. Additionally, floatation protection shall be reviewed by contractor prior to installation for all tanks and accounted for during installation if determined to be required during review.



Schedule 6

Soil and Water Table Information
(Minimum depth of test pit: 2 metres)

R.V.C.A. RECEIVED
APR 23 2019

Do Not Complete

Permit No _____

Revision No _____

Date _____

SEPTIC APPLICATION

18-548

REQUIRED FOR ALL
INQUIRIES

Name of Applicant/Agent: Patrick Leblanc

Date: October 18, 2018 Time: 11:30 AM

Applicant/Agent Signature:

Inspector: _____

Date: April 30/19

Time: 9:00AM

Inspector Signature:

EG (.....)

Soil Description

T

.5m

0.74 m

1.0 m

See Attached
Test Pit Logs

EG (.....)

Soil Description

.5m

1.0 m

1.5m

2.0 m

Test pits not available for inspection.
Engineer assumes all liability for soil
and HGWT info/elev's.

T

EG (.....)

Soil Description

T

.5m

1.0 m

1.5m

2.0 m

1.0 m

1.5m

2.0 m

LEGEND

BR = Bedrock

GWT = Ground water table

HGWT = High ground water table

M = metres

EG = Existing grade

T = percolation rate

PROJECT No: CP-17-0503
SITE: 6688 Franktown Rd.
CLIENT: Bing Professional Engineering Inc.

LOGGED BY: Patrick Leblanc
CONTRACTOR: McIntosh Perry
DATE EXCAVATED: October 18, 2018

R.V.C.A. RECEIVED
APR 23 2019

Depth	Symbol	Description	Notes	Sample Type
ft m				
0		Ground Surface		
		Topsoil (0m to 0.15m)		
0.2				
0.4		Clay (0.15m to 0.90m)		
0.6				
0.8				
1.0		EOH @ 0.90m (Dry)		
1.2				
1.4				
1.6				
1.8				
2.0				

PERMIT APPLICATION
18-548
REQUIRED FOR ALL
INQUIRIES

NOTES Excavated using hand auger

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

R.V.C.A. RECEIVED
APR 23 2019

PROJECT No: CP-17-0503
SITE: 6688 Franktown Rd.
CLIENT: Bing Professional Engineering Inc.

LOGGED BY: Patrick Leblanc
CONTRACTOR: McIntosh Perry
DATE EXCAVATED: October 18, 2018

Depth	Symbol	Description	Notes	Sample Type
0 ft 0 m		Ground Surface		
0.2		Topsoil (0m to 0.25m)		
0.4		Reddish brown Brown Sand becoming lighter brown with depth (0.25m to 0.91m)		
0.6				
0.8				
1.0		EOH @ 0.91m (Dry)		
1.2				
1.4				
1.6				
1.8				
2.0				

SEPTIC APPLICATION
18-548
REQUIRED FOR ALL
INQUIRIES

NOTES Excavated using hand auger

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

McINTOSH PERRY

TEST PIT ID: TP3

SHEET 1 of 1

PROJECT No: CP-17-0503
SITE: 6688 Franktown Rd.
CLIENT: Bing Professional Engineering Inc.

LOGGED BY: Patrick Leblanc
CONTRACTOR: McIntosh Perry
DATE EXCAVATED: October 18, 2018

R.V.C.A. RECEIVED
APR 23 2019

Depth	Symbol	Description	Notes	Sample Type
0 ft 0 m		Ground Surface	SEPTIC APPLICATION 18-548 REQUIRED FOR ALL INQUIRIES	
		Topsoil (0m to 0.1m)		
0.2		Medium Brown Sand (0.1m to 0.30m)		
0.4		Clayey Sand to Sandy Clay, with clay content increasing with depth (0.3m to 0.90m)		
0.6				
0.8		EOH @ 0.90m (Dry)		
1.0				
1.2				
1.4				
1.6				
1.8				
2.0				

NOTES Excavated using hand auger

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

PROJECT No: CP-17-0503
SITE: 6688 Franktown Rd.
CLIENT: Bing Professional Engineering Inc.

LOGGED BY: Patrick Leblanc
CONTRACTOR: McIntosh Perry
DATE EXCAVATED: October 18, 2018

Depth	Symbol	Description	Notes	Sample Type
0 ft m		Ground Surface		
		Topsoil (0m to 0.1m)		
0.2				
0.4		Clayey Sand to Sandy Clay, with clay content increasing with depth (0.1m to 0.90m)		
0.6				
0.8				
1.0		EOH @ 0.90m (Dry)		
1.2				
1.4				
1.6				
1.8				
2.0				

NOTES Excavated using hand auger

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

P.V.C.A. RECEIVED
APR 23 2019
SEPTIC APPLICATION
18-548
REQUIRED FOR ALL
INQUIRIES

PROJECT No: CP-17-0503

LOGGED BY: Patrick Leblanc

SITE: 6688 Franktown Rd.

CONTRACTOR: McIntosh Perry

CLIENT: Bing Professional Engineering Inc.

DATE EXCAVATED: October 18, 2018

APR 23 2019

APR 23 2019

Depth	Symbol	Description	Notes	Sample Type
0 ft m			SEPTIC APPLICATION 18-548 REQUIRED FOR ALL INQUIRIES	
0		Ground Surface		
		Topsoil (0m to 0.1m)		
0.2		Brown sand becoming grey with depth, trace clay (0.1m to 0.9m)		
0.4				
0.6				
0.8				
1.0		EOH @ 0.90m (Dry)		
1.2				
1.4				
1.6				
1.8				
2.0				

NOTES Excavated using hand auger

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

McINTOSH PERRY

TEST PIT ID: TP6

SHEET 1 of 1

PROJECT No: CP-17-0503

LOGGED BY: Patrick Leblanc

SITE: 6688 Franktown Rd.

CONTRACTOR: McIntosh Perry

CLIENT: Bing Professional Engineering Inc.

DATE EXCAVATED: October 18, 2018

Depth	Symbol	Description	Notes	Sample Type
<div><div>ft m</div><div>0 0</div><div>0.2</div><div>0.4</div><div>0.6</div><div>0.8</div><div>1.0</div><div>1.2</div><div>1.4</div><div>1.6</div><div>1.8</div><div>2.0</div></div>		Ground Surface		
		Topsoil (0m to 0.15m)		
		Medium brown sand (0.15m to 0.9m)	Rust mottling visible in upper sand layer	
		EOH @ 0.90m (Dry)		

NOTES Excavated using hand auger

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

RVCA RECEIVED

APR 23 2019

SEPTIC APPLICATION

18-548

REQUIRED FOR ALL INQUIRIES

PROJECT No: CP-17-0503

LOGGED BY: Patrick Leblanc

SITE: 6688 Franktown Rd.

CONTRACTOR: McIntosh Perry

CLIENT: Bing Professional Engineering Inc.

DATE EXCAVATED: October 18, 2018

B.V.C.A. RECEIVED

APR 23 2019

Depth	Symbol	Description	Notes	Sample Type
0 ft m		Ground Surface		
0.2		Topsoil (0m to 0.25m)		
0.4		Rusty red sand becoming lighter brown with depth (0.25m to 0.84m)		
0.6				
0.8				
1.0		EOH @ 0.84m (Dry)		
1.2				
1.4				
1.6				
1.8				
2.0				

NOTES Excavated using hand auger

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

18-548
REQUIRED FOR ALL
INQUIRIES

McINTOSH PERRY TEST PIT ID: TP8

SHEET 1 of 1

PROJECT No: CP-17-0503
SITE: 6688 Franktown Rd.
CLIENT: Bing Professional Engineering Inc.

LOGGED BY: Patrick Leblanc
CONTRACTOR: McIntosh Perry
DATE EXCAVATED: October 18, 2018

R.V.C.A. RECEIVED
APR 23 2019

Depth	Symbol	Description	Notes	Sample Type
0 m		Ground Surface		
0.2		Topsoil (0m to 0.25m)		
0.4		Medium red and brown sand becoming light brown with depth (0.25m to 0.94m)		
0.6				
0.8				
1.0		EOH @ 0.94m (Dry)		
1.2				
1.4				
1.6				
1.8				
2.0				

SEPTIC APPLICATION
18-548
REQUIRED FOR ALL
INQUIRIES

NOTES Excavated using hand auger

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

McINTOSH PERRY		TEST PIT ID: TP9		<div>R.V.C.A. RECEIVED APR 23 2019 SHEET 1 of 1</div>	
PROJECT No: CP-17-0503		LOGGED BY: Patrick Leblanc			
SITE: 6688 Franktown Rd.		CONTRACTOR: McIntosh Perry			
CLIENT: Bing Professional Engineering Inc.		DATE EXCAVATED: October 18, 2018			
Depth	Symbol	Description	Notes	Sample Type	
<div><div>ft m</div><div>0 0.2 0.4 0.6 0.8 1.0 1.2 1.4 1.6 1.8 2.0</div></div>		Ground Surface	<div>SEPTIC APPLICATION 18-548 REQUIRED FOR ALL INQUIRIES</div>		
		Topsoil (0m to 0.25m)			
		Medium brown sand with rust mottling throughout, becoming light brown with depth (0.25m to 0.97m)			
		EOH @ 0.97m (Dry)			
<div>NOTES Excavated using hand auger</div> <div>Descriptions are based on observations and hand testing of grab samples. Mechanical Tests were not performed unless otherwise stated.</div> <div>REVIEWED BY: Patrick Leblanc</div> <div>TEMPLATE: MP - Test Pit</div>					

PROJECT No: CP-17-0503

SITE: 6688 Franktown Rd.

CLIENT: Bing Professional Engineering Inc.

LOGGED BY: Patrick Leblanc

CONTRACTOR: McIntosh Perry

DATE EXCAVATED: October 18, 2018

R.V.O.A. RECEIVED

APR 23 2019

SEPTIC APPLICATION
18-548
REQUIRED FOR ALL
INQUIRIES

Depth	Symbol	Description	Notes	Sample Type
0 m		Ground Surface		
0.10m		Topsoil (0m to 0.10m)		
0.2		Medium brown sand, becoming light brown with depth (0.10m to 0.99m)		
0.4				
0.6				
0.8				
1.0		EOH @ 0.99m (Dry)		
1.2				
1.4				
1.6				
1.8				
2.0				

NOTES Excavated using hand auger

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

PROJECT No: CP-17-0503
SITE: 6688 Franktown Rd.
CLIENT: Bing Professional Engineering Inc.

LOGGED BY: Patrick Leblanc
CONTRACTOR: McIntosh Perry
DATE EXCAVATED: October 18, 2018

APR 23 2019

Depth	Symbol	Description	Notes	Sample Type
0 ft m		Ground Surface		
0.2		Topsoil (0m to 0.20m)		
		Grey sand (0.20m to 0.30m)		
0.4		Rusty red sand, becoming light brown with depth (0.30m to 0.91m)		
0.6				
0.8				
1.0		EOH @ 0.91m (Dry)		
1.2				
1.4				
1.6				
1.8				
2.0				

SEPTIC APPLICATION
18-118
REQUIRED FOR ALL
INQUIRIES

NOTES Excavated using hand auger

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

PROJECT No: CP-17-0503

LOGGED BY: Patrick Leblanc

SITE: 6688 Franktown Rd.

CONTRACTOR: McIntosh Perry

CLIENT: Bing Professional Engineering Inc.

DATE EXCAVATED: October 18, 2018

R.V.C.A. RECEIVED
APR 23 2019

Depth	Symbol	Description	Notes	Sample Type
0		Ground Surface	SEPTIC APPL 18-54- REQUIRED FC INQUIRY	
0.2		Topsoil (0m to 0.20m)		
0.4		Grey sand (0.20m to 0.35m)		
0.6		Rusty red sand, becoming brown then light brown with depth (0.35m to 0.99m)		
1.0		EOH @ 0.99m (Dry)		
1.2				
1.4				
1.6				
1.8				
2.0				

PROJECT No: CP-17-0503

SITE: 6688 Franktown Rd.

CLIENT: Bing Professional Engineering Inc.

LOGGED BY: Patrick Leblanc

CONTRACTOR: McIntosh Perry

DATE EXCAVATED: October 18, 2018

APR 23 2019

SEPTIC APPLICATION
18-010
REQUIRE
INQUIRY

Depth	Symbol	Description	Notes	Sample Type
0 ft m		Ground Surface		
0		Topsoil (0m to 0.15m)		
0.2		Grey sand (0.15m to 0.30m)		
0.4		Brown sand with rust mottling, becoming light brown with depth (0.30m to 0.81m)		
0.6				
0.8		EOH @ 0.81m (Dry)		
1.0				
1.2				
1.4				
1.6				
1.8				
2.0				

NOTES Excavated using hand shovel

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

McINTOSH PERRY

TEST PIT ID: TP14

SHEET 1 of 1

R.V.C.A. RECEIVED

APR 23 2019

PROJECT No: CP-17-0503

LOGGED BY: Patrick Leblanc

SITE: 6688 Franktown Rd.

CONTRACTOR: McIntosh Perry

CLIENT: Bing Professional Engineering Inc.

DATE EXCAVATED: October 18, 2018

Depth	Symbol	Description	Notes	Sample Type
0	m	Ground Surface	SEPTIC APPLICATION 18-548 REQUIRED FOR ALL INQUIRIES	
0.2		Topsoil (0m to 0.25m)		
0.4		Reddish brown sand, becoming light brown with depth (0.25m to 0.81m)		
0.8		EOH @ 0.81m (Dry)		
1.0				
1.2				
1.4				
1.6				
1.8				
2.0				

NOTES Excavated using hand shovel

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit

McINTOSH PERRY

TEST PIT ID: TP15

R.V.C.A. RECEIVED
APR 23 2019
SHEET 1 of 1

PROJECT No: CP-17-0503
SITE: 6688 Franktown Rd.
CLIENT: Bing Professional Engineering Inc.

LOGGED BY: Patrick Leblanc
CONTRACTOR: McIntosh Perry
DATE EXCAVATED: October 18, 2018

Depth	Symbol	Description	Notes	Sample Type
0	ft m	Ground Surface	SEPTIC APPLICATION 18-548 REQUIRED FOR ALL INQUIRIES	
0.2		Topsoil (0m to 0.25m)		
0.4		Reddish brown sand, becoming light brown with depth (0.25m to 0.81m)		
0.8		EOH @ 0.81m (Dry)		
1.0				
1.2				
1.4				
1.6				
1.8				
2.0				

NOTES Excavated using hand shovel

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc
TEMPLATE: MP - Test Pit

McINTOSH PERRY

TEST PIT ID: TP16

PROJECT No: CP-17-0503

LOGGED BY: Patrick Leblanc

SITE: 6688 Franktown Rd.

CONTRACTOR: McIntosh Perry

CLIENT: Bing Professional Engineering Inc.

DATE EXCAVATED: October 18, 2018

SHEET 1 of 1

R.V.C.A. RECEIVED

APR 23 2019

SEPTIC APPLICATION

18-548

REQUIRED FOR ALL INQUIRIES

Depth	Symbol	Description	Notes	Sample Type
0 ft m		Ground Surface		
0.2		Topsoil (0m to 0.30m)		
0.4		Reddish brown sand, becoming light brown with depth (0.30m to 0.81m)		
0.6				
0.8		EOH @ 0.81m (Dry)		
1.0				
1.2				
1.4				
1.6				
1.8				
2.0				

NOTES Excavated using hand shovel

Descriptions are based on observations and hand testing of grab samples.
Mechanical Tests were not performed unless otherwise stated.

REVIEWED BY: Patrick Leblanc

TEMPLATE: MP - Test Pit



Schedule 7
Layout Section

R.V.C.A. RECEIVED
APR 23 2019

Do Not Complete
Permit No _____
Revision No _____
Date _____

SEPTIC APPLICATION

18-548

REQUIRED FOR ALL
INQUIRIES

Scale: 1Block = _____


N


See Attached Drawings

○Dug Well ●Drilled Well ▲Neighbouring Homes ◇Benchmark ---Tile Drainage —Property Line

Elevations (metric only)
B.M. _____ m
B.M Description _____
Exact Location _____

Min. of 5 elevations in proposed system area
(in X pattern)
X₁ _____ X₂ _____
X₃ _____ X₄ _____
X₅ _____ X₆ (toe) _____
X₇ _____ X₈ _____





Do Not Complete
Permit No _____
Revision No _____
Date _____


18-548
SEPTIC APPLICATION
REQUIRED FOR INQUIRIES

Fixtures	# Existing	+ # Proposed	X	unit count	=	Fixture Count
Bathroom						
Bathroom group (toilet, sink and tub or shower) with flush tank		+	X	6	=	
Bathtub with/without overhead shower		+	X	1.5	=	
Shower stall		+	X	1.5	=	
Wash basin (1½inch trap)		+	X	1.5	=	
Watercloset (toilet)	N/A (See Schedule 4)					
Bidet						
Kitchen						
Dishwasher						
Sink with/without garbage grinder(s), domestic and other small type single, double or 2 single with a common trap		+	X	1.5	=	
Other						
Domestic washing machine		+	X	1.5	=	
Combination sink and laundry tray single or double (Installed on 1½ trap)		+	X	1.5	=	

***Total:**

***Insert the TOTAL in section 5 of Schedule 4 (0.Reg 151/13 Table 7.4.9.3)**

1. Sump pumps and floor drains are not to be connected to the sewage system. Connection of such fixtures to a sewage system may lead to a hydraulic failure of the said system. The above mentioned fixtures should be discharged separately to an approved Class 2 (leaching pit) sewage system.
2. Where laundry waste is not more than 20% of the total daily design sanitary sewage flow, it may discharge to a sewage system (Part 8, OBC, 8.1.3.1(2)).


Agent/Owner signature

April 23, 2019
Date




Ottawa Septic Bureau des systèmes
System Office septiques d'Ottawa

SCHEDULE 13 – TYPICAL DRAWING E

Type A Dispersal Bed

MANAGER, O.S.S.O.

DATE



NOT TO SCALE

Sand Mantle
15m(min)

Permeable fill
stabilized against erosion

PROFILE

250mm (min) MANTLE
1% (min)
(if required)

FINISHED GRADE

Geotextile (0.3m recommended)

CLEAR STONE 0.2m(min)

SAND T=6-10 0.3m(min)


SEASONAL HGWT ~ 99.95 mASL

BEDROCK

WATERTABLE

99.95 m
Toe of mantle

T > 50 min/cm



PK May 2/19

SEPTIC APPLICATION
13-54
REQUIRED FOR ALL
INQUIRIES
101.50
101.20
100.90
100.30 (AT HEADER)

PROPOSED
FOGUANGSHAN
TEMPLE
INTERIM BUILDING
AT
6688 FRANKTOWN RD.
RICHMOND, ON
K0J 2Z0



R.V.C.A. RECEIVED
AUG 18 2018

SUSAN D. SMITH ARCHITECT
941 Merivale Rd. Ottawa,
Ontario K1Z 6A1
613-722-5327
s.smith@sdsarch.ca



NO.	REVISION	DATE
1	ISSUED FOR PERMIT REVIEW	04/11/19
2	ISSUED FOR SITE PLAN CONTROL	04/11/19
3	ISSUED FOR REVIEW	04/11/19

NOTES:
1. All dimensions are as indicated on this drawing. Dimensions of materials should be checked prior to construction and verified with the manufacturer. Dimensions of materials should be checked prior to construction and verified with the manufacturer.
2. All interior dimensions are to face of gypsum board.
3. All exterior dimensions are to face of exterior cladding.

SOUTH ELEVATIONS:
WEST ELEVATIONS:

JOB #	DRAWING BY
1770B	SDS & ZL
DATE	SCALE
AUG/18	as noted

A1



SEPTIC APPLICATION
18-548
REQUIRED FOR ALL
INQUIRIES

PROPOSED
FOGUANGSHAN
TEMPLE
INTERIM BUILDING
AT
6688 FRANKTOWN RD.
RICHMOND, ON
K01 2Z0





R.V.C.A. RECEIVED
APR 11 2019
SUSAN D. SMITH ARCHITECT
941 Merivale Rd. Ontario
K3J 6A1
613-722-5327
s.smith@sfsarch.ca

NOTES:
1. All dimensions are to be checked on the drawings and are subject to change without notice.
2. The drawings are to be used in accordance with the Ontario Building Code, latest edition.
3. All interior dimensions are to face of gypsum board.

NORTH ELEVATIONS:
EAST ELEVATIONS:

JOB #	DRAWING BY
17770B	SDS & ZL
DATE	SCALE
AUG/18	as noted

A2



SEPTIC APPLICATION
REQUIRED FOR ALL
INQUIRIES
1-855-548-1111

GENERAL NOTES

1. PROVIDE SANITARY DRAINAGE IN ACCORDANCE WITH THE FOLLOWING NOTES:
2. ALL SANITARY DRAINAGE SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING NOTES:

DRAWING NOTES

1. DOWNSIDE OF TOILETS SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING NOTES:
2. DOWNSIDE OF TOILETS SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING NOTES:
3. DOWNSIDE OF TOILETS SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING NOTES:
4. DOWNSIDE OF TOILETS SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING NOTES:
5. DOWNSIDE OF TOILETS SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING NOTES:

PROPOSED
FOGUANGSHAN
TEMPLE
INTERIM BUILDING
AT
6688 FRANKTOWN RD.
RICHMOND, ON
K0I 2Z0

MECHANICAL & ELECTRICAL
Jp2g Consultants Inc.
PLANNING - PROJECT MANAGEMENT



R.V.C.A. RECEIVED
APR 23 2019


SUSAN D. SMITH ARCHITECT
641 Mervale Rd. Ottawa,
ON K1H 8G4
613-722-5394
s.smith@starch.ca

REVISION	DATE
1	2019/04/04
2	2019/02/25
3	2019/09/28


DRAWING TITLE
**GROUND FLOOR AND
PARTIAL GROUND FLOOR
PLANS - PLUMBING
LAYOUT**

JOB # CC
DRAWING BY CC
DATE AUG/19
SCALE GS noted

M-300




GROUND FLOOR PLAN - DOMESTIC WATER DISTRIBUTION LAYOUT
SCALE: 1/4" = 1'-0"



PARTIAL GROUND FLOOR PLAN - SANITARY DRAINAGE LAYOUT
SCALE: 1/4" = 1'-0"

18-548
REQUIRED FOR ALL
INQUIRIES



N

- FLOATATION PROTECTION REVIEW REQUIRED BY CONTRACTOR FOR ALL TANKS. PROTECTION TO BE PROVIDED USING EXISTING GRADE AS HIGH GROUNDWATER ELEVATION.
- PUMP CHAMBER TO CONTAIN TWO SUBMERSIBLE EFFLUENT PUMPS OPERATING ON AN ALTERNATING TIMER CONTROL PANEL.
- WATERLOO BIOFILTER TO CONTAIN ONE SUBMERSIBLE EFFLUENT PUMP OPERATING ON A TIMER FOR RECIRCULATION LOOP. AS WELL AS TWO ALTERNATING SUBMERSIBLE EFFLUENT PUMPS OPERATING ON DEMAND FOR DISCHARGE TO TYPE A BED.
- DOSE VOLUME TO TYPE A BED IS MINIMUM OF 75% INTERNAL PIPE VOLUME OF DISTRIBUTION PIPES IN STONE LAYER.
- AUDIBLE/VISUAL ALARM REQUIRED FOR ALL TANKS WITH PUMPS.
- LICENSED INSTALLER TO DETERMINE PUMP RATES AND TIMER SETTINGS AS PER MANUFACTURER'S SPECIFICATIONS.
- FOREMANS EITHER TO BE FREE-DRAINING BACK TO PUMP TANK OR FROST PROTECTED.
- INSTALLER TO REVIEW CERTIFIED MAX BURIAL DEPTH FOR ALL PRE-CAST TANKS.
- DESIGN RECIRCULATION RATE IS MINIMUM OF 50% (I.E. 50% OF EACH BIOFILTER DOSE IS RECIRCULATED TO ANAEROBIC DIGESTER INLET).
- FLOW METER TO BE INSTALLED ON FOREMANK TO TYPE A BED.

R.V.C.A. RECEIVED

APR 23 1955

SEPT 10 5 48

REQUIRED INQUIRIES

[illegible]

McINTOSH PERRY

115 Walgreen Road, RR3, Carp, ON K0A 1L0
Tel: 613-836-2184 Fax: 613-836-3742

www.mcintoshperry.com

Stamp:



Client

BING PROFESSIONAL ENGINEERING INC
248 HUNTSVILLE DRIVE
OTTAWA, ON K2T 0C3

Project

PROPOSED BUDDHIST TEMPLE
6688 FRANKTOWN ROAD, RICHMOND, ON

Drawing Title

INTERIM FACILITY SEWAGE SYSTEM DESIGN

Scale:

Project Number: 1-500

BA UCF-17-0503

1

PL

7

1

Date:

1000

SAN-01

1 of 2

(KNOWN AS FRANKTOWN ROAD)

R.V.C.A. RECEIVED

SEPTIC APPLICATION

18
REQUIRED FOR ALL
INQUIRIES

30°E (P1)
259.56(m)
259.47(P1)
P.L.N. 03933-0052 (L)



1	RESUBMISSION TO OSSO	APR/23/2019
No.	Revision/Issue	Date

McINTOSH PERRY
115 Walgreen Road, RR3, Carp, ON K0A 1L0
Tel: 613-836-2184 Fax: 613-836-3742
www.mcintoshperry.com

Stamp:



Client:
BING PROFESSIONAL ENGINEERING INC.
248 HUNTSVILLE DRIVE
OTTAWA, ON K2T 0C3

Project:
PROPOSED BUDDHIST TEMPLE
6668 FRANKTOWN ROAD, RICHMOND, ON

Drawing Title:

**INTERIM FACILITY
SEWAGE SYSTEM DESIGN**

Scale: 1:500

Drawn by: BA

Checked by: PL

Date: SEP/28/2018

Project Number:

OCP-17-0503

Drawing Number:

SAN-02

2 of 2



Ottawa Septic Bureau des systèmes
System Office septiques d'Ottawa

Permit Part 8 – Sewage System Ontario Building Code

Do Not Complete
Permit No. _____
Revision No. 18-548
Date _____
Related Application _____

SEPTIC APPLICATION
REQUIRED FOR ALL
INQUIRIES

A copy of this permit must be posted on the property at all time during construction. OBC, Division C — Part 1, Section 1.3.2.1

This permit verifies that the on-site sewage system was reviewed and approved for construction under the Ontario Building Code and O.Reg. 323/12 as amended by O.Reg. 151/13.

Inspected & Recommended by: J. Hutton Owner: International Buddhist Progress
Inspection Date & Time: April 30/19 (9:00AM) Weather: Society of Ottawa Carleton
Civic Address: 6688 Franktown Rd. Legal: _____

number of bedrooms: _____ fixture units: _____
finished floor area: _____ Q: 9999 L/day

septic/holding tank/pre-treatment tank AD-23000 L
effluent filter _____
pump rate 507 L/15 min
treatment unit WB BT-34000L to bed
number of units 1

weigh bills for filter media	<input type="checkbox"/> yes	<input checked="" type="checkbox"/> no
grain size analysis required	<input type="checkbox"/> yes	<input checked="" type="checkbox"/> no
site to be scarified	<input checked="" type="checkbox"/> yes	<input type="checkbox"/> no
clay seal inspection	<input type="checkbox"/> yes	<input checked="" type="checkbox"/> no
mantle required	<input checked="" type="checkbox"/> yes	<input type="checkbox"/> no
sub-grade inspection	<input checked="" type="checkbox"/> yes	<input type="checkbox"/> no

ELEVATION ☐ In Ground ☐ Partially Raised ☐ Fully Raised

TYPE OF SYSTEM

- ☐ Trench
☐ Pipe and Stone or ☐ Chambers

type of chamber _____
loading area _____ m²
total trench length _____ m
trench configuration _____

☒ Dispersal Bed

- ☐ BMEC ☒ Type A ☐ Type B

stone 201.6 m²
sand 924 m²
pipe 12 runs of 12.8m x 1.2m dc
linear loading _____ L/m²

☐ Shallow Buried Trench

pipe length _____ m
orifice spacing _____ m

☐ Filter Media Bed

stone _____ m²
extended base _____ m²
pipe _____
weight of filter media _____ kg
loading area _____ m²

☐ Class 5 Holding Tank

☐ Septic Tank Only

Manager, Septic System Approvals: Jason Hutton Permit Date: May 2, 2019

Comments: (1) Toe of mantle shall outlet to topsoil or other free-draining soil
(2) OSSO shall inspect subgrade preparation prior to placing sand fill

☒ maintenance/pumping required

☐ ESA permit # required

☐ engineer to verify

☐ subgrade

☐ squirt height _____

☐ Class 5 Holding Tank approval only valid for three years from date of issue

Manager, Septic System Approvals: _____

Revision Date: _____

Comments: _____

NOTE: For further details, refer to corresponding application.

Appendix F – Drawings



JOB NO. 24-0240	DRAWING: 24-0240 FRANKTOWN RD.DWG
THIS PLAN WAS PREPARED FOR: VENERABLE HUI TZU	
 <p>3240 Drummond Con. 5A, R.R. #7 Perth, ON K7H 3C9 Tel: 613-267-6524 Fax: 613-267-7992 www.mcintoshperry.com</p> 	
CHECKED: JG	CAD: DL, CC

TOPOGRAPHIC PLAN OF SURVEY
OF PART OF
LOT 19,
CONCESSION 3
GEOGRAPHIC TOWNSHIP OF
GOULBOURN
CITY OF OTTAWA

SCALE 1 : 500
0 10 20 30 40 50 Metres

McINTOSH PERRY SURVEYING INC.

METRIC :
DISTANCES AND COORDINATES SHOWN ON THIS PLAN ARE IN METRES
AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048.

SURVEYOR'S CERTIFICATE

I CERTIFY THAT:
1. THIS SURVEY AND PLAN ARE CORRECT AND IN ACCORDANCE WITH
THE SURVEY ACT, THE SURVEYORS ACT AND THE REGULATIONS MADE
UNDER THEM.
2. THE SURVEY WAS COMPLETED ON THE 9th DAY OF JANUARY, 2018.

FEBRUARY 21, 2018
DATE
SIMON WAGNER
SURVEYOR

LEGEND AND NOTES

DENOTES	MONUMENT PLANTED
□	MONUMENT FOUND
■	MONUMENT FOUND
SB	STANDARD IRON BAR
SSB	SHORT STANDARD IRON BAR
IB	IRON BAR
RPL	ROCK PLUG
RB	ROUND IRON BAR
BM	BENCHMARK
WT	WITNESS
(m)	MEASURED
(P1)	PLAN 4R-7040
(P2)	PLAN 5R-6743
(P3)	PLAN 5R-14318
(P4)	PLAN 4R-6424
(D1)	INSTRUMENT N733204
(726)	WILLIAM D. RATZ, O.L.S.
(1116)	WILLIAM J. JOHNSTON, O.L.S.
(1442)	JOHN H. KENNEDY, O.L.S.
BP	BELL POLE
BHP	BELL & HYDRO POLE
HP	HYDRO POLE
N.T.S.	NOT TO SCALE
TBM	TEMPORARY BENCHMARK
PWF	POST & WIRE FENCE
MIXED BUSH	MIXED BUSH
— OHW —	OVER HEAD WIRES
— x —	FENCE (TYPE NOTED ON PLAN)

TEMPORARY SITE BENCHMARK - NAIL & WASHER IN FACE OF BELL & HYDRO
POLE, HAVING A GEODETIC ELEVATION OF 100.38

THE LOCATION AND CONFIGURATION OF UNDERGROUND SERVICES AND
UTILITIES HAVE BEEN DERIVED FROM LIMITED FIELD INFO AND CANNOT BE
GUARANTEED TO BE COMPLETE OR ACCURATE. IT IS THE RESPONSIBILITY OF
THE CONTRACTOR TO VERIFY THE CONFIGURATION AND LOCATION OF
UNDERGROUND SERVICES AT THE SITE PRIOR TO CONSTRUCTION.

ELEVATIONS ARE CANADA GEODETIC VERTICAL DATUM 1928-1978
DERIVED FROM REAL TIME NETWORK GPS OBSERVATIONS WITH GEOID
CORRECTION APPLIED.

BEARINGS ARE MTM GRID BEARINGS, DERIVED BY REAL TIME NETWORK GPS
OBSERVATIONS ON OBSERVED REFERENCE POINTS A AND B, SHOWN HEREON,
AND ARE REFERRED TO THE CENTRAL MERIDIAN OF MTM ZONE 9, (75°30'
WEST LONGITUDE) NAD83 (ORIGINAL) 2010.

DISTANCES SHOWN ON THIS PLAN ARE GROUND DISTANCES AND CAN BE
CONVERTED TO GRID DISTANCES BY MULTIPLYING BY A COMBINED SCALE
FACTOR OF 0.99992.

OBSERVED REFERENCE POINTS (ORP) DERIVED FROM GPS OBSERVATIONS USING REAL TIME NETWORK (RTN) SERVICE MTM ZONE 9, NAD83 (ORIGINAL) (2010)		
COORDINATES TO RURAL ACCURACY PER SEC. 14 (2) OF O.REG. 216/10		
POINT ID	NORTHING	EASTING
ORP A	5004357.4	354859.4
ORP B	5004485.2	354848.4
COORDINATES CANNOT, IN THEMSELVES, BE USED TO RE-ESTABLISH CORNERS OR BOUNDARIES SHOWN ON THIS PLAN.		

© COPYRIGHT IN THIS PLAN REMAINS THE PROPERTY OF
McINTOSH PERRY SURVEYING INC.. REPRODUCTION OF
THIS PLAN BY ANY MEANS IS PROHIBITED.

JOB No. 17-4410 DRAWING #17-4410-01
PREPARED FOR: MPCE (BEN CLARE)

McINTOSH PERRY
SURVEYING INC.
3340 Drummond Con. SA, R.R. #2, Perth, ON K7H 3G3
Tel: 613-267-6554 Fax: 613-267-7992
www.mcintoshperry.com

EXAMINED: CHECK:
February 21, 2018 2:11:37 PM

APPROVED

Robert J. Levine
ASSISTANT EXAMINER OF SURVEYS

Robert J. Levine
ASSISTANT EXAMINER OF SURVEYS

20



17

