

NOTES:

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ARCHITECTURAL DRAWINGS BY NEUF ARCHITECTES SENCRL. REFER TO ARCHITECTURAL PLANS FOR DIMENSIONS.
- ALL WATERMANS TO BE INSULATED IF LESS THAN 2.4 METERS COVER AS PER CITY OF OTTAWA STANDARD DETAIL W22. AT ANY PROXIMITY OF SEWER MANHOLES, INSULATE WATERMAIN AS PER CITY DETAIL W22.
- SEWERS ARE TO MAINTAIN 500mm BARRELL TO BARRELL CLEARANCE ABOVE AND 250mm BARRELL TO BARRELL CLEARANCE BELOW WATERMANS AT ALL CROSSINGS (AS PER CITY DWGS W25 AND W25.2). IF 22" BENDS ARE USED ON THE WATER MAIN, THEY MUST BE ONE METER AWAY FROM THE SEWER.
- THRUST BLOCKS TO BE AS PER CITY OF OTTAWA STANDARD DRAWINGS W25.3 AND W25.4. RESTRAINING AND RETAINING RINGS TO BE INSTALLED IN ACCORDANCE WITH CITY STANDARD DETAILS W25.5 AND W25.6.
- TEMPORARY SUPPORT OF EXISTING UNDERGROUND UTILITIES IN ACCORDANCE WITH CITY STANDARD DETAIL W28.
- WATERMAIN TRENCH AND BEDDING TO BE INSTALLED AS PER CITY DETAIL W17.
- TAPPING VALVE SYSTEM CONNECTION TO CITY WATERMAIN BY CITY FORCES: EXCAVATION, BACKFILLING AND REINSTATEMENT BY CONTRACTOR.
- CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATION OF ALL EXISTING UP AND OVERHEAD UTILITIES. VARIOUS UTILITIES CONCERNED TO BE GIVEN REQUIRED ADVANCE NOTICE PRIOR TO ANY DIGGING FOR STAKE OUT. THE OWNER AND CONSULTANT ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THE LOCATION OF EXISTING UTILITIES AS INDICATED ON THIS DRAWING.
- UTILITY INFORMATION WAS SCRIBED IN THE FIELD WHERE POSSIBLE. INDIVIDUAL COMPANIES SHOULD BE CONTACTED BY THE CONTRACTOR PRIOR TO COMMENCEMENT FOR CONFIRMATION OF EXISTENCE AND LOCATION OF UTILITIES.
- WATER SERVICE, STORM SEWERS AND APPURTENANCE TO COMPLY WITH THE REQUIREMENTS OF THE LATEST REVISION OF THE ONTARIO PLUMBING CODE AND APPLICABLE CITY OF OTTAWA ENGINEERING STANDARDS.
- ALL SANITARY SEWERS TO BE INSULATED IF LESS THAN 2.0 METERS COVER. ALL STORM SEWERS TO BE INSULATED IF LESS THAN 2.0 METERS COVER. INSULATE AS PER CITY OF OTTAWA STANDARD DETAIL W22. ALL BUILDING CONNECTIONS TO HAVE SUFFICIENT COVER OR INSULATION IS REQUIRED.
- CONTRACTOR SHALL CONTACT THE CONSULTANT, R.V. ANDERSON PRIOR TO BACKFILLING OF THE WATER SERVICE CONNECTIONS FOR THE PROPOSED LINES AND TIE-INS TO EXISTING LINES FOR AS-BUILT LOCATION RECORDS AND INSPECTION.
- ANY ASPHALT CUT SHALL BE SAW CUT ON BOTH SIDES OF THE TRENCH FOR THE ENTIRE LENGTH OF THE EXCAVATION FOR PIPE INSTALLATIONS. REINSTATEMENT OF THE ROADS SHALL MATCH EXISTING OR MEET CITY STANDARD R10.
- ANY CONCRETE CUT SHALL BE REMOVED AT EXPANSION JOINTS. IF NO JOINTS EXIST, THE CONCRETE SHALL BE SAW CUT ON BOTH SIDES OF THE TRENCH FOR THE ENTIRE LENGTH OF THE EXCAVATION FOR PIPE INSTALLATIONS. REINSTATEMENT SHALL MATCH EXISTING OR MEET CITY REQUIREMENTS.
- PIPE BEDDING SHALL BE GRANULAR "A" AS PER CITY DETAIL S6, AND SHALL BE COMPACTED TO 95% SPD AND APPROVED SELECT NATIVE BACK FILL COMPACTED TO 95% SPD.
- DRAWINGS TO BE READ IN CONJUNCTION WITH CONTRACT SPECIFICATIONS.
- GRANULAR LAYERS BENEATH NEW ASPHALT SURFACES ON PROPERTY SHALL BE PLACED AT A THICKNESS NOT EXCEEDING 300mm. THE GRANULAR "A" AND GRANULAR "B" TYPE II IS TO BE COMPACTED TO A MINIMUM OF 100% SPMD USING SUITABLE VIBRATORY EQUIPMENT.
- THE APPROVAL OF THIS PLAN DOES NOT EXEMPT THE OWNERS BONDED CONTRACTOR FROM THE REQUIREMENTS TO OBTAIN THE VARIOUS PERMITS/APPROVALS NORMALLY REQUIRED TO COMPLETE A CONSTRUCTION PROJECT, SUCH AS, BUT NOT LIMITED TO THE FOLLOWING: ROAD CUT PERMITS, SEWER PERMITS, APPROACH APPROVAL PERMITS, RELOCATION OF SERVICES, COMMITTEE OF ADJUSTMENT, ENCROACHMENT AGREEMENTS, WATER PERMIT, ETC.
- THE OWNER SHALL REQUIRE THAT THE SITE SERVING CONTRACTOR PERFORM FIELD TESTS FOR QUALITY CONTROL OF ALL SANITARY SEWERS. SPECIFICALLY, THE LEAKAGE TESTING SHALL BE COMPLETED IN ACCORDANCE WITH OPS8 410.07.01.16 AND 407.07.26. THE FIELD TESTS SHALL BE PERFORMED IN THE PRESENCE OF A CERTIFIED PROFESSIONAL ENGINEER WHO SHALL SUBMIT A CERTIFIED COPY OF THE TEST RESULTS.
- REFER TO LANDSCAPE DRAWINGS FOR DETAILS ON LANDSCAPING TREATMENTS AND PLANTINGS.
- SEWERS TO BE CONSTRUCTED AS PER CITY OF OTTAWA SPECIFICATIONS - SPECIAL PROVISION F-4100, ALL SEWER STRUCTURES AS PER F-4070, ALL WATER MAINS AS PER F-4411 AND ALL ASSOCIATED SPECIFICATIONS. IRON ADJUSTMENTS PER F-4080.
- EROSION AND SEDIMENT CONTROL MEASURES IN ACCORDANCE WITH THE REQUIREMENTS OF OPS8 805 - NOVEMBER 2018 FOR TEMPORARY MEASURES) CONSISTING OF BOTH PERMANENT AND TEMPORARY MEASURES SHALL BE IMPLEMENTED PRIOR TO THE COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO ENSURE THAT SEDIMENT IS CONTAINED WITHIN THE SITE. PERMANENT EROSION CONTROL MEASURES SHALL ENSURE THAT POTENTIAL LONG-TERM AND LOCALIZED EROSION PROBLEMS ARE DEALT WITH PRIOR TO THEIR OCCURRENCE. FILTER FABRIC SHALL BE INSTALLED UNDER THE FRAME OF ALL PROPOSED AND EXISTING CATCHBASINS AND STORM MANHOLES IMMEDIATELY ADJACENT TO ANY DISTURBED AREAS PRIOR TO CONSTRUCTION TO PREVENT SEDIMENT FROM ENTERING INTO THE STORM SEWER SYSTEM. THE FILTER FABRIC SHALL REMAIN IN PLACE FOR THE DURATION OF CONSTRUCTION ACTIVITIES AND SHALL NOT BE REMOVED UNTIL SUCH TIME AS THE LANDSCAPING HAS BEEN ESTABLISHED AND UPON AUTHORIZATION BY THE ENGINEER. LIGHT DUTY SEDIMENT FENCING SHALL ALSO BE PLACED AROUND THE PERIMETER OF THE SITE FOR THE DURATION OF THE CONSTRUCTION.
- THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.
- CONNECTION OF THE WATER SERVICES TO THE CITY WATERMAIN BY CITY FORCES: EXCAVATION, BACKFILLING AND REINSTATEMENT BY CONTRACTOR.
- REFER TO THE STORM WATER MANAGEMENT & SITE SERVING REPORTS FROM R.V. ANDERSON DATED FEBRUARY 19, 2020 FOR FURTHER DETAILS.
- REFER TO GEOTECHNICAL REPORT BY PINCHIN LTD, DATED APRIL 29, 2020 FOR SOIL INFO.
- SIDEWALK DEPRESSIONS PER CITY DETAIL S6C.
- REFER TO MECHANICAL DRAWINGS FOR INTERNAL PLUMBING INCLUDING WATER METER, BACKFLOW PREVENTION, INTERNAL PIPING, FOUNDATION DRAINAGE CONNECTION ETC.

CONTAMINATED WATER / FOUNDATION DRAIN INFORMATION:
 THE QUALITY OF WATER COLLECTED BY THE FOUNDATION DRAINAGE SYSTEM IS EXAMINED IN THE PHASE I ESA REPORT, DRAFT ISSUED NOVEMBER 30, 2020. THE REMEDIAL TECHNOLOGY EVALUATION - OVERVIEW LETTER, DATED NOVEMBER 26, 2020. THE WATER TAKING & DISCHARGE PLANS REPORT DATED APRIL 7, 2020, AND THE REMEDIAL PLAN FOR ADDRESSING GROUNDWATER IMPACTS MEMO DATED DECEMBER 4, 2020 (ATTACHED IN APPENDIX A) ALL PREPARED BY PINCHIN BASED ON THE FINDINGS OF THE ABOVE REPORTS. IT IS UNDERSTOOD THAT THE GROUNDWATER ON SITE WAS FOUND TO HAVE CONTAMINANTS EXCEEDING THE ALLOWABLE LEVELS ENTERING EITHER THE SANITARY OR STORM SEWER SYSTEMS AS SPECIFIED IN THE SEWER USE BYLAW. THE ABOVE NAMED REPORTS PROPOSE REMEDIAL MEASURES INCLUDING REMOVING THE IMPACTED SOIL FROM THE SITE AND PROVIDING GROUNDWATER MONITORING TO ASSESS RESIDUAL CONTAMINANT LEVELS. FOLLOWING REMEDIAL MEASURES, THESE SCENARIOS ARE PRESENTED WHICH ALL REQUIRE ULTIMATE DISCHARGE TO THE SANITARY SYSTEM.

- SCENARIO 1: REMEDIAL ACTIONS BRING GROUNDWATER QUALITY BELOW BOTH MECP TABLE 7 STANDARDS AND SANITARY SEWER DISCHARGE STANDARDS. IN THIS CASE FOUNDATION DRAINAGE WILL BE PUMPED TO THE SANITARY SYSTEM.
- SCENARIO 2: REMEDIAL ACTIONS FAIL TO BRING GROUNDWATER QUALITY BELOW MECP TABLE 7 STANDARDS BUT SUCCESSFULLY MEET SANITARY SEWER DISCHARGE STANDARDS. IN THIS CASE FOUNDATION DRAINAGE WILL BE PUMPED TO THE SANITARY SYSTEM.
- SCENARIO 3: REMEDIAL ACTIONS FAIL TO BRING GROUNDWATER QUALITY BELOW BOTH MECP TABLE 7 STANDARDS AND ALSO FAIL TO SUCCESSFULLY MEET SANITARY SEWER DISCHARGE STANDARDS. IN THIS CASE PINCHIN HAS RECOMMENDED TREATMENT OF THE GROUNDWATER BE COMPLETED BY PASSING IT THROUGH ACTIVATED CARBON CYLINDERS BEING PUMPED TO THE SANITARY SYSTEM.

REFER TO THE ENVIRONMENTAL AND WATER TAKING REPORTS FOR FURTHER INFORMATION.


ANY WATER TREATMENT SYSTEMS, IF REQUIRED, WILL BE DESIGNED BY OTHERS AS PART OF THE BUILDING SYSTEMS.

AS ALL REMEDIAL SCENARIOS PRESENTED REQUIRE DISCHARGE TO SANITARY SEWER, THE FOUNDATION DRAINAGE FLOW RATE OF 65,000 L/DAY (0.74 L/S) IS INCLUDED IN THE SITE FLOW RATES FOR THE SANITARY SEWER CAPACITY ANALYSIS IN THE SITE SERVING REPORT. IT IS UNDERSTOOD THAT THE WATER COLLECTED BY THE FOUNDATION DRAINAGE WILL BE COLLECTED IN A SUMP PIT(S) AND PUMPED VIA INTERNAL PLUMBING WITH THE CONNECTION TO THE SANITARY SYSTEM WITHIN THE BUILDING.

STORM INVERT SCHEDULE			
STRUCTURE	GROUND	INVERT	COMMENTS
RD#1	63.76	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#2	64.17	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#3	64.24	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#4	64.29	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#5	64.30	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#6	63.35	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#7	64.50	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#8	64.69	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#9	63.85	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#10	63.85	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#11	63.85	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
RD#12	63.85	SEE MECHANICAL	ROOF DRAIN SEE MECHANICAL
CB#1	62.92	EXISTING	REPLACE FRAME AND COVER WITH SURFACE STYLE PER CITY DETAIL S18.1
CB#2	63.17	EXISTING	REPLACE FRAME AND COVER WITH SURFACE STYLE PER CITY DETAIL S18.1
CAP AT PROPERTY LINE	63.91	62.41	CAP SERVICE AT PROPERTY LINE FOR FUTURE CONNECTION
WATERMAIN CROSSING	63.82	62.35	STM LATERAL CROSSSES OVER 200mm WATERMAIN. TOP OF WM = 61.1m (CLEARANCE = 1170mm)
SANITARY CROSSING	63.85	62.33	STM LATERAL CROSSSES OVER 200mm SANITARY SEWER. SEWER INVERT = 61.20m (CLEARANCE = 800mm)
CONNECTION TO CITY SEWER	63.87	62.32	CONNECT TO 200mm R100M SEWER AS PER CITY DWG S11. CITY SEWER INVERT 61.89m
STORM CISTERN CONNECTION	63.80	59.59	CONNECTION TO BUILDING SERVICES. SEE MECHANICAL
MONITORING MANHOLE	63.44	59.57	NEW 250mm DIAMETER MANHOLE PER OPS2 701.015. FRAME COVER PER S24.1 & S26.
WATERMAIN CROSSING	63.23	59.51	STM LATERAL CROSSSES UNDER 150mm WATERMAIN. BOTTOM OF WM = 60.75m (CLEARANCE = 900mm)
SANITARY CROSSING	63.16	59.48	STM LATERAL CROSSSES UNDER 375mm SANITARY SEWER. SEWER INVERT = 60.30m (CLEARANCE = 615mm)
CONNECTION TO CITY SEWER	63.12	59.46	CONNECT TO 100mm STORM SEWER AS PER CITY DWG S11. CITY SEWER INVERT 58.76m

PRIVATE WATERMAIN TABLE				
STATION	DESCRIPTION	TOP OF PIPE ELEVATION	GROUND ELEVATION	COMMENTS
1+00.0	BUILDING/PARKING GARAGE CONNECTION	SEE MECHANICAL	63.99	CONNECTION TO BUILDING SERVICES. SEE MECHANICAL
1+02.3	VALVE & VALVE BOX	61.48	63.88	VALVE AND VALVE BOX PER W24
1+04.7	STORM CROSSING	60.67	63.84	WATERMAIN CROSSSES UNDER 1200mm STORM SEWER (CLEARANCE = 500mm)
1+09.9	CONNECTION TO 203mm WM.	61.01	63.66	CONNECT TO CITY WATERMAIN AS PER W33
2+00.0	BUILDING/PARKING GARAGE CONNECTION	SEE MECHANICAL	63.99	CONNECTION TO BUILDING SERVICES. SEE MECHANICAL
2+02.6	VALVE & VALVE BOX	61.39	63.89	VALVE AND VALVE BOX PER W24
2+04.9	CONNECTION TO 203mm WM.	60.57	63.43	CONNECT TO CITY WATERMAIN AS PER W33
3+00.0	PARK CONNECTION	SEE MECHANICAL LANDSCAPE	64.00	NEW PARK WATER METER CHAMBER PER W31.1
3+00.8	VALVE & VALVE BOX	61.63	64.03	VALVE AND VALVE BOX PER W24
3+06.1	CONNECTION TO 203mm WM.	61.18	63.82	CONNECT TO CITY WATERMAIN AS PER W33

SANITARY INVERT SCHEDULE				
STRUCTURE	GROUND	INVERT	COMMENTS	
BUILDING/PARKING GARAGE CONNECTION	63.48	61.19	CONNECTION TO BUILDING SERVICES. SEE MECHANICAL FOR MONITORING PORT IN PARKING GARAGE	
MONITORING PORT	63.45	61.16	NEW 250mm DIAMETER MANHOLE PER CITY DETAIL S18.1. STEEL COVER REQUIRED.	
WATERMAIN CROSSING	62.82	60.99	SAN LATERAL CROSSSES OVER 100mm WATERMAIN. TOP OF WM = 60.40m (CLEARANCE = 200mm)	
CONNECTION TO MAIN SEWER	62.88	60.82	CONNECT TO 200mm SANITARY SEWER AT NEW 1200mm DIAMETER MANHOLE. SEWER INVERT 61.00. NEW MANHOLE PER OPS2 701.015. FRAME AND COVER PER S24.1 & S26.	
CAP AT PROPERTY LINE	63.91	61.50	CAP NEW SERVICE AT PROPERTY LINE FOR FUTURE CONNECTION	
WATERMAIN CROSSING	63.72	61.40	SAN LATERAL CROSSSES OVER 100mm WATERMAIN. TOP OF WM = 61.15m (CLEARANCE = 200mm). NOTE SEWER SERVICE PIPE SECTION TO BE PLACED TO AVOID JOINT NEAR WATER CROSSING	
CONNECTION TO MAIN SEWER	63.76	61.36	CONNECT TO 200mm SANITARY SEWER PER S11.1. SEWER INVERT 61.26.	



ARCHITECTURE DE PAYSAGE Landscape Architect
James B. Lennox & Associates Inc.
 3332 Carling Ave
 Ottawa, Ontario K2H 5A8
 T 613 722 5168

CIVIL, Civil
R.V. Anderson Associates Limited
 1700 Courtwood Crescent, Suite 220
 Ottawa, ON K2C 2B5
 T 613 226 1844

ARPENTEUR Surveyor
Stantec Geomatics Ltd.
 401-1531 Clyde Avenue
 Ottawa, ON K2C 3G4
 T 613 722 4420

URBANISTE Urban Planner
Fotenn Planning + Design
 398 Cooper Street - Suite 300
 Ottawa, ON K2P 2H7
 T 613 738 7708

ARCHITECTES Architect
NEUF architect(e)s SENCRL
 630, boulevard Lévesque O. 3^e étage, Montréal QC H3B 1S6
 T 514 847 1117 NEUFarchitectes.com

SCALE / Seal



R.V. Anderson Associates Limited
 engineering • environment • infrastructure



OUVRAGE Project
320 MCRAE

EMPLACEMENT Location NO PROJET No.
 320 MCRAE 194453

NO	REVISION	DATE
1	QA SUBMISSION	02/24/2020
2	FOR COORDINATION	02/26/2020
3	SITE PLAN SUBMISSION	03/20/2020
4	SITE PLAN RESUBMISSION	09/23/2020
5	EXCAVATION PERMIT FOR COORDINATION	09/25/2020
6	BUILDING PERMIT	12/22/2020
7	BUILDING PERMIT	01/04/2021
8	SITE PLAN RESUBMISSION	04/30/2021

DESSINÉ PAR Drawn by
 NR
 DATE
 01/04/21
 TITRE DU DESSIN Drawing Title

VERIFIÉ PAR Checked by
 TMK
 ECHELLE Scale
 1:250

SITE SERVING PLAN

REVISION Revision
 NO DESSIN Dwg Number





FIGURE 1: STORMWATER TANK SCHEMATIC DETAIL

NOT FOR CONSTRUCTION - SUBJECT TO CHANGE PENDING OUTSTANDING APPROVALS