

Circum Bicycle Rack
PS-76-101-TP, Circum Bike Rack

Depth: 21(5.1cm)
Diameter: 24(6.1cm)
Height: 37(9.3cm)
Weight: 21.7(9.5kg)

Our Circum Bicycle Rack features a welded tubular and flat bar steel construction. It is available in your choice of HAUSER® powdercoat finishes, or HAUSER® SHIELD Thermoplastic finishes.

sales@hausersite.com
800-268-7328
hausersite.com

Drawing Remains the Property of/Copyright Reserved by Gino J. Aiello Landscape Architect. Do Not Use or Reproduce Without Approval of Gino J. Aiello.

NOT TO Be Used For Construction Unless indicated by Contractor is Responsible for Verification of Site Locations of all Utilities. Report any Discrepancies Between Site and Drawing Immediately to Gino J. Aiello. Do NOT Proceed Until Clarified.

TURF AREAS TO BE SOD C/W 150MM DEPTH TOPSOIL ON APPROVED SUBGRADE | SOD TO BE #1 GRADE TURFGRASS NURSERY SOD per NSGA - Fine Fescue/Kentucky Bluegrass Sod | PLANTING MIX TO BE APPROVED BY LANDSCAPE ARCHITECT | PLANT MATERIAL TO MEET CNLA STANDARDS/BE APPROVED BY LANDSCAPE ARCHITECT PRIOR TO PLANTING | ALL MATERIALS & WORK TO BE MAINTAINED UNTIL FINAL ACCEPTANCE. (MOWING TURF, WEEDING BEDS, WATERING TURF & PLANTS) & INCLUDE 1 YEAR WARRANTY FROM DATE OF FINAL ACCEPTANCE | PROVIDE WATERING OF ALL PLANT MATERIAL AS REQUIRED FOR PROPER ESTABLISHMENT, UNTIL END OF WARRANTY PERIOD | REFER TO CIVIL ENGINEER'S DRAWING FOR ELEVATIONS / GRADING |

The Landscape Plan is to be read in conjunction with the grading, servicing, site and survey plan | Bare root material to be planted in season only | All plant material locations to be staked on site by the landscape contractor and checked by the landscape architect prior to planting | All trees to be preserved on or directly adjacent to the site will be protected | Plant material are to be installed a minimum of, 3.0m away from any part of any hydro transformer, 3.0m corridor between a fire hydrant and the curb, a 2.5m radius beside or behind a fire hydrant, 2.0m from any servicing/utility line or structure |



GENERAL CONCRETE NOTES:
ALL CONCRETE FINISHES TO BE APPROVED BY GJA LANDSCAPE ARCHITECT.

SAWCUT LAYOUT FOR ALL AREAS TO BE MARKED ON SITE IN RED CHALK, REVIEWED, ADJUSTED AND APPROVED BY GJA LANDSCAPE ARCHITECT-PRIOR TO ANY CUTTING.

EXPANSION JOINT LAYOUT FOR ALL AREAS TO BE LAID OUT ON SITE - REVIEWED, ADJUSTED AND APPROVED BY GJA LANDSCAPE ARCHITECT-PRIOR TO ANY CONCRETE POURING.




FINISH: TOOL EDGE FIRST, THEN WIPE OFF TOOL MARKS WHILE APPLYING FINISH

Concrete 125mm Thick, 32mpa, 6% Air Entrainment 6x6 Wire Mesh, Fibre Exp. Joints at all Hard Edges, 6m O.C. in Both Directions, Sawcut Control Joints (1" depth) 2.0m O.C. minimum



SOME QUANTITIES IN THE PLANT LIST MAY BE GREATER THAN WHAT IS SHOWN ON THE PLAN - SUPPLY AND INSTALL QUANTITIES PER PLANT LIST - CHECK WITH GJA INC. ON PLACEMENT OF ANY ADDITIONAL MATERIAL :

TREES - 1518-1526 STITTSVILLE MAIN STREET					
Code	Qty.	Botanical Name	Common Name	Size	Condition
AR	3	Acer rubrum	Red Maple	70mm cal	B + B specimen
AS	9	Acer saccharum	Sugar Maple	70mm cal	B + B specimen
CO	5	Celtis occidentalis	Common Hackberry	60mm cal	B + B specimen
GB	5	Ginkgo biloba	Maidenhair Tree	60mm cal	B + B specimen
PG	5	Picea glauca	White Spruce	1.75m Ht.	B + B specimen
SHRUBS - 1518-1526 STITTSVILLE MAIN STREET					
Code	Qty.	Botanical Name	Common Name	Size	Condition
ac	75	Amelanchier canadensis	Serviceberry	60cm Ht.	Pot
ac	20	Amelanchier canadensis	Serviceberry	100cm Ht.	Pot
ca	5	Cornus alternifolia	Pagoda Dogwood	100cm Ht.	Pot
CR	75	Cornus racemosa	Grey Dogwood	50cm Ht.	Pot
cr	5	Cornus racemosa	Grey Dogwood	100cm Ht.	Pot
HK	200	Hypericum kalmianum	St. John's Wort	40cm Ht.	Pot
SO	125	Symphoricarpos albus	Snowberry	60cm Ht.	Pot
SA	125	Spiraea alba	Meadowsweet	60cm Ht.	Pot
SV	75	Syringa vulgaris 'Alba'	White Common Lilac	60cm Ht.	Pot
VL	75	Viburnum lentago	Nannyberry	60cm Ht.	Pot
vl	10	Viburnum lentago	Nannyberry	100cm Ht.	Pot
PERENNIALS / GROUNDCOVER - 1518-1526 STITTSVILLE MAIN STREET					
Code	Qty.	Botanical Name	Common Name	Condition	
GM	75	Geranium macrorrhizum	Bigroot Geranium	9cm Pot	
GP	75	Geranium psilostemon 'Gerwat'	Rozanne Geranium	9cm Pot	
PV	85	Panicum virgatum	Switch Grass	9cm Pot	



REFER TO TCR

Existing Tree to Remain

LANDSCAPE PLAN LEGEND

Proposed Coniferous Tree

Proposed Deciduous Tree

Proposed Planting Bed

Proposed Pavers

Proposed Patio Fence, Style, Ht. TBD.

Bicycle Parking

PS-76-101-TP - Circum Bike Rack by HAUSER Anchor to Concrete

Light Standard Base

REFER TO CIVIL/CUP

U/G Water Service


U/G Storm Service

U/G Sanitary Service

O/H Hydro Service

U/G Gas Service

U/G TelCo Service



No.	Revision	Date
3	SPC SUBMISSION 3	AUGUST 5 2021
2	SPC SUBMISSION 2	APRIL 27 2021
1	SPC SUBMISSION 1	NOVEMBER 23 2020

Property Owner: **INVERNESS HOMES**
38 Auriga Drive, Suite 200, Ottawa, ON K2E 8A5

Gino J. Aiello | landscape architect GJALA.com
GJA Inc. Gino@GJALA.com (613) 852 1343
110 Dabroy Road Unit # 9 | Ottawa Ontario | K2T 0C2

Project: **THE STATION MIXED USE DEVELOPMENT**
1518 STITTSVILLE MAIN STREET

Drawing: **Landscape Plan**

Date: OCTOBER 2020
Scale: 1:200
City of Ottawa
Dwg - 18309

Sheet Number: **L1**

D07-12-20-0167