

154 Colonnade Road South
Ottawa, Ontario
Canada, K2E 7J5
Tel: (613) 226-7381
Fax: (613) 226-6344

June 03, 2025

File: PH4146-LET.01.REV.05

Stoked Industries Inc.

14 Knoll Terrace
Ottawa (Nepean), Ontario
K2J 2K6

Geotechnical Engineering
Environmental Engineering
Hydrogeology
Geological Engineering
Materials Testing
Building Science

www.patersongroup.ca

Attention: **Jason Kovar**

Subject: **Hydrogeological Report and Terrain Analysis**
2167 McGee Side Road
Carp, Ontario

Introduction

Further to your request, Paterson Group (Paterson) has conducted a Hydrogeological Report and Terrain Analysis in support of the proposed construction of a slab-on-grade commercial building which consists of office space and warehouse units to be located within the central portion of the subject site at 2167 McGee Side Road in Carp, Ontario. The purpose of these works has been to determine the suitability of the water supply aquifer underlying the site to service the proposed development and the suitability of the soils to adequately attenuate sewage effluent through a Class 4 Sewage System.

Description of Proposed Property

The majority of the subject site is currently occupied by a gravel-surfaced parking area. The ground surface is relatively flat within the central portion of the site and slopes down at the eastern and southern boundaries of the subject site, where a culvert system is present. The subject site is bordered to the north by undeveloped, densely tree land, to the east by John Cavanaugh Drive, to the south by McGee Side Road and a commercial building to the west. The site is currently zoned as General Heavy Industrial (RG). The surrounding properties to the north and west are also zoned RG, while the properties to the east and south is zoned as a Rural Commercial (RC).

Field Program

As a means to demonstrate the adequacy of the aquifer underlying the subject lands, with respect to water quality and quantity, a new drilled well was constructed and tested. The new drilled well, with a Water Well Record (WWR) ID of A313110, is referred to as TW1 for the purpose of this assessment. TW1 has a 150 mm diameter steel casing extending to a depth of 17.7 m below ground surface (bgs). The total depth of the well was indicated to be 152.4 m bgs. According to the well record, grey to brown limestone bedrock was encountered at a depth of approximately 3.0 m bgs. Based upon available geological mapping, the drift thickness varies from 3 to 5 m bgs.

The new drilled well is located in the southwest corner of the property. Refer to attached Paterson Drawing PH4146 -2 - Site Plan for the well location. The new drilled well is fully accessible with the 150 mm diameter steel casing extending 0.42 m above the existing ground surface. The well stick-up meets the minimum height requirement as per Ontario Regulation 903.

As a means to evaluate the water supply aquifer intercepted by the well, the well was subjected to a 8 hour constant rate pumping test. Due to observed elevated turbidity of the water during the test, the 8 hour pumping test was subsequently extended by a duration of 1.5 hours, totalling 9.5 hours. The extended 9.5 hour pump test successfully demonstrated a reduction in the turbidity of the water. The pumping test was conducted on March 4, 2021 under the full-time supervision of Paterson personnel.

A submersible pump was provided by Air Rock Drilling Co. (Air Rock) for the 9.5 hour pumping test. A licensed water well technician (Air Rock) was retained to complete the necessary plumbing related activities. A discharge hose assembly with a gate valve was connected to the rented pump. The discharge line was placed at a sufficient distance to ensure that the discharge water was being directed away from the well. Upon completion of the test, the pump was removed and the well was disinfected by Air Rock.

The pumping test was carried out at a pumping rate of 12 L/min for a duration of 9.5 hours. During the pumping test, the pumping rate was periodically measured using the timed volume correlation method. The pump rate was maintained within 5% of the selected pump rate. The static water level was recorded manually and an electronic datalogger (VanEssen TD-Diver) was installed in the test well prior to the start of the pumping test. The data logger recorded water levels at 30 second intervals. In addition, manual water level readings were taken at periodic intervals during the test.

Recovery data was collected from the well following the completion of the pumping. The well was noted to have achieved 95% recovery approximately 2 hours and 35 minutes after the completion of the pumping.

Groundwater samples were collected at 4 hours and 9.5 hours after the start of pumping. Prior to collection of the groundwater samples, the free chlorine residual was verified to be non-detectable. The water samples were submitted for comprehensive testing of bacteriological, chemical and physical water quality parameters consistent with the standard 'Subdivision Supply' suite of parameters.

All samples were collected unfiltered and unchlorinated and were placed directly into clean bottles supplied by the analytical laboratory. Samples were placed immediately into a cooler with ice and were transported directly to the Eurofins laboratory in Ottawa. All samples were received by the laboratory within 24 hours of collection.

A series of field tests of the pumped water were carried out at the well head during the 9.5 hour pumping test. The parameters tested at the well head included: pH, total dissolved solids, conductivity, turbidity and temperature.

Aquifer Analysis

Water Quantity

Pumping test data was analyzed using AquiferTest Pro (v. 2016.1) aquifer analysis software package by Schlumberger Water Services. Drawdown data was measured using an electronic water level tape and an electronic datalogger unit.

TABLE 1:SUMMARY OF WATER SUPPLY AQUIFER CHARACTERISTICS OF TW1	
AQUIFER PARAMETER	RESULT OF ANALYSIS
Transmissivity (m ² /day)	0.09
Pumping Rate (L/min)	12
Pre-test Static Water Level (m)	4.01
Post-test Water level (m)	41.30
Available Drawdown (m)	148.39
% Drawdown During Pumping Test	25.13
Specific Capacity (L/min/m drawdown)	0.32

The drawdown data was analyzed using the Theis (Theis, 1935) and the Theis Recovery methods of analysis. Aquifer transmissivity is estimated to be approximately 0.09 m²/day.

The pumping test results show that TW1 has a high yield to support the water demands for the proposed building. Overall maximum drawdown at a constant pumping rate for a period of 9.5 hrs was approximately 37.29 m (25.13 % of the available drawdown). 95%

recovery was achieved approximately 2.6 hours after the end of pumping. The total volume of water pumped during the 9.5 hour pumping test was approximately 6,840 L. This is approximately 1.6 times the maximum total daily design volume of water required to support the proposed commercial development (maximum 4,327 L/day). The total daily design sewage flow (TDDSF) volume was provided by D.B. Gray Engineering and is discussed in the Terrain Analysis portion of this report.

The suitability of the aquifer to supply the proposed commercial development was assessed using the methodology provided in MECP Procedure D-5-5 (MOEE, 1996).


Based on the information summarized in Table 1, it is readily apparent that the new water supply well has intercepted an adequately strong water supply aquifer. It is considered to have sufficient quantity to service the proposed commercial development under typical usage, in addition to the neighboring buildings whose wells may intercept the same water supply aquifer.

The majority of the available water well records for the neighbouring properties on the MECP Well Record mapping website consist of agricultural use, commercial use, or public use well records. All surrounding WWR are attached to this report.

Water Quality

Field Data

Turbidity, electrical conductivity, total dissolved solids (TDS), pH and temperature were measured at the wellhead during the pumping test. The measurements and time intervals for each of these parameters are summarized on the graphical representation below. In addition, a Hach Pocket Colorimeter II chlorine reader was used to measure the free chlorine residual level. No chlorine residual was detected in the discharge water prior to the collection of the water samples.



Laboratory Data

The laboratory water quality obtained from the pumping test of TW1 is provided in Table 2 below and the laboratory analyses reports can be found attached.

TABLE 2: GROUNDWATER GEOCHEMISTRY (TW1)					
PARAMETER	UNITS	ODWS		TW1	
		LIMIT	TYPE	GW1 (4 hr) 2021-03-05	GW2 (9.5 hr) 2021-03-05
MICROBIOLOGICAL					
Escherichia Coli (E.Coli)	ct/100mL	0	MAC	0	0
Total Coliforms	ct/100mL	0	MAC	0	0
GENERAL CHEMICAL - HEALTH RELATED					
Fluoride	mg/L	1.5(2.4)	MAC	0.15	0.14
N-NO2 (Nitrite)	mg/L	1	MAC	<0.10	<0.10
N-NO3 (Nitrate)	mg/L	10	MAC	<0.10	<0.10
Turbidity (Laboratory)	NTU	1.0 (5.0)	MAC/AO	>100	2.00
Turbidity (Field)	NTU	1.0 (5.0)	MAC/AO	>100	3.83
N-NH3 (Ammonia)	mg/L	-	-	0.02	0.02
Total Kjeldahl Nitrogen	mg/L	-	-	0.20	0.10
GENERAL CHEMICAL - AESTHETIC RELATED					
Hardness (as CaCO3)	mg/L	100	OG	382	391
Ion Balance	unitless	-	-	1.02	1.04
Total Dissolved Solids	mg/L	500	AO	640	640
Alkalinity (as CaCO3)	mg/L	500	OG	346	344
Chloride	mg/L	250	AO	120	119
Colour	TCU	5	AO	<2	<2
Conductivity	uS/cm	-	-	1,100	1,100
pH	unitless	6.5-8.5	AO	7.98	8.02
Sulphide	mg/L	0.05	AO	<0.1	0.03
Sulphate	mg/L	500	AO	83	79
Calcium	mg/L	-	-	115	117
Iron	mg/L	0.3	AO	3.69	0.09
Potassium	mg/L	-	-	5	4
Magnesium	mg/L	-	-	23	24
Manganese	mg/L	0.05	AO	0.06	<0.01
Sodium	mg/L	200	AO	105	103
Phenols	mg/L	-	-	<0.001	<0.001
Tannin & Lignin	mg/L	-	-	<0.1	<0.1
Dissolved Organic Carbon	mg/L	5	AO	1.50	1.50

- ODWS identifies the following types of parameters:
MAC=Maximum Allowable Concentration
AO = Aesthetic Objective
OG= Operational Guideline
- Shaded Concentration Indicates an Exceedance of the ODWS Objective

The bacteriological test results (Certificate of Analysis - Report No. 1948880) indicated that E.Coli and Total Coliforms were non detect in the well water (0 ct/100mL). Paterson personnel confirmed that the free chlorine residual was 0 mg/L prior to the collection of the bacteriological sample.

The water quality of the subject water supply well meets all the Ontario Drinking Water Standards (ODWS) maximum acceptable concentrations (MAC). Furthermore, the water meets all of the aesthetic objectives (AO) and operational guidelines (OG) with the exception of the following:

- ☐ Hardness (As CaCO_3)
- ☐ TDS
- ☐ Turbidity

Each of these groundwater parameters are discussed in detail below. It should be noted that the results of the 4 hour field tests were likely effected by sediments from seams within the bedrock aquifer which were disturbed by the pump test. This is further supported by the substantial reduction in turbidity, iron and manganese observed in the 9.5 hour test results.

Hardness as CaCO_3

Hardness, expressed as calcium carbonate, an operational guideline, does not appear in the ODWS. Rather, it appears in the Technical Support Documents for Ontario Drinking Water Standards, Objectives and Guidelines as a parameter with an operational guideline of 100 mg/L. At the measured concentration of 391 mg/L, the water is considered to be hard. The Technical Support Document for ODWS publication states that water with hardness in excess of 500 mg/L may be unacceptable for most domestic purposes, however, there is no maximum treatable value available. It is expected the hardness concentration can be treated using commercial grade water softener technologies, if desired by the owner.

TDS

Total dissolved solids (TDS) refers to the concentration of inorganic substances dissolved in water. The main constituents are typically chloride, sulphates, calcium, magnesium and bicarbonates. Water with a TDS concentration above 500 mg/L of TDS may not palatable. Procedure D-5-5 does not provide a 'treatability limit' for TDS, but it does require written rationale that corrosion, encrustation, or taste problems will not occur.

If desired, the owner has the ability to install an off-the-shelf reverse osmosis system that can adequately treat the TDS levels noted in the results. It should be noted this is not considered a recommendation and should only be installed if taste is considered an issue

by the end user. The owner has the ability to retain a water treatment specialist to ensure the taste of the water meets their needs.

The Langelier Saturation Index (Langelier, 1936) is used to predict the calcium carbonate stability of water. It indicates whether the water will precipitate, dissolve, or be in equilibrium with calcium carbonate. The results of the Langelier calculation ($LSI = 0.8$) indicate the water is super saturated and tends to precipitate a scale layer of calcium carbonate (scale forming but non-corrosive). See Langelier Saturation Index Calculation attached for calculation details.

Turbidity

Turbidity, which is generally an aesthetic parameter, was detected in the laboratory test samples at values of >100 and 2.0 NTU in the 4 and 9.5 hour tests, respectively. Field testing detected the samples at values of >100 and 3.83 NTU in the 4 and 9.5 hour tests, respectively. The pump test was extended from 8 to 9.5 hours to demonstrate that continued pumping would result in a decrease in turbidity. It is expected that further development of the well would further reduce turbidity values. The elevated turbidity in the laboratory sample from the 4 hour test result (>100 NTU) is attributed to the clearing out of seams within the bedrock.

The ODWS maximum acceptable concentration for turbidity in drinking water entering the distribution system is 1 NTU. The Aesthetic Objective for turbidity in drinking water reaching the consumer is 5 NTU. The field test parameters at 9.5 hours are below the 5 NTU objective.

Sodium

Sodium is an aesthetic parameter, and was detected in the test samples at a concentration of 105 and 103 mg/L, which is less than the ODWS aesthetic objective of 200 mg/L. Sodium is a unique water quality parameter in that it has a cautionary limit of 20 mg/L for health related purposes, but can be present in raw water up to 200 mg/L and still be within the aesthetic objective. It is a requirement of the ODWS that the Medical Officer of Health be notified of the water quality results where sodium is present in concentrations exceeding 20 mg/L and it is intended for consumption. The purpose of this is such that the information can be disseminated to local physicians for their use in the treatment of individuals requiring reduced sodium dietary needs.

Terrain Analysis

Surficial Geology

Field investigations were carried out on November 20, 2020 as part of the Geotechnical Investigation. The investigation consisted of advancing 7 boreholes to maximum depths ranging from 1.6 and 4.8 m below ground surface (bgs), respectively. The test holes were distributed in a manner to provide general coverage of the proposed development taking into consideration site features. The location of the test holes on the property are delineated on the Test Hole Location Plan, Drawing No. PG6662-1 - Test Hole Location Plan, attached.

The test hole locations were recorded and the subsurface conditions, including the soil morphology and depth to the groundwater table (if encountered), were carefully observed and recorded. The soils encountered were classified texturally in the field, and later reviewed in the laboratory.

The subsurface profile consisted of fill material extending to depths of 0.3 to 0.6 m bgs and consists of various amounts of silty sand with crushed stone, gravel and organics. The fill material is underlain by a glacial till deposit consisting of brown silty sand with gravel, cobbles and boulders. Practical refusal to augering was encountered at depths ranging from 1.6 and 4.8 m bgs. Groundwater levels were measured in the boreholes at depths ranging from 0.9 to 4.0 m bgs.

Reference should be made to the borehole logs appended to this report for the details of the soil profiles encountered at each test hole location. The client should be aware that any information pertaining to soils are furnished as a matter of general information only and borehole descriptions are not be interpreted as descriptive of conditions at locations other than those described by the boreholes themselves.

A sieve was submitted from BH 7-20 - SS2 at a depth of 0.8 to 1.4 m near the proposed area of the septic bed. In accordance with Unified Soil Classification System (USCS) the soil type is defined as a silty sand. Analytical results from the sieve testing can be found attached.

Hydrogeological Sensitivity of the Site

The subject site is bordered to the north by undeveloped, densely tree land, to the east by John Cavanaugh Drive, to the south by McGee Side Road and a commercial building to the west. The subject development will be serviced by a private well and septic system.

Based upon the field investigations, the overburden thickness ranges from approximately

1.6 to 4.8 m depth at the borehole locations. The overburden soils are recorded to consist of fill material overlying a glacial till.

As the proposed site is expected to have bedrock within 2 m of the ground surface in areas, the site is considered hydrogeologically sensitive. Horizontal separation distances have been doubled between the septic components and the onsite well to a minimum of 30 m. The minimum well casing depth for the constructed TW1 has been extended to greater than double the minimum length (>12 m), at 17.7 m below ground surface.

The topography of the site is relatively flat within the central portion of the site and slopes down at the eastern and southern boundaries of the subject site, where a culvert system is present. The regional groundwater flow is considered to be in a northeasterly direction, towards the Carp River.

The water quality of the bedrock aquifer targeted as the preferred water supply aquifer for the development, shows no indications of surface water or surface impacts from sewage system effluent.

Additionally, a Phase I Environmental Site Assessment was completed by Paterson in February 2021. At that time, a historical review of neighbouring sites was completed to determine nearby potentially contaminating activities (PCAs). One (1) PCA was identified within the Phase 1 Study Area, however, based on the location and type of waste products produced at the property, the operation was not considered to pose a risk to the subject site. Further, the depth of the well, (152.4 m bgs) and the well casing (17.7 m bgs) protect the well from contamination.

Conceptual Lot Development Plan

It is proposed that a slab-on-grade commercial building which consists of office space and warehouse units will be constructed within the centre of the subject site. The location of the proposed structure can be found on the attached Paterson Drawing PH4146 - 2 - Site Plan. It illustrates that the proposed design layout is adequate to accommodate the associated private services and meet all the regulated separation criteria.

Sewage System Design

In order to minimize the risk of long-term contamination of services, a minimum horizontal separation distance of 30 metres is recommended between the onsite drilled well and the closest distribution pipe of the onsite sewage system. This separation distance shall be increased according to the OBC requirements for beds constructed above the original ground surface. In consideration of the proposed location of the septic area, the existing wells, the proximity of the neighbouring sewage systems and wells with respect to the

proposed sewage system, the minimum regulatory separation distances can be easily attained on the subject property. In addition, a minimum of 100 mm of imported soil seal may be required to provide system isolation due to the shallow overburden (<2 m). The sewage system design is being completed by D.B. Gray Engineering.

Total Daily Design Sewage Flow

A total daily design sewage flow (TDDSF) of 4,327 L/day was provided by D.B. Gray Engineering for the office space and the warehouse unit. It is understood that the above noted TDDSF is based on available design details provided by Stoked Industries Inc. at the time of report preparation. Typical commercial developments will have lower actual loading compared to the conservative design loads as per the OBC.

Proposed Sewage System

Based on the approved septic permit, it is understood that a Class 4 Sewage System will be installed at the subject site. The system is expected to have a daily design load capacity of 4,327 L/day and will govern the allowable flows under the current Ontario Building Code (OBC). Also, a minimum of 100 mm of imported soil seal may be required to provide system isolation due to the shallow overburden (<2 m).

PREDICTIVE NITRATE IMPACT ASSESSMENT

In order to demonstrate that private services would adequately support the proposed commercial development, a predictive nitrate impact assessment for the subject site was completed. The values shown in the Predictive Nitrate Impact Assessment attached to this report are summarized below.

☐	Site area	0.8 Ha
☐	Impervious area %	58 %
☐	Daily sewage flow (Average daily flow - Peak. It is expected that actual volumes will be much lower)	Maximum 4.3 m ³
☐	Concentration of nitrate in effluent (Value based on typical effluent concentration)	40 mg/L
☐	Concentration of nitrate in effluent with treatment (Value based on tertiary treatment system with 90% nitrate reduction)	4 mg/L

- | | | |
|------------------------------|---|-------------|
| ☐ | Surplus Water | 402 mm/year |
| | (The surplus water value was estimated based on Environment Canada Climate Office values with a soil type comprised of fine sand (Urban Lawn/Shallow Rooted Crops) and anthropogenic sources. | |
|
☐ | Combined infiltration factor based on: | 0.65 |
| | ● Topography infiltration factor | 0.25 |
| | ● Soil texture infiltration factor | 0.30 |
| | ● Cover infiltration factor | 0.10 |

The topography infiltration factor of 0.25 is based upon a combination of flat land with average slope < 0.6 m/km and rolling land, average slope 2.8 to 3.8 m/km for the proposed development.

The soil texture infiltration factor was based upon an “open sandy loam” with a value of 0.3 which is a reasonable generalization based upon the site investigation and available geological mapping.

The “vegetative cover infiltration factor” was calculated as 0.1 based upon the minimum value for cultivated land.

An existing approved tertiary treatment system capable of reducing the nitrate loading in the effluent is the Waterloo Biofilter brand. The system has an available nitrate reduction of 25 to 35% based upon the standard single pass system and 50 to 65% based upon a double pass re-circulation system. With the addition of the WaterNOx system, 90 to 95% total nitrogen removal can be achieved. This would reduce the nitrate concentration in the effluent from 40 mg/L down to as low as 4 mg/L. The calculation for the septic system results in a predicted nitrate concentration of 2.6 mg/L nitrate concentration for the subject site, using a value of 4 mg/L nitrate concentration within the effluent.

Based on the predicted nitrate concentration, nitrate reduction in the form of the Waterloo Biofilter WaterNOX treatment system will be required for the sewage system in order for the development to reach the required value at the property boundaries.

Based on the results of the predicted nitrate impact assessment, it is our opinion that the proposed property can adequately support the proposed commercial development without having an adverse impact on the underlying bedrock aquifer.

Conclusions

Based on the information contained within the body of this report, the following conclusions can be drawn:

1. The results of the water supply assessment have provided satisfactory evidence that the water supply aquifer underlying the subject site can support the proposed commercial development from both a quality and quantity perspective.
2. The preferred water supply aquifer intercepted by TW1 contains a water supply that is potable, and contains only elevated concentrations of hardness, TDS, and turbidity. The above noted parameters can be treated with current readily available water conditioning equipment.
3. It is anticipated that further development of the onsite well will reduce turbidity levels to below 1 NTU.
4. The sodium concentrations were measured to be above the 20 mg/L reporting limit and, as such, the Medical Officer of Health for the City of Ottawa should be informed to assist area physicians in the treatment of local residents on sodium reduced diets.
5. The onsite well and septic system components must have a minimum of 30 m horizontal separation as the site is considered hydrogeologically sensitive. Any onsite wells must be designed to have double the minimum casing length required by O.Reg 903 for a total of 12 m.
6. The predicted nitrate concentrations at the property boundaries are predicted to be less than the required 10 mg/L threshold with a Waterloo Biofilter WaterNOx treatment system based on a maximum volume of 4,327 L/day.
7. The subject site is sufficient in size to accommodate a new sewage system and meet all the regulatory separation criteria.
8. A Sewage System Permit and Building Permit need to be issued prior to the commencement of construction on the proposed commercial development or the proposed septic system.
9. The results of the Hydrogeological Report and Terrain Analysis have provided satisfactory evidence that the subject site can support the proposed commercial development with respect to water quality, quantity and sewage system placement.

10. The construction of an onsite sewage system will not affect the performance or water quality associated with a drilled well, contingent upon the on site sewage system is designed in accordance with the Ontario Building Code (i.e. properly sized sewage system and conforming to all separation distances) and a minimum 100 mm soil seal provided beneath the leaching bed/mantle area to ensure system isolation.

We trust that this satisfies your present requirements. Should you have any questions regarding this submission, please do not hesitate to contact the undersigned.

Yours truly,

PATERSON GROUP INC.



Erik Ardley, P.Geo



Michael S. Killam, P.Eng.

Attachments:

- ☐ MECP Water Well Record's
- ☐ Eurofins Certificate of Analysis
- ☐ AquiferTest Pro - Pumping Test Analysis Reports
- ☐ Langelier Saturation Index Calculation
- ☐ PG5602: Soil Profile and Test Data Logs
- ☐ Paterson Drawing PG6662-1 - Test Hole Location Plan
- ☐ Paterson Drawing PH4146-2 - Site Plan
- ☐ Paterson Sieve Analysis
- ☐ Predictive Nitrate Impact Assessment Calculations
- ☐ D.B. Gray Engineering Drawing C - 1 - Site Servicing Plan
- ☐ D.B. Gray Engineering Drawing C - 2 - Septic System
- ☐ Waterloo Biofilter WaterNOx System Information
- ☐ Water Well Disinfection Instructions.

Paterson Group Inc.

Ottawa Head Office
154 Colonnade Road South
Ottawa - Ontario - K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344

Ottawa Laboratory
28 Concourse Gate
Ottawa - Ontario - K2E 7T7
Tel: (613) 226-7381 Fax: (613) 226-6344

Northern Office and Laboratory
63 Gibson Street
North Bay - Ontario - P1B 8Z4
Tel: (705) 472-5331 Fax: (705) 472-2334

Measurements recorded in: ☐ Metric ☒ Imperial

Page ____ of ____

Well Owner's Information

First Name: 11840398 Last Name/Organization: Canada Inc. E-mail Address: ☐ Well Constructed by Well Owner
Mailing Address (Street Number/Name): Unit #4-11 Triston Court Municipality: Nepean Ont Province: KAM Postal Code: 1B4 Telephone No. (inc. area code):

Well Location

Address of Well Location (Street Number/Name): #2167 MCGEE SIDE ROAD Township: Huntley Lot: 11 Concession: 2
County/District/Municipality: Ottawa-Carleton City/Town/Village: Corp Province: Ontario Postal Code:
UTM Coordinates Zone: Easting: Northing: Municipal Plan and Sublot Number: Other:
NAD 83 18421737 5018421 PLAN 5R-126 10

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (mft) From To
(Hard packed)	Sand & Gravel			0' 10'
	Gray limestone			10' 130'
	Gray & Brown limestone			130' 200'
	Gray limestone			200' 500'


Annular Space		
Depth Set at (mft) From To	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
58' 48'	Neat Cement Slurry	10.92
48' 0'	Bentonite Slurry	16.80

Method of Construction		Well Use	
☐ Cable Tool	☐ Diamond	☐ Public	☐ Commercial
☐ Rotary (Conventional)	☐ Jetting	☒ Domestic	☐ Municipal
☐ Rotary (Reverse)	☐ Driving	☐ Livestock	☐ Test Hole
☐ Boring	☐ Digging	☐ Irrigation	☐ Monitoring
☒ Air percussion		☐ Industrial	☐ Cooling & Air Conditioning
☐ Other, specify		☐ Other, specify	


Construction Record - Casing			Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (mft) From To	☒ Water Supply
6 1/4"	Steel	.188"	+2' 58'	☐ Replacement Well
6"	Open Hole		58' 500'	☐ Test Hole
				☐ Recharge Well
				☐ Dewatering Well
				☐ Observation and/or Monitoring Hole
				☐ Alteration (Construction)
				☐ Abandoned, Insufficient Supply
				☐ Abandoned, Poor Water Quality
				☐ Abandoned, other, specify
				☐ Other, specify

Construction Record - Screen			
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (mft) From To


Water Details		Hole Diameter	
Water found at Depth (mft)	Kind of Water: ☐ Fresh ☒ Untested ☐ Other, specify	Depth (mft) From To	Diameter (cm/in)
297'	☐ Gas ☒ Untested	0' 58' 9 3/4"	
487'	☐ Gas ☒ Untested	58' 500' 6"	
	☐ Gas ☐ Untested		
	☐ Gas ☐ Other, specify		

Well Contractor and Well Technician Information			
Business Name of Well Contractor		Well Contractor's Licence No.	
AIR ROCK DRILLING Co LTD		C7681	
Business Address (Street Number/Name)		Municipality	
6639 Franktown Road		Richmond	
Province	Postal Code	Business E-mail Address	
Ont	K6A2Z0		
Bus. Telephone No. (inc. area code)		Name of Well Technician (Last Name, First Name)	
6158382170		HANNA Jeremy	
Well Technician's Licence No.	Signature of Technician and/or Contractor		Date Submitted
T3632			00210430

Results of Well Yield Testing			
After test of well yield, water was:		Draw Down	
☐ Clear and sand free		Time (min)	Water Level (mft)
☐ Other, specify		Time (min)	Water Level (mft)
If pumping discontinued, give reason:		Static Level	
☒		1 18.9	65.8"
Pump intake set at (mft): 290'		2 20.7	61.7
Pumping rate (l/min/GPM): 345		3 22.3	60.6
Duration of pumping: 1 hrs + 0 min		4 23.7	59.4
Final water level end of pumping (mft): 65' 8"		5 25.	58.3
If flowing give rate (l/min/GPM):		10 31.	52.7
☒		15 36.1	47.6
Recommended pump depth (mft): 450'		20 40.8	42.9
Recommended pump rate (l/min/GPM): 2		25 45.	38.8
Well production (l/min/GPM): 2		30 48.9	35.1
Disinfected? ☒ Yes ☐ No		40 52.9	29.1
		50 62.	24.7
		60 65.8"	19.2

Map of Well Location	
Please provide a map below following instructions on the back. 	

Comments: 1HP 5GPM SAT @ 450 FT	
Well owner's information package delivered: ☒ Yes ☐ No	Date Package Delivered: 00210221
Date Work Completed: 00210223	Ministry Use Only: Audit No. Z355007
	Received:



Address. AP 3 Cus

Pumping Test

Static level 16'
 Test-pumping rate 6 G.P.M.
 Pumping level 18'
 Duration of test pumping 1 hr.
 Water clear or cloudy at end of test clear
 Recommended pumping rate 5 G.P.M.
 with pump setting of 35 feet below ground surface

Water Record

Kind of water
(fresh, salty,
sulphur)

Clay Limestone

$$\frac{0}{2}$$
$$\frac{2}{120}$$


120

1703H

O W R C COPY

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



CSF.53

Form 5
15M-58-4149

98



GROUND WATER BRANCH
JUN 15 1962
ONTARIO WATER
RESOURCES COMMISSION

3069

UTM 18 Z 421735 E

5 R 5018140 N

The Ontario Water Resources Commission Act

Elev. 4 R 0380

WATER WELL RECORD

Basin 25
County or District *Carleton*

Township, Village, Town or City *Huntley*

Con. *2* Lot *11*

Date completed *28 May 62*
(day month year)

Address *RR3 Corp*

Casing and Screen Record

Inside diameter of casing *4 1/2"*
Total length of casing *12*
Type of screen
Length of screen
Depth to top of screen
Diameter of finished hole *4"*

Pumping Test

Static level *20'*
Test-pumping rate *6* G.P.M.
Pumping level *55'*
Duration of test pumping *1 1/2*
Water clear or cloudy at end of test *clear*
Recommended pumping rate *5* G.P.M.
with pump setting of *100* feet below ground surface

Well Log

Overburden and Bedrock Record

*previously drilled
limestone*

From ft.

To ft.

Depth(s) at which water(s) found

Kind of water (fresh, salty, sulphur)

<i>70</i>	<i>130</i>	<i>125'</i>	<i>fresh</i>
-----------	------------	-------------	--------------

Water Record

For what purpose(s) is the water to be used?

house

Is well on upland, in valley, or on hillside?

upland

Drilling or Boring Firm *Ben E. Sparks*

Address

Licence Number *700*

Name of Driller or Borer *Ben E. Sparks*

Address *413 Edgeworth*

Date *May 28/62*

(Signature of Licensed Drilling or Boring Contractor)


Ben E. Sparks

Form 7 15M Spts. 60-3930

OWRC COPY

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



RD 17

*CON 2
LOT 10*

UTM 18 Z 421750 E



15 N^o 3070
JUN 10 1964
ONTARIO WATER RESOURCES COMMISSION

5 R 5018265 N

The Ontario Water Resources Commission Act

Elev: 4 R 0380

WATER WELL RECORD

Basin 25
County or District Hamilton

Township, Village, Town or City Huntley

Con. 2 Lot 11

Date completed 5 (day) June (month) 1964 (year)

Address Carp

Casing and Screen Record

Inside diameter of casing 6 1/4"
Total length of casing 22'
Type of screen ✓
Length of screen ✓
Depth to top of screen ✓
Diameter of finished hole 6"

Pumping Test

Static level 20'
Test-pumping rate 8 G.P.M.
Pumping level 90'
Duration of test pumping 1 hr.
Water clear or cloudy at end of test clear
Recommended pumping rate 5 G.P.M.
with pump setting of 100 feet below ground surface

Well Log

Water Record

Overburden and Bedrock Record

From ft.

To ft.

Depth(s) at which water(s) found

Kind of water (fresh, salty, sulphur)

loam gray limestone

4

4
105

71
105

fresh

For what purpose(s) is the water to be used?

New house

Is well on upland, in valley, or on hillside? upland.

Drilling or Boring Firm A. Stanton

Address Pakenham

Licence Number 1475

Name of Driller or Borer A. Stanton


Address Pakenham

Date June 5/64

Arthur Stanton
(Signature of Licensed Drilling or Boring Contractor)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



UTM CON III
78 421600 E
54 5618220 N



15 No. 3126
SEP 14 1964

Elev. 4 R 0390

WATER WELL RECORD

Basin 25
County or District Carleton

Township, Village, Town or City Huntley

Con. 3 Lot 11

Date completed 3 (day) Sept (month) 1964 (year)

Address Carp

Casing and Screen Record

Inside diameter of casing 6 1/4"
Total length of casing 14'
Type of screen ✓
Length of screen ✓
Depth to top of screen ✓
Diameter of finished hole 6"

Pumping Test

Static level 23
Test-pumping rate 6 G.P.M.
Pumping level 90'
Duration of test pumping 1 hr.
Water clear or cloudy at end of test clear
Recommended pumping rate 5 G.P.M.
with pump setting of 100 feet below ground surface

Well Log

Overburden and Bedrock Record

shale
grey limestone

Water Record

From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
<u>0</u>	<u>12</u>	<u>7'</u>	<u>fresh</u>
<u>12</u>	<u>108</u>	<u>108</u>	

For what purpose(s) is the water to be used? house

Is well on upland, in valley, or on hillside? upland

Drilling or Boring Firm A. Stanton

Address Parkexham

Licence Number 1475

Name of Driller or Borer A. Stanton


Address Parkexham

Date Sept 3/64

A. Stanton
(Signature of Licensed Drilling or Boring Contractor)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.





WATER WELL RECORD

319/58

Water management in Ontario

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

11

1511921

15005

CON.

CDN

02

COUNTY OR DISTRICT <i>Carleton Place</i>	TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE <i>Huntley</i>	CON., BLOCK, TRACT, SURVEY, ETC. <i>2</i>	LOT <i>011</i>
OWNER (SURNAME FIRST) <i>[Redacted]</i>	ADDRESS <i>Bram. Marie Rd. R.R. #2</i>	DATE COMPLETED DAY <i>06</i> MO. <i>05</i> YR. <i>72</i>	
ELEVATION <i>018326</i>		BASIN CODE <i>4 394 4 26</i>	

JAN 12, 1975 44

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
<i>brown</i>	<i>sand</i>		<i>fill</i>	<i>0</i>	<i>3</i>
<i>brown</i>	<i>"</i>	<i>stones</i>	<i>packed</i>	<i>3</i>	<i>9</i>
<i>grey</i>	<i>limestone</i>			<i>9</i>	<i>141</i>

31	000362801	000962812	0141215
32			

41 WATER RECORD	
WATER FOUND AT - FEET	KIND OF WATER
10-13	1 ☒ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
15-18	1 ☒ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
20-23	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
25-28	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
30-33	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL

51 CASING & OPEN HOLE RECORD			
INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET
			FROM TO
<i>1 1/4</i>	☒ STEEL	<i>1.88</i>	<i>0 022</i>
<i>5/8</i>	☒ GALVANIZED		<i>22 141</i>
<i>5/8</i>	☐ CONCRETE		
<i>5/8</i>	☐ OPEN HOLE		
<i>06</i>	☒ STEEL		<i>22 0141</i>
	☐ GALVANIZED		
	☐ CONCRETE		
	☐ OPEN HOLE		

61 PLUGGING & SEALING RECORD	
DEPTH SET AT - FEET	MATERIAL AND TYPE (CEMENT GROUT, LEAD PACKER, ETC.)
FROM TO	
10-13	14-17
18-21	22-25
26-29	30-33

71 PUMPING TEST	
PUMPING TEST METHOD 1 ☒ PUMP 2 ☐ BAILER	PUMPING RATE <i>0007</i> GPM.
STATIC LEVEL <i>020</i> FEET	WATER LEVEL END OF PUMPING <i>075</i> FEET
WATER LEVELS DURING 15 MINUTES <i>075</i> FEET 30 MINUTES <i>075</i> FEET 45 MINUTES <i>075</i> FEET 60 MINUTES <i>075</i> FEET	
IF FLOWING, GIVE RATE <i>000.1</i> GPM.	PUMP INTAKE SET AT <i>090</i> FEET
RECOMMENDED PUMP TYPE ☐ SHALLOW ☒ DEEP	RECOMMENDED PUMP SETTING <i>090</i> FEET
	RECOMMENDED PUMPING RATE <i>0005</i> GPM.


FINAL STATUS OF WELL	1 ☒ WATER SUPPLY 2 ☐ OBSERVATION WELL 3 ☐ TEST HOLE 4 ☐ RECHARGE WELL	5 ☐ ABANDONED, INSUFFICIENT SUPPLY 6 ☐ ABANDONED, POOR QUALITY 7 ☐ UNFINISHED
WATER USE	1 ☒ DOMESTIC 2 ☐ STOCK 3 ☐ IRRIGATION 4 ☐ INDUSTRIAL 5 ☐ OTHER	5 ☐ COMMERCIAL 6 ☐ MUNICIPAL 7 ☐ PUBLIC SUPPLY 8 ☐ COOLING OR AIR CONDITIONING 9 ☐ NOT USED
METHOD OF DRILLING	1 ☐ CABLE TOOL 2 ☐ ROTARY (CONVENTIONAL) 3 ☐ ROTARY (REVERSE) 4 ☐ ROTARY (AIR) 5 ☒ AIR PERCUSSION	6 ☐ BORING 7 ☐ DIAMOND 8 ☐ JETTING 9 ☐ DRIVING

LOCATION OF WELL	
IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE. INDICATE NORTH BY ARROW.	
DRILLERS REMARKS:	

NAME OF WELL CONTRACTOR <i>Capital Water Supply</i>	LICENCE NUMBER <i>1558</i>
ADDRESS <i>Box 490 Stittsville Ont.</i>	
NAME OF DRILLER OR BORER <i>Walter Hannagh</i>	LICENCE NUMBER
SIGNATURE OF CONTRACTOR <i>Walter Hannagh</i>	SUBMISSION DATE DAY <i>5</i> MO. <i>5</i> YR. <i>72</i>

DATA SOURCE <i>1</i>	58 CONTRACTOR <i>1558</i>	59-62 DATE RECEIVED <i>041072</i>	63-68
DATE OF INSPECTION	INSPECTOR		
REMARKS:			
	P	R	
	W	I	

OWRC COPY



Water management in Ontario

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

11

1512118

MUNICIP

15005

CON

CON.
CON

b3

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

31 001521128 0125215

32 10 14 15 21 32 12

61 PLUGGING & SEALING RECORD			
DEPTH SET AT - FEET		MATERIAL AND TYPE (CEMENT GROUT, LEAD PACKER, ETC.)	
FROM	TO		
10-13	14-17		
18-21	22-25		
26-29	30-33	80	

LOCATION OF WELL

IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE. INDICATE NORTH BY ARROW.

The diagram shows a vertical line representing a lot boundary and a horizontal line representing a road. The area to the left of the vertical line is labeled 'Lot 10' and contains the Roman numeral 'III'. The area to the right is labeled 'Lot 11' and contains the Roman numeral 'II'. A well location is marked with a cross and the letters 'O.C.' on the vertical line. A horizontal arrow points from the road to the well, labeled '44\''. A vertical arrow points from the road to the well, labeled '157\''. A north arrow is in the upper right corner.

Lot 11

Lot 10

III

II

157'

44'

O.C.

DRILLERS REMARKS:

DRILLERS REMARKS:

OFFICE USE ONLY	DATA SOURCE	58	CONTRACTOR	59-62	DATE RECEIVED	63-68	90
	1		1558		101172		
	DATE OF INSPECTION		INSPECTOR				
			K				
REMARKS:						P	R
						WI	

OWRC COPY



1512382

316/59 P

3502376

3

9

The Ontario Water Resources Commission Act

Basin

WATER WELL RECORD

County or District

Township, Village, Town or City

Con. 2

Lot 11

Date completed

18

(day)

month

year

Address

Casing and Screen Record

Inside diameter of casing 6 1/4"

Total length of casing 22'

Type of screen

Length of screen

Depth to top of screen

Diameter of finished hole 6"

Pumping Test

Static level 10

Test-pumping rate 6 G.P.M.

Pumping level 90

Duration of test pumping 1 hr.

Water clear or cloudy at end of test clear

Recommended pumping rate G.P.M.

with pump setting of 100 feet below ground surface

Well Log

Water Record

Overburden and Bedrock Record

	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
Shale	0	10	63	fresh
grey limestone	10	129	129	

For what purpose(s) is the water to be used?

house

Is well on upland, in valley, or on hillside? upland

Drilling or Boring Firm A. Stanton

Address Pakenham

Licence Number 3060

Name of Driller or Borer SAME


Address

Date Sept 18/68

(Signature of Licensed Drilling or Boring Contractor)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.





WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

11

1516282

MUNICIP 15005

CON. C/N

02

COUNTY OR DISTRICT CARLETON	TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE HUNTLEY	CON. BLOCK, TRACT, SURVEY, ETC. CON. #1 II	LOG 212
Carp Rd - R.R. #1, KANATA		DATE COMPLETED 16 08 77	
ELEVATION 018099		BATHY CODE 0380	

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
BROWN	SAND	Small Boulders	Coarse	0	31
				31	50
White	Sandstone		Coarse	0	21
				21	50

31	002141013	005011863
32		

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER
10-13	1 ☒ FRESH 3 ☐ SULPHUR 4 ☐ MINERAL
15-18	1 ☐ FRESH 3 ☐ SULPHUR 4 ☐ MINERAL
20-23	1 ☐ FRESH 3 ☐ SULPHUR 4 ☐ MINERAL
25-28	1 ☐ FRESH 3 ☐ SULPHUR 4 ☐ MINERAL
30-33	1 ☐ FRESH 3 ☐ SULPHUR 4 ☐ MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET
10-11	1 ☒ STEEL		10-11
11-12	2 ☐ GALVANIZED 3 ☐ CONCRETE 4 ☐ OPEN HOLE		11-12
17-18	1 ☐ STEEL 2 ☐ GALVANIZED 3 ☐ CONCRETE 4 ☐ OPEN HOLE		17-18
24-25	1 ☐ STEEL 2 ☐ GALVANIZED 3 ☐ CONCRETE 4 ☐ OPEN HOLE		24-25

SCREEN

SIZE(S) OF OPENING (SLOT NO.)	DIAMETER INCHES	LENGTH FEET

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET	MATERIAL AND TYPE	CEMENT GROUT LEAD PACKER, ETC.
10-13		
18-21		
26-29		

71 PUMPING TEST

PUMPING TEST METHOD	PUMPING RATE	DURATION OF PUMPING
1 ☒ PUMP 2 ☐ BAILER	0020 GPM	02 HOURS 00 MINS
STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING
007	030	15 MINUTES 030 30 MINUTES 030 45 MINUTES 030 60 MINUTES 030
IF FLOWING, GIVE RATE	PUMP INTAKE SET AT	WATER AT END OF TEST
		1 ☒ CLEAR 2 ☐ CLOUDY
RECOMMENDED PUMP TYPE	RECOMMENDED PUMP SETTING	RECOMMENDED PUMPING RATE
☐ SHALLOW ☒ DEEP	040	0010 GPM

LOCATION OF WELL

IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE. INDICATE NORTH BY ARROW.

FINAL STATUS OF WELL

1 ☒ WATER SUPPLY	5 ☐ ABANDONED, INSUFFICIENT SUPPLY
2 ☐ OBSERVATION WELL	6 ☐ ABANDONED, POOR QUALITY
3 ☐ TEST HOLE	7 ☐ UNFINISHED
4 ☐ RECHARGE WELL	

WATER USE

1 ☒ DOMESTIC	5 ☐ COMMERCIAL
2 ☐ STOCK	6 ☐ MUNICIPAL
3 ☐ IRRIGATION	7 ☐ PUBLIC SUPPLY
4 ☐ INDUSTRIAL	8 ☐ COOLING OR AIR CONDITIONING
9 ☐ OTHER	9 ☐ NOT USED

METHOD OF DRILLING

1 ☐ CABLE TOOL	6 ☐ BORING
2 ☐ ROTARY (CONVENTIONAL)	7 ☐ DIAMOND
3 ☐ ROTARY (REVERSE)	8 ☐ JETTING
4 ☐ ROTARY (AIR)	9 ☐ DRIVING
5 ☒ AIR PERCUSSION	

CONTRACTOR

NAME OF WELL CONTRACTOR MARLE LEAF DRILLING CO.	LICENCE NUMBER 1365
ADDRESS 877 RIDLEY BLVD.	
NAME OF DRILLER OR BORER Simon Skuse	LICENCE NUMBER
SIGNATURE OF CONTRACTOR Robert Bissan	SUBMISSION DATE 27 10 77

OFFICE USE ONLY

DATA SOURCE	CONTRACTOR	DATE RECEIVED
1	1365	181177
DATE OF INSPECTION 12/25/73	INSPECTOR DN	
REMARKS		

Ministry of the
Environment

The Ontario Water Resources Act

31F8E

WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

1516579

MUNICIP

15005

CON.

CƠN

02

COUNTY OR DISTRICT <i>Carleton</i>		TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE <i>Huntley</i>		CON., BLOCK, TRACT, SURVEY, ETC. <i>Can 2</i>		LOT <i>2011</i>	
OWNER (SURNAME FIRST) <i>Anglican Church</i>		DATE COMPLETED <i>27 06 78</i>		DAY		MO. YR.	
U. ZONE <i>18</i>		NORTHING <i>5018300</i>		RC <i>5</i>		ELEVATION <i>038.5</i>	
U. ZONE <i>18</i>		NORTHING <i>5018300</i>		RC <i>5</i>		BASIN CODE <i>26</i>	

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

[illegible]

31	001021411	004221711	0064215						
32									
1 2	10 14 15	21	32	43					

41 WATER RECORD	
WATER FOUND AT - FEET	KIND OF WATER
10-13	1 ☒ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
15-18	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
20-23	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
25-28	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
30-33	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL

CASING & OPEN HOLE RECORD		DEPTH - FEET	
INSIDE DIAM INCHES	MATERIAL	WALL THICKNESS INCHES	FROM TO
10-11	☒ STEEL ☐ GALVANIZED ☐ CONCRETE ☐ OPEN HOLE	12	13-16
17-18	☐ STEEL ☐ GALVANIZED ☐ CONCRETE ☐ OPEN HOLE	19	20-23
24-25	☐ STEEL ☐ GALVANIZED ☐ CONCRETE ☐ OPEN HOLE	26	27-30

SCREEN	54		65		75		80		
	SIZE(S) OF OPENING (SLOT NO.)		31-33		DIAMETER		34-38		
							LENGTH		
							39-40		
				INCHES				FEET	
MATERIAL AND TYPE				DEPTH TO TOP OF SCREEN				41-44	
								80	
								FEET	

61 PLUGGING & SEALING RECORD			
DEPTH SET AT - FEET		MATERIAL AND TYPE (CEMENT GROUT, LEAD PACKER, ETC.)	
FROM	TO		
10-13	14-17		
18-21	22-25		
26-29	30-33	80	

PUMPING TEST METHOD	1 ☒ PUMP		2 ☐ BAILER		10	PUMPING RATE	11-14	DURATION OF PUMPING					
	0006		01		15-16		00		17-18				
	GPM		HOURS		MINS								
	STATIC LEVEL		WATER LEVEL END OF PUMPING		25		WATER LEVELS DURING		1 ☒ PUMPING				
	2 ☐ RECOVERY												
PUMPING TEST	19-21		22-24		15 MINUTES		30 MINUTES		45 MINUTES		60 MINUTES		
	020		050		050		050		050		050		
	FEET		FEET		FEET		FEET		FEET		FEET		
	IF FLOWING, GIVE RATE		38-41		PUMP INTAKE SET AT		WATER AT END OF TEST		42				
	GPM		FEET		FEET		1 ☐ CLEAR		2 ☒ CLOUDY				
RECOMMENDED PUMP TYPE				RECOMMENDED PUMP SETTING				RECOMMENDED PUMPING RATE				46-49	
☐ SHALLOW				☒ DEEP				050				0005	
GPM				FEET				FEET				GPM	
50-53													

LOCATION OF WELL

IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE. INDICATE NORTH BY ARROW.

HWY # 17

↑
N.

150'

250'

OK Rd. J.

mi. GLE
Side Rd. (in E. 1/2)

DRILLERS REMARKS:

FINAL STATUS OF WELL	54 1 ☒ WATER SUPPLY 2 ☐ OBSERVATION WELL 3 ☐ TEST HOLE 4 ☐ RECHARGE WELL	5 ☐ ABANDONED, INSUFFICIENT SUPPLY 6 ☐ ABANDONED, POOR QUALITY 7 ☐ UNFINISHED
WATER USE	55-56 1 ☐ DOMESTIC 2 ☐ STOCK 3 ☐ IRRIGATION 4 ☐ INDUSTRIAL ☐ OTHER	5 ☐ COMMERCIAL 6 ☐ MUNICIPAL 7 ☐ PUBLIC SUPPLY 8 ☐ COOLING OR AIR CONDITIONING 9 ☐ NOT USED
METHOD OF DRILLING	57 1 ☐ CABLE TOOL 2 ☐ ROTARY (CONVENTIONAL) 3 ☐ ROTARY (REVERSE) 4 ☐ ROTARY (AIR) 5 ☒ AIR PERCUSSION	6 ☐ BORING 7 ☐ DIAMOND 8 ☐ JETTING 9 ☐ DRIVING

CONTRACTOR	NAME OF WELL CONTRACTOR <i>Henry Mains Well Drilling</i>		LICENCE NUMBER <i>3644</i>
	ADDRESS <i>Box 32 Richmond Ont</i>		
	NAME OF DRILLER OR BORER <i>Henry Mains</i>		LICENCE NUMBER
	SIGNATURE OF CONTRACTOR <i>Henry Mains</i>		SUBMISSION DATE DAY _____ MO. _____ YR. _____

OFFICE USE ONLY	DATA SOURCE	58	CONTRACTOR	59-62	DATE RECEIVED	63-68	80
	1		3644		27, 08 78		
	DATE OF INSPECTION		INSPECTOR				
	17/05/79		LS		KCM		
	REMARKS:						
	C.B.S.33						



Ministry
of the
Environment
Ontario

The Ontario Water Resources Act

WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

11

1517377

MUNICIPALITY
15.005

CON. CQN

02

COUNTY OR DISTRICT Carleton Place	TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE West Carleton (Hanley)	CON. BLOCK, TRACT, SURVEY, ETC. Con 2.	DATE COMPLETED DAY 30 MO 10 YR 80
18.199		0280	26

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
grey	clay	stones		0	12
grey	shaly limestone			12	84

001720512	008421582
-----------	-----------

41	WATER RECORD
WATER FOUND AT - FEET	KIND OF WATER
0080	1 ☒ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL

51	CASING & OPEN HOLE RECORD		
INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET
06.1	STEEL	1.88	0 020

61	PLUGGING & SEALING RECORD	
DEPTH SET AT - FEET	MATERIAL AND TYPE	CEMENT GROUT LEAD PACKER, ETC.
10-13	14-17	

71	PUMPING TEST METHOD	10	PUMPING RATE	11-12	DURATION OF PUMPING
1 ☒ PUMP 2 ☐ BAILER	0004		01	15-16	00
STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING	1 ☒ PUMPING 2 ☐ RECOVERY		
025	080	15 MINUTES 080 30 MINUTES 080 45 MINUTES 080 60 MINUTES 080			

FINAL STATUS OF WELL	1 ☒ WATER SUPPLY 2 ☐ OBSERVATION WELL 3 ☐ TEST HOLE 4 ☐ RECHARGE WELL	5 ☐ ABANDONED INSUFFICIENT SUPPLY 6 ☐ ABANDONED POOR QUALITY 7 ☐ UNFINISHED
WATER USE	1 ☒ DOMESTIC 2 ☐ STOCK 3 ☐ IRRIGATION 4 ☐ INDUSTRIAL	5 ☐ COMMERCIAL 6 ☐ MUNICIPAL 7 ☐ PUBLIC SUPPLY 8 ☐ COOLING OR AIR CONDITIONING 9 ☐ NOT USED
METHOD OF DRILLING	1 ☐ CABLE TOOL 2 ☐ ROTARY (CONVENTIONAL) 3 ☐ ROTARY (REVERSE) 4 ☐ ROTARY (AIR) 5 ☒ AIR PERCUSSION	6 ☐ BORING 7 ☐ DIAMOND 8 ☐ JETTING 9 ☐ DRIVING

LOCATION OF WELL
IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE. INDICATE NORTH BY ARROW.
DRILLER'S REMARKS

CONTRACTOR	NAME OF WELL CONTRACTOR Herry Mains Well Drilling	LICENCE NUMBER 3644
	ADDRESS Box 326, Richmond Ont.	
	NAME OF DRILLER OR BORER Herry Mains	LICENCE NUMBER
	SIGNATURE OF CONTRACTOR	SUBMISSION DATE DAY 11 MO 11 YR 80

OFFICE USE ONLY	DATA SOURCE 1	CONTRACTOR 3644	DATE RECEIVED 011280
	DATE OF INSPECTION	INSPECTOR km	
	REMARKS		

Ministry
of the
Environment

The Ontario Water Resources Act

WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

11

1517526

MUNICIP.
15005

CON.
CON

02

COUNTY OR DISTRICT Carleton		TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE Huntley		CON. BLOCK, TRACT, SURVEY, ETC 3		LOT 11	
OWNER (SURNAME FIRST) Pri-Tec Ltd.		ADDRESS R. R. # 5, Box 933, Ottawa, Ontario		DATE COMPLETED 22 MO 10 YR 80			

21

U
M

ZONE
78

EASTING
421599

NORTHING
5018299

ELEVATION
0365

BASIN CODE
26

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

[illegible]

31

00046281201	00136051361	015021589
-------------	-------------	-----------

32

WATER RECORD

WATER FOUND AT - FEET		KIND OF WATER	
00-48	10-13	1 ☐ FRESH 2 ☐ SALTY	3 ☐ SULPHUR 4 ☐ MINERAL
01-45	15-18	1 ☐ FRESH 2 ☐ SALTY	3 ☐ SULPHUR 4 ☐ MINERAL
	20-23	1 ☐ FRESH 2 ☐ SALTY	3 ☐ SULPHUR 4 ☐ MINERAL
	25-28	1 ☐ FRESH 2 ☐ SALTY	3 ☐ SULPHUR 4 ☐ MINERAL
	30-33	1 ☐ FRESH 2 ☐ SALTY	3 ☐ SULPHUR 4 ☐ MINERAL

CASING & OPEN HOLE RECORD

INSIDE DIAM INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
6.1 ¹⁰⁻¹¹ 06	☒ STEEL ☐ GALVANIZED ☐ CONCRETE ☐ OPEN HOLE	12	.188	0 0021 ¹³⁻¹⁶
5.7 ¹⁷⁻¹⁸ 06	☐ STEEL ☐ GALVANIZED ☐ CONCRETE ☒ OPEN HOLE	19		21 135 150 ²⁰⁻²¹ 0150
24-25	☐ STEEL ☐ GALVANIZED ☐ CONCRETE ☐ OPEN HOLE	26		27-30

SCREEN	SIZES OF OPENING (SLOT NO.)		DIAMETER		LENGTH	
	31-33		34-38		39-40	
			INCHES		FEET	
	MATERIAL AND TYPE		DEPTH TO TOP OF SCREEN		41-44 10	
					FEET	

PLUGGING & SEALING RECORD

DEPTH SET AT - FEET		MATERIAL AND TYPE CEMENT GROUT LEAD PACKER, ETC.)
FROM	TO	
10-13	14-17	
18-21	22-25	
26-29	30-33	80

71 PUMPING TEST

PUMPING TEST	PUMPING TEST METHOD		11: PUMPING RATE		11-14 DURATION OF PUMPING		
	1 ☒ PUMP 2 ☐ BAILER		00 10		GPM 01 15-16 HOURS 00 17-18 MINS		
	STATIC LEVEL		25 WATER LEVELS DURING		1 ☒ PUMPING 2 ☐ RECOVERY		
	19-21	22-24	15 MINUTES	30 MINUTES	45 MINUTES	60 MINUTES	
	020	040	26-28 040	29-31 040	32-34 040	35-37 040	
	FEET		FEET		FEET		
	IF FLOWING, GIVE RATE		38-41 PUMP INTAKE SET AT		42 WATER AT END OF TEST		
GPM		40		1 ☒ CLEAR 2 ☐ CLOUDY			
RECOMMENDED PUMP TYPE		RECOMMENDED PUMP SETTING		43-45 RECOMMENDED PUMPING RATE		46-49	
☐ SHALLOW ☒ DEEP		060		FEET 0005		GPM	
50-53							

**FINAL
STATUS
OF WELL**

1 ☒ WATER SUPPLY 5 ☐ ABANDONED, INSUFFICIENT SUPPLY
2 ☐ OBSERVATION WELL 6 ☐ ABANDONED, POOR QUALITY
3 ☐ TEST HOLE 7 ☐ UNFINISHED
4 ☐ RECHARGE WELL

WATER USE


1 ☐ DOMESTIC
2 ☒ STOCK
3 ☐ IRRIGATION
4 ☐ INDUSTRIAL
5 ☐ COMMERCIAL
6 ☐ MUNICIPAL
7 ☐ PUBLIC SUPPLY
8 ☐ COOLING OR AIR CONDITIONING
9 ☐ OTHER
10 ☐ NOT USED

METHOD OF DRILLING

1 ☐ CABLE TOOL	6 ☐ BORING
2 ☐ ROTARY (CONVENTIONAL)	7 ☐ DIAMOND
3 ☐ ROTARY (REVERSE)	8 ☐ JETTING
4 ☐ ROTARY (AIR)	9 ☐ DRIVING
5 ☒ AIR PERCUSSION	

LOCATION OF WELL

IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE INDICATE NORTH BY ARROW



DRILLERS REMARKS

CONTRACTOR	NAME OF WELL CONTRACTOR		LICENCE NUMBER
	Capital Water Supply Ltd.		1558
	ADDRESS		
	Box 490, Stittsville, Ontario.		
	NAME OF DRILLER OR BORER		LICENCE NUMBER
	S. Miller		
	SIGNATURE OF CONTRACTOR	SUBMISSION DATE	
	<i>S. Miller</i>	DAY 25 MO 10 YR 8	

OFFICE USE ONLY	DATA SOURCE	58 1	CONTRACTOR 1558	59-62	DATE RECEIVED 20 03 81	68 68	69 69
	DATE OF INSPECTION		INSPECTOR				
REMARKS:							

MINISTRY OF THE ENVIRONMENT COPY

FORM NO. 0506-4-77 FORM 7



The Ontario Water Resources Act

31651

1517781

MUNICIP.
15005

CON
CON

02

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

11

COUNTY OR DISTRICT		TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE		CON., BLOCK, TRACT, SURVEY, ETC.		10 14 15 22 23 24 011 25-27	
Ottawa-Carleton		West Carleton - Huntley		Conc. 2		II 011 25-27	
OWNER (SURNAME FIRST) 28-47		ADDRESS		DATE COMPLETED 48-53		DAY 30 MO. 09 YR. 81	
[REDACTED] Pritec Ltd.		Carp Rd., Carp, Ontario					

ZONE EASTING NORTHING RC ELEVATION RC BASIN CODE
 21 18 421899 5018299 4 0370 4 26

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

[illegible]

31	001562813	0250215	0298815			
32	10 14 15	21	13	43	61	71

WATER RECORD

WATER FOUND AT - FEET		KIND OF WATER	
10-13	1 ☒ FRESH 3 ☐ SULPHUR	14	
0030'	2 ☐ SALTY 4 ☐ MINERAL		
15-18	1 ☐ FRESH 3 ☒ SULPHUR	19	
0290'	2 ☐ SALTY 4 ☐ MINERAL		
20-23	1 ☐ FRESH 3 ☐ SULPHUR	24	
	2 ☐ SALTY 4 ☐ MINERAL		
25-28	1 ☐ FRESH 3 ☐ SULPHUR	29	
	2 ☐ SALTY 4 ☐ MINERAL		
30-33	1 ☐ FRESH 3 ☐ SULPHUR	34	
	2 ☐ SALTY 4 ☐ MINERAL		

CASING & OPEN HOLE RECORD

INSIDE DIAM INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
06 6 1/4	☒ 1 STEEL ☐ 2 GALVANIZED ☐ 3 CONCRETE ☐ 4 OPEN HOLE	188	0	0022
06 6 1/2	☐ 1 STEEL ☐ 2 GALVANIZED ☐ 3 CONCRETE ☒ 4 OPEN HOLE		22	0298
24-25	☐ 1 STEEL ☐ 2 GALVANIZED ☐ 3 CONCRETE ☐ 4 OPEN HOLE			

		65	75	80
OPENING	31-33	DIAMETER	34-38	LENGTH
				39-40

SCREEN		INCHES	FEET
	MATERIAL AND TYPE	DEPTH TO TOP OF SCREEN	41-44 80 FEET


PLUGGING & SEALING RECORD

DEPTH SET AT - FEET		MATERIAL AND TYPE (CEMENT GROUT LEAD PACKER ETC.)
FROM	TO	
10-13	14-17	
18-21	22-25	
26-29	30-33	80

71 PUMPING TEST	PUMPING TEST METHOD		10	PUMPING RATE		11-14		DURATION OF PUMPING	
	1 ☒ PUMP 2 ☐ BAILER			0005		GPM		01 15-16 00	
								HOURS MIN.	
	STATIC LEVEL	WATER LEVEL END OF PUMPING	25	WATER LEVELS DURING					
				1 ☒ PUMPING 2 ☐ RECOVERY					
19-21	22-24	15 MINUTES	26-28	30 MINUTES	29-31	45 MINUTES	32-34	60 MINUTES	35-37
020	125	125	125	125	125	125	125	125	
FEET		FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET
IF FLOWING, GIVE RATE		38-41	PUMP INTAKE SET AT			WATER AT END OF TEST			
						42			
		GPM				1 ☒ CLEAR 2 ☐ CLOUDY			
RECOMMENDED PUMP TYPE		RECOMMENDED PUMP SETTING	43-45	RECOMMENDED PUMPING RATE		46-49			
☐ SHALLOW ☒ DEEP		225	FEET		0005		GPM		
50-53		GPM / FT. SPECIFIC CAPACITY							

LOCATION OF WELL

IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE INDICATE NORTH BY ARROW



DRILLERS REMARKS

FINAL STATUS OF WELL 1	54 1 ☒ WATER SUPPLY 2 ☐ OBSERVATION WELL 3 ☐ TEST HOLE 4 ☐ RECHARGE WELL	5 ☐ ABANDONED, INSUFFICIENT SUPPLY 6 ☐ ABANDONED, POOR QUALITY 7 ☐ UNFINISHED
WATER USE 01	55-56 1 ☒ DOMESTIC 2 ☐ STOCK 3 ☐ IRRIGATION 4 ☐ INDUSTRIAL ☐ OTHER	5 ☐ COMMERCIAL 6 ☐ MUNICIPAL 7 ☐ PUBLIC SUPPLY 8 ☐ COOLING OR AIR CONDITIONING 9 ☐ NOT USED
METHOD OF DRILLING 5	57 1 ☐ CABLE TOOL 2 ☐ ROTARY (CONVENTIONAL) 3 ☐ ROTARY (REVERSE) 4 ☐ ROTARY (AIR) 5 ☒ AIR PERCUSSION	6 ☐ BORING 7 ☐ DIAMOND 8 ☐ JETTING 9 ☐ DRIVING

CONTRACTOR	NAME OF WELL CONTRACTOR		LICENCE NUMBER	
	Capital Water Supply Ltd.		1558	
	ADDRESS			
	Box 490, Stittsville, Ont. KOA 3G0			
CONTRACTOR	NAME OF DRILLER OR BORER		LICENCE NUMBER	
	S. Miller			
	SIGNATURE OF CONTRACTOR		SUBMISSION DATE	
			DAY 05 MO. 10 YR. 81	

OFFICE USE ONLY	DATA SOURCE	58	CONTRACTOR	59-62	DATE RECEIVED	63-68	69
	1		1558		03 03 82		
	DATE OF INSPECTION		INSPECTOR				
REMARKS:		6555 WI P					



Ministry
of the
Environment
Ontario

The Ontario Water Resources Act

3165d

WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK ☒ CORRECT BOX WHERE APPLICABLE

11

1519074

MUNICIPALITY 15005

CON. ESN

02

COUNTY OR DISTRICT Ottawa-Carleton	TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE West Carleton-Huntley	CON. BLOCK, TRACT SURVEY ETC Conc. 2 II	LOT 011
13090; Kanata, Ontario, K2K 1X3			DATE COMPLETED DAY 05 MO 06 YR 84
ELEVATION 182.99		RC 0365	BSIN CODE 4 26

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)					
GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
Brown	Sand		Packed	0	4
Gray	Sand	Gravel	Packed	4	8
Gray	Limestone		Soft	8	12
Gray	Limestone		Medium	12	260



31	000442879	00082281179	001221585	026021578
32				

WATER RECORD	
WATER FOUND AT - FEET	KIND OF WATER
10-13 0155'	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☒ MINERAL
15-18 0250'	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
20-23	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
25-28	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL
30-33	1 ☐ FRESH 3 ☐ SULPHUR 2 ☐ SALTY 4 ☐ MINERAL

CASING & OPEN HOLE RECORD			
DEPTH - FEET	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET
FROM TO			
10-11	1 ☒ STEEL 2 ☐ GALVANIZED 3 ☐ CONCRETE 4 ☐ OPEN HOLE	188	13-16
17-18	1 ☐ STEEL 2 ☐ GALVANIZED 3 ☐ CONCRETE 4 ☒ OPEN HOLE		20-23
24-25	1 ☐ STEEL 2 ☐ GALVANIZED 3 ☐ CONCRETE 4 ☐ OPEN HOLE		27-30

SCREEN	SIZE(S) OF OPENING (SLOT NO.)	DIAMETER	LENGTH
		INCHES	FEET
	MATERIAL AND TYPE	DEPTH TO TOP OF SCREEN	

PLUGGING & SEALING RECORD			
DEPTH SET AT - FEET	MATERIAL AND TYPE	CEMENT GROUT	LEAD PACKER, ETC.
FROM TO			
10-13			
18-21			
26-29			

PUMPING TEST METHOD	PUMPING RATE	DURATION OF PUMPING
1 ☐ PUMP 2 ☒ BAILER	0015 GPM	01 HOURS 00 MINS
STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING
19-21	22-24	15 MINUTES 26-28 30 MINUTES 29-31 45 MINUTES 32-34 60 MINUTES 35-37
020 FEET	060 FEET	060 FEET 060 FEET 060 FEET 060 FEET
IF FLOWING, GIVE RATE	PUMP INTAKE SET AT	WATER AT END OF TEST
	GPM	FEET
RECOMMENDED PUMP TYPE	RECOMMENDED PUMP SETTING	RECOMMENDED PUMPING RATE
☐ SHALLOW ☒ DEEP	080 FEET	0005 GPM

FINAL STATUS OF WELL	1 ☒ WATER SUPPLY 2 ☐ OBSERVATION WELL 3 ☐ TEST HOLE 4 ☐ RECHARGE WELL	5 ☐ ABANDONED, INSUFFICIENT SUPPLY 6 ☐ ABANDONED, POOR QUALITY 7 ☐ UNFINISHED
WATER USE	1 ☐ DOMESTIC 2 ☒ STOCK 3 ☐ IRRIGATION 4 ☐ INDUSTRIAL 5 ☐ OTHER	5 ☐ COMMERCIAL 6 ☐ MUNICIPAL 7 ☐ PUBLIC SUPPLY 8 ☐ COOLING OR AIR CONDITIONING 9 ☐ NOT USED
METHOD OF DRILLING	1 ☐ CABLE TOOL 2 ☒ ROTARY (CONVENTIONAL) 3 ☐ ROTARY (REVERSE) 4 ☐ ROTARY (AIR) 5 ☒ AIR PERCUSSION	6 ☐ BORING 7 ☐ DIAMOND 8 ☐ JETTING 9 ☐ DRIVING

LOCATION OF WELL	
IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE. INDICATE NORTH BY ARROW.	
DRILLERS REMARKS	

NAME OF WELL CONTRACTOR	LICENCE NUMBER
Capital Water Supply Ltd.	1558
ADDRESS	
Box 400; Stittsville, Ontario, K0A 3G0	
NAME OF DRILLER OR BORER	LICENCE NUMBER
W. Kavanagh / J. Moore	
SIGNATURE OF CONTRACTOR	SUBMISSION DATE
	DAY 06 MO 06 YR 84

DATA SOURCE	CONTRACTOR	DATE OF INSPECTION	INSPECTOR
1	1558	07 08 84	
REMARKS			

Well Owner's Information

First Name Camcor Industries	Last Name	E-mail Address	☐ Well Constructed by Well Owner
Mailing Address (Street Number/Name, RR) 2171 McGee Side Road		Municipality Carleton Place	Province Ont
Postal Code K0A 1L0		Telephone No. (inc. area code)	

Part A Construction and/or Major Alteration of a Well

Address of Well Location (Street Number/Name, RR) # 2171 McGee Side Road		Township Huntley	Lot 11	Concession 2
County/District/Municipality Ottawa-Carleton		City/Town/Village Carleton Place	Province Ontario	Postal Code
UTM Coordinates NAD 83 184219215018437	Zone 18Q	Easting 5018437	Northings 5018437	GPS Unit Make Magellan
Model 200		Mode of Operation: ☐ Undifferentiated ☒ Averaged		
☐ Differentiated, specify				

Overburden and Bedrock Materials (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (Metres) From	Depth (Metres) To
	Sand Gravel			0	4.27
	Gray Limestone			4.27	152.3
* Plan RPSR 12610 *					

Annular Space/Abandonment Sealing Record

Depth Set at (Metres) From	Depth Set at (Metres) To	Type of Sealant Used (Material and Type)	Volume Placed (Cubic Metres)
6.10	0	Neat Cement Slurry	2724


Method of Construction		Water Use	
☐ Cable Tool	☐ Diamond	☐ Public	☒ Commercial
☐ Rotary (Conventional)	☐ Jetting	☐ Domestic	☐ Municipal
☐ Rotary (Reverse)	☐ Driving	☐ Livestock	☐ Test Hole
☐ Rotary (Air)	☐ Digging	☐ Irrigation	☐ Cooling & Air Conditioning
☒ Air percussion	☐ Boring	☐ Industrial	
☐ Other, specify		☐ Other, specify	

Status of Well	
☒ Water Supply	☐ Dewatering Well
☐ Replacement Well	☐ Abandoned, Insufficient Supply
☐ Test Hole	☐ Abandoned, Poor Water Quality
☐ Recharge Well	☐ Abandoned, other, specify
☐ Observation and/or Monitoring Hole	☐ Alteration (Construction)
☐ Other, specify	

Location of Well

Please provide a map below showing:

- all property boundaries, and measurements sufficient to locate the well in relation to fixed points,
- an arrow indicating the North direction
- detailed drawings can be provided as attachments no larger than legal size (8.5" by 14")
- digital pictures of inside of well can also be provided



Date Well Completed (yyyy/mm/dd) 2007-08-31	Was the well owner's information package delivered? ☒ Yes ☐ No	Date the Well Record and Package Delivered to Well Owner (yyyy/mm/dd) 2007-08-31
---	---	--

Well Contractor and Well Technician Information

Business Name of Well Contractor AIR ROCK DRILLING CO LTD		Well Contractor's Licence No. 10119
Business Address (Street No./Name, number, RR) RR #1		Municipality RICHMOND
Province ONT	Postal Code K0A 2R0	Business E-mail Address
Bus. Telephone No. (inc. area code) 613 838 2170		Name of Well Technician (Last Name, First Name) Desautels Ken
Well Technician's Licence No. TA	Signature of Technician <i>[Signature]</i>	Date Submitted (yyyy/mm/dd) 2007-10-10

Results of Well Yield Testing

Check box if after test of well yield, water was:		Draw Down		Recovery	
		Time (Min)	Water Level (Metres)	Time (Min)	Water Level (Metres)
☐ Clear and sand free	☒ Cannot develop to sand-free state	Static Level	5.75	Static Level	34.90
If pumping discontinued, give reason:		1	7.08	1	32.36
Pumping test method Sub Pump		2	8.20	2	31.30
Pump intake set at (Metres) 91.44		3	9.30	3	30.22
Pumping rate (Litres/min) 26.5		4	10.30	4	29.18
Duration of pumping 1 hrs + 0 min		5	11.20	5	28.20
Final water level end of pumping (Metres) 34.90		10	15.26	10	23.70
Recommended pump type ☐ Shallow ☒ Deep		15	18.60	15	20.
Recommended pump depth 91.44 Metres		20	21.40	20	16.60
Recommended pump rate (Litres/min) 26.5		25	23.37	25	13.90
If flowing give rate (Litres/min)		30	26.	30	11.58
		40	29.66	40	9.90
		50	32.60	50	7.80
		60	34.90	60	6.30

Water Details

Water found at Depth 105.63 Metres	Kind of Water ☐ Gas ☐ Fresh ☐ Salty ☐ Sulphur ☐ Minerals
Water found at Depth 117.82 Metres	Kind of Water ☐ Gas ☐ Fresh ☐ Salty ☐ Sulphur ☐ Minerals
Water found at Depth Metres	Kind of Water ☐ Gas ☐ Fresh ☐ Salty ☐ Sulphur ☐ Minerals

Casing Used	Screen Used	Casing and Well Details
☐ Galvanized	☒ Galvanized	Diameter of the Hole (Centimetres) 14.28
☒ Steel	☐ Steel	Depth of the Hole (Metres) 152.37
☐ Fibreglass	☐ Fibreglass	Wall Thickness (Metres) 1.48 cm
☐ Plastic	☐ Plastic	Inside Diameter of the Casing (Metres) 1.588
☐ Concrete	☐ Concrete	Depth of the Casing (Metres) 6.11
No Casing and Screen Used		
☒ Open Hole		
Disinfected? ☒ Yes ☐ No		

Ministry Use Only

Audit No. z 60149	Well Contractor No.
Date Received (yyyy/mm/dd) OCT 15 2007	Date of Inspection (yyyy/mm/dd)
Remarks	

Measurements recorded in: ☐ Metric ☐ Imperial

Regulation 903 Ontario Water Resources Act

Page 1 of 1

Well Owner's Information

First Name	Last Name / Organization	E-mail Address			☐ Well Constructed by Well Owner
	Loe-Issa Const. Inc	giles@lorissa.ca			
Mailing Address (Street Number/Name)	Municipality	Province	Postal Code	Telephone No. (inc. area code)	
3140 Carys Rd.	West Carleton	Ont	K9A1N0	613 899 3784	

Well Location

Address of Well Location (Street Number/Name) 139 John Cavanaugh			Township West Carleton		Lot 11	Concession Concession 2	
County/District/Municipality Ottawa Carleton			City/Town/Village Camp		Province Ontario		Postal Code K0A1L0
UTM Coordinates NAD 83		Zone Easting 18H21743501		Northing 8692		Municipal Plan and Sublot Number	
						Other	

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

[illegible]

Annular Space

Depth Set at (m/ft)		Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
From	To		
0	20	cinco ground	4 Bags

Method of Construction

Well Use	
☐ Cable Tool	☐ Diamond
☐ Rotary (Conventional)	☐ Jetting
☐ Rotary (Reverse)	☐ Driving
☐ Boring	☐ Digging
☐ Air percussion	
☐ Other, specify _____	
☐ Public	☐ Commercial
☐ Domestic	☐ Municipal
☐ Livestock	☐ Test Hole
☐ Irrigation	☐ Cooling & Air Conditioning
☐ Industrial	
☐ Other, specify _____	☐ Not used
	☐ Dewatering
	☐ Monitoring

Construction Record - Casing

Construction Record - Casing					Status of Well
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		☒ Water Supply ☐ Replacement Well ☐ Test Hole ☐ Recharge Well ☐ Dewatering Well ☐ Observation and/or Monitoring Hole ☐ Alteration (Construction) ☐ Abandoned
			From	To	
6.4	Steel	188	0	22	

Status of Well

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)	
			From	To
6.4	Steel	188	0	22
Construction Record - Screen				
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To

☐ Water Supply
☐ Replacement Well
☐ Test Hole
☐ Recharge Well
☐ Dewatering Well
☐ Observation and/or Monitoring Hole
☐ Alteration (Construction)
☐ Abandoned, Insufficient Supply
☐ Abandoned, Poor Water Quality
☐ Abandoned, other, specify _____
☐ Other, specify _____

Construction Record - Screen

Outside Diameter <i>(cm/in)</i>	Material <i>(Plastic, Galvanized, Steel)</i>	Slot No.	Depth <i>(m/f)</i>	
			From	To

☐ Abandoned, Poor Water Quality
☐ Abandoned, other, specify _____
☐ Other, specify _____

Water Details

Water found at Depth		Kind of Water:		Hole Diameter		
(m/ft)	☐ Gas	☐ Fresh	☒ Untested	Depth (m/ft)	Diameter (cm/in)	
		☐ Other, specify		From	To	
30	☐ Gas	☐ Other, specify	☒ Untested	0	75	End
35	☐ Gas	☐ Other, specify	☒ Untested			
	☐ Gas	☐ Other, specify	☐ Untested			
	☐ Gas	☐ Other, specify	☐ Untested			

Hole Diameter

Water found at Depth 30 (m/ft) ☐ Gas ☐ Other, specify	Kind of Water: ☐ Fresh ☒ Untested	Depth (m/ft) From	To	Diameter (cm/in)
Water found at Depth 35 (m/ft) ☐ Gas ☐ Other, specify	Kind of Water: ☐ Fresh ☒ Untested	0	75	6 in
Water found at Depth (m/ft) ☐ Gas ☐ Other, specify	Kind of Water: ☐ Fresh ☐ Untested			

Well Contractor and Well Technician Information

Business Name of Well Contractor Anne Cayer LTD		Well Contractor's Licence No. 115117	
Business Address (Street Number/Name) 9 RT 700 Ste Casselman		Municipality Natick	
Province MA	Postal Code K0M1M0	Business E-mail Address	
Telephone No. (inc. area code) 137649232	Name of Well Technician (Last Name, First Name) Regan Cayer		
Technician's Licence No. 7117	Signature of Technician and/or Contractor Regan Cayer	Date Submitted 2015.06.06	

Results of Well Yield Testing

Results of Well Field Testing	
After test of well yield, water was:	Draw Down Recovery
☒ Clear and sand free ☐ Other, <i>specify</i>	Time (min) Water Level (m/ft) Time (min) Water Level (m/ft)
If pumping discontinued, give reason:	Static Level 9.02 11.28
Pump intake set at (m/ft)	1 9.98 1 10.31
Pumping rate (l/min / GPM)	2 10.27 2 10.09
Duration of pumping	3 10.45 3 9.90
hrs + min	4 10.55 4 9.81
Final water level end of pumping (m/ft)	5 10.61 5 9.68
If flowing give rate (l/min / GPM)	10 10.78 10 9.47
Recommended pump depth (m/ft)	15 10.85 15 9.32
Recommended pump rate (l/min / GPM)	20 10.92 20 9.12
Well production (l/min / GPM)	25 11.03 25 9.10
Disinfected?	30 11.10 30 8.97
☒ Yes ☐ No	40 11.18 40 8.95
	50 11.24 50 8.99
	60 11.28 60 8.89

Map of Well Location

Please provide a map below following instructions on the back.

Hand-drawn map of a property. The map is a rectangle with a diagonal line from the top-left corner to the bottom-right corner. The top-left corner is labeled "N" and "N". The top-right corner is labeled "Lot line". The bottom-left corner is labeled "Lot line". The bottom-right corner is labeled "John Carvahaugh". Inside the rectangle, there is a point labeled "37 feet" and "90 feet" with arrows pointing to it. Below this point is a label "WELL" with an arrow pointing to it.

Well owner's information package delivered ☐ Yes ☐ No	Date Package Delivered 20160620	Ministry Use Only
	Date Work Completed 20160620	Audit No. Z232615 JUL 19 2016 Received

Client: Paterson Group
154 Colonnade Rd. South
Nepean, ON
K2E 7T7
Attention: Mr. Erik Ardley
PO#: 31705
Invoice to: Paterson Group

Report Number: 1948880
Date Submitted: 2021-03-05
Date Reported: 2021-03-11
Project: PH4146
COC #: 870803

Page 1 of 7

Dear Erik Ardley:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:


Addrine
Thomas
2021.03.11
15:49:43 -05'00'

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Paterson Group
154 Colonnade Rd. South
Nepean, ON
K2E 7T7
Attention: Mr. Erik Ardley
PO#: 31705
Invoice to: Paterson Group

Report Number: 1948880
Date Submitted: 2021-03-05
Date Reported: 2021-03-11
Project: PH4146
COC #: 870803

					1544901 GW	1544902 GW
					2021-03-04 GW1	2021-03-04 GW2
Group	Analyte	MRL	Units	Guideline		
Anions	Cl	1	mg/L	AO 250	120	119
	F	0.10	mg/L	MAC 1.5	0.15	0.14
	N-NO2	0.10	mg/L	MAC 1.0	<0.10	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10	<0.10
	SO4	1	mg/L	AO 500	83	79
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	346	344
	Colour	2	TCU		<2	<2
	Conductivity	5	uS/cm		1100	1100
	DOC	0.5	mg/L	AO 5	1.5	1.5
	pH	1.00		6.5-8.5	7.98	8.02
	S2-	0.01	mg/L	AO 0.05		0.03
		0.1	mg/L	AO 0.05	<0.1*	
	TDS	10	mg/L	AO 500	640*	640*
	Turbidity	0.1	NTU	AO 5.0	>100	2.0
Hardness	Hardness as CaCO3	1	mg/L	OG 100	382*	391*
Indices/Calc	Ion Balance	0.01			1.02	1.04
Metals	Ca	1	mg/L		115	117
	Fe	0.03	mg/L	AO 0.3	3.69*	0.09
	K	1	mg/L		5	4
	Mg	1	mg/L		23	24
	Mn	0.01	mg/L	AO 0.05	0.06*	<0.01
	Na	2	mg/L	AO 200	105	103
Nutrients	N-NH3	0.010	mg/L		0.023	0.021
	Total Kjeldahl Nitrogen	0.100	mg/L		0.197	0.104
Subcontract-Inorg	Phenols	0.001	mg/L		<0.001	<0.001

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Paterson Group
154 Colonnade Rd. South
Nepean, ON
K2E 7T7
Attention: Mr. Erik Ardley
PO#: 31705
Invoice to: Paterson Group

Report Number: 1948880
Date Submitted: 2021-03-05
Date Reported: 2021-03-11
Project: PH4146
COC #: 870803

					Lab I.D. Sample Matrix Sample Type Sampling Date Sample I.D.	1544901 GW 2021-03-04 GW1	1544902 GW 2021-03-04 GW2
Group	Analyte	MRL	Units	Guideline			
Subcontract-Inorg	Tannin & Lignin	0.1	mg/L			<0.1	<0.1

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Paterson Group
154 Colonnade Rd. South
Nepean, ON
K2E 7T7
Attention: Mr. Erik Ardley
PO#: 31705
Invoice to: Paterson Group

Report Number: 1948880
Date Submitted: 2021-03-05
Date Reported: 2021-03-11
Project: PH4146
COC #: 870803

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 396958 Analysis/Extraction Date 2021-03-05 Analyst AET Method C SM2130B			
Turbidity	<0.1 NTU	100	70-130
Run No 396999 Analysis/Extraction Date 2021-03-09 Analyst SKH Method C SM2540			
TDS	<10 mg/L	99	90-110
Run No 397023 Analysis/Extraction Date 2021-03-08 Analyst R R Method SM 4110			
N-NO2	<0.10 mg/L	113	90-110
N-NO3	<0.10 mg/L	104	90-110
SO4	<1 mg/L	100	90-110
Run No 397049 Analysis/Extraction Date 2021-03-08 Analyst AET Method SM2320,2510,4500H/F			
Alkalinity (CaCO3)	<5 mg/L	106	90-110
Conductivity	<5 uS/cm	100	90-110
F	<0.10 mg/L	102	90-110
pH		100	90-110
Run No 397050 Analysis/Extraction Date 2021-03-09 Analyst AET Method EPA 351.2			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Paterson Group
154 Colonnade Rd. South
Nepean, ON
K2E 7T7
Attention: Mr. Erik Ardley
PO#: 31705
Invoice to: Paterson Group

Report Number: 1948880
Date Submitted: 2021-03-05
Date Reported: 2021-03-11
Project: PH4146
COC #: 870803

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Total Kjeldahl Nitrogen	<0.100 mg/L	93	70-130
Run No 397051 Analysis/Extraction Date 2021-03-09 Analyst AET Method EPA 350.1			
N-NH3	<0.010 mg/L	114	80-120
Run No 397053 Analysis/Extraction Date 2021-03-09 Analyst SKH Method C SM2120C			
Colour	<2 TCU	98	90-110
Run No 397066 Analysis/Extraction Date 2021-03-09 Analyst Z S Method M SM3120B-3500C			
Calcium	<1 mg/L	105	90-110
Potassium	<1 mg/L	105	87-113
Magnesium	<1 mg/L	103	76-124
Sodium	<2 mg/L	117	82-118
Run No 397091 Analysis/Extraction Date 2021-03-09 Analyst R R Method SM 4110			
Chloride	<1 mg/L	100	90-110
Run No 397096 Analysis/Extraction Date 2021-03-10 Analyst AET Method SM 5310B			
DOC	<0.5 mg/L	97	80-120

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Paterson Group
154 Colonnade Rd. South
Nepean, ON
K2E 7T7
Attention: Mr. Erik Ardley
PO#: 31705
Invoice to: Paterson Group

Report Number: 1948880
Date Submitted: 2021-03-05
Date Reported: 2021-03-11
Project: PH4146
COC #: 870803

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 397103 Analysis/Extraction Date 2021-03-10 Analyst AET Method C SM2340B			
Hardness as CaCO ₃			
Ion Balance			
Run No 397167 Analysis/Extraction Date 2021-03-11 Analyst H D Method EPA 200.8			
Iron	<0.03 mg/L	92	80-120
Manganese	<0.01 mg/L	92	80-120
Run No 397168 Analysis/Extraction Date 2021-03-11 Analyst AET Method C SM4500-S2-D			
S2-	<0.01 mg/L	89	80-120
Run No 397177 Analysis/Extraction Date 2021-03-08 Analyst AET Method SUBCONTRACT P-INORG			
Phenols	<0.001 mg/L	88	69-132
Tannin & Lignin	<0.1 mg/L	110	

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Paterson Group
154 Colonnade Rd. South
Nepean, ON
K2E 7T7
Attention: Mr. Erik Ardley
PO#: 31705
Invoice to: Paterson Group

Report Number: 1948880
Date Submitted: 2021-03-05
Date Reported: 2021-03-11
Project: PH4146
COC #: 870803

Sample Comment Summary

Sample ID: 1544901 GW1 Significant amount of solids in preserved bottle were not included in TKN analysis. S2- MRL elevated due to matrix interference (dilution was done).

Guideline = ODWSOG*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Paterson Group
154 Colonnade Rd. South
Nepean, ON
K2E 7T7
Attention: Mr. Erik Ardley
PO#: 31705
Invoice to: Paterson Group

Report Number: 1948884
Date Submitted: 2021-03-05
Date Reported: 2021-03-06
Project: PH4146
COC #: 870803

Page 1 of 2

Dear Erik Ardley:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Dragana Dzeletovic
Dragana
Dzeletovic
2021.03.06
13:30:34 -05'00'

APPROVAL: _____
Dragana Dzeletovic-Andric, Microbiology Team Lead

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Paterson Group
154 Colonnade Rd. South
Nepean, ON
K2E 7T7
Attention: Mr. Erik Ardley
PO#: 31705
Invoice to: Paterson Group

Report Number: 1948884
Date Submitted: 2021-03-05
Date Reported: 2021-03-06
Project: PH4146
COC #: 870803

					1544909 GW 2021-03-04 GW1	1544910 GW 2021-03-04 GW2
Group	Analyte	MRL	Units	Guideline		
Microbiology	Escherichia Coli	0	ct/100mL	MAC 0	0	0
	Total Coliforms	0	ct/100mL	MAC 0	0	0

Guideline = ODWSOG


* = Guideline Exceedence


Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range





				Pumping Test Analysis Report		
				Project: Proposed Commercial Building		
				Number: PH4146		
				Client: Stoked Industries Inc.		
Location: 2167 McGee Side Rd.		Pumping Test: TW1 Pumping Test		Pumping Well: Well 1		
Test Conducted by: EA				Test Date: 19/03/2021		
Aquifer Thickness: NAN m		Discharge: variable, average rate 0.2 [l/s]				
	Analysis Name	Analysis Performed by	Method name	Well	T [m ² /d]	S
1	Theis	EA	Theis	Well 1	9.23×10^{-2}	
2	Theis Recovery	EA	Theis Recovery	Well 1	9.14×10^{-2}	
					Average	9.19×10^{-2}

TW1 inputs			
pH	8.02	A	0.18
TDS	640	B	2.42
Hardness	391	C	2.19
Alkalinity	344	D	2.54
Temp.	8.1		
		pHs =	7.172828503

Langelier Saturation Index (LSI) Calculation			(Langelier, 1936)
$\text{LSI} = \text{pH} - \text{pHs}$ $\text{pHs} = (9.3 + A + B) - (C + D)$ Where:		$A = (\text{Log}_{10} [\text{TDS}] - 1) / 10$ $B = -13.12 \times \text{Log}_{10} (\text{oC} + 273) + 34.55$ $C = \text{Log}_{10} [\text{Ca}^{2+} \text{ as CaCO}_3] - 0.4$ $D = \text{Log}_{10} [\text{alkalinity as CaCO}_3]$	
		LSI =	0.8
LSI	Effect		
0.5 to 2	Water is super saturated and tends to precipitate a scale layer of calcium carbonate (scale forming but non-corrosive)		
0 to 0.5	Water is super saturated and tends to precipitate a scale layer of calcium carbonate (slightly scale forming and corrosive).		
0	Water is saturated (in equilibrium) with calcium carbonate. A scale layer of calcium carbonate is neither precipitated nor dissolved.		
0 to -0.5	Water is under saturated and tends to dissolve solid calcium carbonate (slightly corrosivebut non-scale forming).		
-0.5 to -2	Water is under saturated and tends to dissolve solid calcium carbonate (seriously corrosive).		

DATUM Geodetic

REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE November 20, 2020

FILE NO.

PG5602

HOLE NO.

BH 1-20

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Piezometer Construction
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %				
								20	40	60	80	
GROUND SURFACE												
FILL: Brown silty sand with crushed stone	0.30	AU	1			0	117.98					
		AU	2									
		SS	2	25	48	1	116.98					
		SS	3	67	44	2	115.98					
		SS	4	79	66							
		SS	5	0	50+	3	114.98					
		SS	6	50	50+	4	113.98					
		SS	7	67	50+							
End of Borehole	4.80											
Practical refusal to augering at 4.80m depth												
(GWL @ 3.96m - Dec. 2, 2020)												
								20	40	60	80	100
								Shear Strength (kPa)				
								▲ Undisturbed △ Remoulded				

SOIL PROFILE AND TEST DATA

**Geotechnical Investigation
Prop. Commercial Building - 2167 McGee Side Road
Ottawa, Ontario**

FILE NO. PG5602

HOLE NO. **BH 2-20**

DATE November 20, 2020

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Piezometer Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %					
								20	40	60	80		
GROUND SURFACE													
FILL: Crushed stone with silty sand and gravel	0.30	AU	1			0	-117.96						
GLACIAL TILL: Compact to very dense, brown silty sand with gravel, cobbles and boulders		AU	2										
		SS	3	75	28	1	-116.96						
		SS	4	60	50+								
		SS	5	27	50+	2	-115.96						
		SS	6		50+								
End of Borehole	2.82												
Practical refusal to augering at 2.82m depth													
(Piezometer blocked and dry at 2.04m depth - Dec. 2, 2020)													

DATUM	Geodetic
-------	----------

FILE NO. PG5602

REMARKS

HOLE NO. **BH 3-20**

BORINGS BY CME-55 Low Clearance Drill

DATE November 20, 2020

[illegible]

DATUM	Geodetic
-------	----------

FILE NO. PG5602

REMARKS

HOLE NO. **BH 4-20**

BORINGS BY CME-55 Low Clearance Drill

DATE November 20, 2020

[illegible]

DATUM	Geodetic
-------	----------

FILE NO. PG5602

REMARKS

HOLE NO. **BH 5-20**

BORINGS BY CME-55 Low Clearance Drill

DATE November 20, 2020

[illegible]

DATUM	Geodetic
-------	----------

FILE NO. PG5602

REMARKS

HOLE NO. **BH 6-20**

BORINGS BY CME-55 Low Clearance Drill

DATE November 20, 2020

[illegible]

DATUM	Geodetic
-------	----------

FILE NO. PG5602

REMARKS

HOLE NO. **BH 7-20**

BORINGS BY CME-55 Low Clearance Drill

DATE November 20, 2020

[illegible]



**PATERSON
GROUP**

9 AURIGA DRIVE
OTTAWA, ON
K2E 7T9
TEL: (613) 226-7381

NO.	REVISIONS	DATE	INITIAL


CARP,
Title:


STOKED INDUSTRIES INC.
GEOTECHNICAL INVESTIGATION
PROPOSED BUILDING
2167 MCGEE SIDE ROAD
ONTARIO

TEST HOLE LOCATION PLAN

Scale: 1:400
Drawn by: YA
Checked by: ZA
Approved by: MAS

Date: 05/2023
Report No.: PG6662-1
Dwg. No.: **PG6662-1**
Revision No.:





LEGEND:

BOREHOLE LOCATION

117.96 GROUND SURFACE ELEVATION (m)

(115.14) PRACTICAL REFUSAL TO AUGERING ELEVATION (m)

BENCHMARK INFORMATION:

All ground surface elevations reference a geodetic datum (NAD83 Zone 18T)

REFERENCE:

Survey Plan provided by D.B. Gray Engineering Inc.

07/17/2023	UPDATE	1
Date	Description	Rev.

Client:

Stoked Industries Inc.

Consultant:

paterson group
consulting engineers

Project:

PROPOSED WAREHOUSE & OFFICE
2167 MCGEE SIDE ROAD
OTTAWA, ONTARIO


Drawing:

SITE PLAN

Scale:	1:500	Seal:
Date:	03/2021	
Drawn by:	JM	
Checked by:	KP	
File:	PH4146	

Drawing No.: **PH4146-2**

CLIENT:	MB Ford Construction Ltd.	DESCRIPTION:	Fine Aggregate	FILE NO:	PH4146
CONTRACT NO.:	-	SPECIFICATION:	Soil	LAB NO:	23277
PROJECT:	2167 McGee Side	INTENDED USE:	-	DATE RECEIVED:	6-Jan-21
		PIT OR QUARRY:	-	DATE TESTED:	6-Jan-21
DATE SAMPLED:	20-Nov-21	SOURCE LOCATION:	BH7 - SS2	DATE REPORTED:	8-Jan-21
SAMPLED BY:	-	SAMPLE LOCATION:	2'6 - 4'6	TESTED BY:	D.K




Silt and Clay		Sand			Gravel			Cobble			
		Fine	Medium	Coarse	Fine		Coarse				
Identification	Soil Classification					MC(%)	LL	PL	PI	Cc	Cu
										0.89	8.5
	D100	D60	D30	D10	Gravel (%)	Sand (%)		Silt (%)		Clay (%)	
	26.5	0.17	0.055	0.02	6.0	55.3		38.7			
Comments:											
REVIEWED BY:	Curtis Beadow					Joe Fosyth, P. Eng.					
											

patersongroup consulting engineers						SIEVE ANALYSIS ASTM C136	
CLIENT: MB Ford Construction Ltd.			DESCRIPTION: Fine Aggregate			FILE NO.: PH4146	
CONTRACT NO.: -			SPECIFICATION: Soil			LAB NO.: 23277	
PROJECT: 2167 McGee Side			INTENDED USE: -			DATE REC'D: 6-Jan-21	
			PIT OR QUARRY: -			DATE TESTED: 6-Jan-21	
DATE SAMPLED: 20-Nov			SOURCE LOCATION: BH7 - SS2			DATE REP'D: 8-Jan-21	
SAMPLED BY: -			SAMPLE LOCATION: 2'6 - 4'6			TESTED BY: D.K	
WEIGHT BEFORE WASH						741.8	
WEIGHT AFTER WASH						469.3	
SIEVE SIZE (mm)	WEIGHT RETAINED	PERCENT RETAINED	PERCENT PASSING	LOWER SPEC	UPPER SPEC	REMARK	
150							
106							
75							
63							
53							
37.5							
26.5	0.0	0.0	100.0				
19	26.8	3.6	96.4				
16	26.8	3.6	96.4				
13.2	26.8	3.6	96.4				
9.5	34.9	4.7	95.3				
6.7	38.3	5.2	94.8				
4.75	44.8	6.0	94.0				
2.36	58.4	7.9	92.1				
1.18	75.1	10.1	89.9				
0.6	109.7	14.8	85.2				
0.3	193.8	26.1	73.9				
0.15	321.5	43.3	56.7				
0.075	455.0	61.3	38.7				
PAN	468.5						
SIEVE CHECK FINE		0.17	0.3% max.			REFERENCE MATERIAL	
OTHER TESTS					RESULT	LAB NO.	RESULT
REVIEWED BY:	Curtis Beadow			Joe Forsyth, P. Eng.			
							


Predictive Nitrate Impact Assessment

PRE DEVELOPMENT CONDITIONS				POST DEVELOPMENT CONDITIONS			
Groundwater Flow Through		NOT USED		Groundwater Flow Through		NOT USED	
Background Nitrate Concentration (C _b) =		0	mg/L	Background Nitrate Concentration (C _b) =		0	mg/L
Hydraulic Conductivity (k) =		0	m/s	Hydraulic Conductivity (k) =		0	m/s
Horizontal Gradient (i) =		0		Horizontal Gradient (i) =		0	
Length (L) =		0	m	Length (L) =		0	m
Aquifer Thickness (t) =		0	m	Aquifer Thickness (t) =		0	m
Groundwater Flow (Q _b) =		0	m ³ /day	Groundwater Flow (Q _b) =		0	m ³ /day
Infiltration Factors				Infiltration Factors			
Topography		0		Topography		0.25	
Soil		0.00		Soil		0.30	
Cover		0.00		Cover		0.10	
Total		0		Total		0.65	
Site Characteristics				Site Characteristics			
Area of Site :	-	m ²		Area of Site :	7,621	m ²	
	0			Roof + driveway areas + gravel fill area	4,441	m ²	
	0			Length of roadways:	-	m	
	0			Width of roadways	-	m ²	
				Total area of roadways:	-		
				Impervious Area	4,441	m ²	
				Percent Impervious Area =	58.27	%	
Infiltration Area =	-	m ²		Infiltration Area =	3,180	m ²	
Septic Effluent				Septic Effluent			
Concentration of Effluent (Cs) =		0	mg/L	Concentration of Effluent (Cs) =		4	mg/L
Daily Sewage Flow (Qs)=		0	m ³	Daily Sewage Flow (Qs)=		4.327	m ³
				See Note 1 below.			
Infiltration Calculation				Infiltration Calculation			
Nitrate concentration in precipitation (C _i) =		0	mg/L	Nitrate concentration in precipitation (C _i) =		0	mg/L
Surplus Water (Environment Canada)			mm/yr	Surplus Water (Environment Canada)		402	mm/yr
Factored Water Surplus =		0	mm/yr	Factored Water Surplus =		261	mm/yr
Total volume of Infiltration	-	m ³ /yr		Infiltration % due to stormwater management measures		0%	
				Infiltration rate from stormwater management measures =		0	mm/yr
Infiltration flow entering the system (Q _i) =		0	m ³ /day	Infiltration Flow Entering the System (Q _i) =		2	m ³ /day
Mass Balance Model (MOEE, 1995)				Mass Balance Model (MOEE, 1995)			
C _T = (Q _b C _b +Q _e C _e +Q _i C _i)/(Q _b +Q _e +Q _i) = Cumulative Nitrate Concentration				C _T = (Q _b C _b +Q _e C _e +Q _i C _i)/(Q _b +Q _e +Q _i) = Cumulative Nitrate Concentration			
Q _b = flow entering the system across the upgradient area		0	m ³ /day	Q _b = flow entering the system across the upgradient area		0	m ³ /day
C _b = background nitrate concentration		0	mg/L	C _b = background nitrate concentration		0	mg/L
Q _e = flow entering the system from the septic drainfield		0	m ³ /day	Q _e = flow entering the system from the septic drainfield		4.327	m ³ /day
C _e = concentration of nitrates in the septic effluent		0	mg/L	C _e = concentration of nitrates in the septic effluent		4	mg/L
Q _i = flow entering the system from infiltration		0	m ³ /day	Q _i = flow entering the system from infiltration		2	m ³ /day
C _i = Concentration of nitrates in the infiltrate		0	mg/L	C _i = Concentration of nitrates in the infiltrate		0	mg/L
C_T = #DIV/0!		mg/L		C_T = 2.62		mg/L	
Estimate Number of Lots		4	lots	Estimate Number of Lots		1	lots
* = see separate weighted infiltration factor calculations							

OWNER:
STOKED INDUSTRIES INC
14 KNOLL TERRACE,
NEPEAN ON
K2J 2K6



DRAWING LEGEND	
INV	INVERT OF PIPE
SAN	SANITARY SEWER
WL	WATER LINE
DS	EAVE TROUGH DOWNSPOUT
+67.89	EXISTING GRADE ELEVATION
+67.89	PROPOSED GRADE ELEVATION
2%	EXISTING SLOPE OF GRADE
2%	PROPOSED SLOPE OF GRADE
T.O.S	TOP OF SLOPE
B.O.S	BOTTOM OF SLOPE
---	CENTERLINE OF SWALE
.....	SILT BARRIER FENCE
---	PROPERTY LINE
D.C	150mm CURB/DEPRESSED CURB
///	LIGHT-DUTY PAVEMENT
	HEAVY-DUTY PAVEMENT
----	CONCRETE
.....	LANDSCAPE
C.R.Z	CRITICAL ROOT ZONE
F.F.L	FIRST FLOOR ELEVATION
U.S.F	UNDERSIDE OF FOOTING
---	EMERGENCY OVERLAND FLOW



No.	DATE	REVISION
12	JUN 2-25	RE-ISSUED FOR APPROVAL & ISSUED TO OSSO FOR SEPTIC PERMIT
11	OCT 15-24	RE-ISSUED FOR APPROVAL
10	AUG 2-24	ISSUED TO OPS FOR APPROVAL OF FIRE TANKS LOCATION
9	DEC 21-23	RE-ISSUED FOR APPROVAL
8	AUG 10-23	RE-ISSUED FOR APPROVAL
7	JUN 29-23	RE-ISSUED FOR APPROVAL
6	JUN 23-23	RE-ISSUED FOR COORDINATION
5	JUN 8-23	ISSUED FOR COORDINATION
4	APR 19-23	ISSUED FOR CLIENT REVIEW
3	JUL 26-21	RE-ISSUED FOR APPROVAL
2	JUN 14-21	RE-ISSUED FOR APPROVAL
1	MAR 12-21	ISSUED FOR APPROVAL

D. B. GRAY ENGINEERING INC.
Stormwater Management - Grading & Drainage - Storm & Sanitary Sewers - Watermain
700 Long Point Circle
Ottawa, Ontario
613-425-8044
d.gray@dbgrayengineering.com

Project
OFFICE & WAREHOUSE
2167 MCGEE SIDE ROAD
OTTAWA, ONTARIO

Drawing Title
SITE SERVICING PLAN

Engineer's Seal
D.B. GRAY
17016502
JUN 2-25
PROVINCE OF ONTARIO

NOT VALID UNLESS
SIGNED & DATED




Drawn: D.B.G.
Hor. Scale: 1:250
Vert. Scale:
Date: APR 19-23
Job No.: 23024

Drawing No.
C-1
of 7

REFER TO NOTES & DETAILS
ON DRAWINGS C-5 & C-6

OWNER:
STOKED INDUSTRIES INC
14 KNOLL TERRACE,
NEPEAN ON
K2J 2K6

0283



WATERLOO BIOFILTER: BOYD BROS.
BFCN-10000 TREATMENT UNIT, C/W MINIMUM
6.3 m³ FOAM FILTER MEDIA, PUMP (LIBERTY
280-2 EFFLUENT PUMP OR APPROVED EQUAL
CONTROLLED BY THE 'WATERLOO SMART
PANEL'), INLINE FILTER, HIGHWATER ALARM,
RISER & COVER ASSEMBLIES. THE PUMP
SHALL DOSE THE WATERNOX NITRATE
REDUCTION TANK AND RECIRCULATE TO
ANAEROBIC DIGESTER.

PUMP CHAMBER (MIN. 3150 L):
BOYD BROS. PT-3600 (OR
APPROVED EQUAL) C/W PUMP
(LIBERTY 280-2 EFFLUENT PUMP
OR APPROVED EQUAL), 'WATERLOO
SMART PANEL' CONTROL PANEL
(TIME DOSE TO BIOFILTER TANK 6
-10 L PER m³ FOAM), INLINE
FILTER, HIGHWATER ALARM, RISER
& COVER ASSEMBLIES.

FORCEMAINS SHALL BE
50mm PVC SCH 40 PIPE.
INSTALL INSULATION OVER ALL SEPTIC
FORCEMAINS, SEWERS & OTHER SEPTIC
SYSTEM PIPES AS PER DETAILS ON C-5
ALL TANKS AND CHAMBERS SHALL BE
INSTALLED WITH ±500mm COVER;
INSULATE TOP AND EXTEND 1200mm
DOWN SIDES WITH MIN. 100mm TYPE SM
HI-40 STYROFOAM

WATERLOO BIOFILTER ANAEROBIC
DIGESTER: BOYD BROS. 9400 AD
(9,400 L TANK); C/W INNERTUBE
PIPE (MIN. VOLUME 900 L),
HIGHWATER ALARM, RISER &
COVER ASSEMBLIES.

WATERNOX-LS 9,400 L TWO COMPARTMENT
NITRATE REDUCTION TANK TO WATERLOO
BIOFILTER SPECIFICATIONS C/W LIME-SULFUR
AGGREGATE MEDIA, PUMP (LIBERTY 280-2
EFFLUENT PUMP OR APPROVED EQUAL),
HIGHWATER ALARM, RISER & COVER
ASSEMBLIES. PUMP TO DEMAND DOSE
DISPERSAL BED.


ON-SITE SEWAGE SYSTEM
TOTAL DAILY SEWAGE FLOW:
OFFICE AREAS:
THE GREATER OF:
36 EMPLOYEES x 75 L/DAY PER EMPLOYEE = 2,700 L/DAY
OR
350.5 m² OF OFFICES x 75 L/DAY PER 9.3 m² = 2,827 L/DAY
PLUS
WAREHOUSE AREAS:
10 LOADING BAYS x 150 L/DAY PER BAY = 1,500 L/DAY
TOTAL:
OFFICE AREAS (2,827 L/DAY) + WAREHOUSE AREAS (1,500 L/DAY) = 4,327 L/DAY
THE SYSTEM IS DESIGNED FOR 4,500 L/DAY.

REFER TO NOTES & DETAILS
ON DRAWINGS C-5 & C-6

DRAWING LEGEND

INV	INVERT OF PIPE
SAN	SANITARY SEWER
WL	WATER LINE
DS	EAVE TROUGH DOWNSPOUT
+67.89	EXISTING GRADE ELEVATION
+67.89	PROPOSED GRADE ELEVATION
2%	EXISTING SLOPE OF GRADE
2%	PROPOSED SLOPE OF GRADE
T.O.S	TOP OF SLOPE
B.O.S	BOTTOM OF SLOPE
---	CENTERLINE OF SWALE
.....	SILT BARRIER FENCE
---	PROPERTY LINE
D.C	150mm CURB/DEPRESSED CURB
////	LIGHT-DUTY PAVEMENT
XXXX	HEAVY-DUTY PAVEMENT
CONCRETE	CONCRETE
LANDSCAPE	LANDSCAPE
C.R.Z	CRITICAL ROOT ZONE
F.F.L	FIRST FLOOR ELEVATION
USF	UNDERSIDE OF FOOTING
EMERGENCY OVERLAND FLOW	EMERGENCY OVERLAND FLOW

KEY PLAN



No.	DATE	REVISION
8	JUN 2-25	RE-ISSUED FOR APPROVAL & ISSUED TO OSSO FOR SEPTIC PERMIT
7	OCT 15-24	RE-ISSUED FOR APPROVAL
6	DEC 21-23	RE-ISSUED FOR APPROVAL
5	AUG 10-23	RE-ISSUED FOR APPROVAL
4	JUN 29-23	RE-ISSUED FOR APPROVAL
3	JUN 23-23	RE-ISSUED FOR COORDINATION
2	JUN 8-23	ISSUED FOR COORDINATION
1	APR 19-23	ISSUED FOR CLIENT REVIEW

D. B. GRAY ENGINEERING INC.
Stormwater Management - Grading & Drainage - Storm & Sanitary Sewers - Watermain
700 Long Point Circle
Ottawa, Ontario
613-425-8044
d.gray@dbgrayengineering.com

Project
OFFICE & WAREHOUSE
2167 MCGEE SIDE ROAD
OTTAWA, ONTARIO

Drawing Title
SEPTIC SYSTEM

Engineer's Seal
D.B. GRAY
17016502
JUN 2-25
PROVINCE OF ONTARIO

NOT VALID UNLESS
SIGNED & DATED


Drawn: D.B.G.
Hor. Scale: 1:250
Vert. Scale: 1:250
Date: APR 19-23
Job No.: 23024

Drawing No.:
C-2
of 7

WaterNOx-S & WaterNOx-LS Nitrogen Removal


Removes up to 95% of total nitrogen from residential or commercial septic systems with a simple, passive, and cost-effective denitrification filter.

Available upgrade for *all* Waterloo Biofilter advanced wastewater treatment systems



Nitrogen is a nutrient naturally found in human wastewater. Excess nitrogen in groundwater is a public health concern, while excess nitrogen in surface waters can stimulate algae blooms and lake eutrophication. Not only can this be a nuisance and interfere with the enjoyment of water bodies - but serious health and ecosystem problems can result such as 'blue baby' syndrome, fish kills, and 'brown or red tide' algae toxins that accumulate in shellfish.

Excess nitrogen in the environment can:




Contaminate Drinking Water Sources with High Levels of Nitrate



Limit Recreation Activities such as Swimming, Boating, and Fishing



Lower Property Values by Impairing Quality of Surface Water




Lower Dissolved Oxygen Levels and Reduce Fish Populations

Multiple Levels of Removal

The Waterloo Biofilter system itself removes 25-35% of total nitrogen with a single-pass configuration, and 50-65% of total nitrogen with a double-pass configuration where treated effluent is recirculated back to the septic tank. With a WaterNOx-S or WaterNOx-LS denitrification filter installed after the Waterloo Biofilter treatment unit, up to 95% total nitrogen removal can be achieved.

WaterNOx-S

The WaterNOx-S recirculates nitrified effluent up through a plastic filtration media with external carbon source added for denitrification.




A pump re-circulates the water through the filtration media. External carbon is added.

WaterNOx-S Benefits

- ▶ Permanent filtration medium
- ▶ Easy set-up and servicing
- ▶ No filter media backwashing
- ▶ Safe, non-toxic carbon source
- ▶ Low energy use
- ▶ New or retrofit applications

WaterNOx-LS

The WaterNOx-LS uses autotrophic bacteria to denitrify nitrified effluent in a proprietary blend of agricultural minerals.



Water goes down to the bottom of the tank, then flows up through the media and out the outlet.

WaterNOx-LS Benefits


- ▶ 100% passive, no energy used
- ▶ No extra pump necessary
- ▶ No chemical addition
- ▶ Long, 10+ year filter media lifespan
- ▶ Self-buffered to neutral pH
- ▶ Minimal increase to BOD and TSS

**For more
information:**

www.waterloo-biofilter.com
1-866-366-4329
info@waterloo-biofilter.com



Disinfection Instruction Sheet



If your drinking water continues to test positive on repeated submissions, consult your local health unit, which can help you interpret the results of your tests and provide you with advice on what measures you can take to safeguard your drinking water.

The first step in identifying the reason for repeated adverse water quality is to conduct a visual inspection of your well. Start with a close look at your well. The area around it should be

clear of any potential contaminant sources, such as pets, lawn care products, and gardens. Once you're satisfied that the area around your well is okay, take a good, close look at the well itself. If you have an older well, make sure that the cap and the sealant around the well casing isn't cracked or damaged. If it is, you need to fix or replace it right away.

If the source of the problem can't be detected, consult a licensed well contractor right away to identify the source of the problem and eliminate it. You can save yourself a lot of money by doing this instead of rushing out to buy a home treatment device that may be expensive to install, operate, and maintain. And it may not eliminate the source of your trouble.

(If you have a cistern, please talk to your public health unit about disinfection requirements.)

1. Measure the diameter of the well.
2. Measure the well depth and the static or resting water level, then calculate the depth of water in the well.
3. Using the table on this sheet, measure out the amount of bleach needed. (The table gives the volume of bleach needed for different well sizes.) Then, pour the mixture into your well.
4. If possible, mix the water in the well. This can be accomplished by attaching a hose to a tap, running water from the well, through the hose and back into the well.
5. After adding chlorine to the well, remove or bypass any carbon filters that are in the system for water treatment. If you don't, these filters will remove the chlorine from the water, and any pipes beyond the filter will not get disinfected. Replace with new filters after chlorination to avoid reintroducing bacteria into the system.
6. Run water at every faucet in the house (and barn, if you have one) until a strong chlorine odour is detected. Be aware that your nose may lose its ability to detect chlorine.
7. If there is no chlorine smell or it is very weak, add more bleach to the well and repeat Step 6 above.
8. Drain the water heater and fill with chlorinated water.
9. Backflush the water softener and all water filters (except carbon filters).

Volume of Bleach to Add for Every 3 Metres (10 Feet) of Water in the Well*		
Casing Diameter		Volume of Unscented Bleach (5.25% solution)
Millimetres	Inches	Millilitres
50	2	6
100	4	30
150	6	60
200	8	100
250	10	200
300	12	250
400	16	400
500	20	650
600	24	900
900	36	2000 (2 litres)
1200	48	3600 (3.6 litres)

For example: If you have 6 metres (20 feet) of water in your well and it has a casing diameter of 100 mm or 4 inches, you would add 60 mm or 2 fluid ounces of bleach.

* For questions or more information on how to disinfect your well, contact your local health unit.

For more information

Ontario Government Ministry Abbreviations

Ministry of Health and Long-Term Care
MOHLTC (also MOH)

Ministry of the Environment
MOE (also MOEE)

Ontario Ministry of Agriculture and Food
OMAF (also OMAFRA)

Ontario Government Information Lines

MOE Public Information Centre: 1-800-565-4923

MOE Water Well Records: 1-888-396-9355

MOHLTC INFOline: 1-800-268-1154

OMAF Agricultural Information Contact Centre: 1-877-424-1300

Ontario Government Web Sites

MOE: www.ene.gov.on.ca

MOHLTC: www.health.gov.on.ca

OMAF: www.gov.on.ca/omaf

Publications available on-line

Health Canada: www.hc-sc.gc.ca

- *A Guide to Well Water Treatment and Maintenance*;
- *Water treatment devices for disinfection of drinking water*.

MOHLTC: www.health.gov.on.ca

- *How to use water safely during a "Boil Water Advisory"*;
- *E. coli Bacteria*;
- List of Public Health Units in Ontario.

OMAF: www.gov.on.ca/omaf

- *Assessing the Potential for Ground Water Contamination on Your Farm*, Publication 97-017;
- *Best Management Practices: Water Wells*, OMAFRA and Agriculture and Agri-Food Canada, 2003 (to order).

MOE: www.ene.gov.on.ca

- *Important Facts About Water Well Construction*, Publication 3788;
- *Water Wells and Groundwater Supplies: The Protection of Water Quality in Bored and Dug Wells*, Information Sheet PIB 601b;
- *Water Wells and Groundwater Supplies: The Protection of Water Quality in Drilled Wells*, Information Sheet PIB 602b.