



SITE SERVICING REPORT 21 HUNTMAR DRIVE

Project: 127134-6.04.01

City No.: D07-12-21-0035



Prepared for North American Development Group
by IBI Group
October 29, 2021

1	INTRODUCTION.....	1
1.1	Scope	1
1.2	Subject Site.....	1
1.3	Pre-consultation	1
2	WATER DISTRIBUTION.....	2
2.1	Existing Conditions.....	2
2.2	Design Criteria	2
2.2.1	Water Demands.....	2
2.2.2	System Pressure	2
2.2.3	Fire Flow Rates	2
2.2.4	Boundary Conditions.....	3
2.3	Proposed Water Plan	3
3	WASTEWATER.....	4
3.1	Existing Conditions.....	4
3.2	Design Criteria	4
3.3	Recommended Wastewater Plan	4
4	STORMWATER SYSTEM.....	5
4.1	Existing Conditions.....	5
4.2	Design Criteria	5
4.3	Proposed Minor System	5
4.4	Stormwater Management	6
4.5	Inlet Controls.....	6
4.6	On-Site Detention.....	7
4.6.1	Site Inlet Control	7
4.6.2	Overall Release Rate.....	8
5	SEDIMENT AND EROSION CONTROL PLAN	8
6	SOILS.....	8
7	CONCLUSIONS.....	10

1 INTRODUCTION

1.1 Scope

The purpose of this report is to outline the required municipal services, including water supply, stormwater management and wastewater disposal, needed to support the redevelopment of the subject property. The property is approximately 1.6 hectares in area and is located on the west of Huntmar Drive just south of the intersection of Huntmar Drive and Hazeldean Road. The parcel is located across the road from the owners commercial development, and prior to the creation of Huntmar Drive the subject parcel was part of the main parcel located now located on the east side of Huntmar Dr.. Please refer to **Figure 1 – Location Plan** in **Appendix A** for more details.

This Site Servicing Study, which also includes the Stormwater Management Plan, and Erosion and Sedimentation Control Plans, are being completed in support of the Site Plan Application.

1.2 Subject Site

The subject lands are located within the Kanata West Development Area (KWDA) and therefore are subject to the requirements of the KWDA Master Servicing Reports. Since the first site plan approval in 2010, this parcel was intended to be developed as a commercial site, to address market demands the owner is submitting for Site Plan Approval for two six storey residential buildings, with a total of 344 residential units. The proposed development also includes two level of underground parking. Vehicular access to the site will be from Huntmar Drive, where the proposed driveway is opposite the existing entrance for the existing commercial site. Please refer to Site Plan prepared by RLA Architects located in **Appendix A** for more information.

The site currently consists of vacant lot, a copy of the site topographic survey and legal boundary plan prepared by Fairhall Moffatt and Woodland is included in **Appendix A**

1.3 Pre-consultation

It should be noted that a pre-consultation with the Ministry of the Environment is not required since this site is serviced by existing separated municipal sanitary and storm sewers and is a single owner residential site, thus an ECA is not required. A preconsultation meeting with the City of Ottawa was held on July 31, 2020 and a copy of the meeting notes are included in **Appendix A**.

2 WATER DISTRIBUTION

2.1 Existing Conditions

As previously noted, the site is located west of Huntmar Drive just north of Hazeldean Road. An existing 400 mm diameter watermain is located within the Huntmar Drive right of way. The watermain falls within the City of Ottawa's pressure zone 3W which will provide the water supply to the site. When the CDP and MSS were first completed to support the Kanata West development area, the planning for this area envisioned the adjacent parcels to the west to be serviced through this site. As development projects have advanced those parcels have been constructed or designed to be serviced independently from this site.

2.2 Design Criteria

2.2.1 Water Demands

The population for apartment buildings is assumed at 1.4, 2.1 and 2.8 persons per unit for one, two and three bedroom units respectively, as found in Table 4.1 of the Design Guidelines. A watermain demand calculation sheet is included in **Appendix B** and the total water demands are summarized as follows:

	<u>Subject Site</u>
Average Day	2.00 l/s
Maximum Day	5.01 l/s
Peak Hour	11.02 l/s

2.2.2 System Pressure

The Ottawa Design Guidelines – Water Distribution (WDG001), July 2010, City of Ottawa, Clause 4.2.2 states that the preferred practice for design of a new distribution system is to have normal operating pressures range between 345 kPa (50 psi) and 480 kPa (80 psi) under maximum daily flow conditions. Other pressure criteria identified in Clause 4.2.2 of the guidelines are as follows:

Minimum Pressure	Minimum system pressure under peak hour demand conditions shall not be less than 276 kPa (40 psi)
Fire Flow	During the period of maximum day demand, the system pressure shall not be less than 140 kPa (20 psi) during a fire flow event.
Maximum Pressure	In accordance with the Ontario Building/Plumbing Code, the maximum pressure should not exceed 552 kPa (80 psi). Pressure reduction controls will be required for buildings where it is not possible/feasible to maintain the system pressure below 552 kPa.

2.2.3 Fire Flow Rates

A calculation using the Fire Underwriting Survey (FUS) method was conducted to determine the fire flow requirement for both buildings on the site. The buildings are considered non-combustible construction. Results of the analysis provides a maximum fire flow rate of 11,000 l/min or 183 l/s is required. A copy of the FUS calculation is included in **Appendix B**. The buildings will be designed with a Siamese fire connection for each building and they will be located on the building's frontage on Huntmar Drive.

2.2.4 Boundary Conditions

A boundary condition was provided by the City of Ottawa for the development based on connecting to the 400mm diameter watermain on Huntmar Drive. A copy of the boundary conditions is included in **Appendix B** and summarized in the following table. Since the proposed buildings are adjacent to the supply main and are connected with twin 200mm services no significant headloss is anticipated between the building and the source main which would impact the below noted analysis.

BOUNDARY CONDITIONS	
SCENARIO	HGL (m)
	Huntmar Drive
Maximum HGL	161.1m
Minimum HGL (Peak Hour)	156.7m
Max Day + Fire Flow	155.9m

2.3 Proposed Water Plan

The minimum water pressure inside the building at the connection is determined by the difference between the water entry elevation of 100.6m and the minimum HGL condition, resulting in a pressure 550 kPa which exceeds the minimum requirement of 276 kPa per the guidelines. Because the pressure at the 6th floor under minimum HGL conditions is close to the minimum requirement of 276 kPa, an onsite test will be required to confirm if a domestic water pump will be necessary for this building.

Maximum water pressure is determined by the difference between the water entry elevation of 100.6 m and the maximum HGL condition resulting in a pressure of 593.1 kPa, which is greater than the 552 kPa threshold in the guideline in which pressure control is required. Based on this result, pressure control is required for this building.

The boundary condition for Maximum Day and Fire Flow results in a pressure of 513.44 kPa at the ground floor level. In the guidelines, a minimum residual pressure of 140 kPa must be maintained in the distribution system for a fire flow and maximum day event. As a pressure of 513 kPa is achieved, the fire flow requirement is exceeded.

To service the property twin 200mm dia water services off Huntmar Drive are proposed, the services straddle an existing valve which will provide redundancy for the site, see site servicing plan 127134-C-001 in **Appendix B**. The proposed twin 200mm dia services will provide adequate supply to the building to meet demands while also providing service redundancy for the buildings.

3 WASTEWATER

3.1 Existing Conditions

When the MSS for the area was developed a 750mm dia trunk was designed to service this area, and as previously noted the usage was assumed to be commercial and based on the criteria at the time (50,000 l/d/Ha) this site was to drain into the 750 sewer. The site was also to convey flow from upstream lands to the west, however as previously noted the adjacent lands have been serviced independently.

3.2 Design Criteria

The sanitary sewers for the subject site will be based on the City of Ottawa design criteria. It should be noted that the sanitary sewer design for this study incorporates the latest City of Ottawa design parameters identified in Technical Bulletin ISTB-2018-01. Some of the key criteria will include the following:

- Commercial/Institutional flow 28,000 l/ha/d
- Residential flow 280 l/c/d
- Peaking factor 1.5 if ICI in contributing area >20%
1.0 if ICI in contributing area <20%
- Infiltration allowance 0.33 l/s/ha
- Velocities 0.60 m/s min. to 3.0 m/s max.
-

Given the above criteria, the average wastewater flow from the proposed development will be 2.51 l/s, the detailed sanitary sewer calculations and Tributary area plan are included in **Appendix C**. As noted previously when the supporting sewers were designed the site was assumed to be developed as a commercial site with an average flow of 50,000 l/d/Ha, and an infiltration factor of 0.28l/s/Ha, which would have resulted in an average flow of 1.33 l/s. The current plan estimates an average flow of 2.51 l/s which is approximately 1.18 l/s greater than original design, which within the larger context of discharging into a 750mm trunk with a capacity of over 500l/s it is not anticipated to yield any negative impact on the down stream system.

3.3 Recommended Wastewater Plan

A 250mm dia sanitary service lateral is proposed to be extended from the existing sanitary MH in Huntmar Drive to service this site. Please refer to the site servicing plan 127134-C-001 in **Appendix A** for details.

4 STORMWATER SYSTEM

4.1 Existing Conditions

When the Kanata West MSS was completed this site was limited to a minor system flow (5yr) to 85 l/s/Ha and major flow was to be directed to Huntmar Drive. As noted previously the CDP envisioned a connection through this site to the adjacent sites to the west, however those parcels have advanced their design/construction and are now independent of servicing through this site for both minor and major flows. The MSS noted this parcel to be serviced by an end of pipe SWM facility, Pond 5 and the connecting sewers have yet to be constructed. To allow this parcel and Mattamy's Fairwinds development proceed in advance of Pond 5, an interim SWM pond was constructed by Mattamy and cost shared by North American. The interim pond is constructed an operational providing end of pipe treatment of stormwater runoff which includes 80% TSS removal. See detail design reports by DSEL for the Fairwinds Phase 5 and 8 for details.

4.2 Design Criteria

Since this site is serviced by a storm sewer system that was designed based on 85 l/s/Ha City of Ottawa requires the site to follow the following design criteria;

- Storm sewers designed to a 2 year level of service
- Site to be designed to limit the 100 year post development flow to a maximum of 132.74l/s (1.562 Ha @ 85 l/s/Ha).

The stormwater system was designed following the principles of dual drainage, making accommodations for both major and minor flow.

Some of the key criteria include the following:

- Design Storm 1:2 year return (Ottawa)
- Rational Method Sewer Sizing
- Initial Time of Concentration 10 minutes
- Runoff Coefficients
 - Landscaped Areas C = 0.30
 - Asphalt/Concrete C = 0.90
 - Roof C = 0.90
- Pipe Velocities 0.80 m/s to 6.0 m/s
- Minimum Pipe Size 250 mm diameter (200 mm CB Leads)

4.3 Proposed Minor System

Using the above-noted criteria, the proposed on-site storm sewers were sized accordingly. A detailed storm sewer design sheet and the associated storm sewer drainage area plan are included in **Appendix D**. The current servicing drawing outlines the proposed underground parking structure, all of the deck drains are located above the underground parking structure will be routed inside the building via the mechanical plumbing systems and directed to the building cistern located adjacent to the northern wall. All roof deck inlets will be controlled and will utilize rooftop storage, restricted flow from the roof decks will bypass the cistern and discharge to the storm service. The runoff from the landscaped areas will be collected and conveyed through a

series of clear stone infiltration cells. These cells will provide both infiltration and stormwater storage. Volume of storage below the invert of the perforated pipe will be used for infiltration, and the volume of storage above the invert of the perforated pipe will be used for stormwater storage. Flow from the system will be controlled with an ICD and the outlet will connect to the joint outlet servicing the roof drains, and onsite cistern.

4.4 Stormwater Management

The subject site will be limited to a release rate established using the criteria described in section 4.2. This will be achieved through an inlet control device (ICD) at the outlet of the cistern, and inlet control devices on all roof deck inlets, and ICD at the outlet of the infiltration cells.

When rainfall events generate flows that are in excess of the site's allowable release rate excess volume will be stored within the combination of a cistern, roof top and infiltration cells.

At certain locations within the site, the opportunity to capture runoff is limited due to grading constraints and building geometry. These locations are generally located at the perimeter of the site where it is necessary to tie into public boulevards and adjacent properties, and it is not always feasible to capture or store stormwater runoff. These "uncontrolled" areas, 0.121 hectares in total, based on 1:100 year storm uncontrolled flows the uncontrolled areas generate 50.76 l/s runoff (refer to Section 4.5 for calculation). The various roof decks will have inlets that control flow to a total of 27.72 l/s, which leaves 54.26l/s for the remaining surface inlets discharging into the cistern and infiltration cell, which have been sized to accommodate flow during the 1:100-year event, with no overflow leaving the site.

4.5 Inlet Controls

The allowable release rate for the 1.562 Ha site as noted previously is 132.74 l/s.

As noted in Section 4.4, a portion of the site will be left to discharge to the surrounding boulevards and roadways uncontrolled.

Based on a 1:100 year event, the flow from the three uncontrolled areas can be determined as:

$$Q_{\text{uncontrolled}} = 2.78 \times C \times i_{100\text{yr}} \times A \quad \text{where:}$$

C = Average runoff coefficient of uncontrolled area

i_{100yr} = Intensity of 100-year storm event (mm/hr)
 = $1735.688 \times (T_c + 6.014)^{0.820} = 178.56 \text{ mm/hr}$; where $T_c = 10 \text{ minutes}$

A₁ = Uncontrolled Area = 0.037 Ha, $C_{100} = 1.0$, $Q_1 = 18.37 \text{ l/s}$
A₂ = Uncontrolled Area = 0.025 Ha, $C_{100} = 0.25$, $Q_2 = 3.10 \text{ l/s}$
A₃ = Uncontrolled Area = 0.057 Ha, $C_{100} = 1.00$, $Q_3 = 28.29 \text{ l/s}$

Therefore, the uncontrolled release rate can be determined as:

$$Q_{\text{uncontrolled}} = 18.37 + 3.10 + 28.29 = 49.76 \text{ L/s}$$

The maximum allowable release rate from the remainder of the site can then be determined as:

$$Q_{\text{max allowable}} = Q_{\text{restricted}} - Q_{\text{uncontrolled}}$$

$$= 132.74 \text{ L/s} - 49.76 \text{ L/s} = 82.97 \text{ L/s}$$

4.6 On-Site Detention

As noted in section 4.4 any excess storm water up to the 100-year event is to be stored on-site within the building cistern, infiltration cells, and on the roof decks in order to not surcharge the downstream municipal storm sewer system.

4.6.1 Site Inlet Control

The roof decks will utilize restrictor inlets such as the Watts RD-100-A-ADJ (or approved equal) to limit the inflow from each section of roof to the identified flow rates. Storage of runoff on the roof decks will be required to accommodate the 1:100 yr event, and scuppers will provide for overflow should a more extreme event occur or should an inlet become blocked. The Modified Rational Method (MRM) was used to identify the required storage, see the MRM calculations in **Appendix D** for details. The deck and driveway areas drain to the storm water cistern located adjacent to the building north wall, where a Tempest HF ICD (or approved equal) will restrict the flow from the tank to 42.51l/s at 1.26m head. The landscape areas will drain to the infiltration cells where additional storage above the infiltration volume will be used to accommodate restricting the flow from this system to 11.74 l/s with a Tempest MHF ICD at 0.71m head, the MRM spreadsheet in **Appendix D** identifies the required storage to accommodate the 1:100yr event. The following table summarizes the on-site storage requirements during both the 1:2-year and 1:100-year events.

ICD AREA	TRIBUTARY AREA	AVAILABLE STORAGE (M ³)	100-YEAR STORM		2-YEAR STORM	
			RESTRICTED FLOW (L/S)	REQUIRED STORAGE (M ³)	RESTRICTED FLOW (L/S)	REQUIRED STORAGE (M ³)
Cistern	0.510	210.00	42.51	208.88	42.51	54.60
Roof Deck 1A	0.044	17.60	2.52	16.02	2.52	3.88
Roof Deck 1B	0.041	16.40	2.52	14.50	2.52	3.43
Roof Deck 1C	0.030	12.00	1.89	10.51	1.89	2.47
Roof Deck 1D	0.058	23.49	2.52	23.41	2.52	6.06
Roof Deck 1E	0.061	24.40	3.15	23.11	3.15	5.75
Roof Deck 2A	0.044	17.60	2.52	16.01	2.52	3.87
Roof Deck 2B	0.078	33.15	3.15	32.29	3.15	8.50
Roof Deck 2C	0.029	11.60	1.89	10.01	1.89	2.33
Roof Deck 2D	0.057	23.09	2.52	22.86	2.52	5.89
Roof Deck 2E	0.030	12.00	1.89	10.51	1.89	2.47
Roof Deck 2F	0.058	23.20	3.15	21.56	3.15	5.29
Landscape	0.400	64.80	11.74	64.63	11.74	15.26
Unrestricted	0.119		49.76		23.00	
TOTAL	1.559	489.33	131.73	474.27	104.97	119.81

In all instances the required storage is met with the building cistern, landscape and roof top storage, respectively.

4.6.2 Overall Release Rate

As demonstrated above, the site uses various inlet control devices to restrict the 100 year storm event to 131.73 l/s. Restricted stormwater will be contained onsite by the building cistern,

landscape clear stone cells, and roof top storage. Up to and including the 100 year event, there will be no overflow off-site from restricted areas, if however an more intense storm or should an inlet become blocked, overland routing has been provided to the approved outlet per the original system design.

5 SEDIMENT AND EROSION CONTROL PLAN

During construction, existing stream and storm water conveyance systems can be exposed to significant sediment loadings. A number of construction techniques designed to reduce unnecessary construction sediment loadings may be used such as;

- Filter socks will remain on open surface structures such as manholes and catchbasins until these structures are commissioned and put into use;
- Installation of silt fence, where applicable, around the perimeter of the proposed work area.

During construction of the services, any trench dewatering using pumps will be fitted with a “filter sock.” Thus, any pumped groundwater will be filtered prior to release to the existing surface runoff. The contractor will inspect and maintain the filter sock as needed including sediment removal and disposal.

All catchbasins, and to a lesser degree manholes, convey surface water to sewers. Consequently, until the surrounding surface has been completed these structures will be protected with a sediment capture filter sock to prevent sediment from entering the minor storm sewer system. These will stay in place and be maintained during construction and build-out until it is appropriate to remove them.

The Sediment and Erosion Control Plan 127134-C-900 is included in **Appendix E**.

6 SOILS

Paterson Group was retained to prepare a geotechnical investigation for the proposed development. The objectives of the investigation were to prepare a report to:

- Determine the subsoil and groundwater conditions at the site by means of boreholes and monitoring well program.
- To provide geotechnical recommendations pertaining to design of the proposed development including construction considerations.

The geotechnical report PG5006-1 rev 2, “Geotechnical Investigation 21 Huntmar Drive” dated December 1, 2020. A copy of the report has been included with the SPA application. The report contains recommendations for building construction and site services, which include but are not limited to the following for site servicing:

- Bedding and cover for service pipes: bedding min 150mm compacted (95% SPMDD) OPSS Gran. A to the springline, and covered with OPSS Gran A
- Fill for driveway to be suitable native material or OPSS Select Subgrade Material placed in thin lifts compacted to 95% SPMDD
- Long term groundwater level 3 to 4m below grade
- Permissible Grade raise 1.2m

MATERIAL	Layer Thickness
• Car Only Parking Areas	
• Asphalt Wearing Course (Superpave 12.5)	• 50 mm
• Well Graded Granular Base Course (Granular 'A')	• 150 mm
• Well Graded Granular Sub-Base Course (Granular 'B' Type II)	• 300 mm
• Access Lanes and Heavy Truck Parking	
• Asphalt Wearing Course (Superpave 12.5)	• 40 mm
• Asphalt Binder Course (Superpave 19.0)	• 50 mm
• Well Graded Granular Base Course (Granular 'A')	• 150 mm
• Well Graded Granular Sub-Base Course (Granular 'B' Type II)	• 400 mm

Infiltration targets for the proposed site were outlined in the KWDA MSP. As indicated in Figure 5.4 of the MSS, the soil type within the proposed development area is characterized as clay with low recharge potential, and the geotechnical engineer confirmed the soil has a typical permeability of 7 to 25mm/hr. The infiltration target for the area, as identified within the MSP is 50-70mm/year. The subject site consists of approximately 1.56 Ha of development, the site is comprised of impervious Building deck and roof surfaces, and pervious landscape areas. It is proposed to install infiltration cell within the landscape areas to assist the pervious landscape area meet the infiltration target for the site.

For the previous phases of the original development an infiltration strategy for the site was developed in consultation with the MVCA; see approval email from MVCA (Doug Nuttall) in **Appendix E**. The strategy included three sources: natural infiltration from rainfall, infiltration from irrigation system, and infiltration from a dry well supplied by roof runoff. For this phase where more landscape area is available, we propose to only use infiltration cells supplied with rainfall runoff from the landscape areas.

The Infiltration cells will be drywells constructed approximately 1.5 to 1.8m below grade with clear stone, each cell will be 4m wide by 60m long, and 0.2m clear depth from bottom of perforated pipe to the bottom of the cell. Each cell has a volume of 48m³, clear stones have approximately 30% resulting in approximately 14.4m³ of storage available for each cell for a total of 43.2m³. The geotechnical engineer has confirmed the long range water table is 3 to 4m below the surface and will not impact the cells.

Rainfall from the 4000 m² of landscape areas will supply the infiltration cells, the cells are set up such that if the volume of runoff from the landscape area exceeds the storage capacity of the dry well excess runoff is discharged to the storm sewer, see the Servicing Plan C-100 in **Appendix A**, and the Grading Plan C-200 in **Appendix E**.

Based on previously approved rainfall data where for the months of March up to and including November, 40 days of 5mm or more rain occurred, and for the same period 22 days of 10mm or more rain occurred, a review of 2020 data revealed similar results, 40 days 5mm or more, 19 days 10mm or more. Also for 2020 data there were no back to back rain days of 10mm or more. Since the cells have a relatively shallow storage depth (200mm) the anticipated time to infiltrate is between 8 to 28hrs (7 to 25mm/hr), which could accommodate historic back to back events. Assuming 80% of rainfall either infiltrates naturally or is collected by the drains and discharged into the drywell, the following volume of rainfall will supply the runoff to meet the infiltration targets:

5mm, at 80% = 4mm, for 4000 m² of landscape area = 16.0m³, for 40 events = 640m³

10mm, at 80%= 8mm (less 4mm from above) = 4mm for 4000 m² of landscape area = 16.0m³, for 19 events = 304.0m³. These events provide approximately of 944m³ of rainfall runoff available for infiltration. For the 1.56 Ha site this equates to approximately 60.5mm/yr of infiltration, which is within the guideline of 50 to 70 mm/yr.

7 CONCLUSIONS

Municipal water, wastewater and stormwater systems required to accommodate the proposed development are available to service the proposed development. Prior to construction, existing sewers are to be CCTV inspected to assess sewer condition.

This report has demonstrated sanitary and storm flows from and water supply to the subject site can be accommodated by the existing infrastructure. Also, the proposed servicing has been designed in accordance with MECP and City of Ottawa current level of service requirements.

The use of lot level controls, conveyance controls and end of pipe controls outlined in the report will result in effective treatment of surface stormwater runoff from the site. Adherence to the sediment and erosion control plan during construction will minimize harmful impacts on surface water.

Based on the information provided herein, the development can be serviced to meet City of Ottawa requirements.

Report prepared by:



Demetrius Yannouloupoulos, P. Eng.
Director, Ottawa Office Lead

"J:\127134_21 Huntmar rd_6.0_Technical\6 04_Civil_01brief\1st Submission\CTR-site-servicing-erosion-2021-010-29.docx"

APPENDIX A

- Site Plan
- Topographic Survey
- Preconsultation Meeting Notes



Untitled Map
Write a description for your map.

Legend

PARKLAND

WELLINGS OF STITSVILLE
RETIREMENT COMMUNITY

21 HUNTMAR DR

FOOD
BASICS

KEG
RESTAURANT

Hazeldean Rd
Iber Rd

36

Google Earth

rla / architecture
roderick lahey architect inc.

SITE LOCATION


February 2020

21 HUNTMAR DRIVE

OTTAWA, ONTARIO

1A

METRIC
DISTANCES AND ELEVATIONS SHOWN ON THIS PLAN ARE IN METRES
AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048



**TOPOGRAPHIC SURVEY OF
BLOCK 1
REGISTERED PLAN 4M-1432
CITY OF OTTAWA**

SCALE 1 : 400

FAIRHALL, MOFFATT & WOODLAND LIMITED
ONTARIO LAND SURVEYORS

ELEVATION NOTES

- ELEVATIONS SHOWN HEREON ARE REFERRED TO GEODETIC DATUM.
- ELEVATIONS FOR MANHOLE COVERS AND CATCH BASINS HAVE TO BE INDEPENDENTLY CONFIRMED BEFORE THEY CAN BE ACCEPTED FOR FINAL DESIGN OR CONSTRUCTION PURPOSES.
- IT IS THE RESPONSIBILITY OF THE USER OF THIS INFORMATION TO VERIFY THAT THE JOB BENCHMARKS HAVE NOT BEEN ALTERED OR DISTURBED AND THAT THEIR RELATIVE ELEVATION AND DESCRIPTION AGREE WITH THE INFORMATION SHOWN ON THIS DRAWING.

UTILITY NOTES

- THIS DRAWING CANNOT BE ACCEPTED AS ACKNOWLEDGING ALL OF THE UNDERGROUND UTILITIES AND IT WILL BE THE RESPONSIBILITY OF THE USER TO CONTACT THE RESPECTIVE UTILITY AUTHORITIES FOR CONFIRMATION OR LOCATION.
- UNDERGROUND UTILITIES, AS REPORTED ON THIS DRAWING, ARE NOT BASED ON AN ACTUAL 'FIELD LOCATE' BY THE RESPECTIVE UTILITY AGENCIES BUT HAVE BEEN COMPILED FROM DATA OBTAINED FROM THE FOLLOWING SOURCE:
a) CITY OF OTTAWA PUBLIC UTILITIES REGISTRY
- BEFORE ANY WORK INVOLVING PROBING, EXCAVATING, ETC., A FIELD LOCATION OF UNDERGROUND PLANT BY THE PERTINENT UTILITY AUTHORITY IS MANDATORY.

NOTES

- THE SURVEY REPRESENTED BY THIS PLAN WAS COMPLETED ON AUGUST 25, 2015.
- THE SURVEY REPRESENTED BY THIS PLAN WAS UPDATED ON JULY 29, 2019.
- BEARINGS ARE GRID REFERRED TO THE SOUTHERLY LIMIT OF HUNTMAR DRIVE SHOWN ON PLAN 4M-1432 AS HAVING A BEARING OF N41°11'45"W.

LEGEND

■	- SURVEY MONUMENT FOUND	⊗ UP	- UTILITY POLE
SIB	- STANDARD IRON BAR	⊗ BP	- BELL PEDESTAL
SSIB	- SHORT STANDARD IRON BAR	⊗ MW	- MONITORING WELL
IB	- IRON BAR	⊗	- BOREHOLE
CP	- CONCRETE PIN	⊗	- BOLLARD
DIA.	- DIAMETER	⊗	- GUY WIRE AND ANCHOR
BLK	- BLOCK	⊗	- SIGN
PIN	- PROPERTY IDENTIFIER NUMBER	⊗	- DECIDUOUS TREE
CB	- CATCH BASIN	⊗	- CURB
MH	- MANHOLE	⊗	- GASMAIN
MHST	- STORM MANHOLE	⊗	- SANITARY SEWER
MHSA	- SANITARY MANHOLE	⊗	- WATER MAIN
MWH	- WATER MANHOLE	⊗	- UNDERGROUND BELL
TMH	- TRAFFIC MANHOLE	⊗	- UNDERGROUND HYDRO
HMH	- HYDRO MANHOLE	⊗	- STREET LIGHTING
FH	- FIRE HYDRANT	⊗	- ROGERS CABLE
TCB	- TRAFFIC CONTROL BOX	⊗	- TRAFFIC
WV	- WATER VALVE	⊗	- EDGE OF TREES
TL	- TRAFFIC LIGHT		
LS	- LAMP STANDARD		

SURVEYOR'S CERTIFICATE

I CERTIFY THAT:
1. THIS SURVEY AND PLAN ARE CORRECT AND IN ACCORDANCE WITH THE SURVEYS ACT, THE SURVEYORS ACT AND THE REGULATIONS MADE UNDER THEM.
2. THE SURVEY WAS COMPLETED ON JULY 29, 2019.

2019/08/07
DATE

JOHN H. GUTRI
ONTARIO LAND SURVEYOR

**Fairhall
Moffatt &
Woodland**
LIMITED
ONTARIO LAND SURVEYORS

100-600 TERRY FOX DRIVE, KANATA, ONTARIO K2L 4B6
TEL: (613) 591-2580 FAX: (613) 591-1495
www.fmw.on.ca

JOB No. 224700
E 350751, N 5016205
REFERENCE No. 4(c) - 4M - 1432
2247_topo-up.dwg

© COPYRIGHT 2019. REPRODUCTION, ALTERATION OR DISTRIBUTION OF THIS PLAN WITHOUT THE WRITTEN CONSENT OF FAIRHALL, MOFFATT & WOODLAND LIMITED IS PROHIBITED.

THIS IS NOT A VALID COPY UNLESS EMBOSSED WITH SEAL

21 Huntmar Drive Pre-Consultation Meeting Minutes

Location: Room 4106E, City Hall
Date: July 31, 2019, 3pm to 4pm

Attendee	Role	Organization
Mark Young	Planner	City of Ottawa
Julie Candow	Project Manager (Infrastructure)	
Mike Giampa	Project Manager (Transportation)	
Matthew Ippersiel	Planner (Urban Design)	
Sami Rehman	Planner (Environmental)	
Samantha Gatchene	Planning Assistant	
Ron Richards	Owner's Representative	North American
Paul Ferarro	Owner's Representative	
Abhinav Sukumar	Architect	Roderick Lahey Architects

Comments from Applicant

1. The applicant is proposing the development of two (2) five-storey mid-rise buildings at 21 Huntmar Drive. The buildings would be residential apartments with 210 units total.
2. 334 underground parking spaces and 12 surface parking spaces would be provided.
3. One new access point is proposed off of Huntmar Drive. This driveway would lead to the surface parking lot on the interior of site, providing access to both buildings and the underground parking.

Planning Comments

1. This is a pre-consultation for a Site Plan Control application, Complex, subject to Public Consultation. Application form, timeline and fees can be found [here](#).
2. With regards to maximum building height, the Zoning By-law permits a maximum of 11 metres in areas up to 20 metres from a property line abutting a residential zone.
3. Cash-in-lieu of parkland and associated appraisal fee will be required as a condition of approval as per the [Parkland Dedication By-law](#).

Urban Design Comments

1. The general built form approach and the L-shaped building footprints framing the street are supported and it is recommended that the applicant pursue this approach.
2. The ground-oriented units and proposed individual walkways are supported.
3. As the site plan and landscape plan progress, be mindful of demonstrating how the pedestrian pathway network will be properly lit and CPTED design principles have been applied.

Engineering Comments

1. The Servicing Study Guidelines for Development Applications are available at the following address: <https://ottawa.ca/en/city-hall/planning-and-development/information-developers/development-application-review-process/development-application-submission/guide-preparing-studies-and-plans>
2. Servicing and site works shall be in accordance with the following documents:
 - ⇒ Ottawa Sewer Design Guidelines (October 2012)
 - ⇒ Ottawa Design Guidelines – Water Distribution (2010)
 - ⇒ Geotechnical Investigation and Reporting Guidelines for Development Applications in the City of Ottawa (2007)
 - ⇒ City of Ottawa Slope Stability Guidelines for Development Applications (revised 2012)
 - ⇒ City of Ottawa Environmental Noise Control Guidelines (January 2016)
 - ⇒ City of Ottawa Park and Pathway Development Manual (2012)
 - ⇒ City of Ottawa Accessibility Design Standards (2012)
 - ⇒ Ottawa Standard Tender Documents (latest version)
 - ⇒ Ontario Provincial Standards for Roads & Public Works (2013)
3. Record drawings and utility plans are also available for purchase from the City (Contact the City's Information Centre by email at InformationCentre@ottawa.ca or by phone at (613) 580-2424 x.44455).
4. The Stormwater Management Criteria for the subject site is to be based on the following:
 - i. The allowable storm release rate for the subject site is limited to 85 L/s/ha as per the Kanata West Master Servicing Study.
 - ii. Onsite storm runoff, in excess of the allowable release rate, and up to the 1:100 year storm event must be detained on site.

- iii. Post development infiltration rates are to be increased by 25 percent above the pre-development infiltration rates as per the Kanata West Master Servicing Study.
 - iv. Quantity control to be provided by the downstream stormwater management facility and/or as determined by the Mississippi Valley Conservation Authority (MVCA). Please include correspondence from the MVCA in the stormwater management report.
 - v. A letter of acknowledgment will be required to be obtained from Mattamy to allow storm flows from 21 Huntmar Drive to discharge to Mattamy's temporary SWM pond, within Mattamy's Phase 5 development.
5. No sanitary sewer capacity constraints were identified on Huntmar Drive during the initial review of the concept plan. A sanitary sewer connection to the existing 750mm diameter sanitary sewer within Huntmar Drive is acceptable.
6. As per Section 4.3.1 of the Water Design Guidelines, two watermain connections will be required to provide a looped connection if the basic day demand is greater than 50 m³/day (approx. 50 homes).
7. Water Boundary condition requests must include the location of the service and the expected loads required by the proposed development. Please provide the following information:
- i. Location of service
 - ii. Type of development and the amount of fire flow required (as per FUS, 1999).
 - iii. Average daily demand: ___ l/s.
 - iv. Maximum daily demand: ___ l/s.
 - v. Maximum hourly daily demand: ___ l/s.
8. An MECP Environmental Compliance Approval is not anticipated to be required for the subject site.
9. Phase 1 ESAs and Phase 2 ESAs must conform to clause 4.8.4 of the Official Plan that requires that development applications conform to Ontario Regulation 153/04.

Should you have any questions or require additional information, please contact me directly at (613) 580-2424, x13850 or by email at Julie.Candow@ottawa.ca.

Transportation Comments

1. A TIA is triggered for this site and they should proceed to Scoping (Step 2). This should be done prior to an application.
2. The signalization of the Huntmar access should be further explored.
3. The application will not be deemed complete until the submission of the draft Step 1-4, including the functional draft RMA package (if applicable).
4. A noise study is required.

Environmental Planning

1. The subject property is within the adjacency distance to the Natural Heritage Systems (See OP Section 2.4.2 and Schedule L3) and thus, triggers a requirement for an Environmental Impact Statement (EIS), as per OP Section 4.7.8. Given that butternut trees were identified in the adjacent woodlot, there is a potential for butternuts to be on the subject property. The field on the subject property may also host other endangered or threatened species.
2. The EIS should address and demonstrate no negative impacts on the NHS and to determine the presence of endangered or threatened species or their habitats on the subject property. Further details on the EIS requirements can be found in OP section 4.7.8 and the EIS guidelines.
https://documents.ottawa.ca/sites/default/files/documents/eis_guidelines2015_en.pdf

Forestry

1. Any tree information can be combined into the EIS.
2. A tree permit is required if any trees need to be cut that are 10cm or larger in diameter.

Parks Planning

1. Recommend there is a pathway connection to the Poole Creek corridor (UNA 185);
2. Assumption that play area(s) are to remain as private ownership.
3. Although play area(s) are private, recommend the Owner adhere to City specifications and standards for play area(s) design, construction and maintenance.

4. The site is located within Kanata West CDP area, therefore 100% CIL direction to District Park

Mississippi Valley Conservation Authority

1. There does not appear to be any hazards or heritage features, however it appears to drain into Poole Creek so it is enhanced level of treatment and we generally recommend using LIDs.
2. The Master Serving Study for Kanata West (SWM) indicates infiltration targets 50 – 70 mm/yr., but it should be confirmed.

Requested Plans and Studies

1. A list of required plans and studies required for a complete Site Plan Control application have been attached.

Please refer to the links to "[Guide to preparing studies and plans](#)" and [fees](#) for general information. Additional information is available related to [building permits, development charges, and the Accessibility Design Standards](#). Be aware that other fees and permits may be required, outside of the development review process. You may obtain background drawings by contacting informationcentre@ottawa.ca.

These pre-con comments are valid for one year. If you submit a development application(s) after this time, you may be required to meet for another pre-consultation meeting and/or the submission requirements may change. You are as well encouraged to contact us for a follow-up meeting if the plan/concept will be further refined.

Please contact me at Mark.Young@ottawa.ca or at 613-580-2424 extension 41396 if you have any questions.

Sincerely,



Mark Young, MCIP RPP
Planner III
Development Review - West

APPENDIX B

- Watermain Demand Calculation Sheet
- FUS Fire Flow Calculation
- Watermain Boundary Condition
- C-001 General Plan
- C-010 Details Plan



IBI GROUP
333 PRESTON STREET
OTTAWA, ON
K1S 5N4

WATERMAIN DEMAND CALCULATION SHEET

PROJECT : 21 HUNTMAR DR
LOCATION : City of Ottawa
DEVELOPER : NORTH AMERICAN DEVELOPMENT GROUP

F LE: 127134-6.4.4
DATE PRINTED: 2021-02-08
DESIGN: 2021-01-19
PAGE: 1 OF 1

NODE	RES DENTIAL				NON-RES DENTIAL			AVERAGE DAILY DEMAND (l/s)			MAX MUM DAILY DEMAND (l/s)			MAXIMUM HOURLY DEMAND (l/s)			FIRE DEMAND (l/min)
	UNITS				INDTRL	COMM.	RETAL	Res.	Non-res.	Total	Res.	Non-res.	Total	Res.	Non-res.	Total	
	1bd	2bd	3bd	POP'N	(ha.)	(ha.)	(m ²)										
BUILDING A	38	102		267				0.87	0.00	0.87	2.17	0.00	2.17	4.77	0 00	4.77	
BUILDING B	111	93	0	351				1.14	0.00	1.14	2.84	0.00	2.84	6 25	0 00	6.25	
Total	149	195	0	618				2.00	0.00	2.00	5.01	0.00	5.01	11.02	0 00	11.02	11,000

ASSUMPTIONS

<u>RESIDENTIAL DENSITIES</u>	<u>AVG. DAILY DEMAND</u>	<u>MAX. HOURLY DEMAND</u>
One-bedroom/Studio (1bd) 1.4 p / p / u	Residential:** 280 l / cap / day	Residential: 1,540 l / cap / day
Two-bedroom (2bd) 2.1 p / p / u	Industrial: l / ha / day	Industrial: l / ha / day
Three-bedroom (3bd) 2.8 p / p / u	Commercial: l / ha / day	Commercial: l / ha / day
	Retail: l / 1000m ² / day	Retail: l / 1000m ² / day
** Residential Daily Demand reduced to coincide with current waste water guidelines	<u>MAX. DAILY DEMAND</u>	<u>FIRE FLOW</u>
	Residential: 700 l / cap / day	From FUS Calculation 11,000 l / min
	Industrial: l / ha / day	
	Commercial: l / ha / day	
	Retail: l / 1000m ² / day	

Fire Flow Requirement from Fire Underwriters Survey - 21 Huntmar Drive

Building A

Floor Area (1 & 2)	4,682 m ²
50% Floor Area (3 to 8)	4,557
Total Floor Area	9,239 m²

$F = 220C\sqrt{A}$

C	0.6	C =	1.5 wood frame
A	9,239 m ²		1.0 ordinary
			0.8 non-combustible
F	12,688 l/min		0.6 fire-resistive
use	13,000 l/min		

Floor	Area (m ²)	Two Largest	Floors Above at
1	2341	2341	
2	2341	2341	
3	2341		1170.5
4	2341		1170.5
5	2341		1170.5
6	2091		1045.5
Total	13796	4682	4557

(Note: For fire-resistive buildings, consider two largest adjoining floors plus 50% of each of any floors immediately above them

Occupancy Adjustment

		-25% non-combustible
		-15% limited combustible
Use	-15%	0% combustible
		+15% free burning
Adjustment	-1950 l/min	+25% rapid burning
Fire flow	11,050 l/min	

Sprinkler Adjustment

		-30% system conforming to NFPA 13
		-50% complete automatic system
Use	-30%	
Adjustment	-3315 l/min	

Exposure Adjustment

Building Face	Separation (m)	Adjacent Exposed Wall			Exposure Charge *
		Length	Stories	L*H Facto	
north	40.0				5%
east	25.5	20.0	6	120	9%
south	> 45				0%
west	28.0	100.0	2	200	15%

Total 29%

Adjustment 3,205 l/min

Total adjustments	(111) l/min
Fire flow	10,940 l/min
Use	11,000 l/min
	183 l/s

* Exposure charges from Technical Bulletin ISTB 2018-02 Appendix H (ISO Method)

Fire Flow Requirement from Fire Underwriters Survey - 21 Huntmar Drive

Building B

Floor Area (1 & 2)	5,936 m ²
50% Floor Area (3 to 8)	5,793
Total Floor Area	11,729 m²

$F = 220C\sqrt{A}$

C	0.6	C =	1.5 wood frame
A	11,729 m ²		1.0 ordinary
			0.8 non-combustible
F	14,296 l/min		0.6 fire-resistive
use	14,000 l/min		

Floor	Area (m ²)	Two Largest Floor	Floors Above at 50%
1	2968	2968	
2	2968	2968	
3	2968		1484
4	2968		1484
5	2968		1484
6	2682		1341
Total	17522	5936	5793

(Note: For fire-resistive buildings, consider two largest adjoining floors plus 50% of each of any floors immediately above them up to eight.)

Occupancy Adjustment

		-25% non-combustible
		-15% limited combust ble
Use	-15%	0% combustible
		+15% free burning
Adjustment	-2100 l/min	+25% rapid burning
Fire flow	11,900 l/min	

Sprinkler Adjustment

		-30% system conforming to NFPA 13
		-50% complete automatic system
Use	-30%	
Adjustment	-3570 l/min	

Exposure Adjustment

Building Face	Separation (m)	Adjacent Exposed Wall			Exposure Charge *
		Length	Stories	L*H Factor	
north	> 45				0%
east	> 45				0%
south	> 45				0%
west	25.5	20.0	6	120	9%

Total 9%

Adjustment 1,071 l/min

Total adjustments (2,499) l/min

Fire flow 9,401 l/min

Use 9,000 l/min

150 l/s


* Exposure charges from Technical Bulletin ISTB 2018-02 Appendix H (ISO Method)

Boundary Conditions 21 Huntmar Drive

Provided Information

Scenario	Demand	
	L/min	L/s
Average Daily Demand	120	2.00
Maximum Daily Demand	301	5.01
Peak Hour	661	11.02
Fire Flow Demand #1	11,000	183.33

Location



Results

Connection 1 – Huntmar Dr.

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	161.1	82.4
Peak Hour	156.7	76.0
Max Day plus Fire 1	155.9	74.9

Ground Elevation = 103.2 m

Connection 2 – Huntmar Dr.

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	161.1	82.4
Peak Hour	156.7	76.0
Max Day plus Fire 1	155.9	74.9

Ground Elevation = 103.2 m


Notes

1. Two service connection with a separation valve in-between.
2. As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:
 - a. If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
 - b. Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.

Disclaimer

The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.

ICD LOCATION (MH #)	RELEASE RATE (L/s)	HEAD (m)	ICD
SWM tank	42.51	1.26	Tempest LMF plate
CBMH2	11.74	0.71	Tempest LMF plate



CLIENT

North American
DEVELOPMENT GROUP

2851 John Street, Suite One, Markham, Ontario L3R 5R7 T 905-968-3185

COPYRIGHT

This drawing has been prepared solely for the intended use, and any reproduction or distribution for any purpose other than that authorized by IBI Group is prohibited. IBI Group shall be responsible for all dimensions and conditions on the job, and all changes shall be approved in writing from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to IBI Group for general conformance before proceeding with fabrication.

IBI Group Professional Services (Canada) Inc.
is a member of the IBI Group of companies.

ISSUES	No.	DESCRIPTION	DATE
1	ISSUED FOR SPA	2021-02-16	
2	SPA SUBMISSION	2021-05-30	
3	SPA SUBMISSION	2021-08-17	
4	SPA SUBMISSION	2021-10-29	

SEE 010 FOR NOTES, LEGEND

KEY PLAN

SITE

CONSULTANTS

Project Coordinator:
North American Development Group

Architect:
RLA Architecture

Surveyor:
Fairhall, Moffatt and Woodland Ltd.

Geotechnical:
Paterson Group

Traffic:
JD Halpenny & Assoc.

Electrical:
Hammerschlag & Joffe Inc.

Landscape:
NAK Design Strategies



SEAL

IBI GROUP
Suite 400 - 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 / 613 241 3300 fax 613 225 9668
ibigroup.com

PROJECT
21/35 HUNTMAR DRIVE

PROJECT NO:
127134

DRAWN BY:
EH

CHECKED BY:
DGY




PROJECT MGR:
DGY

APPROVED BY:
DGY

SHEET TITLE
GENERAL PLAN OF SERVICES

SHEET NUMBER
C-001

ISSUE
1



CITY FILE No. D07-12-21-0035
Scale Check
File Location: \\127134_21_huntmar\0_Production\02_Design\04_Civil\Sheets\C-001_GENERAL PLAN OF SERVICES.dwg Last Saved: October 29, 2021, by: Elenwe Plotted: Friday, October 29, 2021 8:51:54 AM by: Eric Harris

CROSSING SCHEDULE					
1	EX300x200 mm SAN	0.681 m	CLEARANCE OVER	375 mm ø STM	
2	EX975 mm ø STM	0.262 m	CLEARANCE OVER	250 mm ø SAN	
3	EX300x200 mm ø SAN	1.711 m	CLEARANCE OVER	250 mm ø SAN	
4	200 mm ø W/M	1.324 m	CLEARANCE OVER	EX750 mm ø SAN	
5	200 mm ø W/M	0.482 m	CLEARANCE OVER	EX975 mm ø STM	
6	200 mm ø W/M	0.296 m	CLEARANCE OVER	EX300x200 mm ø SAN	
7	200 mm ø W/M	1.152 m	CLEARANCE OVER	EX750 mm ø SAN	
8	200 mm ø W/M	0.493 m	CLEARANCE OVER	EX975 mm ø STM	
9	EX300x200 mm ø SAN	0.493 m	CLEARANCE OVER	200 mm ø W/M	

PAVEMENT STRUCTURE **	
CAR ONLY PARKING AREAS:	
50mm WEAR COURSE - HL-3 OR SUPERPAVE 12.5 ASPHALTIC CONCRETE	
150mm BASE - OPSS GRANULAR "A" CRUSHED STONE	
300mm SUBBASE - OPSS GRANULAR "B" TYPE II	
SUBGRADE - EITHER F LL, IN SITU SOIL, OR OPSS GRANULAR "B" TYPE I OR II	
MATERIAL PLACED OVER IN SITU SOIL OR FILL	
ACCESS LANES AND HEAVY TRUCK PARKING AREAS	
40mm WEAR COURSE - HL-3 OR SUPERPAVE 12.5 ASPHALTIC CONCRETE	
50mm BINDER COURSE - HL-8 OR SUPERPAVE 19.0 ASPHALTIC CONCRETE	
150mm BASE - OPSS GRANULAR "A" CRUSHED STONE	
400mm SUBBASE - OPSS GRANULAR "B" TYPE II	
SUBGRADE - EITHER F LL, IN SITU SO L, OR OPSS GRANULAR "B" TYPE I OR II	
MATERIAL PLACED OVER IN SITU SOIL OR FILL	

** REFER TO GEOTECHNICAL REPORT BY PATERSON GROUP - REV # 2 DATED DECEMBER 20, 2020

DRAWING NOTES

1.0 GENERAL

- CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO CONSTRUCTION.
- DO NOT SCALE DRAWINGS.
- CONTRACTOR TO REPORT ALL DISCOVERIES OF ERRORS, OMISSIONS OR DISCREPANCIES TO THE ARCHITECT OR DESIGN ENGINEER AS APPLICABLE.
- USE ONLY THE LATEST REVISED DRAWINGS OR THOSE THAT ARE MARKED "ISSUED FOR CONSTRUCTION".
- ALL CONSTRUCTION SHALL COMPLY WITH CURRENT CITY OF OTTAWA STANDARDS AND SPECIFICATIONS.
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT DRAWINGS AND SPECIFICATIONS.
- FOR LEGAL SURVEY INFORMATION REFER TO REGISTERED PLAN FROM FAIRHALL, MOFFATT AND WOODLAND LTD.
- REFER TO SITE PLAN BY RLA ARCHITECTURE.
- CONTRACTOR TO IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES AS IDENTIFIED IN THE EROSION AND SEDIMENT CONTROL PLAN TO THE SATISFACTION OF THE CITY OF OTTAWA, PRIOR TO UNDERTAKING ANY SITE ALTERATIONS (FILLING, GRADING, REMOVAL OF VEGETATION, ETC.) DURING ALL PHASES OF THE SITE PREPARATION AND CONSTRUCTION THE MEASURES ARE TO BE MAINTAINED TO THE SATISFACTION OF THE ENGINEER AND CITY OF OTTAWA IN ACCORDANCE WITH THE BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROL. SHOULD ANY ADDITIONAL MEASURES BE REQUIRED TO ADDRESS FIELD CONDITIONS THEY SHALL BE INSTALLED AS DIRECTED BY THE ENGINEER OR THE CITY OF OTTAWA. SUCH ADDITIONAL MEASURES MAY INCLUDE BUT NOT BE LIMITED TO INSTALLATION OF SEDIMENT CAPTURE FILTER SOCKS WITHIN MANHOLES AND CATCHBASINS TO PREVENT SEDIMENT FROM ENTERING THE STRUCTURE AND INSTALLATION AND MAINTENANCE OF A LIGHT DUTY SILT FENCE BARRIER AS REQUIRED.
- ALL IRON WORK ELEVATIONS SHOWN ARE APPROXIMATE AND ARE SUBJECT TO MINOR ADJUSTMENTS AS DETERMINED BY THE ENGINEER.
- ALL CONCRETE CURBS AND SIDEWALKS TO CONFORM TO O.P.S. AND CONSTRUCTED TO CITY STANDARDS. ALL ONSITE CURBS TO BE BARRIER TYPE, WITH DEPRESSIONS AS NOTED.
- ALL CONCRETE SHALL BE "NORMAL PORTLAND CEMENT" IN ACCORDANCE WITH O.P.S.S. 1350 AND SHALL ACHIEVE A MINIMUM STRENGTH OF 30MPa AT 28 DAYS.
- ALL CONSTRUCTION TRAFFIC TO ACCESS SITE FROM HUNTMAR DRIVE.
- FOR GEOTECHNICAL REPORT SEE GEOTECHNICAL INVESTIGATION BY PATERSON GROUP, REPORT PG5006-1 REVISION 2 DATED DECEMBER 1, 2020. EXISTING MONITORING WELLS DOCUMENTED IN SECTION 4.1 OF THE GEOTECHNICAL INVESTIGATION WILL BE DECOMMISSIONED PER CODE REQUIREMENTS PRIOR TO COMMENCING CONSTRUCTION.
- CONTRACTOR TO PROTECT EXISTING INFRASTRUCTURE AND PROPERTY SUCH AS TREES, PARKING METERS, SIDEWALKS, CURBS, ASPHALT, AND STREET SIGNS FROM DAMAGE DURING CONSTRUCTION. CONTRACTOR TO PAY THE COST TO REINSTATE OR REPLACE ANY DAMAGED INFRASTRUCTURE OR PROPERTY TO THE SATISFACTION OF THE CITY.
- THE POSITION OF POLE LINES, CONDUITS, WATERMAIN, SEWERS, AND OTHER UNDERGROUND AND ABOVEGROUND UTILITIES AND STRUCTURES ARE NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK THE CONTRACTOR SHALL INFORM ITSELF OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, SHALL PROTECT ALL UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR DAMAGE TO THEM.
- CONTRACTOR TO SUPPLY SUITABLE FILL MATERIAL WHERE REQUIRED TO ROUGH GRADE THE SITE. ALL IMPORTED FILL MATERIAL TO BE CERTIFIED AS ACCEPTABLE BY THE GEOTECHNICAL ENGINEER.
- CONTRACTOR TO HAUL EXCESS MATERIAL OFFSITE AS NECESSARY TO GRADE SITE TO MEET THE PROPOSED GRADES. ALL EXCESS MATERIAL TO BE HAULLED OFFSITE AND DISPOSED OF AT AN APPROVED DUMP SITE. SHOULD THE CONTRACTOR DISCOVER ANY HAZARDOUS MATERIAL, CONTRACTOR IS TO NOTIFY ENGINEER. ENGINEER TO DETERMINE APPROPRIATE DISPOSAL METHOD/LOCATION.
- FILL MATERIAL WITHIN THE PARKING LOT AND BUILDING PAD AREAS, AND SUPPORTING BUILDING FOUNDATIONS SHALL BE COMPACTED TO 98% STANDARD MODIFIED PROCTOR DENSITY AND TO THE SATISFACTION OF THE GEOTECHNICAL ENGINEER.
- ALL COMPACTION METHODS TO BE PERFORMED TO THE SATISFACTION OF THE GEOTECHNICAL ENGINEER TO INCLUDE BUT NOT BE LIMITED TO THE THICKNESS OF LIFTS, AND COMPACTION EQUIPMENT USED.
- ALL DISTURBED BOULEVARDS TO BE REINSTATED WITH SOD ON 100mm TOPSOIL.
- UTILITY DUCTS TO BE INSTALLED PRIOR TO ROAD BASE CONSTRUCTION.
- CLAY DIKES TO BE INSTALLED WHERE INDICATED ON THE DRAWINGS OR AS APPROVED AND DIRECTED BY THE GEOTECHNICAL ENGINEER ALL IN ACCORDANCE WITH CITY OF OTTAWA STANDARDS AND SPECIFICATIONS.
- BACKWATER VALES, PER CITY STANDARDS S14, S14.1 AND S14.2 RE TO BE INSTALLED FOR ALL STORM AND SANITARY SERVICE CONNECTIONS.
- EXISTING STREET LIGHT (TYPICAL) L5 MIN 1.5M FROM FACE OF CURB.

2.0 SANITARY

- ALL SANITARY SEWER MAINS TO BE CSA CERTIFIED, BELL AND SPIGOT TYPE. ONLY FACTORY FITTINGS TO BE USED. SEWER TO BE INSTALLED AS PER OPSD 100.01. SANITARY SEWER MATERIALS TO BE: 375mmØ AND SMALLER - PVC DR 35.
- ALL SANITARY MAINTENANCE HOLES TO BE 1.2m DIAMETER AS PER CITY OF OTTAWA STANDARDS COMPLETE WITH BENCHING, RINGS, FRAME AND COVER, DROP PIPES AND LANDINGS WHERE NEEDED.
- SANITARY MANHOLE COVERS TO BE CITY OF OTTAWA STD. S25 (MOD. OPSD. 401.020). SANITARY MANHOLE COVER TO BE CLOSED COVER TYPE, AS PER CITY STANDARD S24.
- SANITARY SEWER LEAKAGE TEST AND CCTV INSPECTION SHALL BE COMPLETED AS PER CITY SPECIFICATIONS PRIOR TO INSTALLATION OF BASE COURSE ASPHALT.
- ANY SANITARY SEWER WITH LESS THAN 2.0m COVER REQUIRES THERMAL INSULATION AS PER CITY OF OTTAWA STANDARD W22, OR AS APPROVED BY THE ENGINEER.
- CONNECTION TO THE EXISTING SANITARY SEWER TO BE INCLUDED IN THE COST FOR SANITARY SEWER INSTALLATION. THIS INCLUDES REINSTATEMENT OF ROAD CUTS TO CITY STANDARDS.
- ALL SANITARY CONNECTION TO INCLUDE BACKWATER VALVE TYPE 1 PER CITY STANDARD S14.

3.0 STORM

- ALL STORM SEWERS TO BE CSA CERTIFIED, BELL AND SPIGOT TYPE. ALL STORM SEWERS TO BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS. ONLY FACTORY FITTINGS TO BE USED. STORM SEWER MATERIALS TO BE: 375mmØ AND SMALLER - PVC DR 35 - 400mmØ AND LARGER - 100-D REINFORCED CONCRETE, UNLESS NOTED OTHERWISE.
- ALL STORM MAINTENANCE HOLES TO BE SIZED IN ACCORDANCE WITH THE PLANS AND AS PER CITY OF OTTAWA STANDARDS COMPLETE WITH BENCHING, RINGS, AND FRAME AND COVER.
- STORM MH COVERS TO BE OPEN TYPE, AS PER CITY STANDARD S24, FRAMES TO BE PER CITY OF OTTAWA STD. S25. CONTRACTOR TO INSTALL FILTER FABRIC UNDER STORM MH COVER UNTIL SCOURING IS COMPLETE.
- STORM MAINTENANCE HOLES TO BE OPSD, SIZE AS SPECIFIED, TAPER TOP.
- ALL CATCH BASINS TO BE AS PER OPSD 705.010, FRAME & FISH TYPE GRATE AS PER CITY OF OTTAWA STD. S19.1.
- ANY STORM SEWER WITH LESS THAN 2.0m COVER REQUIRES THERMAL INSULATION AS PER CITY OF OTTAWA STANDARD W22, OR AS APPROVED BY THE ENGINEER.
- CONNECTION TO THE EXISTING STORM SEWER TO BE INCLUDED IN THE COST FOR STORM SEWER INSTALLATION. THIS INCLUDES REINSTATEMENT OF ROAD CUT TO CITY STANDARDS.
- CONTRACTOR TO PROVIDE IPX-TEMPEST MHF ICDS SHOP DRAWINGS, OR EQUIVALENT, FOR ENGINEERS REVIEW PRIOR TO ORDERING ICDS.
- ALL STORM CONNECTION TO INCLUDE FOUNDATION BACKWATER VALVE TYPE 1 PER CITY STANDARD S14.
- LANDSCAPE SUBDRAIN AND APPURTENANCES TO BE INSTALLED PER CITY OF OTTAWA STANDARDS INCLUDING BUT NOT LIMITED TO S25, S30, S31.
- WATER
- ALL WATERMANS 100mmØ OR GREATER TO BE PVC DR 18, LESS THAN 100mm Ø TO BE COPPER OR APPROVED EQUAL WITH MINIMUM COVER OF 2.4m AND INSTALLED PER CITY OF OTTAWA STANDARDS. ALL DOMESTIC WATER SERVICES ARE TO BE 25mmØ.
- TRUST HOLES TO BE INSTALLED AT ALL BENDS, TEES, AND CAPS ALL AS PER OPSD 1103.01 AND 1103.02.
- CONTRACTOR TO CONDUCT PRESSURE AND LEAKAGE TESTING OF ALL WATERMANS AND DISINFECT AND CHLORINATE ALL WATERMANS TO THE SATISFACTION OF M.O.E. AND THE CITY OF OTTAWA.
- TRACER WIRE TO BE INSTALLED ALONG THE FULL LENGTH OF WATERMAIN AND ATTACHED TO EACH MAIN STOP AS PER CITY OF OTTAWA STANDARDS.
- ALL COMPONENTS OF THE WATER DISTRIBUTION SYSTEM SHALL BE CATHODICALLY PROTECTED AS PER CITY OF OTTAWA STANDARDS.
- ALL VALVES & VALVE BOXES AND CHAMBERS, HYDRANTS, AND HYDRANT VALVES AND ASSEMBLIES SHALL BE INSTALLED AS PER CITY OF OTTAWA STANDARDS.
- ANY WATERMAIN WITH LESS THAN 2.4m COVER REQUIRES THERMAL INSULATION AS PER CITY OF OTTAWA STANDARD W22, OR AS APPROVED BY THE ENGINEER, OR IN CLOSE PROXIMITY TO OPEN STRUCTURES INSULATE PER W23.
- CONTRACTOR IS RESPONSIBLE FOR ACQUIRING THE WATER PERMIT FROM THE CITY OF OTTAWA AND PAYMENT OF ANY FEES ASSOCIATED WITH SECURING THE WATER PERMIT. OWNER IS RESPONSIBLE FOR REIMBURSING THE CONTRACTOR FOR THE ACTUAL COST OF ACQUIRING THE WATER PERMIT.
- CONNECTION TO EXISTING WATERMAIN TO BE INCLUDED IN THE COST FOR THE WATERMAIN INSTALLATION. THIS COST INCLUDES REINSTATEMENT OF ROAD CUTS TO CITY STANDARDS.
- ALL WATERMAIN CROSSINGS TO BE COMPLETED AS PER CITY OF OTTAWA STANDARDS W25 AND W25.2.

4.0 WATER

- CONTRACTOR TO REINSTATE ROAD CUTS PER CITY OF OTTAWA STANDARD R-10.
- CONTRACTOR SHALL PREPARE A TRAFFIC MANAGEMENT PLAN FOR REVIEW AND APPROVAL BY THE CITY OF OTTAWA. CONTRACTOR TO MAINTAIN TRAFFIC FLOW DURING THE ENTIRE CONSTRUCTION PERIOD. MAINTENANCE OF ROAD CUTS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. PROVISION OF FLAGMEN, DETOURS AS NECESSARY, BARRICADES AND SIGNS TO THE FULL SATISFACTION OF THE ENGINEER AND ROAD AUTHORITY SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
- CONTRACTOR TO PREPARE SUBGRADE, INCLUDING PROOFROLLING, TO THE SATISFACTION OF THE GEOTECHNICAL ENGINEER PRIOR TO THE COMMENCEMENT OF PLACEMENT OF GRANULAR B MATERIAL.
- FILL TO BE PLACED AND COMPACTED PER THE GEOTECHNICAL REPORT REQUIREMENTS.
- CONTRACTOR TO SUPPLY, PLACE AND COMPACT GRANULAR B MATERIAL IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL ENGINEER. CONTRACTOR TO PROVIDE ENGINEER WITH SAMPLES OF GRANULAR B MATERIAL FOR TESTING AND CERTIFICATION FROM THE GEOTECHNICAL ENGINEER THAT THE MATERIAL MEETS THE GRADATION REQUIREMENTS SPECIFIED IN THE GEOTECHNICAL REPORT.
- GRANULAR A MATERIAL TO BE PLACED ONLY UPON APPROVAL BY THE GEOTECHNICAL ENGINEER OF GRANULAR B PLACEMENT.
- ASPHALT MATERIAL TO BE PLACED ONLY UPON APPROVAL BY THE GEOTECHNICAL ENGINEER OF GRANULAR A PLACEMENT.
- CONTRACTOR TO SUPPLY, PLACE AND COMPACT ASPHALT MATERIAL IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL ENGINEER. CONTRACTOR TO PROVIDE ENGINEER WITH SAMPLES OF ASPHALT MATERIAL FOR TESTING AND CERTIFICATION FROM THE GEOTECHNICAL ENGINEER THAT THE MATERIAL MEETS THE REQUIREMENTS SPECIFIED IN THE GEOTECHNICAL REPORT.
- CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING LINE AND GRADE IN ACCORDANCE WITH THE PLANS, AND FOR PROVIDING THE ENGINEER WITH VERIFICATION PRIOR TO PLACEMENT.
- PAVEMENT STRUCTURE (MATERIAL TYPES AND THICKNESSES) FOR HEAVY DUTY AND LIGHT DUTY AREAS TO BE AS SPECIFIED IN THE GEOTECHNICAL REPORT AND SHOWN ON THE PLANS.



2051 John Street, Suite One, Markham, Ontario L3R 5R7 T 905-968-3185


COPYRIGHT

This drawing has been prepared solely for the intended use. No reproduction or distribution for any purpose other than that authorized by IBI Group is permitted. IBI Group is not responsible for any errors or omissions. Contractors shall be responsible for all dimensions and conditions on the job, and IBI Group shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to IBI Group for general confirmation before proceeding with fabrication.

IBI Group Professional Services (Canada) Inc. is a member of the IBI Group of companies.


ISSUES		
No.	DESCRIPTION	DATE
1	ISSUED FOR SPA	2021-02-16
2	SPA SUBMISSION	2021-05-30
3	SPA SUBMISSION	2021-08-17
4	SPA SUBMISSION	2021-10-29

SEE 010 FOR NOTES, LEGEND



CONSULTANTS

Project Coordinator:
North American Development Group
Architect:
RLA Architecture
Surveyor:
Fairhall, Moffatt and Woodland Ltd.
Geotechnical:
Paterson Group
Traffic:
JD Halpenny & Assoc.
Electrical:
Hammerschlag & Joffe Inc.
Landscape:
NAK Design Strategies



LEGEND:		FAIRHALL, MOFFATT AND WOODLAND LTD. TOPOGRAPHIC LEGEND	
MHS3A	SANITARY MANHOLE STORM	■	- SURVEY MONUMENT FOUND
MHST01	MANHOLE	STB	- STANDARD IRON BAR
CB01	CATCHBAS N	SS1B	- SHORT STANDARD IRON BAR
CBMH01	CATCHBAS N MANHOLE	TB	- RON BAR
CBMH02	CATCHBAS N MANHOLE CW ICD	CP	- CONCRETE PIN
ECB01	REAR YARD "END" CATCHBASIN	BLK	- BLOCK
-----	SUBDRAIN	PIN	- PROPERTY IDENTIFIER NUMBER
-----	200mmØ SAN	CB	- CATCH BASIN
-----	300mmØ STM	MH	- MANHOLE
○	SANITARY SEWER	MH-ST	- STORM MANHOLE
○	STORM SEWER	MH-SA	- SANITARY MANHOLE
○	VALVE AND VALVE BOX	WMH	- WATER MANHOLE
○	WATERMAIN	TMH	- TRAFFIC MANHOLE
○	VERTICAL BEND LOCATION	HMH	- HYDRO MANHOLE
○	METER	FH	- FIRE HYDRANT
○	REMOTE METER	TCB	- TRAFFIC CONTROL BOX
○	NUMBER OF RISERS	WV	- WATER VALVE
		TL	- TRAFFIC LIGHT
		LS	- LAMP STANDARD
		UP	- UTILITY POLE
		BP	- BELL PEDESTAL
		MW	- MONITOR NG WELL
		○	- BOREHOLE
		○	- BOLLARD
		○	- GUY WIRE AND ANCHOR
		○	- SIGN
		○	- DECIDUOUS TREE
		○	- CURB
		○	- GASMAIN
		○	- SANITARY SEWER
		○	- STORM SEWER
		○	- WATERMAIN
		○	- UNDERGROUND BELL
		○	- UNDERGROUND HYDRO
		○	- STREET LIGHTING
		○	- ROGERS CABLE
		○	- TRAFFIC
		○	- EDGE OF TREES

STORM STRUCTURE TABLE						
NAME	RIM ELEV.	INVERT IN	INVERT IN ASBUILT	INVERT OUT	INVERT OUT ASBUILT	DESCRIPTION
MHST01	102.66	W100.961				12000 OPSD 701.010
		W100.540		99.974		
		SW 100.088				
CBMH02	102.53	101.164		101.014		12000 OPSD 701.010
CBMH03	102.64	101.300		101.240		12000 OPSD 701.010
CBMH04	102.80	101.400		101.380		12000 OPSD 701.010
CBMH05	102.85	101.540		101.520		12000 OPSD 701.010
CBMH06	102.92	101.700		101.590		12000 OPSD 701.010

WATERMAIN SCHEDULE					
Station	Description	Finished Grade	Top of Watermain	As Built Watermain	
A 0+000.00	TEE 400mmx200mm	102.51	100.51		
0+001.10	VB 200mm	102.90	100.50		
0+004.06	V-BEND 200mm	102.94	100.54		
0+004.36	V-BEND 200mm	102.94	101.09		
0+005.71	V-BEND 200mm	102.94	101.50		
0+010.01	V-BEND 200mm	102.94	100.44		
0+019.83	VB 200mm	103.04	100.64		
B 0+022.17	CAP 200mm	103.05	100.65		
C 0+000.00	TEE 400mmx200mm	103.08	100.68		
0+001.10	VB 200mm	103.13	100.73		
0+003.79	V-BEND 200mm	103.24	100.84		
0+004.09	V-BEND 200mm	103.26	101.14		
0+005.75	V-BEND 200mm	103.11	101.14		
0+007.05	V-BEND 200mm	103.07	100.20		
0+009.71	V-BEND 200mm	102.95	100.20		
0+010.01	V-BEND 200mm	102.94	100.54		
0+019.83	VB 200mm	103.13	100.73		
D 0+022.17	CAP 200mm	103.01	100.61		

PROJECT

21/35 HUNTMAR DRIVE

PROJECT NO: 127134

DRAWN BY: EH CHECKED BY: DGY

PROJECT MGR: DGY APPROVED BY: DGY

SHEET TITLE

GENERAL NOTES, LEGEND AND TABLES

SHEET NUMBER: C-010 ISSUE: 1

CITY FILE No. D07-12-21-0035

APPENDIX C

- C-400 Sanitary Tributary Area Plan
- Sanitary sewer design sheet




IBI GROUP
 400-333 Preston Street
 Ottawa, Ontario K1S 5N4 Canada
 tel 613 225 1311 fax 613 225 9868
 bigroup.com

SANITARY SEWER DESIGN SHEET

21 Huntmar Rd
 CITY OF OTTAWA
 North American Group

LOCATION				RESIDENTIAL						ICI AREAS						INFILTRATION ALLOWANCE			FIXED FLOW (L/s)		TOTAL FLOW (L/s)	PROPOSED SEWER DESIGN											
STREET	AREA ID	FROM MH	TO MH	AREA w/ Units (Ha)	UNIT TYPES			AREA w/o Units (Ha)	POPULATION		RES PEAK FACTOR	PEAK FLOW (L/s)	INSTITUTIONAL		AREA (Ha)		INDUSTRIAL		ICI PEAK FACTOR	PEAK FLOW (L/s)	AREA (Ha)		FLOW (L/s)	IND	CUM	TOTAL FLOW (L/s)	CAPACITY (L/s)	LENGTH (m)	DIA (mm)	SLOPE (%)	VELOCITY (full) (m/s)	AVAILABLE CAPACITY	
					1B	2B	3B		APT	IND			CUM	IND	CUM	IND	CUM	IND			CUM	IND										CUM	L/s
OUTLET TO HUNTMAR RD																																	
	1	BLDG A& B	2	1.96	149	195		618.1	618.1	3.34	6.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1.00	0.00	1.56	1.6	0.51	0.00	0.00	7.21	87.74	1.64	250	2.00	1.731	80.53	91.79%
		2	1					0.0	618.1	3.34	6.69	0.00	0.00	0.00	0.00	0.00	0.00	1.00	0.00	0.00	1.6	0.51	0.00	0.00	7.21	87.74	18.22	250	2.00	1.731	80.53	91.79%	
				1.56	149	0		618.1																									

Design Parameters:		Notes:		Designed: R.M.		No. 1.		Revision: Servicing Brief - Submission No. 1		Date: 2021-02-04	
Residential		ICI Areas		1. Mannings coefficient (n) 0.013		2. Demand (per capita) 280 L/day		3. Infiltration allowance 0.33 L/s/ha		4. Residential Peaking Factor Harmon Formula $1+(14/(4+(P/1000)^0.5))0.8$ where K 0.8 Correction Factor	
3B	2.8 p/p/u	INST	28,000 L/ha/day	5. Commercial and Institutional Peak Factors based on total area, 1.5 if greater than 20% otherwise 1.0							
2B	2.1 p/p/u	COM	28,000 L/ha/day								
1B	1.4 p/p/u	IND	35,000 L/ha/day								
APT	1.8 p/p/u	MOE Chart									
Other	60 p/p/ha	17000 L/ha/day									
Dwg. Reference: 127134-400		File Reference: 127134.6.4.4		Date: 2021-02-04		Sheet No: 1 of 1					



COPYRIGHT
This drawing has been prepared solely for the intended use. No reproduction or distribution for any purpose other than authorized by IBI Group is permitted. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and IBI Group shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to IBI Group for general confirmation before proceeding with fabrication.

IBI Group Professional Services (Canada) Inc.
is a member of the IBI Group of companies.

ISSUES

No.	DESCRIPTION	DATE
1	ISSUED FOR SPA	2021-02-16
2	SPA SUBMISSION	2021-05-30
3	SPA SUBMISSION	2021-08-17
4	SPA SUBMISSION	2021-10-29

SEE 010 FOR NOTES, LEGEND



CONSULTANTS

Project Coordinator:
North American Development Group

Architect:
RLA Architecture



Surveyor:
Fairhall, Moffatt and Woodland Ltd.

Geotechnical:
Paterson Group

Traffic:
JD Halpenny & Assoc.

Electrical:
Hammerschlag & Joffe Inc

Landscape:
NAK Design Strategies



IBI GROUP
Suite 400 - 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 / 613 241 3300 fax 613 225 9668
ibigroup.com

PROJECT
21/35 HUNTMAR DRIVE

PROJECT NO:
127134


DRAWN BY: EH
PROJECT MGR: DGY

CHECKED BY: DGY
APPROVED BY: DGY

SHEET TITLE
SANITARY DRAINAGE PLAN

SHEET NUMBER C-400 **ISSUE** 1

CITY PLAN No. 18424



LEGEND :

01	AREA NUMBER
1.56 619.2	POPULATION
	AREA IN HECTARES

File Location: \\127134_21_huntmar\7_0_Production\02_Design\04_Civil\Sheets\C-400.dwg
 Last Saved: October 28, 2021, by: Elenie
 Plotted: Friday, October 29, 2021 8:32:53 AM by: Eric Henne
 City File No. D07-12-21-0035

APPENDIX D

- C-500 Storm Tributary Area Plan
- Storm sewer design sheets
- Modified Rational Method design sheets



IBI GROUP
400-330 Preston Street
Ottawa, Ontario K1S 0N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

STORM SEWER DESIGN SHEET

21 Huntmar Rd
City of Ottawa
North American Group

STREET	LOCATION				AREA (Ha)							RATIONAL DESIGN FLOW													SEWER DATA												
	AREA ID	FROM	TO		C 0.20	C 0.30	C 0.55	C 0.83	C 0.85	C 0.87	C 0.90	IND 2.78AC	CUM 2.78AC	INLET (min)	TIME IN PIPE	TOTAL (min)	i (2) (mm/hr)	i (5) (mm/hr)	i (10) (mm/hr)	i (100) (mm/hr)	2yr PEAK FLOW (L/s)	5yr PEAK FLOW (L/s)	10yr PEAK FLOW (L/s)	100yr PEAK FLOW (L/s)	FIXED FLOW (L/s)	DESIGN FLOW (L/s)	CAPACITY (L/s)	LENGTH (m)	PIPE SIZE (mm)			SLOPE (%)	VELOCITY (m/s)	AVAIL CAP (2yr)			
																													DIA	W	H			(L/s)	(%)		
OUTLET TO HUNTMAR RD																																					
	Landscape 6a 6b 4b	CBMH6	cell		0.026	0.032						0.07	0.07	10.00	0.08	10.08	76.81	104.19	122.14	178.56	5.42	7.36	8.62	12.61		5.42	58.82	4.08	300				0.34	0.806	53.40	90.78%	
	Landscape 4a	Cell	CBMH5		0.043							0.04	0.11	10.08	0.06	10.15	76.48	103.75	121.62	177.79	8.14	11.05	12.95	18.93		8.14	59.68	3.17	300			0.35	0.818	51.54	86.36%		
	Landscape 2c	CBMH5	CBMH4		0.041							0.03	0.14	10.15	0.70	10.85	76.24	103.41	121.22	177.21	10.72	14.55	17.05	24.93		10.72	58.82	33.72	300			0.34	0.806	48.10	81.77%		
	Landscape 2b	CBMH4	Cell		0.038							0.03	0.17	10.85	0.10	10.95	73.70	99.93	117.12	171.18	12.70	17.22	20.19	29.50		12.70	60.53	5.00	300			0.36	0.839	47.83	79.01%		
	Landscape 2a	Cell	CBMH3		0.032							0.03	0.20	10.95	0.20	11.14	73.35	99.45	116.55	170.35	14.60	19.79	23.20	33.91		14.60	58.82	9.55	300			0.34	0.806	44.22	75.18%		
	Landscape 1d	CBMH3	Cell		0.050							0.04	0.24	11.14	0.22	11.36	72.68	98.52	115.45	168.74	17.50	23.72	27.80	40.62		17.50	60.53	10.85	300			0.36	0.830	43.03	71.09%		
	Landscape 1c 1b	Cell	CBMH2		0.098							0.08	0.32	11.36	0.18	11.54	71.94	97.51	114.27	167.00	23.20	31.45	36.85	53.85		23.20	61.36	9.03	300			0.37	0.841	38.16	62.19%		
	Landscape 1a	CBMH2	MH1		0.036							0.03	0.35	11.54	0.06	11.60	71.36	96.70	113.32	165.60	25.15	34.09	39.95	58.38		25.15	101.89	5.21	300			1.02	1.996	76.73	75.31%		
	roofs 1 and 2	BLDG	MH1								0.529	1.32	1.32	10.00	0.06	10.06	76.81	104.19	122.14	178.56	101.66	137.91	161.66	236.33		101.66	151.66	7.46	300			2.26	2.078	50.00	32.97%		
	deck	cistem	MH1								0.507	1.27	1.27	10.00	0.07	10.07	76.81	104.19	122.14	178.56	97.43	132.17	154.94	226.50		97.43	142.67	8.59	300			2.00	1.955	45.24	31.71%		
		MH1	EX								0.00	2.94	11.54	0.11	11.65	71.36	96.70	113.32	165.60	210.11	284.75	333.68	487.63		210.11	252.13	14.73	375			1.90	2.211	42.02	16.66%			
					0.000	0.364	0.032	0.000	0.000	0.000	1.036		2.94	Total A																							
												1.43	Avg. C																								
												0.74																									
Definitions:				Notes:													Designed: RM		Revision			Date															
Q 2.78CIA, where				1. Mannings coefficient (n)													Checked: DY		1. Servicing Brief - Submission No. 1			2021-02-04															
Q Peak Flow in Litres per Second (L/s)																			2. Servicing Brief - Submission No. 2			2021-06-26															
A Area in Hectares (Ha)																			3. Servicing Brief - Submission No. 3			2021-10-28															
i Rainfall Intensity in milimeters per hour (mm/hr)																																					
i 732.951 / (TC+6.199)^0.810																																					
i 998.071 / (TC+6.053)^0.814																																					
i 1174.184 / (TC+6.014)^0.816																																					
i 1735.688 / (TC+6.014)^0.820																																					
																	Dwg. Reference: 125600-500		File Reference: 127154.6.4.4			Date: 2021-02-04		Sheet No: 1 of 1													



COPYRIGHT
This drawing has been prepared solely for the intended use, and any reproduction or distribution for any purpose other than that authorized by IBI Group is forbidden. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and IBI Group shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to IBI Group for general confirmation before proceeding with fabrication.

IBI Group Professional Services (Canada) Inc.
is a member of the IBI Group of companies.



ISSUES	No.	DESCRIPTION	DATE
1	1	ISSUED FOR SPA	2021-02-16
2	2	SPA SUBMISSION	2021-05-30
3	3	SPA SUBMISSION	2021-08-17
4	4	SPA SUBMISSION	2021-10-29

SEE 010 FOR NOTES, LEGEND



CONSULTANTS

Project Coordinator:
North American Development Group
Architect:
RLA Architecture
Surveyor:
Fairhall, Moffatt and Woodland Ltd.
Geotechnical:
Paterson Group
Traffic:
JD Halpenny & Assoc.
Electrical:
Hammerschlag & Joffe Inc
Landscape:
NAK Design Strategies



IBI GROUP
Suite 400 - 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 / 613 241 3300 fax 613 225 9868
ibigroup.com

PROJECT
21/35 HUNTMAR DRIVE


PROJECT NO:
127134

DRAWN BY: EH	CHECKED BY: DGY
PROJECT MGR: DGY	APPROVED BY: DGY


SHEET TITLE
STORM DRAINAGE PLAN

SHEET NUMBER C-500	ISSUE 1
------------------------------	-------------------

CITY PLAN No. 18424



LEGEND :



CITY FILE No. D07-12-21-0035
File Location: \\127134_21_huntmar\7_0_Production\02_Design\04_Civil\Sheets\C-500.dwg
Last Saved: October 28, 2021, by: Elvienne
Plotted: Friday, October 29, 2021 8:33:09 AM by: Eric Henne



IBI GROUP
400-333 Preston Street
Ottawa, Ontario K1S 5N4 Canada
tel 613 225 1311 fax 613 225 9868
ibigroup.com

PROJECT: 21 HUNTMAR RD
DATE: 2021-06-29
FILE: 127134-6.4
REV #: 2
DESIGNED BY: R.M.
CHECKED BY: D.G.Y.

STORMWATER MANAGEMENT

Maximum Allowable Release Rate

Restricted Flowrate (based on 85l/s/Ha)

$A_{site} = 1.562$ Ha

$Q_{restricted} = 132.74$ L/s

unrestricted flow to boulevards	Area (Ha)	C (C*1.25)	100yr		5yr	
			Q (l/s)	Q (l/s)	Q (l/s)	Q (l/s)
area 1	0.0370	1	18.37	8.49		
area 2	0.0250	0.25	3.10	1.43		
Area 3	0.0570	1	28.29	13.08		
	0.1190		49.76	23.00		

$i_{100yr} = 1:100$ year Intensity = $1735.688 / (T_c + 6.014)^{0.820}$ $t_c = 10$

Maximum Allowable Release Rate ($Q_{max\ allowable} = Q_{restricted} - Q_{uncontrolled}$)

$Q_{max\ allowable} = 82.97$ L/s

Formulas and Descriptions

$i_{2yr} = 1:2$ year Intensity = $732.951 / (T_c + 6.199)^{0.810}$

$i_{5yr} = 1:5$ year Intensity = $998.071 / (T_c + 6.053)^{0.81}$

$i_{100yr} = 1:100$ year Intensity = $1735.688 / (T_c + 6.014)^{0.820}$

T_c = Time of Concentration (min)

C = Average Runoff Coefficient

A = Area (Ha)

Q = Flow = $2.78CIA$ (L/s)

MODIFIED RATIONAL METHOD (100-Year, 5-Year & 2-Year Ponding)

Drainage Area		Roof Area 1A			
Area (Ha)	0.044				
C =	1.00	Restricted Flow Q_r (L/s) = 2.520			
100-Year Ponding					
T_c Variable (min)	i_{100yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{100yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 100yr (m^3)
33	86.03	10.52	2.52	8.00	15.85
38	77.93	9.53	2.52	7.01	15.99
43	71.35	8.73	2.52	6.21	16.02
48	65.89	8.06	2.52	5.54	15.95
58	57.32	7.01	2.52	4.49	15.63

Storage (m^3)				
Overflow	Required	Surface	Sub-surface	Balance
0.00	16.02	17.60	0	0.00

Drainage Area		Roof Area 1A			
Area (Ha)	0.044				
C =	0.90	Restricted Flow Q_r (L/s) = 2.520			
5-Year Ponding					
T_c Variable (min)	i_{5yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{5yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 5yr (m^3)
11	99.19	10.92	2.52	8.40	5.54
16	80.46	8.86	2.52	6.34	6.08
21	68.13	7.50	2.52	4.98	6.28
26	59.35	6.53	2.52	4.01	6.26
31	52.74	5.81	2.52	3.29	6.11

Storage (m^3)				
Overflow	Required	Surface	Sub-surface	Balance
0.00	6.28	17.60	0	0.00

Drainage Area		Roof Area 1A			
Area (Ha)	0.044				
C =	0.90	Restricted Flow Q_r (L/s) = 2.520			
2-Year Ponding					
T_c Variable (min)	i_{2yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{2yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 2yr (m^3)
8	85.46	9.41	2.52	6.89	3.31
13	66.93	7.37	2.52	4.85	3.78
18	55.49	6.11	2.52	3.59	3.88
23	47.66	5.25	2.52	2.73	3.76
33	37.54	4.13	2.52	1.61	3.19

Storage (m^3)				
Overflow	Required	Surface	Sub-surface	Balance
0.00	3.88	17.60	0	0.00

Drainage Area		Roof Area 1B			
Area (Ha)	0.041	Restricted Flow Q_r (L/s)= 2.520			
C =	1.00				
100-Year Ponding					
T_c Variable (min)	i_{100yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{100yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 100yr (m^3)
31	89.83	10.24	2.52	7.72	14.36
36	80.96	9.23	2.52	6.71	14.49
41	73.83	8.42	2.52	5.90	14.50
46	67.96	7.75	2.52	5.23	14.42
56	58.83	6.71	2.52	4.19	14.06

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	14.50	16.40	0	0.00	

Drainage Area		Roof Area 1B			
Area (Ha)	0.041	Restricted Flow Q_r (L/s)= 2.520			
C =	0.90				
5-Year Ponding					
T_c Variable (min)	i_{5yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{5yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 5yr (m^3)
14	86.93	8.92	2.52	6.40	5.37
19	72.53	7.44	2.52	4.92	5.61
24	62.54	6.42	2.52	3.90	5.61
29	55.18	5.66	2.52	3.14	5.46
34	49.50	5.08	2.52	2.56	5.22

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	5.61	16.40	0	0.00	

Drainage Area		Roof Area 1B			
Area (Ha)	0.041	Restricted Flow Q_r (L/s)= 2.520			
C =	0.90				
2-Year Ponding					
T_c Variable (min)	i_{2yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{2yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 2yr (m^3)
8	85.46	8.77	2.52	6.25	3.00
13	66.93	6.87	2.52	4.35	3.39
18	55.49	5.69	2.52	3.17	3.43
23	47.66	4.89	2.52	2.37	3.27
33	37.54	3.85	2.52	1.33	2.64

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	3.43	16.40	0	0.00	

Drainage Area		Roof Area 1C			
Area (Ha)	0.030	Restricted Flow Q_r (L/s)= 1.890			
C =	1.00				
100-Year Ponding					
T_c Variable (min)	i_{100yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{100yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 100yr (m^3)
30	91.87	7.66	1.89	5.77	10.39
35	82.58	6.89	1.89	5.00	10.49
40	75.15	6.27	1.89	4.38	10.51
45	69.05	5.76	1.89	3.87	10.45
55	59.62	4.97	1.89	3.08	10.17

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	10.51	12.00	0	0.00	

Drainage Area		Roof Area 1C			
Area (Ha)	0.030	Restricted Flow Q_r (L/s)= 1.890			
C =	0.90				
5-Year Ponding					
T_c Variable (min)	i_{5yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{5yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 5yr (m^3)
10	104.19	7.82	1.89	5.93	3.56
15	83.56	6.27	1.89	4.38	3.94
20	70.25	5.27	1.89	3.38	4.06
25	60.90	4.57	1.89	2.68	4.02
30	53.93	4.05	1.89	2.16	3.88

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	4.06	12.00	0	0.00	

Drainage Area		Roof Area 1C			
Area (Ha)	0.030	Restricted Flow Q_r (L/s)= 1.890			
C =	0.90				
2-Year Ponding					
T_c Variable (min)	i_{2yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{2yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 2yr (m^3)
6	96.64	7.25	1.89	5.36	1.93
11	73.17	5.49	1.89	3.60	2.38
16	59.50	4.47	1.89	2.58	2.47
21	50.48	3.79	1.89	1.90	2.39
31	39.17	2.94	1.89	1.05	1.95

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	2.47	12.00	0	0.00	

Drainage Area		1D			
Area (Ha)	0.058	Restricted Flow Q_r (L/s)= 2.520			
C =	1.00				
100-Year Ponding					
T_c Variable (min)	i_{100yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{100yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 100yr (m^3)
43	71.35	11.50	2.52	8.98	23.18
48	65.89	10.62	2.52	8.10	23.34
53	61.28	9.88	2.52	7.36	23.41
58	57.32	9.24	2.52	6.72	23.40
68	50.89	8.21	2.52	5.69	23.20

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	23.41	23.49	0	0.00	

Drainage Area		1D			
Area (Ha)	0.058	Restricted Flow Q_r (L/s)= 2.520			
C =	0.90				
5-Year Ponding					
T_c Variable (min)	i_{5yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{5yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 5yr (m^3)
19	72.53	10.52	2.52	8.00	9.13
24	62.54	9.08	2.52	6.56	9.44
29	55.18	8.01	2.52	5.49	9.55
34	49.50	7.18	2.52	4.66	9.51
39	44.98	6.53	2.52	4.01	9.38

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	9.55	23.49	0	0.00	

Drainage Area		1D			
Area (Ha)	0.058	Restricted Flow Q_r (L/s)= 2.520			
C =	0.90				
2-Year Ponding					
T_c Variable (min)	i_{2yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{2yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 2yr (m^3)
14	64.23	9.32	2.52	6.80	5.71
19	53.70	7.79	2.52	5.27	6.01
24	46.37	6.73	2.52	4.21	6.06
29	40.96	5.94	2.52	3.42	5.96
39	33.45	4.85	2.52	2.33	5.46

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	6.06	23.49	0	0.00	

Drainage Area		Roof Area 1E			
Area (Ha)	0.061	Restricted Flow Q_r (L/s)= 3.150			
C =	1.00				
100-Year Ponding					
T_c Variable (min)	i_{100yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{100yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 100yr (m^3)
35	82.58	14.00	3.15	10.85	22.79
40	75.15	12.74	3.15	9.59	23.02
45	69.05	11.71	3.15	8.56	23.11
50	63.95	10.85	3.15	7.70	23.09
60	55.89	9.48	3.15	6.33	22.78

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	23.11	24.40	0	0.00	

Drainage Area		Roof Area 1E			
Area (Ha)	0.061	Restricted Flow Q_r (L/s)= 3.150			
C =	0.90				
5-Year Ponding					
T_c Variable (min)	i_{5yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{5yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 5yr (m^3)
15	83.56	12.75	3.15	9.60	8.64
20	70.25	10.72	3.15	7.57	9.09
25	60.90	9.29	3.15	6.14	9.22
30	53.93	8.23	3.15	5.08	9.14
35	48.52	7.40	3.15	4.25	8.94

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	9.22	24.40	0	0.00	

Drainage Area		Roof Area 1E			
Area (Ha)	0.061	Restricted Flow Q_r (L/s)= 3.150			
C =	0.90				
2-Year Ponding					
T_c Variable (min)	i_{2yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{2yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 2yr (m^3)
9	80.87	12.34	3.15	9.19	4.96
14	64.23	9.80	3.15	6.65	5.59
19	53.70	8.20	3.15	5.05	5.75
24	46.37	7.08	3.15	3.93	5.66
34	36.78	5.61	3.15	2.46	5.03

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	5.75	24.40	0	0.00	

Drainage Area		Roof Area 2A			
Area (Ha)	0.044	Restricted Flow Q_r (L/s)= 2.520			
C =	1.00				
100-Year Ponding					
T_c Variable (min)	i_{100yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{100yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 100yr (m^3)
30	91.87	11.24	2.52	8.72	15.69
35	82.58	10.10	2.52	7.58	15.92
40	75.15	9.19	2.52	6.67	16.01
45	69.05	8.45	2.52	5.93	16.00
55	59.62	7.29	2.52	4.77	15.75

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	16.01	17.60	0	0.00	

Drainage Area		Roof Area 2A			
Area (Ha)	0.044	Restricted Flow Q_r (L/s)= 2.520			
C =	0.90				
5-Year Ponding					
T_c Variable (min)	i_{5yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{5yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 5yr (m^3)
14	86.93	9.57	2.52	7.05	5.92
19	72.53	7.98	2.52	5.46	6.23
24	62.54	6.88	2.52	4.36	6.29
29	55.18	6.07	2.52	3.55	6.18
34	49.50	5.45	2.52	2.93	5.98

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	6.29	17.60	0	0.00	

Drainage Area		Roof Area 2A			
Area (Ha)	0.044	Restricted Flow Q_r (L/s)= 2.520			
C =	0.90				
2-Year Ponding					
T_c Variable (min)	i_{2yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{2yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 2yr (m^3)
9	80.87	8.90	2.52	6.38	3.45
14	64.23	7.07	2.52	4.55	3.82
19	53.70	5.91	2.52	3.39	3.87
24	46.37	5.11	2.52	2.59	3.72
34	36.78	4.05	2.52	1.53	3.12

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	3.87	17.60	0	0.00	

Drainage Area		Roof Area 2B			
Area (Ha)	0.078	Restricted Flow Q_r (L/s)= 3.150			
C =	1.00				
100-Year Ponding					
T_c Variable (min)	i_{100yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{100yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 100yr (m^3)
50	63.95	13.87	3.15	10.72	32.15
55	59.62	12.93	3.15	9.78	32.27
60	55.89	12.12	3.15	8.97	32.29
65	52.65	11.42	3.15	8.27	32.24
75	47.26	10.25	3.15	7.10	31.94

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	32.29	33.15	0	0.00	

Drainage Area		Roof Area 2B			
Area (Ha)	0.078	Restricted Flow Q_r (L/s)= 3.150			
C =	0.90				
5-Year Ponding					
T_c Variable (min)	i_{5yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{5yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 5yr (m^3)
24	62.54	12.21	3.15	9.06	13.04
29	55.18	10.77	3.15	7.62	13.26
34	49.50	9.66	3.15	6.51	13.28
39	44.98	8.78	3.15	5.63	13.17
44	41.29	8.06	3.15	4.91	12.96

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	13.28	33.15	0	0.00	

Drainage Area		Roof Area 2B			
Area (Ha)	0.078	Restricted Flow Q_r (L/s)= 3.150			
C =	0.90				
2-Year Ponding					
T_c Variable (min)	i_{2yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{2yr}A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 2yr (m^3)
14	64.23	12.54	3.15	9.39	7.88
19	53.70	10.48	3.15	7.33	8.36
24	46.37	9.05	3.15	5.90	8.50
29	40.96	7.99	3.15	4.84	8.43
39	33.45	6.53	3.15	3.38	7.91

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	8.50	33.15	0	0.00	

Drainage Area		Roof Area 2C			
Area (Ha)	0.029	Restricted Flow Q _r (L/s)= 1.890			
C =	1.00				
100-Year Ponding					
T _c Variable (min)	i _{100yr} (mm/hour)	Peak Flow Q _p =2.78xCI _{100yr} A (L/s)	Q _r (L/s)	Q _p -Q _r (L/s)	Volume 100yr (m ³)
25	103.85	8.37	1.89	6.48	9.72
30	91.87	7.41	1.89	5.52	9.93
35	82.58	6.66	1.89	4.77	10.01
40	75.15	6.06	1.89	4.17	10.00
50	63.95	5.16	1.89	3.27	9.80

Storage (m ³)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	10.01	11.60	0	0.00	

Drainage Area		Roof Area 2C			
Area (Ha)	0.029	Restricted Flow Q _r (L/s)= 1.890			
C =	0.90				
5-Year Ponding					
T _c Variable (min)	i _{5yr} (mm/hour)	Peak Flow Q _p =2.78xCI _{5yr} A (L/s)	Q _r (L/s)	Q _p -Q _r (L/s)	Volume 5yr (m ³)
9	109.79	7.97	1.89	6.08	3.28
14	86.93	6.31	1.89	4.42	3.71
19	72.53	5.26	1.89	3.37	3.84
24	62.54	4.54	1.89	2.65	3.81
29	55.18	4.00	1.89	2.11	3.68

Storage (m ³)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	3.84	11.60	0	0.00	

Drainage Area		Roof Area 2C			
Area (Ha)	0.029	Restricted Flow Q _r (L/s)= 1.890			
C =	0.90				
2-Year Ponding					
T _c Variable (min)	i _{2yr} (mm/hour)	Peak Flow Q _p =2.78xCI _{2yr} A (L/s)	Q _r (L/s)	Q _p -Q _r (L/s)	Volume 2yr (m ³)
5	103.57	7.51	1.89	5.62	1.69
10	76.81	5.57	1.89	3.68	2.21
15	61.77	4.48	1.89	2.59	2.33
20	52.03	3.78	1.89	1.89	2.26
30	40.04	2.91	1.89	1.02	1.83

Storage (m ³)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	2.33	11.60	0	0.00	

Drainage Area		Roof Area 2D			
Area (Ha)	0.057	Restricted Flow Q _r (L/s)= 2.520			
C =	1.00				
100-Year Ponding					
T _c Variable (min)	i _{100yr} (mm/hour)	Peak Flow Q _p =2.78xCI _{100yr} A (L/s)	Q _r (L/s)	Q _p -Q _r (L/s)	Volume 100yr (m ³)
45	69.05	10.94	2.52	8.42	22.74
50	63.95	10.13	2.52	7.61	22.84
55	59.62	9.45	2.52	6.93	22.86
60	55.89	8.86	2.52	6.34	22.81
70	49.79	7.89	2.52	5.37	22.55

Storage (m ³)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	22.86	23.09	0	0.00	

Drainage Area		Roof Area 2D			
Area (Ha)	0.057	Restricted Flow Q _r (L/s)= 2.520			
C =	0.90				
5-Year Ponding					
T _c Variable (min)	i _{5yr} (mm/hour)	Peak Flow Q _p =2.78xCI _{5yr} A (L/s)	Q _r (L/s)	Q _p -Q _r (L/s)	Volume 5yr (m ³)
19	72.53	10.34	2.52	7.82	8.92
24	62.54	8.92	2.52	6.40	9.21
29	55.18	7.87	2.52	5.35	9.31
34	49.50	7.06	2.52	4.54	9.26
39	44.98	6.41	2.52	3.89	9.11

Storage (m ³)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	9.31	23.09	0	0.00	

Drainage Area		Roof Area 2D			
Area (Ha)	0.057	Restricted Flow Q _r (L/s)= 2.520			
C =	0.90				
2-Year Ponding					
T _c Variable (min)	i _{2yr} (mm/hour)	Peak Flow Q _p =2.78xCI _{2yr} A (L/s)	Q _r (L/s)	Q _p -Q _r (L/s)	Volume 2yr (m ³)
14	64.23	9.16	2.52	6.64	5.58
19	53.70	7.66	2.52	5.14	5.86
24	46.37	6.61	2.52	4.09	5.89
29	40.96	5.84	2.52	3.32	5.78
39	33.45	4.77	2.52	2.25	5.27

Storage (m ³)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	5.89	23.09	0	0.00	

Drainage Area		Roof Area 2E			
Area (Ha)	0.030	Restricted Flow Q _r (L/s)= 1.890			
C =	1.00				
100-Year Ponding					
T _c Variable (min)	i _{100yr} (mm/hour)	Peak Flow Q _p =2.78xCI _{100yr} A (L/s)	Q _r (L/s)	Q _p -Q _r (L/s)	Volume 100yr (m ³)
30	91.87	7.66	1.89	5.77	10.39
35	82.58	6.89	1.89	5.00	10.49
40	75.15	6.27	1.89	4.38	10.51
45	69.05	5.76	1.89	3.87	10.45
55	59.62	4.97	1.89	3.08	10.17

Storage (m ³)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	10.51	12.00	0	0.00	

Drainage Area		Roof Area 2E			
Area (Ha)	0.030	Restricted Flow Q _r (L/s)= 1.890			
C =	0.90				
5-Year Ponding					
T _c Variable (min)	i _{5yr} (mm/hour)	Peak Flow Q _p =2.78xCI _{5yr} A (L/s)	Q _r (L/s)	Q _p -Q _r (L/s)	Volume 5yr (m ³)
9	109.79	8.24	1.89	6.35	3.43
14	86.93	6.53	1.89	4.64	3.89
19	72.53	5.44	1.89	3.55	4.05
24	62.54	4.69	1.89	2.80	4.04
29	55.18	4.14	1.89	2.25	3.92

Storage (m ³)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	4.05	12.00	0	0.00	

Drainage Area		Roof Area 2E			
Area (Ha)	0.030	Restricted Flow Q _r (L/s)= 1.890			
C =	0.90				
2-Year Ponding					
T _c Variable (min)	i _{2yr} (mm/hour)	Peak Flow Q _p =2.78xCI _{2yr} A (L/s)	Q _r (L/s)	Q _p -Q _r (L/s)	Volume 2yr (m ³)
5	103.57	7.77	1.89	5.88	1.77
10	76.81	5.76	1.89	3.87	2.32
15	61.77	4.64	1.89	2.75	2.47
20	52.03	3.91	1.89	2.02	2.42
30	40.04	3.01	1.89	1.12	2.01

Storage (m ³)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	2.47	12.00	0	0.00	

Drainage Area		Roof Area 2F			
Area (Ha)	0.058	ICD Size (L/s)=			
C =	1.00	Restricted Flow Q_r (L/s)= 3.150			
100-Year Ponding					
T_c Variable (min)	i_{100yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{100yr} A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 100yr (m^3)
35	82.58	13.31	3.15	10.16	21.35
40	75.15	12.12	3.15	8.97	21.52
45	69.05	11.13	3.15	7.98	21.56
50	63.95	10.31	3.15	7.16	21.49
60	55.89	9.01	3.15	5.86	21.10

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	21.56	23.20	0	0.00	

Drainage Area		Roof Area 2F			
Area (Ha)	0.058	ICD Size (L/s)=			
C =	0.90	Restricted Flow Q_r (L/s)= 3.150			
5-Year Ponding					
T_c Variable (min)	i_{5yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{5yr} A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 5yr (m^3)
16	80.46	11.68	3.15	8.53	8.18
21	68.13	9.89	3.15	6.74	8.49
26	59.35	8.61	3.15	5.46	8.52
31	52.74	7.65	3.15	4.50	8.38
36	47.58	6.90	3.15	3.75	8.11

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	8.52	23.20	0	0.00	

Drainage Area		Roof Area 2F			
Area (Ha)	0.058	ICD Size (L/s)=			
C =	0.90	Restricted Flow Q_r (L/s)= 3.150			
2-Year Ponding					
T_c Variable (min)	i_{2yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{2yr} A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 2yr (m^3)
8	85.46	12.40	3.15	9.25	4.44
13	66.93	9.71	3.15	6.56	5.12
18	55.49	8.05	3.15	4.90	5.29
23	47.66	6.92	3.15	3.77	5.20
33	37.54	5.45	3.15	2.30	4.55

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	5.29	23.20	0	0.00	

Drainage Area		deck			
Area (Ha)	0.510	ICD Size (L/s)= 42.51			
C =	1.00	Reduced Restricted Flow Q_r (L/s)= 21.255			
100-Year Ponding					
T_c Variable (min)	i_{100yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{100yr} A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 100yr (m^3)
50	63.95	90.67	21.26	69.42	208.26
55	59.62	84.53	21.26	63.28	208.82
58	57.32	81.27	21.26	60.02	208.86
61	55.21	78.28	21.26	57.02	208.70
66	52.05	73.79	21.26	52.54	208.04

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	208.86		210	0.00	

Drainage Area		deck			
Area (Ha)	0.510	ICD Size (L/s)= 42.51			
C =	0.90	Reduced Restricted Flow Q_r (L/s)= 21.255			
5-Year Ponding					
T_c Variable (min)	i_{5yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{5yr} A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 5yr (m^3)
28	56.49	72.08	21.26	50.83	85.39
30	53.93	68.81	21.26	47.56	85.60
32	51.61	65.85	21.26	44.60	85.63
34	49.50	63.16	21.26	41.91	85.50
36	47.58	60.71	21.26	39.45	85.22

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	85.63	0.00	210	0.00	

Drainage Area		deck			
Area (Ha)	0.510	ICD Size (L/s)= 42.51			
C =	0.90	Reduced Restricted Flow Q_r (L/s)= 21.255			
2-Year Ponding					
T_c Variable (min)	i_{2yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{2yr} A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 2yr (m^3)
22	49.02	62.55	21.26	41.30	54.51
23	47.66	60.81	21.26	39.56	54.59
24	46.37	59.18	21.26	37.92	54.60
25	45.17	57.63	21.26	36.38	54.57
26	44.03	56.18	21.26	34.92	54.48

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	54.60	0.00	210	0.00	

AREA	AREA	c	ac
L1A	0.036	0.30	0.011
L1B	0.051	0.30	0.015
L1C	0.047	0.30	0.014
L1D	0.052	0.30	0.016
L2A	0.033	0.30	0.010
L2B	0.038	0.30	0.011
L2C	0.041	0.30	0.012
L4A	0.044	0.30	0.013
L4B	0.027	0.30	0.008
L6A	0.014	0.55	0.008
L6B	0.017	0.55	0.009
	0.400	0.00	0.128
Avg C		0.32	

Drainage Area		LANDSCAPE			
Area (Ha)	0.400	ICD Size (L/s)= 11.74			
C =	0.38	Reduced Restricted Flow Q_r (L/s)= 5.870			
100-Year Ponding					
T_c Variable (min)	i_{100yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{100yr} A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 100yr (m^3)
54	60.44	25.76	5.87	19.89	64.43
59	56.60	24.12	5.87	18.25	64.61
62	54.54	23.24	5.87	17.37	64.63
65	52.65	22.44	5.87	16.57	64.61
70	49.79	21.22	5.87	15.35	64.47

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	64.63		64.8	0.00	

Drainage Area		LANDSCAPE			
Area (Ha)	0.400	ICD Size (L/s)= 11.74			
C =	0.32	Reduced Restricted Flow Q_r (L/s)= 5.870			
5-Year Ponding					
T_c Variable (min)	i_{5yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{5yr} A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 5yr (m^3)
28	56.49	20.06	5.87	14.19	23.84
30	53.93	19.15	5.87	13.28	23.91
32	51.61	18.33	5.87	12.46	23.92
34	49.50	17.58	5.87	11.71	23.89
36	47.58	16.90	5.87	11.03	23.82


Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	23.92	0.00	64.8	0.00	

Drainage Area		LANDSCAPE			
Area (Ha)	0.400	ICD Size (L/s)= 11.74			
C =	0.32	Reduced Restricted Flow Q_r (L/s)= 5.870			
2-Year Ponding					
T_c Variable (min)	i_{2yr} (mm/hour)	Peak Flow $Q_p = 2.78xCI_{2yr} A$ (L/s)	Q_r (L/s)	$Q_p - Q_r$ (L/s)	Volume 2yr (m^3)
22	49.02	17.41	5.87	11.54	15.23
23	47.66	16.93	5.87	11.06	15.26
24	46.37	16.47	5.87	10.60	15.26
25	45.17	16.04	5.87	10.17	15.26
26	44.03	15.64	5.87	9.77	15.24

Storage (m^3)					
Overflow	Required	Surface	Sub-surface	Balance	
0.00	15.26	0.00	64.8	0.00	

APPENDIX E

- C-900 Sediment & Erosion Plan
- MVCA email
- C-200 Grading Plan



COPYRIGHT
This drawing has been prepared solely for the intended use. No reproduction or distribution for any purpose other than that authorized by IBI Group is permitted. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and IBI Group shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to IBI Group for general confirmation before proceeding with fabrication.

IBI Group Professional Services (Canada) Inc.
is a member of the IBI Group of companies.

ISSUES		
No.	DESCRIPTION	DATE
1	ISSUED FOR SPA	2021-02-16
2	SPA SUBMISSION	2021-05-30
3	SPA SUBMISSION	2021-08-17
4	SPA SUBMISSION	2021-10-29

SEE 010 FOR NOTES, LEGEND



CONSULTANTS

Project Coordinator:
North American Development Group

Architect:
RLA Architecture


Surveyor:
Fairhall, Moffatt and Woodland Ltd.

Geotechnical:
Paterson Group

Traffic:
JD Halpenny & Assoc.

Electrical:
Hammerschlag & Joffe Inc

Landscape:
NAK Design Strategies



IBI GROUP
Suite 400 - 333 Preston Street
Ottawa ON K1S 5N4 Canada
tel 613 225 1311 / 613 241 3300 fax 613 225 9868
ibigroup.com

PROJECT
21/35 HUNTMAR DRIVE

PROJECT NO:
127134

DRAWN BY:
EH

PROJECT MGR:
DGY


CHECKED BY:
DGY

APPROVED BY:
DGY

SHEET TITLE
EROSION AND
SEDIMENTATION CONTROL
PLAN



SHEET NUMBER
C-900

ISSUE
1



NOTES:

- SILT FENCE TO BE ERRECTED PRIOR TO EARTH WORKS BEING COMMENCED. SILT FENCE TO BE MAINTAINED UNTIL VEGETATION IS ESTABLISHED OR UNTIL START OF SUBSEQUENT PHASE.
- STRAW BALE SEDIMENT TRAPS TO BE CONSTRUCTED IN EXISTING ROAD SIDE DITCHES. TRAPS TO REMAIN AND BE MAINTAINED UNTIL VEGETATION IS ESTABLISHED.
- SILT SACK TO BE PLACED AND MAINTAINED UNDER COVER OF ALL CATCHBASINS. GEOTEXTILE SILT SACK IN STREET C&S TO REMAIN UNTIL ALL CURBS ARE CONSTRUCTED. ALL CATCHBASINS TO BE REGULARLY INSPECTED AND CLEANED, AS NECESSARY, UNTIL SOD AND CURBS ARE CONSTRUCTED.
- CONTRACTOR TO PROVIDE DETAILS ON LOCATION(S) AND DESIGN OF DEWATERING TRAP(S) PRIOR TO COMMENCING WORK. CONTRACTOR ALSO RESPONSIBLE FOR MAINTAINING TRAP(S) AND ADJUSTING SIZE(S) IF DEEMED REQUIRED BY THE ENGINEER DURING CONSTRUCTION. ALL DEWATERING EFFLUENT TO BE DISCHARGED TO EXISTING STORM SEWER SYSTEM.
- WORKS NOTED ABOVE ARE TO BE INSTALLED, INSPECTED, MAINTAINED AND ULTIMATELY REMOVED BY SERVICING CONTRACTOR. EROSION AND SEDIMENT CONTROL MEASURES TO BE INSPECTED FOLLOWING EACH RAINFALL EVENT.
- THIS IS A "LIVING DOCUMENT" AND MAY BE MODIFIED IN THE EVENT THE PROPOSED CONTROL MEASURES ARE INSUFFICIENT



NOTE:
A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING
Nov 2006 Rev 11

LIGHT-DUTY SILT FENCE BARRIER
OPSD 219.110

Demetrius Yannoulopoulos

From: Doug Nuttall <dnuttall@mvc.on.ca>
Sent: Friday, June 22, 2012 9:10 AM
To: Demetrius Yannoulopoulos
Cc: sean.moore@ottawa.ca
Subject: RE: Infiltration augmentation

Sorry about the delay;

MVC is satisfied with this approach. It is reasonable to expect that there will be sufficient infiltration from this facility to supplement the infiltration that will come from the sand beds and irrigation. It would be very interesting to monitor the water flowing into and out of such a facility, and I would ask the consultant, on behalf of the client, if MVC would be able to install monitoring in MH 35? Ideally, we should be monitoring flows in and out of the facility – thus it would be easier for us if the outlet was directed to CBMH 29, rather than directly to the pipe. There should be lots of grade to make that work.

Douglas Nuttall, P.Eng.
Water Resources Engineer
Mississippi Valley Conservation

From: Demetrius Yannoulopoulos
Sent: Tuesday, June 19, 2012 10:03 AM
To: 'Doug Nuttall'
Subject:

Hi Doug

As discussed yesterday, we propose to add a drywell in front of Box C, within in the parking lot area. The drywell will be a clear stone facility 4m wide by 40m long, and 0.73m clear depth from bottom of perforated pipe. The drywell has a total volume of 116.6m³, with 30% voids in the clear stone there is 35m³ of storage available. Rainfall from the 5992 m² roof of Box C will supply the drywell, the roof of Box C has flow restrictors limiting the outflow to 25l/s. The dry well is set up such that if the volume of runoff from the roof exceeds the storage capacity of the dry well excess runoff is discharged to the storm sewer, see attached PDF illustrating the proposed drywell.

Rainfall data (see attached) indicates for the months of March up to and including November, 40 days of 5mm or more rain occurred, and for the same period 22 days of 10mm or more rain occurred. Assuming 80% of rainfall is collected by the roof drains the following volume of rainfall is collected and discharged into the drywell:

5mm, at 80% = 4mm, for 5992m² roof = 23.96m³, for 40 events = 958.72m³

10mm, at 80%= 8mm (less 4mm from above) = 4mm for 5992m² roof = 23.96m³, for 22 events = 527.29m³

These events provide a approximately of 1486m³ of rainfall for use by the drywell.

For the 84,600m² site, this will add approximately 17.56mm/yr of infiltration.

As we had previously discussed the sand well will provide approximately 20mm/yr of infiltration with natural rainfall, and the irrigation system will also supplement with an additional 20mm/yr.

Combining these three the site will have approximately 57mm/yr of infiltration which falls within the 50 to 70mm/yr target for this area.

As you are aware the City is asking us to provide CA acceptance of the infiltration approach. If you are in agreement with the above, it would be greatly appreciated if you could forward me an email indicating MVCA acceptance of the infiltration approach.

If you have any questions, please call or email.

Thx

Demetrius

Demetrius Yannoulopoulos P.Eng.
Associate Director

IBI Group
400-333 Preston Street
Ottawa ON K1S 5N4 Canada

tel 613 225 1311 ext 590

fax 613 225 9868


cell 613 447 0504

email dyannoulopoulos@IBIGroup.com

web www.ibigroup.com

NOTE: This e-mail message and attachments may contain privileged and confidential information. If you have received this message in error, please immediately notify the sender and delete this e-mail message.

NOTE: Ce courriel peut contenir de l'information privilégiée et confidentielle. Si vous avez reçu ce message par erreur, veuillez le mentionner immédiatement à l'expéditeur et effacer ce courriel.



CLIENT
NorthAMERICAN
 DEVELOPMENT GROUP
 2851 John Street, Suite One, Markham, Ontario L3R 5R7 T:505-968-3185








COPYRIGHT
 This drawing has been prepared solely for the intended use. No reproduction or distribution for any purpose other than that authorized by IBI Group is permitted. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the site, and IBI Group shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to IBI Group for general confirmation before proceeding with fabrication.
 IBI Group Professional Services (Canada) Inc.
 a member of the IBI Group of companies

ISSUES	No.	DESCRIPTION	DATE
	1	ISSUED FOR SPA	2021-02-16
	2	SPA SUBMISSION	2021-05-30
	3	SPA SUBMISSION	2021-08-17
	4	SPA SUBMISSION	2021-10-29

SEE 010 FOR NOTES, LEGEND



CONSULTANTS
 Project Coordinator:
 North American Development Group
 Architect:
 RLA Architecture
 Surveyor:
 Fairhall, Moffatt and Woodland Ltd.
 Geotechnical:
 Paterson Group
 Traffic:
 JD Halpenny & Assoc.
 Electrical:
 Hammerschlag & Joffe Inc
 Landscape:
 NAK Design Strategies



IBI GROUP
 Suite 400 - 333 Preston Street
 Ottawa ON K1S 5N4 Canada
 Tel: 613 225 1311 / 613 241 3300 fax: 613 225 9868
 ibigroup.com

PROJECT
21/35 HUNTMAR DRIVE

PROJECT NO:
 127134

DRAWN BY:
 EH

CHECKED BY:
 DGY

PROJECT MGR:
 DGY

APPROVED BY:
 DGY

SHEET TITLE
GRADING PLAN

SHEET NUMBER
C-200

ISSUE
1

CITY FILE No. D07-12-21-0035
 File Location: \\172134_21_Huntmar\0_Production\02_Design\04_Civil\Sheets\C-200 GRAD NG PLAN.dwg Last Saved: October 28, 2021, by Emeric Plabier, Friday, October 28, 2021 8:32:37 AM by Eric Henne