



Noise Impact Study

145 Loretta Avenue & 951 Gladstone Avenue, Ottawa

TIP Gladstone GP Inc.

9 February 2022

→ **The Power of Commitment**



Prepared by:

Reviewed by:

Ben Wiseman
Acoustical Consultant



Gordon Reusing
Business Group Leader, EHS Compliance

GHD Limited 735

455 Phillip Street, Suite #100A
Waterloo, Ontario N2L 3X2, Canada
T 519-884-0510 | ghd.com

Document Status

| Status Code | Revision | Author | Reviewer | | Approved for issue | | |
|-------------|----------|------------|------------|-----------|--------------------|-----------|----------|
| | | | Name | Signature | Name | Signature | Date |
| S4 | FINAL | B. Wiseman | G. Reusing | | G. Reusing | | Feb.9/22 |
| | | | | | | | |

© GHD 2022

This document is and shall remain the property of GHD. The document may only be used for the purpose for which it was commissioned and in accordance with the Terms of Engagement for the commission. Unauthorised use of this document in any form whatsoever is prohibited.

Executive summary

GHD Limited (GHD) was retained by TIP Gladstone GP Inc. (Applicant) to prepare a Noise Impact Study for the proposed mixed-use residential development (Development) located at 145 Loretta Avenue North and 951 Gladstone Avenue in Ottawa, Ontario (Site). This Study has been prepared in support of the planning approvals for the Development.

The Development consists of three new residential towers (30, 33, and 35 storeys) above a common retail and office podium with two levels of below-grade parking, and the restoration and modernization of an existing heritage building, being the 3-storey Standard Bread building constructed in 1924.

The purpose of this Study is to assess the following potential impacts:

- Noise impacts at the Development due to future road traffic
- Noise impacts at the Development due to future rail traffic
- Stationary noise impacts from off-site industrial/commercial facilities

Ambient noise levels at the Development from road and rail traffic are significant and require noise mitigation in the form of upgraded building façade components, acoustic barriers, installation of air conditioning, and warning clauses.

Stationary noise from the adjacent CBN facility to the Development is a known issue, and TIP is working with CBN to establish an appropriate mitigation plan. A Class 4 designation is recommended as it would significantly facilitate the compatibility of the CBN operations with the Development.

Noise emissions from the Ottawa Traffic Operations facility to the south were also assessed, and based on assumptions provided by Ottawa Traffic Operations staff the noise emissions from this facility are within the applicable sound level limits.

This Study concludes that the Development is feasible provided that the recommendations of this study are followed.

This report is subject to, and must be read in conjunction with, the limitations set out in section 1.2 and the assumptions and qualifications contained throughout the Report.

Contents

| | | |
|-----------|---|-----------|
| 1. | Introduction | 1 |
| 1.1 | Purpose of this Report | 1 |
| 1.2 | Scope and Limitations | 1 |
| 2. | Site and Development Design | 1 |
| 3. | D-6 Screening Assessment | 3 |
| 3.1.1 | Classification of Industries | 3 |
| 3.1.1.1 | Canada Bank Note | 3 |
| 3.1.1.2 | Ottawa Traffic Operations | 4 |
| 3.1.2 | Guideline D-6 Assessment Conclusions | 4 |
| 3.1.2.1 | Existing Industries | 4 |
| 3.1.2.2 | Potential Future Industries | 4 |
| 4. | Sound Level Criteria | 5 |
| 4.1 | City of Ottawa Environmental Noise Control Guidelines | 5 |
| 4.2 | Road and Rail Traffic Criteria | 5 |
| 4.3 | Stationary Noise Limits | 6 |
| 4.3.1 | MECP Standard Limits | 6 |
| 4.3.2 | Background Sound Levels | 7 |
| 4.3.3 | Emergency Equipment | 7 |
| 5. | Transportation Noise Impact Assessment | 8 |
| 5.1 | Methodology | 8 |
| 5.2 | Traffic Input Parameters | 8 |
| 5.2.1 | Road Traffic Data | 8 |
| 5.2.2 | Rail Traffic Data | 8 |
| 5.3 | Results | 9 |
| 5.3.1 | Plane of Window Receivers | 9 |
| 5.3.2 | Outdoor Living Areas | 9 |
| 5.4 | Transportation Noise Mitigation | 10 |
| 5.4.1 | Building Envelope Construction | 10 |
| 5.4.2 | Ventilation | 11 |
| 5.4.3 | Acoustic Barriers | 11 |
| 6. | Stationary Noise Impact Assessment | 12 |
| 6.1 | Canada Bank Note Facility | 12 |
| 6.2 | Ottawa Traffic Operations Facility | 12 |
| 6.2.1 | Methodology | 12 |
| 6.2.2 | Results | 13 |
| 7. | Noise Impacts from the Development | 13 |
| 7.1.1 | Outdoor Noise Impacts | 13 |
| 7.1.2 | Indoor Noise Impacts | 13 |

Contents

| | |
|------------------------------------|-----------|
| 8. Recommendations | 14 |
| 8.1 Building Envelope Construction | 14 |
| 8.2 Ventilation | 14 |
| 8.3 Acoustic Barriers | 14 |
| 8.4 Class 4 Area Designation | 14 |
| 8.5 Warning Clauses | 15 |
| 9. Conclusions | 15 |
| 10. References | 16 |

Figure index

| | |
|--------------------------|---|
| Figure 2.1 Site Location | 2 |
|--------------------------|---|

Table index

| | |
|---|----|
| Table 3.1 Guideline D-6 Industry Separation Distances | 3 |
| Table 4.1 Road and Rail Traffic – Outdoor Sound Level Limits | 5 |
| Table 4.2 Road and Rail Traffic – Indoor Sound Level Limits | 6 |
| Table 4.3 MECP Minimum Exclusionary Sound Level Limits for Steady Sound – Class 1 and 4 Areas | 6 |
| Table 4.4 Background Road Traffic Parameters | 7 |
| Table 4.5 Applicable MECP Sound Level Limits for Steady Sound | 7 |
| Table 5.1 Future (2032) Road Traffic Input Parameters | 8 |
| Table 5.2 Future (2032) Rail Traffic Input Parameters | 8 |
| Table 5.3 Future Road and Rail Noise Levels – Plane of Window | 9 |
| Table 5.4 Future Road and Rail Noise Levels – Outdoor Living Area | 10 |
| Table 5.5 Example Window Assemblies and STC Ratings | 11 |
| Table 6.1 Stationary Noise Results – Ottawa Traffic Operations, Steady | 13 |

Appendices

| | |
|---|--|
| Appendix A Zoning Map and Site Plan | |
| Appendix B STAMSON Calculations | |
| Appendix C Road and Rail Traffic Data | |
| Appendix D Stationary Noise Model Information | |

1. Introduction

1.1 Purpose of this Report

GHD Limited (GHD) was retained by TIP Gladstone GP Inc. (TIP) to prepare a Noise Impact Study (Study) for the proposed high rise residential Development located at 145 Loretta Ave N and 951 Gladstone Ave, Ottawa, Ontario (Development). This Study has been prepared in support of the planning applications for the Development, and includes the following key assessments:

- Noise impacts at the Development due to future road traffic
- Noise impacts at the Development due to future rail traffic
- Stationary noise impacts from off-site industrial/commercial facilities

Rail vibration was assessed previously by J.E. Coulter Associates Limited with results summarized in a report dated August 8, 2019 and determined to be insignificant. Therefore, rail vibration has not been assessed as part of this Study.

1.2 Scope and Limitations

This report: has been prepared by GHD for TIP and may only be used and relied on by TIP for the purpose agreed between GHD and TIP as set out in section 1.1 of this report.

GHD otherwise disclaims responsibility to any person other than TIP arising in connection with this report. GHD also excludes implied warranties and conditions, to the extent legally permissible.

The services undertaken by GHD in connection with preparing this report were limited to those specifically detailed in the report and are subject to the scope limitations set out in the report.

The opinions, conclusions and any recommendations in this report are based on conditions encountered and information reviewed at the date of preparation of the report. GHD has no responsibility or obligation to update this report to account for events or changes occurring subsequent to the date that the report was prepared.

The opinions, conclusions and any recommendations in this report are based on assumptions made by GHD described in this report. GHD disclaims liability arising from any of the assumptions being incorrect.

2. Site and Development Design

The Site is bounded by Loretta Avenue North on the west side, the O-Train Trillium Line to the northeast, and Gladstone Avenue to the south. Figure 2.1 below identifies the location of the Site.



Figure 2.1 Site Location

Existing noise sources surrounding the Site are summarized as follows:

- **Road Traffic:** Highway 417 is located approximately 170 metres (m) south of the Site, and Gladstone Avenue is located immediately south of the Site.
- **Rail Traffic:** The O-Train Trillium Line is located approximately 25 m northeast of the Site.
- **Stationary:** A Canada Bank Note (CBN) facility is located approximately 20 m west of the Site, and an Ottawa Traffic Operations facility is located approximately 20 m south of the Site.

The Site is currently zoned as General Industrial (IG1). The lands surrounding the Site include properties zoned as General Industrial (IG1) to the west and south, and Mixed-Use Centre Zone (*_MC F [1.5]) to the east. A zoning map is included in Figure A.1 of Appendix A.

The area surrounding the Site includes some significant terrain elevation changes, including a deep cut to the O-Train Trillium Line, and there are some intervening structures that obstruct the line-of-sight to the roadways and rail line, particularly at the lower floors.

The Development consists of three new high-rise residential towers, with mixed uses at the lower levels. Towers 1 and 2 are 35 and 33 storeys tall, respectively, and sit atop a 5-storey retail and office podium. Tower 3 is 30 storeys tall, and includes live/work units and amenity spaces on the Ground floor. The exterior of the 3-storey Standard Bread building constructed in 1924 is to be maintained, with the interior to be renovated and used as workspace for artists. There are common outdoor amenity spaces located on the roof of the podium at the base of Towers 1 and 2. There are also pathways/courtyards at grade, which are proposed as privately-owned public spaces and are intended to be used for the purpose of public access to the mixed-use path to the east of the Development.

3. D-6 Screening Assessment

The MECP Guideline D-6 "Compatibility Between Industrial Facilities and Sensitive Land Uses" (Guideline D-6) provides recommended minimum separation distances (RMSD) and potential areas of influence (AOI) based on the class of the industrial facility. RMSDs are provided based on the industry size and operation type. The guideline provides direction for land use planning to maximize compatibility of industrial uses with adjacent land uses. The goal of Guideline D-6 is to minimize encroachment of sensitive land uses on industrial facilities and vice versa, in order to address potential incompatibility due to adverse effects such as noise, odour, and dust.

Guideline D-6 separates industry into three broad categories, depending on the nature of their operations and the types of potential impacts:

- **Class I industries** are small scale, self-contained plants or buildings, which produce and store products internally, and have low probability of fugitive emissions. They have daytime operations only, with infrequent movements of products and/or heavy trucks. Some examples include furniture repair and refinishing, electronics manufacturing, auto parts supply, distribution of dairy products, and beverages bottling.
- **Class II industries** perform medium scale processing, with occasional outputs of point source or fugitive emissions. Activities may include some outdoor storage of wastes and materials, frequent movement of products and/or heavy trucks during the daytime, and shift work. Some examples include paint spray booths, feed packing plant, dairy product manufacturing, and dry-cleaning services.
- **Class III industries** conduct large-scale manufacturing and are characterized by persistent and/or intense dust and/or odour, frequent outputs of major annoyances, and have a high probability of fugitive emissions. Activities may include continuous operations and movements of products, outside storage of raw and finished goods, and high levels of production. Some examples include manufacturing of paint and varnish, manufacturing of resins and coatings, solvent recovery plants, organic chemicals manufacturing, breweries, and metal manufacturing.

The following table summarizes the recommended minimum setback distances and areas of potential influence which represents the distance within which adverse effects could potentially occur.

Table 3.1 Guideline D-6 Industry Separation Distances

| Industry Classification | RMSD (metres) | AOI (metres) |
|-------------------------|---------------|--------------|
| Class I | 20 | 70 |
| Class II | 70 | 300 |
| Class III | 300 | 1,000 |

Guideline D-6 provides criteria for classifying industrial land uses, based on their outputs, scale of operations, processes, schedule, and intensity of operations. Often an industry will fall between two Classes. Guideline D-6 states that no incompatible development should occur within the recommended minimum separation distance as noted in Table 3.1. In cases where the recommended minimum separation distances are not met, further detailed assessment is warranted to ensure compatibility as stated in guideline D-6.

3.1.1 Classification of Industries

GHD has evaluated the size and operations of the commercial/industrial facilities in the general vicinity of the Site to apply the appropriate classification per Guideline D-6. GHD's evaluation and classification of these facilities is summarized as follows.

3.1.1.1 Canada Bank Note

Canada Bank Note (CBN) operates a manufacturing facility located approximately 20 metres west of the Site at 975 Gladstone Avenue. The CBN facility currently operates under MECP Environmental Compliance Approval (ECA) number 3835-A7QLZW, and is obligated to comply with the sound level limits of NPC-300.

Based on aerial imagery, the CBN facility includes heating, ventilating, and air conditioning (HVAC) units, cooling towers, etc. on its roof. There is a loading dock located on the east side of the facility.

It is assumed that the CBN facility may operate 24 hours per day, 7 days per week.

Under Guideline D-6, CBN's current operations could be conservatively described as Class III based on the applicability of the following criteria:

- Noise frequently audible off property
- Daily shift operations permitted

Class III industries have an RMDS of 300 metres and an AOI of 1000 metres under the D-6 compatibility guidelines. The CBN facility is within the 300-metre RMSD of the Site, and therefore warrants detailed noise impact assessment per Guideline D-6.

3.1.1.2 Ottawa Traffic Operations

There is an Ottawa Traffic Operations facility located approximately 20 metres south of the Site at 175 Loretta Avenue North. The facility currently operates under MECP Environmental Compliance Approval (ECA) number 3038-8SLKC7, and is obligated to comply with the sound level limits of NPC-205.

Based on correspondence with facility management, it is understood that the facility operates year round Monday to Friday from 7:00 am to 4:00 pm, with seasonal nighttime operations Monday to Thursday from 8:30 pm to 6:00 am.

The facility includes small rooftop HVAC units and exhausts, with outdoor yard for storage of utility vehicles and materials.

Under Guideline D-6, the assumed operations of the facility would be best described as Class II based on the applicability of the following criteria:

- Noise occasionally audible off property
- Shift operations permitted

Class II industries have an RMDS of 70 metres and an AOI of 300 metres under the D-6 compatibility guidelines. The Ottawa Traffic Operations facility is within the 70-metre RMSD of the Site, and therefore warrants detailed noise impact assessment per Guideline D-6.

3.1.2 Guideline D-6 Assessment Conclusions

3.1.2.1 Existing Industries

Based on the industry classifications noted above and their setbacks relative to the sensitive uses of the Development (see Figure 3.1), GHD has identified the following industries that have potential areas of influence and/or recommended minimum setback distances within which the Development is located:

- Canada Bank Note (975 Gladstone Ave)
- Ottawa Traffic Operations (175 Loretta Ave N)

Section 4.10.3 of the D-6 Guideline allows the proponent to provide a justifying impact assessment to support an application for a change in land use where the minimum distances are not met. Detailed stationary noise impact assessments are included in Section 5 to satisfy this requirement.

3.1.2.2 Potential Future Industries

The lands surrounding the Development do not include vacant lands that are zoned to permit significant industrial uses. There are vacant lands to the east, which are zoned Mixed-Use Centre Zone (MCF[1.5]). GHD has reviewed the conceptual site plan for a proposed development on these lands, which indicates that the development consists of primarily residential uses, which are generally compatible with the 145 Loretta Ave N & 951 Gladstone Ave Development provided appropriate noise controls are incorporated into the design of both developments.

4. Sound Level Criteria

4.1 City of Ottawa Environmental Noise Control Guidelines

The City of Ottawa Environmental Noise Control Guidelines (ENCG) include sound level criteria for transportation and stationary noise sources, which are adopted from the Ontario Ministry of the Environment, Conservation and Parks (MECP) guideline NPC-300.

The ENCG also contains requirements for information to be submitted with noise studies for proposed developments, as well as the City's preferred noise warning clauses. Due to the proximity of the Development to significant industrial uses, it is expected that a Phase 2 Noise Control Detailed Study will be required prior to final approval of the Development. This Study is based on the best information available at the time of writing; however, further information is required to satisfy all of the information requirements of a Phase 2 Noise Control Detailed Study, which is not currently available.

4.2 Road and Rail Traffic Criteria

Under NPC-300, road and rail traffic noise impacts are evaluated separately for exterior receptors and interior receptors based on the average day (07:00 to 23:00) and night (23:00 to 07:00) noise impacts. The sound levels are expressed in terms of A-weighted equivalent sound levels (Leq).

NPC-300 defines two categories of receivers for transportation noise:

- Plane of Window (POW): Point corresponding with the centre of a window of a sensitive space.
- Outdoor Living Area (OLA): Outdoor location intended and designed for quiet enjoyment of the outdoor environment that is readily accessible from the building (e.g., backyards, front yards, gardens, terraces, patios). Private balconies and terraces are only considered OLAs if they are greater than 4 metres in depth and if they are the only outdoor living area for the occupant(s).

NPC-300 specifies sound level limits for POW and OLA receivers as summarized in Table 4.1 below:

Table 4.1 Road and Rail Traffic – Outdoor Sound Level Limits

| Receiver Category | Sound Level Limit (dBA) | |
|---------------------------|-------------------------|--------------------|
| | Day (16-hour Leq) | Night (8-hour Leq) |
| Plane-of-Window (POW) | 55 | 50 |
| Outdoor Living Area (OLA) | 55 | N/A |

For POWs, combined road and rail traffic sound levels exceeding the corresponding criteria above would require additional controls for MECP compliance. Depending on the magnitude of the exceedances, additional controls may include ventilation requirements, requirements for building envelope elements, and/or noise warning clauses.

For OLAs, road traffic sound levels exceeding the daytime limit indicated above would require design of noise barriers to achieve the target, and/or warning clauses. As per the ENCG, the City of Ottawa may, at their discretion, consider minor exceedances (up to 5 dBA) of the sound level criteria in OLAs, provided that it is demonstrated that it is not technically or economically feasible to achieve the criteria.

If POW sound levels from future road traffic exceed 65 dBA during the day or 60 dBA at night, or if sound levels from future rail traffic exceed 60 dBA during the day or 55 dBA at night, building envelope components must be designed to

achieve the indoor sound level limits of NPC-300. The indoor sound level limits for road and rail traffic are summarized in Table 4.2 below.

Table 4.2 Road and Rail Traffic – Indoor Sound Level Limits

| Receiver Category | Road Sound Level Limits (dBA) | | Rail Sound Level Limits (dBA) | |
|---|-------------------------------|--------------------|-------------------------------|--------------------|
| | Day (16-hour Leq) | Night (8-hour Leq) | Day (16-hour Leq) | Night (8-hour Leq) |
| Indoor living areas (excluding sleeping quarters) | 45 | 45 | 40 | 40 |
| Sleeping quarters | 45 | 40 | 40 | 35 |

4.3 Stationary Noise Limits

4.3.1 MECP Standard Limits

NPC-300 defines stationary noise sources as sound from all sources that are normally operated within the property lines of a facility. The noise impact from stationary sources is evaluated based on operations during a predictable worst-case hour. Stationary noise assessment criteria are generally determined based on the MECP's minimum exclusionary sound level limits, as presented in NPC-300, in comparison to the background sound levels experienced in the area.

The Site is in what would generally be considered a Class 1 acoustic environment as defined by NPC-300, as the acoustic environment is dominated by human activities (i.e., road traffic). However, the guideline allows an area otherwise classified as Class 1 or 2 to be designated as Class 4 based on the following:

- Intended for development with new noise sensitive land use(s) that are not yet built.
- In proximity to existing, lawfully established stationary source(s).
- Has formal confirmation from the municipality as a Class 4 area classification, determined during the land use planning process.

Items 'a' and 'b' above are met, and it is within the City of Ottawa's jurisdiction to formally approve a Class 4 designation for the Development to satisfy item 'c'.

One of the goals of the NPC-300 guideline is to resolve conflicts between stationary sources and noise sensitive land uses. The designation of a Class 4 Area is meant to be a tool to allow municipalities to approve a noise sensitive land use with more relaxed noise limits and the option to implement special noise mitigation strategies (e.g., enclosed noise buffer) that would not otherwise be permitted in relation to a noise sensitive land use such as residential dwellings and associated outdoor living areas. The higher Class 4 noise level limits would apply at all designated Class 4 residential uses and would be used as the assessment criteria for the provincial noise permits for the affected industries.

Table 4.3 below summarizes the MECP's minimum exclusionary sound level limits for Class 1 and Class 4 areas, which are expressed in terms of 1-hour equivalent sound levels (1-hour Leq):

Table 4.3 MECP Minimum Exclusionary Sound Level Limits for Steady Sound – Class 1 and 4 Areas

| Point of Reception Type | Class 1 Sound Level Limits (dBA) | | Class 4 Sound Level Limits (dBA) | |
|-------------------------|----------------------------------|--------------------|----------------------------------|--------------------|
| | Day (7am – 11pm) | Night (11pm – 7am) | Day (7am – 11pm) | Night (11pm – 7am) |
| Plane of window | 50 | 45 | 60 | 55 |
| Outdoor space | 50 | -- | 55 | -- |

As seen above, the Class 4 sound level limits are 10 dBA higher at plane of window PORs and 5 dBA higher at outdoor PORs compared to Class 1 noise limits.

4.3.2 Background Sound Levels

GHD conducted a background sound level assessment to evaluate the existing background noise due to road traffic on Highway 417. Background noise was modelled with STAMSON, the MECP's computerized model of the Ontario Road Noise Analysis Method for Environment and Transportation (ORNAMENT). The applicable noise criteria at a point of reception are based on the higher of the background sound level and the MECP's minimum sound level limits, as noted in Section 4.3.2.

The computer model input parameters include, among other data, the number of road segments, number of house rows, the positional relationship of the receptor to a noise source or barrier in terms of distance, elevation and angle, the basic site topography, the ground surface type, traffic volumes, traffic composition, and speed limit.

Hourly traffic counts from 2019 for Highway 417 were obtained from the Ontario Ministry of Transportation, which are included in Appendix C. These counts were used to determine the minimum hourly traffic volumes during the daytime and nighttime periods, which are summarized as follows:

Table 4.4 Background Road Traffic Parameters

| Road Segment | Minimum Hourly Daytime Vehicles | Minimum Hourly Nighttime Vehicles | Commercial Vehicle Rates (medium trucks / heavy trucks) |
|--------------|---------------------------------|-----------------------------------|---|
| Highway 417 | 3,083 | 500 | 5% / 8% |

The above road traffic data was used to calculate background sound levels at the façades and outdoor points of reception of the Development using the traffic noise model methodology described in Section 5.1 of this Study. Predicted noise levels exceed the minimum Class 1 exclusionary limits at the most exposed facades of the Development. The lowest background sound levels generally occur at the lower floors of the Development and increase with height.

Where the predicted background sound level due to road traffic exceeds the corresponding minimum exclusionary sound level limit of NPC-300 (see Table 4.3), the background sound level is instead used as the criteria for assessment of stationary noise impacts. The applicable site-specific sound level limits for the Development are summarized as follows:

Table 4.5 Applicable MECP Sound Level Limits for Steady Sound

| POR ID | POR Description | Sound Level Limits (dBA) | |
|--------|--|--------------------------|--------------------|
| | | Day (7am – 7pm) | Night (11pm – 7am) |
| POR-1 | Plane of window on south façade of Tower 1, 6 th floor (22.3 metres above grade [m AG]) | 63 | 56 |
| POR-2 | Plane of window on east façade Tower 1, 7 th floor (25.3 m AG) | 60 | 52 |
| POR-3 | Plane of window on south façade of Tower 2, 11 th floor (40.3 m AG) | 63 | 56 |

As seen above, predicted background sound levels at the identified worst-case PORs are significant. It is worth noting that background sound levels at other façades with less direct exposure to noise from Highway 417 would be lower. For example, background sound levels at the lowest floors at the west façade of Tower 3 are estimated to be below the Class 1 exclusionary sound level limits due to significantly reduced exposure to noise from Highway 417.

4.3.3 Emergency Equipment

Emergency operation of emergency equipment such as standby power generators is exempt from stationary assessment per NPC-300. However, regular scheduled testing of emergency equipment is considered a stationary source, evaluated separately from other sources, with sound level limits that are 5 dBA higher than the sound level limits otherwise applicable to stationary sources.

5. Transportation Noise Impact Assessment

5.1 Methodology

Future (2032) road and rail traffic sound levels at the Development were predicted using STAMSON v5.04, a computerized model which implements the MECP's ORNAMENT and STEAM algorithms. The computer model input parameters include, among other data, the number of road segments, number of house rows, the positional relationship of the receptor to a noise source or barrier in terms of distance, elevation and angle, the basic site topography, the ground surface type, traffic volumes, traffic composition, and speed limit.

5.2 Traffic Input Parameters

5.2.1 Road Traffic Data

Future road traffic model parameters used in this Study is summarized as follows:

Table 5.1 Future (2032) Road Traffic Input Parameters

| Road Segment | Future AADT | Speed Limit (km/h) | Day / Night Split | Commercial Vehicle Rates (medium trucks / heavy trucks) |
|----------------------|-------------|--------------------|-------------------|---|
| Highway 417 | 241,617 | 100 | 92% / 8% | 7% / 5% |
| Gladstone Avenue | 15,000 | 40 | 92% / 8% | 7% / 5% |
| Somerset Street West | 15,000 | 50 | 92% / 8% | 7% / 5% |

Road traffic volumes for Highway 417 were obtained from data published by the Ontario Ministry of Transportation (MTO) in the form of Annual Average Daily Traffic (AADT) volumes from 1988 to 2016. The average AADT growth rate from 1988 to 2016 was 1.71% (compounded annually), which was used to estimate the future 2032 AADT. The estimated future AADT exceeds the default value recommended by the ENCG, and was therefore used to be conservative. The day / night split and commercial vehicle rates were assumed based on guidance from the ENCG.

Road traffic parameters for Gladstone Avenue and Somerset Street West were assumed based on guidance from the ENCG.

Figure 2.2 shows the location of the roadways noted above in relation to the Site. All road traffic data referenced in this Study is included in Appendix C.

5.2.2 Rail Traffic Data

Future rail traffic model parameters used in this Study is summarized as follows:

Table 5.2 Future (2032) Rail Traffic Input Parameters

| Rail Source | Future Daytime Trains | Future Nighttime Trains | Locomotive Type | Locomotives per Train | Cars per Train | Speed (km/h) |
|-----------------------|-----------------------|-------------------------|-----------------|-----------------------|----------------|--------------|
| O-Train Trillium Line | 205 | 38 | Diesel | 1 | 3 | 35 |

The O-Train Trillium Line (Line 2) is served by high-efficiency diesel multiple unit (DMU) trains. The current fleet includes trains of two to four cars. Based on the train schedule published on the OC Transpo website, the current train schedule would result in approximately 160 train pass-bys during the day and 30 pass-bys at night. To estimate the future train traffic on the Trillium Line, GHD assumed a growth rate of 2.5% per year. Based on communications with OC Transpo staff, it was confirmed that the average speed of trains on the Trillium Line is 35 km/h.

GHD notes that the Corso Italia station is currently under construction immediately east of the Development, and is planned to open in 2023. As such, future trains would be expected to travel slower than assumed in this Study as they would typically stop at this station.

Figure 2.2 shows the location of the rail line noted above in relation to the Site. A copy of the O-Train Trillium Line schedule is included in Appendix C.

5.3 Results

5.3.1 Plane of Window Receivers

Predicted future road and rail traffic noise impacts at the worst-case POW receivers of the Development are summarized as follows:

Table 5.3 Future Road and Rail Noise Levels – Plane of Window

| Building | Façade | Future Noise Levels (dBA) | | | | | | Outdoor Criteria Exceeded? |
|-----------------------------|--------|---------------------------|-------|------|-------|--------------------------|-------|----------------------------|
| | | Road | | Rail | | Cumulative Road and Rail | | |
| | | Day | Night | Day | Night | Day | Night | |
| <i>Sound Level Criteria</i> | | -- | -- | -- | -- | 55 | 50 | -- |
| Tower 1 (35 Storeys) | North | 52 | 45 | 62 | 58 | 62 | 58 | Yes |
| | East | 72 | 65 | 65 | 60 | 73 | 66 | Yes |
| | South | 76 | 68 | 60 | 56 | 76 | 69 | Yes |
| | West | 73 | 66 | 51 | 47 | 73 | 66 | Yes |
| Tower 2 (33 Storeys) | North | 54 | 46 | 66 | 62 | 66 | 62 | Yes |
| | East | 71 | 64 | 67 | 63 | 73 | 66 | Yes |
| | South | 73 | 66 | 63 | 58 | 74 | 66 | Yes |
| | West | 71 | 64 | 55 | 51 | 71 | 64 | Yes |
| Tower 3 (30 Storeys) | North | 55 | 48 | 66 | 61 | 66 | 61 | Yes |
| | East | 70 | 62 | 68 | 63 | 72 | 66 | Yes |
| | South | 72 | 65 | 63 | 58 | 73 | 66 | Yes |
| | West | 71 | 63 | 55 | 51 | 71 | 64 | Yes |

As seen above, future cumulative road and rail noise levels at the façades generally range from 62 dBA to 76 dBA during the day and 58 dBA to 69 dBA at night. These sound levels are sufficiently high that the Development must incorporate physical noise mitigation and noise warning clauses in accordance with NPC-300, which are described further in Section 5.4. POW receiver locations are shown on Figure 5.1.

5.3.2 Outdoor Living Areas

There is a common outdoor amenity space located on the roof of the podium at the base of Towers 1 and 2. All residents of the Development will have access to this amenity space, therefore private balconies and terraces are not considered OLAs per the definition in NPC-300.

There are also pathways/courtyards at grade, which are proposed as privately-owned public spaces and are intended to be used for the purpose of public access to the mixed-use path to the east of the Development. As such, these areas are not considered OLAs in this Study.

Predicted future road and rail traffic noise impacts at the worst-case OLA receivers of the Development are summarized as follows:

Table 5.4 Future Road and Rail Noise Levels – Outdoor Living Area

| Receiver ID | Receiver Description | Future Daytime Noise Levels (dBA) | | | Limit Exceeded? |
|-----------------------------|--|-----------------------------------|------|--------------------------|-----------------|
| | | Road | Rail | Cumulative Road and Rail | |
| <i>Sound Level Criteria</i> | | -- | -- | 55 | -- |
| OLA-01 | Shared outdoor amenity space on podium roof (22.75 m AG), west of Tower 1 | 60 | -- | 60 | Yes |
| OLA-02 | Shared outdoor amenity space on podium roof (22.75 m AG), between Towers 1 and 2 | 57 | 40 | 57 | Yes |

As seen above, the cumulative daytime road and rail noise levels at the OLAs range from 57 dBA to 60 dBA. These noise levels are sufficiently high that physical noise mitigation and/or noise warning clauses are required, which are described further in Section 5.4.3. OLA receiver locations are shown in Figure 5.1.

5.4 Transportation Noise Mitigation

5.4.1 Building Envelope Construction

Predicted future traffic noise levels are sufficiently high that the building envelope must be designed with sufficient sound insulation performance to achieve the sound level criteria of NPC-300 for indoor living spaces. Sound insulation performance for windows and walls are commonly specified in terms of Sound Transmission Class (STC) ratings. Higher STC ratings generally correspond to higher sound insulation performance.

STC rating requirements are dependent on the exterior noise levels, source type/spectrum, angles of incidence, sizes of façade components relative to the room size, and sound absorption characteristics of the subject indoor living space. Using these variables, STC rating requirements can be calculated using the methods described in the National Research Council Canada's "Controlling Sound Transmission into Buildings" (BPN 56) publication. In accordance with NPC-300, STC rating requirements are calculated separately for road, rail, and air traffic noise, and are then combined on a logarithmic energy sum basis.

Given the preliminary nature of the design of the Development, detailed floor plans and building elevations are not yet available. Therefore, minimum STC rating requirements have been calculated based on assumed window-to-floor area ratios (i.e., total window area for a room divided by its floor area) of up to 80% for living spaces at corners (i.e., with two exposed façades), and up to 40% for other living spaces. Note that if the actual window-to-floor area ratios are determined to exceed these values during detailed design, then window STC rating requirements would require an updated assessment to ensure acceptable indoor noise levels.

Based on the above assumptions, the worst-case minimum window STC rating requirement is **STC-39**. Other façades that have less direct exposure to road and rail traffic noise have lower STC rating requirements, as shown in Figure 5.2.

Examples of window assemblies capable of achieving the necessary performance are included in Table 5.5 below:

Table 5.5 Example Window Assemblies and STC Ratings

| STC Requirement | Window Assembly Short Form | Window Assembly Description |
|-----------------|----------------------------|---|
| STC-33 | 6-13AS-6 | Two 6 mm thick monolithic glass panes separated by an air gap of 13 mm |
| STC-35 | 6L-13AS-6 | One 6 mm thick laminated glass pane and one 6 mm monolithic glass pane separated by an air gap of 13 mm |
| STC-37 | 8L-25AS-6 | One 8 mm thick laminated glass pane and one 6 mm monolithic glass pane separated by an air gap of 25 mm |

STC ratings for windows are dependent on a variety of factors (e.g., frame design, quality of seals, etc.), and can vary significantly between manufacturers. Therefore, the final STC rating requirements for the windows should be included in the specifications, and window suppliers should be required to submit laboratory test data with their shop drawings to demonstrate that the STC requirements will be achieved.

In addition to the window STC rating requirements noted above, NPC-300 specifies that exterior wall assemblies should be brick veneer or masonry equivalent high-mass construction (e.g., concrete) from the foundation to the rafters due to the Site's proximity to the O-Train Trillium Line and high associated noise levels. GHD anticipates that the indoor sound level criteria can be achieved with other exterior wall assemblies with modest upgrades (e.g., glass spandrel exterior wall backed by insulated partition with two layers of 16 mm thick Type X gypsum board), which would be considered equivalent subject to further detailed assessment.

5.4.2 Ventilation

Predicted future traffic noise levels at the façades of the Development are sufficiently high that central air conditioning is required to be installed prior to occupancy for all residential dwellings. This will allow windows and doors to remain closed to help ensure that the indoor sound level limits of NPC-300 are met. A warning clause should also be used for all residential dwellings to advise them of potential audibility of transportation noise (wording included in Section 8.5).

5.4.3 Acoustic Barriers

Predicted future traffic noise levels at OLA-01 and OLA-02 are sufficiently high that acoustic barriers and/or warning clauses must be used. OLA-01 and -02 are located on the roof of the podium at the base of Towers 1 and 2. The podium is understood to include a solid parapet along its perimeter with a height of 1.1 m above the finished roof level, which has been considered in the unmitigated road and rail noise predictions presented in section 5.3.2. Predicted noise levels at these OLAs are dominated by noise from road traffic on Highway 417.

In order to mitigate noise levels throughout these amenity spaces, GHD analysed increases to the heights of the parapets. Extending the parapet up to 3.0 metres above the podium roof would reduce the cumulative road and rail traffic sound levels to 58 dBA in OLA-01 and 56 dBA in OLA-02, which are still slightly above the 55 dBA criteria. In a rooftop application, barriers taller than 3.0 metres in height present technical and economic challenges due to the significant associated structural requirements (e.g., wind and snow loading). Therefore, GHD recommends that the City utilize its discretion to permit exceedances up to 5 dBA at the rooftop OLAs. In this case, the solid parapet/barrier height of 1.1 m would be considered sufficient, and a warning clause should be used for all residential dwellings of the Development to advise occupants of the noise exceedance despite the inclusion of noise controls (see wording in section 8.5).

The parapets/acoustic barriers may vary in construction, provided they meet the following requirements:

- A minimum surface density of 20 kg/m² or meet compliance with requirement and certification CAN/CSA-Z107.9-00 (R2004) – Standard for Certification of Noise Barriers (Reaffirmed 2004).
- Be structurally sound and appropriately designed to withstand wind and snow loading as applicable.

- Constructed without any cracks or surface gaps at grade. If gaps are necessary for drainage purposes they should be minimized to mitigate the impact on the acoustical performance of the barrier.

6. Stationary Noise Impact Assessment

6.1 Canada Bank Note Facility

There is a known issue with respect to stationary noise emissions from the CBN facility to the Development, of which detailed assessment is outside of the scope of this Study. TIP is currently in negotiations with CBN to establish an appropriate noise mitigation plan to ensure compliance of the facility at the new sensitive receptors of the Development, and details of the noise mitigation are not yet finalized.

GHD strongly recommends that the City of Ottawa consider designating the Site as a Class 4 Area per NPC-300. Class 4 Areas have sound level limits that are 10 dBA less stringent at plane-of-window PORs and 5 dBA less stringent at outdoor PORs, and would therefore significantly facilitate compatibility between the CBN facility and the Development.

6.2 Ottawa Traffic Operations Facility

GHD and TIP made attempts to contact Ottawa Traffic Operations staff to obtain details regarding their operations. At the time of writing no response has been received. However, based on the ECA for the facility and aerial imagery, GHD assumes that the following noise sources are likely part of the worst-case hour operations of the facility for the purposes of this Study:

- Heavy trucks: It is assumed that five heavy trucks could enter and exit the facility during the worst-case daytime and nighttime hours.
- Light trucks: It is assumed that 15 light trucks could enter and exit the facility during the worst-case daytime and nighttime hours.
- Forklift: It was assumed a forklift could operate outdoors continuously during the worst-case daytime hour.
- Rooftop HVAC Equipment: There appear to be three HVAC units located on the roof of the facility. These sources are each modelled with the source sound power level of a typical 15-ton HVAC unit and assumed to operate continuously during the day and on a 50% duty cycle at night (30 minutes per hour).

Source locations are shown in Figure D.1 of Appendix D, and source sound level data and operating conditions are summarized in Table D.1 of Appendix D.

6.2.1 Methodology

Detailed assessment of noise impacts from the Ottawa Traffic Operations facility has been carried out using CadnaA version 2021 MR 1 (CadnaA). CadnaA is the industry standard for noise modelling of industrial and commercial facilities, and is based on ISO standard 9613 2 "Acoustics – Attenuation of Sound during Propagation Outdoors". CadnaA modelling assumptions used in this Study include:

- Reflection Order: A maximum reflection order of 2 was used to evaluate indirect noise impact from reflecting surfaces.
- Ground Absorption: The model was set up with conservative ground absorption coefficients of 0.25 for asphalt surfaces, 0.5 for gravel, and 1.0 for absorptive areas of grass.
- Receptor Elevation: POR receptor heights were modelled appropriately based on an assumed storey height of 3 m.
- Building Surfaces: The buildings are modelled as reflective surfaces.

6.2.2 Results

Based on the assumptions stated herein, the stationary noise results from the Ottawa Traffic Operations facility at the worst-case PORs are summarized as follows:

Table 6.1 Stationary Noise Results – Ottawa Traffic Operations, Steady

| POR ID | Predicted Noise Levels (dBA) | | Class 1 Sound Level Limits (dBA) | | Class 1 Limits Met? |
|--------|------------------------------|-------|----------------------------------|-------|---------------------|
| | Day | Night | Day | Night | |
| POR-1 | 51 | 51 | 63 | 56 | Yes |
| POR-2 | 51 | 51 | 60 | 52 | Yes |
| POR-3 | 46 | 46 | 63 | 55 | Yes |

As seen above, predicted noise levels from the Ottawa Traffic Operations facility are within the applicable Class 1 sound level limits at the worst-case PORs of the Development. Provided the assumptions described herein are appropriate, noise mitigation will not be required to ensure compliance for the facility. A noise contour plot of noise emissions from this facility is included in Figure 6.1.

7. Noise Impacts from the Development

7.1.1 Outdoor Noise Impacts

Base building cooling and ventilation systems for the Development have the potential to result in outdoor noise impacts at noise sensitive spaces within the Development itself and at existing residential uses surrounding the Site. The specific equipment selections are not available at the time of writing; therefore, it is anticipated that noise emissions from rooftop equipment will be evaluated as part of the detailed design of the Development. GHD recommends that the Developer carry the necessary contingencies for the following noise controls, which may be necessary to achieve compliance with the sound level limits of NPC-300 and the ENCG at all worst-case points of reception both on-site and off-site:

- Acoustic louvers and/or barriers to surround large rooftop cooling equipment (e.g., cooling towers, chillers). Cost contingencies should account for structural requirements due to snow and wind loads associated with the barriers.
- Low-noise condenser fans for make-up air units.
- Acoustic enclosures for any standby emergency generator sets (Level 2 minimum).
- Silencers for parking exhaust shafts and make-up air unit intake openings.

Performance specifications of the above controls is dependent on equipment locations and sound power levels, which may vary. Therefore, the full scope and details of the required noise mitigation should be evaluated during detailed design.

7.1.2 Indoor Noise Impacts

Mechanical equipment and other building services also have the potential to cause annoyance due to noise and vibration transmission to residences. The American Society of Heating, Refrigerating, and Air conditioning Engineers (ASHRAE) guidelines specify acceptable noise levels from such equipment. Specification of noise controls (e.g., silencers, floating concrete slabs, acoustic ceilings, vibration isolators) to achieve these criteria is typically completed as part of the detailed building design, once equipment selections are made and floor layouts are more developed.

The Ontario Building Code stipulates minimum STC and apparent sound transmission class (ASTC) rating requirements for demising partitions separating residential suites from other spaces inside the building. For demising partitions separating suites from elevator shafts or garbage chutes, constructions meeting a minimum STC-55 rating must be used. For demising partitions separating suites from any other space in the building, constructions meeting a minimum STC-50 rating must be used. Suite demising partitions must also achieve a minimum rating of ASTC-47.

8. Recommendations

Recommendations described in the preceding sections of this report are summarized in the subsections that follow for clarity.

8.1 Building Envelope Construction

The windows and exterior walls of the Development must be designed appropriately to ensure that the indoor sound level criteria of the MECP are met. Based on preliminary assumptions, the worst-case windows must be rated at **STC-39** or higher, with lower STC requirements corresponding to other less exposed facades (see Figure 5.2). STC rating requirements should be updated once detailed floor plans and building elevations are available.

Exterior walls should be brick veneer or acoustical equivalent. GHD anticipates that glass spandrel backed by an insulated partition with two layers of 16 mm thick Type X gypsum board will be sufficient to achieve the indoor sound level criteria of the MECP, and would therefore be considered acceptable.

8.2 Ventilation

Central air conditioning is required to be installed prior to occupancy for all residential dwellings. This will allow windows and doors to remain closed to help ensure that the indoor sound level limits of NPC-300 are met.

Predicted future traffic noise levels at the façades of the Development are sufficiently high that, at a minimum, provisions must be made to enable installation of central air conditioning at the occupant's discretion (i.e., ductwork must be designed and installed to accommodate a future central air conditioning system installation). This will allow windows and doors to remain closed to help ensure that the indoor sound level limits of NPC-300 are met.

8.3 Acoustic Barriers

Noise levels at the outdoor amenity space on the podium roof are sufficiently high to require mitigation in the form of acoustic barriers. It is not considered technically feasible to achieve the 55 dBA sound level criteria of the City/MECP; therefore, GHD recommends that the City consider exceedances up to 5 dBA acceptable. Nevertheless, the solid parapets at the perimeter of the rooftop amenity space should be extended to 1.8 m above the finished roof level to ensure no direct line-of-sight exposure to noise from the surrounding roadways and O-Train line.

8.4 Class 4 Area Designation

There is a known issue with respect to noise emissions from the CBN facility to the Development. TIP is currently in negotiations with CBN to establish an appropriate noise mitigation plan. GHD strongly recommends that the City of Ottawa consider designating the Site as a Class 4 Area per NPC-300 to facilitate compatibility between the CBN facility and the Development.

Although specifics of the noise mitigation plan are not yet known, GHD notes that the following requirements will apply to the Development if it is designated as a Class 4 Area:

- **Central air conditioning systems** must be provided for all dwellings of the Development, as the less stringent sound level limits are based on the assumption that windows of dwellings can remain closed.

- A **warning clause** should be used to inform occupants of the fact that adjacent industries are required to comply with sound level limits based on the assumption that windows and exterior doors are closed (see wording in section 8.5).

8.5 Warning Clauses

Per the City of Ottawa's Environmental Noise Control Guidelines, the following warning clauses are recommended to be included in agreements of Offers of Purchase and Sale, lease/rental agreements, and condominium declarations for all residential dwellings of the Development:

Surface Transportation Noise: "Purchasers/tenants are advised that despite the inclusion of noise control features in the development and within the building units, sound levels due to increasing road/rail/Light Rail/transitway traffic may, on occasion, interfere with some activities of the dwelling occupants as the sound levels exceed the sound level limits of the City and the Ministry of the Environment.

To help address the need for sound attenuation this development includes:

- Multi-pane glass; and
- Acoustic barriers

To ensure that provincial sound level limits are not exceeded it is important to maintain these sound attenuation features.

The acoustic barriers shall be maintained and kept in good repair by the property owner. Any maintenance, repair or replacement is the responsibility of the owner and shall be with the same material or to the same standards, having the same colour, appearance and function of the original.

This dwelling unit has also been provided with central air conditioning, which allows windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the sound level limits of the City and the Ministry of the Environment.

Additionally this development includes trees and shrubs to screen the source of noise from occupants."

Stationary Noise: "Purchasers/tenants are advised that sound levels due to the adjacent industry (facility) (utility) may interfere with outdoor activities as the sound levels exceed the sound level limits of the City and the Ministry of the Environment.

Purchasers/tenants are further advised that sound levels due to the adjacent industry (facility) (utility) are required to comply with sound level limits that are protective of indoor areas and are based on the assumption that windows and exterior doors are closed. This dwelling unit has been supplied with a ventilation/air conditioning system which will allow windows and exterior doors to remain closed."

9. Conclusions

The Study concludes that the proposed development is feasible, provided that the proposed development adheres to the noise mitigation recommended in this Study. The recommended noise mitigation at the Development consists of enhanced building envelope construction requirements, installation of central air conditioning, noise warning clauses, and acoustic barriers.

TIP is currently in negotiations with CBN to establish an appropriate noise mitigation plan to ensure compliance with the NPC-300 sound level limits at the new sensitive receptors of the Development. GHD strongly recommends that the City of Ottawa consider designating the Site as a Class 4 Area per NPC-300 to facilitate significantly improved compatibility between the CBN facility and the Development.

10. References

City of Ottawa (Ottawa, 2016), *Environmental Noise Control Guidelines*

Ontario Ministry of Environment, Conservation and Parks (MECP, 1995), Guideline D-6: *Compatibility Between Industrial Facilities and Sensitive Land Uses*

Ontario Ministry of Environment, Conservation and Parks (MECP), Publication NPC-104: *Sound Level Adjustments*

Ontario Ministry of Environment, Conservation and Parks (MECP, 2013), Publication NPC-300: *Environmental Noise Guideline: Stationary and Transportation Sources – Approval and Planning*

National Research Council Canada (NRC, 1985), Building Practice Note 56: Controlling Sound Transmission into Buildings




Source: Google Satellite



NOISE IMPACT STUDY
 TIP GLADSTONE GP INC.
 145 LORETTA AVE N & 951 GLADSTONE AVE
 KEY PLAN

11223331
 02.02.2022

FIGURE 2.2



Source: Google Satellite



Notes:
 RMSD = Recommended Minimum Separation Distance
 AOI = Potential Area of Influence
 Dashed lines represent setbacks from the property lines of the Development



NOISE IMPACT STUDY
 TIP GLADSTONE GP INC.
 145 LORETTA AVE N & 951 GLADSTONE AVE
 GUIDELINE D-6 SETBACKS

11223331
 02.02.2022

FIGURE 3.1



Source: Google Satellite



NOISE IMPACT STUDY
 TIP GLADSTONE GP INC.
 145 LORETTA AVE N & 951 GLADSTONE AVE

ROAD AND RAIL TRAFFIC NOISE - RECEIVER LOCATIONS

11223331
 02.02.2022

FIGURE 5.1



Source: Google Satellite



Notes:
 Minimum STC rating requirements shown above are based on window-to-floor area ratios described in this report. If the final design includes any window-to-floor area ratios greater than those described in this report, then the STC rating requirements should be re-evaluated to help ensure that the indoor sound level criteria of the MECF are met.




NOISE IMPACT STUDY
 TIP GLADSTONE GP INC.
 145 LORETTA AVE N & 951 GLADSTONE AVE

MINIMUM FACADE SOUND TRANSMISSION CLASS REQUIREMENTS

11223331
 02.02.2022

FIGURE 5.2



Source: Google Satellite



Legend

- > 45 dBA
- > 50 dBA

Noise contours predicted at a height of 22.25 metres above grade, which is the height of the worst-case POR.



NOISE IMPACT STUDY
 TIP GLADSTONE GP INC.
 145 LORETTA AVE N & 951 GLADSTONE AVE

11223331
 02.02.2022


ESTIMATED STATIONARY NOISE LEVELS FROM OTTAWA TRAFFIC OPERATIONS FACILITY

FIGURE 6.1

Appendices

Appendix A

Zoning Map and Site Plan



Legend


- Site Boundary
- 1 KM Radius
- City of Ottawa Zoning (By-law No. 2008-250)
- Zoning Amendment Pending
- Institutional
- Industrial
- Commercial/Mixed
- Open Space and Leisure
- Residential

Paper Size ANSI B

0 60 120 180 240

Meters

Map Projection: Transverse Mercator
Horizontal Datum: North American 1983
Grid: NAD 1983 UTM Zone 18N





145 LORETTA AVE & 951 GLADSTONE AVE
OTTAWA, ONTARIO
NOISE IMPACT STUDY

Project No. 11223331
Revision No. -
Date Jan 17, 2022

ZONING MAP

FIGURE A.1

Q:\GIS\PROJECTS\11223331\Layouts\202201_RPT002\11223331_202201_RPT002_GIS001.mxd
Print date: 17 Jan 2022 - 16:24
Data source: Google Earth Imagery, Date: 06/06/2018, City of Ottawa Zoning (By-law No. 2008-250), Accessed 2022




Gladstone and Loretta Mixed-Use Hub Draft Zoning Table

| MC[XXXX] YYYY-h | Requirement | Proposed |
|--|--|--|
| Minimum Lot Width (m) | No minimum | Complies |
| Minimum Lot Area (m ²) | No minimum | Complies |
| Minimum Front Yard Setback (m) | 5 metres, aside from Standard Bread Building (See S.YYY) | 5m |
| Minimum Rear Yard Setback (m) | 3 metres (See S.YYY) | 3m |
| Interior Side Yard Setback (m) | 2 metres, aside from Standard Bread Building (See S.YYY) | 2m |
| Corner Side Yard Setback (m) | 3 metres, (See S.YYY) | 3m |
| Minimum Building Height (m) | 6.7m (See S.YYY) | Complies |
| Maximum Building Height (m) | 0m to 132m (See S.YYY) | Complies |
| Maximum Floor Space Index | No maximum | N/A |
| Minimum Width of Landscaped Area | No minimum, except that where a yard is provided and not used for required driveways, aisles, parking, loading spaces or outdoor commercial patio, the whole yard must be landscaped | Complies |
| Minimum Tower Separation Distance | 23 metres | Complies |
| Minimum Tower Podium Stepback Distance | 2 metres | 2m at Gladstone |
| Parking Requirements (Sec. 101, 102, 106, 111) | Requirement | Proposed |
| Area Z of Schedule 1A | 0 spaces/unit (resident) 0.1 spaces/unit, less first 12 units (visitor), but no more than 30 | Surface: 8 P1: 274 P2: 282 Total: 564 |
| Vehicle Space Dimensions | - Must be 2.6m-3.1m by 5.2m - Up to 40% of required parking aside from visitors spaces may be 2.4m x 4.6m | Complies |
| Bicycle Parking | Res: 0.5/unit Office, Retail, Studio: 1 space per 250m ² GFA | 502 spaces proposed |
| Bicycle Space Dimensions | 0.5 x 846 units = 423 bicycles 79 bicycles Total Bicycle Spaces: 467 | Complies |

| Requirement | Requirement | Proposed |
|---|--|--|
| Drive Aisle Width (Double Traffic Lane) | Parking Lot Minimum: 6.7m Parking Garage Minimum: 6m Maximum: 6.7m | Complies |
| Amenity Space Requirements (Sec. 137) | Requirement | Proposed |
| Total: 6m ² per unit | Total: 5,076 m ² | Rooftop Terrace: 1,441.9m ² |
| Communal: 50% of total required | Communal: 2,538 m ² | Indoor Communal Amenity: 2,006.8m ² Balconies: 3,548.2m ² |
| POPS [Privately Owned Public Space] | | POPS: 984m ² |

NOTE: ALL EXISTING SITE INFORMATION AS PER SITE SURVEY PLAN DATED _____, 2018 AND PREPARED BY STANTEC



| no. | date | revision |
|-----|--------------|--------------------|
| 04 | DEC 17, 2021 | SITE PLAN COMMENTS |
| 03 | APR 04, 2021 | SITE PLAN |
| 02 | FEB 12, 2020 | ZONING & OPA |
| 01 | DEC 04, 2019 | CITY COMMENTS |

It is the responsibility of the appropriate contractor to check and verify all dimensions on site and report all errors and/or omissions to the architect.

All contractors must comply with all pertinent codes and by-laws.

Do not scale drawings.

This drawing may not be used for construction until signed.

Copyright reserved.

Hobin Architecture Incorporated
 63 Pamela Street
 Ottawa, Ontario
 Canada K1S 3K7
 T: 613-238-7200
 F: 613-235-2005
 E: mail@hobinarc.com
 hobinarc.com

HOBIN ARCHITECTURE

PROJECT/LOCATION:
 951 GLADSTONE AVE.
 & 145 LORETTA AVE. NORTH


DRAWING TITLE:
 SITE PLAN

DRAWN BY: TD
 DATE: 18/04/17
 SCALE: 1:300

PROJECT: 1726
 DRAWING NO.: A001

FIGURE 2
 REVISION NO.:

SOUTH



| EXTERIOR MATERIAL LIST FINISH MATERIAL LEGEND | |
|--|---------------------------------------|
| BV-1 | BRICK VENEER - TYPE 1 - RED BRICK |
| BV-2 | BRICK VENEER - TYPE 2 - BLACK BRICK |
| BV-H | BRICK VENEER - HERITAGE |
| STV-1 | STONE VENEER |
| PCP | PRECAST CONCRETE PANEL |
| ALP-1 | ALUMINUM PANEL - COLOR 1 - DARK GREY |
| ALP-2 | ALUMINUM PANEL - COLOR 2 - WHITE |
| ALP-3 | ALUMINUM PANEL - COLOR 3 - RED |
| ALP-4 | ALUMINUM PANEL - COLOR 4 - LIGHT GREY |
| ABG | ALUMINUM & GLASS BALCONY GUARD |
| NMS | NOISE MITIGATION SCREEN |

NORTH



Site Elevations

GLADSTONE + LORETTA



HOBIN
FIGURE 3

DECEMBER 17, 2021
scale 1:500

WEST



| EXTERIOR MATERIAL LIST FINISH MATERIAL LEGEND | |
|--|---------------------------------------|
| BV-1 | BRICK VENEER - TYPE 1 - RED BRICK |
| BV-2 | BRICK VENEER - TYPE 2 - BLACK BRICK |
| BV-H | BRICK VENEER - HERITAGE |
| STV-1 | STONE VENEER |
| PCP | PRECAST CONCRETE PANEL |
| ALP-1 | ALUMINUM PANEL - COLOR 1 - DARK GREY |
| ALP-2 | ALUMINUM PANEL - COLOR 2 - WHITE |
| ALP-3 | ALUMINUM PANEL - COLOR 3 - RED |
| ALP-4 | ALUMINUM PANEL - COLOR 4 - LIGHT GREY |
| ABG | ALUMINUM & GLASS BALCONY GUARD |
| NMS | NOISE MITIGATION SCREEN |



Site Elevations

GLADSTONE + LORETTA



HOBIN
FIGURE 4

DECEMBER 17, 2021
scale 1:500

EAST


| EXTERIOR MATERIAL LIST FINISH MATERIAL LEGEND | |
|--|---------------------------------------|
| BV-1 | BRICK VENEER - TYPE 1 - RED BRICK |
| BV-2 | BRICK VENEER - TYPE 2 - BLACK BRICK |
| BV-H | BRICK VENEER - HERITAGE |
| STV-1 | STONE VENEER |
| PCP | PRECAST CONCRETE PANEL |
| ALP-1 | ALUMINUM PANEL - COLOR 1 - DARK GREY |
| ALP-2 | ALUMINUM PANEL - COLOR 2 - WHITE |
| ALP-3 | ALUMINUM PANEL - COLOR 3 - RED |
| ALP-4 | ALUMINUM PANEL - COLOR 4 - LIGHT GREY |
| ABG | ALUMINUM & GLASS BALCONY GUARD |
| NMS | NOISE MITIGATION SCREEN |




± 118m (35 Storeys)



± 112m (33 Storeys)



± 100m (30 Storeys)




Site Elevations

GLADSTONE + LORETTA



HOBIN
FIGURE 5

DECEMBER 17, 2021
Scale 1:500



CROSS-SECTION (LOOKING EAST) - ELEVATIONS, ANGLES & DISTANCES

Appendix B

STAMSON Calculations

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:34:58
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t1_n.te Time Period: Day/Night 16/8 hours
 Description: North facade of Tower 1, 35th floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !       !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
  1.      ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
  
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : -53.00 deg 25.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 49.00 / 49.00 m
Receiver height  : 116.50 / 116.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : -53.00 deg Angle2 : 25.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
  
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 61.60 ! 49.47 ! -- ! -- ! 61.86 *
-----+-----+-----+-----+-----+-----
Total 61.86 dBA
  
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
  
```

| | | | | | | | | | | |
|-----------|---|-------|---|-------|-----------|----|---|----|---|---------|
| 1.O-Train | ! | 57.29 | ! | 45.16 | ! | -- | ! | -- | ! | 57.55 * |
| Total | | | | | 57.55 dBA | | | | | |

* Bright Zone !

Road data, segment # 1: Somerset (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 50 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Somerset (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 421.00 / 421.00 m
 Receiver height : 116.50 / 116.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -40.00 deg Angle2 : 15.00 deg
 Barrier height : 112.00 m
 Barrier receiver distance : 54.00 / 54.00 m
 Source elevation : 62.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Result summary (day)

| | ! | source | ! | Road | ! | Total |
|------------|---|--------|---|-------|-----------|-------|
| | ! | height | ! | Leq | ! | Leq |
| | ! | (m) | ! | (dBA) | ! | (dBA) |
| 1.Somerset | ! | 1.50 | ! | 52.45 | ! | 52.45 |
| Total | | | | | 52.45 dBA | |

Result summary (night)

| | ! | source | ! | Road | ! | Total |
|-------|---|--------|---|-------|---|-------|
| | ! | height | ! | Leq | ! | Leq |
| | ! | (m) | ! | (dBA) | ! | (dBA) |
| ----- | | | | | | |

| | | | | | | |
|-------------------------|---|------|---|-----------|---|-------|
| 1.Somerset | ! | 1.50 | ! | 44.85 | ! | 44.85 |
| -----+-----+-----+----- | | | | | | |
| Total | | | | 44.85 dBA | | |

TOTAL Leq FROM ALL SOURCES (DAY): 62.33
(NIGHT): 57.78

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:36:33
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t1_e.te Time Period: Day/Night 16/8 hours
 Description: East facade of Tower 1, 35th floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !        !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
  1.      ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
  
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : -60.00 deg 90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 50.00 / 50.00 m
Receiver height  : 116.50 / 116.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : -60.00 deg Angle2 : 90.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
  
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 64.35 ! 52.22 ! -- ! -- ! 64.61 *
-----+-----+-----+-----+-----+-----
Total 64.61 dBA
  
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
  
```

| | | | | | | | | | | |
|-----------|---|-------|---|-------|-----------|----|---|----|---|---------|
| 1.O-Train | ! | 60.04 | ! | 47.91 | ! | -- | ! | -- | ! | 60.30 * |
| Total | | | | | 60.30 dBA | | | | | |

* Bright Zone !

Road data, segment # 1: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

 Angle1 Angle2 : 3.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 200.00 / 200.00 m
 Receiver height : 116.50 / 116.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 3.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 2: Gladstone (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Gladstone (day/night)

 Angle1 Angle2 : -3.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 33.00 / 33.00 m
 Receiver height : 116.50 / 116.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -3.00 deg Angle2 : 90.00 deg

Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 65.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 3: Somerset (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 50 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 3: Somerset (day/night)

 Angle1 Angle2 : 7.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 435.00 / 435.00 m
 Receiver height : 116.50 / 116.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 7.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 62.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Result summary (day)

| | ! source | ! Road | ! Total |
|-------------------------|----------|-----------|-----------|
| | ! height | ! Leq | ! Leq |
| | ! (m) | ! (dBA) | ! (dBA) |
| -----+-----+-----+----- | | | |
| 1.Highway 417 | ! 1.50 | ! 72.17 | ! 72.17 * |
| 2.Gladstone | ! 1.50 | ! 60.39 | ! 60.39 * |
| 3.Somerset | ! 1.50 | ! 50.49 | ! 50.49 * |
| -----+-----+-----+----- | | | |
| Total | | 72.48 dBA | |

* Bright Zone !

Result summary (night)

| ! source | ! Road | ! Total |
|----------|---------|---------|
| ! height | ! Leq | ! Leq |
| ! (m) | ! (dBA) | ! (dBA) |

| | | | | | | |
|---------------|---|-----------|---|-------|---|---------|
| 1.Highway 417 | ! | 1.50 | ! | 64.57 | ! | 64.57 * |
| 2.Gladstone | ! | 1.50 | ! | 52.80 | ! | 52.80 * |
| 3.Somerset | ! | 1.50 | ! | 42.90 | ! | 42.90 * |
| Total | | 64.88 dBA | | | | |

* Bright Zone !

TOTAL Leq FROM ALL SOURCES (DAY): 73.13
(NIGHT): 66.18

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:36:03
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t1_s.te Time Period: Day/Night 16/8 hours
 Description: South facade of Tower 1, 35th floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !       !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
  1.      ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
    
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : 22.00 deg 90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 62.00 / 62.00 m
Receiver height  : 116.50 / 116.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : 22.00 deg Angle2 : 90.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
    
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 59.98 ! 47.85 ! -- ! -- ! 60.24 *
-----+-----+-----+-----+-----+-----
Total 60.24 dBA
    
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
    
```

| | | | | | | | | | | |
|-----------|---|-------|---|-------|-----------|----|---|----|---|---------|
| 1.O-Train | ! | 55.67 | ! | 43.54 | ! | -- | ! | -- | ! | 55.93 * |
| Total | | | | | 55.93 dBA | | | | | |

* Bright Zone !

Road data, segment # 1: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 186.00 / 186.00 m
 Receiver height : 116.50 / 116.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -90.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 2: Gladstone (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Gladstone (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 19.50 / 19.50 m
 Receiver height : 116.50 / 116.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -90.00 deg Angle2 : 90.00 deg

Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 65.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Result summary (day)

| ! source ! | Road ! | Total |
|------------|---------|-------|
| ! height ! | Leq ! | Leq |
| ! (m) ! | (dBA) ! | (dBA) |

| | | | |
|-------------------------|--------|-----------|---------|
| -----+-----+-----+----- | | | |
| 1.Highway 417 ! | 1.50 ! | 75.64 ! | 75.64 * |
| 2.Gladstone ! | 1.50 ! | 65.55 ! | 65.55 * |
| -----+-----+-----+----- | | | |
| Total | | 76.05 dBA | |

* Bright Zone !

Result summary (night)

| ! source ! | Road ! | Total |
|------------|---------|-------|
| ! height ! | Leq ! | Leq |
| ! (m) ! | (dBA) ! | (dBA) |

| | | | |
|-------------------------|--------|-----------|---------|
| -----+-----+-----+----- | | | |
| 1.Highway 417 ! | 1.50 ! | 68.04 ! | 68.04 * |
| 2.Gladstone ! | 1.50 ! | 57.95 ! | 57.95 * |
| -----+-----+-----+----- | | | |
| Total | | 68.45 dBA | |

* Bright Zone !

TOTAL Leq FROM ALL SOURCES (DAY): 76.16
 (NIGHT): 68.68

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:37:06
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t1_w.te Time Period: Day/Night 16/8 hours
 Description: West facade of Tower 1, 35th floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !        !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----
  1.      ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
  
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : 79.00 deg 90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 84.00 / 84.00 m
Receiver height  : 116.50 / 116.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : 79.00 deg Angle2 : 90.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
  
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----
1.O-Train ! 50.75 ! 38.62 ! -- ! -- ! 51.01 *
-----+-----+-----+-----+-----
Total 51.01 dBA
  
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
  
```

| | | | | | | | | | | |
|-----------|---|-------|---|-------|-----------|----|---|----|---|---------|
| 1.O-Train | ! | 46.44 | ! | 34.31 | ! | -- | ! | -- | ! | 46.70 * |
| Total | | | | | 46.70 dBA | | | | | |

* Bright Zone !

Road data, segment # 1: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

 Angle1 Angle2 : -4.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 186.00 / 186.00 m
 Receiver height : 116.50 / 116.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -4.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 2: Gladstone (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Gladstone (day/night)

 Angle1 Angle2 : 0.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 21.00 / 21.00 m
 Receiver height : 116.50 / 116.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 0.00 deg Angle2 : 90.00 deg

Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 65.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 3: Somerset (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 50 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 3: Somerset (day/night)

 Angle1 Angle2 : 12.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 448.00 / 448.00 m
 Receiver height : 116.50 / 116.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 12.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 62.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Result summary (day)

| | ! source ! | Road | ! Total |
|---------------|------------|-----------|-----------|
| | ! height ! | Leq | ! Leq |
| | ! (m) ! | (dBA) | ! (dBA) |
| 1.Highway 417 | ! 1.50 ! | 72.82 | ! 72.82 * |
| 2.Gladstone | ! 1.50 ! | 62.21 | ! 62.21 * |
| 3.Somerset | ! 1.50 ! | 50.10 | ! 50.10 * |
| | | | |
| | Total | 73.20 dBA | |

* Bright Zone !

Result summary (night)

| ! source | ! Road | ! Total |
|----------|---------|---------|
| ! height | ! Leq | ! Leq |
| ! (m) | ! (dBA) | ! (dBA) |

| | | | | | | |
|---------------|---|-----------|---|-------|---|---------|
| 1.Highway 417 | ! | 1.50 | ! | 65.22 | ! | 65.22 * |
| 2.Gladstone | ! | 1.50 | ! | 54.62 | ! | 54.62 * |
| 3.Somerset | ! | 1.50 | ! | 42.50 | ! | 42.50 * |
| Total | | 65.60 dBA | | | | |

* Bright Zone !

TOTAL Leq FROM ALL SOURCES (DAY): 73.23
(NIGHT): 65.66

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:37:51
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t2_n.te Time Period: Day/Night 16/8 hours
 Description: North facade of Tower 2, 33rd floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !        !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
  1.      ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
  
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : -90.00 deg 25.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 27.00 / 27.00 m
Receiver height  : 110.50 / 110.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : -90.00 deg Angle2 : 25.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
  
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 65.87 ! 53.74 ! -- ! -- ! 66.13 *
-----+-----+-----+-----+-----+-----
Total 66.13 dBA
  
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
  
```

| | | | | | | |
|-----------|---|--------|-----------|-----|-----|--------|
| 1.O-Train | ! | 61.57! | 49.43! | --! | --! | 61.83* |
| Total | | | 61.83 dBA | | | |

* Bright Zone !

Road data, segment # 1: Somerset (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 50 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Somerset (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 367.00 / 367.00 m
 Receiver height : 110.50 / 110.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 21.00 deg Angle2 : 64.00 deg
 Barrier height : 100.00 m
 Barrier receiver distance : 48.00 / 48.00 m
 Source elevation : 62.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Result summary (day)

| | ! | source ! | Road ! | Total |
|------------|---|----------|-----------|-------|
| | ! | height ! | Leq ! | Leq |
| | ! | (m) ! | (dBA) ! | (dBA) |
| 1.Somerset | ! | 1.50! | 53.56! | 53.56 |
| Total | | | 53.56 dBA | |

Result summary (night)

| | ! | source ! | Road ! | Total |
|-------|---|----------|---------|-------|
| | ! | height ! | Leq ! | Leq |
| | ! | (m) ! | (dBA) ! | (dBA) |
| ----- | | | | |

| | | | | | | |
|-------------------------|---|------|---|-----------|---|-------|
| 1.Somerset | ! | 1.50 | ! | 45.96 | ! | 45.96 |
| -----+-----+-----+----- | | | | | | |
| Total | | | | 45.96 dBA | | |

TOTAL Leq FROM ALL SOURCES (DAY): 66.36
(NIGHT): 61.94

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:38:56
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t2_e.te Time Period: Day/Night 16/8 hours
 Description: East facade of Tower 2, 33rd floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type       !        !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
  1.       ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
  
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : -65.00 deg 90.00 deg
Wood depth      :    0 (No woods.)
No of house rows :    0 / 0
Surface         :    1 (Absorptive ground surface)
Receiver source distance : 31.00 / 31.00 m
Receiver height : 110.50 / 110.50 m
Topography      :    2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1  : -65.00 deg Angle2 : 90.00 deg
Barrier height  :    0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle :    0.00
  
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 66.57 ! 54.44 ! -- ! -- ! 66.83 *
-----+-----+-----+-----+-----+-----
Total 66.83 dBA
  
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
  
```

| | | | | | | | | | | |
|-----------|---|-------|---|-------|-----------|----|---|----|---|---------|
| 1.O-Train | ! | 62.26 | ! | 50.13 | ! | -- | ! | -- | ! | 62.52 * |
| Total | | | | | 62.52 dBA | | | | | |

* Bright Zone !

Road data, segment # 1: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

 Angle1 Angle2 : 3.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 244.00 / 244.00 m
 Receiver height : 110.50 / 110.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 3.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 2: Gladstone (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Gladstone (day/night)

 Angle1 Angle2 : -3.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 77.00 / 77.00 m
 Receiver height : 110.50 / 110.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -3.00 deg Angle2 : 90.00 deg

Barrier height : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 65.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle : 0.00

Road data, segment # 3: Somerset (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod
Medium truck volume : 966/84 veh/TimePeriod
Heavy truck volume : 690/60 veh/TimePeriod
Posted speed limit : 50 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 3: Somerset (day/night)

Angle1 Angle2 : 4.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 391.00 / 391.00 m
Receiver height : 110.50 / 110.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 4.00 deg Angle2 : 90.00 deg
Barrier height : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 62.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle : 0.00

Result summary (day)

! source ! Road ! Total
! height ! Leq ! Leq
! (m) ! (dBA) ! (dBA)
-----+-----+-----
1.Highway 417 ! 1.50 ! 71.30 ! 71.30 *
2.Gladstone ! 1.50 ! 56.71 ! 56.71 *
3.Somerset ! 1.50 ! 51.11 ! 51.11 *
-----+-----+-----
Total 71.49 dBA

* Bright Zone !

Result summary (night)

! source ! Road ! Total
! height ! Leq ! Leq
! (m) ! (dBA) ! (dBA)

| | ! | ! | ! | ! |
|---------------|---|------|---|-----------|
| 1.Highway 417 | ! | 1.50 | ! | 63.71 |
| 2.Gladstone | ! | 1.50 | ! | 49.12 |
| 3.Somerset | ! | 1.50 | ! | 43.51 |
| Total | | | | 63.90 dBA |

* Bright Zone !

TOTAL Leq FROM ALL SOURCES (DAY): 72.77
(NIGHT): 66.27

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:39:25
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t2_s.te Time Period: Day/Night 16/8 hours
 Description: South facade of Tower 2, 33rd floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !        !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----
 1.        ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
    
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : 22.00 deg 90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 35.00 / 35.00 m
Receiver height  : 110.50 / 110.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : 22.00 deg Angle2 : 90.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
    
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----
1.O-Train ! 62.47 ! 50.33 ! -- ! -- ! 62.73 *
-----+-----+-----+-----+-----
Total 62.73 dBA
    
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
    
```

| | | | | | | |
|-----------|---|--------|-----------|-----|-----|--------|
| 1.O-Train | ! | 58.16! | 46.02! | --! | --! | 58.42* |
| Total | | | 58.42 dBA | | | |

* Bright Zone !

Road data, segment # 1: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 239.00 / 239.00 m
 Receiver height : 110.50 / 110.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 1.00 deg Angle2 : 49.00 deg
 Barrier height : 118.00 m
 Barrier receiver distance : 54.00 / 54.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 2: Gladstone (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Gladstone (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 76.00 / 76.00 m
 Receiver height : 110.50 / 110.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 7.00 deg Angle2 : 56.00 deg

Barrier height : 118.00 m
 Barrier receiver distance : 54.00 / 54.00 m
 Source elevation : 65.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Result summary (day)

| ! source ! | Road ! | Total |
|------------|---------|-------|
| ! height ! | Leq ! | Leq |
| ! (m) ! | (dBA) ! | (dBA) |

| | | | |
|---------------|----------|-----------|-------|
| 1.Highway 417 | ! 1.50 ! | 73.22 ! | 73.22 |
| 2.Gladstone | ! 1.50 ! | 58.27 ! | 58.27 |
| Total | | 73.36 dBA | |

Result summary (night)

| ! source ! | Road ! | Total |
|------------|---------|-------|
| ! height ! | Leq ! | Leq |
| ! (m) ! | (dBA) ! | (dBA) |

| | | | |
|---------------|----------|-----------|-------|
| 1.Highway 417 | ! 1.50 ! | 65.62 ! | 65.62 |
| 2.Gladstone | ! 1.50 ! | 50.68 ! | 50.68 |
| Total | | 65.76 dBA | |

TOTAL Leq FROM ALL SOURCES (DAY): 73.72
 (NIGHT): 66.49

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:45:52
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t2_w.te Time Period: Day/Night 16/8 hours
 Description: West facade of Tower 2, 33rd floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !       !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
  1.      ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
  
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : 70.00 deg 90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 61.00 / 61.00 m
Receiver height  : 110.50 / 110.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : 70.00 deg Angle2 : 90.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
  
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 54.74 ! 42.61 ! -- ! -- ! 55.00 *
-----+-----+-----+-----+-----+-----
Total 55.00 dBA
  
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
  
```

| | | | | | | | | | | |
|-----------|---|-------|---|-------|-----------|----|---|----|---|---------|
| 1.O-Train | ! | 50.43 | ! | 38.30 | ! | -- | ! | -- | ! | 50.69 * |
| Total | | | | | 50.69 dBA | | | | | |

* Bright Zone !

Road data, segment # 1: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

 Angle1 Angle2 : 5.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 245.00 / 245.00 m
 Receiver height : 110.50 / 110.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 5.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 2: Gladstone (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Gladstone (day/night)

 Angle1 Angle2 : 8.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 77.00 / 77.00 m
 Receiver height : 110.50 / 110.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 8.00 deg Angle2 : 90.00 deg

Barrier height : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 65.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle : 0.00

Road data, segment # 3: Somerset (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod
Medium truck volume : 966/84 veh/TimePeriod
Heavy truck volume : 690/60 veh/TimePeriod
Posted speed limit : 50 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 3: Somerset (day/night)

Angle1 Angle2 : 0.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 391.00 / 391.00 m
Receiver height : 110.50 / 110.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 0.00 deg Angle2 : 90.00 deg
Barrier height : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 62.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle : 0.00

Result summary (day)

! source ! Road ! Total
! height ! Leq ! Leq
! (m) ! (dBA) ! (dBA)
-----+-----+-----+-----
1.Highway 417 ! 1.50 ! 71.19 ! 71.19 *
2.Gladstone ! 1.50 ! 56.17 ! 56.17 *
3.Somerset ! 1.50 ! 51.31 ! 51.31 *
-----+-----+-----+-----
Total 71.37 dBA

* Bright Zone !

Result summary (night)

| ! source | ! Road | ! Total |
|----------|---------|---------|
| ! height | ! Leq | ! Leq |
| ! (m) | ! (dBA) | ! (dBA) |

| | | | | | | |
|---------------|---|-----------|---|-------|---|---------|
| 1.Highway 417 | ! | 1.50 | ! | 63.59 | ! | 63.59 * |
| 2.Gladstone | ! | 1.50 | ! | 48.57 | ! | 48.57 * |
| 3.Somerset | ! | 1.50 | ! | 43.71 | ! | 43.71 * |
| Total | | 63.77 dBA | | | | |

* Bright Zone !

TOTAL Leq FROM ALL SOURCES (DAY): 71.47
(NIGHT): 63.98

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:48:43
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t3_n.te Time Period: Day/Night 16/8 hours
 Description: North facade of Tower 3, 30th floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !      ! (km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
 1.       ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
    
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : -90.00 deg 22.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 30.00 / 30.00 m
Receiver height  : 98.50 / 98.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : -90.00 deg Angle2 : 22.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
    
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 65.30 ! 53.17 ! -- ! -- ! 65.56 *
-----+-----+-----+-----+-----+-----
Total 65.56 dBA
    
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
    
```


| | | | | | | | | | | |
|-----------|---|-------|---|-------|-----------|----|---|----|---|---------|
| 1.O-Train | ! | 60.99 | ! | 48.86 | ! | -- | ! | -- | ! | 61.25 * |
| Total | | | | | 61.25 dBA | | | | | |

* Bright Zone !

Road data, segment # 1: Somerset (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 50 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Somerset (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 319.00 / 319.00 m
 Receiver height : 98.50 / 98.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -43.00 deg Angle2 : 11.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 53.00 / 53.00 m
 Source elevation : 62.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Result summary (day)

| | ! | source | ! | Road | ! | Total |
|------------|---|--------|---|-------|-----------|---------|
| | ! | height | ! | Leq | ! | Leq |
| | ! | (m) | ! | (dBA) | ! | (dBA) |
| 1.Somerset | ! | 1.50 | ! | 55.20 | ! | 55.20 * |
| Total | | | | | 55.20 dBA | |

* Bright Zone !

Result summary (night)

 ! source ! Road ! Total
 ! height ! Leq ! Leq

! (m) ! (dBA) ! (dBA)

| | ! (m) | ! (dBA) | ! (dBA) |
|------------|-------|-----------|-----------------|
| 1.Somerset | ! | 1.50 ! | 47.61 ! 47.61 * |
| Total | | 47.61 dBA | |

* Bright Zone !

TOTAL Leq FROM ALL SOURCES (DAY): 65.94
(NIGHT): 61.43

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:49:05
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t3_e.te Time Period: Day/Night 16/8 hours
 Description: East facade of Tower 3, 30th floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !       !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
  1.      ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
  
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : -90.00 deg 90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 30.00 / 30.00 m
Receiver height  : 98.50 / 98.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : -90.00 deg Angle2 : 90.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
  
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 67.36 ! 55.23 ! -- ! -- ! 67.62 *
-----+-----+-----+-----+-----+-----
Total 67.62 dBA
  
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
  
```

| | | | | | | | | | | |
|-----------|---|-------|---|-------|-----------|----|---|----|---|---------|
| 1.O-Train | ! | 63.05 | ! | 50.92 | ! | -- | ! | -- | ! | 63.31 * |
| Total | | | | | 63.31 dBA | | | | | |

* Bright Zone !

Road data, segment # 1: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

 Angle1 Angle2 : 19.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 306.00 / 306.00 m
 Receiver height : 98.50 / 98.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 19.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 2: Gladstone (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Gladstone (day/night)

 Angle1 Angle2 : 16.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 141.00 / 141.00 m
 Receiver height : 98.50 / 98.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 16.00 deg Angle2 : 90.00 deg

Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 65.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 3: Somerset (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 50 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 3: Somerset (day/night)

 Angle1 Angle2 : -16.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 328.00 / 328.00 m
 Receiver height : 98.50 / 98.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -16.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 62.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Result summary (day)

| | ! source ! | Road | ! Total |
|---------------|------------|-----------|-----------|
| | ! height ! | Leq | ! Leq |
| | ! (m) ! | (dBA) | ! (dBA) |
| 1.Highway 417 | ! 1.50 ! | 69.44 | ! 69.44 * |
| 2.Gladstone | ! 1.50 ! | 53.09 | ! 53.09 * |
| 3.Somerset | ! 1.50 ! | 52.78 | ! 52.78 * |
| Total | | 69.63 dBA | |

* Bright Zone !

Result summary (night)

| ! source ! | Road | Total |
|------------|-------|-------|
| ! height ! | Leq | Leq |
| ! (m) ! | (dBA) | (dBA) |

| | | | |
|---------------|----------|-----------|---------|
| 1.Highway 417 | ! 1.50 ! | 61.84 ! | 61.84 * |
| 2.Gladstone | ! 1.50 ! | 45.50 ! | 45.50 * |
| 3.Somerset | ! 1.50 ! | 45.19 ! | 45.19 * |
| Total | | 62.03 dBA | |

* Bright Zone !

TOTAL Leq FROM ALL SOURCES (DAY): 71.75
(NIGHT): 65.73

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:49:37
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t3_s.te Time Period: Day/Night 16/8 hours
 Description: South facade of Tower 3, 30th floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !        !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
  1.      ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
  
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : 21.00 deg 90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 37.00 / 37.00 m
Receiver height  : 98.50 / 98.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : 21.00 deg Angle2 : 90.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
  
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 62.29 ! 50.16 ! -- ! -- ! 62.55 *
-----+-----+-----+-----+-----+-----
Total 62.55 dBA
  
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
  
```

| | | | | | | | | | | |
|-----------|---|-------|---|-------|-----------|----|---|----|---|---------|
| 1.O-Train | ! | 57.98 | ! | 45.85 | ! | -- | ! | -- | ! | 58.24 * |
| Total | | | | | 58.24 dBA | | | | | |

* Bright Zone !

Road data, segment # 1: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 292.00 / 292.00 m
 Receiver height : 98.50 / 98.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -43.00 deg Angle2 : 11.00 deg
 Barrier height : 112.00 m
 Barrier receiver distance : 53.00 / 53.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 2: Gladstone (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Gladstone (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 126.00 / 126.00 m
 Receiver height : 98.50 / 98.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -40.00 deg Angle2 : 14.00 deg

Barrier height : 112.00 m
 Barrier receiver distance : 53.00 / 53.00 m
 Source elevation : 65.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Result summary (day)

| ! source ! | Road ! | Total |
|------------|---------|-------|
| ! height ! | Leq ! | Leq |
| ! (m) ! | (dBA) ! | (dBA) |

| | | | |
|---------------|----------|-----------|-------|
| 1.Highway 417 | ! 1.50 ! | 72.15 ! | 72.15 |
| 2.Gladstone | ! 1.50 ! | 55.91 ! | 55.91 |
| Total | | 72.25 dBA | |

Result summary (night)

| ! source ! | Road ! | Total |
|------------|---------|-------|
| ! height ! | Leq ! | Leq |
| ! (m) ! | (dBA) ! | (dBA) |

| | | | |
|---------------|----------|-----------|-------|
| 1.Highway 417 | ! 1.50 ! | 64.55 ! | 64.55 |
| 2.Gladstone | ! 1.50 ! | 48.32 ! | 48.32 |
| Total | | 64.65 dBA | |

TOTAL Leq FROM ALL SOURCES (DAY): 72.69
 (NIGHT): 65.55

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:50:38
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: t3_w.te Time Period: Day/Night 16/8 hours
 Description: West facade of Tower 3, 30th floor

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !       !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
  1.      ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
    
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : 68.00 deg 90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 66.00 / 66.00 m
Receiver height  : 98.50 / 98.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1   : 68.00 deg Angle2 : 90.00 deg
Barrier height   : 0.00 m
Barrier receiver distance : 10.00 / 10.00 m
Source elevation : 57.00 m
Receiver elevation : 65.00 m
Barrier elevation : 65.00 m
Reference angle  : 0.00
    
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 54.81 ! 42.68 ! -- ! -- ! 55.07 *
-----+-----+-----+-----+-----+-----
Total 55.07 dBA
    
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
    
```

| | | | | | | | | | | |
|-----------|---|-------|---|-------|-----------|----|---|----|---|---------|
| 1.O-Train | ! | 50.50 | ! | 38.37 | ! | -- | ! | -- | ! | 50.76 * |
| Total | | | | | 50.76 dBA | | | | | |

* Bright Zone !

Road data, segment # 1: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

 Angle1 Angle2 : -3.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 297.00 / 297.00 m
 Receiver height : 98.50 / 98.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -3.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 2: Gladstone (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 40 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Gladstone (day/night)

 Angle1 Angle2 : 0.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 133.00 / 133.00 m
 Receiver height : 98.50 / 98.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 0.00 deg Angle2 : 90.00 deg

Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 65.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Road data, segment # 3: Somerset (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 50 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 3: Somerset (day/night)

 Angle1 Angle2 : 0.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 336.00 / 336.00 m
 Receiver height : 98.50 / 98.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 0.00 deg Angle2 : 90.00 deg
 Barrier height : 0.00 m
 Barrier receiver distance : 10.00 / 10.00 m
 Source elevation : 62.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 65.00 m
 Reference angle : 0.00

Result summary (day)

| | ! source ! | Road | ! Total |
|---------------|------------|-----------|-----------|
| | ! height ! | Leq | ! Leq |
| | ! (m) ! | ! (dBA) ! | ! (dBA) |
| 1.Highway 417 | ! 1.50 ! | 70.74 | ! 70.74 * |
| 2.Gladstone | ! 1.50 ! | 54.20 | ! 54.20 * |
| 3.Somerset | ! 1.50 ! | 51.97 | ! 51.97 * |
| Total | | 70.89 dBA | |

* Bright Zone !

Result summary (night)

| ! source ! | Road ! | Total |
|------------|---------|-------|
| ! height ! | Leq ! | Leq |
| ! (m) ! | (dBA) ! | (dBA) |

| | | | | |
|---------------|---|--------|-----------|---------|
| 1.Highway 417 | ! | 1.50 ! | 63.14 ! | 63.14 * |
| 2.Gladstone | ! | 1.50 ! | 46.60 ! | 46.60 * |
| 3.Somerset | ! | 1.50 ! | 44.37 ! | 44.37 * |
| Total | | | 63.29 dBA | |

* Bright Zone !

TOTAL Leq FROM ALL SOURCES (DAY): 71.00
(NIGHT): 63.53

STAMSON 5.0 SUMMARY REPORT Date: 24-01-2022 16:31:53
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: ola1.te Time Period: Day/Night 16/8 hours
Description: OLA on podium roof, west of Tower 1

Road data, segment # 1: Highway 417 (day/night)

Car traffic volume : 195613/17010 veh/TimePeriod
Medium truck volume : 15560/1353 veh/TimePeriod
Heavy truck volume : 11114/966 veh/TimePeriod
Posted speed limit : 100 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

Angle1 Angle2 : -34.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 204.00 / 204.00 m
Receiver height : 1.50 / 1.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -34.00 deg Angle2 : 90.00 deg
Barrier height : 1.10 m
Barrier receiver distance : 21.00 / 21.00 m
Source elevation : 72.00 m
Receiver elevation : 85.00 m
Barrier elevation : 85.00 m
Reference angle : 0.00

Road data, segment # 2: Gladstone (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod
Medium truck volume : 966/84 veh/TimePeriod
Heavy truck volume : 690/60 veh/TimePeriod
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Gladstone (day/night)

Angle1 Angle2 : -31.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 40.00 / 40.00 m
Receiver height : 1.50 / 1.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -31.00 deg Angle2 : 90.00 deg

Barrier height : 1.10 m
 Barrier receiver distance : 21.00 / 21.00 m
 Source elevation : 65.00 m
 Receiver elevation : 85.00 m
 Barrier elevation : 85.00 m
 Reference angle : 0.00

Road data, segment # 3: Somerset (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 50 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 3: Somerset (day/night)

 Angle1 Angle2 : 5.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 1 (Absorptive ground surface)
 Receiver source distance : 435.00 / 435.00 m
 Receiver height : 1.50 / 1.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 5.00 deg Angle2 : 90.00 deg
 Barrier height : 1.10 m
 Barrier receiver distance : 22.00 / 22.00 m
 Source elevation : 62.00 m
 Receiver elevation : 85.00 m
 Barrier elevation : 85.00 m
 Reference angle : 0.00

Result summary (day)

| | ! source | ! Road | ! Total |
|---------------|----------|-----------|---------|
| | ! height | ! Leq | ! Leq |
| | ! (m) | ! (dBA) | ! (dBA) |
| 1.Highway 417 | ! 1.50 | ! 60.09 | ! 60.09 |
| 2.Gladstone | ! 1.50 | ! 42.90 | ! 42.90 |
| 3.Somerset | ! 1.50 | ! 35.04 | ! 35.04 |
| Total | | 60.19 dBA | |

Result summary (night)

| | ! source | ! Road | ! Total |
|--|----------|--------|---------|
| | ! height | ! Leq | ! Leq |

! (m) ! (dBA) ! (dBA)

| | ! | (m) | ! | (dBA) | ! | (dBA) |
|---------------|---|-----------|---|-------|---|-------|
| 1.Highway 417 | ! | 1.50 | ! | 52.49 | ! | 52.49 |
| 2.Gladstone | ! | 1.50 | ! | 35.30 | ! | 35.30 |
| 3.Somerset | ! | 1.50 | ! | 27.44 | ! | 27.44 |
| Total | | 52.59 dBA | | | | |

TOTAL Leq FROM ALL SOURCES (DAY): 60.19
(NIGHT): 52.59

STAMSON 5.0 SUMMARY REPORT Date: 02-02-2022 14:32:28
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: ola2.te Time Period: Day/Night 16/8 hours
 Description: OLA on podium roof, between T1 and T2

Rail data, segment # 1: O-Train (day/night)

```

-----
Train      ! Trains  ! Speed !# loc !# Cars! Eng !Cont
Type      !       !(km/h) !/Train!/Train! type !weld
-----+-----+-----+-----+-----+-----+-----
  1.      ! 205.0/38.0 ! 35.0 ! 1.0 ! 3.0 !Diesel! Yes
  
```

Data for Segment # 1: O-Train (day/night)

```

-----
Angle1 Angle2      : -20.00 deg 70.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 1 (Absorptive ground surface)
Receiver source distance : 53.00 / 53.00 m
Receiver height : 1.50 / 1.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
No Whistle
Barrier angle1  : -20.00 deg Angle2 : 70.00 deg
Barrier height   : 1.10 m
Barrier receiver distance : 16.00 / 16.00 m
Source elevation : 57.00 m
Receiver elevation : 85.00 m
Barrier elevation : 85.00 m
Reference angle  : 0.00
  
```

Result summary (day)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
-----+-----+-----+-----+-----+-----
1.O-Train ! 39.48 ! 26.24 ! -- ! -- ! 39.68 *
-----+-----+-----+-----+-----+-----
Total 39.68 dBA
  
```

* Bright Zone !

Result summary (night)

```

-----
! Loc ! Wheel ! Whistle ! Whistle ! Total
! Leq ! Leq ! Left Leq ! Right Leq! Leq
! (dBA) ! (dBA) ! (dBA) ! (dBA) ! (dBA)
  
```

| | | | | | | |
|-----------|---|--------|-----------|-----|-----|--------|
| 1.O-Train | ! | 35.17! | 21.93! | --! | --! | 35.37* |
| Total | | | 35.37 dBA | | | |

* Bright Zone !

Road data, segment # 1: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417 (day/night)

 Angle1 Angle2 : 50.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 1 (Absorptive ground surface)
 Receiver source distance : 226.00 / 226.00 m
 Receiver height : 1.50 / 1.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 50.00 deg Angle2 : 90.00 deg
 Barrier height : 1.10 m
 Barrier receiver distance : 31.00 / 31.00 m
 Source elevation : 72.00 m
 Receiver elevation : 85.00 m
 Barrier elevation : 85.00 m
 Reference angle : 0.00

Road data, segment # 2: Highway 417 (day/night)

 Car traffic volume : 195613/17010 veh/TimePeriod
 Medium truck volume : 15560/1353 veh/TimePeriod
 Heavy truck volume : 11114/966 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Highway 417 (day/night)

 Angle1 Angle2 : -90.00 deg -43.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 1 (Absorptive ground surface)
 Receiver source distance : 226.00 / 226.00 m
 Receiver height : 1.50 / 1.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -90.00 deg Angle2 : -43.00 deg

Barrier height : 1.10 m
Barrier receiver distance : 17.00 / 17.00 m
Source elevation : 72.00 m
Receiver elevation : 85.00 m
Barrier elevation : 85.00 m
Reference angle : 0.00

Road data, segment # 3: Gladstone (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod
Medium truck volume : 966/84 veh/TimePeriod
Heavy truck volume : 690/60 veh/TimePeriod
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 3: Gladstone (day/night)

Angle1 Angle2 : 53.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 60.00 / 60.00 m
Receiver height : 1.50 / 1.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 53.00 deg Angle2 : 90.00 deg
Barrier height : 1.10 m
Barrier receiver distance : 31.00 / 31.00 m
Source elevation : 65.00 m
Receiver elevation : 85.00 m
Barrier elevation : 85.00 m
Reference angle : 0.00

Road data, segment # 4: Gladstone (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod
Medium truck volume : 966/84 veh/TimePeriod
Heavy truck volume : 690/60 veh/TimePeriod
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 4: Gladstone (day/night)

Angle1 Angle2 : -90.00 deg -40.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 60.00 / 60.00 m
Receiver height : 1.50 / 1.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : -40.00 deg

Barrier height : 1.10 m
 Barrier receiver distance : 17.00 / 17.00 m
 Source elevation : 65.00 m
 Receiver elevation : 85.00 m
 Barrier elevation : 85.00 m
 Reference angle : 0.00

Road data, segment # 5: Somerset (day/night)

 Car traffic volume : 12144/1056 veh/TimePeriod
 Medium truck volume : 966/84 veh/TimePeriod
 Heavy truck volume : 690/60 veh/TimePeriod
 Posted speed limit : 50 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 5: Somerset (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 408.00 / 408.00 m
 Receiver height : 1.50 / 1.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -90.00 deg Angle2 : 90.00 deg
 Barrier height : 1.10 m
 Barrier receiver distance : 12.00 / 12.00 m
 Source elevation : 62.00 m
 Receiver elevation : 85.00 m
 Barrier elevation : 85.00 m
 Reference angle : 0.00

Result summary (day)

| | ! source | ! Road | ! Total |
|--|----------|---------|---------|
| | ! height | ! Leq | ! Leq |
| | ! (m) | ! (dBA) | ! (dBA) |

| | | | | |
|-------------------------|---|--------|---------|-----------|
| 1.Highway 417 | ! | 1.50 ! | 52.63 ! | 52.63 |
| 2.Highway 417 | ! | 1.50 ! | 54.09 ! | 54.09 |
| 3.Gladstone | ! | 1.50 ! | 32.79 ! | 32.79 |
| 4.Gladstone | ! | 1.50 ! | 37.04 ! | 37.04 |
| 5.Somerset | ! | 1.50 ! | 49.03 ! | 49.03 |
| -----+-----+-----+----- | | | | |
| Total | | | | 57.21 dBA |

Result summary (night)

| ! source | ! Road | ! Total |
|----------|---------|---------|
| ! height | ! Leq | ! Leq |
| ! (m) | ! (dBA) | ! (dBA) |

| | | | | | | |
|---------------|---|-----------|---|-------|---|-------|
| 1.Highway 417 | ! | 1.50 | ! | 45.04 | ! | 45.04 |
| 2.Highway 417 | ! | 1.50 | ! | 46.49 | ! | 46.49 |
| 3.Gladstone | ! | 1.50 | ! | 25.20 | ! | 25.20 |
| 4.Gladstone | ! | 1.50 | ! | 29.44 | ! | 29.44 |
| 5.Somerset | ! | 1.50 | ! | 41.43 | ! | 41.43 |
| Total | | 49.62 dBA | | | | |

TOTAL Leq FROM ALL SOURCES (DAY): 57.29
 (NIGHT): 49.78

STAMSON 5.0 SUMMARY REPORT Date: 25-01-2022 21:25:20
 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: por1d.te Time Period: 1 hours
 Description: Minimum day hour, south facade T1, 6th floor

Road data, segment # 1: Highway 417

Car traffic volume : 2713 veh/TimePeriod
 Medium truck volume : 216 veh/TimePeriod
 Heavy truck volume : 154 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417

Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 186.00 m
 Receiver height : 22.25 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -90.00 deg Angle2 : 90.00 deg
 Barrier height : 4.00 m
 Barrier receiver distance : 165.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 72.00 m
 Reference angle : 0.00

Result summary

| | ! source ! | Road ! | Total |
|---------------|------------|-----------|-------|
| | ! height ! | Leq ! | Leq |
| | ! (m) ! | (dBA) ! | (dBA) |
| 1.Highway 417 | ! 1.49 ! | 63.36 ! | 63.36 |
| Total | | 63.36 dBA | |

TOTAL Leq FROM ALL SOURCES: 63.36

Filename: por1n.te Time Period: 1 hours
Description: Minimum night hour, south facade T1, 6th floor

Road data, segment # 1: Highway 417

Car traffic volume : 440 veh/TimePeriod
Medium truck volume : 35 veh/TimePeriod
Heavy truck volume : 25 veh/TimePeriod
Posted speed limit : 100 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 186.00 m
Receiver height : 22.25 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 90.00 deg
Barrier height : 4.00 m
Barrier receiver distance : 165.00 m
Source elevation : 72.00 m
Receiver elevation : 65.00 m
Barrier elevation : 72.00 m
Reference angle : 0.00

Result summary

| ! source ! | Road ! | Total |
|------------|---------|-------|
| ! height ! | Leq ! | Leq |
| ! (m) ! | (dBA) ! | (dBA) |

| | | | |
|---------------|----------|---------|-------|
| 1.Highway 417 | ! 1.50 ! | 55.47 ! | 55.47 |
|---------------|----------|---------|-------|

| | | | |
|-------|--|-----------|--|
| Total | | 55.47 dBA | |
|-------|--|-----------|--|

TOTAL Leq FROM ALL SOURCES: 55.47

Filename: por2d.te Time Period: 1 hours
 Description: Minimum day hour, east facade T1, 7th floor

Road data, segment # 1: Highway 417

 Car traffic volume : 2713 veh/TimePeriod
 Medium truck volume : 216 veh/TimePeriod
 Heavy truck volume : 154 veh/TimePeriod
 Posted speed limit : 100 km/h
 Road gradient : 0 %
 Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417

 Angle1 Angle2 : 2.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 192.00 m
 Receiver height : 22.25 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : 2.00 deg Angle2 : 90.00 deg
 Barrier height : 4.00 m
 Barrier receiver distance : 172.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 72.00 m
 Reference angle : 0.00

Result summary

| | | |
|----------|---------|---------|
| ! source | ! Road | ! Total |
| ! height | ! Leq | ! Leq |
| ! (m) | ! (dBA) | ! (dBA) |

-----+-----+-----+-----

| | | | | | | |
|---------------|---|------|---|-------|---|-------|
| 1.Highway 417 | ! | 1.49 | ! | 59.92 | ! | 59.92 |
|---------------|---|------|---|-------|---|-------|

-----+-----+-----+-----

| | | | |
|-------|--|-------|-----|
| Total | | 59.92 | dBA |
|-------|--|-------|-----|

TOTAL Leq FROM ALL SOURCES: 59.92

Filename: por2n.te Time Period: 1 hours
Description: Minimum night hour, east facade T1, 7th floor

Road data, segment # 1: Highway 417

Car traffic volume : 440 veh/TimePeriod
Medium truck volume : 35 veh/TimePeriod
Heavy truck volume : 25 veh/TimePeriod
Posted speed limit : 100 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417

Angle1 Angle2 : 2.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 192.00 m
Receiver height : 22.25 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 2.00 deg Angle2 : 90.00 deg
Barrier height : 4.00 m
Barrier receiver distance : 172.00 m
Source elevation : 72.00 m
Receiver elevation : 65.00 m
Barrier elevation : 72.00 m
Reference angle : 0.00

Result summary

| ! source ! | Road ! | Total |
|------------|---------|-------|
| ! height ! | Leq ! | Leq |
| ! (m) ! | (dBA) ! | (dBA) |

| | | | |
|---------------|----------|---------|-------|
| 1.Highway 417 | ! 1.50 ! | 52.02 ! | 52.02 |
|---------------|----------|---------|-------|

| | | | |
|-------|--|-----------|--|
| Total | | 52.02 dBA | |
|-------|--|-----------|--|

TOTAL Leq FROM ALL SOURCES: 52.02

STAMSON 5.0 SUMMARY REPORT Date: 28-01-2022 14:13:27
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: por3d.te Time Period: 1 hours
Description: Minimum dau hour, south facade T2, 11th floor

Road data, segment # 1: Highway 417

Car traffic volume : 2713 veh/TimePeriod
Medium truck volume : 216 veh/TimePeriod
Heavy truck volume : 154 veh/TimePeriod
Posted speed limit : 100 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417

Angle1 Angle2 : -90.00 deg -48.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 239.00 m
Receiver height : 40.25 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : -48.00 deg
Barrier height : 4.00 m
Barrier receiver distance : 219.00 m
Source elevation : 72.00 m
Receiver elevation : 65.00 m
Barrier elevation : 72.00 m
Reference angle : 0.00

Road data, segment # 2: Highway 417

Car traffic volume : 2713 veh/TimePeriod
Medium truck volume : 216 veh/TimePeriod
Heavy truck volume : 154 veh/TimePeriod
Posted speed limit : 100 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Highway 417

Angle1 Angle2 : 2.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 239.00 m
Receiver height : 22.25 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 2.00 deg Angle2 : 90.00 deg

Barrier height : 4.00 m
 Barrier receiver distance : 219.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 72.00 m
 Reference angle : 0.00

Result summary

| ! source ! | Road | ! Total |
|------------|-------|---------|
| ! height ! | Leq | ! Leq |
| ! (m) ! | (dBA) | ! (dBA) |

| | | | | |
|-------------------------|---|--------|-----------|---------|
| -----+-----+-----+----- | | | | |
| 1.Highway 417 | ! | 1.49 ! | 61.69 ! | 61.69 * |
| 2.Highway 417 | ! | 1.49 ! | 58.53 ! | 58.53 |
| -----+-----+-----+----- | | | | |
| | | Total | 63.40 dBA | |

TOTAL Leq FROM ALL SOURCES: 63.40

STAMSON 5.0 SUMMARY REPORT Date: 28-01-2022 14:12:16
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: por3n.te Time Period: 1 hours
Description: Minimum night hour, south facade T2, 11th floor

Road data, segment # 1: Highway 417

Car traffic volume : 440 veh/TimePeriod
Medium truck volume : 35 veh/TimePeriod
Heavy truck volume : 25 veh/TimePeriod
Posted speed limit : 100 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 1: Highway 417

Angle1 Angle2 : -90.00 deg -48.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 239.00 m
Receiver height : 40.25 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : -48.00 deg
Barrier height : 4.00 m
Barrier receiver distance : 219.00 m
Source elevation : 72.00 m
Receiver elevation : 65.00 m
Barrier elevation : 72.00 m
Reference angle : 0.00

Road data, segment # 2: Highway 417

Car traffic volume : 440 veh/TimePeriod
Medium truck volume : 35 veh/TimePeriod
Heavy truck volume : 25 veh/TimePeriod
Posted speed limit : 100 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

Data for Segment # 2: Highway 417

Angle1 Angle2 : 2.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 239.00 m
Receiver height : 22.25 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 2.00 deg Angle2 : 90.00 deg

Barrier height : 4.00 m
 Barrier receiver distance : 219.00 m
 Source elevation : 72.00 m
 Receiver elevation : 65.00 m
 Barrier elevation : 72.00 m
 Reference angle : 0.00

Result summary

| ! source ! | Road | ! Total |
|------------|-------|---------|
| ! height ! | Leq | ! Leq |
| ! (m) ! | (dBA) | ! (dBA) |

| -----+-----+-----+----- | | | |
|-------------------------|---|-----------|-----------------|
| 1.Highway 417 | ! | 1.50 ! | 53.79 ! 53.79 * |
| 2.Highway 417 | ! | 1.50 ! | 50.63 ! 50.63 |
| -----+-----+-----+----- | | | |
| Total | | 55.50 dBA | |

TOTAL Leq FROM ALL SOURCES: 55.50

Appendix C

Road and Rail Traffic Data

| Highway | Location Description | Dist. (KM) | Year | Pattern Type | AADT | SADT | SAWDT | WADT | AR |
|---------|---------------------------|---------------|------|-----------------|---------|---------|---------|---------|-----|
| | | | 1994 | UC | 124,300 | 131,800 | 144,200 | 113,100 | 0.6 |
| | | | 1995 | UC | 128,600 | 133,700 | 146,600 | 119,600 | 0.7 |
| | | | 1996 | UC | 132,900 | 141,400 | 155,500 | 126,300 | 0.2 |
| | | | 1997 | UC | 137,200 | 144,100 | 160,500 | 129,000 | 0.6 |
| | | | 1998 | UC | 141,500 | 150,600 | 165,600 | 134,400 | 0.4 |
| | | | 1999 | UC | 138,400 | 147,300 | 161,900 | 131,500 | 0.5 |
| | | | 2000 | UC | 140,500 | 149,500 | 165,500 | 132,100 | 0.4 |
| | | | 2001 | UC | 142,500 | 152,500 | 168,200 | 134,000 | 0.4 |
| | | | 2002 | UC | 144,600 | 154,100 | 170,100 | 135,400 | 0.4 |
| | | | 2003 | UC | 143,400 | 152,000 | 169,200 | 134,800 | 0.4 |
| | | | 2004 | UC | 145,000 | 153,200 | 169,900 | 137,000 | 0.5 |
| | | | 2005 | UC | 149,400 | 158,100 | 174,700 | 140,100 | 0.6 |
| | | | 2006 | UC | 151,300 | 160,000 | 176,800 | 142,400 | 0.3 |
| | | | 2007 | UC | 153,200 | 162,500 | 177,300 | 143,700 | 0.5 |
| | | | 2008 | UC | 155,100 | 163,800 | 153,800 | 145,100 | 0.5 |
| | | | 2009 | UC | 157,000 | 165,800 | 182,900 | 147,700 | 0.5 |
| | | | 2010 | UC | 158,900 | 168,000 | 184,900 | 149,400 | 0.4 |
| | | | 2011 | UC | 160,800 | 160,800 | 165,600 | 152,700 | N/A |
| | | | 2012 | UC | 162,600 | 162,600 | 174,000 | 154,500 | N/A |
| | | | 2013 | UC | 164,500 | 164,500 | 166,200 | 156,300 | N/A |
| | | | 2014 | UC | 166,400 | 166,400 | 159,800 | 158,100 | N/A |
| | | | 2015 | UC | 168,300 | 168,300 | 161,600 | 159,900 | N/A |
| | | | 2016 | UC | 170,200 | 170,200 | 163,400 | 161,700 | N/A |
| 417 | BRONSON AV IC-121A-OTTAWA | 0.5 | 1988 | UC | 105,600 | 110,800 | 119,300 | 99,200 | 1.2 |
| | | | 1989 | UC | 111,300 | 116,800 | 125,700 | 105,600 | 1.2 |
| | | | 1990 | UC | 117,900 | 126,100 | 136,700 | 112,000 | 0.7 |
| | | | 1991 | UC | 120,000 | 127,100 | 137,900 | 116,400 | 1.2 |
| | | | 1992 | UC | 121,100 | 128,300 | 139,200 | 116,200 | 1.3 |
| | | | 1993 | UC | 122,000 | 126,800 | 137,800 | 113,400 | 1.0 |
| | | | 1994 | UC | 131,900 | 139,800 | 153,000 | 120,000 | 1.1 |
| | | | 1995 | UC | 136,700 | 142,200 | 155,800 | 127,100 | 1.0 |
| | | | 1996 | UC | 141,500 | 150,600 | 165,600 | 134,400 | 0.7 |
| | | | 1997 | UC | 146,200 | 153,500 | 171,100 | 137,400 | 1.1 |

| Highway | Location Description | Dist. (KM) | Year | Pattern Type | AADT | SADT | SAWDT | WADT | AR |
|---------|-----------------------------|---------------|------|-----------------|---------|---------|---------|---------|-----|
| | | | 1998 | UC | 151,000 | 160,700 | 176,700 | 143,500 | 0.8 |
| | | | 1999 | UC | 145,700 | 155,000 | 170,500 | 138,400 | 0.9 |
| | | | 2000 | UC | 147,400 | 156,800 | 173,600 | 138,600 | 1.1 |
| | | | 2001 | UC | 149,100 | 159,500 | 175,900 | 140,200 | 0.9 |
| | | | 2002 | UC | 150,800 | 160,700 | 177,400 | 141,200 | 0.8 |
| | | | 2003 | UC | 148,100 | 157,000 | 174,800 | 139,200 | 1.4 |
| | | | 2004 | UC | 151,000 | 159,600 | 176,900 | 142,600 | 1.1 |
| | | | 2005 | UC | 154,700 | 163,700 | 180,900 | 145,100 | 1.0 |
| | | | 2006 | UC | 156,300 | 165,300 | 182,600 | 147,100 | 1.0 |
| | | | 2007 | UC | 157,800 | 167,400 | 182,600 | 148,000 | 0.8 |
| | | | 2008 | UC | 159,400 | 168,400 | 158,100 | 149,100 | 1.1 |
| | | | 2009 | UC | 160,900 | 169,900 | 187,500 | 151,400 | 1.1 |
| | | | 2010 | UC | 162,500 | 171,800 | 189,100 | 152,800 | 0.8 |
| | | | 2011 | UC | 164,000 | 164,000 | 169,000 | 155,800 | N/A |
| | | | 2012 | UC | 165,600 | 165,600 | 177,200 | 157,300 | N/A |
| | | | 2013 | UC | 167,200 | 167,200 | 168,800 | 158,800 | N/A |
| | | | 2014 | UC | 168,700 | 168,700 | 162,000 | 160,300 | N/A |
| | | | 2015 | UC | 170,300 | 170,300 | 163,500 | 161,800 | N/A |
| | | | 2016 | UC | 171,800 | 171,800 | 165,000 | 163,200 | N/A |
| 417 | ROCHESTER ST IC-121B-OTTAWA | 1.5 | 1988 | UC | 114,400 | 120,100 | 129,200 | 107,500 | 0.8 |
| | | | 1989 | UC | 120,600 | 126,500 | 136,200 | 114,500 | 1.2 |
| | | | 1990 | UC | 127,600 | 136,500 | 148,000 | 121,200 | 0.4 |
| | | | 1991 | UC | 130,000 | 137,700 | 149,400 | 126,100 | 0.9 |
| | | | 1992 | UC | 130,800 | 138,500 | 150,300 | 125,500 | 1.2 |
| | | | 1993 | UC | 131,000 | 136,200 | 148,000 | 121,800 | 1.4 |
| | | | 1994 | UC | 143,100 | 151,700 | 166,000 | 130,200 | 0.7 |
| | | | 1995 | UC | 148,500 | 154,400 | 169,300 | 138,100 | 0.7 |
| | | | 1996 | UC | 153,800 | 163,600 | 179,900 | 146,100 | 0.5 |
| | | | 1997 | UC | 159,200 | 167,200 | 186,300 | 149,600 | 0.8 |
| | | | 1998 | UC | 164,500 | 175,000 | 192,500 | 156,300 | 0.5 |
| | | | 1999 | UC | 158,200 | 168,300 | 185,100 | 150,300 | 0.5 |
| | | | 2000 | UC | 160,000 | 170,200 | 188,500 | 150,400 | 0.5 |
| | | | 2001 | UC | 161,800 | 173,100 | 190,900 | 152,100 | 0.5 |

| Highway | Location Description | Dist. (KM) | Year | Pattern Type | AADT | SADT | SAWDT | WADT | AR |
|---------|---------------------------|---------------|------|-----------------|---------|---------|---------|---------|-----|
| | | | 2002 | UC | 163,500 | 174,200 | 192,300 | 153,100 | 0.5 |
| | | | 2003 | UC | 160,200 | 169,800 | 189,000 | 150,600 | 0.6 |
| | | | 2004 | UC | 162,000 | 171,200 | 189,800 | 153,000 | 0.6 |
| | | | 2005 | UC | 167,000 | 176,700 | 195,300 | 156,600 | 0.4 |
| | | | 2006 | UC | 168,600 | 178,300 | 197,000 | 158,700 | 0.4 |
| | | | 2007 | UC | 170,100 | 180,400 | 196,900 | 159,600 | 0.5 |
| | | | 2008 | UC | 171,700 | 181,400 | 170,300 | 160,600 | 0.6 |
| | | | 2009 | UC | 173,200 | 182,900 | 201,800 | 163,000 | 0.7 |
| | | | 2010 | UC | 174,800 | 184,800 | 203,400 | 164,400 | 0.5 |
| | | | 2011 | UC | 176,300 | 176,300 | 181,600 | 167,500 | N/A |
| | | | 2012 | UC | 177,900 | 177,900 | 190,300 | 169,000 | N/A |
| | | | 2013 | UC | 179,400 | 179,400 | 181,200 | 170,500 | N/A |
| | | | 2014 | UC | 181,000 | 181,000 | 173,800 | 171,900 | N/A |
| | | | 2015 | UC | 182,500 | 182,500 | 175,200 | 173,400 | N/A |
| | | | 2016 | UC | 184,100 | 184,100 | 176,700 | 174,900 | N/A |
| 417 | PARKDALE AV IC-122-OTTAWA | 0.9 | 1988 | UC | 110,600 | 116,000 | 124,900 | 103,900 | 1.2 |
| | | | 1989 | UC | 116,700 | 122,500 | 131,800 | 110,800 | 2.3 |
| | | | 1990 | UC | 120,600 | 128,900 | 139,800 | 114,500 | 1.1 |
| | | | 1991 | UC | 121,000 | 128,200 | 139,100 | 117,300 | 1.0 |
| | | | 1992 | UC | 125,400 | 132,800 | 144,100 | 120,300 | 1.7 |
| | | | 1993 | UC | 126,000 | 131,000 | 142,300 | 117,100 | 1.8 |
| | | | 1994 | UC | 135,900 | 144,100 | 157,600 | 123,700 | 1.4 |
| | | | 1995 | UC | 140,800 | 146,400 | 160,500 | 130,900 | 1.2 |
| | | | 1996 | UC | 145,700 | 155,000 | 170,500 | 138,400 | 1.2 |
| | | | 1997 | UC | 150,600 | 158,100 | 176,200 | 141,600 | 0.9 |
| | | | 1998 | UC | 155,500 | 165,500 | 181,900 | 147,700 | 0.9 |
| | | | 1999 | UC | 149,200 | 158,700 | 174,600 | 141,700 | 1.0 |
| | | | 2000 | UC | 150,700 | 160,300 | 177,500 | 141,700 | 1.1 |
| | | | 2001 | UC | 152,200 | 162,900 | 179,600 | 143,100 | 1.0 |
| | | | 2002 | UC | 153,700 | 163,800 | 180,800 | 143,900 | 0.8 |
| | | | 2003 | UC | 150,400 | 159,400 | 177,500 | 141,400 | 1.0 |
| | | | 2004 | UC | 152,000 | 160,600 | 178,100 | 143,600 | 0.8 |
| | | | 2005 | UC | 156,500 | 165,600 | 183,000 | 146,800 | 0.9 |

| Highway | Location Description | Dist. (KM) | Year | Pattern Type | AADT | SADT | SAWDT | WADT | AR |
|---------|------------------------------|---------------|------|-----------------|---------|---------|---------|---------|-----|
| | | | 2006 | UC | 157,800 | 166,900 | 184,400 | 148,500 | 0.9 |
| | | | 2007 | UC | 159,100 | 168,700 | 184,100 | 149,300 | 1.3 |
| | | | 2008 | UC | 160,400 | 169,400 | 159,100 | 150,100 | 0.9 |
| | | | 2009 | UC | 161,700 | 170,700 | 188,400 | 152,100 | 0.9 |
| | | | 2010 | UC | 163,000 | 172,300 | 189,700 | 153,300 | 1.0 |
| | | | 2011 | UC | 164,300 | 164,300 | 169,200 | 156,000 | N/A |
| | | | 2012 | UC | 165,500 | 165,500 | 177,100 | 157,300 | N/A |
| | | | 2013 | UC | 166,800 | 166,800 | 168,500 | 158,500 | N/A |
| | | | 2014 | UC | 168,100 | 168,100 | 161,400 | 159,700 | N/A |
| | | | 2015 | UC | 169,400 | 169,400 | 162,600 | 160,900 | N/A |
| | | | 2016 | UC | 170,700 | 170,700 | 163,900 | 162,100 | N/A |
| 417 | ISLAND PARK DR IC-123-OTTAWA | 0.8 | 1988 | UC | 106,500 | 111,800 | 120,300 | 100,100 | 0.7 |
| | | | 1989 | UC | 112,800 | 118,300 | 127,400 | 107,100 | 1.3 |
| | | | 1990 | UC | 117,100 | 125,200 | 135,700 | 111,100 | 0.6 |
| | | | 1991 | UC | 119,000 | 126,100 | 136,800 | 115,400 | 0.7 |
| | | | 1992 | UC | 121,500 | 128,700 | 139,700 | 116,600 | 1.2 |
| | | | 1993 | UC | 122,000 | 126,800 | 137,800 | 113,400 | 1.1 |
| | | | 1994 | UC | 132,300 | 140,200 | 153,500 | 120,400 | 0.6 |
| | | | 1995 | UC | 137,100 | 142,600 | 156,300 | 127,500 | 0.8 |
| | | | 1996 | UC | 141,900 | 151,000 | 166,000 | 134,800 | 0.9 |
| | | | 1997 | UC | 146,700 | 154,000 | 171,600 | 137,900 | 0.8 |
| | | | 1998 | UC | 151,600 | 161,300 | 177,400 | 144,000 | 0.4 |
| | | | 1999 | UC | 145,500 | 154,800 | 170,200 | 138,200 | 0.4 |
| | | | 2000 | UC | 147,100 | 156,500 | 173,300 | 138,300 | 0.6 |
| | | | 2001 | UC | 148,600 | 159,000 | 175,300 | 139,700 | 0.5 |
| | | | 2002 | UC | 150,100 | 159,900 | 176,600 | 140,500 | 0.4 |
| | | | 2003 | UC | 146,900 | 155,700 | 173,300 | 138,100 | 0.6 |
| | | | 2004 | UC | 150,000 | 158,500 | 175,700 | 141,700 | 0.6 |
| | | | 2005 | UC | 153,500 | 162,400 | 179,500 | 144,000 | 0.7 |
| | | | 2006 | UC | 154,900 | 163,800 | 181,000 | 145,800 | 0.5 |
| | | | 2007 | UC | 156,300 | 165,800 | 180,900 | 146,600 | 0.6 |
| | | | 2008 | UC | 157,700 | 166,600 | 156,400 | 147,500 | 0.5 |
| | | | 2009 | UC | 159,000 | 167,900 | 185,200 | 149,600 | 0.8 |



Weekly Volume Summary

Wed, Apr 03, 2019

Location: Hwy 417 - 0.5 km West of Parkdale Ave IC122

LHRS/Offset: 49460 / 0.0

Region: Eastern

Pattern Type: Urban Commuter

PCS#: 34

Hwy. TVIS#: 417170

Count Direction: EB

Report Dates: Sep 12, 2018 to Sep 18, 2018

| Hour Interval | Wed 18/09/12 | Thu 13 | Fri 14 | Sat 15 | Sun 16 | Mon 17 | Tue 18 | Wed 19 |
|---------------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|
| 0:00- 1:00 | | 574 | 624 | 1,119 | 1,272 | 548 | 457 | 527 |
| 1:00- 2:00 | | 355 | 438 | 789 | 820 | 337 | 282 | 313 |
| 2:00- 3:00 | | 271 | 287 | 606 | 658 | 245 | 237 | 220 |
| 3:00- 4:00 | | 268 | 290 | 405 | 410 | 231 | 238 | 258 |
| 4:00- 5:00 | | 490 | 542 | 335 | 281 | 501 | 469 | 504 |
| 5:00- 6:00 | | 2,154 | 1,917 | 579 | 455 | 2,078 | 2,012 | 2,140 |
| 6:00- 7:00 | | 6,203 | 5,410 | 1,494 | 1,072 | 5,775 | 4,952 | 5,433 |
| 7:00- 8:00 | | 6,429 | 6,318 | 2,164 | 1,513 | 6,559 | 5,658 | 6,567 |
| 8:00- 9:00 | | 6,350 | 6,256 | 3,530 | 2,298 | 6,202 | 5,764 | 6,327 |
| 9:00-10:00 | | 6,075 | 5,972 | 4,548 | 3,716 | 5,819 | 5,655 | 6,121 |
| 10:00-11:00 | | 5,140 | 5,694 | 5,193 | 4,654 | 5,030 | 5,593 | 4,949 |
| 11:00-12:00 | | 4,070 | 5,628 | 5,816 | 4,826 | 5,075 | 5,168 | 5,063 |
| AM Total | 0 | 38,379 | 39,376 | 26,578 | 21,975 | 38,400 | 36,485 | 38,422 |
| 12:00-13:00 | 4,383 | 4,438 | 5,616 | 5,625 | 5,330 | 5,211 | 4,931 | |
| 13:00-14:00 | 4,503 | 5,244 | 5,010 | 5,696 | 5,511 | 5,111 | 5,114 | |
| 14:00-15:00 | 5,293 | 4,889 | 5,159 | 5,403 | 5,417 | 5,551 | 5,335 | |
| 15:00-16:00 | 5,167 | 5,046 | 5,213 | 4,742 | 5,269 | 5,897 | 5,975 | |
| 16:00-17:00 | 3,388 | 3,305 | 5,237 | 5,144 | 4,958 | 5,211 | 5,561 | |
| 17:00-18:00 | 4,819 | 4,457 | 5,421 | 5,067 | 4,928 | 4,883 | 5,941 | |
| 18:00-19:00 | 5,198 | 5,741 | 5,282 | 4,874 | 4,530 | 4,916 | 5,679 | |
| 19:00-20:00 | 4,161 | 4,411 | 4,339 | 4,010 | 3,792 | 3,694 | 4,028 | |
| 20:00-21:00 | 3,610 | 3,896 | 3,807 | 3,756 | 3,345 | 3,165 | 3,548 | |
| 21:00-22:00 | 2,758 | 3,002 | 3,211 | 3,259 | 2,434 | 2,569 | 2,872 | |
| 22:00-23:00 | 1,653 | 1,875 | 2,487 | 2,534 | 1,714 | 1,471 | 1,719 | |
| 23:00-24:00 | 1,071 | 1,265 | 1,824 | 1,950 | 1,036 | 948 | 1,049 | |
| PM Total | 46,004 | 47,569 | 52,606 | 52,060 | 48,264 | 48,627 | 51,752 | 0 |
| 24 Hr. Total | 46,004 | 85,948 | 91,982 | 78,638 | 70,239 | 87,027 | 88,237 | 38,422 |
| Noon - Noon | 84,383 | 86,945 | 79,184 | 74,035 | 86,664 | 85,112 | 90,174 | |



Weekly Volume Summary

Wed, Apr 03, 2019

Location: Hwy 417 - 0.5 km West of Parkdale Ave IC122

LHRS/Offset: 49460 / 0.0

Region: Eastern

Pattern Type: Urban Commuter

PCS#: 34

Hwy. TVIS#: 417170

Count Direction: WB

Report Dates: Sep 12, 2018 to Sep 18, 2018

| Hour Interval | Wed 18/09/12 | Thu 13 | Fri 14 | Sat 15 | Sun 16 | Mon 17 | Tue 18 | Wed 19 |
|---------------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|
| 0:00- 1:00 | | 893 | 948 | 1,614 | 1,853 | 661 | 700 | 746 |
| 1:00- 2:00 | | 508 | 554 | 1,103 | 1,270 | 396 | 375 | 428 |
| 2:00- 3:00 | | 376 | 445 | 953 | 1,031 | 335 | 339 | 341 |
| 3:00- 4:00 | | 283 | 350 | 626 | 696 | 269 | 286 | 293 |
| 4:00- 5:00 | | 424 | 422 | 446 | 397 | 431 | 403 | 444 |
| 5:00- 6:00 | | 1,526 | 1,354 | 570 | 467 | 1,474 | 1,548 | 1,527 |
| 6:00- 7:00 | | 4,382 | 4,195 | 1,314 | 893 | 4,347 | 4,464 | 4,564 |
| 7:00- 8:00 | | 5,971 | 6,014 | 2,258 | 1,570 | 5,949 | 6,102 | 6,242 |
| 8:00- 9:00 | | 5,988 | 6,013 | 3,608 | 2,485 | 5,897 | 6,090 | 6,161 |
| 9:00-10:00 | | 5,615 | 5,653 | 4,857 | 3,854 | 5,223 | 5,564 | 5,363 |
| 10:00-11:00 | | 5,111 | 5,319 | 5,439 | 4,774 | 3,506 | 5,016 | 4,953 |
| 11:00-12:00 | | 5,519 | 5,922 | 5,714 | 5,312 | 3,443 | 5,279 | 5,332 |
| AM Total | 0 | 36,596 | 37,189 | 28,502 | 24,602 | 31,931 | 36,166 | 36,394 |
| 12:00-13:00 | 5,458 | 5,866 | 6,080 | 6,267 | 5,947 | 3,598 | 5,457 | |
| 13:00-14:00 | 5,612 | 5,985 | 5,640 | 5,959 | 3,982 | 4,904 | 5,491 | |
| 14:00-15:00 | 6,287 | 5,913 | 5,556 | 5,910 | 5,466 | 5,834 | 6,113 | |
| 15:00-16:00 | 5,543 | 5,018 | 5,146 | 5,707 | 5,479 | 5,569 | 5,422 | |
| 16:00-17:00 | 4,859 | 4,512 | 3,953 | 5,714 | 5,233 | 4,937 | 4,773 | |
| 17:00-18:00 | 4,847 | 4,388 | 4,267 | 5,152 | 4,667 | 4,991 | 4,951 | |
| 18:00-19:00 | 5,266 | 5,385 | 5,135 | 4,291 | 4,178 | 5,035 | 5,383 | |
| 19:00-20:00 | 4,746 | 4,812 | 5,144 | 3,936 | 4,000 | 4,543 | 4,706 | |
| 20:00-21:00 | 4,073 | 4,212 | 4,149 | 3,624 | 3,474 | 3,818 | 3,935 | |
| 21:00-22:00 | 3,651 | 3,933 | 3,747 | 3,195 | 2,824 | 3,231 | 3,541 | |
| 22:00-23:00 | 2,589 | 2,698 | 2,993 | 2,942 | 2,187 | 2,211 | 2,336 | |
| 23:00-24:00 | 1,787 | 1,960 | 2,431 | 2,486 | 1,357 | 1,332 | 1,395 | |
| PM Total | 54,718 | 54,682 | 54,241 | 55,183 | 48,794 | 50,003 | 53,503 | 0 |
| 24 Hr. Total | 54,718 | 91,278 | 91,430 | 83,685 | 73,396 | 81,934 | 89,669 | 36,394 |
| Noon - Noon | 91,314 | 91,871 | 82,743 | 79,785 | 80,725 | 86,169 | 89,897 | |



Weekly Volume Summary

Wed, Apr 03, 2019

Location: Hwy 417 - 0.5 km West of Parkdale Ave IC122

LHRS/Offset: 49460 / 0.0

Region: Eastern

Pattern Type: Urban Commuter

PCS#: 34

Hwy. TVIS#: 417170

Count Direction: EB/WB

Report Dates: Sep 12, 2018 to Sep 18, 2018

| Hour Interval | Wed 18/09/12 | Thu 13 | Fri 14 | Sat 15 | Sun 16 | Mon 17 | Tue 18 | Wed 19 |
|---------------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|---------------|
| 0:00- 1:00 | | 1,467 | 1,572 | 2,733 | 3,125 | 1,209 | 1,157 | 1,273 |
| 1:00- 2:00 | | 863 | 992 | 1,892 | 2,090 | 733 | 657 | 741 |
| 2:00- 3:00 | | 647 | 732 | 1,559 | 1,689 | 580 | 576 | 561 |
| 3:00- 4:00 | | 551 | 640 | 1,031 | 1,106 | 500 | 524 | 551 |
| 4:00- 5:00 | | 914 | 964 | 781 | 678 | 932 | 872 | 948 |
| 5:00- 6:00 | | 3,680 | 3,271 | 1,149 | 922 | 3,552 | 3,560 | 3,667 |
| 6:00- 7:00 | | 10,585 | 9,605 | 2,808 | 1,965 | 10,122 | 9,416 | 9,997 |
| 7:00- 8:00 | | 12,400 | 12,332 | 4,422 | 3,083 | 12,508 | 11,760 | 12,809 |
| 8:00- 9:00 | | 12,338 | 12,269 | 7,138 | 4,783 | 12,099 | 11,854 | 12,488 |
| 9:00-10:00 | | 11,690 | 11,625 | 9,405 | 7,570 | 11,042 | 11,219 | 11,484 |
| 10:00-11:00 | | 10,251 | 11,013 | 10,632 | 9,428 | 8,536 | 10,609 | 9,902 |
| 11:00-12:00 | | 9,589 | 11,550 | 11,530 | 10,138 | 8,518 | 10,447 | 10,395 |
| AM Total | 0 | 74,975 | 76,565 | 55,080 | 46,577 | 70,331 | 72,651 | 74,816 |
| 12:00-13:00 | 9,841 | 10,304 | 11,696 | 11,892 | 11,277 | 8,809 | 10,388 | |
| 13:00-14:00 | 10,115 | 11,229 | 10,650 | 11,655 | 9,493 | 10,015 | 10,605 | |
| 14:00-15:00 | 11,580 | 10,802 | 10,715 | 11,313 | 10,883 | 11,385 | 11,448 | |
| 15:00-16:00 | 10,710 | 10,064 | 10,359 | 10,449 | 10,748 | 11,466 | 11,397 | |
| 16:00-17:00 | 8,247 | 7,817 | 9,190 | 10,858 | 10,191 | 10,148 | 10,334 | |
| 17:00-18:00 | 9,666 | 8,845 | 9,688 | 10,219 | 9,595 | 9,874 | 10,892 | |
| 18:00-19:00 | 10,464 | 11,126 | 10,417 | 9,165 | 8,708 | 9,951 | 11,062 | |
| 19:00-20:00 | 8,907 | 9,223 | 9,483 | 7,946 | 7,792 | 8,237 | 8,734 | |
| 20:00-21:00 | 7,683 | 8,108 | 7,956 | 7,380 | 6,819 | 6,983 | 7,483 | |
| 21:00-22:00 | 6,409 | 6,935 | 6,958 | 6,454 | 5,258 | 5,800 | 6,413 | |
| 22:00-23:00 | 4,242 | 4,573 | 5,480 | 5,476 | 3,901 | 3,682 | 4,055 | |
| 23:00-24:00 | 2,858 | 3,225 | 4,255 | 4,436 | 2,393 | 2,280 | 2,444 | |
| PM Total | 100,722 | 102,251 | 106,847 | 107,243 | 97,058 | 98,630 | 105,255 | 0 |
| 24 Hr. Total | 100,722 | 177,226 | 183,412 | 162,323 | 143,635 | 168,961 | 177,906 | 74,816 |
| Noon - Noon | 175,697 | 178,816 | 161,927 | 153,820 | 167,389 | 171,281 | 180,071 | |
| | ADT | AWD | AADT | AAWD | SADT | SAWDT | WADT | DHV |
| | 169,857 | 176,466 | | | | | | |

O-Train Line 2

The full-length of O-Train Line 2 is currently closed for Stage 2 construction. Line 2 buses are operating in place of the train. View closure details.

The O-Train Line 2 (the Trillium Line) is an eight-kilometre diesel light-rail service. Line 2 runs from Greenboro Station in the south to Bayview Station just west of downtown.

Line 2 stations

| Station | Stop # |
|--------------|----------------------|
| Greenboro | 3037 |
| Mooney's Bay | 3063 |
| Carleton | 3062 |
| Carling | 3061 |
| Bayview | 3060 |

Choose your station for a map and service information:

Select a Line 2 station ▼

Frequent service

The Trillium Line is in service 7 days a week, until midnight Monday to Saturday and until 11 pm. Sunday. Trains arrive about every 12 minutes on weekdays and Saturdays and between every 12 and 15 minutes on Sundays.

Use the [Travel Planner](#) for Trillium Line schedules and next departures:

You can also find out the current schedule by texting 560560 or calling 613-560-1000 plus the 4-digit stop number (listed above) for your station.

Line 2 trains

The Trillium Line is served by six Alstom Coradia Lint trains.

- High-efficiency, diesel engines
- Advanced technology makes them quiet and fuel efficient
- Low greenhouse gas emissions
- Low operating costs
- Two platform-level double doors per train
- Fully-accessible cars
- Large windows
- Smooth, comfortable ride
- Space for 260 passengers

Train names

In 2017, the City of Ottawa ran a Name the Trains Contest. Children and youth aged 16 and under were invited to name O-Train Line 1 and Line 2 trains.

- [Line 1 train names](#)


The chosen names for Line 2 are:

- Emily Murphy
- Nanuq • Polar Bear
- Portage
- Dreamcatcher
- Northern Lights
- Rocket Richard

All Rights Reserved © OC Transpo
2022

Appendix D

Stationary Noise Model Information



Source: Google Satellite



NOISE IMPACT STUDY
 TIP GLADSTONE GP INC.
 145 LORETTA AVE N & 951 GLADSTONE AVE

INDUSTRY NOISE SOURCE LOCATIONS

11223331
 02.02.2022

FIGURE D.1

Table D.1
Noise Source Sound Level Summary
TIP Gladstone GP Inc.
145 Loretta Ave N & 951 Gladstone Ave, Ottawa, Ontario

| Cadna A ID | Noise Source Description | | 1/1 Octave Band Data | | | | | | | | Unadjusted Total Sound Power Level (dBA) | Tonal Penalty Assessment (dBA) | Height Absolute (m) | Operating Time Day/Eve/Night (min) | Vehicle Volumes Day/Eve/Night (veh/hr) | Speed Reference/Comments (km/hr) | |
|------------|---|-----------------------|----------------------|-------|-------|-------|-------|-------|-------|-------|--|--------------------------------|---------------------|------------------------------------|--|----------------------------------|----------|
| | | | 32 | 63 | 125 | 250 | 500 | 1000 | 2000 | 4000 | | | | | | | 8000 |
| S101 | Ottawa Traffic Operations - HVAC Unit | PWL (dB) | — | 87.1 | 89.9 | 86.4 | 84.0 | 82.7 | 79.0 | 73.9 | 68.6 | 93.9 | | | | | |
| | | A-weighted correction | -39.4 | -26.2 | -16.1 | -8.6 | -3.2 | 0.0 | 1.2 | 1.0 | -1.1 | | | | | | |
| | | PWL (dBA) | — | 60.9 | 73.8 | 77.8 | 80.8 | 82.7 | 80.2 | 74.9 | 67.5 | 87.3 | No | 0 | 75.5 | 60/60/30 | — |
| S102 | Ottawa Traffic Operations - HVAC Unit | PWL (dB) | — | 87.1 | 89.9 | 86.4 | 84.0 | 82.7 | 79.0 | 73.9 | 68.6 | 93.9 | | | | | |
| | | A-weighted correction | -39.4 | -26.2 | -16.1 | -8.6 | -3.2 | 0.0 | 1.2 | 1.0 | -1.1 | | | | | | |
| | | PWL (dBA) | — | 60.9 | 73.8 | 77.8 | 80.8 | 82.7 | 80.2 | 74.9 | 67.5 | 87.3 | No | 0 | 72.6 | 60/60/30 | — |
| S103 | Ottawa Traffic Operations - HVAC Unit | PWL (dB) | — | 87.1 | 89.9 | 86.4 | 84.0 | 82.7 | 79.0 | 73.9 | 68.6 | 93.9 | | | | | |
| | | A-weighted correction | -39.4 | -26.2 | -16.1 | -8.6 | -3.2 | 0.0 | 1.2 | 1.0 | -1.1 | | | | | | |
| | | PWL (dBA) | — | 60.9 | 73.8 | 77.8 | 80.8 | 82.7 | 80.2 | 74.9 | 67.5 | 87.3 | No | 0 | 72.6 | 60/60/30 | — |
| S104 | Ottawa Traffic Operations - Truck Movements | PWL (dB) | — | 104.4 | 99.4 | 92.4 | 94.4 | 91.4 | 90.4 | 87.4 | 78.4 | 106.4 | | | | | |
| | | A-weighted correction | -39.4 | -26.2 | -16.1 | -8.6 | -3.2 | 0.0 | 1.2 | 1.0 | -1.1 | | | | | | |
| | | PWL (dBA) | — | 78.2 | 83.3 | 83.8 | 91.2 | 91.4 | 91.6 | 88.4 | 77.3 | 97.3 | No | 0 | 70.8 | — | 15/15/15 |
| S105 | Ottawa Traffic Operations - Deliveries (Tractor Trailers) | PWL (dB) | 31.0 | 117.0 | 112.0 | 105.0 | 107.0 | 104.0 | 103.0 | 100.0 | 91.0 | 119.0 | | | | | |
| | | A-weighted correction | -39.4 | -26.2 | -16.1 | -8.6 | -3.2 | 0.0 | 1.2 | 1.0 | -1.1 | | | | | | |
| | | PWL (dBA) | — | 90.8 | 95.9 | 96.4 | 103.8 | 104.0 | 104.2 | 101.0 | 89.9 | 109.9 | No | 0 | 69.1 | — | 5/5/5 |
| S106 | Ottawa Traffic Operations - Forklift | PWL (dB) | — | — | — | — | 93.0 | — | — | — | — | 93.0 | | | | | |
| | | A-weighted correction | -39.4 | -26.2 | -16.1 | -8.6 | -3.2 | 0.0 | 1.2 | 1.0 | -1.1 | | | | | | |
| | | PWL (dBA) | — | — | — | — | 89.8 | — | — | — | — | 89.8 | No | 0 | 68.6 | 60/60/60 | — |



ghd.com

➔ **The Power of Commitment**