

UNIVERSITY OF OTTAWA

UNIVERSITY OF OTTAWA FACULTY OF
HEALTH SCIENCES BUILDING
STORMWATER MANAGEMENT REPORT

OCTOBER 07, 2021



uOttawa

wsp



UNIVERSITY OF OTTAWA FACULTY OF HEALTH SCIENCES BUILDING STORMWATER MANAGEMENT REPORT

UNIVERSITY OF OTTAWA

2ND SUBMISSION

PROJECT NO.: 211-01094-01
CLIENT REF: BT20-18477
DATE: OCTOBER 13, 2021

WSP
SUITE 300
2611 QUEENSVIEW DRIVE
OTTAWA, ON, CANADA K2B 8K2

T: +1 613 829-2800
F: +1 613 829-8299
WSP.COM

REVISION HISTORY

FIRST ISSUE

June 21 st , 2021	Draft SWM Report			
Prepared by	Reviewed by	Approved By		
MO	JW	MH		
SECOND ISSUE				
October 13 th , 2021	SWM Report			
Prepared by	Reviewed by	Approved By		
MO	MH	MH		

SIGNATURES

PREPARED BY

Meaghan O'Neill

Designer, Water Resources

October 7th, 2021

APPROVED¹ BY



Michelle Hughes, M.Sc., P.Eng.
Team Lead, Water Resources

October 7th, 2021

WSP Canada Inc. ("WSP") prepared this report solely for the use of the intended recipient, UNIVERSITY OF OTTAWA, in accordance with the professional services agreement. The intended recipient is solely responsible for the disclosure of any information contained in this report. The content and opinions contained in the present report are based on the observations and/or information available to WSP at the time of preparation. If a third party makes use of, relies on, or makes decisions in accordance with this report, said third party is solely responsible for such use, reliance or decisions. WSP does not accept responsibility for damages, if any, suffered by any third party as a result of decisions made or actions taken by said third party based on this report. This limitations statement is considered an integral part of this report.

The original of this digital file will be conserved by WSP for a period of not less than 10 years. As the digital file transmitted to the intended recipient is no longer under the control of WSP, its integrity cannot be assured. As such, WSP does not guarantee any modifications made to this digital file subsequent to its transmission to the intended recipient.

¹ Approval of this document is an administrative function indicating readiness for release and does not impart legal liability on to the Approver for any technical content contained herein. Technical accuracy and fit-for-purpose of this content is obtained through the review process. The Approver shall ensure the applicable review process has occurred prior to signing the document.

CONTRIBUTORS

CLIENT

University of Ottawa

WSP

Water Resources, Designer

Meaghan O'Neill

Water Resources, Team Lead

Michelle Hughes



TABLE OF CONTENTS

1	INTRODUCTION.....	1
1.1	Scope.....	1
1.2	Site Location.....	1
1.3	Stormwater Management Plan Objectives.....	2
1.4	Design Criteria.....	2
2	PRE-DEVELOPMENT CONDITIONS	3
2.1	General	3
2.2	Rainfall Information.....	4
2.3	Allowable Flow Rates.....	4
3	POST-DEVELOPMENT CONDITIONS	5
3.1	General	5
3.2	Water Quantity	6
3.3	Water Quality	7
4	CONCLUSIONS.....	8

TABLES

TABLE 1: PRE-DEVELOPMENT PEAK FLOW RATE CALCULATIONS (BASED ON $T_D = 10$ MINUTES, $C = 0.5$).....	4
TABLE 2: PROPOSED LAND-USE AREA BREAKDOWN	6
TABLE 3: SUMMARY OF HYDROCAD MODELLING RESULTS	7

FIGURES

FIGURE 1: PROJECT LOCATION	1
FIGURE 2: EXISTING CONDITIONS CATCHMENT AREA	3
FIGURE 3: PROPOSED CONDITIONS CATCHMENT AREAS.....	5

APPENDICES

A	EXHIBITS
B	CALCULATIONS & HYDROCAD OUTPUT
C	SUPPORTING DOCUMENTS

1 INTRODUCTION

1.1 SCOPE

WSP Canada Inc. was retained by the University of Ottawa to prepare a Stormwater Management (SWM) report for the proposed construction of a five storey Faculty of Health Sciences building at the University of Ottawa's Lees Campus. This SWM report examines the potential water quality and quantity impacts of the proposed development and summarizes how each will be addressed in accordance with applicable guidelines.

1.2 SITE LOCATION

The proposed development is located at 200 Lees Avenue, Ottawa, Ontario. The subject site is bounded by the 417 to the north, the LRT line to the west, and the Rideau River to the east and south. The location of the proposed development is illustrated in Figure 1.



Figure 1: Project Location

1.3 STORMWATER MANAGEMENT PLAN OBJECTIVES

The objectives of the stormwater management plan are as follows:

- Collect and review background information.
- Determine the site-specific stormwater management requirements to ensure that the proposals are in conformance with the applicable Provincial, Municipal and Conservation Authority stormwater management and development guidelines.
- Evaluate various stormwater management practices that meet the applicable SWM and development requirements and recommend a preferred strategy.
- Prepare a stormwater management report documenting the strategy along with the technical information necessary for the justification and sizing of the proposed stormwater management facilities.

1.4 DESIGN CRITERIA

Design criteria were taken from the Owner's Statement of Requirements Volume 1. Criteria for the University of Ottawa Lees Campus are as follows:

- **Stormwater Quantity**- control post-development flows (2 to 100-year storm events) to the 2-year pre-development discharge with a runoff coefficient that is the lesser of the actual runoff coefficient or 0.5 per City of Ottawa Standards for a redevelopment (OSDG Section 8.3.7.3)
- **Stormwater Quality**- enhanced level of protection per the City of Ottawa, the Rideau Valley Conservation Authority (RVCA) and the Ministry of Environment, Conservation and Parks (MECP) requirements shall be met (80% TSS removal)

2 PRE-DEVELOPMENT CONDITIONS

2.1 GENERAL

The University of Ottawa's Lees Campus is comprised of a building complex (divided into five blocks, A to E), paved parking areas along the north and west boundaries, and a turf sports field at the east end of the property. The site is accessed via an entrance off Lees Avenue at the north west corner of the site.

As can be seen in Figure 2, the subject site for the proposed development is only a portion of the overall Lees Campus, consisting of three of the five blocks (B, C, and D) of the existing building complex, the east parking area, and a portion the north parking area (south of the access road). The subject site is a 1.92 ha parcel of land with a runoff coefficient of 0.69. As discussed in section 1.4, per City of Ottawa criteria, a runoff coefficient of 0.5 was used when evaluating pre-development peak flows. Figures showing exiting drainage and land use are also shown on Exhibits 1 and 2 found in **Appendix A**.



Figure 2: Existing Conditions Catchment Area

2.2 RAINFALL INFORMATION

The rainfall intensity is calculated in accordance with Section 5.4.2 of the Ottawa Sewer Design Guidelines (October, 2012):

Where;

$$i = \left[\frac{A}{(Td + C)^B} \right]$$

- A, B, C = regression constants for each return period (defined in section 5.4.2)
- i = rainfall intensity (mm/hour)
- Td = storm duration (minutes)

The IDF parameters/regression constants are per the Ottawa Sewer Design Guidelines (October, 2012).

2.3 ALLOWABLE FLOW RATES

As noted in section 1.4, relevant policies from the City of Ottawa Sewer Design Guidelines and the Owner's Statement of Requirements require that post development discharge rates from the site match the pre-development 2-year storm event peak discharge rate (0.20m³/s).

HydroCAD software was used to calculate the pre-development peak flow rates for the 2 through 100-year storm events, results are summarized in Table 1. Detailed HydroCAD output is included in **Appendix B**.

Table 1: Pre-Development Peak Flow Rate Calculations (Based on T_d = 10 minutes, C = 0.5)

RETURN PERIOD (Years)	RAINFALL INTENSITY, I (mm/hour)	SITE PEAK FLOW RATE (m ³ /sec)
2	76.8	0.20
5	104.2	0.27
10	122.1	0.32
25	144.7	0.38
50	161.5	0.42
100	178.6	0.47

3 POST-DEVELOPMENT CONDITIONS

3.1 GENERAL

The proposed University of Ottawa Lees Campus project includes the demolition of Blocks B, C, and D of the existing building complex, excavation of contaminated soil, and the construction of a new five store Faculty of Health Sciences Building.

Vehicular access off Lees Avenue, as well as building Blocks A and E, the north parking area, and the sports field are outside of the proposed development boundaries and are not included in the scope of this report.

An estimated area breakdown of the proposed site layout is summarized in Table 2 and shown on Figure 3. Exhibits showing the proposed drainage strategy and proposed land use are shown on Exhibits 3 and Exhibit 4 and found in **Appendix A**.




Figure 3: Proposed Conditions Catchment Areas

Table 2: Proposed Land-Use Area Breakdown

CATCHMENT ID	AREA (ha)	% COVERAGE OF PROJECT AREA	RUNOFF COEFFICIENT
Un-Controlled Drainage Areas			
PR-001	0.25	13%	0.52 (0.65*)
PR-002	0.19	10%	0.68 (0.85*)
PR-004	0.11	6%	0.26 (0.33*)
Sub Total	0.55	29%	0.52 (0.65*)
Controlled Drainage Areas			
PR-003	1.37	71%	0.63 (0.79*)
Sub Total	1.37	71%	0.63 (0.79*)
TOTAL PROJECT AREA	1.92	100%	0.60 (0.75*)

*Runoff coefficients increased by 25% for the 100-year storm per the City of Ottawa Sewer Design Guidelines (Section 5.4.5.2.1)

To meet the stormwater management objectives, as defined by the design criteria outlined in Section 1.4, the following components have been proposed:

- Underground storage chambers (Stormtech MC 4500 or equivalent)
- 100mm flow control device on proposed sewer outlet
- Oil and Grit Separator (OGS) unit (STORMCON SDD3-1200 or equivalent)

The application and sizing of these proposed stormwater management facilities is outlined in the following sections.

3.2 WATER QUANTITY

As noted previously, it is required that the post-development discharge rate from the site be controlled to the pre-development 2-year peak flow.

Proposed features to achieve these targets include;

- 538m³ underground storage chambers
- 100mm orifice plate

HydroCAD software has been used to model the behaviour of the proposed SWM system and determine its response under various storm events. The software calculates flow rates and related storage values. In addition, the software helps identify the critical duration for different components of the system. The critical storm duration (100-year) for peak discharge from the site occurs at 10 minutes, however, the maximum storage utilized occurs at 114 minutes.

Due to site geometry and building placement, there are areas on the site that can not be controlled (PR-001, PR-002, PR-004) and so remain captured by the existing storm system. The west edge of the site will continue to drain to the existing storm sewer that runs along the west edge of the property and outlets to the Rideau River to the south. The north and east edge of the property (PR-002 and PR-004) will continue to drain to the existing storm sewer running along the east edge of the site and discharging to the Rideau River.

The entire controlled portion of the site (PR-003) will be detained in the proposed underground storage unit and released at a controlled rate through a suitably sized orifice plate into the existing sewer running along the east side of the site immediately prior to being released into the Rideau River. The proposed flow control device and proposed inverts have been placed such that runoff collected south of the proposed building will be directed back into the tank prior to being released through the flow control device. It was determined using HydroCAD software

that Stormtech MC-4500 storage chambers (or equivalent) with a storage volume of 538 m³ and outflow controlled with a 100 mm orifice plate is sufficient to achieve the quantity control requirements. In December 2020, a Remediation Action Plan was prepared by Geosyntec for the west portion of the 200 Lees Avenue site (TR0885B_uOttawa_RAP_200Lees Ave Ottawa ON_FINAL). This report states that there is ongoing groundwater collection and treatment just northwest of the site at the City of Ottawa’s Transit Station groundwater collection system. The study found that groundwater is strongly influenced by the presence of the system with the groundwater from the site directed largely to the northwest (Geosyntec 2020). In order to prevent additional mobilization of contaminated groundwater, the storage chambers are proposed with an impermeable liner as to prevent excessive infiltration, beyond what will naturally infiltrate in the softscape areas.

A summary of the modeling results is provided in Table 3, detailed HydroCAD output is included in **Appendix B**.

Table 3: Summary of HydroCAD Modelling Results

Return Period (Years)	Time of Conc. (min)	Utilized Storage	Total Flow Leaving Site	Allowable 100-yr Flow Rate
		(m ³)	(m ³ /s)	(m ³ /s)
100 (Peak Discharge)	10	299	0.20	0.20
100 (Peak Storage)	114	538	0.06	

3.3 WATER QUALITY

As noted previously, a single controlled outlet location is proposed at the south end of the site into the existing storm sewer discharging to the Rideau River. A STORMCON SDD3-1200 (or equivalent) OGS is proposed to achieve a minimum 80% TSS removal for the entire controlled area of the site (PR-003). The location of the proposed OGS unit is shown on Exhibit 3 found in **Appendix A**.

In August, 2013, an Amended Environmental Compliance Approval (ECA) was issued by the MECP regarding stormwater management works to serve the Block A renovation and the addition of an open air stadium on Lees Campus. The ECA states as part of this work, a Stormceptor STC 2000 OGS unit was installed that treats a 1.22 ha area of the site. The existing OGS has been sized to provide 80% TSS removal for the 1.22 ha drainage area with an overall imperviousness of 80%. The 1.22 ha area treated by the existing OGS includes the north parking, which will continue to be parking area under proposed conditions shown on Exhibit 3 as PR-002. Under proposed conditions, the north parking area will maintain the existing drainage patterns and approximate overall imperviousness, therefore, this area will be treated by the existing OGS unit.

As previously discussed, the western and eastern edges of the site will be drained uncontrolled to the existing storm system. These areas (PR-001 and PR-004) are primarily grass, landscaped, and pathway area and will have no vehicular traffic. Therefore, it is assumed that these areas will be free of typical sediment-generating activities and that runoff will leave effectively unchanged and can be considered clean for the purposes of water quality assessment. However, permanent and low maintenance catch basin inserts, that provide a minimum 50% TSS removal, are proposed in existing catch basins that receive uncontrolled flow to further reduce the impact to the receiving Rideau River.

4 CONCLUSIONS

A stormwater management report has been prepared to support the design of the proposed University of Ottawa Faculty of Health Sciences Building at the Lees Campus in the City of Ottawa. The key points are summarized below.

WATER QUALITY

An OGS unit (a STORMCON SDD3-1200 or equivalent) is proposed at the outlet of the proposed sewer system into the existing storm sewer draining to the Rideau River to meet MECP Enhanced treatment standards (80% TSS removal).

WATER QUANTITY

Controlled runoff from the site will be detained in a 538m³ underground storage unit (Stormtech MC-4500 Chambers, or equivalent) and released at a controlled rate using a 100mm orifice plate.

This report has demonstrated the proposed SWM strategy will address stormwater management related impacts from this project and meet the applicable design requirements.

APPENDIX

A EXHIBITS





CLIENT
UNIVERSITY OF OTTAWA

PROJECT
UNIVERSITY OF OTTAWA FACULTY OF HEALTH SCIENCES BUILDING


TITLE
**EXHIBIT 1
EXISTING CONDITIONS
DRAINAGE MOSAIC**



LEGEND

- Existing Storm
- Subcatchment

EX-001
1.92 | 0.50




DRAWN BY	MO	CHECKED BY	MH
	October 2021		
	NAD 1983 MTM 9		
	1:1,275		



CLIENT
UNIVERSITY OF OTTAWA


PROJECT
UNIVERSITY OF OTTAWA FACULTY
OF HEALTH SCIENCES BUILDING

TITLE
**EXHIBIT 2
EXISTING CONDITIONS
LAND USE**




LEGEND

- Subcatchment
- Land Use
 - Impervious
 - Pervious



DRAWN BY	MO	CHECKED BY	MH
	October 2021		
	NAD 1983 MTM 9		
	1:1,275		



CLIENT
UNIVERSITY OF OTTAWA


PROJECT
UNIVERSITY OF OTTAWA FACULTY OF HEALTH SCIENCES BUILDING

TITLE
**EXHIBIT 3
PROPOSED CONDITIONS
DRAINAGE MOSAIC**



- LEGEND**
- OGS Unit
 - ICD
 - Proposed Storm
 - Existing Storm
- Subcatchments
- PR-001
 - PR-002
 - PR-003
 - PR-004

Subcatchment ID	
Area (ha)	Runoff C



DRAWN BY MO

October 2021

NAD 1983 MTM 9

1:1,275

CHECKED BY MH





CLIENT
UNIVERSITY OF OTTAWA


PROJECT
UNIVERSITY OF OTTAWA FACULTY OF HEALTH SCIENCES BUILDING

TITLE
**EXHIBIT 4
PROPOSED CONDITIONS
LAND USE**



LEGEND

- Subcatchments
- Land Use
 - Impervious
 - Pervious



DRAWN BY	MO	CHECKED BY	MH
	October 2021		
	NAD 1983 MTM 9		
	1:1,275		

APPENDIX

B CALCULATIONS & HYDROCAD OUTPUT

PRE-DEVELOPMENT CONDITIONS



EX-001



Pre-Dev Site Discharge



Routing Diagram for uOttawa-LEES_2021-06-09

Prepared by WSP, Printed 6/16/2021

HydroCAD® 10.00-21 s/n 10697 © 2018 HydroCAD Software Solutions LLC

Area Listing (selected nodes)

Area (sq-meters)	C	Description (subcatchment-numbers)
19,200.0	0.50	(207S)
19,200.0	0.50	TOTAL AREA

Soil Listing (selected nodes)

Area (sq-meters)	Soil Group	Subcatchment Numbers
0.0	HSG A	
0.0	HSG B	
0.0	HSG C	
0.0	HSG D	
19,200.0	Other	207S
19,200.0		TOTAL AREA

Ground Covers (selected nodes)

HSG-A (sq-meters)	HSG-B (sq-meters)	HSG-C (sq-meters)	HSG-D (sq-meters)	Other (sq-meters)	Total (sq-meters)	Ground Cover	Subca Numbr
0.0	0.0	0.0	0.0	19,200.0	19,200.0		
0.0	0.0	0.0	0.0	19,200.0	19,200.0	TOTAL AREA	

Time span=0.00-6.00 hrs, dt=0.01 hrs, 601 points

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment207S: EX-001

Runoff Area=1.9200 ha 0.00% Impervious Runoff Depth=6 mm

Tc=10.0 min C=0.50 Runoff=0.20123 m³/s 122.8 m³

Link 103: Pre-Dev Site Discharge

Inflow=0.20123 m³/s 122.8 m³

Primary=0.20123 m³/s 122.8 m³

Total Runoff Area = 19,200.0 m² Runoff Volume = 122.8 m³ Average Runoff Depth = 6 mm

100.00% Pervious = 19,200.0 m² 0.00% Impervious = 0.0 m²

Summary for Subcatchment 207S: EX-001


Runoff = 0.20123 m³/s @ 0.17 hrs, Volume= 122.8 m³, Depth= 6 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
Ottawa 2-Year Duration=10 min, Inten=76.8 mm/hr

Area (ha)	C	Description
1.9200	0.50	
1.9200		100.00% Pervious Area

Tc (min)	Length (meters)	Slope (m/m)	Velocity (m/sec)	Capacity (m³/s)	Description
10.0					Direct Entry,

Subcatchment 207S: EX-001




Summary for Link 103: Pre-Dev Site Discharge

Inflow Area = 19,200.0 m², 0.00% Impervious, Inflow Depth = 6 mm for 2-Year event
Inflow = 0.20123 m³/s @ 0.17 hrs, Volume= 122.8 m³
Primary = 0.20123 m³/s @ 0.17 hrs, Volume= 122.8 m³, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs

Link 103: Pre-Dev Site Discharge



Hydrograph



Area Listing (selected nodes)

Area (sq-meters)	C	Description (subcatchment-numbers)
13,700.0	0.79	Controlled (208S)
1,900.0	0.85	Uncontrolled (210S)
1,200.0	0.33	Uncontrolled (212S)
2,500.0	0.65	Uncontrolled (214S)
19,300.0	0.75	TOTAL AREA

**POST-DEVELOPMENT
CONDITIONS**



Routing Diagram for uOttawa-LEES_2021-10-06

Prepared by WSP, Printed 10/7/2021

HydroCAD® 10.00-21 s/n 10697 © 2018 HydroCAD Software Solutions LLC

Ground Covers (selected nodes)

HSG-A (sq-meters)	HSG-B (sq-meters)	HSG-C (sq-meters)	HSG-D (sq-meters)	Other (sq-meters)	Total (sq-meters)	Ground Cover	Subca Numbx
0.0	0.0	0.0	0.0	13,700.0	13,700.0	Controlle d	
0.0	0.0	0.0	0.0	5,600.0	5,600.0	Uncontrol led	
0.0	0.0	0.0	0.0	19,300.0	19,300.0	TOTAL AREA	

Time span=0.00-6.00 hrs, dt=0.01 hrs, 601 points

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment208S: PR-003 Runoff Area=1.3700 ha 0.00% Impervious Runoff Depth=24 mm
Tc=10.0 min C=0.79 Runoff=0.52742 m³/s 322.0 m³

Subcatchment210S: PR-002 Runoff Area=0.1900 ha 0.00% Impervious Runoff Depth=25 mm
Tc=10.0 min C=0.85 Runoff=0.07870 m³/s 48.0 m³

Subcatchment212S: PR-004 Runoff Area=0.1200 ha 0.00% Impervious Runoff Depth=10 mm
Tc=10.0 min C=0.33 Runoff=0.01930 m³/s 11.8 m³

Subcatchment214S: PR-001 Runoff Area=0.2500 ha 0.00% Impervious Runoff Depth=19 mm
Tc=10.0 min C=0.65 Runoff=0.07919 m³/s 48.3 m³

Pond 207P: Storage Chmabers Peak Elev=59.910 m Storage=299.0 m³ Inflow=0.52742 m³/s 322.0 m³
Outflow=0.02380 m³/s 322.0 m³

Link 209L: Post-Dev Inflow=0.19716 m³/s 430.1 m³
Primary=0.19716 m³/s 430.1 m³

**Total Runoff Area = 19,300.0 m² Runoff Volume = 430.1 m³ Average Runoff Depth = 22 mm
100.00% Pervious = 19,300.0 m² 0.00% Impervious = 0.0 m²**

Summary for Subcatchment 208S: PR-003


Runoff = 0.52742 m³/s @ 0.17 hrs, Volume= 322.0 m³, Depth= 24 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
 Ottawa 100-Year Duration=10 min, Inten=178.6 mm/hr

Area (ha)	C	Description
1.3700	0.79	Controlled
1.3700		100.00% Pervious Area

Tc (min)	Length (meters)	Slope (m/m)	Velocity (m/sec)	Capacity (m³/s)	Description
10.0					Direct Entry,

Subcatchment 208S: PR-003



Summary for Subcatchment 210S: PR-002


Runoff = 0.07870 m³/s @ 0.17 hrs, Volume= 48.0 m³, Depth= 25 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
 Ottawa 100-Year Duration=10 min, Inten=178.6 mm/hr

Area (ha)	C	Description
0.1900	0.85	Uncontrolled
0.1900		100.00% Pervious Area

Tc (min)	Length (meters)	Slope (m/m)	Velocity (m/sec)	Capacity (m³/s)	Description
10.0					Direct Entry,

Subcatchment 210S: PR-002



Summary for Subcatchment 212S: PR-004


Runoff = 0.01930 m³/s @ 0.17 hrs, Volume= 11.8 m³, Depth= 10 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
 Ottawa 100-Year Duration=10 min, Inten=178.6 mm/hr

Area (ha)	C	Description
0.1200	0.33	Uncontrolled
0.1200		100.00% Pervious Area

Tc (min)	Length (meters)	Slope (m/m)	Velocity (m/sec)	Capacity (m³/s)	Description
10.0					Direct Entry,

Subcatchment 212S: PR-004



Summary for Subcatchment 214S: PR-001


Runoff = 0.07919 m³/s @ 0.17 hrs, Volume= 48.3 m³, Depth= 19 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
 Ottawa 100-Year Duration=10 min, Inten=178.6 mm/hr

Area (ha)	C	Description
0.2500	0.65	Uncontrolled
0.2500		100.00% Pervious Area

Tc (min)	Length (meters)	Slope (m/m)	Velocity (m/sec)	Capacity (m³/s)	Description
10.0					Direct Entry,

Subcatchment 214S: PR-001



Summary for Pond 207P: Storage Chmabers

Inflow Area = 13,700.0 m², 0.00% Impervious, Inflow Depth = 24 mm for 100-Year event
 Inflow = 0.52742 m³/s @ 0.17 hrs, Volume= 322.0 m³
 Outflow = 0.02380 m³/s @ 0.33 hrs, Volume= 322.0 m³, Atten= 95%, Lag= 9.5 min
 Primary = 0.02380 m³/s @ 0.33 hrs, Volume= 322.0 m³

Routing by Stor-Ind method, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
 Peak Elev= 59.910 m @ 0.33 hrs Surf.Area= 417.0 m² Storage= 299.0 m³

Plug-Flow detention time= 119.5 min calculated for 321.4 m³ (100% of inflow)
 Center-of-Mass det. time= 119.7 min (129.7 - 10.0)


Volume	Invert	Avail.Storage	Storage Description
#1	59.200 m	834.0 m ³	Custom Stage Data (Prismatic) listed below (Recalc)
#2	58.680 m	3.1 m ³	375 mm Round Pipe Storage
			L= 28.41 m S= 0.0186 m/m
		837.1 m ³	Total Available Storage

Elevation (meters)	Surf.Area (sq-meters)	Inc.Store (cubic-meters)	Cum.Store (cubic-meters)
59.200	417.0	0.0	0.0
61.200	417.0	834.0	834.0

Device	Routing	Invert	Outlet Devices	C
#1	Primary	58.680 m	100 mm Vert. Orifice/Grate	0.630

Primary OutFlow Max=0.02380 m³/s @ 0.33 hrs HW=59.909 m (Free Discharge)
 #1=Orifice/Grate (Orifice Controls 0.02380 m³/s @ 3.03 m/s)

Pond 207P: Storage Chmabers




Summary for Link 209L: Post-Dev

Inflow Area = 19,300.0 m², 0.00% Impervious, Inflow Depth = 22 mm for 100-Year event
 Inflow = 0.19716 m³/s @ 0.17 hrs, Volume= 430.1 m³
 Primary = 0.19716 m³/s @ 0.17 hrs, Volume= 430.1 m³, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs



Link 209L: Post-Dev



Area Listing (selected nodes)

Area (sq-meters)	C	Description (subcatchment-numbers)
13,700.0	0.79	Controlled (208S)
1,900.0	0.85	Uncontrolled (210S)
1,200.0	0.33	Uncontrolled (212S)
2,500.0	0.65	Uncontrolled (214S)
19,300.0	0.75	TOTAL AREA

**POST-DEVELOPMENT
CONDITIONS**



Routing Diagram for uOttawa-LEES_2021-10-06

Prepared by WSP, Printed 10/7/2021

HydroCAD® 10.00-21 s/n 10697 © 2018 HydroCAD Software Solutions LLC

Ground Covers (selected nodes)

HSG-A (sq-meters)	HSG-B (sq-meters)	HSG-C (sq-meters)	HSG-D (sq-meters)	Other (sq-meters)	Total (sq-meters)	Ground Cover	Subca Numbr
0.0	0.0	0.0	0.0	13,700.0	13,700.0	Controlle d	
0.0	0.0	0.0	0.0	5,600.0	5,600.0	Uncontrol led	
0.0	0.0	0.0	0.0	19,300.0	19,300.0	TOTAL AREA	

Time span=0.00-6.00 hrs, dt=0.01 hrs, 601 points
 Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment208S: PR-003 Runoff Area=1.3700 ha 0.00% Impervious Runoff Depth=51 mm
 Tc=10.0 min C=0.79 Runoff=0.10293 m³/s 704.0 m³

Subcatchment210S: PR-002 Runoff Area=0.1900 ha 0.00% Impervious Runoff Depth=55 mm
 Tc=10.0 min C=0.85 Runoff=0.01536 m³/s 105.1 m³

Subcatchment212S: PR-004 Runoff Area=0.1200 ha 0.00% Impervious Runoff Depth=21 mm
 Tc=10.0 min C=0.33 Runoff=0.00377 m³/s 25.8 m³

Subcatchment214S: PR-001 Runoff Area=0.2500 ha 0.00% Impervious Runoff Depth=42 mm
 Tc=10.0 min C=0.65 Runoff=0.01545 m³/s 105.7 m³

Pond 207P: Storage Chmabers Peak Elev=60.482 m Storage=537.6 m³ Inflow=0.10293 m³/s 704.0 m³
 Outflow=0.02901 m³/s 521.5 m³

Link 209L: Post-Dev Inflow=0.06327 m³/s 758.1 m³
 Primary=0.06327 m³/s 758.1 m³

Total Runoff Area = 19,300.0 m² Runoff Volume = 940.6 m³ Average Runoff Depth = 49 mm
100.00% Pervious = 19,300.0 m² 0.00% Impervious = 0.0 m²

Summary for Subcatchment 208S: PR-003


Runoff = 0.10293 m³/s @ 0.17 hrs, Volume= 704.0 m³, Depth= 51 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
 Ottawa 100-Year Duration=114 min, Inten=34.2 mm/hr

Area (ha)	C	Description
1.3700	0.79	Controlled
1.3700		100.00% Pervious Area

Tc (min)	Length (meters)	Slope (m/m)	Velocity (m/sec)	Capacity (m³/s)	Description
10.0					Direct Entry,

Subcatchment 208S: PR-003



Summary for Subcatchment 210S: PR-002


Runoff = 0.01536 m³/s @ 0.17 hrs, Volume= 105.1 m³, Depth= 55 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
 Ottawa 100-Year Duration=114 min, Inten=34.2 mm/hr

Area (ha)	C	Description
0.1900	0.85	Uncontrolled
0.1900		100.00% Pervious Area

Tc (min)	Length (meters)	Slope (m/m)	Velocity (m/sec)	Capacity (m³/s)	Description
10.0					Direct Entry,

Subcatchment 210S: PR-002



Summary for Subcatchment 212S: PR-004


Runoff = 0.00377 m³/s @ 0.17 hrs, Volume= 25.8 m³, Depth= 21 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
 Ottawa 100-Year Duration=114 min, Inten=34.2 mm/hr

Area (ha)	C	Description
0.1200	0.33	Uncontrolled
0.1200		100.00% Pervious Area

Tc (min)	Length (meters)	Slope (m/m)	Velocity (m/sec)	Capacity (m³/s)	Description
10.0					Direct Entry,

Subcatchment 212S: PR-004



Summary for Subcatchment 214S: PR-001


Runoff = 0.01545 m³/s @ 0.17 hrs, Volume= 105.7 m³, Depth= 42 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
 Ottawa 100-Year Duration=114 min, Inten=34.2 mm/hr

Area (ha)	C	Description
0.2500	0.65	Uncontrolled
0.2500		100.00% Pervious Area

Tc (min)	Length (meters)	Slope (m/m)	Velocity (m/sec)	Capacity (m³/s)	Description
10.0					Direct Entry,

Subcatchment 214S: PR-001



Summary for Pond 207P: Storage Chmabers

Inflow Area = 13,700.0 m², 0.00% Impervious, Inflow Depth = 51 mm for 100-Year event
 Inflow = 0.10293 m³/s @ 0.17 hrs, Volume= 704.0 m³
 Outflow = 0.02901 m³/s @ 2.02 hrs, Volume= 521.5 m³, Atten= 72%, Lag= 111.0 min
 Primary = 0.02901 m³/s @ 2.02 hrs, Volume= 521.5 m³

Routing by Stor-Ind method, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs
 Peak Elev= 60.482 m @ 2.02 hrs Surf.Area= 417.0 m² Storage= 537.6 m³

Plug-Flow detention time= 134.6 min calculated for 521.5 m³ (74% of inflow)
 Center-of-Mass det. time= 119.8 min (181.8 - 62.0)


Volume	Invert	Avail.Storage	Storage Description
#1	59.200 m	834.0 m ³	Custom Stage Data (Prismatic) listed below (Recalc)
#2	58.680 m	3.1 m ³	375 mm Round Pipe Storage
			L= 28.41 m S= 0.0186 m/m
		837.1 m ³	Total Available Storage

Elevation (meters)	Surf.Area (sq-meters)	Inc.Store (cubic-meters)	Cum.Store (cubic-meters)
59.200	417.0	0.0	0.0
61.200	417.0	834.0	834.0

Device	Routing	Invert	Outlet Devices	C
#1	Primary	58.680 m	100 mm Vert. Orifice/Gate	0.630

Primary OutFlow Max=0.02901 m³/s @ 2.02 hrs HW=60.482 m (Free Discharge)
 #1=Orifice/Gate (Orifice Controls 0.02901 m³/s @ 3.69 m/s)

Pond 207P: Storage Chmabers




Summary for Link 209L: Post-Dev

Inflow Area = 19,300.0 m², 0.00% Impervious, Inflow Depth > 39 mm for 100-Year event
 Inflow = 0.06327 m³/s @ 1.90 hrs, Volume= 758.1 m³
 Primary = 0.06327 m³/s @ 1.90 hrs, Volume= 758.1 m³, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-6.00 hrs, dt= 0.01 hrs

Link 209L: Post-Dev



APPENDIX

C SUPPORTING DOCUMENTS



PROJECT INFORMATION	
ENGINEERED PRODUCT MANAGER:	HAIDER NASRULLAH 647-850-9417 HAIDER.NASRULLAH@ADS-PIPE.COM
ADS SALES REP:	MICHAEL REID 613-882-4186 MICHAEL.REID@ADS-PIPE.COM
PROJECT NO:	S229751
ADS SITE COORDINATOR:	MATTHEW BEGHIN 519-710-3687 MATTHEW.BEGHIN@ADS-PIPE.COM



SiteASSIST™
FOR STORMTECH
INSTRUCTIONS,
DOWNLOAD THE
INSTALLATION APP



UOTTAWA HEALTH SCIENCE BUILDING

OTTAWA, ON.

MC-4500 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH MC-4500.
- CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE COPOLYMERS.
- CHAMBERS SHALL BE CERTIFIED TO CSA B184, "POLYMERIC SUB-SURFACE STORMWATER MANAGEMENT STRUCTURES", AND MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS" CHAMBER CLASSIFICATION 60x101.
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE CSA S6 CL-625 TRUCK AND THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
- CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 75 mm (3").
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 450 LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 23° C / 73° F), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:
 - THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
 - THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
 - THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2418 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN.
- CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF MC-4500 CHAMBER SYSTEM

- STORMTECH MC-4500 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- STORMTECH MC-4500 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
- CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
 - STONESHOOTER LOCATED OFF THE CHAMBER BED.
 - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
 - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
- MAINTAIN MINIMUM - 230 mm (9") SPACING BETWEEN THE CHAMBER ROWS.
- INLET AND OUTLET MANIFOLDS MUST BE INSERTED A MINIMUM OF 300 mm (12") INTO CHAMBER END CAPS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE WELL GRADED BETWEEN ¾" AND 2" (20-50 mm).
- STONE SHALL BE BROUGHT UP EVENLY AROUND CHAMBERS SO AS NOT TO DISTORT THE CHAMBER SHAPE. STONE DEPTHS SHOULD NEVER DIFFER BY MORE THAN 300 mm (12") BETWEEN ADJACENT CHAMBER ROWS.
- STONE MUST BE PLACED ON THE TOP CENTER OF THE CHAMBER TO ANCHOR THE CHAMBERS IN PLACE AND PRESERVE ROW SPACING.
- THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIAL BEARING CAPACITIES TO THE SITE DESIGN ENGINEER.
- ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.

NOTES FOR CONSTRUCTION EQUIPMENT

- STORMTECH MC-4500 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
- THE USE OF EQUIPMENT OVER MC-4500 CHAMBERS IS LIMITED:
 - NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
 - NO RUBBER Tired LOADER, DUMP TRUCK, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
 - WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
- FULL 900 mm (36") OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.

USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY USING THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.

CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.

PROPOSED LAYOUT


95	STORMTECH MC-4500 CHAMBERS
14	STORMTECH MC-4500 END CAPS
305	STONE ABOVE (mm)
229	STONE BELOW (mm)
40	% STONE VOID
539.0	INSTALLED SYSTEM VOLUME (m³) (PERIMETER STONE INCLUDED)
434.9	SYSTEM AREA (m²)
153.9	SYSTEM PERIMETER (m)

PROPOSED ELEVATIONS

62.815	MAXIMUM ALLOWABLE GRADE (TOP OF PAVEMENT/UNPAVED):
61.443	MINIMUM ALLOWABLE GRADE (UNPAVED WITH TRAFFIC):
61.291	MINIMUM ALLOWABLE GRADE (UNPAVED NO TRAFFIC):
61.291	MINIMUM ALLOWABLE GRADE (BASE OF FLEXIBLE PAVEMENT):
61.291	MINIMUM ALLOWABLE GRADE (TOP OF RIGID PAVEMENT):
60.986	TOP OF STONE:
60.681	TOP OF MC-4500 CHAMBER:
59.988	375 mm TOP MANIFOLD INVERT:
59.904	450 mm TOP MANIFOLD/CONNECTION INVERT:
59.215	600 mm ISOLATOR ROW PLUS INVERT:
59.200	375 mm BOTTOM CONNECTION INVERT:
59.157	BOTTOM OF MC-4500 CHAMBER:
58.928	UNDERDRAIN INVERT:
58.928	BOTTOM OF STONE:

NOTES

- MANIFOLD SIZE TO BE DETERMINED BY SITE DESIGN ENGINEER. SEE TECHNICAL NOTE 6.32 FOR MANIFOLD SIZING GUIDANCE.
- DUE TO THE ADAPTATION OF THIS CHAMBER SYSTEM TO SPECIFIC SITE AND DESIGN CONSTRAINTS, IT MAY BE NECESSARY TO CUT AND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD COMPONENTS IN THE FIELD.
- THE SITE DESIGN ENGINEER MUST REVIEW ELEVATIONS AND IF NECESSARY ADJUST GRADING TO ENSURE THE CHAMBER COVER REQUIREMENTS ARE MET.
- THIS CHAMBER SYSTEM WAS DESIGNED WITHOUT SITE-SPECIFIC INFORMATION ON SOIL CONDITIONS OR BEARING CAPACITY. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR DETERMINING THE SUITABILITY OF THE SOIL AND PROVIDING THE BEARING CAPACITY OF THE INSITU SOILS. THE BASE STONE DEPTH MAY BE INCREASED OR DECREASED ONCE THIS INFORMATION IS PROVIDED.
- ADS DOES NOT DESIGN OR PROVIDE MEMBRANE LINER SYSTEMS. TO MINIMIZE THE LEAKAGE POTENTIAL OF LINER SYSTEMS, THE MEMBRANE LINER SYSTEM SHOULD BE DESIGNED BY A KNOWLEDGEABLE GEOTEXTILE PROFESSIONAL AND INSTALLED BY A QUALIFIED CONTRACTOR.
- **NOT FOR CONSTRUCTION: THIS LAYOUT IS FOR DIMENSIONAL PURPOSES ONLY TO PROVE CONCEPT & THE REQUIRED STORAGE VOLUME CAN BE ACHIEVED ON SITE.**



UOTTAWA HEALTH SCIENCE BUILDING	
OTTAWA, ON.	
DATE: 06/21/21	DRAWN: RCT
PROJECT #: S229751	CHECKED: RCT

DATE	DRWN	CHKD	DESCRIPTION
07/28/21	RCT	RCT	REVISED PER NEW PLAN

StormTech
 Attention: Retention + Water Quality
 520 CROMWELL AVENUE | ROCKY HILL | CT | 06067
 860-529-8188 | 888-892-2894 | WWW.STORMTECH.COM

ADS
 4640 TRUEMAN BLVD
 HILLIARD, OH 43026

SCALE = 1 : 200


THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.

ACCEPTABLE FILL MATERIALS: STORMTECH MC-4500 CHAMBER SYSTEMS

MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
C	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 24" (600 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	AASHTO M145 ¹ A-1, A-2-4, A-3 OR AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 24" (600 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 12" (300 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS.
B	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	AASHTO M43 ¹ 3, 4	NO COMPACTION REQUIRED.
A	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	AASHTO M43 ¹ 3, 4	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. ^{2,3}

PLEASE NOTE:

- THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
- STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 9" (230 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR.
- WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS.
- ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.



NOTES:

- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS" CHAMBER CLASSIFICATION 60x101
- MC-4500 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
 - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 3".
 - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 500 LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.


UTTAWA HEALTH SCIENCE BUILDING
 OTTAWA, ON.
 DATE: 06/21/21
 PROJECT #: S229751
 DRAWN: RCT
 CHECKED: RCT

DATE	DESCRIPTION
07/28/21	RCT REVISED PER NEW PLAN
	RCT DRWN CHKD

520 CROMWELL AVENUE | ROCKY HILL | CT | 06067
 860-529-8188 | 888-892-2894 | WWW.STORMTECH.COM

4640 TRUEMAN BLVD
 HILLIARD, OH 43026

THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.



MC-4500 ISOLATOR ROW PLUS DETAIL


NTS

INSPECTION & MAINTENANCE

- STEP 1) INSPECT ISOLATOR ROW PLUS FOR SEDIMENT
- A. INSPECTION PORTS (IF PRESENT)
 - A.1. REMOVE/OPEN LID ON NYLOPLAST INLINE DRAIN
 - A.2. REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
 - A.3. USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG
 - A.4. LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL)
 - A.5. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
 - B. ALL ISOLATOR PLUS ROWS
 - B.1. REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS
 - B.2. USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW PLUS THROUGH OUTLET PIPE
 - i) MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY
 - ii) FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE
 - B.3. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
- STEP 2) CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS
- A. A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45" (1.1 m) OR MORE IS PREFERRED
 - B. APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN
 - C. VACUUM STRUCTURE SUMP AS REQUIRED
- STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.
- STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

NOTES

1. INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS.
2. CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.



MC-4500 6" (150 mm) INSPECTION PORT DETAIL

NTS

UOTTAWA HEALTH SCIENCE BUILDING
OTTAWA, ON.

DATE:	06/21/21	DRAWN:	RCT
PROJECT #:	S229751	CHECKED:	RCT
DATE	07/28/21	RCT	REVISED PER NEW PLAN
DATE		DRWN	CHKD
DATE		RCT	DESCRIPTION

StormTech
Dedication • Retention • Water Quality

520 CROMWELL AVENUE | ROCKY HILL | CT | 06067
860-525-8188 | 888-892-2894 | WWW.STORMTECH.COM


4640 TRUEMAN BLVD
HILLIARD, OH 43026



THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.


UNDERDRAIN DETAIL

NTS



MC-SERIES END CAP INSERTION DETAIL


NTS



NOTE: MANIFOLD STUB MUST BE LAID HORIZONTAL FOR A PROPER FIT IN END CAP OPENING.

MC-4500 TECHNICAL SPECIFICATION

NTS



NOMINAL CHAMBER SPECIFICATIONS

SIZE (W X H X INSTALLED LENGTH)	100.0" X 60.0" X 48.3"	(2540 mm X 1524 mm X 1227 mm)
CHAMBER STORAGE	106.5 CUBIC FEET	(3.01 m ³)
MINIMUM INSTALLED STORAGE*	162.6 CUBIC FEET	(4.60 m ³)
WEIGHT (NOMINAL)	125.0 lbs.	(56.7 kg)

NOMINAL END CAP SPECIFICATIONS

SIZE (W X H X INSTALLED LENGTH)	90.0" X 61.0" X 32.8"	(2286 mm X 1549 mm X 833 mm)
END CAP STORAGE	39.5 CUBIC FEET	(1.12 m ³)
MINIMUM INSTALLED STORAGE*	115.3 CUBIC FEET	(3.26 m ³)
WEIGHT (NOMINAL)	90 lbs.	(40.8 kg)

*ASSUMES 12" (305 mm) STONE ABOVE, 9" (229 mm) STONE FOUNDATION AND BETWEEN CHAMBERS, 12" (305 mm) STONE PERIMETER IN FRONT OF END CAPS AND 40% STONE POROSITY.

PARTIAL CUT HOLES AT BOTTOM OF END CAP FOR PART NUMBERS ENDING WITH "B"
 PARTIAL CUT HOLES AT TOP OF END CAP FOR PART NUMBERS ENDING WITH "T"
 END CAPS WITH A PREFABRICATED WELDED STUB END WITH "W"

PART #	STUB	B	C
MC4500IEPP06T	6" (150 mm)	42.54" (1081 mm)	---
MC4500IEPP06B	---	---	0.86" (22 mm)
MC4500IEPP08T	8" (200 mm)	40.50" (1029 mm)	---
MC4500IEPP08B	---	---	1.01" (26 mm)
MC4500IEPP10T	10" (250 mm)	38.37" (975 mm)	---
MC4500IEPP10B	---	---	1.33" (34 mm)
MC4500IEPP12T	12" (300 mm)	35.69" (907 mm)	---
MC4500IEPP12B	---	---	1.55" (39 mm)
MC4500IEPP15T	15" (375 mm)	32.72" (831 mm)	---
MC4500IEPP15B	---	---	1.70" (43 mm)
MC4500IEPP18T	---	29.36" (746 mm)	---
MC4500IEPP18TW	18" (450 mm)	---	---
MC4500IEPP18B	---	---	1.97" (50 mm)
MC4500IEPP18BW	---	---	---
MC4500IEPP24T	---	23.05" (585 mm)	---
MC4500IEPP24TW	24" (600 mm)	---	---
MC4500IEPP24B	---	---	2.26" (57 mm)
MC4500IEPP24BW	---	---	---
MC4500IEPP30BW	30" (750 mm)	---	2.95" (75 mm)
MC4500IEPP36BW	36" (900 mm)	---	3.25" (83 mm)
MC4500IEPP42BW	42" (1050 mm)	---	3.55" (90 mm)

NOTE: ALL DIMENSIONS ARE NOMINAL

CUSTOM PREFABRICATED INVERTS ARE AVAILABLE UPON REQUEST. INVENTORIED MANIFOLDS INCLUDE 12-24" (300-600 mm) SIZE ON SIZE AND 15-48" (375-1200 mm) ECCENTRIC MANIFOLDS. CUSTOM INVERT LOCATIONS ON THE MC-4500 END CAP CUT IN THE FIELD ARE NOT RECOMMENDED FOR PIPE SIZES GREATER THAN 10" (250 mm). THE INVERT LOCATION IN COLUMN 'B' ARE THE HIGHEST POSSIBLE FOR THE PIPE SIZE.

OTTAWA HEALTH SCIENCE BUILDING
 OTTAWA, ON.

DATE: 06/21/21 DRAWN: RCT
 PROJECT #: S229751 CHECKED: RCT

5 SHEET OF 6


StormTech
 520 CROMWELL AVENUE | ROCKY HILL | CT | 06067
 860-529-8188 | 866-892-2894 | WWW.STORMTECH.COM

ADS
 4640 TRUEMAN BLVD
 HILLIARD, OH 43026

THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.

NYLOPLAST DRAIN BASIN

NTS



NOTES

- 8-30" (200-750 mm) GRATES/SOLID COVERS SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
- 12-30" (300-750 mm) FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
- DRAIN BASIN TO BE CUSTOM MANUFACTURED ACCORDING TO PLAN DETAILS
- DRAINAGE CONNECTION STUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D3212 FOR CORRUGATED HDPE (ADS & HANCOR DUAL WALL) & SDR 35 PVC
- FOR COMPLETE DESIGN AND PRODUCT INFORMATION: WWW.NYLOPLAST-US.COM
- TO ORDER CALL: **800-821-6710**

A	PART #	GRATE/SOLID COVER OPTIONS		
8" (200 mm)	2808AG	PEDESTRIAN LIGHT DUTY	STANDARD LIGHT DUTY	SOLID LIGHT DUTY
10" (250 mm)	2810AG	PEDESTRIAN LIGHT DUTY	STANDARD LIGHT DUTY	SOLID LIGHT DUTY
12" (300 mm)	2812AG	PEDESTRIAN AASHTO H-10	STANDARD AASHTO H-20	SOLID AASHTO H-20
15" (375 mm)	2815AG	PEDESTRIAN AASHTO H-10	STANDARD AASHTO H-20	SOLID AASHTO H-20
18" (450 mm)	2818AG	PEDESTRIAN AASHTO H-10	STANDARD AASHTO H-20	SOLID AASHTO H-20
24" (600 mm)	2824AG	PEDESTRIAN AASHTO H-10	STANDARD AASHTO H-20	SOLID AASHTO H-20
30" (750 mm)	2830AG	PEDESTRIAN AASHTO H-20	STANDARD AASHTO H-20	SOLID AASHTO H-20

UOTTAWA HEALTH SCIENCE BUILDING
OTTAWA, ON.

DATE: 06/21/21 DRAWN: RCT
PROJECT #: S229751 CHECKED: RCT

DATE	DESCRIPTION
07/28/21	RCT REVISED PER NEW PLAN
	RCT DRWN CHKD


3130 VERONA AVE
BUFORD, GA 30518
PHN (770) 932-2443
FAX (770) 932-2490
www.nyloplast-us.com

Nyloplast

4640 TRUEJMAN BLVD
HILLIARD, OH 43026

ADS

THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEER OR OTHER PROJECT REPRESENTATIVE. THE SITE DESIGN ENGINEER SHALL REVIEW THIS DRAWING PRIOR TO CONSTRUCTION. IT IS THE ULTIMATE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL APPLICABLE LAWS, REGULATIONS, AND PROJECT REQUIREMENTS.



Project: uOttawa Health Science Bldg Rev1



Chamber Model -
 Units -
 Number of Chambers -
 Number of End Caps -
 Voids in the stone (porosity) -
 Base of Stone Elevation -
 Amount of Stone Above Chambers -
 Amount of Stone Below Chambers -

MC-4500	
Metric	Click Here for Imperial
95	
14	
40	%
58.93	m
305	mm
229	mm

Include Perimeter Stone in Calculations

434.9 sq.meters Min. Area - 366.884 sq.meters

Height of System (mm)	Incremental Single Chamber (cubic meters)	Incremental Single End Cap (cubic meters)	Incremental Chambers (cubic meters)	Incremental End Cap (cubic meters)	Incremental Stone (cubic meters)	Incremental Chamber, End Cap and Stone (cubic meters)	Cumulative System (cubic meters)	Elevation (meters)
2057	0.00	0.00	0.00	0.00	4.420	4.42	539.04	60.99
2032	0.00	0.00	0.00	0.00	4.420	4.42	534.62	60.96
2007	0.00	0.00	0.00	0.00	4.420	4.42	530.21	60.93
1981	0.00	0.00	0.00	0.00	4.420	4.42	525.79	60.91
1956	0.00	0.00	0.00	0.00	4.420	4.42	521.38	60.88
1930	0.00	0.00	0.00	0.00	4.420	4.42	516.96	60.86
1905	0.00	0.00	0.00	0.00	4.420	4.42	512.54	60.83
1880	0.00	0.00	0.00	0.00	4.420	4.42	508.13	60.81
1854	0.00	0.00	0.00	0.00	4.420	4.42	503.71	60.78
1829	0.00	0.00	0.00	0.00	4.420	4.42	499.29	60.76
1803	0.00	0.00	0.00	0.00	4.420	4.42	494.88	60.73
1778	0.00	0.00	0.00	0.00	4.420	4.42	490.46	60.71
1753	0.00	0.00	0.11	0.01	4.370	4.49	486.04	60.68
1727	0.00	0.00	0.31	0.01	4.290	4.61	481.56	60.66
1702	0.00	0.00	0.44	0.02	4.230	4.69	476.95	60.63
1676	0.01	0.00	0.56	0.03	4.180	4.77	472.25	60.60
1651	0.01	0.00	0.72	0.03	4.110	4.87	467.48	60.58
1626	0.01	0.00	1.22	0.04	3.910	5.17	462.61	60.55
1600	0.02	0.00	1.79	0.05	3.680	5.52	457.44	60.53
1575	0.02	0.00	2.15	0.06	3.530	5.74	451.92	60.50
1549	0.03	0.01	2.44	0.07	3.410	5.93	446.18	60.48
1524	0.03	0.01	2.70	0.09	3.300	6.09	440.25	60.45
1499	0.03	0.01	2.93	0.10	3.210	6.23	434.16	60.43
1473	0.03	0.01	3.13	0.11	3.120	6.36	427.93	60.40
1448	0.03	0.01	3.32	0.12	3.040	6.48	421.57	60.38
1422	0.04	0.01	3.50	0.13	2.970	6.59	415.09	60.35
1397	0.04	0.01	3.66	0.14	2.900	6.70	408.50	60.33
1372	0.04	0.01	3.82	0.15	2.830	6.80	401.80	60.30
1346	0.04	0.01	3.96	0.16	2.770	6.89	395.01	60.27
1321	0.04	0.01	4.10	0.17	2.710	6.98	388.11	60.25
1295	0.04	0.01	4.24	0.19	2.650	7.07	381.13	60.22
1270	0.05	0.01	4.36	0.20	2.590	7.15	374.06	60.20
1245	0.05	0.01	4.48	0.21	2.540	7.23	366.91	60.17
1219	0.05	0.02	4.60	0.22	2.490	7.30	359.68	60.15
1194	0.05	0.02	4.71	0.22	2.440	7.38	352.38	60.12
1168	0.05	0.02	4.81	0.23	2.400	7.44	345.00	60.10
1143	0.05	0.02	4.92	0.24	2.350	7.51	337.56	60.07
1118	0.05	0.02	5.01	0.25	2.310	7.57	330.04	60.05
1092	0.05	0.02	5.11	0.25	2.270	7.63	322.47	60.02
1067	0.05	0.02	5.20	0.27	2.230	7.70	314.84	59.99
1041	0.06	0.02	5.28	0.28	2.190	7.75	307.14	59.97
1016	0.06	0.02	5.37	0.29	2.150	7.81	299.39	59.94
991	0.06	0.02	5.45	0.29	2.120	7.86	291.58	59.92
965	0.06	0.02	5.52	0.30	2.090	7.91	283.72	59.89
940	0.06	0.02	5.60	0.31	2.050	7.96	275.81	59.87
914	0.06	0.02	5.67	0.32	2.020	8.01	267.84	59.84
889	0.06	0.02	5.74	0.33	1.990	8.06	259.83	59.82
864	0.06	0.02	5.81	0.33	1.960	8.10	251.78	59.79
838	0.06	0.02	5.87	0.34	1.930	8.14	243.68	59.77
813	0.06	0.02	5.93	0.34	1.910	8.18	235.54	59.74
787	0.06	0.03	5.99	0.35	1.880	8.22	227.35	59.72
762	0.06	0.03	6.05	0.36	1.850	8.26	219.13	59.69
737	0.06	0.03	6.10	0.36	1.830	8.30	210.87	59.66
711	0.06	0.03	6.16	0.36	1.810	8.33	202.57	59.64
686	0.07	0.03	6.21	0.37	1.780	8.37	194.24	59.61
660	0.07	0.03	6.26	0.38	1.760	8.40	185.88	59.59
635	0.07	0.03	6.30	0.38	1.740	8.43	177.48	59.56
610	0.07	0.03	6.35	0.39	1.720	8.46	169.05	59.54
584	0.07	0.03	6.39	0.38	1.710	8.48	160.59	59.51
559	0.07	0.03	6.43	0.40	1.680	8.51	152.11	59.49
533	0.07	0.03	6.47	0.40	1.670	8.54	143.59	59.46
508	0.07	0.03	6.51	0.40	1.650	8.56	135.05	59.44
483	0.07	0.03	6.54	0.41	1.640	8.59	126.49	59.41
457	0.07	0.03	6.58	0.41	1.620	8.61	117.90	59.39
432	0.07	0.03	6.61	0.41	1.610	8.63	109.29	59.36
406	0.07	0.03	6.64	0.42	1.590	8.65	100.66	59.33
381	0.07	0.03	6.67	0.42	1.580	8.67	92.01	59.31
356	0.07	0.03	6.69	0.42	1.570	8.68	83.35	59.28
330	0.07	0.03	6.72	0.43	1.560	8.70	74.66	59.26
305	0.07	0.03	6.74	0.43	1.550	8.72	65.96	59.23
279	0.07	0.03	6.76	0.43	1.540	8.73	57.24	59.21
254	0.07	0.03	6.80	0.44	1.520	8.76	48.51	59.18
229	0.00	0.00	0.00	0.00	4.420	4.42	39.75	59.16
203	0.00	0.00	0.00	0.00	4.420	4.42	35.33	59.13
178	0.00	0.00	0.00	0.00	4.420	4.42	30.91	59.11
152	0.00	0.00	0.00	0.00	4.420	4.42	26.50	59.08
127	0.00	0.00	0.00	0.00	4.420	4.42	22.08	59.06
102	0.00	0.00	0.00	0.00	4.420	4.42	17.67	59.03
76	0.00	0.00	0.00	0.00	4.420	4.42	13.25	59.00
51	0.00	0.00	0.00	0.00	4.420	4.42	8.83	58.98
25	0.00	0.00	0.00	0.00	4.420	4.42	4.42	58.95

OTTAWA HEALTH SCIENCE BUILDING

DRAWING INDEX

TITLE	SHEET NO
COVER SHEET	1 OF 4
SIZING REPORT	2 OF 4
SDD PLAN	3 OF 4
OVERLAY SHEET	4 OF 4

PROJECT INFORMATION			
SITE CONTACT	PHIL ALLEN	416-286-5990	PHILALLEN@STORMCON.CA
ENGINEER / TECHNICAL SPECIALIST	PARTH PUSHKARNA, EIT	647-278-7339	PARTH@STORMCON.CA
SALES REP:	GREG DZIEWIECKI	437-231-6080	GREGD@STORMCON.CA
	PARTH PUSHKARNA	647-278-7339	PARTH@STORMCON.CA
PROJECT NO:	21-1.00-SDD3		

NOTES FOR BIDDING AND INSTALLATIONS

- CONTRACTORS ARE EXPECTED TO COMPREHEND AND USE THE MOST CURRENT INSTALLATION INSTRUCTIONS PRIOR TO BEGINNING A SYSTEM INSTALLATION. FOR THE MOST CURRENT INSTRUCTIONS, CONTACT STORMCON AT (647) 463-9803 OR VISIT WWW.STORMCON.CA.
- CONTACT STORMCON AT LEAST TWO WEEKS PRIOR TO SYSTEM INSTALLATION TO ARRANGE FOR A PRE-CONSTRUCTION MEETING.
- USE SDD3 INSTALLATION INSTRUCTIONS AS A GUIDELINE ONLY FOR MINIMUM/MAXIMUM REQUIREMENTS. ACTUAL DESIGN MAY VARY. REFER TO APPROVED CONSTRUCTION DRAWINGS FOR JOB-SPECIFIC DETAILS. ENGINEERING DRAWINGS SUPERSEDE ALL PROVIDED DOCUMENTATION.
- ANY DISCREPANCIES WITH THE SYSTEM SUB-GRADE SOIL'S BEARING CAPACITY MUST BE REPORTED TO THE GEOTECHNICAL ENGINEER.
- EROSION AND SEDIMENT-CONTROL MEASURES MUST MEET LOCAL CODES AND THE DESIGN ENGINEER'S SPECIFICATIONS THROUGHOUT THE ENTIRE SITE CONSTRUCTION PROCESS.

NOTE: THESE SHOP DRAWINGS MAY CONTAIN COMPONENTS INCLUDING BUT NOT LIMITED TO MANHOLES, CATCH BASINS, STORM PIPES AND FITTINGS, MANIFOLDS, CASTINGS AND OTHER NECESSARY APPURTENANCES THAT MAY NOT BE SUPPLIED BY STORMCON. IT IS THE RESPONSIBILITY OF THE CONTRACTOR AND/OR SUPPLIER TO CONFIRM THE MATERIALS PROVIDED.

GENERAL NOTES

- MANHOLES AND APPURTENANCES TO FOLLOW DIVISION 700 OF OPSD OR APPLICABLE LOCAL STANDARDS.
- COORDINATE WITH MANUFACTURER'S REPRESENTATIVE/DISTRIBUTOR FOR PRE-CONSTRUCTION MEETING AND SITE INSPECTION DURING INSTALLATION.
- ENGINEERING DRAWINGS SUPERSEDE ALL PROVIDED DOCUMENTATION. REFER TO SITE ENGINEERS FOR ADDITIONAL INSTRUCTIONS.
- COORDINATE SDD3 INSTALLATION ACTIVITIES WITH OTHER SITE ACTIVITIES
- ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE
- THE SUB-GRADE AND SIDE BACKFILL TO BE COMPACTED TO 95% SPD OR AS DIRECTED BY THE QUALIFIED ENGINEER.
- CONFIRM GEOTECHNICAL SOIL EVALUATION BY A QUALIFIED ENGINEER TO DETERMINE SUITABILITY OF STRUCTURAL INSTALLATION
- CONFIRM FOR BURIED UNDERGROUND UTILITIES INCLUDING GAS, ELECTRICAL, PIPELINES OR CONDUITS
- WHEN INSTALLED IN CONFORMANCE TO THE INSTALLATION GUIDELINES, SDD3 CAN HANDLE STANDARD CL-625 TRUCK LOADING. FOR NON-STANDARD LOADS CONTACT MANUFACTURER'S REPRESENTATIVE/DISTRIBUTOR
- PROTECT THE INSTALLATION AGAINST DAMAGE WITH CONSTRUCTION TAPE, FENCING OR OTHER MEANS TILL THE CONSTRUCTION IS COMPLETE.
- ENSURE THAT CONSTRUCTION FOLLOWS APPLICABLE FEDERAL, PROVINCIAL, LOCAL, MUNICIPAL AND LOCAL LAWS, ORDNANCES, REGULATIONS AND SAFETY REQUIREMENTS.

CHECK - REQUIRED MATERIALS AND EQUIPMENT

- ALL SDD3 COMPONENTS AND ACCESSORIES AS SPECIFIED IN THE ENGINEER'S PLANS INCLUDING FRAME AND COVER, LADDER ND RISER .
 - RECIPROCATING SAW OR ROUTER
 - TRANSIT OR LASER LEVEL MEASURING DEVICE
 - COMPACTION EQUIPMENT
- ACCEPTABLE FILL MATERIAL AS SHOWN IN INSTALLATION INSTRUCTIONS.

THIS DRAWING WAS PREPARED TO SUPPORT THE PROJECT ENGINEER OF RECORD FOR THE PROPOSED SYSTEM. IT IS THE ULTIMATE RESPONSIBILITY OF THE PROJECT ENGINEER OF RECORD TO ENSURE THAT THE SDD3 SYSTEM'S DESIGN IS IN FULL COMPLIANCE WITH ALL APPLICABLE LAWS AND REGULATIONS. IT IS THE CONTRACTOR OF RECORD'S RESPONSIBILITY TO ENSURE THAT THE STORMCON PRODUCTS ARE DESIGNED IN ACCORDANCE WITH STORMCON'S MINIMUM REQUIREMENTS. STORMCON DOES NOT APPROVE PLANS, SIZING, OR SYSTEM DESIGNS.

NO.	REVISION	DATE	BY
A	ISSUED FOR APPROVAL	19/08/2021	MC

ISSUED FOR APPROVAL
NOT FOR CONSTRUCTION
08/19/2021

COVER SHEET

SDD 1200

PROJECT NAME: OTTAWA HEALTH SCIENCE BDG

PROJECT NO: 210819-05 DATE: 08/19/2021

DESIGNED BY: MC CHECKED BY: MS

SCALE: NTS SHEET NO: 1/4






10 CEDAR AVE
THORNHILL, ON
L3T 3W1

SALES@STORMCON.CA
WWW.STORMCON.CA



1625, boul. Mgr. Langlois
Salaberry-de-Valleyfield,
Québec, Canada, J6S 1C2
T: (450) 322-6260
F: (450) 373-3360



NOTES:-

- PRECAST CONCRETE COMPONENTS SHALL BE ACCORDING TO OPSD 701.031, AND 701.032
- STRUCTURE EXCEEDING 5.0m IN DEPTH SHALL INCLUDE SAFETY PLATFORM ACCORDING TO OPSD 404.020.
- FOR ADJUSTMENT UNIT AND FRAME INSTALLATION, SEE OPSD 704.010.
- ALL REINFORCING STEEL HAS 30mm MIN. COVER
- ALL CAST-IN GASKET CONNECTORS ASTM C-923, F-2510
- GALVANIZE STEEL LADDER ACCORDING TO CSA 257.4
- ALL DIMENSIONS ARE NOMINAL.
- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE SHOWN

FLOW AND POLLUTANTS

- TARGETED POLLUTANTS:
 - SEDIMENTS (50-1000 MICRONS)
 - OILS DENSITY (0.85 G/CM³)
- H: PIPE DIAMETER
- NEGLIGIBLE HEAD LOSS
- UNIT CONFIGURATION: IN-LINE

A	ISSUED FOR APPROVAL	19/08/2021	MC
NO.	REVISION	DATE	BY

**ISSUED FOR APPROVAL
NOT FOR CONSTRUCTION
08/19/2021**

SDD PLAN

SDD 1200

PROJECT NAME: OTTAWA HEALTH SCIENCE BDG

PROJECT NO: 210819-05 DATE: 08/19/2021

DESIGNED BY: MC CHECKED BY: MS

SCALE: 1:25 SHEET NO: 4/4

 <small>10 CEDAR AVE THORNHILL, ON L3T 3W1</small>	 <small>1625, boul. Mgr. Langlois Salaberry-de-Valleyfield, Québec, Canada, J6S 1G2 T: (450) 322-6260 F: (450) 373-3360</small>
<small>SALES@STORMCON.CA WWW.STORMCON.CA</small>	