

## Engineering

- Land/Site Development
- Municipal Infrastructure
- Environmental/Water Resources
- Traffic/Transportation
- Recreational

## Planning

- Land/Site Development
- Planning Application Management
- Municipal Planning
- Urban Design
- Expert Witness (LPAT)
- Wireless Industry

## Landscape Architecture

- Streetscapes & Public Amenities
- Open Space, Parks & Recreation
- Community & Residential
- Commercial & Institutional
- Environmental Restoration



## Carré Saint Louis

**1050 Canadian Shield Avenue**

**Ottawa, Ontario**

**Servicing and Stormwater Management Report**

**SERVICING AND STORMWATER MANAGEMENT REPORT**

**CARRÉ SAINT LOUIS  
1050 CANADIAN SHIELD AVENUE  
OTTAWA, ONTARIO**

Prepared by:

**NOVATECH**  
Suite 200, 240 Michael Cowpland Drive  
Kanata, Ontario  
K2M 1P6

July 7, 2021

Novatech File: 120191  
Ref No. R-2021-097

July 7, 2021

Planning and Infrastructure Approvals  
City of Ottawa  
110 Laurier Avenue West  
Ottawa, Ontario, K1P 1J1

**Attention: Lisa Stern, MCIP, RPP**

Dear Ms Stern:

**Reference: Carré Saint Louis  
1050 Canadian Shield Avenue, Ottawa  
Servicing and Stormwater Management Report  
Our File No. : 120191**

---

Please find enclosed the 'Servicing and Stormwater Management Report' for the above noted project. This report is submitted in support of the Site Plan Application for the proposed development.

Should you have any questions or require additional information, please contact the undersigned.

Yours truly,

**NOVATECH**



Cara Ruddle, P.Eng.  
Senior Project Manager | Land Development Engineering

cc: Pascale Lépine, Lepine Corporation

## TABLE OF CONTENTS

<b>1.0</b>	<b>INTRODUCTION .....</b>	<b>1</b>
<b>2.0</b>	<b>EXISTING CONDITIONS .....</b>	<b>1</b>
<b>3.0</b>	<b>PROPOSED DEVELOPMENT .....</b>	<b>1</b>
<b>4.0</b>	<b>SERVICING REPORT REFERENCES .....</b>	<b>1</b>
<b>5.0</b>	<b>WATER SERVICING.....</b>	<b>1</b>
<b>6.0</b>	<b>SANITARY SERVICING .....</b>	<b>3</b>
<b>7.0</b>	<b>STORM SERVICING.....</b>	<b>5</b>
<b>8.0</b>	<b>STORMWATER MANAGEMENT .....</b>	<b>5</b>
<b>8.1</b>	<b>Stormwater Management Criteria.....</b>	<b>5</b>
<b>8.2</b>	<b>Quantity Control .....</b>	<b>5</b>
<b>8.3</b>	<b>Quality Control.....</b>	<b>6</b>
<b>8.4</b>	<b>Major Overland Flow Route .....</b>	<b>7</b>
<b>9.0</b>	<b>EROSION AND SEDIMENT CONTROL .....</b>	<b>7</b>
<b>9.1</b>	<b>Temporary Measures.....</b>	<b>7</b>
<b>10.0</b>	<b>CONCLUSIONS AND RECOMMENDATIONS .....</b>	<b>8</b>

### LIST OF FIGURES

Figure 1	Key Plan
Figure 2	Existing Conditions Plan
Figure 3	Site Plan

### LIST OF APPENDICIES

Appendix A	Correspondence
Appendix B	Water Servicing Information
Appendix C	Sanitary Servicing Information
Appendix D	Stormwater Management Calculations
Appendix E	Referenced Reports
Appendix F	Development Servicing Study Checklist
Appendix G	Drawings

### LIST OF ENGINEERING DRAWINGS

Notes and Details	(120191-ND)
General Plan of Services	(120191-GP)
Grading Plan	(120191-GR)

## 1.0 INTRODUCTION

Novatech has been retained to prepare a Servicing and Stormwater Management Report for the proposed development located at 1050 Canadian Shield Avenue, Ottawa (formerly Kanata), Ontario. The property at 1050 Canadian Shield Avenue is formally Block 2 of the Kanata Town Center Central Business District which is identified on Plan 4M-1325 provided in **Appendix A**. This report will support a Site Plan Application for the subject development. **Figure 1** Key Plan shows the site location.

## 2.0 EXISTING CONDITIONS

The site is currently mostly undeveloped consisting of grass with some shrub, trees, and a gravel parking area. The site is bounded by Campeau Drive to the north, the Red Oak Retirement Residence to the east, Canadian Shield Avenue to the south, and Great Lakes Avenue to the west. The property contains an existing berm on all sides with an opening in the south-east corner. The topography slopes in a south easterly direction towards Canadian Shield Avenue. There are existing municipal services in the Campeau Drive, Great Lakes Avenue and Canadian Shield Avenue Right-of Ways. **Figure 2** shows the existing site conditions.

## 3.0 PROPOSED DEVELOPMENT


The site is 1.10 hectares in size, and it is proposed to develop a six-storey, 244-unit apartment building with an underground parking structure and 274m<sup>2</sup> of commercial space with street access. There will be amenity areas provided in the building (such as a gym facility) but it is understood that these are for residents only. The building footprint is approximately 6205m<sup>2</sup> at the ground floor level. Access to the building and underground parking is proposed from Canadian Shield Avenue. A landscaped courtyard area is proposed within the center of the building over the proposed underground parking garage roof with external access from Campeau Drive. Refer to **Figure 3** for the proposed site layout.

## 4.0 SERVICING REPORT REFERENCES

- J.L. Richards & Associated Limited, Kanata Town Center Stormwater Management Report, Dated January 1999.
- J.L. Richards & Associated Limited, Kanata Town Center Servicing Brief (Revised), Dated June 13, 2012.
- J.L. Richards & Associated Limited, Kanata Town Centre Central Business District Master Design Sheet Update - Sanitary Peak Flows Block 4, Block 5 and Block west of Block 9 (Zone 122), Dated August 18, 2017.

## 5.0 WATER SERVICING

The proposed development is in the 3W pressure zone of the City of Ottawa water distribution network. There is an existing 200mm diameter watermain in the Canadian Shield Avenue right-of-way, a 200mm and a 900mm diameter watermain in the Great Lakes Avenue right-of-way, and a 300mm and 900mm diameter watermain within the Campeau Drive right-of-way. It is proposed to service the development by connecting to the existing 200mm diameter watermain within the Great Lakes Avenue right-of-way. As per the City of Ottawa Technical Bulletin ISDTB-2014-02, the proposed development will require two service connections since the average day demand for the proposed development is greater than 50 cubic meters of water.



M:\2020\120191\CAD\Design\120191-KP.dwg, Keyplan, Mar 23, 2021 - 2:00pm, jkaloudas



Engineers, Planners & Landscape Architects  
 Suite 200, 240 Michael Cowpland Drive  
 Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643  
 Facsimile (613) 254-5867  
 Website [www.novatech-eng.com](http://www.novatech-eng.com)



1050 CANADIAN SHIELD AVENUE

KEYPLAN

SCALE

N.T.S.

DATE

MAR 2021



JOB

120191

FIGURE

1

M:\2020\120191\CAD\Design\Figures\120191 - XCON.dwg, X-CON, Mar 24, 2021 - 9:58am, jkaloudas



**NOVATECH**

Engineers, Planners & Landscape Architects  
 Suite 200, 240 Michael Cowpland Drive  
 Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643  
 Facsimile (613) 254-5867  
 Website www.novatech-eng.com


**1050 CANADIAN SHIELD AVENUE**

**EXISTING CONDITIONS**


SCALE 1 : 750

DATE	MAR 2021	JOB	120191	FIGURE	2
------	----------	-----	--------	--------	---

M:\2020\120191\CAD\Design\Figures\120191 - PR SP.dwg, FIG 3 - PR SP, Mar 24, 2021 - 10:41am, jkaloudas



6 STOREY APARTMENT BUILDING  
FOOTPRINT=6333 SQM  
FFE=102.80  
P1 FFE=99.20  
P2 FFE=96.00



**NOVATECH**

Engineers, Planners & Landscape Architects  
Suite 200, 240 Michael Cowpland Drive  
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643  
Facsimile (613) 254-5867  
Website www.novatech-eng.com

1050 CANADIAN SHIELD AVENUE

PROPOSED SITE PLAN

SCALE 1 : 500

DATE JUN 2021 JOB 120191 FIGURE 3



The City of Ottawa design criteria for Water Distribution systems were used to calculate the theoretical water demand for the proposed six-storey apartment building. The water demand has been calculated for the building based on a population of 561 people and 274m<sup>2</sup> of commercial space, a summary of the flows is provided in **Table 6.1**.

**Table 6.1 Water Demand Summary**

	<b>Proposed Development</b>
<b>Water Demand Rate</b>	Residential: 350 (L/c/d) Commercial: 75 (L/9.3m <sup>2</sup> /day)
<b>Units/Area</b>	25 – 1 Bed, 158 – 2 Bed, 45- 3-Bed, 16 – 4-Bed
<b>Density</b>	1.4 ppu - 1 Bed, 2.1 ppu - 2 Bed, 3.1 ppu - 3 Bed, 3.4
<b>Factors</b>	Residential : MD=2.5, PH=2.20 Commercial: MD=1.5, PH =1.8
<b>Average Day Demand (L/s)</b>	2.30
<b>Maximum Daily Demand (L/s)</b>	5.72
<b>Peak Hour Demand (L/s)</b>	12.57
<b>FUS Fire Flow Requirement (L/s)</b>	183.00
<b>Max Day+Fire Flow (L/s)</b>	188.72

The required fire demand was calculated using the Fire Underwriters Survey (FUS) Guidelines. The proposed building is to be sprinklered with the Siamese connection located by the water services along Great Lakes Avenue. Existing hydrants within the Canadian Shield, Great Lakes Avenue, and Campeau Drive Right-of-Ways will provide fire protection for the proposed development. The required fire demand was calculated to be 2,906 USGPM (or 11,000 L/min). Refer to **Appendix B** for a copy of the water calculations.

The above water demand info was submitted to the City and boundary conditions provided from the City's water model. The boundary conditions are provided in **Table 6.2**.

**Table 6.2 Water Boundary Conditions**

<b>Criteria</b>	<b>Head (m)</b>	<b>Pressure (psi)</b>
<b><u>Connection 1 (Ground Elevation = 99.5m)</u></b>		
Max HGL	161.3	87.7
Peak Hour	156.3	80.5
Max Day + Fire Flow	147.9	68.6
<b><u>Connection 2 (Ground Elevation = 99.4)</u></b>		
Max HGL	161.3	87.9
Peak Hour	156.3	80.7
Max Day + Fire Flow	147.7	68.5

These boundary conditions were used to analyze the performance of the proposed watermain for three theoretical conditions:

- 1) High Pressure check under Average Day conditions
- 2) Peak Hour demand
- 3) Maximum Day + Fire Flow demand.

The following **Table 6.3** summarizes the results from the hydraulic water analysis.

**Table 6.3 Water Analysis Results Summary**

Condition	Demand (L/s)	Min/Max Allowable Operating Pressures (psi)	Limits of Design Operating Pressures (psi) <sup>1</sup>
<b>Connection 1</b>			
High Pressure	2.27	80psi (Max)	88.3
Peak Hour	12.42	40psi (Min)	81.2
Maximum Daily + <i>Fire Flow</i>	188.65	20psi (Min)	69.3
<b>Connection 2</b>			
High Pressure	2.27	80psi (Max)	88.3
Peak Hour	12.42	40psi (Min)	81.2
Maximum Daily + <i>Fire Flow</i>	188.65	20psi (Min)	69.0

<sup>1</sup>Pressures based on a P1 FEE of 99.20m

Based on the proceeding analysis it can be concluded that the watermain, as designed, will provide adequate system pressures for the fire flow + maximum day demand and peak hour demand. Refer to **Appendix B** for detailed hydraulic calculations and boundary conditions.

Since the average day demand for the development is greater than 50 cubic metres, two water services are required to service the building. Therefore, two 200mm diameter water services are proposed to service the building and will connect to the existing 200mm diameter watermain within the Great Lakes Avenue right-of-way. The two services will be separated by an isolation valve within the existing watermain system in the event maintenance on the City system is required. In the average day (high pressure), and the peak hour condition the system pressures are above the 80psi threshold, therefore pressure reducing valves will be required on both service connections. Refer to the General Plan of Services drawing (120191-GP) for the water servicing information.

## 6.0 SANITARY SERVICING

There are existing 200mm diameter sanitary sewers along Canadian Shield and Great Lakes Avenues and a 250mm diameter sanitary sewer along Campeau Drive. It is proposed to service the development by connecting a 200mm dia. sanitary service to the existing 200mm diameter sanitary sewer within the Canadian Shield Avenue right-of-way. This existing sanitary sewer flows east along Canadian Shield Avenue and connects to the existing 200mm sanitary sewer under Maritime Way where it flows south and connects to an existing 825mm sanitary trunk sewer. Refer to the General Plan of Services (120191-GP) for sanitary servicing information.

Flows for the proposed development have been calculated based on a total population of 561 people and 274m<sup>2</sup> of commercial space. The sanitary flows were calculated based on an average domestic demand of 280 L/day, and a commercial area flow of 75 L/9.3m<sup>2</sup>/day. The total peak flow calculated for the apartment building is 6.22 L/s. Sanitary flow calculations are included in **Appendix C** for reference.

The subject site is included in the Kanata Town Centre – Central Business District (KTC-CBD) Subdivision. A Technical Memorandum prepared by J.L. Richards dated June 13, 2012 provides design criteria for the KTC-CBD Subdivision area based on estimated developments within the subdivision. The Memorandum assumed that the subject property, which was denoted as Block 2 would be a commercial development. Refer to **table 7.1** for a comparison of the proposed development and the original allocated sanitary flows for the site from the J.L Richards design memorandum.

**Table 7.1 Sanitary flow summary**

	<b>Proposed Development</b>	<b>J.L. Richards Allocated Flow</b>
<b>Flow Rate</b>	280 L/c/d	50000L/ha/day
<b>Units</b>	25 – 1 Bed, 158 – 2 Bed, 45-3-Bed, 16 – 4-Bed	0
<b>Commercial area (m<sup>2</sup>)</b>	274	13,600m <sup>2</sup>
<b>Density</b>	1.4 ppu - 1 Bed 2.1 ppu - 2 Bed 3.1 ppu - 3 Bed 3.4 ppu - 4 Bed	n/a
<b>Population</b>	561	n/a
<b>Peaking Factor</b>	3.2	3.97
<b>Peak Daily Flow (L/s)</b>	5.77	1.18
<b>Peak Extraneous</b>	0.45	0.38
<b>Total Peak Design</b>	6.22	1.56

The total flow for the proposed development exceeds the allotted flow from the original J.L Richards design by 4.66 L/s. Based on the previous J.L. Richards memo, it is anticipated that the existing sewers will have adequate capacity for the development. The J.L Richards Memorandum includes a drainage area plan and the updated August 2017 sanitary sewer design sheets for the KTC-CBD subdivision and the downstream sanitary sewer system to the intersection of Campeau and Teron Road. A review of these design sheet indicates that there is adequate capacity within the downstream sanitary sewer for the proposed development. Flows for the proposed development have been provided to JL Richards to update their Technical Memorandum and the Master Sanitary Sewer Design Sheets and confirm adequate capacity of the downstream sanitary sewer system. The updated memo from JL Richards will be added to this report upon receipt. A copy of the August 2017 Technical Memorandum with design sheets are included in **Appendix E**.

## 7.0 STORM SERVICING

There is an existing 375mm and 450mm diameter storm sewer within the Canadian Shield Avenue right-of-way, an existing 300mm diameter storm sewer within the Great Lakes right-f-way and a 525mm diameter storm sewer within the Campeau Drive right-of-way. The existing 450mm diameter storm sewer within Canadian Shield Avenue is the proposed storm sewer outlet for the subject site. This existing storm sewer outlets to the existing Stormwater Management Facility downstream of the site at the end of Maritime Way (adjacent to Highway 417).

The building frontage areas will sheet drain across the boulevard area and to the existing storm sewer systems within each of the Campeau Drive, Great Lakes Avenue and Canadian Shield Avenue right-of-ways. Stormwater from the remainder of the site will be collected in area drains and into a private storm sewer system which will outlet to the existing 450mm diameter storm sewer along Canadian Shield Avenue. The storm servicing information is shown on the General Plan of Services (120191-GP).

## 8.0 STORMWATER MANAGEMENT

### 8.1 Stormwater Management Criteria

As indicated previously, the subject site is part of the Kanata Town Centre – Central Business District Subdivision. This subdivision is serviced by a Stormwater Management Facility (wet pond) currently located to the south-east of the site along Maritime Way (adjacent to the highway). The facility provides both quantity and quality control of stormwater. The facility design is outlined in a report entitled 'Stormwater Management Report Kanata Town Centre Central Business District' prepared by J.L. Richards & Associates Ltd. dated January 1999. A subsequent Technical Memorandum was prepared by J.L. Richards dated June 13, 2012. This Technical Memorandum updates the servicing information based on an increase in number of units proposed. The following Stormwater Management criteria is proposed for the subject development based on criteria established in the above noted J.L. Richards Report/Memorandum:

- Post-development peak flows to the existing storm sewer are to be controlled to the 5-year pre-development levels for all storms up to and including the 100-year event with a run-off coefficient of 0.8.

### 8.2 Quantity Control

Stormwater from the proposed development for storms up to and including the 100-year storm event will be controlled to the 5-year pre-development level with a run-off coefficient of 0.8 and a time of concentration of 20 minutes. The allowable release to the existing Canadian Shield Avenue storm sewer was calculated to be 171.9L/s.

The site has been divided into three different drainage areas as follows:

**Area A-1**

- The area surrounding the building that will sheet drain to the surrounding right-of-ways, and properties as per existing conditions

**Area A-2**

- Flows from the building roof and central courtyard area will be directed to the existing storm sewer along Canadian Shield. These flows will be captured by roof drains and area deck drains and will be conveyed by internal building plumbing to an underground storage tank under the front of the building. Flows from the storage tank will be controlled by an inlet control device prior to release to the existing storm sewer along Canadian Shield Avenue. Storage will be provided for storms up to and including the 100-year event within the storage tank.

**Area A-3**

- Flows from the sunken patio area at the south west corner of the building will also be directed to the storm sewer along Canadian Shield Avenue. Stormwater in this area will be collected by deck drains and connect into the storm service downstream of the stormwater storage tank.

Refer to the Stormwater Management Plan (120191-SWM) for the various drainage areas. **Table 9.1** below summarizes the flow, storage required, and storage provided for each of the site drainage areas.

**Table 9.1 Stormwater Management Summary**

Area ID	Area (ha)	1:5 Year Weighted Cw	Orifice Size & Type	5 Year Storm Event			100 Year Storm Event		
				Flow (L/s)	Req Vol (cu.m)	Max. Vol. Prov (cu.m.)	Flow (L/s)	Req Vol (cu.m)	Max. Vol. Prov (cu.m.)
A-1	0.196	0.37	N/A	21.1	N/A	N/A	42.2	N/A	N/A
A-2	0.871	0.90	189mm	82.6	147	>312	116.6	275	>312
A-3	0.025	0.90	N/A	6.5	N/A	N/A	12.4	N/A	N/A
<b>Total Flow</b>				<b>110.2</b>			<b>171.2</b>		
<b>Allowable</b>				<b>171.9</b>			<b>171.9</b>		

Refer to **Appendix D** for Rational Method calculations and modeling results. Refer to the Grading Plans (120191-GR) and the Stormwater Management Plan (120191-SWM) for more details.

**8.3 Quality Control**

Quality control of stormwater is provided from the existing Stormwater Management Facility located downstream of the site at the end of Maritime Way (adjacent to the highway). Sections of the J.L Richards Kanata Town Center Stormwater Management Report dated January 1999 have been provided in Appendix A of the report which details the total treated drainage area and the design parameters used in the QUALHYMO model. The J.L Richards report identifies that the SWMF facility has been designed for a treatment level of 70% TSS removal. The proposed

development of Block 2 of the Kanata Town Center was included in the sub-watershed area number 3 for the QUALHYMO model and has been accounted for in the design of stormwater management facility for quality control.

#### **8.4 Major Overland Flow Route**

A major overland flow route will be provided for storms greater than the 100-year storm event. Stormwater from the central courtyard, and the rear of the site will be directed to Campeau Drive. Stormwater from the storage tank in the building will overflow out of the access lid to Canadian Shield Avenue and will flow towards the existing SWM facility. The major overland system is shown on the Grading Plan (dwg 120191-GR).

### **9.0 EROSION AND SEDIMENT CONTROL**

#### **9.1 Temporary Measures**

Temporary erosion and sediment control measures will be implemented during construction. Silt fence, mud mats and filter socks in catchbasins, and area drains will be used as erosion and sediment control measures.

Erosion and sediment control measures should be inspected daily and after every rain event to determine maintenance, repair or replacement requirements. Sediments or granulars that enter site sewers shall be removed immediately by the contractor. These measures will be implemented prior to the commencement of construction and maintained in good order until vegetation has been established. Refer to the Grading Plan and Notes and Details Plan (dwg 120191-GR, 120191-ND) for additional information.

## 10.0 CONCLUSIONS AND RECOMMENDATIONS

- Water servicing for the proposed development will be serviced by two connections. Two 200mm diameter water services will connect to the existing 200mm diameter watermain within the Great Lakes Avenue right-of-way. The two services will be separated by an isolation valve within the existing watermain system in the event maintenance on the City system is required. The existing watermain infrastructure can provide adequate domestic flows and pressure for fire protection. Pressure reducing valves will be required on both water service connections.
- The proposed building will be serviced by a 200mm diameter sanitary service. The proposed building service will connect to the existing 200mm sanitary sewer within the Canadian Shield Avenue right-of-way. The existing sanitary sewer has adequate excess capacity to service the development.
- Quantity control of stormwater will be provided through a stormwater storage tank to attenuate flows to the existing storm sewer along Canadian Shield Avenue to the 5-year pre-development level for storms up to and including the 100-year event. The allowable release rate is 171.9 L/s and the post-development stormwater release rates are 110.2 L/s and 171.2 L/s for the 5 and 100 year events respectively.
- Quality control of stormwater management will be provided in the existing end of pipe stormwater management facility located on Maritime Way.
- An overland flow route is provided.
- Erosion and sediment control measures will be implemented prior to and during construction.

### NOVATECH

Prepared by:



Paul Newcombe, EIT  
Land Development Engineering

Reviewed by:



Cara Ruddle, P. Eng.  
Senior Project Manager

## **APPENDIX A**

### **Correspondence**




## Planning Comments

1. The proposal is subject to a Minor Zoning By-law Amendment application and a subsequent Site Plan Control, Complex application. The application fee and timeline can be found [here](#).
2. The site is zoned MC15 [2027].

## **Zoning Deficiencies**

3. In the MC15 subzone, there is a requirement for office types uses (FSI of 1.5 or amount equal to residential) before residential is allowed. Similarly, retail and other commercial uses is only allowed when office/residential types use reaches FSI of 0.75 or greater. The goal is to promote office type uses first before allowing a mix of uses within the building.
4. All part of the building facing Campeau requires a maximum setback of 6.5m.



5. Maximum setback from a lot line abutting Great Lakes and Canadian Shield for at least 80% width of any building wall
  - a. 0.5 m; or
  - b. 2 m where a patio is located between the building wall and a lot line
6. Please confirm what the proposed building height is along Great Lakes and Canadian Shield. The cross section shows 7 storeys based on average grade which exceed the zoning and OP requirement of 6 storeys. If this design is kept, an Official Plan Amendment will also be required.
7. Please confirm if the minimum building separation to the adjacent retirement is met. The requirement is 12m for any portion greater than 15m in height. If the proposal changes based on the urban design comments (below) into two buildings, please make sure that proper separation distance is maintained.
8. Exceed maximum gfa of 2,500 sq m above for floors above 15m in height. This means that any floor even with a portion exceeding 15m need to adhere to the 2,500 sq m requirement.
9. Please confirm if minimum landscape area of 30% is met.
10. Please confirm if 50% of the length of any ground floor wall facing a public street must consist of windows and/or entrances.

11. Any proposed non-residential use on the ground floor must have direct access to the street.
12. Please confirm parking count at the time of submission.
13. Please confirm sufficient amenity space is provided as per section 137.

#### **Official Plan**

14. The site is designated as Town Centre within the City's Official Plan.
15. Employment target of at least 10,000 jobs in the Town Centre. Based on the 2016 Employment Survey, the current job number is 8,093. Please confirm that the remaining parcels can sufficient achieve the 10,000 jobs target if there is a request to reduce the amount of employment uses on-site.
16. Please confirm if the proposal meets the 120 people/jobs per gross hectare density target in Figure 2.3 of the OP.
17. The site is designated as Centre Business District with a maximum height of 6 storeys under the [Kanata Town Centre Secondary Plan](#).
18. Under the secondary plan, the following is required. Any deviation will result in the need of an OPA application.

**Development facing Campeau Drive** (between the City lands to the west and Gray Crescent) will be subject to the following provisions:

- a. A minimum building height of three storeys is required
  - b. The maximum building height is three storeys for any development within 25 metres of the lot line abutting Campeau Drive **Current design does not meet this.**
  - c. Mid-rise buildings up to a maximum of six storeys are permitted provided the building transitions from three storeys along Campeau Drive in accordance with the principles in Section 4.11 of the Official Plan. **Current design does not meet this.**
  - d. To maintain a landscaped buffer and parkway character between the edge of the Town Centre and residential neighbourhoods to the north, yard setbacks from a lot line abutting Campeau Drive will generally be 6 metres.
19. A 100% residential building does not meet the intent of the Central Business District. It is the intent of this designation that these lands become an urban place that provides for employment uses, complemented by higher density residential uses. Given that this site has a zoning that requires a minimum of 1.5 FSI for non-residential uses before residential is permitted, an amendment to eliminate all non-residential uses may not be suitable. Please incorporate some non-residential uses into the building and preferably along the ground floor facing

Canadian Shield and Great Lakes. The frontage facing Campeau should remain residential in nature.

20. Cash-in-lieu of parkland will be required based on the Parkland Dedication By-law. If this has been previously paid through the subdivision process, please provide evidence of payment.
21. Please consult the Ward Councillor, Jenna Sudds, prior to application submission.

### **Urban Design Comments**

1. A Design Brief is required. The requirements are attached.
2. Urban Design Review Panel will be required for the proposed increase in height and density beyond the current 2500 sq. m. threshold for all building gfa above 15 metres in height.
3. PRUD staff are concerned with a complete elimination of 100% of the requirement for non-residential uses, given the current requirement for 1.5 FSI of non-residential use. At a minimum the ground floor abutting Canadian Shield Avenue and Great Lakes Avenue should contain non-residential uses.
4. The provision of non-residential uses at grade is not conducive to the proposed 7+/- setback along Canadian Shield. Although some relief to the current 2 m maximum setback may be considered, a complete removal of this requirement is not supported.
5. More points of access and entry to the central courtyard should be provided.
6. Provide an additional main entrance in an additional location (Intersection of Campeau and Great Lakes shown)
7. The eastern yard functions as a rear yard for the site. The setback from this property line should be a minimum of 7.5 metres to provide adequate separation from the abutting second phase of the retirement home to the east. This area should be utilized to provide a north/south pedestrian connection on site.
8. All at grade residential units should have grade related terraces with direct access to the public realm – similar to Place St. Emillion abutting the storm water management pond.
9. Consider two buildings in lieu of one large building to allow for better light penetration into the courtyard and circulation.
10. Non-residential uses should be focused along the Canadian Shield and Great Lakes frontages where on-street parking is provided.

### **Engineering Comments**

#### **General:**

- More comments from Infrastructure Planning Unit will follow, If any.

- It is the sole responsibility of the consultant to investigate the location of existing underground utilities in the proposed servicing area and submit a request for locates. The location of existing utilities and services shall be documented on an **Existing Conditions Plan**.
- All underground and above ground building footprints and permanent walls need to be shown on the plans to confirm that any permanent structure does not encroach within the right-of-way.
- Any easements on the subject site shall be identified and respected by any development proposal and shall adhere to the conditions identified in the easement agreement. A **legal survey plan** shall be provided and all easements shall be shown on the engineering plans.
- Please provide an **Existing Conditions/Removals Plan** as part of the engineering drawing set. Any existing services are to be removed or abandoned in accordance with City standards.
- Please note that the proposed servicing design and site works shall be in accordance with the following documents:
  - Ottawa Sewer Design Guidelines (October 2012)
  - Technical Bulletin PIEDTB-2016-01
  - Technical Bulletins ISTB-2018-01, ISTB-2018-02 and ISTB-2018-03.
  - Ottawa Design Guidelines - Water Distribution (2010)
  - Geotechnical Investigation and Reporting Guidelines for Development Applications in the City of Ottawa (2007)
  - City of Ottawa Slope Stability Guidelines for Development Applications (revised 2012)
  - City of Ottawa Environmental Noise Control Guidelines (January 2016)
  - City of Ottawa Accessibility Design Standards (2012) (City recommends development be in accordance with these standards on private property)
  - Ottawa Standard Tender Documents (latest version)
  - Ontario Provincial Standards for Roads & Public Works (2013)
  - Record drawings and utility plans are also available for purchase from the City (Contact the City's Information Centre by email at [InformationCentre@ottawa.ca](mailto:InformationCentre@ottawa.ca) or by phone at (613) 580-424 x.44455).

#### **Stormwater Management Criteria and Information:**

- It appears the subject site is located within **the KTC SWM Pond (Phase 2)** catchment (see attached). The consultant should review the attached report and confirm SWM criteria, flow allowance to the existing storm system, design assumptions, etc. Consult Operations staff to determine how the existing facility is currently performing (i.e. ability to achieve targets, condition of infrastructure within the SWM block, etc).
- **Water Quality Control:** Please consult with the local conservation authority regarding water quality criteria prior to submission of a Site Plan Control Proposal application to establish any water quality control restrictions, criteria and measures for the site. Correspondence and clearance shall be provided in the Appendix of the report.

- Please note that foundation drain is to be independently connected to sewermain unless being pumped with appropriate back up power, sufficient sized pump and back flow prevention.
- Please note that as per *Technical Bulletin PIEDTB-2016-01 section 8.3.11.1 (p.12 of 14)* **there shall be no surface ponding on private parking areas during the 2-year storm rainfall event.** Depending on the SWM strategy proposed underground or additional underground storage may be required to satisfy this requirement.
- **Underground Storage:** Please note that the Modified Rational Method for storage computation in the Sewer Design Guidelines was originally intended to be used for above ground storage (i.e. parking lot) where the change in head over the orifice varied from 1.5 m to 1.2 m (assuming a 1.2 m deep CB and a max ponding depth of 0.3 m). This change in head was small and hence the release rate fluctuated little, therefore there was no need to use an average release rate.
- When underground storage is used, the release rate fluctuates from a maximum peak flow based on maximum head down to a release rate of zero. This difference is large and has a significant impact on storage requirements. **We therefore require that an average release rate equal to 50% of the peak allowable rate shall be applied to estimate the required volume. Alternatively, the consultant may choose to use a submersible pump in the design to ensure a constant release rate.**
- In the event that there is a disagreement from the designer regarding the required storage, The City will require that the designer demonstrate their rationale utilizing dynamic modelling, that will then be reviewed by City modellers in the Water Resources Group.
- Note that the above will added to upcoming revised Sewer Design Guidelines to account for underground storage, which is now widely used.
- Provide sufficient details and information on any proposed underground storage system. A cross-section of any underground storage system is to be provided with sufficient details and information. In case of a pump failure or blockage an overflow should be provided. Backup power supply is required if using a pump.
- Please note that the minimum orifice dia. for a plug style ICD is 83mm and the minimum flow rate from a vortex ICD is 6 L/s in order to reduce the likelihood of plugging.
- Post-development site grading shall match existing property line grades in order to minimize disruption to the adjacent residential properties. A **topographical plan of survey** shall be provided as part of the submission and a note provided on the plans.
- Please provide a **Pre-Development Drainage Area Plan** to define the pre-development drainage areas/patterns. **Existing drainage patterns shall be maintained and discussed as part of the proposed SWM solution.**
- If rooftop control and storage is proposed as part of the SWM solutions sufficient details (Cl. 8.3.8.4) shall be discussed and document in the report and on the plans. Roof drains are to be connected downstream of any incorporated ICDs within the SWM system and not to the foundation drain system.

### Storm Sewer:

- Storm sewer monitoring maintenance holes are required to be installed at the property line (on the private side of the property) as per City of Ottawa Sewer-Use By-Law 2003-514 (14) *Monitoring Devices*.
- As-built drawings of the existing services within the vicinity of the site shall be obtained and reviewed in order to determine proper servicing and SWM plan for the subject site(s).
- Storm service connections are to have backwater valves.

### Sanitary Sewer:

- **An analysis and demonstration that there is sufficient/adequate residual capacity to accommodate any increase in wastewater flows in the receiving and downstream wastewater system is required to be provided. The City can provide flows for existing areas and direction on how to estimate future flows for vacant areas within the sewer shed.**
- Please apply the wastewater design flow parameters in *Technical Bulletin PIEDTB-2018-01*.
- Sanitary sewer monitoring maintenance holes are required to be installed at the property line (on the private side of the property) as per City of Ottawa Sewer-Use By-Law 2003-514 (14) *Monitoring Devices*.
- Sanitary service connections are to have backwater valves.

### Water:

- **Water Supply Redundancy:** Residential buildings with a basic day demand greater than 50m<sup>3</sup>/day (0.57 L/s) are required to be connected to a minimum of two water services separated by an isolation valve to avoid a vulnerable service area as per the *Ottawa Design Guidelines - Water Distribution, WDG001, July 2010 Clause 4.3.1 Configuration*. The basic day demand for each site anticipated to exceed 50m<sup>3</sup>/day therefore 2 water services will be required. There shall be primary water service and a secondary connection.
- Please review Technical Bulletin ISTB-2018-0, maximum fire flow hydrant capacity is provided in Section 3 Table 1 of Appendix I. A **hydrant coverage figure** shall be provided and **demonstrate there is adequate fire protection**.
- Boundary conditions are required to confirm that the require fire flows can be achieved as well as availability of the domestic water pressure on the City street in front of the development. Use Table 3-3 of the MOE Design Guidelines for Drinking-Water System to determine Maximum Day and Maximum Hour peaking factors for 0 to 500 persons and use Table 4.2 of the Ottawa Design Guidelines, Water Distribution for 501 to 3,000 persons. Please provide the following information to the City of Ottawa via email to request water distribution network boundary conditions for the subject site. Please note that once this information has been provided to the City of Ottawa it takes approximately 5-10 business days to receive boundary conditions.
  - Type of Development and Units
  - Site Address

- A plan showing the proposed water service connection locations.
- **Average Daily Demand** (L/s)
- **Maximum Daily Demand** (L/s)
- **Peak Hour Demand** (L/s)
- **Fire Flow** (L/min)
- [*Fire flow demand requirements shall be based on Fire Underwriters Survey (FUS) Water Supply for Public Fire Protection 1999*]
- *Exposure separation distances shall be defined on a figure to support the FUS calculation and required fore flow (RFF).*
- Hydrant capacity shall be assessed to demonstrate the RFF can be achieved. Please identify which hydrants are being considered to meet the RFF on a fire hydrant coverage plan as part of the boundary conditions request.

#### **Snow Storage:**

- Any portion of the subject property which is intended to be used for permanent or temporary snow storage shall be as shown on the approved site plan and grading plan. Snow storage shall not interfere with approved grading and drainage patterns or servicing. Snow storage areas shall be setback from the property lines, foundations, fencing or landscaping a minimum of 1.5m. Snow storage areas shall not occupy driveways, aisles, required parking spaces or any portion of a road allowance. If snow is to be removed from the site please indicate this on the plan(s).

#### **Permits and Approvals:**

- The consultant shall determine if this project will be subject to an Environmental Compliance Approval (ECA) for Private Sewage Works. It shall be determined if the exemptions set out under Ontario Regulation 525/98: *Approval Exemptions* are satisfied. All regulatory approvals shall be documented and discussed in the report.

#### **Geotechnical Investigation:**

- A Geotechnical Study/Investigation shall be prepared in support of this development proposal.
- Reducing the groundwater level in this area can lead to potential damages to surrounding structures due to excessive differential settlements of the ground. The impact of groundwater lowering on adjacent properties needs to be discussed and investigated to ensure there will be no short term and long term damages associated with lowering the groundwater in this area.
- Geotechnical Study shall be consistent with the **Geotechnical Investigation and Reporting Guidelines for Development Applications.**

<https://documents.ottawa.ca/sites/default/files/documents/cap137602.pdf>

#### **Transportation Comments**

Note that these are for re-zoning only. Additional information will be required at the time of SPA.

- Follow Traffic Impact Assessment Guidelines:
  - o A TIA is required.
  - o Note that because this application is for rezoning only at this time, the Design Review components (Module 4.1-4.4) are excluded.
  - o It is noted that provided parking is identified as T.B.C. within the brochure. If a reduction in parking is sought, then Module 4.2 must also be included within the TIA.
  - o Start this process asap. The application will not be deemed complete until the submission of the draft step 1-4, including the functional draft RMA package (if applicable) and/or monitoring report (if applicable).
  - o Request base mapping asap if RMA is required. Contact Engineering Services (<https://ottawa.ca/en/city-hall/planning-and-development/engineering-services>)
- ROW protection on Campeau Dr between Didsbury and Teron is 40m even.
- The TMP includes the following planned infrastructure within the study area:
  - o LRT along Hwy 417, Grade Separated Crossings (Ultimate Network, Map 3)
  - o BRT along Hwy 417, Grade Separated Crossings (2031 Network Concept, Map 4)
  - o Future BRT along Hwy 417 (2031 Affordable Network, Map 5)
  - o Campeau Dr and Kanata Avenue are identified as Widened Arterials (2031 Network Concept, Map 10)
  - o Kanata Avenue widening is identified as part of Phase 2 works (2031 Affordable Network, Map 11), note that the timing of Kanata Avenue widening is yet to be determined but is anticipated to be somewhere around 2031.
- Ensure the separation between the garage entrance and the moving aisle meets the Private Approach Bylaw.
- Sidewalk is to be continuous across access as per City Specification 7.1.
- Notes of items that will be evaluated at the time of SPA are provide for your information:
  - o Show all details of the roads abutting the site up to and including the opposite curb; include such items as pavement markings, accesses and/or sidewalks.
  - o Turning movement diagrams required for all accesses showing the largest vehicle to access/egress the site.



- Turning movement diagrams required for internal movements (loading areas, garbage).
- Show all curb radii measurements; ensure that all curb radii are reduced as much as possible
- Show lane/aisle widths.

**Forester Comments (Privately Owned Trees)**

1. a Tree Conservation Report (TCR) must be supplied for review along with the suite of other plans/reports required by the City; an approved TCR is a requirement of Site Plan or Plan of Subdivision approval.
2. any removal of privately-owned trees 10cm or larger in diameter requires a tree permit issued under the Urban Tree Conservation Bylaw; the permit is based on the approved TCR
3. any removal of City-owned trees will require the permission of Forestry Services who will also review the submitted TCR
4. the TCR must list all trees on site by species, diameter and health condition
5. the TCR must list all trees on adjacent sites if they have a critical root zone that extends onto the development site
6. If trees are to be removed, the TCR must clearly show where they are, and document the reason they cannot be retained
7. the City encourages the retention of healthy trees; if possible, please seek opportunities for retention of trees that will contribute to the design/function of the site.
8. Please ensure newly planted trees have an adequate soil volume for their size at maturity. Here are the recommended soil volumes:

Tree Type/Size	Single Tree Soil Volume (m3)	Multiple Tree Soil Volume (m3/tree)
Ornamental	15	9
Columnar	15	9
Small	20	12
Medium	25	15
Large	30	18
Conifer	25	15

9. For more information on the process or help with tree retention options, contact Mark Richardson [mark.richardson@ottawa.ca](mailto:mark.richardson@ottawa.ca)

**Forester Comment (City Owned Trees)**

- The site plan must be developed such that there is no excavation or disturbance within the Critical Root Zones of these existing trees.
- Entrances and walkways must be limited in order to reduce the number of trees impacted. Any trees that must be removed from City property will require compensation.
- Metal tree protection fencing must be installed to separate the trees from the construction site prior to any works taking place.

Please refer to the links to "[Guide to preparing studies and plans](#)" and [fees](#) for general information. Additional information is available related to [building permits, development charges, and the Accessibility Design Standards](#). Be aware that other fees and permits may be required, outside of the development review process. You may obtain background drawings by contacting [informationcentre@ottawa.ca](mailto:informationcentre@ottawa.ca).

These pre-con comments are valid for one year. If you submit a development application(s) after this time, you may be required to meet for another pre-consultation meeting and/or the submission requirements may change. You are as well encouraged to contact us for a follow-up meeting if the plan/concept will be further refined.

Please contact me at [stream.shen@ottawa.ca](mailto:stream.shen@ottawa.ca) or at 613-580-2424 extension 24488 if you have any questions.

Sincerely,



Stream Shen MCIP RPP  
Planner II  
Development Review - West

## **APPENDIX B**

### **Water Servicing Information**

# 1050 CANADIAN SHIELD

## Floor areas + room distribution

FLOORS	GROSS AREA m <sup>2</sup>	COMMON SPACES INCLUDING : CIRCULATION, PARKING AND SERVICES m <sup>2</sup>	RENTAL AREA (RESIDENTIAL) m <sup>2</sup>	ROOMS								TOTAL qty	
				1BD - TYPE A (800-850 sqft) qty	1BD+O - TYPE B (851-900 sqft) qty	1BD+O - TYPE C (901-950 sqft) qty	1BD+O - TYPE D (951-1000 sqft) qty	2BD type qty	2BD+O type qty	3BD type qty	3BD+O type qty		
P2 PARKING LEVEL	8 824 m <sup>2</sup>	8 824	0	0	0	0	0	0	0	0	0	0	0
P1 PARKING LEVEL	8 786 m <sup>2</sup>	7 999	513	1	2	1	2	0	0	0	0	0	6
1ST FLOOR LEVEL	6 074 m <sup>2</sup>	1 368	4 706	8	17	1	10	4	8	0	0	1	49
2ND FLOOR LEVEL	6 216 m <sup>2</sup>	788	5 428	8	17	2	7	10	9	0	0	2	55
3RD FLOOR LEVEL	6 248 m <sup>2</sup>	743	5 505	4	17	2	7	14	6	0	0	4	54
4TH FLOOR LEVEL	4 083 m <sup>2</sup>	697	3 386	2	6	2	6	4	5	1	0	5	31
5TH FLOOR LEVEL	3 565 m <sup>2</sup>	415	3 149	2	5	2	6	5	7	2	0	1	30
6TH FLOOR LEVEL	2 762 m <sup>2</sup>	408	2 353	0	1	0	0	8	3	4	0	3	19
<b>TOTAL</b>	<b>46 558 m<sup>2</sup></b>	<b>21 243</b>	<b>25 041</b>	<b>25</b>	<b>65</b>	<b>10</b>	<b>38</b>	<b>138</b>	<b>45</b>	<b>38</b>	<b>7</b>	<b>16</b>	<b>244</b>
<b>TOTAL (sq. ft.)</b>	<b>501 147</b>	<b>228 657</b>	<b>269 539</b>	<b>18%</b>	<b>49%</b>	<b>7%</b>	<b>26%</b>	<b>100%</b>					
				<b>10%</b>	<b>27%</b>	<b>4%</b>	<b>14%</b>		<b>18%</b>	<b>16%</b>	<b>3%</b>	<b>7%</b>	<b>100%</b>
				<b>55%</b>				<b>45%</b>				<b>100%</b>	

COMMERCIAL SPACES ON P1 LEVEL	
LOCAL #3520	76 m <sup>2</sup> (818 ft <sup>2</sup> )
LOCAL #3521	122 m <sup>2</sup> (1313 ft <sup>2</sup> )
LOCAL #356	76 m <sup>2</sup> (818 ft <sup>2</sup> )
<b>TOTAL</b>	<b>274 m<sup>2</sup> (2 949 ft<sup>2</sup>)</b>

GENERAL STATISTICS		
<b>LOT AREA</b>	10 917 m <sup>2</sup>	117 509 sq.ft
<b>BUILDING FOOTPRINT</b>	6 261 m <sup>2</sup>	67 392 sq.ft
	<b>REQUIRED</b>	<b>PROVIDED</b>
<b>LANDSCAPE AREA</b>	30% MIN. / 3275 m <sup>2</sup> 35251 sq.ft	32.4% / 3 541 m <sup>2</sup> 38 115 sq.ft
<b>TOTAL PRIVATE AMENITY SPACE</b>	6 m <sup>2</sup> PER UNIT 1 464 m <sup>2</sup>	2622 m <sup>2</sup>
<b>TOTAL COMMUNAL AMENITY AREA</b>	50% OF PRIVATE AMENITY SPACES 735 m <sup>2</sup>	686 m <sup>2</sup> (INDOOR) 373 m <sup>2</sup> (OUTDOOR) <b>1059 m<sup>2</sup> (TOTAL)</b>
<b>WINDOWS / DOORS - GROUND FLOOR WALL FACING A PUBLIC STREET</b>	50% OF THE WALL LENGHT	<ul style="list-style-type: none"> <li>CAMPEAU DRIVE 52%</li> <li>CANADA SHIELD AVE. 50%</li> <li>GREAT LAKES AVE. 52%</li> </ul>
<b>PARKING REQUIRED</b>		
1.0 Residents (parking space / dwelling unit)		<b>244</b>
0.2 Visitors (parking space / dwelling unit)		<b>49</b>
Commercial parking		<b>10</b>
<b>TOTAL PARKING REQUIRED</b>		<b>303</b>
<b>TOTAL PARKING PROVIDED</b>		<b>351</b>
INCLUDED BARRIER FREE PARKING		
<b>MINIMUM BARRIER FREE PARKING REQUIRED</b>	PROVIDED	
10	10	
Bicycle parking required - Residential → 123 (0,5 bicycle parking / dwelling unit) <b>Provided</b> → 124		

Table 1 Water Demand									
	Unit Type				Commercial	Total	Total Demand (L/s)		
	1 Bed Apartment	2 Bed Apartment	3 Bed Apartment	3 Bed+ Office Apartment			Avg Day	Max. Daily	Peak Hour
Unit Count	25	158	45	16	n/a	244	2.27	5.68	12.50
Area (m <sup>2</sup> )	-	-	-	-	274	274	0.03	0.04	0.07
Population	35	332	140	54	-	561	<b>2.30</b>	<b>5.72</b>	<b>12.57</b>

**Design Parameters:**

- 1 Bed Apartment 1.4 persons/unit
- 2 Bed/ 1 Bed + Office Apartment 2.1 persons/unit
- 3 Bed/ 2 Bed + Office Apartment 3.1 persons/unit
- 3 Bed + Office Apartment 3.4 persons/unit

Section 4.0 Ottawa Sewer Design Guidelines

- Average Domestic Flow 350 L/person/day

Ontario Building Code Table 8.2.1.3

- Office Area Flows 75 l/9.3m<sup>2</sup> /day

Peaking Factors: Table 4.2 Ottawa Design Guidelines - Water Distribution

Max. Daily Demand:

- Residential 2.5 x Avg Day
- Commercial 1.5 x Avg Day

Peak Hourly Demand:

- Residential 2.20 x Max Day
- Commercial 1.80 x Max Day

**BOUNDARY CONDITIONS (Values provided by the City of Ottawa)**

<b>Connection 1 - Ground Elevation = 99.5m</b>		
<b>Demand Scenario</b>	<b>Head (m)</b>	<b>Pressure (psi)</b>
Maximum HGL	161.3	87.7
Peak Hour	156.3	80.5
Max Day plus Fire 1	147.9	68.6
<b>Connection 2 - Ground Elevation = 99.4m</b>		
Maximum HGL	161.3	87.9
Peak Hour	156.3	80.7
Max Day plus Fire 1	147.7	68.5

**PRESSURE TESTS**

To convert Head(m) to PSI: multiply by 1.42

Potential Finished Floor Elevation 99.20 m

**Connection 1**

High Pressure Test = (Max HGL - Avg. Ground Elev.) x 1.42197 PSI/m < 80 PSI  
High Pressure = **88.3** PSI

Low Pressure Test = (Min. HGL - Avg. Ground Elev.) x 1.42197 PSI/m > 40 PSI  
Low Pressure = **81.2** PSI

Max Day + Fire Flow Test = (Max Day + Fire Flow - Avg. Ground Elev.) x 1.42197 PSI/m > 20 PSI  
**69.2** PSI

**Connection 2**

High Pressure Test = (Max HGL - Avg. Ground Elev.) x 1.42197 PSI/m < 80 PSI  
High Pressure = **88.3** PSI

Low Pressure Test = (Min. HGL - Avg. Ground Elev.) x 1.42197 PSI/m > 40 PSI  
Low Pressure = **81.2** PSI

Max Day + Fire Flow Test = (Max Day + Fire Flow - Avg. Ground Elev.) x 1.42197 PSI/m > 20 PSI  
**69.0** PSI

## FUS - Fire Flow Calculations

As per 1999 Fire Underwriter's Survey Guidelines



Engineers, Planners &amp; Landscape Architects

Novatech Project #: 120191  
 Project Name: 1050 Canadian Shield  
 Date: 3/30/2021  
 Input By: Jesse Kaloudas  
 Reviewed By: Matt Hrehoriak

Legend

Input by User

No Information or Input Required

Building Description: 6-Storey Apartment Building  
 Fire Resistive Construction

Step		Choose		Value Used	Total Fire Flow (L/min)	
<b>Base Fire Flow</b>						
1	<b>Construction Material</b>		<b>Multiplier</b>			
	<b>Coefficient related to type of construction</b> <b>C</b>	Wood frame		1.5		0.8
		Ordinary construction		1		
		Non-combustible construction	Yes	0.8		
		Modified Fire resistive construction (2 hrs)		0.6		
Fire resistive construction (> 3 hrs)			0.6			
2	<b>Floor Area</b>				17,000	
	<b>A</b>	Building Footprint (m <sup>2</sup> )	8877.75			
		Number of Floors/Storeys	1			
		Protected Openings (1 hr)	Yes			
		Area of structure considered (m <sup>2</sup> )		8,878		
<b>F</b>	<b>Base fire flow without reductions</b>					
	$F = 220 C (A)^{0.5}$					
<b>Reductions or Surcharges</b>						
3	<b>Occupancy hazard reduction or surcharge</b>		<b>Reduction/Surcharge</b>		14,450	
	<b>(1)</b>	Non-combustible		-25%		-15%
		Limited combustible	Yes	-15%		
		Combustible		0%		
		Free burning		15%		
Rapid burning			25%			
4	<b>Sprinkler Reduction</b>		<b>Reduction</b>		-7,225	
	<b>(2)</b>	Adequately Designed System (NFPA 13)	Yes	-30%		-30%
		Standard Water Supply	Yes	-10%		-10%
		Fully Supervised System	Yes	-10%		-10%
	<b>Cumulative Total</b>		<b>-50%</b>			
5	<b>Exposure Surcharge (cumulative %)</b>		<b>Surcharge</b>		3,613	
	<b>(3)</b>	North Side	> 45.1m			0%
		East Side	10.1 - 20 m			15%
		South Side	30.1- 45 m			5%
		West Side	30.1- 45 m			5%
	<b>Cumulative Total</b>		<b>25%</b>			
<b>Results</b>						
6	<b>(1) + (2) + (3)</b>	<b>Total Required Fire Flow, rounded to nearest 1000L/min</b>		<b>L/min</b>	<b>11,000</b>	
		(2,000 L/min < Fire Flow < 45,000 L/min)		or	<b>L/s</b>	<b>183</b>
				or	<b>USGPM</b>	<b>2,906</b>
7	<b>Storage Volume</b>	Required Duration of Fire Flow (hours)		Hours	2	
		Required Volume of Fire Flow (m <sup>3</sup> )		m <sup>3</sup>	1320	

**From:** Elsayed, Ahmed <[ahmed.elsayed@ottawa.ca](mailto:ahmed.elsayed@ottawa.ca)>  
**Sent:** Wednesday, April 21, 2021 5:34 PM  
**To:** Cara Ruddle <[c.ruddle@novatech-eng.com](mailto:c.ruddle@novatech-eng.com)>  
**Cc:** Shen, Stream <[Stream.Shen@ottawa.ca](mailto:Stream.Shen@ottawa.ca)>  
**Subject:** RE: 1050 Canadian Shield - questions

Hi Cara,

Attached is the BC requested.  
Please note that 2 connections will be needed as units exceeds 50.

Thanks,  
Ahmed

**From:** Cara Ruddle <[c.ruddle@novatech-eng.com](mailto:c.ruddle@novatech-eng.com)>  
**Sent:** Wednesday, April 7, 2021 10:01 AM  
**To:** Elsayed, Ahmed <[ahmed.elsayed@ottawa.ca](mailto:ahmed.elsayed@ottawa.ca)>  
**Cc:** Shen, Stream <[Stream.Shen@ottawa.ca](mailto:Stream.Shen@ottawa.ca)>  
**Subject:** RE: 1050 Canadian Shield - questions

**CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.**

**ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.**

Ahmed:

We are looking for boundary conditions for the existing watermain infrastructure to complete a water servicing analysis for the 1050 Canadian Shield development. The development will consist of an apartment complex with commercial space on the ground level. Attached is a key plan showing the site location, and a geomap image showing the existing water infrastructure. Water Demands for the proposed development are provided below:

AVG DAY = 2.27 L/s  
MAX DAY = 5.65 L/s  
PEAK HOUR = 12.42 L/s  
MAX DAY + FIRE = 188.65 L/s

Due to the demands from the site exceeding 50m<sup>3</sup>/day it is proposed to have 2 service connections to Canadian Shield avenue separated by a valve.

Please do not hesitate to call or email should you have any questions. Thanks.

**Cara Ruddle**, P.Eng., Senior Project Manager | Land Development Engineering

**NOVATECH** Engineers, Planners & Landscape Architects

240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext: 220 | Cell: 613.261.7719 | Fax: 613.254.5867

The information contained in this email message is confidential and is for exclusive use of the addressee.



**From:** Elsayed, Ahmed <[ahmed.elsayed@ottawa.ca](mailto:ahmed.elsayed@ottawa.ca)>  
**Sent:** Tuesday, January 26, 2021 4:35 PM  
**To:** Cara Ruddle <[c.ruddle@novatech-eng.com](mailto:c.ruddle@novatech-eng.com)>  
**Cc:** Shen, Stream <[Stream.Shen@ottawa.ca](mailto:Stream.Shen@ottawa.ca)>  
**Subject:** RE: 1050 Canadian Shield - questions

Hi Cara,

As per the preconsult notes that were provided early (attached);

- **An analysis and demonstration that there is sufficient/adequate residual capacity to accommodate any increase in wastewater flows in the receiving and downstream wastewater system is required to be provided. The City can provide flows for existing areas and direction on how to estimate future flows for vacant areas within the sewer shed.**

As per your below request attached is the latest memo **SANITARY FLOW ANALYSIS MARITIME WAY** .

Please let me know if you need more information.

Thanks,  
Ahmed

**From:** Cara Ruddle <[c.ruddle@novatech-eng.com](mailto:c.ruddle@novatech-eng.com)>  
**Sent:** January 25, 2021 12:59 PM  
**To:** Shen, Stream <[Stream.Shen@ottawa.ca](mailto:Stream.Shen@ottawa.ca)>; Elsayed, Ahmed <[ahmed.elsayed@ottawa.ca](mailto:ahmed.elsayed@ottawa.ca)>  
**Subject:** RE: 1050 Canadian Shield - questions

**CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.**

**ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.**

Ahmed:

Just wanted to follow up on the email below. Are you able to provide the latest JL Richards memo as requested below?

Thanks.

**Cara Ruddle**, P.Eng., Senior Project Manager | Land Development Engineering

**NOVATECH** Engineers, Planners & Landscape Architects

240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext: 220 | Cell: 613.261.7719 | Fax: 613.254.5867

The information contained in this email message is confidential and is for exclusive use of the addressee.

**From:** Shen, Stream <[Stream.Shen@ottawa.ca](mailto:Stream.Shen@ottawa.ca)>  
**Sent:** Wednesday, January 6, 2021 3:52 PM  
**To:** Cara Ruddle <[c.ruddle@novatech-eng.com](mailto:c.ruddle@novatech-eng.com)>; Elsayed, Ahmed <[ahmed.elsayed@ottawa.ca](mailto:ahmed.elsayed@ottawa.ca)>  
**Subject:** RE: 1050 Canadian Shield - questions

Hi Ahmed – Can you please assist Cara with this request.

Thank you,

Stream

**From:** Cara Ruddle <[c.ruddle@novatech-eng.com](mailto:c.ruddle@novatech-eng.com)>  
**Sent:** January 6, 2021 9:56 AM  
**To:** Shen, Stream <[Stream.Shen@ottawa.ca](mailto:Stream.Shen@ottawa.ca)>  
**Subject:** 1050 Canadian Shield - questions

**CAUTION: This email originated from an External Sender. Please do not click links or open attachments unless you recognize the source.**

**ATTENTION : Ce courriel provient d'un expéditeur externe. Ne cliquez sur aucun lien et n'ouvrez pas de pièce jointe, excepté si vous connaissez l'expéditeur.**

Stream:

I am not sure who the reviewing Engineer is for the 1050 Canadian Shield property so I will start with you. We worked on two previous sites at 1088 and 1136 Maritime Way and were required to have a Technical Memorandum updated by JL Richards on the downstream sanitary sewer to confirm capacity. The 1050 Canadian Shield property is in the same drainage area. There have also been some other developments in the area so I was looking to get a copy of the most recent JL Richards Memorandum. The latest memo we have on file is 'Kanata Town Centre Central Business District, Master Design Sheet Update - Sanitary Peak Flows, Block 4, Block 5 and Block west of Block 9 (Zone 122)' by JL Richards dated August 18, 2017. Also, will my client be required to update this JL Richards Memorandum again?

Thanks.

**Cara Ruddle**, P.Eng., Senior Project Manager | Land Development Engineering

**NOVATECH** Engineers, Planners & Landscape Architects

240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 Ext: 220 | Cell: 613.261.7719 | Fax: 613.254.5867

The information contained in this email message is confidential and is for exclusive use of the addressee.

'This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

## Boundary Conditions 1050 Canadian Shield Avenue

### Provided Information

Scenario	Demand	
	L/min	L/s
Average Daily Demand	136	2.27
Maximum Daily Demand	339	5.65
Peak Hour	745	12.42
Fire Flow Demand #1	11,000	183.33

### Location



### Results

#### Connection 1 – Canadian Shield Ave.

Demand Scenario	Head (m)	Pressure <sup>1</sup> (psi)
Maximum HGL	161.3	87.7
Peak Hour	156.3	80.5
Max Day plus Fire 1	147.9	68.6

Ground Elevation = 99.5 m

## Connection 2 – Canadian Shield Ave.

Demand Scenario	Head (m)	Pressure <sup>1</sup> (psi)
Maximum HGL	161.3	87.9
Peak Hour	156.3	80.7
Max Day plus Fire 1	147.7	68.5

Ground Elevation = 99.4 m

### Notes

1. As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:
  - a. If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
  - b. Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.

### **Disclaimer**

*The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.*

## **APPENDIX C**

### **Sanitary Servicing Information**

**1136 MARITIME WAY SANITARY FLOWS**

LOCATION			RESIDENTIAL									COMMERCIAL		INFILTRATION			Total Flow (l/s)	PIPE					
AREA	FROM	TO	Apartment Units				TOTAL					Area	Peak Flow (l/s)	Total Area (ha)	Accum. Area (ha)	Infiltr. Flow (l/s)		Size (mm)	Slope (%)	Length (m)	Capacity (l/s)	Full Flow Vel. (m/s)	Q/Q <sub>full</sub> (%)
			1 Bed Units	2 Bed Units	3 Bed Units	3 Bed + Office	Pop.	Pop.	Accum. Pop.	Peak Factor	Peak Flow (l/s)												
	1055	EX	25	158	45	16	561	561	561	3.2	5.74	290.00	0.03	1.36	1.36	0.45	6.22	200	2.00	14.8	46.3	1.48	13.4%

**Design Parameters:**

- 1 Bed Apartment 1.4 persons/unit
- 2 Bed/ 1 Bed + Office Apartment 2.1 persons/unit
- 3 Bed/ 2 Bed + Office Apartment 3.1 persons/unit
- 3 Bed + Office Apartment 3.4 persons/unit

Ontario Building Code Table 8.2.1.3

- Office Area Flows 75 l/9.3m<sup>2</sup> /day

Section 4.0 Ottawa Sewer Design Guidelines


- Average Domestic Flow 280 L/person/day
- Extraneous Flows 0.33 l/s/ha

Residential Peaking Factor Harmon Equation


Commercial Peaking Factor 1

**APPENDIX D**  
**Stormwater Management Calculations**

CAMPEAU DRIVE



INLET CONTROL DEVICE FOR STORAGE TANK					
DESIGN EVENT	ICD TYPE AND SIZE	DIAMETER OF OUTLET PIPE (mm)	DESIGN FLOW (L/s)	DESIGN HEAD (m)	STORAGE REQUIRED (m³)
1:2 YEAR	189mm	375	68.6	0.91	105
1:5 YEAR			82.6	1.28	147
1:100 YEAR			116.6	2.49	275



**LEGEND**


- PROPERTY LINE
- PROPOSED STORM SEWER AND MANHOLE
- AD → DIRECTION OF FLOW
- AD ○ PROPOSED AREA DECK DRAIN BY OTHERS (REFER TO MECH DRAWINGS FOR MORE INFO)
- RD ○ PROPOSED ROOF DRAIN BY OTHERS (REFER TO MECH DRAWINGS FOR MORE INFO)
- STM/MH ○ EXISTING STORM MANHOLE & SEWER
- CB 1 ○ EXISTING CATCHBASIN
- STORM SEWER DRAINAGE AREA BOUNDARY
- DRAINAGE AREA (ha)
- △-16 DRAINAGE AREA ID
- 0.78 RUNOFF COEFFICIENT

REFER TO 120191-ND FOR ADDITIONAL NOTES

**NOTE:**  
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

**PRELIMINARY  
NOT FOR  
CONSTRUCTION**

No.	REVISION	DATE	BY
2.	ISSUED FOR SITE PLAN APPROVAL	JUL 7/21	CJR
1.	ISSUED FOR COORDINATION	MAR 30/21	CJR



DESIGN	MJH
CHECKED	CJR
DRAWN	MJH
CHECKED	CJR
APPROVED	JLS

**NOVATECH**  
Engineers, Planners & Landscape Architects  
Suite 200, 240 Michael Cowpland Drive  
Ottawa, Ontario, Canada K2M 1P6  
Telephone (613) 254-9643  
Facsimile (613) 254-5867  
Website www.novatech-eng.com

LOCATION		DRAWING NAME	
CITY OF OTTAWA CARRÉ-SAINT-LOUIS		STORMWATER MANAGEMENT PLAN	
PROJECT No.	120191	REV	REV # 2
DRAWING No.		120191-SWM	

M:\2020\120191\120191-ND\SWM.dwg, SWM, Jul 05, 2021, 4:56pm, klabouder



**TABLE 1A: Allowable Runoff Coefficient "C"**

Area	"C"
Total	0.80
1.10	

**TABLE 1B: Allowable Flows**

Outlet Options	Area (ha)	"C"	Tc (min)	Q <sub>5 Year</sub> (L/s)
Candian Shield	1.100	0.80	20	171.9

Time of Concentration      Tc= 20      min  
 Intensity (5 Year Event)      I<sub>5</sub>= 70.25      mm/hr  
 5 year Intensity =  $998.071 / (\text{Time in min} + 6.053)^{0.814}$

**TABLE 2A: Post-Development Runoff Coefficient "C" - A-1**

Area	Surface	Ha	"C"	C <sub>avg</sub>	*C <sub>100</sub>
Total	Hard	0.048	0.90	0.37	0.43
0.196	Soft	0.148	0.20		

Runoff Coefficient Equatic  
 $C = (A_{\text{hard}} \times 0.9 + A_{\text{soft}} \times 0.2) / \text{Total Area}$   
 \* Runoff Coefficient increases by 25% up to a maximum value of

**TABLE 2B: Post-Development A-1 Flows**

Outlet Options	Area (ha)	C <sub>avg</sub>	Tc (min)	Q <sub>2 Year</sub> (L/s)	Q <sub>5 Year</sub> (L/s)	Q <sub>100 Year</sub> (L/s)
Canadian Shield	0.196	0.37	10	15.6	21.1	42.2

Time of Concentration Tc= 10 min  
 Intensity (2 Year Event) I<sub>2</sub>= 76.81 mm/hr  
 Intensity (5 Year Event) I<sub>5</sub>= 104.19 mm/hr  
 Intensity (100 Year Event) I<sub>100</sub>= 178.56 mm/hr

100 year Intensity =  $1735.688 / (\text{Time in min} + 6.014)^{0.820}$   
 5 year Intensity =  $998.071 / (\text{Time in min} + 6.053)^{0.814}$   
 2 year Intensity =  $732.951 / (\text{Time in min} + 6.199)^{0.810}$

**TABLE 3A: Post-Development Runoff Coefficient "C" - A-2**

Area	Surface	Ha	"C"	C <sub>avg</sub>	% IMP
Total	Hard	0.899	0.90	0.90	100%
0.899	Soft	0.000	0.20		

**Note:**

Stormwater from area A-2 is to drain to the stormwater tank, and has been modeled using PCSWMM. Refer to model results for details

**TABLE 4A: Post-Development Runoff Coefficient "C" - A-3**

Area	Surface	Ha	"C"	C <sub>avg</sub>	*C <sub>100</sub>
Total	Hard	0.025	0.90	0.90	1.00
0.025	Soft	0.000	0.20		

Runoff Coefficient Equatic  
 $C = (A_{\text{hard}} \times 0.9 + A_{\text{soft}} \times 0.2) / \text{Total Area}$   
 \* Runoff Coefficient increases by 25% up to a maximum value of

**TABLE 4B: Post-Development A-3 Flows**

Outlet Options	Area (ha)	C <sub>avg</sub>	Tc (min)	Q <sub>2 Year</sub> (L/s)	Q <sub>5 Year</sub> (L/s)	Q <sub>100 Year</sub> (L/s)
Canadian Shield	0.025	0.90	10	4.8	6.5	12.4

Time of Concentration Tc= 10 min  
 Intensity (2 Year Event) I<sub>2</sub>= 76.81 mm/hr  
 Intensity (5 Year Event) I<sub>5</sub>= 104.19 mm/hr  
 Intensity (100 Year Event) I<sub>100</sub>= 178.56 mm/hr

100 year Intensity =  $1735.688 / (\text{Time in min} + 6.014)^{0.820}$   
 5 year Intensity =  $998.071 / (\text{Time in min} + 6.053)^{0.814}$   
 2 year Intensity =  $732.951 / (\text{Time in min} + 6.199)^{0.810}$

**Table 4: Post-Development Stormwater Mangement Summary**

Area ID	Area (ha)	1:5 Year Weighted Cw	1:100 Year Weighted Cw	Outlet Location	Orifice	2 Year Storm Event			5 Year Storm Event			100 Year Storm Event		
						Release (L/s)	Ponding Depth (m)	Req'd Vol (cu.m)	Release (L/s)	Ponding Depth (m)	Req'd Vol (cu.m)	Release (L/s)	Ponding Depth (m)	Req'd Vol (cu.m)
A-1	0.196	0.37	0.43	Canadian Shield	N/A	15.6	N/A	N/A	21.1	N/A	N/A	42.2	N/A	N/A
A-2	0.871	0.90	1.00	Canadian Shield	189mm	68.6	0.91	105.0	82.6	1.28	147.0	116.6	2.49	275.0
A-3	0.025	0.90	1.00	Canadian Shield	N/A	4.8	N/A	N/A	6.5	N/A	N/A	12.4	N/A	N/A
<b>Total</b>						<b>89.0</b>			<b>110.2</b>			<b>171.2</b>		
<b>Allowable</b>						<b>171.9</b>			<b>171.9</b>			<b>171.9</b>		

Notes: Information for drainage area A-2 from PCSWMM model

EPA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.013)

\*\*\*\*\*  
 Element Count  
 \*\*\*\*\*  
 Number of rain gages ..... 1  
 Number of subcatchments ... 1  
 Number of nodes ..... 3  
 Number of links ..... 3  
 Number of pollutants ..... 0  
 Number of land uses ..... 0

\*\*\*\*\*  
 Raingage Summary  
 \*\*\*\*\*

Name	Data Source	Data Type	Recording Interval
RG1	ch3-100	INTENSITY	10 min.

\*\*\*\*\*  
 Subcatchment Summary  
 \*\*\*\*\*

Name	Area	Width	%Imperv	%Slope	Rain Gage
A-2	0.87	435.50	100.00	2.0000	RG1

\*\*\*\*\*  
 Node Summary  
 \*\*\*\*\*

Name	Type	Invert Elev.	Max. Depth	Ponded Area	External Inflow
STM101	JUNCTION	95.95	3.08	0.0	
MH01	OUTFALL	95.40	0.71	0.0	
TANK	STORAGE	96.00	2.90	0.0	

\*\*\*\*\*  
 Link Summary  
 \*\*\*\*\*

Name	From Node	To Node	Type	Length	Slope Roughness
C1	STM101	MH01	CONDUIT	10.4	2.0196
C2	TANK	STM101	CONDUIT	5.0	2.0004

OR1 TANK STM101 ORIFICE

\*\*\*\*\*  
 Cross Section Summary  
 \*\*\*\*\*

Full Conduit Flow	Shape	Full Depth	Full Area	Hyd. Rad.	Max. Width	No. of Barrels
C1 249.18	CIRCULAR	0.38	0.11	0.09	0.38	1
C2 84.11	CIRCULAR	0.25	0.05	0.06	0.25	1

\*\*\*\*\*  
 NOTE: The summary statistics displayed in this report are based on results found at every computational time step, not just on results from each reporting time step.  
 \*\*\*\*\*

\*\*\*\*\*  
 Analysis Options  
 \*\*\*\*\*

Flow Units ..... LPS  
 Process Models:  
 Rainfall/Runoff ..... YES  
 RDII ..... NO  
 Snowmelt ..... NO  
 Groundwater ..... NO  
 Flow Routing ..... YES  
 Ponding Allowed ..... NO  
 Water Quality ..... NO  
 Infiltration Method ..... HORTON  
 Flow Routing Method ..... DYNWAVE  
 Surge Method ..... EXTRAN  
 Starting Date ..... 03/29/2021 00:00:00  
 Ending Date ..... 03/30/2021 00:00:00  
 Antecedent Dry Days ..... 0.0  
 Report Time Step ..... 00:01:00  
 Wet Time Step ..... 00:05:00  
 Dry Time Step ..... 00:05:00  
 Routing Time Step ..... 5.00 sec  
 Variable Time Step ..... YES  
 Maximum Trials ..... 8  
 Number of Threads ..... 1  
 Head Tolerance ..... 0.001524 m

\*\*\*\*\*  
 Runoff Quantity Continuity  
 \*\*\*\*\*  
 Total Precipitation ..... 0.062  
 Volume hectare-m  
 Depth mm  
 71.667

```

Evaporation Loss ..... 0.000 0.000
Infiltration Loss ..... 0.000 0.000
Surface Runoff ..... 0.062 71.714
Final Storage ..... 0.000 0.157
Continuity Error (%) .... -0.286

```

```

*****
Volume Volume
Flow Routing Continuity hectare-m 10^6 ltr
*****
Dry Weather Inflow ..... 0.000 0.000
Wet Weather Inflow ..... 0.062 0.624
Groundwater Inflow ..... 0.000 0.000
RDII Inflow ..... 0.000 0.000
External Inflow ..... 0.000 0.000
External Outflow ..... 0.062 0.624
Flooding Loss ..... 0.000 0.000
Evaporation Loss ..... 0.000 0.000
Exfiltration Loss ..... 0.000 0.000
Initial Stored Volume .... 0.000 0.000
Final Stored Volume ..... 0.000 0.000
Continuity Error (%) .... -0.006

```

```

*****
Time-Step Critical Elements
*****
Link C1 (15.52%)

```

```

*****
Highest Flow Instability Indexes
*****
All links are stable.

```

```

*****
Routing Time Step Summary
*****
Minimum Time Step : 2.30 sec
Average Time Step : 4.68 sec
Maximum Time Step : 5.00 sec
Percent in Steady State : -0.00
Average Iterations per Step : 2.00
Percent Not Converging : 0.00

```

```

*****
Subcatchment Runoff Summary
*****

```

```

-----
Perv Total Total Total Total Total Total Imperv
Runoff Runoff Runoff Peak Runoff Evap Infil Runoff
Precip Runon Coeff

```

```

Subcatchment mm mm mm mm mm
mm mm 10^6 ltr LPS
-----
A-2 71.71 0.62 71.67 0.00 0.00 0.00 71.71
0.00 432.02 1.001

```

```

*****
Node Depth Summary
*****

```

```

-----
Average Maximum Maximum Time of Max Reported
Depth Depth HGL Occurrence Max Depth
Node Type Meters Meters Meters days hr:min Meters
-----
STM101 JUNCTION 0.03 0.18 96.13 0 01:21 0.18
MH01 OUTFALL 0.50 0.52 95.92 0 01:21 0.52
TANK STORAGE 0.20 2.49 98.49 0 01:21 2.49

```

```

*****
Node Inflow Summary
*****

```

```

-----
Total Flow Maximum Maximum Lateral
Inflow Balance Lateral Total Time of Max Inflow
Volume Error Inflow Inflow Occurrence Volume
Node Type LPS LPS days hr:min 10^6 ltr 10^6
ltr Percent
-----
STM101 JUNCTION 0.00 116.59 0 01:21 0
0.624 0.001
MH01 OUTFALL 0.00 116.59 0 01:21 0
0.624 0.000
TANK STORAGE 432.02 432.02 0 01:10 0.624
0.624 0.001

```

```

*****
Node Surge Summary
*****

```

No nodes were surcharged.

```

*****
Node Flooding Summary
*****

```

No nodes were flooded.

\*\*\*\*\*  
Storage Volume Summary  
\*\*\*\*\*

of Max	Maximum	Average	Avg	Evap	Exfil	Maximum	Max	Time
Occurrence	Outflow	Volume	Pcnt	Pcnt	Pcnt	Volume	Pcnt	
Storage Unit	LPS	1000 m3	Full	Loss	Loss	1000 m3	Full	days
hr:min								
TANK		0.023	7	0	0	0.275	88	0
01:21	116.59							

\*\*\*\*\*  
Outfall Loading Summary  
\*\*\*\*\*

Outfall Node	Flow Freq Pcnt	Avg Flow LPS	Max Flow LPS	Total Volume 10^6 ltr
MH01	35.79	34.14	116.59	0.624
System	35.79	34.14	116.59	0.624

\*\*\*\*\*  
Link Flow Summary  
\*\*\*\*\*

Link	Type	Maximum  Flow  LPS	Time of Max Occurrence days hr:min	Maximum  Veloc  m/sec	Max/ Full Flow	Max/ Full Depth
C1	CONDUIT	116.59	0 01:21	2.22	0.47	0.48
C2	CONDUIT	0.00	0 00:00	0.00	0.00	0.00
OR1	ORIFICE	116.59	0 01:21			1.00

\*\*\*\*\*  
Flow Classification Summary  
\*\*\*\*\*

Adjusted /Actual	Fraction of Time in Flow Class						
	Up	Down	Sub	Sup	Up	Down	Norm
Inlet							

Conduit Ctrl	Length	Dry	Dry	Dry	Crit	Crit	Crit	Crit	Ltd
C1	1.00	0.00	0.01	0.00	0.85	0.14	0.00	0.00	0.95
C2	1.00	1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

\*\*\*\*\*  
Conduit Surcharge Summary  
\*\*\*\*\*

No conduits were surcharged.


Analysis begun on: Mon Jul 5 14:14:32 2021  
Analysis ended on: Mon Jul 5 14:14:33 2021  
Total elapsed time: 00:00:01



Ottawa Sewer Design Guidelines

APPENDIX 5-A

OTTAWA INTENSITY DURATION FREQUENCY (IDF) CURVE



## RATIONAL METHOD

The Rational Method was used to determine both the allowable runoff as well as the post-development runoff for the proposed site. The equation is as follows:

$$Q=2.78 CIA$$

Where:

Q is the runoff in L/s

C is the weighted runoff coefficient\*

I is the rainfall intensity in mm/hr\*\*

A is the area in hectares

\*The weighted runoff coefficient is determined for each of the catchment areas as follows:

$$C = \frac{(A_p \times C_p) + (A_{imp} \times C_{imp})}{A_{tot}}$$

Where:

$A_p$  is the pervious area in hectares

$C_p$  is the pervious area runoff coefficient ( $C_{perv}=0.20$ )

$A_{imp}$  is the impervious area in hectares

$C_{imp}$  is the impervious area runoff coefficient ( $C_{imp}=0.90$ )

$A_{tot}$  is the catchment area ( $A_{perv} + A_{imp}$ ) in hectares

\*\* The rainfall intensity is taken from the City of Ottawa IDF Curves using a time of concentration ( $t_c$ ) of 10 minutes resulting in a rainfall intensity of 104.2mm/hr and 178.6mm/hr for the 1:5 year and 1:100 year design events respectively.

Note: The post-development C values are to be increased by 25% for the 1:100 year event (max.  $C_{imp}=1.0$ ).

## **APPENDIX E**

### **Referenced Reports**

# MEMORANDUM



**J.L. Richards  
& Associates Limited**  
864 Lady Ellen Place  
Ottawa, ON Canada  
K1Z 5M2  
Tel: 613 728 3571  
Fax: 613 728 6012

Page 1 of 2

To: Greg MacDonald, P.Eng.  
Novatech Engineering Consultants Ltd.

Date: August 18, 2017

Job No.: 15712-015.1

CC: Lucie Dalrymple, P.Eng.  
J.L. Richards & Associates Ltd.

From: Karla Ferrey, P.Eng.

Re: Kanata Town Centre Central Business District  
Master Design Sheet Update - Sanitary Peak Flows  
Block 4, Block 5 and Block west of Block 9 (Zone 122)

We understand that the City is requesting an update to the Master Sanitary Sewer Design Sheet for the Kanata Town Centre Central Business District (KTC-CBD) from JL Richards such to incorporate the proposed peak flow revision from Block 4, Block 5, and the parcel west of Block 9 (previously Robinson'96 - Zone 122). Refer to attached JLR Sanitary Drainage Plan and Robinson Consultants Figure 7.1 for locations of Block 4, Block 5 and Zone 122.

We understand that the City will ultimately decide (as the owner of the existing sewers within the KTC-CBD and downstream system) whether the proposed peak flow increase is acceptable and that if accepted, it will not require a reduction of the allowable peak flows for the remaining future development in the KTC-CBD.

As requested, we have incorporated the proposed sanitary peak flow increase associated with your following developments:

**a) Proposed Block 4 - Residential development**

The proposed development will result in a theoretical increase in peak flow from 3.88 L/s to 4.71 L/s at MH 513 where the Block 4 development outlets to Maritime Way. This represents a theoretical peak flow increase of 0.83 L/s from the anticipated 2012 land use (i.e., hotel use, based on 270 L/pers/day).

**b) Proposed Block 5 - Residential development**

The proposed development will result in a theoretical increase in peak flow from 3.52 L/s to 5.13 L/s at MH 511 where the Block 5 development outlets to Maritime Way. This represents a theoretical peak flow increase of 1.61 L/s from the anticipated 2012 land use (i.e., hotel use, based on 270 L/pers/day).

**c) Proposed parcel west of Block 9 (previously identified in the 1996 Robinson KTC Sanitary Design as Zone 122) – Retirement Home – Claridge Homes**

The proposed development will result in a theoretical increase in peak flow from 2.84 L/s to 7.19 L/s at MH 7A where Claridge Homes development outlets to Maritime Way. This represents a theoretical peak flow increase of 3.57 L/s from the anticipated 2012 land use (i.e., Commercial use based on 2787m<sup>2</sup> office space and Infiltration based 1.5ha ). Theoretical flows for Zone 122 were taken from Robinson Consultants Sanitary Trunk Information from Table 4.7 and Figure 7.1, see attached copies.

At the most downstream MH at the intersection of Teron Rd and Campeau Dr (MH Ex. 2) shown on the attached Sanitary Sewer Design Sheet for the Kanata Village Green subdivision (prepared in 1998 by JLR), the proposed 3 developments would result in a theoretical increase in peak flow from 475.94 L/s to 480.24 L/s which corresponds to a 4.3 L/s (0.9%) peak flow increase.

Based on the available theoretical residual capacities noted in the attached updated Master Sanitary Sewer Design Sheet, the existing sanitary sewer system from the intersection of Rock Mountain Gate and Maritime Way to the intersection of Campeau Dr and Teron Rd has the capacity to accommodate the additional theoretical peak flows of Block 4, Block 5 and Zone 122. Downstream of the Campeau Drive intersection, JLR does not have on record design sheets for the City's existing downstream sanitary sewer system.

Should you have any questions or require anything further, please do not hesitate to call.

J.L. RICHARDS & ASSOCIATES LIMITED

Prepared by:



Karla Ferrey, P.Eng.







**CITY OF OTTAWA**

KANATA TOWN CENTRE  
CENTRAL BUSINESS DISTRICT  
URBAN DALE CORPORATION  
JLR PROJECT NO.: 15712

Commercial Flow = 50000 L/ha/d  
q residential = 350 l/cap/d  
q hotel = 270 l/cap/d  
q retirement homes = 450 l/cap/d  
i = 0.28 l/s/ha  
SING. HOUSING 3.4 pers/hse  
MULT. HOUSING 2.7 pers/hse  
Hotel/Appartments 1.8 pers/room  
Retirement Homes 1.6 pers/room

MASTER SANITARY SEWER DESIGN SHEET  
Designed: L.D.

2017 Update by: KF  
2017 Check by: LD


Date: August 15, 2017

Manning's Coefficient (n) = 0.013

STREET	M.H. # FROM TO		RESIDENTIAL											COMMERCIAL / INSTITUTIONAL			PLUGGED FLOW		R+C		2017 Updates to Block 4.5, West of 9 Peak Flows SEWER DATA					CAPACITY												
			SING.	Stacks	Towns	Ext. Care		Hotel/Apart.		POPUL. people	AREA ha	CUMMULATIVE POPUL. people	AREA ha	PEAKING FACTOR	POPUL. FLOW l/s	Actual AREA ha	CUMM. AREA ha	COMM. FLOW l/s	FLOW l/s	CUMM. FLOW l/s	PEAK EXTR. FLOW l/s	PEAK DES. FLOW l/s	DIA. mm	SLOPE %	CAPAC. l/s	VEL. m/s	LENGTH m	Residual (L/s)	% Full									
						No units	Act. pop	No units	Act. pop																					Equ. pop.								
COLCHESTER SQUARE	14	11		4						11	0.16	15158	259.68	2.77	170.31			30.02	26.06			201.54	81.48	479.39	900	0.11	600.38	0.94	72.6	120.99	80%							
TERON	11	10										15158	259.68	2.77	170.31			30.02	26.06			201.54	81.48	479.39	900	0.11	600.38	0.94	29.6	120.99	80%							
	10	EX.									0.25	15158	259.93	2.77	170.31			30.02	26.06			201.54	81.55	479.46	900	0.11	600.38	0.94	72.3	120.92	80%							
TERON	O.P.P.	EX.																				0.78	0.78		0.78	100	Forcemain											
TERON	EX.	EX. 2										15158	259.93	2.77	170.31			30.02	26.06			202.32	81.55	480.24	680	0.96	838.61	2.31	9.4	358.37	57%							
			(1)	As per Kanata Town Centre Sanitary Trunk Sewer Study, revised March 27, 1996, by Robinson Consultants Inc.																																		
			(2)	Park or open space area.																																		
			(3)	Equivalent population base on 208 rooms and 20 staff members.																																		
			(4)	Allowance for an ultimate flow of 188 l/s to provide flexibility in future development as per Kanata Town Centre Sanitary Trunk Study.																																		
			(5)	Additional flow associated with hotel amenities including swimming pool with bathrooms and laundry as per design calculations for Block 1 provided by WSP (October 2016)																																		
			(6)	Additional flow associated with overall amenities including beauty salon, staff, dining and laundry as per design calculations for 1250 Maritime Way (Timberwalk Retirement Home) provided by Novatech (July 31, 2017)																																		









DATE	REVISIONS	BY	NO.	DATE	REVISIONS	BY
			5	02/11/06	PER CITY COMMENTS	CSB
12/06/12	REVISED CBD DRAINAGE	JLP	4	13/09/06	ISSUED TO CITY FOR REVIEW	LND
24/07/07	REVISED AS PER CITY COMMENTS	CSB	3	21/07/06	ISSUED TO CITY FOR REVIEW (STREET 'A' NORTH-SOUTH LEG)	LND
25/05/07	PHASE 2 ISSUED FOR CITY REVIEW	CSB	2	05/11/98	REVISED PER RMOC	LND
08/03/07	ISSUED FOR TENDER	CSB	1	08/06/98	ISSUED FOR MOE APPROVAL (SAN)	LND


  

<p>SCALE</p> <p>0 10m 20m 30m 40m</p> <p>HORIZONTAL 1:1000</p>	<p>V:\15712-NAD03.LD\15712 C SAN-NAD03.DWG</p> <p><b>J.L.Richards</b> ENGINEERS ARCHITECTS PLANNERS</p>	<p><b>J.L. Richards &amp; Associates Limited</b> 864 Lady Ellen Place Ottawa, ON Canada K1Z 5M2 Tel: 613 728 3571 Fax: 613 728 6012</p>	<p>THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED OR USED FOR PURPOSES OTHER THAN EXECUTION OF THE DESCRIBED WORK WITHOUT THE EXPRESS WRITTEN CONSENT OF J.L. RICHARDS &amp; ASSOCIATES LIMITED.</p>	<p>DESIGN C.B.</p> <p>CHECKED L.N.D.</p> <p>DRAWN T.S.</p> <p>CHECKED</p> <p>APPROVED</p>	<p><b>Ottawa</b></p> <p><b>URBANDALE CORPORATION</b></p>	<p>KANATA TOWN CENTRE CENTRAL BUSINESS DISTRICT SANITARY DRAINAGE PLAN</p>	<p>PROJECT No. 15712-NAD 83</p> <p>STARTED JUNE 1998</p> <p>DWG. No. 15712-SAN</p>
--	---	---	---	---	--	--	--



NOTE: THIS PLAN WAS PRODUCED ON AN AUTOCAD® DRAFTING SYSTEM

No.	DATE	REVISION	BY	No.	DATE	REVISION	BY
1	05.16.94	REVISED PROFILE	P.A.				
2	06.28.94	GENERAL REVISIONS AND ADDITIONS	P.A.				
3	07.11.94	GENERAL REVISIONS	P.A.				
4	07.28.95	PIPE SIZE PENFIELD DR. AND LOOP	A.J.R.				




**SCALES**  
 1: 4000  
 HORIZONTAL  
 1: 400  
 VERTICAL

**Robinson**  
 Consultants

CONSULTING ENGINEERS  
 136, Michael Coulson Dr.  
 Kanata, Ontario, K2M 2E9  
 Telephone (613) 882-8080

DESIGN P.G.  
 CHECKED A.J.R.  
 DRAWN I.D.M.  
 CHECKED  
 APPROVED A.J.R.



**Figure 7.1**  
**KANATA TOWN CENTRE**  
 Trunk Sanitary Sewer Functional Design

PROJECT No. 93055  
 CONTRACT No. \_\_\_\_\_  
 DATED OCT. 93  
 DWG. No. 93055-C

# Table 4.7 - Revised as per RMOC Letter Dated March 27, 1996

## KANATA TOWN CENTRE SANITARY TRUNK SEWER STUDY

Ultimate Development Flows Worksheet

Revised March, 1996

Project 93055

SR Pump Strn. Qp= 163 l/s

q (res)= 4.1E-03 l/cap x s 0.35 cu. m/capita/day

q (ret)= 5.8E-05 l/s x m2 5000 l/1000m2 x day

q (com)= 5.8E-05 l/s x m2 5000 l/1000m2 x day

q (hot)= 2.6E-03 l/s x bed 225 l/bed x day

Peaking factor for ret & off & hot= 1.5

Flow Scenario - III

2 beds/room

3.8 persons/dwelling (low & med density)

I= 0.28 l/s/ha

2.2 persons/dwelling (high density)

Zone	Area	Residential Units			Retail		Office		Special Gen.		Peaking Factor	Qp (l/s)	Qi (l/s)	Qtot (l/s)	Cummul. Qtot (l/s)	
		Low	Med	High	GLA (m2)	Emp.	Area (m2)	Emp.	Hotel Rooms	Emp.						
112	1.6		100		2230	47	5574	200								
111	2.2															
109	2.2	200	33						200	88						
115	0.8						1394	50								
116	0.20															
114	0.10															
118	1.7			50			9755	350								
120	1.1		87													
100	7.40				16908	386					4.00	1.47	2.07	3.54	166.62	
101	1.30				4041	87					4.00	0.35	0.36	0.71	167.34	
102	0.80				1579	34					4.00	0.14	0.22	0.36	167.70	
104	1.50			168	10080	217					4.00	6.86	0.42	7.28	174.98	
110	8.20		300								3.68	16.98	2.30	19.28	193.78	
103	13.30				74459	1603					3.68	6.46	3.72	10.19	203.97	
105	2.10			90	8826	190					3.64	3.68	0.59	4.27	208.00	
106	1.50				3298	71					3.64	0.29	0.42	0.71	208.70	
117	0.04										3.64	0.00	0.01	0.01	208.72	
119	2.60			100	2230	47	34838	1250			3.60	6.42	0.73	7.15	215.59	
107	9.10								100	88	3.60	0.78	2.55	3.33	218.53	
113	2.10			300	2230	47	16722	600			3.50	10.99	0.59	11.58	229.31	
121	0.10						19509	700			3.50	1.69	0.03	1.72	231.04	
122	1.50						27870	1000			3.50	2.42	0.42	2.84	233.88	
123	1.70		72	50			1394	50			3.45	5.48	0.48	5.95	239.30	
124	0.60										3.45	0.00	0.17	0.17	239.47	
125	1.40										3.45	0.00	0.39	0.39	239.86	
126	2.80										3.45	0.00	0.78	0.78	240.64	
127	1.80		80				4181	150			3.41	4.56	0.50	5.07	245.27	
128	1.20		36				4181	150			3.39	2.24	0.34	2.58	247.65	
129	1.70		70				6968	250			3.37	4.23	0.48	4.71	251.96	
130	1.10						11148	400			3.37	0.97	0.31	1.28	253.24	
131	2.00										3.37	0.00	0.56	0.56	253.80	
132	0.60		40								3.35	2.06	0.17	2.23	255.80	
133	0.60										3.35	0.00	0.17	0.17	255.97	
134	0.70						4181	150			3.35	0.36	0.20	0.56	256.52	
135	0.60		36								3.34	1.85	0.17	2.02	258.33	
136	1.00		18								3.33	0.92	0.28	1.20	259.43	
137	0.80	10	18								3.32	1.43	0.22	1.65	260.92	
138	1.50		93								3.29	4.71	0.42	5.13	265.50	
139	0.80	18	8								3.28	1.31	0.22	1.54	266.88	
156	1.10		37								3.27	1.86	0.31	2.17	268.82	
140	0.90	8	27								3.26	1.75	0.25	2.01	270.62	
141	1.00		59								3.24	2.94	0.28	3.22	273.48	
142	0.50										3.24	0.00	0.14	0.14	273.62	
144	0.60		34								3.23	1.69	0.17	1.86	275.27	
143	1.10	10	30								3.22	1.98	0.31	2.29	277.31	
145	1.30		92								3.19	4.52	0.36	4.88	281.63	
146	1.00	16	19								3.18	1.71	0.28	1.99	283.41	
108	1.20		34								3.17	1.66	0.34	2.00	285.19	
148	1.00	8	18								3.17	1.27	0.28	1.55	286.58	
150	0.70		11								3.16	0.54	0.20	0.73	287.24	
151	0.30										3.16	0.00	0.08	0.08	287.32	
152	2.00										3.16	0.00	0.56	0.56	287.88	
154	1.20		66								3.15	3.20	0.34	3.53	291.00	
155	1.80						3177	114			3.15	0.28	0.50	0.78	291.78	
147	1.30		49								3.13	2.36	0.36	2.73	294.20	
153	0.80			100							3.12	2.78	0.22	3.00	296.84	
149	0.60				1858	39					3.12	0.16	0.17	0.33	297.17	
Totals	90.84	70	1247	808	125509	2768	134169	5414	100	176						
Total Town Centre Population					6782.2											
Average Persons per Dwelling Unit					3.19		Combined Down Stream Flow					425.64				

**CITY OF KANATA**

**SANITARY SEWER DESIGN SHEET**

q (res) = 350 l/cap/day  
 q (com) = 50,000 l/ha/day  
 q (inst) = 50,000 l/ha/day  
 I = 0.280 l/s/ha  
 Singles, Townhouses, Ter. Bungalows = 3.8 pers / unit (low & medium density)  
 Stacked Townhouses / Apartments = 2.2 pers / unit (high density)  
 Stacked Townhouses / Apartments = 80 units / ha (high density)

**KANATA TOWN CENTRE  
(RESIDENTIAL)  
URBAN DALE CORPORATION**

Designed by: L.N.D.

Checked by: M.F.S.

STREET	M.H. #		No. of UNITS		AREA ha	CUMMULATIVE		Peaking Factor	POPUL. FLOW l/s	INFIL. FLOW l/s	PEAK FLOW l/s	SEWER DATA				
	FROM	TO	Singles & Townhouses	Stacked Townhouses		POPUL. peop.	AREA ha					DIA mm	Slope %	CAPAC. l/s	VEL. m/s	LENGTH m
A	90	92	37		0.80	141	0.80	4.00	2.28	0.22	2.50	250	0.60	46.06	0.94	120.0
	92	94	13		1.19	190	1.99	4.00	3.08	0.56	3.64	250	2.20	88.20	1.80	103.0
	94	95			66.80	4831	68.79	3.26	63.77	19.26	270.61	825	0.12	497.22	0.93	17.5
	95	89	10		0.52	4869	69.31	3.26	64.21	19.41	271.20	825	0.12	497.22	0.93	66.6
B	85	87	19		1.19	72	1.19	4.00	1.17	0.33	1.50	250	0.40	37.61	0.77	116.9
	87	89	26		0.82	171	2.01	4.00	2.77	0.56	3.33	250	1.41	70.70	1.44	116.7
A	89	84	12		0.35	5085	71.67	3.24	66.71	20.07	274.35	825	0.12	497.22	0.93	79.0
C	80	82	20		1.08	76	1.08	4.00	1.23	0.30	1.53	250	0.40	37.61	0.77	120.0
	82	84	28		0.83	182	1.91	4.00	2.96	0.53	3.49	250	1.20	65.18	1.33	118.5
A	84	79	14		0.54	5321	74.12	3.22	69.40	20.75	277.74	825	0.12	497.22	0.93	79.0
D	75	76	19		0.37	72	0.37	4.00	1.17	0.10	1.27	250	0.40	37.61	0.77	57.0
	76	77	20		0.29	148	0.66	4.00	2.40	0.18	2.59	250	0.40	37.61	0.77	78.4
	77	79	14		0.63	201	1.29	4.00	3.26	0.36	3.62	250	0.81	53.66	1.09	117.7
PARK EASEMENT	79	67			0.98	5522	76.39	3.20	71.69	21.39	280.66	825	0.12	497.22	0.93	55.0
	67	66	6		0.33	5545	76.72	3.20	71.95	21.48	281.01	825	0.12	497.22	0.93	70.0
BELLROCK DRIVE	70	73	26		2.56	99	2.56	4.00	1.60	0.72	2.32	250	0.40	37.61	0.77	87.2
	73	74	10		0.54	137	3.10	4.00	2.22	0.87	3.08	250	0.40	37.61	0.77	60.3
EASEMENT CAMBRAY LANE	74	62			0.31	137	3.41	4.00	2.22	0.95	3.17	250	0.40	37.61	0.77	39.9
	62	66	25		0.48	232	3.89	4.00	3.76	1.09	4.85	250	0.77	52.18	1.06	100.5
BISHOPS MILLS WAY	66	65	9		0.53	5811	81.14	3.18	74.95	22.72	285.25	825	0.12	497.22	0.93	62.0
SOUTH of HWY 417	EX.	65			191.60	7792	191.60	3.06	96.63	53.65	188.16	900	0.11	600.38	0.94	50.2
BISHOPS MILLS WAY	65	64	2			13610	272.74	2.82	155.52	76.37	457.35	900	0.11	600.38	0.94	17.0
EDENVALE DRIVE KETTLEBY STREET	59	60	8		0.50	30	0.50	4.00	0.49	0.14	0.63	200	1.40	38.80	1.24	77.0
	60	61	24		0.62	122	1.12	4.00	1.97	0.31	2.28	250	0.40	37.61	0.77	103.6
CAMBRAY LANE	58	61	8		0.41	30	0.41	4.00	0.49	0.11	0.61	200	0.70	27.44	0.67	74.5
KETTLEBY STREET	61	64	25		0.42	247	1.95	4.00	4.00	0.55	4.55	250	0.90	56.41	1.15	105.0
	64	63	3			13869	274.69	2.81	158.01	76.91	460.38	900	0.11	600.38	0.94	13.0
BISHOPS MILLS WAY	63	57	10		0.68	13907	275.37	2.81	158.38	77.10	460.94	900	0.11	600.38	0.94	64.9
	57	53	48		0.94	182	0.94	4.00	2.96	0.26	3.22	200	0.70	27.44	0.87	122.3
TER. BUNGALOW Ph.2	53	54	4			198	0.94	4.00	3.20	0.26	3.47	200	0.70	27.44	0.87	13.6
	54	55			0.27	198	1.21	4.00	3.20	0.34	3.54	200	0.70	27.44	0.87	36.7
BISHOPS MILLS WAY	55	56	11		0.81	239	2.02	4.00	3.88	0.57	4.44	250	0.40	37.61	0.77	107.1
	56	57	19		0.65	312	2.67	4.00	5.05	0.75	5.80	250	0.60	46.06	0.94	101.5
PARK	57	34	1		0.37	14222	278.41	2.80	161.40	77.95	464.82	900	0.11	600.38	0.94	53.5
	34	33	3		0.00	14234	278.41	2.80	161.51	77.95	464.93	900	0.11	600.38	0.94	50.3
HAWKSTONE	43	44	16		1.19	61	1.19	4.00	0.99	0.33	1.32	250	1.00	59.46	1.21	51.0
	44	45	8		0.09	91	1.28	4.00	1.48	0.36	1.84	250	0.50	42.05	0.85	29.0
ENDENVALE BIRKENDALE DRIVE	45	35			0.08	91	1.36	4.00	1.48	0.38	1.86	250	0.60	42.05	0.86	39.8
	35	36	7		1.18	118	2.54	4.00	1.91	0.71	2.62	250	0.37	36.18	0.74	93.2
BIRKENDALE DRIVE	36	37	13		0.79	167	3.33	4.00	2.71	0.93	3.64	250	0.37	36.09	0.74	77.1
	37	33	2		0.00	175	3.33	4.00	2.83	0.93	3.76	250	0.40	37.61	0.77	17.9
BIRKENDALE DRIVE	33	32	13		0.56	14458	282.30	2.79	163.66	79.04	468.16	900	0.11	600.38	0.94	72.7
	32	31	18		0.66	68	0.66	4.00	1.11	0.18	1.29	250	0.40	37.61	0.77	75.1
TEESWATER STREET	31	32	19		0.41	141	1.07	4.00	2.28	0.30	2.58	250	0.40	37.61	0.77	77.9
	32	18	4		0.37	14614	283.74	2.79	165.14	79.45	470.05	900	0.11	600.38	0.94	44.4
BIRKENDALE STREET	18	16	6			14636	283.74	2.79	165.36	79.45	470.27	900	0.11	600.38	0.94	44.4
	16	17			0.52	0	0.52	1.50	0.45	0.15	0.60	150	0.90	14.45	0.52	26.5
COMMERCIAL PLAZA COLCHESTER SQUARE	17	16			0.10	0	0.62	4.00	0.45	0.17	0.62	250	0.40	37.61	0.77	33.2
	16	15	10		0.56	14674	284.92	2.79	166.17	79.78	471.41	900	0.11	600.38	0.94	66.0
COLCHESTER SQUARE	15	14 A	2			14682	284.92	2.79	166.25	79.78	471.48	900	0.11	600.38	0.94	25.8
	14 A	14				14895	287.75	2.78	167.82	80.57	473.85	900	0.11	600.38	0.94	14.7
ELSINORE LANE	28	24	22		0.53	84	0.53	4.00	1.35	0.15	1.50	250	1.00	59.46	1.21	56.7
ELSINORE LANE	24	23	12		1.47	137	2.00	4.00	2.22	0.56	2.78	250	0.40	37.61	0.77	43.0
	23	306	8		0.14	182	2.14	4.00	2.96	0.60	3.55	250	0.40	37.61	0.77	34.0
ENDENVALE DRIVE	306	14 A			0.24	213	2.38	4.00	3.45	0.67	4.11	250	0.44	39.41	0.80	48.8
	14 A	14			0.45	213	2.83	4.00	3.45	0.79	4.24	250	0.49	41.68	0.85	46.4
COLCHESTER SQUARE	14 A	14				14895	287.75	2.78	167.82	80.57	473.85	900	0.11	600.38	0.94	14.7
COLCHESTER SQUARE TERON	Church	14			0.52	0	0.52	1.50	0.45	0.15	0.60	150	1.00	15.23	0.86	35.0
	14	11	4		0.16	14910	288.43	2.78	168.87	80.76	475.09	900	0.11	600.38	0.94	72.6
TERON	11	10				14910	288.43	2.78	168.87	80.76	475.09	900	0.11	600.38	0.94	29.6
	10	EX.			0.25	14910	288.68	2.78	168.87	80.83	475.16	900	0.11	600.38	0.94	72.3
TERON	O.P.P.	EX.									0.78	100	Forcemain			
TERON	EX.	EX.									475.94	680	0.96	838.61	2.31	9.4



## Karla Ferrey

---

**From:** Lucie Dalrymple  
**Sent:** August 1, 2017 9:43 AM  
**To:** Karla Ferrey  
**Subject:** FW: Kanata Town Centre - Sanitary Flows  
**Attachments:** 1088 San Drainage.pdf; 1136 San Drainage.pdf

...here it is

**Lucie Dalrymple**, P.Eng.  
Associate  
Senior Civil Engineer

J.L. Richards & Associates Limited  
864 Lady Ellen Place, Ottawa, ON K1Z 5M2  
Tel: 613-728-3571 Fax: 613-728-6012



**J.L. Richards  
& Associates Limited**  
ENGINEERS • ARCHITECTS • PLANNERS



---

**From:** Matthew Hrehoriak [mailto:m.hrehoriak@novatech-eng.com]  
**Sent:** July 31, 2017 10:16 AM  
**To:** Lucie Dalrymple  
**Subject:** RE: Kanata Town Centre - Sanitary Flows

Hi Lucie,

The sanitary info for the block 4 and 5 developments are as follows:

**1088 Maritime Way (Block 4)**

San service connection between SANMH 512-513  
San Drainage Area = 1.121 ha  
No. Units = 144  
Population = 271

**1136 Maritime Way (Block 5)**

San service connection between SANMH 510-511  
San Drainage Area = 0.915 ha  
No. Units = 154  
Population = 301

Regards,



**Matthew Hrehoriak**, B.Eng., EIT

**NOVATECH** Engineers, Planners & Landscape Architects

240 Michael Cowpland Drive, Suite 200, Ottawa, ON, K2M 1P6 | Tel: 613.254.9643 x 273 | Fax: 613.254.5867

The information contained in this email message is confidential and is for exclusive use of the addressee.

M:\2015\115198\cad\design\115198-GP.dwg, SAN, Jul 13, 2017 - 3:58pm, mhrehorlak



**LEGEND**

- 1.121  
1088 - EX  
144 | 271 SANITARY DRAINAGE AREA (ha)
- 1.121  
1088 - EX  
144 | 271 LOCATION
- 144 | 271 UNITS / POPULATION
- SANMH
- SANITARY MANHOLE
- SANITARY SERVICE WITH FLOW DIRECTION



Engineers, Planners & Landscape Architects  
Suite 200, 240 Michael Cowpland Drive  
Ottawa, Ontario, Canada K2M 1P6


Telephone (613) 254-9643  
Facsimile (613) 254-5867  
Website www.novatech-eng.com

**1088 MARITIME WAY**

**SANITARY DRAINAGE AREA PLAN**

SCALE 1 : 500


DATE JULY 2017 JOB 115198 FIGURE A3



0.915  
1136-EX  
154 | 301

**LEGEND**

- 0.915  
1136-EX  
154 | 301 SANITARY DRAINAGE AREA (ha)
- LOCATION
- UNITS / POPULATION
- SANMH
- SANITARY MANHOLE
- SANITARY SERVICE WITH FLOW DIRECTION



Engineers, Planners & Landscape Architects  
Suite 200, 240 Michael Cowpland Drive  
Ottawa, Ontario, Canada K2M 1P6  
Telephone (613) 254-9643  
Facsimile (613) 254-5867  
Website www.novatech-eng.com

**1136 MARITIME WAY**

**SANITARY DRAINAGE AREA PLAN**

SCALE 1 : 500 
0
5
10
15
20

DATE JULY 2017 JOB 115199 FIGURE A3

M:\2015\115199\CAD\Design\115199-GP.dwg, 11x17 portrait, Jul 18, 2017 - 3:12pm, mhrehorjak

# SANITARY SEWER DESIGN SHEET

1250 Maritime Way  
 Timberwalk Retirement Home  
 Developer: Claridge Homes

Date: 31-Jul-17

Designed: CMS  
 Checked: GJM

Location			RESIDENTIAL							INSTITUTIONAL				COMMECIAL			OTHER										INFILTRATION		Total Flow (L/s)	PIPE							
ID	From	To	1 Bedroom		2 Bedroom		Total (Residential)			Assisted Care				Convenience Store			Staff			Beauty Salon			Laundry			Dining				Total Area (ha)	Infil. Flow (L/s)	Size (mm)	Slope (%)	Length (m)	Capacity (l/s)	Full Flow Vel. (m/s)	Q/Q <sub>full</sub> (%)
			Units	Pop.	Units	Pop.	Pop.	Peak Factor	Flow (L/s)	Units / Bed	Pop.	Peak Factor	Flow (L/s)	Area (m2)	Peak Factor	Flow (L/s)	Pop.	Peak Factor	Flow (L/s)	Stations	Peak Factor	Flow (L/s)	Machines	Peak Factor	Flow (L/s)	Seats	Peak Factor	Flow (L/s)									
Part A (current application)	BLD-1	MH101	92	129.0	8	17.0	146.0	4.0	2.37	54	60.0	1.5	0.47	50	1.5	0.004	20	1.5	0.10	2	1.5	0.02	6	1.5	0.13	55	1.5	0.11	0.48	0.13	3.33	200	2.00	2.5	48.4	1.49	6.9%
Part A (current application)	MH101	TEE-1	0	0.0	0	0.0	146.0	4.0	2.37	0	0.0	1.5	0.47	0	1.5	0.004	0	1.5	0.10	0	1.5	0.02	0	1.5	0.13	0	1.5	0.11	0.00	0.13	3.33	200	2.00	13.4	48.4	1.49	6.9%
Part B (future application)	BLD-2	MH103	0	0.0	110	231.0	231.0	4.0	3.74	0	0.0	1.5	0.00	0	1.5	0.000	0	1.5	0.00	0	1.5	0.00	0	1.5	0.00	0	1.5	0.00	0.41	0.11	3.86	200	2.00	2.5	48.4	1.49	8.0%
Part B (future application)	MH103	TEE-2	0	0.0	0	0.0	231.0	4.0	3.74	0	0.0	1.5	0.00	0	1.5	0.000	0	1.5	0.00	0	1.5	0.00	0	1.5	0.00	0	1.5	0.00	0.00	0.11	3.86	200	2.00	13.4	48.4	1.49	8.0%
<b>TOTAL (Parts A + B)</b>	-	-	<b>92</b>	<b>129.0</b>	<b>118</b>	<b>248.0</b>	<b>377.0</b>	<b>4.0</b>	<b>6.11</b>	<b>54</b>	<b>60.0</b>	<b>1.5</b>	<b>0.47</b>	<b>50</b>	<b>1.5</b>	<b>0.004</b>	<b>20</b>	<b>1.5</b>	<b>0.10</b>	<b>2</b>	<b>1.5</b>	<b>0.02</b>	<b>6</b>	<b>1.5</b>	<b>0.13</b>	<b>55</b>	<b>1.5</b>	<b>0.11</b>	<b>0.89</b>	<b>0.25</b>	<b>7.18</b>	<b>200</b>	<b>2.00</b>	<b>2.5</b>	<b>48.4</b>	<b>1.49</b>	<b>14.8%</b>

<b>Design Parameters:</b>	Residential 350 L/cap/day	<b>Peaking Factor:</b>	Residential Harmon Equation (max 4, min 2)	<b>People/Unit:</b>	1.10 Assisted Care
	Institutional 450 L/bed/day		Institutional 1.5		1.40 1 Bedroom
	Commercial 5 L/m <sup>2</sup> per day		Commercial 1.5		2.10 2 Bedroom
	Staff 275 L/cap/day		Other 1.5		1.00 Studio
	Beauty Salon 650 L/day per station				
	Laundry 1200 L/day per machine				
	Dining 115 L/seat/day				
	Infiltration 0.28 L/s/ha				

**Notes:**  
 1. The harmon peaking factor calculated for section 507 to 7A is 3.5 per JLR Design Sheet dated October 12th, 2016  
 2. Residential flows were used for senior apartments (350 L/cap/day, Harmon Peaking Factor)  
 3. Institutional flow used for assisted care units (450 L/bed/day, Peaking Factor = 1.5)  
 4. Future building assumed to be a 10 storey building comprised of 110 2 bedroom units



# TECHNICAL MEMORANDUM



**J.L. Richards  
& Associates Limited**  
864 Lady Ellen Place  
Ottawa, ON Canada  
K1Z 5M2  
Tel: 613 728 3571  
Fax: 613 728 6012

PAGE 1 OF 4

TO: Urbandale Corporation  
c/o Mary Jarvis, MCIP, RPP  
Director of Planning

DATE: June 13, 2012

JOB NO.: 15712-10

FROM: Jonathan Párraga, P.Eng.  
RE: Servicing Brief (Revised)  
Kanata Town Centre  
Central Business District Subdivision

CC: J.L. Richards & Associates Limited  
Attention: Lucie Dalrymple, P.Eng.

## **PURPOSE OF UNDERTAKING**

This Servicing Brief was prepared, in support of Urbandale Corporation's re-zoning application for the Kanata Town Centre - Central Business District (KTC-CBD) Subdivision. The following confirms that water, sanitary and storm sewer services are readily available to accommodate this subdivision.

## **DESCRIPTION OF PROPERTY**

The subject lands encompass an area of approximately 18.8 hectares within the KTC-CBD, in the City of Ottawa (former City of Kanata). The lands are bounded to the north by Campeau Drive, to the west by a partial of land fronting Castlefrank Drive, south by Hwy. 417 and to the east by the Hydro One corridor (refer to Figure 1 attached). This subdivision is comprised of residential and commercial developments. Civil infrastructure (i.e., local watermains, storm and sanitary sewers) within the ROWs are all existing and in service. The trunk storm sewer, sanitary sewer, and watermain along the south leg of Maritime Way were constructed by Urbandale Corporation in 1998 and the remaining local infrastructure in 2007-2008. The 900 mm dia. feedermain on Great Lakes Avenue was constructed for the City of Ottawa in 2008-2009.


## **STORM SEWER SERVICING**

### **Outlet:**

The KTC-CBD lands are tributary to the KTC-CBD Stormwater Management Facility (SWMF) located in the southeast corner of the subdivision (refer to Figure 1 for Pond location), which subsequently drains to Watts Creek. This SWMF was designed, and subsequently constructed, to accommodate the development of the KTC-CBD subdivision and provides quantity as well as quality control for the stormwater flows. Details of the SWMF can be found in the Stormwater Management Report, Kanata Town Centre, Central Business District, dated January 1999 and prepared by J.L. Richards & Associates Limited.

### **Minor/Major System:**

The KTC-CBD storm drainage system has been designed using the dual drainage concept, consisting of a minor and a major system. The minor system conveys storm runoff generated during frequent storm events (i.e., 1:5 year or less) via a local storm sewer collection system outletting to the KTC-CBD



**KANATA TOWN CENTRE  
CENTRAL BUSINESS DISTRICT  
(KTC-CBD)**



PROJECT: KTC-CBD  
URBANDALE CORPORATION  
CITY OF OTTAWA

DRAWING: KEY PLAN



J.L. Richards  
& Associates Limited  
864 Lady Ellen Place  
Ottawa, ON Canada  
K1Z 5M2  
Tel: 613 728 3571  
Fax: 613 728 6012

DESIGN:	DRAWN: T.S.
DATE: OCT. 2006	
SCALE: N.T.S.	

DRAWING No.: <b>FIG. 1</b>
JOB No.: 15712

SWMF where, as noted, water quality and quantity treatment is provided. In accordance with the noted SWMF Design Report, the following runoff coefficients were used at detailed design of the local storm sewers

Residential - Low Density	C=0.40
Residential - Medium Density	C=0.45
Residential - High Density	C=0.50 and 0.60
<b>Commercial Area</b>	<b>C=0.80 and 0.90</b>
Parkland	C=0.20

An excerpt from the noted 1999 Stormwater Management Report, indicating assigned runoff coefficients 'C', allowable capture rates, and required on-site storage volumes for the specific land parcels is included in Attachment 1. The servicing design for each Block in the KTC-CBD shall adhere to these SWM design requirements.

The major system was established at the detailed design stage to convey excess runoff generated during severe events which would not be captured in the minor system. The excess runoff will be conveyed via overland routes to the KTC-CBD SWMF. The grading plans of the KTC-CBD lands have been developed with roadway sags. Local Blocks of land are expected to incorporate parking lot, cistern and roof top storage (or a combination thereof) at Site Plan Control, to ensure that the minor / major drainage concept, as specified in the Attachment 1 Table, is properly implemented.

A Hydraulic Grade Line (HGL) Analysis was carried out during detailed design to verify the anticipated amount of freeboard provided between the maximum storm sewer HGL elevations and the building underside of footing elevations. At detailed design of each Block, and as required at Site Plan Control, the on-site HGL clearance will require confirmation. The analysis was based on the estimated maximum water elevations of the KTC-CBD SWMF.

## **WATER SERVICING**

The local network of water servicing for the KTC-CBD Subdivision was originally developed based on the existing 610 mm and 406 mm diameter watermains on Maritime Way. Water servicing specifics for the subdivision were addressed in detail in the Hydraulic Network Analysis (HNA) Report, which was prepared and submitted to the City in conjunction with the detailed servicing design of this project. The HNA Report for KTC-CBD demonstrated that the proposed (now existing) watermain sizing satisfied the water demand during the maximum hourly and fire flow conditions, as per the City of Ottawa Design Guidelines. Furthermore, the analysis included an assessment of pressures during low demand conditions (i.e., high pressure check) ensuring that the system pressures do not exceed the maximum pressure requirements set by the Ontario Building Code (OBC).

Since then a 900 mm diameter feedermain was constructed in 2008-2009 on Great Lakes Avenue, linking the existing 610 mm diameter feedermain on Maritime Way to the existing 900 mm diameter feedermain on Campeau Drive. At detailed design of each Block, and as required at Site Plan Control, the designer will have to obtain boundary conditions from the City of Ottawa and carry out an HNA for their respective Block.

**SANITARY SEWER SERVICING**

There is an existing 825 mm diameter trunk sanitary sewer along the south leg of Maritime Way and extends easterly along a service easement to Gray Crescent in Village Green. This sanitary trunk sewer was designed by JLR (1998) to accommodate the development of the KTC-CBD subdivision and upstream lands. Local sanitary sewers were subsequently designed by JLR (2007) and constructed. At the time of the original design of the trunk sewer the land parcels were designated for commercial use and the sanitary flows were estimated using 50,000 L/ha/d (MOE guidelines for sanitary flow for commercial zones). Subsequently, the land use was revised to include residential use, as well as commercial use. As such, in 2007, JLR revised the original sanitary flow estimate according to the projected land use to design the local sewers. Currently, Blocks 3, 6 and 8 have been sold and either developed or partially developed. As such, the estimated sanitary flows generated by the local Blocks have currently been updated to reflect exiting conditions and projected development of local Blocks. Table 1 provides a summary of the existing and anticipated land uses.

**Table 1 - Kanata Town Centre Existing and Anticipated Land Uses**

Block No.	Land Use Description	Number of Units/Rooms	Population	Daily Sewage Flow	Area
1	Hotel Suites	167	301	270 L/pp/d*	1.48
2	Commercial			50,000 L/pp/d	1.36
3	Retirement Home	208	333		1.02
4	Apartments	120	216	350 L/pp/d	1.37
5	Apartments	120	216	350 L/pp/d	1.02
6	Apartments with Community Centre			350 L/pp/d**	2.83
7	Commercial	N/A		50,000 L/pp/d	1.70
8	Hotel	125	225	270 L/pp/d*	1.02
9	Commercial	N/A	N/A	50,000 L/pp/d	4.96
10	Walkway Easement	N/A	N/A	N/A	0.28

Note: \* Additional flow of dining room and staff accounted for in design

\*\* Additional flow from Community Centre pool 40 L/pp/d accounted for in design

The current peak flow estimate has been revised in accordance with the land uses presented in Table 1. A comparison of the original peak flow estimate (1998) and the current peak flow estimate is presented in Table 2. The revised peak flow estimate, based on the current land use projections and existing land uses, creates an increase of estimated flow of 4.05 L/s (274.66 L/s – 270.61 L/s) at the Trunk easement. This flow, however, with a reduction in the downstream peaking factor due to the increase in residential units in the CBD, normalizes close to the original (1998) estimated flow and actually estimates a small reduction of 0.15 L/s (475.94 L/s - 475.79L/s) at the end of the residential subdivision at the intersection of Campeau Drive and Teron Road. The original peak flow design estimate (1998) and the updated detailed design spreadsheet, as well as the sanitary drainage boundary plan, can be found in Attachment 2.

**Table 2 - Kanata Town Centre Estimated Sanitary Peak Flow**

Location	Tributary Area	Up MH	Down MH	Original Assigned Flow Estimate (1998)	Current Flow Estimate (2012)
Trunk Easement	Upstream + KTC-CBD	500	94	270.61	274.66
Total Flow at end of Residential	Upstream + KTC-CBD + Residential to Teron Road	Ex.	Ex. 2	475.94	475.79

**SUMMARY**

The existing trunk (1998) and local (2007-2008) infrastructure servicing the subject lands, which are referred to as KTC-CBD, have capacity to service the local Blocks, with regards to stormwater and wastewater; based on the SWM design parameters provided in Attachment 1 and wastewater based on the revised existing and proposed land uses as per Table 1 of this report.. Domestic water is available along the frontage of each Block with the understanding that a site specific HNA is to be carried out at Site Plan Control to demonstrate conformance with the City Guidelines

Revised by:

J.L. RICHARDS & ASSOCIATES LIMITED

Jonathan Párraga, P.Eng.


JP:jd  
Attach.



## **ATTACHMENT 1**

### Kanata Town Centre - Central Business District Stormwater Design Criteria - Tributary Areas to SWMF


DRAINAGE AREA No.	Description	Area (ha)	TIMP (%)	C factor	Allowable Capture Rate	On-Site Storage	Required on-site Storage Volume
1	AMC Site	7.85	85	0.80	1:5 year	Yes	up to 100 yr
2	Park & Ride	1.46	95	0.87	1:5 year	No	
3	Phase IV	3.03	95	0.87	1:5 year	Yes	up to 100 yr
4	Transitway	3.55	95	0.87	1:5 year	No	
5	Hotel Road	0.38	80	0.76	1:5 year	No	
6	Hotel Site	0.80	95	0.87	1:5 year	Yes	up to 100 yr
7	Castlefrank Road	2.84	80	0.76	1:10 year	No	
8	Adjacent Lands	2.77	57	0.60	1:10 year	No	
9	Exist Pond **	0.82	---	0.20	1:10 year	Yes	up to 100 yr
10	Kanata North	4.66	85	0.80	1:5 year	No	
11	Adj Lands (east)	2.16	85	0.80	1:5 year	No	
12	Adj Lands (south-east)	2.11	85	0.80	1:5 year	Yes	up to 100 yr
13	Street "A"	1.32	85	0.80	1:5 year	Limited	up to 10 yr
14	Urbandale North	10.41	85	0.80	1:5 year	Limited	up to 10 yr
15	Urbandale South	4.48	85	0.80	1:5 year	Yes	up to 100 yr
16	Urbandale East	1.82	57	0.60	1:5 year	Limited	up to 10 yr
17	Urbandale East (park)	0.54	---	0.20	1:5 year	No	
18	Queensway	7.87	30	0.41	1:100 year	No	
19	SWMF	0.95	52	0.56	1:100 year	No	



**LEGEND:**

SUB-BASIN I.D. NO.	1
AREA IN HECTARES	3.75
CURVE NUMBER (CN)	12
SUB-BASIN I.D. NO.	2
AREA IN HECTARES	6.1
TOTAL IMPERVIOUSNESS	0.8

NO.	DATE	REVISIONS	BY	NO.	DATE	REVISIONS	BY



**J.L. Richards & Associates Limited**  
 Consulting Engineers, Architect & Planners  
 OTTAWA, KINGSTON, SUDBURY, CANADA

DESIGN C.F.  
 CHECKED C.F.  
 DRAWN T.K.O.B.  
 CHECKED  
 APPROVED

**CITY OF KANATA**  
 DEPARTMENT OF ENGINEERING  
 AND PUBLIC WORKS



**KANATA TOWN CENTRE**  
 FUTURE CONDITIONS


DATED JANUARY 1999  
 DWC No  
 FIGURE 3



**LEGEND**

- CATCH BASIN
- INTERCONNECTED ROADWAY CB C/W ONE 19.8L/S IPEX TYPE 'A' ICD OR CITY APPROVED EQUIVALENT
- CATCH BASIN WITH INDIVIDUAL 19.8 L/S IPEX TYPE 'A' ICD OR CITY APPROVED EQUIVALENT
- HYDRANT
- STORM SEWER & MANHOLE
- LOT NUMBER
- DRAINAGE BOUNDARY
- AREA IN HECTARES
- RUNOFF COEFFICIENT
- PIPE REACH UPSTREAM MANHOLE TO DOWNSTREAM MANHOLE

**NOTE:**  
MINOR SYSTEM CAPTURED RATE (Q<sub>c</sub>) FOR ALL PRIVATE & PUBLIC DEVELOPMENT, NOT TO EXCEED 1:5 YEAR PEAK FLOW AT THE GIVEN RUNOFF COEFFICIENT (REFER TO DWG 15712-STM) USING AN INLET TIME OF T<sub>c</sub>=20min, IN ACCORDANCE WITH THE KTC-CBD STORMWATER MANAGEMENT REPORT PREPARED BY J.L.RICHARDS, JUNE 1999.



DATE	REVISIONS	BY	NO.	DATE	REVISIONS	BY
			5	02/11/06	PER CITY COMMENTS	CB
			4	13/09/06	ISSUED TO CITY FOR REVIEW	LND
8	24/07/07	REVISED AS PER CITY COMMENTS	CSB	3	21/07/06	ISSUED TO CITY FOR REVIEW (STREET 'A' NORTH-SOUTH LEG)
7	25/05/07	PHASE 2 ISSUED TO CITY FOR REVIEW	CB	2	05/11/98	REVISED PER RMOG
6	08/03/07	ISSUED FOR TENDER	CB	1	09/10/98	ISSUED FOR MOE APPROVAL (ST&M)

**J.S.C. BOULIE**  
 100019000  
 July 7, 2007  
 PROFESSIONAL ENGINEER  
 PROVINCE OF ONTARIO

**J.L. Richards**  
 ENGINEERS ARCHITECTS PLANNERS  
 864 Lady Eileen Place  
 Ottawa, ON Canada  
 K1Z 5M2  
 Tel: 613 728 3571  
 Fax: 613 728 6012

THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED OR USED FOR PURPOSES OTHER THAN EXECUTION OF THE DESCRIBED WORK WITHOUT THE EXPRESS WRITTEN CONSENT OF J.L. RICHARDS & ASSOCIATES LIMITED.

**URBANDALE CORPORATION**  
 KANATA TOWN CENTRE  
 CENTRAL BUSINESS DISTRICT  
 STORM DRAINAGE PLAN

PROJECT No. 15712-NAD 83  
 STARTED JUNE 1998  
 DWG. No. 15712-STM



CITY OF OTTAWA

KANATA TOWN CENTRE  
CENTRAL BUSINESS DISTRICT  
URBAN DALE CORPORATION  
JLR PROJECT NO.: 15712

STORM SEWER DESIGN SHEET  
IDF CURVE 1: 5

Designed by: C.B.  
Checked by: D.L.


Date: May 25, 2007

5 YEAR IDF CURVE  
Manning's Coefficient (n) = 0.013

LEGEND  
DENOTES EXISTING SEWERS

MANHOLE NUMBER		DRAINAGE AREAS								1:5 YR PEAK FLOW GENERATION					ACTUAL SEWER DATA						UPSTREAM						DOWNSTREAM												
From	To	0.20	0.30	0.40	0.50	0.60	0.80	0.80	0.90	area (ha)	cumm area (ha)	2.78AR	2.78AR CUMM	Time min	Intens. mm/hr	Peak Flow L/s	Dia (mm)	Dia (mm)	Slope %	Q full (l/s)	V full (m/s)	Length (m)	Flow Time (min)	Ex. Ground	Pr. Center Line	Obvert Drop	Obvert	Invert	Cover	Ex. Ground	Pr. Center Line	Obvert Drop	Forced Drop	Obvert	Invert	Cover	Dstream Bend		
13	607	0.75				4.01	15.53	9.57		29.86	29.86	65.59	65.59	28.52	55.80	3659.80	1676.4	1650	0.19	4155.57	1.88	83.20	0.74		96.32			92.656	91.006	3.66		95.47			-0.15	92.497	90.847	2.97	
607	606						5.60	0.23		5.83	35.69	12.97	78.55	29.26	54.85	4308.72	1828.8	1800	0.21	5495.32	2.09	119.10	0.95		95.47			92.647	90.847	2.82		94.80			0.33	92.397	90.597	2.40	15.00
635	634													20.00	70.25		304.8	300	2.90	171.80	2.35	51.50	0.36		103.38			97.681	97.381	5.70		102.56				96.187	95.887	6.37	13.00
634	633						0.17	0.29		0.46	0.46	1.02	1.02	20.36	69.46	71.06	304.8	300	1.60	127.61	1.75	64.00	0.61		102.56			96.187	95.887	6.37		101.67				95.163	94.863	6.51	90.00
633A	633							0.08		0.08	0.08	0.18	0.18	20.00	70.25	12.50	304.8	300	0.87	94.10	1.29	35.10	0.45		101.49			95.122	94.822	6.37				0.30	94.816	94.516	-94.82		
633	632									0.46		1.20	20.97	68.18	81.88		381	375	1.00	182.91	1.60	64.70	0.67		101.67			95.163	94.788	6.51		101.29				94.516	94.141	6.77	13.00
632	631						1.16	0.31		1.47	1.93	3.27	4.47	21.65	66.83	298.76	533.4	525	1.00	448.66	2.01	74.80	0.62		101.29			94.516	93.991	6.77		97.55				93.768	93.243	3.78	80.00
636	631							0.25		0.25	0.25	0.56	0.56	20.00	70.25	39.06	304.8	300	2.23	150.65	2.06	93.30	0.75		102.26			95.849	95.549	6.41		97.55				93.768	93.468	3.78	
631	630													22.27	65.64	329.91	533.4	525	3.85	880.33	3.94	81.10	0.34		100.65			96.921	96.396	3.73		97.55			0.03	93.798	93.273	3.75	
630	606A	0.36						0.41		0.77	0.77	1.11	6.14	22.61	65.00	398.97	533.4	525	1.35	521.29	2.33	88.90	0.64		97.55			93.768	93.243	3.78		94.64			0.03	92.568	92.043	2.07	18.00
606A	606									0.77			6.14	23.25	63.85	391.91	533.4	525	1.35	521.29	2.33	4.90	0.04		94.64			92.538	92.013	2.10		94.80			0.41	92.472	91.947	2.33	81.00
606	605							0.35		0.35	36.81	0.78	85.47	30.21	53.68	4587.99	(1) 1828.8	(1) 1800	0.25	6049.60	2.30	110.40	0.80		94.80			92.065	90.590	2.74		94.69			0.02	91.784	90.309	2.91	
605	604						2.94	0.25		3.19	40.00	7.09	92.57	31.00	52.73	4881.44	(1) 1828.8	(1) 1800	0.24	5911.34	2.25	67.40	0.50		94.69			91.765	90.290	2.93		94.50	0.06	-0.02	91.601	90.126	2.90	90.00	
642	641							0.13		0.13	0.13	0.29	0.29	20.00	70.25	20.31	381	375	1.85	248.79	2.18	71.30	0.54		100.26			97.259	96.884	3.00		98.94				95.940	95.565	3.00	
641	640						1.10	0.14		1.24	1.37	2.76	3.05	20.54	69.08	210.47	457.2	450	0.80	266.03	1.62	77.70	0.80		98.94			95.940	95.490	3.00		98.33				95.318	94.868	3.01	
640	612							1.02	0.14	1.16	2.53	2.58	5.63	21.34	67.43	379.43	609.6	600	0.66	520.98	1.79	82.30	0.77		98.33			95.318	94.718	3.01		97.86			-0.04	94.774	94.174	3.09	80.00
614	613							0.12		0.12	0.12	0.27	0.27	20.00	70.25	18.75	304.8	300	2.16	148.20	2.03	51.20	0.42		100.07			96.938	96.638	3.13		98.96				95.833	95.533	3.13	
613	612						1.12	0.14		1.26	1.38	2.18	2.45	20.42	69.34	169.64	381	375	1.98	257.25	2.26	51.60	0.38		98.96			95.833	95.458	3.13		97.86				94.813	94.438	3.05	
612	611	0.27						0.16		0.43	4.34	0.51	8.58	22.11	65.93	565.64	685.8	675	3.12	1548.97	4.19	49.60	0.20		97.86			94.813	94.138	3.05		96.45			0.03	93.265	92.590	3.18	
611	601						0.90	0.72		1.78	6.12	3.46	12.04	22.31	65.56	789.16	685.8	675	1.60	1109.24	3.00	44.10	0.24		96.45			93.235	92.560	3.21		94.93	0.06			92.530	91.855	2.40	80.00
601	604							0.07		0.07	6.19	0.16	12.19	22.55	65.10	793.79	685.8	675	1.42	1044.99	2.83	67.50	0.40		94.93			92.470	91.795	2.46		94.50			-0.05	91.511	90.836	2.99	90.00
604	Chamber									46.19		104.76	31.50	52.16	5464.60		(1) 1828.8	(1) 1800	0.21	5495.32	2.09	14.40	0.11		94.50			91.556	90.081	2.94		94.00			-0.01	91.526	90.051	2.47	
Chamber	Pond									46.19		104.76	31.62	52.03	5451.05		1524	2x1500	0.33	8472.67	2.32	11.50	0.08		94.50			91.539	90.039	2.96		94.00				91.501	90.001	2.50	

(1) The equivalent size of a round pipe is shown to simplify spreadsheet calculations. The actual existing pipe is a horizontal elliptical 1475 x 2310 HE III.





CITY OF OTTAWA

KANATA TOWN CENTRE  
CENTRAL BUSINESS DISTRICT  
URBAN DALE CORPORATION  
JLR PROJECT NO.: 15712

STORM SEWER DESIGN SHEET  
IDF CURVE 1: 5

Designed by: C.B.  
Checked by: D.L.

Date: May 25, 2007

5 YEAR IDF CURVE  
Manning's Coefficient (n) = 0.013

LEGEND  
DENOTES EXISTING SEWERS

MANHOLE NUMBER		DRAINAGE AREAS								1-5 YR PEAK FLOW GENERATION					ACTUAL SEWER DATA						UPSTREAM						DOWNSTREAM											
From	To	0.20	0.30	0.40	0.50	0.60	0.80	0.90	area (ha)	cumm area (ha)	2.78AR	2.78AR CUMM	Time min	Intens. mm/hr	Peak Flow L/s	Dia (mm)	Dia (mm)	Slope %	Q full (l/s)	V full (m/s)	Length (m)	Flow Time (min)	Ex. Ground	Pr. Center Line	Obvert Drop	Obvert	Invert	Cover	Ex. Ground	Pr. Center Line	Obvert Drop	Forced Drop	Obvert	Invert	Cover	Dstream Bend		
13	607	0.75				4.01	15.53	9.57	29.86	29.86	65.59	65.59	28.52	55.80	3659.80	1676.4	1650	0.19	4155.57	1.88	83.20	0.74				92.656	91.006	3.66			95.47		-0.15	92.497	90.847	2.97		
607	606					5.60	0.23		5.83	35.69	12.97	78.55	29.26	54.85	4308.72	1828.8	1800	0.21	5495.32	2.09	119.10	0.95				92.647	90.847	2.82			94.80		0.33	92.397	90.597	2.40	15.00	
635	634												20.00	70.25		304.8	300	2.90	171.80	2.35	51.50	0.36				97.681	97.381	5.70			102.56			96.187	95.887	6.37	13.00	
634	633					0.17	0.29		0.46	0.46	1.02	1.02	20.36	69.46	71.06	304.8	300	1.60	127.61	1.75	64.00	0.61				96.187	95.887	6.37			101.67			95.163	94.863	6.51	90.00	
633A	633							0.08	0.08	0.08	0.18	0.18	20.00	70.25	12.50	304.8	300	0.87	94.10	1.29	35.10	0.45				95.122	94.822	6.37				0.30	94.816	94.516	-94.82			
633	632								0.46		1.20	20.97	68.18	81.88	381	375	1.00	182.91	1.60	64.70	0.67				95.163	94.788	6.51			101.29			94.516	94.141	6.77	13.00		
632	631					1.16	0.31		1.47	1.93	3.27	4.47	21.65	66.83	298.76	533.4	525	1.00	448.66	2.01	74.80	0.62				94.516	93.991	6.77			97.55			93.768	93.243	3.78	80.00	
636	631							0.25	0.25	0.25	0.56	0.56	20.00	70.25	39.06	304.8	300	2.23	150.65	2.06	93.30	0.75				95.849	95.549	6.41			97.55			93.768	93.468	3.78		
631	630												22.27	65.64	329.91	533.4	525	3.85	880.33	3.94	81.10	0.34				96.921	96.396	3.73			97.55		0.03	93.798	93.273	3.75		
630	606A	0.36						0.41	0.77	0.77	1.11	6.14	22.61	65.00	398.97	533.4	525	1.35	521.29	2.33	88.90	0.64				93.768	93.243	3.78			94.64		0.03	92.568	92.043	2.07	18.00	
606A	606								0.77		6.14	23.25	63.85	391.91	533.4	525	1.35	521.29	2.33	4.90	0.04					92.538	92.013	2.10			94.80		0.41	92.472	91.947	2.33	81.00	
606	605							0.35	0.35	36.81	0.78	85.47	30.21	53.68	4587.99	(1) 1828.8	(1) 1800	0.25	6049.60	2.30	110.40	0.80				92.065	90.590	2.74			94.69		0.02	91.784	90.309	2.91		
605	604					2.94	0.25		3.19	40.00	7.09	92.57	31.00	52.73	4881.44	(1) 1828.8	(1) 1800	0.24	5911.34	2.25	67.40	0.50				91.765	90.290	2.93			94.50	0.06	-0.02	91.601	90.126	2.90	90.00	
642	641							0.13	0.13	0.13	0.29	0.29	20.00	70.25	20.31	381	375	1.85	248.79	2.18	71.30	0.54				97.259	96.884	3.00			98.94			95.940	95.565	3.00		
641	640					1.10	0.14		1.24	1.37	2.76	3.05	20.54	69.08	210.47	457.2	450	0.80	266.03	1.62	77.70	0.80				95.940	95.490	3.00			98.33			95.318	94.868	3.01		
640	612					1.02	0.14		1.16	2.53	2.58	5.63	21.34	67.43	379.43	609.6	600	0.66	520.98	1.79	82.30	0.77				95.318	94.718	3.01			97.86		-0.04	94.774	94.174	3.09	80.00	
614	613							0.12	0.12	0.12	0.27	0.27	20.00	70.25	18.75	304.8	300	2.16	148.20	2.03	51.20	0.42				96.938	96.638	3.13			98.96			95.833	95.533	3.13		
613	612					1.12	0.14		1.26	1.38	2.18	2.45	20.42	69.34	169.64	381	375	1.98	257.25	2.26	51.60	0.38				95.833	95.458	3.13			97.86			94.813	94.438	3.05		
612	611	0.27						0.16	0.43	4.34	0.51	8.58	22.11	65.93	565.64	685.8	675	3.12	1548.97	4.19	49.60	0.20				94.813	94.138	3.05			96.45		0.03	93.265	92.590	3.18		
611	601					0.90	0.72	0.16	1.78	6.12	3.46	12.04	22.31	65.56	789.16	685.8	675	1.60	1109.24	3.00	44.10	0.24				93.235	92.560	3.21			94.93	0.06		92.530	91.855	2.40	80.00	
601	604							0.07	0.07	6.19	0.16	12.19	22.55	65.10	793.79	685.8	675	1.42	1044.99	2.83	67.50	0.40				92.470	91.795	2.46			94.50		-0.05	91.511	90.836	2.99	90.00	
604	Chamber								46.19		104.76	31.50	52.16	5464.60	(1) 1828.8	(1) 1800	0.21	5495.32	2.09	14.40	0.11						91.556	90.081	2.94			94.00		-0.01	91.526	90.051	2.47	
Chamber	Pond								46.19		104.76	31.62	52.03	5451.05	1524	2x1500	0.33	8472.67	2.32	11.50	0.08						91.539	90.039	2.96			94.00			91.501	90.001	2.50	

(1) The equivalent size of a round pipe is shown to simplify spreadsheet calculations. The actual existing pipe is a horizontal elliptical 1475 x 2310 HE III.





CITY OF OTTAWA

KANATA TOWN CENTRE  
CENTRAL BUSINESS DISTRICT  
URBAN DALE CORPORATION  
JLR PROJECT NO.: 15712

STORM SEWER DESIGN SHEET  
IDF CURVE 1: 5

Designed by: C.B.  
Checked by: D.L.

Date: May 25, 2007

5 YEAR IDF CURVE  
Manning's Coefficient (n) = 0.013

LEGEND: [Symbol] DENOTES EXISTING SEWERS

MANHOLE NUMBER		DRAINAGE AREAS								1:5 YR PEAK FLOW GENERATION					ACTUAL SEWER DATA						UPSTREAM						DOWNSTREAM									
From	To	0.20	0.30	0.40	0.50	0.60	0.80	0.90	area (ha)	cumm area (ha)	2.78AR	2.78AR CUMM	Time min	Intens. mm/hr	Peak Flow L/s	Dia (mm)	Dia (mm)	Slope %	Q full (l/s)	V full (m/s)	Length (m)	Flow Time (min)	Ex. Ground	Pr. Center Line	Obvert Drop	Obvert	Invert	Cover	Ex. Ground	Pr. Center Line	Obvert Drop	Forced Drop	Obvert	Invert	Cover	Ostream Bend
13	607	0.75				4.01	15.53	9.57	29.86	29.86	65.59	65.59	28.52	55.80	3659.80	1676.4	1650	0.19	4155.57	1.88	83.20	0.74		96.32			92.656	91.006	3.66	95.47		-0.15	92.497	90.847	2.97	
607	606						5.60	0.23	5.83	35.69	12.97	78.55	29.26	54.85	4308.72	1828.8	1800	0.21	5495.32	2.09	119.10	0.95		95.47			92.647	90.847	2.82	94.80		0.33	92.397	90.597	2.40	15.00
635	634												20.00	70.25		304.8	300	2.90	171.80	2.35	51.50	0.36		103.38			97.681	97.381	5.70	102.56			96.187	95.887	6.37	13.00
634	633						0.17	0.29	0.46	0.46	1.02	1.02	20.36	69.46	71.06	304.8	300	1.60	127.61	1.75	64.00	0.61		102.56			96.187	95.887	6.37	101.67			95.163	94.863	6.51	90.00
633A	633							0.08	0.08	0.08	0.18	0.18	20.00	70.25	12.50	304.8	300	0.87	94.10	1.29	35.10	0.45		101.49			95.122	94.822	6.37			0.30	94.816	94.516	-94.82	
633	632								0.46		1.20	20.97	68.18	81.88		381	375	1.00	182.91	1.60	64.70	0.67		101.67			95.163	94.788	6.51	101.29			94.516	94.141	6.77	13.00
632	631						1.16	0.31	1.47	1.93	3.27	4.47	21.65	66.83	298.76	533.4	525	1.00	448.66	2.01	74.80	0.62		101.29			94.516	93.991	6.77	97.55			93.768	93.243	3.78	80.00
636	631							0.25	0.25	0.25	0.56	0.56	20.00	70.25	39.06	304.8	300	2.23	150.65	2.06	93.30	0.75		102.26			95.849	95.549	6.41	97.55			93.768	93.468	3.78	
631	630								2.18		5.03	22.27	65.64	329.91		533.4	525	3.85	880.33	3.94	81.10	0.34		100.65			96.921	96.396	3.73	97.55		0.03	93.798	93.273	3.75	
630	606A	0.36						0.41	0.77	0.77	1.11	6.14	22.61	65.00	398.97	533.4	525	1.35	521.29	2.33	88.90	0.64		97.55			93.768	93.243	3.78	94.64		0.03	92.568	92.043	2.07	18.00
606A	606								0.77		6.14	23.25	63.85	391.91		533.4	525	1.35	521.29	2.33	4.90	0.04		94.64			92.538	92.013	2.10	94.80		0.41	92.472	91.947	2.33	81.00
606	605							0.35	0.35	36.81	0.78	85.47	30.21	53.68	4587.99	(1) 1828.8	(1) 1800	0.25	6049.60	2.30	110.40	0.80		94.80			92.065	90.590	2.74	94.69		0.02	91.784	90.309	2.91	
605	604						2.94	0.25	3.19	40.00	7.09	92.57	31.00	52.73	4881.44	(1) 1828.8	(1) 1800	0.24	5911.34	2.25	67.40	0.50		94.69			91.765	90.290	2.93	94.50	0.06	-0.02	91.601	90.126	2.90	90.00
642	641							0.13	0.13	0.13	0.29	0.29	20.00	70.25	20.31	381	375	1.85	248.79	2.18	71.30	0.54		100.26			97.259	96.884	3.00	98.94			95.940	95.565	3.00	
641	640						1.10	0.14	1.24	1.37	2.76	3.05	20.54	69.08	210.47	457.2	450	0.80	266.03	1.62	77.70	0.80		98.94			95.940	95.490	3.00	98.33			95.318	94.868	3.01	
640	612						1.02	0.14	1.16	2.53	2.58	5.63	21.34	67.43	379.43	609.6	600	0.66	520.98	1.79	82.30	0.77		98.33			95.318	94.718	3.01	97.86		-0.04	94.774	94.174	3.09	80.00
614	613							0.12	0.12	0.12	0.27	0.27	20.00	70.25	18.75	304.8	300	2.16	148.20	2.03	51.20	0.42		100.07			96.938	96.638	3.13	98.96			95.833	95.533	3.13	
613	612						1.12	0.14	1.26	1.38	2.18	2.45	20.42	69.34	169.64	381	375	1.98	257.25	2.26	51.60	0.38		98.96			95.833	95.458	3.13	97.86			94.813	94.438	3.05	
612	611	0.27						0.16	0.43	4.34	0.51	8.58	22.11	65.93	565.64	685.8	675	3.12	1548.97	4.19	49.60	0.20		97.86			94.813	94.138	3.05	96.45		0.03	93.265	92.590	3.18	
611	601						0.90	0.72	1.78	6.12	3.46	12.04	22.31	65.56	789.16	685.8	675	1.60	1109.24	3.00	44.10	0.24		96.45			93.235	92.560	3.21	94.93	0.06		92.530	91.855	2.40	80.00
601	604							0.07	0.07	6.19	0.16	12.19	22.55	65.10	793.79	685.8	675	1.42	1044.99	2.83	67.50	0.40		94.93			92.470	91.795	2.46	94.50		-0.05	91.511	90.836	2.99	90.00
604	Chamber								46.19		104.76	31.50	52.16	5464.60	(1) 1828.8	(1) 1800	0.21	5495.32	2.09	14.40	0.11			94.50			91.556	90.081	2.94	94.00		-0.01	91.526	90.051	2.47	
Chamber	Pond								46.19		104.76	31.62	52.03	5451.05	1524	2x1500	0.33	8472.67	2.32	11.50	0.08			94.50			91.539	90.039	2.96	94.00			91.501	90.001	2.50	

(1) The equivalent size of a round pipe is shown to simplify spreadsheet calculations. The actual existing pipe is a horizontal elliptical 1475 x 2310 HE III.





CITY OF OTTAWA

KANATA TOWN CENTRE  
CENTRAL BUSINESS DISTRICT  
URBAN DALE CORPORATION  
JLR PROJECT NO.: 15712

STORM SEWER DESIGN SHEET  
IDF CURVE 1: 5

Designed by: C.B.  
Checked by: D.L.

Date: May 25, 2007

5 YEAR IDF CURVE  
Manning's Coefficient (n) = 0.013

LEGEND  
DENOTES EXISTING SEWERS

MANHOLE NUMBER		DRAINAGE AREAS									1:5 YR PEAK FLOW GENERATION					SEWER DATA						UPSTREAM						DOWNSTREAM											
From	To	0.20	0.30	0.40	0.50	0.60	0.80	0.90	area (ha)	cumm area (ha)	2.78AR	2.78AR CUMM	Time min	Intens. mm/hr	Peak Flow L/s	Dia (mm)	Dia (mm)	Slope %	Q full (l/s)	V full (m/s)	Length (m)	Flow Time (min)	Ex. Ground	Pr. Center Line	Obvert Drop	Obvert	Invert	Cover	Ex. Ground	Pr. Center Line	Obvert Drop	Forced Drop	Obvert	Invert	Cover	Dstream Bend			
13	607	0.75				4.01	15.53	9.57	29.86	29.86	65.59	65.59	28.52	55.80	3659.80	1676.4	1650	0.19	4155.57	1.88	83.20	0.74		96.32			92.656	91.006	3.66		95.47			-0.15	92.497	90.847	2.97		
607	606					5.60	0.23		5.83	35.69	12.97	78.55	29.26	54.85	4308.72	1828.8	1800	0.21	5495.32	2.09	119.10	0.95		95.47			92.647	90.847	2.82		94.80			0.33	92.397	90.597	2.40	15.00	
													30.21																										
635	634												20.00	70.25		304.8	300	2.90	171.80	2.35	51.50	0.36		103.38			97.681	97.381	5.70		102.56			96.187	95.887	6.37	13.00		
634	633					0.17	0.29		0.46	0.46	1.02	1.02	20.36	69.46	71.06	304.8	300	1.60	127.61	1.75	64.00	0.61		102.56			96.187	95.887	6.37		101.67			95.163	94.863	6.51	90.00		
													20.97																										
633A	633								0.08	0.08	0.18	0.18	20.00	70.25	12.50	304.8	300	0.87	94.10	1.29	35.10	0.45		101.49			95.122	94.822	6.37				0.30	94.816	94.516	-94.82			
													20.45																										
633	632									0.46		1.20	20.97	68.18	81.88	381	375	1.00	182.91	1.60	64.70	0.67		101.67			95.163	94.788	6.51		101.29			94.516	94.141	6.77	13.00		
632	631					1.16	0.31		1.47	1.93	3.27	4.47	21.65	66.83	298.76	533.4	525	1.00	448.66	2.01	74.80	0.62		101.29			94.516	93.991	6.77		97.55			93.768	93.243	3.78	80.00		
													22.27																										
636	631						0.25		0.25	0.25	0.56	0.56	20.00	70.25	39.06	304.8	300	2.23	150.65	2.06	93.30	0.75		102.26			95.849	95.549	6.41		97.55			93.768	93.468	3.78			
													20.75																										
631	630									2.18		5.03	22.27	65.64	329.91	533.4	525	3.85	880.33	3.94	81.10	0.34		100.65			96.921	96.396	3.73		97.55		0.03	93.798	93.273	3.75			
630	606A	0.35					0.41		0.77	0.77	1.11	6.14	22.61	65.00	398.97	533.4	525	1.35	521.29	2.33	88.90	0.64		97.55			93.768	93.243	3.78		94.64		0.03	92.568	92.043	2.07	18.00		
606A	606								0.77			6.14	23.25	63.85	391.91	533.4	525	1.35	521.29	2.33	4.90	0.04		94.64			92.538	92.013	2.10		94.80		0.41	92.472	91.947	2.33	81.00		
													23.28																										
606	605						0.35		0.35	36.81	0.78	85.47	30.21	53.68	4587.99	(1) 1828.8	(1) 1800	0.25	6049.60	2.30	110.40	0.80		94.80			92.065	90.590	2.74		94.69		0.02	91.784	90.309	2.91			
605	604					2.94	0.25		3.19	40.00	7.09	92.57	31.00	52.73	4881.44	(1) 1828.8	(1) 1800	0.24	5911.34	2.25	67.40	0.50		94.69			91.765	90.290	2.93		94.50	0.06	-0.02	91.601	90.126	2.90	90.00		
													31.50																										
642	641						0.13		0.13	0.13	0.29	0.29	20.00	70.25	20.31	381	375	1.85	248.79	2.18	71.30	0.54		100.26			97.259	96.884	3.00		98.94			95.940	95.565	3.00			
641	640					1.10	0.14		1.24	1.37	2.76	3.05	20.54	69.08	210.47	457.2	450	0.80	266.03	1.62	77.70	0.80		98.94			95.940	95.490	3.00		98.33			95.318	94.868	3.01			
													21.34																										
640	612					1.02	0.14		1.16	2.53	2.58	5.63	21.34	67.43	379.43	609.6	600	0.66	520.98	1.79	82.30	0.77		98.33			95.318	94.718	3.01		97.86		-0.04	94.774	94.174	3.09	80.00		
													22.11																										
614	613						0.12		0.12	0.12	0.27	0.27	20.00	70.25	18.75	304.8	300	2.16	148.20	2.03	51.20	0.42		100.07			96.938	96.638	3.13		98.96			95.833	95.533	3.13			
613	612					1.12	0.14		1.26	1.38	2.18	2.45	20.42	69.34	169.64	381	375	1.98	257.25	2.26	51.60	0.38		98.96			95.833	95.458	3.13		97.86			94.813	94.438	3.05			
													20.80																										
612	611	0.27					0.16		0.43	4.34	0.51	8.58	22.11	65.93	565.64	685.8	675	3.12	1548.97	4.19	49.60	0.20		97.86			94.813	94.138	3.05		96.45		0.03	93.265	92.590	3.18			
611	601					0.90	0.72		1.78	6.12	3.46	12.04	22.31	65.56	789.16	685.8	675	1.60	1109.24	3.00	44.10	0.24		96.45			93.235	92.560	3.21		94.93	0.06		92.530	91.855	2.40	80.00		
601	604						0.07		0.07	6.19	0.16	12.19	22.55	65.10	793.79	685.8	675	1.42	1044.99	2.83	67.50	0.40		94.93			92.470	91.795	2.46		94.50		-0.05	91.511	90.836	2.99	90.00		
													22.95																										
604	Chamber									46.19		104.76	31.50	52.16	5464.60	(1) 1828.8	(1) 1800	0.21	5495.32	2.09	14.40	0.11		94.50			91.556	90.081	2.94		94.00		-0.01	91.526	90.051	2.47			
													31.62																										
Chamber	Pond									46.19		104.76	31.62	52.03	5451.05	1524	2x1500	0.33	8472.67	2.32	11.50	0.08		94.50			91.539	90.039	2.96		94.00			91.501	90.001	2.50			
													31.70																										

(1) The equivalent size of a round pipe is shown to simplify spreadsheet calculations. The actual existing pipe is a horizontal elliptical 1475 x 2310 HE III.



## **ATTACHMENT 2**



**CITY OF OTTAWA**

KANATA TOWN CENTRE  
CENTRAL BUSINESS DISTRICT  
URBANDALE CORPORATION  
JLR PROJECT NO.: 15712

Commercial Flow = 50000 L/ha/d  
q residential= 350 l/cap/d  
q hotel = 270 l/cap/d  
q retirement homes = 450 l/cap/d  
i = 0.28 l/s/ha  
SING. HOUSING 3.4 pers/hse  
MULT. HOUSING 2.7 pers/hse  
Hotel/Appartments 1.8 pers/room  
Retirement Homes 1.6 pers/room

**SANITARY SEWER DESIGN SHEET**

Designed: C.B.  
Revised by: J.L.P.  
Checked By: D.L.

2016 Update by: HM  
2016 Check by: LD

Date: October 12, 2016

Manning's Coefficient (n) = 0.013

STREET	M.H. # FROM TO		RESIDENTIAL													COMMERCIAL / INSTITUTIONAL			PLUGGED FLOW		R+C		2016 Updates to Block 1 Peak Flows					CAPACITY												
			SING.	Stacks	Towns	NUMBER OF UNITS						POPUL. people	AREA ha	POPUL. people	AREA ha	PEAKING FACTOR	POPUL. FLOW l/s	Actual AREA ha	CUMM. AREA ha	COMM. FLOW l/s	FLOW l/s	CUMM. FLOW l/s	PEAK EXTR. FLOW l/s	PEAK DES. FLOW l/s	DIA. mm	SLOPE %	CAPAC. l/s	VEL. m/s	LENGTH m	Residual (L/s)	% Full									
						Ext. Care		Hotel/Apart.		POPUL. people	AREA ha																					POPUL. people	AREA ha							
						No units	Act. pop	No units	Act. pop																									Equ. pop.						
MARITIME WAY	7A	507									(1) 2588	(1) 28.38	2588	28.38	3.50	36.65	(1) 23.16	23.159	20.10	(1) 162.69	162.69	14.43	233.88	825	0.14	529.34	0.99	81.90	295.46	44%										
MARITIME WAY	507	506									125	225	174	174	1.02	2762	29.40	3.47	38.85	4.91	28.07	24.37			162.69	16.09	242.00	825	0.12	500.32	0.94	119.30	258.32	48%						
CORDILLERA ST.	534	533									125	207	207	207	0.58	207	0.58	4.00	3.35	0.55	0.55	0.48			0.32	4.15	200	1.65	42.13	1.34	66.60	37.98	10%							
CANADIAN SHIELD AV.	533	532														207	0.58	4.00	3.35						0.32	4.15	200	1.20	35.93	1.14	69.60	31.78	12%							
CANADIAN SHIELD AV.	532	531														207	0.91	4.00	3.35						0.41	4.24	200	1.20	35.93	1.14	69.60	31.69	12%							
GREAT LAKES AV.	536	531														100	180	139	139	0.78	139	0.78	4.00	2.25	0.04	0.04	0.03	(5) 0.30	0.30	0.23	2.81	200	2.40	50.81	1.62	60.00	48.00	6%		
GREAT LAKES AV.	531	530															346	1.69	4.00	5.61					0.59	0.51		0.30	0.64	7.05	200	3.75	63.51	2.02	80.80	56.46	11%			
GREAT LAKES AV.	530	506A															346	1.69	4.00	5.61					0.59	0.51		0.30	0.64	7.05	200	1.40	38.80	1.24	85.20	31.75	18%			
GREAT LAKES AV.	506A	506															346	2.07	4.00	5.61					0.59	0.51		0.30	0.74	7.16	200	1.40	38.80	1.24	4.90	31.65	18%			
MARITIME WAY	506	505														176	316.8	269	269	0.57	3377	32.04	3.40	46.49			28.65	24.87		162.99	16.99	251.34	825	0.12	486.76	0.91	111.00	235.41	52%	
MARITIME WAY	505	504														146	262.8	230	230	0.56	3607	32.60	3.37	49.29	1.75	30.40	26.39		162.99	17.64	256.31	825	0.11	484.63	0.91	114.40	228.32	53%		
MARITIME WAY	504	501															3607	32.87	3.37	49.29					30.40	26.39		162.99	17.72	256.39	825	0.11	476.06	0.89	29.90	219.67	54%			
CANADIAN SHIELD AV.	542	541														176	316.8	269	269	0.74	269	0.74	4.00	4.36			0.21	4.57	200	2.20	48.64	1.55	71.30	44.08	9%					
CANADIAN SHIELD AV.	541	540														154	277.2	232	232	0.51	501	1.25	3.97	8.06	1.36	1.36	1.18			0.73	9.98	200	0.90	31.13	0.99	77.70	21.15	32%		
	Block 3	540														208	333		428	428	1.02	428	1.02	4.00	6.93			0.29	7.22	200	0.60	25.40	0.81	12.00	18.18	28%				
CANADIAN SHIELD AV.	540	512																	929	2.57	3.82	14.38				1.36	1.18			1.10	16.66	200	0.71	27.65	0.88	82.60	11.00	60%		
MARITIME WAY	514	513																																						
MARITIME WAY	513	512														120	216	216	216	1.37	216	1.37	4.00	3.50							0.38	3.88	200	2.28	49.52	1.58	51.90	45.64	8%	
MARITIME WAY	512	511																																						
MARITIME WAY	511	510														58	58	(2) 0.73	1203	4.67	3.75	18.26				1.36	1.18			1.69	21.13	200	3.12	57.95	1.84	49.30	36.82	36%		
MARITIME WAY	510	501														120	216	216	216	1.02	1419	5.69	3.70	21.25			1.36	1.18			1.97	24.40	200	1.70	42.76	1.36	38.40	18.36	57%	
TRUNK EASEMENT	501	500																																						
TRUNK EASEMENT	500	94																																						
A	90	92																																						
	92	94																																						
	94	95																																						
	95	89																																						
B	85	87	19																																					
	87	89																																						
A	89	84																																						
C	80	82	19																																					
	82	84																																						
A	84	79																																						
D	75	76																																						
	76	77																																						
	77	79																																						
PARK EASEMENT	79	67																																						
	67	66																																						



**CITY OF OTTAWA**

KANATA TOWN CENTRE  
CENTRAL BUSINESS DISTRICT  
URBAN DALE CORPORATION  
JLR PROJECT NO.: 15712

Commercial Flow = 50000 L/ha/d  
q residential= 350 l/cap/d  
q hotel = 270 l/cap/d  
q retirement homes = 450 l/cap/d  
i = 0.28 l/s/ha  
SING. HOUSING 3.4 pers/hse  
MULT. HOUSING 2.7 pers/hse  
Hotel/Appartments 1.8 pers/room  
Retirement Homes 1.6 pers/room

**SANITARY SEWER DESIGN SHEET**

Designed: C.B.  
Revised by: J.L.P.  
Checked By: D.L.

2016 Update by: HM  
2016 Check by: LD


Date: October 12, 2016

Manning's Coefficient (n) = 0.013

STREET	M.H. # FROM TO		RESIDENTIAL										COMMERCIAL / INSTITUTIONAL			PLUGGED FLOW		R+C		2016 Updates to Block 1 Peak Flows					CAPACITY										
			NUMBER OF UNITS						CUMMULATIVE		PEAKING FACTOR	POPUL. FLOW l/s	Actual AREA ha	CUMM. AREA ha	COMM. FLOW l/s	FLOW l/s	CUMM. FLOW l/s	PEAK EXTR. FLOW l/s	PEAK DES. FLOW l/s	SEWER DATA					Residual (L/s)	% Full									
			SING.	Stacks	Towns	Ext. Care No units Act. pop		Hotel/Apart. No units Act. pop Equ. pop.		POPUL. people										AREA ha	POPUL. people	AREA ha	DIA. mm	SLOPE %			CAPAC. l/s	VEL. m/s	LENGTH m						
BELLROCK DRIVE	70	73		12	14						70	2.56	70	2.56	4.00	1.14							0.72	1.85	250	0.40	37.61	0.77	87.2	35.75	5%				
EASEMENT	74	62									32	0.54	103	3.10	4.00	1.66								0.87	2.53	250	0.40	37.61	0.77	60.3	35.08	7%			
CAMBRAV LANE	62	66			25						68	0.48	170	3.89	4.00	2.76								0.95	2.62	250	0.40	37.61	0.77	39.9	34.99	7%			
BISHOPS MILLS WAY	66	65			9						24	0.53	5857	52.90	3.18	75.47																			
SOUTH of HWY 417	EX.	65									(1) 7792	(1) 191.60	7792	191.60	3.06	96.63				(4) 37.72	37.72				53.65	188.00	900	0.11	600.38	0.94	50.2	412.38	31%		
BISHOPS MILLS WAY	65	64			2						5		13654	244.50	2.82	155.95																			
EDENVALE DRIVE	59	60			8						22	0.50	22	0.50	4.00	0.35									0.14	0.49	200	1.40	38.80	1.24	77.0	38.31	1%		
KETTLEBY STREET	60	61			22						59	0.62	81	1.12	4.00	1.31									0.31	1.63	250	0.40	37.61	0.77	103.6	35.98	4%		
CAMBRAV LANE	58	61			5						14	0.41	14	0.41	4.00	0.22									0.11	0.33	200	0.70	27.44	0.87	74.5	27.10	1%		
KETTLEBY STREET	61	64			25						68	0.42	162	1.95	4.00	2.63										0.55	3.17	250	0.90	56.41	1.15	105.0	53.24	6%	
BISHOPS MILLS WAY	64	63			3						8		13825	246.45	2.81	157.59										77.90	463.77	900	0.11	600.38	0.94	13.0	136.62	77%	
	63	57			10						27	0.68	13852	247.13	2.81	157.85										78.09	464.22	900	0.11	600.38	0.94	64.9	136.17	77%	
TER. BUNGALOW Ph.2	51	53		48							130	0.94	130	0.94	4.00	2.10										0.26	2.36	200	0.70	27.44	0.87	122.3	25.08	9%	
	53	54		4							11		140	0.94	4.00	2.28										0.26	2.54	200	0.70	27.44	0.87	13.6	24.90	9%	
	54	55										0.27	140	1.21	4.00	2.28										0.34	2.61	200	0.70	27.44	0.87	36.7	24.82	10%	
BISHOPS MILLS WAY	55	56	11								37	0.81	178	2.02	4.00	2.88										0.57	3.45	250	0.40	37.61	0.77	107.1	34.16	9%	
	56	57	7		12						56	0.65	234	2.67	4.00	3.79										0.75	4.54	250	0.60	46.06	0.94	101.5	41.52	10%	
PARK	57	34			1						3	0.37	14088	250.17	2.81	160.12										78.94	467.34	900	0.11	600.38	0.94	53.5	133.04	78%	
	34	33			3						8		14096	250.17	2.81	160.20										78.94	467.42	900	0.11	600.38	0.94	50.3	132.96	78%	
HAWKSTONE	43	44		22							59	1.19	59	1.19	4.00	0.96										0.33	1.30	250	1.00	59.46	1.21	51.0	58.17	2%	
	44	45		8							22	0.09	81	1.28	4.00	1.31										0.36	1.67	250	0.50	42.05	0.86	29.0	40.38	4%	
ENDENVALE	45	35										0.08	81	1.36	4.00	1.31										0.38	1.69	250	0.50	42.05	0.86	39.8	40.35	4%	
BIRKENDALE DRIVE	35	36	7								24	1.18	105	2.54	4.00	1.70										0.71	2.41	250	0.37	36.18	0.74	93.2	33.77	7%	
	36	37	13								44	0.79	149	3.33	4.00	2.41										0.93	3.35	250	0.37	36.09	0.74	77.1	32.74	9%	
	37	33	2		3						15		164	3.33	4.00	2.66										0.93	3.59	250	0.40	37.61	0.77	17.9	34.02	10%	
BIRKENDALE DRIVE	33	32			10						27	0.56	14287	254.06	2.80	162.03											80.03	470.34	900	0.11	600.38	0.94	72.7	130.05	78%
TEESWATER STREET	30	31			16						43	0.66	43	0.66	4.00	0.70										0.18	0.88	250	0.40	37.61	0.77	75.1	36.72	2%	
	31	32			19						51	0.41	95	1.07	4.00	1.53										0.30	1.83	250	0.40	37.61	0.77	77.9	35.78	5%	
BIRKENDALE STREET	32	18			6						16	0.37	14398	255.50	2.80	163.09											80.43	471.80	900	0.11	600.38	0.94	44.4	128.58	79%
	18	16			4						11		14409	255.50	2.80	163.19											80.43	471.90	900	0.11	600.38	0.94	44.4	128.48	79%
COMMERCIAL PLAZA	19	17													4.00											0.15	0.60	150	0.90	14.45	0.82	26.5	13.85	4%	
COLCHESTER SQUARE	17	16										0.10	0.10		4.00											0.17	0.62	250	0.40	37.61	0.77	33.2	36.98	2%	
COLCHESTER SQUARE	16	15			10						27	0.56	14436	256.16	2.79	163.45											80.76	472.94	900	0.11	600.38	0.94	66.0	127.44	79%
	15	14 A			2						5		14441	256.16	2.79	163.50											80.76	472.99	900	0.11	600.38	0.94	25.8	127.39	79%
ELSINORE LANE	39	28		32							86	0.53	86	0.53	4.00	1.40										0.15	1.55	250	1.00	59.46	1.21	56.7	57.91	3%	
	28	24		18							49	1.47	135	2.00	4.00	2.19										0.56	2.75	250	0.40	37.61	0.77	43.0	34.86	7%	
	24	23		12							32	0.14	167	2.14	4.00	2.71										0.60	3.31	250	0.40	37.61	0.77	34.0	34.30	9%	
ELSINORE LANE	23	306		8							22	0.24	189	2.38	4.00	3.06										0.67	3.73	250	0.44	39.41	0.80	48.8	35.68	9%	
ENDENVALE DRIVE	306	14 A										0.45	189	2.83	4.00	3.06										0.79	3.85	250	0.49	41.68	0.85	46.4	37.83	9%	







CITY OF OTTAWA LANDS  
 Q = 233.88 l/s PER  
 KANATA TOWN CENTRE  
 TRUNK SANITARY SEWER  
 DESIGN DATED 1998

**LEGEND**

- SANITARY SEWER & MANHOLE
- EXISTING SANITARY SEWER & MH
- CATCH BASIN
- HYDRANT
- DRAINAGE BOUNDARY
- AREA IN HECTARES
- PIPE REACH
- STUB-506

DATE	REVISIONS	BY	NO.	DATE	REVISIONS	BY
12/06/12	REVISED CBD DRAINAGE	JLP	4	13/09/08	ISSUED TO CITY FOR REVIEW	LND
24/07/07	REVISED AS PER CITY COMMENTS	CSB	3	21/07/06	ISSUED TO CITY FOR REVIEW (STREET 'A' NORTH-SOUTH LEG)	LND
25/05/07	PHASE 2 ISSUED FOR CITY REVIEW	CSB	2	05/11/98	REVISED PER RMOC	LND
08/03/07	ISSUED FOR TENDER	CSB	1	08/06/98	ISSUED FOR MOE APPROVAL (SAN)	LND

SCALE  
 0 10m 20m 30m 40m  
 HORIZONTAL 1:1000

J.L. Richards & Associates Limited  
 864 Lady Ellen Place  
 Ottawa, ON Canada  
 K1Z 5M2  
 Tel: 613 728 3571  
 Fax: 613 728 6012

THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED OR USED FOR PURPOSES OTHER THAN EXECUTION OF THE DESCRIBED WORK WITHOUT THE EXPRESS WRITTEN CONSENT OF J.L. RICHARDS & ASSOCIATES LIMITED.

DESIGN C.B.  
 CHECKED L.N.D.  
 DRAWN T.S.  
 CHECKED  
 APPROVED

KANATA TOWN CENTRE  
 CENTRAL BUSINESS DISTRICT  
 SANITARY DRAINAGE PLAN

PROJECT No. 15712-NAD 83  
 STARTED JUNE 1998  
 DWG. No. 15712-SAN

q (res) = 350 l/cap/day  
 q (com) = 50,000 l/ha/day  
 q (inst) = 50,000 l/ha/day  
 I = 0.280 l/s/ha  
 Singles, Townhouses, Ter. Bungalows = 3.8 pers / unit (low & medium density)  
 Stacked Townhouses / Apartments = 2.2 pers / unit (high density)  
 Stacked Townhouses / Apartments = 80 units / ha (high density)

**CITY OF KANATA**

**SANITARY SEWER DESIGN SHEET**

**KANATA TOWN CENTRE  
 (RESIDENTIAL)  
 URBANDALE CORPORATION**

Designed by: L.N.D.

Checked by: M.F.S.

STREET	M.H. #		No. of UNITS		AREA ha	CUMMULATIVE		Peaking Factor	POPUL. FLOW l/s	INFIL. FLOW l/s	PEAK FLOW l/s	SEWER DATA				
	FROM	TO	Singles & Townhouses	Stacked Townhouses		POPUL. peop.	AREA ha					DIA. mm	Slope %	CAPAC. l/s	VEL. m/s	LENGTH m
A	90	92	37		0.80	141	0.80	4.00	2.28	0.22	2.50	250	0.60	46.06	0.94	120.0
	92	94	13		1.19	190	1.99	4.00	3.08	0.56	3.64	250	2.20	88.20	1.80	103.0
	94	95			66.80	4831	68.79	3.26	63.77	19.26	270.61	825	0.12	497.22	0.93	17.5
	95	89	10		0.52	4869	69.31	3.26	64.21	19.41	271.20	825	0.12	497.22	0.93	66.6
B	85	87	19		1.19	72	1.19	4.00	1.17	0.33	1.50	250	0.40	37.61	0.77	116.9
	87	89	26		0.82	171	2.01	4.00	2.77	0.56	3.33	250	1.41	70.70	1.44	116.7
A	89	84	12		0.35	5085	71.67	3.24	66.71	20.07	274.35	825	0.12	497.22	0.93	79.0
	80	82	20		1.08	76	1.08	4.00	1.23	0.30	1.53	250	0.40	37.61	0.77	120.0
C	82	84	28		0.83	182	1.91	4.00	2.96	0.53	3.49	250	1.20	65.18	1.33	118.5
	84	79	14		0.54	5321	74.12	3.22	69.40	20.75	277.74	825	0.12	497.22	0.93	79.0
D	75	76	19		0.37	72	0.37	4.00	1.17	0.10	1.27	250	0.40	37.61	0.77	57.0
	76	77	20		0.29	148	0.66	4.00	2.40	0.18	2.59	250	0.40	37.61	0.77	78.4
	77	79	14		0.63	201	1.29	4.00	3.26	0.36	3.62	250	0.81	53.66	1.09	117.7
PARK EASEMENT	79	67			0.98	5522	76.39	3.20	71.69	21.39	280.66	825	0.12	497.22	0.93	55.0
	67	66	6		0.33	5545	76.72	3.20	71.95	21.48	281.01	825	0.12	497.22	0.93	70.0
BELLROCK DRIVE	70	73	26		2.56	99	2.56	4.00	1.60	0.72	2.32	250	0.40	37.61	0.77	87.2
	73	74	10		0.54	137	3.10	4.00	2.22	0.87	3.08	250	0.40	37.61	0.77	60.3
EASEMENT CAMBRAY LANE	74	62			0.31	137	3.41	4.00	2.22	0.95	3.17	250	0.40	37.61	0.77	39.9
	62	66	25		0.48	232	3.89	4.00	3.76	1.09	4.85	250	0.77	52.18	1.06	100.5
BISHOPS MILLS WAY	66	65	9		0.53	5811	81.14	3.18	74.95	22.72	285.25	825	0.12	497.22	0.93	62.0
SOUTH of HWY 417	EX.	65			191.60	7792	191.60	3.06	96.63	53.65	188.16	900	0.11	600.38	0.94	50.2
BISHOPS MILLS WAY	65	64	2			13610	272.74	2.82	155.52	76.37	457.35	900	0.11	600.38	0.94	17.0
EDENVALE DRIVE KETTLEBY STREET	59	60	8		0.50	30	0.50	4.00	0.49	0.14	0.63	200	1.40	38.80	1.24	77.0
	60	61	24		0.62	122	1.12	4.00	1.97	0.31	2.28	250	0.40	37.61	0.77	103.6
CAMBRAY LANE	58	61	8		0.41	30	0.41	4.00	0.49	0.11	0.61	200	0.70	27.44	0.87	74.5
KETTLEBY STREET	61	64	25		0.42	247	1.95	4.00	4.00	0.55	4.55	250	0.90	56.41	1.15	105.0
BISHOPS MILLS WAY	84	63	3			13869	274.69	2.81	158.01	76.91	460.38	900	0.11	600.38	0.94	13.0
	63	57	10		0.68	13907	275.37	2.81	158.38	77.10	460.94	900	0.11	600.38	0.94	64.9
TER. BUNGALOW Ph.2	51	53	48		0.94	182	0.94	4.00	2.96	0.26	3.22	200	0.70	27.44	0.87	122.3
	53	54	4			198	0.94	4.00	3.20	0.26	3.47	200	0.70	27.44	0.87	13.6
BISHOPS MILLS WAY	54	55			0.27	198	1.21	4.00	3.20	0.34	3.54	200	0.70	27.44	0.87	36.7
	55	56	11		0.81	239	2.02	4.00	3.88	0.57	4.44	250	0.40	37.61	0.77	107.1
	56	57	19		0.65	312	2.67	4.00	5.05	0.75	5.80	250	0.60	46.06	0.94	101.5
PARK	57	34	1		0.37	14222	278.41	2.80	161.40	77.95	464.82	900	0.11	600.38	0.94	53.5
	34	33	3		0.00	14234	278.41	2.80	161.51	77.95	464.93	900	0.11	600.38	0.94	50.3
HAWKSTONE	43	44	16		1.19	61	1.19	4.00	0.99	0.33	1.32	250	1.00	59.46	1.21	51.0
	44	45	8		0.09	91	1.28	4.00	1.48	0.36	1.84	250	0.50	42.05	0.85	29.0
ENDENVALE BIRKENDALE DRIVE	45	35			0.08	91	1.36	4.00	1.48	0.38	1.86	250	0.50	42.05	0.85	39.8
	35	36	7		1.18	118	2.54	4.00	1.91	0.71	2.62	250	0.37	36.18	0.74	93.2
	36	37	13		0.79	167	3.33	4.00	2.71	0.93	3.64	250	0.37	36.09	0.74	77.1
	37	33	2		0.00	175	3.33	4.00	2.83	0.93	3.76	250	0.40	37.61	0.77	17.9
	33	32	13		0.56	14458	282.30	2.79	163.66	79.04	468.16	900	0.11	600.38	0.94	72.7
TEESWATER STREET	30	31	18		0.66	68	0.66	4.00	1.11	0.18	1.29	250	0.40	37.61	0.77	75.1
	31	32	19		0.41	141	1.07	4.00	2.28	0.30	2.58	250	0.40	37.61	0.77	77.9
BIRKENDALE STREET	32	18	4		0.37	14614	283.74	2.79	165.14	79.45	470.05	900	0.11	600.38	0.94	44.4
	18	16	6			14636	283.74	2.79	165.36	79.45	470.27	900	0.11	600.38	0.94	44.4
COMMERCIAL PLAZA COLCHESTER SQUARE	19	17			0.52	0	0.52	1.50	0.45	0.15	0.60	150	0.90	14.45	0.82	26.5
	17	16			0.10	0	0.62	4.00	0.45	0.17	0.62	250	0.40	37.61	0.77	33.2
COLCHESTER SQUARE	16	15	10		0.56	14674	284.92	2.79	166.17	79.78	471.41	900	0.11	600.38	0.94	66.0
	15	14 A	2			14682	284.92	2.79	166.25	79.78	471.48	900	0.11	600.38	0.94	25.8
ELSINORE LANE	39	28	22		0.53	84	0.53	4.00	1.35	0.15	1.50	250	1.00	59.46	1.21	56.7
	28	24	14		1.47	137	2.00	4.00	2.22	0.56	2.78	250	0.40	37.61	0.77	43.0
	24	23	12		0.14	182	2.14	4.00	2.96	0.60	3.55	250	0.40	37.61	0.77	34.0
	23	306	8		0.24	213	2.38	4.00	3.45	0.67	4.11	250	0.44	39.41	0.80	48.8
ENDENVALE DRIVE	306	14 A			0.45	213	2.83	4.00	3.45	0.79	4.24	250	0.49	41.68	0.85	46.4
	14 A	14				14895	287.75	2.78	167.82	80.57	473.85	900	0.11	600.38	0.94	14.7
COLCHESTER SQUARE TERON	Church	14			0.52	0	0.52	1.50	0.45	0.15	0.60	150	1.00	15.23	0.85	35.0
	14	11	4		0.16	14910	288.43	2.78	168.87	80.76	475.09	900	0.11	600.38	0.94	72.6
TERON	11	10				14910	288.43	2.78	168.87	80.76	475.09	900	0.11	600.38	0.94	29.6
	10	EX.			0.25	14910	288.68	2.78	168.87	80.83	475.16	900	0.11	600.38	0.94	72.3
	O.P.P.	EX.									0.78	100	Forcemain			
TERON	EX.	EX.								475.94	680	0.96	838.61	2.31	9.4	



**APPENDIX F**  
**Development Servicing Study Checklist**

## 4. Development Servicing Study Checklist

---

The following section describes the checklist of the required content of servicing studies. It is expected that the proponent will address each one of the following items for the study to be deemed complete and ready for review by City of Ottawa Infrastructure Approvals staff.

The level of required detail in the Servicing Study will increase depending on the type of application. For example, for Official Plan amendments and re-zoning applications, the main issues will be to determine the capacity requirements for the proposed change in land use and confirm this against the existing capacity constraint, and to define the solutions, phasing of works and the financing of works to address the capacity constraint. For subdivisions and site plans, the above will be required with additional detailed information supporting the servicing within the development boundary.

### 4.1 General Content

- N/A  Executive Summary (for larger reports only).
- Date and revision number of the report.
- Location map and plan showing municipal address, boundary, and layout of proposed development.
- Plan showing the site and location of all existing services.
- Development statistics, land use, density, adherence to zoning and official plan, and reference to applicable subwatershed and watershed plans that provide context to which individual developments must adhere.
- Summary of Pre-consultation Meetings with City and other approval agencies.
- Reference and confirm conformance to higher level studies and reports (Master Servicing Studies, Environmental Assessments, Community Design Plans), or in the case where it is not in conformance, the proponent must provide justification and develop a defensible design criteria.
- Statement of objectives and servicing criteria.
- Identification of existing and proposed infrastructure available in the immediate area.
- Identification of Environmentally Significant Areas, watercourses and Municipal Drains potentially impacted by the proposed development (Reference can be made to the Natural Heritage Studies, if available).

- Concept level master grading plan to confirm existing and proposed grades in the development. This is required to confirm the feasibility of proposed stormwater management and drainage, soil removal and fill constraints, and potential impacts to neighbouring properties. This is also required to confirm that the proposed grading will not impede existing major system flow paths.
- N/A  Identification of potential impacts of proposed piped services on private services (such as wells and septic fields on adjacent lands) and mitigation required to address potential impacts.
- N/A  Proposed phasing of the development, if applicable.
- Reference to geotechnical studies and recommendations concerning servicing.
- All preliminary and formal site plan submissions should have the following information:
- Metric scale
  - North arrow (including construction North)
  - Key plan
  - Name and contact information of applicant and property owner
  - Property limits including bearings and dimensions
  - Existing and proposed structures and parking areas
  - Easements, road widening and rights-of-way
  - Adjacent street names

## 4.2 Development Servicing Report: Water

- N/A  Confirm consistency with Master Servicing Study, if available
- Availability of public infrastructure to service proposed development
- N/A  Identification of system constraints
- Identify boundary conditions
- Confirmation of adequate domestic supply and pressure
- Confirmation of adequate fire flow protection and confirmation that fire flow is calculated as per the Fire Underwriter's Survey. Output should show available fire flow at locations throughout the development.
- Provide a check of high pressures. If pressure is found to be high, an assessment is required to confirm the application of pressure reducing valves.
- N/A  Definition of phasing constraints. Hydraulic modeling is required to confirm servicing for all defined phases of the project including the ultimate design
- Address reliability requirements such as appropriate location of shut-off valves
- N/A  Check on the necessity of a pressure zone boundary modification.

- Reference to water supply analysis to show that major infrastructure is capable of delivering sufficient water for the proposed land use. This includes data that shows that the expected demands under average day, peak hour and fire flow conditions provide water within the required pressure range
- Description of the proposed water distribution network, including locations of proposed connections to the existing system, provisions for necessary looping, and appurtenances (valves, pressure reducing valves, valve chambers, and fire hydrants) including special metering provisions.
- N/A  Description of off-site required feeder mains, booster pumping stations, and other water infrastructure that will be ultimately required to service proposed development, including financing, interim facilities, and timing of implementation.
- Confirmation that water demands are calculated based on the City of Ottawa Design Guidelines.
- Provision of a model schematic showing the boundary conditions locations, streets, parcels, and building locations for reference.

### 4.3 Development Servicing Report: Wastewater

- Summary of proposed design criteria (Note: Wet-weather flow criteria should not deviate from the City of Ottawa Sewer Design Guidelines. Monitored flow data from relatively new infrastructure cannot be used to justify capacity requirements for proposed infrastructure).
- Confirm consistency with Master Servicing Study and/or justifications for deviations.
- N/A  Consideration of local conditions that may contribute to extraneous flows that are higher than the recommended flows in the guidelines. This includes groundwater and soil conditions, and age and condition of sewers.
- Description of existing sanitary sewer available for discharge of wastewater from proposed development.
- Verify available capacity in downstream sanitary sewer and/or identification of upgrades necessary to service the proposed development. (Reference can be made to previously completed Master Servicing Study if applicable)
- Calculations related to dry-weather and wet-weather flow rates from the development in standard MOE sanitary sewer design table (Appendix 'C') format.
- Description of proposed sewer network including sewers, pumping stations, and forcemains.



- N/A  Discussion of previously identified environmental constraints and impact on servicing (environmental constraints are related to limitations imposed on the development in order to preserve the physical condition of watercourses, vegetation, soil cover, as well as protecting against water quantity and quality).
- N/A  Pumping stations: impacts of proposed development on existing pumping stations or requirements for new pumping station to service development.
- N/A  Forcemain capacity in terms of operational redundancy, surge pressure and maximum flow velocity.
- N/A  Identification and implementation of the emergency overflow from sanitary pumping stations in relation to the hydraulic grade line to protect against basement flooding.
- Special considerations such as contamination, corrosive environment etc.

#### 4.4 Development Servicing Report: Stormwater Checklist

- Description of drainage outlets and downstream constraints including legality of outlets (i.e. municipal drain, right-of-way, watercourse, or private property)
- N/A  Analysis of available capacity in existing public infrastructure.
- A drawing showing the subject lands, its surroundings, the receiving watercourse, existing drainage patterns, and proposed drainage pattern.
- Water quantity control objective (e.g. controlling post-development peak flows to pre-development level for storm events ranging from the 2 or 5 year event (dependent on the receiving sewer design) to 100 year return period); if other objectives are being applied, a rationale must be included with reference to hydrologic analyses of the potentially affected subwatersheds, taking into account long-term cumulative effects.
- N/A  Water Quality control objective (basic, normal or enhanced level of protection based on the sensitivities of the receiving watercourse) and storage requirements.
- Description of the stormwater management concept with facility locations and descriptions with references and supporting information.
- N/A  Set-back from private sewage disposal systems.
- Watercourse and hazard lands setbacks.
- N/A  Record of pre-consultation with the Ontario Ministry of Environment and the Conservation Authority that has jurisdiction on the affected watershed.
- Confirm consistency with sub-watershed and Master Servicing Study, if applicable study exists.

- Storage requirements (complete with calculations) and conveyance capacity for minor events (1:5 year return period) and major events (1:100 year return period).
- Identification of watercourses within the proposed development and how watercourses will be protected, or, if necessary, altered by the proposed development with applicable approvals.
- Calculate pre and post development peak flow rates including a description of existing site conditions and proposed impervious areas and drainage catchments in comparison to existing conditions.
- N/A  Any proposed diversion of drainage catchment areas from one outlet to another.
- Proposed minor and major systems including locations and sizes of stormwater trunk sewers, and stormwater management facilities.
- N/A  If quantity control is not proposed, demonstration that downstream system has adequate capacity for the post-development flows up to and including the 100-year return period storm event.
- N/A  Identification of potential impacts to receiving watercourses
- N/A  Identification of municipal drains and related approval requirements.
- Descriptions of how the conveyance and storage capacity will be achieved for the development.
- 100 year flood levels and major flow routing to protect proposed development from flooding for establishing minimum building elevations (MBE) and overall grading.
- Inclusion of hydraulic analysis including hydraulic grade line elevations.
- Description of approach to erosion and sediment control during construction for the protection of receiving watercourse or drainage corridors.
- N/A  Identification of floodplains – proponent to obtain relevant floodplain information from the appropriate Conservation Authority. The proponent may be required to delineate floodplain elevations to the satisfaction of the Conservation Authority if such information is not available or if information does not match current conditions.
- N/A  Identification of fill constraints related to floodplain and geotechnical investigation.

## 4.5 Approval and Permit Requirements: Checklist

The Servicing Study shall provide a list of applicable permits and regulatory approvals necessary for the proposed development as well as the relevant issues affecting each approval. The approval and permitting shall include but not be limited to the following:



- Conservation Authority as the designated approval agency for modification of floodplain, potential impact on fish habitat, proposed works in or adjacent to a watercourse, cut/fill permits and Approval under Lakes and Rivers Improvement Act. The Conservation Authority is not the approval authority for the Lakes and Rivers Improvement Act. Where there are Conservation Authority regulations in place, approval under the Lakes and Rivers Improvement Act is not required, except in cases of dams as defined in the Act.
- Application for Certificate of Approval (CofA) under the Ontario Water Resources Act.
- N/A  Changes to Municipal Drains.
- N/A  Other permits (National Capital Commission, Parks Canada, Public Works and Government Services Canada, Ministry of Transportation etc.)

## 4.6 Conclusion Checklist

- Clearly stated conclusions and recommendations
- N/A  Comments received from review agencies including the City of Ottawa and information on how the comments were addressed. Final sign-off from the responsible reviewing agency.
- All draft and final reports shall be signed and stamped by a professional Engineer registered in Ontario

## **APPENDIX G**

### **Drawings**




**LEGEND**

---	PROPERTY LINE	▽	PROPOSED TERRACE ENTRANCE
—DC—	PROPOSED CURB	○	EXISTING UTILITY POLE C/W GUY WIRES
---	PROPOSED DEPRESSED CURB	○	EXISTING WATERMAIN C/W VALVE & VALVE CHAMBER
---	PROPOSED WATER SERVICE	○	EXISTING HYDRANT C/W VALVE & LEAD
SP	PROPOSED STANDPOST	○	EXISTING SANITARY MANHOLE & SEWER
V&VB	PROPOSED VALVE AND VALVE BOX	○	EXISTING STORM MANHOLE & SEWER
⊔	PROPOSED CAP	CB 1	EXISTING CATCHBASIN
⊙	PROPOSED WATER METER	—	EXISTING GAS MAIN
⊙	PROPOSED REMOTE METER	—	EXISTING UNDERGROUND BELL LINE
●	PROPOSED SANITARY SERVICE C/W MANHOLE	—	EXISTING UNDERGROUND TELLUS LINE
○	PROPOSED STORM SEWER C/W MANHOLE	—	EXISTING UNDERGROUND ROGERS LINE
▽	PROPOSED BUILDING ENTRANCE	—	EXISTING UNDERGROUND STREETLIGHT LINE
→	DIRECTION OF FLOW	—	EXISTING UNDERGROUND HYDRO LINE
AD	PROPOSED AREA DECK DRAIN BY OTHERS (REFER TO MECH DRAWINGS FOR MORE INFO)	⊙	EXISTING STREETLIGHT
RD	PROPOSED ROOF DRAIN BY OTHERS (REFER TO MECH DRAWINGS FOR MORE INFO)		
GM	PROPOSED GAS METER		

**NOTE:**  
 THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.


**PRELIMINARY  
 NOT FOR  
 CONSTRUCTION**

No.	REVISION	DATE	BY
3.	ISSUED FOR SITE PLAN APPROVAL	JUL 7/21	CJR
2.	ISSUED FOR COORDINATION	MAY 14/21	CJR
1.	ISSUED FOR COORDINATION	MAR 30/21	CJR



DESIGN: MJH  
 CHECKED: CJR  
 DRAWN: MJH  
 CHECKED: CJR  
 APPROVED: JLS



**FOR REVIEW ONLY**



REFER TO 120191-ND FOR ADDITIONAL NOTES


LOCATION CITY OF OTTAWA CARRÉ-SAINT-LOUIS	
DRAWING NAME <b>GENERAL SERVICING PLAN</b>	
PROJECT No. 120191	REV # 3
DRAWING No. 120191-GP	

M:\2020\120191\120191-GP.dwg, GP, Jul 06, 2021, 4:57pm, kalakodius



**LEGEND**

	PROPERTY LINE		H.P. PROPOSED HIGH POINT
	PROPOSED ELEVATION		PROPOSED CURB
	EXISTING ELEVATION		PROPOSED DEPRESSED CURB
	PROPOSED TOP OF WALL ELEVATION		TERRACING 3:1 SLOPE MAX (UNLESS OTHERWISE INDICATED)
	PROPOSED BOTTOM OF WALL ELEVATION		PROPOSED RETAINING WALL
	PROPOSED TOP OF CURB ELEVATION		PROPOSED DOOR SILL ELEVATION
	PROPOSED DOOR SILL ELEVATION		SAWCUT
	PROPOSED VALVE AND VALVE BOX		ROAD REINSTATEMENT
	PROPOSED BUILDING ENTRANCE		EXISTING VALVE & VALVE CHAMBER
	DIRECTION OF MAJOR OVERLAND FLOW		EXISTING VALVE & VALVE BOX
	PROPOSED AREA DECK DRAIN BY OTHERS (REFER TO MECH DRAWINGS FOR MORE INFO)		EXISTING HYDRANT
	PROPOSED FILTER BAGS AT CATCHBASINS, CATCHBASIN MANHOLES AND TRENCHDRAINS		EXISTING SANITARY MANHOLE
	PROPOSED MUD MAT		EXISTING STORM MANHOLE
	LIGHT DUTY SILT FENCE (OPSD 219.110)		EXISTING CATCHBASIN
			EXISTING LIGHT STANDARD



**PAVEMENT STRUCTURE:**


	HEAVY DUTY PAVEMENT
	40mm HL3 OR SP 12.5
	50mm HL8 PR SP 19.0
	150mm OPSS GRANULAR 1A
	450mm OPSS GRANULAR 5B TYPE II

REFER TO 120191-ND FOR ADDITIONAL NOTES

**NOTE:**  
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.


**PRELIMINARY  
NOT FOR  
CONSTRUCTION**

No.	REVISION	DATE	BY
5.	ISSUED FOR SITE PLAN APPROVAL	JUL 7/21	CJR
4.	ISSUED FOR COORDINATION	JUN 10/21	CJR
3.	ISSUED FOR COORDINATION	MAY 04/21	CJR
2.	ISSUED FOR COORDINATION	APR 23/21	CJR
1.	ISSUED FOR COORDINATION	MAR 30/21	CJR



DESIGN	MJH
CHECKED	CJR
DRAWN	MJH
CHECKED	CJR
APPROVED	JLS

**FOR REVIEW ONLY**



**NOVATECH**  
Engineers, Planners & Landscape Architects  
Suite 200, 240 Michael Cowpland Drive  
Ottawa, Ontario, Canada K2M 1P6

Telephone: (613) 254-9643  
Facsimile: (613) 254-5867  
Website: www.novatech-eng.com

LOCATION CITY OF OTTAWA CARRÉ-SAINT-LOUIS	
DRAWING NAME <b>GRADING PLAN</b>	
PROJECT No. 120191	REV # 5
DRAWING No. 120191-GR	

M:\2020\120191\120191-GR.dwg GR Jul 05 2021 4:57pm lakouras

**GENERAL NOTES:**

- COORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.
- DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME RESPONSIBILITY FOR ALL EXISTING UTILITIES WHETHER OR NOT SHOWN ON THIS DRAWING.
- OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE CITY OF OTTAWA BEFORE COMMENCING CONSTRUCTION.
- BEFORE COMMENCING CONSTRUCTION OBTAIN AND PROVIDE PROOF OF COMPREHENSIVE ALL RISK AND OPERATIONAL LIABILITY INSURANCE FOR \$5,000,000.00. INSURANCE POLICY TO NAME OWNERS, ENGINEERS AND ARCHITECTS AS CO-INSURED AND THE CITY OF OTTAWA AS THIRD PARTY.
- RESTORE ALL DISTURBED AREAS ON-SITE AND OFF-SITE, INCLUDING TRENCHES AND SURFACES ON PUBLIC ROAD ALLOWANCES TO EXISTING CONDITIONS OR BETTER TO THE SATISFACTION OF THE CITY OF OTTAWA AND ENGINEER.
- REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL, ORGANIC MATERIAL AND DEBRIS UNLESS OTHERWISE INSTRUCTED BY ENGINEER. EXCAVATE AND REMOVE FROM SITE ANY CONTAMINATED MATERIAL. ALL CONTAMINATED MATERIAL SHALL BE DISPOSED OF AT A LICENSED LANDFILL FACILITY.
- ALL ELEVATIONS ARE GEODETIC.
- REFER TO GEOTECHNICAL REPORT (No. PG5371-1, DATED MAY 19, 2021), PREPARED BY PATERSON GROUP FOR SUBSURFACE CONDITIONS, CONSTRUCTION RECOMMENDATIONS, AND GEOTECHNICAL INSPECTION REQUIREMENTS. THE GEOTECHNICAL CONSULTANT IS TO REVIEW ON-SITE CONDITIONS AFTER EXCAVATION PRIOR TO PLACEMENT OF THE GRANULAR MATERIAL.
- REFER TO ARCHITECT'S AND LANDSCAPE ARCHITECT'S DRAWINGS FOR BUILDING AND HARDSURFACE AREAS AND DIMENSIONS.
- REFER TO STORMWATER MANAGEMENT REPORT (R-2021-097) PREPARED BY NOVATECH ENGINEERING CONSULTANTS LTD.
- SAW CUT AND KEY GRIND ASPHALT AT ALL ROAD CUTS AND ASPHALT TIE IN POINTS AS PER CITY OF OTTAWA STANDARDS (R10).
- PROVIDE LINE/PARKING PAINTING AS REQUIRED FOR REINSTATEMENT.
- CONTRACTOR TO PROVIDE THE CONSULTANT WITH A GENERAL PLAN OF SERVICES INDICATING ALL SERVICING AS-BUILT INFORMATION SHOWN ON THIS PLAN. AS-BUILT INFORMATION MUST INCLUDE: PIPE MATERIAL, SIZES, LENGTHS, SLOPES, INVERT AND TIG ELEVATIONS, STRUCTURE LOCATIONS, VALVE AND HYDRANT LOCATIONS, TWM ELEVATIONS AND ANY ALIGNMENT CHANGES, ETC.

**SEWER NOTES:**

- | ITEM                             | SPEC. No. | REFERENCE      |
|----------------------------------|-----------|----------------|
| CATCHBASIN (600x600mm)           | 705.010   | OPSD           |
| STORM / SANITARY MANHOLE (1200Ø) | 701.010   | OPSD           |
| CB, FRAME & COVER                | 400.020   | OPSD           |
| STORM / SANITARY MH FRAME        | S25       | CITY OF OTTAWA |
| SANITARY COVER                   | S24       | CITY OF OTTAWA |
| STORM COVER (CLOSED)             | S24.1     | CITY OF OTTAWA |
| STORM COVER (OPEN)               | S28.1     | CITY OF OTTAWA |
| SEWER TRENCH                     | S6 & S7   | CITY OF OTTAWA |
| STORM SEWER                      | PVC DR 35 | CITY OF OTTAWA |
| SANITARY SEWER                   | PVC DR 35 | CITY OF OTTAWA |
| ELBOW CB                         | S31       | CITY OF OTTAWA |
| TEE CB                           | S30       | CITY OF OTTAWA |
- SERVICES ARE TO BE CONSTRUCTED TO 1.0m FROM FACE OF BUILDING AT A MINIMUM SLOPE OF 1.0%.
  - PIPE BEDDING, COVER AND BACKFILL ARE TO BE COMPACTED TO AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY. THE USE OF CLEAR CRUSHED STONE AS A BEDDING LAYER SHALL NOT BE PERMITTED.
  - FLEXIBLE CONNECTIONS ARE REQUIRED FOR CONNECTING PIPES TO MANHOLES (FOR EXAMPLE KOR-N-SEAL, PSX, POSITIVE SEAL AND DURASEAL). THE CONCRETE CRADLE FOR THE PIPE CAN BE ELIMINATED.
  - THE OWNER SHALL REQUIRE THAT THE SITE SERVICING CONTRACTOR PERFORM FIELD TESTS FOR QUALITY CONTROL OF ALL SANITARY SEWERS. LEAKAGE TESTING SHALL BE COMPLETED IN ACCORDANCE WITH OPSS 410.07.16, 410.07.16.04 AND 407.07.24. DYE TESTING IS TO BE COMPLETED ON ALL SANITARY SERVICES TO CONFIRM PROPER CONNECTION TO THE SANITARY SEWER MAIN. THE FIELD TESTS SHALL BE PERFORMED IN THE PRESENCE OF A CERTIFIED PROFESSIONAL ENGINEER WHO SHALL SUBMIT A CERTIFIED COPY OF THE TEST RESULTS.
  - STORM MANHOLES AND CBMHS ARE TO HAVE 300mm SUMPUS UNLESS OTHERWISE INDICATED.
  - CONTRACTOR TO TELEWISE (CCTV) ALL PROPOSED SEWERS, 200mmØ OR GREATER PRIOR TO BASE COURSE ASPHALT. UPON COMPLETION OF CONTRACT, THE CONTRACTOR IS RESPONSIBLE TO FLUSH AND CLEAN ALL SEWERS & APPURTENANCES.
  - DYE TESTING IS TO BE COMPLETED ON SANITARY SERVICES TO CONFIRM PROPER CONNECTION TO THE SANITARY SEWER MAIN.
  - A SANITARY BACKWATER VALVE ON THE SANITARY SERVICE IS REQUIRED.
  - ALL DRAINAGE FOR THE UNDERGROUND PARKING LEVELS IS REQUIRED TO BE DIRECTED TO THE SANITARY SEWER.

**EROSION AND SEDIMENT CONTROL NOTES:**

- THE OWNER AGREES TO PREPARE AND IMPLEMENT AN EROSION AND SEDIMENT CONTROL PLAN TO THE SATISFACTION OF THE CITY OF OTTAWA, APPROPRIATE TO THE SITE CONDITIONS, PRIOR TO UNDERTAKING ANY SITE ALTERATIONS (FILLING, GRADING, REMOVAL OF VEGETATION, ETC.) AND DURING ALL PHASES OF SITE PREPARATION AND CONSTRUCTION IN ACCORDANCE WITH THE CURRENT BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROL SUCH AS BUT NOT LIMITED TO INSTALLING FILTER CLOTHS ACROSS MANHOLE/CATCHBASIN LIDS TO PREVENT SEDIMENTS FROM ENTERING STRUCTURES AND INSTALL AND MAINTAIN A LIGHT DUTY SILT FENCE BARRIER AS REQUIRED.
- THE CONTRACTOR SHALL PLACE FILTER CLOTH UNDER THE CATCHBASIN AND MANHOLE GRATES FOR THE DURATION OF CONSTRUCTION AND WILL REMAIN IN PLACE DURING ALL PHASES OF CONSTRUCTION.
- SILT FENCING FOR ENTIRE PERIMETER OF SITE, SHALL BE UTILIZED TO CONTROL EROSION FROM THE SITE DURING CONSTRUCTION.
- THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.
- EROSION AND SEDIMENT CONTROL MEASURES MAY BE MODIFIED IN THE FIELD AT THE DISCRETION OF THE CITY OF OTTAWA SITE INSPECTOR OR CONSERVATION AUTHORITY.

**GRADING NOTES:**


- ALL TOPSOIL, ORGANIC OR DELETERIOUS MATERIAL MUST BE ENTIRELY REMOVED FROM BENEATH THE PROPOSED PAVED AREAS AS DIRECTED BY THE SITE ENGINEER OR GEOTECHNICAL ENGINEER.
- EXPOSED SUBGRADES IN PROPOSED PAVED AREAS SHOULD BE PROOF ROLLED WITH A LARGE STEEL DRUM ROLLER AND INSPECTED BY THE GEOTECHNICAL ENGINEER PRIOR TO THE PLACEMENT OF GRANULARS.
- ANY SOFT AREAS EVIDENT FROM THE PROOF ROLLING SHOULD BE SUB-EXCAVATED AND REPLACED WITH SUITABLE MATERIAL THAT IS FROST COMPATIBLE WITH THE EXISTING SOILS AS RECOMMENDED BY THE GEOTECHNICAL ENGINEER.
- THE GRANULAR BASE SHOULD BE COMPACTED TO AT LEAST 100% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE. ANY ADDITIONAL GRANULAR FILL USED BELOW THE PROPOSED PAVEMENT SHOULD BE COMPACTED TO AT LEAST 98% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE.
- MINIMUM OF 2% GRADE FOR ALL GRASS AREAS UNLESS OTHERWISE NOTED.
- MAXIMUM TERRACING GRADE TO BE 3:1 UNLESS OTHERWISE NOTED.
- ALL GRADES BY CURBS ARE EDGE OF PAVEMENT GRADES UNLESS OTHERWISE INDICATED.
- ALL CURBS SHALL BE BARRIER CURB (150mm) UNLESS OTHERWISE NOTED AND CONSTRUCTED AS PER CITY OF OTTAWA STANDARDS (SC1.1).
- REFER TO LANDSCAPE PLAN FOR PLANTING AND OTHER LANDSCAPE FEATURE DETAILS.
- CONTRACTOR TO PROVIDE THE CONSULTANT WITH A GRADING PLAN INDICATING AS-BUILT ELEVATIONS OF ALL DESIGN GRADES SHOWN ON THIS PLAN.

**WATERMAIN NOTES:**

- | ITEM                                   | SPEC. No. | REFERENCE      |
|--|-----------|----------------|
| WATERMAIN TRENCHING                    | W17       | CITY OF OTTAWA |
| THERMAL INSULATION IN SHALLOW TRENCHES | W22       | CITY OF OTTAWA |
| WATERMAIN CROSSING BELOW SEWER         | W25       | CITY OF OTTAWA |
| WATERMAIN                              | PVC DR 18 |                |
- SPECIFICATIONS:
  - SUPPLY AND CONSTRUCT ALL WATERMANS AND APPURTENANCES IN ACCORDANCE WITH THE CITY OF OTTAWA STANDARDS AND SPECIFICATIONS. EXCAVATION, INSTALLATION, BACKFILL AND RESTORATION OF ALL WATERMANS BY THE CONTRACTOR. CONNECTIONS AND SHUT-OFFS AT THE MAIN AND CHLORINATION OF THE WATER SYSTEM SHALL BE PERFORMED BY CITY OFFICIALS.
  - WATERMAIN SHALL BE MINIMUM 2.4m DEPTH BELOW GRADE UNLESS OTHERWISE INDICATED.
  - PROVIDE MINIMUM 0.25m CLEARANCE BETWEEN OUTSIDE OF PIPES AT ALL CROSSINGS.
  - WATER SERVICE IS TO BE CONSTRUCTED TO WITHIN 1.0m OF FOUNDATION WALL AND CAPPED, UNLESS OTHERWISE INDICATED.

**SWM TANK NOTES:**


- THE MINIMUM INTERNAL SIZE OF THE STORMWATER MANAGEMENT TANK IS TO BE 312m<sup>3</sup>. REFER TO THE CROSS SECTION DETAIL AND THE ARCHITECT'S DRAWINGS FOR TANK DIMENSIONS, CONFIGURATION, MATERIALS AND WATERPROOFING DETAILS.
- THE ACCESS HATCHES ARE TO OPERATE AS THE EMERGENCY OVERFLOW FOR THE SWM TANK. PROVIDE THE FRAME AND COVERS PER S25 & S28.1 RESPECTIVELY.
- PROVIDE CIRCULAR HOLLOW ALUMINIUM MAINTENANCE HOLE STEPS ALONG TANK WALLS AT THE ACCESS HATCHES PER OPSS 405.010.



**STORMWATER STORAGE TANK TABLE**

DESIGN EVENT	CONTROLLED FLOW FROM STORAGE TANK	STORAGE TANK VOLUME	
		REQUIRED	PROVIDED
1:2 YR	68.6 L/s	105 m <sup>3</sup>	>312 m <sup>3</sup>
1:5 YR	82.6 L/s	147 m <sup>3</sup>	
1:100 YR	116.6 L/s	275 m <sup>3</sup>	

- NOTES:**
- ALL DRAINAGE FROM AREA A-2 (PROPOSED COURTYARD AND ROOF) TO BE DIRECTED TO THE INTERNAL STORMWATER STORAGE TANK. REFER TO MECHANICAL PLANS FOR DETAILS OF INTERNAL STORMWATER STORAGE TANK.
  - REFER TO STRUCTURAL PLANS FOR EXACT SIZE AND DETAILS OF INTERNAL STORMWATER STORAGE TANK.
  - REFER TO ARCHITECTURAL AND MECHANICAL PLANS FOR LOCATION AND CONNECTIONS TO INTERNAL STORMWATER STORAGE TANK.



**NOTE:**  
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

**PRELIMINARY  
NOT FOR  
CONSTRUCTION**

No.	REVISION	DATE	BY
2.	ISSUED FOR SITE PLAN APPROVAL	JUL 07/21	CJR
1.	ISSUED FOR COORDINATION	MAR 30/21	CJR

DESIGN	SCALE
MJH	AS NOTED
CJR	
MJH	
CJR	
JLS	

**FOR REVIEW ONLY**

159

LICENSED PROFESSIONAL ENGINEER  
C.J. BUDDLE  
PROVINCE OF ONTARIO

**NOVATECH**  
Engineers, Planners & Landscape Architects  
Suite 200, 240 Michael Cowpland Drive  
Ottawa, Ontario, Canada K2M 1P6  
Telephone (613) 254-9643  
Facsimile (613) 254-5867  
Website www.novatech-eng.com

**LOCATION**  
CITY OF OTTAWA  
1050 CANADIAN SHIELD

**DRAWING NAME**  
NOTES AND DETAILS PLAN

**PROJECT No.:** 120191  
**REV:** REV # 2  
**DRAWING No.:** 120191-ND