

Engineers, Planners & Landscape Architects

Land / Site Development

Municipal Infrastructure

Environmental / Water Resources

Traffic /

Transportation

Structural

Recreational

Planning

Land / Site Development

Planning Application Management

Municipal Planning Documents & **Studies**

Expert Witness (OMB)

Wireless Industry

Landscape **Architecture**

Urban Design & Streetscapes

Open Space, Parks & **Recreation Planning**

Community & Residential **Developments**

Commercial & **Institutional Sites**

Environmental Restoration

Klondike Road - Block 10

Noise Impact Assessment



Noise Impact Assessment

Maple Leaf Homes Klondike Road – Block 10

Prepared by:

NOVATECH

240 Michael Cowpland Drive, Suite 200 Ottawa, Ontario, K2M 1P6

May 17, 2021

Ref: R-2021-067 Novatech File No. 117034-10



May 17, 2021

BY COURIER

City of Ottawa Planning and Growth Management Department 110 Laurier Avenue West, 4th Floor Ottawa, ON K1P 1J1

Attention: Lisa Stern, Planner

Reference: Maple Leaf Homes Development

Klondike Road – Block 10 Noise Impact Assessment Our File No.: 117034-10

Please find enclosed the 'Noise Impact Assessment' for Maple Leaf Homes Development located at Klondike Road – Block 10.

Please contact the undersigned with any questions, or if you require additional information.

Sincerely,

NOVATECH

Lucas Wilson, P.Eng. Project Coordinator

Cc: Brian Saumure, Maple Leaf Homes

TABLE OF CONTENTS

1.0	INTE	RODUCTION	.1
2.0		OF OTTAWA ENVIRONMENTAL NOISE CONTROL GUIDELINES	
2.1		OUND LEVEL CRITERIA	
2.2		DISE ATTENUATION REQUIREMENTS	
2.	2.1	Noise Barrier	. 5
2.	2.2	Ventilation Requirements	. 5
2.	2.3	Building Component Assessment	. 6
2.	2.4	Warning Clauses	. 6
2.	2.5	Summary of Noise Attenuation Measure Requirements	. 7
3.0	NOIS	SE SOURCES	.8
3.1 3.2	Kı Sı	LONDIKE ROAD (COLLECTOR)ERROR! BOOKMARK NOT DEFINE	.8
4.0		SE LEVEL PREDICTIONS	
4.1		ODELING	
4.2		UTDOOR CONTROL MEASURES	
4.3		DOOR CONTROL MEASURES	
4.4		UILDING COMPONENT ASSESSMENT	
5.0	CON	ICLUSIONS AND RECOMMENDATIONS	11
LIST (OF FI	GURES	
Figure Figure	1-2 3-1	Key Plan Plan of Subdivision Noise Sources Construction Requirements and Warning Clauses	
LIST C)FTA	ABLES	
Table Table Table Table	2-2 Ir 2-3 C 3-1 K 3-2 S 4-1 C	city of Ottawa Outdoor Plane of Window Sound Level Criteria Indoor Sound Level Criteria Outdoor, Ventilation and Warning Clause Requirements (NPC-300) Ilondike Road Noise Parameters andhill Road Noise Parameters OLA Noise Level Summary OW Noise Level Summary	
LIST C	OF AF	PPENDICIES	
• •		: Receiver Location Figures Stamson Model Output : Grading Plan (117034-GR)	

Novatech

:

1.0 INTRODUCTION

This report is submitted on behalf of the developer, Maple Leaf Homes for the proposed development located at 1055 Klondike Road – Block 10, herein called the 'Subject Site'. This report assesses the environmental impact of noise on the proposed development and outlines the mitigation measures that will be required.

The proposed development is located within the Kanata North Community west of the intersection of Klondike Road and Sandhill Road. The development is approximately 0.60ha and is bounded by Klondike Road to the south, Shirley's Brook to the west, and the future 1055 Klondike Road – Orr Ridge Subdivision to the north and east. A key plan of the area is presented below in **Figure 1-1**.




Figure 1-1 Key Plan

This report assesses the impacts of sound from vehicular traffic on the proposed development using the Ministry of the Environment (MOE) Stamson 5.0 software and outlines any necessary noise attenuation requirements for compliance with the City of Ottawa Environmental Noise Control Guidelines (ENCG) and the MOE Environmental Noise Guidelines (MOE Publication NPC-300).

The following describes the existing and planned land uses adjacent to the subject site:


North / **East:** The lands north and east of the proposed site is the future 1055 Klondike Road – Orr Ridge Subdivision consisting of town house and semi-detached units.

South: Klondike Road, a two-lane urban collector road, bounds the Subject Site to the south. The Subject Site is located between March Road and Sandhill Road on the North Side of Klondike Road.

Southeast: To the Southeast of the Subject Site, across Klondike Road, are Brookside Baptist Church and The Greenwoods Academy.

West: The RioCentre Kanata (832-858 March Road) is located to the west of the Subject Site, separated by Shirley's Brook.

Plans are to develop a 4-storey apartment building with underground parking on the subject site, as shown on **Figure 1-2**, which will consist of 53 apartment units townhouse units.



Novatech Page 3

2.0 CITY OF OTTAWA ENVIRONMENTAL NOISE CONTROL GUIDELINES

2.1 Sound Level Criteria

The City of Ottawa is concerned with noise from aircraft, roads, railways and transitways as expressed in the City of Ottawa Official Plan (May 2003). These policies are supported by the Environmental Noise Control Guidelines (ENCG) which is a technical document that outlines the specific sound level criteria. The City of Ottawa's *Environmental Noise Control Guidelines (ENCG)*, January, 2016 and the Ministry of Environment's *Environmental Noise Guidelines, Stationary and Transportation Sources – Approval and Planning, Publication NPC-300* have been used for the purpose of this report. As per Section 2.2 of the City of Ottawa Noise Control Guidelines (2016), unless otherwise noted, developments should be consistent with NPC-300 (MOE publication, 2013).

The areas that must be assessed for acoustic protection include the Outdoor Living Area (OLA) and the Outdoor Plane of Window (POW).

These locations are defined as:

- Outdoor Living Area (OLA): The Outdoor Living Area is defined as that part of the outdoor amenity area provided for the quiet enjoyment of the outdoor environment during the daytime period. These amenity areas are typically backyards, gardens, terraces, patios and common outdoor living areas. The OLA noise target for traffic noise sources is 55 dBA. This criterion may be exceeded by an amount not greater than 5 dBA, subject to justification and the use of a Warning Clause. OLA noise levels are analysed at 3.0m from the building façade, 1.5m above grade.
- Plane of Window (POW): The plane of window is defined as the indoor living space where the sound levels will affect the living room area during daytime hours and bedrooms during night time hours. The residential Plane of Window noise target for traffic noise sources is 55 dBA during the day and 50 dBA at night. If this criterion is exceeded, the property may be subject to building component analysis and warning clauses. The sound criterion is broadly summarized in Table 2-1. POW noise levels are analysed 1.5m above grade for the first storey, 4.5m above grade for the second storey, 7.5m above grade for the third storey and 10m above grade for the fourth storey.

Table 2-1 City of Ottawa Outdoor Plane of Window Sound Level Criteria

TIME PERIOD	RECEIVER LOCATION	SOUND LEVEL CRITERIA
Daytime (07:00 - 23:00 hrs)	Plane of Living Room Window	55 dBA
Night time (23:00 - 07:00 hrs)	Plane of Bedroom Window	50 dBA

Compliance with the outdoor sound level criteria generally ensures compliance with the indoor sound level criteria which is summarized below in **Table 2-2**.

Table 2-2 Indoor Sound Level Criteria

TIME PERIOD	RECEIVER LOCATION	SOUND LEVEL CRITERIA
Daytime (07:00 - 23:00 hrs)	Living/Dining Rooms of residential dwelling units , hospitals, schools, nursing homes, day-care centres, theatres, places of worship, individual or semiprivate offices, conference rooms etc.	45 dBA
Night Time (23:00 - 07:00 hrs)	Sleeping quarters of residential units, hospitals, nursing homes, senior citizen homes, etc.	40 dBA

2.2 Noise Attenuation Requirements

When sound levels are predicted to be less than the specified criteria for daytime and night time conditions, no attenuation measures are required on the part of the proponent. As the noise criteria are exceeded, a combination of attenuation measures is recommended by the City of Ottawa and the MOE to modify the development environment.

These attenuation measures may include any or all of the following:

- Distance setback with soft ground;
- Insertion of noise insensitive land uses between the source and sensitive receptor;
- Orientation of building to provide sheltered zone;
- Construction of a noise barrier wall and/or berm;
- Installation of a forced air ventilation system with provision for central air;
- Installation of central air;
- Acoustically selected building façade components

2.2.1 Noise Barrier

Noise barriers should only be used when other noise control measures have been considered, and there is no other alternative. For the purpose of this study, when noise levels exceed 60 dBA in the Outdoor Living Area, control measures (barriers) are required to reduce the Leq to below 60 dBA and as close to 55 dBA as technically, economically and administratively feasible.

The noise barriers are to be compliant with the City standard for noise barriers and have the following characteristics.

- Minimum height of 2.2m;
- Maximum height of 2.5m (unless approved by the City of Ottawa);
- Situated 0.30m inside the private property;
- A surface mass density not less than 20kg/sq.m; and
- No holes or gaps.

2.2.2 Ventilation Requirements

A forced air heating system with provision for a central air conditioning system is required if the daytime noise levels are between 55 dBA and 65 dBA and/or night time noise levels are between 50 dBA and 60 dBA.

The installation of a central air conditioning system is required when the daytime noise level exceeds 65 dBA and/or night time noise levels exceed 60 dBA.

2.2.3 Building Component Assessment

When noise levels exceed 65 dBA (daytime) or 60 dBA (night time) the exterior cladding system of the building envelope must be acoustically assessed to ensure the indoor sound criteria is achieved. This includes analysis of the exterior wall, door, and/or glazing system specifications as appropriate.

The NRC research *Acoustic Insulation Factor: A Rating for the Insulation of Buildings against Noise* (June 1980, JD Quirt) is used to assess the building components and the required acoustic insulation factor (AIF). This method is recognized by the City of Ottawa.

The required AIF is based on the Outside L_{eq} , Indoor L_{eq} required, and the number of exterior façade components.

Minimum Required AIF = Outside L_{eq} - Indoor L_{eq} + log_{10} (Number of Components) + 2dB

Where, N = Number of components (walls, windows and roof);

L = Sound Level expressed on a common decibel scale.

2.2.4 Warning Clauses

When predicted noise levels exceed the specified criteria, the City of Ottawa and the MOE recommend warning clauses be registered as a notice on title and incorporated into the sales agreements to warn potential purchaser/buyers/tenants of the possible elevated noise levels.

The following typical warning clauses are extracted from Section C8.1 of the MOE NPC-300 document.

Warning Clause Type A

"Purchasers/tenants are advised that sound levels due to increasing road traffic may occasionally interfere with some activities of the dwelling occupants as the sound levels exceed the City's and the Ministry of the Environment's noise criteria."

Warning Clause Type B

"Purchasers/tenants are advised that despite the inclusion of noise control features in the development and within the building units, sound levels due to increasing road traffic may on occasion interfere with some activities of the dwelling occupants as the sound levels exceed the City's and the Ministry of the Environment's noise criteria."

Warning Clause Type C

"This dwelling unit has been designed with the provision for adding central air conditioning at the occupant's discretion. Installation of central air conditioning by the occupant will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the City's and the Ministry of the Environment's noise criteria."

Warning Clause Type D

"This dwelling unit has been supplied with a central air conditioning system which will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the City's and the Ministry of the Environment's noise criteria."

2.2.5 Summary of Noise Attenuation Measure Requirements

Table 2-3 summarizes the noise attenuation measure requirements and warning clauses should sound criteria be exceeded.

Table 2-3 Outdoor, Ventilation and Warning Clause Requirements (NPC-300)

Assessmen	L _{eq} (dBA)	Outdoor Control Measures	Indoor Control Measures			
t Location			Ventilation Requirements	Building Components	Warning Clause	
	Less than 55	None required	N/A	N/A	None required	
Outdoor Living Area (OLA)	Between 55 and 60	Control measures (barriers) may not be required but should be considered	N/A	N/A	Required if resultant L _{eq} exceeds 55 dBA Type A	
	More than 60	Barriers required	N/A	N/A	Required if resultant L _{eq} exceeds 55 dBA Type B	
	Less than 55	N/A	None Required	None Required	None Required	
Plane of Living Room	Between55 and 65	N/A	Forced air heating with provision for central air conditioning	None Required	Required Type C	
Window (POW)	More Than 65	N/A	Central Air Conditioning	Acoustical performance of the windows and walls should be specified	Required Type D	
	Less than 50	N/A	None Required	None Required	None Required	
Plane of Bedroom Window	Between50 and 60	N/A	Forced air heating with provision for central air conditioning	None Required	Required Type C	
(POW)	More than 60	N/A	Central Air Conditioning	Acoustical performance of the windows and walls should be specified	Required Type D	

3.0 NOISE SOURCES

The City of Ottawa Official Plan and Environmental Noise Control Guidelines (ENCG) stipulate that a noise impact assessment is required when a noise sensitive development is within proximity to a surface transportation (road or rail), stationary and aircraft noise sources.

Due to the site location, only roadway noise will be considered. The following distances to roadway noise sources are applicable to the subject site:

• Within 100m from the right-of-way of an existing/proposed arterial/collector

Figure 3-1 shows the noise source that has an impact on this development. Klondike Road (Collector) is located within 100m of the development.


3.1 Klondike Road (Collector)

Klondike Road is classified as an Urban Collector (2-UCU) Roadway in the 2013 Transportation Master Plan. An Annual Average Daily Traffic (AADT) value of 8,000 is specified for this type of road.

As per Table B1 of Appendix B of the ENCG, **Table 3-1** outlines the traffic parameters used to calculate the sound levels for the development.

Table 3-1 Klondike Road Noise Parameters

Roadway Classification	2-Lane Urban Collector	
Annual Average Daily Traffic (AADT)	8,000 veh/day	
Day/Night Split (%)	92/8	
Heavy Trucks (%)	5	
Medium Trucks (%)	7	
Posted Speed Limit	50 km/hr	
Road Gradient	0.5%	



Novatech Page 9

4.0 NOISE LEVEL PREDICTIONS

4.1 Modeling

Noise levels are calculated using the STAMSON computer program, version 5.03. Road data is input into the program as applicable, whereupon the program calculates an A-weighted 16 hour L_{eq} noise level for the daytime and an 8 hour L_{eq} noise level for the night time. The results of these computer calculations are presented in **Appendix B** and summarized in **Table 4-1** and **Table 4-2**.

Table 4-1 OLA Noise Level Summary

LOCATION	OUTDOOR LIVING AREA NOISE LEVEL – Leq - (dBA)
	Unattenuated
R1 (Amenity Area)	53.79

Table 4-2 POW Noise Level Summary

LOCATION	PLANE OF WINDOW (POW) NOISE LEVEL – L _{eq} - (dBA)		
	DAYTIME	NIGHT TIME	
R2 (1st to 4th Floor)	59.63	52.04	
R3 (4 th Floor)	54.10	46.51	
R4 (1st to 4th Floor)	55.01	47.41	

4.2 Outdoor Control Measures

The shared amenity space is located in the interior side yard adjacent to Shirley's Brook. The OLA noise level is below the minimum requirement of 55 dBA (53.79 dBA), therefore no mitigation measures or warning clauses are required.

4.3 Indoor Control Measures

Warning clauses are required on title relating to the requirement of forced air heating with provision for central air conditioning and required central air conditioning.

All units facing Klondike Road and all units facing Shirley's Brook up to receiver location R4 will require forced air heating with provision for central air conditioning and associated warning clause Type C and are identified below in **Figure 5-1**.

Typical wording for Type C warning clause: "This dwelling unit has been designed with the provision for adding central air conditioning at the occupant's discretion. Installation of central air conditioning by the occupant will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the City's and the Ministry of the Environment's noise criteria."

4.4 Building Component Assessment

All plane-of-window noise levels within the development are below 65 dBA; therefore, building component assessment is not required. As long as building components are built to Ontario Building Code minimums, all indoor noise levels will meet the City of Ottawa and MOE guidelines outlined in **Table 2-2** above.

5.0 CONCLUSIONS AND RECOMMENDATIONS

To meet the requirements for compliance with the City of Ottawa Environmental Noise Control Guidelines and the MOE Environmental Noise Guideline the following measures are required.

Outdoor Control Measures

The noise level in the shared amenity space is below 55 dBA, therefore no warning clause is required.

Indoor Control Measures

All units facing Klondike Road and all units facing Shirley's Brook up to receiver location R4 will require forced air heating with provision for central air conditioning and associated warning clause Type C and are presented in **Figure 5-1**.

Building Component Assessment

All building faces will comply with the ENCG indoor noise policy employing Ontario Building Code minimum building components.

Warning Clauses

Warning clauses are to be placed on title and in the purchase and sale agreements as indicated above and in **Figure 5-1**. The following typical warning clauses are extracted from Section C8.1 of the MOE NPC-300 document.

Warning Clause Type 'C'

"This dwelling unit has been designed with the provision for adding central air conditioning at the occupant's discretion. Installation of central air conditioning by the occupant will allow windows and exterior doors to remain closed, thereby ensuring that the indoor sound levels are within the City's and the Ministry of the Environment's noise criteria."




Figure 5-1 Construction Requirements and Warning Clauses

If you have any questions or comments with regards to this report, please do not hesitate to contact the undersigned.

Respectfully issued,

NOVATECH

Prepared By:



Lucas Wilson, P.Eng. Project Coordinator


Reviewed By:




Mark Bissett, P.Eng. Senior Project Manager

APPENDIX A

Receiver Location Figures Stamson Model Output





STAMSON 5.0 NORMAL REPORT Date: 10-05-2021 16:13:13 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r1.te Time Period: Day/Night 16/8 hours

Description: OLA R1

Road data, segment # 1: Klondike (day/night)

Car traffic volume : 6477/563 veh/TimePeriod *
Medium truck volume : 515/45 veh/TimePeriod *
Heavy truck volume : 368/32 veh/TimePeriod *
Posted speed limit : 50 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or cond

0 %1 (Typical asphalt or concrete) Road pavement

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 8000 Percentage of Annual Growth : 0.00 Number of Years of Growth : 0.00 Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: Klondike (day/night) _____

Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods. No of house rows : 0 / 0 Surface : 2 (Reflective (No woods.)

(Reflective ground surface)

Receiver source distance : 112.50 / 112.50 m Receiver height : 1.50 / 4.50 $\,$ m $\,$

: 2 (Flat/gentle slope; with barrier) Topography

Barrier anglel : -62.00 deg Angle2 : 33.00 deg Barrier height : 12.00 m

Barrier receiver distance : 4.50 / 4.50 m

Source elevation : 0.00 mReceiver elevation : 0.00 m Barrier elevation : 0.00 m Reference angle : 0.00

Results segment # 1: Klondike (day)

Source height = 1.50 m

Barrier height for grazing incidence

ROAD (48.92 + 34.22 + 52.01) = 53.79 dBA

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
-90 -62 0.00 65.75 0.00 -8.75 -8.08 0.00 0.00 0.00 48.92
-62 33 0.00 65.75 0.00 -8.75 -2.78 0.00 0.00 -20.00 34.22
33 90 0.00 65.75 0.00 -8.75 -4.99 0.00 0.00 0.00 52.01

Segment Leq: 53.79 dBA

Total Leq All Segments: 53.79 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 53.79

STAMSON 5.0 NORMAL REPORT Date: 10-05-2021 16:12:44 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r2.te Time Period: Day/Night 16/8 hours

Description: POW R2

Road data, segment # 1: Klondike (day/night) _____

Car traffic volume : 6477/563 veh/TimePeriod * Medium truck volume : 515/45 veh/TimePeriod *
Heavy truck volume : 368/32 veh/TimePeriod *

Posted speed limit : 50 km/h

Road gradient :

: 0 %
: 1 (Typical asphalt or concrete) Road pavement

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): Percentage of Annual Growth : 0.00 : 0.00 Number of Years of Growth Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: Klondike (day/night) _____

Angle1 Angle2 : -90.00 deg 90.00 deg Wood depth : 0 (No woods (No woods.)

No of house rows : 0 / 0

2 (Reflective ground surface)

Receiver source distance : 61.40 / 61.40 m Receiver height : 1.50 / 1.50 $\,$ m $\,$

: 1 Topography (Flat/gentle slope; no barrier)

Reference angle : 0.00

Results segment # 1: Klondike (day)

Source height = 1.50 m

ROAD (0.00 + 59.63 + 0.00) = 59.63 dBA

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.00 65.75 0.00 -6.12 0.00 0.00 0.00 0.00 59.63 ______

Segment Leq: 59.63 dBA

Total Leq All Segments: 59.63 dBA

Results segment # 1: Klondike (night)

Source height = 1.50 m

ROAD (0.00 + 52.04 + 0.00) = 52.04 dBA Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq -90 90 0.00 58.16 0.00 -6.12 0.00 0.00 0.00 0.00 52.04

Segment Leq: 52.04 dBA

Total Leq All Segments: 52.04 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 59.63

(NIGHT): 52.04

STAMSON 5.0 NORMAL REPORT Date: 10-05-2021 16:12:12 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r3.te Time Period: Day/Night 16/8 hours

Description: POW R3

Road data, segment # 1: Klondike (day/night)

Car traffic volume : 6477/563 veh/TimePeriod * Medium truck volume : 515/45 veh/TimePeriod * Heavy truck volume : 368/32 veh/TimePeriod *

Posted speed limit : 50 km/h 0 % Road gradient :

1 (Typical asphalt or concrete) Road pavement :

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 8000 Percentage of Annual Growth : 0.00 Number of Years of Growth Medium Truck % of Total Volume : 7.00 Heavy Truck % of Total Volume : 5.00 Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: Klondike (day/night)

Angle1 Angle2 : -90.00 deg 0.00 deg : 0 : 0 / 0 Wood depth (No woods.)

No of house rows

2 (Reflective ground surface)

Receiver source distance : 63.20 / 63.20 m Receiver height : 10.50 / 10.50 m

2 (Flat/gentle slope; with barrier) Topography :

: -90.00 deg Angle2 : -45.00 deg : 6.00 m Barrier angle1

Barrier height

Barrier receiver distance : 44.00 / 44.00 m

Source elevation : 76.51 m Receiver elevation : 78.34 m Barrier elevation : 78.00 m Reference angle 0.00

Results segment # 1: Klondike (day)

Source height = 1.50 m

Barrier height for grazing incidence ______

Source ! Receiver ! Barrier ! Elevation of Height (m) ! Height (m) ! Barrier Top (m) ______ 1.50 ! 10.50 ! 3.30 ! 81.30

ROAD (0.00 + 45.34 + 53.48) = 54.10 dBA

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq ______ -90 -45 0.00 65.75 0.00 -6.25 -6.02 0.00 0.00 -8.15 45.34-45 0 0.00 65.75 0.00 -6.25 -6.02 0.00 0.00 0.00 53.48

Segment Leq: 54.10 dBA

Total Leq All Segments: 54.10 dBA

Results segment # 1: Klondike (night)

Source height = 1.50 m

Barrier height for grazing incidence $% \left(\frac{1}{2}\right) =\frac{1}{2}\left(\frac{1}{2}\right)$

ROAD (0.00 + 37.74 + 45.89) = 46.51 dBA
Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq
-90 -45 0.00 58.16 0.00 -6.25 -6.02 0.00 0.00 -8.15 37.74
-45 0 0.00 58.16 0.00 -6.25 -6.02 0.00 0.00 45.89

Segment Leq: 46.51 dBA

Total Leq All Segments: 46.51 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 54.10 (NIGHT): 46.51

STAMSON 5.0 NORMAL REPORT Date: 10-05-2021 16:11:44 MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r4.te Time Period: Day/Night 16/8 hours

Description: POW R4

Road data, segment # 1: Klondike (day/night) ______

Car traffic volume : 6477/563 veh/TimePeriod * Medium truck volume : 515/45 veh/TimePeriod *
Heavy truck volume : 368/32 veh/TimePeriod *

Posted speed limit : 50 km/h

Road gradient :

: 0 %
: 1 (Typical asphalt or concrete) Road pavement

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 8000 Percentage of Annual Growth : 0.00 : 0.00 Number of Years of Growth Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: Klondike (day/night) _____

Angle1 Angle2 : 0.00 deg 90.00 deg Wood depth : 0 (No woods No of house rows : 0 / 0 Surface : 2 (Reflective (No woods.)

(Reflective ground surface)

Receiver source distance : 89.00 / 89.00 m Receiver height : 1.50 / 1.50 $\,$ m $\,$

: 1 Topography (Flat/gentle slope; no barrier)

Reference angle : 0.00

Results segment # 1: Klondike (day) _____

Source height = 1.50 m

ROAD (0.00 + 55.01 + 0.00) = 55.01 dBA

Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq 0 90 0.00 65.75 0.00 -7.73 -3.01 0.00 0.00 0.00 55.01 ______

Segment Leq: 55.01 dBA

Total Leq All Segments: 55.01 dBA

Results segment # 1: Klondike (night)

Source height = 1.50 m

ROAD (0.00 + 47.41 + 0.00) = 47.41 dBA Angle1 Angle2 Alpha RefLeq P.Adj D.Adj F.Adj W.Adj H.Adj B.Adj SubLeq 0 90 0.00 58.16 0.00 -7.73 -3.01 0.00 0.00 0.00 47.41

Segment Leq: 47.41 dBA

Total Leq All Segments: 47.41 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 55.01

(NIGHT): 47.41

Klο	ndike	Road -	- Block	10

APPENDIX B

117034-GR (Grading Plan)

