GENERAL NOTES:

- 1. COORDINATE AND SCHEDULE ALL WORK WITH OTHER TRADES AND CONTRACTORS.
- 2. DETERMINE THE EXACT LOCATION, SIZE, MATERIAL AND ELEVATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION. PROTECT AND ASSUME RESPONSIBILITY FOR ALL EXISTING UTILITIES WHETHER OR NOT SHOWN ON THIS DRAWING.
- 3. OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE CITY OF OTTAWA BEFORE COMMENCING CONSTRUCTION. 4. BEFORE COMMENCING CONSTRUCTION OBTAIN AND PROVIDE PROOF OF COMPREHENSIVE, ALL RISK AND OPERATIONAL LIABILITY INSURANCE FOR \$5,000,000.00. INSURANCE POLICY TO NAME OWNERS, ENGINEERS AND ARCHITECTS AS CO-INSURED.
- 5. COMPLETE ALL WORKS IN ACCORDANCE WITH THE MOST CURRENT CITY OF OTTAWA STANDARDS AND SPECIFICATIONS USING THE CURRENT GUIDELINES, BYLAWS AND STANDARDS INCLUDING MATERIALS OF CONSTRUCTION, DISINFECTION AND ALL RELEVANT REFERENCES TO OPSS, OPSD & AWWA GUIDELINES - ALL CURRENT VERSIONS AND 'AS AMENDED'.
- 6. RESTORE ALL DISTURBED AREAS ON-SITE AND OFF-SITE, INCLUDING TRENCHES AND SURFACES ON PUBLIC ROAD ALLOWANCES TO EXISTING CONDITIONS OR BETTER TO THE SATISFACTION OF THE CITY OF OTTAWA AND ENGINEER.
- REMOVE FROM SITE ALL EXCESS EXCAVATED MATERIAL, ORGANIC MATERIAL AND DEBRIS UNLESS OTHERWISE INSTRUCTED BY ENGINEER. EXCAVATE AND REMOVE FROM SITE ANY CONTAMINATED MATERIAL. ALL CONTAMINATED MATERIAL SHALL BE DISPOSED OF AT A LICENSED LANDFILL FACILITY. 8. ALL ELEVATIONS ARE GEODETIC.
- 9. REFER TO THE GEOTECHNICAL INVESTIGATION REPORT (NO. PG4811-1, REV. 1, DATED MAY 31, 2021) PREPARED BY PATERSON GROUP INC., FOR SUBSURFACE CONDITIONS, CONSTRUCTION RECOMMENDATIONS, AND GEOTECHNICAL INSPECTION REQUIREMENTS. THE GEOTECHNICAL CONSULTANT IS TO REVIEW ON-SITE CONDITIONS AFTER EXCAVATION PRIOR TO PLACEMENT OF THE GRANULAR MATERIAL
- 10. REFER TO ARCHITECT'S AND LANDSCAPE ARCHITECT'S DRAWINGS FOR BUILDING AND HARD SURFACED AREAS AND DIMENSIONS.
- 11. REFER TO THE 'DEVELOPMENT SERVICING STUDY AND STORMWATER MANAGEMENT REPORT' (R-2020-059) PREPARED BY NOVATECH. 12. SAW CUT AND KEY GRIND ASPHALT AT ALL ROAD CUTS AND ASPHALT TIE IN POINTS AS PER CITY OF OTTAWA STANDARDS
- 13. PROVIDE LINE/PARKING PAINTING.
- 14. CONTRACTOR TO PROVIDE THE CONSULTANT WITH A SERVICING PLAN OF 119171-GP INDICATING ALL SERVICING AS-BUILT INFORMATION SHOWN ON THE SERVICING PLAN. AS-BUILT INFORMATION MUST INCLUDE: PIPE MATERIAL, SIZES, LENGTHS, SLOPES, INVERT AND T/G ELEVATIONS, STRUCTURE LOCATIONS, VALVE AND HYDRANT LOCATIONS, T/WM ELEVATIONS AND ANY ALIGNMENT CHANGES, ETC.

SEWER NOTES

1. SUPPLY AND CONSTRUCT ALL SEWERS AND APPURTENANCES IN ACCORDANCE WITH THE MOST CURRENT CITY OF OTTAWA STANDARDS AND SPECIFICATIONS - ALL CURRENT VERSIONS AND 'AS AMENDED'.

REFERENCE

CITY OF OTTAWA

OPSD OPSD OPSD

OPSD

OPSD


	OTTAWA STANDANDS AND SPECIFICATIONS - ALL	CONNENT VERSIONS AND AS
2.	SPECIFICATIONS:	
	ITEM_	SPEC. No.
	CATCHBASIN (600x600mm)	705.010
	STORM / SANITARY MANHOLE (1200mmØ)	701.010
	STORM / CATCHBASIN MANHOLE (1800mmØ)	701.012
	CB, FRAME & COVER	400.020
	STORM / SANITARY MH FRAME & COVER	401.010
	WATERTIGHT MH FRAME AND COVER	401.030
	SEWER TRENCH	S6

- SANITARY / STORM SEWER / CB LEAD PVC DR 35 STORM SUPER-PIPE (1.0m DIAMETER AND OVER) CONCRETE 65-D
- THE WEEPING TILE SERVICE SHALL BE EQUIPPED WITH A BACKFLOW PREVENTION DEVICE AS PER THE CITY OF OTTAWA STANDARD DETAIL S18, AS INDICATED ON THE PLAN 119171-GP.
- 4. INSULATE ALL PIPES (SAN/STM) THAT HAVE LESS THAN 1.5m COVER WITH HI-40 INSULATION PER INSULATION DETAIL FOR SHALLOW SEWERS. PROVIDE 150mm CLEARANCE BETWEEN PIPE AND INSULATION.
- 5. SERVICES ARE TO BE CONSTRUCTED TO 1.0m FROM FACE OF BUILDING AT A MINIMUM SLOPE OF 1.0%.
- 6. PIPE BEDDING, COVER AND BACKFILL ARE TO BE COMPACTED TO AT LEAST 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY. THE USE OF CLEAR CRUSHED STONE AS A BEDDING LAYER SHALL NOT BE PERMITTED.
- 7. FLEXIBLE CONNECTIONS ARE REQUIRED FOR CONNECTING PIPES TO MANHOLES (FOR EXAMPLE KOR-N-SEAL, PSX: POSITIVE SEAL AND DURASEAL). THE CONCRETE CRADLE FOR THE PIPE CAN BE ELIMINATED.
- THE OWNER SHALL REQUIRE THAT THE SITE SERVICING CONTRACTOR PERFORM FIELD TESTS FOR QUALITY CONTROL OF ALL SANITARY SEWERS. LEAKAGE TESTING SHALL BE COMPLETED IN ACCORDANCE WITH OPSS 410.07.16, 410.07.16.04 AND 407.07.24. DYE TESTING IS TO BE COMPLETED ON ALL SANITARY SERVICES TO CONFIRM PROPER CONNECTION TO THE SANITARY SEWER MAIN. THE FIELD TESTS SHALL BE PERFORMED IN THE PRESENCE OF A CERTIFIED PROFESSIONAL ENGINEER WHO SHALL SUBMIT A CERTIFIED COPY OF THE TEST RESULTS
- TYPICAL STORM MANHOLES AND CATCHBASIN MANHOLES ARE TO HAVE 300mm SUMPS UNLESS OTHERWISE INDICATED. ALL CATCHBASINS ARE TO HAVE 600mm SUMPS UNLESS OTHERWISE INDICATED.
- 10. ALL CATCHBASINS, MANHOLES AND/OR CATCHBASIN MANHOLES THAT ARE TO HAVE ICD'S INSTALLED WITHIN THEM ARE TO HAVE 600mm SUMPS.
- 11. ALL WEEPING TILE CONNECTIONS TO BE MADE TO THE PROPOSED STORM SEWER SYSTEM DOWNSTREAM OF ANY INLET CONTROL DEVICES.
- 12. THE CONTRACTOR IS TO TELEVISE (CCTV) ALL PROPOSED SEWERS, 200mmØ OR GREATER PRIOR TO BASE COURSE ASPHALT, UPON COMPLETION OF CONTRACT, THE CONTRACTOR IS RESPONSIBLE TO FLUSH AND CLEAN ALL SEWERS & PPURTENANCES. PROVIDE A COPY OF ALL CCTV INSPECTION REPORTS TO THE ENGINEER FOR REVIEW

GRADING NOTES:

- ALL TOPSOIL, ORGANIC OR DELETERIOUS MATERIAL MUST BE ENTIRELY REMOVED FROM BENEATH THE PROPOSED PAVED AREAS AS DIRECTED BY THE SITE ENGINEER OR GEOTECHNICAL ENGINEER
- EXPOSED SUBGRADES IN PROPOSED PAVED AREAS SHOULD BE PROOF ROLLED WITH A LARGE STEEL DRUM ROLLER AND INSPECTED BY THE GEOTECHNICAL ENGINEER PRIOR TO THE PLACEMENT OF GRANULARS. ANY SOFT AREAS EVIDENT FROM THE PROOF ROLLING SHOULD BE SUB-EXCAVATED AND REPLACED WITH SUITABLE
- MATERIAL THAT IS FROST COMPATIBLE WITH THE EXISTING SOILS AS RECOMMENDED BY THE GEOTECHNICAL ENGINEER. 4. THE GRANULAR BASE SHOULD BE COMPACTED TO AT LEAST 98% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE. ANY ADDITIONAL GRANULAR FILL USED BELOW THE PROPOSED PAVEMENT SHOULD BE COMPACTED TO AT LEAST
- 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY VALUE. 5. MINIMUM OF 2% GRADE FOR ALL GRASS AREAS UNLESS OTHERWISE NOTED.
- 6. MAXIMUM TERRACING GRADE TO BE 3:1 UNLESS OTHERWISE NOTED.
- 7. ALL GRADES BY CURBS ARE EDGE OF PAVEMENT GRADES UNLESS OTHERWISE INDICATED.
- 8. ALL CURBS SHALL BE BARRIER CURB (150mm) UNLESS OTHERWISE NOTED AND CONSTRUCTED AS PER CITY OF OTTAWA STANDARDS (SC1.1).
- 9. REFER TO LANDSCAPE PLAN FOR PLANTING AND OTHER LANDSCAPE FEATURE DETAILS. 10. CONTRACTOR TO PROVIDE THE CONSULTANT WITH A GRADING PLAN INDICATING AS-BUILT ELEVATIONS OF ALL DESIGN GRADES SHOWN ON PLAN 119171-GR.

PAVEMENT STRUCTURES



THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN. THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

EROSION AND SEDIMENT CONTROL NOTES THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES, TO PROVIDE FOR PROTECTION OF THE AREA DRAINAGE SYSTEM AND THE RECEIVING WATERCOURSE. DURING CONSTRUCTION ACTIVITIES. THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE REGULATORY AGENCY.

- SHOULD INCLUDE AS A MINIMUM THOSE MEASURES INDICATED ON THE PLAN.
- 2. EROSION AND SEDIMENT CONTROL MEASURES WILL BE IMPLEMENTED DURING CONSTRUCTION IN ACCORDANCE WITH THE "GUIDELINES SHALL BE SOLELY RESPONSIBLE FOR MEETING ALL REGULATORY AGENCY REQUIREMENTS.
- AS POSSIBLE AND PROTECT EXPOSED SLOPES WITH NATURAL OR SYNTHETIC MULCHES.
- DAYS.

- REGULATORY AGENCY.
- AND EXPOSED SOILS. USE CHEMICAL DUST SUPPRESSANTS ONLY WHERE NECESSARY ON PROBLEM AREAS.

WATERMAIN NOTES

- WATER SYSTEM SHALL BE PERFORMED BY THE CONTRACTOR IN THE PRESENCE CITY OF OTTAWA FORCES. 2. SPECIFICATIONS:
- WATERMAIN TRENCHING HYDRANT INSTALLATION THERMAL INSULATION IN SHALLOW TRENCHES THERMAL INSULATION AT OPEN STRUCTURES W23 VALVE BOX ASSEMBLY W24 WATERMAIN CROSSING BELOW SEWER W25 WATERMAIN CROSSING OVER SEWER W25 2 DISTRICT METERING CHAMBER W3.3
- WATERMAIN MATERIAL PARK WATER SERVICE MATERIAL
- 3. WATERMAIN SHALL BE MINIMUM 2.4m DEPTH BELOW GRADE UNLESS OTHERWISE INDICATED.

Erosion	and Sedime	ent Contro	l Responsibi	ilities:					
					During Construction		After Construction Prio	r to Final Acceptance	After Final Acceptance
	ESC Measure	Symbol	Specification	Installation Responsibility	Inspection/Maintenance Responsibility	Inspection Frequency	Approval to Remove	Removal Responsibility	Inspection/Maintenanc Responsibility
	Silt Fence (Light Duty)	, ,	OPSD 219.110	Developer's Contractor	Developer's Contractor	Weekly (as a minimum)	Consultant	Developer's Contractor	N/A
	Filter Bags	Location as Indicated in ESC Note #3	Erosion and Sediment Control Notes	Developer's Contractor	Developer's Contractor	Weekly (as a minimum)	Consultant	Developer's Contractor	N/A
	Mud Mat	ММ	Drawing Details	Developer's Contractor	Developer's Contractor	Weekly (as a minimum)	Developer's Contractor	Developer's Contractor	N/A
Temporary Measures	Dust Control	Location as Required Around Site	Erosion and Sediment Control Notes	Developer's Contractor	Developer's Contractor	Weekly (as a minimum)	Consultant	Developer's Contractor	N/A
	Stabilized Material Stockpiling	Location as Required by Contractor	Erosion and Sediment Control Notes	Developer's Contractor	Developer's Contractor	Weekly (as a minimum)	Developer's Contractor	Developer's Contractor	N/A
	Sediment Basin (for flows being pumped out of excavations)	Location as Required by Contractor		Developer's Contractor	Developer's Contractor	After Every Rainstorm	Developer's Contractor	Developer's Contractor	N/A

	CRITICAL SEWER PIPE CROSSING TABLE						
CROSSING	LOWER PIPE	HIGHER PIPE	CLEARANCE	SURFACE ELEVATION			
A	375mmØ STM OBV=60.03	250mmØ SAN INV=61.51	± 1.5m	64.58 m			
B	300mmØ STM OBV=60.86	200mmØ SAN INV=61.87	± 1.0m	64.93 m			
©	1050mmØ STM OBV=61.05	150mmØ U/S WM=61.45	± 0.3m	63.67 m			
D	250mmØ SAN OBV=60.95	150mmØ U/S WM=61.45	± 0.5m	63.69 m			
E	1050mmØ STM OBV=63.45	150mmØ U/S WM=64.25	± 0.7m	66.85 m			
Ē	250mmØ SAN OBV=63.30	150mmØ U/S WM=64.25	± 0.95m	66.80 m			
• SEE 110171	-GP PLAN FOR SEWER CR	OSSING LOCATIONS & and					

1. ALL EROSION AND SEDIMENT CONTROLS ARE TO BE INSTALLED TO THE SATISFACTION OF THE ENGINEER AND THE CITY OF OTTAWA. THEY ARE TO BE APPROPRIATE TO THE SITE CONDITIONS, PRIOR TO UNDERTAKING ANY SITE ALTERATIONS (FILLING, GRADING, REMOVAL

OF VEGETATION, ETC.) AND DURING ALL PHASES OF SITE PREPARATION AND CONSTRUCTION. THESE PRACTICES ARE TO BE IMPLEMENTED IN ACCORDANCE WITH THE CURRENT BEST MANAGEMENT PRACTICES FOR EROSION AND SEDIMENT CONTROL AND

ON EROSION AND SEDIMENT CONTROL FOR URBAN CONSTRUCTION SITES" (GOVERNMENT OF ONTARIO, MAY 1987). THE CONTRACTOR

3. TO PREVENT SURFACE EROSION FROM ENTERING ANY STORM SEWER SYSTEM DURING CONSTRUCTION, FILTER BAGS WILL BE PLACED UNDER GRATES OF NEARBY CATCHBASINS AND STRUCTURES. A LIGHT DUTY SILT FENCE BARRIER WILL ALSO BE INSTALLED AROUND THE CONSTRUCTION AREA (WHERE APPLICABLE). THESE CONTROL MEASURES WILL REMAIN IN PLACE UNTIL CONSTRUCTION IS COMPLETE.

4. TO LIMIT EROSION: MINIMIZE THE AMOUNT OF EXPOSED SOILS AT ANY GIVEN TIME, RE-VEGETATE EXPOSED AREAS AND SLOPES AS SOON 5. FOR MATERIAL STOCKPILING: MINIMIZE THE AMOUNT OF EXPOSED MATERIALS AT ANY GIVEN TIME; APPLY TEMPORARY SEEDING, TARPS,

COMPACTION AND/OR SURFACE ROUGHENING AS REQUIRED TO STABILIZE STOCKPILED MATERIALS THAT WILL NOT BE USED WITHIN 14

6. THE SEDIMENT CONTROL MEASURES SHALL ONLY BE REMOVED WHEN, IN THE OPINION OF THE ENGINEER, THE MEASURES ARE NO LONGER REQUIRED. NO CONTROL MEASURES MAY BE PERMANENTLY REMOVED WITHOUT PRIOR AUTHORIZATION FROM THE ENGINEER. 7. THE CONTRACTOR SHALL IMMEDIATELY REPORT TO THE ENGINEER ANY ACCIDENTAL DISCHARGES OF SEDIMENT MATERIAL INTO ANY

STORM SEWER SYSTEM. APPROPRIATE RESPONSE MEASURES, INCLUDING ANY REPAIRS TO EXISTING CONTROL MEASURES OR THE IMPLEMENTATION OF ADDITIONAL CONTROL MEASURES, SHALL BE CARRIED OUT BY THE CONTRACTOR WITHOUT DELAY.

8. THE CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES, TO PROVIDE FOR PROTECTION OF THE AREA DRAINAGE SYSTEM AND THE RECEIVING WATERCOURSE, DURING CONSTRUCTION ACTIVITIES, THE CONTRACTOR ACKNOWLEDGES THAT FAILURE TO IMPLEMENT APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES MAY BE SUBJECT TO PENALTIES IMPOSED BY ANY APPLICABLE

9. ROADWAYS ARE TO BE SWEPT AS REQUIRED OR AS DIRECTED BY THE ENGINEER AND/OR THE MUNICIPALITY.

10. THE CONTRACTOR SHALL ENSURE PROPER DUST CONTROL IS PROVIDED WITH THE APPLICATION OF WATER (AND IF REQUIRED, CALCIUM CHLORIDE) DURING DRY PERIODS. MONITOR DUST LEVELS DURING SITE PREPARATION/EXCAVATION. AND CONSTRUCTION ACTIVITIES. AND WHEN DUST LEVELS BECOME VISUALLY APPARENT SPRAY WATER TO MINIMIZE THE RELEASE OF DUST FROM GRAVEL, PAVED AREAS

1. SUPPLY AND CONSTRUCT ALL WATERMAINS AND APPURTENANCES IN ACCORDANCE WITH THE CITY OF OTTAWA STANDARDS AND SPECIFICATIONS - ALL CURRENT VERSIONS AND 'AS AMENDED'. EXCAVATION, INSTALLATION, BACKFILL AND RESTORATION OF ALL WATERMAINS BY THE CONTRACTOR. CONNECTIONS AND SHUT-OFFS AT THE MAIN BY CITY OF OTTAWA FORCES. CHLORINATION OF THE

No.	REFERENCE
	CITY OF OTTAWA
2	CITY OF OTTAWA
	CITY OF OTTAWA

PEX / TYPE 'K' SOFT COPPER

PVC DR 18

4. PROVIDE MINIMUM 0.5m CLEARANCE BETWEEN OUTSIDE OF PIPES AT ALL CROSSINGS, WHERE POSSIBLE UNLESS OTHERWISE INDICATED. 5. WATER SERVICE IS TO BE CONSTRUCTED TO WITHIN 1.0m OF FOUNDATION WALL AND CAPPED, UNLESS OTHERWISE INDICATED.

STATION	SURFACE ELEVATION	T/WM ELEVATION	COMMENTS
4+000	69.93±	67.50 *	TEE CONNECTION TO NEW 300mmØ WATERMAIN EXTENSION
4+002.8	70.10	67.45	22.5° VERTICAL BEND
4+005.4	70.12	66.34	22.5° VERTICAL BEND
4+006.7	70.05	66.34 ***	CROSS BELOW EX.600mmØ WM [U/S=67.34m] (±1.0m CLEARANCE)
4+008.0	69.90	66.34	22.5° VERTICAL BEND
4+010.4	69.75	67.35	22.5° VERTICAL BEND
4+018.0	69,30	66,90	22.5° HORIZONTAL BEND
4+020.0	69.29	66.89	CROSS BELOW EX. BELL DUCT (±1.2m CLEARANCE)
4+020.8	69.28	66.88	CROSS BELOW EX. BELL DUCT (±1.5m CLEARANCE)
4+021.8	69.27	66.87	CROSS BELOW EX. COMMS DUCT (±1.5m CLEARANCE)
4+022.1	69.27	66.87	22.5° HORIZONTAL BEND
4+023.1	69,26	66.86	250mmØ VALVE & VALVE BOX @ PROPERTY LINE
4+028.2	69.05	66.65	250 x 250 x 250 TEE
4+050	68.05	65.65	
4+030	67.15	64.75	
4+095.8	66.25	63.85	150 x 250 x 250 BUILDING SERVICE TEE
4+097.1	66.19	63.79	
4+098.3	66.13	63.73	150 x 250 x 250 BUILDING SERVICE TEE
4+119.5	65.15	61.64 ***	CROSS BELOW 250mmØ STM [Inv=63.03m] (±1.4m CLEARANCE)
4+121.0	65.10	61.49 ***	CROSS BELOW 200mmØ SAN [Inv=61.99m] (±0.5m CLEARANCE)
4+125	64.93	61.80	
4+132.9	64.80	62.40	22.5° HORIZONTAL BEND
4+136.6	64.70	62.30 ***	CROSS ABOVE 200mmØ STM [Obv=60.77m] (±1.3m CLEARANCE)
4+140.6	64.56	62.16	22.5° HORIZONTAL BEND
4+150	64.10	61.70	
4+164.1	63.78	61.68 **	45° HORIZONTAL BEND
4+165.5	63.77	61.67 **	45° HORIZONTAL BEND
4+166.9	63.74	61.64 **	150mmØ HYDRANT TEE
4+168.5	63.73	61.63 **	45° HORIZONTAL BEND
4+169.9	63.71	61.61 **	45° HORIZONTAL BEND
4+171.4	63.70	61.60 **	150 x 250 x 250 BUILDING SERVICE TEE
4+172.6	63.69	61.59 **	250mmØ VALVE & VALVE BOX
4+173.9	63.68	61.58 **	150 x 250 x 250 BUILDING SERVICE TEE
4+175 <u>.</u> 5	63.66	61.57 **	INSULATE IN PROXIMITY TO OPEN STRUCTURE
4+197.2	64.48	62.08	250 x 250 x 250 TEE (5+000)
4+199.8	64.50	62.15 ***	CROSS ABOVE 200mmØ STM [Obv=60.70m] (±1.2m CLEARANCE)
4+203.3	64.65	62.20 **	250 x 250 x 250 TEE (5+102.5)
4+204.8	64.68	62.18 **	250mmØ VALVE & VALVE BOX
4+212.5	64.93	61.40 ***	CROSS BELOW 200mmØ SAN [Inv=61.90m] (±0.5m CLEARANCE)
4+214.0	64.96	61.52 ***	CROSS ABOVE 250mmØ STM [Obv=60.87m] (±0.4m CLEARANCE)
4+225	65.43	62.43	/
4+239.5	66.12	63.72	150mmØ HYDRANT TEE
4+242.5	66.17	63.77 **	INSULATE IN PROXIMITY TO OPEN STRUCTURE
4+252.0	66.70	64.30 ***	CROSS ABOVE 200mmØ STM [Obv=62.92m] (±1.1m CLEARANCE)
4+254.1	66.80	64.40	150 x 250 x 250 BUILDING SERVICE TEE
4+255.4	66.85	64.45	250mmØ VALVE & VALVE BOX
4+256.6	66.90	64.50	150 x 250 x 250 BUILDING SERVICE TEE
4+262.6	67.30	64.90	22.5° HORIZONTAL BEND
4+268.6	67.50	65.10	22.5° HORIZONTAL BEND
4+200.0	67.80	65.40	
4+275			
	68.75	66.35	
4+305.7	69.05	66.65	250 x 250 x 250 TEE
4+308.7	69.15	66.75	
4+313.3	69.35	66.95	250mmØ VALVE & VALVE BOX @ PROPERTY LINE
4+317.5	69.48	67.08	50 x 250 x 250 PARK SERVICE TEE
4+319.5	69.57	67.17	45° HORIZONTAL BEND
4+323.9	69.87	67.19	CROSS BELOW EX. COMMS DUCT (±1.5m CLEARANCE)
4+325.3	69.90	67.20	CROSS BELOW EX. BELL DUCTS (±1.6m CLEARANCE)
4.000	1 00.00		

PROPOSED 250mmØ WATERMAIN TABLE - EAST / WEST SITE LOOP

70.02 67.25± * CONNECTION TO EX.150mmØ WM T.V.S. with 250x150 REDUCER 4+328.6 * CONNECTIONS TO EXISTING 150mmØ and NEW 300mmØ WATERMAINS. EXACT ELEVATIONS TO BE FIELD DETERMINED. ****** PROVIDE THERMAL INSULATION AS PER CITY OF OTTAWA DETAILS W22 IN SHALLOW TRENCHES WHERE COVER IS LESS THAN 2.4m AND/OR W23 ADJACENT TO OPEN STRUCTURES. *** PIPE CROSSINGS WITH WATERMAINS ARE TO BE IN ACCORDANCE WITH CITY STANDARDS W25 AND

22.5° HORIZONTAL BEND

4+326.1

69.93

W25.2 TO AVOID CONFLICTS, WHERE POSSIBLE.

67.23

STATION	SURFACE ELEVATION	T/WM ELEVATION	COMMENTS
5+000	64.48	62.08	250 x 250 x 250 TEE (4+197.2)
5+001.0	64.46	62.10 **	250mmØ VALVE & VALVE BOX
5+002.5	64.45	** 62.10 ***	CROSS ABOVE 300mmØ STM [Obv=60.10m] (±1.75m CLEARANCE)
5+004.5	64.45	** 62.15 ***	CROSS ABOVE 250mmØ SAN [Obv=61.62m] (±0.3m CLEARANCE)
5+005.6	64.45	62.15 **	22.5° HORIZONTAL BEND
5+008.0	64.43	62.03	22.5° HORIZONTAL BEND
5+011.0	64.48	62.08	150mmØ HYDRANT TEE
5+025	64.05	61.65 **	
5+040.4	63.72	61.32 ***	CROSS BELOW 200mmØ STM [Inv=61.91m] (±0.6m CLEARANCE)
5+048.3	63.76	61.26	45° HORIZONTAL BEND
5+049.3	63.75	61.25	150mmØ HYDRANT TEE
5+049.7	63.75	61.25	45° HORIZONTAL BEND
5+050.6	63.60	61.20	250mmØ VALVE & VALVE BOX
5+051.4	63.60	61.20 ***	CROSS ABOVE 375mmØ STM [Obv=59.58m] (±1.35m CLEARANCE)
5+052.9	63.60	61.20	45° HORIZONTAL BEND
5+054.3	63.58	61.18	45° HORIZONTAL BEND
5+062.3	63.53	61.13 **	INSULATE IN PROXIMITY TO OPEN STRUCTURE
5+075	63.88	61.48	
5+078.8	64.08	61.68 ***	CROSS ABOVE 200mmØ STM [Obv=59.83m] (±1.6m CLEARANCE)
5+091.9	64.50	62.10	150 x 250 x 250 BUILDING SERVICE TEE
5+093.2	64.55	62.15	250mmØ VALVE & VALVE BOX
5+094.4	64.60	62.20	150 x 250 x 250 BUILDING SERVICE TEE
5+098.0	64.66	62.32 ***	CROSS ABOVE 250mmØ SAN [Obv=61.82m] (±0.25m CLEARANCE)
5+100.0	64.66	62.25 ***	CROSS ABOVE 300mmØ STM [Obv=60.55m] (±1.45m CLEARANCE)
5+102.5	64.65	62.20	250 x 250 x 250 TEE (4+203.3)

** PROVIDE THERMAL INSULATION AS PER CITY OF OTTAWA DETAILS W22 IN SHALLOW TRENCHES WHERE COVER IS LESS THAN 2.4m AND/OR W23 ADJACENT TO OPEN STRUCTURES. *** PIPE CROSSINGS WITH WATERMAINS ARE TO BE IN ACCORDANCE WITH CITY STANDARDS W25 AND W25.2 TO AVOID CONFLICTS, WHERE POSSIBLE.

SID CONFLICTS, WHERE FOSSIBLE.			
		SWM TANK 8 SECTIONS NOT TO SCALE	
		(OUTSIDE TOP (INSIDE TOP	
	▼1:100yr = 64.40m		
	TLET PIPE INSIDE BOTTON	(INSIDE BOTTOM (UNDERSIDE	

OWNER INFORMATION 2 ROBINSON AVENUE LIMITED PARTNERSHIP 88 ALBERT STREET OTTAWA, ONTARIO, K1P 5E9 CONTACT: MR. KIERAN WAUGH PHONE: (416) 903-1377 EMAIL: kwaugh@placedoree.com

(OUTSIDE TOP OF TANK) 63.55m


(INSIDE TOP OF TANK) 63.35m

(INSIDE BOTTOM OF TANK) 60.70m

(UNDERSIDE OF TANK) 60.50m


				SCALE
				NOT TO SCALE
4	RE-ISSUED FOR SITE PLAN APPROVAL	JAN 10/23	FST	
3	RE-ISSUED FOR SITE PLAN APPROVAL	OCT 07/22	FST	
2	REVISED PER CITY COMMENTS / UPDATED SITE PLAN	MAR 30/21	FST	
1	ISSUED FOR SITE PLAN APPROVAL	NOV 15/21	FST	
No.	REVISION	DATE	BY	








DESIC EVE






DES






	INLET	CONTROL		DATA TAB	LE: AREA	A-2.1 (TAN	K 1)	
SIGN ENT	ICD TYPE (PLUG TYPE)	DIAMETER OF OUTLET PIPE (mm)	PEAK DESIGN FLOW (L/s)	12 PEAK DESIGN FLOW (L/s)	DESIGN HEAD (m)	WATER ELEVATION (m)	VOLUME (m ³)	AVAILABLE STORAGE
YR YR	IPEX TEMPEST LMF	200mmØ PVC	12.0 14.0	6.0 7.0	0.75 0.80	61.15 61.20	17.9 25.9	> 65 m ³
) YR	CUSTOM		16.5	8.3	1.50	61.90	60.8	
	INLET	CONTROL		DATA TAB	LE: AREA	A-2.2 (TAN	K 2)	
IGN ENT	ICD TYPE (PLUG TYPE)	DIAMETER OF OUTLET PIPE (mm)	PEAK DESIGN FLOW (L/s)	¹ / ₂ PEAK DESIGN FLOW (L/s)	DESIGN HEAD (m)	WATER ELEVATION (m)	VOLUME (m ³)	AVAILABLE STORAGE
YR YR) YR	IPEX TEMPEST LMF MODEL 100	200mmØ PVC	7.5 9.5 12.0	3.8 4.8 6.0	0.72 1.15 1.80	61.12 61.55 62.20	13.8 19.2 43.3	> 45 m ³
,			12.0	0.0	1.80	02.20	40.0	
	INLET	-		DATA TAB	LE: AREA	A-2.3 (TAN	K 3)	
IGN NT	ICD TYPE (PLUG TYPE)	DIAMETER OF OUTLET PIPE (mm)	PEAK DESIGN FLOW (L/s)	¹ 2 PEAK DESIGN FLOW (L/s)	DESIGN HEAD (m)	WATER ELEVATION (m)	VOLUME (m ³)	AVAILABLE STORAGE
YR YR	IPEX TEMPEST LMF	200mmØ PVC	3.5 4.5	1.8 2.3	0.30 0.50	60.40 60.60	24.7 33.5	> 70 m ³
) YR	MODEL 85		6.0	3.0	0.85	60.95	69.9	
	INLET	CONTROL		DATA TAB	LE: AREA	A-3.1 (TAN	K 4)	
IGN NT	ICD TYPE (PLUG TYPE)	DIAMETER OF OUTLET PIPE (mm)	PEAK DESIGN FLOW (L/s)	12 PEAK DESIGN FLOW (L/s)	DESIGN HEAD (m)	WATER ELEVATION (m)	VOLUME (m ³)	AVAILABLE STORAGE
YR			15.0	7.5	0.58	60.90	20.5	5 7 5 ³
YR) YR	TEMPEST MHF MODEL 'A'	200mmØ PVC	17.5 20.0	8.8 10.0	0.93 1.18	61.25 61.58	29.7 71.0	>75 m ³
	INLET				LE: AREA	A-3.2 (TAN	K 5)	
IGN NT	ICD TYPE (PLUG TYPE)	DIAMETER OF OUTLET PIPE (mm)	PEAK DESIGN FLOW (L/s)	¹ / ₂ PEAK DESIGN FLOW (L/s)	DESIGN HEAD (m)	WATER ELEVATION (m)	VOLUME (m ³)	AVAILABLE STORAGE
YR YR	IPEX TEMPEST LMF	200mmØ PVC	15.0 16.5	7.5 8.3	0.90 1.40	61.30 61.80	20.0 30.0	> 75 m ³
) YR	CUSTOM		18.0	9.0	2.00	62.40	71.7	
	INLET	CONTROL			E: AREA	A-4 (TANK 6	87)	
IGN		DIAMETER	PEAK	¹ ⁄ ₂ PEAK	DESIGN	WATER		AVAILABLE
NT YR	(PLUG TYPE)	OF OUTLET PIPE (mm)	DESIGN FLOW (L/s) 8.0	DESIGN FLOW (L/s) 4.0	HEAD (m)	ELEVATION (m)	(m ³)	STORAGE
YR	IPEX TEMPEST LMF	250mmØ PVC	9.7	4.9	0.68	61.46 61.78	28.9 40.4	91 m ³
) YR	CUSTOM		14.2	7.1	2.15	62.93	83.2	
	INLET	CONTROL		ATA TABL	E: AREA	A-5 (STM MI	H 08)	
IGN ENT	ICD TYPE (PLUG TYPE)	DIAMETER OF OUTLET PIPE (mm)	PEAK DESIGN FLOW (L/s)	¹ / ₂ PEAK DESIGN FLOW (L/s)	DESIGN HEAD (m)	WATER ELEVATION (m)	VOLUME (m ³)	AVAILABLE STORAGE
YR	IPEX		13.8	6.9	0.43	60.39	36.3	400 3
YR) YR	TEMPEST MHF CUSTOM	300mmØ PVC	17.5 36.0	8.8 18.0	0.69 2.90	60.65 62.86	50.1 96.1	106 m ³
				ΠΑΤΑ ΤΑΒ		A-6 (CBMH	05)	
		DIAMETER	PEAK	¹ ⁄ ₂ PEAK	DESIGN		VOLUME	AVAILABLE
IGN INT YR	(PLUG TYPE)	OF OUTLET PIPE (mm)	DESIGN FLOW (L/s) 9.0	DESIGN FLOW (L/s) 4.5	HEAD (m)	ELEVATION (m)	(m ³)	STORAGE
YR YR YR	IPEX TEMPEST LMF CUSTOM	300mmØ PVC	9.0 9.4 12.0	4.5 4.7 6.0	2.03 2.25 3.62	62.81 63.03 64.40	24.4 36.4 83.0	99 m ³
	h = DEPTH (W = D + 300	(1000 min.) OF INSULATION (mr PIPE (mm) R INSULAT THICKNI	n) H TION ESS	, 🎇 — — —	1000mm (min.) ACKFILL AS SPEC		50 L 300	
	1500-12	(mm)			ti INSULATIO	()		




NOT TO SCALE



FS

FS




BENCHMARK INFO:


CITY OF OTTAWA MONUMENT No. 2011-0127 LOCATED NEAR THE SOUTH-WEST CORNER OF THE INTERSECTION OF LEES AVENUE AND ROBINSON AVENUE. GEODETIC ELEVATION = 63.60m.

ALL FLEVATIONS ARE REFERRED TO THE CGVD28 GEODETIC DATUM, DERIVED FROM VERTICAL CONTROL MONUMENT NO. 3603 HAVING AN ELEVATION OF 76.959 METRES. BEARINGS ARE GRID. DERIVED FROM THE NORTHERLY LIMIT OF PART 1 ON PLAN 4R-1381 AND ARE REFERRED TO THE CENTRAL MERIDIAN OF MTM ZONE 9 (76°30' WEST LONGITUDE) NAD-83 (ORIGINAL)

THE EXISTING GRADES SHOWN ON THE PLANS ARE TAKEN DIRECTLY FROM TOPOGRAPHICAL SURVEY PLAN (Ref. # 21029-20 JRE Lt 7 PL 49 T F), PREPARED BY ANNIS, O'SULLIVAN, VOLLEBEKK SIGNED AND DATED AUGUST 14, 2020.

SURROUNDING BACKGROUND TOPO INFORMATION BEYOND THE LIMITS OF THE SITE SURVEY ARE SHOWN FROM CITY OF OTTAWA 1:1000 MAPPING FOR CONTEXT ONLY.





ALL PROJECT NOTES, DETAILS AND SPECIFICATIONS ARE TO MEET THE MOST CURRENT AND AMENDED VERSIONS OF THE CITY OF OTTAWA AND PROVINCIAL STANDARDS

N.T.S.

THIS PLAN IS TO BE READ IN CONJUNCTION WITH CIVIL

LOCATION **CITY OF OTTAWA** NOVATECH RESSH 320 LEES AVENUE (2 ROBINSON AVENUE) Cramini Im DRAWING NAME Engineers, Planners & Landscape Architects F.S. THAUVETTE **CIVIL NOTES, DETAILS & TABLES** Suite 200, 240 Michael Cowpland Drive 100041399 Ottawa, Ontario, Canada K2M 1P6 Jan 10, 2023 Telephone (613) 254-9643 Facsimile (613) 254-5867 Website www.novatech-eng.com

