


**ROADWAY TRAFFIC NOISE
FEASIBILITY ASSESSMENT**

50 The Driveway
Ottawa, Ontario

REPORT: GW21-200 – Traffic Noise



July 5, 2021

PREPARED FOR

Canadian Nurses Association

50 The Driveway
Ottawa, ON
K2P 1E2

PREPARED BY

Tanyon Matheson-Fitchett, B.Eng., Junior Environmental Scientist
Joshua Foster, P.Eng., Principal

EXECUTIVE SUMMARY

This report describes a traffic noise assessment undertaken in support of concurrent Official Plan Amendment (OPA) and Zoning Bylaw Amendment (ZBA) applications for a proposed residential development located at 50 The Driveway in Ottawa, Ontario. The proposed development is a nine-storey residential development for the Canadian Nurses Association. For the purposes of this study, the elevation facing Queen Elizabeth Driveway will be referred to as the north elevation. The major sources of traffic noise are Queen Elizabeth Driveway, Colonel By Drive, Nicholas Street, and the LRT Confederation Line. Figure 1 illustrates a complete site plan with surrounding context.

The assessment is based on (i) theoretical noise prediction methods that conform to the Ministry of the Environment, Conservation and Parks (MECP) and City of Ottawa requirements; (ii) noise level criteria as specified by the City of Ottawa's Environmental Noise Control Guidelines (ENCG); (iii) future vehicular traffic volumes based on the City of Ottawa's Official Plan roadway classifications; and (iv) architectural drawings prepared by Hobin Architecture Incorporated dated June 2021.

The results of the current analysis indicate that noise levels will range between 61 and 68 dBA during the daytime period (07:00-23:00) and between 58 and 61 dBA during the nighttime period (23:00-07:00). The highest noise level (68 dBA) occurs at the north façade, which is nearest and most exposed to Nicholas Street.

The noise levels predicted due to roadway traffic exceed the criteria listed in the ENCG for standard building components, and upgraded building components with a higher Sound Transmission Class (STC) rating will be required. Due to the limited information available at the time of the study, which was prepared for rezoning application, detailed STC calculations could not be performed at this time. A detailed review of the window and wall assemblies should be performed by a qualified engineer with expertise in acoustics during the detailed design stage of the building.

Results of the calculations also indicate that the development will require central air conditioning, or a similar ventilation system, which will allow occupants to keep windows closed and maintain a comfortable living environment. Warning Clauses will also be required be placed on all Lease, Purchase and Sale Agreements.



With respect to the outdoor amenity spaces, the following conclusions were made. Noise levels at the 3rd floor terrace and balconies on the 6th, 7th, 8th and 9th floor were found to exceed the ENCG criteria for Outdoor Living Areas (OLA). The ENCG dictates that noise levels in OLAs must not exceed 60 dBA, and should be targeted below 55 dBA as is technically and administratively feasible. Therefore, noise control measures must be investigated to mitigate noise to acceptable levels. As a general recommendation OLAs be positioned away from the roadway to reduce noise levels, however, these spaces are positioned to maintain view of the Rideau Canal to the north of the development. Therefore, OLA noise mitigation strategies should investigate the implementation of raised perimeter guards. OLA noise mitigation can be addressed during site plan control.

The building's proposed HVAC equipment has potential for noise impacts on surrounding buildings and the study building itself. Typically, noise levels can be controlled by judicious selection and placement of the equipment and the introduction of silencers or noise screens where needed. A stationary noise study will be performed once mechanical plans for the proposed building become available. This study will include recommendations for any noise control measures that may be necessary to ensure noise levels fall below ENCG limits.

The surrounding area was evaluated for sources of stationary noise impacting the proposed development. Rooftop air handling equipment atop the Embassy of Germany is expected to have minimal impact. Given the setback distance of approximately 35 metres and an enclosure surrounding the equipment, noise levels will be dominated by roadway traffic noise. No other stationary noise sources were identified, therefore, stationary noise impacts on the proposed development are expected to be insignificant.

A detailed roadway traffic noise study will be required at the time of site plan approval to determine specific noise control measures for the development.

TABLE OF CONTENTS

1. INTRODUCTION 1

2. TERMS OF REFERENCE 1

3. OBJECTIVES 2

4. METHODOLOGY..... 2

 4.1 Background.....2

 4.2 Roadway and LRT Traffic Noise3

 4.2.1 Criteria for Roadway and LRT Traffic Noise3

 4.2.2 Theoretical Roadway and LRT Noise Predictions4

 4.2.3 Roadway Traffic Volumes.....5

5. RESULTS AND DISCUSSION..... 6

 5.1 Roadway Traffic Noise Levels.....6

6. CONCLUSIONS AND RECOMMENDATIONS 7

FIGURES

APPENDICES

Appendix A – STAMSON 5.04 Input and Output Data and Supporting Information



1. INTRODUCTION

Gradient Wind Engineering Inc. (Gradient Wind) was retained by the Canadian Nurses Association to undertake a roadway traffic noise feasibility assessment in support of concurrent Official Plan Amendment (OPA) and Zoning Bylaw Amendment (ZBA) applications for a proposed residential development at 50 The Driveway in Ottawa, Ontario. This report summarizes the methodology, results, and recommendations related to the assessment of exterior and interior noise levels generated by local roadway traffic.

Our work is based on theoretical noise calculation methods conforming to the City of Ottawa¹ and Ministry of the Environment, Conservation and Parks (MECP)² guidelines. Noise calculations were based on architectural drawings prepared by Hobin Architecture Incorporated dated June 2021, with future traffic volumes corresponding to the City of Ottawa's Official Plan (OP) roadway classifications.


2. TERMS OF REFERENCE

The focus of this traffic noise assessment is a proposed development at 50 The Driveway in Ottawa, Ontario. The study site is located in the middle of a parcel of land bounded by Lewis Street to the west, Queen Elizabeth Driveway to the north, and existing low-rise dwellings to the south and east.

The proposed development comprises a 9-storey residential building rising approximately 30.4 meters (m) above the ground floor to the top of the main roof slab serving the mechanical penthouse. Above two levels of underground parking, the ground floor comprises a main residential entrance served by a vestibule at the northwest corner of building, which provides access to an interior lobby lounge, among other building services. Private residential suites are located along the south and east elevations, as well as within the northwest corner of the floorplate, while an interior amenity area is provided at the north elevation. An exterior lobby lounge is also provided at the north elevation, flanked by the main residential entrance to the west and the interior amenity area to the east. The parking entrance is provided at the southwest corner of the proposed development, providing access to two above grade parking levels. At Level 3, the building steps back from the northeast corner and rises with a uniform floorplate to Level 5.

¹ City of Ottawa Environmental Noise Control Guidelines, January 2016

² Ontario Ministry of the Environment and Climate Change – Environmental Noise Guidelines, Publication NPC-300, Queens Printer for Ontario, Toronto, 2013



At Levels 6 and 8, the floorplates step back from the east elevation to accommodate private terraces. A total of three penthouse suites are provided at Level 9, complete with balconies and terraces. Balconies that extend less than 4 metres from the façade do not require consideration as outdoor living areas (OLA) in this study. Outdoor living areas are considered on levels 3, 6, 7, 8 and 9.

The site is surrounded by low-rise dwellings with isolated mid-rise buildings from southeast clockwise to west-southwest, the dense downtown core consisting of mid-rise and high-rise buildings from the west-southwest clockwise to west-northwest, a mix of mid-rise and high-rise buildings from the west-northwest clockwise to north-northwest, and low-rise dwellings for the remaining compass directions. The subject site is situated approximately 62 m south of the Rideau Canal, which extends nominally east-to-west in the vicinity of the proposed development with a return to the south along the east side of the subject site.

The major sources of transportation noise are Queen Elizabeth Driveway, Colonel By Drive, Nicholas Street, and the LRT Confederation Line. Roadways beyond 200 metres of the study site are not included as sources influencing the study site as per ENCG Section 2.1. Figure 1 illustrates a complete site plan with surrounding context.

3. OBJECTIVES

The principal objectives of this study are to (i) calculate the future noise levels on the study buildings produced by local roadway traffic, and (ii) ensure that interior and exterior noise levels do not exceed the allowable limits specified by the City of Ottawa’s Environmental Noise Control Guidelines as outlined in Section 4.2 of this report.

4. METHODOLOGY

4.1 Background

Noise can be defined as any obtrusive sound. It is created at a source, transmitted through a medium, such as air, and intercepted by a receiver. Noise may be characterized in terms of the power of the source or the sound pressure at a specific distance. While the power of a source is characteristic of that particular source, the sound pressure depends on the location of the receiver and the path that the noise takes to reach the receiver. Measurement of noise is based on the decibel unit, dBA, which is a logarithmic ratio referenced to a standard noise level (2×10^{-5} Pascals). The ‘A’ suffix refers to a weighting scale, which better



represents how the noise is perceived by the human ear. With this scale, a doubling of power results in a 3 dBA increase in measured noise levels and is just perceptible to most people. An increase of 10 dBA is often perceived to be twice as loud.

4.2 Roadway and LRT Traffic Noise

4.2.1 Criteria for Roadway and LRT Traffic Noise

For surface roadway traffic noise, the equivalent sound energy level, L_{eq} , provides a measure of the time varying noise levels, which is well correlated with the annoyance of sound. It is defined as the continuous sound level, which has the same energy as a time varying noise level over a period of time. For roadways, the L_{eq} is commonly calculated on the basis of a 16-hour (L_{eq16}) daytime (07:00-23:00) / 8-hour (L_{eq8}) nighttime (23:00-07:00) split to assess its impact on residential buildings. The City of Ottawa’s Environmental Noise Control Guidelines (ENCG) specifies that the recommended indoor noise limit range (that is relevant to this study) is 45 and 40 dBA for living rooms and sleeping quarters respectively for roadway as listed in Table 1.

TABLE 1: INDOOR SOUND LEVEL CRITERIA (ROAD)³

Type of Space	Time Period	Leq (dBA)
General offices, reception areas, retail stores, etc.	07:00 – 23:00	50
Living/dining/den areas of residences , hospitals, schools, nursing/retirement homes, day-care centres, theatres, places of worship, libraries, individual or semi-private offices, conference rooms, etc.	07:00 – 23:00	45
Sleeping quarters of hotels/motels	23:00 – 07:00	45
Sleeping quarters of residences , hospitals, nursing/retirement homes, etc.	23:00 – 07:00	40

Predicted noise levels at the plane of window (POW) dictate the action required to achieve the recommended sound levels. An open window is considered to provide a 10 dBA reduction in noise, while a standard closed window is capable of providing a minimum 20 dBA noise reduction⁴. A closed window

³ Adapted from ENCG 2016 – Tables 2.2b and 2.2c

⁴ Burberry, P.B. (2014). Mitchell’s Environment and Services. Routledge, Page 125

due to a ventilation requirement will bring noise levels down to achieve an acceptable indoor environment⁵. Therefore, where noise levels exceed 55 dBA daytime and 50 dBA nighttime, the ventilation for the building should consider the need for having windows and doors closed, which triggers the need for forced air heating with provision for central air conditioning. Where noise levels exceed 65 dBA daytime and 60 dBA nighttime, air conditioning will be required and building components will require higher levels of sound attenuation⁶.

The sound level criterion for outdoor living areas is 55 dBA, which applies during the daytime (07:00 to 23:00). When noise levels exceed 55 dBA, mitigation must be provided to reduce noise levels where technically and administratively feasible to acceptable levels at or below the criterion.

4.2.2 Theoretical Roadway and LRT Noise Predictions

Noise predictions were performed with the aid of the MECP computerized noise assessment program, STAMSON 5.04, for road analysis. Appendix A includes the STAMSON 5.04 input and output data.

Roadway traffic noise calculations were performed by treating each roadway segment as separate line sources of noise. In addition to the traffic volumes summarized in Table 2, theoretical noise predictions were based on the following parameters:

- Truck traffic on all roadways was taken to comprise 5% heavy trucks and 7% medium trucks, as per ENCG requirements for noise level predictions.
- The day/night split for all streets was taken to be 92%/8%, respectively.
- Ground surfaces were taken to be absorptive due to the presence of soft (landscaped) ground.
- Topography was assumed to be a flat/gentle slope surrounding the study building.
- The LRT Confederation Line was modelled as a 4-car SRT type in STAMSON
- LRT speed was taken to be 50km/h for trains approaching/leaving the station (stop 3021)
- Receptor height was taken to be 28.6 metres at Level 9 for the centre of the window (height to 9th floor slab + 1.5 metres) for Receptors 1-3; and 8.5 m, 18.6, 21.9, and 25.3 m for Receptors 4-8 respectively.

⁵ MECP, Environmental Noise Guidelines, NPC 300 – Part C, Section 7.8

⁶ MECP, Environmental Noise Guidelines, NPC 300 – Part C, Section 7.1.3

- For select sources where appropriate, Receptors 1-5 considered the proposed building as a barrier with a height of 30.4 metres, partially or fully obstructing exposure to the source as illustrated by exposure angles in Appendix A Figures A1-A5. A standard 1.1 m tall perimeter guard was assumed to enclose each terrace.
- Noise receptors were strategically placed at 8 locations around the study area (see Figure 2).
- Receptor distances and exposure angles are illustrated in Appendix A Figures A1-A5.

4.2.3 Roadway Traffic Volumes

The ENCG dictates that noise calculations should consider future sound levels based on a roadway’s classification at the mature state of development. Therefore, traffic volumes are based on the roadway classifications outlined in the City of Ottawa’s Official Plan (OP) and Transportation Master Plan⁷ which provide additional details on future roadway expansions. Average Annual Daily Traffic (AADT) volumes are then based on data in Table B1 of the ENCG for each roadway classification. Table 2 (below) summarizes the AADT values used for each roadway included in this assessment.

TABLE 2: ROADWAY TRAFFIC DATA

Segment	Roadway Traffic Data	Speed Limit (km/h)	Traffic Volumes
Queen Elizabeth Driveway	2-Lane Urban Arterial Undivided (2-UAU)	60	15,000
Colonel By Drive	2-Lane Urban Arterial Undivided (2-UAU)	40	15,000
Nicholas Street	4-Lane Urban Arterial Divided (4-UAD)	60	35,000
Confederation Line	LRT	50	540/60*

*Daytime/Nighttime volumes

⁷ City of Ottawa Transportation Master Plan, November 2013

5. RESULTS AND DISCUSSION


5.1 Roadway Traffic Noise Levels

The results of the roadway traffic noise calculations are summarized in Table 3 below. A complete set of input and output data from all STAMSON 5.04 calculations are available in Appendix A.

TABLE 3: EXTERIOR NOISE LEVELS DUE TO ROAD TRAFFIC

Receptor Number	Receptor Height Above Grade (m)	Receptor Location	STAMSON 5.04 Noise Level (dBA)	
			Day	Night
1	28.6	POW – 9 th Floor – East Façade	67	59
2	28.6	POW – 9 th Floor – North Façade	68	61
3	28.6	POW – 9 th Floor – West Façade	66	58
4	8.5	OLA – 3 rd Floor Terrace	66	N/A*
5	18.6	OLA – 6 th Floor Balcony	65	N/A*
6	21.9	OLA – 7 th Floor Balcony	62	N/A*
7	25.3	OLA – 8 th Floor Balcony	62	N/A*
8	28.6	OLA – 9 th Floor Balcony	61	N/A*

The results of the current analysis indicate that noise levels will range between 61 and 68 dBA during the daytime period (07:00-23:00) and between 58 and 61 dBA during the nighttime period (23:00-07:00). The highest noise level (68 dBA) occurs at the north façade, which is nearest and most exposed to Nicholas Street.



6. CONCLUSIONS AND RECOMMENDATIONS

The noise levels predicted due to roadway traffic exceed the criteria listed in the ENCG for standard building components, and upgraded building components with a higher Sound Transmission Class (STC) rating will be required. Due to the limited information available at the time of the study, which was prepared for rezoning application, detailed STC calculations could not be performed at this time. A detailed review of the window and wall assemblies should be performed by a qualified engineer with expertise in acoustics during the detailed design stage of the building.

Results of the calculations also indicate that the development will require central air conditioning, or a similar ventilation system, which will allow occupants to keep windows closed and maintain a comfortable living environment. Warning Clauses will also be required be placed on all Lease, Purchase and Sale Agreements.

With respect to the outdoor amenity spaces, the following conclusions were made. Noise levels at the 3rd floor terrace and balconies on the 6th, 7th, 8th and 9th floor were found to exceed the ENCG criteria for Outdoor Living Areas (OLA). The ENCG dictates that noise levels are OLAs must not exceed 60 dBA, and should be targeted below 55 dBA as is technically and administratively feasible. Therefore, noise control measures must be investigated to mitigate noise to acceptable levels. As a general recommendation OLAs be positioned away from the roadway to reduce noise levels, however, these spaces are positioned to maintain view of the Rideau Canal to the north of the development. Therefore, OLA noise mitigation strategies should investigate the implementation of raised perimeter guards. OLA noise mitigation can be addressed during site plan control.

The building's proposed HVAC equipment has potential for noise impacts on surrounding buildings and the study building itself. Typically, noise levels can be controlled by judicious selection and placement of the equipment and the introduction of silencers or noise screens where needed. A stationary noise study will be performed once mechanical plans for the proposed building become available. This study will include recommendations for any noise control measures that may be necessary to ensure noise levels fall below ENCG limits.

The surrounding area was evaluated for sources of stationary noise impacting the proposed development. Rooftop air handling equipment atop the Embassy of Germany is expected to have minimal impact. Given

the setback distance of approximately 35 metres and an enclosure surrounding the equipment, noise levels will be dominated by roadway traffic noise. No other stationary noise sources were identified, therefore, stationary noise impacts on the proposed development are expected to be insignificant.

A detailed roadway traffic noise study will be required at the time of site plan approval to determine specific noise control measures for the development.

This concludes our traffic noise assessment and report. If you have any questions or wish to discuss our findings, please advise us. In the interim, we thank you for the opportunity to be of service.

Sincerely,

Gradient Wind Engineering Inc.





Tanyon Matheson-Fitchett, B.Eng.
Junior Environmental Scientist

Gradient Wind File #21-200



Joshua Foster, P.Eng.
Principal






- # OLA RECEPTOR
- # POW RECEPTOR

PROJECT	50 THE DRIVEWAY, OTTAWA ROADWAY TRAFFIC NOISE FEASIBILITY ASSESSMENT	
SCALE	1:500 (APPROX.)	DRAWING NO. GW21-200-2
DATE	JUNE 23, 2021	DRAWN BY T.M.F.


GRADIENTWIND

ENGINEERS & SCIENTISTS





APPENDIX A

STAMSON 5.04 – INPUT AND OUTPUT DATA



- OLA RECEPTOR
- POW RECEPTOR


PROJECT	50 THE DRIVEWAY, OTTAWA ROADWAY TRAFFIC NOISE FEASIBILITY ASSESSMENT	
SCALE	1:1500 (APPROX.)	DRAWING NO. GW21-200-A1
DATE	JUNE 24, 2021	DRAWN BY T.M.F.




- # OLA RECEPTOR
- # POW RECEPTOR


PROJECT	50 THE DRIVEWAY, OTTAWA ROADWAY TRAFFIC NOISE FEASIBILITY ASSESSMENT	
SCALE	1:1500 (APPROX.)	DRAWING NO. GW21-200-A2
DATE	JUNE 24, 2021	DRAWN BY T.M.F.

DESCRIPTION	FIGURE A2: RECEPTOR 2 STAMSON INPUT PARAMETERS
-------------	---



GRADIENTWIND ENGINEERS & SCIENTISTS 127 WALGREEN ROAD, OTTAWA, ON 613 836 0934 • GRADIENTWIND.COM	PROJECT	50 THE DRIVEWAY, OTTAWA ROADWAY TRAFFIC NOISE FEASIBILITY ASSESSMENT		DESCRIPTION	FIGURE A3: RECEPTOR 3 STAMSON INPUT PARAMETERS
	SCALE	1:1500 (APPROX.)	DRAWING NO.	GW21-200-A3	
	DATE	JUNE 24, 2021	DRAWN BY	T.M.F.	





- # OLA RECEPTOR
- # POW RECEPTOR

GRADIENTWIND ENGINEERS & SCIENTISTS 127 WALGREEN ROAD, OTTAWA, ON 613 836 0934 • GRADIENTWIND.COM	PROJECT	50 THE DRIVEWAY, OTTAWA ROADWAY TRAFFIC NOISE FEASIBILITY ASSESSMENT		DESCRIPTION	FIGURE A5: RECEPTOR 5-8 STAMSON INPUT PARAMETERS
	SCALE	1:1500 (APPROX.)	DRAWING NO.	GW21-200-A5	
	DATE	JUNE 24, 2021	DRAWN BY	T.M.F.	

GRADIENTWIND

ENGINEERS & SCIENTISTS

STAMSON 5.0 NORMAL REPORT Date: 24-06-2021 16:33:48
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r1.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: QueenEliz1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: QueenEliz1 (day/night)

Angle1 Angle2 : 0.00 deg 42.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 50.00 / 50.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



Road data, segment # 2: QueenEliz2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: QueenEliz2 (day/night)

Angle1 Angle2 : 0.00 deg 57.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 68.00 / 68.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 3: ColonelBy1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: ColonelBy1 (day/night)

Angle1 Angle2 : -6.00 deg 49.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 123.00 / 123.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 4: ColonelBy2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: ColonelBy2 (day/night)

Angle1 Angle2 : 7.00 deg 37.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 183.00 / 183.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



Road data, segment # 5: Nicholas (day/night)

Car traffic volume : 28336/2464 veh/TimePeriod *
Medium truck volume : 2254/196 veh/TimePeriod *
Heavy truck volume : 1610/140 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 35000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 5: Nicholas (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 147.00 / 147.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 6: QueenEliz3 (day/night)

```
-----
Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00
```

Data for Segment # 6: QueenEliz3 (day/night)

```
-----
Angle1 Angle2 : 15.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 129.00 / 129.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00
```

Results segment # 1: QueenEliz1 (day)

Source height = 1.50 m

ROAD (0.00 + 58.45 + 0.00) = 58.45 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	42	0.00	70.00	0.00	-5.23	-6.32	0.00	0.00	0.00	58.45

Segment Leq : 58.45 dBA

Results segment # 2: QueenEliz2 (day)

Source height = 1.50 m

ROAD (0.00 + 58.44 + 0.00) = 58.44 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	57	0.00	70.00	0.00	-6.56	-4.99	0.00	0.00	0.00	58.44

Segment Leq : 58.44 dBA



Results segment # 3: ColonelBy1 (day)

Source height = 1.50 m

ROAD (0.00 + 52.40 + 0.00) = 52.40 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-6	49	0.00	66.69	0.00	-9.14	-5.15	0.00	0.00	0.00	52.40

Segment Leq : 52.40 dBA

Results segment # 4: ColonelBy2 (day)

Source height = 1.50 m

ROAD (0.00 + 48.04 + 0.00) = 48.04 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
7	37	0.00	66.69	0.00	-10.86	-7.78	0.00	0.00	0.00	48.04

Segment Leq : 48.04 dBA

Results segment # 5: Nicholas (day)

Source height = 1.50 m

ROAD (0.00 + 63.76 + 0.00) = 63.76 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	73.68	0.00	-9.91	0.00	0.00	0.00	0.00	63.76

Segment Leq : 63.76 dBA

Results segment # 6: QueenEliz3 (day)

Source height = 1.50 m

ROAD (0.00 + 56.85 + 0.00) = 56.85 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
15	90	0.00	70.00	0.00	-9.34	-3.80	0.00	0.00	0.00	56.85

Segment Leq : 56.85 dBA

Total Leq All Segments: 66.53 dBA

Results segment # 1: QueenEliz1 (night)

Source height = 1.50 m

ROAD (0.00 + 50.85 + 0.00) = 50.85 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	42	0.00	62.40	0.00	-5.23	-6.32	0.00	0.00	0.00	50.85

Segment Leq : 50.85 dBA

Results segment # 2: QueenEliz2 (night)

Source height = 1.50 m

ROAD (0.00 + 50.84 + 0.00) = 50.84 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	57	0.00	62.40	0.00	-6.56	-4.99	0.00	0.00	0.00	50.84

Segment Leq : 50.84 dBA



Results segment # 3: ColonelBy1 (night)

Source height = 1.50 m

ROAD (0.00 + 44.80 + 0.00) = 44.80 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-6	49	0.00	59.09	0.00	-9.14	-5.15	0.00	0.00	0.00	44.80

Segment Leq : 44.80 dBA

Results segment # 4: ColonelBy2 (night)

Source height = 1.50 m

ROAD (0.00 + 40.44 + 0.00) = 40.44 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
7	37	0.00	59.09	0.00	-10.86	-7.78	0.00	0.00	0.00	40.44

Segment Leq : 40.44 dBA

Results segment # 5: Nicholas (night)

Source height = 1.50 m

ROAD (0.00 + 56.17 + 0.00) = 56.17 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	66.08	0.00	-9.91	0.00	0.00	0.00	0.00	56.17

Segment Leq : 56.17 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 6: QueenEliz3 (night)

Source height = 1.50 m

ROAD (0.00 + 49.25 + 0.00) = 49.25 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
15	90	0.00	62.40	0.00	-9.34	-3.80	0.00	0.00	0.00	49.25

Segment Leq : 49.25 dBA

Total Leq All Segments: 58.93 dBA

RT/Custom data, segment # 1: LRT (day/night)

1 - 4-car SRT:

Traffic volume : 540/60 veh/TimePeriod
Speed : 50 km/h

Data for Segment # 1: LRT (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 164.00 / 164.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



Results segment # 1: LRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 50.13 + 0.00) = 50.13 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
--------	--------	-------	--------	-------	-------	-------	-------	-------	--------

-90	90	0.00	60.51	-10.39	0.00	0.00	0.00	0.00	50.13
-----	----	------	-------	--------	------	------	------	------	-------

Segment Leq : 50.13 dBA

Total Leq All Segments: 50.13 dBA

Results segment # 1: LRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 43.60 + 0.00) = 43.60 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
--------	--------	-------	--------	-------	-------	-------	-------	-------	--------

-90	90	0.00	53.98	-10.39	0.00	0.00	0.00	0.00	43.60
-----	----	------	-------	--------	------	------	------	------	-------

Segment Leq : 43.60 dBA

Total Leq All Segments: 43.60 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 66.63
(NIGHT): 59.06



GRADIENTWIND

ENGINEERS & SCIENTISTS

STAMSON 5.0 NORMAL REPORT Date: 24-06-2021 16:35:37
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r2.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: QueenEliz1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: QueenEliz1 (day/night)

Angle1 Angle2 : -90.00 deg 61.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 40.00 / 40.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 2: QueenEliz2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: QueenEliz2 (day/night)

Angle1 Angle2 : 21.00 deg 54.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 76.00 / 76.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 3: ColonelBy1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: ColonelBy1 (day/night)

Angle1 Angle2 : -90.00 deg 55.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 116.00 / 116.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 4: ColonelBy2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: ColonelBy2 (day/night)

Angle1 Angle2 : 13.00 deg 46.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 195.00 / 195.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 5: Nicholas (day/night)

```

-----
Car traffic volume   : 28336/2464  veh/TimePeriod  *
Medium truck volume : 2254/196   veh/TimePeriod  *
Heavy truck volume  : 1610/140   veh/TimePeriod  *
Posted speed limit  :    60 km/h
Road gradient       :    0 %
Road pavement      :    1 (Typical asphalt or concrete)
  
```

* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT): 35000
Percentage of Annual Growth       : 0.00
Number of Years of Growth         : 0.00
Medium Truck % of Total Volume    : 7.00
Heavy Truck % of Total Volume     : 5.00
Day (16 hrs) % of Total Volume    : 92.00
  
```

Data for Segment # 5: Nicholas (day/night)

```

-----
Angle1  Angle2      : -90.00 deg  90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 2 (Reflective ground surface)
Receiver source distance : 141.00 / 147.00 m
Receiver height  : 28.60 / 28.60 m
Topography      : 1 (Flat/gentle slope; no barrier)
Reference angle  : 0.00
  
```

Results segment # 1: QueenEliz1 (day)

Source height = 1.50 m

```

ROAD (0.00 + 64.97 + 0.00) = 64.97 dBA
Angle1 Angle2  Alpha RefLeq  P.Adj  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj SubLeq
-----
-90    61    0.00  70.00  0.00  -4.26  -0.76  0.00  0.00  0.00  64.97
-----
  
```

Segment Leq : 64.97 dBA



Results segment # 2: QueenEliz2 (day)

Source height = 1.50 m

ROAD (0.00 + 55.58 + 0.00) = 55.58 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
21	54	0.00	70.00	0.00	-7.05	-7.37	0.00	0.00	0.00	55.58

Segment Leq : 55.58 dBA

Results segment # 3: ColonelBy1 (day)

Source height = 1.50 m

ROAD (0.00 + 56.86 + 0.00) = 56.86 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	55	0.00	66.69	0.00	-8.88	-0.94	0.00	0.00	0.00	56.86

Segment Leq : 56.86 dBA



Results segment # 4: ColonelBy2 (day)

Source height = 1.50 m

ROAD (0.00 + 48.18 + 0.00) = 48.18 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
13	46	0.00	66.69	0.00	-11.14	-7.37	0.00	0.00	0.00	48.18

Segment Leq : 48.18 dBA

Results segment # 5: Nicholas (day)

Source height = 1.50 m

ROAD (0.00 + 63.94 + 0.00) = 63.94 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	73.68	0.00	-9.73	0.00	0.00	0.00	0.00	63.94

Segment Leq : 63.94 dBA

Total Leq All Segments: 68.15 dBA



Results segment # 1: QueenEliz1 (night)

Source height = 1.50 m

ROAD (0.00 + 57.38 + 0.00) = 57.38 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	61	0.00	62.40	0.00	-4.26	-0.76	0.00	0.00	0.00	57.38

Segment Leq : 57.38 dBA

Results segment # 2: QueenEliz2 (night)

Source height = 1.50 m

ROAD (0.00 + 47.98 + 0.00) = 47.98 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
21	54	0.00	62.40	0.00	-7.05	-7.37	0.00	0.00	0.00	47.98

Segment Leq : 47.98 dBA



Results segment # 3: ColonelBy1 (night)

Source height = 1.50 m

ROAD (0.00 + 49.27 + 0.00) = 49.27 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	55	0.00	59.09	0.00	-8.88	-0.94	0.00	0.00	0.00	49.27

Segment Leq : 49.27 dBA

Results segment # 4: ColonelBy2 (night)

Source height = 1.50 m

ROAD (0.00 + 40.58 + 0.00) = 40.58 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
13	46	0.00	59.09	0.00	-11.14	-7.37	0.00	0.00	0.00	40.58

Segment Leq : 40.58 dBA

Results segment # 5: Nicholas (night)

Source height = 1.50 m

ROAD (0.00 + 56.17 + 0.00) = 56.17 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	66.08	0.00	-9.91	0.00	0.00	0.00	0.00	56.17

Segment Leq : 56.17 dBA

Total Leq All Segments: 60.49 dBA

RT/Custom data, segment # 1: LRT (day/night)

1 - 4-car SRT:

Traffic volume : 540/60 veh/TimePeriod
 Speed : 50 km/h

Data for Segment # 1: LRT (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 157.00 / 157.00 m
 Receiver height : 28.60 / 28.60 m
 Topography : 1 (Flat/gentle slope; no barrier)
 Reference angle : 0.00



Results segment # 1: LRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 50.32 + 0.00) = 50.32 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
--------	--------	-------	--------	-------	-------	-------	-------	-------	--------

-90	90	0.00	60.51	-10.20	0.00	0.00	0.00	0.00	50.32
-----	----	------	-------	--------	------	------	------	------	-------

Segment Leq : 50.32 dBA

Total Leq All Segments: 50.32 dBA

Results segment # 1: LRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 43.78 + 0.00) = 43.78 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
--------	--------	-------	--------	-------	-------	-------	-------	-------	--------

-90	90	0.00	53.98	-10.20	0.00	0.00	0.00	0.00	43.78
-----	----	------	-------	--------	------	------	------	------	-------

Segment Leq : 43.78 dBA

Total Leq All Segments: 43.78 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 68.22
(NIGHT): 60.58



GRADIENTWIND

ENGINEERS & SCIENTISTS

STAMSON 5.0 NORMAL REPORT Date: 24-06-2021 16:37:08
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r3.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: QueenEliz (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: QueenEliz (day/night)

Angle1 Angle2 : -90.00 deg 13.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 43.00 / 43.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 2: ColonelBy (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: ColonelBy (day/night)

Angle1 Angle2 : -90.00 deg 7.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 121.00 / 121.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



Road data, segment # 3: Nicholas (day/night)

Car traffic volume : 28336/2464 veh/TimePeriod *
Medium truck volume : 2254/196 veh/TimePeriod *
Heavy truck volume : 1610/140 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 35000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: Nicholas (day/night)

Angle1 Angle2 : -90.00 deg 5.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 146.00 / 146.00 m
Receiver height : 28.60 / 28.60 m
Topography : 1 (Flat/gentle slope; no barrier)
Reference angle : 0.00



Results segment # 1: QueenEliz (day)

Source height = 1.50 m

ROAD (0.00 + 63.00 + 0.00) = 63.00 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	13	0.00	70.00	0.00	-4.57	-2.42	0.00	0.00	0.00	63.00

Segment Leq : 63.00 dBA

Results segment # 2: ColonelBy (day)

Source height = 1.50 m

ROAD (0.00 + 54.93 + 0.00) = 54.93 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	7	0.00	66.69	0.00	-9.07	-2.69	0.00	0.00	0.00	54.93

Segment Leq : 54.93 dBA



Results segment # 3: Nicholas (day)

Source height = 1.50 m

ROAD (0.00 + 61.02 + 0.00) = 61.02 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	5	0.00	73.68	0.00	-9.88	-2.78	0.00	0.00	0.00	61.02

Segment Leq : 61.02 dBA

Total Leq All Segments: 65.53 dBA

Results segment # 1: QueenEliz (night)

Source height = 1.50 m

ROAD (0.00 + 55.40 + 0.00) = 55.40 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	13	0.00	62.40	0.00	-4.57	-2.42	0.00	0.00	0.00	55.40

Segment Leq : 55.40 dBA

Results segment # 2: ColonelBy (night)

Source height = 1.50 m

ROAD (0.00 + 47.34 + 0.00) = 47.34 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	7	0.00	59.09	0.00	-9.07	-2.69	0.00	0.00	0.00	47.34

Segment Leq : 47.34 dBA



Results segment # 3: Nicholas (night)

 Source height = 1.50 m

ROAD (0.00 + 53.42 + 0.00) = 53.42 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	5	0.00	66.08	0.00	-9.88	-2.78	0.00	0.00	0.00	53.42

Segment Leq : 53.42 dBA

Total Leq All Segments: 57.93 dBA

RT/Custom data, segment # 1: LRT (day/night)

 1 - 4-car SRT:

Traffic volume : 540/60 veh/TimePeriod
 Speed : 50 km/h

Data for Segment # 1: LRT (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 162.00 / 162.00 m
 Receiver height : 28.60 / 28.60 m
 Topography : 1 (Flat/gentle slope; no barrier)
 Reference angle : 0.00



Results segment # 1: LRT (day)

Source height = 0.50 m

RT/Custom (0.00 + 50.18 + 0.00) = 50.18 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	60.51	-10.33	0.00	0.00	0.00	0.00	50.18

Segment Leq : 50.18 dBA

Total Leq All Segments: 50.18 dBA

Results segment # 1: LRT (night)

Source height = 0.50 m

RT/Custom (0.00 + 43.65 + 0.00) = 43.65 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	53.98	-10.33	0.00	0.00	0.00	0.00	43.65

Segment Leq : 43.65 dBA

Total Leq All Segments: 43.65 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 65.65
(NIGHT): 58.09



GRADIENTWIND

ENGINEERS & SCIENTISTS

STAMSON 5.0 NORMAL REPORT Date: 24-06-2021 14:39:58
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r4.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: QueenEliz1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: QueenEliz1 (day/night)

Angle1 Angle2 : -90.00 deg 40.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 46.00 / 46.00 m
Receiver height : 8.50 / 8.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 40.00 deg
Barrier height : 8.10 m
Barrier receiver distance : 4.00 / 4.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 2: QueenEliz2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: QueenEliz2 (day/night)

Angle1 Angle2 : 0.00 deg 62.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 59.00 / 59.00 m
Receiver height : 8.50 / 8.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 0.00 deg Angle2 : 62.00 deg
Barrier height : 8.10 m
Barrier receiver distance : 6.00 / 6.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



Road data, segment # 3: ColonelBy1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: ColonelBy1 (day/night)

Angle1 Angle2 : -90.00 deg 48.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 118.00 / 118.00 m
Receiver height : 8.50 / 8.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 48.00 deg
Barrier height : 8.10 m
Barrier receiver distance : 4.00 / 4.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



Road data, segment # 4: ColonelBy2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: ColonelBy2 (day/night)

Angle1 Angle2 : 6.00 deg 37.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 174.00 / 174.00 m
Receiver height : 8.50 / 8.50 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 6.00 deg Angle2 : 37.00 deg
Barrier height : 8.10 m
Barrier receiver distance : 6.00 / 6.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 5: Nicholas (day/night)

```

-----
Car traffic volume   : 28336/2464   veh/TimePeriod  *
Medium truck volume : 2254/196    veh/TimePeriod  *
Heavy truck volume  : 1610/140    veh/TimePeriod  *
Posted speed limit  :    60 km/h
Road gradient       :    0 %
Road pavement      :    1 (Typical asphalt or concrete)
  
```

* Refers to calculated road volumes based on the following input:

```

24 hr Traffic Volume (AADT or SADT): 35000
Percentage of Annual Growth       : 0.00
Number of Years of Growth         : 0.00
Medium Truck % of Total Volume    : 7.00
Heavy Truck % of Total Volume     : 5.00
Day (16 hrs) % of Total Volume    : 92.00
  
```

Data for Segment # 5: Nicholas (day/night)

```

-----
Angle1  Angle2      : -90.00 deg   90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 2 (Reflective ground surface)
Receiver source distance : 142.00 / 142.00 m
Receiver height  : 8.50 / 8.50 m
Topography      : 2 (Flat/gentle slope; with barrier)
Barrier angle1   : -90.00 deg   Angle2 : 90.00 deg
Barrier height   : 8.10 m
Barrier receiver distance : 4.00 / 4.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle  : 0.00
  
```

Results segment # 1: QueenEliz1 (day)

Source height = 1.50 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          1.50 !          8.50 !          7.89 !          7.89
  
```

ROAD (0.00 + 58.50 + 0.00) = 58.50 dBA

```

-----
Angle1 Angle2  Alpha RefLeq  P.Adj  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
   -90   40   0.00  70.00   0.00  -4.87  -1.41   0.00   0.00  -5.22  58.50
  
```

Segment Leq : 58.50 dBA





GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 2: QueenEliz2 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	8.50	!
7.79	!	7.79	!

ROAD (0.00 + 54.05 + 0.00) = 54.05 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	62	0.00	70.00	0.00	-5.95	-4.63	0.00	0.00	-5.37	54.05

Segment Leq : 54.05 dBA

Results segment # 3: ColonelBy1 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	8.50	!
8.26	!	8.26	!

ROAD (0.00 + 56.57 + 0.00) = 56.57 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	48	0.00	66.69	0.00	-8.96	-1.15	0.00	0.00	-4.87	51.71*
-90	48	0.00	66.69	0.00	-8.96	-1.15	0.00	0.00	0.00	56.57

* Bright Zone !

Segment Leq : 56.57 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 4: ColonelBy2 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	8.50	8.26	8.26

ROAD (0.00 + 48.40 + 0.00) = 48.40 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
6	37	0.00	66.69	0.00	-10.64	-7.64	0.00	0.00	-4.89	43.51*
6	37	0.00	66.69	0.00	-10.64	-7.64	0.00	0.00	0.00	48.40

* Bright Zone !

Segment Leq : 48.40 dBA

Results segment # 5: Nicholas (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	8.50	8.30	8.30

ROAD (0.00 + 63.91 + 0.00) = 63.91 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	73.68	0.00	-9.76	0.00	0.00	0.00	-4.82	59.10*
-90	90	0.00	73.68	0.00	-9.76	0.00	0.00	0.00	0.00	63.91

* Bright Zone !

Segment Leq : 63.91 dBA

Total Leq All Segments: 65.96 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 1: QueenEliz1 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	8.50	!
7.89	!	7.89	!

ROAD (0.00 + 50.90 + 0.00) = 50.90 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	40	0.00	62.40	0.00	-4.87	-1.41	0.00	0.00	-5.22	50.90

Segment Leq : 50.90 dBA

Results segment # 2: QueenEliz2 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	8.50	!
7.79	!	7.79	!

ROAD (0.00 + 46.45 + 0.00) = 46.45 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
0	62	0.00	62.40	0.00	-5.95	-4.63	0.00	0.00	-5.37	46.45

Segment Leq : 46.45 dBA



Results segment # 3: ColonelBy1 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	8.50	8.26	8.26

ROAD (0.00 + 48.98 + 0.00) = 48.98 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	48	0.00	59.09	0.00	-8.96	-1.15	0.00	0.00	-4.87	44.11*
-90	48	0.00	59.09	0.00	-8.96	-1.15	0.00	0.00	0.00	48.98

* Bright Zone !

Segment Leq : 48.98 dBA

Results segment # 4: ColonelBy2 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	8.50	8.26	8.26

ROAD (0.00 + 40.81 + 0.00) = 40.81 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
6	37	0.00	59.09	0.00	-10.64	-7.64	0.00	0.00	-4.89	35.91*
6	37	0.00	59.09	0.00	-10.64	-7.64	0.00	0.00	0.00	40.81

* Bright Zone !

Segment Leq : 40.81 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 5: Nicholas (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	8.50	!
		8.30	!
			8.30

ROAD (0.00 + 56.32 + 0.00) = 56.32 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	66.08	0.00	-9.76	0.00	0.00	0.00	-4.82	51.50*
-90	90	0.00	66.08	0.00	-9.76	0.00	0.00	0.00	0.00	56.32

* Bright Zone !

Segment Leq : 56.32 dBA

Total Leq All Segments: 58.37 dBA

RT/Custom data, segment # 1: LRT (day/night)

1 - 4-car SRT:

Traffic volume : 540/60 veh/TimePeriod
 Speed : 50 km/h

Data for Segment # 1: LRT (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 158.00 / 158.00 m
 Receiver height : 8.50 / 8.50 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -90.00 deg Angle2 : 90.00 deg
 Barrier height : 8.10 m
 Barrier receiver distance : 4.00 / 4.00 m
 Source elevation : 0.00 m
 Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00



Results segment # 1: LRT (day)

Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
0.50	8.50	8.30	8.30

RT/Custom (0.00 + 50.29 + 0.00) = 50.29 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	60.51	-10.23	0.00	0.00	0.00	-4.83	45.46*
-90	90	0.00	60.51	-10.23	0.00	0.00	0.00	0.00	50.29

* Bright Zone !

Segment Leq : 50.29 dBA

Total Leq All Segments: 50.29 dBA

Results segment # 1: LRT (night)

Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
0.50	8.50	8.30	8.30

RT/Custom (0.00 + 43.76 + 0.00) = 43.76 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	53.98	-10.23	0.00	0.00	0.00	-4.83	38.93*
-90	90	0.00	53.98	-10.23	0.00	0.00	0.00	0.00	43.76

* Bright Zone !

Segment Leq : 43.76 dBA

Total Leq All Segments: 43.76 dBA

TOTAL Leq FROM ALL SOURCES (DAY) : 66.08
(NIGHT) : 58.52



GRADIENTWIND

ENGINEERS & SCIENTISTS

STAMSON 5.0 NORMAL REPORT Date: 24-06-2021 16:48:14
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r5.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: QueenEliz1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: QueenEliz1 (day/night)

Angle1 Angle2 : -90.00 deg 44.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 51.00 / 51.00 m
Receiver height : 18.60 / 18.60 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 44.00 deg
Barrier height : 18.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



Road data, segment # 2: QueenEliz2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: QueenEliz2 (day/night)

Angle1 Angle2 : 4.00 deg 55.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 71.00 / 71.00 m
Receiver height : 18.60 / 18.60 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 4.00 deg Angle2 : 55.00 deg
Barrier height : 18.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 3: ColonelBy1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: ColonelBy1 (day/night)

Angle1 Angle2 : -90.00 deg 49.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 127.00 / 127.00 m
Receiver height : 18.60 / 18.60 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 49.00 deg
Barrier height : 18.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 4: ColonelBy2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: ColonelBy2 (day/night)

Angle1 Angle2 : 7.00 deg 36.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 187.00 / 187.00 m
Receiver height : 18.60 / 18.60 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 7.00 deg Angle2 : 36.00 deg
Barrier height : 18.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



Road data, segment # 5: Nicholas (day/night)

Car traffic volume : 28336/2464 veh/TimePeriod *
Medium truck volume : 2254/196 veh/TimePeriod *
Heavy truck volume : 1610/140 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 35000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 5: Nicholas (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 149.00 / 149.00 m
Receiver height : 18.60 / 18.60 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 90.00 deg
Barrier height : 18.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 1: QueenEliz1 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	18.60	17.59	17.59

ROAD (0.00 + 56.59 + 0.00) = 56.59 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	44	0.00	70.00	0.00	-5.31	-1.28	0.00	0.00	-6.81	56.59

Segment Leq : 56.59 dBA

Results segment # 2: QueenEliz2 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	18.60	17.88	17.88

ROAD (0.00 + 52.05 + 0.00) = 52.05 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
4	55	0.00	70.00	0.00	-6.75	-5.48	0.00	0.00	-5.71	52.05

Segment Leq : 52.05 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 3: ColonelBy1 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	18.60	18.20	18.20

ROAD (0.00 + 51.29 + 0.00) = 51.29 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	49	0.00	66.69	0.00	-9.28	-1.12	0.00	0.00	-5.00	51.29

Segment Leq : 51.29 dBA

Results segment # 4: ColonelBy2 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	18.60	18.33	18.33

ROAD (0.00 + 47.80 + 0.00) = 47.80 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
7	36	0.00	66.69	0.00	-10.96	-7.93	0.00	0.00	-4.87	42.93*
7	36	0.00	66.69	0.00	-10.96	-7.93	0.00	0.00	0.00	47.80

* Bright Zone !

Segment Leq : 47.80 dBA



Results segment # 5: Nicholas (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	18.60	18.26	18.26

ROAD (0.00 + 63.71 + 0.00) = 63.71 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	73.68	0.00	-9.97	0.00	0.00	0.00	-4.98	58.72*
-90	90	0.00	73.68	0.00	-9.97	0.00	0.00	0.00	0.00	63.71

* Bright Zone !

Segment Leq : 63.71 dBA

Total Leq All Segments: 65.00 dBA

Results segment # 1: QueenEliz1 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	18.60	17.59	17.59

ROAD (0.00 + 48.99 + 0.00) = 48.99 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	44	0.00	62.40	0.00	-5.31	-1.28	0.00	0.00	-6.81	48.99

Segment Leq : 48.99 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 2: QueenEliz2 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	18.60	!
		17.88	!
			17.88

ROAD (0.00 + 44.46 + 0.00) = 44.46 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
4	55	0.00	62.40	0.00	-6.75	-5.48	0.00	0.00	-5.71	44.46

Segment Leq : 44.46 dBA

Results segment # 3: ColonelBy1 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	18.60	!
		18.20	!
			18.20

ROAD (0.00 + 43.69 + 0.00) = 43.69 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	49	0.00	59.09	0.00	-9.28	-1.12	0.00	0.00	-5.00	43.69

Segment Leq : 43.69 dBA



Results segment # 4: ColonelBy2 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	18.60	18.33	18.33

ROAD (0.00 + 40.20 + 0.00) = 40.20 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
7	36	0.00	59.09	0.00	-10.96	-7.93	0.00	0.00	-4.87	35.33*
7	36	0.00	59.09	0.00	-10.96	-7.93	0.00	0.00	0.00	40.20

* Bright Zone !

Segment Leq : 40.20 dBA

Results segment # 5: Nicholas (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	18.60	18.26	18.26

ROAD (0.00 + 56.11 + 0.00) = 56.11 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	66.08	0.00	-9.97	0.00	0.00	0.00	-4.98	51.13*
-90	90	0.00	66.08	0.00	-9.97	0.00	0.00	0.00	0.00	56.11

* Bright Zone !

Segment Leq : 56.11 dBA

Total Leq All Segments: 57.40 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

RT/Custom data, segment # 1: LRT (day/night)

1 - 4-car SRT:
 Traffic volume : 540/60 veh/TimePeriod
 Speed : 50 km/h

Data for Segment # 1: LRT (day/night)

```

-----
Angle1  Angle2      : -90.00 deg   90.00 deg
Wood depth      :          0   (No woods.)
No of house rows :          0 / 0
Surface         :          2   (Reflective ground surface)
Receiver source distance : 165.00 / 165.00 m
Receiver height  : 18.60 / 18.60 m
Topography      :          2   (Flat/gentle slope; with barrier)
Barrier angle1   : -90.00 deg   Angle2 : 90.00 deg
Barrier height   : 18.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle  : 0.00
  
```

Results segment # 1: LRT (day)

Source height = 0.50 m

Barrier height for grazing incidence

```

-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          0.50 !          18.60 !          18.27 !          18.27
  
```

RT/Custom (0.00 + 50.10 + 0.00) = 50.10 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	60.51	-10.41	0.00	0.00	0.00	-4.97	45.13*
-90	90	0.00	60.51	-10.41	0.00	0.00	0.00	0.00	50.10

* Bright Zone !

Segment Leq : 50.10 dBA

Total Leq All Segments: 50.10 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 1: LRT (night)

 Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
0.50	!	18.60	!
		18.27	!
			18.27

RT/Custom (0.00 + 43.57 + 0.00) = 43.57 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	53.98	-10.41	0.00	0.00	0.00	-4.97	38.60*
-90	90	0.00	53.98	-10.41	0.00	0.00	0.00	0.00	43.57

* Bright Zone !

Segment Leq : 43.57 dBA

Total Leq All Segments: 43.57 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 65.14
 (NIGHT): 57.57



GRADIENTWIND

ENGINEERS & SCIENTISTS

STAMSON 5.0 NORMAL REPORT Date: 24-06-2021 16:50:22
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r6.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: QueenEliz1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: QueenEliz1 (day/night)

Angle1 Angle2 : -90.00 deg 44.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 51.00 / 51.00 m
Receiver height : 21.90 / 21.90 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 44.00 deg
Barrier height : 21.50 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



Road data, segment # 2: QueenEliz2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: QueenEliz2 (day/night)

Angle1 Angle2 : 4.00 deg 55.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 71.00 / 71.00 m
Receiver height : 21.90 / 21.90 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 4.00 deg Angle2 : 55.00 deg
Barrier height : 21.50 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 3: ColonelBy1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: ColonelBy1 (day/night)

Angle1 Angle2 : -90.00 deg 49.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 127.00 / 127.00 m
Receiver height : 21.90 / 21.90 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 49.00 deg
Barrier height : 21.50 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 4: ColonelBy2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: ColonelBy2 (day/night)

Angle1 Angle2 : 7.00 deg 36.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 187.00 / 187.00 m
Receiver height : 21.90 / 21.90 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 7.00 deg Angle2 : 36.00 deg
Barrier height : 21.50 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



Road data, segment # 5: Nicholas (day/night)

Car traffic volume : 28336/2464 veh/TimePeriod *
Medium truck volume : 2254/196 veh/TimePeriod *
Heavy truck volume : 1610/140 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 35000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 5: Nicholas (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 149.00 / 149.00 m
Receiver height : 21.90 / 21.90 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 90.00 deg
Barrier height : 21.50 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 1: QueenEliz1 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	21.90	20.70	20.70

ROAD (0.00 + 55.69 + 0.00) = 55.69 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	44	0.00	70.00	0.00	-5.31	-1.28	0.00	0.00	-7.71	55.69

Segment Leq : 55.69 dBA

Results segment # 2: QueenEliz2 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	21.90	21.04	21.04

ROAD (0.00 + 51.41 + 0.00) = 51.41 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
4	55	0.00	70.00	0.00	-6.75	-5.48	0.00	0.00	-6.35	51.41

Segment Leq : 51.41 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 3: ColonelBy1 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	21.90	21.42	21.42

ROAD (0.00 + 51.24 + 0.00) = 51.24 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	49	0.00	66.69	0.00	-9.28	-1.12	0.00	0.00	-5.04	51.24

Segment Leq : 51.24 dBA

Results segment # 4: ColonelBy2 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	21.90	21.57	21.57

ROAD (0.00 + 47.80 + 0.00) = 47.80 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
7	36	0.00	66.69	0.00	-10.96	-7.93	0.00	0.00	-4.96	42.84*
7	36	0.00	66.69	0.00	-10.96	-7.93	0.00	0.00	0.00	47.80

* Bright Zone !

Segment Leq : 47.80 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 5: Nicholas (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	21.90	21.49	21.49

ROAD (0.00 + 58.70 + 0.00) = 58.70 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	73.68	0.00	-9.97	0.00	0.00	0.00	-5.00	58.70

Segment Leq : 58.70 dBA

Total Leq All Segments: 61.59 dBA

Results segment # 1: QueenEliz1 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	21.90	20.70	20.70

ROAD (0.00 + 48.09 + 0.00) = 48.09 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	44	0.00	62.40	0.00	-5.31	-1.28	0.00	0.00	-7.71	48.09

Segment Leq : 48.09 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 2: QueenEliz2 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	21.90	!
		21.04	!
			21.04

ROAD (0.00 + 43.82 + 0.00) = 43.82 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
4	55	0.00	62.40	0.00	-6.75	-5.48	0.00	0.00	-6.35	43.82

Segment Leq : 43.82 dBA

Results segment # 3: ColonelBy1 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	21.90	!
		21.42	!
			21.42

ROAD (0.00 + 43.65 + 0.00) = 43.65 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	49	0.00	59.09	0.00	-9.28	-1.12	0.00	0.00	-5.04	43.65

Segment Leq : 43.65 dBA



Results segment # 4: ColonelBy2 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	21.90	21.57	21.57

ROAD (0.00 + 40.20 + 0.00) = 40.20 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
7	36	0.00	59.09	0.00	-10.96	-7.93	0.00	0.00	-4.96	35.25*
7	36	0.00	59.09	0.00	-10.96	-7.93	0.00	0.00	0.00	40.20

* Bright Zone !

Segment Leq : 40.20 dBA

Results segment # 5: Nicholas (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	21.90	21.49	21.49

ROAD (0.00 + 51.11 + 0.00) = 51.11 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	66.08	0.00	-9.97	0.00	0.00	0.00	-5.00	51.11

Segment Leq : 51.11 dBA

Total Leq All Segments: 54.00 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

RT/Custom data, segment # 1: LRT (day/night)

 1 - 4-car SRT:
 Traffic volume : 540/60 veh/TimePeriod
 Speed : 50 km/h

Data for Segment # 1: LRT (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 165.00 / 165.00 m
 Receiver height : 18.60 / 18.60 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -90.00 deg Angle2 : 90.00 deg
 Barrier height : 18.20 m
 Barrier receiver distance : 3.00 / 3.00 m
 Source elevation : 0.00 m
 Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Results segment # 1: LRT (day)

 Source height = 0.50 m

Barrier height for grazing incidence

Source	! Receiver	! Barrier	! Elevation of
Height (m)	! Height (m)	! Height (m)	! Barrier Top (m)
0.50 !	18.60 !	18.27 !	18.27

RT/Custom (0.00 + 50.10 + 0.00) = 50.10 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	60.51	-10.41	0.00	0.00	0.00	-4.97	45.13*
-90	90	0.00	60.51	-10.41	0.00	0.00	0.00	0.00	50.10

* Bright Zone !

Segment Leq : 50.10 dBA

Total Leq All Segments: 50.10 dBA



Results segment # 1: LRT (night)

 Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
0.50	!	18.60	!
		18.27	!
			18.27

RT/Custom (0.00 + 43.57 + 0.00) = 43.57 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	53.98	-10.41	0.00	0.00	0.00	-4.97	38.60*
-90	90	0.00	53.98	-10.41	0.00	0.00	0.00	0.00	43.57

* Bright Zone !

Segment Leq : 43.57 dBA

Total Leq All Segments: 43.57 dBA

TOTAL Leq FROM ALL SOURCES (DAY) : 61.89
 (NIGHT) : 54.38



GRADIENTWIND

ENGINEERS & SCIENTISTS

STAMSON 5.0 NORMAL REPORT Date: 24-06-2021 16:53:10
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r7.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: QueenEliz1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: QueenEliz1 (day/night)

Angle1 Angle2 : -90.00 deg 44.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 51.00 / 51.00 m
Receiver height : 25.30 / 25.30 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 44.00 deg
Barrier height : 24.90 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 2: QueenEliz2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: QueenEliz2 (day/night)

Angle1 Angle2 : 4.00 deg 55.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 71.00 / 71.00 m
Receiver height : 25.30 / 25.30 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 4.00 deg Angle2 : 55.00 deg
Barrier height : 24.90 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 3: ColonelBy1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: ColonelBy1 (day/night)

Angle1 Angle2 : -90.00 deg 49.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 127.00 / 127.00 m
Receiver height : 25.30 / 25.30 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 49.00 deg
Barrier height : 24.90 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 4: ColonelBy2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: ColonelBy2 (day/night)

Angle1 Angle2 : 7.00 deg 36.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 187.00 / 187.00 m
Receiver height : 25.30 / 25.30 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 7.00 deg Angle2 : 36.00 deg
Barrier height : 24.90 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 5: Nicholas (day/night)

```
-----
Car traffic volume   : 28336/2464   veh/TimePeriod  *
Medium truck volume : 2254/196    veh/TimePeriod  *
Heavy truck volume  : 1610/140    veh/TimePeriod  *
Posted speed limit  :    60 km/h
Road gradient       :    0 %
Road pavement      :    1 (Typical asphalt or concrete)
```

* Refers to calculated road volumes based on the following input:

```
24 hr Traffic Volume (AADT or SADT): 35000
Percentage of Annual Growth       : 0.00
Number of Years of Growth         : 0.00
Medium Truck % of Total Volume    : 7.00
Heavy Truck % of Total Volume     : 5.00
Day (16 hrs) % of Total Volume    : 92.00
```

Data for Segment # 5: Nicholas (day/night)

```
-----
Angle1  Angle2      : -90.00 deg   90.00 deg
Wood depth      : 0 (No woods.)
No of house rows : 0 / 0
Surface         : 2 (Reflective ground surface)
Receiver source distance : 149.00 / 149.00 m
Receiver height  : 25.30 / 25.30 m
Topography      : 2 (Flat/gentle slope; with barrier)
Barrier angle1   : -90.00 deg   Angle2 : 90.00 deg
Barrier height   : 24.90 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle  : 0.00
```

Results segment # 1: QueenEliz1 (day)

Source height = 1.50 m

Barrier height for grazing incidence

```
-----
Source      ! Receiver      ! Barrier      ! Elevation of
Height (m) ! Height (m) ! Height (m) ! Barrier Top (m)
-----+-----+-----+-----
          1.50 !      25.30 !      23.90 !      23.90
```

ROAD (0.00 + 54.80 + 0.00) = 54.80 dBA

```
-----
Angle1 Angle2  Alpha RefLeq  P.Adj  D.Adj  F.Adj  W.Adj  H.Adj  B.Adj SubLeq
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
   -90   44   0.00  70.00   0.00  -5.31  -1.28   0.00   0.00  -8.60  54.80
-----+-----+-----+-----+-----+-----+-----+-----+-----+-----+-----
```

Segment Leq : 54.80 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 2: QueenEliz2 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	25.30	!
24.29	!	24.29	!

ROAD (0.00 + 50.65 + 0.00) = 50.65 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
4	55	0.00	70.00	0.00	-6.75	-5.48	0.00	0.00	-7.12	50.65

Segment Leq : 50.65 dBA

Results segment # 3: ColonelBy1 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	25.30	!
24.74	!	24.74	!

ROAD (0.00 + 51.12 + 0.00) = 51.12 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	49	0.00	66.69	0.00	-9.28	-1.12	0.00	0.00	-5.16	51.12

Segment Leq : 51.12 dBA



Results segment # 4: ColonelBy2 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	25.30	24.92	24.92

ROAD (0.00 + 47.80 + 0.00) = 47.80 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
7	36	0.00	66.69	0.00	-10.96	-7.93	0.00	0.00	-5.00	42.80*
7	36	0.00	66.69	0.00	-10.96	-7.93	0.00	0.00	0.00	47.80

* Bright Zone !

Segment Leq : 47.80 dBA

Results segment # 5: Nicholas (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	25.30	24.82	24.82

ROAD (0.00 + 58.67 + 0.00) = 58.67 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	73.68	0.00	-9.97	0.00	0.00	0.00	-5.03	58.67

Segment Leq : 58.67 dBA

Total Leq All Segments: 61.28 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 1: QueenEliz1 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	25.30	23.90	23.90

ROAD (0.00 + 47.21 + 0.00) = 47.21 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	44	0.00	62.40	0.00	-5.31	-1.28	0.00	0.00	-8.60	47.21

Segment Leq : 47.21 dBA

Results segment # 2: QueenEliz2 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	25.30	24.29	24.29

ROAD (0.00 + 43.05 + 0.00) = 43.05 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
4	55	0.00	62.40	0.00	-6.75	-5.48	0.00	0.00	-7.12	43.05

Segment Leq : 43.05 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 3: ColonelBy1 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	25.30	24.74	24.74

ROAD (0.00 + 43.53 + 0.00) = 43.53 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	49	0.00	59.09	0.00	-9.28	-1.12	0.00	0.00	-5.16	43.53

Segment Leq : 43.53 dBA

Results segment # 4: ColonelBy2 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	25.30	24.92	24.92

ROAD (0.00 + 40.20 + 0.00) = 40.20 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
7	36	0.00	59.09	0.00	-10.96	-7.93	0.00	0.00	-5.00	35.21*
7	36	0.00	59.09	0.00	-10.96	-7.93	0.00	0.00	0.00	40.20

* Bright Zone !

Segment Leq : 40.20 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 5: Nicholas (night)

 Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	25.30	24.82	24.82

ROAD (0.00 + 51.07 + 0.00) = 51.07 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	66.08	0.00	-9.97	0.00	0.00	0.00	-5.03	51.07

Segment Leq : 51.07 dBA

Total Leq All Segments: 53.69 dBA

RT/Custom data, segment # 1: LRT (day/night)

1 - 4-car SRT:

Traffic volume : 540/60 veh/TimePeriod
 Speed : 50 km/h

Data for Segment # 1: LRT (day/night)

Angle1	Angle2	: -90.00 deg	90.00 deg
Wood depth		: 0	(No woods.)
No of house rows		: 0 / 0	
Surface		: 2	(Reflective ground surface)
Receiver source distance		: 165.00 / 165.00 m	
Receiver height		: 18.60 / 18.60 m	
Topography		: 2	(Flat/gentle slope; with barrier)
Barrier angle1		: -90.00 deg	Angle2 : 90.00 deg
Barrier height		: 18.20 m	
Barrier receiver distance		: 3.00 / 3.00 m	
Source elevation		: 0.00 m	
Receiver elevation		: 0.00 m	
Barrier elevation		: 0.00 m	
Reference angle		: 0.00	



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 1: LRT (day)

Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
0.50	18.60	18.27	18.27

RT/Custom (0.00 + 50.10 + 0.00) = 50.10 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	60.51	-10.41	0.00	0.00	0.00	-4.97	45.13*
-90	90	0.00	60.51	-10.41	0.00	0.00	0.00	0.00	50.10

* Bright Zone !

Segment Leq : 50.10 dBA

Total Leq All Segments: 50.10 dBA

Results segment # 1: LRT (night)

Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
0.50	18.60	18.27	18.27

RT/Custom (0.00 + 43.57 + 0.00) = 43.57 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	53.98	-10.41	0.00	0.00	0.00	-4.97	38.60*
-90	90	0.00	53.98	-10.41	0.00	0.00	0.00	0.00	43.57

* Bright Zone !

Segment Leq : 43.57 dBA

Total Leq All Segments: 43.57 dBA

TOTAL Leq FROM ALL SOURCES (DAY) : 61.60
(NIGHT) : 54.09



GRADIENTWIND

ENGINEERS & SCIENTISTS

STAMSON 5.0 NORMAL REPORT Date: 24-06-2021 16:42:10
MINISTRY OF ENVIRONMENT AND ENERGY / NOISE ASSESSMENT

Filename: r8.te Time Period: Day/Night 16/8 hours
Description:

Road data, segment # 1: QueenEliz1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 1: QueenEliz1 (day/night)

Angle1 Angle2 : -90.00 deg 44.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 51.00 / 51.00 m
Receiver height : 28.60 / 28.60 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 44.00 deg
Barrier height : 28.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



Road data, segment # 2: QueenEliz2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 2: QueenEliz2 (day/night)

Angle1 Angle2 : 4.00 deg 55.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 1 (Absorptive ground surface)
Receiver source distance : 71.00 / 71.00 m
Receiver height : 28.60 / 28.60 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 4.00 deg Angle2 : 55.00 deg
Barrier height : 28.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



Road data, segment # 3: ColonelBy1 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 3: ColonelBy1 (day/night)

Angle1 Angle2 : -90.00 deg 49.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 127.00 / 127.00 m
Receiver height : 28.60 / 28.60 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 49.00 deg
Barrier height : 28.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 4: ColonelBy2 (day/night)

Car traffic volume : 12144/1056 veh/TimePeriod *
Medium truck volume : 966/84 veh/TimePeriod *
Heavy truck volume : 690/60 veh/TimePeriod *
Posted speed limit : 40 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 15000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 4: ColonelBy2 (day/night)

Angle1 Angle2 : 7.00 deg 36.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 187.00 / 187.00 m
Receiver height : 28.60 / 28.60 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : 7.00 deg Angle2 : 36.00 deg
Barrier height : 28.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Road data, segment # 5: Nicholas (day/night)

Car traffic volume : 28336/2464 veh/TimePeriod *
Medium truck volume : 2254/196 veh/TimePeriod *
Heavy truck volume : 1610/140 veh/TimePeriod *
Posted speed limit : 60 km/h
Road gradient : 0 %
Road pavement : 1 (Typical asphalt or concrete)

* Refers to calculated road volumes based on the following input:

24 hr Traffic Volume (AADT or SADT): 35000
Percentage of Annual Growth : 0.00
Number of Years of Growth : 0.00
Medium Truck % of Total Volume : 7.00
Heavy Truck % of Total Volume : 5.00
Day (16 hrs) % of Total Volume : 92.00

Data for Segment # 5: Nicholas (day/night)

Angle1 Angle2 : -90.00 deg 90.00 deg
Wood depth : 0 (No woods.)
No of house rows : 0 / 0
Surface : 2 (Reflective ground surface)
Receiver source distance : 149.00 / 149.00 m
Receiver height : 28.60 / 28.60 m
Topography : 2 (Flat/gentle slope; with barrier)
Barrier angle1 : -90.00 deg Angle2 : 90.00 deg
Barrier height : 28.20 m
Barrier receiver distance : 3.00 / 3.00 m
Source elevation : 0.00 m
Receiver elevation : 0.00 m
Barrier elevation : 0.00 m
Reference angle : 0.00



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 1: QueenEliz1 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	28.60	27.01	27.01

ROAD (0.00 + 54.02 + 0.00) = 54.02 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	44	0.00	70.00	0.00	-5.31	-1.28	0.00	0.00	-9.38	54.02

Segment Leq : 54.02 dBA

Results segment # 2: QueenEliz2 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	28.60	27.45	27.45

ROAD (0.00 + 49.87 + 0.00) = 49.87 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
4	55	0.00	70.00	0.00	-6.75	-5.48	0.00	0.00	-7.90	49.87

Segment Leq : 49.87 dBA



Results segment # 3: ColonelBy1 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	28.60	27.96	27.96

ROAD (0.00 + 50.94 + 0.00) = 50.94 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	49	0.00	66.69	0.00	-9.28	-1.12	0.00	0.00	-5.34	50.94

Segment Leq : 50.94 dBA

Results segment # 4: ColonelBy2 (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	28.60	28.17	28.17

ROAD (0.00 + 42.79 + 0.00) = 42.79 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
7	36	0.00	66.69	0.00	-10.96	-7.93	0.00	0.00	-5.01	42.79

Segment Leq : 42.79 dBA



Results segment # 5: Nicholas (day)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	28.60	28.05	28.05

ROAD (0.00 + 58.59 + 0.00) = 58.59 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	73.68	0.00	-9.97	0.00	0.00	0.00	-5.12	58.59

Segment Leq : 58.59 dBA

Total Leq All Segments: 60.85 dBA

Results segment # 1: QueenEliz1 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	Receiver Height (m)	Barrier Height (m)	Elevation of Barrier Top (m)
1.50	28.60	27.01	27.01

ROAD (0.00 + 46.42 + 0.00) = 46.42 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	44	0.00	62.40	0.00	-5.31	-1.28	0.00	0.00	-9.38	46.42

Segment Leq : 46.42 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

Results segment # 2: QueenEliz2 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	28.60	!
		27.45	!
			27.45

ROAD (0.00 + 42.27 + 0.00) = 42.27 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
4	55	0.00	62.40	0.00	-6.75	-5.48	0.00	0.00	-7.90	42.27

Segment Leq : 42.27 dBA

Results segment # 3: ColonelBy1 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	28.60	!
		27.96	!
			27.96

ROAD (0.00 + 43.34 + 0.00) = 43.34 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	49	0.00	59.09	0.00	-9.28	-1.12	0.00	0.00	-5.34	43.34

Segment Leq : 43.34 dBA



Results segment # 4: ColonelBy2 (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	28.60	!
		28.17	!
			28.17

ROAD (0.00 + 35.19 + 0.00) = 35.19 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
7	36	0.00	59.09	0.00	-10.96	-7.93	0.00	0.00	-5.01	35.19

Segment Leq : 35.19 dBA

Results segment # 5: Nicholas (night)

Source height = 1.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
1.50	!	28.60	!
		28.05	!
			28.05

ROAD (0.00 + 50.99 + 0.00) = 50.99 dBA

Angle1	Angle2	Alpha	RefLeq	P.Adj	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	66.08	0.00	-9.97	0.00	0.00	0.00	-5.12	50.99

Segment Leq : 50.99 dBA

Total Leq All Segments: 53.25 dBA



GRADIENTWIND

ENGINEERS & SCIENTISTS

RT/Custom data, segment # 1: LRT (day/night)

 1 - 4-car SRT:
 Traffic volume : 540/60 veh/TimePeriod
 Speed : 50 km/h

Data for Segment # 1: LRT (day/night)

 Angle1 Angle2 : -90.00 deg 90.00 deg
 Wood depth : 0 (No woods.)
 No of house rows : 0 / 0
 Surface : 2 (Reflective ground surface)
 Receiver source distance : 165.00 / 165.00 m
 Receiver height : 28.60 / 28.60 m
 Topography : 2 (Flat/gentle slope; with barrier)
 Barrier angle1 : -90.00 deg Angle2 : 90.00 deg
 Barrier height : 28.20 m
 Barrier receiver distance : 3.00 / 3.00 m
 Source elevation : 0.00 m
 Receiver elevation : 0.00 m
 Barrier elevation : 0.00 m
 Reference angle : 0.00

Results segment # 1: LRT (day)

 Source height = 0.50 m

Barrier height for grazing incidence

Source	! Receiver	! Barrier	! Elevation of
Height (m)	! Height (m)	! Height (m)	! Barrier Top (m)
0.50 !	28.60 !	28.09 !	28.09

RT/Custom (0.00 + 45.03 + 0.00) = 45.03 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	60.51	-10.41	0.00	0.00	0.00	-5.07	45.03

Segment Leq : 45.03 dBA

Total Leq All Segments: 45.03 dBA



Results segment # 1: LRT (night)

 Source height = 0.50 m

Barrier height for grazing incidence

Source Height (m)	! Receiver ! Height (m)	! Barrier ! Height (m)	! Elevation of ! Barrier Top (m)
0.50	!	28.60	!
		28.09	!
			28.09

RT/Custom (0.00 + 38.50 + 0.00) = 38.50 dBA

Angle1	Angle2	Alpha	RefLeq	D.Adj	F.Adj	W.Adj	H.Adj	B.Adj	SubLeq
-90	90	0.00	53.98	-10.41	0.00	0.00	0.00	-5.07	38.50

 Segment Leq : 38.50 dBA

Total Leq All Segments: 38.50 dBA

TOTAL Leq FROM ALL SOURCES (DAY): 60.96
 (NIGHT): 53.39

