



DESIGN BRIEF

FOR

MINTO COMMUNITIES—CANADA BARRHAVEN TOWN CENTRE—STAGE 1 3265 JOCKVALE ROAD

CITY OF OTTAWA

PROJECT NO.: 15-816

JUNE 2023 REVISION 2 © DSEL

DESIGN BRIEF FOR 3265 JOCKVALE ROAD MINTO COMMUNITIES

TABLE OF CONTENTS

1.0	INTRODUCTION & BACKGROUND	1
1.1	Development Concept	2
1.2	Existing Conditions	4
1.3	Required Permits / Approvals	4
1.4	Pre-Consultation	5
2.0	GUIDELINES, PREVIOUS STUDIES, AND REPORTS	6
2.1	Existing Studies, Guidelines, and Reports	6
3.0	WATER SUPPLY SERVICING	8
3.1	Existing Water Supply Services	8
3.2	Water Supply Servicing Design	
	3.2.1 Watermain Modelling	
3.3	Fire Hydrant location	10
3.4	Water Supply Conclusion	11
4.0	WASTEWATER SERVICING	12
4.1	Existing Wastewater Services	12
4.2	Wastewater Design	12
4.3	Wastewater Servicing Conclusions	13
5.0	STORMWATER MANAGEMENT	14
5.1	Existing Stormwater Drainage	14
5.2	Stormwater Management Criteria	14
5.3	Stormwater Management Strategy	15
	5.3.1 Minor System	
	5.3.2 Quality Control	
5.4	Stormwater Management Calculations	
5.5	Grading & Drainage	
5.6	Stormwater Servicing Conclusions	
6.0	EROSION AND SEDIMENT CONTROL	19

7.0 CONCLUSIONS AND RE	COMMENDATIONS21
	IN-TEXT FIGURES
Figure 1.1: Site Location	1
	<u>TABLES</u>
Table 1.1: Development Statisti	c Projections3
Table 1.2: Anticipated Permit/A	pproval Requirements4
	· Criteria8
	emands9
	s9
	e Service Pressures10
	e Fire Flows10
	Criteria 13
•	vw13
	Criteria 16
	Requirements for Block A17
	Requirements for Block B18
i abio cio. Ciorrinator Storage	

APPENDICES

Appendix A Legal Drawings, Site Plan, Pre-consult Notes, City checklist

Appendix B Hydraulic Network Analysis

Appendix C Sanitary Servicing Documents

Appendix D Stormwater Servicing Documents

DESIGN BRIEF FOR 3265 JOCKVALE ROAD MINTO COMMUNITIES

JUNE 2023 CITY OF OTTAWA PROJECT NO.: 15-816

1.0 INTRODUCTION & BACKGROUND

David Schaeffer Engineering Limited (DSEL) has prepared this Design Brief in support of development of 3265 Jockvale Road on behalf of Minto Communities.

The study area is located within 3265 Jockvale Road in the City of Ottawa urban boundary, in the Ward 22 – Gloucester-South Nepean as illustrated in *Figure 1.1*, the study area is bounded by Longfields Drive to the east, future Chapman Mills Drive to the south, an extension of Riocan Avenue to be completed as part of these works in the west, and a mix of existing commercial and residential to the north which is crossed by Glenroy Gilbert Drive which will also be extended as part of these works. The site is a 5.21-hectar parcel located within South Nepean Town Centre Community Design Plan (CDP (City of Ottawa, 2006).




Figure 1.1: Site Location

The study area is governed by the broader *South Nepean Town Centre Community Design Plan* (CDP) (City of Ottawa, 2006) and its *Appendix I, South Nepean Town Centre Community Design Plan Preliminary Serviceability Report* (CCL, December 2005). The design plan and preliminary serviceability report were completed to prepare a preferred servicing strategy and cohesive development concept for the core of the South Nepean Town Centre Community (SNTC) development area (165 ha.). The reports identify existing infrastructure and environmental constraints, describe the neighborhood-level trunk services that will service all properties within the study area, establish targets for future site-specific stormwater management plans, and identify required infrastructure upgrades to support the proposed development of the SNTC area.

Since the completion of the reports, many of the identified neighbourhood-level infrastructure projects have been completed, including the Nepean-South Chapman Mills stormwater management pond and associated trunk storm sewers, sanitary trunk sewers, and trunk watermain connections. Furthermore, the planning and design of Chapman Mills Drive have been recently completed via the Municipal Class Environmental Assessment (October 2000, as amended 2007 and 2011) Schedule C process, with the Environmental Study Report filed on 18 November 2016.

This Design Brief is provided to demonstrate conformance with the design criteria of the City of Ottawa, the Community Design Plan, background studies including the *MSS*, and general industry practice. It provides detailed water, sanitary sewer, stormwater management and grading design information to support the development of the study area. This report should be read in conjunction with the Engineering Drawings (DSEL, June 30, 2023).

This Design Brief and detailed engineering submission have been prepared by **David Schaeffer Engineering Ltd.**, with site boundary conditions for the municipal water supply provided by the City of Ottawa, and geotechnical analysis prepared by **Paterson Group Inc.**

1.1 Development Concept

The site plan for the proposed development concept at 3265 Jockvale Road is presented in *Appendix A*. The proposed development consists of a total of 604 stacked townhouse units. *Table 1.1* presented below provides a projected population count for the site. The site is comprised of two private blocks bounded by municipal right-of-ways (ROW). The north block, referred to as Block A, is located north of Glenroy Gilbert Drive between Riocan Ave and Sue Holloway Way. The south block, referred to as Block B, is located south of Glenroy Gilbert Drive between Riocan and Longfields Drive. DSEL has also been retained by Minto Group to undertake detailed design of Glenroy Gilbert Drive and Riocan Avenue. Detailed designs for both of these municipal ROWs are being submitted to the City in parallel with the site plan application for the private lands.

Table 1.1: Development Statistic Projections

Land Use	Total Area (ha)	Projected Residential Units	Residential Population per Unit *	Projected Population *
Block A (North) Stacked Townhouse Units	0.64	60	2.1	126
Block B (South) Stacked Townhouse Units	4.19	544	2.1	1142
Glenroy Gilbert Drive Extension	0.39	-	-	-
TOTAL	5.21	604		1268

^{*} NOTE: Population projections may differ from population estimates used in background Transportation Studies, Planning Rationale, and other studies. Population projection and residential population per unit values are based on Ministry of Environment, Conservation and Parks guidelines for servicing demand calculations. Local Roads are included in Total Area estimates above.

1.2 Existing Conditions

Under existing conditions, the study area consists of undeveloped vacant lands. The existing elevations within the study area generally range from 101.8 m in the northwest corner of the study area to 95 m where Chapman Mills Drive meets Longfields Drive.

Paterson Group conducted a geotechnical investigation for the entirety of the Barrhaven Town Centre which is summarized in the *Geotechnical Investigation – Proposed Mixed-Use Commercial and Residential Development – 3265 Jockvale Road* (Paterson Group, August 27, 2021). The investigation explains a layer of topsoil was found overlying stiff silty clay and dense glacial till. The bedrock and groundwater depths for the study area were reported to be roughly 5-15 m and 3-6 m below existing ground respectively.

1.3 Required Permits / Approvals

Development of the study area is expected to be subject to the following permits and approvals presented in *Table 1.2*.

Table 1.2: Anticipated Permit/Approval Requirements

Agency	Permit/Approval Required	Trigger	Remarks
MECP/City of Ottawa	Environmental Compliance Approval	Construction of new sanitary sewers, storm sewers, and stormwater management works.	The City of Ottawa is expected to review all stormwater collection system, stormwater management, and wastewater collection system on behalf of the MECP by transfer of review authority.
MECP	Permit to Take Water (PTTW)	Construction of proposed land uses (e.g. basements for residential homes) and services.	Pumping of groundwater or surface water may be required during construction, given site conditions, proposed land uses, and on-site/off-site municipal infrastructure.
MECP/City of Ottawa	MECP Form 1 – Record of Watermains Authorized as a Future Alteration.	Construction of watermains.	The City of Ottawa is expected to review the watermains on behalf of the MECP through the Form 1 – Record of Watermains Authorized as a Future Alteration.
City of Ottawa	MOE Form 1 – Record of Watermains Authorized as a Future Alteration.	Construction of watermains.	The City of Ottawa is expected to review the watermains on behalf of the MECP through the Form 1 – Record of Watermains Authorized as a Future Alteration.
City of Ottawa	Commence Work Notification (CWN)	Construction of new sanitary and storm sewer throughout the subdivision.	The City of Ottawa will issue a commence work notification for construction of the sanitary and storm sewers once an ECA is issued by the MECP.

1.4 Pre-Consultation

Pre-application consultation was conducted on October 22, 2020, between the City of Ottawa and the developers as part of the Plan of Subdivision Application process. Various stakeholders provided written comments that were recorded and formalized in meeting minutes.

Per the City of Ottawa Transfer of Review Agreement No. TOR-OTT-E-2019-01, it is assumed that MECP pre-consultation is not required, as the City of Ottawa is expected to agree that the proposed works fall under Schedule A of the agreement. As such, the City of Ottawa is expected to review the proposed infrastructure on behalf of MECP as part of issuing Environmental Compliance Approval for the appropriate works.

2.0 GUIDELINES, PREVIOUS STUDIES, AND REPORTS

2.1 Existing Studies, Guidelines, and Reports

The following key studies were utilized in the preparation of this report:

- Ottawa Sewer Design Guidelines, City of Ottawa, SDG002, October 2012 (Sewer Design Guidelines)
- Technical Bulletin ISDTB-2014-01, Revisions to Ottawa Design Guidelines Sewer, City of Ottawa, February 5, 2014. (ISDTB-2014-01)
- Technical Bulletin PIEDTB-2016-01, Revisions to Ottawa Design Guidelines Sewer, City of Ottawa, September 6, 2016. (PIEDTB-2016-01)
- Technical Bulletin ISTB-2018-01, Revisions to Ottawa Design Guidelines Sewer, City of Ottawa, March 21, 2018 (ISTB-2018-01)
- Technical Bulletin ISTB-2019-02, Revisions to Ottawa Design Guidelines Sewer, City of Ottawa, July 8, 2019. (ISTB-2019-02)
- Ottawa Design Guidelines Water Distribution, City of Ottawa, July 2010. (Water Supply Guidelines)
- Technical Bulletin ISD-2010-2 City of Ottawa, December 15, 2010. (ISDTB-2010-2)
- Technical Bulletin ISDTB-2014-02 City of Ottawa, May 27, 2014. (ISDTB-2014-02)
- Technical Bulletin ISTB-2018-02 City of Ottawa, March 21, 2018 (ISDTB-2018-02)
- Technical Bulletin ISTB-2021-03 City of Ottawa, August 18, 2021 (ISDTB-2021-03)
- Fire Underwriters Survey, 1999. (FUS)
- ➤ **Design Guidelines for Drinking-Water Systems**, Ministry of the Environment, 2008. (*MECP Water Guidelines*)

- Design Guidelines for Sewage Works, Ministry of the Environment, 2008. (MECP Design Guidelines)
- Stormwater Planning and Design Manual, Ministry of the Environment, 2003. (SWMP Design Manual)
- Ontario Building Code Compendium, Ministry of Municipal Affairs and Housing Building Development Branch, 2012 and as updated from time to time. (OBC)
- Ontario Building Code Compendium, Ministry of Municipal Affairs and Housing Building Development Branch, 2012 and as updated from time to time. (OBC)
- South Nepean Town Centre Community Design Plan City of Ottawa, July 2006. (CDP)
- Kennedy Burnett Potable Water Master Servicing Study Stantec Consulting Ltd, April 29, 2014.
- South Nepean Collector: Phase 2, Hydraulics Review, Technical Memorandum Novatech, August 20, 2015.
- Kennedy-Burnett Stormwater Management Facility Functional Design Report CH2M, February 17, 2017.
- Nepean South Chapman Mills Stormwater Management Servicing, Fourth Addendum, IBI Group, February 16, 2018.
- ➤ **Geotechnical Investigation** Proposed Mixed-Use Commercial and Residential Development 3265 Jockvale Road, Paterson Group, August 27, 2021

3.0 WATER SUPPLY SERVICING

3.1 Existing Water Supply Services

The subject property lies within the existing City of Ottawa 3SW pressure zone. To the northeast of the subject property, a 200mm diameter watermain exists within the Glenroy Gilbert Drive ROW, as well as a 300mm diameter watermain in the Chapman Mills Drive ROW which is capped at the study area boundary. To the northwest, a 200mm watermain is capped at the study area boundary running from the Chapman Mills Marketplace retail development and existing infrastructure on Riocan Avenue.

3.2 Water Supply Servicing Design

Per the 2006 *CDP* and *Kennedy Burnett Potable Water Master Servicing Study* (Stantec 2014), the subject lands were considered to be serviced a local network of watermains connecting to trunk watermains running within Longfields Drive and through the SNTC.

The study area is proposed to be serviced by a 150 mm diameter internal watermain network with three connections to the existing watermains within Glenroy Gilbert Drive, Chapman Mills Drive, and Riocan Avenue. Block A, to the north of Glenroy Gilbert, is serviced by a 150 mm watermain system with two connections to the 200 mm watermain being extended along Glenroy Gilbert Drive. 50mm services are extended from this 150mm system. The proposed watermain network is shown in *Drawings 3-4.* The units in Blocks A and B that do not have an underground garage will be equipped with individual water meters and have their own water service. The sizing of the proposed watermain network is based on the *Water Supply Guidelines* summarized in *Table 3.1* below.

Table 3.1: Water Supply Design Criteria

Design Parameter	Value
Residential – Stacked Townhouse	2.1 p/unit
Residential Average Daily Demand	280 L/d/p
Residential – Maximum Daily Demand	2.5 x Average Daily Demand 4.9 x Average Day Demand
Residential – Maximum Hourly Demand	5.5 x Maximum Daily Demand 7.4 x Average Day Demand
Minimum Watermain Size	150 mm diameter
Minimum Depth of Cover	2.4 m from top of watermain to finished grade
During normal operating conditions desired operating pressure is within	350 kPa and 480kPa
During normal operating conditions pressure must not drop below	275 kPa
During normal operating conditions pressure must not exceed	552 kPa
During fire flow operating pressure must not drop below Notes:	140 kPa

- Block A Peaking Factors based on MOE (MECP) Table 3-3 Design Guidelines For Drinking-Water Systems (2008)
- Block B Peaking Factors based on Section 4: Ottawa Design Guidelines, Water Distribution (July 2010), Table 4.1 Per Unit Populations and Table 4.2 – Consumption Rates for Subdivisions of 501 to 3,000 Persons.
- No Outdoor Water Demand considered for residential uses.
- Residential Average Daily Demand assumed to be 280 L/dP in accordance with 2018 changes to Sanitary Design Guidelines, see Section 4.0.

A summary of the anticipated water demands for the study area are summarized in **Table 3.2**. Boundary conditions have been provided by the City of Ottawa based on these demands, and can be found in **Appendix B**.

Table 3.4: Summary of Water Demands

Dwelling Type	Number of Units	Population per unit	Allocated Demand	Avg Day (L/min)	Max Day 2.5 x Avg Day (L/min)	Peak Hour 5.5 x Max Day (L/min)	Fire Flow Demand (L/min)
Block B	544	2.1	280 L/d/P	222.3	555.6	1222.7	17000.0

Dwelling Type	Number of Units	Population per unit	Allocated Demand	Avg Day (L/min)	Max Day 4.9 x Avg Day (L/min)	Peak Hour 7.4 x Avg Day (L/min)	Fire Flow Demand (L/min)
Block A	60	2.1	280 L/d/P	24.5	120.1	181.3	17000.0

The fire flows are calculated in accordance with the Fire Underwriters Survey's Water Supply for Public Fire Protection Guideline (1999) as amended by ISTB-2014-02 & ISTB-2018-02.

- Type of construction: Wood Frame Construction;
- Sprinkler protection: Non-Sprinklered

The result of these parameters is an estimated fire flow of approximately 17,000 L/min. Detailed calculations are presented in *Appendix B*.

The boundary conditions provided by the City of Ottawa for use in the hydraulic analysis related to the subject site are summarized in *Table 3.3*. Correspondence with the City of Ottawa related to boundary conditions is included in *Appendix B*.

Table 3.5: Boundary Conditions

	Connection 1 (Riocan Ave.) 102.2m Ground Elev.		(Glenroy G	Connection 2 (Glenroy Gilbert Drive) 99.3m Ground Elev		Connection 3 (Chapman Mills Drive) 94.7m Ground Elev	
Condition	HGL (m)	Pressure (psi)	HGL (m)	Pressure (psi)	HGL (m)	Pressure (psi)	
Max HGL	147.9	64.9	147.9	69.1	147.9	69.1	
Peak Hour	145.4	61.3	145.4	65.5	145.4	65.5	
Max Day + Fire 1 (283.33 L/s)	129.0	38.1	138.7	56.0	144.9	71.2	

3.2.1 Watermain Modelling

A hydraulic analysis was completed for the study area. The analysis, including the watermain network configuration and sizing, is provided in *Appendix B*.

Modelling was carried out for minimum hour, peak hour and maximum day plus fire flow. Modelling results shown in *Table 3.4* indicate that the development can be adequately serviced for minimum hour and peak hour criteria.

Table 3.6: Summary of Available Service Pressures

Average Day Demand	Peak Hour Demand
Maximum Pressure	Minimum Pressure
55.36 m (543 kPa)	46.93 m (431kPa)

The results presented in the table above indicate that the pressures during average day demand are not quite within the OSDG best practices for new water distribution systems to operate between 350 kPa and 480 kPa however, they are below the maximum allowable pressure of 552 kPa. The use of pressure reducing valves may be recommended during construction should the actual pressure in the watermain exceed what has been used for the boundary conditions.

Per *Table 3.1*, the minimum allowable pressure under fire flow conditions is 140 kPa (20 psi) at the location of the fire. A summary of available fire is shown below in *Table 3.5*. Further details can be found in *Appendix B*.

Table 3.7: Summary of Available Fire Flows

Required Fire Flow	Minimum Pressure
17000 (L/min)	14.64m (143.57kPa)

3.3 Fire Hydrant location

Fire Hydrant location were provided by a fire consultant Vortex Fire Protection Inc. The Hydraulic analysis presented above is based on the fire hydrant locations provided by Vortex Fire Inc. The Hydrants were laid out by Vortex Fire Protection Inc. to ensure a minimum distance of 45m between any opening and the nearest fire hydrant. Our understanding is that this requirement is not conformant to Section 3.10.3.4 of the Ontario Building code. The acceptability of this should be verified by the City and/or fire services to ensure conformance. The layout provided to DSEL by Vortex Fire Protection Inc. has been added to *Appendix B*.

3.4 Water Supply Conclusion

The proposed watermain network conforms to all relevant City and MECP *Water Supply Guidelines*. The hydraulic analysis of the proposed watermain network, concludes that all required domestic and fire flows can be met throughout the study area upon full buildout of the development. Anticipated fire flow requirements can be met throughout the development lands according to City Guidelines and ISTB-2018-02.

4.0 WASTEWATER SERVICING

4.1 Existing Wastewater Services

The study area lies within the South Nepean Collector Sewer (SNC) catchment. The SNC sewer operates at the intersection of Jockvale Road and Longfields Drive before conveying wastewater under the Jock River. A 200 mm diameter sanitary sewer exists within the Glenroy Gilbert Drive ROW and a 250 mm diameter sanitary sewer exists in the Longfields Drive ROW.

4.2 Wastewater Design

The South Nepean Town Centre Community Design Plan Preliminary Serviceability Report (CCL, December 2005) and the South Nepean Collector: Phase 2, Hydraulics Review, Technical Memorandum (Novatech, August 2015) identify the outlet for the development area as the South Nepean Collector Trunk sanitary sewer.

In March 2018, the City of Ottawa provided DSEL with the latest sanitary drainage information for the Longfields Drive sanitary sewer. This information includes conceptual drainage area plans for the Barrhaven Town Centre prepared by David McManus Engineering in February 2010 and a sanitary design sheet prepared by the City of Ottawa in October 2016. We have since been made aware of updates to the March 2018 sanitary drainage areas as zoning by-law amendments have been updated to reflect higher density developments. An amalgamated design sheet has been therefore been provided in *Appendix C* to include the new drainage plans and updated population count. The spreadsheet indicates that there is still sufficient in the existing Longfields sanitary sewer to accept the projected peak flows from the Barrhaven Town Centre development.

The proposed development area is to be serviced by two internal gravity sewer systems directing flows to the existing Longfields Drive sanitary sewer. The block to the north will be serviced by 200 mm dia. sewers directed to the extended Glenroy Gilbert Drive and connecting to the existing sewer that connects to Longfields Drive. The block to the south will be serviced by 250 m dia. sewers directed to the future Chapman Mills Drive (CMD) and connecting to existing sewers on future CMD. The proposed sanitary sewer network is presented in *Drawings 3-4.*

The sanitary sewer network was designed in accordance with the wastewater design parameters from ISTB-2018-01 and the *Sewer Design Guidelines*, summarized in *Table* **4.1** below.

Table 4.1: Wastewater Design Criteria

Design Parameter	Value			
Residential Stacked Townhouse	2.1 p/unit			
Average Daily Demand	280 L/d/per			
Peaking Factor	Harmon's Peaking Factor. Max 4.0, Min 2.0			
_	Harmon Correction Factor 0.8			
Infiltration and Inflow Allowance	0.33 L/s/ha			
Sanitary sewers are to be sized employing the	$\frac{1}{2} \frac{1}{2} \frac{2}{3} \frac{1}{3} \frac{1}{3}$			
Manning's Equation	$Q = \frac{1}{n} A R^{\frac{2}{3}} S^{\frac{1}{2}}$			
Minimum Sewer Size	200 mm diameter			
Minimum Manning's 'n'	0.013			
Minimum Depth of Cover	2.5 m from crown of sewer to grade			
Minimum Full Flowing Velocity	0.6 m/s			
Maximum Full Flowing Velocity	3.0 m/s			
Extracted from Sections 4 and 6 of the City of Ottawa Sewer Design Guidelines, October 2012,				
Technical Bulletins, and recent residential subdivisions in the City of Ottawa.				

A flow allocation of 1.71 L/s was allocated for the Glenroy Gilbert Drive extension and 18.54 L/s at the Longfields Drive Intersection with future Chapman Mills as per the Longfields drive sewer design sheet provided by the City and included in Appendix C.

Table 4.2: Wastewater Peak Flow

		Population		Allacatad	Aven			Dools	
Area (Ha.)		Number of Units	Persons per unit	Population	Allocated Demand (L/c/d)	Avg Day (L/s)	I/I (L/s)	Peak Factor	Peak Flow (L/s)
Block A & Glenroy Gilbert Extension	0.64	60	2.1	126	280 L/c/d	0.41	0.21	3.57	1.67
Block B	4.19	544	2.1	1142	280 L/c/d	3.70	1.38	3.21	13.26
Total	5.21	604							14.93

A wastewater peak flow for the proposed development 14.93 L/s was calculated based on the parameters presented in *Table 4.1*. The peak flow is less than the allocated flow for the BTC Phase 1 lands based on the Longfields Drive sanitary design sheet. Based on the sanitary design sheet for Longfields Drive presented in *Appendix C* there is sufficient residual capacity in the receiving sewer system to accommodate the development.

4.3 Wastewater Servicing Conclusions

The proposed wastewater system for the development area is designed to conform to all relevant City Standards and MECP Guidelines. Two networks of local sanitary sewers are proposed to serve the study area directing flows towards the existing sanitary sewer in the Longfields Drive ROW. The South Nepean Collector sanitary sewer has been sized for the long-term development of the SNTC lands, which includes the study area.

5.0 STORMWATER MANAGEMENT

5.1 Existing Stormwater Drainage

The study area is considered to be within the planned catchment of the existing stormwater management facility (SWMF) east of Longfields Drive and south of Paul Metivier Drive. The existing storm sewers surrounding the study area are depicted in **Drawings 3-4** and can be summarized as:

- 600 mm diameter storm sewer within the Glenroy Gilbert Drive ROW,
- ➤ 1650 mm diameter trunk storm sewer within the future extension of the Riocan Avenue ROW.
- ➤ 1500 mm diameter trunk sewer within the Longfields Drive ROW running south of Glenroy Gilbert Drive, and,
- 750 mm diameter storm sewer at future Chapman Mills Drive.

5.2 Stormwater Management Criteria

Consistent with *Nepean South Chapman Mills Stormwater Management Servicing* (IBI Group, February 16, 2018), the study has been considered to be part of the tributary area of the existing SWMF east of Longfields Drive. Flows from the study area were considered to drain to the SWMF via existing sewers on Glenroy Gilbert Drive and Longfields Drive. Excerpts from the report can be found in *Appendix D*.

The following criteria was considered as part of the stormwater management strategy within the study area and conveyance to the existing SWMF east of Longfields Drive, among other requirements:

Storm sewers on local roads are designed to provide a minimum 2-year level of service per the City's latest Technical Bulletin PIEDTB-2016-01. Collector and arterial roads are to provide a 5-year and 10-year level of service respectively.

Under full flow conditions, the allowable velocity in storm sewers is to be no less than 0.80 m/s and no greater than 6.0 m/s.

For the 100-year storm and for local and collector roads, the maximum depth of water (static and/or dynamic) on streets, rear yards, public space, and parking areas shall not exceed 0.35 m at the gutter. For arterial roads, no barrier curb overtopping is permitted.

No surface ponding on the subject site, or local roads, during the 2-year event.

The major system is designed with sufficient capacity to allow the excess runoff from storms above the 100-year storm to be conveyed within the public ROW or adjacent to the right-of-way provided that the water level must not touch any part of the building envelope, and must maintain 15 cm vertical clearance between spill elevation on the street and the ground elevation at the nearest building envelope.

The proposed stormwater management strategy for the study area is to respect the 100-year storm sewer capture rate of 784 L/s from the development area that is set out in the *Nepean South Chapman Mills Stormwater Management Servicing* (IBI Group, February 16, 2018) and summarized below.

- ➤ Block A & Glenroy Gilbert Drive: 147.0 L/s 100-year release rate to the proposed storm sewer in the Glenroy Gilbert Drive ROW
- ➤ Block B: 637 L/s 100-year release rate to the proposed storm sewer in the Chapman Mills Drive ROW

5.3 Stormwater Management Strategy

Stormwater runoff will be directed to a series of catch basins located at sags that will collect the runoff and discharge to the minor system. Underground storage tanks will be utilized to store excess runoff generated by larger storm events in order to respect the allocated release rate for the site set out by the Nepean South Chapman Mills Stormwater Management Servicing design brief.

5.3.1 Minor System

The study area is to be serviced by a storm sewer system designed in accordance with the amendment to the storm sewer and stormwater management elements of *PIETB-2016-01*. As described in **Section 5.2**, the minor storm system is proposed to be designed for a minimum of the 5-year event as the site is comprised of private parking areas.

The proposed gravity storm sewer network within the private site ranges from 250 mm to 675 mm dia. To service the block B, a 750 mm dia. storm sewer will be installed and connected to the existing 750mm dia. storm sewer within the future Chapman Mills Drive ROW. Similarly, a 450 mm and 525 mm dia. storm sewer will be extended along the Glenroy Gilbert Drive extension ROW to service the Block B. The proposed sewers collect stormwater runoff from the Minto Barrhaven Town Centre – Stage 1 development and directs stormwater to Longfields Drive. There is an existing 1500 mm dia. storm sewer located in the Longfields Drive ROW, this sewer directs flow south to the existing SWMF east of Longfields Drive and north of the Jock River.

The South Nepean Chapman Mills hydraulic model was reviewed to establish 100-year HGL levels on the 1500 dia. storm sewer on Longfields drive near the BTC Stage 1 outlet locations. The review determined that the HGL levels are below the obvert at the connection locations of this site and a flow allocation was given to BTC stage 1. As the allocated release rate is being respected, the receiving sewer system is expected to remain free-flowing. Therefore, an on-site HGL analysis was not undertaken.

Table 5.1 summarizes the standards that have been employed in the detailed design of the storm sewer network, meeting the criteria described in **Section 5.2**.

Table 5.1: Storm Sewer Design Criteria

Design Parameter	Value			
Minor System Design Return Period	Per requirements in the Nepean South Chapman Mills Stormwater Management Servicing (IBI Group, February 16, 2018). Sewers to be sized per 2-Year (Local Streets), 5- Year (Collector Streets), 10-Year (Arterial Streets)			
	– PIEDTB-2016-01			
Major System Design Return Period	100-Year			
Intensity Duration Frequency Curve (IDF)	A			
2-year storm event:	$i = \frac{1}{(t + B)^C}$			
A = 723.951, B = 6.199, C = 0.810	$(t_c + B)^{\circ}$			
5-year storm event:				
A = 998.071, B = 6.053, C = 0.814				
Minimum Time of Concentration	10 minutes			
Rational Method	Q = CiA			
Runoff coefficient for paved and roof areas	0.90			
Runoff coefficient for landscaped areas	0.20			
Storm sewers are to be sized employing the Manning's Equation	$Q = \frac{1}{n} A R^{\frac{2}{3}} S^{\frac{1}{2}}$			
Minimum Sewer Size	250 mm diameter			
Minimum Manning's 'n'	0.013			
Minimum Depth of Cover	2 m from crown of sewer to grade			
Minimum Full Flowing Velocity	0.8 m/s			
Maximum Full Flowing Velocity	6.0 m/s			
Extracted from City of Ottawa Sewer Design Guidelines, October 2012, as amended by PIEDTB-2016-01, and based on recently approved residential subdivision designs in City of Ottawa.				

5.3.2 Quality Control

The storm outlets are tributary to the existing SWMF east of Longfields Drive and south of Paul Metivier Drive. This facility provides end of pipe quality control and as such, no quality control is provided on-site.

5.3.3 Quantity Control

Minor system allowable release rates were established for both outlets based the existing reports as described in **Section 5.3**. Excess runoff during larger storm events will be stored in underground tanks where the flow will be directed to the minor system at a controlled rate.

Stormtech Chambers are being proposed to accomplish the required storage volumes. Street drainage will be directed towards catch basins that outlet to the storage chambers. The chambers will be connected upstream of maintenance holes that will be equipped with ICDs which will restrict the flow to the allowable release rates established in section 5.3. These storage chambers are "offline" to the network that collects the foundation drainage. As the storm sewer system that conveys foundation drainage is not upstream of any inlet control devices, basements will remain protected should the tank outlets become obstructed or plugged.

5.4 Stormwater Management Calculations

The modified rational method (MRM) was used to size the storage tanks and at-grade ponding to ensure that allowable release rates are respected. Any uncontrolled flow was subtracted to the total controlled flow rate to ensure the sum of the controlled and uncontrolled peak runoffs respect the allowable release rates. The tables below provide a summary of the MRM calculations, detailed calculations are provided in Appendix D.

Control Area 5-year 5-year 100-Year 100-Year 100-Year Release Required Release Required **Available** Rate Storage Rate **Storage** Storage (L/s) (m3)(L/s) (m3)(m3)**Unattenuated Areas** 61.6 0.0 61.6 0.0 0.0 (CB9 - CB14) DCB 15 20.1 0.0 24.3 24.1 25.1 **DCB 16** 16.0 0.0 31.8 18.0 21.2 STM108 10.0 6.8 21.8 60.1 60.1 STM105 5.0 45.4 7.6 117.2 117.9 STM101 6.7 14.5 10.7 40.6 40.6 Total 116.8 81.7 146.3 259.9 264.9

Table 5.2: Stormwater Storage Requirements for Block A

As indicated in **Table 5.2** the allowable release rate of 147 L/s prescribed under the Nepean South Chapman Mills SWM servicing report has been respected. In order to achieve the allowable release a total storage volume of 259.9m³ will be required. Three Stormtech chambers are being proposed in addition to surface storage to achieve this requirement as shown in **Drawings 3 and 4**.

Table 5.3: Stormwater Storage Requirements for Block B

Control Area	5-year Release Rate	5-year Required Storage	100-Year Release Rate	100-Year Required Storage	100-Year Available Storage
	(L/s)	(m3)	(L/s)	(m3)	(m3)
Unattenuated Areas					
Glenroy Gilbert	29.7	0.0	50.8	0.0	0.0
Riocan	25.6	0.0	43.8	0.0	0.0
Chapman Mills	65.4	0.0	111.9	0.0	0.0
Longfields	26.0	0.0	44.5	0.0	0.0
Attenuated Areas					
STM115	46.6	41.4	69.5	134.6	135.1
STM126	10.9	38.2	21.7	103.2	105.5
STM124	7.6	104.8	9.5	272.7	275.1
STM134	86.5	6.9	141.3	76.2	79.7
STM164	6.5	78.3	11.3	200.0	203.5
STM159	6.7	81.5	13.0	206.4	210.3
STM149	54.3	19.0	119.1	74.4	74.8
Total	365.9	370.1	636.6	1067.6	1084.1

As indicated in *Table 5.3* the allowable release rate of 637 L/s prescribed under the Nepean South Chapman Mills SWM servicing report has been respected. In order to achieve the allowable release a total storage volume of 1067m³ will be required. A number of Stormtech chambers are being proposed in order to achieve this requirement as shown in *Drawings 3 and 4*.

The Modified Rational Method was originally intended to be used for above grade storage where the change in head applied through the orifice equation had little variation. As the release rates fluctuate from maximum peak flow for underground storage due to the varying head, the variation in head has been accounted for in the storage volume calculations. Average release rate calculated using the orifice equation were used to size the tanks. Maximum release rates were verified (maximum head) to ensure the maximum allowable was respected. Complete stormwater management calculations are presented in *Appendix D*.

5.5 Grading & Drainage

The elevations drop significantly between Glenroy Gilbert and the future Chapman Mills. As such, terracing and retaining walls are being proposed at strategic locations across the site. The grading plan has been developed to provide adequate drainage and allow landscape features to be incorporated within the site. Detailed grading design is presented in **Drawings 5 and 6**. Major overland flow routes have been designed to safely convey water to municipal ROWs should there be any blockages in drainage structures.

5.6 Stormwater Servicing Conclusions

A network of local gravity sewers is proposed within the study area to capture stormwater and convey the flows to the proposed trunk storm sewer network. The storm sewers have been sized by the rational method and inlet control devices and orifices are used to maintain the allowable release to the existing minor system. Quality control will be achieved via existing stormwater management facilities.

6.0 EROSION AND SEDIMENT CONTROL

Soil erosion occurs naturally and is a function of soil type, climate, and topography. The extent of erosion losses is exaggerated where vegetation has been removed during construction and the top layer of soil becomes agitated, and where increased stormwater runoff is directed to natural areas.

Prior to earthworks or underground construction, erosion and sediment controls will be implemented and will be maintained throughout construction.

The erosion and sediment controls will include (but are not limited to):

Minimize the area to be cleared and grubbed.

Plan construction at proper time to avoid flooding.

Provide sediment traps and basins during dewatering.

Silt fence to be installed around the perimeter of the site and to be cleaned and maintained throughout construction. Silt fence to remain in place until the working areas have been stabilized and re-vegetated. See **Drawings 11 & 12.**

A mud mat to be installed at the construction access in order to prevent mud tracking onto adjacent roads.

Catch basins to have inserts installed under the grate during construction to protect from silt entering the storm sewer system.

Extent of exposed soils to be limited at any given time, and exposed areas will be revegetated as soon as possible.

Exposed slopes to be protected with plastic or synthetic mulches.

Stockpiles of cleared materials as well as equipment fueling and maintenance areas to be located away from swales, watercourses, and other conveyance routes.

Seepage barriers such as silt fencing, straw bale check dams and other sediment and erosion control measures to be installed in any temporary drainage stormwater conveyance channels and around disturbed areas during construction and stockpiles of fine material.

Filter inserts to remain on open surface structures such as manholes and catch basins until these structures are commissioned and put into use, streets are asphalted and curbed, and the surrounding landscape is stabilized.

The contractor will, at every rainfall, complete inspections and guarantee proper performance. The inspection is to include:

- Verification that water is not flowing under silt barriers.
- Clean and change inserts at catch basins.

A qualified Inspector will give recommendations related to the mitigation measures that are being implemented and maintained. Bulkhead barriers, filter clothes on open surface structures, silt fencing, and other E&SC measures may require removal of sediment and repairs. The City of Ottawa's Protocol for Wildlife Protection is to be followed during construction.

After build-out of the development, applicable sewers will be inspected and cleaned. All sediment and construction fencing should be removed following construction, providing there is no exposed soil or other potential sources of sedimentation.

7.0 CONCLUSIONS AND RECOMMENDATIONS

This Design Brief has been prepared on behalf of Minto Communities - Canada.

This Design Brief is to be read in conjunction with the first submission of the Minto Barrhaven Town Centre – Stage 1 detailed engineering drawing package, dated June 30, 2023

The key features of the detailed design of the proposed development are as follows:

- ➤ Three connections will be made to the existing watermains located on Riocan Avenue, Glenroy Gilbert Drive, and Chapman Mills Drive. The proposed watermain network conforms to all relevant City and MECP *Water Supply Guidelines*.
- ➤ Wastewater service will be provided through gravity sewers that have generally been designed in conformance with all relevant City of Ottawa and MECP Guidelines and Policies. A series of gravity sewers will direct wastewater to an existing sewer on Longfields Drive.
- Stormwater management will be achieved using a series of local storm sewers and retention tanks that collect surface water. Two connections to the existing Longfields Drive storm sewer will be made and established release rates for the system will be respected.

The infrastructure identified in this Design Brief is expected to require approval from the City of Ottawa, Ontario Ministry of the Environment, Conservation and Parks prior to construction.

Prepared by, **David Schaeffer Engineering Ltd.**



Per: Alexandre Tourigny, P.Eng.

Reviewed by, **David Schaeffer Engineering Ltd.**





Per: Laurence Coulson, P.Eng.

© DSEL

APPENDIX A

Legal Plan and Site Plan City of Ottawa Correspondence





A100 SCALE: NTS

A100 SCALE: NTS

A¹⁰¹/ SCALE: N.T.S.

File:H:\Acad SRN Projects\S21001 - Minto.BarrhavenTownCentre.Ottawa.GR\ACAD Drawings\02 WORKING\S21001-SP-100.dwg Plotted: Jun 26, 2023 By:AndrewB

THESE DRAWINGS ARE NOT TO BE SCALED: ALL DIMENSIONS MUST BE VERIFIED BY CONTRACTOR PRIOR TO COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES MUST BE REPORTED DIRECTLY TO SRN ARCHITECTS INC.

> BICYCLE PARKING, REFER TO LANDSCAPE DRAWINGS BARRIER FREE PARKING RESIDENT PARKING

FOR SITE GRADING AND SERVICING REFER TO CIVIL DRAWINGS

PRELIMINARY, NOT FOR CONSTRUCTION ALL AREAS CALCULATIONS ARE

8395 JANE STREET, SUITE 203

Minto Communities Canada

SCALE: 1:500 CHECKED BY: GR DRAWING NUMBER:

3M

9.1M

MIN. SEPARTION BETWEEN BUILDINGS (WITHIN A PUD):

Braden Kaminski

From: Moore, Sean <Sean.Moore@ottawa.ca>
Sent: Thursday, November 5, 2020 12:07 PM

To: Carl Furney; Bronwyn Anderson

Cc: Shillington, Jeffrey; Krabicka, Jeannette; Young, Mark; Rehman, Sami; Gervais, Josiane;

Neermul, Dhaneshwar; Richardson, Mark; Siddigue, Jabbar

Subject: Minto Barrhaven Town Centre preconsult

Attachments: 201023_BTC-Minto_PFP preconsult comments.pdf; SNTC - Minto Pre-Consult -

Illustration.pdf; SNC-Sanitary Drainage Areas.pdf; SWM-DrainagePlan.pdf;

Minto_BTC_design_brief_submission requirements.pdf

Carl and Bronwyn,


Regarding our pre-consultation meeting on October 22, 2020 for a plan of subdivision and rezoning on our lands in the Barrhaven Town Centre please find the submission requirements and preliminary comments below:

List of required Plans/Reports with your Plan of Subdivision and Zoning By-law Amendment applications:

Required Plans/Studies:

- Draft Plan of Subdivision
- Survey Plan
- Planning Rationale, with Integrated Environmental Review please include a Parks rationale for the park location, size, configuration and how it meets the parks policies / guidelines of the City of Ottawa
- Urban Design Brief see ToR attached
- Stormwater Management Report / Brief
- Serviceability Study
- Transportation Impact Assessment
- Noise Feasibility Study should also address proximity of residential to the LRT tail track south of Chapman Mills
 Drive
- Vibration Study should address the proximity of residential to the LRT tail track south of Chapman Mills Drive
- Geotechnical Study
- Phase 1 ESA to conformity with OReg 153/04 (and subsequent Phase 2 and or 3 ESA's if required)
- Tree Conservation Report
- Archaeological Resource Assessment
- Roadway Modification Plan for functional design of any road mods / intersections / medians etc
- Concept Plan ultimate use of lands
- Environmental Impact Statement please address the water course shown below and butternut trees in your
 EIS

Watercourse to address in EIS:



All required plans & reports are to be provided in digital format (.pdf through an FTP site) at application submission and sent to planningcirculations@ottawa.ca and cc'd to myself. Please ensure the application forms for plan of subdivision and zoning are also scanned and sent as a pdf to this email. Once received we will create the file numbers for you and advise of them, so you can make payment at a Client Service Centre.

Link to Planning Application process

https://ottawa.ca/en/planning-development-and-construction/developing-property/development-application-review-process

Link to development application forms:

https://ottawa.ca/en/planning-development-and-construction/developing-property/development-application-review-process/development-application-submission/development-application-forms

Preliminary Staff Comments:

Parks Planning

1. See attached comments entitled 'BTC Minto PFP preconsult comments'

Urban Design:

- 2. Proposed units facing Riocan Avenue should be designed to allow for additional at grade uses in the future (home based business) or local scale commercial given the "active frontage" designation in the Secondary Plan.
- 3. Consider re-aligning the access street from Riocan Avenue to allow for a larger multiresidential block at the north end of the subject site.
- 4. Sidewalks should be provided on local streets as directed in the Secondary Plan. Please review cross-section widths to ensure that adequate space is provided for sidewalks and tree planting.
- 5. Please ensure building setbacks allow for tree planting in accordance with the 2017 Sensitive Clay Soils direction.

- 6. PRUD supports the comments provided by Parks and Facilities Planning as it relates to the size and contiguous shape for the Linear Park proposed on the western end of the lands.
- 7. Additional analysis should be undertaken to ensure that the design for a bus-loop and park and ride do not hinder future development opportunities on Minto's abutting lands. It is suggested that a public or "private" north/south street be introduced as a division between the proposed park and ride and the future development block to the west. This new street could also serve as access to the bus-loop which could be located along the northern edge of the site (mid-block)
- 8. Illustration provided in attachment entitled 'SNTC Minto Pre-Consult illustration'

Engineering:

- 9. For SWM the latest document produced was the Nepean South-Chapman Mills SWM Servicing Addendum. See the excerpt showing the Drainage Area Plan for the area. It shows an existing trunk storm sewer within future Riocan Drive just north of the existing pond. This storm sewer will need to be extended into their subdivision. Major Overland Flow is be conveyed through the City owned lands just south of the subject lands and continue through the Minto built Riverbend subdivision and Major Overland Flow outfall to the Jock River.
- 10. For Sanitary, South Nepean Collector: Phase 2 Hydraulic Review/Assessment completed by Novatech was completed in August 2015. I've attached an excerpt that shows the South Nepean Collector extending just north of the Jock River. There is a 1050 mm on Longfields that extends from the SNC up to the future RioCan ROW. Minto can connect to the 1050 mm dia. at Longfield's and future Riocan (capacity subject to review by Infrastructure Policy).
- 11. For water, Minto is to construct a 305 mm dia. watermain within the Chapman Mills Road corridor.

General Planning comments:

- 1. Please ensure a signalized intersection is planned for Riocan Ave and Chapman Mills Drive and removed from Sue Holloway Drive and Chapman Mills.
- 2. On your concept plan please illustrate a park on the 'civic block' lands, representing the urban public square
- 3. On your concept plan please illustrate the park and ride on the lands west of the civic block
- 4. Please follow the Barrhaven Downtown Secondary Plan on the general placement of Park #6 do not create any road patterns that force its location along Longfields Drive
- 5. The City will be looking for the dedication of the re-aligned BRT/LRT corridor as per the EA that went to Committee on Nov 2nd 2020
- 6. The City will engage Minto on discussions concerning the proposed park and ride lot, and the civic block.
- 7. We need to assess the viability of tree planting with soil types, proposed zoning setbacks, and street cross sections (please speak to soils in this Geotech as it relates to tree planting and make recommendations in the Planning Rationale concerning this)

Transportation:

- Follow Traffic Impact Assessment Guidelines
 - Traffic Impact Assessment will be required. Please proceed to submitting Screening/Scoping at your earliest convenience.
 - Start this process asap. The application will not be deemed complete until the submission of the draft step 1-4, including the functional draft RMA package (if applicable), draft functional plans (if applicable) and/or monitoring report (if applicable).
 - Request base mapping asap if RMA is required. Contact Engineering Services (https://ottawa.ca/en/city-hall/planning-and-development/engineering-services)

- All new collector streets within the subdivision should be designed following the City's Collector Guidelines (desired 26m ROW for collector Roads).
- All new local residential streets should be designed with a target operating speed of 30km/h
 per the new Strategic Road Safety Action Plan Update. A 30 km/h Design Guideline with
 further guidance on how to achieve a 30km/h target for new roadways is being developed.
 TES may be contacted for interim guidance on how to achieve a 30km/h design speed on local
 streets.
- Corner triangles as per OP Annex 1 Road Classification and Rights-of-Way at the following locations on the final plan will be required:
 - Local Road to Local Road: 3 m x 3 m
 - Local Road to Collector Road: 5 m x 5 m
 - Collector Road to Collector Road: 5 m x 5 m
 - Collector Road to Arterial Road: 5 m x 5 m
- ROW protection on Greenbank between Strandherd and Chapman Mills is 37.5m even and from Chapman Mills to Cambrian is 41.5m (Subject to varying widening requirements of Greenbank Road ESR).
- ROW on Longfields between Strandherd and Jockvale is 37.5m even.
- The Greenbank Road realignment construction is anticipated for post-2031.
- RMA is underway at the Greenbank Rd/Street E intersection.
- Geometric Road Design drawings will be required with the first submission of underground infrastructure and grading drawings.
- Noise Impact Studies are required. Feasibility Study required before draft approval and Detailed Study required before registration. Both studies must assess:
 - Road
 - o Rail, due to the proximity to the future LRT.
 - o Aircraft, site falls within Airport Vicinity Development Zone.
 - Stationary (due to the proximity to neighbouring exposed mechanical equipment) or (if there will be any exposed mechanical equipment due to the proximity to neighbouring noise sensitive land uses)

Forestry

- 1. a Tree Conservation Report (TCR) must be supplied for review along with the suite of other plans/reports required by the City; an approved TCR is a requirement for Plan of Subdivision approval.
- 2. any removal of privately-owned trees 10cm or larger in diameter requires a tree permit issued under the Urban Tree Conservation Bylaw; the permit is based on the approved TCR
- 3. any removal of City-owned trees will require the permission of Forestry Services who will also review the submitted TCR
- 4. the TCR must list all trees on site by species, diameter and health condition
- 5. the TCR must list all trees on adjacent sites if they have a critical root zone that extends onto the development site
- 6. If trees are to be removed, the TCR must clearly show where they are, and document the reason they cannot be retained
- 7. the City encourages the retention of healthy trees; if possible, please seek opportunities for retention of trees that will contribute to the design/function of the site.
- 8. Please ensure newly planted trees have an adequate soil volume for their size at maturity. Here are the recommended soil volumes:

Tree Type/Size	Single Tree Soil	Multiple Tree Soil
	Volume (m3)	Volume (m3/tree)
Ornamental	15	9

Columnar	15	9
Small	20	12
Medium	25	15
Large	30	18
Conifer	25	15

9. For more information on the process or help with tree retention options, contact Mark Richardson mark.richardson@ottawa.ca

Regards,

Sean Moore, RPP/MCIP
Senior Planner
Development Review South Unit
Planning, Infrastructure and Economic Development Dept.
City of Ottawa

Cell: 613-805-9804

- Please note I am working from home during this crisis until further notice

This e-mail originates from the City of Ottawa e-mail system. Any distribution, use or copying of this e-mail or the information it contains by other than the intended recipient(s) is unauthorized. Thank you.

Le présent courriel a été expédié par le système de courriels de la Ville d'Ottawa. Toute distribution, utilisation ou reproduction du courriel ou des renseignements qui s'y trouvent par une personne autre que son destinataire prévu est interdite. Je vous remercie de votre collaboration.

•



PRE-CONSULTATION COMMENTS Parks & Facilities Planning

Project: Barrhaven Town Centre - Minto

Date: 23 October, 2020

1. Parkland Dedication

The Parkland Dedication By-Law calls for the dedication calculation for the Barrhaven Town
 Centre to be 5% of the gross land area of the area

- The current plan shows land conveyance of 2.15% / 0.50 ha (according to the chart on the Concept Plan). Therefore, the land conveyance shown in the development concept is significantly under-dedicated.
- Based on a development area of 23.26 ha, and a calculation of 5% of the gross area, the parkland dedication needs to be a minimum of 1.161 ha
- Parks & Facilities Planning is looking for the parkland dedication to be wholly fulfilled through land conveyance for the gross development area within the currently proposed subdivision.

2. Park shape and location

Please provide a contiguous park block with no road crossings.

3. Timing

The park block shown as '8' on Schedule A: Land Use Plan of the Barrhaven Town Centre Secondary Plan is to be dedicated in the first Draft Plan of Subdivision for the property.

4. To be included in the 1st Submission

- Please show a revised park block
- Please show high level park grading on the on the subdivision Preliminary Grading plan including key spot elevations, flow arrows and slope percentages. Keep in mind that:
 - Park is to be graded to subdivision levels
 - Show positive surface drainage towards the ROW
 - The park is to have <u>no</u> encumbrances or easements either below or above ground level. This includes any current or future LRT requirements, utilities, etc. It also includes any stormwater flows from neighbouring properties.
- Please include the parkland dedication as part of the Planning Rationale provide an explanation of how the proposed development will address and meet the Parkland Dedication requirements.
- Please include the park block specifically as part of the Geotechnical Report please include text that speaks to the suitability of the soils for construction and load bearing, and any potential required amendments to make it suitable (if needed).
- Confirmation that there are no existing or proposed encumbrances on the proposed park block.



5. Developer Requirements for Land Conveyance of a Park Block

Please review the following reference documents which outline the requirements for parkland dedication and park block conveyance to the City:

- City of Ottawa Park Development Manual, 2nd edition
- City of Ottawa Parkland Dedication By-Law
- The standard parks Conditions of Draft Plan Approval

6. Concept revision for consideration

Please consider the following revision to the subdivision concept – or similar:



Benefits:

- Park block size is increased to meet dedication requirements
- Road crossing is eliminated
- Parkland dedication is balanced for the entirety of the Minto property
 - Phase 1 Draft Plan: 0.913 ha park
 - Phase 2 Draft Plan: 0.250 ha Civic Centre urban plaza or parkette
- Road frontage along the proposed park is increased
- Park block is adjacent to the LRT tail track. Therefore, the surface of those lands could blend into the park design.

Please don't hesitate to contact me if you have any questions. Regards,

Jeannette.

Jeannette Krabicka Planner, Parks & Facilities Planning City of Ottawa



Alex Tourigny

From: Michael Hanifi <MHanifi@minto.com>

Sent: February 28, 2023 3:20 PM

To: Alex Tourigny Cc: Carl Furney

Subject: RE: Barrhaven Town Centre Unit types

EXTERNAL E-MAIL - Do not click links or open attachments unless you recognize the sender.

Hi Alex,

As a follow up, I was able to retrieve this table from a colleague for the Metro Town product at BTC. The Metro Towns are 2-bedroom units. Hope this helps.

PRODUCT TYPE		MODEL NAME		UNIT TYPE		BUILDING # STOREYS	ELEV.	BED FLOOR SQ FT	MAIN FLOOR SQ FT	TOTAL SQ FT	
	Υ,		*		Y		1			×.	
Stacked		Yorkdale		Lower Interior		3.5 storey	2	581	481	1062	
Stacked		Woodbine		Upper Interior		3.5 storey	2	580	679	1260	
Stacked		Union		Lower End/ Corner		3.5 storey	2	590	490	1081	
Stacked		Leaside		Upper End/ Corner		3.5 storey	2	587	686	1274	
Stacked		Yorkdale		Lower Interior		3.5 storey	2	581	481	1062	
Stacked		Woodbine		Upper Interior		3.5 storey	2	580	679	1260	
Stacked		Union		Lower End/ Corner		3.5 storey	2	590	490	1081	
Stacked		Leaside		Upper End/ Corner		3.5 storey	2	587	686	1274	

Let me know if you need anything else.

Thanks, Michael

Michael Hanifi
Land Development Project Coordinator
MINTO COMMUNITIES - CANADA
200 - 180 Kent Street, Ottawa, ON, K1P 0B6
T 343.961.2615
A division of The Minto Group

Join Our Team! Minto Career Opportunities

You are receiving this email because you may have expressly consented to receive commercial electronic messages from Minto Group of Companies (Minto Properties Inc, Minto Communities Canada Inc., Minto Communities LLC.) and affiliates. To unsubscribe, please **click here**. Contact Minto Group of Companies at 200-180 Kent Street, Ottawa ON K1P 0B6 or 1-877-751-2852. **Click here** to access our privacy policy.

The information in this email is intended solely for the addressee(s) named and may contain privileged, confidential or

personal information. If you have received this communication in error, please reply by e-mail to the sender and delete or destroy all copies of this message. Any other distribution, disclosure or copying is strictly prohibited.

From: Michael Hanifi

Sent: Tuesday, February 28, 2023 1:53 PM **To:** Alex Tourigny <ATourigny@dsel.ca> **Cc:** Carl Furney <CFurney@minto.com>

Subject: RE: Barrhaven Town Centre Unit types

Hi Alex,

It is correct to assume they are 2-bedroom units. I've asked around about if we have a table (I'll get back to you with it if we do). Do you need the latest floor plans or anything else? I'll follow up with the Andrews about your request from yesterday as well.

Thanks, Michael

From: Alex Tourigny <<u>ATourigny@dsel.ca</u>>
Sent: Tuesday, February 28, 2023 1:12 PM
To: Michael Hanifi <<u>MHanifi@minto.com</u>>
Cc: Carl Furney <<u>CFurney@minto.com</u>>
Subject: Barrhaven Town Centre Unit types

Hi Michael,

We assumed the units were mostly 2bedroom units when completing our supporting calculations for BTC. Does Minto have a table with a unit type description (1bed, 2bed, bachelors etc...)?

Thanks,

Alex Tourigny, P.Eng.

DSEL

david schaeffer engineering ltd.

120 Iber Road, Unit 103 Stittsville, ON K2S 1E9

phone: 613-845-2106 (NEW NUMBER)

cell: (343) 542-8847 e-mail: atourigny@dsel.ca

This email, including any attachments, is for the sole use of the intended recipient(s) and may contain private, confidential, and privileged information. Any unauthorized review, use, disclosure, or distribution is prohibited. If you are not the intended recipient or if this information has been inappropriately forwarded to you, please contact the sender by reply email and destroy all copies of the original.

CAUTION: This email originated from outside your organization. Exercise caution when opening attachments or clicking links, especially from unknown senders.

APPENDIX B

Hydraulic Network Analysis

BTC Stage 1 - Block A Proposed Site Conditions

Water Demand Design Flows per Unit Count City of Ottawa - Water Distribution Guidelines, July 2010



Domestic Demand

Type of Housing	Per / Unit	Units	Pop
Single Family	3.4	-	0
Semi-detached	2.7	-	0
Townhouse	2.7	-	0
Apartment			0
Bachelor	1.4	-	0
1 Bedroom	1.4	-	0
2 Bedroom	2.1	60	126
3 Bedroom	3.1	-	0
Average	1.8	-	0

	Pop	Avg. Daily		Max Day		Peak Hour	
		m³/d	L/min	m³/d	L/min	m³/d	L/min
Total Domestic Demand	126	35.3	24.5	172.9	120.1	261.1	181.3

Institutional / Commercial / Industrial Demand

			Avg. [Daily	Max I	Day	Peak I	Hour
Property Type	Unit Rate	Units	m³/d	L/min	m³/d	L/min	m³/d	L/min
Commercial floor space	2.5 L/m ² /d	-	0.00	0.0	0.0	0.0	0.0	0.0
Office	75 L/9.3m ² /d	-	0.00	0.0	0.0	0.0	0.0	0.0
Restaurant*	125 L/seat/d	-	0.00	0.0	0.0	0.0	0.0	0.0
Industrial - Light	35,000 L/gross ha/d	-	0.00	0.0	0.0	0.0	0.0	0.0
Industrial - Heavy	55,000 L/gross ha/d	-	0.00	0.0	0.0	0.0	0.0	0.0
	Total	I/CI Demand	0.0	0.0	0.0	0.0	0.0	0.0
	To	otal Demand _	35.3	24.5	172.9	120.1	261.1	181.3

^{*} Estimated number of seats at 1 seat per 9.3m²

BTC Stage 1 - Block B Proposed Site Conditions

Water Demand Design Flows per Unit Count City of Ottawa - Water Distribution Guidelines, July 2010



Domestic Demand

Type of Housing	Per / Unit	Units	Pop
Single Family	3.4	-	0
Semi-detached	2.7	-	0
Townhouse	2.7	-	0
Apartment			0
Bachelor	1.4	-	0
1 Bedroom	1.4	-	0
2 Bedroom	2.1	544	1143
3 Bedroom	3.1	-	0
Average	1.8	-	0

	Pop	Avg. Daily		Max Day		Peak Hour	
		m³/d	L/min	m³/d	L/min	m³/d	L/min
Total Domestic Demand	1143	320.0	222.3	800.1	555.6	1760.2	1222.4

Institutional / Commercial / Industrial Demand

			Avg. [Daily	Max I	Day	Peak I	Hour
Property Type	Unit Rate	Units	m³/d	L/min	m³/d	L/min	m³/d	L/min
Commercial floor space	2.5 L/m ² /d	-	0.00	0.0	0.0	0.0	0.0	0.0
Office	75 L/9.3m ² /d	-	0.00	0.0	0.0	0.0	0.0	0.0
Restaurant*	125 L/seat/d	-	0.00	0.0	0.0	0.0	0.0	0.0
Industrial - Light	35,000 L/gross ha/d	-	0.00	0.0	0.0	0.0	0.0	0.0
Industrial - Heavy	55,000 L/gross ha/d	-	0.00	0.0	0.0	0.0	0.0	0.0
	Total I	/CI Demand	0.0	0.0	0.0	0.0	0.0	0.0
	To	tal Demand	320.0	222.3	800.1	555.6	1760.2	1222.4

^{*} Estimated number of seats at 1 seat per 9.3m²

Minto BTC Stage 1 (Block 10) FUS-Fire Flow Demand

Fire Flow Estimation per Fire Underwriters Survey

Water Supply For Public Fire Protection - 2020

Fire Flow Required

1. Base Requirement

Type of Construction:

Where \mathbf{F} is the fire flow, \mathbf{C} is the Type of construction and \mathbf{A} is the Total floor area

Wood Frame

C 1.5 Type of Construction Coefficient per FUS Part II, Section 1

A 1301.0 \mathbf{m}^2 Total floor area based on FUS Part II section 1

Fire Flow

11902.9 L/min 12000.0 L/min rounded to the nearest 1,000 L/min

Adjustments

2. Reduction for Occupancy Type

Limited Combustible -15%

Fire Flow 10200.0 L/min

3. Reduction for Sprinkler Protection

Non-Sprinklered 0%

Reduction 0 L/min

4. Increase for Separation Distance

Cons. of Exposed Wall	S.D	Lw Ha	LH	E	3	
N Wood Frame	20.1m-30m	33	3	99	10%	
S Wood Frame	10.1m-20m	33	3	99	15%	
E Wood Frame	3.1m-10m	13	3	39	18%	
W Wood Frame	0m-3m	13	3	39	23%	
	% Increase				66 % value	e not to exceed 75%

Increase 6732.0 L/min

Lw = Length of the Exposed Wall

Ha = number of storeys of the adjacent structure. Max 5 stories

LH = Length-height factor of exposed wall. Value rounded up.

EC = Exposure Charge

Total Fire Flow

Fire Flow	16932.0 L/min	fire flow not to exceed 45,000 L/min nor be less than 2,000 L/min per FUS Section
	17000.0 L/min	rounded to the nearest 1,000 L/min

Notes:

-Type of construction, Occupancy Type and Sprinkler Protection information provided by _____

-Calculations based on Fire Underwriters Survey - Part II





Fig 1 – AVERAGE DAY



Page 1	2023-06	-29 11:18:22 AM
********	**************	******
*	EPANET	*
*	Hydraulic and Water Quality	*
*	Analysis for Pipe Networks	*
*	Version 2.0	*
********	**************************************	******

Input File: 2023-06-28_816_avgday.net

15-816: Minto - BTC Stage 1

Link - Node Table:

Link	Start	End	Length	Diameter
ID	Node	Node	m	mm
1	CON-1	4	38.0	200
2	4	24	5.0	200
3	24	25	65.0	200
4	25	26	65.0	200
12	4	7	25.0	200
13	5	6	9.0	200
16	8	9	70.5	200
17	9	10	19.0	200
18	10	11	2.5	200
19	11	CON-2	39.0	200
24	33	14	23.5	50
26	15	16	23.5	50
30	19	20	23.5	50
35	35	36	47.0	50
36	36	37	52.5	50
37	36	38	21.5	50
39	40	6	29.5	200
43	11	43	40	150
46	42	45	22.0	150
47	45	30	34.0	150
49	46	47	9.1	200
50	47	48	6.0	150
51	48	49	17.0	150
52	48	50	24.5	50
53	50	51	39.5	50
54	50	52	57.5	50
56	53	32	20.5	200
57	54	49	23.0	50
48	42	3	63.0	200
58	3	46	61	200
9	28	32	41	300
61	28	CON-3	41	300
62	17	18	23.5	50
63	12	14	57.5	50
64	14	15	10	150
65	15	17	10	150
66	17	19	10	150

Page 2 15-816: Minto - BTC Stage 1 Link - Node Table: (continued)

Link Start End Length Diameter

Link	Start	End	Length L	Diameter
ID	Node	Node	m	mm
67	19	31	10	150
68	31	22	10	150
69	29	31	26.0	50
70	23	22	23.5	50
71	22	10	15.5	150
72	5	14	15.5	150

AVERAGE DAY

75	30	55	61.5	150
78	38	41	32.0	150
79	7	6	17.5	200
80	5	8	53.5	200
81	34	57	60.5	150
82	57	30	31.0	150
83	38	1	64	200
84	1	58	60	200
85	58	42	32.0	200
86	43	42	26.5	150
87	55	59	60.5	150
88	59	32	33.5	150
89	47	60	14.5	200
90	60	53	25.0	200
91	40	61	25.0	200
92	61	38	6.0	200
93	41	62	18.5	150
94	62	34	68.5	150

Node Results:

Node ID		Head m	Pressure m	Quality	
4 5	0.00				
6	0.00 0.00	144.65 145.18			
8 9	0.00 0.00	143.76 142.60			
10	0.00	142.22	45.02	0.00	
11 12	0.00 2.50	141.97 144.04			
14 15	0.00 0.00	144.04 143.79			
16	5.00	143.79	45.68	0.00	
17 18	0.00 2.50	143.55 143.54		0.00 0.00	
19 20	0.00 2.50	143.30 143.30			
22	0.00	142.81	45.54	0.00	
23	2.50	142.81	45.29	0.00	

Node ID	Demand LPM		Pressure m	Quality	
 24	0.00	146.68	48.84	0.00	
25	0.00		49.42		
26	0.00	146.68	49.53	0.00	
30	0.00	145.70	51.31	0.00	
32	0.00	147.64	55.13	0.00	
33	2.50	144.04	45.79	0.00	
35	5.10	145.29	47.38	0.00	
36	0.00	145.29	47.81	0.00	
37	5.10	145.29	48.04	0.00	
38	0.00	145.31	47.92	0.00	
40	0.00	145.24	47.44	0.00	
41	0.00	145.37	48.18	0.00	
42	0.00	145.42	50.51	0.00	
43	0.00	144.13	47.36	0.00	
45	0.00	145.52	50.97	0.00	
46	45.90	146.67	52.74	0.00	
47	5.80	146.88	53.74	0.00	

AVERAGE DAY

50	0.00	146.86	53.51	0.00
51	4.10	146.86	53.34	0.00
52	5.80	146.85	53.94	0.00
53	0.00	147.32	54.55	0.00
54	4.10	146.87	50.29	0.00
1	0.00	145.35	48.82	0.00
3	0.00	146.12	51.87	0.00
28	0.00	147.76	55.36	0.00
29	5.00	143.05	45.49	0.00
31	0.00	143.05	45.41	0.00
34	0.00	145.53	49.80	0.00
55	0.00	146.42	52.70	0.00
7	0.00	145.73	47.96	0.00
57	45.90	145.63	50.36	0.00
58	45.90	145.38	49.25	0.00
59	45.90	147.13	53.90	0.00
60	5.80	147.06	54.04	0.00
61	5.10	145.29	47.78	0.00
62	5.10	145.40	48.36	0.00
CON-2	6432.88	138.70	0.00	0.00 Reservoir
CON-3	-3155.01	147.90	0.00	0.00 Reservoir
CON-1	-3529.96	147.90	0.00	0.00 Reservoir

Page 4 15-816: Minto - BTC Stage 1 Link Results:

LINK NESUICS.				
Link ID	Flow LPM	VelocityUnit m/s	Headloss m/km	Status
1	3529.96	1.87	32.09	Open
2	0.00	0.00	0.00	0pen
3	0.00	0.00	0.00	0pen
4	0.00	0.00	0.00	0pen
12	3529.96	1.87	37.92	0pen
13	-4351.10	2.31	58.93	0pen
16	2799.54	1.49	16.34	0pen
17	2799.54	1.49	20.11	0pen
18	4328.60	2.30	98.94	0pen
19	6432.88	3.41	83.97	0pen
24	-2.50	0.02	0.04	0pen
26	5.00	0.04	0.14	0pen
30	2.50	0.02	0.04	0pen
35	-5.10	0.04	0.14	0pen
36	5.10	0.04	0.14	0pen
37	-10.20	0.09	0.52	0pen
39	821.14	0.44	2.24	0pen
43	-2104.27	1.98	53.94	0pen
46	-599.49	0.57	4.88	0pen
47	-599.49	0.57	5.25	0pen
49	-2078.73	1.10	22.48	0pen
50	14.00	0.01	0.01	0pen
51	4.10	0.00	0.00	0pen
52	9.90	0.08	0.49	0pen
53	4.10	0.03	0.09	0pen
54	5.80	0.05	0.17	0pen
56	-2104.33	1.12	15.26	0pen
57	-4.10	0.03	0.09	0pen
48	-2032.83	1.08	11.14	0pen
58	-2032.83	1.08	9.08	0pen
9	3155.01	0.74	2.95	0pen
61	-3155.01	0.74	3.50	0pen
62	2.50	0.02	0.04	0pen
63	-2.50	0.02	0.04	0pen
64	1546.56	1.46	24.82	0pen
65	1541.56	1.45	24.68	0pen
66	1539.06	1.45	24.60	0pen

AVERAGE DAY


67	1536.56	1.45	24.53	0pen
68	1531.56	1.44	24.38	0pen
69	-5.00	0.04	0.13	0pen
70	-2.50	0.02	0.04	0pen
71	1529.06	1.44	37.98	0pen
72	1551.56	1.46	39.05	0pen
75	-1004.78	0.95	11.61	0pen
78	-354.30	0.33	2.05	0pen
79	3529.96	1.87	31.79	0pen
80	2799.54	1.49	16.64	0pen

Page 5
Link Results: (continued)

15-816: Minto - BTC Stage 1
Link Results: (continued)

Link ID	Flow LPM	VelocityUn: m/s	it Headloss m/km	Status	
81	-359.40	0.34	1.74	Open	
82	-405.30	0.38	2.27	Open	
83	-482.14	0.26	0.63	Open	
84	-482.14	0.26	0.63	0pen	
85	-528.04	0.28	1.03	0pen	
86	-2104.27	1.98	48.45	0pen	
87	-1004.78	0.95	11.77	0pen	
88	-1050.68	0.99	15.12	0pen	
89	-2098.53	1.11	12.50	0pen	
90	-2104.33	1.12	10.59	0pen	
91	-821.14	0.44	1.82	0pen	
92	-826.24	0.44	2.91	0pen	
93	-354.30	0.33	1.80	0pen	
94	-359.40	0.34	1.78	0pen	

Fig 2 - MAX DAY + FIRE FLOW



Page 1	2023-06-29	2:19:07	PΜ
*************	*******	******	**
* EPANET			*
* Hydraulic and Water Qual	ity		*
* Analysis for Pipe Networ	ks		*
* Version 2.0			*
***********	*********	*****	**

Input File: 2023-06-28_816_max-ff(blk10).net

15-816: Minto - BTC Stage 1

Link - Node Table:

Link	Start	End	Length	Diameter
ID	Node	Node	m	mm
1	CON-1	4	38.0	200
2	4	24	5.0	200
3	24	25	65.0	200
4	25	26	65.0	200
12	4	7	25.0	200
13	5	6	9.0	200
16	8	9	70.5	200
17	9	10	19.0	200
18	10	11	2.5	200
19	11	CON-2	39.0	200
24	33	14	23.5	50
26	15	16	23.5	50
30	19	20	23.5	50
35	35	36	47.0	50
36	36	37	52.5	50
37	36	38	21.5	50
39	40	6	29.5	200
43	11	43	40	150
46	42	45	22.0	150
47	45	30	34.0	150
49	46	47	9.1	200
50	47	48	6.0	150
51	48	49	17.0	150
52	48	50	24.5	50
53	50	51	39.5	50
54	50	52	57.5	50
56	53	32	20.5	200
57	54	49	23.0	50
48	42	3	63.0	200
58	3	46	61	200
9	28	32	41	300
61	28	CON-3	41	300
62	17	18	23.5	50
63	12	14	57.5	50
64	14	15	10	150
65	15	17	10	150
66	17	19	10	150

Page 2 Link - Node Table: (continued) 15-816: Minto - BTC Stage 1

Link	Start	End	Length	Diameter	
ID	Node	Node	m	mm	
67	19	31	10	150	
68	31	22	10	150	
69	29	31	26.0	50	
70	23	22	23.5	50	
71	22	10	15.5	150	
72	5	14	15.5	150	

MAX DAY + FIRE FLOW

70 20 41 22 0	150
78 38 41 32.0	
79 7 6 17.5	200
80 5 8 53.5	200
81 34 57 60.5	150
82 57 30 31.0	150
83 38 1 64	200
84 1 58 60	200
85 58 42 32.0	200
86 43 42 26.5	150
87 55 59 60.5	150
88 59 32 33.5	150
89 47 60 14.5	200
90 60 53 25.0	200
91 40 61 25.0	200
92 61 38 6.0	200
93 41 62 18.5	150
94 62 34 68.5	150

Node Results:

Node ID		Head m	Pressure m	Quality	
4	0.00				
5	0.00				
6	0.00	128.93			
8	0.00	131.04	33.38	0.00	
9	0.00	132.76	35.53	0.00	
10	0.00	133.33	36.13	0.00	
11	0.00	133.71	36.48	0.00	
12	6.25	130.57	31.56	0.00	
14	0.00	130.59	32.63	0.00	
15	0.00	130.94	32.82	0.00	
16	12.50	130.93	32.82	0.00	
17	0.00	131.31	33.66	0.00	
18	6.25	131.30	33.54	0.00	
19	0.00	131.67	34.13	0.00	
20	6.25	131.67	34.04	0.00	
22	0.00	132.41	35.14	0.00	
23	6.25	132.41	34.89	0.00	

	s: (continued) 				
Node			Pressure	Quality	
ID	LPM	m	m		
24	0.00	128.97	31.13	0.00	
25	0.00	128.97	31.71	0.00	
26	0.00	128.97	31.82	0.00	
30	0.00	125.43	31.04	0.00	
32	0.00	142.93	50.42	0.00	
33	6.25	130.58	32.33	0.00	
35	12.75	123.52	25.61	0.00	
36	0.00	123.56	26.08	0.00	
37	12.75	123.52	26.27	0.00	
38	0.00	123.62	26.23	0.00	
40	0.00	126.17	28.37	0.00	
41	4500.00	111.92	14.73	0.00	
42	0.00	128.42	33.51	0.00	
43	0.00	130.39	33.62	0.00	
45	2500.00	125.76	31.21	0.00	
46	114.75	136.54	42.61	0.00	
47	14.50	137.95	44.81	0.00	
48	0.00	137.95	44.90	0.00	
49	0.00	137.95	44.75	0.00	

MAX DAY + FIRE FLOW

50	0.00	137.89	44.54	0.00
51	10.25	137.87	44.35	0.00
52	14.50	137.83	44.92	0.00
53	0.00	140.84	48.07	0.00
54	10.25	137.94	41.36	0.00
1	5000.00	123.60	27.07	0.00
3	0.00	133.01	38.76	0.00
28	0.00	143.82	51.42	0.00
29	12.50	132.02	34.46	0.00
31	0.00	132.04	34.40	0.00
34	5000.00	110.85	15.12	0.00
55	0.00	131.88	38.16	0.00
7	0.00	128.94	31.17	0.00
57	114.75	120.13	24.86	0.00
58	114.75	126.20	30.07	0.00
59	114.75	138.32	45.09	0.00
60	14.50	139.14	46.12	0.00
61	12.75	124.37	26.86	0.00
62	12.75	111.68	14.64	0.00
CON-2	-8050.22	138.70	0.00	0.00 Reservoir
CON-3	-9072.03	144.90	0.00	0.00 Reservoir
CON-1	-508.00	129.00	0.00	0.00 Reservoir

Page 4 15-816: Minto - BTC Stage 1 Link Results:


Link ID	Flow LPM	.*	it Headloss m/km	Status	
	LPM	m/s	III/ KIII		
1	508.00	0.27	0.83	Open	
2	0.00	0.00	0.00	Open	
3	0.00	0.00	0.00	Open	
4	0.00	0.00	0.00	Open	
12	508.00	0.27	0.95	Open	
13	5345.16	2.84	87.36	Open	
16	-3469.53	1.84	24.35	Open	
17	-3469.53	1.84	30.15	Open	
18	-5401.41	2.87	152.33	Open	
19	-8050.22	4.27	127.82	Open	
24	-6.25	0.05	0.21	Open	
26	12.50	0.11	0.75	Open	
30	6.25	0.05	0.21	Open	
35	-12.75	0.11	0.76	Open	
36	12.75	0.11	0.75	Open	
37	-25.50	0.22	2.88	Open	
39	-5853.17	3.11	93.57	Open	
43	2648.81	2.50	83.14	Open	
46	3325.87	3.14	120.73	Open	
47	825.87	0.78	9.59	Open	
49	-5611.54	2.98	154.97	0pen	
50	35.00	0.03	0.03	0pen	
51	10.25	0.01	0.00	0pen	
52	24.75	0.21	2.67	0pen	
53	10.25	0.09	0.50	0pen	
54	14.50	0.12	0.95	0pen	
56	-5675.54	3.01	101.99	0pen	
57	-10.25	0.09	0.51	0pen	
48	-5496.79	2.92	72.91	0pen	
58	-5496.79	2.92	57.92	0pen	
9	9072.03	2.14	21.71	0pen	
61	-9072.03	2.14	26.26	0pen	
62	6.25	0.05	0.21	0pen	
63	-6.25	0.05	0.20	0pen	
64	-1888.14	1.78	35.92	0pen	
65	-1900.64	1.79	36.37	0pen	
66	-1906.89	1.80	36.59	0pen	

MAX DAY + FIRE FLOW

67	-1913.14	1.80	36.81	0pen
68	-1925.64	1.82	37.26	0pen
69	-12.50	0.11	0.74	0pen
70	-6.25	0.05	0.20	0pen
71	-1931.89	1.82	59.30	0pen
72	-1875.64	1.77	56.05	0pen
75	-3281.74	3.10	104.76	0pen
78	5519.89	5.21	365.49	0pen
79	508.00	0.27	0.82	0pen
80	-3469.53	1.84	24.82	0pen

Link	Elow	VolocityUr	nit Headloss	Status	
ID	LPM	m/s		Scacus	
81	-3992.86	3.77	153.35	Open	
82	-4107.61	3.87	171.27	0pen	
83	295.03	0.16	0.25	0pen	
84	-4704.97	2.50	43.40	0pen	
85	-4819.72	2.56	69.12	0pen	
86	2648.81	2.50	74.44	0pen	
87	-3281.74	3.10	106.45	0pen	
88	-3396.49	3.20	137.78	0pen	
89	-5661.04	3.00	82.01	0pen	
90	-5675.54	3.01	68.01	0pen	
91	5853.17	3.11	72.06	0pen	
92	5840.42	3.10	125.24	0pen	
93	1019.89	0.96	13.01	0pen	
94	1007.14	0.95	12.16	Open	

Fig 3 – PEAK HOUR



Ρ	Page 1 2023-06-29 1	1:20:10 AM
*	*********************	*******
*	EPANET	*
*	Hydraulic and Water Quality	*
*	Analysis for Pipe Networks	*
*	Version 2.0	*
*	***********************	******

Input File: 2023-06-28_816_peakhour.net

15-816: Minto - BTC Stage 1

Link - Node Table:

LIIK - NOGE 18				
Link	Start	End	Length	Diameter
ID	Node	Node	m	mm
1	CON-1	4	38.0	200
2	4	24	5.0	200
3	24	25	65.0	200
4	25	26	65.0	200
12	4	7	25.0	200
13	5	6	9.0	200
16	8	9	70.5	200
17	9	10	19.0	200
18	10	11	2.5	200
19	11	CON-2	39.0	200
24	33	14	23.5	50
26	15	16	23.5	50
30	19	20	23.5	50
35	35	36	47.0	50
36	36	37	52.5	50
37	36	38	21.5	50
39	40	6	29.5	200
43	11	43	40	150
46	42	45	22.0	150
47	45	30	34.0	150
49	46	47	9.1	200
50	47	48	6.0	150
51	48	49	17.0	150
52	48	50	24.5	50
53	50	51	39.5	50
54	50	52	57.5	50
56	53	32	20.5	200
57	54	49	23.0	50
48	42	3	63.0	200
58	3	46	61	200
9	28	32	41	300
61	28	CON-3	41	300
62	17	18	23.5	50
63	12	14	57.5	50
64	14	15	10	150
65	15	17	10	150
66	17	19	10	150

Page 2 15-816: Minto - BTC Stage 1 Link - Node Table: (continued)

		, 		
Link	Start	End	Length	Diameter
ID	Node	Node	m	mm
67	19	31	10	150
68	31	22	10	150
69	29	31	26.0	50
70	23	22	23.5	50
71	22	10	15.5	150
72	5	14	15.5	150

PEAK HOUR

75	30	55	61.5	150
78	38	41	32.0	150
79	7	6	17.5	200
80	5	8	53.5	200
81	34	57	60.5	150
82	57	30	31.0	150
83	38	1	64	200
84	1	58	60	200
85	58	42	32.0	200
86	43	42	26.5	150
87	55	59	60.5	150
88	59	32	33.5	150
89	47	60	14.5	200
90	60	53	25.0	200
91	40	61	25.0	200
92	61	38	6.0	200
93	41	62	18.5	150
94	62	34	68.5	150

Node Results:

Node ID	Demand LPM	Head m	Pressure m	Quality	
4	0.00				
5	0.00				
6	0.00	143.08	45.08	0.00	
8	0.00	142.09	44.43	0.00	
9	0.00	141.30	44.07	0.00	
10	0.00	141.04	43.84	0.00	
11	0.00	140.88	43.65	0.00	
12	13.75	142.21	43.20	0.00	
14	0.00	142.26	44.30	0.00	
15	0.00	142.08	43.96	0.00	
16	27.50	142.00	43.89	0.00	
17	0.00	141.91	44.26	0.00	
18	13.75	141.89	44.13	0.00	
19	0.00	141.74	44.20	0.00	
20	13.75	141.72	44.09	0.00	
22	0.00	141.41	44.14	0.00	
23	13.75	141.39	43.87	0.00	

ode D 4 5 6	Demand LPM 0.00 0.00 0.00	m 144.36	Pressure m 46.52		
- 	0.00 0.00	144.36	46.52	0.00	
5 6	0.00			0.00	
6		144.36			
	0.00		47.10	0.00	
0	0.00	144.36	47.21	0.00	
	0.00	143.32	48.93	0.00	
2	0.00	145.11	52.60	0.00	
3	13.75	142.24	43.99	0.00	
5	28.05	142.68	44.77	0.00	
6	0.00	142.84	45.36	0.00	
7	28.05	142.67	45.42	0.00	
8	0.00	143.11	45.72	0.00	
0	0.00	143.09	45.29	0.00	
1	0.00	143.13	45.94	0.00	
2	0.00	143.16	48.25	0.00	
3	0.00	142.31	45.54	0.00	
5	0.00	143.22	48.67	0.00	
6	252.45	144.12	50.19	0.00	
7	31.90	144.32	51.18	0.00	

PEAK HOUR

50	0.00	144.03	50.68	0.00
51	22.55	143.95	50.43	0.00
52	31.90	143.80	50.89	0.00
53	0.00	144.78	52.01	0.00
54	22.55	144.27	47.69	0.00
1	0.00	143.12	46.59	0.00
3	0.00	143.70	49.45	0.00
28	0.00	145.24	52.84	0.00
29	27.50	141.49	43.93	0.00
31	0.00	141.57	43.93	0.00
34	0.00	143.18	47.45	0.00
55	0.00	143.91	50.19	0.00
7	0.00	143.55	45.78	0.00
57	252.45	143.23	47.96	0.00
58	252.45	143.13	47.00	0.00
59	252.45	144.50	51.27	0.00
60	31.90	144.50	51.48	0.00
61	28.05	143.10	45.59	0.00
62	28.05	143.14	46.10	0.00
CON-2	5177.25	138.70	0.00	0.00 Reservoir
CON-3	-3317.80	145.40	0.00	0.00 Reservoir
CON-1	-3246.00	145.40	0.00	0.00 Reservoir

Page 4 15-816: Minto - BTC Stage 1 Link Results:

Link ID	LPM	VelocityUnit m/s		Status	
1	3246.00	1.72	27.38	Open	
2	0.00	0.00	0.00	Open	
3	0.00	0.00	0.00	Open	
4	0.00	0.00	0.00	Open	
12	3246.00	1.72	32.31	0pen	
13	-3611.53	1.92	41.27	0pen	
16	2287.33	1.21	11.22	0pen	
17	2287.33	1.21	13.74	0pen	
18	3487.78	1.85	64.96	0pen	
19	5177.25	2.75	55.90	0pen	
24	-13.75	0.12	0.89	0pen	
26	27.50	0.23	3.24	0pen	
30	13.75	0.12	0.89	0pen	
35	-28.05	0.24	3.30	0pen	
36	28.05	0.24	3.23	0pen	
37	-56.10	0.48	12.54	0pen	
39	365.53	0.19	0.48	0pen	
43	-1689.47	1.59	35.71	0pen	
46	-436.75	0.41	2.70	0pen	
47	-436.75	0.41	2.90	0pen	
49	-2017.29	1.07	21.20	0pen	
50	77.00	0.07	0.12	0pen	
51	22.55	0.02	0.01	0pen	
52	54.45	0.46	11.63	0pen	
53	22.55	0.19	2.18	0pen	
54	31.90	0.27	4.11	0pen	
56	-2158.08	1.14	16.01	0pen	
57	-22.55	0.19	2.21	0pen	
48	-1764.83	0.94	8.53	0pen	
58	-1764.83	0.94	6.98	0pen	
9	3317.80	0.78	3.25	0pen	
61	-3317.80	0.78	3.86	0pen	
62	13.75	0.12	0.89	0pen	
63	-13.75	0.12	0.87	0pen	
64	1296.70	1.22	17.91	0pen	
65	1269.20	1.20	17.21	0pen	
66	1255.45	1.18	16.87	0pen	

PEAK HOUR

67	1241.70	1.17	16.53	0pen
68	1214.20	1.15	15.86	0pen
69	-27.50	0.23	3.22	0pen
70	-13.75	0.12	0.86	0pen
71	1200.45	1.13	23.95	0pen
72	1324.20	1.25	28.87	0pen
75	-907.27	0.86	9.61	0pen
78	-190.02	0.18	0.63	0pen
79	3246.00	1.72	27.13	0pen
80	2287.33	1.21	11.42	0pen


	lts: (continued) 				
Link	Flow	VelocityUnit	Headloss	Status	
ID	LPM	m/s	m/km		
81	-218.07	0.21	0.69	Open	
82	-470.52	0.44	3.00	0pen	
83	-259.66	0.14	0.20	0pen	
84	-259.66	0.14	0.20	0pen	
85	-512.11	0.27	0.97	0pen	
86	-1689.47	1.59	32.17	0pen	
87	-907.27	0.86	9.74	0pen	
88	-1159.72	1.09	18.20	0pen	
89	-2126.18	1.13	12.82	0pen	
90	-2158.08	1.14	11.10	0pen	
91	-365.53	0.19	0.40	0pen	
92	-393.58	0.21	0.70	0pen	
93	-190.02	0.18	0.56	0pen	
94	-218.07	0.21	0.70	0pen	

Boundary Conditions Minto Barrhaven Town Centre – Stage 1

Provided Information

Saamania	D	emand
Scenario	L/min	L/s
Average Daily Demand	245	4.08
Maximum Daily Demand	668	11.13
Peak Hour	1,392	23.20
Fire Flow Demand #1	17,000	283.33

Location



Results - Existing Conditions

Connection 1 - Riocan Avenue

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	157.7	78.8
Peak Hour	140.9	54.9
Max Day plus Fire 1	130.0	39.5

Ground Elevation = 102.2 m

Connection 2 - Glenroy Gilbert Drive

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	157.7	83.0
Peak Hour	140.9	59.0
Max Day plus Fire 1	139.6	57.2

Ground Elevation = 99.3 m

Connection 3 - Chapman Mills Drive

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	157.7	89.5
Peak Hour	140.8	65.5
Max Day plus Fire 1	145.7	72.4

Ground Elevation = 94.7 m

Results - SUC Zone Reconfiguration

Connection 1 - Riocan Avenue

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	147.9	64.9
Peak Hour	145.4	61.3
Max Day plus Fire 1	129.0	38.1

Ground Elevation = 102.2 m

Connection 2 - Glenroy Gilbert Drive

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	147.9	69.1
Peak Hour	145.4	65.5
Max Day plus Fire 1	138.7	56.0

Ground Elevation = 99.3 m

Connection 3 - Chapman Mills Drive

Demand Scenario	Head (m)	Pressure ¹ (psi)
Maximum HGL	147.9	69.1
Peak Hour	145.4	65.5
Max Day plus Fire 1	144.9	71.2

Ground Elevation = 94.7 m

Notes

- 1. As per the Ontario Building Code in areas that may be occupied, the static pressure at any fixture shall not exceed 552 kPa (80 psi.) Pressure control measures to be considered are as follows, in order of preference:
 - a. If possible, systems to be designed to residual pressures of 345 to 552 kPa (50 to 80 psi) in all occupied areas outside of the public right-of-way without special pressure control equipment.
 - b. Pressure reducing valves to be installed immediately downstream of the isolation valve in the home/ building, located downstream of the meter so it is owner maintained.

Disclaimer

The boundary condition information is based on current operation of the city water distribution system. The computer model simulation is based on the best information available at the time. The operation of the water distribution system can change on a regular basis, resulting in a variation in boundary conditions. The physical properties of watermains deteriorate over time, as such must be assumed in the absence of actual field test data. The variation in physical watermain properties can therefore alter the results of the computer model simulation. Fire Flow analysis is a reflection of available flow in the watermain; there may be additional restrictions that occur between the watermain and the hydrant that the model cannot take into account.

APPENDIX C

Sanitary Servicing Documents



Manning's n=0.013

SERVICING 1100	Vianning's n=0.013 Location Residential area and population Comm In.								INSTIT PARK C+I+I INFILTRATION						PIPE															
## PATRICULAR S 15								POPULATION											C+I+I											
SERVICING S SERVI	STREET			AREA	UNITS			POP.					AREA		AREA		AREA							DIST	DIA	SLOPE		-	VEVE	(ACT.)
SERVICING 6 136. 1144. 0.05 6 6 0 13 0.05 17 17 17 17 17 18 18 18 18 18 18 18 18 18 18 18 18 18		IVI.□.	IVI.IT.	(ba)		Sirigles	Townhouse			POP.	FACT.		(ba)		(ha)		(ha)							(m)	(mm)	(0/)		Q act/Q cap		(m/s)
114				(IIa)					(IIa)			(1/5)	(IIa)	(IIa)	(IIa)	(IIa)	(IIa)	(IIa)	(1/5)	(IIa)	(IIa)	(#5)	(1/5)	(111)	(111111)	(70)	(1/5)		(111/5)	(111/5)
114	SERVICING 6																													
SERVICING 1. Fig. 1134 - 1144 114	OEKVIOINO O	113∆	1144	0.10	6	6		13	0.10	13	3.72	0.16		0.00		0.00		0.00	0.00	0.10	0.10	0.03	0.19	24.5	200	3.10	57 75	0.00	1 84	0.41
Columbia 114A 115A	Contribution From SERVICING 1 Pine		11-77	0.10		Ŭ		10			0.72	0.10							0.00			0.00	0.10	24.0	200	0.10	01.10	0.00	1.04	0.71
TAGELINON GLIBERT OR Per 119A - 119A 119A	Contribution 1 Tom CERTIFICATION 1, 1 Ipo		115A								3.57	1.50							0.00			0.20	1.71	11.0	200	0.35	19.40	0.09	0.62	0.38
SERVICING 8 1 11 11 11 11 11 11 11 11 11 11 11 11 1	To GLENROY GILBERT DR. Pipe 115/																													
To SERVICING 1 Pipe 10A-110A	, ,																													
TO SERVICING 1961 124-114A	SERVICING 5																													
SERVICING Pipe 119A - 119A		111A	112A	0.08	12	12		26	0.08	26	3.69	0.31				0.00		0.00	0.00	0.08	0.08	0.03	0.34	27.0	200	0.65	26.44	0.01	0.84	0.28
SERVICING Pipe 110A 112A 100A	To SERVICING 1, Pipe 112A - 114A								0.08	26				0.00		0.00		0.00			0.08									
TO SERVICING Pge 108A - 10A 109A 109																														
To SERVICING 4 TO SERVICING 5, Pipe 100A - 112A TO SERVICING 5, Pipe 100A - 110A TO SERVICING 9, Pipe 100A - 110A TO SERVICING 1, Pipe 100A - 100A TO SERVICING 1, Pi	SERVICING 5																													
SERVICING 4 107A 108A 1		109A	110A	0.09	6	6		13			3.72	0.16							0.00	0.09		0.03	0.19	24.5	200	0.75	28.40	0.01	0.90	0.25
TO SERVICING 1 Pipe 108A - 108A 0.09 6 6 13 0.09 13 3.72 0.16 0.00 0.00 0.00 0.00 0.00 0.09 0.09 0.03 0.19 24.5 200 0.85 28.44 0.01 0.84	To SERVICING 1, Pipe 110A - 112A								0.09	13				0.00		0.00		0.00			0.09									
TO SERVICING 1, Pipe 108A - 108A 0.09 6 6 13 0.09 13 3.72 0.16 0.00 0.00 0.00 0.00 0.09 0.99 0.03 0.19 24.5 200 0.85 28.44 0.01 0.84																														
To SERVICING 1, Pipe 108A - 110A	SERVICING 4	1074	1004	0.00	6	6		10	0.00	10	2.70	0.16		0.00		0.00		0.00	0.00	0.00	0.00	0.03	0.10	24.5	200	0.65	26.44	0.01	0.04	0.00
SERVICING 3 105A 106A 0.08 12 12 2 8 0.08 25 3.69 0.31 0.00 0.00 0.00 0.00 0.08 0.03 0.34 25.0 200 0.65 28.44 0.01 0.84 1.05 1.05 1.05 1.05 1.05 1.05 1.05 1.05	To SEDVICING 1 Ding 1004 1104	1U/A	TU8A	0.09	6	ь		13			3.72	0.76			.				0.00	0.09		0.03	0.19	24.5	∠00	0.65	∠0.44	0.01	U.84	0.23
TO SERVICING 1 Pipe 108A - 109A	TO SERVICING 1, PIPE TUBA - TTUA			1	-	 			0.09	13	-	-	 	0.00	-	0.00		0.00		1	0.09			-	+	1	+	-		
TO SERVICING 1 Pipe 108A - 109A	SERVICING 3			<u> </u>																1	<u> </u>			1	1	<u> </u>	1			
To SERVICING 1, Pipe 108A - 109A	SERVICING S	105A	106A	0.08	12	12		26	0.08	26	3 69	0.31		0.00		0.00		0.00	0.00	0.08	0.08	0.03	0.34	26.0	200	0.65	26 44	0.01	0.84	0.28
SERVICING 2 105A 105A 105A 105A 105A 105A 105A 105A	To SERVICING 1 Pipe 106A - 108A	100/1	100/1	0.00	12	- '-		20			0.00	0.01							0.00	0.00		0.00	0.01	20.0	200	0.00	20.11	0.01	0.04	0.20
103A 104A 0.13 12 12 26 0.13 26 3.69 0.31 0.00 0.00 0.00 0.00 0.00 0.13 0.13 0.04 0.35 24.5 200 1.75 43.39 0.01 1.38 1	1,1,00,100,1,100,1								0.00					0.00		0.00		0.00			0.00									
103A 104A 0.13 12 12 26 0.13 26 3.69 0.31 0.00 0.00 0.00 0.00 0.00 0.13 0.13 0.04 0.35 24.5 200 1.75 43.39 0.01 1.38 1	SERVICING 2																													
SERVICING 1 100A 101A 101A 100A 100A		103A	104A	0.13	12	12		26	0.13	26	3.69	0.31		0.00		0.00		0.00	0.00	0.13	0.13	0.04	0.35	24.5	200	1.75	43.39	0.01	1.38	0.40
SERVICING 1 100A 101A	To SERVICING 1, Pipe 104A - 106A								0.13	26				0.00		0.00		0.00			0.13									
100A																														
101A 102A 102A 104A 0.05 6 6 13 0.05 13 3.72 0.16 0.00 0.00 0.00 0.00 0.00 0.00 0.00	SERVICING 1																													
102A																													1.76	0.10
To SERVICING 1, Pipe 104A - 106A																														0.11
Contribution From SERVICING 1, Pipe 102A - 104A Contribution From SERVICING 2, Pipe 103A - 104A Contribution From SERVICING 3, Pipe 103A - 104A Contribution From SERVICING 3, Pipe 105A - 106A Contribution From SERVICING 3, Pipe 105A - 106A Contribution From SERVICING 4, Pipe 105A - 106A Contribution From SERVICING 4, Pipe 107A - 108A Contribution From SERVICING 5, Pipe 107A - 108A Contribution From SERVICING 5, Pipe 111A - 112A Contribution From SERVICING 5, Pipe 111A - 112A Contribution From SERVICING 5, Pipe 111A - 112A Contribution From SERVICING 6, Pipe 114A - 115A Contribution From SERVICING 6, Pipe 1	T 0550 (100 10 1 5) 1011 1001	102A	104A	0.05	6	6		13			3.72	0.16							0.00	0.05		0.02	0.17	30.0	200	0.85	30.24	0.01	0.96	0.25
Contribution From SERVICING 2, Pipe 103A - 104A 106A	To SERVICING 1, Pipe 104A - 106A								0.05	13				0.00		0.00		0.00			0.05									
Contribution From SERVICING 2, Pipe 103A - 104A 106A	Contribution From CEDVICING 4 Disc	1004 1014				1			0.05	40				0.00		0.00		0.00		0.05	0.05			1	1					
104A 106A 106B 104B 106B 108B																														
Contribution From SERVICING 3, Pipe 105A - 106A 0.08	CONTIDUCION FIOR SERVICING 2, PIPE		1064								3.67	0.46					-		0.00			0.06	0.52	33.5	200	0.35	10.40	0.03	0.62	0.26
106A 108A	Contribution From SERVICING 3 Pine		100A								3.07	0.40							0.00			0.00	0.52	33.3	200	0.00	13.40	0.03	0.02	0.20
Contribution From SERVICING 4, Pipe 107A - 108A 110A 10BA 110A 110BA 110A 10BA 110A 110BA	Contribution From CERVIONVC 3, 1 spc		108A								3 63	0.77							0.00			0.09	0.85	31.5	200	0.35	19 40	0.04	0.62	0.31
108A 110A	Contribution From SERVICING 4. Pipe		10071								0.00	0							0.00			0.00	0.00	00		0.00	10.10	0.01	0.02	0.0.
110A 112A 114A 91 3.60 1.06 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.44 0.15 1.21 31.0 200 0.35 19.40 0.06 0.62			110A								3.62	0.91						0.00	0.00			0.12	1.03	20.5	200	1.60	41.49	0.02	1.32	0.55
110A 112A 114A 91 3.60 1.06 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.44 0.15 1.21 31.0 200 0.35 19.40 0.06 0.62	Contribution From SERVICING 5, Pipe		-										İ														1			
To SERVICING 6, Pipe 114A - 115A		110A	112A						0.44		3.60	1.06							0.00			0.15	1.21	31.0	200	0.35	19.40	0.06	0.62	0.34
To SERVICING 6, Pipe 114A - 115A	Contribution From SERVICING 5, Pipe																													
Contribution From SERVICING 6, Pipe 114A - 115A		112A	114A								3.58	1.36							0.00	0.00		0.17	1.53	32.0	200	0.40	20.74	0.07	0.66	0.38
Contribution From SERVICING 6, Pipe 114A - 115A	To SERVICING 6, Pipe 114A - 115A			ļ					0.52	117				0.00		0.00		0.00			0.52					ļ				ļ
Contribution From SERVICING 6, Pipe 114A - 115A	OLENBOY OF BEEF 22			<u> </u>									ļ							4				1	1	<u> </u>	1			
115A EX SAN118A 0.38 0 1.00 130 3.57 1.50 0.00 0.00 0.00 0.00 0.00 0.38 1.00 0.33 1.83 12.5 200 0.40 20.74 0.09 0.66		4444 4454		<u> </u>		<u> </u>			0.00	400				0.00		0.00		0.00		0.00	0.00			-		<u> </u>				
DESIGN PARAMETERS	Contribution From SERVICING 6, Pipe		EV CANIAACA	0.20		1		0			2 57	1.50					-		0.00			0.22	1.02	10.5	200	0.40	20.74	0.00	0.66	0.41
Park Flow = 9300 L/ha/da 0.10764 l/s/Ha cpb Minto - Barrhaven Town Centre Stage 1 Average Daily Flow = 280 l/p/day Industrial Peak Factor = as per MOE Graph		HOA	EV SUILINY	0.30		}		U	1.00	130	3.57	1.50		0.00		0.00		0.00	0.00	0.36	1.00	0.33	1.03	12.5	200	0.40	20.74	0.09	0.00	0.41
Park Flow = 9300 L/ha/da 0.10764 l/s/Ha cpb Minto - Barrhaven Town Centre Stage 1 Average Daily Flow = 280 l/p/day Industrial Peak Factor = as per MOE Graph	 			1		1						1								 	1			1	1	1	1			
Park Flow = 9300 L/ha/da 0.10764 l/s/Ha certain CPB Minto - Barrhaven Town Centre Stage 1 Average Daily Flow = 280 l/p/day Industrial Peak Factor = as per MOE Graph	1	j			DESIGN P	ARAMETI	FRS		ı	1	1	1			ı	Designer	d·	I		ı	PROJEC:	T.		1	1	ı	1			
Average Daily Flow = 280 <i>Vp/</i> day Industrial Peak Factor = as per MOE Graph	Park Flow =	9300	L/ha/da	0.10764	DEGIGINI		0									2 congrice	٠.			CPB	. 110020	••		Minto	- Barrha	ven Towi	n Centre S	Stage 1		
									Industrial F	Peak Facto	or = as p	er MOE G	raph															-		
				0.3241		l/s/Ha										Checked	l:				LOCATIO	N:								
Industrial Flow = 35000 L/ha/da 0.40509 l/s/Ha Minimum Velocity = 0.600 m/s SLM City of Ottawa	Industrial Flow =		L/ha/da			l/s/Ha			Minimum \	Velocity =		0.600	m/s			l				SLM						City of	Ottawa			
Max Res. Peak Factor = 4.00 Manning's n = (Conc) 0.013 (Pvc) 0.013	Max Res. Peak Factor =	4.00							Manning's	n =	(Conc)	0.013	(Pvc)	0.013												-				
Commercial/Inst./Park Peak Factor = 1.00 2 Bedroom coeff= 2.1 Dwg. Reference: File Ref: Date: Sheet No.	Commercial/Inst./Park Peak Factor =	1.00									,					Dwg. Re	ference:				File Ref:				Date:			Sheet		1
		0.32	l/s/Ha															an, Dwgs.	No.					15-816		29 Jun 202	:3			4



Manning's n=0.013 RESIDENTIAL AREA AND POPULATION INFILTRATION LOCATION COMM INSTIT PARK C+I+I STREET FROM UNITS UNITS CUMULATIVE PEAK ACCU ACCU PEAK ACCU. INFILT TOTAL мн мн ARFA POP FACT. FLOW AREA AREA AREA FLOW AREA AREA FLOW FLOW (FULL) Q act/Q cap (FULL) Singles (ACT (ha) (ha) (l/s) (ha) (ha) (ha) (l/s) (ha) (ha) (l/s) (l/s) (%) (l/s) (m/s) (m/s) RIOCAN AVE 155A 156A 0.00 0.00 46.38 0.00 1.48 0.24 0.19 Ω 0.19 0 0.00 0.00 0.19 0.19 0.06 0.06 52.0 200 2.00 156A 157A 0 0.39 0 0.00 0.00 200 0.35 19.40 0.01 0.62 0.20 0.00 0.00 0.20 0.39 0.13 0.13 95.0 0.17 **SERVICING 21** Plug 150A 0.37 64 64 135 0.37 135 3 56 1.56 0.00 0.00 0.00 0.00 0.37 0.37 0.12 1.68 4.0 0.65 26.44 0.06 0.84 0.47 200 150A 151A 0.37 135 3.56 1.56 0.00 0.00 0.00 0.00 0.00 0.37 0.12 1.68 29.0 200 2.05 46.96 0.04 1.49 0.69 To SERVICING 19, Pipe 151A - 152A 0.37 135 0.00 0.00 0.00 0.37 **SERVICING 16** Plua 147A 0.57 64 64 135 0.57 135 3.56 1.56 0.00 0.00 0.00 0.00 0.57 0.57 0.19 1.75 11.0 200 0.65 26.44 0.07 0.84 0.47 To SERVICING 9, Pipe 147A - 148A 0.57 135 0.00 0.00 0.00 0.57 SERVICING 20 141A 143A 0.10 14 14 30 0.10 30 3.68 0.36 0.00 0.00 0.00 0.00 0.10 0.10 0.03 0.39 53.5 200 0.65 26.44 0.01 0.84 0.29 To SERVICING 17 SERVICING 18, Pipe 143A - 145A 0.10 30 0.00 0.00 0.00 0.10 143A 0.07 10 21 0.07 21 3.70 0.25 0.00 0.00 0.00 0.00 0.07 0.07 0.02 0.28 43.5 200 0.65 26.44 0.01 0.84 0.27 10 To SERVICING 17 SERVICING 18, Pipe 143A - 145A 0.07 0.00 0.00 0.00 0.07 21 **SERVICING 18** Contribution From SERVICING 20, Pipe 141A - 143A 0.10 30 0.00 0.00 0.00 0.10 0.10 Contribution From SERVICING 20, Pipe 142A - 143A 0.07 21 0.00 0.00 0.00 0.07 0.17 145A 0.01 0.18 3.65 0.60 0.00 0.00 0.00 0.00 0.01 0.18 0.06 0.66 30.0 200 0.35 19.40 0.03 0.62 0.29 Ω 51 To SERVICING 19, Pipe 145A - 148A 0.00 0.00 0.18 51 0.00 0.18 SERVICING 19 144A 145A 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 44.0 200 1.35 38.11 0.00 1.21 0.07 Contribution From SERVICING 18, Pipe 143A - 145A 0.18 51 0.00 0.00 0.00 0.18 0.18 148A 0.16 10 10 21 0.34 72 3.62 0.00 0.00 0.00 0.00 0.16 0.34 0.11 0.96 6.0 200 0.35 19.40 0.05 0.62 0.32 Contribution From SERVICING 9, Pipe 147A - 148A 135 0.00 0.00 0.00 0.57 0.57 0.91 148A 30 1.09 237 3.50 0.00 0.00 0.00 1.09 0.10 0.61 0.39 14 0.00 0.18 0.36 3.04 56.0 250 0.25 29.73 Contribution From SERVICING 21, Pipe 150A - 151A 0.37 135 0.00 0.00 0.00 1.46 0.37 152A 1.46 372 4.13 0.00 0.00 0.00 0.00 0.00 1.46 0.48 4.62 15.0 250 0.25 29.73 0.16 0.61 0.44 To FUTURE CHAPMAN MILLS DR. Pipe 152A - 153A 1.46 372 0.00 0.00 0.00 1.46 SERVICING 15 135A 135 0.00 Plug 0.31 64 64 0.31 135 3.56 1.56 0.00 0.00 0.00 0.31 0.31 0.10 1.66 4.0 200 0.65 26.44 0.06 0.84 0.46 135A 138A 0.31 135 0.00 0.00 0.00 0.00 0.00 0.31 0.10 1.66 26.5 200 6.00 80.34 0.02 2.56 0.99 To SERVICING 14, Pipe 138A - 139A 0.31 135 0.00 0.00 0.00 0.31 Plug 137A 0.24 48 48 101 0.24 101 3.59 0.00 0.00 0.00 0.00 0.24 0.24 0.08 1.26 3.5 200 0.65 26.44 0.05 0.84 0.43 137A 138A 0.24 101 3 59 1 18 0.00 0.00 0.00 0.00 0.00 0.24 0.08 1.26 14.0 200 0.35 19.40 0.06 0.62 0.34 To SERVICING 14, Pipe 138A - 139A 0.24 101 0.00 0.00 0.00 0.24 **SERVICING 13** 132A 0.36 48 101 101 3.59 1.18 0.00 0.00 0.00 0.00 0.36 0.36 0.12 1.30 10.0 200 4.05 66.01 0.02 2.10 0.82 Plua 48 0.36 To SERVICING 9. Pipe 132A - 133A 0.36 101 0.00 0.00 0.00 0.36 DESIGN PARAMETERS Designed: ROJECT Park Flow = 9300 L/ha/da 0.10764 Minto - Barrhaven Town Centre Stage 1 Average Daily Flow = 280 Industrial Peak Factor = as per MOE Graph l/p/day Comm/Inst Flow = LOCATION: 28000 L/ha/da 0.3241 I/s/Ha Extraneous Flow = 0.330 L/s/ha Checked: Industrial Flow = 35000 L/ha/da 0.40509 I/s/Ha Minimum Velocity = 0.600 m/s SLM City of Ottawa 4.00 Max Res. Peak Factor = Manning's n = (Conc) 0.013 (Pvc) Commercial/Inst./Park Peak Factor = 1.00 2 Bedroom coeff= 2.1 Dwg. Reference: File Ref: Sheet No. Institutional = 0.32 l/s/Ha Sanitary Drainage Plan, Dwgs, No. 15-816 29 Jun 2023



Manning's n=0.013 RESIDENTIAL AREA AND POPULATION INFILTRATION LOCATION COMM INSTIT PARK C+I+I STREET FROM UNITS UNITS CUMULATIVE PEAK ACCU AREA ACCU PEAK ACCU. INFILT TOTAL мн мн ARFA POP FACT. FLOW AREA AREA AREA FLOW AREA AREA FLOW FLOW (FULL) Q act/Q cap (FULL) Singles (ACT (ha) (ha) (l/s) (ha) (ha) (ha) (l/s) (ha) (ha) (l/s) (l/s) (%) (l/s) (m/s) (m/s) **SERVICING 11** Plua 129A 0.47 64 64 135 0.47 135 3.56 1.56 0.00 0.00 0.00 0.00 0.47 0.47 0.16 1.71 11.5 200 6.00 80.34 0.02 2.56 1.03 To SERVICING 9, Pipe 129A - 130A 0.47 135 0.00 0.00 0.00 0.47 SERVICING 10 127A 202 3.52 2.30 0.00 0.00 0.00 0.59 0.59 0.19 2.50 11.5 200 80.34 0.03 2.56 1.15 Plua 0.59 96 96 0.59 202 0.00 6.00 To SERVICING 9, Pipe 127A - 129A 0.59 202 0.00 0.00 0.00 0.59 126A 127A 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 1.02 0.00 10.5 200 0.95 31.97 0.06 To SERVICING 9, Pipe 127A - 129A 0.00 0.00 0.00 0.00 0.00 0 SERVICING 8 0.00 0.10 121A 124A 0.10 26 0.10 3.69 0.31 0.00 0.00 0.00 0.10 0.03 0.34 50.5 200 0.65 26.44 0.01 0.84 0.29 12 26 To SERVICING 9. Pipe 124A - 127A 0.10 26 0.00 0.00 0.00 0.10 122A 123A 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 44.5 200 0.75 28.40 0.00 0.90 0.05 123A 124A 0.10 12 26 0.10 26 3.69 0.31 0.00 0.00 0.00 0.00 0.10 0.10 0.03 0.34 5.5 200 3.45 60.92 0.01 1.94 0.50 To SERVICING 9, Pipe 124A - 127A 0.10 26 0.00 0.00 0.00 0.10 SERVICING ' 118A 26 0.00 120A 0.08 12 12 26 3.69 0.31 0.00 0.00 0.00 0.08 0.08 0.03 0.34 49.5 200 0.90 31.12 0.01 0.99 0.32 0.08 0.00 0.00 To SERVICING 9, Pipe 120A - 124A 0.08 26 0.00 0.08 119A 120A 26 0.00 0.08 12 12 0.08 26 3.69 0.31 0.00 0.00 0.00 0.08 0.08 0.03 0.34 49.0 200 0.65 26.44 0.01 0.84 0.28 To SERVICING 9, Pipe 120A - 124A 0.08 26 0.00 0.00 0.00 0.08 SERVICING 9 Contribution From SERVICING 13, Pipe 131A - 132A 0.36 101 0.00 0.00 0.00 0.36 0.36 133A 0.36 101 3.59 1.18 0.00 0.00 0.00 0.00 0.36 0.12 1.30 20.0 200 0.35 19.40 0.07 0.62 0.35 0.00 To SERVICING 14, Pipe 133A - 138A 0.36 101 0.00 0.00 0.00 0.36 Contribution From SERVICING 16, Pipe 146A - 147A 0.57 135 0.00 0.00 0.00 0.57 0.57 148A 0.57 135 3.56 1.56 0.00 0.00 0.00 0.00 0.00 0.57 0.19 1.75 29.0 200 1.65 42.13 0.04 1.34 0.65 To SERVICING 19, Pipe 148A - 151A 0.57 135 0.00 0.00 0.00 0.57 Contribution From SERVICING 7, Pipe 118A - 120A 0.08 26 0.00 0.00 0.00 0.08 0.08 Contribution From SERVICING 7, Pipe 119A - 120A 0.08 26 0.00 0.00 0.00 0.08 0.16 124A 0.02 0.18 52 3.65 0.61 0.00 0.00 0.00 0.00 0.02 0.18 0.06 0.67 27.0 200 1.05 33.61 0.02 1.07 0.42 Contribution From SERVICING 8, Pipe 121A - 124A 0.10 26 0.00 0.00 0.00 0.28 0.10 Contribution From SERVICING 8, Pipe 123A - 124A 0.10 26 0.00 0.00 0.00 0.10 0.38 127A 0.38 104 3.59 1.21 0.00 0.00 0.00 0.00 0.00 0.38 0.13 1.34 46.5 200 0.35 19.40 0.07 0.62 0.35 Contribution From SERVICING 10, Pipe 125A - 127A 0.59 202 0.00 0.00 0.00 0.59 0.97 Contribution From SERVICING 10, Pipe 126A - 127A 0.00 0 0.00 0.00 0.00 0.00 0.97 127A 129A 0.97 306 3.46 3.43 0.00 0.00 0.00 0.00 0.00 0.97 0.32 3.75 76.0 200 0.35 19.40 0.19 0.62 0.47 Contribution From SERVICING 11, Pipe 128A - 129A 0.47 135 0.00 0.00 0.00 0.47 1.44 129A 1.45 441 3.40 4.86 0.00 0.00 0.00 0.01 1.45 0.48 5.34 12.5 0.35 19.40 0.28 0.62 0.52 130A 0.01 0.00 200 130A 133A 441 3.40 4.86 0.00 0.00 0.00 1.68 0.55 19.5 200 0.35 19.40 0.62 0.53 0.23 0 1.68 0.00 0.23 5.42 0.28 To SERVICING 14, Pipe 133A - 138A 1.68 0.00 1.68 441 0.00 0.00 DESIGN PARAMETERS Designed: ROJECT Park Flow = 9300 0.10764 CPR Minto - Barrhaven Town Centre Stage 1 I /ha/da I/s/Ha Average Daily Flow = 280 l/p/day Industrial Peak Factor = as per MOE Graph 28000 0.3241 0.330 L/s/ha LOCATION: Comm/Inst Flow = L/ha/da I/s/Ha Extraneous Flow = Checked: City of Ottawa Industrial Flow = 35000 L/ha/da 0.40509 I/s/Ha Minimum Velocity = 0.600 m/s Max Res Peak Factor = 4 00 Manning's n = (Conc) 0.013 (Pvc) 0.013 Dwg. Reference: Commercial/Inst./Park Peak Factor = 1.00 2 Bedroom coeff= 2.1 File Ref: Date: Sheet No Institutional = 0.32 l/s/Ha Sanitary Drainage Plan, Dwgs. No. 15-816 29 Jun 2023



Manning's n=0.013 RESIDENTIAL AREA AND POPULATION INFILTRATION LOCATION COMM INSTIT PARK C+I+I STREET FROM UNITS UNITS CUMULATIVE PEAK ACCU. AREA ACCU. PEAK ACCU. INFILT. TOTAL AREA AREA мн мн AREA POP. FACT. FLOW AREA AREA FLOW AREA FLOW FLOW (FULL) Q act/Q cap (FULL) (ACT. Singles (ha) (ha) (l/s) (ha) (ha) (ha) (l/s) (ha) (ha) (l/s) (l/s) (%) (l/s) (m/s) (m/s) SERVICING 14 Contribution From SERVICING 9, Pipe 130A - 133A 1.68 441 0.00 0.00 0.00 1.68 1.68 101 Contribution From SERVICING 9, Pipe 132A - 133A 0.36 0.00 0.00 0.00 0.36 2.04 133A 138A 0.15 2.19 542 3.36 5.91 0.00 0.00 0.00 0.00 0.15 2.19 0.72 6.63 42.0 200 0.75 28.40 0.23 0.90 0.73 Contribution From SERVICING 15, Pipe 135A - 138A 0.31 135 0.00 0.00 0.00 0.31 2.50 0.24 0.00 0.00 0.24 Contribution From SERVICING 15, Pipe 137A - 138A 101 0.00 2.74 138A 139A 2.74 778 3.29 8.31 0.00 0.00 0.00 0.00 0.00 2.74 0.90 9.21 15.0 200 0.35 19.40 0.47 0.62 0.61 To FUTURE CHAPMAN MILLS DR, Pipe 139A - 140A 2.74 0.00 0.00 778 0.00 2.74 FUTURE CHAPMAN MILLS DR Contribution From SERVICING 14, Pipe 138A - 139A 2.74 778 0.00 0.00 0.00 2.74 2.74 0.00 0.00 139A 140A 1.06 3.80 778 3.29 8.31 0.00 0.00 1.06 3.80 1.25 9.56 250 0.32 0.61 0.54 80.5 0.25 29.73 140A 152A 0.30 0.00 250 37.61 0.64 0 4.10 778 3.29 8.31 0.00 0.00 0.00 0.30 4.10 1.35 9.66 74.5 0.40 0.26 0.77 Contribution From SERVICING 19, Pipe 151A - 152A 1.46 372 0.00 0.00 0.00 1.46 5.56 152A EX SAN 138A 0.13 0 5.69 1150 3.21 11.96 0.00 0.00 0.00 0.00 0.13 5.69 1.88 13.83 36.0 250 0.25 29.73 0.47 0.61 0.59 DESIGN PARAMETERS Designed: ROJECT: L/ha/da Minto - Barrhaven Town Centre Stage 1 Park Flow = 9300 0.10764 CPB Average Daily Flow = 280 l/p/day Industrial Peak Factor = as per MOE Graph Comm/Inst Flow = 28000 L/ha/da 0.3241 l/s/Ha Extraneous Flow = 0.330 L/s/ha Checked: LOCATION: City of Ottawa Industrial Flow = 35000 L/ha/da 0.40509 l/s/Ha Minimum Velocity = 0.600 m/s SLM Max Res. Peak Factor = 4.00 Manning's n = (Conc) 0.013 (Pvc) 0.013 Commercial/Inst./Park Peak Factor = 1.00 2 Bedroom coeff= 2.1 Dwg. Reference: File Ref: Sheet No. Institutional = 0.32 l/s/Ha Sanitary Drainage Plan, Dwgs. No. 15-816 29 Jun 2023 4

CLIENT: LOCATION: FILE REF: DATE:

Minto Communities Barrhaven Town Centre Phase 1 16-816 06-Mar-23

 Avg. Daily Flow Res.
 280
 L/p/d

 Avg. Daily Flow Comm
 28,000
 L/ha/d

 Avg. Daily Flow Instit.
 28,000
 L/ha/d

 Avg. Daily Flow Instit.
 28,000
 L/ha/d

 Avg. Daily Flow Instit.
 35,000
 L/ha/d

 Harmens Corr Factor
 0.8
 0.8

Peak Fact Res. Per Harmons: Min = 2.0, Max =4.0 Peak Fact. Res. Per Hamilons. Will –
Peak Fact. Comm. 1
Peak Fact. Instit. 1
Peak Fact. Indust. per MOE graph

Infiltration / Inflow Min. Pipe Velocity Max. Pipe Velocity Mannings N 0.33 L/s/ha 0.60 m/s full flowing 3.00 m/s full flowing 0.013



	Location				Residential Area and Po	nulation				Commercial	Instit	tutional	Industrial	: 1		Infiltration	1		I				Pipe Data				
Area ID	IDENTIFIER	Up	Down	Area	Number of Units		umulative	Peak.	Q _{res}	Area Accu.			Area Accu.	Q _{C+I+I}	Total	Accu.	Infiltration	Total	DIA	DIA	Slope		Ahvdraulic	R	Velocity	Q _{cap}	Q / Q fu
					by type	Are	a Pop.	Fact.		Area		Area	Area		Area	Area	Flow	Flow	Nominal	Actual			nyaraane		•	псар	
				(ha)	Singles Semi's Town's Apt's	(ha)	(-)	(L/s)	(ha) (ha)	(ha)	(ha)	(ha) (ha)	(L/s)	(ha)	(ha)	(L/s)	(L/s)	(mm)	(mm)	(%)	(m)	(m²)	(m)	(m/s)	(L/s)	(-)
Longfields Drive	School on Longfieds	School	101	0.000		0.0 0.0	0.0	3.80	0.00	0.00	5.61	1 5.61	0.00	1.82	5.610	5.610	1.851	3.67	200	203.2	1.00	14.5	0.032	0.050	1.04	33.9	0.
Longilous Brive	Genoor on Eurigheus	101	102	0.600		0.0 0.6			0.00	0.00		5.61	0.00		0.600			3.87	250	254	0.50	58.0	0.051	0.063	0.86	43.4	
Langfielda Driva	Barrhaven Court Retirement Home	Retirementhome	102	0.000		0.0 0.0	0.0	3.80	0.00	0.00	1.42	2 1.42	0.00	0.46	1.420	1.420	0.469	0.93	200	203.2	2.43	28.0	0.032	0.050	1.63	52.8	0.0
Longfields Drive	Barmaven Court Retilement Home	Retirementionie	102	0.000		0.0 0.0	0.0	3.00	0.00	0.00	1.42	2 1.42	0.00	0.46	1.420	1.420	0.469	0.93	200	203.2	2.43	20.0	0.032	0.050	1.03	52.0	0.0
Longfields Drive		102	103	2.720		174.1 3.3	320 174.1	3.54	1.99	0.00		7.03	0.00	2.28	2.720	10.350	3.416	7.69	250	254	0.74	49.0	0.051	0.063	1.04	52.8	0.1
Marketplace Ave	Dymon Storage	McGarry Terrace	121			0.0	0.0	3.80	0.00	0.603 0.60		0.00	0.00	0.20	0.603	0.603	0.199	0.39	200	203.2	0.65	96.0	0.032	0.050	0.84	27.3	0.0
'	, ,	,																									
	1012-McGarry Street	121	103	0.640		418.0 0.6	418.0	3.41	4.62	0.60		0.00	0.00	0.20	0.640	1.243	0.410	5.23	250	254	2.61	77.5	0.051	0.063	1.96	99.2	0.0
Marketplace Ave	1034 McGary Street & 117 Longfieds Towe	s San Stub	103	0.960		618.0 0.9	618.0	3.34	6.69	0.00		0.00	0.00	0.00	0.960	0.960	0.317	7.01	200	203.4	0.65	18.5	0.032	0.050	0.84	27.3	0.2
Longfields Drive	ROW Only	103	5062	0.280		0.0 5.2	200 1210.1	3.20	12.53	0.60		7.03	0.00	2.47	0.280	12.833	4.235	19.24	250	254	0.70	91.0	0.051	0.063	1.01	51.4	0.3
Longituda Dilvo		100	0002	0.200		0.0 0.1	1210.1	5.20	12.00	0.00		7.03	0.00	2.41	0.200	12.000	4.233	13.24	230	2.04	0.70	31.0	0.001	0.003	1.01	51.4	0.0
Lindshade Drive	Waterford Community Centre + Minto Ampersand	Lindenshade	5062	1.590		642.2 1.5	90 642.2	2 22	6.94	0.00		0.00	0.00	0.00	1.590	1.590	0.525	7.46	200	203.4	1.00	18.0	0.032	0.050	1.04	33.9	0.1
Linushade Drive	+ Minto Ampersand	Lindenshade	5002	1.590		042.2 1.3	90 042.2	3.33	0.94	0.00		0.00	0.00	0.00	1.590	1.590	0.525	7.40	200	203.4	2.75	89.0	0.032	0.050	1.73	56.3	0.2
Longfields	ROW	5062	5063B	0.090			1852.3		18.54	0.60		7.03	0.00		0.090			25.81	250	254	0.50	61.0	0.051	0.063	0.86	43.4	0.5
Longfields	ROW	5063B	5063-A	0.200		7.0	1852.3	3.09	18.54	0.60		7.03	0.00	2.47	0.200	14.713	4.855	25.87	250	254	0.70	29.0	0.051	0.063	1.01	51.4	0.0
Bayrose Drive	Minto Ampersand	Bayrose Drive	5063-A	0.850		25.0 0.8	350 25.0	3.69	0.30	0.00		0.00	0.00	0.00	0.850	0.850	0.281	0.58	250	254	0.70	56.5	0.051	0.063	0.98	49.9	
1 1 - 1 - 1 - 1	DOW	5063-A	5063	0.220			50 4077.0	0.00	40.77	0.60		7.03	0.00	0.47	0.000	45 700	5.000	00.45	000	000.4	4.05	00.0	0.000	0.050	1.17	37.9	0.
Longfields Longfields	ROW ROW	5063-A 5063	5063-B	0.220			1877.3 280 1877.3		18.77 18.77	0.60		7.03	0.00		0.220 0.130			26.45 26.50	200 200	203.4 203.4	1.25 2.84	86.0 96.0	0.032	0.050 0.050	1.17	57.2	0.7
Sue Holloway	Minto Ampersand Minto Ampersand	Sue Holloway	Glenroy Gilbert 5063-B	0.960 1.560		122.4 0.9 100.8 2.5			1.42	0.00		0.00	0.00		0.960 1.560			1.73 3.37	250	254	0.50	53.0	0.051	0.063	0.86	43.4	0.0
Glenroy Gilbert	Minto Ampersand	Glenroy Gilbert	2003-B	1.560		100.8 2.3	520 223.2	3.50	2.53	0.00		0.00	0.00	0.00	1.560	2.520	0.832	3.37	200	203.4	1.10	102.0	0.032	0.050	1.09	35.6	0.0
Barrhaven TC Block 1	Barrhaven TC Block A		5063-B	0.640		126.0 0.6	126.0	3.57	1.46	0.00		0.00	0.00	0.00	0.640	0.640	0.211	1.67									
Longfields Drive	Logfields/Glenroy Gilbert	5063-B	5066	0.180		0.0 11.6	2226.5	3.04	21.93	0.6		7.0	0.0	2.47	0.180	19.253	6.353	30.76	250	254	0.70	53.0	0.051	0.063	1.01	51.4	0.6
	7	5066	5067	0.170		0.0 11.7			21.93	0.60		7.03	0.00	2.47	0.170			30.81	250	254	0.70	45.0	0.051	0.063	1.01	51.4	0.6
		5067	5067-A			11.7	90 2226.5	3.04	21.93	0.60		7.03	0.00	2.47	0.000	19.423	6.410	30.81	250	254	0.70	37.5	0.051	0.063	1.01	51.4	0.6
Chapman Mills Drive Exter	ension Barrhaven TC Block B	13	5067-A	4.190		1142.0 4.1	90 1142.0	3.21	11.88	0.00		0.00	0.00	0.00	4.190	4.190	1.383	13.26	250	254	0.50	187.0	0.051	0.063	0.86	43.4	0.3
		5007.4	5070	0.700				0.00	04.07			7.00		0.47	0.700	04.040	0.000	40.07	050	054		05.0	0.054		0.05	40.0	
Longfields Drive		5067-A 5070	5070 5071	0.700 0.180		0.0 16.8			31.87 31.87	0.60		7.03 7.03	0.00		0.700 0.180			42.37 42.43	250 250	254 254	0.62	65.0 49.0	0.051	0.063	0.95 1.01	48.3 51.4	8.0
		5070	5072	0.100		0.0 16.8			31.87	0.60		7.03	0.00		0.180			42.43	250	254	0.70	60.0	0.051	0.063	1.01	51.4	
		5072	5073	0.210		0.0 17.3			31.87	0.60		7.03	0.00		0.210			42.57	250	254	0.70	55.0	0.051	0.063	1.01	51.4	
		5073	5076	0.160		0.0 17.4			31.87	0.60		7.03	0.00		0.160			42.62	250	254	0.70	43.5	0.051	0.063	1.01	51.4	
		5076	5077	0.220		0.0 17.6			31.87	0.60		7.03	0.00		0.220			42.69	250	254	1.56	59.5	0.051	0.063	1.51	76.7	0.5
Garrity Crescent		124	5077	7.690		623.7 7.6	90 623.7	3.34	6.75	0.00		0.00	0.00	0.00	7.690	7.690	2.538	9.29	200	203.4	0.50	24.3	0.032	0.050	0.74	24.0	0.3
Longfields Drive		5077	5051	0.280		0.0 25.6	3992.2	2.87	37.10	0.60		7.03	0.00	2.47	0.280	33.273	10.980	50.55	250	254	1.91	78.5	0.051	0.063	1.67	84.8	0.6
Paul Metivier Drive		101	5051	34.580		4954.3 34.5		2.80	44.94	0.00	5.07		0.00		39.650			59.67	450	457.2	0.15	79.5	0.164	0.113	0.69	114.0	0.5
		100A	5051	1.430		89.1 1.4	30 89.1	3.61	1.04	0.00		0.00	0.00	0.00	1.430	1.430	0.472	1.51	200	203.4	0.32	3.4	0.032	0.050	0.59	19.2	0.0
Longfields Drive		5051	5079	0.160		0.0 61.8	9035.6	2.60	76.09	0.60		12.10	0.00	4.12	0.160	74.513	24.589	104.80	1050	1066.8	0.10	68.0	0.894	0.263	1.00	891.4	0.1
		5079	5080	0.160		0.0 61.9			76.09	0.60		12.10	0.00		0.160			104.85	1050	1066.8	0.10	60.0	0.894	0.263	1.00		0.1
		5080	5081	0.210		0.0 62.			76.09	0.60		12.10	0.00		0.210			104.92	1050	1066.8	0.52	75.0	0.894	0.263	2.27		0.0
		5081	5082	0.150		0.0 62.3	9035.6	2.60	76.09	0.60		12.10	0.00	4.12	0.150	75.033	24.761	104.97	1050	1066.8	0.02	55.0	0.894	0.263	0.45	398.6	0.2



DYMOND STORAGE

Dymon Self Stroage - 1000 N

Wastewater Design Ca McGary Terrace - 121 0.603 ha Commercial

Calculation Method 1 (City of Ottawa Design Guidelines):

0.603 ha Total Gross Area =

28,000 L/ha/day - per City of Ottawa Design Guidelines Theoritical Unit Rate =

Average Wastewater Flow = 16884 L/day

Average Wastewater Volume = 0.39 L/s (assuming 12 hour operation)

1.5 Peaking Factor = Infiltration 0.33 L/s/ha= 0.20 L/s

Peak Design Flow = 0.79 L/s

Calculation Method 2 (Mechanical Fixture Count):

75 GPM = 4.73 L/sProposed 5-Storey Building Sani. Flow = 10 GPM = 0.63 L/sProposed Floor Drains of Building = Anticipated Total Peak Flow = 85 GPM = 5.36 L/s

Peak Design Flow = 5.36 L/s

Use the most conservative method; Q = 5.36 L/s

The proposed 150 mm diameter sanitary service with a slope of ± 0.5% has a capacity of 11.2 L/s and a full flow velocity of 0.62 m/s. Therefore, the proposed sanitary service has sufficient capacity to accommodate the Peak Design Flow of 5.36 L/s.

Howard Grant 1012-1024 McGarry Terrace Proposed Site Conditions

Wastewater Design Flows per Unit Count City of Ottawa Sewer Design Guidelines, 2004



Site Area	0.640 ha
-----------	-----------------


Extraneous Flow Allowances


	Infiltration / Inflow (Dry) Infiltration / Inflow (Wet) Infiltration / Inflow (Total)		0.03 L/ 0.16 L/ 0.21 L/	s
Domestic Contributions				
Unit Type	Unit Rate	Units	Рор	
Single Family	3.4		0	
Semi-detached and duplex	2.7		0	
Townhouse	2.7		0	
Stacked Townhouse	2.3		0	
Apartment				
Bachelor	1.4		0	
1 Bedroom	1.4		0	
2 Bedroom	2.1		0	
3 Bedroom	3.1		0	
Average	1.8	232	418	


Total Pop	418	
Average Domestic Flow	1.35 L	/s
Peaking Factor	3.41	
Peak Domestic Flow	4.62 L	/s

Total Estimated Average Dry Weather Flow Rate	1.39 L/s
Total Estimated Peak Dry Weather Flow Rate	4.65 L/s
Total Estimated Peak Wet Weather Flow Rate	4.86 L/s

1012 McGARY STREET 121-103 0.64 ha - 418pers.











Table 1.1: Development Statistic Projections

Land Use	Total Area (ha)	Projected Residential Units	Residential Population per Unit *	Projected Population *
Block A – Stacked Townhouse Units	0.64	60	2.1	126
Block B – Stacked Townhouse Units	4.19	544	2.1	1142
Glenroy Gilbert Drive Extension	0.39	-	-	-
TOTAL	5.21	604		1268

^{*} NOTE: Population projections may differ from population estimates used in background Transportation Studies, Planning Rationale, and other studies. Population projection and residential population per unit values are based on Ministry of Environment, Conservation and Parks guidelines for servicing demand calculations. Local Roads are included in Total Area estimates above.


MINTO BTC BLOCK A 5063-B 0.64 ha. - 126 pers.

MINTO BTC BLOCK B 13 -5067-A 0.65ha. - 1142 pers.




APPENDIX D

Stormwater Servicing Documents



STORM SEWER CALCULATION SHEET (RATIONAL METHOD)

Local Roads Return Frequency = 2 years Collector Roads Return Frequency = 5 years Arterial Roads Return Frequency = 10 years





Manning	0.013	i	Arterial Ro	oads Return	Frequency	= 10 years				1551 (11)											A11/			Г								
	LOC	ATION		0.1/	EAR		1		YEAR	AREA (Ha)	10 YE	4 D		1	400.1	YEAR		Time of	Intensity		LOW	Indonesia.	D 1 F1	DIA ()	Inta (TVDE		SEWER DAT	CAPACITY	TI OCIT	TREOF	DATIO
		1	AREA	2 Y		A ======	ADEA	5 1	Indiv.	Accum. AREA	10 YE	Indiv.	Accum.	AREA	100	Indiv.	Accum.	Conc.	2 Year	5 Year	Intensity 10 Year			DIA. (mm)	DIA. (mm	IYPE	SLOPE	LENGIH	CAPACITY	VELOCII	TIME OF	KAHO
Location	From Node	e To Node	4	R	Indiv. 2.78 AC	Accum. 2.78 AC	AREA (Ha)	R	2.78 AC		R		2.78 AC	4	R		2.78 AC	(min)	(mm/h)	(mm/h)	(mm/h)	(mm/h)	Q (1/s)	(actual)	(nominal)		(%)	(m)	(l/s)	(m/s)	LOW (mir	O/O full
			, ,				` '							` ′				,	, ,	, ,		,										``
SERVICI	NG 6																															
	107	108			0.00	0.00	0.17	0.74		0.35		0.00	0.00			0.00	0.00	10.00		104.19		178.56	36	300	300	PVC		15.5	167.4906			0.218
	108	109			0.00	0.00			0.00	0.35		0.00	0.00			0.00	0.00	10.11	76.39	103.62	121.47	177.57	36	300	300	PVC	0.35	15.5	57.2089	0.8093	0.3192	0.633
To GLEN	ROY GILB	BERT DR, I	Pipe 109 -	110		0.00				0.35			0.00				0.00	10.43														
SERVICI	NG 5				1	1	1		1																							
OLIVIOI	104	105			0.00	0.00	0.25	0.77	0.54	0.54	+	0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	56	300	300	PVC	0.65	16.0	77.9626	1.1029	0.2418	0.715
	105	106			0.00	0.00			0.00	0.54		0.00	0.00			0.00	0.00	10.24	75.89	102.93			55	300	300	PVC	0.55	15.5	71.7152		0.2546	
To GLEN	ROY GILB	ERT DR, I	Pipe 106 -	109		0.00				0.54			0.00				0.00	10.50														
SERVICI																																
	100	101			0.00	0.00	0.13	0.74	0.27	0.27		0.00	0.00			0.00	0.00	10.00	76.81	104.19			28	300	300	PVC	1.80	16.5	129.7377		0.1498	
To CLEN	101	103	Pipe 103 -	106	0.00	0.00		ļ	0.00	0.27 0.27		0.00	0.00	-		0.00	0.00	10.15 10.47	76.23	103.41	121.22	177.20	28	300	300	PVC	0.35	15.5	57.2089	0.8093	0.3192	0.483
10 GLEIN	KOT GILB	EKI DK, I	Pipe 103 -	100		0.00				0.27			0.00				0.00	10.47														
GLENRO	Y GILBER	RT DR																														
		T	1		0.00	0.00	0.05	0.64	0.09	0.09		0.00	0.00	1	1	0.00	0.00	1	1	1	1	1	1	1	1	1	1	1		1	1	1
					0.00	0.00	0.04	0.58	0.06	0.15		0.00	0.00			0.00	0.00															
	102				0.00	0.00	0.03	0.64	0.05	0.21		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	22	300	300	PVC	0.35	30.0	57.2089	0.8093	0.6178	0.377
Contribut	ion From S	SERVICINO	G 2, Pipe 1	01 - 103		0.00				0.27			0.00				0.00	10.47														
					0.00	0.00	0.03	0.54		0.52		0.00	0.00			0.00	0.00					1										
					0.00	0.00	0.07	0.64		0.64		0.00	0.00			0.00	0.00															
	103	106			0.00	0.00	0.08	0.64	0.14	0.79		0.00	0.00			0.00	0.00	10.62	74 51	101.04	118.43	173 10	97	450	450	CONC	0.25	85.0	142.5531	0.8963	1 5805	0.679
Contribut			G 5, Pipe 1	05 - 106	0.00	0.00	0.00	0.77	0.17	0.54		0.00	0.00			0.00	0.00	10.50	74.01	101.04	110.40	170.10	- 07	400	400	00110	0.20	00.0	142.0001	0.0000	1.0000	0.070
			1		0.00	0.00	0.01	0.77	0.02	1.51		0.00	0.00			0.00	0.00															
					0.00	0.00	0.03	0.54	0.05	1.56		0.00	0.00			0.00	0.00															
					0.00	0.00	0.09	0.64	0.16	1.72		0.00	0.00			0.00	0.00															
	106	109	0.0.0: 4	00 100	0.00	0.00	0.10	0.64	0.18	1.90		0.00	0.00			0.00	0.00	12.20	69.28	93.86	109.97	160.68	178	525	525	CONC	0.45	68.0	288.4945	1.3327	0.8504	0.617
Contribut		EX STM	3 6, Pipe 1	08 - 109	0.00	0.00		1	0.00	0.35 2.25		0.00	0.00			0.00	0.00	10.43 13.05	66.79	90.44	105.95	154.78	203	525	525	CONC	0.40	10.5	271.9953	4.0505	0.1393	0.747
	109	EX 31IVI	112		0.00	0.00			0.00	2.23		0.00	0.00			0.00	0.00	13.03	00.79	90.44	105.95	134.76	203	323	323	CONC	0.40	10.5	21 1.9933	1.2303	0.1393	0.747
RIOCAN	AVE																															
	154	155			0.00	0.00	0.05	0.72	0.10	0.10		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	10	300	300	PVC	2.00	56.0	136.7555	1.9347	0.4824	0.076
					0.00	0.00	0.16	0.66	0.29	0.39		0.00	0.00			0.00	0.00															
	155	156			0.00	0.00	0.32	0.72		1.03		0.00	0.00			0.00	0.00	10.48			119.22			450	450		0.25		142.5531		1.4504	
	156	EX STM	MH		0.00	0.00			0.00	1.03		0.00	0.00			0.00	0.00	11.93	70.10	94.98	111.30	162.63	98	450	450	CONC	0.20	6.0	127.5033	0.8017	0.1247	0.770
SERVICI	NG 21				-	-			+		-																					
SERVICI	Plug	146			0.00	0.00			0.00	0.00		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122 14	178.56	0	300	300	PVC	1.00	2.5	96.7008	1.3680	0.0305	0.000
	146	150			0.00	0.00			0.00	0.00		0.00	0.00			0.00	0.00	10.03	76.69	104.03			0	300	300	PVC	0.35	25.5	57.2089	0.8093	0.5251	
To SERV	ICING 19,	Pipe 150 -	- 151			0.00				0.00			0.00				0.00	10.56														
																													,			
	Plug	148	ļ		0.00	0.00	0.18	0.78		0.39		0.00	0.00	ļ		0.00	0.00	10.00		104.19		178.56	41	375	375	PVC	1.00	1.0			0.0105	
	148 149	149 150	1		0.00	0.00	0.24	0.74	0.00	0.39		0.00	0.00	1	1	0.00	0.00	10.01	76.76		122.08 119.24		41	450 600	450 600	CONC	0.20 0.15	22.5	127.5033 237.8056		0.4678	0.319
To SERV	149 ICING 19,		. 151		0.00	0.00	0.24	0.74	0.49	0.88 0.88		0.00	0.00			0.00	0.00	10.48 10.52	75.02	101.73	119.24	174.30	90	600	600	CONC	0.15	2.0	237.8056	0.8411	0.0396	0.378
TO SLIV	ICING 19,	Fipe 130 -	- 131			0.00				0.00	+		0.00				0.00	10.52														
SERVICI	NG 16	1	1			1	1	1	1					1	1	1		1	1	1	1	1	1	1	1	1	1	1		1	1	1
	Plug	141			0.00	0.00			0.00	0.00		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	0	300	300	PVC	1.00	2.5	96.7008	1.3680	0.0305	0.000
To SERV	ICING 17,	Pipe 141 -	- 143			0.00				0.00			0.00				0.00	10.03														
OED: "C:	10.45	 	 			-	 	 						 					<u> </u>	 						 	<u> </u>				<u> </u>	
SERVICI		L CONTIONAL	2.46 Die	140 141	-	0.00	1	 	+	0.00		-	0.00	1	1		0.00	10.00	1	1	1	1	1	1		1	1	1			1	
Contribut	ion From S		G 16, Pipe	140 - 141	0.00	0.00	-	}	0.00	0.00	\longrightarrow	0.00	0.00	}	1	0.00	0.00	10.03	76 60	104.03	121.95	179 29	0	300	300	D//C	0.35	25.5	57.2089	U 8003	0.5251	0.000
To SFRV	ICING 19,		- 144	1	0.00	0.00	1	1	0.00	0.00	-+	0.00	0.00	1	 	0.00	0.00	10.03	10.08	104.03	121.53	110.20	T -	500	300	1 40	0.00	20.0	31.2009	0.0083	0.0201	0.000
. U ULIKV			T			0.00	1		1	1			0.00				0.00				1	1	1									
			Ì				İ	İ	1					i e						Ì	Ì	İ	Ì			Ì						
Definition												•											Designed:			PROJECT	1					
Q = 2.78 A	AIR, where									Notes:															CPB	<u></u>		Mir	nto - Barrha	ven Town	Centre Stag	ge 1

Q = Peak Flow in Litres per second (L/s)

A = Areas in hectares (ha)


I = Rainfall Intensity (mm/h) R = Runoff Coefficient

1) Ottawa Rainfall-Intensity Curve

2) Min. Velocity = 0.80 m/s

Minto - Barrhaven Town Centre Stage 1 Checked: LOCATION: SLM City of Ottawa Dwg. Reference: File Ref: Date: Sheet No. 15-816 29 Jun 2023 SHEET 1 OF 3

STORM SEWER CALCULATION SHEET (RATIONAL METHOD) Local Roads Return Frequency = 2 years Collector Roads Return Frequency = 5 years Arterial Roads Return Frequency = 10 years





wanning	0.013		Arteriai Ko	aus Ketuili	rrequency	- 10 years				AREA (Ha)										FI	LOW							SEWER DAT	TΛ			
	LOC	ATION		2 YI	EAR		1	5.	YFAR	ANEA (III)	10 YEA	R			100	YEAR		Time of	Intensity	Intensity		Intensity	Peak Flow	DIA. (mm)	DIA. (mm	TYPE			CAPACITY	VELOCIT	TIME OF	RATIO
			AREA		Indiv.	Accum.	AREA		Indiv.	Accum. AREA		Indiv.	Accum.	AREA		Indiv.	Accum.	Conc.	2 Year	5 Year										1		
ocation	From Nod	To Node	(Ha)	R	2.78 AC		(Ha)	R		2.78 AC (Ha)			2.78 AC		R	2.78 AC	2.78 AC	(min)	(mm/h)	(mm/h)	(mm/h)	(mm/h)	Q (l/s)	(actual)	(nominal))	(%)	(m)	(l/s)	(m/s)	LOW (min	Q/Q ful
																															-	
		400			0.00	0.00	0.40	0.70	0.40	0.40		0.00				0.00		10.00	70.04	40440	100.11	470.50		075	075	D) (0	4.00		475.0004	4.5075	0.0405	0.005
	Plug 160	160 159			0.00	0.00	0.18	0.79	0.40	0.40 0.40		0.00	0.00			0.00	0.00	10.00	76.81	104.19 104.14			41 41	375 375	375 375	PVC	1.00 0.30	1.0 22.5	175.3301 96.0323		0.0105 0.4313	0.235
	159	143			0.00	0.00	0.25	0.71		0.40		0.00	0.00			0.00	0.00	10.01			119.46			375	375	PVC			117.6150			
o SFRV		Pipe 143 -	144		0.00	0.00	0.23	0.71	0.49	0.89		0.00	0.00			0.00	0.00	10.44	73.13	101.92	119.40	174.02	91	313	313	FVC	0.43	2.0	117.0130	1.0043	0.0313	0.770
0 02.11	100	1 100 1 10	1			0.00				0.00			0.00				0.00													•		
ERVICI	NG 19																															
	142	143			0.00	0.00			0.00	0.00		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	0	375	375	PVC	0.30	6.0	96.0323	0.8695	0.1150	0.000
			3 17, Pipe			0.00				0.00			0.00				0.00	10.56													L	
Contribut			3 17, Pipe	159 - 143	0.00	0.00			2.22	0.89			0.00			0.00	0.00	10.47		404.05	440.70	470.00		450	450	00110		40.5	407 5000	0.0047	0.0500	0.700
		144	0.0.0	04 444	0.00	0.00	1	1	0.00	0.89		0.00	0.00			0.00	0.00	10.56	74.74	101.35	118.79	173.63	90	450	450	CONC	0.20	12.5	127.5033	0.8017	0.2599	0.706
ontribut		150	3 9, Pipe 1	64 - 144	0.00	0.00			0.00	0.86 1.75		0.00	0.00			0.00	0.00	10.05 10.82	72 01	100.07	117.29	171 /2	175	600	600	CONC	0.15	50.0	227 9056	0.9411	0.9908	0.735
Contribut			3 21, Pipe	146 - 150	0.00	0.00			0.00	0.00		0.00	0.00			0.00	0.00	10.56	73.01	100.07	117.29	17 1.43	173	000	000	CONC	0.13	30.0	237.0030	0.0411	0.9900	0.733
			3 21, Pipe			0.00				0.88			0.00				0.00	10.52														
	150				0.00	0.00			0.00	2.63		0.00	0.00			0.00	0.00	11.81	70.50	95.53	111.94	163.58	251	675	675	CONC	0.15	13.5	325.5584	0.9098	0.2473	0.772
Γο FUTU	RE CHAP	MAN MILLS	S DR, Pipe	151 - 152		0.00				2.63			0.00				0.00	12.05												1		
																															·	
SERVICI																															L	
	Plug	129			0.00	0.00			0.00	0.00		0.00	0.00			0.00	0.00	10.00		104.19		178.56	0	300	300	PVC		2.5	96.7008		0.0305	
T. OEDV	129	135	100		0.00	0.00	1	1	0.00	0.00		0.00	0.00			0.00	0.00	10.03	76.69	104.03	121.95	178.28	0	300	300	PVC	2.50	23.0	152.8973	2.1631	0.1772	0.000
IO SERV	ICING 14,	Pipe 135 -	138			0.00			+	0.00			0.00	-			0.00	10.21		<u> </u>				-					-	+		
	Plug	133			0.00	0.00	0.11	0.79	0.24	0.24		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	25	375	375	PVC	1.00	1.0	175.3301	1.5875	0.0105	0.144
	133	134			0.00	0.00	0.11	0.19	0.00	0.24		0.00	0.00			0.00	0.00	10.00			122.14			450	450		0.20		127.5033			
	100	134			0.00	0.00			0.00	0.24		0.00	0.00			0.00	0.00	10.01	70.70	104.14	122.00	170.40	20	430	430	CONC	0.20	10.0	127.0000	0.0017	0.5222	0.137
	Plug	131			0.00	0.00	0.18	0.76	0.38	0.38		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	40	375	375	PVC	1.00	1.0	175.3301	1.5875	0.0105	0.226
	131	134			0.00	0.00			0.00	0.38		0.00	0.00			0.00	0.00	10.01		104.14		178.46	40	375	375	PVC	2.45	20.0	274.4351		0.1342	0.144
	134	135			0.00	0.00	0.22	0.76	0.46	1.09		0.00	0.00			0.00	0.00	10.33	75.55	102.47	120.11	175.57	111	600	600	CONC	0.15	2.0	237.8056	0.8411	0.0396	0.468
To SERV	ICING 14,	Pipe 135 -	138			0.00				1.09			0.00				0.00	10.37														
SERVICI					0.00	0.00		0.04	0.40	0.40		0.00				0.00		10.00	70.04	10110	100.11	470.50	- 10	075	075	D) (0	0.55	45.5	0000170	0.0040	0.0004	
To CEDV	Plug	115 Pipe 115 - 1	116		0.00	0.00	0.08	0.81	0.18	0.18 0.18		0.00	0.00	-		0.00	0.00	10.00	76.81	104.19	122.14	178.56	19	375	375	PVC	3.55	15.5	330.3473	2.9910	0.0864	0.057
IU SERV	ICING 9, F	-ipe 115 -	110			0.00			+	0.16			0.00				0.00	10.09		1										+		
	Plug	115			0.00	0.00	0.11	0.79	0.24	0.24		0.00	0.00			0.00	0.00	10.00	76.81	104 19	122.14	178 56	25	375	375	PVC.	0.30	6.5	96.0323	0.8695	0.1246	0.262
To SERV		Pipe 115 - 1	116		0.00	0.00	0	0.10	0.2.	0.24		0.00	0.00			0.00	0.00	10.12	70.01	101110		110.00		0.0	0.0		0.00	0.0	00.0020	0.0000	0.12.0	0.202
SERVICI	NG 9																															
	164				0.00		0.46	0.67	0.86	0.86		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	89	450	450	CONC	0.20	2.5	127.5033	0.8017	0.0520	0.700
		Pipe 144 -		L		0.00				0.86			0.00				0.00	10.05													<u> </u>	
			3 10, Pipe			0.00	1	1	+ +	0.18			0.00	1		1	0.00	10.09	1	1	1	1	1	1		1	1	1	1	+		
Contribut	115		ıu, Pipe	114 - 115	0.00	0.00	0.36	0.68	0.68	0.24 1.10	-	0.00	0.00			0.00	0.00	10.12 10.12	76.32	103.54	121 27	177.43	114	375	375	CONC	0.70	3.0	146 6017	1 2202	0.0376	0.778
	110	110			0.00	0.00	0.30	0.08	0.00	1.10		0.00	0.00			0.00	0.00	10.12	10.33	103.34	121.37	177.43	114	3/3	3/3	CONC	0.70	3.0	140.0917	1.3202	0.0370	0.778
	112	116		1	0.00	0.00	1	1	0.00	0.00		0.00	0.00	1	1	0.00	0.00	10.00	76.81	104.19	122.14	178.56	0	300	300	PVC	0.35	61.0	57.2089	0.8093	1.2562	0.000
	116	117			0.00	0.00	1	1	0.00	1.10		0.00	0.00			0.00	0.00	11.26	72.30				108	525	525		0.20	82.0		0.8885		
	117	127			0.00	0.00			0.00	1.10		0.00	0.00			0.00	0.00	12.79	67.52	91.43	107.12	156.50	101	525	525		0.20	19.5	192.3297	0.8885	0.3658	0.524
To SERV	ICING 14,	Pipe 127 -	135			0.00				1.10			0.00				0.00	13.16														
SERVICI		4				0	1	1	1					ļ				40		40	105	480						L	00 ===	1.5	100:00	
- OED)	Plug		105		0.00	0.00		-	0.00	0.00	L	0.00	0.00	1		0.00	0.00	10.00	76.81	104.19	122.14	178.56	0	300	300	PVC	1.00	4.0	96.7008	1.3680	0.0487	0.000
IO SERV	ICING 12,	Pipe 119 -	125	-		0.00	1	1	+	0.00			0.00	 		-	0.00	10.05	 	 	1	<u> </u>	 	-		-	 	<u> </u>	 	-	 	
	Plua	121			0.00	0.00	0.18	0.78	0.39	0.39		0.00	0.00	1		0.00	0.00	10.00	76.81	10// 10	122.14	178 56	41	375	375	PVC	1.00	2.5	175 3301	1 5975	0.0262	0.333
To SERV		Pipe 121 -	124		0.00	0.00	0.10	0.70	0.08	0.39		5.00	0.00	1		0.00	0.00	10.00	70.01	104.18	122.14	170.00		515	513	1 40	1.00	2.3	170.0001	1.5015	0.0202	0.232
. J OLIKY	1 12,	. ipo 121 -	.27	1		5.00	1	1	1 1	3.00			0.00	1	1	1	0.00	10.00	1	1	1	1	1	1	1	1	1	1	1		+	
							1	1													1										\vdash	
Definition	s:		•	•			•	•		t l					•	•		•	•			•	Designed:		•	PROJECT	:	•		•		
Q = 2.78 A	AIR, where									Notes:															CPB			Mi	nto - Barrha	ven Town	Centre Star	ge 1

Q = 2.78 AIR, where Q = Peak Flow in Litres per second (L/s)

A = Areas in hectares (ha)

I = Rainfall Intensity (mm/h) R = Runoff Coefficient

1) Ottawa Rainfall-Intensity Curve

2) Min. Velocity = 0.80 m/s

CPB

Minto - Barrhaven Town Centre Stage 1 Checked: LOCATION: City of Ottawa SLM Dwg. Reference: Sheet No. SHEET 2 OF 3 File Ref: 15-816 29 Jun 2023

STORM SEWER CALCULATION SHEET (RATIONAL METHOD)



Manning	0.013	:		Roads Retu Roads Returr																				MULLIVY					MYY	U		
viailillig			Anchair	coaus Returi	rrequency	/ = 10 years				AREA (Ha)										FI	_OW			I				SEWER DA	TA			
	LOC	ATION		2 Y	ÆAR			5 `	YEAR	1	10 Y	/EAR			100 \	/EAR		Time of	Intensity	Intensity		Intensity	Peak Flow	DIA. (mm)	DIA. (mm) TYPE			CAPACITY	VELOCITY	TIME OF	RATIO
			AREA	R	Indiv.	Accum.	AREA	R	Indiv.	Accum. AREA	R	Indiv.	Accum.	AREA	R	Indiv.	Accum.	Conc.	2 Year	5 Year	10 Year	100 Year					(0.1)		40			0.10.0
ocation	From Nod	e To Node	(Ha)		2.78 AC	2.78 AC	(Ha)		2.78 AC	2.78 AC (Ha)		2.78 AC	2.78 AC	(Ha)		2.78 AC	2.78 AC	(min)	(mm/h)	(mm/h)	(mm/h)	(mm/h)	Q (l/s)	(actual)	(nominal)		(%)	(m)	(l/s)	(m/s)	LOW (min	Q/Q fu
FRVIC	ING 13					1	1																							-	-	
	Plug	123			0.00	0.00	0.08	0.81	0.18	0.18		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	19	375	375	PVC	1.00	2.5	175.3301	1.5875	0.0262	0.107
o SER\	/ICING 12,	Pipe 123	- 124			0.00				0.18			0.00				0.00	10.03														
EDV/IC	ING 12																													<u> </u>	ļ	
		SERVICIN	G 11 Pine	118 - 119		0.00	1			0.00			0.00				0.00	10.05												-	-	
01141104		125	1	1	0.00	0.00			0.00	0.00		0.00	0.00			0.00	0.00	10.05	76.62	103.94	121.84	178.11	0	300	300	PVC	1.05	23.0	99.0888	1.4018	0.2735	0.00
	/ICING 14,					0.00				0.00			0.00				0.00	10.32														
ontribu				122 - 123		0.00			0.00	0.18		0.00	0.00			0.00	0.00	10.03	70.70	404.05	404.00	470.00	40	275	275	D) (C	0.20	45.0	00 0000	0.0005	0.0075	0.40
Contribu	123			120 - 121	0.00	0.00	-		0.00	0.18 0.39		0.00	0.00			0.00	0.00	10.03	76.70	104.05	121.98	1/8.32	19	375	375	PVC	0.30	15.0	90.0323	0.8695	0.2875	0.19
, , , , , , , , , , , , , , , ,	121			1	0.00				0.00	0.39		0.00	0.00			0.00	0.00	10.03	76.70	104.05	121.98	178.32	41	375	375	PVC	1.35	20.0	203.7152	1.8445	0.1807	0.199
Contribu				e 162 - 124		0.00				0.54			0.00				0.00	10.47														
o SED	124 /ICING 14,	125 Pino 125		+	0.00	0.00	+	1	0.00	1.11	-	0.00	0.00	-		0.00	0.00	10.47 10.51	75.06	101.80	119.32	174.42	113	450	450	CONC	0.20	2.0	127.5033	0.8017	0.0416	0.88
U SEKI	TICING 14,	ripe 125	- 12/	+	 	0.00		+	+	1.11	+		0.00				0.00	10.51												 	 	
ERVIC	NG 14																															
				1	0.00	0.00	0.01	0.69	0.02	0.02		0.00	0.00			0.00	0.00	40	70 - :	40	105	480							404			
	163 162	162 124			0.00	0.00	0.06	0.69	0.12	0.13 0.54		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14 119.92		14 55	300 300	300 300	PVC PVC	1.65 0.45	38.5 5.5			0.3651	
To SER\	/ICING 12,		- 125		0.00	0.00	0.20	0.73	0.41	0.54		0.00	0.00			0.00	0.00	10.37	73.43	102.30	119.92	173.25	33	300	300	FVC	0.43	3.3	04.0000	0.9177	0.0555	0.002
Contribu	tion From S	SERVICIN	G 12, Pipe	119 - 125		0.00				0.00			0.00				0.00	10.32														
Contribu			G 12, Pipe	124 - 125		0.00			0.00	1.11		0.00	0.00				0.00	10.51	74.04	404.50	440.00	474.00	440	222	222	00110	0.45	00.0	207.2252	0.0444	0.4000	0.47
	125	127			0.00	0.00			0.00	1.11		0.00	0.00			0.00	0.00	10.51	74.91	101.59	119.08	174.06	113	600	600	CONC	0.15	22.0	237.8056	0.8411	0.4360	0.474
	126	127			0.00	0.00	0.34	0.64	0.60	0.60		0.00	0.00			0.00	0.00	10.00	76.81	104.19	122.14	178.56	63	450	450	CONC	0.20	3.0	127.5033	0.8017	0.0624	0.494
Contribu				117 - 127		0.00				1.10			0.00				0.00	13.16														
> 4il		135		100 105	0.00	0.00			0.00	2.82		0.00	0.00			0.00	0.00	13.16	66.48	90.01	105.45	154.04	254	600	600	CONC	0.30	39.0	336.3080	1.1894	0.5465	0.754
				e 129 - 135 e 134 - 135		0.00				1.09			0.00				0.00	10.21												 		
Jonanba	135			7 104 100	0.00				0.00	3.90		0.00	0.00			0.00	0.00	13.71	65.00	87.98	103.06	150.53	344	675	675	CONC	0.30	13.5	460.4091	1.2866	0.1749	0.746
o FUTL	IRE CHAP	MAN MILL	S DR, Pip	e 138 - 13	9	0.00				3.90			0.00				0.00	13.88														
UTUDE	CHAPMA	N MILLO		-	1	-		1																						ļ	ļ	
UIUKE	CHAPMA	N MILLS	JK I																											 		
Contribu	tion From S	SERVICIN	G 14, Pipe	135 - 138		0.00				3.90			0.00				0.00	13.88														
	138	139			0.00				0.00	3.90		0.00	0.00			0.00	0.00	13.88	64.54	87.35	102.32	149.45	341	750	750	CONC	0.25	80.0	556.6385	1.2600	1.0582	0.613
	139	151		-	0.00	0.00			0.00	3.90 0.72	0.70	0.00 1.40	0.00 1.40			0.00	0.00	14.94	61.91	83.75	98.08	143.23	464	750	750	CONC	0.40	75.5	704.0982	1.5938	0.7895	0.660
Contribu			I G 19. Pipe	e 150 - 151		0.00			0.00	2.63	0.70	1.40	0.00			0.00	0.00	12.05	01.91	03.73	90.00	143.23	404	730	730	CONC	0.40	13.3	704.0902	1.5950	0.7093	0.000
		EX STM			0.00				0.00	6.53		0.00	1.40			0.00	0.00	15.73	60.10	81.27	95.17	138.95	664	750	750	CONC	0.70	36.5	931.4344	2.1083	0.2885	0.713
																															ļ	
																														 		
	1		<u> </u>	†	†	1	1	†	+		<u> </u>			<u> </u>	t											<u> </u>						
			1	+	1	1		1																						 	 	-
	1	 	 	+	 	+		+	+		+																			 	 	
	1		1	+	1	1	1	1	-			1	-	ļ	-				1			-	1			 				<u> </u>	<u> </u>	-
	1		1	+	1	1	1	1			-			1	1										1	 	1			 		
				<u> </u>				1																								
efinition	s: AIR, where									Notes:													Designed:		CPB	PROJECT	:		nto - Barrha	won T	Contro Ct-	no 1
	AIK, where Flow in Liti		nd (I /s)							Notes: 1) Ottawa Rainfall-In	toneity Curve												Checked:		Crb	LOCATIO	NI.	IMI	iiio - Darrna	veil rown C	sentre stag	ye i

-							
C) =	2	78	ΑĬ	R	wh	ere

Q = Peak Flow in Litres per second (L/s) A = Areas in hectares (ha)

I = Rainfall Intensity (mm/h)
R = Runoff Coefficient

Ottawa Rainfall-Intensity Curve
 Min. Velocity = 0.80 m/s

Checked: LOCATION: SLM City of Ottawa Dwg. Reference: File Ref: Date: Sheet No. SHEET 3 OF 3

15-816

29 Jun 2023

Area ID	Total Area (m²)	Pervious Area (m²)	Impervious Area (m²)	RC
		South Block		
155-156	1634	560	1074	0.66
115-116	3649	1147	2502	0.68
PLUG-115	818	105	713	0.81
PLUG-115	1094	172	922	0.79
136-137	115	54	61	0.57
137-138	1575	158	1418	0.83
PLUG-131	1836	367	1469	0.76
126-127	3378	1255	2123	0.64
PLUG-121	1756	301	1455	0.78
103-106	767	142	625	0.77
106-109	104	19	85	0.77
163-162	742	223	519	0.69
162-124	1965	477	1488	0.73
134-135	2165	433	1732	0.76
122-123	818	105	713	0.81
161-160	1756	276	1480	0.79
164-144	4609	1514	3095	0.67
PLUG-133	1094	172	922	0.79
147-148	1796	308	1488	0.78
139-151	1730	384	1346	0.74
159-143	2464	657	1807	0.71
149-150	2442	551	1891	0.74
to Ex.Glenroy Gilbert	1657	417	1240	0.72
to Ex. Longfields	1736	660	1076	0.63
		North Block		
102-103	376	170	206	0.58
100-101	1342	304	1038	0.74
103-106	266	137	129	0.54
104-105	2459	460	1999	0.77
107-108	1658	372	1286	0.74
106-109	276	142	134	0.54



Report

Nepean South Chapman Mills Stormwater Management Servicing Fourth Addendum



NEPEAN SOUTH CHAPMAN MILLS STORMWATER MANAGEMENT SERVICING FOURTH ADDENDUM

Prepared for Minto Communities - Canada

Table 2.9 Revised drainage areas

		2006					UPDATE	D	
DRAINAGE AREA ID	AREA (HA)	TIMP (%)	SURFACE STORAGE (CU-M)	MINOR SYSTEM CAPTURE (L/S)	DRAINAGE AREA ID	AREA (HA)	TIMP (%)	SURFACE STORAGE (CU-M)	MINOR SYSTEM CAPTURE (L/S)
F2	14.4	85	3012(1)	1575	DME- 9063A (DME3)	1.82	66	252	435 ⁽²⁾
					Block A	5.21	74 ⁽³⁾	750	784(4)(5)(6)
					R-9066	0.54	71	0	211
					Riocan Avenue	0.33	99	0	28 ⁽⁷⁾
F3	9.4	85	2057(1)	956	CMD1B	1.50	90(3)	0	752(4)(7)
					CMD2	0.71	90(3)	0	457(4)(5)
					Block B	2.89	93(3)	0	1331 ⁽⁴⁾
					Block H Civic	1.96	93(3)	0	900(4)
					CMD1A	0.86	90(3)	0	383(4)
					Е	3.11 ⁽⁹⁾	86	0	280(10)
					F	4.72(9)	86	0	425(10)
					С	3.40	74(13)	0	306(10)
					C_ROAD	0.25	99	0	122(4)
					D	4.33	74 ⁽¹³⁾	0	389(10)
					D_ROAD	0.13	99	0	66(4)
F4	31.6	85	5814 ⁽¹⁾	3750	Parcel A	5.17	74 ⁽¹³⁾	0	465(10)
					A_ROAD	0.13	99	0	65 ⁽⁴⁾
					105W	2.10	79 ⁽³⁾	0	189(10)
					105WA ⁽¹⁶⁾	0.70	71 (15)	0	63(10)
					105S	0.85	71(3)	0	77 ⁽¹⁰⁾
					103	1.30	71(3)	0	117 ⁽¹⁰⁾
					101	2.48	76 ⁽³⁾	0	223(10)
F6	7.37	37	863(1)	627	F6 ⁽¹⁴⁾	7.84	39	680	831(4)
H1	3.2	80	392	530	H1	3.67	74	1056	556
G1	10.40	78	0	1544	G1	10.06	78	0	1869(8)
G2	1.08	85	0	268	G2 ⁽¹¹⁾	1.06	85	0	268(12)
G3	1.88	87	0	478	G3 ⁽¹¹⁾	1.88	87	0	478(12)

- (1) 100 year on-site storage
- (2) Based on rational method for Ampersand Stage I
- (3) Weighted c value (from which imperviousness was calculated) established by engineering consultant completing conceptual design
- (4) 100 year flow capture (based on 100 year 3 hour Chicago storm)
- (5) 100 year flow from a 0.358 ha portion of Block A flow cascades to Chapman Mills Drive (CMD2)
- (6) Minor flow from a 0.915 ha portion of Block A drains via the storm sewer on Glenroy Gilbert Drive (via Ampersand Stage I); minor flow from a 3.936 ha portion and 100 year flow from a 0.358 ha portion drains via the storm sewer on Chapman Mills Drive
- (7) Major flow from Riocan Avenue cascades to Chapman Mills Drive (CMD1B) (8) Minor system capture per Stantec/AECOM July 2009
- (9) Drainage area extended west to Greenbank Road
- (10) Minor system capture increased to 90 l/s/ha from 85 l/s/ha
- (11) Water quality treatment for areas G2, G3 to be provided by an independent BMP
- (12) Minor system capture per TSH May 2006
- (13) Imperviousness consistent with that of Block A
- (14) Per detailed design of site
- (15) Per email from DSEL November 6, 2017
- (16) Major flow conveyed toward Greenbank Road


ΙВΙ

Scale

Project Title

Drawing Title

Sheet No.



Minto BTC Stage 1 - Block A Glenroy Gilbert Extension **Proposed Conditions**

Stormwater - Proposed Development City of Ottawa Sewer Design Guidelines, 2012



Target Flow Rate

Q 147.00 L/s

Estimated Post Development Peak Flow from Unattenuated Areas

0.04 0.08 Area 0.58

0.12 ha <-- Sum of Drainage to CB 9, CB 10 Total Area

0.62 Rational Method runoff coefficient

	5-year					100-year				
t _c	i	Q _{actual}	Q _{release}	Q _{stored}	V _{stored}	i	Q _{actual} *	Q _{release}	Q _{stored}	V_{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)
13.1	90.4	18.5	18.5	0.0	0.0	154.8	31.7	31.7	0.0	0.0

Note: Tc = 13.05 min per Design Sheet

--> 5-year flow conveyed within Glenroy Gilbert Drive Extension storm sewer sytem.

--> Flows exceeding the 5-year storm directed overland towards Riocan Avenue Extension.

Area 0.03 0.07 С 0.54 0.64

Total Area 0.10 ha <-- Drainage to CB 13 0.61 Rational Method runoff coefficient

	5-year					100-year				
t _c	i	Q _{actual}	Q _{release}	Q _{stored}	V_{stored}	i	Q _{actual}	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)
13.1	90.4	15.4	15.4	0.0	0.0	154.8	26.3	26.3	0.0	0.0

Note:

Tc = 13.05 min per Design Sheet

--> 5-year flow conveyed within Glenroy Gilbert Drive Extension storm sewer sytem.

--> Flows exceeding the 5-year storm directed to DCB 15.

Area 0.08 0.08 0.77 0.64

Total Area

<-- Drainage to CB 12, CB 14 0.70 Rational Method runoff coefficient

> 5-year 100-year tc Q_{actual} Q_{release} Q_{stored} $V_{\rm stored}$ Q_{actual} Q_{release} Q_{stored} V_{stored} (mm/hr) (L/s) (L/s) (L/s) (m³) (mm/hr) (L/s) (L/s) (L/s) (m³) (min)

Note:

Tc = 13.05 min per Design Sheet

--> 5-year flow conveyed within Glenroy Gilbert Drive Extension storm sewer sytem.
--> Flows exceeding the 5-year storm directed to DCB 16.

Estimated Post Development Peak Flow from Attenuated Areas

Area ID DCB 15 Available Sub-surface Storage

Total Subsurface Storage (m³)

Stage Attenuated Areas Storage Summary

		Sı	ırface Stora	ge	Surfa	ce and Sub	surface Sto	rage
	Stage	Ponding	h _o	delta d	V*	V _{acc} **	Q _{release} †	V _{drawdown}
	(m)	(m²)	(m)	(m)	(m ³)	(m³)	(L/s)	(hr)
Orifice INV	97.96		0.00			0.0	0.0	0.00
T/G	99.34	0.7	1.38	1.38	0.0	0.0	22.0	0.00
	99.49	56.0	1.53	0.15	3.2	3.2	23.2	0.04
Max Ponding	99.64	261.6	1.68	0.15	21.9	25.1	24.3	0.29

Orifice Location DCB 15 Area 0.03 0.09 0.54 0.64

> 0.13 ha **Total Area**

0.62 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V_{stored}	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)
13	90.4	20.1	20.1	0.0	0.0	154.8	54.0	24.2	29.8	23.3
15	83.6	18.6	18.6	0.0	0.0	142.9	50.7	24.2	26.4	23.8
20	70.3	15.6	15.6	0.0	0.0	120.0	44.3	24.2	20.1	24.1
25	60.9	13.6	13.6	0.0	0.0	103.8	39.8	24.2	15.6	23.4
30	53.9	12.0	12.0	0.0	0.0	91.9	36.5	24.2	12.3	22.1
35	48.5	10.8	10.8	0.0	0.0	82.6	33.9	24.2	9.7	20.3
40	44.2	9.8	9.8	0.0	0.0	75.1	31.8	24.2	7.6	18.2
45	40.6	9.0	9.0	0.0	0.0	69.1	30.2	24.2	5.9	15.9
50	37.7	8.4	8.4	0.0	0.0	64.0	28.7	24.2	4.5	13.4
55	35.1	7.8	7.8	0.0	0.0	59.6	27.5	24.2	3.3	10.8
60	32.9	7.3	7.3	0.0	0.0	55.9	26.5	24.2	2.2	8.1
65	31.0	6.9	6.9	0.0	0.0	52.6	25.6	24.2	1.3	5.2
70	29.4	6.5	6.5	0.0	0.0	49.8	24.8	24.2	0.5	2.3
75	27.9	6.2	6.2	0.0	0.0	47.3	24.1	24.1	0.0	0.0
80	26.6	5.9	5.9	0.0	0.0	45.0	23.5	23.5	0.0	0.0
85	25.4	5.6	5.6	0.0	0.0	43.0	22.9	22.9	0.0	0.0
90	24.3	5.4	5.4	0.0	0.0	41.1	22.4	22.4	0.0	0.0
95	23.3	5.2	5.2	0.0	0.0	39.4	21.9	21.9	0.0	0.0
100	22.4	5.0	5.0	0.0	0.0	37.9	21.5	21.5	0.0	0.0
105	21.6	4.8	4.8	0.0	0.0	36.5	21.1	21.1	0.0	0.0
110	20.8	4.6	4.6	0.0	0.0	35.2	20.7	20.7	0.0	0.0

20.1 L/s 24.3 L/s 5-year Qattenuated 100-year Qattenuated 5-year Max. Storage Required Est. 5-year Storage Elevation 100-year Max. Storage Required Est. 100-year Storage Elevation 0.0 m³ 24.1 m³ 97.96 m 99.63 m

^{*} V=Incremental storage volume **V_{acc}=Total surface and sub-surface

 $[\]dagger$ Q_{release} = Release rate calculated from orifice equation

Area ID DCB 16 Available Sub-surface Storage

Total Subsurface Storage (m³)

Stage Attenuated Areas Storage Summary

		Sı	ırface Stora	ge	Surfa	ce and Sub	surface Sto	rage
	Stage	Ponding	h _o	delta d	٧*	V _{acc} **	Q _{release} †	$V_{drawdown}$
	(m)	(m²)	(m)	(m)	(m ³)	(m ³)	(L/s)	(hr)
Orifice INV	97.96		0.00			0.0	0.0	0.00
T/G	99.34	0.7	1.38	1.38	0.0	0.0	29.1	0.00
	99.49	47.9	1.53	0.15	2.7	2.7	30.6	0.02
Max Ponding	99.64	219.2	1.68	0.15	18.5	21.2	32.1	0.18

^{*} V=Incremental storage volume

Orifice Location DCB 16 Dia 108 Area 0.01 0.09 0.77 0.64

> Total Area C 0.10 ha

0.65 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c (min)	i (mm/hr)	Q _{actual} ‡ (L/s)	Q _{release} (L/s)	Q _{stored} (L/s)	V _{stored} (m ³)	i (mm/hr)	Q _{actual} ‡ (L/s)	Q _{release} (L/s)	Q _{stored} (L/s)	V _{stored} (m ³)
13	89.9	16.0	16.0	0.0	0.0	153.9	54.2	31.8	22.4	17.7
15	83.6	14.9	14.9	0.0	0.0	142.9	51.8	31.8	19.9	18.0
20	70.3	12.5	12.5	0.0	0.0	120.0	46.7	31.8	14.8	17.8
25	60.9	10.8	10.8	0.0	0.0	103.8	43.1	31.8	11.3	16.9
30	53.9	9.6	9.6	0.0	0.0	91.9	40.4	31.8	8.6	15.5
35	48.5	8.6	8.6	0.0	0.0	82.6	38.3	38.3	0.0	0.0
40	44.2	7.9	7.9	0.0	0.0	75.1	36.7	36.7	0.0	0.0
45	40.6	7.2	7.2	0.0	0.0	69.1	35.3	35.3	0.0	0.0
50	37.7	6.7	6.7	0.0	0.0	64.0	34.2	34.2	0.0	0.0
55	35.1	6.3	6.3	0.0	0.0	59.6	33.2	33.2	0.0	0.0
60	32.9	5.9	5.9	0.0	0.0	55.9	32.4	32.4	0.0	0.0
65	31.0	5.5	5.5	0.0	0.0	52.6	31.7	31.7	0.0	0.0
70	29.4	5.2	5.2	0.0	0.0	49.8	31.0	31.0	0.0	0.0
75	27.9	5.0	5.0	0.0	0.0	47.3	30.5	30.5	0.0	0.0
80	26.6	4.7	4.7	0.0	0.0	45.0	30.0	30.0	0.0	0.0
85	25.4	4.5	4.5	0.0	0.0	43.0	29.5	29.5	0.0	0.0
90	24.3	4.3	4.3	0.0	0.0	41.1	29.1	29.1	0.0	0.0
95	23.3	4.2	4.2	0.0	0.0	39.4	28.7	28.7	0.0	0.0
100	22.4	4.0	4.0	0.0	0.0	37.9	28.4	28.4	0.0	0.0
105	21.6	3.8	3.8	0.0	0.0	36.5	28.1	28.1	0.0	0.0
110	20.8	3.7	3.7	0.0	0.0	35.2	27.8	27.8	0.0	0.0

5-year Qattenuated 16.0 L/s 31.8 L/s 100-year Qattenuated 5-year Max. Storage Required Est. 5-year Storage Elevation 0.0 m³ 97.96 m 100-year Max. Storage Required Est. 100-year Storage Elevation 18.0 m³ 99.61 m

^{**}V_{acc}=Total surface and sub-surface

[†] Q_{release} = Release rate calculated from orifice equation

BTC Stage 1 - Block A Glenroy Gilbert Extension Proposed Conditions

Area ID STM108 Available Sub-surface Storage

Total Subsurface Storage (m³)

40.3 <-- Provided storage excludes storage volume below system invert

Stage Attenuated Areas Storage Summary

		Sı	ırface Stora	ge	Surfa	ice and Sub	surface Sto	rage
	Stage	Ponding	h _o	delta d	V*	V _{acc} **	Q _{release} +	$V_{drawdown}$
	(m)	(m²)	(m)	(m)	(m ³)	(m ³)	(L/s)	(hr)
Orifice INV	96.49		0.00			0.0	0.0	0.00
Storage Chamber INV	97.54		1.05	1.05	0.0	0.0	5.8	0.00
Storage Chamber OBV	98.30		1.81	0.76	40.3	40.3	7.6	1.47
T/G	99.39	0.4	2.90	1.09	0.0	40.3	9.7	1.15
Max Ponding	99.69	189.7	3.20	0.30	19.8	60.1	10.0	1.67

^{*} V=Incremental storage volume

Orifice Location

STM108

ICD Tempest LMF 80

Total Area 0.17 ha

0.74 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)
13	90.4	31.6	6.8	24.8	19.4	154.8	67.6	7.9	59.7	46.7
15	83.6	29.2	6.8	22.4	20.2	142.9	62.4	7.9	54.5	49.1
20	70.3	24.5	6.8	17.8	21.3	120.0	52.4	7.9	44.5	53.4
25	60.9	21.3	6.8	14.5	21.8	103.8	45.4	7.9	37.5	56.2
30	53.9	18.8	6.8	12.1	21.7	91.9	40.1	7.9	32.2	58.0
35	48.5	17.0	6.8	10.2	21.4	82.6	36.1	7.9	28.2	59.2
40	44.2	15.4	6.8	8.7	20.8	75.1	32.8	7.9	24.9	59.8
45	40.6	14.2	6.8	7.4	20.0	69.1	30.2	7.9	22.3	60.1
50	37.7	13.2	6.8	6.4	19.2	64.0	27.9	7.9	20.0	60.1
55	35.1	12.3	6.8	5.5	18.2	59.6	26.0	7.9	18.1	59.9
60	32.9	11.5	6.8	4.7	17.1	55.9	24.4	7.9	16.5	59.5
65	31.0	10.8	6.8	4.1	15.9	52.6	23.0	7.9	15.1	58.9
70	29.4	10.3	6.8	3.5	14.7	49.8	21.7	7.9	13.8	58.2
75	27.9	9.7	6.8	3.0	13.4	47.3	20.6	7.9	12.7	57.3
80	26.6	9.3	6.8	2.5	12.0	45.0	19.7	7.9	11.8	56.4
85	25.4	8.9	6.8	2.1	10.7	43.0	18.8	7.9	10.9	55.4
90	24.3	8.5	6.8	1.7	9.3	41.1	18.0	7.9	10.1	54.3
95	23.3	8.1	6.8	1.4	7.8	39.4	17.2	7.9	9.3	53.2
100	22.4	7.8	6.8	1.1	6.3	37.9	16.6	7.9	8.7	51.9
105	21.6	7.5	6.8	0.8	4.9	36.5	15.9	7.9	8.0	50.7
110	20.8	7.3	6.8	0.5	3.3	35.2	15.4	7.9	7.5	49.3

5-year Qattenuated 5-year Max. Storage Required 6.8 L/s

100-year Q_{attenuated} 100-year Max. Storage Required Est. 100-year Storage Elevation 10.0 L/s

60.1 m³

99.69 m

Est. 5-year Storage Elevation

21.8 m³ 97.95 m

Notes:

Required storage volumes calculated using the average Q release rate between storage tank invert and max ponding elevation
 Flow from the storage tank assumes maximum Q Release at max ponding elevation

^{**}V_{acc}=Total surface and sub-surface

[†] Q_{release} = Release rate per Tempest LMF Flow Curve

BTC Stage 1 - Block A Glenroy Gilbert Extension Proposed Conditions

STM105 Area ID Available Sub-surface Storage

> Total Subsurface Storage (m³) 67.4 <-- Provided storage excludes storage volume below system invert

Stage Attenuated Areas Storage Summary

_		Sı	ırface Stora	ge	Surfa	ice and Sub	surface Sto	rage
	Stage	Ponding	h _o	delta d	V*	V _{acc} **	Q _{release} †	$V_{drawdown}$
	(m)	(m²)	(m)	(m)	(m³)	(m³)	(L/s)	(hr)
Orifice INV	97.00		0.00			0.0	0.0	0.00
Storage Chamber INV	97.83		0.83	0.83		0.0	4.0	0.00
Storage Chamber OBV	98.59		1.59	0.76	67.4	67.4	5.5	3.40
T/G	99.69	0.4	2.69	1.10	0.0	67.4	7.2	2.60
Max Ponding	99.99	491.1	2.99	0.30	50.5	117.9	7.6	4.31

^{*} V=Incremental storage volume

Orifice Location

STM105 ICD Tempest LMF 70

Total Area 0.25 ha

0.77 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)
13	90.4	48.4	5.0	43.3	33.9	154.8	103.5	5.8	97.7	76.5
15	83.6	44.7	5.0	39.7	35.7	142.9	95.5	5.8	89.7	80.7
20	70.3	37.6	5.0	32.6	39.1	120.0	80.2	5.8	74.4	89.3
25	60.9	32.6	5.0	27.6	41.3	103.8	69.4	5.8	63.6	95.4
30	53.9	28.8	5.0	23.8	42.9	91.9	61.4	5.8	55.6	100.1
35	48.5	25.9	5.0	20.9	44.0	82.6	55.2	5.8	49.4	103.7
40	44.2	23.6	5.0	18.6	44.7	75.1	50.2	5.8	44.4	106.6
45	40.6	21.7	5.0	16.7	45.1	69.1	46.2	5.8	40.4	109.0
50	37.7	20.1	5.0	15.1	45.4	64.0	42.7	5.8	36.9	110.8
55	35.1	18.8	5.0	13.8	45.4	59.6	39.9	5.8	34.1	112.4
60	32.9	17.6	5.0	12.6	45.4	55.9	37.4	5.8	31.6	113.6
65	31.0	16.6	5.0	11.6	45.2	52.6	35.2	5.8	29.4	114.6
70	29.4	15.7	5.0	10.7	44.9	49.8	33.3	5.8	27.5	115.4
75	27.9	14.9	5.0	9.9	44.6	47.3	31.6	5.8	25.8	116.0
80	26.6	14.2	5.0	9.2	44.1	45.0	30.1	5.8	24.3	116.5
85	25.4	13.6	5.0	8.6	43.6	43.0	28.7	5.8	22.9	116.8
90	24.3	13.0	5.0	8.0	43.1	41.1	27.5	5.8	21.7	117.1
95	23.3	12.5	5.0	7.5	42.5	39.4	26.4	5.8	20.6	117.2
100	22.4	12.0	5.0	7.0	41.8	37.9	25.3	5.8	19.5	117.2
105	21.6	11.5	5.0	6.5	41.1	36.5	24.4	5.8	18.6	117.1
110	20.8	11.1	5.0	6.1	40.4	35.2	23.5	5.8	17.7	117.0

5-year Qattenuated 5-year Max. Storage Required Est. 5-year Storage Elevation

5.0 L/s 45.4 m³ 98.34 m

100-year Q_{attenuated}

7.6 L/s 100-year Max. Storage Required 117.2 m³ Est. 100-year Storage Elevation 99.99 m

^{**}V_{acc}=Total surface and sub-surface

[†] Q_{release} = Release rate per Tempest LMF Flow Curve

Required storage volumes calculated using the average Q release rate between storage tank invert and max ponding elevation
 Flow from the storage tank assumes maximum Q Release at max ponding elevation

Area ID STM101 Available Sub-surface Storage

Total Subsurface Storage (m³)

35.0 <-- Provided storage excludes storage volume below system invert

Stage Attenuated Areas Storage Summary

_		Sı	ırface Stora	ge	Surface and Subsurface Storage				
	Stage	Ponding	h _o	delta d	V*	V _{acc} **	Q _{release} †	$V_{drawdown}$	
	(m)	(m²)	(m)	(m)	(m³)	(m³)	(L/s)	(hr)	
Orifice INV	97.59		0.00			0.0	0.0	0.00	
Storage Chamber INV	98.39		0.80	0.80		0.0	5.8	0.00	
Storage Chamber OBV	99.15		1.56	0.76	35.0	35.0	7.9	1.23	
T/G	100.25	0.4	2.66	1.10	0.0	35.0	10.3	0.94	
Max Ponding	100.41	98.8	2.82	0.16	5.6	40.6	10.7	1.05	

^{*} V=Incremental storage volume

Orifice Location

STM101

Dia Tempest LMF 95

Total Area 0.13 ha

0.74 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)
13	90.4	24.2	6.7	17.5	13.7	154.8	51.7	8.3	43.4	34.0
15	83.6	22.3	6.7	15.7	14.1	142.9	47.7	8.3	39.5	35.5
20	70.3	18.8	6.7	12.1	14.5	120.0	40.1	8.3	31.8	38.2
25	60.9	16.3	6.7	9.6	14.4	103.8	34.7	8.3	26.4	39.7
30	53.9	14.4	6.7	7.7	13.9	91.9	30.7	8.3	22.4	40.4
35	48.5	13.0	6.7	6.3	13.2	82.6	27.6	8.3	19.3	40.6
40	44.2	11.8	6.7	5.1	12.3	75.1	25.1	8.3	16.9	40.4
45	40.6	10.9	6.7	4.2	11.3	69.1	23.1	8.3	14.8	40.0
50	37.7	10.1	6.7	3.4	10.2	64.0	21.4	8.3	13.1	39.3
55	35.1	9.4	6.7	2.7	9.0	59.6	19.9	8.3	11.7	38.5
60	32.9	8.8	6.7	2.1	7.7	55.9	18.7	8.3	10.4	37.5
65	31.0	8.3	6.7	1.6	6.3	52.6	17.6	8.3	9.3	36.4
70	29.4	7.8	6.7	1.2	4.9	49.8	16.6	8.3	8.4	35.2
75	27.9	7.5	6.7	0.8	3.5	47.3	15.8	8.3	7.5	33.9
80	26.6	7.1	6.7	0.4	2.0	45.0	15.0	8.3	6.8	32.5
85	25.4	6.8	6.7	0.1	0.5	43.0	14.3	8.3	6.1	31.1
90	24.3	6.5	6.5	0.0	0.0	41.1	13.7	8.3	5.5	29.6
95	23.3	6.2	6.2	0.0	0.0	39.4	13.2	8.3	4.9	28.1
100	22.4	6.0	6.0	0.0	0.0	37.9	12.7	8.3	4.4	26.5
105	21.6	5.8	5.8	0.0	0.0	36.5	12.2	8.3	3.9	24.8
110	20.8	5.6	5.6	0.0	0.0	35.2	11.8	8.3	3.5	23.2

5-year Qattenuated 5-year Max. Storage Required Est. 5-year Storage Elevation

6.7 L/s 14.5 m³ 98.71 m

100-year Q_{attenuated} 100-year Max. Storage Required

Est. 100-year Storage Elevation

10.7 L/s 40.6 m³ 100.41 m

Notes:

- Required storage volumes calculated using the average Q release rate between storage tank invert and max ponding elevation
- Flow from the storage tank assumes maximum Q Release at max ponding elevation

Summary of Release Rates and Storage Volumes

Control Area	5-year Release Rate (L/s)	5-year Required Storage (m³)	100-Year Release Rate (L/s)	100-Year Required Storage (m³)	100-Year Available Storage (m³)
Unattenuated Areas (CB9 - CB14)	61.9	0.0	61.9	0.0	0.0
DCB 15	20.1	0.0	24.3	24.1	25.1
DCB 16	16.0	0.0	31.8	18.0	21.2
STM108	6.8	21.8	10.0	60.1	60.1
STM105	5.0	45.4	7.6	117.2	117.9
STM101	6.7	14.5	10.7	40.6	40.6
Total	116.5	81.7	146.3	259.9	264.9

^{**}V_{acc}=Total surface and sub-surface

[†] Q_{release} = Release rate per Tempest LMF Flow Curve

Stormwater - Proposed Development City of Ottawa Sewer Design Guidelines, 2012



Target Flow Rate

637.00 L/s Q

Estimated Post Development Peak Flow from Unattenuated Areas

0.17 ha <-- Sum of Unattenuated Drainage to Glenroy Gilbert Drive 0.72 Rational Method runoff coefficient Area

	5-year					100-year				
t _c	i	i Q _{actual} Q _{release} Q _{stored} V _{stored}					Q _{actual} *	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)
13.9	87.4	29.7	29.7	0.0	0.0	149.5	50.8	50.8	0.0	0.0

Note: Tc = 13.88 min per Design Sheet

0.16 ha <-- Sum of Unattenuated Drainage to Riocan Avenue Area C

0.66 Rational Method runoff coefficient

		5-year					100-year					
	t _c (min)	i (mm/hr)	Q _{actual} (L/s)	Q _{release} (L/s)	Q _{stored} (L/s)	V _{stored} (m ³)	i (mm/hr)	Q _{actual} * (L/s)	Q _{release} (L/s)	Q _{stored} (L/s)	V _{stored} (m ³)	
ı	13.9	87.4	25.6	25.6	0.0	0.0		43.8	43.8	0.0	0.0	

Note: Tc = 13.88 min per Design Sheet

0.01 0.16 0.17 Area C 0.01 0.57 0.83 0.74 0.53

0.35 ha <-- Sum of Unattenuated Drainage to Chapman Mills Drive 0.77 Rational Method runoff coefficient Total Area

	5-year					100-year						
t _c	i	Q _{actual}	Q _{release}	Q _{stored}	V _{stored}	i	Q _{actual}	Q _{release}	Q _{stored}	V_{stored}		
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)		
13.9	87.4	65.4	65.4	0.0	0.0	149.5	111.9	111.9	0.0	0.0		

Tc = 13.88 min per Design Sheet

<-- Sum of Unattenuated Drainage to Longfields Drive

0.63 Rational Method runoff coefficient

		5-year					100-year					
	tc	i	Q _{actual}	Q _{release}	Q _{stored}	V_{stored}	i	Q _{actual}	Q _{release}	Q _{stored}	V_{stored}	
	(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)	
ſ	13.9	87.4	26.0	26.0	0.0	0.0	149.5	44.5	44.5	0.0	0.0	

Note:

Tc = 13.88 min per Design Sheet

Estimated Post Development Peak Flow from Attenuated Areas

STM115 Area ID Available Sub-surface Storage

Sewers

ID	450mm	525mm	1500mm	U/G Tank
Storage Pipe Dia (mm)	450	525	1500	
L (m)	60	43.5	47	
V _{sewer} (m ³)	9.5	9.4	83.1	27.9

*Top of lid or max ponding elevation : 98.87

Total Subsurface Storage (m³)

129.9 <-- Provided storage excludes storage volume below system invert

Stage Attenuated Areas Storage Summary

_		Sı	rface Stora	ge	Surface and Subsurface Storage			
	Stage	Ponding	h _o	delta d	٧*	V _{acc} **	Q _{release} †	$V_{drawdown}$
	(m)	(m²)	(m)	(m)	(m³)	(m³)	(L/s)	(hr)
Orifice INV	95.11		0.00			0.0	0.0	0.00
Storage Pipe INV	96.17		1.06	1.06	0.0	0.0	36.9	0.00
Storage Pipe OBV	98.62		3.51	2.45	129.9	129.9	67.2	0.54
T/G	98.67	0.4	3.56	0.05	0.0	129.9	67.7	0.53
Max Ponding	98.87	72.3	3.76	0.20	5.2	135.1	69.5	0.54

[†] Q_{release} = Release rate calculated from orifice equation

Orifice Location	STM115	Dia	130
Area	0.08	0.36	0.11
C	0.81	0.68	0.79

Total Area C 0.55 ha

0.72 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)
14	87.4	96.2	46.6	49.7	41.4	149.5	205.8	53.2	152.5	127.0
20	70.3	77.4	46.6	30.8	37.0	120.0	165.1	53.2	111.9	134.3
25	60.9	67.1	46.6	20.5	30.8	103.8	143.0	53.2	89.7	134.6
30	53.9	59.4	46.6	12.8	23.1	91.9	126.5	53.2	73.2	131.8
35	48.5	53.4	46.6	6.9	14.5	82.6	113.7	53.2	60.5	127.0
40	44.2	48.7	46.6	2.1	5.1	75.1	103.5	53.2	50.2	120.5
45	40.6	44.7	44.7	0.0	0.0	69.1	95.1	53.2	41.8	112.9
50	37.7	41.5	41.5	0.0	0.0	64.0	88.0	53.2	34.8	104.4
55	35.1	38.7	38.7	0.0	0.0	59.6	82.1	53.2	28.9	95.2
60	32.9	36.3	36.3	0.0	0.0	55.9	77.0	53.2	23.7	85.4
65	31.0	34.2	34.2	0.0	0.0	52.6	72.5	53.2	19.2	75.1
70	29.4	32.3	32.3	0.0	0.0	49.8	68.5	53.2	15.3	64.3
75	27.9	30.7	30.7	0.0	0.0	47.3	65.1	53.2	11.8	53.2
80	26.6	29.3	29.3	0.0	0.0	45.0	61.9	53.2	8.7	41.8
85	25.4	27.9	27.9	0.0	0.0	43.0	59.1	53.2	5.9	30.1
90	24.3	26.8	26.8	0.0	0.0	41.1	56.6	53.2	3.4	18.2
95	23.3	25.7	25.7	0.0	0.0	39.4	54.3	53.2	1.1	6.0
100	22.4	24.7	24.7	0.0	0.0	37.9	52.2	53.2	0.0	0.0
105	21.6	23.8	23.8	0.0	0.0	36.5	50.2	53.2	0.0	0.0
110	20.8	22.9	22.9	0.0	0.0	35.2	48.5	53.2	0.0	0.0
115	20.1	22.2	22.2	0.0	0.0	34.0	46.8	53.2	0.0	0.0

100-year Q_{attenuated} 46.6 L/s 69.5 L/s 5-year Qattenuated 5-year Max. Storage Required Est. 5-year Storage Elevation 41.4 m³ 96.95 m 100-year Max. Storage Required Est. 100-year Storage Elevation 134.6 m³ 98.85 m

- Required storage volumes calculated using the average Q release rate between storage pipe invert to max ponding elevation.
- Flow from the control area assumes Q Release at maximum ponding elevation.

2023-06-29

^{*} V=Incremental storage volume

**V_{acc}=Total surface and sub-surface

Estimated Post Development Peak Flow from Attenuated Areas

STM126 Area ID Available Sub-surface Storage

Total Subsurface Storage (m³)

105.5 <-- Provided storage excludes storage volume below system invert

Stage Attenuated Areas Storage Summary _

		Sı	ırface Stora	ge	Surface and Subsurface Storage			
	Stage	Ponding	h _o	delta d	V*	V _{acc} **	Q _{release} †	V _{drawdown}
	(m)	(m²)	(m)	(m)	(m³)	(m³)	(L/s)	(hr)
Orifice INV	94.76		0.00			0.0	0.0	0.00
Storage Chamber INV	94.84		0.07	0.07	0.0	0.0	4.7	0.00
Storage Chamber OBV	96.36		1.60	1.53	105.5	105.5	21.7	1.35

Orifice Location Total Area C STM126

0.34 ha

0.64 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V_{stored}	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)
14	87.4	52.0	10.9	41.1	34.3	149.5	111.3	13.2	98.0	81.6
20	70.3	41.8	10.9	31.0	37.2	120.0	89.3	13.2	76.1	91.3
25	60.9	36.3	10.9	25.4	38.1	103.8	77.3	13.2	64.1	96.1
30	53.9	32.1	10.9	21.2	38.2	91.9	68.4	13.2	55.2	99.3
35	48.5	28.9	10.9	18.0	37.8	82.6	61.5	13.2	48.3	101.3
40	44.2	26.3	10.9	15.4	37.0	75.1	55.9	13.2	42.7	102.5
45	40.6	24.2	10.9	13.3	36.0	69.1	51.4	13.2	38.2	103.1
50	37.7	22.4	10.9	11.5	34.6	64.0	47.6	13.2	34.4	103.2
55	35.1	20.9	10.9	10.0	33.1	59.6	44.4	13.2	31.2	102.8
60	32.9	19.6	10.9	8.7	31.5	55.9	41.6	13.2	28.4	102.2
65	31.0	18.5	10.9	7.6	29.7	52.6	39.2	13.2	26.0	101.3
70	29.4	17.5	10.9	6.6	27.8	49.8	37.1	13.2	23.8	100.1
75	27.9	16.6	10.9	5.7	25.8	47.3	35.2	13.2	22.0	98.8
80	26.6	15.8	10.9	4.9	23.7	45.0	33.5	13.2	20.3	97.3
85	25.4	15.1	10.9	4.2	21.6	43.0	32.0	13.2	18.8	95.6
90	24.3	14.5	10.9	3.6	19.4	41.1	30.6	13.2	17.4	93.9
95	23.3	13.9	10.9	3.0	17.1	39.4	29.4	13.2	16.1	92.0
100	22.4	13.3	10.9	2.5	14.8	37.9	28.2	13.2	15.0	89.9
105	21.6	12.9	10.9	2.0	12.4	36.5	27.2	13.2	13.9	87.9
110	20.8	12.4	10.9	1.5	10.0	35.2	26.2	13.2	13.0	85.7
115	20.1	12.0	10.9	1.1	7.6	34.0	25.3	13.2	12.1	83.4

5-year Qattenuated 5-year Max. Storage Required Est. 5-year Storage Elevation 10.9 L/s

38.2 m³

100-year Qattenuated 100-year Max. Storage Required Est. 100-year Storage Elevation

21.7 L/s 103.2 m³ 96.33 m

^{*} V=Incremental storage volume **V_{acc}=Total surface and sub-surface

 $[\]dagger$ Q_{release} = Release rate calculated from orifice equation

⁻ Required storage volumes calculated using the average Q release rate within the tank - Flow from the storage tank assumes maximum Q Release at the tank obvert

STM124 Area ID

Available Sub-surface Storage 79.92 195.22

> Total Subsurface Storage (m³) 275.1 <-- Provided storage excludes storage volume below system invert

Stage Attenuated Areas Storage Summary

		Sı	ırface Stora	ge	Surface and Subsurface Storage			
	Stage	Ponding	h _o	delta d	٧*	V _{acc} **	Q _{release} †	$V_{drawdown}$
	(m)	(m²)	(m)	(m)	(m ³)	(m ³)	(L/s)	(hr)
Orifice INV	94.90		0.00			0.0	0.0	0.00
Storage Chamber INV	96.19		1.28	1.28	0.0	0.0	6.5	0.00
Storage Chamber OBV	97.71		2.81	1.53	275.1	275.1	9.5	8.05

0.07

0.69

0.73

Orifice Location STM124 ICD Tempest LMF 80 Area 0.18 0.20 0.78

> Total Area C 0.53 ha

0.81

0.75 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)
14	87.4	96.9	7.6	89.3	74.4	149.5	207.3	8.0	199.3	166.0
20	70.3	78.0	7.6	70.3	84.4	120.0	166.4	8.0	158.4	190.1
30	53.9	59.8	7.6	52.2	94.0	91.9	127.4	8.0	119.4	215.0
40	44.2	49.0	7.6	41.4	99.3	75.1	104.2	8.0	96.2	231.0
50	37.7	41.8	7.6	34.1	102.4	64.0	88.7	8.0	80.7	242.1
60	32.9	36.6	7.6	28.9	104.1	55.9	77.5	8.0	69.5	250.3
70	29.4	32.6	7.6	25.0	104.8	49.8	69.1	8.0	61.1	256.5
80	26.6	29.5	7.6	21.8	104.8	45.0	62.4	8.0	54.4	261.2
90	24.3	27.0	7.6	19.3	104.3	41.1	57.0	8.0	49.0	264.7
100	22.4	24.9	7.6	17.2	103.3	37.9	52.6	8.0	44.6	267.5
110	20.8	23.1	7.6	15.5	102.1	35.2	48.8	8.0	40.8	269.5
120	19.5	21.6	7.6	14.0	100.5	32.9	45.6	8.0	37.6	270.9
130	18.3	20.3	7.6	12.7	98.7	30.9	42.9	8.0	34.9	271.9
140	17.3	19.2	7.6	11.5	96.8	29.2	40.4	8.0	32.4	272.5
150	16.4	18.2	7.6	10.5	94.6	27.6	38.3	8.0	30.3	272.7
160	15.6	17.3	7.6	9.6	92.3	26.2	36.4	8.0	28.4	272.6
170	14.8	16.5	7.6	8.8	89.9	25.0	34.7	8.0	26.7	272.3
180	14.2	15.7	7.6	8.1	87.4	23.9	33.2	8.0	25.2	271.7
190	13.6	15.1	7.6	7.4	84.8	22.9	31.8	8.0	23.8	270.9
200	13.0	14.5	7.6	6.8	82.1	22.0	30.5	8.0	22.5	269.9
210	12.6	13.9	7.6	6.3	79.2	21.1	29.3	8.0	21.3	268.8

7.6 L/s 5-vear Qattenuated 5-year Max. Storage Required Est. 5-year Storage Elevation 104.8 m³ 96.77 m

100-year Q_{attenuated} 9.5 L/s 100-year Max. Storage Required Est. 100-year Storage Elevation 272.7 m³ 97.70 m

^{*} V=Incremental storage volume

^{**}V_{acc}=Total surface and sub-surface

[†] Q_{release} = Release rate per Tempest LMF Flow Curve

⁻ Required storage volumes calculated using the average Q release rate within the tank

⁻ Flow from the storage tank assumes maximum Q Release at the tank obvert

Area ID STM134 Available Sub-surface Storage

Total Subsurface Storage (m³)

79.7 <-- Provided storage excludes storage volume below system invert

Stage Attenuated Areas Storage Summary

		Sı	ırface Stora	ge	Surfa	ce and Sub	surface Stor	rage
	Stage	Ponding	h _o	delta d	V*	V _{acc} **	Q _{release} †	$V_{drawdown}$
	(m)	(m²)	(m)	(m)	(m³)	(m³)	(L/s)	(hr)
Orifice INV	93.41		0.00			0.0	0.0	0.00
Storage Chamber INV	94.17		0.75	0.75		0.0	81.3	0.00
Storage Chamber OBV	95.69		2.28	1.53	79.7	79.7	141.3	0.16

^{*} V=Incremental storage volume

[†] Q_{release} = Release rate calculated from orifice equation

Orifice Location	STM134	dia	210
Area	0.18	0.22	0.11
С	0.76	0.76	0.79

Total Area C

0.51 ha

0.77 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c (min)	i (mm/hr)	Q _{actual} ‡ (L/s)	Q _{release} (L/s)	Q _{stored} (L/s)	V _{stored} (m ³)	i (mm/hr)	Q _{actual} ‡ (L/s)	Q _{release} (L/s)	Q _{stored} (L/s)	V _{stored} (m ³)
14	87.4	94.9	86.5	8.3	6.9	149.5	202.9	111.3	91.5	76.2
20	70.3	76.3	76.3	0.0	0.0	120.0	162.8	111.3	51.5	61.8
25	60.9	66.1	66.1	0.0	0.0	103.8	141.0	111.3	29.6	44.5
30	53.9	58.6	58.6	0.0	0.0	91.9	124.7	111.3	13.4	24.1
35	48.5	52.7	52.7	0.0	0.0	82.6	112.1	111.3	0.8	1.6
40	44.2	48.0	48.0	0.0	0.0	75.1	102.0	102.0	0.0	0.0
45	40.6	44.1	44.1	0.0	0.0	69.1	93.7	93.7	0.0	0.0
50	37.7	40.9	40.9	0.0	0.0	64.0	86.8	86.8	0.0	0.0
55	35.1	38.1	38.1	0.0	0.0	59.6	80.9	80.9	0.0	0.0
60	32.9	35.8	35.8	0.0	0.0	55.9	75.9	75.9	0.0	0.0
65	31.0	33.7	33.7	0.0	0.0	52.6	71.5	71.5	0.0	0.0
70	29.4	31.9	31.9	0.0	0.0	49.8	67.6	67.6	0.0	0.0
75	27.9	30.3	30.3	0.0	0.0	47.3	64.1	64.1	0.0	0.0
80	26.6	28.8	28.8	0.0	0.0	45.0	61.1	61.1	0.0	0.0
85	25.4	27.5	27.5	0.0	0.0	43.0	58.3	58.3	0.0	0.0
90	24.3	26.4	26.4	0.0	0.0	41.1	55.8	55.8	0.0	0.0
95	23.3	25.3	25.3	0.0	0.0	39.4	53.5	53.5	0.0	0.0
100	22.4	24.3	24.3	0.0	0.0	37.9	51.4	51.4	0.0	0.0
105	21.6	23.4	23.4	0.0	0.0	36.5	49.5	49.5	0.0	0.0
110	20.8	22.6	22.6	0.0	0.0	35.2	47.8	47.8	0.0	0.0
115	20.1	21.8	21.8	0.0	0.0	34.0	46.2	46.2	0.0	0.0

5-year Qattenuated 86.5 L/s 5-year Max. Storage Required Est. 5-year Storage Elevation 6.9 m³ 94.30 m

141.3 L/s 100-year Qattenuated 100-year Max. Storage Required Est. 100-year Storage Elevation 76.2 m³ 95.62 m

^{**}V_{acc}=Total surface and sub-surface

⁻ Required storage volumes calculated using the average Q release rate within the tank

⁻ Flow from the storage tank assumes maximum Q Release at the tank obvert

STM164 Area ID Available Sub-surface Storage

Total Subsurface Storage (m³)

203.5 <-- Provided storage excludes storage volume below system invert

Stage Attenuated Areas Storage Summary

		Sı	ırface Stora	ge	Surface and Subsurface Storage			
	Stage	Ponding	h _o	delta d	V*	V _{acc} **	Q _{release} †	$V_{drawdown}$
	(m)	(m²)	(m)	(m)	(m³)	(m³)	(L/s)	(hr)
Orifice INV	92.98		0.00			0.0	0.0	0.00
Storage Chamber INV	93.14		0.16	0.16		0.0	3.5	0.00
Storage Chamber OBV	94.28		1.30	1.14	203.5	203.5	11.3	5.00

^{*} V=Incremental storage volume

Orifice Location

STM164 0.46 ha

ICD Tempest LMF 105

Total Area

0.67 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V_{stored}	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m ³)
14	87.4	74.8	6.5	68.3	56.9	149.5	159.9	7.4	152.5	127.0
20	70.3	60.1	6.5	53.6	64.4	120.0	128.4	7.4	121.0	145.2
25	60.9	52.1	6.5	45.6	68.4	103.8	111.1	7.4	103.7	155.6
30	53.9	46.2	6.5	39.7	71.4	91.9	98.3	7.4	90.9	163.6
35	48.5	41.5	6.5	35.0	73.6	82.6	88.4	7.4	81.0	170.0
40	44.2	37.8	6.5	31.3	75.2	75.1	80.4	7.4	73.0	175.2
45	40.6	34.8	6.5	28.3	76.4	69.1	73.9	7.4	66.5	179.5
50	37.7	32.2	6.5	25.7	77.2	64.0	68.4	7.4	61.0	183.1
55	35.1	30.1	6.5	23.6	77.8	59.6	63.8	7.4	56.4	186.1
60	32.9	28.2	6.5	21.7	78.1	55.9	59.8	7.4	52.4	188.7
65	31.0	26.6	6.5	20.1	78.3	52.6	56.3	7.4	48.9	190.9
70	29.4	25.1	6.5	18.6	78.3	49.8	53.3	7.4	45.9	192.7
75	27.9	23.9	6.5	17.4	78.2	47.3	50.6	7.4	43.2	194.3
80	26.6	22.7	6.5	16.2	77.9	45.0	48.1	7.4	40.7	195.6
85	25.4	21.7	6.5	15.2	77.6	43.0	46.0	7.4	38.6	196.7
90	24.3	20.8	6.5	14.3	77.2	41.1	44.0	7.4	36.6	197.6
95	23.3	20.0	6.5	13.5	76.7	39.4	42.2	7.4	34.8	198.4
100	22.4	19.2	6.5	12.7	76.1	37.9	40.6	7.4	33.2	199.0
105	21.6	18.5	6.5	12.0	75.4	36.5	39.1	7.4	31.7	199.4
110	20.8	17.8	6.5	11.3	74.7	35.2	37.7	7.4	30.3	199.8
115	20.1	17.2	6.5	10.7	74.0	34.0	36.4	7.4	29.0	200.0
120	19.5	16.7	6.5	10.2	73.2	32.9	35.2	7.4	27.8	200.2
125	18.9	16.1	6.5	9.6	72.3	31.9	34.1	7.4	26.7	200.2
130	18.3	15.7	6.5	9.2	71.5	30.9	33.1	7.4	25.7	200.2

5-year Qattenuated 5-year Max. Storage Required Est. 5-year Storage Elevation

6.5 L/s 78.3 m³ 93.58 m

100-year Qattenuated 100-year Max. Storage Required Est. 100-year Storage Elevation

11.3 L/s 200.0 m³ 94.26 m

Notes:

- Required storage volumes calculated using the average Q release rate within the tank Flow from the storage tank assumes maximum Q Release at the tank obvert

2023-06-29

^{**}V_{acc}=Total surface and sub-surface

[†] Q_{release} = Release rate per Tempest LMF Flow Curve

STM159 Area ID

Available Sub-surface Storage 48.75 161.53

> Total Subsurface Storage (m³) 210.3 <-- Provided storage excludes storage volume below system invert

Stage Attenuated Areas Storage Summary

		Surface Storage			Surface and Subsurface Storage			
	Stage	Ponding	h _o	delta d	V*	V _{acc} **	Q _{release} †	$V_{drawdown}$
	(m)	(m ²)	(m)	(m)	(m ³)	(m ³)	(L/s)	(hr)
Orifice INV	93.17		0.00			0.0	0.0	0.00
Storage Chamber INV	93.22		0.05	0.05		0.0	2.7	0.00
Storage Chamber OBV	94.36		1.19	1.14	210.3	210.3	13.0	4.49

^{*} V=Incremental storage volume

[†] Q_{release} = Release rate calculated from orifice equation

Orifice Location	STM159	Dia	75
Area	0.18	0.25	
C	0.79	0.71	

Total Area C 0.43 ha

0.74 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c (min)	i (mm/hr)	Q _{actual} ‡ (L/s)	Q _{release} (L/s)	Q _{stored} (L/s)	V _{stored} (m ³)	i (mm/hr)	Q _{actual} ‡ (L/s)	Q _{release} (L/s)	Q _{stored} (L/s)	V _{stored} (m ³)
14	87.4	77.6	6.7	70.9	59.0	149.5	165.9	7.8	158.1	131.6
20	70.3	62.4	6.7	55.7	66.8	120.0	133.2	7.8	125.3	150.4
30	53.9	47.9	6.7	41.2	74.2	91.9	102.0	7.8	94.1	169.4
40	44.2	39.2	6.7	32.6	78.1	75.1	83.4	7.8	75.6	181.4
50	37.7	33.4	6.7	26.8	80.3	64.0	71.0	7.8	63.1	189.4
60	32.9	29.3	6.7	22.6	81.3	55.9	62.0	7.8	54.2	195.1
70	29.4	26.1	6.7	19.4	81.5	49.8	55.3	7.8	47.4	199.2
80	26.6	23.6	6.7	16.9	81.2	45.0	49.9	7.8	42.1	202.1
90	24.3	21.6	6.7	14.9	80.4	41.1	45.6	7.8	37.8	204.1
100	22.4	19.9	6.7	13.2	79.3	37.9	42.1	7.8	34.2	205.4
110	20.8	18.5	6.7	11.8	77.9	35.2	39.1	7.8	31.2	206.1
120	19.5	17.3	6.7	10.6	76.4	32.9	36.5	7.8	28.7	206.4
130	18.3	16.2	6.7	9.6	74.6	30.9	34.3	7.8	26.5	206.3
140	17.3	15.3	6.7	8.7	72.7	29.2	32.4	7.8	24.5	205.9
150	16.4	14.5	6.7	7.8	70.6	27.6	30.6	7.8	22.8	205.2
160	15.6	13.8	6.7	7.1	68.5	26.2	29.1	7.8	21.3	204.3
170	14.8	13.2	6.7	6.5	66.2	25.0	27.8	7.8	19.9	203.2
180	14.2	12.6	6.7	5.9	63.8	23.9	26.5	7.8	18.7	201.8
190	13.6	12.1	6.7	5.4	61.4	22.9	25.4	7.8	17.6	200.3
200	13.0	11.6	6.7	4.9	58.9	22.0	24.4	7.8	16.6	198.7
210	12.6	11.1	6.7	4.5	56.3	21.1	23.5	7.8	15.6	196.9

6.7 L/s 5-year Qattenuated 5-year Max. Storage Required Est. 5-year Storage Elevation 81.5 m³ 93.66 m

13.0 L/s 100-year Qattenuated 100-year Max. Storage Required Est. 100-year Storage Elevation 206.4 m³ 94.34 m

Notes:

- Flow from the storage tank assumes maximum Q Release at the tank obvert

^{**}V_{acc}=Total surface and sub-surface

⁻ Required storage volumes calculated using the average Q release rate within the tank

Area ID STM149 Available Sub-surface Storage

Total Subsurface Storage (m³)

74.8 <-- Provided storage excludes storage volume below system invert

Stage Attenuated Areas Storage Summary

_		Surface Storage		ge	Surface and Subsurface Stor			rage
	Stage	Ponding	h _o	delta d	V*	V _{acc} **	Q _{release} +	$V_{drawdown}$
	(m)	(m²)	(m)	(m)	(m³)	(m³)	(L/s)	(hr)
Orifice INV	92.84		0.00			0.0	0.0	0.00
Storage Chamber INV	92.93		0.09	0.09		0.0	32.2	0.00
Storage Chamber OBV	94.07		1.23	1.14	74.8	74.8	119.1	0.17
	* \ /							

^{*} V=Incremental storage volume

 Orifice Location
 STM149
 Dia
 225

 Area C
 0.18 0.78
 0.24 0.74

Total Area 0.42 ha

C 0.76 Rational Method runoff coefficient Note: Rational Method Coefficient "C" increased by 25% for 100-year calculations

	5-year					100-year				
t _c	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}	i	Q _{actual} ‡	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)
14	87.4	77.2	54.3	22.8	19.0	149.5	165.0	75.7	89.3	74.4
20	70.3	62.1	54.3	7.7	9.3	120.0	132.4	75.7	56.8	68.1
25	60.9	53.8	53.8	0.0	0.0	103.8	114.7	75.7	39.0	58.5
30	53.9	47.6	47.6	0.0	0.0	91.9	101.4	75.7	25.7	46.3
35	48.5	42.9	42.9	0.0	0.0	82.6	91.2	75.7	15.5	32.5
40	44.2	39.0	39.0	0.0	0.0	75.1	83.0	75.7	7.3	17.5
45	40.6	35.9	35.9	0.0	0.0	69.1	76.2	75.7	0.6	1.5
50	37.7	33.3	33.3	0.0	0.0	64.0	70.6	70.6	0.0	0.0
55	35.1	31.0	31.0	0.0	0.0	59.6	65.8	65.8	0.0	0.0
60	32.9	29.1	29.1	0.0	0.0	55.9	61.7	61.7	0.0	0.0
65	31.0	27.4	27.4	0.0	0.0	52.6	58.1	58.1	0.0	0.0
70	29.4	25.9	25.9	0.0	0.0	49.8	55.0	55.0	0.0	0.0
75	27.9	24.6	24.6	0.0	0.0	47.3	52.2	52.2	0.0	0.0
80	26.6	23.5	23.5	0.0	0.0	45.0	49.7	49.7	0.0	0.0
85	25.4	22.4	22.4	0.0	0.0	43.0	47.4	47.4	0.0	0.0
90	24.3	21.5	21.5	0.0	0.0	41.1	45.4	45.4	0.0	0.0
95	23.3	20.6	20.6	0.0	0.0	39.4	43.5	43.5	0.0	0.0
100	22.4	19.8	19.8	0.0	0.0	37.9	41.9	41.9	0.0	0.0
105	21.6	19.1	19.1	0.0	0.0	36.5	40.3	40.3	0.0	0.0
110	20.8	18.4	18.4	0.0	0.0	35.2	38.9	38.9	0.0	0.0
115	20.1	17.8	17.8	0.0	0.0	34.0	37.5	37.5	0.0	0.0

5-year Qattenuated 54.3 L/s 5-year Max. Storage Required 19.0 m³ Est. 5-year Storage Elevation 93.22 m

 100-year Q_{attenuated}
 119.1 L/s

 100-year Max. Storage Required
 74.4 m³

 Est. 100-year Storage Elevation
 94.06 m

Notes:

Summary of Release Rates and Storage Volumes

Control Area	5-year Release Rate (L/s)	5-year Required Storage (m³)	100-Year Release Rate (L/s)	100-Year Required Storage (m³)	100-Year Available Storage (m³)
Unattenuated Areas					
Glenroy Gilbert	29.7	0.0	50.8	0.0	0.0
Riocan	25.6	0.0	43.8	0.0	0.0
Chapman Mills	65.4	0.0	111.9	0.0	0.0
Longfields	26.0	0.0	44.5	0.0	0.0
Attenuated Areas					
STM115	46.6	41.4	69.5	134.6	135.1
STM126	10.9	38.2	21.7	103.2	105.5
STM124	7.6	104.8	9.5	272.7	275.1
STM134	86.5	6.9	141.3	76.2	79.7
STM164	6.5	78.3	11.3	200.0	203.5
STM159	6.7	81.5	13.0	206.4	210.3
STM149	54.3	19.0	119.1	74.4	74.8
Total	365.9	370.1	636.6	1067.6	1084.1

^{**}V_{acc}=Total surface and sub-surface

[†] Q_{release} = Release rate calculated from orifice equation

⁻ Required storage volumes calculated using the average Q release rate within the tank

⁻ Flow from the storage tank assumes maximum Q Release at the tank obvert

Glenroy Gilbert Extension and Riocan Ave

Date: June, 2023 DSEL File: 816

ICD Sizing (CBs within City ROW)

Orifice Dia (mm)	Head (m)	Flow (L/s)	
83	1.38	17.5	
94	1.38	22.4	
102	1.38	26.4	
108	1.38	29.6	
127	1.38	40.9	
152	1.38	58.5	
178	1.38	80.3	

CB ID	Area (Ha)	RC	Design Flow (5yr	ICD Size (mm)
CICB 3	0.08	0.72	16.7	83
CB 4	0.08	0.72	16.7	83
CB 5	0.08	0.72	16.7	83
CB 6	0.08	0.72	16.7	83
CB 7	0.03	0.72	6.3	83
CB 8	0.03	0.72	6.3	83
CB 9	0.09	0.61	15.9	83
CB 10	0.03	0.64	5.6	83
CB 12	0.08	0.70	16.2	83
CB 13	0.10	0.61	17.7	83
CB 14	0.08	0.70	16.2	83

104.2 mm/hr

i T_c 10.0 min 2023-06.29

Stormwater - Proposed Development City of Ottawa Sewer Design Guidelines, 2012



Estimated Post Development Peak Flow to DICB 1

0.72 ha <-- Sum of Unattenuated Drainage from Future Chapman Mills Drive 0.70 Rational Method runoff coefficient Area C

	10-year				
t _c	i	Q _{actual}	Q _{release}	Q _{stored}	V _{stored}
(min)	(mm/hr)	(L/s)	(L/s)	(L/s)	(m³)
13.9	102.3	143.3	143.3	0.0	0.0

Note: Tc = 13.88 min per Design Sheet

Area C 0.01 0.16 0.17 0.01 0.83 0.57 0.74 0.53

0.35 ha <-- Sum of Unattenuated Drainage to Chapman Mills Drive (from Block B) **Total Area**

0.77 Rational Method runoff coefficient

	5-year				
t _c (min)	i (mm/hr)	Q _{actual} (L/s)	Q _{release} (L/s)	Q _{stored} (L/s)	V _{stored} (m ³)
13	.9 87.4	65.4	65.4	0.0	0.0

Note:

Tc = 13.88 min per Design Sheet

Design Parameters

Max Head: 1.380 m 0.2087 m³/s Controlled Flow Rate:

Calculations

A blockage factor has also been applied.

Orifice Flow

 $Q = CA(2gH)^{0.5}$ $A=\pi r^2$


where: C = 0.62 A = area of ICD oulet H = maximum depth

Area of ICD required = Diameter of Circular ICD= $0.06 \text{ m}^2 \\ 0.2870 \text{ m}$

287.0 mm

Diameter ICD Provided = 285 mm

TEMPEST LMF flow curves



The Next Generation in Storm Sewer Inlet Controls





STORM WATER FLOW CONTROL

THE COST-EFFECTIVE SOLUTION TO YOUR STORM WATER SURCHARGE PROBLEMS

- Conserves sewer system capacity
- System accommodates low to high flows
- Integrated odour and floatable control
- Fast and easy to install and maintain



We build tough products for tough environments®



THE NEXT GENERATION IN STORM SEWER INLET CONTROLS

Reduces Sewer Overflows and Basement Backups

Tempest is a family of cost-effective inlet control devices that work together across a series of catch basins to limit the amount of storm water runoff that can enter a combined sewer system during a storm event. Basement backups and sewer overflows are avoided because storm water surcharges are controlled at the sewer inlet and are allowed to remain in catch basins or temporarily above ground.

Integrated Odour and Floatable Control

In addition to flow control, Tempest systems can also alleviate sewer system odour emissions as well as prevent floating debris from entering the sewer system.

Wide Range of Models & Pre-set Flow Rates

Available in a wide range of patent pending models and pre-set flow rates,
Tempest systems can accommodate most storm water flow control requirements
from 32 GPM to 270 GPM and beyond. Application specific solutions can also be
engineered to meet your unique needs in both wet and dry catch basin environments.

Easy to Install and Maintain


Constructed from durable PVC, Tempest units are corrosion free and built to last. The Tempest's light weight design accommodates both square and round catch basins and features a universal back plate and interchangeable components with no moving parts that makes the units quick and easy to install over a catch basin outlet pipe.

These devices also include a quick release mechanism to allow easy access for service without the need to drain the installation.


IPEX has been a great partner for us in terms of providing a quality system that meets all requirements and a knowledgeable staff that delivers reliable field support

Kevin Secord Multi-Drain Inc. (Ottawa, Ontario)





Tempest Inlet Control Devices restrict flow to a narrower range than traditional methods regardless of head







THE TEMPEST FAMILY OF SYSTEMS

TEMPEST LMF

Restricts:

- ✓ Flow
- ✓ Odours
- √ Floatables



LOW to MODERATE FLOW RATES

32 GPM (2 L/s) - 270 GPM (17 L/s)

14 pre-set flow rates

The Tempest LMF system features a vortex inlet design that allows a low flow rate to be set and eliminates the passage of odours and floatables and allows for debris and sediment to collect in the structure.

TEMPEST HF & HF SUMP



- ✓ Flow
- ✓ Odours
- √ Floatables



HIGH FLOW RATES

240 GPM (15 L/s) or greater

5 pre-set flow rates

The standard Tempest HF system allows a near constant discharge rate to be set and eliminates the passage of odours and floatables and allows for debris and sediment to collect in the structure.

The Tempest HF SUMP system is designed for catch basins & manholes in which there is no sump or the outlet pipe is too low to install standard Tempest device.

TEMPEST MHF

Restricts: ✓ Flow





MEDIUM TO HIGH FLOW RATES

143 GPM (9L/s) or greater

Specified pre-set flow rates

The Tempest MHF is a standard orifice plate or plug device designed to allow a specified flow volume through the outlet pipe at a specified head.




PROBLEM: SURCHARGED SEWER SYSTEMS



During heavy rain events, storm sewers can become overloaded causing sewer backups into residential basements and onto urban environments and streets. These events cause significant environmental and property damage and are all too common in older sections of municipalities where combined, undersized sewer systems often end up discharging a mixture of storm water runoff and sanitary wastewater into homes, streets and lakes when sewer capacities exceed historical norms.

Traditional approaches to overcoming these challenges have been expensive, disruptive and time consuming for municipalities and the private sector.

SOLUTION: TEMPEST INLET CONTROL SYSTEMS



CUSTOMER SERVICE CENTER

IPEX USA LLC

2441 Royal Windsor Drive Mississauga, Ontario L5J 4C7 Phone: (905) 403-0264 Toll Free: (800) 463-9572

Fax: (905) 403-9195

www.ipexamerica.com

About the IPEX Group of Companies

As leading suppliers of thermoplastic piping systems, the IPEX Group of Companies provides our customers with some of the largest and most comprehensive product lines. All IPEX products are backed by more than 50 years of experience. With state-of-the-art manufacturing facilities and distribution centers across North America, we have established a reputation for product innovation, quality, end-user focus and performance.

Markets served by IPEX group products are:

- · Electrical systems
- Telecommunications and utility piping systems
- PVC, CPVC, PP, ABS, PEX, FR-PVDF and PE pipe and fittings (1/4" to 48")
- Industrial process piping systems
- Municipal pressure and gravity piping systems
- Plumbing and mechanical piping systems
- PE Electrofusion systems for gas and water
- · Industrial, plumbing and electrical cements
- · Irrigation systems

Products manufactured by IPEX Inc. and distributed in the United States by IPEX USA LLC.

TEMPEST™ is a trademark of IPEX Branding Inc.

This literature is published in good faith and is believed to be reliable. However, it does not represent and/or warrant in any manner the information and suggestions contained in this brochure. Data presented is the result of laboratory tests and field experience.

A policy of ongoing product improvement is maintained. This may result in modifications of features and/or specifications without notice.



