2024-11-01

PROJECT STATISTICS

1186 Wellington St Proposed Residential Development
Ottawa Ontario
16 Storey Concept - 6 Podium
BUILDING PERMIT SUBMISSION - AS PER CITY OF OTTAWA ZONING BY-LAW 2008-250 CONSULIDATION

1.0 SITE AREA

Overall Site Area

	acres	sq.m.	sq.ft.
Site Area	**0.6170221**	**2,497**	**26,877**

2.0 GROSS FLOOR AREAS (GFA)

Gross floor area means the total area of each floor whether located above, at or below grade, measured from the **interiors** of outside walls and including floor area occupied by interior walls and floor area created by bay windows, but excluding;
(a) floor area occupied by shared mechanical, service and electrical equipment that serve the building (By-law 2008-326)
(b) common hallways, corridors, stairwells, elevator shafts and other voids, steps and landings; (By-law 2008-326) (By-law 2017-302)
(c) bicycle parking; motor vehicle parking or loading facilities;
(d) common laundry, storage and washroom facilities that serve the building or tenants;
(e) common storage areas that are accessory to the principal use of the building; (By-law 2008326)
(f) common amenity area and play areas accessory to a principal use on the lot; and (By-law 2008-326)
(g) living quarters for a caretaker of the building. (surface de plancher hors secure locale)

Buildings GFA 1.0

	GFA	No. of Levels	sq.m.	sq.ft.
Commercial - Non-Residential GFA			**1,099**	**11,830**
Level Ground (retail)	1,099	1	1,099	11,830
Residential GFA			**12,733**	**137,057**
Level Ground (residential)	84	1	84	904
Level 2	1,298	1	1,298	13,972
Level 3-4	1,319	2	2,638	28,395
Level 5	1,126	1	1,126	12,120
Level 6	1,145	1	1,145	12,325
Level 7	523	1	523	5,630
Level 8-14	657	7	4,599	49,503
Level 15-16	660	2	1,320	14,208
Total Proposed GFA		**16**	**13,832.0**	**148,886**

3.0 FLOOR SPACE INDEX (FSI)

Total Proposed GFA / Site Area	**5.54**

5.0 GROSS BUILDING AREAS (GBA)

Total area measured from the **exterior** surface of outside walls but excluding shaft/void spaces.

Buildings GBA

	GBA	No. of Levels	sq.m.	sq.ft.
Level Ground	1,900	1	1,900	20,451
Level 2	1,448	1	1,448	15,586
Level 3-4	1,472	2	2,944	31,689
Level 5	1,266	1	1,266	13,627
Level 6	1,288	1	1,288	13,864
Level 7	747	1	747	8,041
Level 8-16	746	9	6,714	72,269
Mech PH	461	1	461	4,962
Total Proposed GBA		**17**	**16,768.0**	**180,489**

6.0 GROSS CONSTRUCTION AREAS (GCA)

Buildings GCA

	GCA	No. of Levels	sq.m.	sq.ft.
Level P3	1831	1	1831	19,709
Level P2	2286	1	2286	24,606
Level P1	2286	1	2286	24,606
Level Ground	1983	1	1983	21,345
Level 2	1501	1	1501	16,157
Level 3-4	1526	2	3052	32,851
Level 5	1319	1	1319	14,198
Level 6	1342	1	1342	14,445
Level 7	804	1	804	8,654
Level 8-16	786	9	7074	76,144
Mech PH	506	1	506	5,447
Total Proposed GCA		**20**	**23,984.0**	**258,162**

7.0 NO. OF RESIDENTIAL UNITS

Residential Units

	Units / Floor	Levels	Units
Level Ground (retail)	0	1	0
Level 2	22	1	22
Level 3-4	22	2	44
Level 5	19	1	19
Level 6	20	1	20
Level 7	9	1	9
Level 8-14	12	7	84
Level 15-16	8	2	16
Total No. of Units		16	**214**

8.0 AMENITY

Total Amenity Required

	Total
6 sq.m. per dwelling unit	**1,284 sq.m.**

Communal Amenity Required

	Total
50% of total amenity	**642 sq.m.**

Private Amenity Required

	Total
(Private balconies, terraces, patios)	**642 sq.m.**

Indoor Communal Amenity Provided

	Total
Level 1	122 sq.m.
Level 7	135 sq.m.

Outdoor Communal Amenity Provided

	Total
Level 7	508 sq.m.

Total Communal Amenity Provided

	Total
	765 sq.m.

Total Private Amenity Provided

	Total
(Private balconies, terraces, patios)	**>642 sq.m.**

Total Amenity Provided

	Total
Total Communal + Total Private	**>1,407 sq.m.**

9.0 PARKING

Parking Required		
Residential	**0.5** per dwelling unit after first 12 units, minus 10 percent if all located below gr	**91**
Visitor	0.1 per dwelling unit after first 12 units	**21**
Retail	1.25 per 100 m2 of GFA	**14**
Total Parking Required		**126**

Parking Proposed		
Residential	**0.5** per dwelling unit after first 12 units	**122**
Visitor	0.1 per dwelling unit after first 12 units	**21**
Retail	0 per 100 m2 of GFA	**0**
Total Parking Proposed		**143**

Parking Provided	**Residential**	**Visitor**	**Retail**	
Level P3	47			
Level P2	60			
Level P1	28	21	0	
Total Parking Provided	**135**	**21**	**0**	**156**

Barrier Free Parking Required	**Type A**	**Type B**	**Total**
Total Barrier Free Parking Required	**3**	**3**	**6**

Barrier Free Parking Provided	**Type A**	**Type B**	**Total**
Level P3	1	1	
Level P2	1	1	
Level P1	1	1	
Total Barrier Free Parking Provided	**3**	**3**	**6**

10.0 BICYCLE PARKING

Total Residential Bicycle Spaces Required

	Total
0.5. per dwelling unit	**107**

Total Retail Bicycle Spaces Required

	Total
1 per 250 sq.m. of gross floor area	**5**

Total Residential Bicycle Spaces Provided

	Total
Level P3	**72**
Level P2	**70**
Level P1	**40**
Level 1	**32**
Total	**214**
	(1.0 per unit)

Total Retail Bicycle Spaces Provided

	Total
Level 1	**5**

11.0 LOCKER ROOM

Total Residential Locker Room Provided

	Total
Level P3	**49**
Level P2	**46**
Level P1	**11**
Total	**106**

SURVEY COMPLETED BY STANTEC GEOMATICS LTD.
DATED APRIL 26, 2021
PART OF LOTS A, B, C & D
REGISTERED PLAN 58
PROJECT NO. - 161614215-111

SURVEY CREDIT 8 A1.01
SCALE: 1 : 1



9 A1.01

Typical Bicycle Parking Dimension 7 A1.01
SCALE: 1 : 50



Typical Stacked Bicycle Parking Dimension 6 A1.01
SCALE: 1 : 25

BARRIER FREE PARKING SPACES REQUIRED:
TYPE A: 3
TYPE B: 3
TOTAL: 6

BARRIER FREE PARKING SPACES PROVIDED:
TYPE A: 3
TYPE B: 3
TOTAL: 6



Typical Vehicular Parking Dimension 5 A1.01
SCALE: 1 : 150



CONTEXT PLAN 4 SP03
SCALE: 1 : 2000



SITE PLAN 1 SP03
SCALE: 1 : 125

DIALOG®

ISSUED FOR

1	2021-06-25	ISSUED FOR OPA/ZBLA
2	2021-11-25	RE-ISSUED FOR OPA/ZBLA
3	2022-06-29	ISSUED FOR SPA
4	2022-12-09	RE-ISSUED FOR SPA
5	2023-04-19	RE-ISSUED FOR SPA
6	2024-11-08	RE-ISSUED FOR CITY AND OLT COORDINATION
7	2024-11-21	ISSUED FOR FINAL SPA
8	2024-11-29	ISSUED FOR FINAL SPA

METRIC

THIS DRAWING IS COPYRIGHTED AND MUST NOT BE USED, REPRODUCED, OR REVISED WITHOUT WRITTEN PERMISSION.

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.
VERIFY DIMENSIONS.
DO NOT SCALE THIS DRAWING.

REPORT INCONSISTENCIES AND OMISSIONS TO THE CONSULTANT FOR CLARIFICATION BEFORE COMMENCING WITH THE WORK.

DEVIATIONS FROM THE CONTRACT DOCUMENTS WITHOUT WRITTEN APPROVAL FROM THE CONSULTANT ARE SUBJECT TO CORRECTION AT THE CONTRACTOR'S EXPENSE.

CLIENT
WELLDALE LIMITED PARTNERSHIP
200-180 KENT STREET
OTTAWA, ON. K1P 0B6
Tel: 613-230-7051

ARCHITECT
DIALOG
35 JOHN STREET, SUITE 500
TORONTO, ON. CANADA, M5V 3G6
Tel: 416.996.0220

URBAN PLANNER
FOTENN
396 COOPER ST. SUITE 300
OTTAWA, ON. K2P 2H7
Tel: 613-730-5709

LANDSCAPE ARCHITECT
DIALOG
35 JOHN STREET, SUITE 500
TORONTO, ON. CANADA, M5V 3G6
Tel: 416.996.0220

ENVIRONMENTAL/GEOTECHNICAL
TERRAPEX ENVIRONMENTAL
20 GURDWARA ROAD, UNIT 1
OTTAWA, ON. K2E 8B3
Tel: 613-745-6411

HERITAGE CONSULTANT
MTBA
222 LAURIER AVENUE EAST, STUDIO 201
OTTAWA, ON. K1N 6P2
Tel: 613-244-2323

CIVIL ENGINEER
DSEL
120 IBER ROAD, SUITE 103
OTTAWA, ON. K2S 1E9
Tel: 613-836-0856

TRAFFIC CONSULTANT
CGH TRANSPORTATION
6 PLAZA COURT
OTTAWA, ON. K2H 7W1
Tel: 613-691-3797

SURVEY
STANTEC
1331 CLYDE AVE. SUITE 400
OTTAWA, ON. K2C 3G4
Tel: 613-722-4420

NOISE/WIND CONSULTANT
GRADIENT WIND
127 WALGREEN ROAD
OTTAWA, ON. K0A 1L0
Tel: 613-836-0934

KEYPLAN



ONTARIO ASSOCIATION OF ARCHITECTS — FRANK WANG — LICENCE 7680

PROJECT NORTH / TRUE NORTH

CITY PLAN No.: 18573

1186-1194 WELLINGTON ST W

1186-1194 Wellington St W
Ottawa, ON K1Y 2Z5

SITE PLAN, CONTEXT PLAN, STATISTICS

DRAWN: Author CHECKED: Checker
PLOT DATE: 11/28/2024 3:16:21 PM

CITY FILE No.: D07-12-22-0150

SP03

ABXXXXXX - 2002323