

1649 MONTREAL ROAD  
MONTREAL AND BLAIR ROAD

LIST OF DRAWINGS

PLAN No:	DESCRIPTION
C000	COVER PAGE
C001	TOPOGRAPHICAL SURVEY PLAN
C002	SEDIMENT AND EROSION CONTROL PLAN
C003	NOTES PLAN – 1 of 2
C004	NOTES PLAN – 2 of 2
C005	GRADE CONTROL AND DRAINAGE PLAN
C006	SITE SERVICING PLAN
C006B	SANITARY SEWER LID REPLACEMENTS
C007	STORM WATER MANAGEMENT PLAN
C008	CIVIL DETAILS PLAN – 1 of 7
C009	CIVIL DETAILS PLAN – 2 of 7
C010	CIVIL DETAILS PLAN – 3 of 7
C011	CIVIL DETAILS PLAN – 4 of 7
C012	CIVIL DETAILS PLAN – 5 of 7
C013	CIVIL DETAILS PLAN – 6 of 7
C014	CIVIL DETAILS PLAN – 7 of 7



T: 613-860-2402  
600-1400 Blair Towers Place, Ottawa, ON K1U 8B8 CANADA

BERTONE DEVELOPMENT CORPORATION  
1649 MONTREAL ROAD  
RE-ISSUED FOR SITE PLAN CONTROL REV. 6 - FEBRUARY 11, 2025

C000

D07-12-22-0132  
#18876



Z:\Cimac-C10\CHL Projects\A\4001000-4001498\4001101\_Blair - MtL Road Towers\4001460\_Civil\C000\_Cover.dwg  
11 February 2025 David Smith Varghese











# NOTE OF CAUTION

THE GEOETIC COORDINATES OF EVERY ITEM INCLUDED AS PART OF THIS DOCUMENT ARE IN **NAD83 - ORIGINAL /MTM - REFERENCE SYSTEM** AND HAVE NO LEGAL VALUE. THE SITE LAYOUT MUST BE COMPLETED USING THE OFFICIAL BENCHMARKS OF AN ACCREDITED LAND SURVEYOR IN THE **NAD83 - ORIGINAL /MTM - REFERENCE SYSTEM**.

THE UNDERGROUND FEATURES AND INFORMATION THAT APPEAR ON THE DRAWINGS WERE OBTAINED FROM THE PUBLIC UTILITY COMPANIES AND/OR FROM THE CITY EACH RESPECTIVELY.

ALL INFORMATION UNDER THE LEGEND 'EXISTING IS' FOR INFORMATION ONLY. COMPLETE OR EXACT LOCATION AND ELEVATION OF UNDERGROUND SERVICES ARE NOT GUARANTEED.

CERTAIN UNDERGROUND FEATURES ON PRIVATE PROPERTY ARE NOT SHOWN ON THE CURRENT DRAWING.

ANYONE WHO PROCEEDS WITH EXCAVATION WORK MUST VERIFY THE EXACT LOCATION OF ALL UNDERGROUND FEATURES. BY EXCAVATING WITHOUT EXCAVATION SERVICES AND ASSUME FULL RESPONSIBILITY IF THERE IS ANY DAMAGE THAT OCCURS DURING WORK.

THE CONTRACTOR WILL HAVE THE RESPONSIBILITY AND THE OBLIGATION TO VALIDATE, BY EXPLORATORY EXCAVATION, THE SIZE OF THE PUBLIC UTILITY UNDERGROUND SERVICES AND TO WARN THE ENGINEER OF ANY CONFLICT WITH THE PROJECTED WORK.

EXISTING			PROPOSED	
	MH-S-1			Maintenance Hole (Storm)
	MH-S			Maintenance Hole (Sanitary)
	MH-T			Maintenance Hole (Traffic)
	VC			Valve Chamber (Waterman)
	S			Underground Storm Sewer
	W			Underground Sanitary Sewer
	UG-W			Underground Water
	P			Underground Power
	CAS			Underground Gas
	B			Underground Bell
	TV			Underground Cable
	OHS			Overhead Wires
	UP			Utility Pole
	AN			Anchor
	LS			Light Standard
	CB			Catch Basin
	FH			Fire Hydrant
	IVV			Water Valve
	VV			Gas Valve
	GM			Gas Meter
	TB-B			Bell Terminal Box
	STS			Traffic Signal Post
	TSL			Traffic Light
	S			Bollard
	TEL			Sign
	Gate			Telephone Booth
	Diameter			Chain Link Fence
	Board Fence			Metal Fence
	Concrete Retaining Wall			Stone Retaining Wall
	Invert			Top of Grate
	Underside of Eave			Top of Foundation
	Centreline			Location of Elevation
	Top of Concrete Curb/Retaining Wall Elevation			Property Line
	Eastment			Shrub
	Deciduous Tree			Confertious Tree
	Work Limit			Borehole (Loc. Approx.)
	Silt Fence Per OPSD 219.110			SF
	Overland Flow			Temporary Construction Entrance

7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.F.	
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.F.	
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.F.	
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.F.	
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.F.	
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.F.	
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.F.	
No.	Date	Description		By

STAMPS:

ENGINEER:	DESIGNED BY:	APPROVED BY:

CLIENT:	 <b>BERTONE</b>
PROJECT NAME:	<b>1649 MONTREAL ROAD MONTREAL AND BLAIR</b>
SHEET TITLE:	<b>SEDIMENT EROSION AND CONTROL PLAN</b>
DISCIPLINE:	<b>CIVIL</b>
DRAWN: D. VAGHELA	SCALE: 1:250
DESIGNED: E. POTVIN	DATE: 22/08/31
APPROVER: C.L. LABEL	CITY APPLICATION No.: D07-12-22-0132
PROJECT No. A00101	DRAWING No.:
SHEET No.:	<b>C002</b>



<div><div>1. SEDIMENT AND EROSION CONTROL</div><div><div>1.1. Unless otherwise indicated, all materials and construction methods to be in accordance with the requirements of the latest edition of the Ontario Provincial Standard Specifications and Drawings (OPSS and OPSD), the Ontario Ministry of Environment, Conservation and Parks (MECP), applicable Conservation authorities, the municipal standard specifications and drawings, and all other governing authorities as they apply.</div><div>1.2. Wherever standards, laws and/or regulations are mentioned they refer to their current versions, modifications included.</div><div>1.3. Specifically, sediment and erosion control measures to be constructed as per OPSS:MUNI 80S.</div><div>1.4. The Contractor must implement best management practices and provide adequate sediment and erosion control measures during construction:<div><div>- Prevent soil erosion which can result from stormwater runoff or wind erosion during construction;</div><div>- Prevent sediment deposits in the storm sewer and/or collecting streets and;</div><div>- Prevent air pollution from dust and particulate matter.</div></div></div><div>1.5. Provisions must be made for sediment and erosion control measures prior to stripping the site of vegetation and other deleterious materials. Measures such as phase stripping, vegetation buffer zones, silt fences, straw bales, sediment traps/basins, rock checks, etc. must be constructed and maintained in order to control sediment, as required by the provincial and municipal governing authorities.</div><div>1.6. The Contractor must set up the measures shown on the plan, inspect them frequently and clean and repair or replace the deteriorated structures.</div><div>1.7. When the sediment and erosion control measures have to be removed in order to complete a portion of the work, these same measures must be reinstated.</div><div>1.8. When storing soil on site in piles the Contractor must cover each pile with tarps, straw or a geotextile fabric to avoid fine particle transport by wind and/or streaming rain water.</div><div>1.9. During the construction period, sediment capture silt sacks or filter cloths must be installed and maintained between the frame and cover of all catchbasins and catchbasin/manholes to minimize sediments entering the storm sewer system. All landscaping areas must be completed prior to the removal of the silt sacks or filter cloths.</div><div>1.10. The light duty silt fence barrier must be installed as per OPSPD 219.110.</div><div>1.11. At all times the Contractor must maintain the municipal access roads clean and free of sediments. When cleaning the access roads, the Contractor must take the necessary precautions to clear the surfaces covered with sediment prior to cleaning with water.</div><div>1.12. For dust control, Contractor to apply calcium chloride (Type I - OPSS 2501 and CAN/CGSB-15-1) and water with equipment approved by the Owner's representative at rate in accordance to OPSS:MUNI 506 when directed by Owner's representative.</div><div>1.13. At the end of the construction period, the Contractor is responsible for removal of the temporary sediment and erosion control measures and reconditioning the affected areas.</div><div>1.14. This plan is a "Living Document" which may be revised in the event that the control measures are not sufficient.</div></div></div> <div><div>2. GRADE CONTROL AND DRAINAGE - GENERAL</div><div><div>2.1. The Contractor must conform to all laws, codes, ordinances, and regulations adopted by federal, provincial or municipal government councils and government agencies, applying to work to be carried out.</div><div>2.2. Unless otherwise indicated, all materials and construction methods to be in accordance with the requirements of the latest edition of the Ontario Provincial Standard Specifications and Drawings (OPSS and OPSD), the Ontario Ministry of Environment, Conservation and Parks (MECP), applicable Conservation Authorities, the municipal standard specifications and drawings, and all other governing authorities as they apply.</div><div>2.3. Wherever standards, laws and/or regulations are mentioned they refer to their current versions, modifications included.</div><div>2.4. The boreholes and test pits shown on the plan are for information purposes only. Their location on the plan is approximate. The Contractor must refer to the boreholes and test pit records to obtain information about observed stratigraphy on site.</div><div>2.5. The Contractor is responsible for obtaining all permits required to complete all works and bear cost of same, including road cut permit and water permit and their associated costs.</div><div>2.6. The Contractor is responsible for the coordination of his activities with others on site.</div><div>2.7. Independent geotechnical laboratory for quality control:<div><div>2.7.1. An independent geotechnical laboratory hired by the Owner will perform material testing, inspection and quality control services.</div><div>2.7.2. Geotechnical laboratory to review asphalt and concrete mix designs as requested.</div><div>2.7.3. The Contractor must provide equipment required for executing inspection and testing by appointed geotechnical firm.</div><div>2.7.4. The Contractor must provide labour and facilities to obtain and handle samples and materials on site. Provide sufficient space to store and cure test samples.</div><div>2.7.5. Employment of geotechnical laboratory does not relax responsibility to perform work in accordance with Contract Documents.</div><div>2.7.6. If defects are revealed during inspection and/or testing, appointed geotechnical firm will request additional inspection and/or testing to ascertain full degree of defect. Contractor to correct defect and irregularities at no cost to Owner. Contractor to pay costs for retesting and reinspection.</div><div>2.7.7. Submit copies of inspection and test reports to Owner's representative.</div></div></div><div>2.8. The location of existing underground municipal services and public utilities as shown on the plans are approximate. The Contractor must determine the exact location, size, material and elevation of all existing utilities (on-site and off-site) prior to any excavation work. Damage to any existing services and/or existing utilities during construction, whether or not shown on the drawings must be repaired by the Contractor at his own expense.</div><div>2.9. Site preparation, including clearing, grubbing, stripping of topsoil, demolition, removal of unsuitable materials, cut, fill and rough grading of all areas to receive finished surfaces.</div><div>2.10. All material must be compacted as per the requirements of the governing authority and be approved by the Consultant prior to delivery to the site.</div><div>2.11. Compaction must conform to the following requirements:<div><div>- Exposed subgrade:<div><div>95% Standard Proctor maximum dry density (SPMDD)</div><div>- Granular Subbase Foundations:<div><div>99% Standard Proctor maximum dry density (SPMDD)</div><div>- Granular Base Foundations:<div><div>99% Standard Proctor maximum dry density (SPMDD)</div><div>- Asphalt pavement:<div><div>As per City of Ottawa Special Provision F-3130</div><div>- Subgrade fill (pavement areas - OPSS Select Subgrade Material):<div><div>95% Standard Proctor Maximum Dry Density (SPMDD)</div><div>- Structural fill (building and light standard footprints OPSS Granular 'A' or Granular 'B' Type II Material):<div><div>98% Standard Proctor Maximum Dry Density (SPMDD)</div></div></div></div></div></div></div></div></div></div></div></div></div></div></div></div></div> <div>2.12. If groundwater is encountered during construction, dewatering of excavations could be required as per OPSS:MUNI 51S. It is assumed that groundwater may be controlled by sump and pumping methods. As required under the "Ontario Water Resources Act (OWRA)", the Contractor must register all water taking activities on Ontario's "Environmental Activity and Sector Registry (EASR)" if water taking exceeds 50,000 l/day, and obtain a "Permit to Take Water (PTTW)" if water taking exceeds 400,000 l/day. Furthermore, Contractor must provide all necessary measures required to ensure dewatering operations does not affect in any way the integrity of the existing surrounding buildings and must plan his work accordingly. Water Taking and Discharge Plan to be prepared by a Qualified Person as stipulated under O.Reg. 63/16.</div>
--

2.13. Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements and as follows:

2.13.1. Provide flocculation tanks, settling basins, or other treatment facilities to remove suspended solids or other materials to within the required parameters of the receiving body before discharging to storm sewers, watercourses or drainage areas.

2.13.2. Before discharging to storm sewers, watercourses or drainage areas, discharge water must be sampled and tested to ensure quality requirements in accordance with City of Ottawa Sewer Use By-Law No. 2003-514 and the MECP are adhered to. The Contractor is to perform all additional sampling and testing as required by City of Ottawa. All associated fees to be paid by the Contractor.

2.13.3. Where water is not suitable for discharge into the adjacent storm sewers, watercourses or drainage areas it must be discharged into the on-site sanitary sewer collection system, or disposed off-site at an approved disposal facility.

2.13.4. Sanitary Sewer Discharge:

When discharging to the sanitary sewer, the Contractor must obtain a Sanitary Sewer Agreement for Dewatering from the City of Ottawa in accordance with City of Ottawa Sewer Use By-Law No. 2003-514 and pay all associated fees.

- A copy of the signed Sanitary Sewer Agreement for Dewatering must be provided to the Owner's Representative in advance of dewatering and discharge.

- The Contractor must ensure all requirements of the Discharge Agreement are adhered to and all prerequisite requirements of the Agreement are in place prior to commencing dewatering.

- Provide flow meter and record discharge rate in accordance with City of Ottawa requirements.

- Dewatering discharge rate to sanitary sewer not to exceed rate specified by City.

- For off-site disposal of dewatering effluent, Contractor to provide Departmental Representative proof of receipt that dewatering effluent was received at a licensed landfill facility and pay all associated disposal fees.

- Contractor must provide name of proposed licensed disposal facility to Owner's Representative in advance of any dewatering waste leaving the site.

- Contractor is responsible for paying all costs associated with any water quality sampling and testing required.

2.14. The Contractor must maintain benchmarks and landmark references as is. Otherwise these references will be repositioned by a certified land surveyor at the Contractor's expense.

2.15. The Contractor is the only person in charge of safety on the building site. The Contractor is responsible for providing adequate protection of the workers, other personnel and the general public, protection of materials, as well as maintain in good condition the control works and works to be completed. The Contractor must supply, install and maintain an appropriate safety fence along the work perimeter until the work is complete.

2.16. The Contractor must provide at any time:

- A sufficient number barriers, posters, guards and others to ensure safety;

- Necessary conveniences for the completion of the work such as heating, lighting, ventilation, etc.

2.17. Temporary excavations in the overburden must be completed as per the requirements of the Occupational Health and Safety Act (OHSA), O. Reg. 213/91, Part II - Excavations:

The side slopes of excavations in the soil and fill overburden materials should either be cut back at acceptable slopes or should be retained by shoring systems from the star of the excavation until the structure is backfilled.

The excavation side slopes above the groundwater level extending to a maximum depth of 3 m should be cut back at 1H:1V or flatter. The flatter slope is required for excavation below the groundwater level. The subsurface soil is considered to be mainly a Type 2 and 3 soil according to the Occupational Health and Safety Act and Regulations for Construction Projects. Slopes in excess of 3 m in height should be periodically inspected by the geotechnical consultant in order to detect if the slopes are exhibiting signs of distress.

2.18. The Contractor must pace deliveries and removals in order to minimize and control stockpiles.

2.19. Excavated soil must not be stockpiled directly at the top of excavations and heavy equipment kept away from the excavation sides.

2.20. Cleanliness on the site:

- The Contractor must clean roadways at his own cost as directed by the Owner's representative;

- All site roads and walkways to and from the construction zone must be kept clean at all times, from mud, dirt, granular material, debris, etc.;

- The Contractor must leave the work area clean at the end of each day;

- Materials and equipment must be laid out in an organized and safe manner;

- All material, equipment and temporary structures which are no longer necessary for the execution of the - Contract must be removed from the site;

- If required the Contractor must use screens, bulkheads, or any other recognized means in order to reduce noise, dust, interference, obstruction, etc., in conformity with the requirements of the provincial and municipal authorities having jurisdiction.

2.21. During the construction period the Contractor is responsible for installing and maintaining temporary traffic signage, including traffic signs, traffic markings and temporary traffic lights, and flagmen, as required by the Owner, the Consultant, the Municipality, and other governing authorities.

2.22. The Contractor must control surface runoff from precipitation during construction.

2.23. Protection of existing trees and shrubs:

- Where trees and naturalized areas are to be retained, the following best management practices as outlined in the City of Ottawa Tree Protection - By-law No. 2020-340 (City of Ottawa 2021b) should be followed when construction activities occur near trees. These protection measures must be in place prior to any work and maintained until the work is complete.

- Establish a buffer (i.e., fencing, stakes) around the critical root zone (CRZ) of trees as per TREE PROTECTION SPECIFICATION detail of drawing C013.

- Do not attach any signs, notices, or posters to any tree.

- Do not damage the root system, trunk, or branches of any tree.

- Do not place any material or equipment within the CRZ of the tree.

- Do not raise or lower the existing grade within the CRZ.

- Do not direct exhaust fumes from equipment towards any tree's canopy.

- Construction equipment and heavy equipment should arrive at the site clean and free of mud and debris to prevent the spread of additional noxious weeds species to the site. Upon completion of work, the equipment should be cleaned to prevent the spread of weeds to the next work area.

- Prune tree branches as needed to complete the work.

- The Contractor must perform any tree cutting prior to April 15 or after August 31 (i.e., outside of the migratory birds General Nesting Period).

2.24. The Contractor must ensure the following mitigation measures are implemented in order to reduce the risk of ground contamination from petroleum products:

- The list of persons and agencies to contact in the event of an emergency must be posted in plain sight on the work site for the duration of the construction period;

- Machinery must be clean and kept clean to limit any grease or oil deposits inside the work area;

- Frequent inspections must be performed to detect any oil, fuel, grease or other leaks. If a leak is detected, the necessary corrective action must be taken immediately.

- An emergency kit for the recovery of petroleum products must be kept on site at all times. The kit must include at least 30 m of absorbent booms, a box of absorbent pads and solid absorbent material (powder or granules). The kit must be stored near the location of work and machinery, and kept within easy reach at all times to ensure a rapid response.

- In the event of a spill the Contractor must immediately report to the Spills Action Centre of the MECP at 1-800-268-6060. Hydrocarbons and contaminated soils will be recovered by a specialized firm.

2.25. The Contractor must ensure the following measures are implemented regarding the handling of concrete:

- Concrete should either be mixed away from the site or should be prepared on paved surfaces if only small quantities are required (i.e. minor repairs);

- Excess concrete must be disposed off-site at a location that meets all regulatory requirements;

- The washing of concrete trucks and other equipment used for mixing concrete should not be carried out within 30 m of a watercourse or wetland and should take place outside of the work site;

- All concrete trucks should collect their wash water and recycle it back into their trucks for disposal off-site at a location meeting all regulatory requirements.

3. DEMOLITION AND REMOVALS

3.1. The Contractor must visit the premises in order to be fully aware of existing conditions on site, including all elements to be removed and demolished. No claim will be accepted due to a poor evaluation of the work to be completed.

3.2. The Contractor must protect and maintain in service the existing works which must remain in place. If they are damaged, the Contractor must immediately make the replacements and necessary repairs to the satisfaction of the Owner's representative and without additional expense to the Owner.

3.3



1. MUNICIPAL SERVICES - GENERAL

- 1.1. Unless otherwise indicated, all materials and construction methods to be in accordance with the requirements of the latest edition of the Ontario Provincial Standard Specifications and Drawings (OPSS and OPSD), the Ontario Ministry of Environment, Conservation and Parks (MECP), applicable Conservation Authorities, the municipal standard specifications and drawings, and all other governing authorities as they apply.
- 1.2. Wherever standards, laws and/or regulations are mentioned they refer to their current versions, modifications included.
- 1.3. The boreholes and test pits shown on the plan are for information purposes only. Their location on the plan is approximate. The Contractor must refer to the boreholes and test pit records to obtain information about observed stratigraphy on site.
- 1.4. The location of existing underground municipal services and public utilities as shown on the plans are approximate. The Contractor must determine the exact location, size, material and elevation of all existing utilities (on-site and off-site) prior to any excavation work. Damage to any existing services and/or existing utilities during construction, whether or not shown on the drawings must be repaired by the Contractor at his own expense.
- 1.5. The Contractor is responsible for obtaining all permits required to complete all works and bear cost of same, including water permit and associated costs.
- 1.6. The Contractor is responsible for the coordination of his activities with others on-site.
- 1.7. Terminate and plug all service connections at 1.0 meter from edge of the building.
- 1.8. The Contractor must complete trench and backfill compaction as per OPSS.MUNI 401/City special provisions and OPSS.MUNI 501:

MATERIALS	COMPACTION
Pipe bedding	99% SPMDD
Pipe cover	99% SPMDD
Trench backfill	95% SPMDD
Structure bedding	98% SPMDD

- 1.9. The Contractor is responsible for making or arranging all connections to the existing sewers as per municipal requirements. Prior to connection, the Contractor must provide, to the Engineer and the City for approval, all test results performed on the internal services. Test results must include C.C.T.V. inspection of sewers, infiltration/exfiltration tests for sewers and manholes, deformation tests of sewers, watermain hydrostatic leakage test, flushing and disinfecting operations, and bacteriological water analysis.
- 1.10. Advise the City Public Works at least 72 hours in advance before any connection to the City services. Coordinate with City as required.
- 1.11. The Contractor must determine the exact invert (geodetic elevation), diameter and construction material of the existing conduits at the proposed connections. He must also carry out, if necessary, exploratory excavations in order to determine the exact location and inverts of existing duct banks. This information must immediately be provided to the Engineer prior to start undertaking any municipal services work and a 48 hour period must be allocated to the Engineer for design review.
- 1.12. The Contractor is responsible for all excavation, backfill and reinstatement of all areas disturbed during construction to existing conditions or better and all associated works to the satisfaction of the Engineer and municipal authorities.
- Asphalt reinstatement must be in accordance with OPSS.MUNI 310 and City of Ottawa Special Provisions.
- Landscape areas to be reinstated with 150 mm of topsoil and sod in accordance with OPSS.MUNI 802 and OPSS.MUNI 803.
- 1.13. It is recommended that a trench box be used at all times to protect personnel working in trenches with steep or vertical sides. Service are expected to be installed by "cut and cover" methods and excavations should not remain open for extended periods of time.
- 1.14. The pipe bedding for sewer and water pipes must consist of at least 150 mm of OPSS Granular A material. The material must be placed in maximum 300 mm thick lifts and compacted to a minimum of 95% of its SPMDD. The bedding material should extend at least to the spring line of the pipe.
- 1.15. The cover material, which must consist of OPSS Granular A, will extend from the spring line of the pipe to at least 300 mm above the obvert of the pipe. The material must be placed in maximum 300 mm thick loose lifts and compacted to a minimum of 95% of its SPMDD.
- 1.16. Where hard surface areas are considered above the trench backfill, the trench backfill material within the frost zone (about 1.8 m below finished grade) must match the soils exposed at the trench walls to minimize differential frost heaving. The trench backfill must be placed in maximum 300 mm thick loose lifts and compacted to a minimum of 95% of the material's SPMDD.
- 1.17. Dewatering of pipeline, utility and associated structure in rock excavations to be completed as per OPSS.MUNI 403.
- 1.18. Trenching, backfilling and compacting must conform to OPSS.MUNI 401.

2. WATERMAIN

- 2.1. Watermain, water service connections and associated appurtenances must be constructed in accordance with the Ontario Provincial Standard Specifications and the City of Ottawa Standards Specifications. Specifically watermain must conform to OPSS.MUNI 441.
- 2.2. Watermain must be constructed as per OPSS.MUNI 441 and specifically OPSD 802.010 for earth excavations and 802.013 for rock excavation.
- 2.3. Watermain pipe materials must be class 150 PVC DR 18 or approved equivalent, unless otherwise shown on the Drawings. Materials must conform to City of Ottawa Material Specification MW-18.1: Manufactured to AWWA C-900 and CSA B137.3 or Pressure Class 235psi/1620 kPa AWWA C-909 and CSA B137.3.1 standards. Pipe shall have the cast iron outside diameter dimensions, be blue in colour and supplied complete with gaskets.
- 2.4. All watermain must be installed with a minimum of 240 metres cover from finished grade. Where a minimum of 240 metres cover is not reached, thermal insulation is required as per City of Ottawa Details W22. Insulation for use in made over pipe trenches shall:
- be type Extruded Polystyrene Foam Insulation Boards (XPS) in 600 x 2400 x 50mm size;
  - meet the requirements of OPSS.MUNI 1605;
  - Grade A (275 kPa compressive strength shall meet ASTM C578 Type VI;
  - Grade B (400 kPa compressive strength shall meet ASTM C578 Type VII.
- 2.5. Cathodic protection (if required) must be installed as per City of Ottawa Details W40 and W42.
- 2.6. Thrust block and restraints must be as per City of Ottawa Details W25.3, W25.4, W25.5 and W25.6.
- 2.7. Valves to be installed as per OPSS 441 and City of Ottawa Special Provision F-4413 and conform to the following:
- All valves must open in a clockwise direction;
  - Designed for cold water working pressure of 1035 kPa;
  - Valves greater than or equal to 75 mm, and less than or equal to 300 mm, to be cast or ductile iron gate valves;
- 2.8. A continuous 12 gauge copper tracer wire must be installed over all watermain.
- 2.9. Valve box assembly to be as per City of Ottawa Detail W24 and valve chamber assembly to be as per City of Ottawa Detail W3.
- 2.10. Watermain must be thoroughly flushed and cleaned to remove all dirt and debris prior to the disinfection process.
- 2.11. All watermain must be hydrostatically and bacteriologically tested as per provincial and municipal regulations. It is the Contractor's responsibility to ensure that all requirements are followed.
- 2.12. The Contractor must make arrangements with and give a minimum of 24 hours' notice to the City for the closing off of necessary valves in the water distribution system. The City will operate valves at the time of tie-ins, etc. at no expense to the Contractor under normal conditions; however the Contractor will be responsible for all costs associated with emergency shutdowns if they occur outside of the normal working hours of the City forces (Monday to Friday, 7:00 a.m. to 5:00 p.m.)

- 2.13. Hydrostatic testing to be completed as per OPSS 441.07.24. Testing must be completed under the supervision of the Contract Administrator. The test section will be either a section between valves or the completed watermain. Test pressure to be 1035 kPa.
- 2.14. Flushing and Disinfecting to be completed as per OPSS 441.07.25 under the supervision of the Contract Administrator.
- 2.15. The Contractor must obtain a permit from the City before using an existing fire hydrant located within the City's territory.
- 2.16. The Contractor must coordinate and pay the cost of connection, inspection and disinfection by municipal personnel.
- 2.17. Contractor must coordinate the supply and installation of water meter and remote water meter for the building with the mechanical engineer.

3. STORM SEWER

- 3.1. Storm sewers, laterals and storm service connections must be constructed in accordance with the Ontario Provincial Standard Specifications / City of Ottawa Standards Specifications / Ministry of Environment and Climate Change Requirements. Specifically storm sewers must conform to OPSS.MUNI 410 and City of Ottawa Special Provisions.
- 3.2. PVC storm sewer material to conform to OPSS.MUNI 1841 and City of Ottawa Material Specification MS-18.1. PVC storm sewers to be installed as per OPSD 802.010 for earth excavation and 802.013 for rock excavation. Bedding and cover material to be OPSS Granular 'A'.
- 3.3. The allowable deflected pipe diameter when using flexible pipe is as follows:
- Pipes 100 to 750 mm: 7.5% of the base inside diameter of the pipe
  - Greater than 750 mm: 5.0% of the base inside diameter of the pipe
- 3.4. Final backfill material for storm sewers must be approved native material or select subgrade material in conformance with OPSS.MUNI 212 and City of Ottawa Special Provision F-2120.
- 3.5. Storm sewer pipes must be type PVC SDR-35, unless noted otherwise on the drawings.
- 3.6. All storm sewers to be C.C.T.V. inspected by the Contractor as per OPSS.MUNI 409 and City of Ottawa Special Provision F-4090. Report must be provided to the Engineer in two (2) copies and the C.C.T.V. inspection in DVD format only.
- 3.7. Storm manholes, manhole/catchbasins, catchbasins, ditch inlets and valve chambers to be installed as per OPSS.MUNI 407 and conform to OPSS 1351 and City of Ottawa Special Provision F-4070.
- 3.8. Adjustment or rebuilding of manholes, manhole/catchbasins, catchbasins, ditch inlets and valve chambers to be completed as per OPSS.MUNI 408 and City of Ottawa Special Provisions F-4080 and F-4081.
- 3.9. Excavating, backfilling, and compacting for manholes, manhole/catchbasins, catchbasins, ditch inlets and valve chambers to be completed as per OPSS 402.
- 3.10. Storm manhole, manhole/catchbasin and catchbasin excavations to be backfilled with OPSS Granular 'B'. Joints between sections must be wrapped in a non-woven geotextile.
- 3.11. Concrete storm manholes and manhole/catchbasins to be as per OPSD 701.010 and must be equipped with safety platform as per OPSD 404.020 when exceeding 5.0 m to the lowest invert.
- 3.12. Concrete storm manhole frame and cover to be as per OPSD 401.010 Type "A" closed cover on private property and City of Ottawa Details S24.1 and S25 on municipal ROW.
- 3.13. Storm private roadway catch basin to be as per OPSD 704.010 and 705.010.
- 3.14. Storm rear yard elbow catch basin to be as per City of Ottawa Detail S31.
- 3.15. For building roof drain sizes and location refer to architectural and mechanical drawings.
- 3.16. When a minimum cover of 1.5 m is not reached, frost protection is required required as per detail 500.


4. SANITARY SEWER

- 4.1. Sanitary sewers, laterals and service connections must be constructed in accordance with the Ontario Provincial Standard Specifications / City of Ottawa Standards Specifications / Ministry of Environment and Climate Change Requirements. Specifically sanitary sewers must conform to OPSS.MUNI 410 / City of Ottawa Special Provisions.
- 4.2. If specified in the servicing drawings that the sanitary sewer pipes are to be PVC SDR-25, the sewer must be constructed with materials and joints that are equivalent to watermain standards of construction (as per F-6-1 procedures) and must be pressure tested in accordance with the OPSS.MUNI 441, with no leakage.
- 4.3. PVC sanitary sewer pipe material to conform to City of Ottawa Material Specification MS-18.1. PVC sanitary sewers to be installed as per OPSD 802.010 (Class B Bedding) for earth excavation and 802.013 (Class B Bedding) for rock excavation. Bedding and cover material to be OPSS Granular 'A'.
- 4.4. The allowable deflected pipe diameter when using flexible pipe is as follows:
- Pipes 100 to 750 mm: 7.5% of the base inside diameter of the pipe
  - Greater than 750 mm: 5.0% of the base inside diameter of the pipe
- 4.5. Final backfill material for sanitary sewers must be approved native material or select subgrade material in conformance with OPSS.MUNI 212 and City of Ottawa Special Provision F-2120.
- 4.6. All sanitary sewers to be C.C.T.V. inspected by the Contractor as per OPSS.MUNI 409 and City of Ottawa Special Provision F-4090. Report must be provided to the Engineer in two (2) copies and the C.C.T.V. inspection in DVD format only.
- 4.7. Sanitary manholes to be installed as per OPSS.MUNI 407 and conform to OPSS 1351 and City of Ottawa Special Provision F-4070.
- 4.8. Adjustment or rebuilding of sanitary manholes to be completed as per OPSS.MUNI 408 and City of Ottawa Special Provisions F-4080 and F-4081.
- 4.9. Excavating, backfilling, and compacting for sanitary manholes to be completed as per OPSS.MUNI 402.
- 4.10. Sanitary manholes to be backfilled with OPSS Granular 'B'. Joints between sections must be wrapped in a non-woven geotextile.
- 4.11. Sanitary manholes to be as per OPSD 701.010 and must be equipped with safety platform as per OPSD 404.020 when exceeding 5.0 m to the lowest invert.
- 4.12. Sanitary manhole frame and cover to be as per OPSD 401.010 Type "A" closed cover.
- 4.13. Sanitary manhole frame and cover to be as per OPSD 401.010 on private property and Watertight frame and covers as per OPSD 401.030 on municipal ROW (Refer to drawing C006B).
- 4.14. Benching is required inside the concrete bottom of sanitary manholes as per OPSD 701.021.
- 4.15. When a minimum cover of 1.8 m is not reached, frost protection is required as per detail 500.

7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.
No.	Date	Description	By
STAMPS:			
<div><div></div></div>			
DESIGNED BY		APPROVED BY	
ENGINEER: <div></div>			
CLIENT: <div></div>			
PROJECT NAME: <div>1649 MONTREAL ROAD MONTREAL AND BLAIR</div>			
SHEET TITLE: <div>NOTES PLAN</div>			
DISCIPLINE: <div>CIVIL</div>			
DRAFTER: <div>D. VAGHELA</div>		SCALE:	
DESIGNER: <div>E. POTVIN</div>		DATE: <div>22/08/31</div>	
APPROVER: <div>C.L. LEBEL</div>		CITY APPLICATION No: <div>D07-12-22-0132</div>	
PROJECT No: <div>A001101</div>		DRAWING No: <div>C004</div>	
SHEET No: <div>4 of 15</div>			



TITLE LOCK 24x36 VERT ENG 3.0  
PRINT DATE: 2025/02/11 (PAPER SIZE: ISO A4 (210.00 x 297.00 MM))  
PATH: Z:\Cma-C10101\Projects\A1000-1000-A00-1699A01101\_Blar - Mt Road Towers\400460\_Civil\0005\_Grading.dwg LAYOUT: C005



**NOTE OF CAUTION**

THE GEODETIC COORDINATES OF EVERY ITEM INCLUDED AS PART OF THIS DOCUMENT ARE IN **NAD83 - ORIGINAL / MTM - REFERENCE SYSTEM** AND HAVE NO LEGAL VALUE. THE SITE LAYOUT MUST BE COMPLETED USING THE OFFICIAL BENCHMARKS OF AN ACCREDITED LAND SURVEYOR IN THE **NAD83 - ORIGINAL / MTM - REFERENCE SYSTEM**.

THE UNDERGROUND FEATURES AND INFORMATION THAT APPEAR ON THE DRAWINGS WERE OBTAINED FROM THE PUBLIC UTILITY COMPANIES AND/OR FROM THE CITY EACH RESPECTIVELY.

ALL INFORMATION UNDER THE LEGEND 'EXISTING' IS FOR INFORMATION ONLY. COMPLETE OR EXACT LOCATION AND ELEVATION OF UNDERGROUND SERVICES ARE NOT GUARANTEED.

CERTAIN UNDERGROUND FEATURES ON PRIVATE PROPERTY ARE NOT SHOWN ON THE CURRENT DRAWING.

ANYONE WHO PROCEEDS WITH EXCAVATION WORK SHALL VERIFY THE EXACT LOCATION OF ALL UNDERGROUND FEATURES, BY EXPLORATORY EXCAVATIONS, AND SHALL ASSUME FULL RESPONSIBILITY IF THERE IS ANY DAMAGE THAT OCCURS DURING WORK.

THE CONTRACTOR WILL HAVE THE RESPONSIBILITY AND THE OBLIGATION TO VALIDATE, BY EXPLORATORY EXCAVATION, THE SIZE OF THE PUBLIC UTILITIES UNDERGROUND SERVICES AND TO WARN THE ENGINEER OF ANY CONFLICT WITH THE PROJECTED WORK.

**NOTE**

1. BEFORE REPLACING THE EXISTING MUNICIPAL CONCRETE SIDEWALK ALONG BLAIR ROAD AND MONTREAL ROAD, CONTRACTOR TO SUBMIT A CONSTRUCTION SITE PEDESTRIAN CONTROL PLAN AND CONSTRUCT A TEMPORARY GRANULAR 'A' PEDESTRIAN WALKWALK (1.8m x 0.15m) AS PER CITY OF OTTAWA REGULATIONS.

**SURFACE LEGEND**

City concrete sidewalk - As per detail SC2

Pavers - As per details 217C and 217D

Bioswale surface storm water treatment pond - As per detail 333A

Existing city road reinstatement - As per detail R10

Heavy duty road structure - As per detail 202

Heavy duty road structure - As per detail 203

**EXISTING**

Maintenance Hole (Storm)

Maintenance Hole (Sanitary)

Maintenance Hole (Traffic)

Valve Chamber (Watermain)

Overhead Wires

Utility Pole

Anchor

Light Standard

Catch Basin

Fire Hydrant

Water Valve

Gas Valve

Gas Meter

Bell Terminal Box

Traffic Signal Post

Traffic Light

Bollard

Sign

Gate

Telephone Booth

Diameter

Chain Link Fence

Board Fence

Metal Fence

Concrete Retaining Wall

Stone Retaining Wall

Invert

Top of Grate

Underside of Eave

Top of Foundation

Centreline

Location of Elevations

Top of Concrete Curb / Retaining Wall Elevation

Drainage Direction

Property Line

Easement

Concrete Curb

Depressed Concrete Curb/Sidewalk

Curb / Retaining Wall

Shrub

Deciduous Tree

Coniferous Tree

Work Limit

Borehole (Loc. Approx.)

Overland Flow

Top of Slope

Ditch CL

Bottom of Slope

Two way vehicle circulation

Air Intake / Exhaust grill

Light Standard

Underground Parking Outline

Sawcut

Fence

**PROPOSED**

Maintenance Hole (Storm)

Maintenance Hole (Sanitary)

Maintenance Hole (Traffic)

Valve Chamber (Watermain)

Overhead Wires

Utility Pole

Anchor

Light Standard

Catch Basin

Fire Hydrant

Water Valve

Gas Valve

Gas Meter

Bell Terminal Box

Traffic Signal Post

Traffic Light

Bollard

Sign

Gate

Telephone Booth

Diameter

Chain Link Fence

Board Fence

Metal Fence

Concrete Retaining Wall

Stone Retaining Wall

Invert

Top of Grate

Underside of Eave

Top of Foundation

Centreline

Location of Elevations

Top of Concrete Curb / Retaining Wall Elevation

Drainage Direction

Property Line

Easement

Concrete Curb

Depressed Concrete Curb/Sidewalk

Curb / Retaining Wall

Shrub

Deciduous Tree

Coniferous Tree

Work Limit

Borehole (Loc. Approx.)

Overland Flow

Top of Slope

Ditch CL

Bottom of Slope

Two way vehicle circulation

Air Intake / Exhaust grill

Light Standard

Underground Parking Outline

Sawcut

Fence

**STAMPS**

DESIGNED BY: **CIMA+**

APPROVED BY: **BERTONE**

PROJECT NAME: **1649 MONTREAL ROAD MONTREAL AND BLAIR**

SHEET TITLE: **GRADE CONTROL AND DRAINAGE PLAN**

DISCIPLINE: **CIVIL**

DRAWER: **D. VAGHELA**

DESIGNER: **E. POTVIN**

APPROVER: **C.L. LABEL**

PROJECT No: **A001101**

SHEET No: **5 of 15**

SCALE: **1:250**

DATE: **22/08/31**

CITY APPLICATION No: **D07-12-22-0132**

DRAWING No: **C005**

D07-12-22-0132



TITLE LOCK 24x36 VERT ENG 3.0

PRINT DATE: 2025/02/11 / PAPER SIZE: ISO A4 (210.00 x 297.00 MM)  
PATH: Z:\Cms-C10\OTC\Projects\A001000-A001699\A001101\_Blar - Mt Road Towers\A0040460\_Civil\0006\_Servicing.dwg / LAYOUT: C006



- NOTES:**
1. FOUNDATION DRAIN BACKWATER VALVE REQUIRED ON SERVICE LATERAL PER CITY DETAIL S14.
  2. SANITARY BACKWATER VALVE REQUIRED ON SERVICE LATERAL PER CITY DETAIL S14.1.
  3. ALL FLOOR DRAINS WITHIN THE UNDERGROUND PARKING MUST BE DIRECTED TO THE SANITARY LATERAL.
  4. INTERNAL WATER METER TO BE LOCATED IN WATER ENTRY AND FIRE PUMP ROOM ON LEVEL P1.
  5. SEWER LATERALS MUST CROSS THE WATERMAIN WITH A MINIMUM CLEARANCE OF EITHER 0.5m ABOVE THE WATERMAIN OR 0.3 m BELOW THE WATERMAIN. THE CONTRACTOR MUST CONFIRM THE EXACT INVERT (GEODETIC ELEVATION), DIAMETER AND CONSTRUCTION MATERIAL OF THE EXISTING WATERMAIN AT THE PROPOSED CROSSINGS. IN THE EVENT OF A CONFLICT BETWEEN NEW SEWER LATERALS AND THE EXISTING WATERMAIN, A PORTION OF THE WATERMAIN CAN BE RECONSTRUCTED LOCALLY AS PER DETAIL W25.2. HE MUST ALSO CARRY OUT, IF NECESSARY, EXPLORATORY EXCAVATIONS IN ORDER TO DETERMINE THE EXACT LOCATION AND INVERTS OF EXISTING DUCK BANKS. THIS INFORMATION MUST IMMEDIATELY BE PROVIDED TO THE ENGINEER PRIOR TO START UNDERTAKING ANY MUNICIPAL SERVICES WORK AND A 48 HOUR PERIOD MUST BE ALLOCATED TO THE ENGINEER FOR DESIGN REVIEW.
  6. EVEN IF NOT SHOWN ON THIS DRAWING, ALL CB AND CB/MH STRUCTURES MUST BE EQUIPPED WITH 150mm SUBDRAINS AS PER DETAIL 305. THE SUBDRAINS MUST EXTEND 3m LONG IN THE TWO OPPOSITE DIRECTIONS OF THE STRUCTURES.

**SURFACE LEGEND**

City concrete sidewalk - As per detail S02

Pavers - As per details 217C and 217D

Bioswale surface storm water treatment pond - As per detail 333A

Existing city road reinstatement - As per detail R10

Heavy duty road structure - As per detail 202

Heavy duty road structure - As per detail 203

Bioswale Surface Storm Water Treatment Pond

**EXISTING**

- MH-ST
- MH-S
- MH-T
- VC
- ST
- S
- W
- P
- GA
- B
- TV
- UP
- AN
- LS
- CB
- PH
- WV
- OV
- BM
- TB-B
- TP
- SL
- S
- TEL
- 8
- CLF
- BF
- WF
- CRW
- SRW
- W
- T/G
- U/G
- TF
- on
- C/A
- +65.00
- +65.00

**PROPOSED**

- MH-ST
- MH-S
- MH-T
- VC
- ST
- S
- W
- P
- GA
- B
- TV
- UP
- AN
- LS
- CB
- PH
- WV
- OV
- BM
- TB-B
- TP
- SL
- S
- TEL
- 8
- CLF
- BF
- WF
- CRW
- SRW
- W
- T/G
- U/G
- TF
- on
- C/A
- +65.00
- +65.00

**NOTES:**

1. FOUNDATION DRAIN BACKWATER VALVE REQUIRED ON SERVICE LATERAL PER CITY DETAIL S14.
2. SANITARY BACKWATER VALVE REQUIRED ON SERVICE LATERAL PER CITY DETAIL S14.1.
3. ALL FLOOR DRAINS WITHIN THE UNDERGROUND PARKING MUST BE DIRECTED TO THE SANITARY LATERAL.
4. INTERNAL WATER METER TO BE LOCATED IN WATER ENTRY AND FIRE PUMP ROOM ON LEVEL P1.
5. SEWER LATERALS MUST CROSS THE WATERMAIN WITH A MINIMUM CLEARANCE OF EITHER 0.5m ABOVE THE WATERMAIN OR 0.3 m BELOW THE WATERMAIN. THE CONTRACTOR MUST CONFIRM THE EXACT INVERT (GEODETIC ELEVATION), DIAMETER AND CONSTRUCTION MATERIAL OF THE EXISTING WATERMAIN AT THE PROPOSED CROSSINGS. IN THE EVENT OF A CONFLICT BETWEEN NEW SEWER LATERALS AND THE EXISTING WATERMAIN, A PORTION OF THE WATERMAIN CAN BE RECONSTRUCTED LOCALLY AS PER DETAIL W25.2. HE MUST ALSO CARRY OUT, IF NECESSARY, EXPLORATORY EXCAVATIONS IN ORDER TO DETERMINE THE EXACT LOCATION AND INVERTS OF EXISTING DUCK BANKS. THIS INFORMATION MUST IMMEDIATELY BE PROVIDED TO THE ENGINEER PRIOR TO START UNDERTAKING ANY MUNICIPAL SERVICES WORK AND A 48 HOUR PERIOD MUST BE ALLOCATED TO THE ENGINEER FOR DESIGN REVIEW.
6. EVEN IF NOT SHOWN ON THIS DRAWING, ALL CB AND CB/MH STRUCTURES MUST BE EQUIPPED WITH 150mm SUBDRAINS AS PER DETAIL 305. THE SUBDRAINS MUST EXTEND 3m LONG IN THE TWO OPPOSITE DIRECTIONS OF THE STRUCTURES.

1:250

0 2.5 5 10 15m

No.	Date	Description	By
8	2025/02/11	RE-ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.

STAMPS:

DESIGNED BY: **CIMA+**

APPROVED BY: **BERTONE**

CLIENT: **BERTONE**

PROJECT NAME: **1649 MONTREAL ROAD MONTREAL AND BLAIR**

SHEET TITLE: **SITE SERVICING PLAN**

DISCIPLINE: **CIVIL**

DRAWER: **D. VAGHELA**

DESIGNER: **E. POTVIN**

APPROVER: **C.L. LABEL**

PROJECT No: **A001101**

SHEET No: **6 of 15**

SCALE: **1:250**

DATE: **22/08/31**

CITY APPLICATION No: **D07-12-22-0132**

DRAWING No: **C006**

**NOTE OF CAUTION**

THE GEODETIC COORDINATES OF EVERY ITEM INCLUDED AS PART OF THIS DOCUMENT ARE IN **NAD83 - ORIGINAL / MTM -** REFERENCE SYSTEM AND HAVE NO LEGAL VALUE. THE SITE LAYOUT MUST BE COMPLETED USING THE OFFICIAL BENCHMARKS OF AN ACCREDITED LAND SURVEYOR IN THE **NAD83 - ORIGINAL / MTM -** REFERENCE SYSTEM.

THE UNDERGROUND FEATURES AND INFORMATION THAT APPEAR ON THE DRAWINGS WERE OBTAINED FROM THE PUBLIC UTILITY COMPANIES AND/OR FROM THE CITY EACH RESPECTIVELY.

ALL INFORMATION UNDER THE LEGEND 'EXISTING' IS FOR INFORMATION ONLY. COMPLETE OR EXACT LOCATION AND ELEVATION OF UNDERGROUND SERVICES ARE NOT GUARANTEED.

CERTAIN UNDERGROUND FEATURES ON PRIVATE PROPERTY ARE NOT SHOWN ON THE CURRENT DRAWING.

ANYONE WHO PROCEEDS WITH EXCAVATION WORK SHALL VERIFY THE EXACT LOCATION OF ALL UNDERGROUND FEATURES, BY EXPLORATORY EXCAVATIONS, AND SHALL ASSUME FULL RESPONSIBILITY IF THERE IS ANY DAMAGE THAT OCCURS DURING WORK.

THE CONTRACTOR WILL HAVE THE RESPONSIBILITY AND THE OBLIGATION TO VALIDATE, BY EXPLORATORY EXCAVATION, THE SIZE OF THE PUBLIC UTILITIES UNDERGROUND SERVICES AND TO WARN THE ENGINEER OF ANY CONFLICT WITH THE PROJECTED WORK.



TITLE LOCK 24x38 VERT ENG 3.0  
PRINT DATE: 2025/01/28 (PAPER SIZE: ISO A4 (210.00 x 297.00 MM))  
PATH: Z:\Cine\10101\Projects\A001000-A001699\A001101\_Blar - Mt Road Towers\400460\_Civil\0009\_Sanitary lid.dwg / LAYOUT: C006B



**NOTES:**

1. REPLACE 32 LIDS AND FRAMES OF THE EXISTING SANITARY MAINTENANCE HOLES (REFER TO MHSA WHITE TAGS) WITH WATERTIGHT LIDS AND FRAMES AS PER OPSD 401.030

1:1000

0 10 20 40 60m

No.	Date	Description	By
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.

STAMPS:

DESIGNED BY: **CIMA+** APPROVED BY:

ENGINEER: **BERTONE**

CLIENT:

PROJECT NAME: 1649 MONTREAL ROAD  
MONTREAL AND BLAIR

SHEET TITLE: SANITARY SEWER LID REPLACEMENTS

DISCIPLINE: CIVIL

DRAWN: D. VAGHELA	SCALE: 1:1000
DESIGNER: E. POTVIN	DATE: 22/08/31
APPROVER: C.L. LEBEL	CITY APPLICATION No: D07-12-22-0132
PROJECT No: A001101	DRAWING No: C006B
SHEET No: 7 of 15	

**NOTE OF CAUTION**

THE GEODETIC COORDINATES OF EVERY ITEM INCLUDED AS PART OF THIS DOCUMENT ARE IN NAD83 - ORIGINAL / MTM - REFERENCE SYSTEM AND HAVE NO LEGAL VALUE. THE SITE LAYOUT MUST BE COMPLETED USING THE OFFICIAL BENCHMARKS OF AN ACCREDITED LAND SURVEYOR IN THE NAD83 - ORIGINAL / MTM - REFERENCE SYSTEM.

THE UNDERGROUND FEATURES AND INFORMATION THAT APPEAR ON THE DRAWINGS WERE OBTAINED FROM THE PUBLIC UTILITY COMPANIES AND/OR FROM THE CITY EACH RESPECTIVELY.

ALL INFORMATION UNDER THE LEGEND 'EXISTING' IS FOR INFORMATION ONLY. COMPLETE OR EXACT LOCATION AND ELEVATION OF UNDERGROUND SERVICES ARE NOT GUARANTEED.

CERTAIN UNDERGROUND FEATURES ON PRIVATE PROPERTY ARE NOT SHOWN ON THE CURRENT DRAWING.

ANYONE WHO PROCEEDS WITH EXCAVATION WORK SHALL VERIFY THE EXACT LOCATION OF ALL UNDERGROUND FEATURES, BY EXPLORATORY EXCAVATIONS, AND SHALL ASSUME FULL RESPONSIBILITY IF THERE IS ANY DAMAGE THAT OCCURS DURING WORK.

THE CONTRACTOR WILL HAVE THE RESPONSIBILITY AND THE OBLIGATION TO VALIDATE, BY EXPLORATORY EXCAVATION, THE SIZE OF THE PUBLIC UTILITIES UNDERGROUND SERVICES AND TO WARN THE ENGINEER OF ANY CONFLICT WITH THE PROJECTED WORK.



TITLE LOCK 24x36 VERT ENG 3.0  
PRINT DATE: 2025/02/05 (PAPER SIZE: ISO A4 (210.00 x 297.00 MM))  
PATH: Z:\C:\na\c1\0101\Projects\A\A01000-A00-1699\A01101\_Blar - Mt Road Towers\400460\_Civil\007\_SWM.dwg / LAYOUT C007



STORM WATER MANAGEMENT LEGEND

STORM DRAINAGE BOUNDARY

AREA ID

AREA IN m<sup>2</sup>

RUNOFF COEFFICIENT

**A1**

588 m<sup>2</sup>

100-YR= 0.95  
5-YR= 0.50

Sub-Area	Total Area (m <sup>2</sup> )	Available Storage Area (m <sup>2</sup> )	Catchbasin/ Roof Drain Elevation (m)	Maximum Ponding Elevation (m)	Y <sub>max</sub> (m)	V <sub>max</sub> (m <sup>3</sup> )	V <sub>sub</sub> (m <sup>3</sup> )	V <sub>ret</sub> (m <sup>3</sup> )	Y <sub>sub</sub> (m)	Elev <sub>sub</sub> (m)	A <sub>sub</sub> (m <sup>2</sup> )	Q (L/s)	Cistern Release Rate (L/s)	Drawdown Time (min)	Comments
A1	2310	Refer to note 1	-	-	-	55.0	12.7	12.9	-	-	-	43.9	-	-	Building Roof + Cistern
A2.a	245	8	98.25	98.30	0.05	0.1	0.4	0.1	-	-	-	4.1	51.4	-	Back East
A2.b	1348	Refer to note 2	97.65	98.00	0.35	33.0	33.0	33.0	-	-	-	0.4	-	-	Back West
A3.a	475	Refer to note 3	97.65	98.00	0.35	17.5	17.5	17.5	-	-	-	0.2	-	-	Front (Entrance)
A3.b	172	45	97.48	97.57	0.09	1.3	1.1	1.1	-	-	-	2.8	-	-	Front (POPS)
A4	332	0	-	-	-	0.0	0.0	0.0	-	-	-	8.7	-	-	Area between Building & Montreal Rd (unattenuated)
Total	4882					107.0	64.7	64.7				60.1	51.4		

**NOTES:**

- 12.9 m<sup>3</sup> are retained inside building Cistern (max 55m<sup>3</sup>). No water retained on rooftop.
- 33 m<sup>3</sup> are retained in the north raingarden.
- 17.5 m<sup>3</sup> are retained in the south raingarden.

Sub-Area	Total Area (m <sup>2</sup> )	Available Storage Area (m <sup>2</sup> )	Catchbasin/ Roof Drain Elevation (m)	Maximum Ponding Elevation (m)	Y <sub>max</sub> (m)	V <sub>max</sub> (m <sup>3</sup> )	V <sub>sub</sub> (m <sup>3</sup> )	V <sub>ret</sub> (m <sup>3</sup> )	Y <sub>sub</sub> (m)	Elev <sub>sub</sub> (m)	A <sub>sub</sub> (m <sup>2</sup> )	Q (L/s)	Cistern Release Rate (L/s)	Drawdown Time (min)	Comments
A1	2310	Refer to note 1	-	-	-	55.0	44.0	47.4	-	-	-	38.3	-	-	Building Roof + Cistern
A2.a	245	8	98.25	98.30	0.05	0.1	1.6	0.1	-	-	-	4.1	51.4	-	Back East
A2.b	1348	Refer to note 2	97.65	98.00	0.35	33.0	33.0	33.0	-	-	-	4.1	-	-	Back West
A3.a	475	Refer to note 3	97.65	98.00	0.35	17.5	17.5	17.5	-	-	-	2.2	-	-	Front (Entrance)
A3.b	172	45	97.48	97.57	0.09	1.3	3.3	1.3	-	-	-	2.8	-	-	Front (POPS)
A4	332	0	-	-	-	0.0	0.0	0.0	-	-	-	15.0	-	-	Area between Building & Montreal Rd (unattenuated)
Total	4882					107.0	99.4	99.4				66.4	51.4		

**NOTES:**

- 47.4 m<sup>3</sup> are retained inside building Cistern (max 55m<sup>3</sup>). No water retained on rooftop.
- 33 m<sup>3</sup> are retained in the north raingarden.
- 17.5 m<sup>3</sup> are retained in the south raingarden.

**DEFINITIONS OF ABBREVIATIONS USED IN CALCULATION TABLE:**

NC = Area is not controlled (unattenuated)  
Available Area = Area of water accumulated in sub-area at Max. Elev.  
Catchbasin Elev. = Elevation of catchbasin inlet (top of grate).  
Max. Elev. = Maximum elevation of water that may be accumulated within sub-area.  
Y<sub>max</sub> = Maximum depth of water that may be accumulated within the sub-area.  
V<sub>max</sub> = Maximum volume of water (capacity) that may be accumulated within the sub-area.  
V<sub>sub</sub> = Volume of water generated by rainfall.  
V<sub>ret</sub> = Total volume of water accumulated within the sub-area in the event of a specific rainfall.  
Y<sub>sub</sub> = Depth of water generated by rainfall.  
Elev<sub>sub</sub> = Elevation of water generated by rainfall.  
A<sub>sub</sub> = Area of water generated by rainfall.  
Q = Release flow rate.  
Tank Release Rate = Release rate from the underground storage tank equal to 1/2 the allowable release rate.  
Drawdown Time = Time required for the total volume of water accumulated within sub-area to subside.

**NOTE OF CAUTION**

THE GEODETIC COORDINATES OF EVERY ITEM INCLUDED AS PART OF THIS DOCUMENT ARE IN NAD83 - ORIGINAL / MTM - REFERENCE SYSTEM AND HAVE NO LEGAL VALUE. THE SITE LAYOUT MUST BE COMPLETED USING THE OFFICIAL BENCHMARKS OF AN ACCREDITED LAND SURVEYOR IN THE NAD83 - ORIGINAL / MTM - REFERENCE SYSTEM.

THE UNDERGROUND FEATURES AND INFORMATION THAT APPEAR ON THE DRAWINGS WERE OBTAINED FROM THE PUBLIC UTILITY COMPANIES AND/OR FROM THE CITY EACH RESPECTIVELY.

ALL INFORMATION UNDER THE LEGEND 'EXISTING' IS FOR INFORMATION ONLY. COMPLETE OR EXACT LOCATION AND ELEVATION OF UNDERGROUND SERVICES ARE NOT GUARANTEED.

CERTAIN UNDERGROUND FEATURES ON PRIVATE PROPERTY ARE NOT SHOWN ON THE CURRENT DRAWING.

ANYONE WHO PROCEEDS WITH EXCAVATION WORK SHALL VERIFY THE EXACT LOCATION OF ALL UNDERGROUND FEATURES, BY EXPLORATORY EXCAVATIONS, AND SHALL ASSUME FULL RESPONSIBILITY IF THERE IS ANY DAMAGE THAT OCCURS DURING WORK.

THE CONTRACTOR WILL HAVE THE RESPONSIBILITY AND THE OBLIGATION TO VALIDATE, BY EXPLORATORY EXCAVATION, THE SIZE OF THE PUBLIC UTILITIES UNDERGROUND SERVICES AND TO WARN THE ENGINEER OF ANY CONFLICT WITH THE PROJECTED WORK.

**EXISTING**

- MH-ST
- MH-S
- MH-T
- VC
- ST
- S
- W
- P
- GAS
- B
- TV
- SW
- LP
- AN
- LS
- CB
- FH
- WV
- GV
- DM
- TB
- TL
- SL
- S
- TEL
- CLP
- BF
- WP
- CRW
- SRW
- Inv
- T/G
- U/Eave
- Tf/en
- C

**PROPOSED**

- MH-ST
- MH-S
- MH-T
- VC
- ST
- S
- W
- P
- GAS
- B
- TV
- SW
- LP
- AN
- LS
- CB
- FH
- WV
- GV
- DM
- TB
- TL
- SL
- S
- TEL
- CLP
- BF
- WP
- CRW
- SRW
- Inv
- T/G
- U/Eave
- Tf/en
- C

**STANDARD**

- Maintenance Hole (Storm)
- Maintenance Hole (Sanitary)
- Maintenance Hole (Traffic)
- Valve Chamber (Watermain)
- Underground Storm Sewer
- Underground Sanitary Sewer
- Underground Water
- Underground Power
- Underground Gas
- Underground Bell
- Underground Cable
- Overhead Wires
- Utility Pole
- Anchor
- Light Standard
- Catch Basin
- Fire Hydrant
- Water Valve
- Gas Valve
- Gas Meter
- Ball Terminal Box
- Traffic Signal Post
- Traffic Light
- Bollard
- Sign
- Gate
- Telephone Booth
- Diameter
- Chain Link Fence
- Board Fence
- Metal Fence
- Concrete Retaining Wall
- Stone Retaining Wall
- Invert
- Top of Grate
- Underside of Eave
- Top of Foundation
- Centreline
- Location of Elevations
- Top of Concrete Curb/Retaining Wall Elevation
- Drainage Direction
- Property Line
- Easement
- Curb/Retaining Wall
- Shrub
- Deciduous Tree
- Coniferous Tree
- Work Limit
- Borehole (Loc. Approx.)
- Bioswale Surface Storm Water Treatment Pond
- Remote Water Metering Reading Device
- Fire Department (Siamese) Connection

1:250

0 2.5 5 10 15m

No.	Date	Description	By
1	2025/02/11	RE-ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.

**STAMPS:**

DESIGNED BY: **CIMA+**

APPROVED BY: **BERTONE**

PROJECT NAME: **1649 MONTREAL ROAD MONTREAL AND BLAIR**

SHEET TITLE: **STORM WATER MANAGEMENT PLAN**

DISCIPLINE: **CIVIL**

DRAWER: **D. VAGHELA**

DESIGNER: **E. POTVIN**

APPROVER: **C.L. LABEL**

PROJECT No: **A001101**

SHEET No: **8 of 15**

SCALE: **1:250**

DATE: **22/08/31**


CITY APPLICATION No: **D07-12-22-0132**

DRAWING No: **C007**



TITLE LOCK 24x38 VERT ENG 3.0


PRINT DATE: 2025/01/28 / PAPER SIZE: ISO A4 (210.00 x 297.00 MM)  
PATH: Z:\Cma-C\101\01\Projects\A\A001000-A001699\A001101\_Blar - Mt Road Towers\400460\_Civil\0008@\_13\_Details.dwg / LAYOUT: C008



COMPLETELY DEPRESSED CONCRETE CURB  
(NOT LOCATED OVER UNDERGROUND PARKING)

AUCUNE / NTS


113B



TYPICAL SECTION - GRANULAR FOUNDATION  
AND ASPHALT PAVEMENT (HEAVY DUTY CIRCULATION  
OUTSIDE OF UNDERGROUND PARKING AREA)

AUCUNE / NTS


202



TYPICAL SECTION - GRANULAR FOUNDATION  
AND ASPHALT PAVEMENT (HEAVY DUTY CIRCULATION  
ABOVE UNDERGROUND PARKING AREA)

AUCUNE / NTS

203




- NOTES:
- CONCRETE CLASS: C-2;
  - WATER/BINDER MAX. RATIO: 0.45;
  - MINIMUM 28-DAY COMPRESSION RESISTANCE: 32 MPa;
  - GRANULAR MAXIMUM NOMINAL Ø: 20mm;
  - AIR CONTENT: 5% TO 8%;
  - SLUMP: 80mm ± 30mm FOR FIXED FORMWORK;  
30mm ± 30mm FOR SLIDING FORMWORK;
  - DUMMY JOINTS SHALL BE 25mm DEEP, FRONT, BACK AND TOP OF SECTION AT 4m SPACING OR MATCH JOINTING WHERE SIDEWALK IS ADJACENT.

CONCRETE CURB (LOCATED  
OVER UNDERGROUND PARKING)

AUCUNE / NTS


112B



CONCRETE PAVERS STRUCTURE  
(LOCATED ABOVE UNDERGROUND PARKING)

AUCUNE / NTS


217C



CONCRETE PAVERS STRUCTURE  
(OUTSIDE OF UNDERGROUND PARKING)

AUCUNE / NTS


217D



SWALE IN LANDSCAPED AREA (TYPICAL)

NTS

333




- NOTES:
- 1 SOIL TYPES AS DEFINED IN THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJETS.
  - 2 ALL DIMENSIONS ARE IN MILLIMETRES.

HDPE MANHOLE - PREFABRICATED (OFF-ROAD)

AUCUNE / NTS

304B



NOTES  
THE STONE DIAPHRAGM MUST BE LARGER  
BY 300mm ON EITHER SIDE OF THE DEPRESSED  
CURBS.

\*PLANTATION SOILS COMPOSITION:  
SAND: 85-88%  
FINES: 8-12%  
ORGANICS: 3-5%

RAIN GARDEN CROSS (R.G.) SECTION

NTS

333A

No.	Date	Description	By
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.

DESIGNED BY	APPROVED BY

ENGINEER:	


CLIENT:	

PROJECT NAME:	1649 MONTREAL ROAD MONTREAL AND BLAIR
---------------	--

SHEET TITLE:	DETAILS PLAN
--------------	--------------

DISCIPLINE:	CIVIL
DRAWER:	D. VAGHELA
DESIGNER:	E. POTVIN
APPROVER:	C.L. LEBEL
PROJECT No:	A001101
SHEET No:	9 of 15
SCALE:	
DATE:	22/08/31
CITY APPLICATION No:	D07-12-22-0132
DRAWING No:	C008





CONCRETE BARRIER CURB


NOTES:

1. THE FULL CURB DEPTH SHALL BE CARRIED THROUGH THE DEPRESSED ACCESS CROSSING
2. A CONCRETE SUPPORT IS REQUIRED WHEN BUILT ADJACENT TO THE SIDEWALK
3. IF AN EXTRUSION CURBING MACHINE IS USED, THE EXPANSION BITUMINOUS MATERIAL AND THE #15 DOWELS ARE TO BE PLACED AT THE END OF THE EXTRUSION
4. ALL MEASUREMENTS ARE IN MILLIMETRES UNLESS OTHERWISE NOTED
5. EXPANSION AND DUMMY JOINTS AS PER SC5
6. FOR DEPRESSED CURB AT ENTRANCES USE 250
7. DEPRESSED CURB HEIGHT - FOR PEDESTRIAN CURB RAMPS 0 TO 6mm AND FOR PRIVATE ENTRANCES 0 TO 13mm




TITLE: CONCRETE BARRIER CURB FOR GRANULAR BASE PAVEMENT (MODIFIED OPSD-600.110)

DATE: JAN 2003  
REV: FEB 2025  
DWG No: SC1.1



TYPICAL SIDEWALK SECTION



EXPANSION JOINT PROFILE

DUMMY JOINT PROFILE


NOTES:

1. ALL MEASUREMENTS ARE IN MILLIMETRES UNLESS OTHERWISE NOTED
2. THE MAXIMUM SLOPE IS NOT TO EXCEED 2%
3. FOR CURB RAMPS, SLOPE OF 2% TO 5%, MAXIMUM 8%
4. EXPANSION AND DUMMY JOINTS AS PER SC5
5. DEPRESSED CURB HEIGHT - FOR PEDESTRIAN CURB RAMPS 0 TO 6 mm AND FOR PRIVATE ENTRANCES 0 TO 13mm




TITLE: MONOLITHIC CONCRETE CURB AND SIDEWALK


DATE: MAY 2001  
REV: FEB 2025  
DWG No: SC2



PLAN: SIDEWALK 2.5m WIDE AND OVER



PLAN: SIDEWALK LESS THAN 2.5m WIDE




NOTES:

1. FOR CURBS THE EXPANSION JOINTS SHALL BE SPACED 4M APART OR COINCIDE WITH THE JOINTS IN THE ADJOINING SIDEWALK
2. TRANSVERSE EXPANSION JOINTS ARE REQUIRED AT THE ENDS, THE MIDPOINT, AT INTERVALS OF 4m MAXIMUM, AND ALSO TO ISOLATE OBSTRUCTIONS FROM SIDEWALK, HYDRANTS, POLES, BUILDINGS, ETC
3. EDGES ARE TO BE FINISHED WITH A 75mm EDGING TOOL
4. ALL CONCRETE SIDEWALKS ARE TO HAVE A BROOM FINISH UNLESS OTHERWISE SPECIFIED
5. ALL MEASUREMENTS ARE IN MILLIMETRES UNLESS OTHERWISE NOTED
6. INSTALL TRANSVERSE JOINTS AS REQUIRED SO THERE IS A MAXIMUM SPACING OF 2m BETWEEN ALL JOINTS
7. CONTRACTION JOINTS ARE TO BE SAWCUTTING WITH A GREEN SAW OR BY HANDTOOLING
8. JOINTS SHALL BE CONSTRUCTED TRANSVERSELY ACROSS THE SIDEWALK PERPENDICULAR TO THE FACE OF CURB FOR SIDEWALK
9. WHEN JOINTS ARE CONSTRUCTED ADJACENT TO TWSIS, THE JOINTS SHALL EXTEND FROM THE BACK CORNERS OF THE OUTSIDE TWSI PLATES TO THE BACK OF SIDEWALK, OR TERMINATE AT AN ADJACENT JOINT
10. THE TERMINATION OF THE JOINTS AT BOTH THE FRONT AND BACK OF SIDEWALK SHALL BE NO LESS THAN 600mm APART
11. JOINTS IN ALL CONCRETE ELEMENTS SHALL BE LAID OUT TO ENSURE THAT NO INDIVIDUAL RESULTING CONCRETE PANEL IS LESS THAN 0.5m<sup>2</sup> OR GREATER THAN 6m<sup>2</sup>




TITLE: SIDEWALK CONSTRUCTION JOINTS

DATE: MAY 2001  
REV: FEB 2025  
DWG No: SC5



MID BLOCK CROSSING AND PARALLEL CURB RAMPS




NOTES:

1. DOUBLE RAMP WIDTH SHOULD MATCH SIDEWALK WIDTH, BE A MINIMUM OF 3.3m WIDE AND PERMIT WHEELCHAIRS TO ENTER CROSSING AT RIGHT ANGLES
2. APPROVED 610 x WIDTH OF CURB RAMP (1500 MIN.) TACTILE WALKING SURFACE INDICATOR, RADIUS TO MATCH CURB
3. 150 TO 200 GAP
4. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE
5. FOR TRANSITIONARE, MAXIMUM SLOPE OF 2%
6. DEPRESSED CURB HEIGHT SHALL BE 0 TO 6mm FOR PEDESTRIAN CURB RAMPS AND 0 TO 25mm FOR PRIVATE ENTRANCES, OR EQUAL HEIGHT OF CROSSWALK WHERE APPLICABLE
7. FOR CURB RAMPS, SLOPE OF 2% TO 5% MAXIMUM 8%
8. REFER TO R15 AND R15.1 FOR RAISED CROSSWALK AND R15.2 FOR AT - GRADE CONCRETE CROSSWALK, SUBJECT TO AVOIDANCE OF MEDIANS, CROSSWALK LINES TO CENTRED ON THE CURB RAMP
9. FOR RAMP APPLICATIONS ONLY
10. FOR MONOLITHIC SIDEWALK, TWSI SHALL BE 300 TO 350mm BACK FROM CURB FACE



TITLE: PEDESTRIAN CURB RAMP WITHOUT BOULEVARD

DATE: MAY 2001  
REV: MARCH 2022  
DWG No: SC6




NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.
2. CURB DETAILS SEE SC1.1, SC1.2 AND SC1.3
3. SIDEWALK DETAILS SEE SC2 AND SC3
4. MAXIMUM SLOPE VARIES, SEE PRIVATE APPROACH BYLAW.
5. UNCONTROLLED INTERSECTION MEANS AN ENTRANCE NOT LOCATED AT A TRAFFIC SIGNAL OR ALL-WAY STOP CONTROL.




TITLE: CURB RETURN ENTRANCES - UNCONTROLLED INTERSECTIONS

DATE: MARCH 2007  
REV: MARCH 2021  
DWG No: SC7.1



TWSI DETAIL




NOTES:

1. TOPS OF TWSIS (TACTILE WALKING SURFACE INDICATOR) SHALL BE ALIGNED & LEVEL WITH THE ADJACENT CONCRETE SURFACE & INSTALLATION IN WET CONCRETE SHALL BE EFFECTIVE IN PERMANENTLY SECURING THE TWSI IN PLACE ONCE DRY
2. FOR MONOLITHIC SIDEWALKS, TWSI SHALL BE 300 TO 350mm BACK FROM THE CURB FACE
3. JOINTS SHALL BE CONSTRUCTED TRANSVERSELY ACROSS THE SIDEWALK, PERPENDICULAR TO THE FACE OF CURB FOR SIDEWALK
4. WHEN JOINTS ARE CONSTRUCTED ADJACENT TO TWSIS, THE JOINTS SHALL EXTEND FROM THE BACK CORNERS OF THE OUTSIDE TWSI PLATES TO THE BACK OF SIDEWALK, OR TERMINATE AT AN ADJACENT JOINT
5. THE TERMINATION OF THE JOINTS AT BOTH THE FRONT AND BACK OF SIDEWALK SHALL BE NO LESS THAN 600mm APART
6. JOINTS IN ALL CONCRETE ELEMENTS SHALL BE LAID OUT TO ENSURE THAT NO INDIVIDUAL RESULTING CONCRETE PANEL IS LESS THAN 0.5m<sup>2</sup> OR GREATER THAN 6m<sup>2</sup>



TITLE: TWSI DETAIL

DATE: MAR 2015  
REV: FEB 2025  
DWG No: SC7.3




NOTES:

1. BACKWATER VALVE, CLEAN-OUTS AND ANY OTHER FITTINGS MUST BE INSTALLED A MINIMUM OF 300mm INSIDE OF THE BASEMENT FOOTING. THIS IS TO ENSURE THERE IS SUFFICIENT ROOM TO REPLACE THESE COMPONENTS IN THE FUTURE WITHOUT HAVING TO DAMAGE THE FOOTINGWALL DURING THE PROCESS
2. JOINTS BETWEEN THE SLEEVE AND THE BACKWATER VALVE AND THE FLOOR SHALL BE WATERTIGHT.



TITLE: SUPPORT DETAIL FOR EXISTING UTILITY CROSSING SEWER OR WATERMAIN TRENCH

DATE: MAY 2001  
REV: NONE  
DWG No: S10



NOTES:

1. BACKWATER VALVE, CLEAN-OUTS AND ANY OTHER FITTINGS MUST BE INSTALLED A MINIMUM OF 300mm INSIDE OF THE BASEMENT FOOTING. THIS IS TO ENSURE THERE IS SUFFICIENT ROOM TO REPLACE THESE COMPONENTS IN THE FUTURE WITHOUT HAVING TO DAMAGE THE FOOTINGWALL DURING THE PROCESS
2. JOINTS BETWEEN THE SLEEVE AND THE BACKWATER VALVE AND THE FLOOR SHALL BE WATERTIGHT.



TITLE: FOUNDATION DRAIN BACKWATER VALVE INSTALLATION

DATE: DEC 2002  
REV: MARCH 2011  
DWG No: S14

No.	Date	Description	By
8	2025/02/11	RE-ISSUED FOR SITE PLAN CONTROL REV.6	E.P.
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.

No.	Date	Description	By
8	2025/02/11	RE-ISSUED FOR SITE PLAN CONTROL REV.6	E.P.
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.

No.	Date	Description	By
8	2025/02/11	RE-ISSUED FOR SITE PLAN CONTROL REV.6	E.P.
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.








No.	Date	Description	By
8	2025/02/11	RE-ISSUED FOR SITE PLAN CONTROL REV.6	E.P.
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.

No.	Date	Description	By
8	2025/02/11	RE-ISSUED FOR SITE PLAN CONTROL REV.6	E.P.
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.

No.	Date	Description	By
8	2025/02/11	RE-ISSUED FOR SITE PLAN CONTROL REV.6	E.P.
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.

No.	Date	Description	By
8	2025/02/11	RE-ISSUED FOR SITE PLAN CONTROL REV.6	E.P.
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.






8	2025/02/11	RE-ISSUED FOR SITE PLAN CONTROL REV.6	E.P.
7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.
No.	Date	Description	By
STAMPS:			
<div><div>DESIGNED BY</div><div>APPROVED BY</div><div><div><div><div></div><div>J.M.E. POTVIN</div><div>100208490</div><div>FEBRUARY 11, 2025</div></div><div>PROVINCE OF ONTARIO</div></div></div></div>			
ENGINEER:			
CLIENT:			
PROJECT NAME:			
1649 MONTREAL ROAD MONTREAL AND BLAIR			
SHEET TITLE:			
DETAILS PLAN			
DISCIPLINE:			
CIVIL			
DRAFTER: D. VAGHELA		SCALE:	
DESIGNER: E. POTVIN		DATE: 22/08/31	
APPROVER: C.L. LEBEL		CITY APPLICATION No: D07-12-22-0132	
PROJECT No: A001101		DRAWING No:	
SHEET No:		C010	
11 of 15			










- NOTES:
- PIPE EMBEDMENT MATERIAL - GRANULAR 'A'.
  - FINAL BACKFILL - APPROVED NATIVE MATERIAL OR SELECT SUBGRADE IN ACCORDANCE WITH F-2120
  - ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.
  - TABLE
- | PIPE OUTSIDE DIA. | CLEARANCE (mm) |
|-------------------|----------------|
| 900 OR LESS       | 450            |
| OVER 900          | 500            |
5. WHEN APPROVED BY THE CONTRACT ADMINISTRATOR, POOR SOILS SHALL BE EXCAVATED TO CREATE A FOUNDATION THAT SHALL BE FILLED TO THE BEDDING WITH GRANULAR 'B'.

STANDARD TRENCH DETAIL


DATE: MAY 2001  
REV. DATE: MARCH 2016  
DWG. No.: W17



- NOTES
- FOR VALVES ON 300mm (NOMINAL) WATERMANS:
- CLEARANCE AROUND PIPE AT CHAMBER WALL TO BE 50mm MINIMUM.
  - VALVE CHAMBERS IN LIEU OF BOXES ON WATERMANS SMALLER THAN 300mm ONLY TO BE USED, IF APPROVED BY THE CONTRACT ADMINISTRATOR.
  - REFER TO MW-15.1 FOR ADDITIONAL REQUIREMENTS.
  - REFER TO MW-15.15 FOR APPROVED MANUFACTURERS.
  - ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.
  - CATHODIC PROTECTION MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH W08, W40 AND W42.
  - TRACER WIRE REQUIRED FOR PVC, PEK AND HDPE WATERMAIN PIPE ONLY AS PER W08. TRACER WIRE TO BE CONNECTED TO VALVE BOLT AS PER W08 AND SECURED TO TOP OF CHAMBER.

CIRCULAR CHAMBER GATE VALVES


DATE: MAY 2001  
REV. DATE: MARCH 2001  
DWG. No.: W0



- NOTES
- REFER TO DETAILS W2, W3, W5.
- REFER TO MW-13.1 FOR ADDITIONAL REQUIREMENTS.
  - REFER TO MW-19.15 FOR APPROVED MANUFACTURERS.
  - ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.

CIRCULAR CHAMBER SECTION


DATE: MAY 2001  
REV. DATE: NONE  
DWG. No.: W6



- NOTES
- REFER TO DETAIL W3, GATE VALVES.
- REFER TO WSM-6 FOR ADDITIONAL REQUIREMENTS.
  - REFER TO WSM-15 FOR APPROVED MANUFACTURERS.
  - ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.

PRECAST TOP FOR GATE VALVE CHAMBERS


DATE: MAY 2001  
REV. DATE: NONE  
DWG. No.: W8



- NOTES:
- FOR ALL VALVE CHAMBERS:
- REFER TO MW-15.1 FOR ADDITIONAL REQUIREMENTS.
  - REFER TO MW-19.15 FOR APPROVED MANUFACTURERS.
  - ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.

ADJUSTMENT SECTION


DATE: MAY 2001  
REV. DATE: NONE  
DWG. No.: W9



- NOTES
- FOR ALL VALVE CHAMBERS:
- MATERIAL - GREY IRON.
  - FOR VALVE CHAMBER COVER SEE DETAIL W15.
  - FOR FRAME DETAILS SEE DETAIL W16.
  - TOLERANCES ± 1.5mm.
  - ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.

STANDARD COVER FOR VALVE CHAMBERS


DATE: MAY 2001  
REV. DATE: MARCH 2019  
DWG. No.: W15



- NOTES
- FOR ALL VALVE CHAMBERS:
- MATERIAL - GREY IRON.
  - FOR VALVE CHAMBER COVER SEE DETAIL W15.
  - TOLERANCES ± 1.5mm.
  - ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.
  - NON-STANDARD FRAMES WITH CENTERING TABS MAY ALSO BE USED FOR VALVE CHAMBERS.
  - OPSD 400.001 HOISTING HOOKS ALSO ACCEPTED.

STANDARD FRAME FOR VALVE CHAMBERS (MODIFIED OPSD-401.020)

DATE: MAY 2001  
REV. DATE: MARCH 2016  
DWG. No.: W16





- NOTES:
- FOR CROSSING WITH A CLEARANCE LESS THAN 1m:
- CONCRETE ENCASED STEEL MANS SHALL BE SUPPORTED WITH CONCRETE TO UNDERSIDE OF MAIN.
  - ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.

SUPPORT DETAIL FOR CROSSING BELOW AN EXISTING WATERMAIN

DATE: MAY 2001  
REV. DATE: NONE  
DWG. No.: W29

7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.
No.	Date	Description	By
STAMPS:			
<div></div>			
DESIGNED BY		APPROVED BY	
ENGINEER:			
<div></div>			
CLIENT:			
<div></div>			
PROJECT NAME:			
1649 MONTREAL ROAD MONTREAL AND BLAIR			
SHEET TITLE:			
DETAILS PLAN			
DISCIPLINE:			
CIVIL			
DRAFTER: D VAGHELA		SCALE:	
DESIGNER: E. POTVIN		DATE: 22/08/31	
APPROVER: C.L. LEBEL		CITY APPLICATION No: D07-12-22-0132	
PROJECT No: A001101		DRAWING No:	
SHEET No:		C012	
13 of 15			






### THERMAL INSULATION FOR SEWER PIPES IN SHALLOW TRENCHES


NTS

500




### WATERMAIN CROSSING OVER SEWER

DATE: MAY 2001  
REV. DATE: MARCH 2013  
DWG. No.: W25.2




### VALVE BOX ASSEMBLY

DATE: MAY 2001  
REV. DATE: MARCH 2013  
DWG. No.: W24




### CONCRETE THRUST BLOCKS FOR PVC AND DI PIPE 400mm AND UNDER

DATE: MAY 2001  
REV. DATE: MARCH 2013  
DWG. No.: W25.3




### THRUST BLOCK DIMENSION TABLES FOR PVC AND DI PIPE 400mm AND UNDER



### RESTRAINING AND RETAINING RINGS FOR PVC AND DI PIPE 400mm AND UNDER

DATE: MAY 2001  
REV. DATE: MARCH 2013  
DWG. No.: W25.5



### TABLES OF RESTRAINED LENGTHS FOR PVC AND DI PIPE 400mm AND UNDER

DATE: MAY 2001  
REV. DATE: MARCH 2013  
DWG. No.: W25.6

7	2025/01/28	ISSUED FOR SITE PLAN CONTROL REV. 6	E.P.
6	2024/12/13	ISSUED FOR SITE PLAN CONTROL REV. 5	E.P.
5	2024/10/25	ISSUED FOR SITE PLAN CONTROL REV. 4	E.P.
4	2023/08/25	ISSUED FOR SITE PLAN CONTROL REV. 3	E.P.
3	2023/07/28	ISSUED FOR SITE PLAN CONTROL REV. 2	E.P.
2	2023/03/17	ISSUED FOR SITE PLAN CONTROL REV. 1	E.P.
1	2022/08/12	ISSUED FOR SITE PLAN CONTROL	E.P.
No.	Date	Description	By
STAMPS:			
DESIGNED BY: APPROVED BY:			
ENGINEER:			
CLIENT:			
PROJECT NAME:			
1649 MONTREAL ROAD MONTREAL AND BLAIR			
SHEET TITLE:			
DETAILS PLAN			
DISCIPLINE:			
CIVIL			
DRAFTER:		SCALE:	
D. VAGHELA			
DESIGNER:		DATE:	
E. POTVIN		22/08/31	
APPROVER:		CITY APPLICATION No.:	
C.L. LEBEL		D07-12-22-0132	
PROJECT No.:		DRAWING No.:	
A001101			
SHEET No.:		C013	
14 of 15			



