

Geotechnical Investigation

Proposed Multi-Storey Building

1649 Montreal Road and 741 Blair Road
Ottawa, Ontario

Prepared for 10869279 Canada Inc.

Report PG5663-1 Revision 4 dated October 9, 2024




Table of Contents

	PAGE
1.0 Introduction	1
2.0 Proposed Development	1
3.0 Method of Investigation	2
3.1 Field Investigation	2
3.2 Field Survey	3
3.3 Laboratory Testing	3
4.0 Observations	4
4.1 Surface Conditions	4
4.2 Subsurface Profile	4
4.3 Groundwater	5
5.0 Discussion	6
5.1 Geotechnical Assessment	6
5.2 Site Grading and Preparation	6
5.2.1 Vibration Monitoring and Control Plan	8
5.3 Foundation Design	10
5.4 Design for Earthquakes	12
5.5 Basement Slab	13
5.6 Basement Wall	14
5.7 Rock Anchor Design	15
5.8 Pavement Structure	18
6.0 Design and Construction Precautions	20
6.1 Foundation Drainage and Backfill	20
6.2 Protection Against Frost Action	21
6.3 Excavation Side Slopes	21
6.4 Pipe Bedding and Backfill	23
6.5 Groundwater Control	23
6.6 Winter Construction	25
7.0 Recommendations	26
8.0 Statement of Limitations	27

Appendices

- Appendix 1** Soil Profile and Test Data Sheets
 Symbols and Terms
 Photographs of Rock Core
- Appendix 2** Figure 1 - Key Plan
 Figures 2 & 3 – Seismic Shear Wave Velocity Profiles
 Drawing PG5663-1 – Test Hole Location Plan
 Drawing PG5663-1 – Bedrock Quality Zone Plan

1.0 Introduction

Paterson Group (Paterson) was commissioned by 10869279 Canada Inc. to conduct a geotechnical investigation for the proposed high-rise building to be located at 1649 Montreal Road and 741 Blair Road, in the City of Ottawa (refer to Figure 1 - Key Plan presented in Appendix 2).

The objective of the investigation was to:

- ❑ determine the subsoil and groundwater conditions at this site by means of test holes.
- ❑ provide geotechnical recommendations for the design of the proposed development including construction considerations which may affect the design.

The following report has been prepared specifically and solely for the aforementioned project which is described herein. The report contains our findings and includes geotechnical recommendations pertaining to the design and construction of the proposed development as understood at the time of this report.

Investigating the presence or potential presence of contamination on the proposed development was not part of the scope of work.

2.0 Proposed Development

It is understood based on available information that the proposed development will consist of a twenty-six storey building constructed over an underground parking structure with 3 levels, occupying the majority of the subject site. Associated access lanes and landscaped areas are also anticipated for the proposed development. It is further understood that the proposed development will be municipally serviced.

3.0 Method of Investigation

3.1 Field Investigation

Field Program

The field program for the current geotechnical investigation was conducted from April 11 to 20, 2023, and consisted of five (5) boreholes advanced to a maximum depth of 21.2 m below the existing ground surface. Furthermore, a previous investigation was carried out on October 15 and 16, 2020. At that time, seven (7) boreholes were completed across the subject site extending to a maximum depth of 6.5 m below the ground surface. The test hole locations were placed in a manner to provide general coverage of the subject site. The test hole locations are illustrated on Drawing PG5663-1 - Test Hole Location Plan presented in Appendix 2.

The boreholes were completed using a low-clearance auger drill rig operated by a two-person crew. All fieldwork was conducted under the full-time supervision of Paterson personnel under the direction of a senior engineer from the geotechnical division. The testing procedure consisted of augering to the required depths at the selected locations and sampling the overburden.

Sampling and In Situ Testing

Soil samples were collected from the boreholes using two different techniques, namely, sampled directly from the auger flights (AU) or collected using a 50 mm diameter split spoon (SS) sampler. The bedrock was cored to assess the bedrock quality. All samples were visually inspected and initially classified on site. The auger and split-spoon samples were placed in sealed plastic bags, and rock cores (RC) were placed in cardboard boxes. All samples were transported to our laboratory for further examination and classification. The depths at which the auger, split spoon and rock core samples were recovered from the boreholes are shown as AU, SS and RC, respectively, on the Soil Profile and Test Data sheets presented in Appendix 1. Photographs of the rock core are presented in Appendix 1.

The Standard Penetration Tests (SPT) were conducted in conjunction with the recovery of the split-spoon samples. The SPT results are recorded as “N” values on the Soil Profile and Test Data sheets. The “N” value is the number of blows required to drive the split-spoon sampler 300 mm into the soil after a 150 mm initial penetration using a 63.5 kg hammer falling from a height of 760 mm.

The subsurface conditions observed at the test hole locations were recorded in detail in the field. The soil profiles are presented on the Soil Profile and Test Data sheets in Appendix 1 of this report.

Groundwater

Monitoring wells were installed at eight (8) borehole locations during the 2020 and 2023 investigations to permit monitoring of the groundwater levels subsequent to the completion of the sampling programs. The groundwater level readings were obtained after suitable stabilization periods subsequent to the completion of the field investigations.

Monitoring Well Installation

Typical monitoring well construction details are described below:

- 3.0 m of slotted 51 mm diameter PVC screen at base the base of the boreholes.
- 51 mm diameter PVC riser pipe from the top of the screen to the ground surface.
- No.3 silica sand backfill within annular space around screen.
- 300 mm thick bentonite hole plug directly above PVC slotted screen.
- Clean backfill from top of bentonite plug to the ground surface.

Refer to the Soil Profile and Test Data sheets in Appendix 1 for specific well construction details.

3.2 Field Survey

The test holes were located in the field by Paterson personnel using a GPS unit, and the ground surface elevation at the test hole locations from the current investigation were referenced to a geodetic datum. The ground surface elevation and location of the test holes are presented on Drawing PG5663-1 - Test Hole Location Plan in Appendix 2.

3.3 Laboratory Testing

The soil samples recovered from the field investigation were examined in our laboratory to review field notes and soil samples. All samples will be stored in the laboratory for a period of one month after issuance of the report. They will then be discarded unless we are otherwise directed.

4.0 Observations

4.1 Surface Conditions

At the present time, an automotive repair shop and an associated parking lot occupy the south portion of the subject site. An abandoned residential dwelling is present on the north-west portion of the site with an associated driveway and landscaped area. The north-east portion of the subject site is occupied by mature trees. The majority of the ground surface across the subject site is relatively flat at an approximate geodetic elevation of 98 m. The site is at grade with surrounding roadways and developments.

A section of outcropping bedrock is present on the north-east corner of the site which slopes up towards the north-east to an approximate elevation of 104 m.

The site is bound by residential dwellings and landscaped areas to the north, a one-storey church to the east, Montreal Road to the south, and Blair Road to the west.

4.2 Subsurface Profile

Overburden

Generally, the soil conditions encountered at the majority of the test hole locations consisted of a concrete slab/asphaltic concrete layer followed by fill overlying a compact glacial till layer. The fill material consisted of brown silty sand with crushed stone and/or silty clay. Silty clay, sandy silt, or silty sand were occasionally encountered below the fill. At the north-west corner of the site silty clay was encountered directly below a thin topsoil layer.

Bedrock

Bedrock was encountered at cored borehole locations at depths ranging from 0.7 to 5.7 m below the existing ground surface. Generally, the bedrock throughout the majority of the subject site was generally observed to consist of a very poor to fair quality limestone with shale interbeds at some locations. The bedrock quality overall improved to a poor to good or excellent quality near the north-east portion of the site.

Based on available geological mapping, the bedrock in this area mostly consists of interbedded limestone and dolomite of the Gull River formation with an overburden drift thickness of 1 to 5 m depth.

Reference should be made to the Soil Profile and Test Data sheets in Appendix 1 for specific details of the soil profiles encountered at each test hole location.

4.3 Groundwater

Groundwater levels (GWL) were measured in the piezometers and monitoring wells, and the results are presented in Table 1. It should be noted that surface water can become perched within a backfilled borehole, which can lead to higher than normal groundwater level readings. The long-term groundwater level can also be estimated based on moisture levels and colour of the recovered soil samples. Based on these observations, the long-term groundwater table is expected to be located below the bedrock surface. It should be noted that groundwater levels are subject to seasonal fluctuations. Therefore, the groundwater levels could vary at the time of construction.

Table 1 - Summary of Groundwater Level Readings				
Borehole Number	Ground Surface Elevation (m)	Groundwater Level (m)	Groundwater Elevation (m)	Recording Date
BH 1-23	97.78	1.43	96.35	May 2, 2023
BH 2-23	98.04	0.66	97.38	
BH 3-23	98.32	1.17	97.15	
BH 4-23	98.16	1.43	96.73	
BH 5-23	97.68	17.76	79.92	
BH 1	97.76	2.42	95.34	October 19, 2020
BH 2	97.48	2.59	94.89	
BH 3	97.66	2.31	95.35	
BH 6	97.92	1.35	96.57	
BH 7	97.98	1.81	96.17	October 21, 2020

5.0 Discussion

5.1 Geotechnical Assessment

The subject site is considered satisfactory, from a geotechnical perspective, for the proposed development. Due to the varying quality of the bedrock encountered throughout the subject site at the anticipated underside of footing level, the bedrock quality at the site has been separated into two zones, Zone 1 – Very Poor to Fair Quality Bedrock, and Zone 2 – Good or Excellent Quality Bedrock. Reference should be made to Drawing PG5663-2 – Bedrock Quality Zone Plan in Appendix 2. Paterson recommends a sub-excavation below design footing level within Zone 1 due to the presence of poor quality bedrock at footing level, where encountered. A minimum 300 mm concrete slab should be placed over the fractured bedrock up to design footing level. It is anticipated that the north-east portion of the proposed high-rise building will be founded on shallow footings placed on a clean, surface sounded bedrock at the location of Zone 2.

The above and other considerations are further discussed in the following sections.

5.2 Site Grading and Preparation

Stripping Depth

Due to the depth of the bedrock at the subject site and the anticipated founding level for the proposed high-rise building, it is anticipated that all existing overburden material will be excavated from within the footprint of the proposed multi-storey building.

Bedrock Removal

It is expected that line-drilling in conjunction with hoe-ramming, rock grinding and controlled blasting will be required to remove the bedrock for the underground parking levels. In areas of weathered bedrock and where only a small quantity of bedrock is to be removed, bedrock removal may be possible by hoe-ramming.

Prior to considering blasting operations, the blasting effects on the existing services, buildings, and other structures should be addressed. A pre-blast or pre-construction survey of the existing structures located in the proximity of the blasting operations should be carried out prior to commencing site activities. The extent of the survey should be determined by the blasting consultant and should be sufficient to respond to any inquiries or claims related to the blasting operations.

As a general guideline, peak particle velocities (measured at the structures) should not exceed the below noted vibration limits during the blasting program to reduce the risks of damage to the existing surrounding structures. The blasting operations should be planned and conducted under the supervision of a licensed professional engineer who is also an experienced blasting consultant.

Excavation side slopes in sound bedrock can be carried out using near vertical sidewalls. A minimum 1 m horizontal ledge should be left between the bottom of the overburden excavation and the top of the bedrock surface to provide an area to allow for potential sloughing. The 1 m horizontal ledge set back can be eliminated with a shoring program which has drilled piles extending below the proposed founding elevation.

Fill Placement

Excavated limestone bedrock could be used as select subgrade material around the proposed building footings, provided the excavated bedrock is suitably crushed to 50 mm in its longest dimension and approved by the geotechnical consultant at the time of placement. Alternatively, an engineered fill such as an OPSS Granular A or Granular B Type II compacted to 98% of its SPMDD could be placed around the proposed footings.

Bedrock Excavation Face Reinforcement

Due to the bedrock quality encountered at the site, horizontal rock anchors and chain link fencing connected to the excavation face will be required at specific locations to prevent bedrock pop-outs, especially in areas where bedrock fractures are conducive to the failure of the bedrock surface. It is expected that Zone 1, as indicated on Drawing PG5663-2 in Appendix 2 will require a large number of rock anchors to be installed for bedrock stabilization purposes due to the poor quality of bedrock encountered. The requirements for bedrock stabilization measures will be evaluated during the excavation operations.

Vibration Considerations

Construction operations could cause vibrations, and possibly, sources of nuisance to the community. Therefore, means to reduce the vibration levels as much as possible should be incorporated in the construction operations to maintain a cooperative environment with the residents.

Two parameters determine the recommended vibration limit, the maximum peak particle velocity and the frequency. For low frequency vibrations, the maximum allowable peak particle velocity is less than that for high frequency vibrations. As recommended by the regulations, the peak particle velocity should be less than 20 mm/s below 40 Hz, and 50 mm/s above a frequency of 40 Hz. These regulations are for both infrastructure (pipelines) as in addition to buildings. A pre-construction survey is recommended to minimize the risks of claims during or following the construction of the proposed building.

5.2.1 Vibration Monitoring and Control Plan

A monitoring instrumentation remote exchange network (MIREN) set up by Paterson, will provide real-time results of vibrations to the blasting consultant, construction team and Paterson for immediate review. Following each recorded event, an email will be sent out containing the following:


- A breakdown of the vibration event including the PPV, dominant frequency, and zero cross frequency in each direction (transverse, vertical, longitudinal).
- The monitor serial, calibration date, and the location of the monitor recording the event.
- A statement indicating if the vibration is either within the agreed upon limits or in exceedance.
- A PDF attachment containing the full waveforms and FFT report.

For warning or exceedance level events, the procedures described below will be followed.

Proposed Vibration Limits

The excavation operations should be planned and conducted under the supervision of a licensed professional engineer. The vibration limits for the associated infrastructure, outlined in the figure below, are 20 mm/s for frequencies below 40 Hz, and 50 mm/s for frequencies 40 Hz and higher. The warning level limits are 10 mm/s for frequencies below 40 Hz, and 40 mm/s for frequencies 40 Hz and higher.

Vibrational Limits - S.P. No: F-1201



Monitoring Data

The monitoring protocol should include the following information:

Warning Level Event

- Review the waveforms of the event to determine the cause of the event and confirm monitor function.
- Paterson will notify the contractor if any vibrations occur due to construction activities and are close to exceedance level.
- A site visit may be required to confirm the monitor placement, source of exceedance, provide mitigation recommendations and/or to review the field conditions.

Exceedance Level Event

- Review the waveforms of the event to determine the cause of the event and confirm monitor function.
- Paterson will notify the blasting contractor of the exceedance.

- A site visit may be required to confirm the monitor placement, source of exceedance, provide mitigation recommendations and/or to review the field conditions.
- An exceedance report will be created and issued.

Incident/Exceedance Reporting

In case an incident/exceedance occurs from construction activities, the Senior Project Management and any relevant personnel should be notified immediately. A report should be completed which contains the following:

- Identify the location of the vibration exceedance,
- The date, time and nature of the exceedance/incident,
- Purpose of the exceeded monitor and current vibration criteria,
- Identify the likely cause of the exceedance/incident,
- Describe the initial response action that has been completed to date,
- Describe the proposed measures to address the exceedance/incident and provide an immediate action plan and prevention measures to eliminate the cause of the exceeded vibrations(s) during future work.

5.3 Foundation Design

Bearing Resistance Values

Due to the varying quality of the bedrock encountered throughout the subject site at the anticipated underside of footing elevation, the bedrock quality at the site has been separated into two zones, Zone 1 – Very Poor to Fair Quality Bedrock, and Zone 2 – Good or Excellent Quality Bedrock. Reference should be made to drawing PG5663-2 – Bedrock Quality Zone Plan in Appendix 2. The following outlines recommendations for each respective bedrock quality zone.

Zone 1 – Very Poor to Fair Quality Bedrock

Due to the highly fractured bedrock encountered at Zone 1 of the site, it is recommended that a minimum 300 mm thick minimum 25 MPa (28-day compressive strength) concrete slab extending at least 1 m horizontally beyond the footing face be placed over the fractured bedrock surface prior to the placement of the footings. The bedrock surface should be cleaned of any loose fragments prior to the placement of the concrete raft slab. The concrete raft slab should be continuous across the entirety of Zone 1 and effort should be made at the time of placement of the raft slab to infill any surficial fractures and/or voids with concrete.

Therefore, the bedrock must be sub-excavated a minimum depth of 300 mm below the proposed underside of footing elevation to allow space for the placement of the raft slab at Zone 1.

Footings placed on a concrete raft slab placed over a clean, fractured bedrock surface at the proposed founding elevation can be designed using a factored bearing resistance value at ultimate limit states (ULS) of **3,000 kPa** incorporating a geotechnical resistance factor of 0.5 was applied to the bearing resistance value at ULS. The modulus of subgrade reaction was calculated to be **500 MPa/m** for a contact pressure of **3,000 kPa**.

For a foundation placed on a concrete raft slab placed on fractured bedrock, the total and differential settlement are expected to be negligible.

Zone 2 – Good or Excellent Quality Bedrock

At the location of Zone 2, footings may be placed directly over a clean, surface sounded bedrock bearing surface, provided that the bedrock is free of seams, fractures, and voids within 1.5 m below the founding level. This could be verified by completing and probing 50 mm diameter drill holes to a depth of 1.5 m below the founding level within the footing footprint(s) or assessing the bedrock profile at depth.

Footings placed on a clean, surface sounded bedrock surface free of any seams, fractures or voids within 1.5 m of the founding level may be designed using a factored bearing resistance value of **3,000 kPa (ULS)** incorporating a geotechnical resistance factor of 0.5.

A clean, surface-sounded bedrock bearing surface should be free of loose materials, and have no near surface seams, voids, fissures or open joints which can be detected from surface sounding with a rock hammer.

For a foundation placed on a bedrock bearing surface, the total and differential settlement are expected to be negligible.

Lateral Support

The bearing medium under footing-supported structures is required to be provided with adequate lateral support with respect to excavations and different foundation levels. Adequate lateral support is provided to a sound bedrock bearing medium when a plane extending down and out from the bottom edge of the footing at a minimum of 1H:6V (or flatter) passes only through sound bedrock or a material of the same or higher capacity as the bedrock, such as concrete. A weathered or highly fractured bedrock bearing medium will require a lateral support zone of 1H:1V (or flatter).

5.4 Design for Earthquakes

Seismic shear wave velocity testing was completed for the subject site to accurately determine the applicable seismic site classification for the proposed building in accordance with Table 4.1.8.4.A of the Ontario Building Code 2012. The shear wave velocity testing was completed by Paterson personnel. The results of the shear wave velocity test are provided in Figures 2 and 3, which are presented in Appendix 2 of this report.

Field Program

The seismic array testing location was placed as presented in Drawing PG5663-1 - Test Hole Location Plan, attached to the present report. Paterson field personnel placed 18 horizontal 2.4 Hz. geophones mounted to the surface by means of two 75 mm ground spikes attached to the geophone land case. The geophones were spaced at 1 m intervals and connected by a geophone spread cable to a Geode 24 Channel seismograph.

The seismograph was also connected to a computer laptop and a hammer trigger switch attached to a 12-pound dead blow hammer. The hammer trigger switch sends a start signal to the seismograph. The hammer is used to strike an I-Beam seated into the ground surface, which creates a polarized shear wave. The hammer shots are repeated between four (4) to eight (8) times at each shot location to improve signal to noise ratio. The shot locations were 15, 1.5 and 1.0 m away from the first and last geophone and at the centre of the seismic array.

Data Processing and Interpretation

Interpretation for the shear wave velocity results were completed by Paterson personnel. Shear wave velocity measurement was made using reflection/refraction methods. The interpretation is performed by recovering arrival times from direct and refracted waves.

The interpretation is repeated at each shot location to provide an average shear wave velocity, V_{s30} , of the upper 30 m profile, immediately below the foundation of the building. The layer intercept times, velocities from different layers and critical distances are interpreted from the shear wave records to compute the bedrock depth at each location. The bedrock velocity was interpreted using the main refractor wave velocity.

It is understood that the foundations will be placed directly or indirectly upon a clean, sound bedrock surface. Based on the results of the shear wave velocity testing, the average shear wave velocity, V_{s30} , for the proposed building is **2,033 m/s** provided the footings are placed directly or indirectly on bedrock. The V_{s30} was calculated using the standard equation for average shear wave velocity provided in the OBC 2012 and as presented below:

$$V_{s30} = \frac{\text{Depth}_{of\ interest}(m)}{\left(\frac{\text{Depth}_{Layer1}(m)}{V_{sLayer1}(m/s)} + \frac{\text{Depth}_{Layer2}(m)}{V_{sLayer2}(m/s)} \right)}$$

$$V_{s30} = \frac{30\ m}{\left(\frac{30\ m}{2,033\ m/s} \right)}$$

$$V_{s30} = 2,033\ m/s$$

Based on the results of the shear wave velocity testing, the average shear wave velocity V_{s30} , is 2,033 m/s. Therefore, a **Site Class A** is applicable for the design of proposed building bearing on bedrock, as per Table 4.1.8.4.A of the OBC 2012. The soils underlying the subject site are not susceptible to liquefaction.

5.5 Basement Slab

The basement floor slab at the final underground level will be placed over a minimum 200 mm thick layer OPSS Granular A crushed stone followed by Granular B Type II to the top of the bedrock subgrade. The sub-floor granular material within the footprint of the building will be placed in maximum 300 mm thick lifts and compacted to at least 98% of the material's SPMDD.

An underfloor drainage system is required between the finished floor and the underlying bedrock subgrade to direct water infiltration to the building sump pit.

5.6 Basement Wall

It is understood that the basement walls are to be poured against a composite drainage system, which will be placed against the exposed bedrock face. A nominal coefficient for at-rest earth pressure of 0.05 is recommended in conjunction with a bulk unit weight of 24.5 kN/m^3 (effective 15.5 kN/m^3). A seismic earth pressure component will not be applicable for the foundation wall, which is to be poured against the bedrock face.

Where soil is to be retained, the conditions can be well-represented by assuming the retained soil consists of a material with an angle of internal friction of 30 degrees and a bulk (drained) unit weight of 20 kN/m^3 . Undrained conditions are anticipated (i.e. below the groundwater level). Therefore, the applicable effective (undrained) unit weight of the retained soil can be taken as 13 kN/m^3 , where applicable. A hydrostatic pressure should be added to the total static earth pressure when using the effective unit weight.

Two (2) distinct conditions, static and seismic, must be reviewed for design calculations. The parameters for design calculations for the two (2) conditions are presented below.

Static Conditions

The static horizontal earth pressure (P_o) can be calculated using a triangular earth pressure distribution equal to $K_o \cdot \gamma \cdot H$ where:

K_o = at-rest earth pressure coefficient of the applicable retained soil, 0.5

γ = unit weight of fill of the applicable retained soil (kN/m^3)

H = height of the wall (m)

An additional pressure having a magnitude equal to $K_o \cdot q$ and acting on the entire height of the wall should be added to the above diagram for any surcharge loading, q (kPa), that may be placed at ground surface adjacent to the wall. The surcharge pressure will only be applicable for static analyses and should not be used in conjunction with the seismic loading case.

Actual earth pressures could be higher than the “at-rest” case if care is not exercised during the compaction of the backfill materials to maintain a minimum separation of 0.3 m from the walls with the compaction equipment.

Seismic Conditions

The total seismic force (P_{AE}) includes both the earth force component (P_o) and the seismic component (ΔP_{AE}).

The seismic earth force (ΔP_{AE}) can be calculated using $0.375 \cdot a_c \cdot \gamma \cdot H^2/g$ where:

$$a_c = (1.45 - a_{\max}/g)a_{\max}$$

γ = unit weight of fill of the applicable retained soil (kN/m³)

H = height of the wall (m)

g = gravity, 9.81 m/s²

The peak ground acceleration, (a_{\max}), for the Ottawa (City Hall) area is 0.281 g according to OBC 2012 (R2019). Note that the vertical seismic coefficient is assumed to be zero.

The earth force component (P_o) under seismic conditions can be calculated using $P_o = 0.5 K_o \gamma H^2$, where $K_o = 0.5$ for the soil conditions noted above.

The total earth force (P_{AE}) is considered to act at a height, h (m), from the base of the wall, where:

$$h = \{P_o \cdot (H/3) + \Delta P_{AE} \cdot (0.6 \cdot H)\} / P_{AE}$$

The earth forces calculated are unfactored. For the ULS case, the earth loads should be factored as live loads, as per OBC 2012.

5.7 Rock Anchor Design

The geotechnical design of grouted rock anchors in sedimentary bedrock is based upon two possible failure modes. The anchor can fail either by shear failure along the grout/rock interface or by pullout of a 60 to 90 degree cone of rock with the apex of the cone near the middle of the bonded length of the anchor. It should be noted that interaction may develop between the failure cones of anchors that are relatively close to one another resulting in a total group capacity smaller than the sum of the load capacity of each anchor taken individually.

A third failure mode of shear failure along the grout/steel interface should also be reviewed by a qualified structural engineer to ensure all typical failure modes have been reviewed. Typical rock anchor suppliers, such as Dywidag Systems International (DSI Canada), have qualified personnel on staff to recommend appropriate rock anchor size and materials.

It should be further noted that centre to centre spacing between bond lengths be at least four (4) times the anchor hole diameter and greater than 1.2 m to lower the group influence effects. It is also recommended that anchors in close proximity to each other be grouted at the same time to ensure any fractures or voids are completely in-filled and that fluid grout does not flow from one hole to an adjacent empty one.

Anchors can be of the “passive” or the “post-tensioned” type, depending on whether the anchor tendon is provided with post-tensioned load or not prior to being put into service.

Regardless of whether an anchor is of the passive or the post tensioned type, it is recommended that the anchor be provided with a bonded length, or fixed anchor length, at the base of the anchor, which will provide the anchor capacity, as well an unbonded length, or free anchor length, between the rock surface and the start of the bonded length. As the depth at which the apex of the shear failure cone develops is midway along the bonded length, a fully bonded anchor would tend to have a much shallower cone, and therefore less geotechnical resistance, than one where the bonded length is limited to the bottom part of the overall anchor.

Permanent anchors should be provided with corrosion protection. As a minimum, this requires that the entire drill hole be filled with cementitious grout. The free anchor length is provided by installing a plastic sleeve to act as a bond break.

Grout to Rock Bond

Generally, the unconfined compressive strength of limestone ranges between 60 and 120 MPa, which is stronger than most routine grouts. A factored tensile grout to rock bond resistance value at ULS of **1.0 MPa**, incorporating a resistance factor of 0.3, can be used. A minimum grout strength of 40 MPa is recommended.

Rock Cone Uplift

As discussed previously, the geotechnical capacity of the rock anchors depends on the dimensions of the rock anchors and the configuration of the anchorage system. Based on existing subsoils information, a **Rock Mass Rating (RMR) of 65** was assigned to the bedrock, and Hoek and Brown parameters (**m and s**) were taken as **0.575 and 0.00293**, respectively.

Recommended Rock Anchor Lengths

Rock anchor lengths can be designed based on the required loads. Rock anchor lengths for some typical loads have been calculated and are presented in Table 2. Load specified rock anchor lengths can be provided, if required.

For our calculations the following parameters were used.

Table 2 - Parameters used in Rock Anchor Review	
Grout to Rock Bond Strength - Factored at ULS	1.0 MPa
Compressive Strength - Grout	40 MPa
Rock Mass Rating (RMR) - Good quality Limestone Hoek and Brown parameters	65 m=0.575 and s=0.00293
Unconfined compressive strength - Limestone bedrock	60 MPa
Unit weight - Submerged Bedrock	15 kN/m ³
Apex angle of failure cone	60°
Apex of failure cone	mid-point of fixed anchor length

From a geotechnical perspective, the fixed anchor length will depend on the diameter of the drill holes. Recommended anchor lengths for a 75 and 125 mm diameter hole are provided in Table 3.

Table 3 - Recommended Rock Anchor Lengths - Grouted Rock Anchor				
Diameter of Drill Hole (mm)	Anchor Lengths (m)			Factored Tensile Resistance (kN)
	Bonded Length	Unbonded Length	Total Length	
75	1.2	0.6	1.8	250
	1.9	1.0	2.9	500
	3	1.5	4.5	1000
125	1.1	0.5	1.6	250
	1.5	0.9	2.4	500
	2.6	1.0	3.6	1000

It is recommended that the anchor drill hole diameter be within 1.5 to 2 times the rock anchor tendon diameter and the anchor drill holes be inspected by geotechnical personnel and should be flushed clean prior to grouting. The use of a grout tube to place grout from the bottom up in the anchor holes is further recommended.

The geotechnical capacity of each rock anchor should be proof tested at the time of construction. More information on testing can be provided upon request. Compressive strength testing is recommended to be completed for the rock anchor grout. A set of grout cubes should be tested for each day grout is prepared.

5.8 Pavement Structure

Where required at the subject site, the recommended pavement structures for car only parking areas and access lanes are shown in Tables 4 and 5.

Table 4 - Recommended Pavement Structure - Car Only Parking Areas	
Thickness (mm)	Material Description
50	Wear Course - HL 3 or Superpave 12.5 Asphaltic Concrete
150	BASE - OPSS Granular A Crushed Stone
300	SUBBASE - OPSS Granular B Type II
SUBGRADE - Either fill, in situ soil or OPSS Granular B Type I or II material placed over in situ soil or fill.	

Table 5 - Recommended Pavement Structure - Access Lanes and Heavy Truck Parking/Loading Areas	
Thickness (mm)	Material Description
40	Wear Course - HL3 or Superpave 12.5 Asphaltic Concrete
50	Binder Course - HL8 or Superpave 19.0 Asphaltic Concrete
150	BASE - OPSS Granular A Crushed Stone
450	SUBBASE - OPSS Granular B Type II
SUBGRADE - Either fill, in situ soil or OPSS Granular B Type I or II material placed over in situ soil or fill.	

Where a podium deck is located below the pavement structures, including parking areas and access lanes, can be designed using the pavement structure shown on Table 6 below.

Table 6 - Recommended Pavement Structure – Access Lanes and Heavy Truck Parking Areas	
Thickness (mm)	Material Description
50	Wear Course - Superpave 12.5 Asphaltic Concrete
300	BASE - OPSS Granular A Crushed Stone
SUBGRADE - To consist of concrete podium deck including waterproofing and insulation.	

If soft spots develop in the subgrade during compaction or due to construction traffic, the affected areas should be excavated and replaced with OPSS Granular B Type II material. Weak subgrade conditions may be experienced over service trench fill materials.

Minimum Performance Graded (PG) 58-34 asphalt cement should be used for this project. The pavement granular base and subbase should be placed in maximum 300 mm thick lifts and compacted to a minimum of 100% of the material's SPMDD using suitable vibratory equipment.

6.0 Design and Construction Precautions

6.1 Foundation Drainage and Backfill

Foundation Drainage and Waterproofing

It is anticipated that the building foundation walls will be placed in close proximity to the site boundaries. It is expected that the foundation wall will be blind side poured against a foundation drainage and waterproofing system fastened against the temporary shoring system and bedrock face.

A waterproofing membrane, such as a granular bentonite sheeting, will be required to lessen the effect of water infiltration. The waterproofing membrane can be placed and fastened to the shoring system and should extend from 3 m below finished grade to the bottom of the excavation at the founding level of the perimeter footings. The waterproofing should be extended a minimum of 600 mm below the underside of the perimeter footings.

It is recommended that a composite drainage blanket, such as Delta Drain 6000 or equivalent, extend from the exterior finished grade to the founding elevation. The purpose of the composite drainage system is to direct any water infiltration resulting from a breach of the waterproofing membrane to the building sump pit(s). It is recommended that 150 mm diameter sleeves at 3 m centres be cast in the foundation wall at the perimeter footing interface to allow water infiltration into to an interior perimeter and underfloor drainage system. The perimeter and underfloor drainage system should direct water to sump pit(s) within the lower basement area.

It should be noted that due to the poor-quality bedrock and bedrock seams and voids encountered throughout the subject site, preparation of the bedrock substrate surface prior to application of the waterproofing membrane will be required. This may include the application of shotcrete, infilling of voids with concrete, and bedrock gridding. Recommendations will be made at the time of excavation when the bedrock is exposed and can be better assessed.

Underfloor Drainage

Underfloor drainage will be required to control water infiltration below the lowest level floor slab. For design purposes, it is recommended that 150 mm diameter perforated, corrugated pipes be placed along the interior perimeter of the foundation wall and one drainage line within each bay. The spacing of the underfloor drainage system should be confirmed at the time of construction when water infiltration can be better assessed.

Foundation Backfill

Where space is available for conventional wall construction, backfill against the exterior sides of the foundation walls should consist of free-draining, non-frost susceptible granular materials. Imported granular materials, such as clean sand or OPSS Granular B Type I, should be used for this purpose.

6.2 Protection Against Frost Action

Perimeter footings of heated structures are required to be insulated against the deleterious effect of frost action. A minimum 1.5 m thick soil cover (or equivalent) should be provided in this regard.

Exterior unheated footings, such as those for isolated exterior piers, are more prone to deleterious movement associated with frost action than the exterior walls of the structure proper and require additional protection, such as soil cover of 2.1 m or a combination of soil cover and foundation insulation.

6.3 Excavation Side Slopes

Unsupported Side Slopes

The side slopes of excavations in the soil and fill overburden materials should either be excavated at acceptable slopes or should be retained by shoring systems from the beginning of the excavation until the structure is backfilled. Insufficient room is expected for the majority of the excavation to be constructed by open-cut methods (i.e. unsupported excavations).

The excavation side slopes above the groundwater level extending to a maximum depth of 3 m should be excavated at 1H:1V or shallower. The shallower slope is required for excavation below groundwater level. The subsurface soils are considered to be a Type 2 and 3 soil according to the Occupational Health and Safety Act and Regulations for Construction Projects.

Excavated soil should not be stockpiled directly at the top of excavations and heavy equipment should be kept away from the excavation sides.

Slopes in excess of 3 m in height should be periodically inspected by the geotechnical consultant in order to detect if the slopes are exhibiting signs of distress.

A trench box is recommended to protect personnel working in trenches with steep or vertical sides. Services are expected to be installed by “cut and cover” methods and excavations should not remain open for extended periods of time.

Temporary Shoring

It is anticipated that temporary shoring is required to complete the required excavation where insufficient room is available for open cut methods. The shoring requirements designed by a structural engineer specializing in those works will depend on the depth of the excavation, the proximity of the adjacent structures and the elevation of the adjacent building foundations and underground services. The design and implementation of these temporary systems will be the responsibility of the excavation contractor and their design team. Inspections and approval of the temporary system will also be the responsibility of the designer. Geotechnical information provided below is to assist the designer in completing a suitable and safe shoring system. The designer should take into account the impact of a significant precipitation event and designate design measures to ensure that a precipitation event will not negatively impact the shoring system or soils supported by the system. Any changes to the approved shoring design system should be reported immediately to the owner's structural designer prior to implementation.

The temporary system could consist of soldier pile and lagging system or interlocking steel sheet piling. Any additional loading due to street traffic, construction equipment, adjacent structures and facilities, etc., should be included to the earth pressures described below. These systems could be cantilevered, anchored or braced. Generally, it is expected that the shoring systems will be provided with tie-back rock anchors to ensure their stability. The shoring system is recommended to be adequately supported to resist toe failure and inspected to ensure that the sheet piles extend well below the excavation base. It should be noted if consideration is being given to utilizing a raker style support for the shoring system that lateral movements can occur and the structural engineer should ensure that the design selected minimizes these movements to tolerable levels.

The earth pressures acting on the temporary shoring system may be calculated with the following parameters.

Table 7 - Soil Parameters for Shoring System Design	
Parameters	Values
Active Earth Pressure Coefficient (K_a)	0.33
Passive Earth Pressure Coefficient (K_p)	3
At-Rest Earth Pressure Coefficient (K_o)	0.5
Unit Weight (γ), kN/m ³	20
Submerged Unit Weight (γ), kN/m ³	13

The active earth pressure should be calculated where wall movements are permissible while the at-rest pressure should be calculated if no movement is permissible. The dry unit weight should be calculated above the groundwater level while the effective unit weight should be calculated below the groundwater level.

The hydrostatic groundwater pressure should be included to the earth pressure distribution wherever the effective unit weight are calculated for earth pressures. If the groundwater level is lowered, the dry unit weight for the soil/bedrock should be calculated full weight, with no hydrostatic groundwater pressure component.

For design purposes, the minimum factor of safety of 1.5 should be calculated.

6.4 Pipe Bedding and Backfill

The pipe bedding for sewer and water pipes should consist of at least 150 mm of OPSS Granular A material. The material should be placed in maximum 300 mm thick lifts and compacted to a minimum of 99% of the SPMDD. The bedding material should extend at least to the spring line of the pipe.

The cover material, which should consist of OPSS Granular A crushed stone, should extend from the spring line of the pipe to at least 300 mm above the obvert of the pipe. The material should be placed in maximum 300 mm thick lifts and compacted to a minimum of 99% of the SPMDD.

Generally, it should be possible to re-use the site material above the cover material if the excavation and backfilling operations are completed in dry weather conditions.

Where hard surface areas are considered above the trench backfill, the trench backfill material within the frost zone (about 1.8 m below finished grade) should match the soils exposed at the trench walls to minimize differential frost heaving. The trench backfill should be placed in maximum 300 mm thick loose lifts and compacted to a minimum of 95% of the SPMDD.

6.5 Groundwater Control

Groundwater Control for Building Construction

Due to the highly fractured bedrock encountered at the site, it is anticipated that groundwater infiltration into the excavation may be higher than expected. Pumps should be appropriately sized to handle the expected groundwater influx.

The contractor should be prepared to direct water away from all bearing surfaces and subgrades, regardless of the source, to prevent disturbance to the founding medium.

A temporary Ministry of the Environment, Conservation and Parks (MECP) permit to take water (PTTW) Category 3 may be required for this project if more than 400,000 L/day of ground and/or surface water is to be pumped during the construction phase. A minimum 4 to 5 months should be allowed for completion of the PTTW application package and issuance of the permit by the MECP.

For typical ground or surface water volumes, being pumped during the construction phase, between 50,000 to 400,000 L/day, it is required to register on the Environmental Activity and Sector Registry (EASR). A minimum of two to four weeks should be allotted for completion of the EASR registration and the Water Taking and Discharge Plan to be prepared by a Qualified Person as stipulated under O.Reg. 63/16. If a project qualifies for a PTTW based upon anticipated conditions, an EASR will not be allowed as a temporary dewatering measure while awaiting the MECP review of the PTTW application.

Long-term Groundwater Control

Our recommendations for the proposed building's long-term groundwater control are presented in Subsection 6.1. Any groundwater which breaches the building's perimeter groundwater infiltration control system will be directed to the proposed building's sump pit. Provided the proposed groundwater infiltration control system is properly implemented and approved by the geotechnical consultant at the time of construction, it is expected that groundwater flow will be low to negligible (less than 20,000 L/day).

Impacts on Neighboring Structures

It is understood that three levels of underground parking are planned for the proposed building. Based on the existing groundwater level and considering that the proposed building will be surrounded by a waterproofing membrane, long-term groundwater lowering will be minimal and will take place within a limited range of the proposed building. Based on the proximity of neighboring buildings and the minimal zone impacted by the groundwater lowering, the proposed development will not negatively impact the neighbouring structures. It should be noted that no issues are expected with respect to groundwater lowering that would cause long term damage to adjacent structures surrounding the proposed building.

6.6 Winter Construction

Precautions must be taken if winter construction is considered for this project. The subsoil conditions at this site consist of frost susceptible materials. In the presence of water and freezing conditions, ice could form within the soil mass. Heaving and settlement upon thawing could occur. In the event of construction during below zero temperatures, the founding stratum should be protected from freezing temperatures by the use of straw, propane heaters and tarpaulins or other suitable means. In this regard, the base of the excavations should be insulated from sub-zero temperatures immediately upon exposure and until such time as heat is adequately supplied to the building and the footings are protected with sufficient soil cover to prevent freezing at founding level. Trench excavations and pavement construction are also difficult activities to complete during freezing conditions without introducing frost in the subgrade or in the excavation walls and bottoms. Precautions should be taken if such activities are to be carried out during freezing conditions. Additional information could be provided, if required.

Shotcrete Application in Winter Conditions

It is recommended that the application of shotcrete to the excavated bedrock sidewalls as a bedrock stabilization and/or substrate surface preparation measure be avoided during winter conditions. The application of shotcrete during winter conditions can result in ice formation on the bedrock excavation sidewalls, resulting in delamination of the shotcrete which could present a safety hazard. If winter construction is considered, alternate recommendations for bedrock stabilization and substrate surface preparation can be made at the time of construction.

7.0 Recommendations

It is a requirement for the foundation design data provided herein to be applicable that the following material testing and observation program be performed by the geotechnical consultant.

- Observation of all bearing surfaces prior to the placement of concrete.
- Inspection of the foundation waterproofing and all foundation drainage systems.
- Sampling and testing of the concrete and fill materials placed.
- Periodic observation of the condition of unsupported excavation side slopes in excess of 3 m in height, if applicable.
- Observation of all subgrades prior to backfilling.
- Field density tests to determine the level of compaction achieved.

A report confirming that these works have been conducted in general accordance with Paterson's recommendations could be issued upon request, following the completion of a satisfactory material testing and observation program by the geotechnical consultant.

8.0 Statement of Limitations

The recommendations provided in this report are in accordance with our present understanding of the project. We request permission to review our recommendations when the grading plan, drawings and specifications are completed.

A geotechnical investigation of this nature is a limited sampling of a site. The recommendations are based on information gathered at the specific test locations and can only be extrapolated to an undefined limited area around the test locations. Should any conditions at the site be encountered which differ from those at the test locations, we request notification immediately in order to permit reassessment of our recommendations.

The present report applies only to the project described in this document. Use of this report for purposes other than those described herein or by person(s) other than 10869279 Canada Inc. or their agent(s) is not authorized without review by Paterson Group for the applicability of our recommendations to the altered use of the report.

Paterson Group Inc.



Nicole R.L. Patey, P.Eng.



David J. Gilbert, P.Eng.

APPENDIX 1

SOIL PROFILE AND TEST DATA SHEETS

SYMBOLS AND TERMS

PHOTOGRAPHS OF ROCK CORE

DATUM Geodetic

REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE April 11, 2023

FILE NO.
PG5663

HOLE NO.
BH 1-23

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %					
GROUND SURFACE								20	40	60	80		
Asphaltic concrete	0.15					0	97.78						
FILL: Crushed stone	0.46	AU	1										
FILL: Brown silty sand, some organics, trace gravel	1.21	SS	2	50	6	1	96.78						
Compact to dense, brown SILTY SAND , trace clay and gravel	2.26	SS	3	67	50+	2	95.78						
BEDROCK: Very poor to fair quality, grey limestone		RC	1	100	82	3	94.78						
- crystallized calcite at 3.3, 3.9, 6.15, 7.4, 7.6, 9.3, 9.6, 9.75, 10.7, 11.2, 11.5, 12.4, 12.8 and 16.4m depths		RC	2	100	72	4	93.78						
		RC	3	100	47	5	92.78						
		RC	4	100	59	7	90.78						
		RC	5	93	46	8	89.78						
		RC	6	89	68	10	87.78						
						11	86.78						
								20	40	60	80	100	
								Shear Strength (kPa)					
								▲ Undisturbed △ Remoulded					

DATUM Geodetic

REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE April 11, 2023

FILE NO.
PG5663

HOLE NO.
BH 1-23

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %				
GROUND SURFACE								20	40	60	80	
BEDROCK: Poor to fair quality, grey limestone		RC	7	100	56	11	86.78					
		RC	8	93	56	12	85.78					
		RC	9	100	14	13	84.78					
		RC	10	100	59	14	83.78					
		RC	11	100	53	15	82.78					
						16	81.78					
						17	80.78					
					18	79.78						
End of Borehole (GWL @ 1.43m - May 2, 2023)	18.39											

20 40 60 80 100
Shear Strength (kPa)
▲ Undisturbed △ Remoulded

DATUM Geodetic


REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE April 12, 2023

FILE NO.
PG5663

HOLE NO.
BH 2-23



SOIL PROFILE AND TEST DATA

Geotechnical Investigation
 1649 Montreal Road and 741 Blair Road
 Ottawa, Ontario

DATUM Geodetic

REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE April 12, 2023

FILE NO.
PG5663

HOLE NO.
BH 2-23

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Piezometer Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			20	40	60	80		
Ground Surface						11	87.04						
BEDROCK: Poor to good quality, grey limestone		RC	7	100	93	12	86.04						
		RC	8	100	85	13	85.04						
		RC	9	85	47	14	84.04						
		RC	10	80	37	15	83.04						
		RC	11	98	41	16	82.04						
						17	81.04						
End of Borehole (GWL @ 0.66m - May 2, 2023)	18.16					18	80.04						
								20	40	60	80	100	
								Shear Strength (kPa)					
								▲ Undisturbed △ Remoulded					

SOIL PROFILE AND TEST DATA

Geotechnical Investigation
1649 Montreal Road and 741 Blair Road
Ottawa, Ontario

DATUM Geodetic

REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE April 12, 2023

FILE NO.
PG5663

HOLE NO.
BH 3-23

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Piezometer Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			20	40	60	80		
Ground Surface													
FILL: Brown silty sand with crushed stone and gravel, occasional cobbles		AU	1			0	98.32						
FILL: Brown silty sand, trace clay, occasional cobbles		SS	2	71	3	1	97.32						
GLACIAL TILL: Dense, brown silty sand to sandy silt with gravel, cobbles and boulders		SS	3	79	34	2	96.32						
End of Borehole													
Practical refusal to augering at 2.23m depth (GWL @ 1.17m - May 2, 2023)													

20 40 60 80 100
Shear Strength (kPa)
▲ Undisturbed △ Remoulded

SOIL PROFILE AND TEST DATA

Geotechnical Investigation
1649 Montreal Road and 741 Blair Road
Ottawa, Ontario

DATUM Geodetic

REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE April 13, 2023

FILE NO.
PG5663

HOLE NO.
BH 4-23

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction		
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			20	40	60	80			
GROUND SURFACE								○ Water Content %						
TOPSOIL						0	98.16							
Loose to compact, brown SILTY SAND , trace gravel	0.30 0.66	AU	1											
BEDROCK: Poor to excellent quality, grey limestone						1	97.16							
- crystallized calcite at 2.4m depth		RC	1	100	26									
- vertical fracture from 9.9 to 10.4m depth.		RC	2	100	59									
- vertical fracture with crystallized calcite from 13.6 to 13.8m depth		RC	3	100	73									
- 25mm thick mud seam at 15.4m depth		RC	4	100	64									
		RC	5	100	90									
		RC	6	100	97									
		RC	7	100	85									
						10	88.16							
						11	87.16							



DATUM Geodetic

REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE April 13, 2023

FILE NO.
PG5663

HOLE NO.
BH 4-23

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			20	40	60	80		
GROUND SURFACE						11	87.16						
BEDROCK: Good to excellent quality, grey limestone		RC	8	100	86	12	86.16						
		RC	9	100	88	13	85.16						
		RC	10	100	100	14	84.16						
		RC	11	100	83	15	83.16						
End of Borehole	16.64					16	82.16						
(GWL @ 1.43m - May 2, 2023)													

20 40 60 80 100
Shear Strength (kPa)
▲ Undisturbed △ Remoulded

DATUM Geodetic

FILE NO.
PG5663

REMARKS

HOLE NO.
BH 5-23

BORINGS BY Truck-Mount Power Auger

DATE April 20, 2023

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %					
								20	40	60	80		
GROUND SURFACE													
Asphaltic concrete 0.03		AU	1			0	97.68						
FILL: Brown silty sand with crushed stone and gravel 0.30													
FILL: Brown silty sand with clay, some crushed stone, organics and asphalt fragments		SS	2	50	8	1	96.68						
		SS	3	67	5	2	95.68						
		SS	4	67	14	3	94.68						
		SS	5	67	8	4	93.68						
		SS	6	75	22	5	92.68						
GLACIAL TILL: Loose to dense, brown silty sand with gravel, cobbles and boulders - trace clay by 4.6m depth		SS	7	75	13	6	91.68						
		SS	8	89	50+	7	90.68						
BEDROCK: Very poor to fair quality, grey limestone - some fractures between 14.4 and 16.6m depth - mud seams at 12.5, 14.3, 14.5, 16.9 and 17.8m depths - crystallized calcite at 20.6m depth		RC	1	100	0	8	89.68						
		RC	2	100	60	9	88.68						
		RC	3	100	49	10	87.68						
		RC	4	100	63	11	86.68						
		RC	5	100	32								
								20	40	60	80	100	
								Shear Strength (kPa)					
								▲ Undisturbed △ Remoulded					

DATUM Geodetic

REMARKS

BORINGS BY Truck-Mount Power Auger

DATE April 20, 2023

FILE NO.
PG5663

HOLE NO.
BH 5-23

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %					
GROUND SURFACE								20	40	60	80		
BEDROCK: Very poor to fair quality, grey limestone						11	86.68						
		RC	6	98	69	12	85.68						
		RC	7	100	75	13	84.68						
		RC	8	50	5	14	83.68						
		RC	9	100	57	15	82.68						
		RC	10	100	50	16	81.68						
		RC	11	100	52	17	80.68						
						18	79.68						
						19	78.68						
						20	77.68						
						21	76.68						
End of Borehole (GWL @ 17.76m - May 3, 2023)	21.18												

20 40 60 80 100
Shear Strength (kPa)
▲ Undisturbed △ Remoulded

DATUM Geodetic

REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE October 15, 2020

FILE NO. **PG5663**

HOLE NO. **BH 1-20**

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %					
								20	40	60	80		
GROUND SURFACE													
Asphaltic concrete	0.08					0	97.76						
FILL: Brown silty sand with crushed stone	0.66	AU	1										
FILL: Brown silty sand with clay	1.37	SS	2	29	7	1	96.76						
FILL: Brown silty sand		SS	3	33	7	2	95.76						
		SS	4	58	2								
		SS	5	17	W	3	94.76						
GLACIAL TILL: Loose to very dense, grey silty sand with gravel		SS	6	75	5	4	93.76						
		SS	7	25	14	5	92.76						
		SS	8	91	50+								
Weathered BEDROCK	6.15					6	91.76						
End of Borehole		SS	9	50	50+								
Practical refusal to augering at 6.15m depth (GWL @ 2.42m - Oct. 19, 2020)													

20 40 60 80 100
Shear Strength (kPa)
▲ Undisturbed △ Remoulded

DATUM Geodetic

REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE October 15, 2020

FILE NO. **PG5663**

HOLE NO. **BH 2-20**

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %					
								20	40	60	80		
GROUND SURFACE													
Asphaltic concrete	0.08					0	97.48						
FILL: Brown silty sand, trace crushed stone	0.56	AU	1										
FILL: Grey/black silty sand with gravel and crushed stone		SS	2	54	10	1	96.48						
	1.83	SS	3	33	7								
Grey SILTY CLAY , some sand	2.13					2	95.48						
GLACIAL TILL: Compact to dense, brown silty sand with clay and gravel		SS	4	50	14								
	3.61	SS	5	25	50+	3	94.48						
BEDROCK: Poor to fair quality, grey limestone		RC	1	100	45	4	93.48						
		RC	2	100	58	5	92.48						
End of Borehole (GWL @ 2.59m - Oct. 19, 2020)	5.92												

20 40 60 80 100
Shear Strength (kPa)
▲ Undisturbed △ Remoulded

DATUM Geodetic

REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE October 15, 2020

FILE NO. **PG5663**

HOLE NO. **BH 3-20**

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %					
								20	40	60	80		
GROUND SURFACE													
Asphaltic concrete	0.08	AU	1			0	97.66						
FILL: Brown silty sand with crushed stone		SS	2	62	27	1	96.66						
		SS	3	54	32	2	95.66						
		SS	4	46	18								
		SS	5	17	3	3	94.66						
GLACIAL TILL: Brown silty sand with gravel	3.05	SS	6	0	50+	4	93.66						
BEDROCK: Poor quality, grey limestone	3.83	RC	1	57	45								
		RC	2	100	48	5	92.66						
						6	91.66						
End of Borehole (GWL @ 2.31m - Oct. 19, 2020)	6.48												

20 40 60 80 100
Shear Strength (kPa)
▲ Undisturbed △ Remoulded

DATUM Geodetic

REMARKS


BORINGS BY CME-55 Low Clearance Drill

DATE October 15, 2020

FILE NO. **PG5663**

HOLE NO. **BH 4-20**

SOIL DESCRIPTION	STRATA PLOT	SAMPLE			DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %			N VALUE or RQD	○ Water Content %				
GROUND SURFACE							20	40	60	80		
Asphaltic concrete	0.08				0	97.77						
FILL: Brown silty sand, some crushed stone	0.51	AU	1									
Compact, brown SILTY SAND with gravel		SS	2	71	16	1	96.77					
		SS	3	62	26	2	95.77					
GLACIAL TILL: Compact, brown silty sand with gravel, cobbles and boulders	2.29											
	3.02	SS		46	15	3	94.77					
End of Borehole												
Practical refusal to augering at 3.02m depth.												



DATUM Geodetic

REMARKS


BORINGS BY CME-55 Low Clearance Drill

DATE October 15, 2020

FILE NO. **PG5663**

HOLE NO. **BH 5-20**

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %					
GROUND SURFACE								20	40	60	80		
Asphaltic concrete	0.08					0	97.93						
FILL: Brown silty sand with crushed stone	0.60	AU	1										
FILL: Brown silty sand with gravel		SS	2	33	7	1	96.93						
Brown SILT , some sand and gravel	1.52	SS	3	59	50+								
End of Borehole	1.96												
Practical refusal to augering at 1.96m depth													



DATUM Geodetic



REMARKS

BORINGS BY Portable Drill

DATE October 16, 2020

FILE NO. **PG5663**

HOLE NO. **BH 6-20**

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %					
GROUND SURFACE								20	40	60	80		
Concrete slab	0.16					0	97.92						
FILL: Brown silty sand		SS	1	83									
		SS	2	67		1	96.92						
		SS	3	60									
BEDROCK: Poor to fair quality, grey limestone interbedded with shale		RC	1	100	42	2	95.92						
		RC	2	100	36								
		RC	3	100	47								
		RC	4	100	0		3	94.92					
		RC	5	100	0								
		RC	6	69	0								
		RC	7	100	55		4	93.92					
End of Borehole (GWL @ 1.35m - Oct. 19, 2020)	4.47												
								20	40	60	80	100	
								Shear Strength (kPa)					
								▲ Undisturbed △ Remoulded					

DATUM Geodetic

REMARKS


BORINGS BY Portable Drill

DATE October 16, 2020

FILE NO. **PG5663**

HOLE NO. **BH 7-20**

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction
		TYPE	NUMBER	RECOVERY %	N VALUE or RQD			○ Water Content %				
GROUND SURFACE							20	40	60	80		
Concrete slab	0.13				0	97.98						
FILL: Brown silty sand with crushed stone	0.56	SS	1	83								
FILL: Brown silty sand, trace gravel, clay and crushed stone		SS	2	67	1	96.98						
		SS	3	42								
	1.80				2	95.98						
Compact, brown SILT, some sand, occasional gravel		SS	4	58								
	2.74											
BEDROCK: Poor to fair quality, grey limestone interbedded with shale		RC	1	100	70	3	94.98					
		RC	2	100	0							
		RC	3	100	50							
		RC	4	100	42							
		RC	5	100	31	4	93.98					
		RC	6	100	30							
		RC	7	100	42							
		RC	8	100	33	5	92.98					
		RC	98	100	50							
End of Borehole (GWL @ 1.81m - Oct. 21, 2020)	5.49											





JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Geotechnical and Environmental Engineers
28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II Environmental Site Assessment
1649 Montreal Road
Gloucester, Ontario

DATUM

REMARKS

BORINGS BY CME 55 Power Auger

DATE 6 DEC 00

FILE NO.

E2071

HOLE NO.

BH 1

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				MONITORING WELL CONSTRUCTION	
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit %	20	40	60		80
GROUND SURFACE													
Asphaltic concrete	0.05	AU	1			0							
FILL: Light brown to brown sand		SS	2	50	2	1							
		SS	3	75	4	2							
Firm, grey SILTY CLAY, trace sand	1.83 2.13												
Compact, grey to brown SILTY SAND, some gravel		SS	4	67	21	3							
		SS	5	33	8								
End of Borehole	3.50												
Spoon refusal @ 3.50m depth													
(Open hole WL @ 0.8m depth)													
								100	200	300	400	500	
								Gastech 1314 Rdg. (ppm)					
								▲ Full Gas Resp. Δ Methane Elim.					



JOHN D. PATERSON & ASSOCIATES LTD.
 Consulting Geotechnical and Environmental Engineers
 28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II Environmental Site Assessment
 1649 Montreal Road
 Gloucester, Ontario

DATUM

REMARKS

BORINGS BY CME 55 Power Auger

DATE 7 DEC 00

FILE NO.

E2071

HOLE NO.

BH 2

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				MONITORING WELL CONSTRUCTION	
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit %	20	40	60		80
GROUND SURFACE						0							
Dark brown sandy TOPSOIL	0.25												
FILL: Brown sand, some gravel, trace silt		SS	6	50	10	1							
		SS	7	50	11	2							
		SS	8	58	17	3							
		SS	9	33	2	3.81							
End of Borehole	3.81	SS	10	100									
Spoon refusal @ 3.81m depth													
(Open hole WL @ 2.0m depth)													
								100	200	300	400	500	
								Gastech 1314 Rdg. (ppm)					
								▲ Full Gas Resp. Δ Methane Elim.					



JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Geotechnical and Environmental Engineers
28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II Environmental Site Assessment
1649 Montreal Road
Gloucester, Ontario

DATUM

REMARKS

BORINGS BY CME 55 Power Auger

DATE 6 DEC 00

FILE NO.

E2071

HOLE NO.

BH 3

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				MONITORING WELL CONSTRUCTION	
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit %	20	40	60		80
GROUND SURFACE													
Asphaltic concrete	0.05					0							
FILL: Light brown sand to sand, clay and gravel mixture	XXXXXX	AU	11										
		SS	12	44	12	1							
Stiff, dark brown SILTY CLAY	1.37												
Compact, dark grey SILTY SAND-GRAVEL	SS	SS	13	67	13	2							
		SS	14		4								
End of Borehole	2.74												
Spoon refusal @ 2.74m depth													
(Open hole WL @ 1.8m depth)													
								100	200	300	400	500	
								Gastech 1314 Rdg. (ppm)					
								▲ Full Gas Resp. Δ Methane Elim.					



JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Geotechnical and Environmental Engineers
28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II Environmental Site Assessment
1649 Montreal Road
Gloucester, Ontario

DATUM

REMARKS

BORINGS BY Portable Drill

DATE 7 DEC 00

FILE NO.

E2071

HOLE NO.

CH 4

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				MONITORING WELL CONSTRUCTION	
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit %	20	40	60		80
GROUND SURFACE						0							
Concrete slab	0.18												
FILL: Light brown to brown sand, trace to some gravel		SS	1		20								
		SS	2		10	1							
		SS	3		22								
		SS	4										
End of Corehole	1.88												
Spoon refusal @ 1.88m depth													
								100	200	300	400	500	
								Gastech 1314 Rdg. (ppm)					
								▲ Full Gas Resp. Δ Methane Elim.					



JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Geotechnical and Environmental Engineers
28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II Environmental Site Assessment
1649 Montreal Road
Gloucester, Ontario

DATUM

REMARKS

BORINGS BY Portable Drill

DATE 7 DEC 00

FILE NO.

E2071

HOLE NO.

CH 5

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				MONITORING WELL CONSTRUCTION	
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit %	20	40	60		80
GROUND SURFACE						0							
Concrete slab	0.10												
FILL: Reddish brown to brown sand		SS	5		3								
		SS	6		2	1							
		SS	7										
End of Corehole	1.96												
Spoon refusal @ 1.96m depth													
								100	200	300	400	500	
								Gastech 1314 Rdg. (ppm)					
								▲ Full Gas Resp. Δ Methane Elim.					



JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Geotechnical and Environmental Engineers
28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II Environmental Site Assessment
1649 Montreal Road
Gloucester, Ontario

DATUM

REMARKS

BORINGS BY Portable Drill

DATE 7 DEC 00

FILE NO.

E2071

HOLE NO.

CH 6

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				MONITORING WELL CONSTRUCTION	
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit %					
								20	40	60	80		
GROUND SURFACE						0							
Concrete slab	0.13												
FILL: Light brown to brown sand		SS	8		15								
		SS	9		8	1							
		SS	10										
End of Corehole	1.96												
Spoon refusal @ 1.96m depth													
								100	200	300	400	500	
								Gastech 1314 Rdg. (ppm)					
								▲ Full Gas Resp. Δ Methane Elim.					



JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Engineers

28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II-Environmental Site Assessment
 1651 Montreal Road and 741 Blair Road
 Ottawa (Gloucester), Ontario

DATUM

FILE NO.

E2662

REMARKS

HOLE NO.

BH 1

BORINGS BY CME 55 Power Auger

DATE 17 JUN 03

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit %	20	40	60		80
GROUND SURFACE						0							
TOPSOIL													
FILL: Brown silty fine to medium sand with crushed gravel	0.18	AU	1										
	0.70												
Very dense, brown SILTY SAND-GRAVEL with cobbles		SS	2	33	72	1							
		SS	3	50	68	2							
		SS	4	38	69								
End of Borehole	2.92												
Practical refusal to augering @ 2.92m depth (Open hole WL @ 2.5m depth)													

100 200 300 400 500
Gastech 1314 Rdg. (ppm)
 ▲ Full Gas Resp. △ Methane Elim.



JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Engineers

28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II-Environmental Site Assessment
 1651 Montreal Road and 741 Blair Road
 Ottawa (Gloucester), Ontario

DATUM

FILE NO.

E2662

REMARKS

HOLE NO.

BH 2A

BORINGS BY CME 55 Power Auger

DATE 17 JUN 03

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit % 20 40 60 80				
GROUND SURFACE						0						
TOPSOIL	0.23											
FILL: Dark brown silty fine to medium sand with organic matter		AU	5									
		SS	6	27	50+	1						
End of Borehole	1.37											
Practical refusal to augering @ 1.37m depth (Open hole WL @ 1.0m depth)												

100 200 300 400 500
Gastech 1314 Rdg. (ppm)
 ▲ Full Gas Resp. △ Methane Elim.



JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Engineers

28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II-Environmental Site Assessment
 1651 Montreal Road and 741 Blair Road
 Ottawa (Gloucester), Ontario

DATUM

FILE NO.

E2662

REMARKS

HOLE NO.

BH 2B

BORINGS BY CME 55 Power Auger

DATE 17 JUN 03

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit %	20	40	60		80
GROUND SURFACE						0							
TOPSOIL	0.10												
FILL: Brown silty fine to medium sand, some gravel		AU	7			1							Monitoring Well Construction
	1.30												
Very dense, brown SILTY SAND-GRAVEL with cobbles		SS	8	56	50+	2							
		AU	8A										
End of Borehole	2.74												
Practical refusal to augering @ 2.74m depth (Open hole WL @ 0.6m depth)													

100 200 300 400 500

Gastech 1314 Rdg. (ppm)

▲ Full Gas Resp. Δ Methane Elim.



JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Engineers

28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II-Environmental Site Assessment
 1651 Montreal Road and 741 Blair Road
 Ottawa (Gloucester), Ontario

DATUM

FILE NO.

E2662

REMARKS

HOLE NO.

BH 3

BORINGS BY CME 55 Power Auger

DATE 17 JUN 03

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit % 20 40 60 80				
GROUND SURFACE						0						
FILL: Dark brown silty fine to medium sand with organic matter and rock fragments		AU	9									
FILL: Brown sandy silty clay, trace gravel												
Very stiff, brown SILTY CLAY		SS	10	83	11	1						
		SS	11	79	27	2						
		SS	12	62	34	3						
Loose to very dense, brown to greyish brown SILTY fine SAND , occasional cobbles		SS	13	58	52	4						
		SS	14	29	3	4						
End of Borehole (Open hole WL @ 1.3m depth)						4.42						

100 200 300 400 500
Gastech 1314 Rdg. (ppm)
 ▲ Full Gas Resp. △ Methane Elim.



JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Engineers

28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II-Environmental Site Assessment
1651 Montreal Road and 741 Blair Road
Ottawa (Gloucester), Ontario

DATUM

FILE NO.

E2662


REMARKS

HOLE NO.

BH 4

BORINGS BY CME 55 Power Auger

DATE 17 JUN 03





JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Engineers

28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II-Environmental Site Assessment
 1651 Montreal Road and 741 Blair Road
 Ottawa (Gloucester), Ontario

DATUM

FILE NO.

E2662

REMARKS

HOLE NO.

BH 5

BORINGS BY CME 55 Power Auger

DATE 17 JUN 03

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction		
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit %	20	40	60		80	
GROUND SURFACE						0								
FILL: Brown silty fine to medium sand with crushed gravel, cobbles and asphalt pieces		AU	22				0							
1.17		SS	23	33	29	1								
FILL: Crushed rock, some silty sand		SS	24	21	65 +		2							
2.18														
End of Borehole														
Practical refusal to augering @ 2.18m depth.														

100 200 300 400 500

Gastech 1314 Rdg. (ppm)

▲ Full Gas Resp. Δ Methane Elim.



JOHN D. PATERSON & ASSOCIATES LTD.

Consulting Engineers

28 Concourse Gate, Unit 1, Nepean, Ont. K2E 7T7

SOIL PROFILE & TEST DATA

Phase II-Environmental Site Assessment
 1651 Montreal Road and 741 Blair Road
 Ottawa (Gloucester), Ontario

DATUM

FILE NO.

E2662

REMARKS

HOLE NO.

BH 6

BORINGS BY CME 55 Power Auger

DATE 17 JUN 03

SOIL DESCRIPTION	STRATA PLOT	SAMPLE				DEPTH (m)	ELEV. (m)	Pen. Resist. Blows/0.3m ● 50 mm Dia. Cone				Monitoring Well Construction	
		TYPE	NUMBER	% RECOVERY	N VALUE or RQD			○ Lower Explosive Limit %	20	40	60		80
GROUND SURFACE													
Asphaltic concrete	0.05					0							
FILL: Brown sand with crushed gravel		AU	25										
		AU	26										
End of Borehole	1.01					1							
Practical refusal to augering @ 1.01m depth													

100 200 300 400 500

Gastech 1314 Rdg. (ppm)

▲ Full Gas Resp. △ Methane Elim.

SYMBOLS AND TERMS

SOIL DESCRIPTION

Behavioural properties, such as structure and strength, take precedence over particle gradation in describing soils. Terminology describing soil structure are as follows:

Desiccated	-	having visible signs of weathering by oxidation of clay minerals, shrinkage cracks, etc.
Fissured	-	having cracks, and hence a blocky structure.
Varved	-	composed of regular alternating layers of silt and clay.
Stratified	-	composed of alternating layers of different soil types, e.g. silt and sand or silt and clay.
Well-Graded	-	Having wide range in grain sizes and substantial amounts of all intermediate particle sizes (see Grain Size Distribution).
Uniformly-Graded	-	Predominantly of one grain size (see Grain Size Distribution).

The standard terminology to describe the strength of cohesionless soils is the relative density, usually inferred from the results of the Standard Penetration Test (SPT) 'N' value. The SPT N value is the number of blows of a 63.5 kg hammer, falling 760 mm, required to drive a 51 mm O.D. split spoon sampler 300 mm into the soil after an initial penetration of 150 mm.

Relative Density	'N' Value	Relative Density %
Very Loose	<4	<15
Loose	4-10	15-35
Compact	10-30	35-65
Dense	30-50	65-85
Very Dense	>50	>85

The standard terminology to describe the strength of cohesive soils is the consistency, which is based on the undisturbed undrained shear strength as measured by the in situ or laboratory vane tests, penetrometer tests, unconfined compression tests, or occasionally by Standard Penetration Tests.

Consistency	Undrained Shear Strength (kPa)	'N' Value
Very Soft	<12	<2
Soft	12-25	2-4
Firm	25-50	4-8
Stiff	50-100	8-15
Very Stiff	100-200	15-30
Hard	>200	>30

SYMBOLS AND TERMS (continued)

SOIL DESCRIPTION (continued)

Cohesive soils can also be classified according to their "sensitivity". The sensitivity is the ratio between the undisturbed undrained shear strength and the remoulded undrained shear strength of the soil.

Terminology used for describing soil strata based upon texture, or the proportion of individual particle sizes present is provided on the Textural Soil Classification Chart at the end of this information package.

ROCK DESCRIPTION

The structural description of the bedrock mass is based on the Rock Quality Designation (RQD).

The RQD classification is based on a modified core recovery percentage in which all pieces of sound core over 100 mm long are counted as recovery. The smaller pieces are considered to be a result of closely-spaced discontinuities (resulting from shearing, jointing, faulting, or weathering) in the rock mass and are not counted. RQD is ideally determined from NXL size core. However, it can be used on smaller core sizes, such as BX, if the bulk of the fractures caused by drilling stresses (called "mechanical breaks") are easily distinguishable from the normal in situ fractures.

RQD %	ROCK QUALITY
90-100	Excellent, intact, very sound
75-90	Good, massive, moderately jointed or sound
50-75	Fair, blocky and seamy, fractured
25-50	Poor, shattered and very seamy or blocky, severely fractured
0-25	Very poor, crushed, very severely fractured

SAMPLE TYPES

SS	-	Split spoon sample (obtained in conjunction with the performing of the Standard Penetration Test (SPT))
TW	-	Thin wall tube or Shelby tube
PS	-	Piston sample
AU	-	Auger sample or bulk sample
WS	-	Wash sample
RC	-	Rock core sample (Core bit size AXT, BXL, etc.). Rock core samples are obtained with the use of standard diamond drilling bits.

SYMBOLS AND TERMS (continued)

GRAIN SIZE DISTRIBUTION

MC%	-	Natural moisture content or water content of sample, %
LL	-	Liquid Limit, % (water content above which soil behaves as a liquid)
PL	-	Plastic limit, % (water content above which soil behaves plastically)
PI	-	Plasticity index, % (difference between LL and PL)
D _{xx}	-	Grain size which xx% of the soil, by weight, is of finer grain sizes These grain size descriptions are not used below 0.075 mm grain size
D ₁₀	-	Grain size at which 10% of the soil is finer (effective grain size)
D ₆₀	-	Grain size at which 60% of the soil is finer
C _c	-	Concavity coefficient = $(D_{30})^2 / (D_{10} \times D_{60})$
C _u	-	Uniformity coefficient = D_{60} / D_{10}

C_c and C_u are used to assess the grading of sands and gravels:

Well-graded gravels have: $1 < C_c < 3$ and $C_u > 4$

Well-graded sands have: $1 < C_c < 3$ and $C_u > 6$

Sands and gravels not meeting the above requirements are poorly-graded or uniformly-graded.

C_c and C_u are not applicable for the description of soils with more than 10% silt and clay (more than 10% finer than 0.075 mm or the #200 sieve)

CONSOLIDATION TEST

p' _o	-	Present effective overburden pressure at sample depth
p' _c	-	Preconsolidation pressure of (maximum past pressure on) sample
C _{cr}	-	Recompression index (in effect at pressures below p' _c)
C _c	-	Compression index (in effect at pressures above p' _c)
OC Ratio		Overconsolidation ratio = p'_c / p'_o
Void Ratio		Initial sample void ratio = volume of voids / volume of solids
W _o	-	Initial water content (at start of consolidation test)

PERMEABILITY TEST

k	-	Coefficient of permeability or hydraulic conductivity is a measure of the ability of water to flow through the sample. The value of k is measured at a specified unit weight for (remoulded) cohesionless soil samples, because its value will vary with the unit weight or density of the sample during the test.
---	---	--

SYMBOLS AND TERMS (continued)


STRATA PLOT



Topsoil




Asphalt




Fill




Peat



Sand




Silty Sand




Silt



Sandy Silt



Clay




Silty Clay




Clayey Silty Sand



Glacial Till




Shale




Bedrock

MONITORING WELL AND PIEZOMETER CONSTRUCTION

MONITORING WELL CONSTRUCTION



PIEZOMETER CONSTRUCTION



Photographs of Rock Cores

Photo 1: Photograph of RC 1 from BH 1-23 – Depth from 2.34 to 3.18 m – RQD = 82 % and REC = 100 %



Photo 2: Photograph of RC 2 from BH 1-23 – Depth from 3.18 to 4.65 m – RQD = 72 % and REC = 100 %



Photographs of Rock Cores

Photo 3: Photograph of RC 3 from BH 1-23 – Depth from 4.65 to 6.15 m – RQD = 47 % and REC = 100 %



Photo 4: Photograph of RC 4 from BH 1-23 – Depth from 6.15 to 7.65 m – RQD = 59 % and REC = 100 %



Photo 5: Photograph of RC 5 from BH 1-23 – Depth from 7.65 to 9.14 m – RQD = 46 % and REC = 93 %



Photo 6: Photograph of RC 6 from BH 1-23 – Depth from 9.14 to 10.64 m – RQD = 68 % and REC = 89 %



Photo 7: Photograph of RC 7 from BH 1-23 – Depth from 10.64 to 12.14 m –
RQD = 56 % and REC = 100 %



Photo 8: Photograph of RC 8 from BH 1-23 – Depth from 12.14 to 13.64 m –
RQD = 56 % and REC = 93 %



Photo 9: Photograph of RC 9 from BH 1-23 – Depth from 13.64 to 15.14 m –
RQD = 14 % and REC = 100 %



Photo 10: Photograph of RC 10 from BH 1-23 – Depth from 15.14 to 16.51 m –
RQD = 59 % and REC = 100 %



Photographs of Rock Cores

Photo 11: Photograph of RC 11 from BH 1-23 – Depth from 16.51 to 18.39 m –
RQD = 53 % and REC = 100 %



Photo 12: Photograph of RC 1 from BH 2-23 – Depth from 2.51 to 3.18 m –
RQD = 62 % and REC = 100 %



Photo 13: Photograph of RC 2 from BH 2-23 – Depth from 3.18 to 4.67 m –
RQD = 76 % and REC = 100 %



Photo 14: Photograph of RC 3 from BH 2-23 – Depth from 4.67 to 6.17 m –
RQD = 73 % and REC = 100 %



Photo 15: Photograph of RC 4 from BH 2-23 – Depth from 6.17 to 7.67 m –
RQD = 71 % and REC = 100 %



Photo 16: Photograph of RC 5 from BH 2-23 – Depth from 7.67 to 9.17 m –
RQD = 59 % and REC = 100 %



Photo 17: Photograph of RC 6 from BH 2-23 – Depth from 9.17 to 10.67 m –
RQD = 42 % and REC = 100 %



Photo 18: Photograph of RC 7 from BH 2-23 – Depth from 10.67 to 12.17 m –
RQD = 93 % and REC = 100 %



Photo 19: Photograph of RC 8 from BH 2-23 – Depth from 12.17 to 13.67 m –
RQD = 85 % and REC = 100 %



Photo 20: Photograph of RC 9 from BH 2-23 – Depth from 13.67 to 15.16 m –
RQD= 47 % and REC = 85 %



Photo 21: Photograph of RC 10 from BH 2-23 – Depth from 15.16 to 16.69 m –
RQD = 37 % and REC = 80 %



Photo 22: Photograph of RC 11 from BH 2-23 – Depth from 16.69 to 18.16 m –
RQD = 41 % and REC = 98 %



Photo 23: Photograph of RC 1 from BH 4-23 – Depth from 0.66 to 1.63 m – RQD = 26 % and REC = 100 %



Photo 24: Photograph of RC 2 from BH 4-23 – Depth from 1.63 to 3.12 m – RQD = 59 % and REC = 100 %



Photo 25: Photograph of RC 3 from BH 4-23 – Depth from 3.12 to 4.62 m – RQD = 73 % and REC = 100 %



Photo 26: Photograph of RC 4 from BH 4-23 – Depth from 4.62 to 6.12 m – RQD = 64 % and REC = 100 %



Photo 27: Photograph of RC 5 from BH 4-23 – Depth from 6.12 to 7.62 m – RQD = 90 % and REC = 100 %



Photo 28: Photograph of RC 6 from BH 4-23 – Depth from 7.62 to 9.12 m – RQD = 97 % and REC = 100 %



Photo 29: Photograph of RC 7 from BH 4-23 – Depth from 9.12 to 10.62 m –
RQD = 85 % and REC = 100 %



Photo 30: Photograph of RC 8 from BH 4-23 – Depth from 10.62 to 12.12 m –
RQD = 86 % and REC = 100 %



Photo 31: Photograph of RC 9 from BH 4-23 – Depth from 12.12 to 13.61 m –
RQD = 88 % and REC = 100 %



Photo 32: Photograph of RC 10 from BH 4-23 – Depth from 13.61 to 15.11 m –
RQD = 100 % and REC = 100 %



Photo 33: Photograph of RC 11 from BH 4-23 – Depth from 15.11 to 16.64 m – RQD = 83 % and REC = 100 %



Photo 34: Photograph of RC 1 from BH 5-23 – Depth from 5.72 to 6.32 m – RQD = 0 % and REC = 100 %



Photo 35: Photograph of RC 2 from BH 5-23 – Depth from 6.32 to 7.04 m –
RQD = 60 % and REC = 100 %



Photo 36: Photograph of RC 3 from BH 5-23 – Depth from 7.04 to 8.69 m –
RQD = 49 % and REC = 100 %



Photo 37: Photograph of RC 4 from BH 5-23 – Depth from 8.69 to 10.13 m –
RQD = 63 % and REC = 100 %



Photo 38: Photograph of RC 5 from BH 5-23 – Depth from 10.13 to 11.63 m –
RQD = 32 % and REC = 100 %



Photo 39: Photograph of RC 6 from BH 5-23 – Depth from 11.63 to 13.00 m –
RQD = 69 % and REC = 98 %



Photo 40: Photograph of RC 7 from BH 5-23 – Depth from 13.00 to 14.40 m –
RQD = 75 % and REC = 100 %



Photo 41: Photograph of RC 8 from BH 5-23 – Depth from 14.40 to 16.59 m – RQD = 5 % and REC = 50 %



Photo 42: Photograph of RC 9 from BH 5-23 – Depth from 16.59 to 18.11 m – RQD = 57 % and REC = 100 %



Photo 43: Photograph of RC 10 from BH 5-23 – Depth from 18.11 to 19.58 m – RQD = 50 % and REC = 100 %



Photo 44: Photograph of RC 11 from BH 5-23 – Depth from 19.58 to 21.18 m – RQD = 52 % and REC = 100 %



APPENDIX 2

FIGURE 1 - KEY PLAN

FIGURES 2 & 3 – SEISMIC SHEAR WAVE VELOCITY PROFILES

DRAWING PG5663-1 - TEST HOLE LOCATION PLAN

DRAWING PG5663-2 – BEDROCK QUALITY ZONE PLAN




FIGURE 1

KEY PLAN




Figure 2 – Shear Wave Velocity Profile at Shot Location -1.5 m






Figure 3 – Shear Wave Velocity Profile at Shot Location 18 m



- LEGEND:**
- BOREHOLE LOCATION
 - BOREHOLE WITH MONITORING WELL LOCATION
 - BOREHOLE LOCATION (PATERSON GROUP REPORT E2662-1, JULY 2003)
 - BOREHOLE LOCATION (PATERSON GROUP REPORT E2071-1, MAY 2001)
 - 97.76 GROUND SURFACE ELEVATION (m)
 - [95.24] BEDROCK SURFACE ELEVATION (m)
 - (95.95) PRACTICAL REFUSAL TO AUGERING
 - GEOPHONE LOCATIONS
 - GEOPHONE NUMBER
 - SHOT LOCATION
- CONCEPTUAL PLAN PROVIDED BY RLA ARCHITECTURE.
- GROUND SURFACE ELEVATIONS AT BOREHOLE LOCATIONS ARE REFERENCED TO A GEODETIC DATUM.
- SCALE: 1:400
-

PATERSON GROUP

9 AURIGA DRIVE
OTTAWA, ON
K2E 7S9
TEL: (613) 226-7381

NO.	REVISIONS	DATE	INITIAL
3	ADDED LATEST CONCEPTUAL PLAN	02/08/2024	NP
2	ADDED 2023 BOREHOLE LOCATIONS TO PLAN	27/04/2023	YZ
1	ADDED SEISMIC SHEAR WAVE VELOCITY TEST LOCATION	08/08/2022	FC

10869279 CANADA INC.

**GEOTECHNICAL INVESTIGATION
PROPOSED HIGH-RISE BUILDING**

1649 MONTREAL ROAD AND 741 BLAIR ROAD


ONTARIO

OTTAWA,
Title:

TEST HOLE LOCATION PLAN

Scale:	1:400	Date:	01/2021
Drawn by:	YA	Report No.:	PG5663-1
Checked by:	NP	Dwg. No.:	PG5663-1
Approved by:	DJG	Revision No.:	3

p:\autocad\drawings\geotechnical\pg5663\pg5663-1-test hole location plan (rev.03).dwg



- LEGEND:**
- BOREHOLE LOCATION
 - BOREHOLE WITH MONITORING WELL LOCATION
 - BOREHOLE LOCATION (PATERSON GROUP REPORT E2662-1, JULY 2003)
 - BOREHOLE LOCATION (PATERSON GROUP REPORT E2071-1, MAY 2001)
 - 97.76 GROUND SURFACE ELEVATION (m)
 - [95.24] BEDROCK SURFACE ELEVATION (m)
 - (95.95) PRACTICAL REFUSAL TO AUGERING
 - GEOPHONE LOCATIONS
 - GEOPHONE NUMBER
 - SHOT LOCATION

CONCEPTUAL PLAN PROVIDED BY RLA ARCHITECTURE.

GROUND SURFACE ELEVATIONS AT BOREHOLE LOCATIONS ARE REFERENCED TO A GEODETIC DATUM.

SCALE: 1:400

- BEDROCK QUALITY ZONE LEGEND:**
- ZONE 1: VERY POOR TO FAIR QUALITY BEDROCK EXTENDING BELOW ANTICIPATED DESIGN USF LEVEL
 - ZONE 2: GOOD OR EXCELLENT QUALITY BEDROCK EXTENDING BELOW ANTICIPATED DESIGN USF LEVEL

9 AURIGA DRIVE
OTTAWA, ON
K2E 7S9
TEL: (613) 226-7381

NO.	REVISIONS	DATE	INITIAL
1	ADDED LATEST CONCEPTUAL PLAN	02/08/2024	NP

10869279 CANADA INC.
GEOTECHNICAL INVESTIGATION
PROPOSED HIGH-RISE BUILDING
 1649 MONTREAL ROAD AND 741 BLAIR ROAD
 OTTAWA, ONTARIO

Title: **BEDROCK QUALITY ZONE PLAN**

Scale:	1:400	Date:	05/2023
Drawn by:	NFRV	Report No.:	PG5663-1
Checked by:	NP	Dwg. No.:	PG5663-2
Approved by:	DJG	Revision No.:	1

p:\autocad\drawings\geotechnical\pg5663\pg5663-1-test-hole location plan (rev.03).dwg