



Kollaard Associates

Engineers

210 Prescott Street

P.O. Box 189

Kemptville, Ontario K0G 1J0

Civil • Geotechnical •
Structural • Environmental •
Hydrogeology •

(613) 860-0923

FAX: (613) 258-0475

REPORT ON

**HYDROGEOLOGICAL AND TERRAIN STUDY
PROPOSED COMMERCIAL BUILDINGS
3904 MARCH ROAD
CITY OF OTTAWA
ONTARIO**

Submitted to:

Dog World Kennel
3904 March Road
Carp, Ontario
K0A 1L0

DATE April 25, 2022

DISTRIBUTION

1 digital copy City of Ottawa
1 digital copy Tracy Kim Holden
1 copy Kollaard Associates Inc.

190622



Kollaard Associates

Engineers

210 Prescott Street

P.O. Box 189

Kemptville, Ontario K0G 1J0

Civil • Geotechnical •
Structural • Environmental •
Hydrogeology •

(613) 860-0923

FAX: (613) 258-0475

April 25, 2022

190622

Dog World Bedrock Kennels
3904 March Road
Carp, Ontario
K0A 1L0

Attention: Ms. Tracy Kim Holden

RE: HYDROGEOLOGICAL AND TERRAIN STUDY
EXISTING SUPPLY WELL
PROPOSED COMMERCIAL BUILDINGS
3904 MARCH ROAD
WEST CARLETON-MARCH WARD
CITY OF OTTAWA, ONTARIO

Dear Madam:

This letter presents the results of an evaluation of the water quality and quantity for the well that will supply water for the above noted proposed expansion to an existing mixed used commercial and residential property at 3904 March Road, City of Ottawa, Ontario (see Key Plan, Figure 1). It is understood that the proposed development is to consist of an expansion of an existing dog kennel business on a property that also contains a single family dwelling.

The well in question was constructed by George H. Law and Son Ltd. of Calibogie, Ontario on September 24, 2000. A Ministry of the Environment, Conservation and Parks (MECP) Well Record for the subject well (TW1) and a Certificate of Well Compliance is provided as Attachment A.

This report consists of an evaluation of the water quality and quantity of an existing well on the subject property to ensure that the water quality and quantity of future wells drilled on the other proposed severed properties is acceptable using the following guidelines; Ministry of the Environment, Conservation and Parks (MECP) Guideline D-5-5 and the Ontario Drinking Water Standards, Objectives and Guidelines (ODWSOG). Consideration has also been given to the groundwater impact assessment guidelines under MECP D-5-4. A pumping test was carried out at the well, TW1, by a member of our engineering staff on October 7, 2020. The terrain study includes information from boreholes installed at the site to determine the soil and groundwater conditions with regards to sewage impact considerations.

Background

Based on a review of the surficial geology map for the site area, it is expected that the site is underlain by stone-poor sandy silt to silty sand-textured till on Paleozoic Terrain. Bedrock geology mapping indicates that the bedrock underlying the site consists of limestone, dolostone, shale and sandstone of the Ottawa Group, Simcoe Group and Shadow Lake Formation.



Based on a review of overburden thickness mapping for the site area, the overburden is estimated to be between about 0 to 10 metres in thickness above bedrock in the area. The three boreholes put down as part of a geotechnical investigation at the site indicates soil types of sand, silt and silty clay with overburden thicknesses of some 3.6 to 4.5 metres were encountered in boreholes put down at the site. The groundwater elevation was observed at 0.8 to 0.9 metres below existing ground surface on May 28, 2020.

GROUNDWATER SUPPLY INVESTIGATION

Water Demand

The water demand is calculated using the information from the sewage system daily design flow and the City of Ottawa Water Distribution Guidelines, 2010. The sewage design flows are provided below, based on the sewage design information (preliminary sewage design by Kollaard Associates Inc.). The calculations are as follows:

Commercial Daily sewage design flow:

- Existing (20 cages plus 6 employees) and Proposed Dog Kennel (plus additional 19 cages and 6 employees)
- 75 litres per cage x 39 cages = 2,925 L/day
- 75 litres per employee x 12 employees = 900 L/day
- Total Commercial design flow = 5,025 L/day

Existing Residential Water demand:

- 4 bedroom home, per person water demand based on 450 L/day per person = 2,250 L/day
- MHD = 5 x 3.75 L/min/person = 18.75 L/min

TOTAL WATER DEMAND = 7,275 Litres Per Day

Since sewage system design is based on the maximum expected daily use, it is equivalent to the Average Daily Demand (ADD). The ADD is based on an eight hour operation schedule (i.e. full day occurs over an eight hour period and not over 24 hours).

City of Ottawa calculates the Maximum Hour Demand (MHD) for a commercial or industrial demand to be 1.8 x MDD.

$$\begin{aligned} \text{MDD} &= 5,025 \text{ litres / day} \times 1 \text{ day} / 8 \text{ hours} \times 1 \text{ hour} / 60 \text{ minutes} \\ &= 10.5 \text{ litres / minute} \end{aligned}$$

$$\begin{aligned} \text{MHD} &= 1.8 \times \text{MDD} \\ &= 1.8 \times 10.5 \text{ litres / minute} \\ &= 18.9 \text{ litres / minute} \end{aligned}$$

Alternatively, the City of Ottawa Water Distribution Guideline Section 4.2.8 indicates the average water demand for commercial usage is 28,000 L/gross ha/day. The gross area of the site is 9.6 hectares. However, this is not an appropriate way to calculate the commercial water demand on



the site as the site is very sparsely developed over its area. The total building footprint after development (based on the Stormwater Report) is 1,440 square metres, with some 2,640 square metres of gravel surfaced areas. As such, the total developed area (including parking) for the commercial use is 4,080 square metres (0.4 ha). This represents only 4% of the site area. That is the area used for the following calculation.

$$\begin{aligned} \text{ADD} &= 0.4 \text{ ha} \times 28,000 \text{ L/gross ha/day} \\ &= 7.8 \text{ L/min} \\ \text{MDD} &= 1.5 \times \text{ADD} \\ &= 11.7 \text{ L/min} \\ \text{MHD} &= 11.7 \text{ L/min} \times 1.8 = 21.1 \text{ L/min} \end{aligned}$$

Using the more conservative figure for groundwater usage, the City of Ottawa predicated water usage for MDD and MHD of 11.7 L/min and 21.1 L/min, respectively, are used. As the well is also supplying water for residential demand, the peak residential demand rate is also considered as an additional water demand of 18.75 L/min. It should be noted that these peaks are unlikely to coincide as residential peaks occur usually early in the morning and in the early evening, whereas commercial water demand is typical throughout the daily operations between 8 am and 5 pm.

The Maximum Hourly Demand (MHD) for the site based on its proposed use is expected to be about ~39.9 litres/minute, compared to the pumping test rate which was 57 litres/minute.

Water Quantity

The well was pumped for six hours at a pumping rate of about 57 litres per minute. Over the course of the pumping test, the water level in the well dropped some ~0.4 metres. At the end of the pumping test, about 3 hours and 10 minutes was required for 100 percent recovery of the total drawdown in the static water level created during pumping.

The pumping test drawdown and recovery data and plots for TW1 are provided as Attachment B. The drawdown and recovery data provided were measured with reference to the top of the well casing at the test well location.

The pumping test data for the test well was analyzed using the method of Cooper and Jacob (1946). Although the assumptions on which these equations are based are not strictly met, this method provides a reasonable estimate of the aquifer transmissivity.

Transmissivity was calculated using the following relationship:

$$T = \frac{2.3Q}{4\pi ds}$$

where Q is the pump rate, m³/day
ds is the change in drawdown over one time log cycle, m
T is the transmissivity, m²/day

$$\begin{aligned} \text{Specific Capacity} &= Q / \text{TD} \\ &= 81.9 \text{ m}^3/\text{day} / 0.41 \text{ m} \\ &= 199.7 \text{ m}^3/\text{day/m} \end{aligned}$$

where Q = test pumping rate (m³/day)
TD = total drawdown (m)



Based on the pumping test drawdown data the transmissivity of the aquifer is estimated to be about 83 m²/day. Based on the recovery data the aquifer transmissivity is estimated to be about 52 m²/day. It should be noted that pumping tests should typically be carried out for a period of between 24 hours or greater to establish transmissivity for a confined aquifer in order to assess boundary conditions. Over the course of the six hour test, some ~20,450 litres of water was pumped from the well and only 3% of the available drawdown was used. The available drawdown at the well is about 12.9 metres (based on recommended pump intake and static water level at the time of the test). As the expected maximum daily water demand is about 7,275 litres per day, the expected drawdown at the well is well within the available drawdown for the well.

Water Quality

To determine the water quality of the groundwater supply, groundwater samples were obtained from the well during the pumping test and prepared/preserved in the field using appropriate techniques and submitted to Eurofins Environmental Testing in Ottawa, Ontario for the chemical, physical and bacteriological analyses listed in the MECP guideline entitled Procedure D-5-5, Technical Guideline for Private Wells: Water Supply Assessment, August 1996. The temperature, conductivity, pH, total dissolved solids, turbidity and residual chlorine levels of the groundwater were measured at periodic intervals during the pumping test. The results of the chemical, physical and bacteriological analyses of the water samples obtained from the test well and the field water quality are provided as Attachment C and in Table I, respectively.

The water quality as determined from the results of the analyses is acceptable. The water meets all the Ontario Drinking Water Standards (ODWS) health and aesthetic parameters tested for at the test well except for aesthetic objective for hardness, turbidity (lab based), iron and manganese.

Hardness

The water is considered to be hard by water treatment standards. Water with hardness above 80 to 100 milligrams per litre as CaCO₃ is often softened for domestic use. The hardness at the well is 253 to 271 milligrams per litre. Treatment consisting of water softening by conventional sodium ion exchange is effective to reduce scale formation associated with hardness. Ion exchange water softening may introduce relatively high concentrations of sodium into the drinking water. Treatment by water softening can also contribute a significant percentage to the daily sodium intake for a consumer on a sodium restricted diet. Where ion exchange water softeners are used, a separate unsoftened water supply could be used for drinking and culinary purposes. The untreated water had sodium levels that were less than the medical advisory level of 20 mg/l.

Turbidity (lab based)

The turbidity was measured hourly during the pumping test and the turbidity levels were below 5 NTU and were declining throughout pumping. However, the lab based turbidity levels were measured to be 7.3 NTU for the sample obtained after three hours and 5.5 NTU for the sample obtained after six hours. Turbidity (lab based) declined throughout pumping. It is considered that the turbidity level is due to the presence of iron and manganese, which were also present at or above their aesthetic objectives and contribute to turbidity. It is considered that with appropriate treatment to reduce iron and manganese, that turbidity is expected to be less than 5 NTU in treated water. There are concerns with regards to the level of turbidity measured in the lab sample as the field readings for turbidity are less than 5 NTU.



Iron

Iron was measured at a level of 0.68 after three hours and lowered to 0.52 mg/l after six hours, compared to the aesthetic objective of 0.3 mg/l. Excessive iron levels may cause brown or black discolouration of laundry and fixtures, affect the taste and colour of water, and iron precipitation in pipes and hot water tank can also promote the growth of iron bacteria. Iron can be effectively removed using conventional ion exchange water softeners. However, depending on the form that iron is in (reduced or oxidized) as well as the concentration levels and other factors, iron filters may be more effective in removing iron the water supply.

Manganese

The level of manganese was 0.05 mg/l and 0.06 mg/l after three and six hours, respectively. The aesthetic objective for manganese is 0.05 mg/l. Manganese can stain laundry and fixtures black. For a commercial usage, where domestic usages such as laundry are not anticipated, and the expected manganese concentration, which is elevated but did meet the aesthetic objective for one water sample, it may not be necessary to treat the water for this parameter. If desired, manganese can be effectively treated using a manganese greensand filter or some other proprietary filter for manganese removal.

Bacteria (Total Coliforms and E. Coli)

The initial testing encountered total coliform levels of 2-3 counts/100 ml and an absence of E. Coli. This was shortly after well construction and during well development. On September 29, 2021, the water was resampled once it had been connected to the existing kennel building. At that time, the total coliforms were measured to be 0 counts/100 ml. A free chlorine residual was measured to be 0.00 ppm prior to obtaining the water sample. It is considered by Kollaard Associates Inc. that the bacteriological water quality is acceptable for the supply well at the site.

Other Parameters

The investigation was carried out in 2020, prior to the City of Ottawa Hydrogeological and Terrain Analysis Guidelines, which were provided in March 2021. It is understood that the current requirements for Site Plan would include trace metals and VOCs. Other parameters may also be required, based on the land use and/or geological setting. It should be noted that the site is located in a very sparsely developed area and that previous Phase I Environmental Site Assessment did not encounter any industrial or commercial activity that would involve any handling of VOCs either at the site or within 250 metres of the site. As such, it is considered that there is no need to test for VOCs or other parameters that would represent any existing contamination. It is possible that natural strontium levels at the site may be present in relation to the water supply being limestone and sandstone which are sedimentary bedrock types in the Ottawa area which are associated with strontium. It will be noted that strontium levels could be present above the interim maximum allowable concentration (IMAC) and that water softening is an appropriate treatment to reduce strontium.

TERRAIN STUDY

Soils information was obtained from geotechnical boreholes put down at the subject site. The field work for this investigation was carried out on May 28, 2020, at which time three boreholes were put down at the site, identified as BH1, BH2 and BH3. The boreholes encountered about sand to depths of some 1.3 to 1.7 metres overlying silt followed by silty clay to depths of some 3.5 to 3.8 metres overlying silty sand and gravel. The boreholes were terminated at depths of 3.6 to 4.5



metres all with refusal to advance on either large boulders or bedrock. Water was observed at about 0.8 to 0.9 metres below the ground surface at all three boreholes.

The size of the septic envelopes are a function of the percolation time of the native soil in the vicinity of the septic envelope and/or the fill used for construction of a septic bed and the daily effluent loading to the septic bed. A preliminary sewage design was prepared by Kollaard Associates for the commercial building including the proposed expansion. The sewage system is indicated to consist of a conventional partially raised leaching bed with a contact area of 502.5 square metres. The design is based on the native silty sand soils contact area at the site having a percolation rate of about 15 min/cm. No imported mantle was needed for the sewage system design.

The sewage design is based on a daily design flow of 5,025 Litres per day on the design flow information. An existing sewage system design is in place already for the existing single family dwelling. The proposed commercial sewage system is to replace the holding tank that was previously used for the kennel which will be replaced by the proposed sewage system.

The sewage dilution calculations, provided as Attachment D, indicate that the impact is within 10 mg/l N-NO₃ for two sewage systems, including the existing sewage system for the single family dwelling and a separate sewage system for the commercial kennel.

Based on the terrain information provided, there is sufficient space at the site to accommodate the two sewage systems. They are both located along the east portion of the site with at least 30 metres of separation between the well and the sewage systems. It is considered that the operation of the sewage system at the site will not cause impact to the well on the existing site or surrounding properties. There are no other wells indicated to be within at least 100 metres or more of the proposed sewage system area at the site.

Animal Waste Disposal

An area was set aside on the property for disposal of dog waste. All solid waste from the kennels is placed at a solid manure storage location that is distant from sensitive receptors and that is not prone to significant runoff. The area is to be surrounded by a berm.

The proposed solid manure storage location is shown on Kollaard drawing 190622-SER (see attached). The manure storage location is surrounded by a berm which will prevent all stormwater originating on the area of the manure storage location from running off the site. The following Table provides a summary of the design conformance of the solid manure storage location to site requirements under the NMA regulations.

Table - Conformance of Solid Manure Storage to Regulations

Design Element	Design Objective	Minimum Criteria	Design Conformance
Minimum depth of Soil to Bedrock	minimum potential for runoff to reach bedrock	3.0 m of un-consolidated (not compacted) soil	3.6 m At least 1 m of silty clay above bedrock
Minimum depth to water table	minimum potential for runoff to reach water table	0.9 m	0.9 m to perched groundwater. Permanent ground water below surface



			of bedrock
Soil Type	minimize potential for nutrient flow into the bedrock	Cannot be Soil Group A	Soil Group B
Storage location	minimize potential for flooding	Cannot be in the floodplain	Is not in the floodplain.
Site slope	minimize runoff rate	< 3%	Relatively flat in proposed storage area <1%
Distance to Surface Water	minimize potential for surface water contamination	50 m	94 m to the regulation limit surrounding the adjacent wetland
Separations	minimize risk to drinking water and provide separation to the residence	45 m to drilled well	133
		90 m to dug well	N/A
		100 m to municipal well	N/A
		125 m to single residence	127 m

As shown in the above table, the solid waste from the facilities will be placed at a location in keeping with the requirements for the storage of solid manure. As such, the proposed practices with respect to the management of the canine feces will ensure that contamination from canine feces is not carried off of the site by stormwater runoff. There are no stormwater management ponds proposed on site.

Based on the above noted information, it is considered that the storage of dog waste at the site will be in keeping with Nutrient Management Act policies to prevent any detrimental impact on the surface water and groundwater in the area.

WELLHEAD PROTECTION / FLOODPLAIN CONSIDERATIONS

The supply well is located within the north portion of the site close to the dwelling, with the existing sewage system for the dwelling located on the east side of the site. The proposed location for the commercial sewage system is south of the existing sewage also on the east side of the property. The sewage systems are at least 30 metres or more from the existing wells. The well casing must extend to greater than 400 millimetres above grade at the time of construction. It should be verified that the top of the well casing is at least 400 millimetres above the finished grade at the well location.

Additionally, the ground surface shall be graded such that the well is the highest point on the ground surface within 3 metres radially from the exterior of the well casing and shall ensure that water does not collect or pond near the well head. The well has been grouted and cased to a depth of about 6.4 metres below the existing ground surface, according to information provided on the well record (Attachment A). The well is physically separated from the driveway by at least 3 metres. With these measures in place, it is considered that an adequate amount of wellhead protection is going to be in place to protect the water supply for the proposed commercial use of the property. The well location is also appropriate for access in case of repairs and well maintenance.

Recommendations for wellhead protection include ensuring that potential contaminant sources are at least 15 metres or more from the well. Possible contaminant sources that could be present at the site include; waste storage (dog feces), garage and related chemicals, such as antifreeze, gasoline,



oils, vehicle/boat/equipment storage, sewer lines, septic systems, animal enclosures, manure or compost piles. The sewage systems and dog waste storage area are greater than 30 metres or more from the well location.

Recommendations for well maintenance include; inspect wellhead annually to ensure that the casing is structurally sound, verify well cap is sealed and that surface water is not pooling around wellhead. The well is located such that it is easily accessible for maintenance/repairs.

Based on the results of this evaluation it is considered that the well in question should supply water of adequate quantity and quality for the proposed development with suitable treatment and wellhead protection as indicated above.

RECOMMENDATIONS

The following wellhead protection measures are required:

- Ensure that potential contaminant sources are at least 15 metres or more from the well. Possible contaminant sources that could be present at the site include; waste storage (dog feces), garage and related chemicals, such as antifreeze, gasoline, oils, vehicle/boat/equipment storage, sewer lines, septic systems, animal enclosures, manure or compost piles. The sewage systems and dog waste storage area are greater than 30 metres or more from the well location.
- Maintain well at least 3 metres from the edge of the driveway/laneway at the site to ensure adequate separation distance to prevent damage from vehicles and surface water drainage is away from the well.

The following should be considered for water quality considerations:

- Well water at the site has elevated hardness, iron, manganese and iron-related turbidity.

The following treatment considerations are recommended:

- **Hardness:** Water softening by conventional sodium ion exchange is recommended to reduce hardness. However, this is expected to introduce relatively high concentrations of sodium into the drinking water, which may contribute a significant percentage to the daily sodium intake for a consumer on a sodium restricted diet. The water may be scale forming if water softeners are not used.
- **Iron, manganese and iron-related turbidity (inorganic):** Water softening to reduce hardness should have a corresponding effect on iron, provided the water softener is designed and calibrated for iron removal. A manganese greensand filter or oxidation with filtration through a proprietary filter media may be more effective at removing iron and manganese. Treatment for iron is expected to have a corresponding effect on turbidity, which was elevated in samples that had been stored and tested at the laboratory. The field turbidity levels were less than 1 NTU.
- **Trace Metals and VOCs testing** was not carried out as the requirement for such testing has only been required after the field work for this project was carried out. It is considered that VOCs testing is not necessary for this property as it is in a rural residential setting rather than a typical commercial or industrial park setting. The Phase I ESA indicated there are no potential contaminant sources in the site vicinity. It should be noted that there is a potential for elevated strontium due to the sedimentary limestone and sandstone aquifer that is present at the site. If strontium is elevated, conventional water softening is appropriate to remove strontium from any drinking water. Strontium currently has a proposed Maximum Acceptable Concentration (MAC) by Health Canada of 7.0 mg/L. The proposed MAC is



established as there are a few studies that indicate a potential for adverse effects of strontium for humans. Since the highest sensitivity to adverse bone effects occurs in the first year of life, infants are the most sensitive to strontium toxicity. The level of strontium measured in the raw water supply at this site is 23.5 mg/L, which is above the acceptable proposed limit. Strontium may be reduced from water by the use of ion exchange water softeners or a point of use reverse osmosis treatment unit for any water used for drinking or culinary purposes.

We trust this letter provides sufficient information for your purposes. If you have any questions concerning this letter, please do not hesitate to contact our office.

Yours truly,
Kollaard Associates Inc.



Colleen Vermeersch, P. Eng.

Attachments:	Figure 1	- Key Plan
	Site Servicing Plan	- Fig. 190622-SER
	Table I	- Field Water Quality
	Attachment A	- Well Record and Certificate of Well Compliance
	Attachment B	- Pumping Test Data
	Attachment C	- Well Water Laboratory Test Results
	Attachment D	- Sewage Dilution Calculations

KEY PLAN

FIGURE 1




NOT TO SCALE



Kollaard Associates
Engineers


Project No. 190622
Date April 2022




KEY PLAN
NOT TO SCALE

LEGEND

	EXISTING ELEVATION
	PROPOSED/EXISTING ELEVATIONS
	PROPOSED ELEVATION
	DRAINAGE SLOPE
	EXISTING DRAINAGE
	CENTRELINE OF ROAD
	EDGE OF ROAD
	TOP OF SLOPE
	PROPERTY LINE
	EXISTING FENCE
	SILT FENCE
	OVERLAND FLOW ROUTE
	EXISTING UTILITY POLE
	EXISTING HYDRO GUY WIRE ANCHOR
	TEMPORARY BENCHMARK



SITE SERVICING PLAN
(DEVELOPMENT)
SCALE = 1:500



SITE PLAN (OVERALL)
SCALE = 1:1250

- NOTES:
- ALL DIMENSIONS ARE IN METRES, UNLESS OTHERWISE SPECIFIED; ALL ELEVATIONS ARE IN METRES AND ARE GEODETIC.
 - THIS IS NOT A LEGAL SURVEY.
 - BOUNDARY INFORMATION WAS DERIVED FROM ANNIS, O-SULLIVAN, VOLLEBEKK LTD. JOB NO. 20074-19.
 - EXISTING SERVICES INFORMATION SHOWN ARE BASED ON BEST CURRENT INFORMATION. CONTRACTOR TO VERIFY EXACT LOCATION AND REPORT ANY DISCREPANCIES TO KOLLAARD ASSOCIATES INC.
 - CLIENT IS RESPONSIBLE FOR ACQUIRING ALL NECESSARY PERMITS.
 - CONTRACTOR TO VERIFY THAT APPROPRIATE PERMITS HAVE BEEN ACQUIRED PRIOR TO ANY CONSTRUCTION.
 - CONTRACTOR IS RESPONSIBLE FOR LOCATION AND PROTECTION OF UTILITIES.
 - ALL DIMENSIONS TO BE VERIFIED ON SITE BY CONTRACTOR PRIOR TO CONSTRUCTION.
 - THIS DRAWING IS NOT FOR CONSTRUCTION UNTIL ALL APPROVALS HAVE BEEN GRANTED.
 - INSPECTION OF ROUGH GRADE BY KOLLAARD ASSOCIATES INC. AND CITY OF OTTAWA MUST BE CONDUCTED PRIOR TO PLACEMENT OF TOPSOIL OR SOG.
 - HYDRO SERVICE TO BE INSTALLED ACCORDING TO THE SPECIFICATIONS OF SERVICE PROVIDER AND THE MECHANICAL ENGINEER.
 - ALL MATERIALS AND CONSTRUCTION TO BE IN ACCORDANCE WITH CITY OF OTTAWA STANDARDS AND ONTARIO PROVINCIAL STANDARDS AND SPECIFICATIONS.
 - ANY CHANGES MADE TO THIS PLAN MUST BE VERIFIED AND APPROVED BY KOLLAARD ASSOCIATES, INC.
 - THIS DRAWING IS PART OF KOLLAARD ASSOCIATES DESIGN REPORT # 190622.

No.	REVISION	DATE	BY
0	ISSUED FOR SITE PLAN CONTROL	APR.19.2022	ML

DESIGN	STAMP	CLIENT NAME	PROJECT No.
SD		DOG WORLD (TRACY KIM HOLDEN)	190622
ML		3904 MARCH ROAD, CARP, ON K0A 1L0	DATE
SD		PROPOSED KENNEL ADDITION	NOV. 19, 2019
SD		3904 MARCH ROAD, CARP, ON K0A 1L0	SCALE
SD		AS NOTED	
SD		DRAWING	190622-SER

Kollaard Associates Engineers

BOX 189
210 PRESCOTT STREET
KEMPVILLE, ONTARIO
K0G 1A0
FACSIMILE (613) 258-0475

(613) 860-0923

DESIGN	STAMP	CLIENT NAME	PROJECT No.
SD		DOG WORLD (TRACY KIM HOLDEN)	190622
ML		3904 MARCH ROAD, CARP, ON K0A 1L0	DATE
SD		PROPOSED KENNEL ADDITION	NOV. 19, 2019
SD		3904 MARCH ROAD, CARP, ON K0A 1L0	SCALE
SD		AS NOTED	
SD		DRAWING	190622-SER


TABLE I
FIELD WATER QUALITY MEASUREMENTS
FOR TEST WELL 1

Time Since Pumping Test Started (min)	Temperature (°C)	pH	Turbidity (NTU)	Total Dissolved Solids (ppm)	Conductivity (µS)	Free Chlorine (ppm)
60	9.9	8.1	2.1	253	505	0.0
120	10.0	7.9	2.4	250	555	-
180	10.0	8.0	1.2	257	517	0.0
240	10.2	8.1	0.8	262	525	-
300	10.0	8.0	0.5	268	530	-
360	10.1	8.1	0.5	255	551	0.0



ATTACHMENT A

MOE WELL RECORD AND CERTIFICATE OF WELL COMPLIANCE FOR TW1
PROVIDED BY WELL DRILLER
AND AREA WELL RECORDS



Ministry of the Environment, Conservation and Parks

Well Tag No. (Ontario Water Resources Act) Tag#: A305312

Well Record

Regulation 903 Ontario Water Resources Act

Measurements recorded in: Metric Imperial

Well Owner's Information

First Name: Tracy Last Name / Organization: Holden Mailing Address: 3904 March Rd Municipality: Carp Province: ON Postal Code: K0A1Z0L6 Telephone No. (inc. area code): 132563649

Well Location: Address of Well Location (Street Number/Name): 3904 March Rd Township: Nuntley City/Town/Village: Carp Lot: P1 of 15 10

County/District/Municipality: Ottawa UTM Coordinates: Northing: 184120305013471 Easting: 10

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)
brown	Sand			0 - 10'
grey	Clay			10' - 14'
white/grey	Limestone			14' - 50'
brown	Sandstone			50' - 52'
grey	Limestone			52' - 60'

Annular Space			
Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m ³ /ft ³)	
0 - 20'	Neat Cement	6.40	

Method of Construction		Well Use	
<input type="checkbox"/> Cable Tool	<input type="checkbox"/> Diamond	<input type="checkbox"/> Public	<input type="checkbox"/> Commercial
<input type="checkbox"/> Rotary (Conventional)	<input type="checkbox"/> Jetting	<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Municipal
<input type="checkbox"/> Rotary (Reverse)	<input type="checkbox"/> Driving	<input type="checkbox"/> Livestock	<input type="checkbox"/> Test Hole
<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	<input type="checkbox"/> Irrigation	<input type="checkbox"/> Cooling & Air Conditioning
<input checked="" type="checkbox"/> Air percussion		<input type="checkbox"/> Industrial	
<input type="checkbox"/> Other, specify		<input type="checkbox"/> Other, specify	

Construction Record - Casing				Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		
6.25	Steel	0.188	2' - 20'	<input checked="" type="checkbox"/> Water Supply	
6	open hole		20' - 60'	<input type="checkbox"/> Replacement Well	
				<input type="checkbox"/> Test Hole	
				<input type="checkbox"/> Recharge Well	
				<input type="checkbox"/> Dewatering Well	
				<input type="checkbox"/> Observation and/or Monitoring Hole	
				<input type="checkbox"/> Alteration (Construction)	
				<input type="checkbox"/> Abandoned, Insufficient Supply	
				<input type="checkbox"/> Abandoned, Poor Water Quality	
				<input type="checkbox"/> Abandoned, other, specify	
				<input type="checkbox"/> Other, specify	

Construction Record - Screen			
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)
			From To

Water Details		Hole Diameter	
Water found at Depth: 50' (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft) From: 0 To: 20'	Diameter (cm/in): 10"
Water found at Depth: (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested	Depth (m/ft) From: 20' To: 60'	Diameter (cm/in): 6"
Water found at Depth: (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested		

Well Contractor and Well Technician Information

Business Name of Well Contractor: George H. Law + Son Ltd Well Contractor's Licence No.: 3323


Business Address (Street Number/Name): 4848A Calabogie Rd, P.O. Box 155 Calabogie Municipality: Calabogie

Province: ON Postal Code: K0J1H0 Business E-mail Address:

Bus. Telephone No. (inc. area code): 6137522080 Name of Well Technician (Last Name, First Name): Law Alfred

Well Technician's Licence No.: 0433 Signature of Technician and/or Contractor: [Signature] Date Submitted: 20201009

Results of Well Yield Testing				
After test of well yield, water was:	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
<input checked="" type="checkbox"/> Clear and sand free				
<input type="checkbox"/> Other, specify				
If pumping discontinued, give reason:	Static Level	9.0'		
Pump intake set at (m/ft): 50	1	9.3'	1	9.0'
Pumping rate (l/min / GPM): 12	2	9.4'	2	9.0'
Duration of pumping: 1 hrs + 0 min	3	9.4'	3	
Final water level end of pumping (m/ft): 9.5'	4	9.4'	4	
If flowing give rate (l/min / GPM):	5	9.5	5	
	10	9.5	10	
	15		15	
	20		20	
Recommended pump depth (m/ft): 30'	25		25	
Recommended pump rate (l/min / GPM): 10	30		30	
Well production (l/min / GPM): 15+	40		40	
Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	50		50	
	60	9.5	60	9.0'



Well owner's information package delivered: Yes No

Date Package Delivered: 20201006 Date Work Completed: 20200924

Ministry Use Only

Audit No.: 339783

Received:

CERTIFICATE OF WELL COMPLIANCE

I, Alfred Law do hereby certify that I am licensed to drill wells in the Province of Ontario, and that I have supervised the drilling of a well on the property of Tracy Holden (Name of Landowner), located at 3904 March Rd, P11+15, Con 10 (Legal Description, Lot/Plan No.) in the City of Ottawa.

I certify further that I am aware of the well drilling requirements, the guidelines, recommendations and regulations of the Ministry of the Environment governing well installations in the Province of Ontario, and the standards specified in any subdivision agreement and hydrogeological report applicable to the site and City standards.

I do hereby certify that the said well has been drilled, cased, grouted (cement or bentonite) as applicable, and constructed in strict conformity with the standards required.

Signed this 24 day of Sept, 2020.

George H. Law + Son Ltd
(Well Driller/ Company)

The Engineer, on behalf of the landowner set out above, certifies that he/she has inspected the well and it was constructed in accordance with the specifications in O. Reg. 903, this report and the Hydrogeological report (where applicable) with regards to casing length and grouting requirements.

Signed this 24 day of Sept 2020

B. [Signature]
(Engineer)

Green In-Tents Inc., 104 Country Meadow Drive, Carp, ON K0A 1L0
(613)839-5336 (ph); (613)978-5336 (cell); (613)839-0251 (fx)



The Ontario Water Resources Commission Act WATER WELL RECORD

31 Feb

Water management in Ontario

1. PRINT ONLY IN SPACES PROVIDED

2. CHECK CORRECT BOX WHERE APPLICABLE

11

1511661

MUNICIP.

15005T

CON.

QPN

10

COUNTY OR DISTRICT

TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE

CON., BLOCK, TRACT, SURVEY, ETC.

LOT

Pelee

Henley

10

016

DATE COMPLETED

DAY 21 MO 08 YR 71

13520

4

0420

4

25

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
grey limestone			hard	0	59

31 0059215

32

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER			
10-13	<input checked="" type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
15-18	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
20-23	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
25-28	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
30-33	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
06	<input checked="" type="checkbox"/> STEEL		0023	13-18
14	<input checked="" type="checkbox"/> GALVANIZED	188	0	21
17-18	<input type="checkbox"/> STEEL			20-23
24-25	<input type="checkbox"/> STEEL			27-30

SCREEN


SIZE(S) OF OPENING (SLOT NO.)	DIAMETER	LENGTH

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET		MATERIAL AND TYPE (CEMENT GROUT, LEAD PACKER, ETC.)
FROM	TO	
10-13	14-17	
18-21	22-25	
26-29	30-33	

71 PUMPING TEST

PUMPING TEST METHOD	PUMPING RATE	DURATION OF PUMPING
<input checked="" type="checkbox"/> PUMP	0020 GPM	01 HOURS 00 MINS.
STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING
002 FEET	012 FEET	15 MINUTES: 012 FEET, 30 MINUTES: 012 FEET, 45 MINUTES: 012 FEET, 60 MINUTES: 012 FEET
RECOMMENDED PUMP TYPE	RECOMMENDED PUMP SETTING	RECOMMENDED PUMPING RATE
<input type="checkbox"/> SHALLOW	030 FEET	0020 GPM



FINAL STATUS OF WELL

WATER SUPPLY

WATER USE

12 DOMESTIC

METHOD OF DRILLING

CABLE TOOL

CONTRACTOR

NAME OF WELL CONTRACTOR: Austin Stanton
ADDRESS: 19 Kenilworth
LICENCE NUMBER: 4806

NAME OF DRILLER OR BORER: [Signature]
SUBMISSION DATE: DAY 21 MO 5 YR 71

OFFICE USE ONLY

DATA SOURCE: 1
CONTRACTOR: 4806
DATE RECEIVED: 280172
INSPECTOR: K

REMARKS: PK
WI



WATER WELL RECORD

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

11

1517169

MUNICIPALITY 15005

CON. CON

10

COUNTY OR DISTRICT HUNTLEY	TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE WEST CARLTON	CON., BLOCK, TRACT, SURVEY, ETC. 10 X PART 3	LOT 016
DATE COMPLETED DAY 23 MO. 10 YR. 79			
APPROVAL RR 2		ELEVATION 5 0425	
BASIN CODE 5 26			

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
BROWN	SAND-GRAVEL			0	11'
GRAY	LIMESTONE			11'	130'

31 **001162811** **0130215**

41 **WATER RECORD**

WATER FOUND AT - FEET	KIND OF WATER			
10-13	1 <input checked="" type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR		
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL		
15-18	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR		
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL		
20-23	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR		
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL		
25-28	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR		
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL		
30-33	1 <input type="checkbox"/> FRESH	3 <input type="checkbox"/> SULPHUR		
	2 <input type="checkbox"/> SALTY	4 <input type="checkbox"/> MINERAL		

51 **CASING & OPEN HOLE RECORD**

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
10-11	1 <input checked="" type="checkbox"/> STEEL			
	2 <input type="checkbox"/> GALVANIZED			
	3 <input type="checkbox"/> CONCRETE			
	4 <input type="checkbox"/> OPEN HOLE			
17-18	1 <input type="checkbox"/> STEEL			
	2 <input type="checkbox"/> GALVANIZED			
	3 <input type="checkbox"/> CONCRETE			
	4 <input type="checkbox"/> OPEN HOLE			
24-25	1 <input type="checkbox"/> STEEL			
	2 <input type="checkbox"/> GALVANIZED			
	3 <input type="checkbox"/> CONCRETE			
	4 <input type="checkbox"/> OPEN HOLE			

SCREEN


SIZE(S) OF OPENING (SLOT NO.)	DIAMETER	LENGTH
	INCHES	FEET
MATERIAL AND TYPE		DEPTH TO TOP OF SCREEN
		41-44
		FEET

61 **PLUGGING & SEALING RECORD**

DEPTH SET AT - FEET	MATERIAL AND TYPE (CEMENT GROUT, LEAD PACKER, ETC.)
FROM TO	
10-13	14-17
18-21	22-25
26-29	30-33

71 **PUMPING TEST**

PUMPING TEST METHOD 1 <input type="checkbox"/> PUMP 2 <input checked="" type="checkbox"/> BAILER	PUMPING RATE 0010 GPM	DURATION OF PUMPING 11-14 HOURS 01 15-16 HOURS 00 17-18 MINS
STATIC LEVEL 010 FEET	WATER LEVEL END OF PUMPING 050 FEET	WATER LEVELS DURING
1 <input type="checkbox"/> PUMPING 2 <input type="checkbox"/> RECOVERY		
15 MINUTES 26-28 FEET 29-31 FEET 45 MINUTES 32-34 FEET 60 MINUTES 35-37 FEET		
IF FLOWING, GIVE RATE	PUMP INTAKE SET AT	WATER AT END OF TEST
GPM	FEET	1 <input checked="" type="checkbox"/> CLEAR 2 <input type="checkbox"/> CLOUDY
RECOMMENDED PUMP TYPE <input type="checkbox"/> SHALLOW <input checked="" type="checkbox"/> DEEP	RECOMMENDED PUMP SETTING 100 FEET	RECOMMENDED PUMPING RATE GPM



54 **FINAL STATUS OF WELL**

1 <input checked="" type="checkbox"/> WATER SUPPLY	5 <input type="checkbox"/> ABANDONED, INSUFFICIENT SUPPLY
2 <input type="checkbox"/> OBSERVATION WELL	6 <input type="checkbox"/> ABANDONED, POOR QUALITY
3 <input type="checkbox"/> TEST HOLE	7 <input type="checkbox"/> UNFINISHED
4 <input type="checkbox"/> RECHARGE WELL	

55-56 **WATER USE**

1 <input checked="" type="checkbox"/> DOMESTIC	5 <input type="checkbox"/> COMMERCIAL
2 <input type="checkbox"/> STOCK	6 <input type="checkbox"/> MUNICIPAL
3 <input type="checkbox"/> IRRIGATION	7 <input type="checkbox"/> PUBLIC SUPPLY
4 <input type="checkbox"/> INDUSTRIAL	8 <input type="checkbox"/> COOLING OR AIR CONDITIONING
<input type="checkbox"/> OTHER	9 <input type="checkbox"/> NOT USED

57 **METHOD OF DRILLING**

1 <input checked="" type="checkbox"/> CABLE TOOL	6 <input type="checkbox"/> BORING
2 <input type="checkbox"/> ROTARY (CONVENTIONAL)	7 <input type="checkbox"/> DIAMOND
3 <input type="checkbox"/> ROTARY (REVERSE)	8 <input type="checkbox"/> JETTING
4 <input type="checkbox"/> ROTARY (AIR)	9 <input type="checkbox"/> DRIVING
5 <input type="checkbox"/> AIR PERCUSSION	

CONTRACTOR

NAME OF WELL CONTRACTOR F FLEURY	LICENCE NUMBER 2101
ADDRESS 1171 MERVALE RD OTTAWA	
NAME OF DRILLER OR BORER	LICENCE NUMBER
SIGNATURE OF CONTRACTOR <i>F Fleury</i>	SUBMISSION DATE DAY 23 MO. 10 YR. 79

OFFICE USE ONLY

DATA SOURCE 1	CONTRACTOR 2101	DATE RECEIVED 061179
DATE OF INSPECTION	INSPECTOR	
REMARKS		

1520885

1. PRINT ONLY IN SPACES PROVIDED
2. CHECK CORRECT BOX WHERE APPLICABLE

COUNTY OR DISTRICT: Ontario TOWNSHIP, BOROUGH, CITY, TOWN, VILLAGE: West Carleton CON., BLOCK, TRACT, SURVEY, ETC.: Conc 10 LOT: 15
Styles Side Rd. DATE COMPLETED: DAY 25 MO. 5 YR. 85

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
<u>Clay</u> <u>Blue</u> <u>Red</u>	<u>Clay</u> <u>Granite</u>		<u>Plastic</u> <u>Hard</u>	<u>0</u>	<u>36</u> <u>75</u>

31 _____
32 _____

41 WATER RECORD

WATER FOUND AT - FEET	KIND OF WATER			
<u>68</u>	<input checked="" type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL
	<input type="checkbox"/> FRESH	<input type="checkbox"/> SALTY	<input type="checkbox"/> SULPHUR	<input type="checkbox"/> MINERAL

51 CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET	
			FROM	TO
<u>64</u>	<input checked="" type="checkbox"/> STEEL	<u>158</u>	<u>0</u>	<u>36</u>
<u>68</u>	<input checked="" type="checkbox"/> STEEL		<u>36</u>	<u>75</u>

SCREEN

SIZE(S) OF OPENING (SLOT NO.)	DIAMETER INCHES	LENGTH FEET

61 PLUGGING & SEALING RECORD

DEPTH SET AT - FEET		MATERIAL AND TYPE (CEMENT GROUT, LEAD PACKER, ETC.)
FROM	TO	
<u>10-13</u>	<u>14-17</u>	
<u>18-21</u>	<u>22-25</u>	
<u>26-29</u>	<u>30-33</u>	


71 PUMPING TEST

PUMPING METHOD	PUMPING RATE	DURATION OF PUMPING
<input checked="" type="checkbox"/> PUMP	<u>6</u> GPM	<u>1</u> HOURS

STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING			
<u>2</u>	<u>65</u>	15 MINUTES	30 MINUTES	45 MINUTES	60 MINUTES
		<u>17</u>	<u>17</u>	<u>17</u>	<u>17</u>

IF FLOWING, GIVE RATE	PUMP INTAKE SET AT	WATER AT END OF TEST
	<u>65</u>	<input checked="" type="checkbox"/> CLEAR

RECOMMENDED PUMP TYPE	RECOMMENDED PUMP SETTING	RECOMMENDED PUMPING RATE
<input checked="" type="checkbox"/> DEEP	<u>65</u>	<u>5</u>



FINAL STATUS OF WELL

<input checked="" type="checkbox"/> WATER SUPPLY	<input type="checkbox"/> ABANDONED, INSUFFICIENT SUPPLY
<input type="checkbox"/> OBSERVATION WELL	<input type="checkbox"/> ABANDONED, POOR QUALITY
<input type="checkbox"/> TEST HOLE	<input type="checkbox"/> UNFINISHED
<input type="checkbox"/> RECHARGE WELL	

WATER USE

<input type="checkbox"/> DOMESTIC	<input type="checkbox"/> COMMERCIAL
<input type="checkbox"/> STOCK	<input type="checkbox"/> MUNICIPAL
<input type="checkbox"/> IRRIGATION	<input type="checkbox"/> PUBLIC SUPPLY
<input type="checkbox"/> INDUSTRIAL	<input type="checkbox"/> COOLING OR AIR CONDITIONING
<input type="checkbox"/> OTHER	<input type="checkbox"/> NOT USED

METHOD OF DRILLING

<input checked="" type="checkbox"/> CABLE TOOL	<input type="checkbox"/> BORING
<input type="checkbox"/> ROTARY (CONVENTIONAL)	<input type="checkbox"/> DIAMOND
<input type="checkbox"/> ROTARY (REVERSE)	<input type="checkbox"/> JETTING
<input type="checkbox"/> ROTARY (AIR)	<input type="checkbox"/> DRIVING
<input type="checkbox"/> AIR PERCUSSION	

CONTRACTOR

NAME OF WELL CONTRACTOR: Valley Drilling LICENCE NUMBER: 5222
 ADDRESS: P.O. Box 437 Carp Ont.
 NAME OF DRILLER OR BOBER: S/SRUSE LICENCE NUMBER: 5222
 SIGNATURE OF CONTRACTOR: [Signature] SUBMISSION DATE: DAY 25 MO. 3 YR. 86

OFFICE USE ONLY

DATA SOURCE: _____ CONTRACTOR: _____ DATE RECEIVED: 020986
 DATE OF INSPECTION: _____ INSPECTOR: _____
 REMARKS: _____

Print only in spaces provided.
Mark correct box with a checkmark, where applicable.

11

1529163

Municipality
15005

Con.
CON

10

OTTAWA-CARLETON

Country or District: [Redacted] Township/Borough/City/Town/Village: West Carleton. 10 Con block tract survey, etc.: 15 Lot: 25-27
Address: R.R. 2 Camp 3904 Date completed: 12 9 96
RC Highway Code: [Redacted]

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)

General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
Brown	Sand	Clay	Packed	0	4
Brown	Silt		Packed	4	9
Brown	Limestone		Hard	9	70

31
32

41 WATER RECORD

Water found at - feet	Kind of water	
43-64	<input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Salty	<input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty	<input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty	<input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas
	<input type="checkbox"/> Fresh <input type="checkbox"/> Salty	<input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas

51 CASING & OPEN HOLE RECORD

Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic	188	0	21
	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			
	<input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			

SCREEN

Sizes of opening (Slot No)	Diameter inches	Length feet


Material and type: [Redacted] Depth at top of screen: [Redacted] feet

61 PLUGGING & SEALING RECORD

Depth set at - feet		Material and type (Cement grout, bentonite, etc.)
From	To	
0	8	Rock Cuttings
8	21	TPC 10 Cement

71 PUMPING TEST

Pumping test method	Pumping rate	Duration of pumping
<input type="checkbox"/> Pump <input checked="" type="checkbox"/> Bailor	4 1/2 GPM	1 Hours 0 Mins
Static level	Water level end of pumping	Water levels during
1 feet	60 feet	15 minutes: 26 feet 30 minutes: 10 feet 45 minutes: 7 feet 60 minutes: 6 feet
If flowing give rate	Pump intake set at	Water at end of test
	65 feet	<input type="checkbox"/> Clear <input checked="" type="checkbox"/> Cloudy
Recommended pump type	Recommended pump setting	Recommended pump rate
<input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep		4 GPM



FINAL STATUS OF WELL

<input checked="" type="checkbox"/> Water supply	<input type="checkbox"/> Abandoned, insufficient supply	<input type="checkbox"/> Unfinished
<input type="checkbox"/> Observation well	<input type="checkbox"/> Abandoned, poor quality	<input type="checkbox"/> Replacement well
<input type="checkbox"/> Test hole	<input type="checkbox"/> Abandoned (Other)	
<input type="checkbox"/> Recharge well	<input type="checkbox"/> Dewatering	

WATER USE

<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used
<input type="checkbox"/> Stock	<input type="checkbox"/> Municipal	<input type="checkbox"/> Other
<input type="checkbox"/> Irrigation	<input type="checkbox"/> Public supply	
<input type="checkbox"/> Industrial	<input type="checkbox"/> Cooling & air conditioning	

METHOD OF CONSTRUCTION

<input checked="" type="checkbox"/> Cable tool	<input type="checkbox"/> Air percussion	<input type="checkbox"/> Driving
<input type="checkbox"/> Rotary (conventional)	<input type="checkbox"/> Boring	<input type="checkbox"/> Digging
<input type="checkbox"/> Rotary (reverse)	<input type="checkbox"/> Diamond	<input type="checkbox"/> Other
<input type="checkbox"/> Rotary (air)	<input type="checkbox"/> Jetting	

Name of Well Contractor: BOYD CAMERON 1567
Address: R.R. 2 Clayton Ont
Name of Well Technician: Boyd Cameron
Signature of Technician/Contractor: [Signature]
Well Contractor's Licence No.: 1567
Well Technician's Licence No.: 70089
Submission date: 31 9 96

MINISTRY USE ONLY

Data source	Contractor: 1567	Date received: OCT 31 1996
Date of inspection	Inspector	
Remarks		

CSS.ES
0506 (07/94) Front Form 9

Print only in spaces provided.
Mark correct box with a checkmark, where applicable.

1529163

Municipality
15005

Con.
CON

10

OTTAWA-CARLETON

11

Country or District: [Redacted] Township/Borough/City/Town/Village: West Carleton, 10 Con block tract survey, etc.: 15 Lot: 25-27
Address: R.R. 2 Camp 3904 Date completed: 12 9 96
RC Highway Code: [Redacted]

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)

General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
Brown	Sand	Clay	Packed	0	4
Brown	Silt		Packed	4	9
Brown	Limestone		Hard	9	70

31
32

41 WATER RECORD

Water found at - feet	Kind of water
43-64	<input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Salty <input type="checkbox"/> Sulphur <input type="checkbox"/> Minerals <input type="checkbox"/> Gas

51 CASING & OPEN HOLE RECORD

Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic	188	0	21

SCREEN

Sizes of opening (Slot No)	Diameter inches	Length feet


61 PLUGGING & SEALING RECORD

Depth set at - feet	Material and type (Cement grout, bentonite, etc.)
0-8	Rock Cuttings
8-21	TPC 10
21-29	Cement

71 PUMPING TEST

Pumping test method	Pumping rate	Duration of pumping
<input type="checkbox"/> Pump <input checked="" type="checkbox"/> Bailor	4 1/2 GPM	1 Hours 0 Mins

Static level	Water level end of pumping	Water levels during	Water at end of test
1 feet	60 feet	15 minutes: 26 feet 30 minutes: 10 feet 45 minutes: 7 feet 60 minutes: 6 feet	<input type="checkbox"/> Clear <input checked="" type="checkbox"/> Cloudy



FINAL STATUS OF WELL

<input checked="" type="checkbox"/> Water supply	<input type="checkbox"/> Abandoned, insufficient supply	<input type="checkbox"/> Unfinished
<input type="checkbox"/> Observation well	<input type="checkbox"/> Abandoned, poor quality	<input type="checkbox"/> Replacement well
<input type="checkbox"/> Test hole	<input type="checkbox"/> Abandoned (Other)	
<input type="checkbox"/> Recharge well	<input type="checkbox"/> Dewatering	

WATER USE

<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not used
<input type="checkbox"/> Stock	<input type="checkbox"/> Municipal	<input type="checkbox"/> Other
<input type="checkbox"/> Irrigation	<input type="checkbox"/> Public supply	
<input type="checkbox"/> Industrial	<input type="checkbox"/> Cooling & air conditioning	

METHOD OF CONSTRUCTION

<input checked="" type="checkbox"/> Cable tool	<input type="checkbox"/> Air percussion	<input type="checkbox"/> Driving
<input type="checkbox"/> Rotary (conventional)	<input type="checkbox"/> Boring	<input type="checkbox"/> Digging
<input type="checkbox"/> Rotary (reverse)	<input type="checkbox"/> Diamond	<input type="checkbox"/> Other
<input type="checkbox"/> Rotary (air)	<input type="checkbox"/> Jetting	

Name of Well Contractor: BOYD CAMERON 1567
Address: R.R. 2 Clayton Ont
Name of Well Technician: Boyd Cameron
Signature of Technician/Contractor: [Signature]
Well Contractor's Licence No.: 1567
Well Technician's Licence No.: 70089
Submission date: 31 9 96

MINISTRY USE ONLY

Data source	Contractor: 1567	Date received: OCT 31 1996
Date of inspection	Inspector	
Remarks		

CSS.ES
0506 (07/94) Front Form 9


Print only in spaces provided.
Mark correct box with a checkmark, where applicable.

11


1529993

Municipality: 15005
Con: CON
10
S Wharf Point

County or District: [Redacted] Township/Borough/City/Town/Village: West Carleton
Con block tract survey, etc.: 10 Lot: 14
Address: Ottawa Ont Date completed: 24 12 97



LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)					
General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
grey	Sand			0	25
grey	Sandstone			25	120




41 WATER RECORD			
Water found at - feet	Kind of water		
63	<input checked="" type="checkbox"/> Fresh	<input type="checkbox"/> Sulphur	<input type="checkbox"/> Minerals
91	<input checked="" type="checkbox"/> Salty	<input type="checkbox"/> Gas	<input type="checkbox"/> Minerals
113	<input checked="" type="checkbox"/> Fresh	<input type="checkbox"/> Sulphur	<input type="checkbox"/> Minerals
	<input type="checkbox"/> Salty	<input type="checkbox"/> Gas	<input type="checkbox"/> Minerals

51 CASING & OPEN HOLE RECORD				
Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4	Steel	188	0	31
8 3/4	Galvanized		0	29
6	Concrete		29	120

SCREEN	Sizes of opening (Slot No.)	Diameter	Length
		inches	feet

61 PLUGGING & SEALING RECORD			
Depth set at - feet		Material and type (Cement grout, bentonite, etc.)	
2	31	Cement grout	

71 PUMPING TEST	Pumping test method		Pumping rate	Duration of pumping
	<input checked="" type="checkbox"/> Pump	<input type="checkbox"/> Bailer	30 GPM	12 Hours 16 Mins
	Static level	Water level end of pumping	Water levels during	
	10 feet	100 feet	15 minutes: 10 feet	30 minutes: 10 feet



FINAL STATUS OF WELL

1 Water supply
2 Observation well
3 Test hole
4 Recharge well

WATER USE

1 Domestic
2 Stock
3 Irrigation
4 Industrial

METHOD OF CONSTRUCTION

1 Cable tool
2 Rotary (conventional)
3 Rotary (reverse)
4 Rotary (air)

Name of Well Contractor: Air Rock Drilling Co Ltd
Well Contractor's Licence No.: 1119
Address: RR#2 Jasper Ont
Name of Well Technician: Shannon Purcell
Well Technician's Licence No.: T2122
Signature of Technician/Contractor: [Signature]
Submission date: 29 12 97

MINISTRY USE ONLY

Data source: 1119
Date received: APR 08 1998
Date of inspection: [Blank]
Inspector: [Blank]
Remarks: [Blank]

Print only in spaces provided.
Mark correct box with a checkmark, where applicable.

11

1532850

Municipality
15005

Con.
CON 10

County or District Ottawa Carleton	Township/Borough/City/Town/Village West Carleton - Huntley	Con block tract survey, etc. 10	Lot 15
Address P O Box 942 Almonte, Ontario KOA 1A0		Date completed 27 day 5 month 02 year	

21

U
M 10 12 17 18 24 25 26 30 31 47

Northing RC Elevation RC Basin Code ii iii iv

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)					
General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
Brown	Sandy Clay			0	12
Gray	Clay			12	40
Gray & White	Sandstone			40	75
Note Casing was left 1.5 feet above ground level at time of drilling					

31

32


41 WATER RECORD			
Water found at - feet	Kind of water		
10-13 59	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty	3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas	14
15-18 NOT TESTED	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty	3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas	19
20-23	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty	3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas	24
25-28	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty	3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas	29
30-33	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty	3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas	34

51 CASING & OPEN HOLE RECORD				
Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4	1 <input checked="" type="checkbox"/> Steel 2 <input type="checkbox"/> Galvanized 3 <input type="checkbox"/> Concrete 4 <input type="checkbox"/> Open hole 5 <input type="checkbox"/> Plastic	.188	0	44.5
6	1 <input type="checkbox"/> Steel 2 <input type="checkbox"/> Galvanized 3 <input type="checkbox"/> Concrete 4 <input checked="" type="checkbox"/> Open hole 5 <input type="checkbox"/> Plastic		44.5	75
	1 <input type="checkbox"/> Steel 2 <input type="checkbox"/> Galvanized 3 <input type="checkbox"/> Concrete 4 <input type="checkbox"/> Open hole 5 <input type="checkbox"/> Plastic			27-30

SCREEN Sizes of opening (Slot No.)	31-33 Diameter inches		34-38 Length feet	
	Material and type			
	Depth at top of screen		41-44 feet	

61 PLUGGING & SEALING RECORD			
Depth set at - feet		Material and type (Cement grout, bentonite, etc.)	
From	To		
10-13	14-17	Grouted - Cement (8)	
18-21	22-25		
26-29	30-33		

71 PUMPING TEST	
Pumping test method 1 <input checked="" type="checkbox"/> Pump 2 <input type="checkbox"/> Bailer	Pumping rate 50 GPM
Static level 6'1" feet	Water level end of pumping 20 feet
Water levels during 15 minutes 70 feet 30 minutes 50 feet 45 minutes 30 feet 60 minutes 20 feet	Duration of pumping 1 Hours 15 Mins
If flowing give rate GPM	Water at end of test <input type="checkbox"/> Clear <input checked="" type="checkbox"/> Cloudy
Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep	Recommended pump setting 35 feet
	Recommended pump rate 5 GPM



54 FINAL STATUS OF WELL		
1 <input checked="" type="checkbox"/> Water supply	5 <input type="checkbox"/> Abandoned, insufficient supply	9 <input type="checkbox"/> Unfinished
2 <input type="checkbox"/> Observation well	6 <input type="checkbox"/> Abandoned, poor quality	10 <input type="checkbox"/> Replacement well
3 <input type="checkbox"/> Test hole	7 <input type="checkbox"/> Abandoned (Other)	
4 <input type="checkbox"/> Recharge well	8 <input type="checkbox"/> Dewatering	

55-56 WATER USE		
1 <input checked="" type="checkbox"/> Domestic	5 <input type="checkbox"/> Commercial	9 <input type="checkbox"/> Not use
2 <input type="checkbox"/> Stock	6 <input type="checkbox"/> Municipal	10 <input type="checkbox"/> Other
3 <input type="checkbox"/> Irrigation	7 <input type="checkbox"/> Public supply	
4 <input type="checkbox"/> Industrial	8 <input type="checkbox"/> Cooling & air conditioning	

57 METHOD OF CONSTRUCTION		
1 <input type="checkbox"/> Cable tool	5 <input checked="" type="checkbox"/> Air percussion	9 <input type="checkbox"/> Driving
2 <input type="checkbox"/> Rotary (conventional)	6 <input type="checkbox"/> Boring	10 <input type="checkbox"/> Digging
3 <input type="checkbox"/> Rotary (reverse)	7 <input type="checkbox"/> Diamond	11 <input type="checkbox"/> Other
4 <input checked="" type="checkbox"/> Rotary (air)	8 <input type="checkbox"/> Jetting	

Name of Well Contractor Capital Water Supply Ltd.	Well Contractor's Licence No. 1558
Address P.O. Box 490 Stittsville, Ontario K2S 1A6	
Name of Well Technician S. Miller	Well Technician's Licence No. T0097
Signature of Technician/Contractor <i>[Signature]</i>	Submission date day 28 mo 5 year 02

MINISTRY USE ONLY	
Data source 1558	Contractor 1558
Date of inspection	Inspector
Remarks CSS.ES2	

Print only in spaces provided.
Mark correct box with a checkmark, where applicable.

11

1532850

Municipality
15005

Con.
CON 10

County or District Ottawa Carleton	Township/Borough/City/Town/Village West Carleton - Huntley	Con block tract survey, etc. 10	Lot 15
Address P O Box 942 Almonte, Ontario KOA 1A0		Date completed 27 day 5 month 02 year	

21

U
M 10 12 17 18 24 25 26 30 31 47

Northing RC Elevation RC Basin Code ii iii iv

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)					
General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
Brown	Sandy Clay			0	12
Gray	Clay			12	40
Gray & White	Sandstone			40	75
Note Casing was left 1.5 feet above ground level at time of drilling					

31

32


41 WATER RECORD			
Water found at - feet	Kind of water		
10-13 59	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty	3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas	14
15-18 NOT TESTED	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty	3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas	19
20-23	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty	3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas	24
25-28	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty	3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas	29
30-33	1 <input type="checkbox"/> Fresh 2 <input type="checkbox"/> Salty	3 <input type="checkbox"/> Sulphur 4 <input type="checkbox"/> Minerals 5 <input type="checkbox"/> Gas	34

51 CASING & OPEN HOLE RECORD				
Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4	1 <input checked="" type="checkbox"/> Steel 2 <input type="checkbox"/> Galvanized 3 <input type="checkbox"/> Concrete 4 <input type="checkbox"/> Open hole 5 <input type="checkbox"/> Plastic	.188	0	44.5
6	1 <input type="checkbox"/> Steel 2 <input type="checkbox"/> Galvanized 3 <input type="checkbox"/> Concrete 4 <input checked="" type="checkbox"/> Open hole 5 <input type="checkbox"/> Plastic		44.5	75
	1 <input type="checkbox"/> Steel 2 <input type="checkbox"/> Galvanized 3 <input type="checkbox"/> Concrete 4 <input type="checkbox"/> Open hole 5 <input type="checkbox"/> Plastic			27-30

SCREEN Sizes of opening (Slot No.)	Diameter inches	Length feet	Material and type	Depth at top of screen feet

61 PLUGGING & SEALING RECORD			
Depth set at - feet		Material and type (Cement grout, bentonite, etc.)	
From	To		
10-13	14-17	Grouted - Cement (8)	
18-21	22-25		
26-29	30-33		

71 PUMPING TEST	Pumping test method 1 <input checked="" type="checkbox"/> Pump 2 <input type="checkbox"/> Bailer	Pumping rate 50 GPM	Duration of pumping 1 <input type="checkbox"/> Hours 17-18 Mins	
	Static level 19-21 6'1" feet	Water level end of pumping 22-24 20 feet	Water levels during 1 <input checked="" type="checkbox"/> Pumping 2 <input type="checkbox"/> Recovery	
	15 minutes 25-28 70 feet	30 minutes 29-31 50 feet	45 minutes 32-34 30 feet	60 minutes 35-37 20 feet
	If flowing give rate 38-41 GPM	Pump intake set at 42 feet	Water at end of test 43 <input type="checkbox"/> Clear 44 <input checked="" type="checkbox"/> Cloudy	
Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep	Recommended pump setting 43-45 35 feet	Recommended pump rate 46-49 5 GPM		



54 FINAL STATUS OF WELL		
1 <input checked="" type="checkbox"/> Water supply	5 <input type="checkbox"/> Abandoned, insufficient supply	9 <input type="checkbox"/> Unfinished
2 <input type="checkbox"/> Observation well	6 <input type="checkbox"/> Abandoned, poor quality	10 <input type="checkbox"/> Replacement well
3 <input type="checkbox"/> Test hole	7 <input type="checkbox"/> Abandoned (Other)	
4 <input type="checkbox"/> Recharge well	8 <input type="checkbox"/> Dewatering	
55-56 WATER USE		
1 <input checked="" type="checkbox"/> Domestic	5 <input type="checkbox"/> Commercial	9 <input type="checkbox"/> Not use
2 <input type="checkbox"/> Stock	6 <input type="checkbox"/> Municipal	10 <input type="checkbox"/> Other
3 <input type="checkbox"/> Irrigation	7 <input type="checkbox"/> Public supply	
4 <input type="checkbox"/> Industrial	8 <input type="checkbox"/> Cooling & air conditioning	
57 METHOD OF CONSTRUCTION		
1 <input type="checkbox"/> Cable tool	5 <input checked="" type="checkbox"/> Air percussion	9 <input type="checkbox"/> Driving
2 <input type="checkbox"/> Rotary (conventional)	6 <input type="checkbox"/> Boring	10 <input type="checkbox"/> Digging
3 <input type="checkbox"/> Rotary (reverse)	7 <input type="checkbox"/> Diamond	11 <input type="checkbox"/> Other
4 <input checked="" type="checkbox"/> Rotary (air)	8 <input type="checkbox"/> Jetting	

Name of Well Contractor Capital Water Supply Ltd.	Well Contractor's Licence No. 1558
Address P.O. Box 490 Stittsville, Ontario K2S 1A6	
Name of Well Technician S. Miller	Well Technician's Licence No. T0097
Signature of Technician/Contractor <i>[Signature]</i>	Submission date day 28 mo 5 year 02

MINISTRY USE ONLY	Data source 1558	Contractor 1558	Date received JUN 24 2002
	Date of inspection	Inspector	
	Remarks CSS.ES2		



Print only in spaces provided. Mark correct box with a checkmark, where applicable.

11

1533879

Municipality 15005 Con. CON 110

County or District, Township/Borough/City/Town/Village West Carleton, Con block tract survey, etc. Con 10, Lot 15 of 15, Address of Well Location March Rd. RR#2 Carp, Ont K0A-1K0, Date completed 15 07 2003

Zone, Easting, Northing, RC, Elevation, RC, Basin Code, ii, iii, iv

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions) Table with columns: General colour, Most common material, Other materials, General description, Depth - feet (From, To)

31, 32


41 WATER RECORD Table with columns: Water found at - feet, Kind of water (Fresh, Salty, Sulphur, Minerals, Gas)

51 CASING & OPEN HOLE RECORD Table with columns: Inside diam inches, Material, Wall thickness inches, Depth - feet (From, To)

54 SCREEN Table with columns: Sizes of opening (Slot No.), Diameter, Length, Material and type, Depth at top of screen

61 PLUGGING & SEALING RECORD Table with columns: Depth set at - feet (From, To), Material and type (Cement grout, bentonite, etc.)

71 PUMPING TEST Table with columns: Pumping test method, Pumping rate, Duration of pumping, Static level, Water level end of pumping, Water levels during, Pump intake set at, Water at end of test, Recommended pump type, Recommended pump setting, Recommended pump rate



54 FINAL STATUS OF WELL, 55-56 WATER USE, 57 METHOD OF CONSTRUCTION

Name of Well Contractor George H Law & Son Ltd, Well Contractor's Licence No. 3323, Address Box 155 Culabogie, Ont K0A-1H0, Name of Well Technician Allan Fougere, Well Technician's Licence No. T-0432, Signature of Technician/Contractor, Submission date 15 07 2003

MINISTRY USE ONLY Table with columns: Data source, Contractor, Date received, Date of inspection, Inspector, Remarks

Instructions for Completing Form

- For use in the Province of Ontario only. This document is a **perpetual** document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Management Coordinator at 416-235-6203.
- **All metre measurements shall be reported to 1/10th of a metre.**
- Please print clearly in blue or black ink only.

Well Owner's Information and Location of Well Information

Ministry Use Only											
MUN										CON	LOT

Ottawa Carleton **West Carleton- Huntley** **15** **11**

RR#/Street Number/Name: **Dwyer Hill Rd.** City/Town/Village: **Almonte** Site/Compartment/Block/Tract etc.

GPS Reading: NAD **83** Zone **18** Easting **411646** Northing **5013248** Unit Make/Model: **Garmin** Mode of Operation: Undifferentiated Averaged Differentiated, specify

Log of Overburden and Bedrock Materials (see instructions)

General Colour	Most common material	Other Materials	General Description	Depth Metres	
				From	To
Brown	soil	busted rock	loose	0	1.21
grey	sand		wet	1.21	2.74
grey	clay			2.74	9.75
grey grey & white	sandston		med	9.75	18.28

Hole Diameter

Depth From	Metres To	Diameter Centimetres
0	10.36	22.75
10.36	18.28	15.25

Water Record

Water found at **0** Metres Kind of Water

m Fresh Sulphur Gas Salty Minerals Other:

m Fresh Sulphur Gas Salty Minerals Other:

m Fresh Sulphur Gas Salty Minerals Other:

After test of well yield, water was Clear and sediment free Other, specify

Chlorinated Yes No

Construction Record

Inside diam centimetres	Material	Wall thickness centimetres	Depth Metres	
			From	To
15.86	<input type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized	.48	+1.06	10.36
15.23	<input type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized		10.36	18.28

Screen

Outside diam Steel Fibreglass Plastic Concrete Galvanized Slot No.

No Casing or Screen

Open hole

Test of Well Yield

Pumping test method	Draw Down		Recovery	
	Time min	Water Level Metres	Time min	Water Level Metres
Pump intake set at - (metres)	Static Level			
Pumping rate - (litres/min)	1		1	
Duration of pumping hrs + min	2		2	
Final water level end of pumping metres	3		3	
Recommended pump type. <input type="checkbox"/> Shallow <input type="checkbox"/> Deep	4		4	
Recommended pump depth. metres	NOT TESTED		5	
Recommended pump rate. (litres/min)	10		10	
If flowing give rate - (litres/min)	15		15	
	20		20	
	25		25	
If pumping discontinued, give reason.	30		30	
	40		40	
	50		50	
	60		60	

Plugging and Sealing Record Annular space Abandonment

Depth set at - Metres From	To	Material and type (bentonite slurry, neat cement slurry) etc.	Volume Placed (cubic metres)
1.21	0	Crushed Stone	.42m3
10.36	1.21	Bentonite Slurry	

Method of Construction

Cable Tool Rotary (air Mud) Diamond Digging

Rotary (conventional) Air percussion Jetting Other

Rotary (reverse) Boring Driving

Water Use

Domestic Industrial Public Supply Other **test hole**

Stock Commercial Not used

Irrigation Municipal Cooling & air conditioning

Final Status of Well

Water Supply Recharge well Unfinished Abandoned, (Other)

Observation well Abandoned, insufficient supply Dewatering

Test Hole Abandoned, poor quality Replacement well

Well Contractor/Technician Information

Name of Well Contractor: **Capital Water Supply Ltd** Well Contractor's Licence No.: **1558**

Business Address (street name, number, city etc.): **Box 490 Stittsville Ontario K2S 1A6**

Name of Well Technician (last name, first name): **Miller, Stephen** Well Technician's Licence No.: **T0097**

Signature of Technician/Contractor: *[Signature]* Date Submitted: **2006 7 12**

Location of Well

In diagram below show distances of well from road, lot line, and building. Indicate north by arrow.

A hand-drawn diagram showing a well location (marked with a circled 'X') relative to three roads: Dwyer Hill Rd (horizontal), Park and Ride (diagonal), and March Rd (vertical). A north arrow is drawn in the upper left corner.

Audit No. **Z 47011** Date Well Completed **2006 7 12**

Was the well owner's information package delivered? Yes No Date Delivered **2006 7 12**

Ministry Use Only

Data Source Contractor **1558**


Date Received **AUG 25 2006** Date of Inspection **2006 7 12**

Remarks Well Record Number



ATTACHMENT B
PUMPING TEST DATA FOR TW1

TW1-WELL DRAWDOWN VS. TIME-KOLLAARD FILE 190622



DRAWDOWN DATA TW1


Time Lapsed (minutes)	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)
0	252.955	8.68	-2.3	0.00
1	252.24	8.68	-2.373	0.07
2	252.046	8.68	-2.393	0.09
3	251.754	8.68	-2.422	0.12
4	251.624	8.68	-2.436	0.14
5	251.526	8.68	-2.446	0.15
6	251.461	8.68	-2.452	0.15
7	251.397	8.68	-2.459	0.16
8	251.332	8.68	-2.465	0.17
9	251.299	8.68	-2.469	0.17
10	251.234	8.68	-2.475	0.18
11	251.234	8.68	-2.475	0.18
12	251.202	8.68	-2.479	0.18
13	251.169	8.68	-2.482	0.18
14	251.137	8.68	-2.485	0.19
15	251.104	8.68	-2.489	0.19
16	251.04	8.68	-2.495	0.20
17	251.04	8.68	-2.495	0.20
18	251.007	8.68	-2.499	0.20
19	251.007	8.68	-2.499	0.20
20	250.942	8.68	-2.505	0.21
21	250.942	8.68	-2.505	0.21
22	250.91	8.68	-2.509	0.21
23	250.877	8.68	-2.512	0.21
24	250.845	8.68	-2.515	0.22
25	250.877	8.68	-2.512	0.21
26	250.812	8.68	-2.519	0.22
27	250.812	8.68	-2.519	0.22
28	250.78	8.68	-2.522	0.22
29	250.78	8.68	-2.522	0.22
30	250.747	8.68	-2.525	0.23
31	250.683	8.68	-2.532	0.23
32	250.683	8.68	-2.532	0.23
33	250.65	8.68	-2.535	0.24
34	250.65	8.68	-2.535	0.24
35	250.228	8.68	-2.578	0.28
36	250.488	8.68	-2.552	0.25
37	250.423	8.68	-2.558	0.26
38	250.358	8.68	-2.565	0.27
39	250.326	8.68	-2.568	0.27
40	250.293	8.68	-2.571	0.27
41	250.293	8.68	-2.571	0.27
42	250.293	8.68	-2.571	0.27
43	250.228	8.68	-2.578	0.28
44	250.228	8.68	-2.578	0.28
45	250.196	8.68	-2.581	0.28
46	250.196	8.68	-2.581	0.28
47	250.163	8.68	-2.585	0.29
48	250.131	8.68	-2.588	0.29
49	250.131	8.68	-2.588	0.29
50	250.098	8.68	-2.591	0.29
51	250.098	8.68	-2.591	0.29
52	250.098	8.68	-2.591	0.29
53	250.066	8.68	-2.595	0.30
54	250.034	8.68	-2.598	0.30
55	250.034	8.68	-2.598	0.30
56	250.034	8.68	-2.598	0.30
57	250.001	8.68	-2.601	0.30
58	250.001	8.68	-2.601	0.30
59	249.969	8.68	-2.604	0.30
60	249.969	8.68	-2.604	0.30
61	249.936	8.68	-2.608	0.31
62	249.936	8.68	-2.608	0.31
63	249.904	8.68	-2.611	0.31
64	249.871	8.68	-2.614	0.31
65	249.871	8.68	-2.614	0.31
66	249.871	8.68	-2.614	0.31
67	249.839	8.68	-2.618	0.32
68	249.839	8.68	-2.618	0.32
69	249.839	8.68	-2.618	0.32
70	249.839	8.68	-2.618	0.32
71	249.806	8.68	-2.621	0.32
72	249.806	8.68	-2.621	0.32
73	249.806	8.68	-2.621	0.32
74	249.806	8.68	-2.621	0.32
75	249.806	8.68	-2.621	0.32
76	249.806	8.68	-2.621	0.32
77	249.774	8.68	-2.624	0.32
78	249.774	8.68	-2.624	0.32
79	249.774	8.68	-2.624	0.32
80	249.774	8.68	-2.624	0.32
81	249.741	8.68	-2.628	0.33
82	249.741	8.68	-2.628	0.33
83	249.709	8.68	-2.631	0.33
84	249.709	8.68	-2.631	0.33
85	249.677	8.68	-2.634	0.33
86	249.709	8.68	-2.631	0.33

87	249.644	8.68	-2.638	0.34
88	249.677	8.68	-2.634	0.33
89	249.677	8.68	-2.634	0.33
90	249.644	8.68	-2.638	0.34
91	249.644	8.68	-2.638	0.34
92	249.644	8.68	-2.638	0.34
93	249.612	8.68	-2.641	0.34
94	249.612	8.68	-2.641	0.34
95	249.612	8.68	-2.641	0.34
96	249.579	8.68	-2.644	0.34
97	249.579	8.68	-2.644	0.34
98	249.579	8.68	-2.644	0.34
99	249.547	8.68	-2.648	0.35
100	249.547	8.68	-2.648	0.35
101	249.547	8.68	-2.648	0.35
102	249.547	8.68	-2.648	0.35
103	249.547	8.68	-2.648	0.35
104	249.547	8.68	-2.648	0.35
105	249.547	8.68	-2.648	0.35
106	249.514	8.68	-2.651	0.35
107	249.514	8.68	-2.651	0.35
108	249.514	8.68	-2.651	0.35
109	249.514	8.68	-2.651	0.35
110	249.482	8.68	-2.654	0.35
111	249.482	8.68	-2.654	0.35
112	249.482	8.68	-2.654	0.35
113	249.449	8.68	-2.658	0.36
114	249.449	8.68	-2.658	0.36
115	249.482	8.68	-2.654	0.35
116	249.449	8.68	-2.658	0.36
117	249.449	8.68	-2.658	0.36
118	249.417	8.68	-2.661	0.36
119	249.417	8.68	-2.661	0.36
120	249.417	8.68	-2.661	0.36
121	249.449	8.68	-2.658	0.36
122	249.417	8.68	-2.661	0.36
123	249.417	8.68	-2.661	0.36
124	249.417	8.68	-2.661	0.36
125	249.417	8.68	-2.661	0.36
126	249.385	8.68	-2.664	0.36
127	249.385	8.68	-2.664	0.36
128	249.385	8.68	-2.664	0.36
129	249.385	8.68	-2.664	0.36
130	249.385	8.68	-2.664	0.36
131	249.385	8.68	-2.664	0.36
132	249.352	8.68	-2.667	0.37
133	249.385	8.68	-2.664	0.36
134	249.352	8.68	-2.667	0.37
135	249.352	8.68	-2.667	0.37
136	248.963	8.68	-2.707	0.41
137	249.222	8.68	-2.681	0.38
138	249.287	8.68	-2.674	0.37
139	249.255	8.68	-2.677	0.38
140	249.287	8.68	-2.674	0.37
141	249.255	8.68	-2.677	0.38
142	249.287	8.68	-2.674	0.37
143	249.255	8.68	-2.677	0.38
144	249.287	8.68	-2.674	0.37
145	249.255	8.68	-2.677	0.38
146	249.255	8.68	-2.677	0.38
147	249.255	8.68	-2.677	0.38
148	249.255	8.68	-2.677	0.38
149	249.255	8.68	-2.677	0.38
150	249.255	8.68	-2.677	0.38
151	249.255	8.68	-2.677	0.38
152	249.222	8.68	-2.681	0.38
153	249.222	8.68	-2.681	0.38
154	249.222	8.68	-2.681	0.38
155	249.255	8.68	-2.677	0.38
156	249.255	8.68	-2.677	0.38
157	249.222	8.68	-2.681	0.38
158	249.222	8.68	-2.681	0.38
159	249.19	8.68	-2.684	0.38
160	249.222	8.68	-2.681	0.38
161	249.19	8.68	-2.684	0.38
162	249.222	8.68	-2.681	0.38
163	249.19	8.68	-2.684	0.38
164	249.157	8.68	-2.687	0.39
165	249.19	8.68	-2.684	0.38
166	249.157	8.68	-2.687	0.39
167	249.157	8.68	-2.687	0.39
168	249.157	8.68	-2.687	0.39
169	249.125	8.68	-2.691	0.39
170	249.125	8.68	-2.691	0.39
171	249.125	8.68	-2.691	0.39
172	249.125	8.68	-2.691	0.39
173	249.125	8.68	-2.691	0.39
174	249.125	8.68	-2.691	0.39
175	249.125	8.68	-2.691	0.39
176	249.125	8.68	-2.691	0.39
177	249.092	8.68	-2.694	0.39
178	249.125	8.68	-2.691	0.39
179	249.125	8.68	-2.691	0.39

180	249.092	8.68	-2.694	0.39
181	249.125	8.68	-2.691	0.39
182	249.092	8.68	-2.694	0.39
183	249.125	8.68	-2.691	0.39
184	249.125	8.68	-2.691	0.39
185	249.092	8.68	-2.694	0.39
186	249.125	8.68	-2.691	0.39
187	249.092	8.68	-2.694	0.39
188	249.06	8.68	-2.697	0.40
189	249.092	8.68	-2.694	0.39
190	249.092	8.68	-2.694	0.39
191	249.06	8.68	-2.697	0.40
192	249.092	8.68	-2.694	0.39
193	249.06	8.68	-2.697	0.40
194	249.06	8.68	-2.697	0.40
195	249.092	8.68	-2.694	0.39
196	249.06	8.68	-2.697	0.40
197	249.06	8.68	-2.697	0.40
198	249.06	8.68	-2.697	0.40
199	249.06	8.68	-2.697	0.40
200	249.028	8.68	-2.7	0.40
201	249.06	8.68	-2.697	0.40
202	249.028	8.68	-2.7	0.40
203	249.028	8.68	-2.7	0.40
204	249.028	8.68	-2.7	0.40
205	249.028	8.68	-2.7	0.40
206	249.028	8.68	-2.7	0.40
207	249.028	8.68	-2.7	0.40
208	249.028	8.68	-2.7	0.40
209	249.028	8.68	-2.7	0.40
210	248.995	8.68	-2.704	0.40
211	248.963	8.68	-2.707	0.41
212	249.028	8.68	-2.7	0.40
213	249.028	8.68	-2.7	0.40
214	248.995	8.68	-2.704	0.40
215	248.995	8.68	-2.704	0.40
216	248.995	8.68	-2.704	0.40
217	248.995	8.68	-2.704	0.40
218	248.995	8.68	-2.704	0.40
219	248.995	8.68	-2.704	0.40
220	248.995	8.68	-2.704	0.40
221	248.963	8.68	-2.707	0.41
222	248.995	8.68	-2.704	0.40
223	248.995	8.68	-2.704	0.40
224	248.963	8.68	-2.707	0.41
225	248.93	8.68	-2.71	0.41
226	248.963	8.68	-2.707	0.41
227	248.671	8.68	-2.737	0.44
228	248.865	8.68	-2.717	0.42
229	248.93	8.68	-2.71	0.41
230	248.93	8.68	-2.71	0.41
231	248.898	8.68	-2.714	0.41
232	248.93	8.68	-2.71	0.41
233	248.93	8.68	-2.71	0.41
234	248.963	8.68	-2.707	0.41
235	248.963	8.68	-2.707	0.41
236	248.93	8.68	-2.71	0.41
237	248.963	8.68	-2.707	0.41
238	248.93	8.68	-2.71	0.41
239	248.93	8.68	-2.71	0.41
240	248.508	8.68	-2.753	0.45
241	248.8	8.68	-2.724	0.42
242	248.865	8.68	-2.717	0.42
243	248.833	8.68	-2.72	0.42
244	248.865	8.68	-2.717	0.42
245	248.865	8.68	-2.717	0.42
246	248.898	8.68	-2.714	0.41
247	248.865	8.68	-2.717	0.42
248	248.865	8.68	-2.717	0.42
249	248.865	8.68	-2.717	0.42
250	248.865	8.68	-2.717	0.42
251	248.898	8.68	-2.714	0.41
252	248.865	8.68	-2.717	0.42
253	248.898	8.68	-2.714	0.41
254	248.865	8.68	-2.717	0.42
255	248.898	8.68	-2.714	0.41
256	248.865	8.68	-2.717	0.42
257	248.898	8.68	-2.714	0.41
258	248.865	8.68	-2.717	0.42
259	248.865	8.68	-2.717	0.42
260	248.865	8.68	-2.717	0.42
261	248.898	8.68	-2.714	0.41
262	248.865	8.68	-2.717	0.42
263	248.865	8.68	-2.717	0.42
264	248.865	8.68	-2.717	0.42
265	248.898	8.68	-2.714	0.41
266	248.898	8.68	-2.714	0.41
267	248.898	8.68	-2.714	0.41
268	248.898	8.68	-2.714	0.41
269	248.573	8.68	-2.747	0.45
270	248.768	8.68	-2.727	0.43
271	248.444	8.68	-2.76	0.46
272	248.314	8.68	-2.773	0.47

273	248.281	8.68	-2.777	0.48
274	248.573	8.68	-2.747	0.45
275	248.314	8.68	-2.773	0.47
276	248.216	8.68	-2.783	0.48
277	248.541	8.68	-2.75	0.45
278	248.638	8.68	-2.74	0.44
279	248.703	8.68	-2.734	0.43
280	248.768	8.68	-2.727	0.43
281	248.703	8.68	-2.734	0.43
282	248.736	8.68	-2.73	0.43
283	248.736	8.68	-2.73	0.43
284	248.768	8.68	-2.727	0.43
285	248.8	8.68	-2.724	0.42
286	248.768	8.68	-2.727	0.43
287	248.768	8.68	-2.727	0.43
288	248.8	8.68	-2.724	0.42
289	248.8	8.68	-2.724	0.42
290	248.8	8.68	-2.724	0.42
291	248.8	8.68	-2.724	0.42
292	248.768	8.68	-2.727	0.43
293	248.833	8.68	-2.72	0.42
294	248.8	8.68	-2.724	0.42
295	248.833	8.68	-2.72	0.42
296	248.833	8.68	-2.72	0.42
297	248.833	8.68	-2.72	0.42
298	248.833	8.68	-2.72	0.42
299	248.833	8.68	-2.72	0.42
300	248.833	8.68	-2.72	0.42
301	248.833	8.68	-2.72	0.42
302	248.865	8.68	-2.717	0.42
303	248.865	8.68	-2.717	0.42
304	248.865	8.68	-2.717	0.42
305	248.865	8.68	-2.717	0.42
306	248.865	8.68	-2.717	0.42
307	248.865	8.68	-2.717	0.42
308	248.865	8.68	-2.717	0.42
309	248.898	8.68	-2.714	0.41
310	248.898	8.68	-2.714	0.41
311	248.93	8.68	-2.71	0.41
312	248.898	8.68	-2.714	0.41
313	248.898	8.68	-2.714	0.41
314	248.898	8.68	-2.714	0.41
315	248.898	8.68	-2.714	0.41
316	248.898	8.68	-2.714	0.41
317	248.736	8.68	-2.73	0.43
318	248.8	8.68	-2.724	0.42
319	248.865	8.68	-2.717	0.42
320	248.865	8.68	-2.717	0.42
321	248.865	8.68	-2.717	0.42
322	248.865	8.68	-2.717	0.42
323	248.833	8.68	-2.72	0.42
324	248.898	8.68	-2.714	0.41
325	248.833	8.68	-2.72	0.42
326	248.865	8.68	-2.717	0.42
327	248.865	8.68	-2.717	0.42
328	248.898	8.68	-2.714	0.41
329	248.898	8.68	-2.714	0.41
330	248.898	8.68	-2.714	0.41
331	248.898	8.68	-2.714	0.41
332	248.898	8.68	-2.714	0.41
333	248.898	8.68	-2.714	0.41
334	248.898	8.68	-2.714	0.41
335	248.898	8.68	-2.714	0.41
336	248.898	8.68	-2.714	0.41
337	248.898	8.68	-2.714	0.41
338	248.898	8.68	-2.714	0.41
339	248.898	8.68	-2.714	0.41
340	248.898	8.68	-2.714	0.41
341	248.898	8.68	-2.714	0.41
342	248.898	8.68	-2.714	0.41
343	248.898	8.68	-2.714	0.41
344	248.898	8.68	-2.714	0.41
345	248.898	8.68	-2.714	0.41
346	248.898	8.68	-2.714	0.41
347	248.898	8.68	-2.714	0.41
348	248.898	8.68	-2.714	0.41
349	248.898	8.68	-2.714	0.41
350	248.93	8.68	-2.71	0.41
351	248.93	8.68	-2.71	0.41
352	248.93	8.68	-2.71	0.41
353	248.93	8.68	-2.71	0.41
354	248.93	8.68	-2.71	0.41
355	248.93	8.68	-2.71	0.41
356	248.93	8.68	-2.71	0.41
357	248.93	8.68	-2.71	0.41
358	248.93	8.68	-2.71	0.41
359	248.963	8.68	-2.707	0.41
360	248.93	8.68	-2.71	0.41

TW1- WELL RECOVERY VS. TIME - KOLLAARD FILE 190622



RECOVERY DATA TW-1

t'	t / t'	Abs Pres (kPa)	Temp (°C)	Water Level (m)	Drawdown (m)	Recovery (%)
1	361	249.904	8.68	-2.611	0.31	24%
2	181.0	250.196	8.68	-2.581	0.28	31%
3	121.0	250.326	8.68	-2.568	0.27	34%
4	91.0	250.391	8.68	-2.561	0.26	36%
5	73.0	250.52	8.68	-2.548	0.25	39%
6	61.0	250.585	8.68	-2.542	0.24	41%
7	52.4	250.618	8.68	-2.538	0.24	42%
8	46.0	250.65	8.68	-2.535	0.24	42%
9	41.0	250.715	8.68	-2.528	0.23	44%
10	37.0	250.747	8.68	-2.525	0.23	45%
11	33.7	250.812	8.68	-2.519	0.22	46%
12	31.0	250.845	8.68	-2.515	0.22	47%
13	28.7	250.91	8.68	-2.509	0.21	49%
14	26.7	250.942	8.68	-2.505	0.21	50%
15	25.0	250.975	8.68	-2.502	0.20	50%
16	23.5	250.975	8.68	-2.502	0.20	50%
17	22.2	251.04	8.68	-2.495	0.20	52%
18	21.0	251.072	8.68	-2.492	0.19	53%
19	19.9	251.104	8.68	-2.489	0.19	54%
20	19.0	251.104	8.68	-2.489	0.19	54%
21	18.1	251.137	8.68	-2.485	0.19	55%
22	17.4	251.169	8.68	-2.482	0.18	55%
23	16.7	251.202	8.68	-2.479	0.18	56%
24	16.0	251.234	8.68	-2.475	0.18	57%
25	15.4	251.234	8.68	-2.475	0.18	57%
26	14.8	251.04	8.68	-2.495	0.20	52%
27	14.3	251.104	8.68	-2.489	0.19	54%
28	13.9	251.267	8.68	-2.472	0.17	58%
29	13.4	251.04	8.68	-2.495	0.20	52%
30	13.0	251.299	8.68	-2.469	0.17	58%
31	12.6	251.397	8.68	-2.459	0.16	61%
32	12.3	251.397	8.68	-2.459	0.16	61%
33	11.9	251.429	8.68	-2.456	0.16	62%
34	11.6	251.429	8.68	-2.456	0.16	62%
35	11.3	251.461	8.68	-2.452	0.15	63%
36	11.0	251.461	8.68	-2.452	0.15	63%
37	10.7	251.494	8.68	-2.449	0.15	63%
38	10.5	251.526	8.68	-2.446	0.15	64%
39	10.2	251.559	8.68	-2.442	0.14	65%
40	10.0	251.559	8.68	-2.442	0.14	65%
41	9.8	251.559	8.68	-2.442	0.14	65%
42	9.6	251.559	8.68	-2.442	0.14	65%
43	9.4	251.559	8.68	-2.442	0.14	65%
44	9.2	251.267	8.68	-2.472	0.17	58%
45	9.0	251.494	8.68	-2.449	0.15	63%
46	8.8	251.559	8.68	-2.442	0.14	65%

47	8.7	251.591	8.68	-2.439	0.14	66%
48	8.5	251.624	8.68	-2.436	0.14	67%
49	8.3	251.624	8.68	-2.436	0.14	67%
50	8.2	251.656	8.68	-2.432	0.13	68%
51	8.1	251.656	8.68	-2.432	0.13	68%
52	7.9	251.656	8.68	-2.432	0.13	68%
53	7.8	251.689	8.68	-2.429	0.13	68%
54	7.7	251.721	8.68	-2.426	0.13	69%
55	7.5	251.721	8.68	-2.426	0.13	69%
56	7.4	251.721	8.68	-2.426	0.13	69%
57	7.3	251.754	8.68	-2.422	0.12	70%
58	7.2	251.786	8.68	-2.419	0.12	71%
59	7.1	251.754	8.68	-2.422	0.12	70%
60	7.0	251.786	8.68	-2.419	0.12	71%
61	6.9	251.819	8.68	-2.416	0.12	71%
62	6.8	251.819	8.68	-2.416	0.12	71%
63	6.7	251.851	8.68	-2.413	0.11	72%
64	6.6	251.883	8.68	-2.409	0.11	73%
65	6.5	251.851	8.68	-2.413	0.11	72%
66	6.5	251.883	8.68	-2.409	0.11	73%
67	6.4	251.883	8.68	-2.409	0.11	73%
68	6.3	251.916	8.68	-2.406	0.11	74%
69	6.2	251.948	8.68	-2.403	0.10	75%
70	6.1	251.948	8.68	-2.403	0.10	75%
71	6.1	251.948	8.68	-2.403	0.10	75%
72	6.0	251.948	8.68	-2.403	0.10	75%
73	5.9	251.948	8.68	-2.403	0.10	75%
74	5.9	251.981	8.68	-2.399	0.10	76%
75	5.8	251.981	8.68	-2.399	0.10	76%
76	5.7	252.013	8.68	-2.396	0.10	76%
77	5.7	252.013	8.68	-2.396	0.10	76%
78	5.6	252.046	8.68	-2.393	0.09	77%
79	5.6	252.046	8.68	-2.393	0.09	77%
80	5.5	252.046	8.68	-2.393	0.09	77%
81	5.4	252.046	8.68	-2.393	0.09	77%
82	5.4	252.078	8.68	-2.389	0.09	78%
83	5.3	252.078	8.68	-2.389	0.09	78%
84	5.3	252.078	8.68	-2.389	0.09	78%
85	5.2	252.078	8.68	-2.389	0.09	78%
86	5.2	252.078	8.68	-2.389	0.09	78%
87	5.1	252.111	8.68	-2.386	0.09	79%
88	5.1	252.143	8.68	-2.383	0.08	80%
89	5.0	252.143	8.68	-2.383	0.08	80%
90	5.0	252.143	8.68	-2.383	0.08	80%
91	5.0	252.176	8.68	-2.379	0.08	81%
92	4.9	252.176	8.68	-2.379	0.08	81%
93	4.9	252.176	8.68	-2.379	0.08	81%
94	4.8	252.176	8.68	-2.379	0.08	81%
95	4.8	252.208	8.68	-2.376	0.08	81%
96	4.8	252.24	8.68	-2.373	0.07	82%

97	4.7	252.24	8.68	-2.373	0.07	82%
98	4.7	252.24	8.68	-2.373	0.07	82%
99	4.6	252.24	8.68	-2.373	0.07	82%
100	4.6	252.24	8.68	-2.373	0.07	82%
101	4.6	252.273	8.68	-2.37	0.07	83%
102	4.5	252.24	8.68	-2.373	0.07	82%
103	4.5	252.273	8.68	-2.37	0.07	83%
104	4.5	252.305	8.68	-2.366	0.07	84%
105	4.4	252.305	8.68	-2.366	0.07	84%
106	4.4	252.305	8.68	-2.366	0.07	84%
107	4.4	252.305	8.68	-2.366	0.07	84%
108	4.3	252.338	8.68	-2.363	0.06	85%
109	4.3	252.338	8.68	-2.363	0.06	85%
110	4.3	252.338	8.68	-2.363	0.06	85%
111	4.2	252.013	8.68	-2.396	0.10	76%
112	4.2	252.24	8.68	-2.373	0.07	82%
113	4.2	252.273	8.68	-2.37	0.07	83%
114	4.2	252.338	8.68	-2.363	0.06	85%
115	4.1	252.338	8.68	-2.363	0.06	85%
116	4.1	252.338	8.68	-2.363	0.06	85%
117	4.1	252.403	8.68	-2.356	0.06	86%
118	4.1	252.403	8.68	-2.356	0.06	86%
119	4.0	252.403	8.68	-2.356	0.06	86%
120	4.0	252.403	8.68	-2.356	0.06	86%
121	4.0	252.403	8.68	-2.356	0.06	86%
122	4.0	252.403	8.68	-2.356	0.06	86%
123	3.9	252.435	8.68	-2.353	0.05	87%
124	3.9	252.468	8.68	-2.35	0.05	88%
125	3.9	252.468	8.68	-2.35	0.05	88%
126	3.9	252.468	8.68	-2.35	0.05	88%
127	3.8	252.468	8.68	-2.35	0.05	88%
128	3.8	252.468	8.68	-2.35	0.05	88%
129	3.8	252.5	8.68	-2.346	0.05	89%
130	3.8	252.5	8.68	-2.346	0.05	89%
131	3.7	252.5	8.68	-2.346	0.05	89%
132	3.7	252.5	8.68	-2.346	0.05	89%
133	3.7	252.5	8.68	-2.346	0.05	89%
134	3.7	252.533	8.68	-2.343	0.04	89%
135	3.7	252.533	8.68	-2.343	0.04	89%
136	3.6	252.533	8.68	-2.343	0.04	89%
137	3.6	252.565	8.68	-2.34	0.04	90%
138	3.6	252.565	8.68	-2.34	0.04	90%
139	3.6	252.565	8.68	-2.34	0.04	90%
140	3.6	252.565	8.68	-2.34	0.04	90%
141	3.6	252.63	8.68	-2.333	0.03	92%
142	3.5	252.597	8.68	-2.337	0.04	91%
143	3.5	252.597	8.68	-2.337	0.04	91%
144	3.5	252.597	8.68	-2.337	0.04	91%
145	3.5	252.63	8.68	-2.333	0.03	92%
146	3.5	252.63	8.68	-2.333	0.03	92%

147	3.4	252.63	8.68	-2.333	0.03	92%
148	3.4	252.662	8.68	-2.33	0.03	93%
149	3.4	252.63	8.68	-2.333	0.03	92%
150	3.4	252.662	8.68	-2.33	0.03	93%
151	3.4	252.662	8.68	-2.33	0.03	93%
152	3.4	252.695	8.68	-2.327	0.03	93%
153	3.4	252.695	8.68	-2.327	0.03	93%
154	3.3	252.695	8.68	-2.327	0.03	93%
155	3.3	252.338	8.68	-2.363	0.06	85%
156	3.3	252.533	8.68	-2.343	0.04	89%
157	3.3	252.63	8.68	-2.333	0.03	92%
158	3.3	252.37	8.68	-2.36	0.06	85%
159	3.3	252.533	8.68	-2.343	0.04	89%
160	3.3	252.63	8.68	-2.333	0.03	92%
161	3.2	252.662	8.68	-2.33	0.03	93%
162	3.2	252.695	8.68	-2.327	0.03	93%
163	3.2	252.727	8.68	-2.323	0.02	94%
164	3.2	252.727	8.68	-2.323	0.02	94%
165	3.2	252.727	8.68	-2.323	0.02	94%
166	3.2	252.76	8.68	-2.32	0.02	95%
167	3.2	252.76	8.68	-2.32	0.02	95%
168	3.1	252.792	8.68	-2.317	0.02	96%
169	3.1	252.76	8.68	-2.32	0.02	95%
170	3.1	252.792	8.68	-2.317	0.02	96%
171	3.1	252.792	8.68	-2.317	0.02	96%
172	3.1	252.792	8.68	-2.317	0.02	96%
173	3.1	252.792	8.68	-2.317	0.02	96%
174	3.1	252.825	8.68	-2.313	0.01	97%
175	3.1	252.825	8.68	-2.313	0.01	97%
176	3.0	252.825	8.68	-2.313	0.01	97%
177	3.0	252.825	8.68	-2.313	0.01	97%
178	3.0	252.857	8.68	-2.31	0.01	98%
179	3.0	252.89	8.68	-2.307	0.01	98%
180	3.0	252.857	8.68	-2.31	0.01	98%
181	3.0	252.857	8.68	-2.31	0.01	98%
182	3.0	252.89	8.68	-2.307	0.01	98%
183	3.0	252.89	8.68	-2.307	0.01	98%
184	3.0	252.89	8.68	-2.307	0.01	98%
185	2.9	252.89	8.68	-2.307	0.01	98%
186	2.9	252.89	8.68	-2.307	0.01	98%
187	2.9	252.922	8.68	-2.303	0.00	99%
188	2.9	252.922	8.68	-2.303	0.00	99%
189	2.9	252.922	8.68	-2.303	0.00	99%
190	2.9	252.955	8.68	-2.3	0.00	100%



ATTACHMENT C
RESULTS OF LABORATORY TESTING
OF WELL WATER SAMPLES

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#: 190622
Invoice to: Kollaard Associates Inc.


Report Number: 1940492
Date Submitted: 2020-10-08
Date Reported: 2020-10-20
Project: 190622
COC #: 198013

Page 1 of 5

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: 
Addrine Thomas, Inorganics Supervisor

Addrine
Thomas
2020.10.20
09:54:00 -04'00'

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#: 190622
 Invoice to: Kollaard Associates Inc.

Report Number: 1940492
 Date Submitted: 2020-10-08
 Date Reported: 2020-10-20
 Project: 190622
 COC #: 198013

Group	Analyte	MRL	Units	Guideline	1521365 GW 2020-10-07 3904 March Rd - 3hr	1521366 GW 2020-10-07 3904 March Rd - 6hr
Anions	Cl	1	mg/L	AO 250	23	24
	F	0.10	mg/L	MAC 1.5	0.20	<0.10
	N-NO2	0.10	mg/L	MAC 1.0	<0.10	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	0.21	1.54
	SO4	1	mg/L	AO 500	39	44
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	247	240
	Colour	2	TCU		<2	<2
	Conductivity	5	uS/cm		578	611
	DOC	0.5	mg/L	AO 5	1.2	1.4
	pH	1.00		6.5-8.5	8.12	8.14
	S2-	0.01	mg/L	AO 0.05	<0.01	<0.01
	TDS (COND - CALC)	1	mg/L	AO 500	376	397
	Turbidity	0.1	NTU	AO 5.0	7.3*	5.5*
Hardness	Hardness as CaCO3	1	mg/L	OG 100	253*	271*
Indices/Calc	Ion Balance	0.01			0.92	0.99
Metals	Ca	1	mg/L		70	74
	Fe	0.03	mg/L	AO 0.3	0.68*	0.52*
	K	1	mg/L		5	8
	Mg	1	mg/L		19	21
	Mn	0.01	mg/L	AO 0.05	0.05	0.06*
	Na	2	mg/L	AO 200	17	18
Subcontract-Inorg	N-NH3	0.01	mg/L		0.17	0.22
	Phenols	0.001	mg/L		<0.001	<0.001
	Tannin & Lignin	0.1	mg/L		<0.1	<0.1
	Total Kjeldahl Nitrogen	0.1	mg/L		0.2	0.3

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#: 190622
 Invoice to: Kollaard Associates Inc.

Report Number: 1940492
 Date Submitted: 2020-10-08
 Date Reported: 2020-10-20
 Project: 190622
 COC #: 198013

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 390581 Analysis/Extraction Date 2020-10-08 Analyst AG			
Method C SM2130B			
Turbidity	<0.1 NTU	100	70-130
Run No 390585 Analysis/Extraction Date 2020-10-08 Analyst AET			
Method C SM4500-S2-D			
S2-	<0.01 mg/L	105	80-120
Run No 390720 Analysis/Extraction Date 2020-10-13 Analyst H D			
Method EPA 200.8			
Iron	<0.03 mg/L	92	80-120
Manganese	<0.01 mg/L	98	80-120
Run No 390727 Analysis/Extraction Date 2020-10-13 Analyst Z S			
Method M SM3120B-3500C			
Calcium	<1 mg/L	104	90-110
Potassium	<1 mg/L	95	87-113
Magnesium	<1 mg/L	112	76-124
Sodium	<2 mg/L	97	82-118
Run No 390755 Analysis/Extraction Date 2020-10-14 Analyst QT			
Method C SM2120C			
Colour	<2 TCU	101	90-110

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#: 190622
 Invoice to: Kollaard Associates Inc.

Report Number: 1940492
 Date Submitted: 2020-10-08
 Date Reported: 2020-10-20
 Project: 190622
 COC #: 198013

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 390759 Analysis/Extraction Date 2020-10-14 Analyst QT			
Method SM2320,2510,4500H/F			
Alkalinity (CaCO3)	<5 mg/L	102	90-110
Conductivity	<5 uS/cm	99	90-110
F	<0.10 mg/L	102	90-110
pH		99	90-110
Run No 390799 Analysis/Extraction Date 2020-10-09 Analyst AET			
Method SUBCONTRACT P-INORG			
Phenols	<0.001 mg/L	100	69-132
Tannin & Lignin	<0.1 mg/L	80	
Run No 390857 Analysis/Extraction Date 2020-10-15 Analyst AG			
Method SM 5310B			
DOC	<0.5 mg/L	102	80-120
Run No 390921 Analysis/Extraction Date 2020-10-17 Analyst SKH			
Method SM 4110			
Chloride	<1 mg/L	100	90-110
N-NO2	<0.10 mg/L	107	90-110
N-NO3	<0.10 mg/L	107	90-110
SO4	<1 mg/L	100	90-110

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#: 190622
 Invoice to: Kollaard Associates Inc.

Report Number: 1940492
 Date Submitted: 2020-10-08
 Date Reported: 2020-10-20
 Project: 190622
 COC #: 198013

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 391015 Analysis/Extraction Date 2020-10-19 Analyst AET Method SUBCONTRACT P-INORG			
N-NH3	<0.01 mg/L	88	
Total Kjeldahl Nitrogen	<0.1 mg/L	101	81-126
Run No 391018 Analysis/Extraction Date 2020-10-20 Analyst AET Method C SM2340B			
Hardness as CaCO3			
Ion Balance			
TDS (COND - CALC)			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



Certificate of Analysis

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#: 190622
Invoice to: Kollaard Associates Inc.

Report Number: 1940498
Date Submitted: 2020-10-08
Date Reported: 2020-10-11
Project: 190622
COC #: 198013

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Dragana
Dzeletovic
2020.10.11
13:01:36
-04'00'

APPROVAL: _____
Dragana Dzeletovic-Andric, Microbiology Team Lead

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Certificate of Analysis

Client: Kollaard Associates Inc.
 210 Prescott St., Box 189
 Kemptville, ON
 K0G 1J0
 Attention: Ms. Colleen Vermeersch
 PO#: 190622
 Invoice to: Kollaard Associates Inc.

Report Number: 1940498
 Date Submitted: 2020-10-08
 Date Reported: 2020-10-11
 Project: 190622
 COC #: 198013

Group	Analyte	MRL	Units	Guideline	Lab I.D. Sample Matrix Sample Type Sampling Date Sample I.D.	1521376 GW 2020-10-07 3904 March Rd - 3hr	1521377 GW 2020-10-07 3904 March Rd - 6hr
Microbiology	Escherichia Coli	0	ct/100mL	MAC 0		0	0
	Faecal Coliforms	0	ct/100mL			0	0
	Heterotrophic Plate Count	0	ct/1mL			34	6
	Total Coliforms	0	ct/100mL	MAC 0		3*	2*

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



Certificate of Analysis

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1963628
Date Submitted: 2021-09-29
Date Reported: 2021-09-30
Project: 3904 March Rd
COC #: 880746

Dear Colleen Vermeersch:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Dragana
Dzeletovic
2021.09.30
16:31:12

Dragana Andric

APPROVAL: _____ -04'00'
Dragana Dzeletovic-Andric, Microbiology Team Lead

All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise indicated.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at: <http://www.cala.ca/scopes/2602.pdf>.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is licensed by the Ontario Ministry of the Environment, Conservation, and Parks (MECP) for specific tests in drinking water (license #2318). A copy of the license is available upon request.

Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) is accredited by the Ontario Ministry of Agriculture, Food, and Rural Affairs for specific tests in agricultural soils.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.



Certificate of Analysis

Client: Kollaard Associates Inc.
210 Prescott St., Box 189
Kemptville, ON
K0G 1J0
Attention: Ms. Colleen Vermeersch
PO#:
Invoice to: Kollaard Associates Inc.

Report Number: 1963628
Date Submitted: 2021-09-29
Date Reported: 2021-09-30
Project: 3904 March Rd
COC #: 880746

Lab I.D. 1586042
Sample Matrix Water
Sample Type
Sampling Date 2021-09-29
Sample I.D. 3904 March Rd

Group	Analyte	MRL	Units	Guideline	
Microbiology	Total Coliforms	0	ct/100mL	MAC 0	0

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



ATTACHMENT D
SEWAGE EFFLUENT DILUTION CALCULATIONS

SEPTIC EFFLUENT DILUTION CALCULATIONS

Sewage Effluent for single family dwelling	365 m ³ /year
Sewage Effluent for commercial use	1834.13 m ³ /year
Total sewage design	2199.13 m ³ /year
Gross Site Area	95,800 m ²
Env. Can. Water Surplus (NPI)	372.2 mm

Hard Surface Area (Post-Development)

Roofs	1440
gravel area	<u>2640</u>
Total	4080 m ²

Net Infiltration Area = Gross Site Area - Hard Surface Area (Post-Development)
91,720 m²

Infiltration Reduction Factor:

Topography (rolling)	0.30
Soil (open sandy loam)	0.40
<u>Cover (cultivated/orchard)</u>	<u>0.15</u>
Total IRF	0.85

Septic Dilution For the combined effluent for the site:

$$\frac{\text{Volume Effluent Per Year} \times 40 \text{ mg/L NO}_3}{\text{Volume Effluent Per Year} + (\text{Net Infiltration Area} \times \text{NPI} \times \text{IRF})} = 2.8 \text{ mg/L NO}_3\text{-N}$$