

Geotechnical Investigation

Client:

Conseil des École Catholiques du Centre-Est (CECCE) 4000 Labelle Street, Ottawa, Ontario K1J 1A1 Attn: Denis Chabot, C.E.T., LEED G.A.

Type of Document:

Final Report

Project Name:

Geotechnical Investigation Proposed Avalon III Elementary School 2666 Tenth Line Road Orleans (Ottawa), Ontario

Project Number:

OTT-22017859-A0

Prepared By:

EXP Services Inc. 100-2650 Queensview Drive Ottawa, Ontario K2B 8H6 Canada

Date Submitted:

2023-03-07

Table of Contents

Execu	utive Sur	nmary	1
1.	Intro	duction	3
2.	Site D	Description	4
3.	Proce	edure	5
4.	Subsu	urface Conditions and Groundwater Levels	7
	4.1	Topsoil	7
	4.2	Granular Fill	7
	4.3	Reclaimed Asphalt Pavement (RAP) Fill	7
	4.4	Fill	7
	4.5	Clay	8
	4.6	Glacial Till	9
	4.7	Cone Refusal	10
	4.8	Limestone Bedrock	10
	4.9	Groundwater Level Measurements	10
5.	Site C	Classification for Seismic Site Response and Liquefaction Potential of Soils	11
	5.1	Site Classification for Seismic Site Response	11
	5.2	Liquefaction Potential of Soils	11
6.	Grade	e Raise Restrictions	12
7.	Site G	Grading	13
8.	Found	dation Considerations	14
	8.1	Spread and Strip Footings	14
	8.2	Pile Foundation	14
	8.3	General Comments	16
9.	Floor	Slab and Drainage Requirements	17
10.	Excav	ration and De-Watering Requirements	18
	10.1	Excess Soil Management	18
	10.2	Excavations	18
	10.3	De-Watering Requirements	18
11.	Pipe I	Bedding Requirements	20
12.	Backf	illing Requirements and Suitability of On-Site Soils for Backfilling Purposes	21
13.	Acces	ss Roads and Parking Lots	22
14.	Chem	nical Test Results and Corrosion Potential of Subsurface Soils	24

CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

15.	Tree Planting Restrictions	. 25
16.	Additional Comments	.26
17.	General Comments	.27
List o	of Tables	
Table I:	Summary of Laboratory Testing Program	5
Table II	: Summary of Grain-size Analysis Results – Fill Sample	8
Table II	II: Summary of Grain-size Analysis and Atterberg Limits Test Results – Brown Clay Crust Samples	8
Table I\	V: Summary of Grain-size Analysis and Atterberg Limits Test Results – Grey Clay Samples	9
Table V	': One-Dimensional Oedometer Test Results - Grey Clay Samples	9
Table V	/I: Summary of Groundwater Level Measurements	.10
Table V	II: Factored Geotechnical Resistance at Ultimate Limit State (ULS) and Estimated Negative Skin Friction of Steel Pipe and H-Piles	. 15
Table V	/III: Recommended Pavement Structure Thicknesses	.22
Table I	X: Chemical Analyses Test Results and Corrosion Potential of Soil	.24

Appendices

Appendix A – Multi-channel Analysis of Surface Waves (MASW) Survey Report

Appendix B – Laboratory Certificate of Analysis

Legal Notification

List of Distribution

List of Figures

Figure 1 – Site Location Plan

Figures 2 – Borehole Location Plan

Figures 3 to 32 – Borehole and Test Pit Logs

Figures 33 - Borehole 1 Rock Core Photographs

Figure 34 – Grain-size Distribution Curve of Fill

Figures 35 to 40 – Grain Size Analyses and Atterberg Limit Tests on Desiccated Clay

Figures 41 to 46 – Grain Size Analyses and Atterberg Limit Tests on Grey Clay

Figures 47 and 48 – Consolidation Test Results on Clay Samples

March 7, 2023

Executive Summary

EXP Services Inc. (EXP) is pleased to present the results of the geotechnical investigation completed for the proposed Avalon III Elementary school to be located on the parcel of land registered by the street address of 2666 Tenth Line Road, City of Ottawa, Ontario (Figure 1). Written authorization to proceed with this geotechnical investigation was provided by the Conseil Catholique de Centre East (CECCE).

The proposed school will consist of a two-storey basementless structure with associated outdoor sports fields, parking lots and access roads, future portables and the installation of underground municipal services. The finished ground floor of the proposed school building and exterior grades were not available at the time of preparation of this report.

The site is currently occupied by several residential buildings which will be demolished to allow the construction of the proposed school. The rest of the site is currently used as a storage facility for a local developer.

A Phase I and II environmental site assessments were also completed by exp concurrently with the geotechnical investigation and were presented under separate cover.

The fieldwork was undertaken from December 8 to 22, 2022 and on January 12, 2023, and consisted of the drilling of thirteen (13) boreholes and excavating seventeen (17) test pits advanced to depths ranging between 1 m and 37.7 m below grade. Standpipes and monitoring wells were installed in selected boreholes for long term monitoring and sampling of the groundwater table at the site.

The borehole information indicates the subsurface conditions consist of surficial fill underlain by an original topsoil layer which extends to depths of 1.2 m to 2.4 m (Elevation 84.5 to 85.7 m). The fill and topsoil are underlain by a thick deposit of soft to hard clay extending to the maximum depth investigated in all the boreholes except in Borehole No. 1 where the clay deposit was proven to extend to a depth of 33 m (Elevation 54.1 m). It is underlain by a 0.8 m thick glacial till layer and limestone bedrock proven to a depth of 37.7 m below grade (Elevation 49.4 m). The groundwater is expected to be at a depth of 3 m to 4 m below the existing ground surface, i.e., Elevation 83.0 m to Elevation 86.9 m approximately.

One-dimensional consolidation tests conducted on two undisturbed clay samples revealed the clay to be pre-consolidated to 65 kPa to 115 kPa.

Based on the results of the Multi-channel Analysis of Surface Waves (MASW) survey (shear wave velocity) and comparison of the survey results to Table 4.1.8.4.A of the 2012 Ontario Building Code (as amended May 2, 2019), the site classification for seismic response is **Class E.** The subsurface soils are not susceptible to liquefaction during a seismic event.

The site is underlain by a clay deposit that is prone to consolidation settlement if overstressed by loads imposed on it by site grade raise, foundations and by permanent lowering of the groundwater level following construction. Overstressing of the clay will result in its consolidation and subsequent settlement of foundations, which may exceed tolerable limits of the structure resulting in cracking of the structure.

Based on a review of the engineering properties of the existing on-site fill and clay in conjunction with the recommended bearing pressure at serviceability limit state (SLS) for foundations presented in Section 8 of the report, it is considered that the existing grades at the site should not be raised.

Based on a review of the borehole information and laboratory test results, it is considered feasible to support the proposed school building on strip and spread square footings founded on the native upper desiccated brown clay crust or engineered fill provided that the conditions listed in Section 8.1 of the report are satisfied. If these conditions cannot be satisfied, the proposed structure should be founded on piles. Assuming that the conditions listed in Section 8.1 can be satisfied, the structure may be founded on spread and strip footings using Serviceability Limit State (SLS) bearing pressure of 60 kPa and factored geotechnical resistance of 75 kPa. The maximum width of the strip footing should be limited to 1.0 m and that of the square footings 3 m by 3 m. The settlements of the structure under the recommended design loads are expected to be close to 25 mm total and 19 mm differential.



March 7, 2023

If the above grade raise restriction and available SLS bearing pressure is insufficient to use spread and strip foundations, it would be necessary to found the proposed school building on end bearing piles as per the recommendation stated in this report.

The fill and original topsoil should be removed from the envelope of the proposed school building, access road, parking lot and future portable and replaced with well engineered material as per the recommendations of the report. Handling of excess soil off site should be undertaken as per the recommendations of the Phase I/II environmental assessment reports completed by exp for the site.

The lowest level floor slab (ground floor) of the proposed building may be designed as a slab-on-grade constructed on the engineered fill pad. Perimeter drains are recommended. Underfloor drains will not be required.

All excavations must be undertaken in accordance with the Occupational Health and Safety Act (OHSA), Ontario Reg. 213/91. Based on the definitions provided in OHSA, the subsurface soils on site are considered to be Type 3 and as such the sidewalls of the excavation must be cut back at 1H:1V from the bottom of the excavation. Below the groundwater level, the excavation side slopes are expected to slough and eventually stabilize at a slope of 3H:1V to 2H:1V.

Seepage of the surface and subsurface water into the excavations is anticipated and it should be possible to collect any water entering the excavations at low points and to remove it by conventional pumping techniques.

It is anticipated that all the material required for backfilling purposes in the interior and exterior of the building and for trench backfill would have to be imported and should preferably conform to the requirement presented in Section 12 of the report.

The above and other related considerations are discussed in greater detail in the main body of the report.



March 7, 2023

1. Introduction

EXP Services Inc. (EXP) is pleased to present the results of the geotechnical investigation completed for the proposed Avalon III Elementary school to be located on the parcel of land registered by the street address of 2666 Tenth Line Road, City of Ottawa, Ontario (Figure 1). Written authorization to proceed with this geotechnical investigation was provided by the Conseil Catholique de Centre East (CECCE).

The proposed school will consist of a two-storey basementless structure with associated outdoor sports fields, parking lots and access roads, future portables, and the installation of underground municipal services. The finished ground floor of the proposed school building and exterior grades were not available at the time of preparation of this report.

The site is currently occupied by several residential buildings which will be demolished to allow the construction of the proposed school. The rest of the site is used as a storage facility by a local developer.

A Phase I and II environmental site assessments were also completed by exp concurrently with the geotechnical investigation and were presented under separate cover.

The geotechnical investigation was undertaken to:

- a) Establish the subsurface soil and groundwater conditions at thirteen (13) boreholes and seventeen (17) test pits put down throughout the site;
- b) Classify the site for seismic site response in accordance with the requirements of the 2012 Ontario Building Code (as amended May 2, 2019) and assess the potential for liquefaction of the subsurface soils during a seismic event;
- c) Comment on grade-raise restrictions;
- d) Make recommendations regarding the most suitable type of foundations, founding depth and bearing pressure at serviceability limit state (SLS) and factored geotechnical resistance at ultimate limit state (ULS) of the founding strata and comment on the anticipated total and differential settlements of the recommended foundation type;
- e) Provide comment regarding slab-on-grade construction and the requirement for perimeter and underfloor drainage systems;
- f) Comment on excavation conditions and de-watering requirements during construction;
- g) Provide pipe bedding requirements for underground services;
- h) Discuss backfilling requirements and suitability of on-site soils for backfilling purposes;
- i) Recommend pavement structure thicknesses for access roads and parking lots; and,
- j) Comment on subsurface concrete requirements and corrosion potential of subsurface soils to buried metal structures/ members.

The comments and recommendations given in this report are based on the assumption that the above-described design concepts will proceed into construction. If changes are made either in the design phase or during construction, this office must be retained to review these modifications. The result of this review may be a modification of our recommendations or it may require additional field or laboratory work to check whether the changes are acceptable from a geotechnical viewpoint.



March 7, 2023

2. Site Description

The site is bounded by Tenth Line Road to the east, Sweetvalley Drive to the north, McKinnon Creek to the west and a single-family residential dwelling to the south. McKinnon Creek of the South Nation Conservation Authority flows north to south along the west site boundary towards bear brook. The site is located in a residential area with vacant land to the west.

The site is a relatively flat parcel of land currently occupied by an abandoned single-family residential dwelling, a temporary construction site office, and a garage and yard used for storage of construction materials. The ground cover of the site consists primarily of tall grass, gravel driveways and parking surfaces.



CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

3. Procedure

The fieldwork was undertaken on December 8 to 22, 2022, and January 12, 2023, and consisted of thirteen (13) boreholes advanced to termination and cone refusal depths of 4.9 m to 37.7 m below existing grade, and seventeen (17) test pits advanced to termination depths of 1 m to 2.6 m below existing grade. The borehole and test pit locations and geodetic elevations were established on site by EXP. The borehole and test pit locations are shown on the borehole location plan, Figure 2. The fieldwork was supervised on a full-time basis by a representative from EXP.

The borehole locations were cleared of private and public underground services, prior to the start of drilling operations. The boreholes were drilled using a CME-45 track mounted drill rig equipped with continuous flight hollow stem augers and soil sampling capabilities. Auger samples were obtained in some of the boreholes from the ground surface to a 0.6 m depth. Standard penetration tests (SPTs) were performed in all the boreholes at 0.75 m to 1.5 m depth intervals with the soil samples retrieved by the split-barrel sampler. Dynamic cone penetration test (DCPT) was conducted in Borehole No. 3 from an 8.5 m depth to cone refusal depth at 36.3 m below existing grade. The shear strength of the clayey soils was measured by conducting penetrometer and in-situ vane (field and Nilcon) tests at selected depth intervals. Relatively undisturbed samples (Shelby tube samples) of the clayey soils were retrieved at selected depth intervals. Borehole No. 1 was advanced with casing and wash boring techniques from 6.1 m depth to 33.0 m depth and then coring techniques were used to retrieve samples of bedrock to a termination depth of 37.7 m below ground surface.

Nineteen-millimetre diameter standpipes with slotted sections were installed in three (3) boreholes and 50 mm diameter monitoring wells with screened section were installed in three (3) boreholes for long-term monitoring of the groundwater levels. The standpipes were installed in accordance with EXP standard practice and the installation configuration is documented on the respective borehole log. All boreholes were backfilled upon completion of drilling and the installation of the standpipes and monitoring wells.

All the soil samples were visually examined in the field for textural classification, logged, preserved in plastic bags and identified. On completion of the fieldwork, all soil and rock samples were transported to the EXP laboratory in Ottawa.

A multi-channel analysis of surface waves (MASW) survey was conducted on site on November 24, 2022, by Geophysics (GPR) International Inc. in order to measure the shear wave velocity and to determine the site classification for seismic site response based on the shear wave velocity measurements. The procedure and report of the MASW survey are included in Appendix A.

A summary of the soil and rock sample laboratory testing program is shown in Table I. The laboratory testing program for selected soil samples from the boreholes were undertaken in accordance with the American Society for Testing and Materials (ASTM) specifications. The corrosion analysis of selected soil samples was undertaken in accordance with the methods outlined in the Laboratory Certificate of Analysis included in Appendix B.

Table I: Summary of Laboratory Testing Program						
Type of Test	Number of Tests Completed					
Soil Samples						
Moisture Content Determination	129					
Unit Weight Determination	25					
Grain Size Analysis	7					
Atterberg Limit Determination	6					
One-Dimensional Consolidation Test	2					
Corrosion Analysis (pH, sulphate, chloride and resistivity)	3					



Project Name: Geotechnical Investigation – Proposed Avalon III Elementary School

2666 Tenth Line Road, Ottawa, Ontario CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

Table I: Summary of Laboratory Testing Program							
Type of Test	Number of Tests Completed						
Rock Cores							
Unit Weight Determination	2						
Unconfined Compressive Strength	2						



CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

4. Subsurface Conditions and Groundwater Levels

A detailed description of the subsurface conditions and groundwater levels from the test holes are given on the attached borehole logs and test pit logs, Figures 3 to 32. The test hole logs and related information depict subsurface conditions only at the specific locations and times indicated. Subsurface conditions and water levels at other locations may differ from conditions at the locations where sampling was conducted. The passage of time also may result in changes in the conditions interpreted to exist at the locations where sampling was conducted.

Test holes were completed to provide representation of subsurface conditions as part of a geotechnical exploration program and are not intended to provide evidence of potential environmental conditions.

It should be noted that the soil boundaries indicated on the borehole logs are inferred from non-continuous sampling and observations during drilling operations. These boundaries are intended to reflect approximate transition zones for the purpose of geotechnical design and should not be interpreted as exact planes of geological change. The "Note on Sample Descriptions" preceding the borehole logs form an integral part of this report and should be read in conjunction with this report.

A review of the test hole logs indicates the following subsurface conditions with depth and groundwater level measurements.

4.1 Topsoil

A surficial topsoil layer was contacted in Borehole Nos. 10, 12 and 15 as well as Test Pit Nos. 1, 2, 8, 9, 11, 13, and 14. The topsoil ranges in thickness from 100 mm to 300 mm.

A buried topsoil layer was encountered in Borehole Nos. 1, 2, 3, 5, 11, 12, and 13, as well as Test Pit Nos. 1, 4, 5, 6, 7, 8, 9, 10, 13, 14, 15, and 16. It was encountered at depths of 0.8 m to 2.0 m (Elevation 86.0 m to 85.3 m) and extended to depths of 1.1 m to 2.3 m (Elevation 85.7 m to 85.1 m)

4.2 Granular Fill

Granular fill consisting of crushed limestone sand and gravel, sometimes containing topsoil inclusions was encountered from the surface in Borehole Nos. 2, 3, and 8 as well as Test Pit Nos. 4, 5, 6, and 10. Granular fill was buried in Test Pit No. 13 at a depth of 0.7 m and extends to a depth of 1.0 m (Elevation 86.6 m to 86.3 m). The granular fill had a moisture content ranging from 5 percent to 23 percent.

4.3 Reclaimed Asphalt Pavement (RAP) Fill

Reclaimed asphalt pavement was encountered from the surface in Borehole No. 11 and Test Pit No. 7 with a thickness of 130 mm to 150 mm respectively.

4.4 Fill

Pre-grade fill materials were found in Borehole Nos. 1, 2, 5, 6, 7, 8, 10, 11, 12, 13, 14, and 15, as well as all of the test pits. The pre-grade fill material is found at the surface or directly underlying surficial topsoil, granular fill or RAP material and extends to depths of 0.8 m to 2.3 m (Elevation 86.5 m to 84.6 m). The fill materials varied in soil classification from sand to silty sand to clayey silt to silty clay containing topsoil inclusions, cobbles and boulders measured up to 1 m diameter and often containing construction debris such as concrete, asphalt, brick, and wood pieces. The SPT "N" values range from 7 to 48 blows per 300 mm of penetration of the sampler. The higher N values may be due to the presence of large debris or frozen soil. The moisture content of the fill ranges from 6 percent to 39 percent and its unit weight was measured as 18.5 kN/m³ and 19.8 kN/m³.

Grain size analysis was conducted on one (1) sample of the fill and the test results are summarized in Table II. The grain size distribution curve is shown in Figure 34.



CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

Table II: Summary of Grain-size Analysis Results – Fill Sample									
Borehole No. –	Depth (m)		Grain-size	Analysis (%)	Soil Classification (USCS)				
Sample No.		Gravel	Sand	Fines (Silt and Clay)					
BH13 - SS2	0.8 - 1.4	21	40	39	Silty Sand with gravel (SM)				

4.5 Clay

A clay was contacted beneath the topsoil and fill materials in all of the boreholes and test pits. The clay consists of two (2) parts, an upper brown desiccated crust underlain by a grey non-desiccated zone.

4.5.1 Upper Brown Desiccated Clay to Clay Crust

The upper brown desiccated clay crust extends to approximate depths of 2.1 m to 3.4 m (Elevation 84.8 m to Elevation 83.3 m) below existing grade. The undrained shear strength of the crust ranges from 53 kPa to 120 kPa based on vane shear test results, and up to 215 kPa based on penetrometer readings, indicating the crust has a stiff to hard consistency. The sensitivity values of the brown crust are 6.7 to 12.0 indicating the crust has low to medium sensitivity. The natural moisture content of the crust ranges from 27 percent to 45 percent. The natural unit weight of the crust is 17.3 kN/m³ to 21.2 kN/m³.

Grain size analysis and Atterberg limit determination were conducted on three (3) samples of the crust and the test results are summarized in Table III. The grain size distribution curves are shown in Figure 35 to Figure 37. Atterberg Limit Test results are shown on Figures 38 to 40.

Table	Table III: Summary of Grain-size Analysis and Atterberg Limits Test Results – Brown Clay Crust Samples										
Borehole	Depth (m)	Grain-size Analysis (%)			Atterberg Limits (%)						
No. – Sample No.		Gravel	Sand	Fines (Silt and Clay)	Natural Moisture Content	Liquid Limit	Plastic Limit	Plasticity Index	Soil Classification (USCS)		
BH 1 – SS4	2.3 – 2.9	0	4	96	32	61	19	42	Clay of High Plasticity (CH)		
BH 8 - SS3	2.3 – 2.9	0	0	100	41	70	29	41	Clay of High Plasticity (CH)		
BH14 – SS3	1.5 – 2.1	0	2	98	34	67	27	40	Clay of High Plasticity (CH)		

Based on a review of the results of the grain-size analysis and Atterberg limits, the tested soil samples may be classified as clay of high plasticity (CH) in accordance with the USCS.

4.5.2 Lower Grey Clay

The upper brown desiccated clay crust is underlain by grey clay contacted at approximate depths of 2.1 m to 3.4 m (Elevation 84.8 m to Elevation 83.3 m) below existing grade in all of the boreholes. The grey clay extends to inferred and observed depths of approximately 31.5 m and 33.0 m (Elevation 55.3 m to Elevation 54.1 m) in Borehole Nos. 3 and 1, respectively. The depth of 31.5 m (Elevation 55.3 m) was inferred from the DCPT conducted in Borehole No. 3. The remaining boreholes were terminated within the grey clay at 4.9 m to 8.5 m depths (Elevation 82.3 m to Elevation 78.4 m). The undrained shear strength of the grey clay typically ranges from 10 kPa to 34 kPa indicating a very soft to firm consistency. The sensitivity values of the clay range from 2.0 to 20.0, and in some cases the clay had no remolded strength, indicating the clay is of a sensitive to ultra-sensitive nature.



CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

The natural moisture content of the grey clay ranges from 39 percent to 95 percent. The natural unit weight of the grey clay was measured at 17.2 kN/m^3 .

Grain size analysis and Atterberg limit determination were conducted on three (3) samples of the grey clay and the test results are summarized in Table IV. The grain size distribution curves and Atterberg Limit Tests are shown in Figures 41 to 43 and Figures 44 to 46 respectively.

Т	Table IV: Summary of Grain-size Analysis and Atterberg Limits Test Results – Grey Clay Samples										
Borehole No. – Sample No.	Depth (m)	Grain-size Analysis (%)			Atterberg Limits (%)						
		Gravel	Sand	Fines (Silt and Clay)	Natural Moisture Content	Liquid Limit	Plastic Limit	Plasticity Index	Soil Classification (USCS)		
BH2 – SS8	7.6 – 8.2	0	0	100	45	66	26	40	Clay of High Plasticity (CH)		
BH5 – SS7	6.1 – 6.7	0	0	100	70	66	22	44	Clay of High Plasticity (CH)		
BH8 – SS4	3.8 – 4.4	0	0	100	59	70	27	43	Clay of High Plasticity (CH)		

Based on a review of the results of the grain-size analysis and Atterberg limits, the tested soil samples may be classified as a clay of high plasticity (CH) in accordance with the USCS.

One dimensional consolidation tests were performed on two (2) samples of the grey clay. The test results are summarized in Table V and presented in Figures 47 and 48.

Table V: One-Dimensional Oedometer Test Results - Grey Clay Samples									
Borehole No Sample No.	Sample Depth (m)	ර'∞ (kPa)	w _c (%)	γ (kN/m³)	σ' _P (kPa)	e _o	Cr	Cc	OCR
5/ST5	3.0 – 3.6	59.0	53.03	16.76	115.0	1.462	0.046	0.551	1.95
3/ST7	6.0 – 6.6	73.8	65.66	15.9	65.0	1.812	0.033	0.457	0.88*

σ'v0 = calculated effective overburden pressure (kPa); Wc: natural moisture content (%), γ* estimated natural unit weight σ'; p = pre-consolidation pressure (kPa); eo = initial void ratio; Cr = re-compression index; Cc = compression index; OCR= Over-Consolidation Ratio; * sample likely disturbed

Based on a review of the consolidation test results, the over-consolidation ratio is greater than 1 for the sample from Borehole 5 from 3.0 to 3.6 m depth, indicating the grey clay in the upper levels is over-consolidated. The results of soil sample from Borehole 3 indicate that the sample was somewhat disturbed. The clay is expected to be normally consolidated.

4.6 Glacial Till

The clay is underlain by glacial till contacted in Borehole No. 1 and inferred in Borehole No. 3 at 33.0 m and 31.5 m depths respectively (Elevation 54.1 m to Elevation 55.3 m). The glacial till contains cobbles and boulders. Based on dynamic cone penetration test (DCPT) N-values of 43 to 95, the glacial till is in a dense to very dense state. The higher N-values may be a result of the soil sampler making contact with a cobble or boulder within the glacial till.



March 7, 2023

4.7 Cone Refusal

Dynamic cone penetration test (DCPT) conducted in Borehole No. 3 encountered cone refusal at a 36.3 m depth (Elevation 50.5 m). Cone refusal may have been met on possible cobbles or boulders within the glacial till or on possible bedrock.

4.8 Limestone Bedrock

Bedrock was cored in Borehole 1. Grey limestone bedrock was contacted at 33.8 m depth (Elevation 53.3 m) and cored to a termination depth of 37.7 m (Elevation 49.4 m). The Total Core Recovery (TCR) varied from 0 to 98% for the runs. Rock Quality Designation (RQD) varied from 0 to 87%. On this basis, the bedrock quality may be described as very poor in the upper levels to good quality below 34.5 m depth.

The bedrock geology map (Map 1508A – Generalized Bedrock Geology, Ottawa-Hull, Ontario and Quebec, Geological Survey of Canada, printed by the Surveys and Mapping Branch, 1979) indicates the site is underlain by Limestone bedrock of the Ottawa formation containing some shaly partings and some sandstone in the basal part.

4.9 Groundwater Level Measurements

A summary of the groundwater level measurements taken in the boreholes equipped with standpipes is shown in Table VI.

Table VI: Summary of Groundwater Level Measurements									
Borehole No.	Ground Surface Elevation (m)	(
		January 6, 2023	January 10, 2023						
BH-05	86.96	0.68 (86.28) [22]	0.61 (86.35) [26]						
BH-08	87.39	0.57 (86.82) [15]	0.83 (86.56) [19]						
BH-10	87.69	1.45 (86.24) [15]	1.45 (86.24) [19]						
BH-11	86.95	0.75 (86.20) [15]	0.93 (86.02) [19]						
BH-12	87.22	0.59 (86.63) [16]	0.67 (86.55) [20]						
BH-14	86.67	0.41 (86.26) [16]	0.47 (86.20) [20]						

The groundwater level in the boreholes equipped with standpipes was measured at 0.4 m to 1.5 m depths (Elevation 86.82 m to Elevation 86.02 m). This water table is likely perched in the fill. Based on a review of the moisture content of the soil samples, the groundwater table is expected to be at a depth of 3 m to 4 m below the existing ground surface, i.e., Elevation 83.0 m to Elevation 86.9 m approximately.

Note that fluctuations in the level of groundwater may occur due to a seasonal variation such as precipitation, snowmelt, rainfall activities, and other factors not evident at the time of measurement and therefore may be at a higher level during wet weather periods.



March 7, 2023

5. Site Classification for Seismic Site Response and Liquefaction Potential of Soils

5.1 Site Classification for Seismic Site Response

Based on the results from the Multi-channel Analysis of Surface Waves (MASW) survey (shear wave velocity) shown in Appendix A and comparison of the survey results with Table 4.1.8.4.A of the 2012 Ontario Building Code (as amended May 2, 2019), the site classification for seismic response is **Class E**.

5.2 Liquefaction Potential of Soils

The subsurface soils are not susceptible to liquefaction during a seismic event.



March 7, 2023

6. Grade Raise Restrictions

The site is underlain by a clay deposit that is prone to consolidation settlement if overstressed by loads imposed on it by site grade raise, foundations and by permanent lowering of the groundwater level following construction. Overstressing of the clay will result in its consolidation and subsequent settlement of foundations, which may exceed tolerable limits of the structure resulting in cracking of the structure.

It is noted that approximately 0.8 m to 2.1 m of fill has already been placed on the site. The time of placement of the fill on the site is not known. It appears that the fill has partly consolidated the clay in the upper levels. However, the degree of consolidation of the clay could not be established as the time of placement of fill and stages of its placement on the site are not known. It is therefore considered that the clay is not capable of supporting any additional grade raise loads from the current grades. It is recommended that the grade at the site should not be raised above the existing grade. The average existing ground surface elevation in the building area was computed based on the elevation of the boreholes as Elevation 87.1 m. It is understood that this elevation approximately coincides with the road level and that the proposed grade will be approximately 0.3 m lower than the road level. Therefore, it has been assumed that the finished grade at the site will be at Elevation 86.8 m, approximately.

An allowance for permanent groundwater lowering is not required, since the foundations will be at or above the groundwater level and measures will be employed by the installation of clay seals in new municipal service trenches to minimize the permanent lowering of the groundwater level at the site, as discussed in Section 11 of this report.

Once the exterior grades and Finished floor of the proposed school building are set, this office must be contacted to update the recommendation of this reports as deemed required.



March 7, 2023

7. Site Grading

Site grading within the footprint of the proposed building, paved areas, future portables and outdoor sports fields should consist of the excavation and removal of all existing surficial topsoil and organic stained soils, fill and buried original topsoil layer from the site down to the native undisturbed clay.

The exposed subgrade should be reviewed by a geotechnician prior to placement of engineered fill to raise the site grades. Granular B Type II in accordance with Ontario Provincial Standard Specification (OPSS) 1010 should be used as engineered fill to raise the site grades to the underside of the floor slab inside the proposed building. The engineered fill should be placed in 300 mm thick lifts and compacted to 98 percent of the standard Proctor maximum dry density (SPMDD) in the interior of the building. Exterior to the building against foundation walls and in footing trenches, OPSS 1010 Granular B Type II should be placed and compacted to 95 percent of the SPMDD.

For the proposed outdoor sports fields, parking lot and access roads, the site grades may be raised to the design subgrade level by the placement of soil fill meeting the requirements of OPSS 1010 select subgrade material (SSM) placed in 300 mm thick lifts and compacted to 95 percent of the SPMDD. In any wet soft areas, crusher-run granular material may be required in the lower levels of the fill to stabilize the subgrade.

In place density tests should be performed on each lift of placed material to ensure that it has been compacted to the project specifications.



CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

8. Foundation Considerations

8.1 Spread and Strip Footings

Finished floor elevation and exterior grades of the proposed school building and facilities were not available at the time of preparation of this report. Therefore, once this information become available, they should be forwarded to EXP so the recommendations below are reviewed and validated.

The feasibility of using spread and strip footings for the proposed school building was investigated. It is considered that it may be feasible to support the proposed building on spread and strip footings provided all conditions listed below can be satisfied.

- 1. The finished grade at the site should be set at Elevation 86.8 m, i.e., no grade raise above existing grades.
- 2. All existing fill and buried topsoil will need to be removed from the envelope of the building as noted in Section 7.0 of the report.
- 3. All the exterior spread and strip footings should be set either on the engineered fill or on the desiccated clay at a depth of 1.5 m below the finished grade in order to provide the requisite frost cover, i.e., at Elevation 85.3 m. Interior footings may be set at higher level. If any footings need to be set at lower elevations than noted above, this office must be consulted for additional recommendation
- 4. The maximum width of the strip footings should be limited to 1 m and that of the spread footings to 3.0 m by 3.0 m.
- 5. The footings should be designed using a maximum Ultimate Serviceability Limit State bearing pressure of 60 kPa and factored geotechnical resistance at Ultimate State of 75 kPa. Settlement of the footings are expected to be 25 mm total and 19 mm differential. The anticipated settlements may be reduced by placing the footings at a higher level, i.e., at 0.5 to 0.75 m below the finished grade and providing a combination of earth cover and extruded polystyrene insulation as frost protection. This would result in reducing the stress on the soft clay underlying the desiccated clay crust and the resultant settlements.
- 6. 50 mm mud slab is recommended to be placed on the surface of the clay immediately upon review and approval.

If the above conditions cannot be satisfied, the proposed structure would have to be founded on end bearing piles as described below.

8.2 Pile Foundation

The proposed school addition may be supported by steel H or concrete filled pipe piles designed in end-bearing and driven to practical refusal into the underlying bedrock. The bedrock is anticipated to be present at or below a depth of 32 m to 34 m below the existing ground surface, i.e., Elevation 53.1 m to Elevation 55.1 m approximately. Additional boreholes are recommended to collect data on the depth/elevation of the bedrock throughout the site if the piling option is selected.

Since the piles are expected to meet refusal in the bedrock, the factored geotechnical resistance at ultimate limit state (ULS) will govern the design. The factored geotechnical resistance values at ULS for various pile sections are shown in Table VII. The factored geotechnical resistance values at ULS are based on steel piles with a yield strength of 350 MPa and concrete compressive strength of 35 MPa and a geotechnical resistance factor of 0.4.

It is noted that the piles will be subjected to down-drag forces (negative skin friction) due to consolidation of the marine clay as a result of the grade raise at the site. The negative skin friction that the piles would be subjected to is also listed in Table VII. The allowable load on a pile may be computed by subtracting the negative skin friction from the factored geotechnical resistance at ULS.



CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

	Table VII: Factored Geotechnical Resistance at Ultimate Limit State (ULS) and Estimated Negative Skin Friction of Steel Pipe and H-Piles								
Pile Section	Description	Factored Geotechnical Resistance at ULS (kN)	Estimated Negative Skin Friction (kN)	Estimated Load Carrying Capacity of Pile (kN)					
Steel Pipe	245 mm O.D. by 10 mm wall thickness	1275	610	665					
	245 mm O.D. by 12 mm wall thickness	1445	610	835					
	324 mm O.D. by 12 mm wall thickness	2120	805	1315					
Steel H	HP 310 x 79	1260	960	300					
	HP 310 x 110	1775	980	795					
	HP 310 x 125	2000	990	1010					

Total and differential settlement of the piles are expected to be less than 10 mm.

To achieve the capacity given previously, the pile-driving hammer must seat the pile in the overburden without overstressing the pile material. For guidance purposes, it is estimated that a hammer with rated energy of 54 kJ to 70 kJ (40,000 to 52,000 ft. lbs.) per blow would be required to drive the piles to practical refusal. Practical refusal is considered to have been achieved at a set of 5 blows for 6 mm or less of pile penetration. However, the driving criteria for a particular hammer-pile system must be established at the beginning of the project using the Pile Driving Analyzer.

The site is underlain by glacial till with cobbles and boulders in the lower levels. It is therefore recommended that the piles should be equipped with driving shoes to protect them from damage during driving as per Ontario Provincial Standard Drawing (OPSD) 3001.100, Type II, Revision No. 2 dated November 2017 shown in Figure 13.

A number of test piles should be monitored with the Pile Driving Analyzer during the initial driving and re-striking at the beginning of the project. This monitoring will allow for the evaluation of transferred energy into the pile from the hammer, determination of driving criteria and an evaluation of the ultimate bearing capacity of the piles. Depending on the results of the pile driving analysis, the pile capacity may have to be proven by at least one pile load test for each pile type before production piling begins. If necessary, the pile load test should be performed in accordance with the American Society for Testing and Materials (ASTM) D 1143.

Closed end pipe piles tend to displace a relatively large volume of soil. When driven in a cluster or group, they may tend to jack up the adjacent piles in the group. Consequently, the elevation and the location of the top of each pile in a group should be monitored immediately after driving and after all the piles in the group have been driven. This is to ensure that the piles are not heaving or being displaced. Any piles found to heave more than 3 mm should be re-tapped.

Piles driven at the site may be subject to relaxation (loss of set with time). It is therefore recommended that all the piles should be re-tapped at least 24 hours after initially driving and at 24-hour intervals thereafter until it can be proven that relaxation is no longer a problem.

The installation of the piles at the site should be monitored on a full-time basis by a geotechnician working under the direction and supervision of a qualified geotechnical engineer to verify that the piles are driven in accordance with the project specifications.

The concrete grade beams and pile caps for heated structures should be protected from frost action by providing the beams and caps with 1.5 m of earth cover. For non-heated structures, the pile caps and beams should be provided with 2.4 m of earth cover in areas where the snow will be removed and 2.1 m of earth cover where the snow will not be removed. Alternatively, frost protection may be provided by rigid insulation or a combination of rigid insulation and earth cover.

It is recommended that a 50 mm thick concrete mud slab should be installed under the grade beams and pile caps immediately upon excavation and approval of the subgrade to protect the surface of the clay from disturbance from water, freeze and thaw effects, and foot traffic from construction workers.



March 7, 2023

Temporary granular roads and mats (at least 900 mm thick) will be required to provide access to the pile driving rig. The actual thickness required for the granular roads and mats will have to be established by the piling contractor, based on the type of piling rig that will be used on site and subsurface condition.

The recommended factored geotechnical resistances at ULS have been calculated by EXP from the borehole information for the design stage only. The investigation and comments are necessarily on-going as new information of underground conditions becomes available. For example, more specific information is available with respect to conditions between boreholes, when foundation construction is underway. The interpretation between boreholes and the recommendations of this report must therefore be checked through field monitoring provided by an experienced geotechnical engineer to validate the information for use during the construction stage.

8.3 General Comments

A minimum of 1.5 m of earth cover should be provided to the footings to protect them from damage due to frost penetration. The frost cover should be increased to 2.1 m for unheated structures if snow will not be removed from their vicinity. If snow will be removed from the vicinity of the unheated structures, the frost cover should be increased to 2.4 m. Rigid insulation thermally equivalent to the required soil cover may be used instead of the soil cover. Alternatively, a combination of rigid insulation and soil cover may be used to achieve the required frost protection for the footings.

The recommended factored geotechnical resistance at ULS and bearing pressure at SLS have been calculated by EXP from the borehole information for the design stage only. The investigation and comments are necessarily on-going as new information of underground conditions becomes available. For example, more specific information is available with respect to conditions between boreholes when foundation construction is underway. The interpretation between boreholes and the recommendations of this report must therefore be checked through field monitoring provided by an experienced geotechnical engineer to validate the information for use during the construction stage.



March 7, 2023

9. Floor Slab and Drainage Requirements

The lowest level floor slab of the proposed school building will be the ground floor and may be constructed as slab-on-grade provided it is set on a bed of well compacted 19 mm clear stone of at least 200 mm thick placed on the engineered fill pad as described in Section 7. The clear stone would minimize the capillary rise of moisture from the sub-soil to the floor slab. Adequate saw cuts should be provided in the floor slab to control cracking. Alternatively, the floor slab may be cast on a 200 mm thick bed of OPSS 1010 Granular A overlain by a vapour barrier.

As indicated above, all fill must be removed from the envelope of the proposed school building and replaced with well compacted engineered fill as per Section 7 of the report.

It is recommended that perimeter drains should be provided for the proposed school building. Underfloor drains are not required.

The finished floor slab should be set at least 150 mm higher than the finished exterior grade.

The finished exterior grade should be sloped away from the building to prevent ponding of surface water close to the exterior walls of the proposed building.

Modulus of subgrade reaction of 16 kN/mm may be used for designing the floor slab.



CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

10. Excavation and De-Watering Requirements

10.1 Excess Soil Management

Ontario Regulation 406/19 made under the Environmental Protection Act (November 28, 2019) is scheduled to be implemented on January 1, 2021. The new regulation will dictate the testing protocol that will be required for the management and disposal of excess soils. As set forth in the regulation, specific analytical testing protocols will need to be implemented and followed based on the volume of soil to be managed. The testing protocols are specific as to whether the soils are stockpiled or *in situ*. In either scenario, the testing protocols are far more onerous than have been historically carried out as part of standard industry practices. These decisions should be factored in and accounted for prior to the initiation of the project-defined scope of work. Disposal of any excess soils must be completed as per the recommendation stated in the Phase I/II Environmental site assessment reports completed by exp for this site.

10.2 Excavations

Excavations for the construction of the foundations and underground services of the proposed facility are expected to extend to a depth of 2.0 m to 3.0 m below the existing ground surface. These excavations will be undertaken through the topsoil and into the brown and grey clay and are expected to extend below the perched water table but will be above the groundwater table.

Excavations maybe undertaken by conventional heavy equipment. The native clay is susceptible to disturbance due to movement of construction equipment and personnel on its surface. It is therefore recommended that the excavation at the site should be undertaken by equipment that does not travel on the excavated surface, such as a Gradall or mechanical shovel. It is anticipated that temporary gravel roads may be required to gain access to the site by heavy construction equipment during construction.

The excavation within the subsurface soils should comply with the most recent Occupational Health and Safety Act (OHSA), Ontario Regulations 213/91 (August 1, 1991). Based on the definitions contained in OHSA, the subsurface soils at the site are classified as Type 3 soil and excavation sidewalls must be cut back at 1H:1V from the bottom of the excavation. Below the groundwater table, the excavation side slopes are expected to slough and will eventually stabilize at a slope of 2H:1V to 3H:1V. If space restrictions prevent open cut excavations, underground services may be installed within the confines of a prefabricated support system which is designed and installed in accordance with the above-noted regulations.

Base heave type failure is not anticipated in excavations that extend to a 3.0 m depth below existing grade. If excavations will extend below 3 m depth below existing grade, EXP should be contacted to determine if the deeper excavation will be susceptible to base heave type failure.

Many geologic materials deteriorate rapidly upon exposure to meteorological elements. Unless otherwise specifically indicated in this report, walls and floors of excavations must be protected from moisture, desiccation, and frost action throughout the course of construction.

10.3 De-Watering Requirements

Seepage of the surface and subsurface water into the excavations is anticipated. However, it should be possible to collect any water entering the excavations in perimeter ditches and to remove it by pumping from sumps. In areas of high infiltration or in areas where more permeable soil layers (such as sand seams and layers) may exist, a higher seepage rate should be anticipated. Therefore, the need of high-capacity pumps to keep the excavation dry should not be ignored.

The dewatering of excavations on site during short-term construction operations is not expected to adversely impact adjacent existing structures and infrastructure. Further, since the lowest slab and the footings for the proposed school building are anticipated to be at or above the groundwater level, the permanent perimeter drainage system recommended for the proposed building is also not expected to adversely impact adjacent existing structures and infrastructure.

It is anticipated that groundwater will need to be removed from the excavations. It is noteworthy to mention that new legislation came into force in Ontario on March 29, 2016, to regulate groundwater takings for construction dewatering purposes. Prior to



Project 2022AVN115. Project Number: 011-22017859-AU March 7, 2023

March 29, 2016, a Category 2 Permit to Take Water (PTTW) was required from the Ontario Ministry of the Environment, Conservation and Parks (MECP) for groundwater takings related to construction dewatering, where taking volumes in excess of 50 m³/day, but less than 400 m³/day, and the taking duration was no more than 30 consecutive days. The new legislation replaces the Category 2 PTTW for construction dewatering with a new process under the Environmental Activity and Sector Registry (EASR). The EASR is an on-line registry, which allows persons engaged in prescribed activities, such as water takings, to register with the MECP instead of applying for a PTTW.

To be eligible for the new EASR process, the construction dewatering taking must be less than 400 m³/day under normal conditions. The water taking can be groundwater, storm water, or a combination of both. It should be noted that the 30-consecutive day limit on the water taking under the old Category 2 PTTW process has been removed in the new EASR process. Also, it should be noted that the EASR process requires two technical studies be prepared by a Qualified Person, prior to any water taking. These studies include a Water Taking Report, which provides assurance that the taking will not cause any unacceptable impacts, and a Discharge Plan, which provides assurance that the discharge will not result in any adverse impacts to the environment. EXP has qualified persons who can prepare these types of reports, if required. A significant advantage of the new EASR process over the former Category 2 PTTW process, is that the groundwater taking may begin immediately after completing the on-line registration of the taking and paying the applicable fee, assuming the accompanying technical studies have been completed. The former PTTW process typically took more than 90 days, which had the potential to impact construction schedules.

Although this investigation has estimated the groundwater levels at the time of the fieldwork, and commented on dewatering and general construction problems, conditions may be present which are difficult to establish from standard boring and excavating techniques and which may affect the type and nature of dewatering procedures used by the contractor in practice. These conditions include local and seasonal fluctuations in the groundwater table, erratic changes in the soil profile, thin layers of soil with large or small permeabilities compared with the soil mass, etc. Only carefully controlled tests using pumped wells and observation wells will yield the quantitative data on groundwater volumes and pressures that are necessary to adequately engineer construction dewatering systems.



March 7, 2023

11. **Pipe Bedding Requirements**

For site servicing, it is anticipated that the subgrade for the proposed underground services will consist of native clay set at a maximum depth of 4 m below the existing grade.

It is recommended that the bedding for the underground services including material specifications, thickness of cover material and compaction requirements conform to municipal requirements and/or Ontario Provincial Standard Specification and Drawings (OPSS and OPSD).

It is recommended that the pipe bedding be 300 mm thick and consist of OPSS Granular A. The bedding material should be placed along the sides and on top of the pipe to provide a minimum cover of 300 mm. The bedding should be compacted to at least 98 percent of the SPMDD. In areas of soft subgrade, a 300 mm thick sub-bedding of OPSS Granular B Type II material completely wrapped with non-woven geotextile should be placed beneath the Granular A bedding.

Since paved surfaces are anticipated to be located over service trenches, it is recommended that the trench backfill material within the frost zone (up to 1.8 m below finished grade), should match the existing material in the roadway to minimize differential frost heaving of the subgrade. The trench backfill should be placed in 300 mm thick lifts and each lift should be compacted to 95 percent SPMDD.

If the backfill for the service trenches will consist of granular fill, clay seals should be installed in the service trenches at select intervals as per City of Ottawa Drawing No. S8. The seals should be 1 m long, extend over the entire trench width and extend from the bottom of the trench to the underside of the pavement structure. The clay should be compacted to 95 percent SPMDD. The purpose of the clay seals is to prevent the permanent lowering of the groundwater level.

The underground services should be installed in short open trench sections that are excavated and backfilled the same day.



March 7, 2023

12. Backfilling Requirements and Suitability of On-Site Soils for Backfilling Purposes

The on-site soils to be excavated are fill, topsoil and clay. These soils are not considered suitable for re-use as material beneath structural elements, paved areas and portable or for backfilling purposes. However, these materials may be re-used for general grading purposes in landscaped areas.

It is anticipated that the majority of the material required for backfilling purposes in the interior and exterior of the building and for trench backfill would have to be imported and should preferably conform to the following specifications. The listed materials should be placed in 300 mm thick lifts and compacted to the specified degree of compaction indicated below.

- Engineered Fill under footings and floor slab OPSS 1010 Granular B Type II compacted to 100 and 98 percent of the SPMDD respectively;
- Backfill material for footing trenches and against foundation walls located inside and outside the building OPSS 1010
 Granular B Type II compacted to 98 percent SPMDD inside the building and 95 percent of the SPMDD outside the building; and,
- Trench backfill and subgrade fill in outdoor sports field areas, parking areas and access roads OPSS 1010 Select Subgrade Material (SSM) compacted to 95 percent of the SPMDD.

It is noted that the on-site clay is wet of its optimum moisture content. Therefore, its use for construction of the clay dykes may necessitate either drying the clay (if construction is undertaken during dry summer months) or a suitable source of compactible clay may have to be procured from off-site.



CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

13. Access Roads and Parking Lots

Pavement structures for the surface parking lot, access roads, playgrounds, walkways and pathways are given on Table VII below for the anticipated engineered fill and clay subgrades. The pavement structures are based upon the assumption that the subgrade will be properly prepared and assumes a functional design life of fifteen (15) to eighteen (18) years. The proposed functional design life represents the number of years to the first rehabilitation, assuming regular maintenance is carried out.

Table VIII: Recommended Pavement Structure Thicknesses									
Pavement Layer	Compaction Requirements	Pathways and Walkways	Play Ground	Pavement Design to be used by Light Duty Vehicles (Cars)	Heavy Duty Vehicles (Cars and Trucks, Bus Drop off)				
Asphaltic Concrete (PG 58-34)	92 to 97 percent MRD*	50 mm HL3F	50 mm HL3	40 mm HL3/SP12.5 Category B 40 mm HL8/SP19.0 Cat B	50 mm HL3/SP12.5 Caty B 60 mm HL8/SP19.0 Cat B				
OPSS 1010 Granular A Base	100 percent SPMDD**	150	150	150 mm	150 mm				
OPSS 1010 Granular B Sub-Base, Type II	100 percent SPMDD**	300	300	450 mm	600 mm				

^{*}Denotes maximum relative density.

Additional comments on the construction of the access roads and parking lots are as follows:

- As part of the subgrade preparation, the proposed parking areas and access roads should be stripped of topsoil, fill, buried original topsoil and other obviously unsuitable material. The subgrade should be properly shaped, crowned, then proofrolled with a heavy vibratory roller in the full-time presence of a representative of this office. Any soft or spongy subgrade areas detected should be sub excavated and properly replaced with suitable approved backfill compacted to 95 percent SPMDD (ASTM D698-12e2).
- 2. The long-term performance of the pavement structure is highly dependent upon the subgrade support conditions. Stringent construction control procedures should be maintained to ensure that uniform subgrade moisture and density conditions are achieved. The need for adequate drainage cannot be over-emphasized. Subdrains should be installed on both sides of the access road(s). Subdrains must be installed in the proposed parking area at low points and should be continuous between catchbasins to intercept excess surface and subsurface moisture and to prevent subgrade softening. This will ensure no water collects in the granular course, which could result in pavement failure during the spring thaw. The location and extent of subdrains required within the paved areas should be reviewed by this office in conjunction with the proposed site grading.
- 3. To minimize the problems of differential movement between the pavement and catchbasins/manhole due to frost action, the backfill around the structures should consist of free-draining granular material preferably conforming to OPSS Granular B Type II material. Weep holes should be provided in the catchbasins/manholes to facilitate drainage of any water that may accumulate in the granular fill.
- 4. The most severe loading conditions on light-duty pavement areas and the subgrade may occur during construction. Consequently, special provisions such as restricted lanes, half-loads during paving and/or temporary construction roadways may be required, especially if construction is carried out during unfavorable weather.



^{**} Denotes standard Proctor maximum dry density, ASTM-D698-12e2.

March 7, 2023

- 5. The finished pavement surface should be free of depressions and should be sloped (preferably at a minimum cross fall of two (2) percent) to provide effective surface drainage towards catch basins. Surface water should not be allowed to pond adjacent to the outside edges of paved areas.
- 6. Relatively weaker subgrade may develop over service trenches at subgrade level. These areas may require the use of thicker/coarser sub-base material and the use of a geotextile at the subgrade level. If this is the case, it is recommended that additional 150 mm thick granular sub-base, OPSS Granular B Type II, should be provided in these areas, in addition to the use of a geotextile at the subgrade level.
- 7. The granular materials used for pavement construction should conform to Ontario Provincial Standard Specifications (OPSS 1010) for Granular A and Granular B Type II and should be compacted to 100 percent of the SPMDD.

The asphaltic concrete used, and its placement should meet OPSS 1150 or 1151 requirements. It should be compacted from 92 percent to 97 percent of the MRD (ASTM D2041). Asphalt placement should be in accordance with OPSS 310 and OPSS 313.

It is recommended that EXP be retained to review the final pavement structure design and drainage plans prior to construction to ensure they are consistent with the recommendations of this report.



March 7, 2023

14. Chemical Test Results and Corrosion Potential of Subsurface Soils

Chemical tests limited to pH, sulphate, chloride and resistivity were undertaken on three (3) soil samples. A summary of the results is shown in Table VIII. The laboratory certificate of analysis is shown in Appendix A

Table IX: Chemical Analyses Test Results and Corrosion Potential of Soil										
Borehole – Sample No.	Depth (m)	Soil Type	рН	Sulphate (%)	Chloride (%)	Resistivity (ohm-cm)				
BH1 - SS5	3.0 - 3.6	Grey Clay	9.24	0.0108	0.0456	1040				
BH6 - SS3	1.5-2.1	Brown Clay Crust	8.19	0.0089	0.0022	5050				
BH7 – SS8	7.6 - 7.9	Grey Clay	9.43	0.0084	0.15	256				

The results indicate the soils have a negligible potential of sulphate attack on subsurface concrete. The concrete should be designed in accordance with CSA A.23.1-14.

The results of the resistivity tests indicate that the brown clay crust is mildly corrosive and the grey clay samples are corrosive to very corrosive to bare steel as per the National Association of Corrosion Engineers (NACE). Appropriate measures should be taken to protect any buried bare steel from corrosion.



March 7, 2023

15. Tree Planting Restrictions

The modified plasticity index of the upper brown desiccated clay crust is estimated at 36 percent and for the grey clay the modified plasticity index is estimated to range from 13 percent to 21 percent.

The City of Ottawa document titled, "Tree Planting in Sensitive Marine Clay Soils – 2017 Guidelines" indicates that for a modified plasticity index of less than 40 percent, the soil has a low/medium potential for soil volume change and the tree planting restrictions and setbacks from structures should follow the 2017 guidelines.

A landscape architect should be consulted to ensure the applicable tree planting restrictions and setbacks for the proposed school development are in accordance with the 2017 guidelines.



March 7, 2023

16. Additional Comments

All earthwork activities from placement and compaction of fill in the service trenches to subgrade preparation, engineered fill pad construction, placement and compaction of granular materials and asphaltic concrete should be inspected by qualified geotechnicians to ensure that construction of the sewers and pavement proceeds according to the specifications. All the footing beds should also be examined by a geotechnical engineer to ensure that the design bearing pressure is available at the founding level and that the footing beds have been properly cleaned.

If piles are considered, it is recommended to drill additional holes to confirm the depth/elevation of bedrock throughout the site in order to reduce potential claims by the piling contractors.



CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

17. General Comments

The comments given in this report are intended only for the guidance of design engineers. The number of boreholes required to determine the localized underground conditions between boreholes affecting construction costs, techniques, sequencing, equipment, scheduling, etc., would be much greater than has been carried out for the design purposes. Contractors bidding on or undertaking the works should, in this light, decide on their own investigations, as well as their own interpretations of the factual borehole results, so that they may draw their own conclusions as to how the subsurface conditions may affect them.

The information contained in this report is not intended to reflect on environmental aspects of the soils. Should specific information be required, including for example, the presence of pollutants, contaminants or other hazards in the soil, additional testing may be required.

We trust that the information contained in this report will be satisfactory for your purposes. Should you have any questions, please do not hesitate to contact this office

Surinder K. Aggarwal, M.Sc., P.Eng.

POVINCE OF Senior Project Manager, Geotechnical Service

Earth & Environment

Ismail M. Taki, M. Eng., P.Eng.

Senior Manager Earth & Environment

Eastern Region





EXP Services Inc.

Project Name: Geotechnical Investigation – Proposed Avalon III Elementary School 2666 Tenth Line Road, Ottawa, Ontario CECCE Project 2022AVN115. Project Number: OTT-22017859-A0 March 7, 2023

Figures








CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

Notes On Sample Descriptions

1. All sample descriptions included in this report follow the Canadian Foundations Engineering Manual soil classification system. This system follows the standard proposed by the International Society for Soil Mechanics and Foundation Engineering. Laboratory grain size analyses provided by exp Services Inc. also follow the same system. Different classification systems may be used by others; one such system is the Unified Soil Classification. Please note that, with the exception of those samples where a grain size analysis has been made, all samples are classified visually. Visual classification is not sufficiently accurate to provide exact grain sizing or precise differentiation between size classification systems.





UNIFIED SOIL CLASSIFICATION

- 2. Fill: Where fill is designated on the borehole log it is defined as indicated by the sample recovered during the boring process. The reader is cautioned that fills are heterogeneous in nature and variable in density or degree of compaction. The borehole description may therefore not be applicable as a general description of site fill materials. All fills should be expected to contain obstruction such as wood, large concrete pieces or subsurface basements, floors, tanks, etc., none of these may have been encountered in the boreholes. Since boreholes cannot accurately define the contents of the fill, test pits are recommended to provide supplementary information. Despite the use of test pits, the heterogeneous nature of fill will leave some ambiguity as to the exact composition of the fill. Most fills contain pockets, seams, or layers of organically contaminated soil. This organic material can result in the generation of methane gas and/or significant ongoing and future settlements. Fill at this site may have been monitored for the presence of methane gas and, if so, the results are given on the borehole logs. The monitoring process does not indicate the volume of gas that can be potentially generated nor does it pinpoint the source of the gas. These readings are to advise of the presence of gas only, and a detailed study is recommended for sites where any explosive gas/methane is detected. Some fill material may be contaminated by toxic/hazardous waste that renders it unacceptable for deposition in any but designated land fill sites; unless specifically stated the fill on this site has not been tested for contaminants that may be considered toxic or hazardous. This testing and a potential hazard study can be undertaken if requested. In most residential/commercial areas undergoing reconstruction, buried oil tanks are common and are generally not detected in a conventional geotechnical site investigation.
- 3. Till: The term till on the borehole logs indicates that the material originates from a geological process associated with glaciation. Because of this geological process the till must be considered heterogeneous in composition and as such may contain pockets and/or seams of material such as sand, gravel, silt or clay. Till often contains cobbles (60 to 200 mm) or boulders (over 200 mm). Contractors may therefore encounter cobbles and boulders during excavation, even if they are not indicated by the borings. It should be appreciated that normal sampling equipment cannot differentiate the size or type of any obstruction. Because of the horizontal and vertical variability of till, the sample description may be applicable to a very limited zone; caution is therefore essential when dealing with sensitive excavations or dewatering programs in till materials.



Log of Borehole BH-01





Continued Next Page

Borehole data requires interpretation by EXP before use by others

2. The borehole was backfilled upon completion.

3. Field work supervised by an EXP representative.

4. See Notes on Sample Descriptions

5.Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS						
Date	Water Level (m)	Hole Open To (m)				
Upon Completion	3.7	no cave				

CORE DRILLING RECORD						
Run	RQD %					
No.	(m)					
1	33 - 33.8	0	0			
2	33.8 - 34.5	88	0			
3	34.5 - 36.2	97	78			
4	36.2 - 37.7	98	86			

Log of Borehole BH-01

Project No: OTT-22017859-A0 Figure No. 3

Project: Proposed Avalon III School Page. 2 of 3

	S		Double Dolone	D	Standard Pe	netration 7	Test N Value		apour Reading (ppm)	S	Nistra
G W L	SY M BOL	SOIL DESCRIPTION	Depth Below Ground	Depth		40 6	80 80	250 Natural Mo	500 750 isture Content % nits (% Dry Weight)	S A M P	Natural Unit Wt.
L	۱ŏ		m	t h	Shear Strength	00 4	kPa			L E S	kN/m³
\vdash	1//	CLAY	75.14	12	50	00 1	50 200	20	40 60	S	$\overline{}$
		Grey, wet (soft to firm) (continued)								1	
									:::::::::::::::::::::::::::::::::::::	1	
					301311301	18198	1386316386	180981980		1	ı l
		-		13	3813 1381	1000	 	3 2 2 3 1 3 2	140000000		ı l
]	ı l
		-								1	ı l
										:	ı
		_		14]	ı l
		_			331341331	10100	1336346336	36134336	140130 3013]	ı l
					381311381			3013 130		:	ı l
				15]	ı l
							1.3.0.7.3.4.3.3.3.3.3.3.3.3.3.3.3.3.3.3.3.3.3			1	ı l
					-2-4-1-2-1-2-4-1	0.000	1-3-0-1-3-1-3-0-1-		<u> </u>	1	ı l
]	ı l
		- -		16	 		133311331	 	11:11:11:11:11:	:	ı l
					331311331	13433	1356346356	2012 120	142132 3213	:	ı l
		- -			.5 2. 1.5 . 1.5 2. 1	2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2		13.7.3.3.1.3.3.	1	1	ı l
										:	ı l
		-		17	 			 : : : : : : : :		-	ı l
							1888 1888]	ı
		-				13133	10010111100	lenehet		:	ı
				10						:	
		_		18	., ., ., ., ., ., ., .,						ı
		_							1]	ı
										:	ı
				19	-> -> ->	0.1.2.0		10000	1		
					381311381]	
		/					 	 	 	:	ı
								:::::		:	ı
		/- -		20		0.000			1	-	ı
										1	ı
		-						 : : : : : : : :			ı
g]	ı
22/2		-		21	331311331	13133	lasia kiasi		11:11:2:11:2:11:3:	:	
72										:	ı
9		_]	ı
₹		_		22]	ı
≨l										:	ı
TROW OTTAWA.GDT 2/22/23					20101001				112121 2212	1	ı
S S						18198	1386316386	130031030		1	ı
		<u>_</u> _		23		 	 	 :: :: :: :: :: :	11.5.1.5.5.1.5.5.1.5.	:	ı
2023.GPJ											ı
23.0		-				2.7.5.2.			3	-	ı
1,20							1321311321			1	.
B 22,		/- -		24					 	†	.
						1888	100000000000000000000000000000000000000]	.
gg		_	1		331321331	3133				1	.
뷔				2-			10000010000			;	.
南]	25]	.
≣		_			351311351					1	
										;	.
359 - AVALON III - BH LOGS FEB		/_		26	100000000000000000000000000000000000000	10100	1-2-0-1-2-1-1-2-1-1		1		
9-6							4 - 5 - 7 - 7 - 5 - 4 - 7 - 5 - 7 - 7 -		. 5 . 6 . 7 . 5 . 5 . 7 . 8 . 5 . 7 . 5 . 5 .	1	
ب این	V//	7 /				1	1	1 1	- 1		

NOTES:

Borehole data requires interpretation by EXP before use by others

Continued Next Page


- 2. The borehole was backfilled upon completion.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

Date Water Level (m) Hole Open To (m) Upon Completion 3.7 no cave	WATER LEVEL RECORDS					
Upon Completion 3.7 no cave	Date					
	Upon Completion		no cave			

CORE DRILLING RECORD					
Run	Depth	% Rec.	RQD %		
No.	(m)				
1	33 - 33.8	0	0		
2	33.8 - 34.5	88	0		
3	34.5 - 36.2	97	78		
4	36.2 - 37.7	98	86		

Project No: OTT-22017859-A0 Figure No.


Project: Proposed Avalon III School 3 of 3Page.




- Borehole data requires interpretation by EXP before use by others
- 2. The borehole was backfilled upon completion.
- $3. \mbox{{\it Field}}$ work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS										
Date	Water Level (m)	Hole Open To (m)								
Upon Completion	3.7	no cave								

	CORE DRILLING RECORD									
Run	Depth	RQD %								
No.	(m)									
1	33 - 33.8	0	0							
2	33.8 - 34.5	88	0							
3	34.5 - 36.2	97	81							
4	36.2 - 37.7	98	87							





NOTES:

- Borehole data requires interpretation by EXP before use by others
- 2. The borehole was backfilled upon completion.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. Log to be read with EXP Report OTT-22017859-A0

WAT	WATER LEVEL RECORDS										
Date	Water Level (m)	Hole Open To (m)									
Upon Completion	4.6	no cave									

	CORE DRILLING RECORD										
Run	Depth	% Rec.	RQD %								
No.	(m)										

•		OTT-22017859-A0									F	igure	No	5	_		
Projec		Proposed Avalon III School	- ON									Pa	age	of	_3_		-
ocatio		2666 Tenth Line Road, Orlean	ns, ON														
		'Dec. 16, 2022			-	Split Spo Auger Sa		mple	•				istible Va _l I Moisture		-		□ X
rill Ty		CME-45 Track Mounted Drill F	Rig		-	SPT (N)	Value			0		Atterbe	erg Limits			<u> </u>	-
atum		Depth Below Ground			-	Dynamic Shelby T		les	t		I	% Strai	ned Triaxi in at Failu	re			\oplus
ogged	d by:	M.Z. Checked by:	I.T.	_		Shear St Vane Te		ı by		+ s	-		Strength I ometer Te				•
S Y M B O		SOIL DESCRIPTION		Depth Below	w E		20	40	etration T		llue 80 kPa		ustible Va 250 atural Moi rberg Lim	500	750	- M	Natura Unit W
XXX	GRAI	NULAR FILL		86.81	ŕ	J	50	10	0 1	50 2	200		20	40	60	E S	kN/m ³
	Sand	l and gravel, with topsoil inclusi n, moist	ions, _	86.0		3313			200		215 kPa		×				AS1
	Brow	n, wet (soft)		85.6	1	9 O					215 KFa_		×			X	SS2
	Brow	<u>f</u> n, moist (stiff to hard)	_	1		8.			0100		215 kPa		×				SS3
	_		_	1	2	· · · · · · ·	1:1:2	(+ (+) (+ (+) (+ (+)								1	17.8
	_ CLAY	<i>,</i>	_	84.2		2. O 24 kPa	80	kPa					×			$\langle \rangle$	SS4
		, wet (soft to firm)	-		3	1s = 3.3									×	X	SS5
			_			19 kPa										::7 ::rr	1
	_		_	1	4	s=4			2122								1
	_		_	Har	nm	er Weight										85	; ;
	<u> </u>		_	-	5	er Weight O 14 kPa			3133	3333						**	SS6
	_		_	-		s = 3			2112		1000					-[1
	_		_	-	e	3 2 3 3 3 3											
	_		_	<u> </u>		3 3 1 1 3			01.00								ST7
	_		_	-	7	34 kP	a: : ::										1
	_		_			s = 3.	5										
	_		_	Har	mm 	er Weight									×	X	ss8
				78.3		29 kPa										\ 	4
	Cond	mic Cone Penetration Test (DO lucted from 9 m depth to cone	CPT) refusal			s = 4											_
	at 36	.1 m depth	_	1	S												
	_		_	1													
-	_		_	-	1						+ 1 + 2 + 1 + 1 + 2 + 2 + 1						
	_		_	1					2.1.2.2								
	_		_	-	1	1 2 2 2 2			2112		10000						
	_		_	-							1000						
		Continued Next Page				<u>, </u>			2002								
IOTES:	alo dat-	Continued Next Page		WATE	RL	EVEL R	ECO	RDS	;			C	ORE DR	ILLING	RECOR	.D	
use by	ole data requires interpretation by EXP before y others Date					Water _evel (m))	ŀ	Hole Ope To (m)		Run No.		pth n)	% R	ec.	F	RQD %
		as backfilled upon completion. rvised by an EXP representative.	Upon Cor	mpletion		3.0			no cave								
		ample Descriptions															

Project No: OTT-22017859-A0 Figure No. Project: Proposed Avalon III School

_	ojec	Proposed Avaion III School				<u> </u>		_					ge	2_ of			
G W L	SYMBOL	SOIL DESCRIPTION	Depth Belo	w D			ndard I 0	Pene 40	etration T		llue 80	2	250	500 Fead	750	SAMPLES	Natural Unit Wt
Ľ	B O L	SOIL DESCRIPTION	m	w e p	Sh	near S	trengtl	h 10			kPa 200		turai ivioi berg Lim 20	sture Cont its (% Dry '	Weight)	L	kN/m ³
		Dynamic Cone Penetration Test (DCPT	74.81	12	2			ij			1:::::::	300	1	10000	1:::::		
		Conducted from 9 m depth to cone refuse at 36.1 m depth (continued)	sal _										1:3:2:				
				13					0100		11001		1000				
			7								 	 : : : :	 			:	
		_	_	14	1												
					1				21.32								
			7	15	Ì												
		_	-						4-1-2-0-1 2-1-2-1		1.1.1.1.1		1:1:2:2:				
		_	_	16	3												
											1000						
			7	17	7	\ ::::											
		_	-		122	1122	11122				1111111		1111111			31	
				18	3												
		-	-	19	9	+			0-1-2-0-1 2:1:3:2:1		11111111		1:1:0:0:				
		_				1			: : : : : : : : : : : : : : : : : : :								
						1											
				20	'				2022		1000	200	1336				
			-														
		_	_	21	1	-			2:1:2 2:: 2:1:3 2::		1111111		1333				
			7	22	2												
		_	-		133				20 1 1 3 20 1 20 1 1 3 20 1		1 2 2 2 2 2					::: ::::::::::::::::::::::::::::::::::	
				23	3		\										
					1000)							1			
							/		3133	3333	1000		1000		333		
		-	-	24	1												
		_	_		33	:::::::::::::::::::::::::::::::::::::::	1::::		2122	33333	1000		1320			31	
							1										
				25) ::::		7		3133								
		-	-				133		::::::::::::::::::::::::::::::::::::::								
		_	_	26	3		_				#11121		11 2 2			::: <u> </u>	
		Continued Next Page			33	: [::] :)		31331	33333	\$1331	10000	1333	140136		31	
	TES:		WATE	R L	.EVE	L RE	COR	RDS				CC	RE DR	RILLING F	RECOR	D.	
1.	Boreh	ole data requires interpretation by EXP before y others	Date		Wa				ole Ope To (m)		Run No.	Dep (m	oth	% Re			QD %
			on Completion		3.				no cave		140.	(11	'/				
		work supervised by an EXP representative.															
4.		lotes on Sample Descriptions be read with EXP Report OTT-22017859-A0															
2. 3. 4. 5.	Log 10	, 55 rodd with EAR Report OTT-2201/009-A0															


- Borehole data requires interpretation by EXP before use by others
- 2. The borehole was backfilled upon completion.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS										
Date	Water Level (m)	Hole Open To (m)								
Upon Completion	3.0	no cave								

CORE DRILLING RECORD								
Run No.	Depth (m)	% Rec.	RQD %					
	• •							

Project No: OTT-22017859-A0 Figure No.

Project: Proposed Avalon III School of 33 Page.



- Borehole data requires interpretation by EXP before use by others
- 2. The borehole was backfilled upon completion.
- $3. \mbox{{\it Field}}$ work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS										
Date	Water Level (m)	Hole Open To (m)								
Upon Completion	3.0	no cave								

	CORE DRILLING RECORD							
Run No.	Depth (m)	% Rec.	RQD %					
	, ,							

Project No:	OTT-22017859-A0										<u>04</u>	=iaı	ure N	No.		5A			'
Project:	Proposed Avalon III School										_ '	igi		-	1	of	_		٠,
Location:	2666 Tenth Line Road, Orlean	s, ON									_		Pa	ge. ₋		_ 01			
Date Drilled:	'Dec. 15, 2022			_	Split Spo	on San	nple			\boxtimes		Co	mbus	tible Va	apou	ır Readi	ng		
Drill Type:	CME-45 Track Mounted Drill R	ig		_	Auger Sa SPT (N)									Moistur g Limits		ontent	ĺ		X ⊕
Datum:	Depth Below Ground			_	Dynamic	Cone 7	Гest			_		Un	drain	ed Tria: at Fail	xial a	at		ļ!	⊕
Logged by:	M.Z. Checked by:	I.T.			Shelby To Shear St	rength	by			+ s		Sh	ear S	rai raii trength meter T	by				A
					Vane Tes														,
S Y M B C	SOIL DESCRIPTION		Depth Below		2	ndard F 20	ene 40	tration 1	rest N 30		ue 60		2	50	500	0 7	ng (ppm 50) SAMPLES	Natura Unit Wi
ĭ			m 87.24	t h	Shear S				50		kPa 00		Atterb	perg Lin	nits (re Conte (% Dry V	Veight) 60	L E S	kN/m ³
FILL Auger	r through fill to start Nilcon vane	e at 2.1		ľ	0.000														
m dep	oth	_	1		3 2:1:3:				22										
		_	1	1	13 5 1 3					:::: ::::::									
		-	1		1000100														
		-	-	2	8 kPa					;;;;; ;;;;;						201000 201000			Ī
—		_	-		8 kPa				122	: : : : : : : : :									
		_	84.0	3	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1					::::: ::::::::::::::::::::::::::::::::						2.1.0.2.			
CLAY	n vane completed from 2.1 m 18	97m -	04.0		21 kPa-					:::::									
depth	i valle completed from 2.1 m 10	0.7 111		١.	S = 12														Ī
		_	1	4	3 3 4 4 3				0.0										
		_	1		-2-2-1-2					: : : : : : :						****			
		_	-	5	−28 kPa				333	· · · · · · · · · · · · · · · · · · ·							3		Ī
		_	-		-2 (-1-2					; ; ; ; ; ; ; ; ;			<u> </u>			2.1.2.2.			
		_	-	6	12 2: 1:2:				133	: : : : : : : : :									
		_	-		-25 kPa-											· · · · · · · ·			
		_		7	S = 14														
				ľ	3 2 1 3					: -									
					3 3 1 3														
		_	1	8	13313														
		_	1		33313				333	; . ; . ; . ; ;					:;;;	(-) (-) (-) (-) (-) (-)	3 (:1:		
		_	+	9	1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2					::::: ::::::::::::::::::::::::::::::::						******			
		_	-		-28 kPa				12.2	:::::: :::::::::::::::::::::::::::::::			1:1:2 1:1:3:			() () () () () ()			
		_		10	:: : : :														
		_																	
			1	11															
		_	1																
NOTES:	Continued Next Page			_ 12	2	(-1-)-(-)	<u>::E</u>	0-1-3-0	1-2-5	; ; ; ; 	1-1-2-0-1	1 :	(-)-0	1-2-5-3	:::1:	4-1-0-4-	1-2-4-12	<u>: </u>	
NOTES: 1. Borehole data re	equires interpretation by EXP before			RL	EVEL RE	ECOR		ole Op	en		Run		CO		RILL	ING R	ECOR		QD %
use by others 2. The borehole wa	s backfilled upon completion.	Dat	te	L	_evel (m)	_		To (m)		$\left. \right \left. \right $	No.		(m			70 KE	J.		·ダレ /0
	vised by an EXP representative.																		
4. See Notes on Sa																			
n I on to be read w	ith EXP Report OTT-22017859-A0	i	1			- 1									1		- 1		

Project No: OTT-22017859-A0
Project: Proposed Avalon III School

Figure No. 5A

Combustible Vapour Reading (ppm) 250 500 750 Standard Penetration Test N Value Natural Depth Below G W L SOIL DESCRIPTION Natural Moisture Content % Atterberg Limits (% Dry Weight) Unit Wt. Shear Strength 75.24 CLAY Nilcon vane completed from 2.1 m 18.7 m depth (continued) 68.5 Borehole Terminated at 18.7 m Depth

NOTES:

LOG OF 1

OTT-22017859 - AVALON III - BH LOGS FEB 22, 2023.GPJ TROW OTTAWA.GDT 2/22/23


- Borehole data requires interpretation by EXP before use by others
- $\label{eq:completion} \textbf{2.The borehole was backfilled upon completion}.$
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0


WATER LEVEL RECORDS										
Date	Water Level (m)	Hole Open To (m)								

CORE DRILLING RECORD				
Depth (m)	% Rec.	RQD %		
· · · · · · · · · · · · · · · · · · ·				

of 2

Page.







NOTES:

- Borehole data requires interpretation by EXP before use by others
- $2.\mbox{A 19}\ \mbox{mm}$ diameter standpipe was installed as shown.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS				
Date	Hole Open To (m)			
Upon Completion	4.6	no cave		
Jan 6, 2023	0.7			
Jan 10, 2023	0.6			

CORE DRILLING RECORD							
Run	Run Depth % Rec. RQD %						
No.	(m)						







LOG OF

- Borehole data requires interpretation by EXP before use by others
- 2. The borehole was backfilled upon completion.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

WAT	WATER LEVEL RECORDS					
Date	Hole Open To (m)					
Upon Completion	3.0	no cave				

CORE DRILLING RECORD				
Run No.	Depth (m)	% Rec.	RQD %	
	, ,			







LOG OF

- Borehole data requires interpretation by EXP before use by others
- 2. The borehole was backfilled upon completion.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS				
Date	Hole Open To (m)			
Upon Completion	3.0	no cave		

CORE DRILLING RECORD							
Run	Run Depth % Rec. RQD %						
No.	(m)						






- Borehole data requires interpretation by EXP before use by others
- 2.A 50 mm diameter monitoring well was installed as shown.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS				
Date	Hole Open To (m)			
Upon Completion	no water	no cave		
Jan 6, 2023	0.6			
Jan 10, 2023	0.8			

CORE DRILLING RECORD							
Run	Run Depth % Rec. RQD %						
No.	(m)						


	Log of	f Bo	r	ehole Bh	I-10		\bigcirc	xr
Project No:	OTT-22017859-A0					-: 10		
Project:	Proposed Avalon III School					Figure No10_		ı
Location:	2666 Tenth Line Road, Orleans, ON					Page. <u>1</u> of <u>1</u>		
Date Drilled:	'Dec. 22, 2022			Split Spoon Sample		Combustible Vapour Reading		
Drill Type:	CME-75 Track Mounted Drill Rig			Auger Sample SPT (N) Value	Ⅲ ○	Natural Moisture Content Atterberg Limits		× →
Datum:	Depth Below Ground			Dynamic Cone Test ——Shelby Tube	_	Undrained Triaxial at % Strain at Failure		\oplus
Logged by:	M.Z. Checked by: I.T.	_		Shear Strength by Vane Test	+ s	Shear Strength by Penetrometer Test		•
G Y M B O L	SOIL DESCRIPTION	Depth Below Ground m 87.69	D e p t h	Standard Penetration Test N 20	80 kPa	Combustible Vapour Reading (ppm 250 500 750 Natural Moisture Content % Atterberg Limits (% Dry Weight) 20 40 60	SAMPLIE	Natural Unit Wt. kN/m³
FILL	SOIL ~150 mm thick	-87.5	0	00 100		×	Ť	AS1




- Borehole data requires interpretation by EXP before use by others
- 2. A 50 mm diameter monitoring well was installed as shown.
- $3. \mbox{Field}$ work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS				
Date	Hole Open To (m)			
Jan 6, 2023	1.5			
Jan 10, 2023	1.5			

CORE DRILLING RECORD							
Run	Run Depth % Rec. RQD %						
No.	(m)						






- Borehole data requires interpretation by EXP before use by others
- 2.A 50 mm diameter monitoring well was installed as shown.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS								
Date	Water Level (m)	Hole Open To (m)						
Jan 6, 2023	0.8							
Jan 10, 2023	0.9							

CORE DRILLING RECORD									
Run	Depth % Rec. RQD %								
No.	(m)								

	Log of	Borehole BH-12	<u> </u>	ΘXI
Project No:	OTT-22017859-A0	-	- 10	$\mathcal{O}_{\mathcal{N}}$
Project:	Proposed Avalon III School		Figure No12 Page. 1 of 1	ı
Location:	2666 Tenth Line Road, Orleans, ON		·	_
Date Drilled:	'Dec. 21, 2022	Split Spoon Sample	Combustible Vapour Reading	
Drill Type:	CME-55LC Track Mounted Drill Rig	Auger Sample SPT (N) Value	Natural Moisture Content Atterberg Limits	× —⊖
Datum:	Depth Below Ground	Dynamic Cone Test Shelby Tube	Undrained Triaxial at % Strain at Failure	\oplus
Logged by:	M.Z. Checked by: I.T.	Shear Strength by + Vane Test S	Shear Strength by Penetrometer Test	•
S		Standard Penetration Test N Value	Combustible Vapour Reading (pp	m) S Noture




LOG OF 1

- Borehole data requires interpretation by EXP before use by others
- 2.A 19 mm diameter standpipe was installed as shown.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS							
Date	Water Level (m)	Hole Open To (m)					
Jan 6, 2023	0.6						
Jan 10, 2023	0.7						

CORE DRILLING RECORD							
Run No.	Depth	% Rec.	RQD %				
INO.	(111)						

	Log of	Bo	rehole _	BH-13		O Yr
Project No:	OTT-22017859-A0		_		·	
Project:	Proposed Avalon III School				Figure No. 13	
Location:	2666 Tenth Line Road, Orleans, ON				Page. <u>1</u> of <u>1</u>	-
Date Drilled:	'Dec. 21, 2022		Split Spoon Sample		Combustible Vapour Reading	
Drill Type:	CME-55LC Track Mounted Drill Rig		Auger Sample SPT (N) Value		Natural Moisture Content Atterberg Limits	× ≎
Datum:	Depth Below Ground		Dynamic Cone Test Shelby Tube		Undrained Triaxial at % Strain at Failure	⊕
Logged by:	M.Z. Checked by: I.T.		Shear Strength by Vane Test	+ s	Shear Strength by Penetrometer Test	•
SYMBOL	SOIL DESCRIPTION	Depth Below Ground m	Standard Penetrati De	60 80 kPa 150 200	Combustible Vapour Reading (pp 250 500 750 Natural Moisture Content % Atterberg Limits (% Dry Weight 20 40 60	M Natural
XXX EILI			0	: :: I :: :: : : I : : : : : :		::: 1




LOG OF BOREHOLE

- Borehole data requires interpretation by EXP before use by others
- 2. The borehole was backfilled upon completion.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS								
Date	Water Level (m)	Hole Open To (m)						

CORE DRILLING RECORD								
Run	Depth % Rec. RQD %							
No.	(m)							

		Log of	Bo	r	ehole	BH	-14		\leftarrow	اXد
Proje	ect No:	OTT-22017859-A0			_			-: 1.1		//\
Proje	ect:	Proposed Avalon III School						Figure No14_		
Loca	ition:	2666 Tenth Line Road, Orleans, ON						Page1_ of	<u> </u>	
Date	Drilled:	'Dec. 21, 2022			Split Spoon Sample		\boxtimes	Combustible Vapour Reading		
Orill ⁻	Туре:	CME-55LC Track Mounted Drill Rig			Auger Sample SPT (N) Value		Ⅲ ○	Natural Moisture Content Atterberg Limits	⊢	X —⊙
Datu	m:	Depth Below Ground			Dynamic Cone Test Shelby Tube		_	Undrained Triaxial at % Strain at Failure		\oplus
_ogg	ed by:	M.Z. Checked by: I.T.			Shear Strength by Vane Test		+ s	Shear Strength by Penetrometer Test		•
G M B O	,	SOIL DESCRIPTION	Depth Below Ground m	D e p t h	Standard Penetrati 20 40 Shear Strength	tion Test N 60	Value 80 kPa	Combustible Vapour Reading 250 500 750 Natural Moisture Content 9 Atterberg Limits (% Dry Weig	% P	Unit W



LOG OF BOREHOLE

- Borehole data requires interpretation by EXP before use by others
- 2.A 19 mm diameter standpipe was installed as shown.
- $3. \mbox{Field}$ work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS							
Date	Water Level (m)	Hole Open To (m)					
Jan 6, 2023	0.4						
Jan 10, 2023	0.5						

CORE DRILLING RECORD									
Run	Depth % Rec. RQD %								
No.	(m)								

	Log of	f Bo	r	ehole	BH-	-15			***	ے	χr
Project No:	OTT-22017859-A0							15	•	رم	ハト
Project:	Proposed Avalon III School						Figure No.	15_	4		•
Location:	2666 Tenth Line Road, Orleans, ON						Page.	_1_ of _	1_		
Date Drilled:	'Dec. 21, 2022			Split Spoon Sample	×	3	Combustible V	/apour Readin	ng		
Drill Type:	CME-55LC Track Mounted Drill Rig			Auger Sample SPT (N) Value		-	Natural Moistu Atterberg Limit		⊢		X ⊕
Datum:	Depth Below Ground			Dynamic Cone Test		- -	Undrained Tria % Strain at Fa				⊕
Logged by:	M.Z. Checked by: I.T.			Shelby Tube Shear Strength by Vane Test	+	-	Shear Strengtl	h by			A
G Y M B O L	SOIL DESCRIPTION	Depth Below Ground m 86.92	Depth	Standard Penetration 20 40 Shear Strength 50 100	60	80 kPa	250 Natural M	/apour Readin 500 75 loisture Conter mits (% Dry W	nt % reight)	Ρ̈́Ι	Natural Unit Wt. kN/m³
	SOIL ~300 mm thick ey, with wood pieces	86.6	0	21 O			×			X	SS1
Silty	clay with topsoil inclusions, brown and moist,	-	1								

SS2 84.6 **CLAY** SS3 X Brown, moist (stiff) 18.4 s = 7.8 83.5 Grey, wet (soft to firm) Hammer Weight SS4 X 26 kPa : || | | 82.0 Borehole Terminated at 4.9 m Depth OTT-22017859 - AVALON III - BH LOGS FEB 22, 2023. GPJ TROW OTTAWA. GDT 2/22/23


LOG OF BOREHOLE

- Borehole data requires interpretation by EXP before use by others
- 2. The borehole was backfilled upon completion.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5.Log to be read with EXP Report OTT-22017859-A0

WATER LEVEL RECORDS						
Date	Water Level (m)	Hole Open To (m)				

CORE DRILLING RECORD						
Run No.	Depth (m)	% Rec.	RQD %			
	···/					

Project No:	OTT-22017859-A0	<u> </u>		ロス
riojectivo.	O11-22017659-A0		Figure No. 16	
Project:	Proposed Avalon III School			_
Location:	2666 Tenth Line Road, Ottawa, ON		Page. <u>1</u> of <u>1</u>	_
Date Drilled:	'Dec 9, 2022	Split Spoon Sample	Combustible Vapour Reading	
Orill Type:	Case 580 Rubber Tire Backhoe	Auger Sample SPT (N) Value	Natural Moisture Content Atterberg Limits	
Datum:	Geodetic Elevation	Dynamic Cone Test Shelby Tube	Undrained Triaxial at % Strain at Failure	\oplus
_ogged by:	MZ Checked by: SMP	Shear Strength by	Shear Strength by Penetrometer Test	•




₽

- 2. Test pit backfilled upon completion of excavating
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS						
Elapsed	Water	Hole Open				
Time	Level (m)	To (m)				

CORE DRILLING RECORD						
Run No.	Depth (m)	% Rec.	RQD %			

	Log	of Te	est Pit <u>TP-0</u>)2		<u>'</u>	Y
Project No:	OTT-22017859-A0				Figure No. 17		/ \
Project:	Proposed Avalon III School					-	
Location:	2666 Tenth Line Road, Ottawa, ON				Page1_ of _1_		
Date Drilled:	'Dec 9, 2022		Split Spoon Sample	3	Combustible Vapour Reading		
Drill Type:	Case 580 Rubber Tire Backhoe		Auger Sample	0	Natural Moisture Content	-	X
Datum:	Geodetic Elevation		SPT (N) Value Dynamic Cone Test Shelby Tube) - ■	Atterberg Limits Undrained Triaxial at % Strain at Failure		⊕
Logged by:	MZ Checked by: SMP		Shear Strength by Vane Test	- - 5	Shear Strength by Penetrometer Test		A
G M M B O L	SOIL DESCRIPTION	Geodetic Elevation m 87.03		80 kPa	Combustible Vapour Reading (ppr 250 500 750 Natural Moisture Content % Atterberg Limits (% Dry Weight) 20 40 60	- AM	Natuı Unit V kN/n
M. TOPS	SOIL ~100 mm thick	96.0	0		 		




- Test pit backfilled upon completion of excavating operation.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS						
Elapsed	Water	Hole Open				
Time	Level (m)	To (m)				

CORE DRILLING RECORD						
Run No.	Depth (m)	% Rec.	RQD %			
	···/					

		Log	of Te	9:	st Pit	: 1	⁻ P-	03				\triangle	ΥI
Projec	t No:	OTT-22017859-A0							"		10		$^{\prime}$
Projec	t:	Proposed Avalon III School							igure No.		18		ı
Locatio	on:	2666 Tenth Line Road, Ottawa, ON							Page.		of <u>1</u>		
Date D	rilled:	'Dec 8, 2022			Split Spoon Sam	ple		\boxtimes	Combustible V	apour R	eading		
Orill Ty	pe:	Case 580 Rubber Tire Backhoe			Auger Sample SPT (N) Value			II	Natural Moistur Atterberg Limit		ent H		× ⊕
Datum	:	Geodetic Elevation			Dynamic Cone T Shelby Tube	est	_	_ _	Undrained Tria % Strain at Fai				\oplus
_ogge	d by:	MZ Checked by: SMP	_		Shear Strength by Vane Test	у		+ s	Shear Strength Penetrometer				•
G M B O L		SOIL DESCRIPTION	Geodetic Elevation m 86.68	Depth	Standard F 20 Shear Strength 50	40	60 150	Value 80 kPa 200	Combustible V 250 Natural M Atterberg Lir 20	500 pisture C	750 ontent %	J⋒l	Natura Unit W kN/m
	FILL Silty	sand with gravel, cobbles, red brick		0									




- Test pit backfilled upon completion of excavating operation.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS						
Elapsed	Water	Hole Open				
Time	Level (m)	To (m)				

CORE DRILLING RECORD						
Run No.	Depth (m)	% Rec.	RQD %			

	Log of	Test Pit TP-	04		eyn
Project No:	OTT-22017859-A0			=: 10	
Project:	Proposed Avalon III School		¹	Figure No. 19	_
Location:	2666 Tenth Line Road, Ottawa, ON			Page. <u>1</u> of <u>1</u>	_
Date Drilled:	'Dec 8, 2022	Split Spoon Sample	\boxtimes	Combustible Vapour Reading	
Drill Type:	Case 580 Rubber Tire Backhoe			Natural Moisture Content Atterberg Limits	× ⊷
Datum:	Geodetic Elevation	Dynamic Cone Test Shelby Tube	<u> </u>	Undrained Triaxial at % Strain at Failure	Φ
Logged by:	MZ Checked by: SMP	Shear Strength by	+	Shear Strength by Penetrometer Test	A




₽

- 2. Test pit backfilled upon completion of excavating operation.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS				
Elapsed Time	Water	Hole Open To (m)		
rime	Level (m)	10 (m)		

CORE DRILLING RECORD				
Run No.	Depth (m)	% Rec.	RQD %	
	` ,			

	Log o	f Test Pit TP-05		eyn
Project No:	OTT-22017859-A0			
Project:	Proposed Avalon III School		Figure No. 20	_
Location:	2666 Tenth Line Road, Ottawa, ON		Page. <u>1</u> of <u>1</u>	_
Date Drilled:	'Dec 8, 2022	Split Spoon Sample	Combustible Vapour Reading	
Drill Type:	Case 580 Rubber Tire Backhoe	Auger Sample SPT (N) Value O	Natural Moisture Content Atterberg Limits	× ⊷
Datum:	Geodetic Elevation	Dynamic Cone Test Shelby Tube	Undrained Triaxial at % Strain at Failure	\oplus
Loaaed bv:	MZ Checked by: SMP	Shear Strength by	Shear Strength by	A





₽

- 2. Test pit backfilled upon completion of excavating
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS				
Elapsed Time	Water Level (m)	Hole Open To (m)		
	2010. (,	,		

CORE DRILLING RECORD				
Run No.	Depth (m)	% Rec.	RQD %	
	` ,			







₽

- 2. Test pit backfilled upon completion of excavating
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS				
Water Level (m)	Hole Open To (m)			
	Water			

CORE DRILLING RECORD					
Run No.	Depth (m)	% Rec.	RQD %		






₽

- 2. Test pit backfilled upon completion of excavating
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS				
Water Level (m)	Hole Open To (m)			
	Water			

CORE DRILLING RECORD			
Run	Depth	% Rec.	RQD %
No.	(m)		


		_09 0.	100t 1 tt 11 0t	<u> </u>	CX
Project No:	OTT-2201785	<u>9-A0</u>		Figure No. 22	O / \
Project:	Proposed Ava	alon III School		Figure No. 23	_
Location:	2666 Tenth Li	ne Road, Ottawa, ON		Page. <u>1</u> of <u>1</u>	_
Date Drilled:	'Dec 9, 2022		Split Spoon Sample	Combustible Vapour Reading	
Orill Type:	Case 580 Rub	ber Tire Backhoe	Auger Sample SPT (N) Value	Natural Moisture Content Atterberg Limits	× ⊢—≎
Datum:	Geodetic Elev	ation	Dynamic Cone Test Shelby Tube	Undrained Triaxial at % Strain at Failure	\oplus
_oaaed bv:	MZ	Checked by: SMP	Shear Strength by	Shear Strength by	•




- 2. Test pit backfilled upon completion of excavating
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS				
Elapsed Time	Water Level (m)	Hole Open To (m)		
Tille	Lever (III)	10 (111)		

CORE DRILLING RECORD				
Run No.	Depth (m)	% Rec.	RQD %	






₽

- 2. Test pit backfilled upon completion of excavating
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS			
Water	Hole Open		
Level (m)	To (m)		

CORE DRILLING RECORD				
Run No.	Depth (m)	% Rec.	RQD %	

		Log	of Te	est Pit <u>TP</u>	P-10		- CYI
Project No:	OTT-2201785					5: N 0E	
Project:	Proposed Ava	lon III School				Figure No. 25	- 1
Location:	2666 Tenth Lir	ne Road, Ottawa, ON				Page. <u>1</u> of <u>1</u>	-
Date Drilled:	'Dec 9, 2022			Split Spoon Sample	\boxtimes	Combustible Vapour Reading	
Orill Type:	Case 580 Rubl	oer Tire Backhoe		Auger Sample SPT (N) Value		Natural Moisture Content Atterberg Limits	X —→
Datum:	Geodetic Eleva	ation		Dynamic Cone Test Shelby Tube		Undrained Triaxial at % Strain at Failure	•
_ogged by:	MZ	Checked by: SMP		Shear Strength by Vane Test	+ s	Shear Strength by Penetrometer Test	A
S			Geodetic	D Standard Penetration Te	st N Value	Combustible Vapour Reading (pp	om) S A Natura




LOG OF TEST PIT

- Test pit backfilled upon completion of excavating operation.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0 $\,$

WATER LEVEL RECORDS			
Elapsed	Water	Hole Open	
Time	Level (m)	To (m)	
L			

CORE DRILLING RECORD					
Run No.	Depth (m)	% Rec.	RQD %		

Project No:	OTT-22017859-A0	<u> </u>	_	$\nabla \lambda$
Project No.	O11-22017659-A0		Figure No. 26	
Project:	Proposed Avalon III School			_
Location:	2666 Tenth Line Road, Ottawa, ON		Page. <u>1</u> of <u>1</u>	_
Date Drilled:	'Dec 8, 2022	Split Spoon Sample	Combustible Vapour Reading	
Orill Type:	Case 580 Rubber Tire Backhoe	Auger Sample	Natural Moisture Content	×
Jilli Type.	Case 360 Rubber Tile Backiloe	SPT (N) Value	Atterberg Limits	\longrightarrow
Datum:	Geodetic Elevation	Dynamic Cone Test	Undrained Triaxial at % Strain at Failure	\oplus
_ogged by:	MZ Checked by: SMP	Shelby Tube Shear Strength by	Shear Strength by	•




₽

- 2. Test pit backfilled upon completion of excavating
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS			
Elapsed	Water	Hole Open	
Time	Level (m)	To (m)	
L			

CORE DRILLING RECORD					
Run Depth % Rec. RQD % No. (m)					
	···/				

	3	0 00tt <u>2</u>			ヒス
Project No:	OTT-22017859-A0_		Figure No. 27	7	•
Project:	Proposed Avalon III School		·		
Location:	2666 Tenth Line Road, Ottawa, ON		Page. <u>1</u> of	f <u>1</u>	
Date Drilled:	'Dec 8, 2022	Split Spoon Sample	Combustible Vapour Rea	ading	
Orill Type:	Case 580 Rubber Tire Backhoe	Auger Sample SPT (N) Value	Natural Moisture Content Atterberg Limits	t j	× —⊖
Datum:	Geodetic Elevation	Dynamic Cone Test Shelby Tube	Undrained Triaxial at % Strain at Failure		\oplus
odded pv.	M7 Checked by: SMP	Chan Chan ath hu	Shear Strength by		



₽

- 2. Test pit backfilled upon completion of excavating
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS				
Elapsed Time	Water Level (m)	Hole Open To (m)		

CORE DRILLING RECORD				
Run No.	Depth (m)	% Rec.	RQD %	
	, ,			

		103t 1 1t <u>11 10</u>	•	$\leftarrow x$
Project No:	OTT-22017859-A0			
Project:	Proposed Avalon III School		Figure No. 28	_
Location:	2666 Tenth Line Road, Ottawa, ON		Page. <u>1</u> of <u>1</u>	_
Date Drilled:	'Dec 8, 2022	Split Spoon Sample	Combustible Vapour Reading	
Drill Type:	Case 580 Rubber Tire Backhoe	Auger Sample SPT (N) Value O	Natural Moisture Content Atterberg Limits	× ⊢—⊙
Datum:	Geodetic Elevation	Dynamic Cone Test Shelby Tube	Undrained Triaxial at % Strain at Failure	\oplus
Logged by:	MZ Checked by: SMP	Shear Strength by +	Shear Strength by	•


, I	S Y		Geodetic	D		Star	ndaro	Pen	etrat	ion T	est N	ı Val	ıe			25	0	500)	750	g (ppm)	1) S A	Nat
,	S M B O	SOIL DESCRIPTION	Elevation	p t h	She	20 ar S		4 gth	0	6	0	8	0 kF	Pa	At	Natu	ral Mo	istur nits (e Con % Dry	itent We	% eight)	n) SAMPLES	Uni
4	. z ₄ 1 ^N	TOPSOIL ~ 100mm thick	87.26 87.2	n 0		50) ::	10	00	15	50	2	00		:::	20		40		60		<u> </u>	+
		FILL Silty sand with topsoil inclusions, as pieces and brick fragments												.5 p			.;;						
k		-	86.6				• ! • !			: :				ٳ]	×							G
*		GRANULAR FILL 50 mm Crushed Limestone, sand ar												0 pj	om X							m	y G
		gravel, grey, wet	86.3	1			111					:::			7. 3.			+	1111	+			-
		Silty clay, grey, moist												0 pj	om]			×				m	g G
k						**	· ! · ? · ! · ?														2 (* 1 2 (* 1		1
		-					•					: : : : : :						#			: : :	:	
		TOPSOIL	85.5											0 pj	om								-
		dark brown, wet, soft	85.3	2			· [·] · [·	<u> </u>				;;;·]:- {-		×	#	***	+	: ::: : :::		g G
		Grey, wet Test Pit Terminated at 2.2 m De	85.1			• • •					÷												
		Note:																					
		No water seepage or cave-in																					
		.,,																					
0.	TES:	/Test Pit data requires Interpretation by exp.	WATE		EVEL	RE	CO	RDS	3] [COF	RE DI	RILL	ING	RF	COF	 RD	
.В	orehole	/ Lest Pit data requires interpretation by exp	**/\\\L																				

- 2. Test pit backfilled upon completion of excavating operation.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS									
Elapsed	Water	Hole Open							
Time	Level (m)	To (m)							
		•							

CORE DRILLING RECORD									
Run No.	Depth (m)	% Rec.	RQD %						

		01 1036116 <u>11 14</u>		$\leftarrow x$
Project No:	OTT-22017859-A0		5: No. 20	
Project:	Proposed Avalon III School		Figure No. 29	_
Location:	2666 Tenth Line Road, Ottawa, ON		Page. <u>1</u> of <u>1</u>	-
Date Drilled:	'Dec 8, 2022	Split Spoon Sample	Combustible Vapour Reading	
Orill Type:	Case 580 Rubber Tire Backhoe	Auger Sample SPT (N) Value O	Natural Moisture Content Atterberg Limits	× ⊢—⊖
Datum:	Geodetic Elevation	Dynamic Cone Test Shelby Tube	Undrained Triaxial at % Strain at Failure	\oplus
odded pv.	M7 Checked by: SMP	Shear Strength by	Shear Strength by	




₽

- 2. Test pit backfilled upon completion of excavating
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS										
Elapsed	Water	Hole Open								
Time	Level (m)	To (m)								

CORE DRILLING RECORD										
Depth (m)	% Rec.	RQD %								
` ,										

Project No:	3 -	· · · · · · · · · · · · · · · · · · ·	_	$\nabla \Lambda$
Project No.	OTT-22017859-A0		Figure No. 30	
Project:	Proposed Avalon III School			_
Location:	2666 Tenth Line Road, Ottawa, ON		Page. <u>1</u> of <u>1</u>	_
Date Drilled:	'Dec 8, 2022	Split Spoon Sample	Combustible Vapour Reading	
Orill Type:	Case 580 Rubber Tire Backhoe	Auger Sample	Natural Moisture Content	×
Jilli Type.	Case 500 Rubber Tile Backiloe	SPT (N) Value	Atterberg Limits	\longrightarrow
Datum:	Geodetic Elevation	Dynamic Cone Test	Undrained Triaxial at % Strain at Failure	\oplus
_ogged by:	MZ Checked by: SMP	Shelby Tube Shear Strength by	Shear Strength by	•



- 2. Test pit backfilled upon completion of excavating operation. ₽
 - 3. Field work supervised by an EXP representative.
 - 4. See Notes on Sample Descriptions
 - 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS										
Elapsed	Water	Hole Open								
Time	Level (m)	To (m)								

CORE DRILLING RECORD										
Run No.	Depth (m)	% Rec.	RQD %							

Project No: OTT-22017859-A0 Figure No. Project: Proposed Avalon III School Page. _1_ of 1 Location: 2666 Tenth Line Road, Ottawa, ON Date Drilled: 'Dec 8, 2022 Split Spoon Sample \boxtimes Combustible Vapour Reading × Auger Sample Natural Moisture Content Drill Type: Case 580 Rubber Tire Backhoe 0 SPT (N) Value 0 Atterberg Limits Dynamic Cone Test Undrained Triaxial at Datum: Geodetic Elevation \oplus Shelby Tube % Strain at Failure Shear Strength by Logged by: Checked by: SMP Ť Shear Strength by


T		Geodetic D Standard Penetration Test N Value				Combustible Vapour Reading (ppm) 250 500 750							Notes							
	SOIL DESCRIPTION	Elevation	D e p t h		20		40	6	0	8	0		N	25 aţu	0 50 ral Moistu erg Limits	Ire Conte	50 nt %	 	SAMP LES	Natur Unit W
		m		Shear	Stre 50		00	11	50	20		a	Atte	erbe 20			Veigh 60	t)	Ĕ	kN/m
Ø	FILL_	86.73	0		Ť	'	Ť∷	::'`	Ĭ	: : '	::	::	<u> </u>	: 1			Tii	T		
8	Silty clay with topsoil inclusions, cobbles																			
Ø	and boulders measured up to 1 m					.i.i.i.				. : . : .	. i . i .	0 p					1.1.1	. i .i. L		
Ø	diameter, brown, moist				. . :		ļ :: :			. : . : .		[]:-:-:-	⊹♭	K		1:::	4	m	GS
ऄ		+			+:	+++	+::	÷÷		:::	+++			\vdots			1::	+++	\dashv	
X						÷÷		+		• • • • •				9			1::	- - -		
X							1::	****		· { · } · : :		: : : : :	· · · · · · · · · · · · · · · · · · ·	1						
X																				
X		85.7	1	1 1 1	1:	<u> </u>	::	::	1 : :	<u>:::</u>		: :	: : :	:	: : : :		1::			
	TOPSOIL Wet						ļ.:.;				. ; . ; .	15	opm	4					m	GS
1.1	Wet	85.4			1	÷÷	10			· {· }·	· {· }·	: ;.L	H. ; . ; .	H	×		133	· ; ; ; · [Y		GS
	CLAY	-05.4		****		***	1:1	• • • • •	111	• • • • •		10	pm		•		123		000	GS
1	Brown, wet	85.2						.,			; ; ;	::1		*				1	m	19
	Test Pit Terminated at 1.5 m Depth																			
														1			; ;			
							: :										1 : :			
																	1 : :			
																	1 : :			
														1			! !			
																	1 : :			
				1 : : : :	:	$\vdots \vdots \vdots$: :	::	::	: :	::	: :	:::	:	::::		1 : :	: :		
																	1 : :			
				1 : : : :	: :	$\vdots \vdots \vdots$: :	::	::	: :	::	: :	: : :	:	:::::	::::	1 : :	: :		
														1						
														1			1 : :			
						: : :	1::	::	::	: :		: :	: : :	:			1 : :			
							: :										1 : :			
	Note:						1::	::	1 : :	: :		: :	: : :				1 : :			
	1) Water gushing in from 1.0 m depth filling						: :							:			1 : :			
	test pit to 1 m depth				:		: :	::	; ;	: :		: :		:			1::			
							1::	::	1 : :	: :		: :		:			1::	::		
							1::			: :							: :			
- [1		[::::		:::	1::	::	1::	: :	::	::	:::	:	::::	::::	1::	::[


₽

- Test pit backfilled upon completion of excavating operation.
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS										
Elapsed Time	Water	Hole Open To (m)								
Time	Level (m)	10 (111)								

CORE DRILLING RECORD										
Run No.	Depth (m)	% Rec.	RQD %							





₽

- 2. Test pit backfilled upon completion of excavating
- 3. Field work supervised by an EXP representative.
- 4. See Notes on Sample Descriptions
- 5. This Figure is to read with exp. Services Inc. report OTT-22017859-A0

WATER LEVEL RECORDS							
Elapsed	Water	Hole Open					
Time	Level (m)	To (m)					

CORE DRILLING RECORD						
Run No.	Depth (m)	% Rec.	RQD %			
	, ,					

DRY BEDROCK CORES

WET BEDROCK CORES





EXP Services Inc. www.exp.com

t: +1.613.688.1899 | f: +1.613.225.7337 2650 Queensview Drive, Suite 100 Ottawa, ON K2B 8H6, Canada


borehole no.		project	project no.		
BH-1	Run 1: 33.0m - 33.8m Run 2: 33.8m - 34.5m Run 3: 34.5m - 36.2m	New Avalon III School - 2666 Tenth Line Road, Ottawa	OTT-22017859-A0		
date cored	Run 4: 36.2m - 37.7m				
Jan 12, 2023	end of borehole	Borehole 1 Rock Core Photographs	FIG 33		



Grain-Size Distribution Curve Method of Test For Particle Size Analysis of Soil ASTM C-136/ASTM D422

100-2650 Queensview Drive Ottawa, ON K2B 8H6

Unified Soil Classification System




EXP Project No.:	OTT-22017859-A0	Project Name :	Project Name : Proposed New Avalon III Elementary School							
Client :	CECCE	Project Location	Project Location : Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa							
Date Sampled :	December 21, 2023	Borehole No:		BH13 Sample No.:			SS2		Depth (m):	0.8-1.4
Sample Description :		% Silt and Clay	39	% Sand	40	% Gravel		21	Figure .	24
Sample Description : FILL: Silty Sand with Gravel (SM), Some Clay						Figure :	34			



Percent Passing

Grain-Size Distribution Curve Method of Test For Particle Size Analysis of Soil ASTM C-136/ASTM D422

100-2650 Queensview Drive Ottawa, ON K2B 8H6




EXP Project No.:	OTT-22017859-A0	Project Name :	roject Name : Proposed New Avalon III Elementary School									
Client :	CECCE	Project Location	oject Location: Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa									
Date Sampled :	December 19, 2023	Borehole No:		BH1 Sample No.: SS4				S4	Depth (m):	2.3-2.9		
Sample Description :		% Silt and Clay	% Silt and Clay 96 % Sand 4 % Gravel 0					Figure :	25			
Sample Description :	Clay of High Plasticity (CH)								rigule .	35		



Percent Passing

Grain-Size Distribution Curve Method of Test For Particle Size Analysis of Soil ASTM C-136/ASTM D422

100-2650 Queensview Drive Ottawa, ON K2B 8H6




EXP Project No.:	OTT-22017859-A0	Project Name :	roject Name : Proposed New Avalon III Elementary School									
Client :	CECCE	Project Location	oject Location: Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa									
Date Sampled :	December 22, 2023	Borehole No:		BH8 Sample No.: SS				S3	Depth (m):	2.3-2.9		
Sample Description :		% Silt and Clay	% Silt and Clay 100 % Sand 0 % Grave					0	Figure :	36		
Sample Description :	Clay of High Plasticity (CH)								rigure .	30		



Grain-Size Distribution Curve Method of Test For Particle Size Analysis of Soil ASTM C-136/ASTM D422

100-2650 Queensview Drive Ottawa, ON K2B 8H6



EXP Project No.:	OTT-22017859-A0	Project Name :	Project Name : Proposed New Avalon III Elementary School									
Client :	CECCE	Project Location	roject Location: Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa									
Date Sampled :	December 21, 2023	Borehole No:		BH14	San	Depth (m):	1.5-2.1					
Sample Description :		% Silt and Clay	98	% Sand 2 % Gravel 0				Eiguno .				
Sample Description : Clay of High Plasticity (CH)									Figure :	37		

Project: Geotechnical Investigation - Proposed New Avalon III Elementary **Project Location:** Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa

Client CECCE

Borehole No. BH1 SS4 **Sample Depth** 2.3-2.9m



ASTM D-2487, Unified Soils Classification System


Clay of High Plasticity (CH)


Liquid Limit Determination

Elquia Ellint Determination						
	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	31.90	29.36	31.94			
Weight of Dry Soils + Pan:	27.35	25.59	27.09			
Weight of Pan:	19.67	19.49	19.68			
Weight of Dry Soils:	7.68	6.10	7.41			
Weight of Moisture:	4.55	3.77	4.85			
% Moisture:	59.2 %	61.8 %	65.5 %			
N:	29	22	12			

Liquid Limit @ 25 Blows: 60.7 %
Plastic Limit: 18.9 %
Plasticity Index, I_P: 41.8 %

	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	20.57	20.37				
Weight of Dry Soils + Pan:	20.40	20.25				
Weight of Pan:	19.49	19.62				
Weight of Dry Soils:	0.91	0.63				
Weight of Moisture:	0.17	0.12				
% Moisture:	18.7 %	19.1 %				





Project: Geotechnical Investigation - Proposed New Avalon III Elementary **Project Location:** Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa

Client CECCE

Borehole No. BH8 SS3 **Sample Depth** 2.3-2.9m



ASTM D-2487, Unified Soils Classification System


Clay of High Plasticity (CH)


Liquid Limit Determination

	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	28.03	28.86	28.79			
Weight of Dry Soils + Pan:	24.65	24.97	24.78			
Weight of Pan:	19.53	19.38	19.38			
Weight of Dry Soils:	5.12	5.59	5.40			
Weight of Moisture:	3.38	3.89	4.01			
% Moisture:	66.0 %	69.6 %	74.3 %			
N:	35	25	14			

Liquid Limit @ 25 Blows: 69.8 %
Plastic Limit: 29.4 %
Plasticity Index, I_P: 40.5 %

T table Emile Determination						
	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	21.39	20.92				
Weight of Dry Soils + Pan:	21.00	20.63				
Weight of Pan:	19.70	19.62				
Weight of Dry Soils:	1.30	1.01				
Weight of Moisture:	0.39	0.29				
% Moisture:	30.0 %	28.7 %				





Project:Geotechnical Investigation - Proposed New Avalon III Elementary**Project Location:**Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa

Client CECCE

Borehole No. BH14 SS3 **Sample Depth** 1.5-2.1m



ASTM D-2487, Unified Soils Classification System


Clay of High Plasticity (CH)


Liquid Limit Determination

Elquiu Ellint Determination						
	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	30.15	28.72	29.54			
Weight of Dry Soils + Pan:	26.11	24.94	25.50			
Weight of Pan:	19.73	19.39	19.86			
Weight of Dry Soils:	6.38	5.55	5.64			
Weight of Moisture:	4.04	3.78	4.04			
% Moisture:	63.3 %	68.1 %	71.6 %			
N:	34	20	12			

Liquid Limit @ 25 Blows: 66.6 %
Plastic Limit: 27.4 %
Plasticity Index, I_P: 39.2 %

	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	22.16	22.22				
Weight of Dry Soils + Pan:	21.60	21.65				
Weight of Pan:	19.54	19.58				
Weight of Dry Soils:	2.06	2.07				
Weight of Moisture:	0.56	0.57				
% Moisture:	27.2 %	27.5 %				








Percent Passing

Grain-Size Distribution Curve Method of Test For Particle Size Analysis of Soil ASTM C-136/ASTM D422

100-2650 Queensview Drive Ottawa, ON K2B 8H6




EXP Project No.:	OTT-22017859-A0	Project Name :	roject Name : Proposed New Avalon III Elementary School									
Client :	CECCE	Project Location	oject Location: Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa									
Date Sampled :	December 15, 2023	Borehole No:		BH2 Sample No.: SS8				S8	Depth (m) :	7.6-8.2		
Sample Description :		% Silt and Clay	Silt and Clay 100 % Sand 0 % Gravel 0					Figure :	41			
Sample Description :	Clay of High Plasticity (CH)								rigule .	41		



Percent Passing

Grain-Size Distribution Curve Method of Test For Particle Size Analysis of Soil ASTM C-136/ASTM D422

100-2650 Queensview Drive Ottawa, ON K2B 8H6




EXP Project No.:	OTT-22017859-A0	Project Name :	Project Name : Proposed New Avalon III Elementary School									
Client :	CECCE	Project Location	oject Location: Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa									
Date Sampled :	December 15, 2023	Borehole No:		BH5 Sample No.: SS7				S 7	Depth (m):	6.1-6.7		
Sample Description :		% Silt and Clay	% Silt and Clay 100 % Sand 0 % Gravel 0					Figure :	42			
Sample Description :	Clay of High Plasticity (CH)								rigule .	42		



Grain-Size Distribution Curve Method of Test For Particle Size Analysis of Soil ASTM C-136/ASTM D422

100-2650 Queensview Drive Ottawa, ON K2B 8H6



EXP Project No.:	OTT-22017859-A0	Project Name :	Project Name : Proposed New Avalon III Elementary School									
Client :	CECCE	Project Location	roject Location : Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa									
Date Sampled :	December 22, 2023	Borehole No:	orehole No: BH8 Sample No.: SS4							3.8-4.4		
Sample Description :		% Silt and Clay	100	% Sand 0 % Gravel 0				Figure 1	40			
Sample Description : Clay of High Plasticity (CH)									Figure :	43		

Project: Geotechnical Investigation - Proposed New Avalon III Elementary **Project Location:** Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa

Client CECCE

Borehole No. BH2 SS8 **Sample Depth** 7.6-8.2m



ASTM D-2487, Unified Soils Classification System


Clay of High Plasticity (CH)


Liquid Limit Determination

Erquit Emili E titi immunon						
	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	30.02	31.73	28.40			
Weight of Dry Soils + Pan:	25.90	26.74	24.83			
Weight of Pan:	19.66	19.31	19.84			
Weight of Dry Soils:	6.24	7.43	4.99			
Weight of Moisture:	4.12	4.99	3.57			
% Moisture:	66.0 %	67.2 %	71.5 %			
N:	27	17	12			

Liquid Limit @ 25 Blows: 66.1 %
Plastic Limit: 26.3 %
Plasticity Index, I_P: 39.8 %

Tastic Dillit Determination						
	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	21.38	21.31				
Weight of Dry Soils + Pan:	20.99	20.97				
Weight of Pan:	19.54	19.65				
Weight of Dry Soils:	1.45	1.32				
Weight of Moisture:	0.39	0.34				
% Moisture:	26.9 %	25.8 %				





Project:Geotechnical Investigation - Proposed New Avalon III Elementary**Project Location:**Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa

Client CECCE

Borehole No. BH5 SS7 **Sample Depth** 6.1-6.7m



ASTM D-2487, Unified Soils Classification System


Clay of High Plasticity (CH)


Liquid Limit Determination

	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	29.35	29.15	29.64			
Weight of Dry Soils + Pan:	25.54	25.26	25.46			
Weight of Pan:	19.52	19.38	19.34			
Weight of Dry Soils:	6.02	5.88	6.12			
Weight of Moisture:	3.81	3.89	4.18			
% Moisture:	63.3 %	66.2 %	68.3 %			
N:	34	23	16			

Liquid Limit @ 25 Blows: 65.7 %
Plastic Limit: 22.3 %
Plasticity Index, I_P: 43.5 %

	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	20.54	20.36				
Weight of Dry Soils + Pan:	20.38	20.23				
Weight of Pan:	19.68	19.63				
Weight of Dry Soils:	0.70	0.60				
Weight of Moisture:	0.16	0.13				
% Moisture:	22.9 %	21.7 %				





Project:Geotechnical Investigation - Proposed New Avalon III Elementary**Project Location:**Sweet Valley Drive between Mer Bleu & Tenth Line Rd, Ottawa

Client CECCE

Borehole No. BH8 SS4 **Sample Depth** 3.8-4.4m



ASTM D-2487, Unified Soils Classification System


Clay of High Plasticity (CH)


Liquid Limit Determination

	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	29.83	30.69	31.82			
Weight of Dry Soils + Pan:	25.77	26.05	26.75			
Weight of Pan:	19.65	19.36	19.87			
Weight of Dry Soils:	6.12	6.69	6.88			
Weight of Moisture:	4.06	4.64	5.07			
% Moisture:	66.3 %	69.4 %	73.7 %			
N:	34	26	13			

Liquid Limit @ 25 Blows: 69.6 %
Plastic Limit: 27.0 %
Plasticity Index, I_P: 42.6 %

	#1	#2	#3	#4	#5	#6
Weight of Wet Soils + Pan:	21.36	21.53				
Weight of Dry Soils + Pan:	20.97	21.13				
Weight of Pan:	19.53	19.64				
Weight of Dry Soils:	1.44	1.49				
Weight of Moisture:	0.39	0.40				
% Moisture:	27.1 %	26.9 %				







One-Dimensional Consolidation Properties of Soils Using Incremental Loading
ASTM D2435/D2435M - 11(2020)


Project Project No. Borehole No. Sample No. Sample Depth Proposed CECCE Avalon III School, Exp# OTT-0022017859-A0

121623683

BH 5

ST 5

10-12 ft



Results:

 σ'_p = 115 kPa

 $c_c = 0.551$

 $c_r = 0.046$

 $\sigma'_{v0} = 59.0 \text{ kPa}$

 $w_c = 53.03 \%$

 $\gamma = 16.76 \text{ kN/m}^3$

 $e_0 = 1.462$

OCR = 1.95



One-Dimensional Consolidation Properties of Soils Using Incremental Loading
ASTM D2435/D2435M - 11(2020)

Project No.
Borehole No.
Sample No.
Sample Depth


Proposed CECCE Avalon III School, Exp# OTT-0022017859-A0

121623683

BH 3

ST 7

20-22 ft



Results:

 $\sigma'_p = 65 \text{ kPa}$

 $c_c = 0.457$

 $c_r = 0.033$

 $\sigma'_{v0} = 73.8 \text{ kPa}$

 $w_c = 65.66 \%$

 $\gamma = 15.9 \text{ kN/m}^3$

 $e_0 = 1.812$

OCR = 0.88*

Project Name: Geotechnical Investigation – Proposed Avalon III Elementary School 2666 Tenth Line Road, Ottawa, Ontario CECCE Project 2022AVN115. Project Number: OTT-22017859-A0 March 7, 2023

Appendix A – Multi-channel Analysis of Surface Waves (MASW) Survey Report



100 – 2545 Delorimier Street Tel.: (450) 679-2400 Longueuil (Québec) Fax: (514) 521-4128 Canada J4K 3P7 info@geophysicsgpr.com www.geophysicsgpr.com

January 10th, 2023

Transmitted by email: lsmail.Taki@exp.com

Our Ref.: GPR-22-04246

Mr. Ismail Taki, M.Eng., P.Eng. Senior Manager, Earth & Environment, Eastern Region **exp** Services inc. 100 – 2650 Queensview Drive Ottawa ON K2B 8H6

Shear Wave Velocity Sounding for the Site Class Identification Tenth Line Road, Ottawa (ON)

[Project: OTT-22017859]

Dear Sir.

Geophysics GPR International inc. has been mandated by **exp** Services inc. to carry out a seismic shear wave survey at the intersection of Sweet Valley Drive and Tenth Line Road, in Ottawa (ON). The geophysical investigation used the Multi-channel Analysis of Surface Waves (MASW), the Spatial AutoCorrelation (SPAC), and the seismic reflexion methods. From the subsequent results, the seismic shear wave velocity values were calculated for the soil to determine the Site Class.

The surveys were carried out on November 24th, 2022, by Mr. Timothy Ward, geophysics technician, and Mr. Ewen Pasdeloup, intern. Figure 1 shows the regional location of the site and Figure 2 illustrates the location of the seismic spread. Both figures are presented in the Appendix.

The following paragraphs briefly describe the survey design, the principles of the testing methods, and the results presented in table and graph.

MASW PRINCIPLE

The *Multi-channel Analysis of Surface Waves* (MASW) and the *SPatial AutoCorrelation* (SPAC or MAM for *Microtremors Array Method*) are seismic methods used to evaluate the shear wave velocities of subsurface materials through the analysis of the dispersion properties of the Rayleigh surface wave. The MASW is considered an "active" method, as the seismic signal is induced at known location and time in the geophones' spread axis. Conversely, the SPAC is considered a "passive" method, using the low frequency "signals" produced far away. The method can also be used with "active" seismic source records. The SPAC method generally allows deeper Vs soundings. Its dispersion curve can then be merged with the one of higher frequency from the MASW to calculate a more complete inversion. The dispersion properties are expressed as a change of velocities with respect to frequencies. Surface wave energy will decay exponentially with depth. Lower frequency surface waves will travel deeper and thus be more influenced by deeper velocity layering than the shallow higher frequency waves. The inversion of the Rayleigh wave dispersion curve yields a shear wave (V_S) velocity depth profile (sounding).

Figure 3 schematically outlines the basic operating procedure for the MASW method. Figure 4 illustrates an example of one of the MASW/SPAC records, the corresponding spectrogram analysis and resulting 1D $V_{\rm S}$ model.

INTERPRETATION

The main processing sequence involved data inspection and edition when required; spectral analysis ("phase shift" for MASW, and "cross-correlation" for SPAC); picking the fundamental mode; and 1D inversion of the MASW and SPAC shot records using the SeisImagerSW™ software. The data inversions used a nonlinear least squares algorithm.

In theory, all the shot records for a given seismic spread should produce a similar shear-wave velocity profile. In practice, however, differences can arise due to energy dissipation, local surface seismic velocities variations, and/or dipping of overburden layers or rock. In general, the precision of the calculated seismic shear wave velocities ($V_{\rm S}$) is close to 15% or better.

More detailed descriptions of these methods are presented in *Shear Wave Velocity Measurement Guidelines for Canadian Seismic Site Characterization in Soil and Rock*, Hunter, J.A., Crow, H.L., et al., Geological Surveys of Canada, General Information Product 110, 2015.



SURVEY DESIGN

The seismic acquisition spreads were laid perpendicular to the Tenth Line Road (Figure 2). The geophone spacing was of 3.0 metres for the main spread and 1.0 metre dedicated to the near surface materials. The seismic records were produced with a seismograph Terraloc Pro 2 (from ABEM Instrument), and the geophones were 4.5 Hz. The seismic records counted 4096 data, sampled at 1000 μs for the MASW surveys, and 40 μs for the seismic refraction. The records included a pre-trigged portion of 10 ms. An 8 kg sledgehammer was used as the energy source with impacts being recorded off both ends of the seismic spreads. A stacking procedure was also used to improve the Signal / Noise ratio for the seismic records.

The shear wave depth sounding can be considered as the average of the bulk area within the geophone spread, especially for its central half-length.

RESULTS

The MASW calculated V_S results are illustrated at Figure 5.

By seismic reflection, the bedrock depth was calculated between 36 and 38.6 meters.

The \overline{V}_{S30} value results from the harmonic mean of the shear wave velocities, from the surface to 30 metres deep. It is calculated by dividing the total depth of interest (30 metres) by the sum of the time spent in each velocity layer from the surface down to 30 metres, as:

$$\bar{V}_{S30} = \frac{\sum_{i=1}^{N} H_i}{\sum_{i=1}^{N} H_i / V_i} \mid \sum_{i=1}^{N} H_i = 30 \text{ m}$$

(N: number of layers; H_i : thickness of layer "i"; V_i : V_s of layer "i")

Thus, the \overline{V}_{S30} value represents the seismic shear wave velocity of an equivalent homogeneous single layer response, between the surface and 30 meters deep.

The calculated \overline{V}_{S30} value of the actual site is 128,1 m/s (Table 1), corresponding to the Site Class "E". It must be noted that very low and low seismic velocities were calculated for the clayey materials, from the surface to approximately 27 meters deep.



CONCLUSION

Geophysical surveys were conducted to identify the Site Class at the intersection of Sweet Valley Drive and Tenth Line Road, in Ottawa (ON). The seismic surveys used the MASW and the SPAC analysis, and the seismic reflection to calculate the \overline{V}_{S30} value. Its calculation is presented at Table 1.

The \overline{V}_{S30} value of the actual site is 128 m/s, corresponding to the Site Class "E" (\overline{V}_{S30} < 180 m/s), as determined through the MASW and SPAC methods, Table 4.1.8.4.-A of the NBC, and the Building Code, O. Reg. 332/12. It must be noted that very low and low seismic velocities were calculated from the surface to approximately 27 meters deep. A geotechnical assessment of the corresponding materials should be produced for the potential of liquefaction, the clay degree of sensitivity, and possibly other critical parameters.

It must also be noted that other geotechnical information gleaned on site; including the presence of liquefiable soils, very soft clays, high moisture content etc. (cf. Table 4.1.8.4.- A of the NBC) can supersede the Site classification provided in this report based on the \overline{V}_{S30} value.

The V_S values calculated are representative of the in-situ materials and are not corrected for the total and effective stresses.

Hoping the whole to your satisfaction, we remain yours truly,

Alexis Marchand, Eng.

Project Manager

(OIQ Number: 6008271)






Figure 1: Regional location of the Site (Source: OpenStreetMap®)



Figure 2: Location of the seismic spread (Source: Google Earth)






Figure 3: MASW Operating Principle




Figure 4: Example of a MASW/SPAC record, Phase Velocity - Frequency curve of the Rayleigh wave and resulting 1D Shear Wave Velocity Model






Figure 5: MASW Shear-Wave Velocity Sounding



 $\frac{\text{TABLE 1}}{V_{S30}} \ \text{Calculation for the Site Class (actual site)}$

Doubh		Vs		Thisluses	Cumulative	Delay for	Cumulative	Vs at given
Depth	Min.	Median	Max.	Thickness	Thickness	Median Vs	Delay	Depth
(m)	(m/s)	(m/s)	(m/s)	(m)	(m)	(s)	(s)	(m/s)
0	108.8	117.6	123.9	Gro	und level wh	ile survey (N	ovember 24tl	h, 2022)
1.07	108.0	117.6	127.6	1.07	1.07	0.009113	0.009113	117.6
2.31	91.4	99.1	107.4	1.24	2.31	0.010511	0.019624	117.6
3.71	87.2	95.2	103.2	1.40	3.71	0.014137	0.033761	109.9
5.27	86.1	102.2	108.6	1.57	5.27	0.016450	0.050211	105.1
7.01	98.1	104.4	124.6	1.73	7.01	0.016933	0.067144	104.3
8.90	98.1	106.0	125.3	1.90	8.90	0.018154	0.085298	104.4
10.96	104.7	110.3	113.3	2.06	10.96	0.019429	0.104727	104.7
13.19	103.5	120.9	127.6	2.23	13.19	0.020169	0.124896	105.6
15.58	111.7	131.0	148.4	2.39	15.58	0.019768	0.144664	107.7
18.13	135.4	147.1	155.8	2.55	18.13	0.019509	0.164173	110.4
20.85	148.5	161.1	177.8	2.72	20.85	0.018487	0.182660	114.2
23.74	163.7	178.8	218.5	2.88	23.74	0.017907	0.200568	118.3
26.79	167.0	194.6	287.6	3.05	26.79	0.017052	0.217620	123.1
30				3.21	30.00	0.016515	0.234135	128.1

Vs30 (m/s)	128.1
Site Class	E ⁽¹⁾

(1) Conditional to geotechnical assessment results of the materials associated with the very low to low seismic velocity values, for the potential of liquefaction, the clay degree of sensitivity, and/or other critical parameters.



Project Name: Geotechnical Investigation – Proposed Avalon III Elementary School 2666 Tenth Line Road, Ottawa, Ontario CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

Appendix B – Laboratory Certificate of Analysis





5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

CLIENT NAME: EXP SERVICES INC
2650 QUEENSVIEW DRIVE, UNIT 100

OTTAWA, ON K2B8H6 (613) 688-1899

ATTENTION TO: Matthew Zammit PROJECT: OTT-22017859-AO

AGAT WORK ORDER: 23Z986235

SOIL ANALYSIS REVIEWED BY: Nivine Basily, Inorganics Report Writer

DATE REPORTED: Jan 13, 2023

PAGES (INCLUDING COVER): 5 VERSION*: 1

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

Notes	

Disclaimer:

**!---

- All work conducted herein has been done using accepted standard protocols, and generally accepted practices and methods. AGAT test methods may
 incorporate modifications from the specified reference methods to improve performance.
- All samples will be disposed of within 30 days after receipt unless a Long Term Storage Agreement is signed and returned. Some specialty analysis may
 be exempt, please contact your Client Project Manager for details.
- AGAT's liability in connection with any delay, performance or non-performance of these services is only to the Client and does not extend to any other
 third party. Unless expressly agreed otherwise in writing, AGAT's liability is limited to the actual cost of the specific analysis or analyses included in the
 services.
- This Certificate shall not be reproduced except in full, without the written approval of the laboratory.
- The test results reported herewith relate only to the samples as received by the laboratory.
- Application of guidelines is provided "as is" without warranty of any kind, either expressed or implied, including, but not limited to, warranties of
 merchantability, fitness for a particular purpose, or non-infringement. AGAT assumes no responsibility for any errors or omissions in the guidelines
 contained in this document.
- All reportable information as specified by ISO/IEC 17025:2017 is available from AGAT Laboratories upon request.

AGAT Laboratories (V1)

Page 1 of 5

Member of: Association of Professional Engineers and Geoscientists of Alberta (APEGA)

Western Enviro-Agricultural Laboratory Association (WEALA) Environmental Services Association of Alberta (ESAA) AGAT Laboratories is accredited to ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA) and/or Standards Council of Canada (SCC) for specific tests listed on the scope of accreditation. AGAT Laboratories (Mississauga) is also accredited by the Canadian Association for Laboratory Accreditation Inc. (CALA) for specific drinking water tests. Accreditations are location and parameter specific. A complete listing of parameters for each location is available from www.cala.ca and/or www.scc.ca. The tests in this report may not necessarily be included in the scope of accreditation. Measurement Uncertainty is not taken into consideration when stating conformity with a specified requirement.



Certificate of Analysis

AGAT WORK ORDER: 23Z986235 PROJECT: OTT-22017859-AO 5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.aqatlabs.com

CLIENT NAME: EXP SERVICES INC

SAMPLING SITE:2666 Tenth Line Rd., Ottawa

ATTENTION TO: Matthew Zammit

SAMPLED BY:EXP

(Soil) Inorganic Chemistry

DATE RECEIVED: 2023-01-09							DATE REPORTED: 2023-0
	SA	AMPLE DES	CRIPTION:	BH1 SS5 10'-12'	BH6 SS3 5'-7'	BH7 SS8 25'-27'	
		SAM	PLE TYPE:	Soil	Soil	Soil	
		DATE	SAMPLED:	2022-12-19	2022-12-14	2022-12-14	
Parameter	Unit	G/S	RDL	4669537	4669539	4669540	
Chloride (2:1)	μg/g		2	456	22	1500	
Sulphate (2:1)	μg/g		2	108	89	84	
pH (2:1)	pH Units		NA	9.24	8.19	9.43	
Resistivity (2:1) (Calculated)	ohm.cm		1	1040	5050	256	

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard

4669537-4669540 pH, Chloride and Sulphate were determined on the extract obtained from the 2:1 leaching procedure (2 parts DI water: 1 part soil). Resistivity is a calculated parameter. Analysis performed at AGAT Toronto (unless marked by *)

CHARTERD BOSILY 9



5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

Quality Assurance

CLIENT NAME: EXP SERVICES INC

PROJECT: OTT-22017859-AO

AGAT WORK ORDER: 23Z986235

ATTENTION TO: Matthew Zammit

SAMPLING SITE:2666 Tenth Line Rd., Ottawa SAMPLED BY:EXP

Soil Analysis															
RPT Date: Jan 13, 2023	RPT Date: Jan 13, 2023 DUPLICATE REFERENCE MATERIAL METHOD BLANK SPIKE MATRIX SPIKE							KE							
PARAMETER	Batch	Sample	Dup #1	Dup #2	RPD	Method Blank	Measured		ptable nits	Recovery	Lie	ptable nits	Recovery	Lie	ptable nits
. ,		ld					Value	Lower	Upper	,		Upper	,		Upper
(Soil) Inorganic Chemistry															
Chloride (2:1)	4663797		35	35	0.0%	< 2	93%	70%	130%	97%	80%	120%	96%	70%	130%
Sulphate (2:1)	4663797		257	255	0.8%	< 2	97%	70%	130%	100%	80%	120%	NA	70%	130%
pH (2:1)	4671172		10.3	10.3	0.0%	NA	94%	80%	120%						

Comments: NA signifies Not Applicable.

pH duplicates QA acceptance criteria was met relative as stated in Table 5-15 of Analytical Protocol document.

Matrix spike NA: Spike level < native concentration. Matrix spike acceptance limits do not apply and are not calculated.

Certified By:





5835 COOPERS AVENUE MISSISSAUGA, ONTARIO CANADA L4Z 1Y2 TEL (905)712-5100 FAX (905)712-5122 http://www.agatlabs.com

Method Summary

CLIENT NAME: EXP SERVICES INC AGAT WORK ORDER: 23Z986235 PROJECT: OTT-22017859-AO **ATTENTION TO: Matthew Zammit SAMPLED BY:EXP**

SAMPLING SITE:2666 Tenth Line Rd., Ottawa

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Soil Analysis			
Chloride (2:1)	INOR-93-6004	modified from SM 4110 B	ION CHROMATOGRAPH
Sulphate (2:1)	INOR-93-6004	modified from SM 4110 B	ION CHROMATOGRAPH
pH (2:1)	INOR 93-6031	modified from EPA 9045D and MCKEAGUE 3.11	PH METER
Resistivity (2:1) (Calculated)	INOR-93-6036	McKeague 4.12, SM 2510 B,SSA #5 Part 3	CALCULATION



Laboratories

5835 Coopers Avenue Mississauga, Ontario L4Z 1Y2 Ph: 905.712.5100 Fax: 905.712.5122 webearth agatlabs.com

if required ☐ Yes ☐ No

CrVI, ☐ Hg, ☐ HWSB

Laboratory	Use	Only
------------	-----	------

Notes:

THE PROPERTY OF THE PROPERTY O	Work Order #:	2379	86235
--	---------------	------	-------

Cooler Quantity:	- bag	_ no i	O. /
Arrival Temperatures:	19.2	119.1	19.1
LT	6.0	16.2	16.3
Custody Seal Intact:	□Yes	□No	□N/A

Turnaround Time (TAT) Required:

		Regular TAT (Most Analysis) Rush TAT (Rush Surcharges Apply)											
			Day OR	Date F	Requi	red (R		Surch	arges		Day / Appl		ness
			*TAT or 'Sam	Please is excline Day'	usive	of we	eken	ds an	d sta	tutoi	y holi	days	
ı		0. Reg 558	O. Re	g 406	1	-		-				14	(N)
30%	200	Landfill Disposal Characterization TCLP: TCLP: □ M&I □ VOCS □ ABNs □ B(a)P□ PCBs	Excess Soils SPLP Rainwater Leach SPLP: ☐ Metals ☐ vocs ☐ Svocs	Excess Soils Characterization Package ph, ICPMS Metals, BTEX, F1-F4	Salt - EC/SAR	N & I	Sulphylos	Chlorides	1 Resistivity	0			Potentially Hazardous or High Concentration (Y/N)
L						/							
L						/							
L				4.		-	_		_				
L	_			ULS B			-			JAX)	_		
H	4			10.									
H	-		_										
H	+	0			-				-				
-	1			ries.					-				
H	-			-	_								
-													
0		0085	Time							-	l		

Chain of C	ustody Record If this is a Drinking Water sample, please	use Drinking Water Chain o	f Custody Form (potable wat	ter consumed by humans)
Report Inform Company:	EXP	Regulatory Requ		
Contact: Address:	Matthew Zammit 7650 Accession de Scile 100 Ottoma, ON, K2B 8HC	Regulation 153/04 Table Indicate One	Excess Soils R406 Table	Sewer Use Sanitary Segion
Phone; Reports to be sent to:	613-698-1819 Fax:	Res/Park Agriculture	Regulation 558	Prov. Water Qual
1. Email:	Matthew. Zean: + Qexp. con	Soil Texture (Check One) ☐Coarse	ССМЕ	Other
2. Email:		□Fine		//

Project Infor	mation:								
Project:	07T- 22017859-AD								
Site Location:	2666 teath Line Rd, Offang								
Sampled By:	EKP								
AGAT ID #:	PO:								
	Please note: If quotation number is not provided, client will be billed full price for analysis.								

Bill To Same: Yes 👠 No 🗌

Regulatory Requ											
Regulation 153/04	Excess Soils R	406	Sewer Use								
Table Ind/Com	Table Indicate One	2	Region								
□Res/Park □Agriculture	Regulation 558	3	Prov. Water Quality Objectives (PWQO)								
Soil Texture (Check One)	ССМЕ		Other								
Fine			Indicate One								
Is this submission Record of Site Co			Report Guideline on Pertificate of Analysis								
☐ Yes ☐ No			☐ Yes ☐ No								
Sample Matrix Le	gend	DOC	O. Reg 153								

Filtered - Metals, Hg, CrVI,

J								Field	- W - L		F1-F e F4	S C C	3	Disp	Soil	Soil	EC/S		40	0	7		H He
2000	Sample Ident	ification	Date Sampled	Time Sampled	# of Containers	Sample Matrix	Comments/ Special Instructions	Y/N	Metals	Metals	BTEX, F1-F Analyze F4	Total PCRe	VOC	Landfil	Excess Soil SPLP: Me	Excess Soil pH, ICPMS	Salt - E	PH	5-1	7	2		Potentially Ha
BH 1	555	10'-12'	Dec 19	AM PM	1													1	-				
BH G	553	51-71	Dec 14	AN PM														/		-	/		
RH7	558	251-271	De 14	AM PM		7-11										N.		1	/	-	-		
				AM PM												ULV 0							
				AM PM												10.							
				AM PM												10						1	
				AM PM			per and the second		100					12		-							
				AM PM					MINU					0.		щу		=11			. 2		
				AM PM					10,65							95							
				AM PM												-							
				AM PM																	1 10		
Samples Relinquish	ed By (Print Name ar	nd Sign):		Date	Time		Samples Received By (Print Name and Sign):					D	M O	905	5 Time								

Biota **Ground Water**

Paint

Soil Sediment Surface Water

0

S

2023 Kenoo

Document ID: DIV 78-1511,020

of_

Page _

Project Name: Geotechnical Investigation – Proposed Avalon III Elementary School 2666 Tenth Line Road, Ottawa, Ontario CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

Legal Notification

This report was prepared by EXP Services for the account of Conseil des École Catholiques du Centre-Est.

Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. EXP Services Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this project.



Project Name: Geotechnical Investigation – Proposed Avalon III Elementary School 2666 Tenth Line Road, Ottawa, Ontario

CECCE Project 2022AVN115. Project Number: OTT-22017859-A0

March 7, 2023

List of Distribution

Report Distributed To:

Denis Chabot , Project Manager, CECCE, chabod@ecolecatholique.ca

