


THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

OWNER INFORMATION COLLIERS 181 BAY STREET TORONTO, ONTARIO, M5J 2V1 AARON CLODD PHONE: (647) 798-9534 EMAIL: Aaron.Clodd@colliers.com



					SCALE	DESIGN	FOR REVIEW ONL
						ТСВ	
N					DRAWN TCB CHECKED	RGJ	ON
	5.	REVISED PER CITY COMMENTS	FEB 08/24	RGJ			I STORY
	4.	ADDRESS INSERTION ON TITLEBLOCK	DEC 21/23	RGJ			SS SS
	3.	REVISED PER CITY COMMENTS	DEC 05/23	RGJ			
	2.	REVISED PER CITY COMMENTS	NOV 08/23	RGJ			
	1.	ISSUED FOR CITY REVIEW	OCT 02/23	RGJ		No. AND	
	No.	REVISION	DATE	BY		RGJ	



SEED MIX AND APPLICATION

For areas steeper than 3:1, Contractor to apply erosion control blanket. Erosion control blanket to be machine woven mats made from natural wood, coco or cotton fiber, or combination depending on manufacturer, with stitching between two photo-degradable natural organic fiber nettings. Submit products for approval by extended herein.

In addition to the specified seed mixes, all applications are to include a nurse crop as noted. NURSE CROP

Annual Ryegrass Seeding Rate: 15kg/hectare

SEED MIX A

(FOR PARKING ISLANDS AND REINSTATEMENT AREA) CAMPUS GREEN MIX by DLF Pickseed Seeding Rate: 25kg/hectare

SEED MIX B (FOR SWM FACILITY)

RETENTION AREA MIX by DLF Pickseed Seeding Rate: 25kg/hectare


other requirements: a. Plant Beds - (8-32-16), i.e. 8% Nitrogen, 32% Phosphorus, 16% Potash per manufacturer specifications. b. Sod Areas - (8-32-16), i.e. 8% Nitrogen, 32% Phosphorus, 16% Potash at a rate of 350kg/ha.

11. Where applicable, for any plant areas with a mix of species/ cultivars notes, Contractor is to cluster like plants in groups of 3-5 and evenly distribute these in the noted area.

CONSTRUCTION

- 1. All general site information and conditions are compiled from Consultant field notes and plans provided by the Owner and are supplied for information purposes only. It is the responsibility of the Contractor to verify the accuracy of all the information obtained from this plan. Consultant. OPSS 804 applies except as may be amended and 2. Together with all Subcontractors involved, the Contractor is to examine all surfaces or conditions relating to the work, in
 - order to determine the acceptability of such surfaces or conditions for the work to commence. Notify the Contract Administrator in writing of conditions which could be detrimental to installation and do not commence work until instructed by the Contract Administrator. The commencement of work implies Contractor acceptance of the conditions.
 - 3. Contractor to check and report any discrepancies before commencing work. No responsibility is borne by the Consultants for subsurface conditions.
 - 4. Contractor to check and verify all dimensions and quantities on site and report any errors or omissions to the Consultant. Contractor is responsible for all fees arising from the completion of works conveyed by these drawings, details, and specifications.
 - 6. Carry out all construction in accordance with the most current provincial and municipal standards and specifications. 7. Contractor to coordinate all access and protect the public and users of the site with appropriate control fence and supervision throughout the construction period, to the satisfaction of the Consultant.
 - 8. Contract Administrator is to approve access point(s) prior to mobilization. 9. A Contractor flagman is required to direct all deliveries of
 - machinery or materials to the site. 10. Contractor to coordinate and schedule all work with other trades and contractors. Contractor is to notify Contract Administrator of any schedule difficulties.
 - 11. Contractor responsible for the removal and off-site disposal of all materials as required to facilitate new construction. Store all items and materials identified by the Consultant for salvage at a location on site as identified by the Consultant. Excavate and remove from site any contaminated material. Dispose all contaminated material at a licensed landfill facility.
 - 12. Maintain site in a clean and orderly state for the duration of construction; perform all work in accordance with the Occupational Health and Safety Act. Remove all excess materials, packaging, and debris from the site. 13. Contractor is responsible to take all necessary measures to
 - control dust on the project site and to the satisfaction of the Contract Administrator. 14. Contractor is responsible for all layout for construction
 - bars by Owner at the Contractor expense.

for acceptance.



Engineers, Planners & Landscape Architects

Suite 200, 240 Michael Cowpland Drive

Ottawa, Ontario, Canada K2M 1P6

www.novatech-eng.com

Telephone Facsimile Website

CITY OF OTTAWA 600 MARCH ROAD - NOKIA PARKING LOT EXPANSION NOVATECH DRAWING NAME

> LANDSCAPE ENLARGEMENTS AND (613) 254-9643 DETAILS (613) 254-5867

LOCATION

REV/ AWING No. 121334-L2

121334-00

purposes 15. Contractor is to protect all iron bars. Replace any disturbed 16. The Contractor is to notify the Contract Administrator upon completion of the required works to schedule an inspection