



Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.
The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Legend

	PROPOSED WATERMAIN
	PROPOSED VALVE AND VALVE BOX
	PROPOSED HYDRANT
	PROPOSED SANITARY SEWER
	PROPOSED STORM SEWER
	PROPOSED SUBDRAIN CATCH BASIN
	PROPOSED CATCH BASIN
	AREA DRAIN
	THERMAL INSULATION ABOVE STORM AS PER S35
	EXISTING WATERMAIN
	EXISTING VALVE AND VALVE BOX
	EXISTING FIRE HYDRANT
	EXISTING SANITARY SEWER
	EXISTING STORM SEWER
	EXISTING CATCH BASIN
	PROPOSED WATER METER
	PROPOSED REMOTE WATER METER
	EXISTING CABLE
	EXISTING BELL
	EXISTING TELUS
	EXISTING TRAFFIC
	EXISTING HYDRO
	EXISTING STREETLIGHT

NOTES:

1. FINAL SERVICE LATERAL SIZE, LOCATION AND ELEVATION TO BE CONFIRMED BY MECHANICAL CONSULTANT.
2. CONTRACTOR TO LOCATE EXISTING SERVICES AND ANY CONFLICTS WITH EXISTING SERVICES MUST BE REPORTED TO THE ENGINEER PRIOR TO CONTINUING WITH CONSTRUCTION.
3. SITE PLAN PREPARED BY WOODMAN ARCHITECT INC. DATED: DECEMBER 16 2024
4. AS-BUILT INFORMATION FROM STANTEC CONSULTING, DATED DEC 11, 2012
5. FINAL METER AND REMOTE METER LOCATIONS TO BE CONFIRMED BY MECHANICAL CONSULTANT.
6. INTERNAL PLUMBING AND SUMP PUMPS TO BE DESIGNED BY THE MECHANICAL CONSULTANT.
7. UNDERGROUND PARKING STRUCTURE FLOOR DRAINS TO BE CONNECTED TO SANITARY SEWER SERVICE.
8. STORMWATER MANAGEMENT TO BE PROVIDED THROUGH A CISTERN. FINAL CISTERN LOCATION AND ASSOCIATED OVERFLOW TO BE COORDINATED WITH ARCHITECT AND MECHANICAL CONSULTANT.
9. BUILDING CISTERN = 80.0m³ AND RELEASE RATE 10.4L/s PUMP RATE
10. TOTAL PERMITTED RELEASE RATE FROM SITE = 13 L/s
11. TOTAL POST DEVELOPMENT RELEASE RATE FROM SITE= 13 L/s (100 YR)

3	ISSUED FOR CITY REVIEW	JP	D7/SGG	25.04.03
2	ISSUED FOR CITY REVIEW	JP	D7/SGG	25.01.14
1	ISSUED FOR CITY REVIEW	JP	DT	24.07.15

Revision

File Name:	160401885-D81.dwg	JP	SGG/MW	JP	24.07.10
		Dwn.	Chkd.	Dsgn.	YY.MM.DD

Permit-Seal

Client/Project

CAMPANALE HOMES
200 - 1187 Bank Street, Ottawa, ON

609 LONGFIELDS DRIVE
BLOCK 10
Ottawa, ON

Title

SITE SERVICING PLAN

Project No.
160401885

Drawing No.

SSP-1

Scale
1:150

Sheet

3 of 7

Revision

3

DWG# 19161

