

[illegible]

WATERMAIN PROFILE TABLE					
MATERIAL: PVC DR18					
STATION	DESCRIPTION	GRADE ELEVATION	TOP OF PIPE	DEPTH OF COVER	NOTES
A+000.0 (B+000.0 C+000.0)	200x200mm TEE TO CITY OF OTTAWA STANDARDS	122.18	119.78	2.40	–
A+003.0	22.5' HORIZONTAL BEND TO CITY OF OTTAWA STANDARDS	122.13	119.73	2.40	–
A+009.5	–	122.11	119.71	2.40	CROSSING 450 ST U/S 120.89 WM TOP 119.71 – 1180mm CLEARANCE (MIN. 500mm REQ'D)
A+030.5	–	122.14	119.65	2.49	CROSSING 450 ST U/S 120.84 WM TOP 119.65 – 1190mm, CLEARANCE (MIN. 500mm REQ'D)
A+041.0	–	122.03	119.63	2.40	CROSSING 375 ST INV. 120.94 WM TOP 119.63 – 1310mm CLEARANCE (MIN. 500mm REQ'D)
A+056.1	22.5' HORIZONTAL BEND TO CITY OF OTTAWA STANDARDS	122.18	119.64	2.54	–
A+070.4	–	122.36	119.64	2.72	CROSSING 150 SAN INV 120.14 WM TOP 119.64 – 500mm CLEARANCE (MIN. 500mm REQ'D)
A+086.9	–	122.26	119.67	2.59	CROSSING 250 ST INV 121.00 WM TOP 119.67 – 1330mm CLEARANCE (MIN. 500mm REQ'D)
A+093.3	–	122.21	119.69	2.52	CROSSING 450 ST U/S 120.67 WM TOP 119.69 – 360mm CLEARANCE (MIN. 500mm REQ'D)
A+103.3	45' HORIZONTAL BEND TO CITY OF OTTAWA STANDARDS	122.28	119.71	2.57	–
A+111.8	200mm TO 150mm REDUCER TO CITY OF OTTAWA STANDARDS	122.21	119.73	2.48	–
A+113.8	FH-1 – FIRE HYDRANT AVK 2760 NOSTALGIC WITH SEALED WEEP HOLES TO AWWA C-502 & CITY OF OTTAWA STANDARDS	122.13	119.73	2.40	–

REFER TO NOTES, DETAILS & SCHEDULES
ON DRAWINGS C-7, C-9, C-14 & C-15

FFL	FINISHED FLOOR ELEVATION
USF	UNDERSIDE OF FOOTING
---	PROPERTY LINE
CB	CATCH-BASIN
○	STORM MANHOLE
○	CATCH-BASIN/MANHOLE
SAN	SANITARY SEWER
SAN	SANITARY FORCEMAIN
ST	STORM SEWER
W/W	WELL WATER LINE/WATERMAIN
SPL	SPRINGLINE OF PIPE
INV	INVERT OF PIPE
T.O.S	TOP OF SLOPE
B.O.S	BOTTOM OF SLOPE
---	CENTERLINE OF SWALE
==	150mm BARRIER CURB

[illegible]

Water Management - Grading & Drainage - Storm & Sanitary Sewers - Watermaining

Long Point Circle 613-425-8044
Iowa, Ontario d.gray@dbgrayengineering.com

UNBELT RENTALS INC. -
EQUIPMENT MAINTENANCE
FACILITY
CARP, ONTARIO

**WATER
PROFILE TABLE**
(LINE A)

Drawn	D.B.G	
H. Scale	1:250	
V. Scale		
Date	AUG 16-23	
Job No.	22111	

Drawing No. **C-8** of **17**