

C:\Temp\AspPublish\210616124107_TCR Commercial-new.dwg, TCR Commercial, Aug 19, 2025 - 10:27am, tbankle



NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS, WATERMANS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES AND ASSUME ALL LIABILITY FOR DAMAGE TO THEM.

Owner:
Bank & Dun Developments Inc.
c/o Paul Pagliarunga
209 Wicksteed Avenue, Suite 30
Toronto, ON, M4G 0B1
Phone: (416) 335-0090

DISCLAIMER
The elements on this plan illustrate the design intent and general constructability of the proposed landscape which will support the associated development. This is to demonstrate how the canopy cover, urban design, health, and climate change objectives of the Official Plan will be met through tree planting and site design. This drawing is for City review only and is not intended for construction. Final detailed design and construction documentation is to be provided with certified 'Issued for Construction' drawings and specifications prior to construction.

No.	REVISION	DATE	BY
6.	REVISED PER ADJUSTED FIELD SURVEY OF TREES	AUG 19/25	SC
5.	ISSUED FOR TENDER	APR 24/25	SC
4.	ISSUED FOR FINAL APPROVAL	MAR 26/25	SC
3.	REVISED PER CITY COMMENTS	JAN 13/25	SC
2.	ISSUED FOR COMPLETENESS COMMENTS	DEC 6/24	RGJ
1.	ISSUED FOR SITE PLAN APPLICATION	OCT 24/24	RGJ

TREE IMPACT ANALYSIS

Using data collected during the tree inventory and assessment, a tree impact analysis was performed. Determination of each Tree's recommended action (i.e. Retain, Protect, Remove/Conflict) were based on several factors including each tree's current condition and its location in relation to the limits of construction. As outlined in the City's Tree Preservation By-law (2020), a Critical Root Zone (CRZ) was applied around each tree. The CRZ is defined as an area around each tree and is typically established based on the species and size of the tree and are intended to provide a buffer protecting the tree from potential impacts, including root and soil compaction and mechanical damage to above-ground parts. Based on the City's guidelines, the CRZ is established as being 10cm from the trunk of a tree for every 1cm of trunk diameter. The CRZ for multi-stemmed trees was based on the DBH of the largest stem.

Generally, the following guidelines are followed in deriving a tree's recommendation:

- Trees with equal or greater than 40% of its CRZ affected by proposed work activities (**Conflict**) are recommended for **Removal** as there would likely be detrimental impacts to the tree.
- Trees with 0-39% of its CRZ affected by the proposed work activities are recommended for **Protection** as outlined in the Tree Protection Notes on the plan.
- Trees with CRZs that are outside the proposed work areas are recommended for **Retention** with no protection as it is unlikely that there will be negative impacts to the tree.

CITY DETAILS


Related details from City of Ottawa Standard Tender Documents
Volume No. 2 Standard Detail Drawings.

F7: Tree Preservation Protection Fence

No.	Botanical Name	Common Name	DBH (cm)	CRZ (m)	Condition	Owner	Remarks	Recomm.
1	<i>Fraxinus pennsylvanica</i>	Green Ash	33.0	3.30	F	City (ROW)		PROTECT
2	Dead		57.0	5.70	D	City (ROW)		Remove
3	<i>Acer negundo</i>	Manitoba Maple	46.0	4.60	F	City (ROW)	3 trunks, 30" and 45" lean, dead branches (Completely dead on Aug 6, 2025)	Field Conflict
4	<i>Fraxinus pennsylvanica</i>	Green Ash	11.0	1.10	F	Owner	dead branches	Field Conflict
5	<i>Fraxinus pennsylvanica</i>	Green Ash	28.0	2.80	F	Owner		Conflict
6	<i>Malus sp.</i>	Apple	54.0	5.40	VP	Owner	Trunk is wounded and rotten	Remove
7	<i>Acer saccharum</i>	Sugar Maple	37.0	3.70	G	Owner		Conflict
8	<i>Acer saccharum</i>	Sugar Maple	46.0	4.60	G	Neighbour		Conflict
9	<i>Ulmus americana</i>	White Elm	46.0	4.60	G	Owner		Conflict
10	<i>Fraxinus pennsylvanica</i>	Green Ash	39.0	3.90	F	Neighbour	Bend in trunk,	Field Conflict
11	<i>Acer saccharum</i>	Sugar Maple	34.0	3.40	G	Owner		Conflict
12	<i>Ulmus americana</i>	White Elm	28.0	2.80	G	Owner		Conflict
13	<i>Acer saccharum</i>	Sugar Maple	34.0	3.40	G	Owner		Conflict
14	<i>Ulmus americana</i>	White Elm	36.0	3.60	G	Owner		Conflict
15	<i>Acer saccharum</i>	Sugar Maple	63.0	6.30	F	Owner	Twin leader, evidence of internal rot	Remove
16	<i>Acer saccharum</i>	Sugar Maple	27.0	2.70	G	Owner		Conflict
17	<i>Ulmus americana</i>	White Elm	33.0	3.30	G	Owner		Conflict
18	<i>Acer saccharum</i>	Sugar Maple	40.0	4.00	G	Owner		Conflict
19	<i>Picea sp.</i>	Spruce	25.0	2.50	G	Owner		Conflict
20	<i>Picea sp.</i>	Spruce	31.0	3.10	G	Owner		Conflict
21	<i>Picea sp.</i>	Spruce	24.0	2.40	G	Owner		Conflict
22	<i>Picea sp.</i>	Spruce	32.0	3.20	G	Owner		Conflict
23	<i>Picea sp.</i>	Spruce	25.0	2.50	G	Owner		Conflict
24	<i>Picea sp.</i>	Spruce	40.0	4.00	G	Owner		Conflict
25	<i>Acer saccharum</i>	Sugar Maple	84.0	8.40	P	Shared	Dead branches, multi-leader, rot	Remove
26	<i>Acer saccharum</i>	Sugar Maple	30.0	3.00	P	Owner	Black fungus, growing out of stump/wire fence	Remove
27	<i>Picea sp.</i>	Spruce	39.0	3.90	G	Owner		Conflict
28	<i>Pinus banksiana</i>	Jack Pine	30.0	3.00	G	Owner		Conflict
29	Dead		48.0	4.80	D	Owner		Remove
30	Dead		39.0	3.90	D	Neighbour		Remove
31	<i>Acer saccharum</i>	Sugar Maple	140.0	14.00	P	Shared	Internal rot, dead branches	Remove
32	<i>Malus sp.</i>	Apple	43.0	4.30	P	Owner	60" lean	Remove
33	<i>Acer saccharum</i>	Sugar Maple	12.0	1.20	G	Owner		Conflict
34	<i>Ulmus americana</i>	White Elm	18.0	1.80	G	Owner		Conflict
35	<i>Acer saccharum</i>	Sugar Maple	30.0	3.00	G	Owner		Conflict
36	<i>Acer saccharum</i>	Sugar Maple	14.0	1.40	G	Owner		Conflict
37	<i>Acer saccharum</i>	Sugar Maple	10.0	1.00	G	Owner		Conflict
38	<i>Acer saccharum</i>	Sugar Maple	24.0	2.40	G	Owner		Conflict
39	<i>Acer saccharum</i>	Sugar Maple	59.0	5.90	F	Neighbour	"braided" trunks	PROTECT
40	Dead		43.0	4.30	D	Neighbour		Remove
41	<i>Picea sp.</i>	Spruce	28.0	2.80	G	Owner		Conflict
42	<i>Acer saccharum</i>	Sugar Maple	24.0	2.40	G	Owner		Conflict
43	<i>Acer saccharum</i>	Sugar Maple	36.0	3.60	G	Owner		Conflict
44	<i>Acer saccharum</i>	Sugar Maple	53.0	5.30	P	Owner	Twining trunk, rot, split in trunk	Remove
45	<i>Malus sp.</i>	Apple	34.0	3.40	P	Owner	Twin trunk, dead branches, Sever bend	Remove
46	<i>Ulmus americana</i>	White Elm	43.0	4.30	G	Owner		Conflict
47	<i>Acer saccharum</i>	Sugar Maple	78.0	7.80	P	Neighbour	Twining trunk, rot, split	Remove
48	<i>Acer saccharum</i>	Sugar Maple	53.0	5.30	G	Owner		Conflict
49	<i>Acer saccharum</i>	Sugar Maple	39.0	3.90	G	Neighbour		PROTECT
50	<i>Acer saccharum</i>	Sugar Maple	29.0	2.90	G	Neighbour		PROTECT
51	<i>Acer saccharum</i>	Sugar Maple	25.0	2.50	G	Owner		Conflict
52	<i>Acer saccharum</i>	Sugar Maple	32.0	3.20	G	Neighbour		PROTECT
53	<i>Acer saccharum</i>	Sugar Maple	45.0	4.50	G	Neighbour		PROTECT
54	<i>Acer saccharum</i>	Sugar Maple	57.0	5.70	F	Neighbour	Three trunks - 1 dead	Field Conflict
55	<i>Acer saccharum</i>	Sugar Maple	64.0	6.40	G	Owner		Conflict
56	Dead		47.0	4.70	D	Owner		Remove
57	<i>Acer saccharum</i>	Sugar Maple	92.0	9.20	G	Owner		Conflict
58	Dead		52.0	5.20	D	Owner	Fallen Elm	Conflict
59	<i>Acer saccharum</i>	Sugar Maple	99.0	9.90	G	Neighbour		Conflict
60	Dead		76.0	7.60	D	Owner		Remove
61	<i>Acer saccharum</i>	Sugar Maple	40.0	4.00	G	Neighbour		PROTECT
62	<i>Fraxinus pennsylvanica</i>	Green Ash	48.0	4.80	D	Neighbour	Dead	Remove
63	<i>Acer saccharum</i>	Sugar Maple	39.0	3.90	G	Owner		Conflict
64	<i>Acer saccharum</i>	Sugar Maple	37.0	3.70	G	Neighbour		Conflict
65	<i>Ulmus americana</i>	White Elm	56.0	5.60	G	Owner		Conflict
66	<i>Acer saccharum</i>	Sugar Maple	65.0	6.50	P	Neighbour	Twin trunk, split, rot	Conflict
67	<i>Acer saccharum</i>	Sugar Maple	73.0	7.30	G	Owner		Conflict
68	<i>Acer saccharum</i>	Sugar Maple	20.0	2.00	G	Neighbour		PROTECT
69	<i>Acer saccharum</i>	Sugar Maple	34.0	3.40	G	Neighbour		PROTECT
70	<i>Ulmus americana</i>	White Elm	37.0	3.70	F	Owner	bow in trunk,	PROTECT
71	<i>Acer saccharum</i>	Sugar Maple	10.0	1.00	F	Owner	intertwined with dead tree	PROTECT
72	<i>Acer saccharum</i>	Sugar Maple	12.0	1.20	G	Owner		PROTECT
73	<i>Acer saccharum</i>	Sugar Maple	41.0	4.10	P	Owner	Twin trunk, rot, dead tree fallen between two trunks, split trunks	Remove
74	<i>Acer saccharum</i>	Sugar Maple	32.0	3.20	G	Neighbour		Field Conflict
75	<i>Ulmus americana</i>	White Elm	60.0	6.00	F	Neighbour	Minor splitting	Field Conflict
76	<i>Acer saccharum</i>	Sugar Maple	37.0	3.70	G	Owner		Field Conflict
77	<i>Picea sp.</i>	Spruce	10.0	1.00	G	Owner		Conflict

Legend

G Good	Conflict	Remove due to conflict with construction.
F Fair	Remove	Remove due to tree health or invasive status.
P Poor	PROTECT	Protect trees as per contract details and specifications.
VP Very Poor	Field Conflict	Remove due to Field Condition



NORTH

LEGEND

- 3-D1 DETAIL SHEET # - NOVATECH OR CITY DETAIL NUMBER SEE LIST FOR CODE
- PROPERTY LIMIT
- EXISTING TREE TO REMAIN, SYMBOL SIZE REFLECTS CRZ
- EXISTING TREE TO REMOVE, SYMBOL SIZE REFLECTS CRZ
- TREE PROTECTION FENCE
- EXISTING VEGETATION WITH DBH LESS THAN 10cm

CONSTRUCTION


- All general site information and conditions are compiled from Consultant field notes and plans provided by the Owner and are supplied for information purposes only. It is the responsibility of the Contractor to verify the accuracy of all the information obtained from this plan.
- Together with all Subcontractors involved, the Contractor is to examine all surfaces or conditions relating to the work, in order to determine the acceptability of such surfaces or conditions for the work to commence. Notify the Contract Administrator in writing of conditions which could be detrimental to installation and do not commence work until instructed by the Contract Administrator. The commencement of work implies Contractor acceptance of the conditions.
- Contractor to check and report any discrepancies before commencing work. No responsibility is borne by the Consultants for subsurface conditions.
- Contractor to check and verify all dimensions and quantities on site and report any errors or omissions to the Consultant.
- Contractor is responsible for all fees arising from the completion of works conveyed by these drawings, details, and specifications.
- Carry out all construction in accordance with the most current provincial and municipal standards and specifications.
- Contractor to coordinate all access and protect the public and users of the site with appropriate control fence and supervision throughout the construction period, to the satisfaction of the Consultant.
- Contract Administrator is to approve access point(s) prior to mobilization.
- A Contractor flagman is required to direct all deliveries of machinery or materials to the site.
- Contractor to coordinate and schedule all work with other trades and contractors. Contractor is to notify Contract Administrator of any schedule difficulties.
- Contractor responsible for the removal and off-site disposal of all materials as required to facilitate new construction. Store all items and materials identified by the Consultant for salvage at a location on site as identified by the Consultant. Excavate and remove any site any contaminated material. Dispose all contaminated material at a licensed landfill facility.
- Maintain site in a clean and orderly state for the duration of construction; perform all work in accordance with the Occupational Health and Safety Act. Remove all excess materials, packaging, and debris from the site.
- Contractor is responsible to take all necessary measures to control dust on the project site and to the satisfaction of the Contract Administrator.
- Contractor is responsible for all layout for construction purposes.
- Contractor is to protect all iron bars. Replace any disturbed bars by Owner at the Contractor expense.
- The Contractor is to notify the Contract Administrator upon completion of the required works to schedule an inspection for acceptance.

Geraldine Wildman

GERALDINE WILDMAN
MANAGER, DEVELOPMENT REVIEW SOUTH
PLANNING, DEVELOPMENT AND BUILDING SERVICES
DEPARTMENT, CITY OF OTTAWA

APPROVED

By Geraldine Wildman at 2:20 pm, Sep 10, 2025



GENERAL

- Read and interpret this drawing/ drawing set in conjunction with all the contract details and specifications, including related civil, utility, structural, architectural, mechanical, electrical, environmental, geotechnical, and survey information.
- The Contractor is to determine the exact location, size, material, and elevation of all existing utilities prior to commencing construction. Protect and assume responsibility for all existing utilities regardless of being shown on the drawings.
- It is essential to use the plans and details in conjunction with the specifications and notes.
- Do not scale drawings. Work to dimensions only.
- Protect all existing and retained vegetation for the duration of construction according to the contract details and specifications.
- Reinstate all areas and items damaged or disturbed, beyond the Limit of Work, because of construction activities, including but not limited to construction staging areas, haul roads, stockpile areas, etc. to the satisfaction of the Consultant. Unless otherwise noted, Contractor is to reinstate all areas to pre-construction condition or better to the satisfaction of the Contract Administrator.

TREE PROTECTION

Implement the following protection measures for retained trees, both on site and on adjacent sites, prior to any work activity, including tree removal. Maintain tree protection fence in place and in good condition for the duration of site works:

- The Landscape Architect or Certified Arborist is to determine the location of the tree protection fencing and detail it on any associated plans for the site (e.g. tree conservation report, tree disclosure report, etc.).
- Under the guidance of a Landscape Architect or Certified Arborist, erect a fence at the critical root zone (CRZ) of trees. Diameter at breast height (DBH) is the trunk diameter measured at 1.3m height on the tree trunk. The CRZ is calculated as DBH x 10. Refer to the Tree Protection Fence detail.
- Refer to the Tree Protection Plan for fence location. City Forestry Staff are to approve both the plan and the installed fence prior to work commencement.
- Do not place any material or equipment within 2m of the CRZ of any tree, including outhouses.
- Do not attach any signs, notices, or posters to any tree.
- Do not disturb, raise, or lower the existing grade within the CRZ without approval.
- Only tunnel or bore when digging within the CRZ of a tree. Hand work only where required within the CRZ; absolutely no machinery permitted.
- Do not damage the root system, trunk, or branches, or any tree.
- Do not extend hard surface or significantly change landscaping.
- Ensure that exhaust fumes from all equipment are directed away from any tree canopy.
- When trees marked for removal overlap with the CRZ of trees marked for preservation: cut roots at the edge of the CRZ and grind down stumps after tree removals, do not pull out stumps. Ensure there is not root pulling or disturbance of the ground within the CRZ.
- Prior to work taking place, notify and consult the Landscape Architect and City Forestry Staff if roots must be cut. Roots 20mm or larger should be cut at right angles with clean, sharp horticultural tools without tearing, crushing, or pulling. Refer to City of Ottawa Specification S.P. F-8011 Tree Protection, Excavation of Root Zone.
- If damaged or objectionable branches are observed, consult the Landscape Architect, before any work is conducted. Do not prune leaders. Do not prune more than 1/4 of crown.
- Set up a water and fertilizing program, if trees are being affected by site works, to the satisfaction of the Landscape Architect.
- The Landscape Architect is to prescribe mitigation measures if the protected fenced area must be reduced to facilitate construction. Measures may include the placement of plywood, wood chips, or steel plating over the roots for protection. City Forestry Staff are to approve said measures prior to fence movement.
- City of Ottawa By-law: Protects municipal trees and municipal natural areas in the City of Ottawa and trees on private property in the urban area of the City of Ottawa (2020-340).

CITY OF OTTAWA
150 DUN SKIPPER

DRAWING NAME

TREE CONSERVATION PLAN

PROJECT No.

124107

REV

REV # 6

DRAWING No.

124107-TCR

PLANNING DEPARTMENT

#19259

D07-12-24-0134

*Planting bed 11 note: the existing trees retained have access to additional soil volume beyond the north property line.

Area of a circle = $(r \times r) \times \pi$
Canopy coverage per tree calculation: $(\text{average mature spread}/2) \times (\text{average mature spread}/2) \times \pi$

Proposed Planting: Ownership	Total
Private	66
City-Owned	4

CITY DETAILS

Related details from City of Ottawa Standard Tender Documents
Volume No. 2 Standard Detail Drawings.



SC4.	Typical Concrete Sidewalk on Boulevard
SC5	Sidewalk Construction Joints

HYDRO OTTAWA DETAILS

3. TREE PROTECTION

Implement the following protection measures for retained trees, both on site and on adjacent sites, prior to any work activity, including tree removal. Maintain tree protection fence in place and in good condition for the duration of site works:

1. The Landscape Architect or Certified Arborist is to determine the location of the tree protection fencing and detail it on any associated plans for the site (e.g. tree conservation report, tree disclosure report, etc.).
2. Under the guidance of a Landscape Architect or Certified Arborist, erect a fence at the critical root zone (CRZ) of trees. Diameter at breast height (DBH) is the trunk diameter measured at 1.3m height on the tree trunk. The CRZ is calculated as DBH x 10. Refer to the Tree Protection Fence detail.
3. Refer to the Tree Protection Plan for fence location. City Forestry Staff are to approve both the plan and the installed fence prior to work commencement.
4. Do not place any material or equipment within 2m of the CRZ of any tree, including outcousers.
5. Do not attach any signs, notices, or posters to any tree.
6. Do not disturb, raise, or lower the existing grade within the CRZ without approval.
7. Only tunnel or bore when digging within the CRZ of a tree. Hand work only where required within the CRZ; absolutely no machinery permitted.
8. Do not damage the root system, trunk, or branches, or any tree.
9. Do not extend hard surface or significantly change landscaping.
10. Ensure that exhaust fumes from all equipment are directed away from any tree canopy.
11. When trees marked for removal overlap with the CRZ of trees marked for preservation: cut roots at the edge of the CRZ and grind down stumps after tree removals, do not pull out stumps. Ensure there is not root pulling or disturbance of the ground within the CRZ.
12. Prior to taking place, notify and consult with a Landscape Architect and City Forestry Staff if roots must be cut. Roots 20mm or larger should be cut at right angles with clean, sharp horticultural tools without tearing, crushing, or pulling. Refer to City of Ottawa Specification S.P. F-801 Tree Protection, Excavation of Root Zone.
13. If damaged or objectionable branches are observed, consult the Landscape Architect, before any work is conducted. Do not prune leaders. Do not prune more than 1/4 of crown.
14. Set up a water and fertilizing program, if trees are being affected by site works, to the satisfaction of the Landscape Architect.
15. The Landscape Architect is to prescribe mitigation measures if the protected fenced area must be reduced to facilitate construction. Measures may include the placement of plywood, wood chips, or steel plating over the roots for protection. City Forestry Staff are to approve said measures prior to fence movement.
16. City of Ottawa By-law: Protects municipal trees and municipal natural areas in the City of Ottawa and trees on private property in the urban area of the City of Ottawa (2020-340).



- ## GENERAL
1. Read and interpret this drawing/ drawing set in conjunction with all the contract details and specifications, including related civil, utility, structural, architectural, mechanical, electrical, environmental, geotechnical, and survey information.
 2. The Contractor is to determine the exact location, size, material, and elevation of all existing utilities prior to commencing construction. Protect and assume responsibility for all existing utilities regardless of being shown on the contract documents.
 3. It is essential to use the plans and details in conjunction with the specifications and notes.
 4. Do not scale drawings. Work to dimensions only.
 5. Protect all existing and retained vegetation for the duration of construction according to the contract details and specifications.
 6. Reinstatement of all areas and items damaged or disturbed, beyond the Limit of Work, because of construction activities, including but not limited to construction staging areas, haul roads, borrow areas, etc. to the satisfaction of the Consultant. Unless otherwise noted, Contractor is to reinstate all areas to pre-construction condition or better to the satisfaction of the Contract Administrator.
 7. The landscape plans have been developed in accordance with the Geotechnical Investigation (Report # PG7262-2 dated October 1, 2024).

1. Plant material to be No. 1 Grade and is to comply with Canadian Standards for Nursery Stock (latest edition) published by the Canadian Nursery Landscape Association.
2. Use structurally sound plant material with strong fibrous root system free of disease, defects, and injuries. Use trees with straight trunks, well and consistently branched for specimens. Obtain approval from consultant of plant material at source prior to digging. All trees and shrubs to be container grown, potted, W/B or B/B, as indicated on Plant List. Bare root plants are only acceptable for certain species and as approved by the Landscape Architect.
3. Plant material substitutions are not be permitted without the written approval from consultant, with **48 hours notice** prior to shipping plant material.
4. Plant locations are schematic / approximate only. **Contractor is to stake out locations on site for approval by the Landscape Architect prior to installation.**
5. The estimated number of plants indicated in the Planting Plan shall represent the estimated numbers in the Plant List. Contractor to report any discrepancies to the Landscape Architect prior to installation. Contractor will assume full responsibility if the Landscape Architect is not notified. Ensure trees are thoroughly watered following planting. Irrigate plants and ensure adequate moisture until acceptance.
7. In heavy clay or poorly drained soils, set root ball with root collar 75-100mm higher than finished grade.
8. Approved topsoil depths are as follows:
 - a. Sod / Beds - **450mm** minimum depth. Applies to shrubs, perennials, vines, and groundcovers.
 - b. Sod / Seed Areas - **100mm** depth.
 - c. Reforestation - **300mm** depth.
9. Sod to be No. 1 Kentucky Bluegrass Sod grown from minimum mixture of 2 Kentucky Bluegrass cultivars. Quality and source are to comply with Canadian Standards for Nursery Stock, Section 17, (latest edition) published by the Canadian Nursery Landscape Nursery Landscape Association.
10. Seed:
 - a. GREENFIELD SEED MIX BY DLF
 - b. Seeding Rate: 175kg/ha/acre
11. Where applicable, for any plant areas with a mix of species/ cultivars, Contractors to cluster the same species in groups of 3-5 and evenly distribute these in the noted area.

Install products as per manufacturer specifications. Shop drawings required.

PAVERS
Edge of pavers to receive edge restraint.
Blu 60 Smooth by Techo-bloc
Location: Patio on East side of Building C
Pattern: Modular Pattern 01
Colour: Greyed Nickel

RETAINING WALL
 ↳Skyscraper by Techo-bloc
 Location: South side of Building C
 Pattern: Linear
 Colour: Shale Grey

SITE FURNITURE
Fasten all site furnishing to surface with stainless steel anti-vandal anchors.

3200 Bike Racks by Maglin
Product Number: MBR-0200-00005
Mounting Type: Surface Mount
Colour: Powdercoat Saffron Yellow RAL 1017

[illegible]

