

SITE INFORMATION			
PROJECT DESCRIPTION	1 - MULTIFAMILY RESIDENTIAL APARTMENT (6 STOREY)		
TOTAL UNITS	177 UNITS		
ROOF TYPE	GABLE ROOF		
CIVIC ADDRESS	425 CULDAFF RD.		
MUNICIPALITY	CITY OF OTTAWA		
ZONING	GM		
LEGAL DESCRIPTION	PART BLOCK 242, PLAN 4M1687, PART 1 AND 2 ON 4R35406; SUBJECT TO AN EASEMENT IN GROSS OVER PART 4, 4R34110 AS IN OC2424260; CITY OF OTTAWA		
LOT AREA	9,728.16 m ²	2.40 ACRES	0.973 HECTARES
BUILDING AREA	16,335.42	m ²	
DENSITY	74.2 DU/ACRE		
FLOOR SPACE INDEX (FSI)	1.68		

ZONING SUMMARY				
	REQUIRED		PROPOSED	
MAX. BUILDING HEIGHT	18.0 m		18.0 m	
MIN. FRONT YARD S.B.	3.0	m	7.0	m
MIN. REAR YARD S.B.	7.5	m	7.5	m
MIN. INTERIOR SIDE YARD S.B.	3.0	m	3.0	m
MIN. CORNER SIDE YARD S.B.	3.0	m	3.0	m
MIN. LOT AREA	No minimum	m ²	-	m ²
MIN. LOT WIDTH	No minimum	m	-	m

VEHICULAR PARKING				
	REQUIRED	UNITS/AREA	REQUIRED	PROPOSED
APARTMENT - REGULAR	1.2 / UNIT	177	212	177
VISITORS	0.2 / UNIT	177	35	35
TOTAL PARKING STALLS			247	212 *
OTHER PARKING PROVISIONS				
SMALL CAR	MAX 50%		MAX 107	90
ACCESSIBLE TYPE A			3	3
ACCESSIBLE TYPE B			4	4

* SUBJECT TO VARIANCE

BUILDING INFORMATION				
BUILDING	STOREYS	UNIT COUNT	FOOTPRINT	GROSS BUILDING AREA
A	6	177	2722.57 m ²	16,335.42 m ²


UNIT BREAKDOWN		
	BUILDING A	
TOTAL PER BUILDING	177	
		%
STUDIO	24	13%
1 BED / 1 BATH	24	13%
2 BED / 1 BATH	6	3%
2 BED / 2 BATH	87	51%
3 BED / 2 BATH	36	20%
TOTAL	177 UNITS	

LANDSCAPE		
	REQUIRED	PROPOSED
PERCENTAGE OF LOT AREA		35%
m ²		3387 m ²

BICYCLE PARKING				
	RATE	UNITS/AREA	REQUIRED	PROPOSED
APARTMENT BUILDING	0.5 / UNIT	177	89	108
TOTAL BICYCLE			89	108
OTHER BICYCLE PROVISIONS				
MAX BIKE STALLS IN LANDSCAPED AREA	50%	-	45	40
MIN HORIZONTAL BIKE STALL	50%	-	45	48
MIN SECURED BIKE STALLS	25%	-	22	68

AMENITY			
	RATE	REQUIRED	PROPOSED
TOTAL AMENITY SPACE	6m ² / DU	1062 m ²	1331.35 m ²
COMMUNITY AMENITY AREA (50% MIN OF TOTAL)		531 m ²	1331.35 m ²


LEGEND			
---	PROPERTY LINE	×××	CHAINLINK FENCE
- - -	SETBACK LINE		LANDSCAPE AREA
---	BUILDING OUTLINE		CROSSWALK 1.5 X .45 STRIPS
●	FIRE HYDRANT		SIDEWALK LETDOWN
⦿	EV CAPABLE CHARGER		ACCESSIBLE PARKING
---	WOODEN FENCE		BIKE PARKING (NUMBER REPRESENTS COUNT)



PROPERTY BOUNDARY &
TOPOGRAPHIC INFORMATION
PROVIDED BY FARLEY, SMITH &
DENIS SURVEYING LTD.



BROADSTREET
PROPERTIES' LTD.
100 St Anns, Campbell River, B.C.
(T)250.286.8045 (F)250.286.8046
www.broadstreet.ca



PROJECT STATUS:
DEVELOPMENT PERMIT

Revision Schedule		
No.	Description	Revision Date
A	ISSUED FOR D.P.	OCT 15, 2024
B	RE-ISSUED FOR D.P.	FEB 14, 2025
C	RE-ISSUED FOR DP.P. - 1	JUN 02, 2025
D	RE-ISSUED FOR DP.P. - 2	AUG 14, 2025

SEAL: **ABELEARCHITECTURE**
THOMAS C. ABELE ARCHITECT
ONTARIO ASSOCIATION OF ARCHITECTS
THOMAS C. ABELE
LICENCE
9553
2025-08-19

TRADE CONTRACTORS SHALL VERIFY ALL DIMENSIONS AND REPORT ANY DISCREPANCIES OR INCONSISTENCIES TO SEYMOUR PACIFIC DEVELOPMENTS LTD., WITHOUT DELAY, FOR CLARIFICATION AND/OR CONFIRMATION. DO NOT SCALE DRAWINGS. DESIGNS REPRESENTED AND DRAWINGS USED AS INSTRUMENTS OF SERVICE SHALL REMAIN THE COPYRIGHT AND PROPERTY OF SEYMOUR PACIFIC DEVELOPMENTS LTD. ANY REPRODUCTION OR USE FOR ANY PURPOSE OTHER THAN THAT AUTHORIZED BY SEYMOUR PACIFIC DEVELOPMENTS LTD. IS PROHIBITED.

CONTRACTORS SHALL REMAIN FAMILIAR WITH, SHALL REFER TO, AND SHALL PERFORM IN ACCORDANCE WITH LOCAL LAWS, REGULATIONS AND BUILDING CODES. CONTRACTORS SHALL MAINTAIN GOOD INDUSTRY BUILDING AND SAFETY PRACTICES CONSISTENT WITH THE CONTRACT INTENT AND THE REQUIREMENTS OF JURISDICTIONAL AUTHORITIES.

ADDITIONAL CLAIMS AND COSTS RELATED TO NON-MATERIAL CHANGES WILL NOT BE ACCEPTED BY SEYMOUR PACIFIC DEVELOPMENTS LTD. NON-MATERIAL CHANGES ARE DEEMED TO BE PLAN CHANGES OR SPECIFICATION ADJUSTMENTS THAT DO NOT SUBSTANTIALLY AFFECT THE VALUE, TIME, COST AND QUALITY OF CONSTRUCTION.

CONTRACTORS SHALL MAKE EVERY REASONABLE EFFORT TO MAINTAIN SCHEDULE TARGETS AND PROVIDE GOOD EFFICIENCY, PROGRESS, WORKMANSHIP AND QUALITY TOWARD DEFICIENCY-FREE RESULTS.

PROJECT NAME:
PALLADIUM TERRACE

PROJECT NUMBER:
VP 2402

ADDRESS:
425 CULDAFF RD
OTTAWA, ON

DRAWING TITLE:
SITE PLAN

DRAWN BY: NG
CHECKED BY: TH
DATE: AUG 14, 2025
SCALE: As indicated
DRAWING #:

REV #:

A1.00

D