



No.	Botanical Name	Common Name	DBH (cm)	CRZ (m)	Condition	Owner	Remarks	Recomm.
70	Ulmus americana	White Elm	37.0	3.70	F	Owner	bow in trunk,	PROTECT
71	Acer saccharum	Sugar Maple	10.0	1.00	F	Owner	intertwined with dead tree	PROTECT
72	Acer saccharum	Sugar Maple	12.0	1.20	G	Owner		PROTECT
73	Acer saccharum	Sugar Maple	41.0	4.10	Р	Owner	Twin trunk, rot, dead tree fallen between two trunks, split trunks	Remove
74	Acer saccharum	Sugar Maple	32.0	3.20	G	Neighbour		Conflict
75	Ulmus americana	White Elm	60.0	6.00	F	Neighbour	Minor splitting	Conflict
76	Acer saccharum	Sugar Maple	37.0	3.70	G	Owner		Conflict
78	Acer saccharum	Sugar Maple	27.0	2.70	G	Owner		Conflict
79	Thuja sp.	Cedar	20.0	2.00	G	Owner		Conflict
80	Quercus rubra	Red Oak	10.0	1.00	G	City		PROTECT

Legen	Legend							
G	Good	Conflict	Remove du	ue to conflic	t with const	truction.		
F	Fair	Remove	Remove du	ue to tree he	elath or inva	asive status.		
Р	Poor	PROTECT	Protect tre	ees as per d	ontract de	tails and sp	ecifications	
VP	Very Poor							






LEGEND

3-D1

DETAIL SHEET # NOVATECH OR CITY

EG. 14 12 ETC DETAIL NUMBER SEE LIST EG. L1, L2, ETC. FOR CODE



EXISTING TREE TO REMAIN, SYMBOL SIZE REFLECTS CRZ



SYMBOL SIZE REFLECTS CRZ TREE PROTECTION FENCE



EXISTING VEGETATION WITH DBH LESS THAN 10cm

CONSTRUCTION

- 1. All general site information and conditions are compiled from Implement the following protection measures for retained trees, are supplied for information purposes only. It is the responsibility of the Contractor to verify the accuracy of all the in good condition for the duration of site works: information obtained from this plan.
- 2. Together with all Subcontractors involved, the Contractor is to 1. examine all surfaces or conditions relating to the work, in order to determine the acceptability of such surfaces or conditions for the work to commence. Notify the Contract Administrator in writing of conditions which could be detrimental to installation and do not commence work until instructed by the Contract Administrator. The commencement of work implies Contractor acceptance of the
- 3. Contractor to check and report any discrepancies before commencing work. No responsibility is borne by the Consultants for subsurface conditions.
- 4. Contractor to check and verify all dimensions and quantities
- on site and report any errors or omissions to the Consultant. 5. Contractor is responsible for all fees arising from the completion of works conveyed by these drawings, details, and 5. specifications.
- 6. Carry out all construction in accordance with the most current provincial and municipal standards and specifications.
- users of the site with appropriate control fence and
- supervision throughout the construction period, to the
- 8. Contract Administrator is to approve access point(s) prior to 9. A Contractor flagman is required to direct all deliveries of

satisfaction of the Consultant.

- machinery or materials to the site.
- 10. Contractor to coordinate and schedule all work with other trades and contractors. Contractor is to notify Contract Administrator of any schedule difficulties.
- 11. Contractor responsible for the removal and off-site disposal of all materials as required to facilitate new construction. Store all items and materials identified by the Consultant for salvage at a location on site as identified by the Consultant. Excavate and remove from site any contaminated material. Dispose all
- contaminated material at a licensed landfill facility. 12. Maintain site in a clean and orderly state for the duration of construction; perform all work in accordance with the Occupational Health and Safety Act. Remove all excess
- materials, packaging, and debris from the site. 13. Contractor is responsible to take all necessary measures to control dust on the project site and to the satisfaction of the Contract Administrator.
- 14. Contractor is responsible for all layout for construction
- 15. Contractor is to protect all iron bars. Replace any disturbed bars by Owner at the Contractor expense.
- 16. The Contractor is to notify the Contract Administrator upon completion of the required works to schedule an inspection for acceptance.

Related details from City of Ottawa Standard Tender Documents Volume No. 2 Standard Detail Drawings.

GENERAL

- 1. Read and interpret this drawing/ drawing set in conjunction with all the contract details and specifications, including related civil, utility, structural, architectural, mechanical, electrical, environmental, geotechnical, and survey information.
- 2. The Contractor is to determine the exact location, size, material, and elevation of all existing utilities prior to commencing construction. Protect and assume responsibility for all existing utilities regardless of being shown on the drawings.
- 3. It is essential to use the plans and details in conjunction with the specifications and notes.
- 4. Do not scale drawings. Work to dimensions only. 5. Protect all existing and retained vegetation for the duration of construction according to the contract details and
- 6. Reinstate all areas and items damaged or disturbed, beyond the Limit of Work, because of construction activities, including but not limited to construction staging areas, haul roads, stockpile areas, etc. to the satisfaction of the Consultant. Unless otherwise noted, Contractor is to reinstate all areas to pre-construction condition or better to the satisfaction of the Contract Administrator.

TREE PROTECTION

specifications.

Consultant field notes and plans provided by the Owner and both on site and on adjacent sites, prior to any work activity, including tree removal. Maintain tree protection fence in place and

- The Landscape Architect or Certified Arborist is to determine the location of the tree protection fencing and detail it on any associated plans for the site (e.g. tree conservation report, tree disclosure report, etc.).
- 2. Under the guidance of a Landscape Architect or Certified Arborist, erect a fence at the critical root zone (CRZ) of trees. Diameter at breast height (DBH) is the trunk diameter measured at 1.3m height on the tree trunk. The CRZ is calculated as DBH x 10. Refer to the Tree Protection Fence
- 3. Refer to the Tree Protection Plan for fence location. City Forestry Staff are to approve both the plan and the installed fence prior to work commencement.
- Do not place any material or equipment within 2m of the CRZ of any tree, including outhouses.
- Do not attach any signs, notices, or posters to any tree. 6. Do not disturb, raise, or lower the existing grade within the CRZ without approval.
- 7. Only tunnel or bore when digging within the CRZ of a tree. machinery permitted. 8. Do not damage the root system, trunk, or branches, or any
- 9. Do not extend hard surface or significantly change
 - landscaping.
- 10. Ensure that exhaust fumes from all equipment are directed away from any tree canopy.
- When trees marked for removal overlap with the CRZ of trees marked for preservation: cut roots at the edge of the CRZ and grind down stumps after tree removals, do not pull out stumps. Ensure there is not root pulling or disturbance of the ground within the CRZ.
- Prior to work taking place, notify and consult the Landscape Architect and City Forestry Staff if roots must be cut. Roots 20mm or larger should be cut at right angles with clean, sharp horticultural tools without tearing, crushing, or pulling. Refer to City of Ottawa Specification S.P. F-8011 Tree Protection. Excavation of Root Zone.
- 13. If damaged or objectionable branches are observed, consult the Landscape Architect, before any work is conducted. Do not prune leaders. Do not prune more than 1/4 of crown. Set up a water and fertilizing program, if trees are being affected by site works, to the satisfaction of the Landscape
- 15. The Landscape Architect is to prescribe mitigation measures if the protected fenced area must be reduced to facilitate construction. Measures may include the placement of plywood, wood chips, or steel plating over the roots for
- protection. City Forestry Staff are to approve said measures prior to fence movement 16. City of Ottawa By-law: Protects municipal trees and municipal natural areas in the City of Ottawa and trees on private

property in the urban area of the City of Ottawa (2020-340).

CITY DETAILS

F7. Tree Preservation Protection Fence

www.novatech-eng.com

(613) 254-5867

CITY OF OTTAWA 150 DUN SKIPPER DRIVE - RESIDENTIAL DEVELOPMENT

DRAWING NAME TREE CONSERVATION PLAN

124107-R-TCR

THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER general constructability of the proposed landscape which UNDERGROUND AND OVERGROUND UTILITIES AND will support the associated development. This is to STRUCTURES IS NOT NECESSARILY SHOWN ON Bank & Dun Developments Inc, demonstrate how the canopy cover, urban design, health THE CONTRACT DRAWINGS, AND WHERE SHOWN, c/o Paul Paglialunga 209 Wicksteed Avenue, Suite 30 and climate change objectives of the Official Plan will be THE ACCURACY OF THE POSITION OF SUCH met through tree planting and site design. This drawing is Toronto, ON, M4G 0B1 UTILITIES AND STRUCTURES IS NOT GUARANTEED. Phone: (416) 335-0090 for City review only and is not intended for construction. BEFORE STARTING WORK, DETERMINE THE EXACT REVISED PER CITY COMMENTS Final detailed design and construction documentation is to LOCATION OF ALL SUCH UTILITIES AND be provided with certified 'Issued for Construction' ISSUED FOR SPC APPLICATION STRUCTURES AND ASSUME ALL LIABILITY FOR drawings and specifications prior to construction. DAMAGE TO THEM. REVISION


FOR REVIEW ONLY SCALE TCB 1:400 CAIA TCB APR 11/25 JAN 17/25

DATE

APR 11, 2025/6 Telephone Facsimile

Suite 200, 240 Michael Cowpland Drive Ottawa, Ontario, Canada K2M 1P6 (613) 254-9643

Website



SOIL AVAILABILITY CALCULATIONS

Planting bed no.	Available Soil Area (sq m)	Available Soil Volume (cu m)		No. of trees proposed			Total No. of trees	Min. required Soil volume total (cu m)
			Small/ Column (25m³)	Medium (30m³)	Large (35m³)	Evergreen (30m³)		
Planting bed 1	1185.2	1,185.2	3		7	5	15	395.0
Planting bed 2	94.9	94.9			1		1	35.0
Planting bed 3	113.6	113.6			2		2	60.0
Planting bed 4	198.4	198.4			3		3	90.0
Planting bed 5	25.0	25.0	1				1	25.0
Planting bed 6	55.4	55.4		2			2	50.0
Planting bed 7	56.4	56.4			1		1	35.0
Planting bed 8	17.4	17.4					0	0.0
Planting bed 9	130.4	130.4		1	1		2	55.0
Planting bed 10	25.8	25.8		1			1	30.0
Planting bed 11	144.5	144.5			1		1	35.0
Planting bed 12	37.2	37.2			1		1	35.0
Planting bed 13	81.0	81.0			1		1	35.0
Planting bed 14	17.2	17.2					0	0.0
Planting bed 15	28.6	28.6		1			1	30.0
Planting bed 16	28.4	28.4			1		1	35.0
Planting bed 17	743.4	743.4			6	8	14	380.0
Planting bed 18	177.4	177.4	2	2			4	90.0
Note: For all plantin	g beds proposed	l, the available so	oil depth is	considered t	o be 1m.			

)					
Note: For all planting	hade proposad	l +ba availabla c	ail danth is e	oncidarad t	aha 1m
inote: For all blanting	. Deus brobosed	i. the avallable si	on aebin is i	onsidered i	.o be ini.
		,			

SIZE COND SPACING

50mm Cal WB As Shown Nativar

50mm Cal WB As Shown Nativar

50mm Cal W/B As Shown Native

50mm Cal WB As Shown Nativar

200cm Ht | W/B | As Shown | Native

200cm Ht WB As Shown Native

200cm Ht WB As Shown Native

50mm Cal WB As Shown Nativar

50mm Cal W/B As Shown Nativar

50mm Cal WB As Shown Nativar

50mm Cal WB As Shown Native

50mm Cal WB As Shown Nativar

50mm Cal WB As Shown Nativar

50mm Cal WB As Shown Nativar

3g PT As Shown Nativar

30cm Spr PT As Show n Nativar

80cm3g As Show n Nativar

175cm Ht PT As Shown Nativar

60cm Ht PT 200cm O.C Native

2g PT As Show n Nativar

60cm Ht PT 100cm O.C Nativar

60cm Ht PT As Show n Nativar

60cm Ht PT As Shown Native

60cm Ht PT As Shown Native

9cm PT 45cm O.C Nativar

3g PT 60cm O.C Native

1g PT 50cm O.C Non-native

1g PT 50cm O.C Native

1g PT 60cm O.C Native

1g PT 50cm O.C Native

PT 40cm O.C Nativar

1g PT 50cm O.C

60cm Ht PT 140cm O.C Nativar

Nativar


50cm Ht PT 80cm O.C


50mm Cal WB As Shown

ESTIMATED CANOTI COVERAGE AT MIXTORITI								
SIZE OF TREE	AVERAGE MATURE	CANOPY COVERAGE PER	QUANTITY OF	TOTAL CANOPY COVERAGE (m2)				
SIZE OF TREE	SPREAD	TREE (m2)	TREES					
Deciduous - Small/Column (<7.5m tall)	7m	38	5	190				
Deciduous - Medium (7.5-14m tall)	10m	79	5	393				
Deciduous - Large (14m+ tall)	15m	177	27	4771				
Coniferous	5m	20	13	255				
PROPOSED TOTAL CANOPY COVERAGE (m2):			5609				
TOTAL SITE AREA (m2):				10,010				
EST. CANOPY COVERAGE (%):				56%				
Area of a circle = $(r \times r) \times \pi$								
, , , , , , , , , , , , , , , , , , ,								

ESTIMATED CANOPY COVERAGE AT MATURITY

Canopy coverage per tree calculation: (average mature spread/2) x (average mature spread/2) x π





LEGEND

DETAIL SHEET # NOVATECH OR CITY

FG. 14.1.2 FTC — DETAIL NUMBER SEE LIST 3-D1 EG. L<u>1</u>, L<u>2</u>, ETC.

PROPERTY LIMIT

PROPOSED CONCRETE

PAVERS TYPE 1

PAVERS TYPE 2

PROPOSED DECIDUOUS TREE PROPOSED CONIFEROUS TREE

RIVER STONE

PROPOSED SHRUBS

PERENNIALS

- SPECIES (SEE PLANT LIST)

ORNAMENTAL GRASSES

RETAINING WALLS

LANDSCAPE PLANTER WALLS

PROPOSED WOOD PRIVACY FENCE

-x -x - PROPOSED CHAIN LINK FENCE

SEE 124107-R-TCR

TREE PROTECTION FENCE FOR COMMERCIAL DEVELOPMENT (BY OTHERS)

BIKE RACKS, SEE DETAIL D6 PICNIC BENCH

SEATING

RAISED PLANTERS

3. Growing medium to be:

c. 1 part peat moss

a. 6 parts good quality topsoil

b. 2 parts well rotted horse or cow manure

d. 1 lb. bonemeal per cubic yard soil

BBQ ON CONCRETE PAD

BUILDING LINE

OVERHANG

LIMIT OF UNDERGROUND GARAGE

growing medium, at the bottom, to eliminate settlement.

lifts. Tamp and water each lift to eliminate air pockets or

4. Cover top of the planter surface with 75mm of shredded bark

2. Backfill around the root ball with growing medium in 150mm

PRODUCT INFORMATION

nstall products as per manufacturer specifications. Shop drawings 1. Set plants in raised planters on a bed of heavily compacted

40cm Ht PT As Shown Non-native PAVER TYPE 1 Edge of pavers to receive edge restraint • Blu 60 Smooth by Techo-bloc Location: Patio Pavers Size: 60mm HD² - All sizes

> PAVER TYPE 2 PT 30cm O.C Non-native Edge of pavers to receive edge restraint. • Westmount by Techo-Bloc Location: Walkway Pavers

> > Pattern:Linear Pattern

Colour: Shale Grey

Pattern: Modular Pattern 01

Colour: Greyed Nickel

PLANTER WALLS - TBD

1g PT 90cm O.C Nativar SITE FURNITURE Fasten all site furnishing to surface with stainless steel anti-vandal anchors. • 200 Bike Racks by Maglin

Product Number: MBR-0200-00005 Mounting Type: Surface Mount Colour: Powdercoat Saffron Yellow RAL1017

GENERAL

- Read and interpret this drawing/ drawing set in conjunction with all the contract details and specifications, including related civil, utility, structural, architectural, mechanical, electrical, environmental, geotechnical, and survey information
- 2. The Contractor is to determine the exact location, size, material, and elevation of all existing utilities prior to commencing construction. Protect and assume responsibility for all existing utilities regardless of being shown on the
- 3. It is essential to use the plans and details in conjunction with the specifications and notes.
- 4. Do not scale drawings. Work to dimensions only. 5. Protect all existing and retained vegetation for the duration of construction according to the contract details and
- 6. Reinstate all areas and items damaged or disturbed, beyond the Limit of Work, because of construction activities, including but not limited to construction staging areas, haul roads, stockpile areas, etc. to the satisfaction of the Consultant. Unless otherwise noted, Contractor is to reinstate all areas to pre-construction condition or better to the satisfaction of the Contract Administrator.

PLANTING

drawings.

specifications.

- 1. Plant material to be No. 1 Grade and is to comply with Canadian Standards for Nursery Stock (latest edition) published by the Canadian Nursery Landscape Association. 2. Use structurally sound plant material with strong fibrous root system free of disease, defects, and injuries. Use trees with
- straight trunks, well and characteristically branched for species. Obtain approval from consultant of plant material at source prior to digging. All trees and shrubs to be container grown, potted, W/B or B/B, as indicated on Plant List. Bare root plants are only acceptable for certain species and as approved by the Landscape Architect. 3. Plant material substitutions are not be permitted without the
- written approval from the Consultant, with 48 hours notice, prior to shipping plant material.
- 4. Plant locations are schematic / approximate only. Contractor is to stake out locations on site for approval by the
- Landscape Architect prior to installation. 5. The illustrated number of plants shown in the Planting Plan supersedes the estimated number in the Plant List. Contractor to report any discrepancies to the Landscape Architect prior to installation. Contractor will assume full
- responsibility if the Landscape Architect is not notified. 6. Ensure trees are thoroughly watered following planting. Monitor material and ensure adequate moisture until
- 7. In heavy clay or poorly drained soils, set root ball with root collar 75-100mm higher than finished grade. Approved topsoil depths are as follows:
- Plant Beds **450mm** continuous depth. Applies to shrubs, perennials, vines, and groundcovers.
- b. Sod/ Seed Areas 100mm depth. c. Reforestation - 300mm depth.
- 9. Sod to be No. 1 Kentucky Bluegrass Sod grown from minimum mixture of 3 Kentucky Bluegrass cultivars. Quality and source are to comply with Canadian Standards for Nursery Stock. Section 17, (latest edition) published by the
- 10. Apply the following mineral fertilizer unless soil tests show
- other requirements: a. Plant Beds - (8-32-16), i.e. 8% Nitrogen, 32% Phosphorus, 16% Potash per manufacturer specifications.

Canadian Nursery Landscape Nursery Landscape

b. Sod Areas - (8-32-16), i.e. 8% Nitrogen, 32% Phosphorus, 16% Potash at a rate of 350kg/ha. 12. Where applicable, for any plant areas with a mix of species/ cultivars notes. Contractor is to cluster like plants in groups of

3-5 and evenly distribute these in the noted area. **CITY DETAILS**

Related details from City of Ottawa Standard Tender Documents Volume No. 2 Standard Detail Drawings.

Typical Concrete Sidewalk in Boulevard Sidewalk Construction Joints

NOVATECH DETAILS

Found on Sheet L2.

- D1. Standard Deciduous Tree Planting D2. Standard Coniferous Tree Planting D3. Shrub and Perennial Planting
- D4. Shrub and Perennial Planting with Granular
- D5. Shrub and Perennial Planting on slab
- D6. Wood Screen Detail
- D7. Bike Layout
- D8. River stone Detail
- D9. Paving Detail

PRELIMINARY

FOR REVIEW ONLY SCALE DISCLAIMER: Owner: Architect TCE THE POSITION OF ALL POLE LINES, CONDUITS, The elements on this plan illustrate the design inten Bank & Dun Developments Inc, PMA Architects WATERMAINS, SEWERS AND OTHER c/o Paul Paglialunga 209 Wicksteed Avenue, Suite 30 and general constructability of the proposed 3070 Chemin Des Quatre-Bourgeois Quebec, QC G1W 2K4 landscape which will support the associated UNDERGROUND AND OVERGROUND UTILITIES AND 1:400 Toronto, ON, M4G 0B1 Phone: (416) 335-0090 STRUCTURES IS NOT NECESSARILY SHOWN ON

City-Owned

THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND 240 Michael Cowpland Drive, STRUCTURES AND ASSUME ALL LIABILITY FOR Ottawa, ON, K2M 1P6 DAMAGE TO THEM.

Civil: Novetech Engineers, Planners & Landscape Architects,

Phone: 613.254.9643

Phone: 418.651.8954

Surveyor:

J.D. Barnes Ltd.

62 Steacie Drive, Suite 103

Kanata, ON K2K 2A9

Phone: 613.731.7244

3-D1

development. This is to demonstrate how the canopy cover, urban design, health, and climate change objectives of the Official Plan will be met through tree planting and site design. This drawing is for City review only and is not intended for construction. Final detailed design and construction documentation is to be provided with certified 'Issued for Construction' drawings and specifications prior to construction.

TCB REVISED AS PER CITY COMMENTS APR 11/25 1:400 ISSUED FOR SPC APPLICATION JAN 17/25 ISSUED FOR COORDINATION JAN 13/25 REVISION DATE

41





Telephone

Facsimile

Website

(613) 254-9643


(613) 254-5867


www.novatech-eng.com


CITY OF OTTAWA 150 DUN SKIPPER DRIVE - RESIDENTIAL DEVELOPMENT


DRAWING NAME LANDSCAPE PLAN REV # 3

124107-R-L²









EXCAVATE CONTINUOUS PLANTING

- PRUNE BRANCHES TO CAREFULLY

WHILE RETAINING NATURAL FORM

OF PLANT. IF CONIFEROUS, DO NOT

- 75mm THICK LAYER OF RIVERSTONE

CUT AND REMOVE BURLAP AND WIRE

BASKET FROM TOP 1/3 OF ROOT BALL,

INTEGRITY. IF POTTED, REMOVE POT

- SCARIFY PIT BEFORE PLACING SOIL.

INSTALL FILTER CLOTH BELOW SOIL

IF PLANTING ON CLEAR STONE

* BACKFILL PLANTING SOIL IN 150mm

LIFTS. TAMP EACH LIFT TO ELIMINATE AIR POCKETS AND SETTLEMENT.

- UNDISTURBED SUBGRADE

- PLANTING SOIL AS PER SPECIFICATION

AROUND EXCAVATED

100mm RAISED SAUCER

A CLEAN DEFINED EDGE

TE AREA. MULCH IS TO HAVE

DO NOT DISTURB THE ROOT BALL

(TERRAFIX 270r OR APPROVED

AND INTERFERING BRANCHES,


REMOVE DEAD, BROKEN, DAMAGED,


BED AS SHOWN ON PLAN.


DAMAGE OR CUT LEADER

MULCH OVER GEOTEXTILE

FNTIRFI Y







THE POSITION OF ALL POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED. BEFORE STARTING WORK, DETERMINE THE EXACT LOCATION OF ALL SUCH UTILITIES AND

STRUCTURES AND ASSUME ALL LIABILITY FOR

DAMAGE TO THEM.

Owner: Bank & Dun Developments Inc, c/o Paul Paglialunga 209 Wicksteed Avenue, Suite 30 Toronto, ON, M4G 0B1 Phone: (416) 335-0090

DISCLAIMER: The elements on this plan illustrate the design intent and general constructability of the proposed landscape which will support the associated development. This is to demonstrate how the canopy cover, urban design, health and climate change objectives of the Official Plan will be met through tree planting and site design. This drawing is for City review only and is not intended for construction. Final detailed design and construction documentation is to be provided with certified 'Issued for Construction' drawings and specifications prior to construction.

SCALE TCB TCB REVISED AS PER CITY COMMENTS APR 11/25 ISSUED FOR SPC APPLICATION JAN 17/25 ISSUED FOR COORDINATION JAN 13/25 DATE REVISION

FOR REVIEW ONLY CALA APR 11, 2025

Suite 200, 240 Michael Cowpland Drive Ottawa, Ontario, Canada K2M 1P6 (613) 254-9643 Telephone (613) 254-5867 Facsimile

Website

www.novatech-eng.com

CITY OF OTTAWA 150 DUN SKIPPER DRIVE - RESIDENTIAL DEVELOPMENT

DRAWING NAME LANDSCAPE DETAILS

124107 REV # 3 124107-R-L2