



- 1. CONTRACTOR TO VERIFY LOCATION OF ALL UTILITIES PRIOR TO EXCAVATION.**
- 2. LOCATION OF ALL PLANT MATERIAL TO BE STAKED BY THE CONTRACTOR AND VERIFIED IN THE FIELD BY THE PROJECT MANAGER PRIOR TO THE EXCAVATION OF TREE PITS AND PLANTING BEDS.**
- 3. ALL PLANT MATERIAL SHALL BE NURSERY GROWN STOCK UNLESS OTHERWISE NOTED.**
- 4. DECIDUOUS TREES TO HAVE A MINIMUM 1800mm CLEAR STEM ABOVE GRADE WITH THE EXCEPTION OF POCKET FOREST SAPLINGS.**
- 5. ALL PLANT MATERIAL SHALL BE WARRANTIED FOR TWO YEARS FROM THE DATE OF PERFORMANCE ACCEPTANCE AS DETERMINED BY THE PROJECT MANAGER.**
- 6. ANY PROPOSED PLANT MATERIAL SUBSTITUTIONS SHALL BE MADE WITH PLANTS OF EQUIVALENT OVERALL FORM, HEIGHT, HABIT, FLOWER, LEAF, COLOUR AND CULTURE AND ONLY AFTER WRITTEN APPROVAL FROM THE PROJECT MANAGER.**
- 7. ALL SEEDED AREAS TO RECEIVE A MINIMUM 100 mm OF IMPORTED TOPSOIL.**
- 8. REFER TO ENGINEERING DRAWINGS FOR ALL HARDSCAPE AND SERVICING.**
- 9. TREES TO BE SPACED A MINIMUM OF 1500mm FROM CURBS AND RETAINING WALLS 2000mm FROM LIGHT STANDARDS.**

