



June 17, 2025

PH4905-LET.02.REV.02.

Ottawa Sivan Temple
2104 Roger Stevens Drive
Ottawa, Ontario
K0A 2T0

Attention: **Kula Sellathurai**

Subject: **Hydrogeological Assessment and Terrain Analysis**
Proposed Temple Redevelopment
2104 Roger Stevens Drive Ottawa, Ontario

Consulting Engineers

9 Auriga Drive
Ottawa, Ontario
K2E 7T9
Tel: (613) 226-7381

Geotechnical Engineering
Environmental Engineering
Hydrogeology
Materials Testing
Building Science
Rural Development Design
Retaining Wall Design
Noise and Vibration Studies

patersongroup.ca

INTRODUCTION

Further to your request, Paterson Group (Paterson) has conducted a Hydrogeological Assessment and Terrain Analysis in support of a Site Plan Control Application for the proposed redevelopment of the temple located at 2104 Roger Stevens Drive in Ottawa, Ontario. Please refer to the Key Plan (attached) for the approximate site location. The subject site refers to the parcel at 2104 Roger Steven Drive.

The purpose of this work has been to determine the suitability of the water supply aquifer underlying the site to support the Site Plan Application for the proposed redevelopment.

The proposed Site Plan Application is for the construction of a new temple and priest residence that is replacing the currently existing temple. Details of the proposed temple redevelopment can be found in the attached P² Concepts drawing SP01 - Site Plan – dated May 13, 2025.

The Subject Site consists of a 2.04 hectares (ha) lot and is currently occupied by the existing temple with associated private infrastructure. The ground surface is generally flat at the location of the temple and is sloped to the south behind the temple and towards the rear of the property. The surficial groundwater flow is anticipated to be towards the southeast, while general groundwater flow is anticipated to be to the east towards an unnamed tributary which eventually drains into Stevens Creek.



The Subject Site is situated in a rural area which is serviced by private water supplies and private on-site septic fields. The site is bordered to the north by Roger Stevens Drive, followed by a residential dwelling and agricultural land, to the west by residential dwellings, and to the south and east by agricultural land.

Description of Subject Site

The subject site is approximately 2.04 ha in size and is currently occupied by a one-storey commercial building; Ottawa Sivan Temple. The Site Plan application is for a proposed redevelopment. The proposed redevelopment includes the construction of a new temple and a priest residence. Please refer to Figure-1 Key Plan and P² Concepts Site Plan Drawing SP01 dated May 13, 2025, attached, for the proposed site location and site layout.

The subject site is currently serviced by an onsite sewage system and a private drilled well. A new drilled well was installed onsite to support the redevelopment. A new sewage system is proposed to be located on the western side, behind the priest residence. D.B Gray Engineering Inc. (hereby referred to as DBG Engineering) has designed a new sewage system due to the nitrate reduction required as part of the Nitrate Impact Assessment (NIA). A septic flow calculation was completed by DBG Engineering and resulted in a total daily water demand calculation of 7,250 L/day. Please refer to DBG Engineering Sewage System design, attached, for full details.

The existing well is currently servicing the existing building, however, a new drilled well, hereafter referred to as Test Well 1 (TW1) was installed on September 9, 2024 and is intended to service the proposed temple and priest residence following the completion of the proposed redevelopment. The existing well will be decommissioned in accordance with O.Reg.903 once it is no longer required.

The suitability of the aquifer to supply the subject site was assessed using the methodology provided in City of Ottawa Hydrogeological and Terrain Analysis Guidelines (HTAG).

Karst Mapping

Available Karst mapping (OGS GRS005) was reviewed as part of this assessment. The available mapping does not indicate the presence of any inferred or potential karstic features. Furthermore, no indication of karstic features were observed during the site visits completed by Paterson personnel.

Mississippi-Rideau Source Protection Plan

The Mississippi-Rideau Source Protection Plan (MRSP) provides guidance as to which policies apply to a given property, municipality or specific activity and if there are specific designations that apply to the area. The subject site has not been designated as any of the four groundwater related vulnerable areas identified within the Clean Water Act



(2006). The four vulnerable areas consist of Significant Groundwater Recharge Area (SGRA), Highly Vulnerable Aquifer (HVA), Intake Protection Zone (IPZ) and Wellhead Protection Area (WHPA).

As the subject site has not been designated as any of the four groundwater related vulnerable areas, there is no prohibition of land uses on the subject site based upon its existing or proposed usage.

HYDROGEOLOGICAL ASSESSMENT

The purpose of this work has been to determine the suitability of the water supply aquifer underlying the site to support the Site Plan Application for the proposed temple redevelopment for potable supply usage. Specifically, the intent of this report is to review the availability of a safe and reliable water supply having sufficient quantity and quality to provide potable water for the proposed redevelopment.

Fieldwork Program

Geotechnical Program

A geotechnical investigation was carried out on September 19, 2023, and consisted of a total of 3 boreholes excavated to a maximum depth of 6.7 m below ground surface (bgs). Practical refusal to DCPT was encountered at a depth of 10.8 m bgs in BH3-23. The boreholes were distributed in a manner to provide general coverage of the proposed redevelopment, taking into account underground utilities and site features. The locations of the boreholes are shown on Drawing PG6832-1 – Test Hole Location Plan (attached). The geotechnical analysis is completed under report no. PG6832-1.Revision 2, dated October 15, 2024.

Well Testing

As a means to demonstrate the adequacy of the aquifer underlying the subject lands, with respect to water quality and quantity, the newly drilled well (TW1) on the subject site was tested. TW1 has a Water Well Record (WWR) Well ID of A395525. TW1 has a 158.7 mm diameter steel casing that extends to 17.67 m below ground surface (bgs) with a 0.62 m stick up. The well itself extends to a depth of 54.9 m bgs. Based on available geological mapping, the drift thickness at TW1 varies from 15 to 25 m. According to the Water Well Record (WWR) for the newly drilled well, the overburden generally consists of sand and gravel, boulders, clay and hardpan to a depth of 15.84 m, where limestone bedrock was encountered. Refer to P²Concepts - Site Plan Drawing-SP01 attached, for the approximate location of TW1.

As a means to evaluate the water supply aquifer intercepted by the well, the well was subjected to an 8-hour constant rate pumping test. The pumping test was conducted on September 24, 2024 under the full-time supervision of Paterson personnel. Prior to the



pumping test the well was disinfected as per the MECP Disinfection Instruction Sheet (attached), and a data-logger was installed to monitor the background groundwater levels.

The submersible pump was rented from and installed by a licensed well technician (Air Rock Drilling Inc.) and used for the 8-hour pumping test. A licensed water well technician (Air Rock) completed the necessary plumbing related activities. The discharge line was placed at a sufficient distance to ensure that the discharge water was being directed away from the well as well as any septic systems in the area. Upon completion of the test, the system was returned to its normal configuration.

The pumping test was carried out at a pumping rate of 58 L/min for a duration of 8 hours. During the pumping test, the pumping rate was periodically measured using the timed volume correlation method. The pump rate was maintained within 5% of the selected pump rate. The static water level was recorded manually and an electric datalogger (VanEssen TD-Diver) was installed in the test well prior to the start of the pumping test. The selected rate of 58 L/min provides approximately 3.8 times the maximum total daily design volume for the septic system during the 8-hour pumping test. The rate was determined to be representative of a flow rate which would be in excess of what the proposed redevelopment would require.

The data logger recorded water levels at 30 second intervals. In addition, manual water level readings were taken at periodic intervals during the test.

Recovery data was collected from the well following the completion of the pumping. The well was noted to have fully recovered within 2 minutes after the end of pumping.

Groundwater samples were collected 4 hours and 8 hours after the start of pumping. Prior to collection of the groundwater samples, the free chlorine residual was verified as non-detectable. The water samples were submitted for comprehensive testing of bacteriological, chemical, and physical water quality parameters consistent with the standard "Subdivision Supply" suite of parameters plus trace metals, and volatile organic compounds (VOCs).

All samples were collected unfiltered and unchlorinated and were placed directly into clean bottles supplied by the analytical laboratory. Samples were placed immediately into a cooler with ice and were transported directly to Environmental Testing Canada Inc.(Eurofins) laboratory in Ottawa. All samples were received by the laboratory within 24 hours of collection.

A series of field tests of the pumped water were carried out at the well head during the 8-hour pumping test. The parameters tested at the well head included: pH, total dissolved solids, conductivity, turbidity, apparent colour, and temperature.



Well Inspection

A visual inspection of TW1 was performed by Paterson personnel and confirmed that the well casing and well cap are in good condition. The grading around the well was noted to be sufficiently graded to direct surface water away from the wellhead, as required by O.Reg 903. The stickup was measured to be 0.62 m above ground surface. Based on a visual inspection by Paterson personnel, the well was deemed to be in good condition.

Aquifer Analysis

Water Quantity

Pumping test data was analyzed using AQTESOLV Pro Version 4 aquifer analysis software package by HydroSOLVE Inc. Drawdown data was measured using an electronic water level tape and an electronic datalogger unit.

| Table 1: SUMMARY OF WATER SUPPLY AQUIFER CHARACTERISTICS OF TW1 | |
|--|---------------------------|
| AQUIFER PARAMETER | RESULT OF ANALYSIS |
| Transmissivity (m ² /day) | 1971 |
| Pumping Rate (L/min) | 58 |
| Pre-test Static Water Level (m) | 4.62 |
| Post-test Static Water Level (m) | 4.88 (4.98 max) |
| Available Drawdown (m) | 50.28 |
| % Drawdown During Pump Test (%) | 0.7 |
| Specific Capacity (L/min/m drawdown) | 161 |

The drawdown data was analyzed using the Cooper Jacob method of analysis. Aquifer transmissivity is estimated to be 1971 m²/day. Refer to the Cooper Jacob method of analysis data sheet attached to this report. Note that there was very little draw down during the pumping test at the associated pumping rate.

The pumping test results show that TW1 has a high yield to support the water demands that may be required. Overall maximum drawdown at a constant pumping rate for a period of 8 hours was approximately 0.36 m (0.7% of the available drawdown). It should be noted that full recovery was achieved within 2 minutes after the end of pumping.

The total volume of water pumped during the 8-hour pumping event was approximately 27,840 L. This is approximately 3.8 times the maximum total daily design volume of water required (7,250 L/day) to support the proposed redevelopment.

The suitability of the aquifer to supply the proposed Site Plan Application for the proposed commercial modification was assessed using the methodology provided in the City of Ottawa Hydrogeological and Terrain Analysis Guidelines (HTAG).



Based on the information summarized in Table 1, it is readily apparent that the water supply well has intercepted an adequately strong water supply aquifer which has sufficient quantity to service the proposed Site Plan Control Application.

Given the analyses presented and summarized above, it is our opinion that there is an adequate supply of water to support the proposed redevelopment as well as the neighbouring lots. Available water well records (WWR) of the neighboring properties on the MECP Well Record mapping website indicated that the wells were screened in limestone and sandstone. Surrounding WWR's are attached to this report.

Water Quality

Field Data

Turbidity, electrical conductivity, total dissolved solids (TDS), pH, apparent color and temperature were measured at the wellhead during the pumping test. The measurements and time intervals for each of these parameters are summarized on the graphical representation below. In addition, a HACH Pocket Colorimeter II chlorine reader was used to measure the free chlorine residual level. No chlorine residual was detected in the discharge water prior to the collection of the water samples.




Figure 1: Field Measurements

**Laboratory Data**

The Subdivision Package suite of parameters and trace metals laboratory water quality obtained from the pumping test of TW1 is provided in Table 2a, 2b, and 2c below and the laboratory analyses reports can be found attached. VOC laboratory analytical testing were completed and measured to be non-detect in the sample results. All laboratory test results can be found attached to this report.

| TABLE 2a: GROUNDWATER MICROBIOLOGY & GENERAL GEOCHEMISTRY | | | | | |
|---|----------|-----------|--------|----------------|----------------|
| PARAMETER | UNITS | ODWS | | TW1 | |
| | | LIMIT | TYPE | TW1 GW1 (4 hr) | TW1 GW2 (8 hr) |
| | | | | 9/24/2024 | 9/24/2024 |
| MICROBIOLOGICAL | | | | | |
| Escherichia Coli (E.Coli) | ct/100mL | 0 | MAC | 0 | 0 |
| Total Coliforms | ct/100mL | 0 | MAC | 0 | 0 |
| GENERAL CHEMICAL - HEALTH RELATED | | | | | |
| Fluoride (F) | mg/L | 1.5 | MAC | 0.64 | 0.63 |
| Ammonia (N-NH ₃) | mg/L | - | - | 0.154 | 0.153 |
| Nitrite (N-NO ₂) | mg/L | 1 | MAC | <0.1 | <0.1 |
| Nitrate (N-NO ₃) | mg/L | 10 | MAC | <0.1 | <0.1 |
| Total Kjeldahl Nitrogen | mg/L | - | - | 0.231 | 0.236 |
| Turbidity (Field) | NTU | 1.0 (5.0) | MAC/AO | 1.56 | 1.56 |
| Turbidity (Laboratory) | NTU | 1.0 (5.0) | MAC/AO | 1.6 | 2.3 |
| GENERAL CHEMICAL - AESTHETIC RELATED | | | | | |
| Alkalinity (as CaCO3) | mg/L | 30-500 | OG | 229 | 236 |
| Chloride (Cl) | mg/L | 250 | AO | 90 | 85 |
| Colour (Apparent - Lab) | TCU | 5 | AO | 6 | 7 |
| Colour (Apparent - Field) | TCU | 5 | AO | 4 | 3 |
| Conductivity | uS/cm | - | - | 781 | 766 |
| Dissolved Organic Carbon | mg/L | 5 | AO | 0.7 | 1.1 |
| Hardness (as CaCO3) | mg/L | 100 | OG | 226 | 226 |
| Ion Balance | unitless | - | - | 1.01 | 1.00 |
| pH@25°C | unitless | 6.5-8.5 | AO | 7.99 | 7.95 |
| Phenols | mg/L | - | - | <0.001 | <0.001 |
| Sulphate (SO ₄) | mg/L | 500 | AO | 47 | 47 |
| Sulphide (S ₂ ⁻) | mg/L | 0.05 | AO | <0.01 | <0.01 |
| Tannin & Lignin | mg/L | - | - | 0.10 | <0.01 |
| Total Dissolved Solids | mg/L | 500 | AO | 508 | 498 |

1. ODWS identifies the following types of parameters:

MAC = Maximum Allowable Concentration

AO = Aesthetic Objective

OG = Operational Guideline

2. Shaded Concentration Indicates an Exceedance of the ODWS Objective

**TABLE 2b: GROUNDWATER GEOCHEMISTRY - METALS**

| PARAMETER | UNITS | ODWS | | TW1 | |
|-----------------|-------|-------|------|----------------|----------------|
| | | LIMIT | TYPE | TW1 GW1 (4 hr) | TW1 GW2 (8 hr) |
| | | | | 9/24/2024 | 9/24/2024 |
| METALS | | | | | |
| Aluminum (Al) | mg/L | 0.1 | OG | 0.03 | 0.01 |
| Antimony (Sb) | mg/L | 0.006 | IMAC | <0.0005 | <0.0005 |
| Arsenic (As) | mg/L | 0.01 | IMAC | <0.001 | <0.001 |
| Barium (Ba) | mg/L | 1.0 | MAC | 0.07 | 0.06 |
| Beryllium (Be) | mg/L | - | - | <0.0005 | <0.0005 |
| Boron (B) | mg/L | 5.0 | IMAC | 0.20 | 0.20 |
| Cadmium (Cd) | mg/L | 0.005 | MAC | <0.0001 | <0.0001 |
| Calcium (Ca) | mg/L | - | - | 42 | 42 |
| Chromium (Cr) | mg/L | 0.05 | MAC | <0.001 | <0.001 |
| Cobalt (Co) | mg/L | - | - | <0.0002 | <0.0002 |
| Copper (Cu) | mg/L | 1.0 | AO | <0.001 | <0.001 |
| Iron (Fe) | mg/L | 0.3 | AO | 0.19 | 0.33 |
| Lead (Pb) | mg/L | 0.01 | MAC | <0.001 | <0.001 |
| Magnesium (Mg) | mg/L | - | - | 30 | 29 |
| Manganese (Mn) | mg/L | 0.05 | AO | <0.01 | <0.01 |
| Molybdenum (Mo) | mg/L | - | - | <0.005 | <0.005 |
| Nickel (Ni) | mg/L | - | - | <0.005 | <0.005 |
| Potassium (K) | mg/L | - | - | 8 | 8 |
| Selenium (Se) | mg/L | 0.05 | MAC | <0.001 | <0.001 |
| Silver (Ag) | mg/L | - | - | <0.0001 | <0.0001 |
| Sodium (Na) | mg/L | 200 | AO | 81 | 78 |
| Strontium (Sr) | mg/L | - | - | 1.75 | 1.77 |
| Thallium (Tl) | mg/L | - | - | <0.0001 | <0.0001 |
| Uranium (U) | mg/L | 0.02 | MAC | <0.001 | <0.001 |
| Vanadium (V) | mg/L | - | - | <0.001 | <0.001 |
| Zinc (Zn) | mg/L | 5.0 | AO | <0.01 | <0.01 |

1. ODWS identifies the following types of parameters:

MAC = Maximum Acceptable Concentration

IMAC = Interim Maximum Acceptable Concentration

AO = Aesthetic Objective

OG = Operational Guideline

2. Shaded Concentration Indicates an Exceedance of the ODWS Objective

**TABLE 2c: GROUNDWATER GEOCHEMISTRY - VOLATILES**

| PARAMETER | UNITS | ODWS | | TW1 | |
|-----------------------------------|-------|-------|------|----------------|----------------|
| | | LIMIT | TYPE | TW1 GW1 (4 hr) | TW1 GW2 (8 hr) |
| | | | | 9/24/2024 | 9/24/2024 |
| VOCs Surrogates | | | | | |
| 1,2-dichloroethane-d4 | % | - | - | - | 113 |
| 4-bromofluorobenzene | % | - | - | - | 81 |
| Toluene-d8 | % | - | - | - | 99 |
| Volatiles | | | | | |
| 1,1,1,2-tetrachloroethane | µg/L | - | - | - | <0.5 |
| 1,1,1-trichloroethane | µg/L | - | - | - | <0.4 |
| 1,1,2,2-tetrachloroethane | µg/L | - | - | - | <0.5 |
| 1,1,2-trichloroethane | µg/L | - | - | - | <0.4 |
| 1,1-dichloroethane | µg/L | - | - | - | <0.4 |
| 1,1-dichloroethylene | µg/L | 14.0 | MAC | - | <0.5 |
| 1,2-dichlorobenzene | µg/L | 200.0 | MAC | - | <0.4 |
| 1,2-dichloroethane | µg/L | 5.0 | IMAC | - | <0.2 |
| 1,2-dichloropropane | µg/L | - | - | - | <0.5 |
| 1,3,5-trimethylbenzene | µg/L | - | - | - | <0.3 |
| 1,3-dichlorobenzene | µg/L | - | - | - | <0.4 |
| 1,3-Dichloropropylene (cis+trans) | µg/L | - | - | - | <0.3 |
| 1,4-dichlorobenzene | µg/L | 5.0 | MAC | - | <0.4 |
| Acetone | µg/L | - | - | - | <30 |
| Benzene | µg/L | 1.0 | MAC | - | <0.5 |
| Bromodichloromethane | µg/L | - | - | - | <0.3 |
| Bromoform | µg/L | - | - | - | <0.4 |
| Bromomethane | µg/L | - | - | - | <0.5 |
| c-1,2-Dichloroethylene | µg/L | - | - | - | <0.4 |
| c-1,3-Dichloropropylene | µg/L | - | - | - | <0.2 |
| Carbon Tetrachloride | µg/L | 2.0 | MAC | - | <0.2 |
| Chloroethane | µg/L | - | - | - | <0.2 |
| Chloroform | µg/L | - | - | - | <0.5 |
| Dibromochloromethane | µg/L | - | - | - | <0.3 |
| Dichlorodifluoromethane | µg/L | - | - | - | <0.5 |
| Dichloromethane | µg/L | 50 | MAC | - | <4.0 |
| Ethylbenzene | µg/L | 140 | MAC | - | <0.5 |
| Ethylene Dibromide | µg/L | - | - | - | <0.2 |
| Hexane | µg/L | - | - | - | <5 |
| m/p-xylene | µg/L | - | - | - | <0.4 |
| Methyl Ethyl Ketone (MEK) | µg/L | - | - | - | <10 |
| Methyl Isobutyl Ketone (MIBK) | µg/L | - | - | - | <10 |
| Methyl Tert Butyl Ether (MTBE) | µg/L | 15 | AO | - | <2 |
| Monochlorobenzene | µg/L | 80 | MAC | - | <0.5 |
| o-xylene | µg/L | - | - | - | <0.4 |
| Styrene | µg/L | - | - | - | <0.5 |
| t-1,2-Dichloroethylene | µg/L | - | - | - | <0.4 |
| t-1,3-Dichloropropylene | µg/L | - | - | - | <0.2 |
| Tetrachloroethylene | µg/L | 10 | MAC | - | <0.3 |
| Toluene | µg/L | 60 | MAC | - | <0.4 |
| Trichloroethylene | µg/L | 5 | MAC | - | <0.3 |
| Trichlorofluoromethane | µg/L | - | - | - | <0.5 |
| Vinyl Chloride | µg/L | 1 | MAC | - | <0.2 |
| Xylene; total | µg/L | 90 | MAC | - | <0.5 |



The bacteriological test results (Certificate of Analysis – Report No. 4102006) indicated that the test samples at the 4 and 8 hour interval were non-detect (0 ct/100 mL) for E.Coli and Total Coliforms.

The water quality of the subject water supply well meets all the Ontario Drinking Water Standards maximum acceptable concentrations (MAC). Furthermore, the water meets all of the Aesthetic Objectives (AO) and Operational Guidelines (OG) with the exception of the following.

- ☐ Hardness (as CaCO_3)
- ☐ Turbidity
- ☐ Iron (Fe)

Exceedances of the above parameters are not uncommon of the water supply in the subject aquifer. Each of these groundwater parameters are discussed in detail below.

Hardness as CaCO_3

Hardness, expressed as calcium carbonate, is an operation guideline and does not appear in the ODWS. Rather, it appears in the Technical Support Documents for Ontario Drinking Water Standards, Objectives and Guidelines (ODWS) as a parameter with an operational guideline at 100 mg/L. At the measured concentration of 226 mg/L, the water is considered to be hard, however, it is below the reasonable treatable limit of 500 mg/L specified in Table 3 of the MOECC guidance document Procedure D-5-5 (1996). The hardness concentration can be treated using conventional softening technologies, if desired by the owner.

Turbidity

Turbidity, which is generally an aesthetic parameter, was detected in the laboratory test samples at values of 1.6 and 2.3 NTU in the 4- and 8-hours tests, respectively. Field testing of the samples detected values of 1.56 NTU in the 4- and 8-hour field tests, respectively. It is expected that continued use of the well would further reduce turbidity values. The elevated turbidity in the laboratory analyzed samples is attributed to the precipitation of iron.

The ODWS maximum acceptable concentration for turbidity in drinking water entering the distribution system is 1 NTU. The health-related Ontario Drinking Water Objective (ODWO) is 1 NTU. The Aesthetic Objective for turbidity in drinking water reaching the consumer is 5 NTU. The City's HTAG has a Maximum Concentration Considered Reasonably Treatable (MCCRT) of 5 NTU.

The field test parameters are below the 5 NTU objective. Furthermore, total coliforms and E.Coli were non-detect (0 ct/100 mL) in both the 4 and 8-hour samples, which meets the health requirements of the City's HTAG when the sample results are above the health-related ODWO of 1 NTU. Therefore, treatment for turbidity is not required



Iron

Concentrations of iron above 0.3 mg/L can contribute to staining of fixtures and a metallic taste at higher concentrations. Precipitation of iron can promote the growth of iron bacteria in pipes. The concentration of iron in the groundwater in TW1 was measured to be 0.33 mg/L at the 8-hour mark. The concentration of iron in the groundwater in the test well is considered to be reasonably treatable in accordance with Procedure D-5-5. It is recommended that an iron filter be used to reduce the levels of iron and reduce the potential for excessive precipitate occurring in the water supply system, if desired by the owner.

Colour

Colour may occur in drinking water for several reasons. It may be due to organic substances from the decay of vegetation, or the presence of metals such as iron, manganese, and copper, which are abundant in nature. The provincial aesthetic objective for colour in drinking water is 5 True Colour Units (TCU). The federal (Health Canada) guideline aesthetic objective limit for colour is 15 TCU (Guidelines for Canadian Drinking Water Quality, Health Canada June 2019). Procedure D-5-5 gives a maximum concentration considered reasonably treatable for colour as 7 TCU. As colour is a strictly aesthetic parameter, it can be reduced from the water supply, if desired, through the use of a manganese greensand treatment.

During the field pumping test, a DR900 colorimeter was used to measure apparent colour in the groundwater at regular intervals. Apparent colour in the groundwater was measured as 4 and 3 TCU at the 4- and 8- hour marks, which are below the aesthetic guideline of 5 TCU, whereas apparent colour from laboratory measurements was 6 and 7 TCU which is above the guideline but within treatable limits. The elevated colour levels detected in the lab samples is attributed to the precipitation of iron out of the groundwater.

Total Dissolved Solids (TDS)

TDS refers to the concentration of inorganic substances dissolved in water. The main constituents are typically chloride, sulphates, calcium, magnesium, and bicarbonates. The TDS concentration of 508 mg/L at the 4-hour mark exceeds the Aesthetic Objective of 500 mg/L. At concentrations above 500 mg/L, some consumers may find the taste objectionable, however, as the objective is an aesthetic objective, no treatment is required. At the 8-hour mark, the TDS concentration was 498 mg/L which is below the Aesthetic Objective. As the TDS concentration was decreasing with time and was below the Aesthetic Objective no taste problems are anticipated to occur and treatment is not likely to be required. If desired by the owner, a point of use reverse osmosis unit can be installed to reduce TDS levels for drinking purposes.

The Langelier calculation provided an LSI of 0.0. Based on the evaluation of the result, the water is saturated and does not precipitate a scale layer of calcium carbonate or dissolve calcium carbonate (neither scale forming nor corrosive). Based on the stable



value, there are no mitigative measures needed. See Langelier Saturation Index Calculation attached for calculation details.

Sodium

Sodium (Na), an aesthetic parameter, was detected in the laboratory test sample at concentrations of 81 and 78 mg/L, which does not exceed the ODWS aesthetic objective of 200 mg/L. Although sodium is not toxic and no maximum acceptable concentration has been set, concentrations above 20 mg/L require that the Medical Officer of Health be notified of the water quality results, so that this information may be passed on to local physicians for use in treatment of those requiring a sodium-restricted diet.

O.Reg 903

All wells must be maintained in accordance with O.Reg 903. If a well is no longer in use, it must be decommissioned in accordance with O.Reg 903.

TERRAIN ANALYSIS

The purpose of this study is to determine the site's suitability for private on-site wastewater systems. Specifically, the intent of this report is to provide design details for private septic servicing and lot development potential.

Surficial Geology

Paterson carried out a Geotechnical Investigation on September 19, 2023 where 3 boreholes were installed in a manner to provide general coverage of the subject site, with specific consideration to the redevelopment. The general overburden was observed to be a thin layer of topsoil followed by fill and/or glacial till. Fill, consisting of brown silty sand with gravel, was encountered in BH2-23 and BH3-23, to a maximum depth of 2.1 m bgs. Glacial till, consisting of silty sand to sandy silt with varying amounts of gravel and, cobbles and boulders, was found in each borehole to the maximum depth of the boreholes. Practical refusal to augering was observed at a depth of 5 m in BH1-23 and DCPT refusal was observed in BH3-23 at a depth of 10.8 m bgs. The results of the geotechnical program are generally consistent with available geological mapping provided by the Ontario Geological Survey (OGS MRD128) and with the available historical surrounding Water Well Records (WWR). Further details can be found in geotechnical report PG6832-1.Revision 2, dated October 15, 2024.

Available bedrock geological mapping provided by the Ontario Geological Survey (MRD 219) indicates that the bedrock underlying the subject site consists of dolostone, minor shale and sandstone of the Oxford Formation in the Beekmantown Group. Available overburden thickness mapping shows a drift thickness of 10 to 15 m across the subject site.



Hydrogeological Sensitivity of the Site

The subject site currently consists of a temple with associated infrastructure and private servicing. The subject site is serviced by a private potable well and septic system. The subject site is currently occupied by a one-story commercial building, specifically the Ottawa Sivan Temple. The site is bordered to the north by Roger Stevens Drive, followed by a residential dwelling and agricultural land, to the west by residential dwellings, and to the south and east by agricultural land. All surrounding properties are on private services. The adjacent properties are serviced by private wells and septic systems.

The overburden at the subject site and surrounding WWRs is recorded as a sand based glacial till.

According to the Ontario Building Code (OBC) Section 8.7.2.1 (1) (b)(i), highly permeable soils as it relates to sewage system design is defined by soils having a percolation rate of less than 1 minute per cm. According to the Ministry of Municipal Affairs and Housing (MMAH) Supplementary Standard SB-6 – Percolation time and soil descriptions dated January 1, 2024 only “Well graded gravels, gravel-sand mixtures, little or no fines” or “Poorly graded gravels, gravel-sand mixtures, little or no fines” have a percolation time of less than 1 minute per cm. The onsite soils were noted to be a glacial till consisting of silty sand to sandy silt with varying amounts of gravel and, cobbles and boulders. Due to the presence of silty sand to sandy silt (a high composition of fines), the percolation time is anticipated to be greater than 1 min/cm and therefore is not considered a highly permeable soil. As such, septic impacts due to observed soils are not anticipated onsite.

According to the Geotechnical Investigation, the overburden thickness was observed to be greater than 2 m.

As the proposed site does not have bedrock within 2 m of the ground surface and the site does not contain any highly permeable soils, the site is not considered hydrogeologically sensitive. Separation distances are not required to be increased between the septic components and the onsite well.

To corroborate our position in this matter, the water quality of the bedrock aquifer targeted by the onsite drilled potable supply well shows no indication of surface water or surface impacts.

Lot Development Plan

The Site Plan for the proposed redevelopment was produced by P² Concepts and is attached (Drawing-SP01). The location of the temple, priest residence, proposed sewage system, and related infrastructure are shown. Please note that although a “permeable parking area” was designated in the site plan drawing, the material was considered impermeable as a conservative approach for this Nitrate Impact Assessment.



Sewage System Volumes

The sewage system has been designed by D.B. Gray Engineering and can be found attached to this report. The maximum total daily design sanitary sewage flow volume (TDDSSF) was determined to be 7,250 L/day. An approved Ottawa Septic System Office (OSSO) permit will be submitted with the Site Plan Application.

Predictive Nitrate Impact Assessment

In order to demonstrate that private services would adequately support the proposed Site Plan application, a Predictive Nitrate Impact Assessment (NIA) for the subject site was completed. The values shown in the Predictive NIA attached to this report are summarized below.

| | |
|---|------------------------|
| <input type="checkbox"/> Site area | 2.04 ha |
| <input type="checkbox"/> Impervious area (%) | 27 % |
| <input type="checkbox"/> Daily sewage flow | 7.25 m ³ /d |
| <input type="checkbox"/> Concentration of nitrate in effluent (Value based on typical effluent concentration) | 40 mg/L |
| <input type="checkbox"/> Concentration of nitrate in effluent with treatment (Value based on BNQ/NSF 245 certified nitrate reduction system with 50% nitrate reduction) | 20 mg/L |
| <input type="checkbox"/> Surplus Water (The surplus water value was estimated based on Environment Canada Climate Office values with a soil type comprised of a fine sandy loam (Urban lawns / Shallow Rooted Crops) and anthropogenic sources.) | 378 mm/yr |
| <input type="checkbox"/> Combined infiltration factor based on: | 0.70 |
| • Topography infiltration factor | 0.20 |
| • Soil texture infiltration factor | 0.40 |
| • Cover infiltration factor | 0.10 |

The topography infiltration factor of 0.20 is based upon a generally rolling land with an average slope between 2.8 to 3.8 m/km. The soil texture infiltration factor was based upon an “open sandy loam” with a value of 0.4 which is a reasonable generalization based upon the site investigations and available geological mapping. The “cover infiltration factor” was calculated at 0.10 based upon a cultivated land type cover.

The calculation for a conventional septic system results in a predicted nitrate concentration of 16.05 mg/L nitrate for the subject site, using a value of 40 mg/L nitrate concentration within the effluent. This value was based upon a daily sewage flow of 7,250 L/day. It is expected that the actual usage should be lower. The inclusion of nitrate reduction technology (50 % nitrogen reduction of the effluent nitrate, with a BNQ or NSF



245 certified technology) would result in a nitrate concentration of 8.03 mg/L at the property boundary using a value of 20 mg/L nitrate within the effluent, which is below the maximum property value of 10 mg/L nitrate by the property boundary.

Based on the results of the predictive NIA, it is our opinion that the property can adequately support the proposed Site Plan application without having an adverse impact on the underlying bedrock aquifer, provided that an BNQ/NSF 245 certified nitrate reduction system with a minimum of 50% nitrate reduction is used in the sewage system.



CONCLUSIONS

Based on the information contained within the body of this report the following conclusions can be drawn:

1. The water supply aquifer intercepted by the existing well is considered to be adequate to support the water quantity demands for the proposed redevelopment.
2. Based on a visual inspection performed by Paterson personnel, the well casing, stickup, well cap, and surrounding grading around the well are of sufficient standard to meet O.Reg 903. It is a requirement that the well continue to adhere to and be maintained in accordance with O.Reg 903.
3. The preferred water supply intercepted by TW1 contains a water supply that is potable, and contains only elevated concentrations of hardness, turbidity, iron, and apparent colour. The noted parameters can be treated with current readily available water conditioning equipment if desired by the owner.
4. A residential grade water softener is recommended to facilitate the reduction of the hardness concentration. If a water softener is used for the proposed redevelopment, the owner should be made aware that additional sodium will be added to the water to reduce hardness. If desired, a point-of-use reverse osmosis system can be also used to provide a drinking tap source.
5. If desired, the owner can use an iron filter to treat the potential iron values.
6. The sodium concentration was measured to be above the 20 mg/L reporting limit and, as such, the Medical Officer of Health for the City of Ottawa should be informed to assist area physicians in the treatment of local residents on sodium reduced diets.
7. The site is not considered hydrogeologically sensitive.
8. The predicted nitrate concentrations at the property boundary is calculated to be below the required 10 mg/L threshold when a standard denitrification system (50% nitrate reduction) using BNQ/NSF 245 certified nitrate reduction technology is used.
9. A Sewage System Permit and Building Permit need to be issued prior to the commencement of construction on the proposed redevelopment or the proposed septic system.
10. The existing well will be decommissioned in accordance with O.Reg.903 once it is no longer needed.



11. The results of the Hydrogeological Assessment and Terrain Analysis have provided satisfactory evidence that the subject site can support the proposed redevelopment with respect to water quality, quantity and sewage system placement.

We trust that the current submission satisfies your immediate requirements.

Best Regards,

Paterson Group Inc.

Alexander Schopf, PhD, EIT



Erik Ardley, P.Geo

Attachments:

- ☐ Key Plan
- ☐ P²Concepts - Drawing SP.01 dated May 13, 2025
- ☐ MECP Water Well Records
- ☐ Eurofins Certificate of Analysis
- ☐ AQTESOLV - Pumping Test Analysis Reports
- ☐ Langelier Saturation Calculation
- ☐ Testhole Soil Profile and Data Sheets
- ☐ Nitrate Impact Assessment Calculations
- ☐ PG6832-1 – Test Hole Location Plan
- ☐ DBG Engineering Septic System Design






FIGURE 1

KEY PLAN

| | | | | | | |
|---|------------|------------------------|--|-----------------------|--|---|
| 2104 Roger Stevens | R13 [608r] | S. 1A - Area D (Rural) | S. 58 - Floodplain overlay | Official Plan - S. B9 | Rural Transect - Village | Temple GFA 2,013 m2 Priest Residence GFA 551 m2 Temple Assembly Area GFA 1,067.74 m2 |
| General Provisions | | Section | Required | | Proposed | |
| Permitted uses* | | S. 240 [608r] | School, Place of Worship, or Dwelling unit accessory to these uses | | Place of Worship, Dwelling unit | |
| Min. lot area (sq. m) | | Table 224A, (a) | 10,000 m2 | | 20,395 m2 | |
| Min. lot width (m) | | Table 224A, (b) | 75 m | | 82.95 m | |
| Max. building height (m) | | Table 224A, (g) | 12 m | | 8.44 m (Temple), 9.53m (Priest Residence) | |
| Min. front yard setback (m) | | Table 224A, (c) | 9 m | | 26.20 m | |
| Min. rear yard setback (m) | | Table 224A, (d) | 10 m | | 140.88 m | |
| Min. int. side yard setback (m) | | Table 224A, (e) | 9 m | | 16.69 m (east), 9 m (west) | |
| Max. lot coverage (%) | | Table 224A, (h) | 30% lot area = 6,118.50 m2 | | 6% lot area = 1,309.56 m2 | |
| Min. landscaped area (%) | | Table 224A, (i) | 20% lot area = 4,079 m2 | | 94% lot area = 19,085.44 m2 | |
| * 608r exception | | | | | | |
| Parking Provisions | | Section | Required | | Proposed | |
| Place of Worship | | Table 101, N66 | 10 spaces / 100 m2 of assembly area GFA = 107 Spaces | | 60 spaces | MV REQUIRED |
| Dwelling unit | | Table 101, R4 | 1 space | | 1 space | |
| Parking space size | | S. 106, (1) | 2.6 m x 5.2 m | | 2.6 m x 5.2 m | |
| B/F parking (included in total) | | AODA, S. 80.36 | 4% of the total provided spaces = 2 spaces | | 3 spaces (2 type A, 1 type B) | |
| Type A parking space dimensions | | AODA, S. 80.34 (1) | 3.4 m x 5.2 m (plus 1.5 m aisle) | | 3.4 m x 5.2 m with 1.5 m shared aisle | |
| Type B parking space dimensions | | AODA, S. 80.34 (2) | 2.4 m x 5.2 m (plus 1.5 m aisle) | | 2.4 m x 5.2 m with 1.5 m shared aisle | |
| Min. drive aisle width (m) | | S. 107, (1) (d) | 6.7 m | | 6.7 m | |
| Min. driveway width (m) | | S. 107, (1) (a) | 3 m - single lane; 6 m - double lane | | 6.7 m | |
| Min. landscaped area for parking lots (%) | | S. 110, (1) | 15% (322.32 m2) | | 24% (757.31 m2) | |
| Min. landscaped buffer for parking lot (m) | | Table 110, (1) | 3 m abutting street; 1.5 m not abutting street | | 11.94 abutting a street; 3.02 not abutting street | |
| Min. setback for outdoor refuse (in-ground container) | | S. 110, (3) | 9 m from a lot line abutting a public street 3 m from any other lot line | | 77.71 m from a lot line abutting a public street 4.57 m from any other lot line | |
| Permitted parking lot material | | S. 100, (3) (b) | Screened by soft landscaping 2 m in height gravel; B/F spaces must be hard and stable | | Asphalt, interlock pavers | |
| Min. number of bike parking spaces | | Table 111A, (i) | 1 space / 1,500 m2 GFA = 1 Space | | 3 spaces | |
| Min. number of loading spaces | | Table 113A, (a) | 1 space if 2,000 - 4,999 m2 of GFA = 1 Space | | 0 spaces | MV REQUIRED |

PHASING DIAGRAM:



- PHASE 1 : CONSTRUCTION OF A TWO STOREY BUILDING (TEMPORARY TEMPLE / PRIEST RESIDENCE) DRIVEWAY / PARKING)
- PHASE 2 : DEMOLITION OF THE OF EXISTING BUILDING
- PHASE 3 : CONSTRUCTION OF A ONE STOREY BUILDING - TEMPLE

LEGEND:

INTERNAL ROAD / FIRE ROUTE

S.O.D.

SNOW STORAGE AREA

PERMEABLE PARKING AREA

TERRACES

BARRIER FREE CAR PARKING SPACES
TYPE A (3.4 x 5.2 m)
TYPE B (2.4 x 5.2 m)
ACCESS AISLE (1.5 x 5.2 m)

CAR PARKING SPACES

PROPOSED BUILDING

PROPOSED WALKWAY

SHRUB / BUSHES

EXISTING VEGETATION

PROPOSED TREES

BIKES PARKING SPACE

MOLOK BIN

SANITARY MANHOLE

STORM / CATCH BASIN MANHOLE

CATCH BASIN

LIMIT OF SITE DEVELOPMENT



EXISTING STATUE

ACCESSIBLE BENCH WITH CONCRETE PAD

PROPOSED PICNIC TABLE

EXISTING TREE TO REMAIN

SITE SIGNAGE



OWNER NAME & ADDRESS
Valluvambiga Sri Talyaynayaki Sametha
Vaihiyanathan Swamy Koll Inc.
Kugendran Sabaratnam
2104 Roger Stevens Rd North Gower, ON, K0A 2T0

ARCHITECT
OM P. MADAN ARCHITECT
8 AVE. Q, QUA. M1M4C
7 SPARKER CRES.
OTTAWA, ONTARIO K2B 1B3
T: (613) 203-1805

APPLICANT AND DESIGNER
P-SQUARED CONCEPTS INC.
P²concepts

PROJECT TEAM (ENGINEERS)
PATerson GROUP
CIMAX
D.B. Gray Engineering Inc.
James B. Lemox & Associates Inc.
LANDSCAPE ARCHITECTS

PLAN OF SURVEY
INFORMATION SHOWN HAS BEEN TAKEN FROM
J.D. BARNES LIMITED
62 STEACIE DRIVE, SUITE 103,
KANATA, ON K2K 2A9
(613) 731-7244

TOPOGRAPHIC PLAN OF
PART OF LOT 21
CONCESSION 3
GEOGRAPHIC TOWNSHIP OF NORTH GOWER
NOW IN THE
CITY OF OTTAWA

BENCHMARK NOTE

1. IT IS THE RESPONSIBILITY OF THE USER OF THIS INFORMATION TO VERIFY THAT THE SITE BENCHMARK HAVE NOT BEEN ALTERED OR DISTURBED AND THAT ITS RELATIVE ELEVATION AND DESCRIPTION AGREES WITH THE INFORMATION SHOWN ON THIS DRAWING.

2. ELEVATIONS ARE GEODETIC AND REFERRED TO PUBLISHED CONTROL POINT 01019791716 HAVING A PUBLISHED ELEVATION OF 91.214 METRES (GVD28-78 DATUM)

| | | |
|-----|--------------------------------|------------|
| 09 | ISSUED FOR COORDINATION | 2025-05-13 |
| 08 | ISSUED FOR REVIEW | 2025-04-09 |
| 07 | ISSUED FOR REVIEW | 2025-04-03 |
| 06 | ISSUED FOR COORDINATION | 2025-03-06 |
| 05 | ISSUED FOR COORDINATION | 2024-10-04 |
| 04 | ISSUED FOR COORDINATION | 2024-09-26 |
| 04 | ISSUED FOR COORDINATION | 2024-08-08 |
| 03 | ISSUED FOR CIVIL COORDINATION | 2024-05-21 |
| 02 | ISSUED FOR CLIENT REVIEW | 2024-04-09 |
| 01 | ISSUED FOR PHASE I PRE-CONSULT | 2024-03-01 |
| No. | REVISIONS | DATE |

NOT AUTHENTIC UNLESS SIGNED AND DATED

P²concepts
2001 HURON ST. SUITE 205
OTTAWA, ONTARIO, K1G 4E1

DESIGNED BY: S.A. DRAWN BY: P.S. APPROVED BY: P.R.

PROJECT

NEW OTTAWA SIVAN TEMPLE

DRAWING TITLE

SITE PLAN

PROJECT NO. 0399
DATE MAY, 13, 2025

SP01

Measurements recorded in: ☐ Metric ☒ Imperial

A395525

Regulation 903 Ontario Water Resources Act

Page _____ of _____

Well Owner's Information

| | | | |
|---|--|-----------------------|---|
| First Name | Last Name/Organization Ottawa Sivan Temple | E-mail Address | <input type="checkbox"/> Well Constructed by Well Owner |
| Mailing Address (Street Number/Name) 2104 Roger Stevens Drive | Municipality North Gower | Province ON | Postal Code K0A 2T0 |
| Telephone No. (inc. area code) | | | |

Well Location

| | | | |
|--|---|--|------------------------|
| Address of Well Location (Street Number/Name) 2104 Roger Stevens Drive | Township Rideau | Lot P/L 21 | Concession 3 |
| County/District/Municipality Ottawa Carleton | City/Town/Village North Gower | Province Ontario | Postal Code |
| UTM Coordinates Zone Easting NAD 83 18 445192 | Northing 4998614 | Municipal Plan and Sublot Number 5R-6158 | Other |

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

| General Colour | Most Common Material | Other Materials | General Description | Depth From (m) | To (m) |
|----------------|----------------------|-----------------|---------------------|----------------|--------|
| | Sand | Clay | | 0 | 25 |
| | Gravel | Boulders | Hard Pan | 25 | 52 |
| Grey & Black | Limestone | | | 52 | 154 |
| Grey & Black | Limestone | | | 154 | 160 |
| Grey | Sandstone | | | 160 | 170 |
| Grey | Sandstone | | | 170 | 174 |
| Grey | Sandstone | | | 174 | 180 |

*Owner - Vallavambiga Sri Taiyalayaki Sametha
Vaithiyaratha Swamy Koil Inc. (AS) Ottawa Sivan Temple*

| Annular Space | | | Results of Well Yield Testing | | | |
|------------------|--|---------------------------------|---|--------------|--------------------|------------|
| Depth Set at (m) | Type of Sealant Used (Material and Type) | Volume Placed (m ³) | After test of well yield, water was: | Draw Down | Recovery | |
| 58' | Neat cement | 10.92 | <input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify Not tested | Time (min) | Water Level (m/ft) | Time (min) |
| 48' | Bentonite slurry | 21.00 | If pumping discontinued, give reason: | Static Level | 14'3" | 16.5" |
| | | | | 1 | 16.1 | 1 |
| | | | Pump intake set at (m) | 2 | 16.2 | 2 |
| | | | 170 | 3 | 16.2 | 3 |
| | | | Pumping rate (l/min / GPM) | 4 | 16.2 | 4 |
| | | | 20 | 5 | 16.2 | 5 |
| | | | Duration of pumping | 10 | 16.3 | 10 |
| | | | 1 hrs + 0 min | 15 | 16.3 | 15 |
| | | | Final water level end of pumping (m/ft) | 20 | 16.4 | 20 |
| | | | 16.5" | 25 | 16.4 | 25 |
| | | | If flowing give rate (l/min/GPM) | 30 | 16.4 | 30 |
| | | | | 40 | 16.5 | 40 |
| | | | Recommended pump depth (m/ft) | 50 | 16.5 | 50 |
| | | | 100 | 60 | 16.5 | 60 |
| | | | Recommended pump rate (l/min/GPM) | | | |
| | | | 20 | | | |
| | | | Well production (l/min/GPM) | | | |
| | | | 20 | | | |
| | | | Disturbed? | | | |
| | | | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | | | |

| Method of Construction | | Well Use | |
|--|----------------------------------|--|---|
| <input type="checkbox"/> Cable Tool | <input type="checkbox"/> Diamond | <input type="checkbox"/> Public | <input type="checkbox"/> Not used |
| <input type="checkbox"/> Rotary (Conventional) | <input type="checkbox"/> Jetting | <input checked="" type="checkbox"/> Domestic | <input type="checkbox"/> Dewatering |
| <input type="checkbox"/> Rotary (Reverse) | <input type="checkbox"/> Driving | <input type="checkbox"/> Livestock | <input type="checkbox"/> Test Hole |
| <input type="checkbox"/> Boring | <input type="checkbox"/> Digging | <input type="checkbox"/> Irrigation | <input type="checkbox"/> Monitoring |
| <input checked="" type="checkbox"/> Air percussion | | <input type="checkbox"/> Industrial | <input type="checkbox"/> Cooling & Air Conditioning |
| <input type="checkbox"/> Other, specify | | <input type="checkbox"/> Other, specify | |

| Construction Record - Casing | | | | Status of Well | |
|------------------------------|--|------------------------|--------------|---|--|
| Inside Diameter (cm/in) | Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel) | Wall Thickness (cm/in) | Depth (m/ft) | <input checked="" type="checkbox"/> Water Supply | |
| 6 1/4" | Steel | .188" | +2' 58' | <input type="checkbox"/> Replacement Well | |
| 6" | Open Hole | | 58' 180' | <input type="checkbox"/> Test Hole | |
| | | | | <input type="checkbox"/> Recharge Well | |
| | | | | <input type="checkbox"/> Dewatering Well | |
| | | | | <input type="checkbox"/> Observation and/or Monitoring Hole | |
| | | | | <input type="checkbox"/> Alteration (Construction) | |
| | | | | <input type="checkbox"/> Abandoned, Insufficient Supply | |
| | | | | <input type="checkbox"/> Abandoned, Poor Water Quality | |
| | | | | <input type="checkbox"/> Abandoned, other, specify | |
| | | | | <input type="checkbox"/> Other, specify | |

| Construction Record - Screen | | | |
|------------------------------|---------------------------------------|-----------|--------------|
| Outside Diameter (cm/in) | Material (Plastic, Galvanized, Steel) | Slot Size | Depth (m/ft) |
| | | | From To |
| | | | |
| | | | |
| | | | |

| Water Details | | Hole Diameter | |
|-----------------------------|---|---------------|------------------|
| Water found at Depth (m/ft) | Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Gas <input type="checkbox"/> Other, specify | Depth (m/ft) | Diameter (cm/in) |
| 154' (m/ft) | | 0' 58' | 9 3/4" |
| 170' (m/ft) | | 58' 180' | 6" |
| 174' (m/ft) | | | |

| Well Contractor and Well Technician Information | |
|---|--|
| Business Name of Well Contractor Air Rock Drilling Co. Ltd. | Well Contractor's Licence No. 7881 |
| Business Address (Street Number/Name) 5550 Parktown Road | Municipality Richmond |

| | | |
|---|---|---|
| Province ON | Postal Code K0A 2Z0 | Business E-mail Address air-rock@sympatico.ca |
| Bus. Telephone No. (inc. area code) 6138382170 | Name of Well Technician (Last Name, First Name) Hanna, Jeremy | Well Technician's Licence No. 13632 |
| Signature of Technician and/or Contractor <i>[Signature]</i> | | |
| Date 2024 09 30 | | |

| Map of Well Location | | | |
|--|--|--|--|
| Please provide a map below following instructions on the back. | | | |
| #2104 ROGER STEVENS DRIVE | | | |
| Trailwood Drive | | | |
| 150m | | | |
| 170 FT | | | |

| | |
|---|---|
| Comments: 1HP-20 GPM Jet @ 100 FT | |
| Well owner's information package delivered <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | Date Package Delivered 2024 09 30 |
| Ministry Use Only Audit No. 2427310 | |
| Received 2024 09 09 | |



The Ontario Water Resources Act

WATER WELL RECORD

Mark correct box with a checkmark, where applicable.

1531768

County or District **CARLETON** Township/Borough/City/Town/Village **RIDEAU** Con block tract survey, etc. **3** Lot **2012** Part of

Address **6626 3RD Line RD KARS** Date completed **16** day **01** month **2001** year

25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100

| General colour | Most common material | Other materials | General description | Depth - feet | |
|----------------|----------------------|-------------------------|---------------------|--------------|----|
| | | | | From | To |
| Brown | clay | | Thick | 0 | 10 |
| Grey | Clay | | Runny | 10 | 20 |
| Grey | Clay | Sandy, with Boulders, | HARD Pan | 20 | 36 |
| Grey | Limestone | Broken Layers, Sand | MED HARD | 36 | 48 |
| Grey | Limestone | | MED HARD | 48 | 65 |
| | | 43' of 6 1/4" casing | | | |
| | | 20' of 5" casing | | | |
| | | 1 Heavy Duty DRIVE shoe | | | |
| | | 1 well cap | | | |
| | | 10 Bags of Cement | | | |

31

32

| 41 WATER RECORD | | | |
|-----------------------|----------------------------------|--|----|
| Water found at - feet | Kind of water | | |
| 53 | 1 <input type="checkbox"/> Fresh | 3 <input type="checkbox"/> Sulphur | 14 |
| | 2 <input type="checkbox"/> Salty | 4 <input checked="" type="checkbox"/> Minerals | |
| | | 6 <input type="checkbox"/> Gas | |
| 15-18 | 1 <input type="checkbox"/> Fresh | 3 <input type="checkbox"/> Sulphur | 19 |
| | 2 <input type="checkbox"/> Salty | 4 <input type="checkbox"/> Minerals | |
| | | 6 <input type="checkbox"/> Gas | |
| 20-23 | 1 <input type="checkbox"/> Fresh | 3 <input type="checkbox"/> Sulphur | 24 |
| | 2 <input type="checkbox"/> Salty | 4 <input type="checkbox"/> Minerals | |
| | | 6 <input type="checkbox"/> Gas | |
| 25-28 | 1 <input type="checkbox"/> Fresh | 3 <input type="checkbox"/> Sulphur | 29 |
| | 2 <input type="checkbox"/> Salty | 4 <input type="checkbox"/> Minerals | |
| | | 6 <input type="checkbox"/> Gas | |
| 30-33 | 1 <input type="checkbox"/> Fresh | 3 <input type="checkbox"/> Sulphur | 34 |
| | 2 <input type="checkbox"/> Salty | 4 <input type="checkbox"/> Minerals | |
| | | 6 <input type="checkbox"/> Gas | |

| 51 CASING & OPEN HOLE RECORD | | | | |
|------------------------------|---|-----------------------|--------------|-------|
| Inside diam inches | Material | Wall thickness inches | Depth - feet | |
| | | | From | To |
| 6 1/4 | 1 <input checked="" type="checkbox"/> Steel | .188 | 0 | 38 |
| | 2 <input type="checkbox"/> Galvanized | | | |
| | 3 <input type="checkbox"/> Concrete | | | |
| | 4 <input type="checkbox"/> Open hole | | | |
| | 5 <input type="checkbox"/> Plastic | | | |
| 5 1/4 | 1 <input checked="" type="checkbox"/> Steel | .188 | 30 | 50 |
| | 2 <input type="checkbox"/> Galvanized | | | |
| | 3 <input type="checkbox"/> Concrete | | | |
| | 4 <input checked="" type="checkbox"/> Open hole | | 50 | 65 |
| | 5 <input type="checkbox"/> Plastic | | | |
| 4 3/8 | 1 <input type="checkbox"/> Steel | | | |
| | 2 <input type="checkbox"/> Galvanized | | | |
| | 3 <input type="checkbox"/> Concrete | | | |
| | 4 <input type="checkbox"/> Open hole | | | |
| | 5 <input type="checkbox"/> Plastic | | | |
| 24-25 | 1 <input type="checkbox"/> Steel | | | 27-30 |
| | 2 <input type="checkbox"/> Galvanized | | | |
| | 3 <input type="checkbox"/> Concrete | | | |
| | 4 <input type="checkbox"/> Open hole | | | |
| | 5 <input type="checkbox"/> Plastic | | | |

| SCREEN | Sizes of opening (Slot No.) | | Diameter | Length | 31-33 |
|--------|-----------------------------|--|------------------------|--------|-------|
| | | | | | |
| | | | inches | feet | |
| | Material and type | | Depth at top of screen | | |
| | | | feet | | |

| 61 PLUGGING & SEALING RECORD | | | |
|--|-------|---|--|
| X Annular space <input type="checkbox"/> Abandonment | | | |
| Depth set at - feet | | Material and type (Cement grout, bentonite, etc.) | |
| From | To | | |
| 0 | 38 | Cement Grout | |
| 18-21 | 22-25 | | |
| 26-29 | 30-33 | | |

| | | | | | | |
|--|---|--|--|---|---|-----------------------------|
| 71 | Pumping test method ¹⁰ 1 <input type="checkbox"/> Pump 2 <input checked="" type="checkbox"/> Bailor | | Pumping rate ¹¹⁻¹⁴ 10 GPM | | Duration of pumping ⁵⁻¹⁶ 1 Hours 17-18 Mins | |
| | Static level | | Water level end of pumping ²⁵ | | Water levels during 1 <input checked="" type="checkbox"/> Pumping 2 <input type="checkbox"/> Recovery | |
| | 19-21 | 22-24 | 15 minutes ²⁶⁻²⁸ | 30 minutes ²⁹⁻³¹ | 45 minutes ³²⁻³⁴ | 60 minutes ³⁵⁻³⁷ |
| | 3 feet | 40 feet | 40 feet | 40 feet | 40 feet | 40 feet |
| | If flowing give rate ³⁸⁻⁴¹ GPM | | Pump intake set at feet | | Water at end of test ⁴² <input checked="" type="checkbox"/> Clear <input type="checkbox"/> Cloudy | |
| Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep | | Recommended pump setting ⁴³⁻⁴⁵ 50 feet | | Recommended pump rate ⁴⁶⁻⁴⁹ 7 GPM | | |

1 ☒ Water supply 5 ☐ Abandoned, insufficient supply 9 ☐ Unfinished
2 ☐ Observation well 6 ☐ Abandoned, poor quality 10 ☐ Replacement well
3 ☐ Test hole 7 ☐ Abandoned (Other)
4 ☐ Recharge well 8 ☐ Dewatering

1 ☒ Domestic
2 ☐ Stock
3 ☐ Irrigation
4 ☐ Industrial
5 ☐ Commercial
6 ☐ Municipal
7 ☐ Public supply
8 ☐ Cooling & air conditioning

1 ☒ Cable tool
2 ☐ Rotary (conventional)
3 ☐ Rotary (reverse)
4 ☐ Rotary (air)
5 ☐ Air percussion
6 ☐ Boring
7 ☐ Diamond
8 ☐ Jetting
9 ☐ Driving
10 ☐ Digging
11 ☐ Other ...

In diagram below show distances of well from road and lot line. Indicate north by arrow.

indicate north by arrow.

Roger Stevens DR.

Address

3rd Line RD

Trst. 416

Pumped well for 49 hrs until clear

227611

| | |
|---------------------------|-------------------------------|
| Name of Well Contractor | Well Contractor's License No. |
| B. MOORE Well Drilling | 6455 |
| Address | |
| Box 436 OSGOOD ONT KOA 2W | |
| Name of Well Technician | Well Technician's Licence No. |
| Bob MOORE | T-0319 |
| Signature of Technician | Submission date |
| Bob Moore | 17 01 2001 |
| | day mo yr |

| | | | | | | |
|-------------------|--------------------|---------------|-------|---------------|-------|----|
| MINISTRY USE ONLY | Data source | 58 Contractor | 59-62 | Date received | 63-66 | 80 |
| | | 64 55 | | MAR 01 2001 | | |
| | Date of inspection | Inspector | | | | |
| Remarks | | | | | | |
| CSS.ES1 | | | | | | |

Print only in spaces provided.

Mark correct box with a checkmark, where applicable.

11

1532449

Municipality

Con.

03

Plan # 4 15004 CAN 11773

| | | | |
|--------------------------------|--|--|---|
| County or District O'Hanlon | Township/Borough/City/Town/Village North Limerick | Con block tract survey, etc. 3 block 21 | Lot 5 |
| Owner's surname Hans and Jo | First Name Construct | Address North Limerick 2160 | Date completed 24/1/01 day month year |

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)

[illegible]

31

32

10 14 15 21 32 43 54 65 75 8

| 41 | | WATER RECORD | | | | 42 | |
|-----------------------|---|---|---|-----------------------------------|----|----|--|
| Water found at - feet | | Kind of water | | | | | |
| 10-13 70 | 1 | <input checked="" type="checkbox"/> Fresh | 3 | <input type="checkbox"/> Sulphur | 14 | | |
| | 2 | <input type="checkbox"/> Salty | 4 | <input type="checkbox"/> Minerals | | | |
| 15-18 | 1 | <input type="checkbox"/> Fresh | 3 | <input type="checkbox"/> Sulphur | 19 | | |
| | 2 | <input type="checkbox"/> Salty | 4 | <input type="checkbox"/> Minerals | | | |
| 20-23 | 1 | <input type="checkbox"/> Fresh | 3 | <input type="checkbox"/> Sulphur | 24 | | |
| | 2 | <input type="checkbox"/> Salty | 4 | <input type="checkbox"/> Minerals | | | |
| 25-28 | 1 | <input type="checkbox"/> Fresh | 3 | <input type="checkbox"/> Sulphur | 29 | | |
| | 2 | <input type="checkbox"/> Salty | 4 | <input type="checkbox"/> Minerals | | | |
| 30-33 | 1 | <input type="checkbox"/> Fresh | 3 | <input type="checkbox"/> Sulphur | 34 | | |
| | 2 | <input type="checkbox"/> Salty | 4 | <input type="checkbox"/> Minerals | | | |

| 51 CASING & OPEN HOLE RECORD | | | | | |
|------------------------------|---|-----------------------|--------------|-------------|--|
| Inside diam inches | Material | Wall thickness inches | Depth - feet | | |
| | | | From | To | |
| 10-11 8 3/4" | <input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input checked="" type="checkbox"/> Open hole <input type="checkbox"/> Plastic | 12 | 0 | 13-16 48 | |
| 17-18 6 7/8" | <input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic | 19 | +2 | 20-23 48 | |
| 24-25 6" | <input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic | 26 | 48 | 27-30 85 | |

| | | | | | | |
|---------------|--------------------------------|-------|----------|------------------------|--------|-------|
| SCREEN | Sizes of opening (Slot No.) | 31-33 | Diameter | 34-35 | Length | 39-40 |
| | | | inches | | feet | |
| | Material and type | | | Depth at top of screen | 41-44 | 35 |
| | | | | feet | | 36 |

| | | | |
|---|-------|---|--|
| 61 | | PLUGGING & SEALING RECORD | |
| <input checked="" type="checkbox"/> Annular space | | <input type="checkbox"/> Abandonment | |
| Depth set at - feet | | Material and type (Cement grout, bentonite, etc.) | |
| From | To | | |
| 10-33 | 78 | Cement Grout | |
| 18-21 | 22-25 | | |
| 26-29 | 30-33 | 80 | |

| | | | | | | |
|--------------|---|------------------|--|--|---|--|
| PUMPING TEST | Pumping test method ¹⁰ <input type="checkbox"/> Pump <input checked="" type="checkbox"/> Bailor | | Pumping rate ¹¹⁻¹⁴ 12 GPM | | Duration of pumping ¹⁵⁻¹⁸ 1 Hours 0 Mins | |
| | Static level | | Water level end of pumping ²⁵ | | Water levels during <input type="checkbox"/> Pumping <input checked="" type="checkbox"/> Recovery | |
| | 19-21 25 feet | 22-24 85 feet | 15 minutes ²⁶⁻²⁸ 25 feet | 30 minutes ²⁹⁻³¹ 25 feet | 45 minutes ³²⁻³⁴ 25 feet | 60 minutes ³⁵⁻³⁷ 25 feet |
| | If flowing give rate ³⁸⁻⁴¹ GPM | | Pump intake set at ⁴² 85 feet | | Water at end of test ⁴³ <input type="checkbox"/> Clear <input checked="" type="checkbox"/> Cloudy | |
| | Recommended pump type ⁴⁶⁻⁴⁹ <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep | | Recommended pump setting ⁵⁰⁻⁵³ 75 feet | | Recommended pump rate ⁵⁴⁻⁵⁷ 10 GPM | |

| | | | |
|--|---|--|----|
| FINAL STATUS OF WELL | | | 54 |
| 1 <input checked="" type="checkbox"/> Water supply | 5 <input type="checkbox"/> Abandoned, insufficient supply | 9 <input type="checkbox"/> Unfinished | |
| 2 <input type="checkbox"/> Observation well | 6 <input type="checkbox"/> Abandoned, poor quality | 10 <input type="checkbox"/> Replacement well | |
| 3 <input type="checkbox"/> Test hole | 7 <input type="checkbox"/> Abandoned (Other) | | |
| 4 <input type="checkbox"/> Recharge well | 8 <input type="checkbox"/> Dewatering | | |

| | | |
|--|---|------------------------------------|
| WATER USE | | 55-56 |
| 1 <input checked="" type="checkbox"/> Domestic | 5 <input type="checkbox"/> Commercial | 9 <input type="checkbox"/> Not use |
| 2 <input type="checkbox"/> Stock | 6 <input type="checkbox"/> Municipal | 10 <input type="checkbox"/> Other |
| 3 <input type="checkbox"/> Irrigation | 7 <input type="checkbox"/> Public supply | |
| 4 <input type="checkbox"/> Industrial | 8 <input type="checkbox"/> Cooling & air conditioning | |

| | | |
|--|---|-------------------------------------|
| METHOD OF CONSTRUCTION | | 57 |
| 1 <input type="checkbox"/> Cable tool | 5 <input type="checkbox"/> Air percussion | 9 <input type="checkbox"/> Driving |
| 2 <input type="checkbox"/> Rotary (conventional) | 6 <input type="checkbox"/> Boring | 10 <input type="checkbox"/> Digging |
| 3 <input type="checkbox"/> Rotary (reverse) | 7 <input type="checkbox"/> Diamond | 11 <input type="checkbox"/> Other |
| 4 <input checked="" type="checkbox"/> Rotary (air) | 8 <input type="checkbox"/> Jetting | |

LOCATION OF WELL

In diagram below show distances of well from road and lot line.
Indicate north by arrow.

Gower

↑ N

Rye Shales Lane

+ R All wood P...

80' *

232401

| | |
|---|---|
| Name of Well Contractor <i>Gilles Bourgeois well drill</i> | Well Contractor's Licence No. <i>14/14</i> |
| Address <i>St-Alexbert</i> | |
| Name of Well Technician <i>Jacques Raymond</i> | Well Technician's Licence No. <i>0264</i> |
| Signature of Technician/Contractor <i>Gilles Bourgeois</i> | Submission date <i>24 10 01</i> day mo yr |

| | | | | | |
|-------------------|--------------------|---------------|-------|---------------|-------|
| MINISTRY USE ONLY | Data source | 58 Contractor | 59-62 | Date received | 63-68 |
| | | 1414 | | NOV 02 2001 | |
| | Date of inspection | Inspector | | | |
| | Remarks | | | | |



The Ontario Water Resources Act

WATER WELL RECORD

Print only in spaces provided.

Mark correct box with a checkmark, where applicable.

11

1532710

Municipality **15004** Con. **CON** **03**

| | | | | |
|---------------------------------------|--|---|----------|-------|
| County or District Ottawa Carleton | Township/Borough/City/Town/Village Rideau | Con block tract survey, etc. 3 | Lot 1 | 25-27 |
| Address Northower, Ont | | Date completed 04 04 02 day month year | | |

21

1 2

0
T
M

10 12 13 14 15 16 17

Northing

18 19 20 21 22 23 24

RC

Elevation

25 26 27 28 29 30

Basin Code

ii iii iv

31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)

[illegible]

31

32

| 41 | | 10 | | 14 | | 15 | | 21 | |
|-----------------------|--|----|---------------|---|---|-----------------------------------|----|----|--|
| WATER RECORD | | | | | | | | | |
| Water found at - feet | | | Kind of water | | | | | | |
| 10-13 | | | 1 | <input checked="" type="checkbox"/> Fresh | 3 | <input type="checkbox"/> Sulphur | 14 | | |
| 142 | | | 2 | <input type="checkbox"/> Salty | 4 | <input type="checkbox"/> Minerals | 15 | | |
| 15-18 | | | 1 | <input type="checkbox"/> Fresh | 3 | <input type="checkbox"/> Gas | 19 | | |
| | | | 2 | <input type="checkbox"/> Salty | 4 | <input type="checkbox"/> Minerals | | | |
| | | | | | 6 | <input type="checkbox"/> Gas | | | |
| 20-23 | | | 1 | <input type="checkbox"/> Fresh | 3 | <input type="checkbox"/> Sulphur | 24 | | |
| | | | 2 | <input type="checkbox"/> Salty | 4 | <input type="checkbox"/> Minerals | | | |
| | | | | | 6 | <input type="checkbox"/> Gas | | | |
| 25-28 | | | 1 | <input type="checkbox"/> Fresh | 3 | <input type="checkbox"/> Sulphur | 29 | | |
| | | | 2 | <input type="checkbox"/> Salty | 4 | <input type="checkbox"/> Minerals | | | |
| | | | | | 6 | <input type="checkbox"/> Gas | | | |
| 30-33 | | | 1 | <input type="checkbox"/> Fresh | 3 | <input type="checkbox"/> Sulphur | 34 | | |
| | | | 2 | <input type="checkbox"/> Salty | 4 | <input type="checkbox"/> Minerals | | | |
| | | | | | 6 | <input type="checkbox"/> Gas | | | |

| CASING & OPEN HOLE RECORD | | | | |
|---------------------------|---|-----------------------|--------------|-----|
| Inside diam inches | Material | Wall thickness inches | Depth - feet | |
| | | | From | To |
| 10-11 6 $\frac{1}{4}$ | <input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic | 12 188 | 0 | 46 |
| 17-18 8 $\frac{3}{4}$ | <input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input checked="" type="checkbox"/> Open hole <input type="checkbox"/> Plastic | 19 | 0 | 44 |
| 24-25 6 | <input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input checked="" type="checkbox"/> Open hole <input type="checkbox"/> Plastic | 26 | 44 | 150 |

| | | | | | | |
|---------------|--------------------------------|-------|------------------------|-------|--------|-------|
| SCREEN | 54 | 60 | 75 | 86 | | |
| | Sizes of opening (Slot No.) | 31-33 | Diameter | 34-38 | Length | 39-40 |
| | | | inches | | feet | |
| | Material and type | | Depth at top of screen | | 30 | |
| | | | 41-44 | | | |
| | | | feet | | | |

| | | | |
|---|-------|---|--|
| 61 | | PLUGGING & SEALING RECORD | |
| <input checked="" type="checkbox"/> Annular space | | <input type="checkbox"/> Abandonment | |
| Depth set at - feet | | Material and type (Cement grout, bentonite, etc.) | |
| From | To | | |
| 10-13 | 14-17 | bentonite | |
| 24-26 | 27-29 | | |
| 30-32 | 33-35 | | |
| 36-38 | 39-41 | 80 | |

| | | | | | | |
|--|---|--|--|---|---|--|
| PUMPING TEST | Pumping test method ¹⁰ 1 <input checked="" type="checkbox"/> Pump 2 <input type="checkbox"/> Bailer | | Pumping rate ¹¹⁻¹⁴ 20 GPM | | Duration of pumping ¹⁵⁻¹⁸ 1 Hours ¹⁷⁻¹⁸ Mins | |
| | Static level | | Water level end of pumping ²⁵ | | Water levels during 1 <input type="checkbox"/> Pumping 2 <input checked="" type="checkbox"/> Recovery | |
| | ¹⁹⁻²¹ 8 feet | | ²²⁻²⁴ 70 feet | | ²⁶⁻²⁸ 15 minutes 8 feet | |
| | | | ²⁹⁻³¹ 30 minutes 8 feet | | ³²⁻³⁴ 45 minutes 8 feet | |
| | | | | | ³⁵⁻³⁷ 60 minutes 8 feet | |
| | If flowing give rate ³⁸⁻⁴¹ | | Pump intake set at | | Water at end of test ⁴² | |
| GPM | | feet | | <input type="checkbox"/> Clear <input checked="" type="checkbox"/> Cloudy | | |
| Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep | | Recommended pump setting ⁴³⁻⁴⁵ 70 feet | | Recommended pump rate ⁴⁶⁻⁴⁹ 20 GPM | | |
| ⁵⁰⁻⁵³ | | | | | | |

| | | | |
|--|---|--|----|
| FINAL STATUS OF WELL | | | 54 |
| 1 <input checked="" type="checkbox"/> Water supply | 5 <input type="checkbox"/> Abandoned, insufficient supply | 9 <input type="checkbox"/> Unfinished | |
| 2 <input type="checkbox"/> Observation well | 6 <input type="checkbox"/> Abandoned, poor quality | 10 <input type="checkbox"/> Replacement well | |
| 3 <input type="checkbox"/> Test hole | 7 <input type="checkbox"/> Abandoned (Other) | | |
| 4 <input type="checkbox"/> Recharge well | 8 <input type="checkbox"/> Dewatering | | |

| | | | |
|--|---|---|-------|
| WATER USE | | | 55-56 |
| 1 <input checked="" type="checkbox"/> Domestic | 5 <input type="checkbox"/> Commercial | 9 <input type="checkbox"/> Not use | |
| 2 <input type="checkbox"/> Stock | 6 <input type="checkbox"/> Municipal | 10 <input type="checkbox"/> Other | |
| 3 <input type="checkbox"/> Irrigation | 7 <input type="checkbox"/> Public supply | | |
| 4 <input type="checkbox"/> Industrial | 8 <input type="checkbox"/> Cooling & air conditioning | | |

| | | | |
|--|--|---|----|
| METHOD OF CONSTRUCTION | | | 57 |
| 1 <input type="checkbox"/> Cable tool | 5 <input checked="" type="checkbox"/> Air percussion | 9 <input type="checkbox"/> Driving | |
| 2 <input type="checkbox"/> Rotary (conventional) | 6 <input type="checkbox"/> Boring | 10 <input type="checkbox"/> Digging | |
| 3 <input type="checkbox"/> Rotary (reverse) | 7 <input type="checkbox"/> Diamond | 11 <input type="checkbox"/> Other | |
| 4 <input type="checkbox"/> Rotary (air) | 8 <input type="checkbox"/> Jetting | | |

LOCATION OF WELL

In diagram below show distances of well from road and lot line.
Indicate north by arrow.


↑ N

100'

← 11 Km

Trailwood.

237826

| | |
|--|--|
| Name of Well Contractor A. Koch Drilling Ltd | Well Contractor's Licence No. 1119 |
| Address RR #1 Richmond, Ont | |
| Name of Well Technician Shannon Purcell | Well Technician's Licence No. T2122 |
| Signature of Technician/Contractor  | Submission date 10 day 04 mo 02 yr |

| | | | | | | | |
|-------------------|--------------------|---------|------------|-------|---------------|-------|----|
| MINISTRY USE ONLY | Data source | 58 | Contractor | 59-62 | Date received | 63-68 | 69 |
| | | | 1119 | | APR 15 2002 | | |
| | Date of inspection | | Inspector | | | | |
| | Remarks | CSS.ES2 | | | | | |

Print only in spaces provided.

Mark correct box with a checkmark, where applicable.

11

1533234

Municipality
15009

Con.

| | | | | |
|--|---|---|-------------------------|-------|
| County or District <i>Ottawa Carleton</i> | Township/Borough/City/Town/Village <i>Osgood</i> | Con block tract survey, etc. <i>PLAN 4/M-773</i> | Lot <i>8</i> | 25-27 |
| Address <i>2180 TRAILWOOD DRIVE North Gower</i> | | Date completed <i>01/10/62</i> | 48-53 day month year | |

Figure 1 illustrates the data structure for the 1997-1998 season. The diagram shows a grid of data points for 21 basins (1-21) across four time points (I, II, III, IV). The basins are grouped into four categories: Normal (1-10), No (11-17), Elevation (18-20), and No (21). The time points are labeled I, II, III, and IV. The diagram shows that data is available for all basins in all time points, except for basin 21 which has data only in time point I.

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)

[illegible]

| 41 | | 10 14 15 21 | | | | WATER RECORD | |
|-----------------------|---|-------------------------------------|--------------------------|-----|--------------------------|---------------------|----|
| Water found at - feet | | Kind of water | | | | | |
| 10-13 <i>80</i> | 1 | <input checked="" type="checkbox"/> | Fresh | 3 | <input type="checkbox"/> | Sulphur | 14 |
| | 2 | <input type="checkbox"/> | Salty | 4 | <input type="checkbox"/> | Minerals | |
| | | 6 | <input type="checkbox"/> | Gas | | | |
| 15-18 | 1 | <input type="checkbox"/> | Fresh | 3 | <input type="checkbox"/> | Sulphur | 19 |
| | 2 | <input type="checkbox"/> | Salty | 4 | <input type="checkbox"/> | Minerals | |
| | | 6 | <input type="checkbox"/> | Gas | | | |
| 20-23 | 1 | <input type="checkbox"/> | Fresh | 3 | <input type="checkbox"/> | Sulphur | 24 |
| | 2 | <input type="checkbox"/> | Salty | 4 | <input type="checkbox"/> | Minerals | |
| | | 6 | <input type="checkbox"/> | Gas | | | |
| 25-28 | 1 | <input type="checkbox"/> | Fresh | 3 | <input type="checkbox"/> | Sulphur | 29 |
| | 2 | <input type="checkbox"/> | Salty | 4 | <input type="checkbox"/> | Minerals | |
| | | 6 | <input type="checkbox"/> | Gas | | | |
| 30-33 | 1 | <input type="checkbox"/> | Fresh | 3 | <input type="checkbox"/> | Sulphur | 34 |
| | 2 | <input type="checkbox"/> | Salty | 4 | <input type="checkbox"/> | Minerals | |
| | | 6 | <input type="checkbox"/> | Gas | | | |

| CASING & OPEN HOLE RECORD | | | | |
|---------------------------|---|-----------------------|--------------|----|
| Inside diam inches | Material | Wall thickness inches | Depth - feet | |
| | | | From | To |
| 10-11 8 3/4" | <input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input checked="" type="checkbox"/> Open hole <input type="checkbox"/> Plastic | | 0 | 45 |
| 17-18 6 1/4" | <input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic | 1.88 | + 2 | 45 |
| 24-25 6" | <input type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input checked="" type="checkbox"/> Open hole <input type="checkbox"/> Plastic | | 45 | 90 |

| | | | | | | |
|--------|--------------------------------|-------|----------|------------------------|--------|-------|
| SCREEN | Sizes of opening (Slot No.) | 31-33 | Diameter | 34-38 | Length | 39-40 |
| | | | inches | | feet | |
| | Material and type | | | Depth at top of screen | | |
| | | | feet | | | |

| | | | | |
|---|-------|---|--------------------------------------|--|
| 61 | | | PLUGGING & SEALING RECORD | |
| <input checked="" type="checkbox"/> Annular space | | | <input type="checkbox"/> Abandonment | |
| Depth set at - feet | | Material and type (Cement grout, bentonite, etc.) | | |
| From | To | | | |
| 10-13 | 14-17 | Cement Grout | | |
| 18-21 | 22-25 | | | |
| 26-29 | 30-33 | | | |
| | | 80 | | |

| | | | | | | |
|--------------|--|--|---|--|--|--|
| PUMPING TEST | 71 Pumping test method ¹⁰ 1 <input type="checkbox"/> Pump <u>A</u> <input checked="" type="checkbox"/> <u>A</u> ² Water | | Pumping rate ¹¹⁻¹⁴ <u>7</u> GPM | | Duration of pumping ¹⁵⁻¹⁶ <u>1</u> Hours <u>2</u> ¹⁷⁻¹⁸ Mins | |
| | Static level | | 25 Water level end of pumping | | Water levels during 1 <input type="checkbox"/> Pumping 2 <input checked="" type="checkbox"/> <u>Recovery</u> | |
| | 19-21 <u>18</u> feet | | 22-24 <u>90</u> feet | | 15 minutes ²⁶⁻²⁸ <u>24</u> feet | |
| | | | 30 minutes ²⁹⁻³¹ <u>22</u> feet | | 45 minutes ³²⁻³⁴ <u>20</u> feet | |
| | | | 60 minutes ³⁵⁻³⁷ <u>18</u> feet | | | |
| | If flowing give rate ³⁸⁻⁴¹ GPM | | Pump intake set at <u>90</u> feet | | Water at end of test ⁴² <input type="checkbox"/> Clear <input checked="" type="checkbox"/> <u>Cloudy</u> | |
| | Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> <u>Deep</u> | | Recommended pump setting ⁴³⁻⁴⁵ <u>80</u> feet | | Recommended pump rate ⁴⁶⁻⁴⁹ <u>6</u> GPM | |
| 50-53 | | | | | | |

| | | | |
|--|---|--|----|
| FINAL STATUS OF WELL | | | 54 |
| 1 <input checked="" type="checkbox"/> Water supply | 5 <input type="checkbox"/> Abandoned, insufficient supply | 9 <input type="checkbox"/> Unfinished | |
| 2 <input type="checkbox"/> Observation well | 6 <input type="checkbox"/> Abandoned, poor quality | 10 <input type="checkbox"/> Replacement well | |
| 3 <input type="checkbox"/> Test hole | 7 <input type="checkbox"/> Abandoned (Other) | | |
| 4 <input type="checkbox"/> Recharge well | 8 <input type="checkbox"/> Dewatering | | |

| | | | |
|--|---|---|-------|
| WATER USE | | | 55-56 |
| 1 <input checked="" type="checkbox"/> Domestic | 5 <input type="checkbox"/> Commercial | 9 <input type="checkbox"/> Not use | |
| 2 <input type="checkbox"/> Stock | 6 <input type="checkbox"/> Municipal | 10 <input type="checkbox"/> Other | |
| 3 <input type="checkbox"/> Irrigation | 7 <input type="checkbox"/> Public supply | | |
| 4 <input type="checkbox"/> Industrial | 8 <input type="checkbox"/> Cooling & air conditioning | | |

| | | | |
|--|---|---|----|
| METHOD OF CONSTRUCTION | | | 57 |
| 1 <input type="checkbox"/> Cable tool | 5 <input type="checkbox"/> Air percussion | 9 <input type="checkbox"/> Driving | |
| 2 <input type="checkbox"/> Rotary (conventional) | 6 <input type="checkbox"/> Boring | 10 <input type="checkbox"/> Digging | |
| 3 <input type="checkbox"/> Rotary (reverse) | 7 <input type="checkbox"/> Diamond | 11 <input type="checkbox"/> Other | |
| 4 <input checked="" type="checkbox"/> Rotary (air) | 8 <input type="checkbox"/> Jetting | | |

LOCATION OF WELL

In diagram below show distances of well from road and lot line.
Indicate north by arrow.

N ↑

Roger Steven drive

Trailwood

Maple
Forest
Estate
Subd.

★

252700

| | |
|--|--|
| Name of Well Contractor <i>Gilles Bourgeois Woodskill</i> | Well Contractor's Licence No. <i>1414</i> |
| Address <i>St-Albert Ont.</i> | |
| Name of Well Technician <i>Jacques Raymond</i> | Well Technician's Licence No. <i>T-0264</i> |
| Signature of Technician/Contractor | Submission date day mo yr |

| | | | | | | | |
|-------------------|--------------------|----|------------|-------|---------------|-------|-------|
| MINISTRY USE ONLY | Data source | 58 | Contractor | 59-62 | Date received | 63-68 | 69-72 |
| | | | 1414 | | OCT 21 2002 | | |
| | Date of inspection | | Inspector | | | | |
| | Remarks | | | | | | |
| | CSS.ES2 | | | | | | |

Instructions for Completing Form

- For use in the Province of Ontario only. This document is a permanent legal document. Please retain for future reference.
- All Sections must be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Management Coordinator at 416-235-6203.
- All metre measurements shall be reported to 1/10th of a metre.
- Please print clearly in blue or black ink only.

Well Owner's Information and Location of Well Information

| | | | | | | | |
|--|------------------|--|----------------------------|--|------------------------------------|--|------------------------|
| First Name Hansand J | | Last Name Construction | | Mailing Address (Street Number/Name, RR, Lot, Concession) 2108 Regional Rd 8 | | | |
| County/District/Municipality City of Ottawa | | Township/City/Town/Village NORTH LOWER | | Province Ontario | Postal Code K0A 2T0 | Telephone Number (include area code) 613-838-2463 | |
| Address of Well Location (County/District/Municipality) City of Ottawa | | | | Township Osgood | | Lot 38 | Concession 4 |
| RR#/Street Number/Name 6647 Stillwood DRIVE | | | | City/Town/Village NORTH LOWER | | Site/Compartment/Block/Tract etc. Plan 4M-1209 | |
| GPS Reading | NAD 83 | Zone 18 | Easting 445173 E | Northing 4998194 | Unit Make/Model Magellan | Mode of Operation: <input type="checkbox"/> Undifferentiated <input checked="" type="checkbox"/> Averaged <input type="checkbox"/> Differentiated, specify | |

Log of Overburden and Bedrock Materials (see instructions)

| General Colour | Most common material | Other Materials | General Description | Depth From | Metres To |
|----------------|----------------------|-----------------|---------------------|------------|-----------|
| brown | fill | | Hard | 0 | 3.0 |
| gray | fill | boulders | Hard | 3.0 | 11.88 |
| gray | limestone | | layered | 11.88 | 27.43 |

| Hole Diameter | | | Construction Record | | | | Test of Well Yield | | | | |
|---------------|-----------|----------------------|-------------------------|----------|----------------------------|------------|--------------------|--|--------------|--------------------|--|
| Depth From | Metres To | Diameter Centimetres | Inside diam centimetres | Material | Wall thickness centimetres | Depth From | Metres To | Pumping test method | Draw Down | Recovery | |
| 0 | 11.88 | 22.23 | | | | | | 34H.P.S. 46 | Time min | Water Level Metres | |
| 11.88 | 27.43 | 15.55 | | | | | | Pump intake set at - (metres) 25 | Static Level | 5.10 | |
| | | | | | | | | Pumping rate - (litres/min) 60 | 1 | 5.58 | |
| | | | | | | | | Duration of pumping 1 hrs + 0 min | 2 | 5.70 | |
| | | | | | | | | Final water level end of pumping 5.90 metres | 3 | 5.73 | |
| | | | | | | | | Recommended pump type. <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep | 4 | 5.80 | |
| | | | | | | | | Recommended pump depth. 25 metres | 5 | 5.90 | |
| | | | | | | | | Recommended pump rate. (litres/min) 44 | 10 | 5.81 | |
| | | | | | | | | If flowing give rate - (litres/min) 25 | 15 | 5.86 | |
| | | | | | | | | If pumping discontinued, give reason. | 20 | 5.89 | |
| | | | | | | | | | 25 | 5.90 | |
| | | | | | | | | | 30 | 5.90 | |
| | | | | | | | | | 40 | 5.90 | |
| | | | | | | | | | 50 | 5.90 | |
| | | | | | | | | | 60 | 5.90 | |

| Plugging and Sealing Record | | | Annular space | Abandonment |
|-----------------------------|-------|---|------------------------------|-------------|
| Depth set at - Metres From | To | Material and type (bentonite slurry, neat cement slurry) etc. | Volume Placed (cubic metres) | |
| 0 | 11.88 | neat cement grout | 96 bag | |

| Method of Construction | | | |
|--|--|----------------------------------|----------------------------------|
| <input type="checkbox"/> Cable Tool | <input checked="" type="checkbox"/> Rotary (air) | <input type="checkbox"/> Diamond | <input type="checkbox"/> Digging |
| <input type="checkbox"/> Rotary (conventional) | <input type="checkbox"/> Air percussion | <input type="checkbox"/> Jetting | <input type="checkbox"/> Other |
| <input type="checkbox"/> Rotary (reverse) | <input type="checkbox"/> Boring | <input type="checkbox"/> Driving | |

| Water Use | | | |
|--|-------------------------------------|---|--------------------------------|
| <input checked="" type="checkbox"/> Domestic | <input type="checkbox"/> Industrial | <input type="checkbox"/> Public Supply | <input type="checkbox"/> Other |
| <input type="checkbox"/> Stock | <input type="checkbox"/> Commercial | <input type="checkbox"/> Not used | |
| <input type="checkbox"/> Irrigation | <input type="checkbox"/> Municipal | <input type="checkbox"/> Cooling & air conditioning | |

| Final Status of Well | | | |
|--|---|---|---|
| <input checked="" type="checkbox"/> Water Supply | <input type="checkbox"/> Recharge well | <input type="checkbox"/> Unfinished | <input type="checkbox"/> Abandoned, (Other) |
| <input type="checkbox"/> Observation well | <input type="checkbox"/> Abandoned, insufficient supply | <input type="checkbox"/> Dewatering | |
| <input type="checkbox"/> Test Hole | <input type="checkbox"/> Abandoned, poor quality | <input type="checkbox"/> Replacement well | |

| Well Contractor/Technician Information | | | |
|--|--|---|--|
| Name of Well Contractor Gilles Bougeois | | Well Contractor's Licence No. 1414 | |
| Business Address (street name, number, etc.) 5741 16th ave | | | |
| Name of Well Technician (last name, first name) SA me | | Well Technician's Licence No. 0-193 | |
| Signature of Technician/Contractor x Gilles Bougeois | | Date Submitted 04 09 16 | |

| Location of Well | |
|---|--|
| In diagram below show distances of well from road, lot line, and building. Indicate north by arrow. | |
| | |

| | |
|---|-----------------------------------|
| Audit No. 2 | Well Completed 04 09 16 |
| Was the well owner's information package delivered? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | Date Delivered 04 09 16 |

| Ministry Use Only | |
|-------------------------------------|---------------------------------------|
| Data Source | Contractor 1414 |
| Date Received AUG 30 2004 | Date of Inspection 04 09 16 |
| Remarks | Well Record Number 1534867 |

Instructions for Completing Form

- For use in the **Province of Ontario** only. This document is a permanent **legal** document. Please retain for future reference.
 • All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
 • Questions regarding completing this application can be directed to the Water Well Management Coordinator at 416-235-6203.
 • **All metre measurements shall be reported to 1/10th of a metre.**
 • Please print clearly in blue or black ink only.
- | | |
|--|--------------------------|
| | Ministry Use Only |
|--|--------------------------|

Well Owner's Information and Location of Well Information

| | | | | | | | |
|--|------------------|---|----------------------------|--|------------------------------------|---|--|
| First Name Hans and JO | | Last Name Const Ruction | | Mailing Address (Street Number/Name, RR, Lot, Concession) 72471 ont Ltd 2108 Regional Rd 8 | | | |
| County/District/Municipality City of Ottawa | | Township/City/Town/Village OS gowde | | Province Ontario | Postal Code | Telephone Number (include area code) 613-838-2463 | |
| Address of Well Location (County/District/Municipality) City of Ottawa | | | | Township OS gowde | | Lot 37 | Concession 4 |
| RR#/Street Number/Name N.A. still wood DRIVE | | | | City/Town/Village NORTH Limer | | Site/Compartment/Block/Tract etc. Plan 4M-1209 | |
| GPS Reading | NAD 83 | Zone 18 | Easting 445170 E | Northing 4998147 | Unit Make/Model McCallan | Mode of Operation: <input type="checkbox"/> Undifferentiated <input checked="" type="checkbox"/> Differentiated, specify u+m | <input checked="" type="checkbox"/> Averaged |

| | | | | | | | | | |
|---|--|----|-----|-----|-----|---|-----|-----|----|
| | | 99 | 106 | 144 | 179 | - | 111 | 101 | 11 |
| Log of Overburden and Bedrock Materials (see instructions) | | | | | | | | | |

[illegible]

| Hole Diameter | | | Construction Record | | | Test of Well Yield | | | | | | | |
|---|--------|--|---|--|----------------------------------|---------------------|-------|--|-----------------------|--------------|-----------------------|------|------|
| Depth | Metres | Diameter | Inside diam centimetres | Material | Wall thickness centimetres | Depth | | Draw Down | | Recovery | | | |
| From | To | Centimetres | | | | From | To | Time min | Water Level Metres | Time min | Water Level Metres | | |
| 0 | 10.36 | 22.23 | 15.55 | <input checked="" type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized | 0.48 | 0 | 10.36 | Pumping test method | | 3 HP sub | | | |
| 10.36 | 24.38 | 15.55 | | | | | | Pump intake set at - (metres) 1.8 | | Static Level | | 3.90 | 4.52 |
| | | | | | | | | Pumping rate - (litres/min) 60 | | 1 | 4.28 | 1 | 4.24 |
| | | | | | | | | Duration of pumping 1 hrs + 0 min | | 2 | 4.33 | 2 | 4.16 |
| | | | | | | | | Final water level end of pumping 4.52 metres | | 3 | 4.34 | 3 | 4.14 |
| | | | | | | | | Recommended pump type. <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep | | 4 | 4.37 | 4 | 4.10 |
| | | | | | | | | Recommended pump depth. 1.8 metres | | 5 | 4.57 | 5 | 4.08 |
| | | | | | | | | Recommended pump rate. 44 (litres/min) | | 10 | 4.46 | 10 | 4.05 |
| | | | | | | | | If flowing give rate - (litres/min) | | 15 | 4.46 | 15 | 4.01 |
| | | | | | | | | | | 20 | 4.51 | 20 | 4.00 |
| | | | | | | | | | | 25 | 4.54 | 25 | 4.00 |
| | | | | | | | | If pumping discontinued, give reason. | | 30 | 4.54 | 30 | 4.00 |
| | | | | | | | | | | 40 | 4.54 | 40 | 3.99 |
| | | | | | | | | | | 50 | 4.52 | 50 | 3.99 |
| | | | | | | | | | | 60 | 4.52 | 60 | 3.99 |
| Water Record | | | Screen | | | No Casing or Screen | | | | | | | |
| Water found at | Metres | Kind of Water | Outside diam | <input type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized | Slot No. | | | | | | | | |
| 24 m | | <input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other: | | | | | | | | | | | |
| | | <input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other: | | | | | | | | | | | |
| | | <input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other: | | | | | | | | | | | |
| After test of well yield, water was | | | | | | | | | | | | | |
| <input type="checkbox"/> Clear and sediment free <input type="checkbox"/> Other, specify | | | | | | | | | | | | | |
| Chlorinated <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | | | <input checked="" type="checkbox"/> Open hole | | | 10.36 | | 24.38 | | | | | |

[illegible]

| Method of Construction | | | |
|--|--|----------------------------------|----------------------------------|
| <input type="checkbox"/> Cable Tool | <input checked="" type="checkbox"/> Rotary (air) | <input type="checkbox"/> Diamond | <input type="checkbox"/> Digging |
| <input type="checkbox"/> Rotary (conventional) | <input type="checkbox"/> Air percussion | <input type="checkbox"/> Jetting | <input type="checkbox"/> Other |
| <input type="checkbox"/> Rotary (reverse) | <input type="checkbox"/> Boring | <input type="checkbox"/> Driving | |

| Water Use | | | |
|--|-------------------------------------|---|--------------------------------|
| <input checked="" type="checkbox"/> Domestic | <input type="checkbox"/> Industrial | <input type="checkbox"/> Public Supply | <input type="checkbox"/> Other |
| <input type="checkbox"/> Stock | <input type="checkbox"/> Commercial | <input type="checkbox"/> Not used | |
| <input type="checkbox"/> Irrigation | <input type="checkbox"/> Municipal | <input type="checkbox"/> Cooling & air conditioning | |

| Final Status of Well | | | |
|--|---|---|---|
| <input checked="" type="checkbox"/> Water Supply | <input type="checkbox"/> Recharge well | <input type="checkbox"/> Unfinished | <input type="checkbox"/> Abandoned, (Other) |
| <input type="checkbox"/> Observation well | <input type="checkbox"/> Abandoned, insufficient supply | <input type="checkbox"/> Dewatering | |
| <input type="checkbox"/> Test Hole | <input type="checkbox"/> Abandoned, poor quality | <input type="checkbox"/> Replacement well | |

| Well Contractor/Technician Information | | |
|---|-------------------------------|--|
| Name of Well Contractor | Well Contractor's Licence No. | |
| Gilles Bourgeois | 1414 | |
| Business Address (street name, number, city etc.) | | |
| 5111 16th Ave | | |
| Name of Well Technician (last name, first name) | Well Technician's Licence No. | |
| SA me | 0-193 | |
| Signature of Technician/Contractor | Date Submitted | |
| G. Gilles | YYMMDD 04/08/16 | |

| Location of Well | | | |
|--|---|---------------------|--|
| <p>In diagram below show distances of well from road, lot line, and building. Indicate north by arrow.</p> | | | |
| Audit No. | Z 12198 | Date Well Completed | YYYY 04 MM 08 DD 16 |
| Was the well owner's information package delivered? | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Date Delivered | YYYY 04 MM 08 DD 16 |

| Ministry Use Only | | | | |
|-------------------|------|--------------------|----|--------------------|
| Data Source | | Contractor | | |
| | | 1414 | | |
| Date Received | YYYY | MM | DD | Date of Inspection |
| | 2004 | 03 | 08 | |
| Remarks | | Well Record Number | | |
| | | 1534868 | | |



022904

Well Record

Regulation 903 Ontario Water Resources Act

page _____ of _____

Instructions for Completing Form

- For use in the **Province of Ontario** only. This document is a permanent **legal** document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Management Coordinator at 416-235-6203.
- **All metre measurements shall be reported to 1/10th of a metre.**
- Please print clearly in blue or black ink only.

Well Owner's Information and Location of Well Information

MUN

CON

LOT

| | | | | | | | |
|--|--|------------|--|---|--|---|--|
| Street Number/Name * 2134 TRAILWOOD DRIVE | | | | City/Town/Village NORTH GOWER | | Site/Compartment/Block/Tract/etc. PLAN 4M-113, S/L 9 | |
| Grids Reading NAD 8 3 | | Zone 18 | | Easting 445119 | | Northing 4998321 | |
| Unit Make/Model MAGELLAN | | | | Mode of Operation: <input type="checkbox"/> Undifferentiated <input checked="" type="checkbox"/> Averaged <input type="checkbox"/> Differentiated, specify | | | |

Log of Overburden and Bedrock Materials (see instructions)

[illegible]

| Hole Diameter | | | Construction Record | | | | Test of Well Yield | | | | | |
|---------------|--------|-------------|----------------------------|----------|----------------------------------|-------|--------------------|--------------------------------------|--------------|-----------------------|-------------|-----------------------|
| Depth | Metres | Diameter | Inside diam centimetres | Material | Wall thickness centimetres | Depth | | Pumping test method | Draw Down | | Recovery | |
| From | To | Centimetres | | | | From | To | | Time min | Water Level Metres | Time min | Water Level Metres |
| 0 | 36.54 | 15.23 | | | | | | Sub pump | Static Level | 6.88 | | 7.05 |
| | | | | | | | | Pump intake set at - (metres) | 1 | 7.77 | 1 | 7.06 |
| | | | | | | | | Pumping rate - (litres/min) | 2 | 7.23 | 2 | 7.95 |
| | | | | | | | | Duration of pumping | 3 | 7.23 | 3 | 7.90 |
| | | | | | | | | Final water level end of pumping | 4 | 7.03 | 4 | 7.88 |
| | | | | | | | | Recommended pump type | 5 | 7.23 | 5 | |
| | | | | | | | | Recommended pump depth | 10 | 7.23 | 10 | |
| | | | | | | | | Recommended pump rate | 15 | 7.23 | 15 | |
| | | | | | | | | If flowing give rate - (litres/min) | 20 | 7.23 | 20 | |
| | | | | | | | | If pumping discontinued, give reason | 25 | 7.23 | 25 | |
| | | | | | | | | | 30 | 7.23 | 30 | |
| | | | | | | | | | 40 | 7.24 | 40 | |
| | | | | | | | | | 50 | 7.24 | 50 | |
| | | | | | | | | | 60 | 7.23 | 60 | |

| Water Record | | | |
|---|---|--|--|
| Water found at | Kind of Water | | |
| 33.32 m | <input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur | | |
| <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals | | | |
| <input type="checkbox"/> Other: | | | |
| | <input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur | | |
| <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals | | | |
| <input type="checkbox"/> Other: | | | |
| After test of well yield, water was | | | |
| <input type="checkbox"/> Clear and sediment free | | | |
| <input type="checkbox"/> Other, specify | | | |
| Chlorinated <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | | | |

| Casing | | | |
|---------------------|---|----------|---------|
| 15.88 | <input checked="" type="checkbox"/> Steel <input type="checkbox"/> Fibreglass | .48 | 0 17.37 |
| | <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete | | |
| | <input type="checkbox"/> Galvanized | | |
| | <input type="checkbox"/> Steel <input type="checkbox"/> Fibreglass | | |
| | <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete | | |
| | <input type="checkbox"/> Galvanized | | |
| | <input type="checkbox"/> Steel <input type="checkbox"/> Fibreglass | | |
| | <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete | | |
| | <input type="checkbox"/> Galvanized | | |
| Screen | | | |
| Outside diam | <input type="checkbox"/> Steel <input type="checkbox"/> Fibreglass | Slot No. | |
| | <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete | | |
| | <input type="checkbox"/> Galvanized | | |
| No Casing or Screen | | | |
| | <input checked="" type="checkbox"/> Open hole | 16.76 | 36.57 |

| Plugging and Sealing Record | | <input checked="" type="checkbox"/> Annular space | <input type="checkbox"/> Abandonment |
|-------------------------------|-------|---|--------------------------------------|
| Depth set at - Metres From | To | Material and type (bentonite slurry, neat cement slurry) etc. | Volume Placed (cubic metres) |
| 11.76 | 13.71 | NEAT CEMENT SLURRY | - 454 |
| 13.71 | 0 | BENTONITE SLURRY | - 123 |
| | | | |
| | | | |
| | | | |

| Method of Construction | | | |
|--|--|----------------------------------|----------------------------------|
| <input type="checkbox"/> Cable Tool | <input type="checkbox"/> Rotary (air) | <input type="checkbox"/> Diamond | <input type="checkbox"/> Digging |
| <input type="checkbox"/> Rotary (conventional) | <input checked="" type="checkbox"/> Air percussion | <input type="checkbox"/> Jetting | <input type="checkbox"/> Other |
| <input type="checkbox"/> Rotary (reverse) | <input checked="" type="checkbox"/> Boring | <input type="checkbox"/> Driving | |


| Water Use | | | |
|--|-------------------------------------|---|--------------------------------|
| <input checked="" type="checkbox"/> Domestic | <input type="checkbox"/> Industrial | <input type="checkbox"/> Public Supply | <input type="checkbox"/> Other |
| <input type="checkbox"/> Stock | <input type="checkbox"/> Commercial | <input type="checkbox"/> Not used | |
| <input type="checkbox"/> Irrigation | <input type="checkbox"/> Municipal | <input type="checkbox"/> Cooling & air conditioning | |

| Final Status of Well | | | |
|--|---|---|---|
| <input checked="" type="checkbox"/> Water Supply | <input type="checkbox"/> Recharge well | <input type="checkbox"/> Unfinished | <input type="checkbox"/> Abandoned, (Other) |
| <input type="checkbox"/> Observation well | <input type="checkbox"/> Abandoned, insufficient supply | <input type="checkbox"/> Dewatering | |
| <input type="checkbox"/> Test Hole | <input type="checkbox"/> Abandoned, poor quality | <input type="checkbox"/> Replacement well | |

| Well Contractor/Technician Information | |
|--|--|
| Name of Well Contractor AIRLOCK DRILLING CO LTD | Well Contractor's Licence No. TU119 |
| Business Address (street name, number, city etc.) RR#1 RICHMOND ONT K0A2Z0 | |
| Name of Well Technician (last name, first name) HOSEAN DAN | Well Technician's Licence No. T3058 |
| Signature of Technician/Contractor [Signature] | Date Submitted yyyy mm dd 2050502 |

Location of Well

In diagram below show distances of well from road, lot line, and building. Indicate north by arrow.



| | |
|---|---------------------------------------|
| Audit No. Z 23248 | Date Well Completed 2005 04 27 |
| Was the well owner's information package delivered? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | Date Delivered 2005 04 27 |

| Ministry Use Only | | | |
|-------------------|--------------------|----|----|
| Data Source | Contractor | | |
| Date Received | YYYY | MM | DD |
| JUN 06 2005 | | | |
| Remarks | Well Record Number | | |

Instructions for Completing Form

page ____ of ____

- For use in the **Province of Ontario** only. This document is a permanent **legal** document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Management Coordinator at 416-235-6203.
- All metre measurements shall be reported to 1/10th of a metre.
- Please print clearly in blue or black ink only.

Well Owner's Information and Location of Well Information

| Ministry Use Only | | | | | | | | | |
|-------------------|--|--|--|--|--|--|--|-----|-----|
| MUN | | | | | | | | CON | LOT |
| | | | | | | | | | |

City/Town/Village **City of Ottawa** North Corner **39**

RR#/Street Number/Name **6643 5011 Wood DR.** City/Town/Village **NORTH Corner** Site/Compartment/Block/Tract etc. **Plan 4 M-1209**

GPS Reading **8.3** NAD **18** Zone **44** Easting **5174 E** Northing **4998222** Unit Make/Model **Magellan** Mode of Operation: ☐ Undifferentiated ☒ Averaged ☐ Differentiated, specify

Log of Overburden and Bedrock Materials (see instructions)

| General Colour | Most common material | Other Materials | General Description | Depth From | Metres To |
|----------------|----------------------|-----------------|---------------------|------------|-----------|
| Brown | fill | boulders | Hard | 0 | 4.26 |
| grey | fill | boulders | Hard | 4.26 | 9.14 |
| grey | 11 m. stone | | Fracture | 9.14 | 11.27 |
| grey | 11 m. stone | | layered | 11.27 | 27.43 |

| Hole Diameter | | | Construction Record | | | | Test of Well Yield | | | | | |
|---------------|-----------|----------------------|-------------------------|------------|----------------------------|------------|--------------------|--|--------------------|--------------------|-------------------|--------------------|
| Depth From | Metres To | Diameter Centimetres | Inside diam centimetres | Material | Wall thickness centimetres | Depth From | Metres To | Pumping test method | Draw Down Time min | Water Level Metres | Recovery Time min | Water Level Metres |
| 0 | 11.27 | 21.23 | | | | | | 2. H.P. sub | | | | |
| 11.27 | 27.43 | 15.55 | 15.55 | Steel | 0.48 | +0.60 | 11.27 | Pump intake set at (metres) 15 | 1 | 3.36 | 1 | 3.93 |
| | | | | Plastic | | | | Pumping rate - (litres/min) 40 | 2 | | 2 | |
| | | | | Galvanized | | | | Duration of pumping 1 hrs + 0 min | 3 | 3.70 | 3 | 3.36 |
| | | | | | | | | Final water level end of pumping 2.93 metres | 4 | 3.78 | 4 | |
| | | | | | | | | Recommended pump type. <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep | 5 | 3.83 | 5 | |
| | | | | | | | | Recommended pump depth. 15 metres | 10 | 3.93 | 10 | |
| | | | | | | | | Recommended pump rate. 40 (litres/min) | 15 | 3.93 | 15 | |
| | | | | | | | | If flowing give rate - (litres/min) | 20 | 3.93 | 20 | |
| | | | | | | | | | 25 | 3.93 | 25 | |
| | | | | | | | | If pumping discontinued, give reason. | 30 | 3.93 | 30 | |
| | | | | | | | | | 40 | 3.93 | 40 | |
| | | | | | | | | | 50 | 3.93 | 50 | |
| | | | | | | | | | 60 | 3.93 | 60 | |

| Plugging and Sealing Record | | | |
|-----------------------------|-----------|---|------------------------------|
| Depth set at - Metres From | Metres To | Material and type (bentonite slurry, neat cement slurry) etc. | Volume Placed (cubic metres) |
| 0 | 11.27 | neat cement slurry | 6 Bags |

| Method of Construction | | | |
|--|--|----------------------------------|----------------------------------|
| <input type="checkbox"/> Cable Tool | <input checked="" type="checkbox"/> Rotary (air) | <input type="checkbox"/> Diamond | <input type="checkbox"/> Digging |
| <input type="checkbox"/> Rotary (conventional) | <input type="checkbox"/> Air percussion | <input type="checkbox"/> Jetting | <input type="checkbox"/> Other |
| <input type="checkbox"/> Rotary (reverse) | <input type="checkbox"/> Boring | <input type="checkbox"/> Driving | |

| Water Use | | | |
|--|-------------------------------------|---|--------------------------------|
| <input checked="" type="checkbox"/> Domestic | <input type="checkbox"/> Industrial | <input type="checkbox"/> Public Supply | <input type="checkbox"/> Other |
| <input type="checkbox"/> Stock | <input type="checkbox"/> Commercial | <input type="checkbox"/> Not used | |
| <input type="checkbox"/> Irrigation | <input type="checkbox"/> Municipal | <input type="checkbox"/> Cooling & air conditioning | |

| Final Status of Well | | | |
|--|---|---|---|
| <input checked="" type="checkbox"/> Water Supply | <input type="checkbox"/> Recharge well | <input type="checkbox"/> Unfinished | <input type="checkbox"/> Abandoned, (Other) |
| <input type="checkbox"/> Observation well | <input type="checkbox"/> Abandoned, insufficient supply | <input type="checkbox"/> Dewatering | |
| <input type="checkbox"/> Test Hole | <input type="checkbox"/> Abandoned, poor quality | <input type="checkbox"/> Replacement well | |

| Well Contractor/Technician Information | |
|---|--|
| Name of Well Contractor Gilles Bourgeois | Well Contractor's Licence No. 1414 |
| Business Address (street name, number, city etc.) 5011 Wood DR. | |
| Name of Well Technician (last name, first name) Claude Boucher | Well Technician's Licence No. 3310 |
| Signature of Technician/Contractor C. Boucher | Date Submitted 05/11/18 |

| Location of Well | | | |
|---|--|--|--|
| In diagram below show distances of well from road, lot line, and building. Indicate north by arrow. | | | |
| | | | |
| Audit No. Z 40061 | Date Well Completed 05/11/18 | | |
| Was the well owner's information package delivered? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Date Delivered 05/11/18 | | |

| Ministry Use Only | | | |
|-------------------------------------|---------------------------------------|--|--|
| Data Source | Contractor 1414 | | |
| Date Received DEC 20 2005 | Date of Inspection 05/11/18 | | |
| Remarks | Well Record Number | | |

A 035451

A035451

Instructions for Completing Form

- For use in the **Province of Ontario** only. This document is a permanent **legal** document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Management Coordinator at 416-235-6203.
- All metre measurements shall be reported to 1/10th of a metre.**
- Please print clearly in blue or black ink only.

Well Owner's Information and Location of Well Information

| MUN | | | | CON | | | | LOT | | | |
|-----|--|--|--|-----|--|--|--|-----|--|--|--|
| | | | | | | | | | | | |

Ministry Use Only

| | | |
|---|--|---|
| Ottawa Carleton RR#/Street Number/Name | Rideau - North Gower City/Town/Village | 19/20 4 Site/Compartment/Block/Tract etc. |
| Stillwood Drive, Maple Forest GPS Reading | North Gower Unit Make/Model | Mode of Operation: <input type="checkbox"/> Undifferentiated <input checked="" type="checkbox"/> Averaged <input type="checkbox"/> Differentiated, specify _____ |
| NAD Zone Easting Northing | | |
| 8 3 18 44 51 45 499 82 79 | Garmin | |

Log of Overburden and Bedrock Materials (see instructions)

| General Colour | Most common material | Other Materials | General Description | Depth Metres | |
|----------------|----------------------|------------------|---------------------|--------------|-------|
| | | | | From | To |
| Brown | Hardpan | Boulders | Packed | 0 | 9.14 |
| Gray | Sand & Gravel | | | 9.14 | 12.19 |
| Gray | Hardpan | | | 12.19 | 13.71 |
| Gray | Limestone | Sandstone Layers | Hard | 13.71 | 52.72 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

| Hole Diameter | | | Construction Record | | | | Test of Well Yield | | | |
|--|-----------|----------------------|--|----------|----------------------------|------------|---------------------|---------------------|-----------|----------|
| Depth From | Metres To | Diameter Centimetres | Inside diam centimetres | Material | Wall thickness centimetres | Depth From | Metres To | Pumping test method | Draw Down | Recovery |
| 0 | 17.98 | 22.75 | | | | | | | | |
| 17.98 | 52.72 | 15.23 | | | | | | | | |
| Water Record | | | Casing | | | | Static Level | | | |
| Water found at Metres / Kind of Water | | | 15.86 <input checked="" type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized .48 + .45 17.98 | | | | 1 5.61 | | | |
| 51.50 <input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other: not tested | | | | | | | 2 6.17 1 5.57 | | | |
| | | | | | | | 3 6.23 2 5.57 | | | |
| | | | | | | | 4 6.26 3 5.57 | | | |
| | | | | | | | 5 6.26 4 5.64 | | | |
| | | | | | | | 6 6.28 5 5.64 | | | |
| | | | | | | | 7 6.29 6 5.63 | | | |
| | | | | | | | 8 6.30 7 5.63 | | | |
| | | | | | | | 9 6.30 8 5.62 | | | |
| | | | | | | | 10 6.32 9 5.62 | | | |
| | | | | | | | 11 6.33 10 5.61 | | | |
| | | | | | | | 12 6.34 11 5.61 | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

Instructions for Completing Form

- For use in the **Province of Ontario** only. This document is a permanent **legal** document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Help Desk (Toll Free) at 1-888-396-9355.
- All metre measurements shall be reported to 1/10th of a metre.**
- Please print clearly in blue or black ink only.

Well Owner's Information and Location of Well Information

| Ministry Use Only | | | | | | | | | |
|-------------------|--|--|--|--|--|--|--|-----|-----|
| MUN | | | | | | | | CON | LOT |
| | | | | | | | | | |

| | | | | | | | | | | | |
|------------------------|--|-----|------|-------------------|--|-----------|--|-----------------------------------|--|---|--|
| Ottawa Carleton | | | | Rideau | | | | 21 | | 3 | |
| RR#/Street Number/Name | | | | City/Town/Village | | | | Site/Compartment/Block/Tract etc. | | | |
| Lot 36, Maple Forest | | | | North Gower | | | | | | | |
| GPS Reading | | NAD | Zone | Easting | | Northing | | Unit Make/Model | | Mode of Operation: | |
| 8 3 | | 18 | | 44 51 85 | | 49 981 12 | | Garmin | | <input type="checkbox"/> Undifferentiated <input checked="" type="checkbox"/> Averaged <input type="checkbox"/> Differentiated, specify | |

Log of Overburden and Bedrock Materials (see instructions)

| General Colour | Most common material | Other Materials | General Description | Depth From | Metres To |
|----------------|----------------------|-----------------|---------------------|------------|-----------|
| Brown | Soil | Stones | Packed | 0 | 3.65 |
| Gray | Sandy Soil | | Packed | 3.65 | 7.01 |
| Gray | Hardpan | | Packed | 7.01 | 10.05 |
| Gray | Limestone | | Medium | 10.05 | 29.86 |
| Gray & White | Sandstone | | Hard | 29.86 | 48.76 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

| Hole Diameter | | |
|---------------|-----------|----------------------|
| Depth From | Metres To | Diameter Centimetres |
| 0 | 11.88 | 22.75 |
| 11.88 | 48.76 | 15.07 |

| Water Record | |
|--|--|
| Water found at Metres | Kind of Water |
| 46.63 | <input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other: not tested |
| | <input type="checkbox"/> m <input type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other: |
| After test of well yield, water was | |
| <input checked="" type="checkbox"/> Clear and sediment free <input type="checkbox"/> Other, specify | |
| Chlorinated <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | |

| Construction Record | | | | |
|----------------------------|--|----------------------------|------------|-----------|
| Inside diam centimetres | Material | Wall thickness centimetres | Depth From | Metres To |
| Casing | | | | |
| 15.86 | <input checked="" type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized | .48 | + .45 | 11.88 |
| Screen | | | | |
| Outside diam | <input type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized | Slot No. | | |
| No Casing or Screen | | | | |
| 15.07 | <input checked="" type="checkbox"/> Open hole | | 11.88 | 48.76 |

| Test of Well Yield | | | | |
|-------------------------------------|---|--------------------|----------|--------------------|
| Pumping test method | Draw Down | Recovery | | |
| | Time min | Water Level Metres | Time min | Water Level Metres |
| submersible | | | | |
| Pump intake set at - (metres) | 42.66 | Static Level | 3.78 | |
| Pumping rate - (litres/min) | 72.80 | 1 | 5.87 | 1 8.91 |
| Duration of pumping | 2 hrs + min | 2 | 6.22 | 2 6.10 |
| Final water level end of pumping | 13.66 metres | 3 | 7.01 | 3 4.87 |
| Recommended pump type | <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep | 4 | 7.95 | 4 4.25 |
| Recommended pump depth | 22.85 metres | 5 | 8.64 | 5 3.96 |
| Recommended pump rate | 45.5 (litres/min) | 10 | 9.57 | 10 3.78 |
| If flowing give rate - (litres/min) | | 15 | 11.46 | 15 3.77 |
| | | 20 | 12.29 | 20 3.78 |
| | | 25 | 12.53 | 25 3.78 |
| | | 30 | 12.65 | 30 3.78 |
| | | 40 | 13.47 | 40 3.78 |
| | | 50 | 13.54 | 50 3.78 |
| | | 60 | 13.58 | 60 3.78 |

| Plugging and Sealing Record | | |
|-----------------------------|---|------------------------------|
| Depth set at - Metres | Material and type (bentonite slurry, neat cement slurry) etc. | Volume Placed (cubic metres) |
| 11.88 | 0 Grouted - Cement Slurry | .42m3 |
| | | |
| | | |
| | | |
| | | |

| Method of Construction | | | |
|--|---|---|---|
| <input type="checkbox"/> Cable Tool | <input checked="" type="checkbox"/> Rotary (air) | <input type="checkbox"/> Diamond | <input type="checkbox"/> Digging |
| <input type="checkbox"/> Rotary (conventional) | <input checked="" type="checkbox"/> Air percussion | <input type="checkbox"/> Jetting | <input type="checkbox"/> Other |
| <input type="checkbox"/> Rotary (reverse) | <input type="checkbox"/> Boring | <input type="checkbox"/> Driving | |
| Water Use | | | |
| <input checked="" type="checkbox"/> Domestic | <input type="checkbox"/> Industrial | <input type="checkbox"/> Public Supply | <input type="checkbox"/> Other |
| <input type="checkbox"/> Stock | <input type="checkbox"/> Commercial | <input type="checkbox"/> Not used | |
| <input type="checkbox"/> Irrigation | <input type="checkbox"/> Municipal | <input type="checkbox"/> Cooling & air conditioning | |
| Final Status of Well | | | |
| <input checked="" type="checkbox"/> Water Supply | <input type="checkbox"/> Recharge well | <input type="checkbox"/> Unfinished | <input type="checkbox"/> Abandoned, (Other) |
| <input type="checkbox"/> Observation well | <input type="checkbox"/> Abandoned, insufficient supply | <input type="checkbox"/> Dewatering | |
| <input type="checkbox"/> Test Hole | <input type="checkbox"/> Abandoned, poor quality | <input type="checkbox"/> Replacement well | |

| Well Contractor/Technician Information | |
|---|-------------------------------|
| Name of Well Contractor | Well Contractor's Licence No. |
| Capital Water Supply Ltd. | 1558 |
| Business Address (street name, number, city etc.) | |
| Box 490 Stittsville, Ontario K2S 1A6 | |
| Name of Well Technician (last name, first name) | Well Technician's Licence No. |
| Miller, Stephen | T0097 |
| Signature of Technician/Contractor | Date Submitted |
| | 2006 11 03 |

| Location of Well | |
|---|---------------------|
| In diagram below show distances of well from road, lot line, and building. Indicate north by arrow. | |
| | |
| Audit No. | Date Well Completed |
| Z 58707 | 2006 11 02 |
| Was the well owner's information package delivered? | Date Delivered |
| <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | 2006 11 02 |

| Ministry Use Only | |
|-------------------|--------------------|
| Data Source | Contractor |
| | 1558 |
| Date Received | Date of Inspection |
| JAN 25 2007 | |
| Remarks | Well Record Number |
| | |

Instructions for Completing Form

- For use in the **Province of Ontario** only. This document is a permanent **legal** document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Help Desk (Toll Free) at 1-888-396-9355.
- All metre measurements shall be reported to 1/10th of a metre.**
- Please print clearly in blue or black ink only.

Ministry Use Only

Address of Well Location (County/District/Municipality)

Ottawa - Carleton

Township

Rideau

Lot

20

Concession

3

RR# / Street Number / Name

2121 Roger Stevens

City / Town / Village

North Gower

Site / Compartment / Block / Tract etc.

GPS Reading

NAD

8 3

Zone

18

Easting

444967

Northing

4998642

Unit Make / Model

Mogellon

Mode of Operation:

☐ Undifferentiated

☒ Averaged

☐ Differentiated, specify

Log of Overburden and Bedrock Materials (see instructions)

| General Colour | Most common material | Other Materials | General Description | Depth | | Metres |
|----------------|----------------------|-----------------|---------------------|-------|-------|--------|
| | | | | From | To | |
| | Sand, Boulders | | | 0 | 12.19 | 12.19 |
| | Gray Limestone | | | 12.19 | 36.57 | 36.57 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Hole Diameter

Depth

Metres

Diameter

From

To

Centimetres

0 36.57 14.59

Water Record

Water found at

Metres

36

Kind of Water

☒ Fresh
 ☐ Sulphur
 ☐ Gas
 ☐ Salty
 ☐ Minerals
 ☐ Other:

TESTED

Construction Record

Inside diam

Material

Wall thickness

Depth

Metres

centimetres

centimetres

From

To

15.88

☒ Steel
 ☐ Fibreglass
 ☐ Plastic
 ☐ Concrete
 ☐ Galvanized

48 0 16.46

Casing

☐ Steel
 ☐ Fibreglass
 ☐ Plastic
 ☐ Concrete
 ☐ Galvanized

Screen

Outside diam

☐ Steel
 ☐ Fibreglass
 ☐ Plastic
 ☐ Concrete
 ☐ Galvanized

Slot No.

No Casing or Screen

☒ Open hole

15.85 36.57

Test of Well Yield

Pumping test method

Draw Down

Recovery

Sub Pump

Time min

Water Level Metres

Time min

Water Level Metres

Pump intake set at (metres)

Static Level

1

2

3

4

5

10

15

20

25

30

40

50

60

2.75

5.24

6.20

7.06

7.67

8.22

9.48

9.89

10.36

10.40

10.48

10.48

10.50

10.50

10.50

5.73

3.69

2.75

Duration of pumping

1 hrs + 0 min

Final water level end of pumping

metres

10.50

Recommended pump type

☐ Shallow
 ☒ Deep

Recommended pump depth

metres

30.48

Recommended pump rate

(litres/min)

9.1

If flowing give rate

(litres/min)

If pumping discontinued, give reason

Plugging and Sealing Record

☒ Annular space
 ☐ Abandonment

Depth set at - Metres

Material and type (bentonite slurry, neat cement slurry) etc.

Volume Placed (cubic metres)

From

To

15.85 12.80

Neat Cement Slurry .227

12.80 0

Bentonite Slurry .613

Method of Construction

☐ Cable Tool
 ☐ Rotary (air)
 ☐ Diamond
 ☐ Digging
 ☐ Rotary (conventional)
 ☒ Air percussion
 ☐ Jetting
 ☐ Other
 ☐ Rotary (reverse)
 ☐ Boring
 ☐ Driving

Water Use

☒ Domestic
 ☐ Industrial
 ☐ Public Supply
 ☐ Other
 ☐ Stock
 ☐ Commercial
 ☐ Not used
 ☐ Irrigation
 ☐ Municipal
 ☐ Cooling & air conditioning

Final Status of Well

☒ Water Supply
 ☐ Recharge well
 ☐ Unfinished
 ☐ Abandoned, (Other)
 ☐ Observation well
 ☐ Abandoned, insufficient supply
 ☐ Dewatering
 ☐ Test Hole
 ☐ Abandoned, poor quality
 ☐ Replacement well

Well Contractor/Technician Information

Name of Well Contractor

Well Contractor's Licence No.

Business Address (street name, number, city etc.)

RR#1 Richmond Ont L6A2Z0

Name of Well Technician (last name, first name)

Well Technician's Licence No.

Signature of Technician/Contractor

Date Submitted

Desautels Ken

14

2007 07 27

Location of Well

In diagram below show distances of well from road, lot line, and building. Indicate north by arrow.

Audit No.

Date Well Completed

Z 65105

2007 06 28

Was the well owner's information package delivered?

Date Delivered

☒ Yes ☐ No

2007 06 28

Ministry Use Only

Data Source

Contractor

Date Received

Date of Inspection

Remarks

Well Record Number

AUG 07 2007

11119

Measurements recorded in: ☒ Metric ☐ Imperial

Well Owner's Information

| | | | | |
|---|--|-----------------------------|------------------------------|---|
| First Name <i>Mary and</i> | Last Name / Organization <i>Jo Construction</i> | E-mail Address <i>NA</i> | | <input type="checkbox"/> Well Constructed by Well Owner |
| Mailing Address (Street Number/Name) <i>6639 Stillwood Drive</i> | Municipality <i>North York</i> | Province <i>Ontario</i> | Postal Code <i>K0A2E0</i> | Telephone No. (inc. area code) <i>613 838 2463</i> |

Well Location

| | | | | |
|---|------|----------------------------------|---------------------|----------------------------------|
| Address of Well Location (Street Number/Name) 6639 Stillwood Drive | | Township Osgood (Rideau) | Lot 4021 | Concession 3 |
| County/District/Municipality Ottawa | | City/Town/Village North Gower | Province Ontario | Postal Code K0A2T0 |
| UTM Coordinates | Zone | Easting | Northing | Municipal Plan and Sublot Number |
| NAD | 8 | 3 | 118445166 | 4998242 |
| | | 4m 1209- Lot 40 | | |
| | | Other | | |

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

| General Colour | Most Common Material | Other Materials | General Description | Depth (m/ft) | |
|----------------|----------------------|-----------------|---------------------|--------------|-------|
| | | | | From | To |
| Brown | Clay | Silt, Boulder | Hard | 0 | 4.6 |
| Grey | Clay | Silt, Boulder | Hard | 4.6 | 10.2 |
| Grey | gravel | | packed | 10.2 | 10.9 |
| Grey | limestone | | layered | 10.9 | 30.48 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

Annular Space

| Depth Set at (m/ft) | | Type of Sealant Used (Material and Type) | Volume Placed (m ³ /ft ³) |
|---------------------|------|---|---|
| From | To | | |
| 0 | 12.8 | Ciment grout | 10 Bag |
| | | | |
| | | | |

Results of Well Yield Testing

| Draw Down | | Recovery | |
|--------------|--------------------|------------|--------------------|
| Time (min) | Water Level (m/ft) | Time (min) | Water Level (m/ft) |
| Static Level | 4.84 | | 7.69 |
| 1 | 6.05 | 1 | 5.56 |
| 2 | 6.58 | 2 | 4.95 |
| 3 | 6.90 | 3 | 4.84 |
| 4 | 7.00 | 4 | 4.84 |
| 5 | 7.14 | 5 | |
| 10 | 7.40 | 10 | |
| 15 | 7.54 | 15 | |
| 20 | 7.56 | 20 | |
| 25 | 7.54 | 25 | |
| 30 | 7.60 | 30 | |
| 40 | 7.60 | 40 | |
| 50 | 7.61 | 50 | |
| 60 | 7.69 | 60 | |

Construction Record - Casing

| Inside Diameter (cm/in) | Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel) | Wall Thickness (cm/in) | Depth (m/ft) | | <input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned |
|----------------------------|---|---------------------------|--------------|-------|--|
| | | | From | To | |
| 15.55 | Steel | 0.48 | 4.6 | 12.8 | |
| 15.55 | open Hole | | 12.8 | 30.48 | |
| | | | | | |

Status of Well

☒ Water Supply
☐ Replacement Well
☐ Test Hole
☐ Recharge Well
☐ Dewatering Well
☐ Observation and/or Monitoring Hole
☐ Alteration (Construction)
☐ Abandoned, Unidentified Supply
☐ Abandoned, Poor Water Quality
☐ Abandoned, other, specify _____
☐ Other, specify _____

Construction Record - Screen

| Outside Diameter (cm/in) | Material (Plastic, Galvanized, Steel) | Slot No. | Depth (m/ft) | |
|-----------------------------|--|----------|--------------|----|
| | | | From | To |
| | | | | |
| | | | | |
| | | | | |

☐ Abandoned, Poor Water Quality
☐ Abandoned, other, specify _____
☐ Other, specify _____


Water Details

| | |
|--|---|
| Water found at Depth 26 (m/ft) <input type="checkbox"/> Gas | Kind of Water: <input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Other, specify |
| Water found at Depth (m/ft) <input type="checkbox"/> Gas | Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Other, specify |
| Water found at Depth (m/ft) <input type="checkbox"/> Gas | Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Other, specify |

Hole Diameter

| Depth (m/ft) | | Diameter (cm/in) |
|--------------|-------|------------------|
| From | To | |
| 0 | 12.8 | 21.23 |
| 12.8 | 30.48 | 15.55 |

Well Contractor and Well Technician Information

| | | | |
|---------------------------------------|---|-------------------------------|--|
| Business Name of Well Contractor | | Well Contractor's Licence No. | |
| Bourgeois's well Drilling | | 11414 | |
| Business Address (Street Number/Name) | | Municipality | |
| 1182 900 East | | Nation | |
| Province | Postal Code | Business E-mail Address | |
| Ontario | K0A3C0 | NA | |
| Bus. Telephone No. (inc. area code) | Name of Well Technician (Last Name, First Name) | | |
| 6139875291 | Michael Genier | | |
| Well Technician's Licence No. | Signature of Technician and/or Contractor | Date Submitted | |
| 3493 |  | 2008/11/28 | |

Map of Well Location

Please provide a map below following instructions on the back.

A hand-drawn map of the study area. At the top, a horizontal line is labeled "North Groyne". Below this line, a vertical line is labeled "Trashwood". To the right of the "Trashwood" line, a horizontal line is labeled "300m". Below the "300m" line, a vertical line is labeled "Stillwood". To the right of the "Stillwood" line, a horizontal line is labeled "1 km". A small circle is labeled "well". On the far right, the number "416" is written vertically.

Comments:

Well owner's information package delivered

☐ Yes

☒ No

Date Package Delivered
Y Y Y Y M M D
Date Work Completed
2008 11 2

Ministry Use Only

Audit No. **Z 90529**

Received

Ministry of
the Environment

A113230

W _____ (Print Below)

Well Record

Regulation 903 Ontario Water Resources Act

Measurements recorded in: ☐ Metric ☒ Imperial

Page _____ of _____

Well Owner's Information

| | | | |
|---|--|-----------------------|---|
| First Name | Last Name / Organization Grizzly Homes | E-mail Address | <input type="checkbox"/> Well Constructed by Well Owner |
| Mailing Address (Street Number/Name) PO Box 422, RR#4 | Municipality Ashton | Province On | Postal Code K0A 1B0 |

Well Location

| | | | |
|---|---|--|------------------------|
| Address of Well Location (Street Number/Name) 2134 Maple Forest Drive | Township Rideau | Lot 21 | Concession 3 |
| County/District/Municipality Ottawa-Carleton | City/Town/Village North Gower | Province Ontario | Postal Code |
| UTM Coordinates Zone Easting NAD 8 3 18 445224 | Northings 4998033 | Municipal Plan and Sublot Number 4M-1209 | Other S/L 32 |

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

| General Colour | Most Common Material | Other Materials | General Description | Depth (m/ft) |
|----------------|----------------------|-----------------|---------------------|--------------|
| | | | | From To |
| | Sand & Gravel | Boulders | | 0' 30' |
| Grey + Brown | Limestone | | | 30' 88' |
| Grey + Brown | Limestone | | | 88' 157' |
| Grey + Brown | Limestone | | | 157' 162' |

| Annular Space | | | Volume Placed (m³) |
|---------------------|--|--|--------------------|
| Depth Set at (m/ft) | Type of Sealant Used (Material and Type) | | |
| 40' 0' | Neat cement slurry | | 26.5 |

| Method of Construction | Well Use |
|--|---|
| <input type="checkbox"/> Cable Tool <input type="checkbox"/> Rotary (Conventional) <input type="checkbox"/> Rotary (Reverse) <input type="checkbox"/> Boring <input checked="" type="checkbox"/> Air percussion <input type="checkbox"/> Other, specify | <input type="checkbox"/> Public <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Livestock <input type="checkbox"/> Irrigation <input type="checkbox"/> Industrial <input type="checkbox"/> Other, specify <input type="checkbox"/> Commercial <input type="checkbox"/> Municipal <input type="checkbox"/> Test Hole <input type="checkbox"/> Cooling & Air Conditioning <input type="checkbox"/> Not used <input type="checkbox"/> Dewatering <input type="checkbox"/> Monitoring |

| Construction Record - Casing | | | Status of Well | |
|------------------------------|--|------------------------|----------------|--|
| Inside Diameter (cm/in) | Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel) | Wall Thickness (cm/in) | Depth (m/ft) | |
| 6" | Steel | .188" | +2' 40' | <input checked="" type="checkbox"/> Water Supply |
| 515/16" | Open Hole | | 40' 162' | <input type="checkbox"/> Replacement Well |

| Construction Record - Screen | | | Status of Well | |
|------------------------------|---------------------------------------|----------|----------------|------------------------------------|
| Outside Diameter (cm/in) | Material (Plastic, Galvanized, Steel) | Slot No. | Depth (m/ft) | |
| | | | From To | <input type="checkbox"/> Test Hole |

| Water Details | | Hole Diameter | |
|--|--|---------------|------------------|
| Water found at Depth | Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested | Depth (m/ft) | Diameter (cm/in) |
| 88 (m/ft) <input type="checkbox"/> Gas <input checked="" type="checkbox"/> Other, specify | | From To | |
| Water found at Depth | Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested | 0' 40' | 6" |
| 157 (m/ft) <input type="checkbox"/> Gas <input checked="" type="checkbox"/> Other, specify | | 40' 162' | 515/16" |
| Water found at Depth | Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested | | |
| (m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify | | | |

| Well Contractor and Well Technician Information | |
|---|--|
| Business Name of Well Contractor Air Rock Drilling Co. Ltd. | Well Contractor's Licence No. 1119 |
| Business Address (Street Number/Name) 6659 Franktown Road, RR#1 | Municipality Richmond |
| Province ON | Postal Code K0A 2Z0 |
| Business E-mail Address air-rock@sympatico.ca | |

| | | |
|--|--|-------------------------------------|
| Bus. Telephone No. (inc. area code) 6138382170 | Name of Well Technician (Last Name, First Name) Hogan, Dan | Date Submitted 2011 03 31 |
| Well Technician's Licence No. T3058 | Signature of Technician and/or Contractor | |

| Results of Well Yield Testing | | | |
|---|--|--------------|--------------------|
| After test of well yield, water was: | | Draw Down | |
| <input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify Not tested | | Time (min) | Water Level (m/ft) |
| If pumping discontinued, give reason: | | Static Level | 28.9' |
| Pump intake set at (m/ft) 140' | | 1 15.5 | 1 17.3 |
| Pumping rate (l/min / GPM) 12 | | 2 18.5 | 2 9.2 |
| Duration of pumping 1 hrs + 0 min | | 3 21.5 | 3 9.2 |
| Final water level end of pumping (m/ft) 28.9' | | 4 24.6 | 4 9.2 |
| If flowing give rate (l/min / GPM) | | 5 27.7 | 5 9.2 |
| Recommended pump depth (m/ft) 100' | | 10 27.9 | 10 9.2 |
| Recommended pump rate (l/min / GPM) 12 | | 15 28 | 15 9.2 |
| Well production (l/min / GPM) 12 | | 20 28.1 | 20 9.2 |
| Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | | 25 28.2 | 25 9.2 |
| | | 30 28.2 | 30 9.2 |
| | | 40 28.4 | 40 9.2 |
| | | 50 28.7 | 50 9.2 |
| | | 60 28.9 | 60 9.2 |

Map of Well Location

Please provide a map below following instructions on the back.

Roger Stevens Drive

Trailwood Drive 1KM

Maple Forest 50'

#2134 Maple Forest Drive

Comments:

| | | |
|--|---|--------------------------------|
| Well owner's information package delivered <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | Date Package Delivered 20110325 | Ministry Use Only |
| Date Work Completed 20110328 | Audit No. z119813 | Received APR 26 2011 |

| | | | | |
|---|--------------------------|---|--|------------------------|
| Address of Well Location (Street Number/Name) 2130 Maple Forest Drive | | Township Rideau | Lot 21 | Concession 3 |
| County/District/Municipality Ottawa-Carleton | | City/Town/Village North Gower | Province Ontario | Postal Code |
| UTM Coordinates Zone 18 | Easting 445253 | Northing 4998049 | Municipal Plan and Sublot Number 4M-1209 | Other S/L 33 |

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

| General Colour | Most Common Material | Other Materials | General Description | Depth (m/ft) |
|----------------|----------------------|-----------------|---------------------|--------------|
| | Sand & Gravel | Clay | | 0' 26' |
| Grey | Limestone | | | 26' 68' |
| Grey | Limestone | | | 68' 156' |
| Grey | Limestone | | | 156' 162' |

| Annular Space | | |
|---------------------|--|------------------------|
| Depth Set at (m/ft) | Type of Sealant Used (Material and Type) | Volume Placed (m³/gal) |
| 36' 0' | Neat cement slurry | 20.3 |

| Method of Construction | Well Use |
|--|--|
| <input type="checkbox"/> Cable Tool <input type="checkbox"/> Rotary (Conventional) <input type="checkbox"/> Rotary (Reverse) <input type="checkbox"/> Boring <input checked="" type="checkbox"/> Air percussion <input type="checkbox"/> Other, specify | <input type="checkbox"/> Public <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Livestock <input type="checkbox"/> Irrigation <input type="checkbox"/> Industrial <input type="checkbox"/> Other, specify |

| Construction Record - Casing | | | Status of Well | |
|------------------------------|--|------------------------|----------------|------|
| Inside Diameter (cm/in) | Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel) | Wall Thickness (cm/in) | Depth (m/ft) | |
| 6" | Steel | .188 | +2' | 36' |
| 515/16" | Open Hole | | 36' | 162' |

| Construction Record - Screen | | | Status of Well | |
|------------------------------|---------------------------------------|----------|----------------|----|
| Outside Diameter (cm/in) | Material (Plastic, Galvanized, Steel) | Slot No. | Depth (m/ft) | |
| | | | From | To |

| Water Details | | Hole Diameter | |
|-----------------------------|--|---------------|------------------|
| Water found at Depth (m/ft) | Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested | Depth (m/ft) | Diameter (cm/in) |
| 68' (n/ft) | <input type="checkbox"/> Gas <input checked="" type="checkbox"/> Other, specify | From | To |
| 156' (n/ft) | <input type="checkbox"/> Gas <input checked="" type="checkbox"/> Other, specify | 0' 36' | 6" |
| | <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify | 36' 162' | 515/16" |

| Well Contractor and Well Technician Information | |
|---|--|
| Business Name of Well Contractor Air Rock Drilling Co. Ltd. | Well Contractor's Licence No. 1119 |
| Business Address (Street Number/Name) 6659 Franktown Road, RR#1 | Municipality Richmond |

| | | |
|--|---|---|
| Province ON | Postal Code K0A 2Z0 | Business E-mail Address air-rock@sympatico.ca |
| Bus. Telephone No. (inc. area code) 6138382170 | | |
| Name of Well Technician (Last Name, First Name) Hogan, Dan | | |
| Well Technician's Licence No. T3058 | Signature of Technician and/or Contractor | Date Submitted 2011 03 31 |

| Results of Well Yield Testing | | | |
|---|--------------|--------------------|------------|
| After test of well yield, water was: | Draw Down | Recovery | |
| <input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify Not tested | Time (min) | Water Level (m/ft) | Time (min) |
| If pumping discontinued, give reason: | Static Level | 6.8' | 10.7' |
| Pump intake set at (m/ft) 140' | 1 | 9.3 | 6.8 |
| Pumping rate (l/min / GPM) 20 | 2 | 10.7 | 6.8 |
| Duration of pumping 1 hrs + 0 min | 3 | 10.7 | 6.8 |
| Final water level end of pumping (m/ft) 10.7' | 4 | 10.7 | 6.8 |
| If flowing give rate (l/min / GPM) | 5 | 10.7 | 6.8 |
| Recommended pump depth (m/ft) 100' | 10 | 10.7 | 6.8 |
| Recommended pump rate (l/min / GPM) 20 | 15 | 10.7 | 6.8 |
| Well production (l/min / GPM) 20+ | 20 | 10.7 | 6.8 |
| Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | 25 | 10.7 | 6.8 |
| | 30 | 10.7 | 6.8 |
| | 40 | 10.7 | 6.8 |
| | 50 | 10.7 | 6.8 |
| | 60 | 10.7 | 6.8 |

Map of Well Location

Please provide a map below following instructions on the back.

Rogar Stevens Drive

Trailwood Drive 1KM

45'

#2130

Maple Forest Drive

Comments: **Maple Forest Drive**

| | | |
|---|---|--|
| Well owner's information package delivered <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | Date Package Delivered 2011 03 25 | Date Work Completed 2011 03 23 |
|---|---|--|

| Ministry Use Only | |
|-----------------------------|--------------------------------|
| Audit No. z119812 | Received APR 26 2011 |



Ontario

Ministry of
the Environment

Well Tag No. (Place Sticker and/or Print Below)

A117425

Well Record

Regulation 903 Ontario Water Resources Act

Measurements recorded in: ☐ Metric ☒ Imperial

Page _____ of _____

Well Owner's Information

| | | | |
|--|--|-----------------------|--|
| First Name 1504107 Ontario Inc | Last Name / Organization da Lockwood Brothers Construction | E-mail Address | <input checked="" type="checkbox"/> Well Constructed by Well Owner |
| Mailing Address (Street Number/Name) 2010 Totem Ranch Road | Municipality Oxford Station | Province ON | Postal Code K0G 1T0 |
| Telephone No. (inc. area code) 613 258 4225 | | | |

Well Location

| | | | |
|---|---|----------------------------|--|
| Address of Well Location (Street Number/Name) 2127 Rodger Stevens Drive | Township Rideau | Lot 20 | Concession 3 |
| County/District/Municipality Ottawa | City/Town/Village North Gower | Province Ontario | Postal Code K0A 2T0 |
| UTM Coordinates Zone 18 | Easting 444956 | Northing 4998590 | Municipal Plan and Sublot Number Plan 4R 16097 |
| Other | | | |

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

| General Colour | Most Common Material | Other Materials | General Description | Depth (m/ft) From | To |
|----------------|----------------------|-----------------|---------------------|----------------------|------|
| Brown | Fill | Cement | Packed | 0 | 3' |
| Brown | Clay | Stone's | Packed | 3' | 24' |
| Gray | Clay | Stone's | Packed | 24' | 47' |
| Gray | Limestone | | Hard | 47' | 115' |
| Gray | Limestone | Sandstone | Hard | 115' | 141' |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

| Annular Space | | |
|-----------------------------|-----|---|
| Depth Set at (m/ft) From | To | Type of Sealant Used (Material and Type) |
| 52' | 40' | Cement Pressure Grouted |
| 40' | 0 | Bentonite Pressure Grouted |
| | | |
| | | |
| | | |

| Method of Construction | | Well Use | | |
|---|----------------------------------|--|---|-------------------------------------|
| <input type="checkbox"/> Cable Tool | <input type="checkbox"/> Diamond | <input type="checkbox"/> Public | <input type="checkbox"/> Commercial | <input type="checkbox"/> Not used |
| <input checked="" type="checkbox"/> Rotary (Conventional) | <input type="checkbox"/> Jetting | <input checked="" type="checkbox"/> Domestic | <input type="checkbox"/> Municipal | <input type="checkbox"/> Dewatering |
| <input type="checkbox"/> Rotary (Reverse) | <input type="checkbox"/> Driving | <input type="checkbox"/> Livestock | <input type="checkbox"/> Test Hole | <input type="checkbox"/> Monitoring |
| <input type="checkbox"/> Boring | <input type="checkbox"/> Digging | <input type="checkbox"/> Irrigation | <input type="checkbox"/> Cooling & Air Conditioning | |
| <input checked="" type="checkbox"/> Air percussion | | <input type="checkbox"/> Industrial | | |
| <input type="checkbox"/> Other, specify | | <input type="checkbox"/> Other, specify | | |

| Construction Record - Casing | | | Status of Well | |
|------------------------------|---|------------------------|----------------------|------|
| Inside Diameter (cm/in) | Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel) | Wall Thickness (cm/in) | Depth (m/ft) From | To |
| 9 7/8" | Open Hole | | 0 | 52' |
| 6 1/4" | Steel | 0.188 | 0 | 52' |
| 6 1/8" | Open Hole | | 52' | 141' |
| | | | | |
| | | | | |

| | |
|--|---|
| <input type="checkbox"/> Water Supply | <input checked="" type="checkbox"/> Replacement Well |
| <input type="checkbox"/> Test Hole | <input type="checkbox"/> Recharge Well |
| <input type="checkbox"/> Dewatering Well | <input type="checkbox"/> Observation and/or Monitoring Hole |
| <input type="checkbox"/> Alteration (Construction) | <input type="checkbox"/> Abandoned, Insufficient Supply |
| <input type="checkbox"/> Abandoned, Poor Water Quality | <input type="checkbox"/> Abandoned, other, specify |
| <input type="checkbox"/> Other, specify | |

| Construction Record - Screen | | | Status of Well | |
|------------------------------|--|----------|----------------------|----|
| Outside Diameter (cm/in) | Material (Plastic, Galvanized, Steel) | Slot No. | Depth (m/ft) From | To |
| | | | | |
| | | | | |
| | | | | |

| | |
|---|--|
| <input type="checkbox"/> Other, specify | |
|---|--|

| Water Details | | Hole Diameter | |
|--|--|----------------------|------|
| Water found at Depth 128' (m/ft) | Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested | Depth (m/ft) From | To |
| | <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify | 0 | 52' |
| Water found at Depth 52' (m/ft) | Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested | 52' | 141' |
| | <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify | | |
| Water found at Depth 52' (m/ft) | Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested | | |
| | <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify | | |

| | | |
|--|--|--|
| Business Name of Well Contractor 1425486 Ontario Ltd | | Well Contractor's Licence No. 4877 |
| Business Address (Street Number/Name) PO Box 1083 | | Municipality Prescott |
| Province ON | Postal Code K0E 1T0 | Business E-mail Address |
| Telephone No. (inc. area code) 39254885 | Name of Well Technician (Last Name, First Name) Ferguson, Todd | |
| Technician's Licence No. 478 | Signature of Technician and/or Contractor Todd Ferguson | Date Submitted 2011/11/10 |

| Results of Well Yield Testing | | | |
|--|--|--------------|--------------------|
| After test of well yield, water was: <input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify | | Draw Down | |
| If pumping discontinued, give reason: | | Time (min) | Water Level (m/ft) |
| Pump intake set at (m/ft) 120' | | Static Level | 17.9 |
| Pumping rate (l/min / GPM) 21 gpm | | 1 | 18.1 |
| Duration of pumping 1 hrs + 0 min | | 2 | 18.2 |
| Final water level end of pumping (m/ft) 18.4 | | 3 | 18.3 |
| If flowing give rate (l/min / GPM) | | 4 | 18.3 |
| Recommended pump depth (m/ft) 120' | | 5 | 18.3 |
| Recommended pump rate (l/min / GPM) 10 gpm | | 10 | 18.4 |
| Well production (l/min / GPM) | | 15 | 18.4 |
| Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No 150 | | 20 | 18.4 |
| | | 25 | 18.4 |
| | | 30 | 18.4 |
| | | 40 | 18.4 |
| | | 50 | 18.4 |
| | | 60 | 18.4 |

Map of Well Location

Please provide a map below following instructions on the back.

Map of Well Location

1 Mile to North

Rodger Stevens Drive

Comments:
150 Chlorine after Drilling
0 Chlorine after Yield Test

| | | |
|--|---|--|
| Well owner's Information package delivered <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | Date Package Delivered 2011/11/04 | Date Work Completed 2011/10/26 |
|--|---|--|

| | |
|-----------------------------|--------------------------------|
| Ministry Use Only | |
| Audit No. 2138522 | Received DEC 05 2011 |



Measurements recorded in: ☐ Metric ☒ Imperial

Page of

| | | | | |
|--|------------|----------------------------------|----------------------|---|
| Address of Well Location (Street Number/Name) 2126 Maple Forest Drive | | Township Rideau | Lot 21 | Concession 3 |
| County/District/Municipality Ottawa-Carleton | | City/Town/Village North Gower | Province Ontario | Postal Code |
| UTM Coordinates NAD 83 | Zone 18 | Easting 445286 | Northings 4998074 | Municipal Plan and Sublot Number 4M-1209 |
| | | Other S/I 34 | | |

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

| General Colour | Most Common Material | Other Materials | General Description | Depth (m/ft) From | To |
|----------------|----------------------|-----------------|---------------------|----------------------|------|
| | Sandy | Clay | | 0' | 15' |
| | Gravel | Boulders | | 15' | 37' |
| Grey | Limestone | | | 37' | 162' |
| Grey | Limestone | | | 162' | 168' |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

| Annular Space | | | |
|-----------------------------|----|---|---------------------------|
| Depth Set at (m/ft) From | To | Type of Sealant Used (Material and Type) | Volume Placed (m³/ft³) |
| 47' | 0' | Neat cement | 32.8 |
| | | | |
| | | | |
| | | | |

| Method of Construction | Well Use |
|--|---|
| <input type="checkbox"/> Cable Tool <input type="checkbox"/> Rotary (Conventional) <input type="checkbox"/> Rotary (Reverse) <input type="checkbox"/> Boring <input checked="" type="checkbox"/> Air percussion <input type="checkbox"/> Other, specify | <input type="checkbox"/> Diamond <input type="checkbox"/> Jetting <input type="checkbox"/> Driving <input type="checkbox"/> Digging <input type="checkbox"/> Public <input type="checkbox"/> Commercial <input type="checkbox"/> Not used <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Municipal <input type="checkbox"/> Dewatering <input type="checkbox"/> Livestock <input type="checkbox"/> Test Hole <input type="checkbox"/> Monitoring <input type="checkbox"/> Irrigation <input type="checkbox"/> Cooling & Air Conditioning <input type="checkbox"/> Industrial <input type="checkbox"/> Other, specify |

| Construction Record - Casing | | | | Status of Well | |
|------------------------------|--|------------------------|----------------------|----------------|---|
| Inside Diameter (cm/in) | Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel) | Wall Thickness (cm/in) | Depth (m/ft) From | To | |
| 6 1/4" | Steel | .188" | +2' | 47' | <input checked="" type="checkbox"/> Water Supply |
| 5 15/16" | Open Hole | | 47' | 168' | <input type="checkbox"/> Replacement Well |
| | | | | | <input type="checkbox"/> Test Hole |
| | | | | | <input type="checkbox"/> Recharge Well |
| | | | | | <input type="checkbox"/> Dewatering Well |
| | | | | | <input type="checkbox"/> Observation and/or Monitoring Hole |
| | | | | | <input type="checkbox"/> Alteration (Construction) |
| | | | | | <input type="checkbox"/> Abandoned, Insufficient Supply |
| | | | | | <input type="checkbox"/> Abandoned, Poor Water Quality |
| | | | | | <input type="checkbox"/> Abandoned, other, specify |
| | | | | | <input type="checkbox"/> Other, specify |

| Construction Record - Screen | | | | |
|------------------------------|---------------------------------------|----------|----------------------|----|
| Outside Diameter (cm/in) | Material (Plastic, Galvanized, Steel) | Slot No. | Depth (m/ft) From | To |
| | | | | |
| | | | | |
| | | | | |

| Water Details | | Hole Diameter | |
|---|--|----------------------|------|
| Water found at Depth 162 (m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify | Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested | Depth (m/ft) From | To |
| Water found at Depth (m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify | Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested | 0' | 47' |
| Water found at Depth (m/ft) <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify | Kind of Water: <input type="checkbox"/> Fresh <input type="checkbox"/> Untested | 47' | 168' |

| | |
|--|------------------|
| | Diameter (cm/in) |
| | 9 3/4" |
| | 5 15/16" |

| Well Contractor and Well Technician Information | | | |
|--|------------------------|--|--|
| Business Name of Well Contractor Air Rock Drilling Co. Ltd. | | Well Contractor's Licence No. 1119 | |
| Business Address (Street Number/Name) 6659 Franktown Road, RR#1 | | Municipality Richmond | |
| Province ON | Postal Code K0A 2Z0 | Business E-mail Address air-rock@sympatico.ca | |
| Bus. Telephone No. (inc. area code) 613-838-2170 | | Name of Well Technician (Last Name, First Name) Hanna, Jeremy | |
| Well Technician's Licence No. T B6B2 | | Signature of Technician and/or Contractor [Signature] | |
| | | Date Submitted 2013 07 31 | |

| Results of Well Yield Testing | | | | |
|--|--------------|--------------------|------------|--------------------|
| After test of well yield, water was: <input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify Not tested | Draw Down | | Recovery | |
| | Time (min) | Water Level (m/ft) | Time (min) | Water Level (m/ft) |
| If pumping discontinued, give reason: X | Static Level | 10.4' | | 77' |
| | 1 | 14.8 | 1 | 56.3 |
| Pump intake set at (m/ft) 150 | 2 | 17.3 | 2 | 43.2 |
| Pumping rate (l/min / GPM) 20 | 3 | 19.7 | 3 | 34.6 |
| Duration of pumping 1 hrs + 0 min | 4 | 22 | 4 | 27.3 |
| Final water level end of pumping (m/ft) 77' | 5 | 24.2 | 5 | 20.9 |
| If flowing give rate (l/min / GPM) X | 10 | 33 | 10 | 10.4 |
| | 15 | 38.6 | 15 | 10.4 |
| Recommended pump depth (m/ft) 100' (3/4 HP - 157 m) | 20 | 44.2 | 20 | 10.4 |
| Recommended pump rate (l/min / GPM) 20 | 25 | 48.7 | 25 | 10.4 |
| Well production (l/min / GPM) 20 | 30 | 53.2 | 30 | 10.4 |
| Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | 40 | 62.2 | 40 | 10.4 |
| | 50 | 70 | 50 | 10.4 |
| | 60 | 77' | 60 | 10.4' |

| Map of Well Location | |
|--|--|
| Please provide a map below following instructions on the back. | |
| | |

| | |
|---|--|
| Comments: 3/4 HP - 15 GPM - SET @ 100 FT | |
| Well owner's information package delivered <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | Date Package Delivered 2013 07 30 |
| Date Work Completed 2013 07 29 | Ministry Use Only Audit No. 2155162 AUG 19 2013 |

OFFICIAL CERTIFICATE OF ANALYSIS : 4102006
WORK REQUEST : 100315477
Report Date : 2024-10-01
Paterson Group

9 Auriga Dr
Nepean, Ontario
K2E 7T9
Attention : Alex Schopf

Reception Date : 2024-09-25

Project : PH4905

Sampler : NA

PO Number : 61375

Temperature : 15 °C

| Analysis | Quantity | External Method |
|--|----------|--|
| Alkalinity (Water, Automated) | 2 | Modified from SM 2320 B |
| Ammonia, Total (Water, Colorimetry) | 2 | Modified from EPA 350.1 |
| Chloride (Water, IC) | 2 | Modified from SM 4110 B and C |
| Colour, Apparent (Water, Spectrophotometry) | 2 | Modified from SM 2120 C |
| Conductivity (Water, Automated) | 2 | Modified from SM 2510 B |
| DOC (Water, IR) | 2 | Modified from SM 5310 B |
| Escherichia coli (DC Plate) | 2 | Modified from MECP E3407 |
| Fluoride (Water, Auto/ISE) | 2 | Modified from SM 4500-F A and 4500-F C |
| Hardness (Water, Calculation Only) | 2 | SM 2340 B |
| Ion Balance (Water, Calculation) | 2 | Modified from SM1030 E |
| Metals Scan (Water, ICP/MS) | 2 | Modified from EPA 200.8 |
| Metals Scan (Water, ICP/OES) | 2 | Modified from SM 3120 B |
| Nitrate (Water, IC) | 2 | Modified from SM 4110 B and C |
| Nitrite (Water, IC) | 2 | Modified from SM 4110 B and C |
| pH (25°C) (Water, Automated) | 2 | Modified from SM 4500-H+ B |
| Phenols (Water, Colorimetry) | 2 | Modified from EPA 420.2 |
| Sulphate (Water, IC) | 2 | Modified from SM 4110 B and C |
| Sulphide (Water, Colorimetry) | 2 | Modified from SM 4500-S2 D |
| Tannin and Lignin (Water, Spec) | 2 | Modified from SM 5550 B |
| TDS (Estimated) | 2 | Modified from SM 2510 A |
| Total Coliforms (DC Plate) | 2 | Modified from MECP E3407 |
| Total Kjeldahl Nitrogen (Water, Colorimetry) | 2 | Modified from EPA 351.2 |
| Turbidity (Water, Turbidimeter) | 2 | Modified from SM 2130 B |
| VOCs (Water, GC/MS) | 1 | Modified from EPA 8260 |

Criteria :
A : Ontario Regulation 169/03 (Non-Regulated Drinking Water)

Sample status upon receipt :

8059996 8059998

Compliant
Notes :

- All analysis is completed at Eurofins Environment Testing Canada Inc. (Ottawa, Ontario) unless otherwise stated.
- Eurofins Environment Testing Canada Inc. is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on the scope of accreditation. The scope is available at <https://directory.cala.ca/>
- Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline or regulatory limits listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official guideline or regulation as required. Unless otherwise stated, measurement uncertainty is not taken into account when determining guideline or regulatory exceedances.

Legend :

RL : Reporting limit

QC : Reference material (QC)

N/A : Not applicable

1 : Results in annex

* : Analysis conducted by external subcontracting

^ : Analysis not accredited

OFFICIAL CERTIFICATE OF ANALYSIS - EXCEEDENCE SUMMARY

Client : Paterson Group
Project : PH4905

Reception Date : 2024-09-25

| Eurofins Sample No | Client Sample Identification | Analyte | Result | Units | Exceeded Criteria | | |
|---|---------------------------------|---------------------------------|--------|-------|-------------------|---|---|
| | | | | | A | B | C |
| Colour, Apparent (Water, Spectrophotometry) | | | | | | | |
| 8059996 | TW1 - GW1 | Colour (Apparent) | 6 | TCU | 5 | | |
| 8059998 | TW1 - GW2 | Colour (Apparent) | 7 | TCU | 5 | | |
| Hardness (Water, Calculation Only) | | | | | | | |
| 8059996 | TW1 - GW1 | Hardness as CaCO3 (Calculation) | 226 | mg/L | 80-100 | | |
| 8059998 | TW1 - GW2 | Hardness as CaCO3 (Calculation) | 226 | mg/L | 80-100 | | |
| Metals Scan (Water, ICP/MS) | | | | | | | |
| 8059998 | TW1 - GW2 | Iron | 0.33 | mg/L | 0.3 | | |
| TDS (Estimated) | | | | | | | |
| 8059996 | TW1 - GW1 | TDS (Estimated)^ | 508 | mg/L | 500 | | |

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Paterson Group
Project : PH4905

Reception Date: 2024-09-25

| Eurofins Sample No : | | | | 8059996 | 8059998 | | | |
|--------------------------------|-----|------|----------|-------------|-------------|------|------|--|
| Matrix : | | | | Groundwater | Groundwater | | | |
| Sampling Date : | | | | 2024-09-24 | 2024-09-24 | | | |
| Client Sample Identification : | | | | TW1 - GW1 | TW1 - GW2 | | | |
| Anions | RL | Unit | Criteria | | | | | |
| | | | A | B | C | | | |
| Chloride | 0.5 | mg/L | 250 | | | 90.2 | 85.2 | |
| Nitrate (as Nitrogen) | 0.1 | mg/L | 10.0 | | | <0.1 | <0.1 | |
| Nitrite (as Nitrogen) | 0.1 | mg/L | 1.0 | | | <0.1 | <0.1 | |
| Sulphate | 1 | mg/L | 500 | | | 47 | 47 | |

| Eurofins Sample No : | | | | 8059996 | 8059998 | | | |
|--------------------------------|-----|------|------|-------------|-------------|--|--|--|
| Matrix : | | | | Groundwater | Groundwater | | | |
| Sampling Date : | | | | 2024-09-24 | 2024-09-24 | | | |
| Client Sample Identification : | | | | TW1 - GW1 | TW1 - GW2 | | | |
| Calculations | RL | Unit | | | | | | |
| Ion Balance (Calculation)^ | 0.1 | | 1.01 | 1.00 | | | | |

| Eurofins Sample No : | | | | 8059996 | 8059998 | | | |
|---|-------|-------|----------|-------------|-------------|--------|--------|--|
| Matrix : | | | | Groundwater | Groundwater | | | |
| Sampling Date : | | | | 2024-09-24 | 2024-09-24 | | | |
| Client Sample Identification : | | | | TW1 - GW1 | TW1 - GW2 | | | |
| General Chemistry | RL | Unit | Criteria | | | | | |
| | | | A | B | C | | | |
| Alkalinity (as CaCO ₃) | 5 | mg/L | 500 | | | 229 | 236 | |
| Colour (Apparent) | 2 | TCU | 5 | | | 6 | 7 | |
| Conductivity @ 25°C | 5 | µS/cm | | | | 781 | 766 | |
| Dissolved Organic Carbon | 0.5 | mg/L | 5 | | | 0.7 | 1.1 | |
| Fluoride | 0.1 | mg/L | 1.5 | | | 0.64 | 0.63 | |
| Hardness as CaCO ₃ (Calculation) | 1 | mg/L | 80-100 | | | 226 | 226 | |
| pH @ 25°C | 1 | | 6.5-8.5 | | | 7.99 | 7.95 | |
| Phenols-4AAP | 0.001 | mg/L | | | | <0.001 | <0.001 | |
| Sulphide (S ₂ -) | 0.01 | mg/L | 0.05 | | | <0.01 | <0.01 | |
| Tannin and Lignin | 0.1 | mg/L | | | | 0.1 | <0.1 | |
| TDS (Estimated)^ | 5 | mg/L | 500 | | | 508 | 498 | |
| Turbidity | 0.1 | NTU | 5 | | | 1.6 | 2.3 | |

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Paterson Group
Project : PH4905

Reception Date: 2024-09-25

| | | | | | | | | | | |
|--------------------------------|--------|------|----------|---|---|-------------|-------------|--|--|--|
| Eurofins Sample No : | | | | | | 8059996 | 8059998 | | | |
| Matrix : | | | | | | Groundwater | Groundwater | | | |
| Sampling Date : | | | | | | 2024-09-24 | 2024-09-24 | | | |
| Client Sample Identification : | | | | | | TW1 - GW1 | TW1 - GW2 | | | |
| Metals | RL | Unit | Criteria | | | | | | | |
| | | | A | B | C | | | | | |
| Metals Scan (Water, ICP/MS) | | | | | | | | | | |
| Aluminum | 0.01 | mg/L | 0.1 | | | 0.03 | 0.01 | | | |
| Antimony | 0.0005 | mg/L | 0.006 | | | <0.0005 | <0.0005 | | | |
| Arsenic | 0.001 | mg/L | 0.01 | | | <0.001 | <0.001 | | | |
| Barium | 0.001 | mg/L | 1 | | | 0.066 | 0.062 | | | |
| Beryllium | 0.0005 | mg/L | | | | <0.0005 | <0.0005 | | | |
| Boron | 0.01 | mg/L | 5 | | | 0.20 | 0.20 | | | |
| Cadmium | 0.0001 | mg/L | 0.005 | | | <0.0001 | <0.0001 | | | |
| Chromium | 0.001 | mg/L | 0.05 | | | <0.001 | <0.001 | | | |
| Cobalt | 0.0002 | mg/L | | | | <0.0002 | <0.0002 | | | |
| Copper | 0.001 | mg/L | 1 | | | <0.001 | <0.001 | | | |
| Iron | 0.03 | mg/L | 0.3 | | | 0.19 | 0.33 | | | |
| Lead | 0.001 | mg/L | 0.01 | | | <0.001 | <0.001 | | | |
| Manganese | 0.01 | mg/L | 0.05 | | | <0.01 | <0.01 | | | |
| Mercury | 0.0001 | mg/L | 0.001 | | | <0.0001 | <0.0001 | | | |
| Molybdenum | 0.005 | mg/L | | | | <0.005 | <0.005 | | | |
| Nickel | 0.005 | mg/L | | | | <0.005 | <0.005 | | | |
| Selenium | 0.001 | mg/L | 0.05 | | | <0.001 | <0.001 | | | |
| Silver | 0.0001 | mg/L | | | | <0.0001 | <0.0001 | | | |
| Strontium | 0.001 | mg/L | | | | 1.75 | 1.77 | | | |
| Thallium | 0.0001 | mg/L | | | | <0.0001 | <0.0001 | | | |
| Uranium | 0.001 | mg/L | 0.02 | | | <0.001 | <0.001 | | | |
| Vanadium | 0.001 | mg/L | | | | <0.001 | <0.001 | | | |
| Zinc | 0.01 | mg/L | 5 | | | <0.01 | <0.01 | | | |
| Metals Scan (Water, ICP/OES) | | | | | | | | | | |
| Calcium | 1 | mg/L | | | | 42 | 42 | | | |
| Magnesium | 1 | mg/L | | | | 30 | 29 | | | |
| Potassium | 1 | mg/L | | | | 8 | 8 | | | |
| Sodium | 1 | mg/L | 200 | | | 81 | 78 | | | |

| | | | Eurofins Sample No : | | | 8059996 | 8059998 | | | |
|-----------------------|----|-----------|--------------------------------|---|---|-------------|-------------|--|--|--|
| | | | Matrix : | | | Groundwater | Groundwater | | | |
| | | | Sampling Date : | | | 2024-09-24 | 2024-09-24 | | | |
| | | | Client Sample Identification : | | | TW1 - GW1 | TW1 - GW2 | | | |
| Microbiology | RL | Unit | Criteria | | | | | | | |
| | | | A | B | C | | | | | |
| Escherichia coli (DC) | 0 | CFU/100mL | 0 | | | 0 | 0 | | | |
| Total Coliforms (DC) | 0 | CFU/100mL | 0 | | | 0 | 0 | | | |

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Paterson Group
Project : PH4905

Reception Date: 2024-09-25

| | | | | | | | | | |
|--------------------------------|------|------|-------------|-------------|--|--|--|--|--|
| Eurofins Sample No : | | | 8059996 | 8059998 | | | | | |
| Matrix : | | | Groundwater | Groundwater | | | | | |
| Sampling Date : | | | 2024-09-24 | 2024-09-24 | | | | | |
| Client Sample Identification : | | | TW1 - GW1 | TW1 - GW2 | | | | | |
| Nutrients | RL | Unit | | | | | | | |
| Ammonia (Total, as Nitrogen) | 0.02 | mg/L | 0.154 | 0.153 | | | | | |
| Total Kjeldahl Nitrogen | 0.1 | mg/L | 0.231 | 0.236 | | | | | |

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Paterson Group
Project : PH4905

Reception Date: 2024-09-25

| | | | | | | | | | | |
|-----------------------------------|-----|------|----------|-------------|---|------|--|--|--|--|
| Eurofins Sample No : | | | | 8059998 | | | | | | |
| Matrix : | | | | Groundwater | | | | | | |
| Sampling Date : | | | | 2024-09-24 | | | | | | |
| Client Sample Identification : | | | | TW1 - GW2 | | | | | | |
| Volatile Organic Compounds | RL | Unit | Criteria | | | | | | | |
| | | | A | B | C | | | | | |
| VOCs (Water, GC/MS) | | | | | | | | | | |
| 1,1,1,2-Tetrachloroethane | 0.5 | ug/L | | | | <0.5 | | | | |
| 1,1,1-Trichloroethane | 0.4 | ug/L | | | | <0.4 | | | | |
| 1,1,2,2-Tetrachloroethane | 0.5 | ug/L | | | | <0.5 | | | | |
| 1,1,2-Trichloroethane | 0.4 | ug/L | | | | <0.4 | | | | |
| 1,1-Dichloroethane | 0.4 | ug/L | | | | <0.4 | | | | |
| 1,1-Dichloroethene | 0.4 | ug/L | 14 | | | <0.5 | | | | |
| 1,2-Dibromoethane | 0.2 | ug/L | | | | <0.2 | | | | |
| 1,2-Dichlorobenzene | 0.4 | ug/L | 200 | | | <0.4 | | | | |
| 1,2-Dichloroethane | 0.2 | ug/L | 5 | | | <0.2 | | | | |
| 1,2-Dichloropropane | 0.5 | ug/L | | | | <0.5 | | | | |
| 1,3,5-Trimethylbenzene | 0.3 | ug/L | | | | <0.3 | | | | |
| 1,3-Dichlorobenzene | 0.4 | ug/L | | | | <0.4 | | | | |
| 1,4-Dichlorobenzene | 0.4 | ug/L | 5 | | | <0.4 | | | | |
| Acetone | 5 | ug/L | | | | <5.0 | | | | |
| Benzene | 0.5 | ug/L | 1 | | | <0.5 | | | | |
| Bromodichloromethane | 0.3 | ug/L | | | | <0.3 | | | | |
| Bromoform | 0.4 | ug/L | | | | <0.4 | | | | |
| Bromomethane | 0.5 | ug/L | | | | <0.5 | | | | |
| Carbon tetrachloride | 0.2 | ug/L | 2 | | | <0.2 | | | | |
| Chloroethane | 0.2 | ug/L | | | | <0.5 | | | | |
| Chloroform | 0.5 | ug/L | | | | <0.5 | | | | |
| Chloromethane | 0.2 | ug/L | | | | <0.2 | | | | |
| cis-1,2-Dichloroethene | 0.4 | ug/L | | | | <0.4 | | | | |
| cis-1,3-Dichloropropene | 0.5 | ug/L | | | | <0.5 | | | | |
| Dibromochloromethane | 0.3 | ug/L | | | | <0.3 | | | | |
| Dichloromethane | 4 | ug/L | 50 | | | <4.0 | | | | |
| Diethyl ether | 5 | ug/L | | | | <5.0 | | | | |
| Ethylbenzene | 0.5 | ug/L | 140 | | | <0.5 | | | | |
| m/p-Xylene | 0.4 | ug/L | | | | <0.4 | | | | |
| Methyl ethyl ketone (MEK) | 2 | ug/L | | | | <2.0 | | | | |
| Methyl isobutyl ketone (MIBK) | 5 | ug/L | | | | <5.0 | | | | |
| Methyl tert-butyl ether (MTBE) | 2 | ug/L | | | | <2.0 | | | | |
| Monochlorobenzene | 0.5 | ug/L | 80 | | | <0.5 | | | | |
| o-Xylene | 0.4 | ug/L | | | | <0.4 | | | | |
| Styrene | 0.5 | ug/L | | | | <0.5 | | | | |
| Tetrachloroethylene (PCE) | 0.3 | ug/L | 10 | | | <0.3 | | | | |
| Toluene | 0.4 | ug/L | 60 | | | <0.4 | | | | |
| trans-1,2-dichloroethene | 0.4 | ug/L | | | | <0.4 | | | | |
| trans-1,3-dichloropropene | 0.5 | ug/L | | | | <0.5 | | | | |
| Trichloroethylene (TCE) | 0.3 | ug/L | 5 | | | <0.3 | | | | |
| Trichlorofluoromethane | 0.5 | ug/L | | | | <0.5 | | | | |
| Vinyl chloride | 0.2 | ug/L | 1 | | | <0.2 | | | | |
| Xylene (Total) | 0.5 | ug/L | 90 | | | <0.5 | | | | |
| 1,2-dichloroethane-d4 (surrogate) | 0 | % | | | | 113 | | | | |
| 4-bromofluorobenzene (surrogate) | 0 | % | | | | 81 | | | | |

OFFICIAL CERTIFICATE OF ANALYSIS - RESULTS

Client : Paterson Group
Project : PH4905

Reception Date: 2024-09-25

| | | | | | | | | | | |
|----------------------------|----|------|--------------------------------|---|---|-------------|--|--|--|--|
| | | | Eurofins Sample No : | | | 8059998 | | | | |
| | | | Matrix : | | | Groundwater | | | | |
| | | | Sampling Date : | | | 2024-09-24 | | | | |
| | | | Client Sample Identification : | | | TW1 - GW2 | | | | |
| Volatile Organic Compounds | | | Criteria | | | | | | | |
| | RL | Unit | A | B | C | | | | | |
| Toluene-d8 (surrogate) | 0 | % | | | | 99 | | | | |

Approved by : 
Emma-Dawn Ferguson, M.Sc.
Environmental Chemist

Approved by : 
Jason Kennedy,
Project Manager

OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Paterson Group
Project : PH4905

Reception Date: 2024-09-25

| Parameter | Unit | RL | Blank | QC | | Matrix Spike | | Duplicate | |
|--|-----------|------|--------|------------|---------|--------------|---------|--|---------|
| | | | | Recovery % | Range % | Recovery % | Range % | RPD % | Range % |
| Alkalinity (Water, Automated) | | | | | | | | | |
| Method : Alkalinity (water, titration to pH 4.5, automated). Internal method: OTT-I-AT-WI45398. | | | | | | | | | |
| Alkalinity (as CaCO3) | mg/L | 5 | <5 | 99 | 95-105 | | | 1 | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-30 | |
| Ammonia, Total (Water, Colorimetry) | | | | | | | | | |
| Method : Ammonia (Water, Colorimetry). Internal method: OTT-I-NUT-WI46201. | | | | | | | | | |
| Ammonia (Total, as Nitrogen) | mg/L | 0.02 | <0.020 | 112 | 80-120 | 112 | 80-120 | 0 | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-29 Analysis Date: 2024-10-01 | |
| Chloride (Water, IC) | | | | | | | | | |
| Method : Anions (Water, Ion Chromatography). Internal method: OTT-I-IC-WI45985. | | | | | | | | | |
| Chloride | mg/L | 0.5 | <0.5 | 102 | 80-120 | 105 | 80-120 | 2 | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-27 | |
| Colour, Apparent (Water, Spectrophotometry) | | | | | | | | | |
| Method : Colour (Water, Spectrophotometric). Internal method: OTT-I-SPEC-WI45980. | | | | | | | | | |
| Colour (Apparent) | TCU | 2 | <2 | 99 | 39-159 | | | 9 | 0-40 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-30 Analysis Date: 2024-09-30 | |
| Conductivity (Water, Automated) | | | | | | | | | |
| Method : Conductivity (Water, Autotitrator). Internal Method: OTT-I-AT-WI45398. | | | | | | | | | |
| Conductivity @ 25°C | uS/cm | 5 | <5 | 101 | 98-102 | | | 1 | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-30 | |
| DOC (Water, IR) | | | | | | | | | |
| Method : Organic carbon (water, IR, combustion). Internal method: OTT-I-DEM-WI46148. | | | | | | | | | |
| Dissolved Organic Carbon | mg/L | 0.5 | <0.5 | 100 | 84-116 | 85 | 80-120 | - | 0-15 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-30 Analysis Date: 2024-10-01 | |
| Escherichia coli (DC Plate) | | | | | | | | | |
| Method : Total Coliforms and E.Coli by MF (Water, DC plate). Internal method: OTT-M-BAC-WI45296. | | | | | | | | | |
| Escherichia coli (DC) | CFU/100mL | 0 | 0 | | | | | - | 0-30 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-25 Analysis Date: 2024-09-26 | |
| Fluoride (Water, Auto/ISE) | | | | | | | | | |
| Method : Fluoride by autotitrator, ion selective electrode. Internal method: OTT-I-AT-WI45398. | | | | | | | | | |
| Fluoride | mg/L | 0.1 | <0.10 | 98 | 90-110 | | | - | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-30 | |

OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Paterson Group
Project : PH4905

Reception Date: 2024-09-25

| Parameter | Unit | RL | Blank | QC | | Matrix Spike | | Duplicate | |
|---|------|--------|---------|------------|---------|--------------|---------|--|---------|
| | | | | Recovery % | Range % | Recovery % | Range % | RPD % | Range % |
| Metals Scan (Water, ICP/MS) | | | | | | | | | |
| Method : Metals (Water, ICP/MS). Internal method: AMMTFQE1. | | | | | | | | | |
| Aluminum | mg/L | 0.01 | <0.01 | 100 | 80-120 | 114 | 70-130 | - | 0-20 |
| Antimony | mg/L | 0.0005 | <0.0005 | 87 | 80-120 | 93 | 70-130 | - | 0-20 |
| Arsenic | mg/L | 0.001 | <0.001 | 99 | 80-120 | 106 | 70-130 | - | 0-20 |
| Barium | mg/L | 0.001 | <0.001 | 100 | 80-120 | 91 | 70-130 | 0 | 0-20 |
| Beryllium | mg/L | 0.0005 | <0.0005 | 108 | 80-120 | 108 | 70-130 | - | 0-20 |
| Boron | mg/L | 0.01 | <0.01 | 100 | 80-120 | 102 | 70-130 | - | 0-20 |
| Cadmium | mg/L | 0.0001 | <0.0001 | 106 | 80-120 | 100 | 70-130 | - | 0-20 |
| Chromium | mg/L | 0.001 | <0.001 | 100 | 80-120 | 105 | 70-130 | - | 0-20 |
| Cobalt | mg/L | 0.0002 | <0.0002 | 102 | 80-120 | 94 | 70-130 | - | 0-20 |
| Copper | mg/L | 0.001 | <0.001 | 110 | 80-120 | 93 | 70-130 | - | 0-20 |
| Iron | mg/L | 0.03 | <0.03 | 100 | 80-120 | 101 | 70-130 | - | 0-20 |
| Lead | mg/L | 0.001 | <0.001 | 110 | 80-120 | 86 | 70-130 | - | 0-20 |
| Manganese | mg/L | 0.01 | <0.01 | 100 | 80-120 | 99 | 70-130 | - | 0-20 |
| Mercury | mg/L | 0.0001 | <0.0001 | 106 | 80-120 | 78 | 70-130 | - | 0-20 |
| Molybdenum | mg/L | 0.005 | <0.005 | 90 | 80-120 | 100 | 70-130 | - | 0-20 |
| Nickel | mg/L | 0.005 | <0.005 | 100 | 80-120 | 96 | 70-130 | - | 0-20 |
| Selenium | mg/L | 0.001 | <0.001 | 102 | 80-120 | 101 | 70-130 | - | 0-20 |
| Silver | mg/L | 0.0001 | <0.0001 | 117 | 80-120 | 93 | 70-130 | - | 0-20 |
| Strontium | mg/L | 0.001 | <0.001 | 100 | 80-120 | 88 | 70-130 | 0 | 0-20 |
| Thallium | mg/L | 0.0001 | <0.0001 | 104 | 80-120 | 87 | 70-130 | - | 0-20 |
| Uranium | mg/L | 0.001 | <0.001 | 90 | 80-120 | 92 | 70-130 | - | 0-20 |
| Vanadium | mg/L | 0.001 | <0.001 | 100 | 80-120 | 108 | 70-130 | - | 0-20 |
| Zinc | mg/L | 0.01 | <0.01 | 110 | 80-120 | 88 | 70-130 | - | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-27 | |
| Metals Scan (Water, ICP/OES) | | | | | | | | | |
| Method : Metals (Water, ICP/OES). Internal method: OTT-I-MET-WI48491. | | | | | | | | | |
| Calcium | mg/L | 1 | <1 | 104 | 86-115 | 101 | 70-130 | 1 | 0-20 |
| Magnesium | mg/L | 1 | <1 | 100 | 91-109 | 100 | 70-130 | - | 0-20 |
| Potassium | mg/L | 1 | <1 | 107 | 87-113 | 114 | 70-130 | - | 0-20 |
| Sodium | mg/L | 1 | <1 | 106 | 85-115 | 107 | 70-130 | - | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-30 Analysis Date: 2024-09-25 | |
| Nitrate (Water, IC) | | | | | | | | | |
| Method : Anions (Water, Ion Chromatography). Internal method: OTT-I-IC-WI45985. | | | | | | | | | |
| Nitrate (as Nitrogen) | mg/L | 0.1 | <0.1 | 106 | 80-120 | | | | |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-27 | |
| Nitrite (Water, IC) | | | | | | | | | |
| Method : Anions (Water, Ion Chromatography). Internal method: OTT-I-IC-WI45985. | | | | | | | | | |
| Nitrite (as Nitrogen) | mg/L | 0.1 | <0.1 | 105 | 80-120 | | | | |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-27 | |
| pH (25°C) (Water, Automated) | | | | | | | | | |
| Method : pH (Water, Automated Meter). Internal method: OTT-I-AT-WI45398. | | | | | | | | | |
| pH @ 25°C | | 1 | 5.71 | 100 | 97-103 | | | 1 | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-30 | |

OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Paterson Group

Project : PH4905

Reception Date: 2024-09-25

| Parameter | Unit | RL | Blank | QC | | Matrix Spike | | Duplicate | |
|--|-----------|-------|--------|------------|---------|--------------|---------|--|---------|
| | | | | Recovery % | Range % | Recovery % | Range % | RPD % | Range % |
| Phenols (Water, Colorimetry) | | | | | | | | | |
| Method : Phenols (Water, Colorimetry). Internal method: OTT-I-4AAP-WI46150. | | | | | | | | | |
| Phenols-4AAP | mg/L | 0.001 | <0.001 | 114 | 75-125 | 118 | 70-130 | - | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-27 Analysis Date: 2024-09-27 | |
| Sulphate (Water, IC) | | | | | | | | | |
| Method : Anions (Water, Ion Chromatography). Internal method: OTT-I-IC-WI45985. | | | | | | | | | |
| Sulphate | mg/L | 1 | <1 | 105 | 90-110 | 110 | 80-120 | 1 | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-27 | |
| Sulphide (Water, Colorimetry) | | | | | | | | | |
| Method : Sulphide, S2- (Water, Colorimetry). Internal method: OTT-I-SPEC-WI45931. | | | | | | | | | |
| Sulphide (S2-) | mg/L | 0.01 | <0.01 | 100 | 80-120 | | | - | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-26 | |
| Tannin and Lignin (Water, Spec) | | | | | | | | | |
| Method : Tannin and Lignin (Water, Spec), Internal method: OTT-I-SPEC-WI57693. | | | | | | | | | |
| Tannin and Lignin | mg/L | 0.1 | <0.1 | 92 | 80-120 | | | - | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-30 Analysis Date: 2024-09-30 | |
| Total Coliforms (DC Plate) | | | | | | | | | |
| Method : Total Coliforms and E.Coli by MF (Water, DC plate). Internal method: OTT-M-BAC-WI45296. | | | | | | | | | |
| Total Coliforms (DC) | CFU/100mL | 0 | 0 | | | | | - | 0-30 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-25 Analysis Date: 2024-09-26 | |
| Total Kjeldahl Nitrogen (Water, Colorimetry) | | | | | | | | | |
| Method : TKN (Water, colorimetry). Internal method: OTT-I-NUT-WI46201. | | | | | | | | | |
| Total Kjeldahl Nitrogen | mg/L | 0.1 | <0.100 | 98 | 70-130 | 111 | 70-130 | 3 | 0-20 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-27 Analysis Date: 2024-09-29 | |
| Turbidity (Water, Turbidimeter) | | | | | | | | | |
| Method : Turbidity (Water, Turbidimeter). Internal method: OTT-I-TUR-WI46288. | | | | | | | | | |
| Turbidity | NTU | 0.1 | <0.1 | 103 | 80-120 | | | - | 0-30 |
| Associated Samples : 8059996, 8059998 | | | | | | | | Prep Date: 2024-09-26 Analysis Date: 2024-09-26 | |

OFFICIAL CERTIFICATE OF ANALYSIS - QUALITY CONTROL

Client : Paterson Group

Project : PH4905

Reception Date: 2024-09-25

| Parameter | Unit | RL | Blank | QC | | Matrix Spike | | Duplicate | |
|--|------|-----|-------|------------|---------|--------------|---------|-----------|---------|
| | | | | Recovery % | Range % | Recovery % | Range % | RPD % | Range % |
| VOCs (Water, GC/MS) | | | | | | | | | |
| Method : Volatile Organic Compounds (Water, GC/MS). Internal method: AMVOMSE8. | | | | | | | | | |
| 1,1,1,2-Tetrachloroethane | ug/L | 0.5 | <0.5 | 121 | 70-130 | 126 | 70-130 | - | 0-30 |
| 1,1,1-Trichloroethane | ug/L | 0.4 | <0.4 | 116 | 70-130 | 122 | 70-130 | - | 0-30 |
| 1,1,2,2-Tetrachloroethane | ug/L | 0.5 | <0.5 | 117 | 70-130 | 116 | 70-130 | - | 0-30 |
| 1,1,2-Trichloroethane | ug/L | 0.4 | <0.4 | 109 | 70-130 | 115 | 70-130 | - | 0-30 |
| 1,1-Dichloroethane | ug/L | 0.4 | <0.4 | 102 | 70-130 | 125 | 70-130 | - | 0-30 |
| 1,1-Dichloroethene | ug/L | 0.4 | <0.5 | 122 | 70-130 | 125 | 70-130 | - | 0-30 |
| 1,2-Dibromoethane | ug/L | 0.2 | <0.2 | 100 | 70-130 | 105 | 70-130 | - | 0-30 |
| 1,2-Dichlorobenzene | ug/L | 0.4 | <0.4 | 100 | 70-130 | 102 | 70-130 | - | 0-30 |
| 1,2-Dichloroethane | ug/L | 0.2 | <0.2 | 87 | 70-130 | 120 | 70-130 | - | 0-30 |
| 1,2-Dichloropropane | ug/L | 0.5 | <0.5 | 107 | 70-130 | 117 | 70-130 | - | 0-30 |
| 1,3,5-Trimethylbenzene | ug/L | 0.3 | <0.3 | 112 | 70-130 | 115 | 70-130 | - | 0-30 |
| 1,3-Dichlorobenzene | ug/L | 0.4 | <0.4 | 98 | 70-130 | 100 | 70-130 | - | 0-30 |
| 1,4-Dichlorobenzene | ug/L | 0.4 | <0.4 | 101 | 70-130 | 104 | 70-130 | - | 0-30 |
| Acetone | ug/L | 5 | <5.0 | 117 | 70-130 | 89 | 70-130 | - | 0-30 |
| Benzene | ug/L | 0.5 | <0.5 | 121 | 70-130 | 126 | 70-130 | - | 0-30 |
| Bromodichloromethane | ug/L | 0.3 | <0.3 | 119 | 70-130 | 128 | 70-130 | - | 0-30 |
| Bromoform | ug/L | 0.4 | <0.4 | 90 | 70-130 | 95 | 70-130 | - | 0-30 |
| Bromomethane | ug/L | 0.5 | <0.5 | 87 | 70-130 | 87 | 70-130 | - | 0-30 |
| Carbon tetrachloride | ug/L | 0.2 | <0.2 | 111 | 70-130 | 118 | 70-130 | - | 0-30 |
| Chloroethane | ug/L | 0.2 | <0.5 | 101 | 70-130 | 112 | 70-130 | - | 0-30 |
| Chloroform | ug/L | 0.5 | <0.5 | 121 | 70-130 | 127 | 70-130 | - | 0-30 |
| Chloromethane | ug/L | 0.2 | <0.2 | 86 | 70-130 | 89 | 70-130 | - | 0-30 |
| cis-1,2-Dichloroethene | ug/L | 0.4 | <0.4 | 118 | 70-130 | 125 | 70-130 | - | 0-30 |
| cis-1,3-Dichloropropene | ug/L | 0.5 | <0.5 | 75 | 70-130 | 85 | 70-130 | - | 0-30 |
| Dibromochloromethane | ug/L | 0.3 | <0.3 | 103 | 70-130 | 108 | 70-130 | - | 0-30 |
| Dichloromethane | ug/L | 4 | <4.0 | 77 | 70-130 | 110 | 70-130 | - | 0-30 |
| Diethyl ether | ug/L | 5 | <5.0 | 100 | 70-130 | 95 | 70-130 | - | 0-30 |
| Ethylbenzene | ug/L | 0.5 | <0.5 | 129 | 70-130 | 110 | 70-130 | - | 0-30 |
| m/p-Xylene | ug/L | 0.4 | <0.4 | 124 | 70-130 | 106 | 70-130 | - | 0-30 |
| Methyl ethyl ketone (MEK) | ug/L | 2 | <2.0 | 124 | 70-130 | 124 | 70-130 | - | 0-30 |
| Methyl isobutyl ketone (MIBK) | ug/L | 5 | <5.0 | 107 | 70-130 | 114 | 70-130 | - | 0-30 |
| Methyl tert-butyl ether (MTBE) | ug/L | 2 | <2.0 | 110 | 70-130 | 113 | 70-130 | - | 0-30 |
| Monochlorobenzene | ug/L | 0.5 | <0.5 | 110 | 70-130 | 114 | 70-130 | - | 0-30 |
| o-Xylene | ug/L | 0.4 | <0.4 | 123 | 70-130 | 112 | 70-130 | - | 0-30 |
| Styrene | ug/L | 0.5 | <0.5 | 123 | 70-130 | 106 | 70-130 | - | 0-30 |
| Tetrachloroethylene (PCE) | ug/L | 0.3 | <0.3 | 82 | 70-130 | 86 | 70-130 | - | 0-30 |
| Toluene | ug/L | 0.4 | <0.4 | 122 | 70-130 | 128 | 70-130 | - | 0-30 |
| trans-1,2-dichloroethene | ug/L | 0.4 | <0.4 | 126 | 70-130 | 111 | 70-130 | - | 0-30 |
| trans-1,3-dichloropropene | ug/L | 0.5 | <0.5 | 90 | 70-130 | 101 | 70-130 | - | 0-30 |
| Trichloroethylene (TCE) | ug/L | 0.3 | <0.3 | 97 | 70-130 | 101 | 70-130 | - | 0-30 |
| Trichlorofluoromethane | ug/L | 0.5 | <0.5 | 116 | 70-130 | 118 | 70-130 | - | 0-30 |
| Vinyl chloride | ug/L | 0.2 | <0.2 | 95 | 70-130 | 108 | 70-130 | - | 0-30 |
| Xylene (Total) | ug/L | 0.5 | <0.5 | | | | - | | - |
| Associated Samples : 8059998 | | | | | | | | | |
| Prep Date: 2024-09-26 | | | | | | | | | |
| Analysis Date: 2024-10-01 | | | | | | | | | |

Where RPD % is reported as "-" the calculation is not available because one or both of the duplicates is within 5 times the RL.



STANDARD CHAIN-OF-CUSTODY

146 Colonnade Road, Unit #8, Ottawa, ON K2E 7Y1 • Phone 613-271-5692, Fax 613-271-5222

CLIENT INFORMATION

INVOICE INFORMATION

100315477

Order #: ☒ YES ☐ NO

Company: Paterson Group

Contact: Alex Schopf

Address: 9 Auriga Drive

Telephone: 613-218-3444

Email: #1: earldley@patersongroup.ca, mlafamme@patersongroup.ca

Email: #2: aschopf@patersongroup.ca

Project: PH4905

TURN-AROUND TIME (Business Days)

☐ 1 Day* (100%) ☐ 2 Day** (50%) ☐ 3-5 Days (25%) ☒ 5-7 Days (Standard)

*For results reported after rush due date, surcharges will apply: before 12:00 - 100%, after 12:00 - 50%.

**For results reported after rush due date, surcharges will apply: before 12:00 - 50%, after 12:00 - 25%.

The optimal temperature conditions during transport should be less than 10°C. Sample(s) cannot be frozen, unless otherwise indicated or agreed upon with the Laboratory. Note that this COC is not to be used for drinking water samples. The COC must be complete upon submission of the samples, there will be a \$25 surcharge if required information is missing (required fields are shaded in grey).

Sample Matrix

Field Filtered -->

Sample Analysis Required

RM# (Lab Use Only)

Sample ID

Date/Time Collected

of Containers

PHC F1 - F4

BTEX

TW1 - GW1

September 24, 2024

GW

7

98

TW1 - GW2

September 24, 2024

GW

9

98

PRINT

SIGN

DATE/TIME

TEMP (°C)

COMMENTS:

Sampled By: Alex Schopf

Relinquished By: Alex Schopf

Received By: S.S. Hu


September 24, 2024

September 25, 2024

401 Magnetic Drive, Unit #1, North York, ON M3J 3H9 • Telephone: 416-661-5287 • 800 Vansickle Road, Unit H630, St. Catharines, ON, L2S 0B5 • Telephone: 905-680-8687 • 608 Morris Court, Kingston, ON, K7P 2H9 • Telephone: 613-634-9307

Pumping Test Analysis Report

| | | | |
|---------------|-----------------------------|---------------------------------------|---------------------|
| File No. | PH4905 | Well ID: | TW1 |
| Date: | Tuesday, September 24, 2024 | Solution Method: | Cooper-Jacob |
| Client: | Ottawa Sivan Temple | Transmissivity (m ² /day): | 1970.7 |
| Site Address: | 2104 Roger Stevens Road | Discharge Rate (L/min) | 58 |
| Project: | Proposed Redevelopment | Analysis performed by: | AS |



Pumping Test Analysis Report

File No. PH4905
Date: Tuesday, September 24, 2024
Client: Ottawa Sivan Temple
Site Address: 2104 Roger Stevens Road
Project: Proposed Redevelopment

| Summary Table: | | |
|------------------|----------|---------------------------------------|
| Solution Method: | Well ID: | Transmissivity (m ² /day): |
| Cooper-Jacob | TW1 | 1970.7 |
| Average: | | 1970.70 |

| MW1 inputs | | | |
|------------|------|-------|-------------|
| pH | 7.95 | A | 0.17 |
| TDS | 498 | B | 2.09 |
| Calcium | 42 | C | 1.22 |
| Alkalinity | 236 | D | 2.37 |
| Temp. | 25 | | |
| | | pHs = | 7.961844256 |

| Langelier Saturation Index (LSI) Calculation | | (Langelier, 1936) |
|---|---|---|
| $LSI = pH - pH_s$ $pH_s = (9.3 + A + B) - (C + D)$ Where: | | $A = (\log_{10} [TDS] - 1) / 10$ $B = -13.12 \times \log_{10} (oC + 273) + 34.55$ $C = \log_{10} [Ca^{2+} \text{ as } CaCO_3] - 0.4$ $D = \log_{10} [\text{alkalinity as } CaCO_3]$ |
| | | LSI = 0.0 |
| LSI | Effect | |
| 0.5 to 2 | Water is super saturated and tends to precipitate a scale layer of calcium carbonate (scale forming but non-corrosive) | |
| 0 to 0.5 | Water is super saturated and tends to precipitate a scale layer of calcium carbonate (slightly scale forming and corrosive). | |
| 0 | Water is saturated (in equilibrium) with calcium carbonate. A scale layer of calcium carbonate is neither precipitated nor dissolved. | |
| 0 to -0.5 | Water is under saturated and tends to dissolve solid calcium carbonate (slightly corrosivebut non-scale forming). | |
| -0.5 to -2 | Water is under saturated and tends to dissolve solid calcium carbonate (seriously corrosive). | |



**PATERSON
GROUP**

SOIL PROFILE AND TEST DATA

GEOTECHNICAL INVESTIGATION

2104 Roger Stevens Drive, Ottawa, Ontario

DATUM: Geodetic **EASTING:** 367934.449 **NORTHING:** 5000149.976 **ELEVATION:** 91.00

PROJECT: Proposed Hindu Temple

FILE NO. PG6832

BORINGS BY: CME 55 Low Clearance Drill

REMARKS:

DATE: September 19, 2023

HOLE NO. BH 1-23

| SAMPLE DESCRIPTION | STRATA PLOT | SAMPLE | | SAMPLE % RECOVERY | N VALUE or RQD | WATER CONTENT % | DEPTH (m) | Remoulded Shear Strength (kPa) | | | | | Peak Shear Strength (kPa) | | | | | Pen. Resist. Blows/0.3m (50 mm Dia. Cone) | | | | | Piezometer Construction |
|---|-------------|--------|------|----------------------|----------------|-----------------|-----------|--------------------------------|----|----|----|-----|---------------------------|----|----|----|-----|---|----|----|----|-----|-------------------------|
| | | No. | Type | | | | | 0 | 25 | 50 | 75 | 100 | 0 | 25 | 50 | 75 | 100 | 0 | 25 | 50 | 75 | 100 | |
| Ground Surface | | | | | | | | | | | | | | | | | | | | | | | |
| EL 91 m | | | | | | | | | | | | | | | | | | | | | | | |
| TOPSOIL | | | | | | | | | | | | | | | | | | | | | | | |
| 0.05 m EL 90.95 m | | AU 1 | ● | | | | 0 | | | | | | | | | | | | | | | | |
| | | SS 2 | ▽ | 75 | 46 | | 1 | | | | | | | | | | | | | | | | |
| | | SS 3 | ▽ | 60 | 50+ | | 2 | | | | | | | | | | | | | | | | |
| GLACIAL TILL: Dense to very dense, brown silty sand to sandy silt with gravel, cobbles and boulders, trace clay | | SS 4 | ▽ | 50 | 50+ | | 3 | | | | | | | | | | | | | | | | |
| | | SS 5 | ▽ | 58 | 50+ | | 4 | | | | | | | | | | | | | | | | |
| | | SS 6 | ▽ | 67 | 24 | | 5 | | | | | | | | | | | | | | | | |
| 4.95 m EL 86.05 m | | SS 7 | ▽ | 25 | 50+ | | 6 | | | | | | | | | | | | | | | | |
| End of Borehole | | | | | | | 7 | | | | | | | | | | | | | | | | |
| Practical refusal to augering at 4.98m depth. | | | | | | | 8 | | | | | | | | | | | | | | | | |
| (GWL @ 2.20m - Sep. 21, 2023) | | | | | | | 9 | | | | | | | | | | | | | | | | |
| | | | | | | | 10 | | | | | | | | | | | | | | | | |
| | | | | | | | 11 | | | | | | | | | | | | | | | | |
| | | | | | | | 12 | | | | | | | | | | | | | | | | |
| | | | | | | | 13 | | | | | | | | | | | | | | | | |
| | | | | | | | 14 | | | | | | | | | | | | | | | | |

DISCLAIMER: THE DATA PRESENTED IN THIS LOG IS THE PROPERTY OF PATERSON GROUP AND THE CLIENT FOR WHO IT WAS PRODUCED. THIS LOG SHOULD BE READ IN CONJUNCTION WITH ITS CORRESPONDING REPORT. PATERSON GROUP IS NOT RESPONSIBLE FOR THE UNAUTHORIZED USE OF THIS DATA.

SOIL PROFILE AND TEST DATA

GEOTECHNICAL INVESTIGATION

2104 Roger Stevens Drive, Ottawa, Ontario


DATUM: Geodetic **EASTING:** 367950.643 **NORTHING:** 5000130.909 **ELEVATION:** 90.49

PROJECT: Proposed Hindu Temple

FILE NO. PG6832

BORINGS BY: CME 55 Low Clearance Drill

REMARKS:
DATE: September 19, 2023

HOLE NO. BH 2-23


DISCLAIMER: THE DATA PRESENTED IN THIS LOG IS THE PROPERTY OF PATERSON GROUP AND THE CLIENT FOR WHO IT WAS PRODUCED. THIS LOG SHOULD BE READ IN CONJUNCTION WITH ITS CORRESPONDING REPORT. PATERSON GROUP IS NOT RESPONSIBLE FOR THE UNAUTHORIZED USE OF THIS DATA.




2104 Roger Stevens Drive, Ottawa, Ontario

REMARKS: DATE: September 19, 2023

DISCLAIMER: THE DATA PRESENTED IN THIS LOG IS THE PROPERTY OF PATERSON GROUP AND THE CLIENT FOR WHO IT WAS PRODUCED. THIS LOG SHOULD BE READ IN CONJUNCTION WITH ITS CORRESPONDING REPORT. PATERSON GROUP IS NOT RESPONSIBLE FOR THE UNAUTHORIZED USE OF THIS DATA.

| PREDICTIVE NITRATE IMPACT ASSESSEMENT | | |
|---|-------------|----------------------|
| Infiltration Factors | | |
| Topography | 0.20 | |
| Soil | 0.40 | |
| Cover | 0.10 | |
| Total | 0.70 | |
| Site Characteristics | | |
| Area of Site : | 20405 | m ² |
| Total of roof areas: | 1040 | m ² |
| Total area of paved driveway areas: | 4448 | m ² |
| Roof + paved driveway areas | 5488 | m ² |
| Impervious Area | 5488 | m ² |
| Percent Impervious Area = | 27 | % |
| Infiltration Area = | 14917 | m ² |
| Septic Effluent | | |
| Concentration of Effluent (Cs) = | 20 | mg/L |
| Infiltration Calculation | | |
| Nitrate concentration in precipitation (C _i) = | 0 | mg/L |
| Surplus Water (Environment Canada) | 378 | mm/yr |
| Factored Water Surplus = | 265 | mm/yr |
| Infiltration % due to stormwater management measures | - | % |
| Infiltration rate from stormwater management measures = | 0 | mm/yr |
| Infiltration Flow Entering the System (Q _i) = | 11 | m ³ /day |
| Mass Balance Model (MOEE, 1995) | | |
| $C_T = (Q_b C_b + Q_e C_e + Q_i C_i) / (Q_b + Q_e + Q_i)$ = Cumulative Nitrate Concentration | | |
| Q _b = flow entering the system across the upgradient area | 0 | m ³ /day |
| C _b = background nitrate concentration | 0 | mg/L |
| Q _e = flow entering the system from the septic drainfield | 7.25 | m ³ /day |
| C _e = concentration of nitrates in the septic effluent | 20 | mg/L |
| Q _i = flow entering the system from infiltration | 11 | m ³ /day |
| C _i = Concentration of nitrates in the infiltrate | 0 | mg/L |
| C_T = | 8.03 | mg/L |
| Sewage Flow Volume | | |
| Daily Sewage Flow (Q _s)= | 7.25 | m³ |
| <i>Notes: Site characteristic values were measured as approximate values from the available site plans and GeoOttawa.</i> | | |



LEGEND:

BOREHOLE LOCATION

76.67 GROUND SURFACE ELEVATION (m)


(65.69) PRACTICAL REFUSAL TO DCPT ELEV. (m)


SLOPE STABILITY CROSS-SECTIONS

CONCEPTUAL PLAN PROVIDED BY P2 CONCEPTS.

GROUND SURFACE ELEVATIONS AT BOREHOLE LOCATIONS ARE REFERENCED TO A GEODETIC DATUM.

SCALE: 1:1000


| | | | | | | | | |
|--|-----|---|------------|---------|--|---|----------------------------|---------------------------------|
| <div><div><div>PATERSON GROUP</div><div>9 AURIGA DRIVE OTTAWA, ON K2E 7T9 TEL: (613) 226-7381</div></div></div> | | | | | OTTAWA, Title: <div>TEST HOLE LOCATION PLAN</div> | OTTAWA SIVAN TEMPLE GEOTECHNICAL INVESTIGATION PROPOSED HINDU TEMPLE 2104 ROGER STEVENS DRIVE ONTARIO | Scale: <div>1:1000</div> | Date: <div>09/2023</div> |
| | | | | | | | Drawn by: <div>NFRV</div> | Report No.: <div>PG6832-1</div> |
| | 2 | ADDED SLOPE STABILITY CROSS SECTION C-C TO PLAN | 27/01/2025 | DR | | | Checked by: <div>OM</div> | Dwg. No.: <div>PG6832-1</div> |
| | 1 | AS PER REVISED CONCEPTUAL PLAN | 24/06/2024 | OM | | | Approved by: <div>SD</div> | |
| | NO. | REVISIONS | DATE | INITIAL | | | | Revision No.: <div>2</div> |
| | | | | | | | | |



| H (DEPTH OF COVER) | INSULATION THICKNESS | W (WIDTH OF INSULATION) |
|--------------------|----------------------|-------------------------|
| 1800 TO 2400mm | 50mm | 1200mm |
| 1500 TO 1800mm | 75mm | 1800mm |
| 1200 TO 1500mm | 100mm | 2400mm |

INSULATE SEWER AS INDICATED AND WHERE DEPTH OF COVER IS LESS THAN 2400mm. PROVIDE A MINIMUM 1200mm COVER. CENTER INSULATION OVER PIPE. JOINTS BETWEEN SHEETS OF INSULATION SHALL BE STAGGERED.

INSULATION OF WELL WATER LINE SHALLOW TRENCHES N.T.S.



| H (DEPTH OF COVER) | INSULATION THICKNESS | W (WIDTH OF INSULATION) |
|--------------------|----------------------|---------------------------|
| 1400 TO 2000mm | 50mm | 1200mm + DIAMETER OF PIPE |
| 1100 TO 1400mm | 75mm | 1800mm + DIAMETER OF PIPE |
| 800 TO 1100mm | 100mm | 2400mm + DIAMETER OF PIPE |
| 500 TO 800mm | 125mm | 3000mm + DIAMETER OF PIPE |



INSULATE SEWER AS INDICATED AND AS PER CITY DRAWING S35 AND WHERE DEPTH OF COVER IS LESS THAN 2000mm. CENTER INSULATION OVER PIPE. JOINTS BETWEEN SHEETS OF INSULATION SHALL BE STAGGERED.

INSULATION OF SEWERS IN SHALLOW TRENCHES AS PER CITY OF OTTAWA DRAWING No. S35 N.T.S.

LEGEND

- FFL FIRST FLOOR ELEVATION
TOF TOP OF FOUNDATION
BFL BASEMENT FLOOR ELEVATION
USF UNDERSIDE OF FOOTING
--- PROPERTY LINE
CB CATCH BASIN
MH STORM MANHOLE
CB/MH CATCH BASIN/MANHOLE
MH SANITARY MANHOLE
--- SAN SANITARY SEWER
--- ST STORM SEWER
--- WL WELL WATER LINE
INV INVERT OF PIPE
RDO ROOF DRAIN OUTLET
+99.99 EXISTING GRADE ELEVATION

KEY PLAN



- ① INSULATION 50mm THICK, 1.2m WIDE
② INSULATION 75mm THICK, 1.8m WIDE
③ INSULATION 100mm THICK, 2.4m WIDE
④ INSULATION 125mm THICK, 3.0m WIDE

| No. | DATE | REVISION |
|-----|-----------|---|
| 8 | JUN 12-25 | RE-ISSUED FOR APPROVAL & BUILDING PERMIT FOR PRIEST RESIDENCE |
| 7 | APR 10-25 | RE-ISSUED FOR APPROVAL |
| 6 | OCT 25-24 | ISSUED FOR APPROVAL |
| 5 | OCT 18-24 | ISSUED FOR COORDINATION |
| 4 | OCT 15-24 | ISSUED FOR COORDINATION |
| 3 | SEP 20-24 | ISSUED FOR COORDINATION |
| 2 | AUG 6-24 | ISSUED FOR COORDINATION |
| 1 | OCT 23-24 | ISSUED FOR APPROVAL |


D. B. GRAY ENGINEERING INC.

Stormwater Management - Grading & Drainage - Sewer & Sanitary Sewers - Watermain

700 Long Point Circle
Ottawa, Ontario
613-425-8044
d.gray@dbgrayengineering.com

Project
PROPOSED HINDU TEMPLE
2104 ROGER STEVENS DR
NORTH GOWER, ONTARIO

Drawing Title
SITE SERVICING PLAN




Drawn D.B.G.
H. Scale 1:300
V. Scale
Date JUN 11-24
Job No. 20029

Drawing No.
C-1
of 7

REFER TO NOTES & DETAILS
ON DRAWING C-5 & C-6

RDO: ROOF DRAIN OUTLET TO BE 0.30m ABOVE GRADE - TURN END OF PIPE DOWN ON TO SPLASH PAD
REFER TO DRAWING C-2 FOR INSULATION OF SEPTIC SYSTEM PIPES (SEWERS & FORCEMAINS)



DRIVE
STEVEN'S
Road Alliance Between Lot 20 & 21

ROGER STEVENS DRIVE

PROVIDE AN OUTLET TYPE RODENT GRATE (HORIZONTAL BARS)

REMOVE EXISTING HOPE CULVERT
NEW 16.0m-525 HOPE CULVERT


INV 90.43 (IMBED 0.15m)

INV 91.33 (IMBED 0.15m)

NEW 12.0m-525 HOPE CULVERT

INV 90.39 (IMBED 0.15m)

WATER CHUTE WITH VENT



LEGEND

FFL FIRST FLOOR ELEVATION
TOF TOP OF FOUNDATION
BFL BASEMENT FLOOR ELEVATION
USF UNDERSIDE OF FOOTING
--- PROPERTY LINE
CB CATCH BASIN
MH STORM MANHOLE
CB/MH CATCH BASIN/MANHOLE
MH SANITARY MANHOLE
--- SAN SANITARY SEWER
--- ST STORM SEWER
--- WL WELL WATER LINE
INV INVERT OF PIPE
RDO ROOF DRAIN OUTLET
+39.99 EXISTING GRADE ELEVATION

KEY PLAN

| | | |
|-----|-----------|---|
| | | |
| 8 | JUN 12-25 | RE-ISSUED FOR APPROVAL & BUILDING PERMIT FOR PRIEST RESIDENCE |
| 7 | APR 10-25 | RE-ISSUED FOR APPROVAL |
| 6 | OCT 25-24 | ISSUED FOR APPROVAL |
| 5 | OCT 18-24 | ISSUED FOR COORDINATION |
| 4 | OCT 15-24 | ISSUED FOR COORDINATION |
| 3 | SEP 20-24 | ISSUED FOR COORDINATION |
| 2 | AUG 6-24 | ISSUED FOR COORDINATION |
| 1 | JUL 11-24 | PRELIMINARY |
| No. | DATE | REVISION |

D. B. GRAY ENGINEERING INC.
Stormwater Management - Grading & Drainage - Sewer & Sanitary Sewers - Watermain
700 Long Point Circle
Ottawa, Ontario
613-425-8044
d.gray@dbgrayengineering.com

Project
PROPOSED HINDU TEMPLE
2104 ROGER STEVENS DR
NORTH GOWER, ONTARIO


Drawing Title
SEPTIC SYSTEM

Engineer's Seal

NOT VALID UNLESS SIGNED & DATED

Drawn D.B.G.
H. Scale 1:300
V. Scale
Date JUN 11-24
Job No. 20029

Drawing No.
C-2
of 7



REFER TO NOTES & DETAILS
ON DRAWING C-5 & C-6