



Engineers, Planners & Landscape Architects

Engineering

Land/Site
Development

Municipal
Infrastructure

Environmental/
Water Resources

Traffic/
Transportation

Recreational

Planning

Land/Site
Development

Planning Application
Management

Municipal Planning
Urban Design

Expert Witness
(OLT)

Wireless Industry

Landscape Architecture

Streetscapes & Public
Amenities

Open Space, Parks &
Recreation

Community &
Residential

Commercial &
Institutional

Environmental
Restoration

Queensway Carleton Hospital – Part 4 Expansion

Transportation Impact Assessment

Prepared for: PARKIN Architects Limited

Engineering excellence.

Planning progress.

Liveable landscapes.

Queensway Carleton Hospital – Part 4 Expansion
3045 Baseline Road
Transportation Impact Assessment

Prepared By:

NOVATECH
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario
K2M 1P6

November 28, 2025

Novatech File: 123089
Ref: R-2025-112

November 28, 2025

Parkin Architects Limited
200 Laurier Avenue West, 3rd Floor
Ottawa, Ontario K1P 6M7

Attention: Mr. Derek Judson

Dear Mr. Judson:

**Reference: Queensway Carleton Hospital – Part 4 Expansion
Transportation Impact Assessment
Our File No.: 123089**

We are pleased to submit the following Transportation Impact Assessment (TIA) in support of Site Plan Control (SPC) application for the proposed Part 4 expansion of the above noted property for your review and signoff. The structure and format of this report is in accordance with the City of Ottawa 2017 TIA Guidelines and its 2023 revisions.

If you have any questions or comments regarding this report, please feel free to contact Brad Byvelds or the undersigned.

Yours truly,

NOVATECH



Mohammed Talha, M. Eng.
Engineering Intern | Transportation



Certification Form for Transportation Impact Assessment (TIA) Study Program Manager

TIA Plan Reports

On April 14, 2022, the Province's Bill 109 received Royal Assent providing legislative direction to implement the More Homes for Everyone Act, 2022 aiming to increase the supply of a range of housing options to make housing more affordable. Revisions have been made to the TIA guidelines to comply with Bill 109 and streamline the process for applicants and staff.

Individuals submitting TIA reports will be responsible for all aspects of development-related transportation assessment and reporting, and undertaking such work, in accordance and compliance with the City of Ottawa's Official Plan, the Transportation Master Plan and the Transportation Impact Assessment (2017) Guidelines.

By submitting the attached TIA report (and any associated documents) and signing this document, the individual acknowledges that they meet the four criteria listed below.

Certification

- ☒ I have reviewed and have a sound understanding of the objectives, needs and requirements of the City of Ottawa's Official Plan, Transportation Master Plan and the Transportation Impact Assessment (2017) Guidelines (Update Effective July 2023);
- ☒ I have a sound knowledge of industry standard practice with respect to the preparation of transportation impact assessment reports, including multi modal level of service review;
- ☒ I have substantial experience (more than 5 years) in undertaking and delivering transportation impact studies (analysis, reporting and geometric design) with strong background knowledge in transportation planning, engineering or traffic operations; and

City of Ottawa
Transportation Engineering Services
Planning, Real Estate and Economic Development
110 Laurier Avenue West, 4th fl.
Ottawa, ON K1P 1J1
Tel. : 613-580-2424
Fax: 613-560-6006

Revision Date: June, 2023

Transportation Impact Assessment Guidelines

☒ I am either a licensed or registered¹ professional in good standing, whose field of expertise [check ☒ appropriate field(s)]:

☒ is either transportation engineering

☐ or transportation planning.

Dated at this day of , 20.

(City)

Name:

Professional Title:

B. Byvelds

Signature of Individual certifier that they meet the above four criteria

Office Contact Information (Please Print)	
Address:	<input type="text" value="240 Michael Cowpland Drive"/>
City / Postal Code:	<input type="text" value="K2M 1P6"/>
Telephone / Extension:	<input type="text" value="613-254-9643 EXT 286"/>
E-Mail Address:	<input type="text" value="b.byvelds@novatech-eng.com"/>

Stamp

--

¹ License of registration body that oversees the profession is required to have a code of conduct and ethics guidelines that will ensure appropriate conduct and representation for transportation planning and/or transportation engineering works.

Table of Contents

1.0 SCREENING	1
1.1 Introduction	1
1.2 Proposed Development	1
1.3 Screening Form	3
2.0 SCOPING	3
2.1 Existing Conditions	3
2.1.1 Roadways	3
2.1.2 Study Intersections	5
2.1.3 Driveways	9
2.1.4 Pedestrian and Cycling Facilities	9
2.1.5 Transit	10
2.1.6 Area Traffic Management	13
2.1.7 Existing Traffic Volumes	15
2.1.8 Collision History	17
2.2 Planned Conditions	21
2.2.1 Transportation Projects	21
2.2.2 Other Area Developments	26
2.3 Study Area and Time Periods	26
2.4 Development Generated Travel Demand	27
2.4.1 Trip Generation	27
2.4.2 Trip Distribution	33
2.4.3 Trip Assignment	33
2.5 Exemptions Review	36
3.0 FORECASTING	37
3.1 Background Traffic	37
3.1.1 Other Area Developments	37
3.1.2 Background Growth Rate	38
3.1.3 Future Traffic Conditions	38
3.2 Demand Rationalization	46
3.2.1 Existing Conditions	46
3.2.2 2030 Background Traffic Operations	47
3.2.3 2035 Background Traffic Operations	49
4.0 ANALYSIS	50
4.1 Development Design	50
4.1.1 Design for Sustainable Modes	50
4.1.2 Circulation and Access	51
4.2 Parking	65
4.2.1 Existing Parking Supply	65
4.2.2 Part 4 Expansion Parking	65
4.3 Boundary Streets	67
4.4 Transportation Demand Management	68
4.4.1 Context for TDM	68
4.4.2 Need and Opportunity	68
4.4.3 TDM Program	69
4.5 Neighborhood Traffic Calming	70
4.6 Transit	70
4.6.1 Transit Capacity	70
4.6.2 Transit Priority	71

4.7	Network Concept	72
4.8	Intersection Design	72
4.8.1	Existing Intersection MMLOS Review	72
4.8.2	2030 Total Intersection Operations	75
4.8.3	2035 Total Intersection Operations	77
4.8.4	Total 2035 Operations with Mainstreet Protected Left Turns at Richmond Road/John Sutherland Drive and Baseline Road/John Sutherland Drive	78
5.0	CONCLUSIONS AND RECOMMENDATIONS	79

Figures

Figure 1:	An aerial view of the subject site and its vicinity	2
Figure 2:	OC Transpo Bus Stop Locations	11
Figure 3:	Existing Traffic Volumes.....	16
Figure 4:	Baseline Transitway Functional Design STA 18+925 to 19+520	22
Figure 5:	Baseline Transitway Functional Design STA 19+520 to 30+100	23
Figure 6:	Baseline Transitway Functional Design STA 19+920 to 30+600	24
Figure 7:	Baseline Transitway Functional Design STA 30+600 to 31+260	25
Figure 8:	Estimation of Cut-through Traffic on John Sutherland Drive	28
Figure 9:	Trip Assignment	35
Figure 10:	Background 2030 Traffic Volumes	40
Figure 11:	Background 2035 Traffic Volumes	41
Figure 12:	Site Redistributed Traffic Volumes	42
Figure 13:	Net Site Generated Traffic Volumes	43
Figure 14:	Total 2030 Traffic Volumes	44
Figure 15:	Total 2035 Traffic Volumes	45
Figure 16:	Material Management Facility WB-20 Turning Movement 1	52
Figure 17:	Material Management Facility WB-20 Turning Movement 2	53
Figure 18:	Material Management Facility WB-20 Turning Movement 3	54
Figure 19:	Material Management Facility WB-20 Turning Movement 4	55
Figure 20:	Material Management Facility WB-20 Turning Movement 5	56
Figure 21:	Material Management Facility WB-20 Turning Movement 6	57
Figure 22:	Material Management Facility WB-20 Turning Movement 7	58
Figure 23:	7000 WD Standard Tanker Turning Movement	59
Figure 24:	Parking Lot TL2 WB-20 Turning Movement 1	60
Figure 25:	Parking Lot TL2 WB-20 Turning Movement 2	61
Figure 26:	Parking Lot TL2 WB-20 Turning Movement 3	62
Figure 27:	Turning Movements in the Ambulance Bay	64

Tables

Table 1:	Existing and Forecasted Capacities of the Hospital	2
Table 2:	OC Transpo Transit Stops.....	11
Table 3:	OC Transpo Route Information	12
Table 4:	OC Transpo Peak Period Transit Data at Nearby Stops	14
Table 5:	OC Transpo Peak Period Data converted to Peak Hour Volume	14
Table 6:	Collision History	17
Table 7:	Estimation of Cut-through Traffic	29
Table 8:	Vehicles Trips Generated by QCH under Existing Conditions	29
Table 9:	Vehicle Trip Generation Rates from ITE Trip Generation Manual 11th Edition	30
Table 10:	QCH Local Vehicle Trip Generation Rates	30

Table 11: QCH Person Trip Generation Rates	31
Table 12: Net Person Trips Generated by Proposed QCH Expansion.....	31
Table 13: Part 4 Expansion Net New Person Trips Based on Assumed QCH Modal Shares	32
Table 14: TIA Exemptions	36
Table 15: Existing Conditions Intersection Operations	46
Table 16: 2030 Background Traffic Operations	48
Table 17: 2035 Background Traffic Operations	49
Table 18: Existing Campus Parking Supply.....	65
Table 19: Part 4 Expansion Parking Supply	65
Table 20: Part 4 Expansion Minimum Required Parking Spaces.....	66
Table 21: Segment MMLOS Summary.....	67
Table 22: Part 4 Expansion Addition Transit Usage	71
Table 23: Transit Delays – 2030 Background Traffic Conditions	71
Table 24: Intersection MMLOS Summary.....	72
Table 25: 2030 Total Intersection Operations.....	75
Table 26: Mitigated Intersection Operations at Richmond Road & John Sutherland Drive.....	76
Table 27: 2035 Total Intersection Operations.....	77
Table 28: Mitigated Intersection Operations at Richmond Road & John Sutherland Drive.....	78
Table 29: Analysis Results for Protected Mainstreet Left Turns at QCH intersections	79

Appendices

Appendix A: Existing Site Plan & Part 4 Phasing Plans
Appendix B: TIA Screening Form
Appendix C: OC Transpo Maps
Appendix D: Traffic Count Data
Appendix E: Signal Timing Plans
Appendix F: Collision Data
Appendix G: Other Background Development Excerpts
Appendix H: BRBRT EAS Excerpts
Appendix I: Long Range Model Snapshots
Appendix J: Synchro Analysis Reports for Existing Conditions
Appendix K: Synchro Analysis Reports for Background Conditions
Appendix L: TDM Checklists
Appendix M: Detailed Parking Calculations
Appendix N: Detailed MMLOS Analysis
Appendix O: Synchro Analysis Reports for Total Conditions
Appendix P: Functional Design of Proposed Roadway Modifications
Appendix Q: Synchro Analysis Reports for Protected Left Turn Movements Scenario

EXECUTIVE SUMMARY

This Transportation Impact Assessment (TIA) has been prepared in support of Site Plan Control (SPC) application for the proposed Queensway Carleton Hospital (QCH) Part 4 expansion in Ward 8, College, in Ottawa. The subject site is located on a National Capital Commission (NCC) parcel. The Part 4 expansion will be constructed in phases with an ultimate buildout in 2030.

The subject site has frontage on Baseline Road, Richmond Road, and John Sutherland Drive. It is located in the Greenbelt Transect as per the City's *Official Plan* (OP). In the study area, it is classified as a greenbelt facility within Schedule B4 of the OP.

The subject site currently is surrounded by the following:

- Tubman Funeral Home, and Académie de la Capitale, to the north;
- An off-road multiuse trail and Baseline Road, followed by vacant lands to the south;
- Semi-detached houses followed by Sioux Crescent to the east;
- Vacant lands containing a pathway network used by the Hospital, followed by HWY416, Baseline Road, and Richmond Road to the west.

The Part 4 expansion is anticipated to be completed in 5 phases with various modifications and additions to the campus infrastructure. Some of the transportation related works include extension of West Ring Road to John Sutherland Drive, addition of a new parking garage, realignment of John Sutherland Drive east of the hospital, and modifications to loading bays. With the proposed Part 4 expansion, the capacity of the hospital is anticipated to increase to 444 beds from the existing 287 beds.

The study area for this report includes the boundary roadways Richmond Road and Baseline Road, as well as the intersections Richmond Road/Holly Acres Road/Nanaimo Drive, Richmond Road/John Sutherland Drive, Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp, Baseline Road/Cedarview Road, Baseline Road/John Sutherland Drive/Valley Stream Drive, Baseline Road/Sandcastle Drive, and all QCH access on John Sutherland Drive.

The selected time periods for the analysis are the weekday AM and PM peak hours, as they represent the 'worst case' combination of site generated traffic and adjacent street traffic. Analysis has been completed for the Part 4 expansion buildout year 2030 and 2035 horizon year.

The conclusions and recommendations of this TIA can be summarized as follows:

Trip Generation

- Based on the target modals shares, it is anticipated that the Part 4 expansion will generate 588 net new person trips (227 vehicle trips) during the AM peak and 506 net new person trips (195 vehicle trips) during the PM peak.

Existing Traffic Operations

- All study area intersections operate within acceptable Level of Service (LOS) during the AM and PM peaks.
- At Richmond Road/Holly Acres Road/Nanaimo Drive intersection, during the AM and PM peaks, the 95th percentile queue length of the westbound through/left turn movement

exceeds the available storage length of 20m. The 95th percentile queue length of the northbound left turn movement exceeds the available storage length of 25m.

- At Richmond Road/John Sutherland Drive intersection, the 95th percentile queue length for the southbound left turn movement exceeds the available storage length of 45m during the AM peak hour.
- At Baseline Road/Cedarview Road, the 95th percentile queue length for the northbound left turn movement exceeds the available storage of 25m potentially blocking the adjacent northbound right turn lane during the AM and PM peak hours.

Background Traffic Operations

- Under the 2030 and 2035 background traffic operations, the intersection operations within the study area are anticipated to be generally consistent with the existing conditions.

Development Design

- Under the existing campus conditions, a sidewalk network is provided along the periphery of the campus buildings. As part of Part 4 expansion, pedestrian facilities near the main entrance at the south end of the building will remain unchanged.
- The existing pathways north/west of the existing parking garage will be reconfigured to accommodate the new parking garage and west ring road. The pathway on the west side of the new west ring will continue to function as part of the City's Crosstown Bikeway network. Two new uncontrolled pedestrian crossings are proposed on the west ring road to provide connectivity to the western pathway networks.
- John Sutherland Drive east of the hospital will be realigned further east to allow for the hospital expansion. As part of this, sidewalks will be provided on both sides of the road from the West Ring Road to the Emergency Department, where the sidewalk on the west side of the road continues to the Irving Greenberg Cancer Centre.
- A new off-road pedestrian pathway is proposed on the east side of John Sutherland Drive along its entire stretch. Three accesses to this pathway are proposed: one each at the extremes of John Sutherland Drive, and one to the east of Irving Greenberg Cancer Center.
- Three new uncontrolled pedestrian crossings are proposed along John Sutherland Drive to provide connectivity to the bus stops, pathways, and parking north/east of the road. It is recommended that all new uncontrolled pedestrian crossings be designed in accordance with Ontario Traffic Manual (OTM) Book 15 requirements for a PXO Type D.
- Minor modifications to the south parking lots are proposed to increase the parking supply.
- Transit will be maintained on John Sutherland Drive as part of this development. The existing bus stops and shelters near the Irving Greenberg Cancer Centre (Stops #0727 and #0728) will be maintained as part of the site plan. The existing bus stops and shelters near the emergency center (#0947 and #0950) will be relocated to the realigned roadway. The southbound bus stop (#0950) will be relocated to the intersection of John Sutherland Drive/West Ring Road.

- A total of 105 bicycle parking spaces will be provided on-site. 78 spaces will be provided within the new parking garage, 4 spaces will be provided in the landscaped area in front of parking lot TL2, 5 spaces will be provided at the entrance of Irving Greenberg Cancer Center, 14 spaces will be provided within the visitors parking lot, and 4 spaces will be provided in the middle of the new proposed pathway on the east side of John Sutherland Drive.
- All required TDM-supportive design and infrastructure measures in the TDM checklist are met.

Circulation and Access

- All hospital related material delivery/pickup, and garbage collection activities will take place from the material management facility's loading/unloading docks located beside Irving Greenberg Cancer Center.
- Propane gas delivery will occur within parking lot TL2 as the propane storage tanks are located beside this parking lot.
- Diesel delivery will take place at the diesel storage tanks located between the two parking garages
- John Sutherland Drive between Richmond Road and Main QCH Access/John Sutherland Drive intersection is designated as a fire route. Whole of QCH west ring road, and ambulance/police bay in front of the emergency department are also designated as fire routes. All three of these fire routes meet the minimum clear width requirement of 6.0m for a fire route.
- Ambulance garage is located beside the emergency department off John Sutherland Drive. In front of the emergency department, an ambulance bay and parking for ambulance/police is also provided.

Parking

- The ratio of existing parking supply to the anticipated visits is approximately 0.68 spaces per visitor. While this parking demand has been calculated based on the current parking supply, QCH staff have advised that there is a waitlist for parking, and the current demands are not met based on the current parking supply.
- Based on the proposed site plan, Part 4 expansion will have a supply of 1760 parking spaces.
- While QCH has committed to providing TDM measures within the development to help shift modal shares, the effectiveness of measures is not known, and measures may take time to alter employee and visitor travel behaviors. Additionally, there are no major transit improvements proposed by the city to assist in shifting modal shares. As such, the proposed parking supply will meet the maximum parking demand while the modal shares from the development shift over time. As such, the proposed parking supply will be roughly midway between the anticipated parking demand based on the existing and proposed modal shares.

- The proposed number of vehicle, bicycle, and accessible parking spaces adhere to the minimum requirements of the Zoning By-law (ZBL).

Boundary Streets

- The results of the segment MMLOS can be summarised as follows:
 - None of the boundary streets meet the target pedestrian LOS D;
 - None of the boundary streets meet the target bicycle LOS B or C;
 - Both the boundary streets meet the target transit LOS D;
 - Both the boundary streets meet the target truck LOS D.
- Richmond Road can achieve the target PLOS D by providing a sidewalk of minimum 2.0m width and a boulevard of width >2.0m if the existing operating speed of 90kmph is to be maintained.
- Richmond Road can only achieve the target BLOS B through the implementation of a separated cycling facility.
- Baseline Road can achieve the target PLOS D by providing a sidewalk of minimum 2.0m width and a boulevard of width >2.0m on the south side of the road if the existing operating speed of 80kmph is to be maintained. It is noted that the subject site frontage meets the target PLOS D.
- Baseline Road can only achieve the target BLOS C through the implementation of a separated cycling facility. It is noteworthy that the city's Baseline BRT project will provide new sidewalks and cycle tracks along the corridor, achieving the target PLOS and BLOS.

Transportation Demand Management

- TDM measures that are currently in place within the QCH hospital include:
 - Provide opportunities for staff to work from home, if they have the ability.
 - Partnerships with rural hospitals, to allow doctors to travel to rural areas to provide health care services typically provided at QCH. This would reduce the number of patients visiting from rural areas outside the city.
 - Provide safe, secure, convenient, and comfortable bike parking to encourage cycling.
 - Provide a dynamic parking policy that prioritizes rural patients, carpoolers, pick up/drop off patients/employees.
 - Charge for long-term parking (daily, weekly, monthly). To reduce the incentive to drive, increase daily parking rates for employees.
 - Charge for short-term parking (hourly).
 - Provide a multi-modal travel information package for new staff.
 - Provide patients with information on specialized mobility incentives that are available to them (i.e. Para Transpo, Taxi Reimbursements, etc.)
 - Provide clinics during evenings and weekends to shift trips outside the weekday peak periods.
 - Explore opportunities for some employees to work outside peak periods.
- In addition to the above measures that are currently in place, the following TDM measures will be implemented within the QCH hospital:

- Provide virtual care to reduce the number of patients who need to come to the QCH campus
 - Provide full- or part-time staff who will be dedicated to collecting data, managing incentives, and evaluating impacts of TDM measures. This staff will liaise with various leadership groups to develop a TDM strategy.
 - Develop a TDM platform to track multimodal commute data, provide rewards and incentives, and serving as a resource/communications hub. This is overseen by the Transportation Coordinator.
 - Build a high quality, secure, indoor bike parking facility that meets the needs of cyclists and sets a cycling culture/foundation for employees
 - Purchase or lease a fleet of bikes and e-bikes that can be rented out to employees at minimal cost.
 - Provide real-time transit display screens near main building entrances.
 - Incentivize employees to use sustainable modes by introducing cycling challenges, etc.
- The proposed TDM program will assist in achieving a higher auto passenger, transit, and cycling modal share for the hospital. The implementation of a TDM coordinator will allow the hospital to track TDM programs for effectiveness and develop an improved program over time.

Transit

- The proposed Part 4 expansion is anticipated to generate the following number of additional transit trips: 75 IN and 36 OUT in the AM peak, and 26 IN and 69 OUT in the PM peak.
- Peak period transit utilization data dated April 1, 2025, was obtained from OC Transpo. The data obtained reflects the routes and the stops they had served prior to the recent implementation (April 27, 2025) of OC Transpo initiative “New Ways to Bus”. As transit data for the new routes is not available, the specific bus loads departing QCH have not been reviewed. However, based on the anticipated transit distribution, the additional transit usage has been calculated.

Transit Priority

- The eastbound left turn movement at the Richmond Road/Holly Acres Road/Nanaimo Drive intersection and the westbound left turn movement at the Baseline Road/Richmond Road/Robertson Road intersection are not anticipated to meet the target TLOS D during the AM and PM peak hours. The City's recently approved 2025 TMP CIP includes the Robertson Road and Richmond Road Transit Priority project. Consideration should be given by the city to implementing left turn queue jump lanes at the aforementioned intersections as part of this project.
- The westbound left and right turn movements at the Richmond Road/John Sutherland Drive intersection are not anticipated to meet the target TLOS D during the PM peak hour. To provide additional capacity and improved transit operations, consideration have been given to widening the John Sutherland Drive approach to this intersection to provide two outbound lanes.

Intersection MMLOS

- The results of the intersection MMLOS analysis can be summarized as follows:

- No study area intersections meet the target PLOS;
 - No study area intersections meet the target BLOS;
 - No study area intersections meet the target TLOS, except for the Baseline Road/Cedarview Road intersection and Baseline Road/Sandcastle Drive intersection;
 - All the study area intersections meet the target TkLOS except for the Richmond Road/John Sutherland Drive, and Baseline Road/John Sutherland Drive/Valley Stream Drive.
- At all the study area intersections, there is limited opportunity to improve the PLOS without reducing the number of travel lanes crossed and restricting turning movements.
- At Richmond Road/Holly Acres Road/Nanaimo Drive, Richmond Road/John Sutherland Drive, Baseline Road/John Sutherland Drive/Valley Stream Drive intersections, the target BLOS can be achieved by implementation of two-stage left turn facilities.
- At Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp intersection, there is limited opportunity to improve BLOS without implementing a fully protected intersection.
- At Baseline Road/Cedarview Road intersection, as the bike lane remains to the left of the right turn lane from Robertson Road to Cedarview Road and there is limited opportunity to transition the bike lane to a cycle track on the intersection approach due to high traffic volumes, and the bridge over Highway 416. As such, no recommendations have been identified to improve the BLOS.
- To improve TLOS at Richmond Road/Holly Acres Road/Nanaimo Drive, consideration should be given by the city to implement an eastbound left turn queue jump lane as part of the Robertson Road and Richmond Road Transit Priority Project.
- To improve TLOS at Richmond Road/John Sutherland Drive, consideration has been given to widen the John Sutherland Drive approach to provide two outbound lanes.
- To improve TLOS at Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp, consideration should be given by the city to implement a westbound left turn queue jump lane as part of the Robertson Road and Richmond Road Transit Priority Project.

Total Traffic Operations

- All study area intersections except for the Richmond Road/John Sutherland intersection operate within acceptable LOS during the AM and PM peaks.
- At Richmond Road/Holly Acres Road/Nanaimo Drive intersection, during the AM and PM peaks, the 95th percentile queue length of the westbound through/left turn movement exceeds the available storage length of 20m. The 95th percentile queue length of the northbound left turn movement exceeds the available storage length of 25m.
- At Richmond Road/John Sutherland Drive intersection, the 95th percentile queue length for the southbound left turn movement is anticipated to exceed the available storage length of 45m during the AM peak. The westbound approach is anticipated to operate with a LOS F during the PM peak hour.

- The proposed implementation of a permitted and protected southbound left turn phase and widening of the westbound approach to two outbound lanes is anticipated to yield a LOS A during the AM peak hour and a LOS C during the PM peak hour. The 95th percentile southbound left turn queues are anticipated to reduce during the AM peak hour and will be accommodated within the existing storage length.
- At Baseline Road/Cedarview Road, the 95th percentile queue length for the northbound left turn movement exceeds the available storage of 25m potentially blocking the adjacent northbound right turn lane during the AM and PM peak hours.
- At Baseline Road/John Sutherland Drive/Valley Stream Drive intersection, the 95th percentile queue length for the eastbound left movement is anticipated to exceed the available storage length of approximately 35m during the AM peak hour. The LOS is anticipated to decrease to LOS B from LOS A.

The proposed development is recommended from transportation perspective.

1.0 SCREENING

1.1 Introduction

This Transportation Impact Assessment (TIA) has been prepared in support of Site Plan Control (SPC) application for the proposed Queensway Carleton Hospital (QCH) Part 4 expansion in Ward 8, College, in Ottawa. The subject site is located on a National Capital Commission (NCC) parcel. The Part 4 expansion will be constructed in phases with an ultimate buildout in 2030.

The subject site has frontage on Baseline Road, Richmond Road, and John Sutherland Drive. It is located in the Greenbelt Transect as per the City's *Official Plan* (OP). In the study area it is classified as a greenbelt facility within Schedule B4 of the OP.

The subject site currently is surrounded by the following:

- Tubman Funeral Home, and Académie de la Capitale, to the north;
- An off-road multiuse trail and Baseline Road, followed by vacant lands to the south;
- Semi-detached houses followed by Sioux Crescent to the east;
- Vacant lands containing a pathway network used by the Hospital, followed by HWY416, Baseline Road, and Richmond Road to the west.

An aerial view of the subject site and its vicinity is shown in **Figure 1**.

1.2 Proposed Development


The breakdown of the proposed redevelopment and expansion works constituting Part 4 of the masterplan expansion can be summarised as follows:

- Phase 1 – Realign loading dock access road, extension of west ring road to John Sutherland Drive, addition of new parking garage, reconfiguration of the visitor parking lot 6, construction of new electrical substation, loading bay traffic island demolition, and propane tank removal.
- Phase 2 – (a) Installation of new diesel tanks, construction of interim loading docks, installation of propane tanks, and the construction of new north parking lot. (b) Construction of new generator facility. (c) Construction of materials management and E.V.S. addition. (d) Materials management and E.V.S., and food services internal renovation.
- Phase 3 – Construction of inpatient tower addition.
- Phase 4 – (a) Realign John Sutherland Drive east of the hospital, construction of temporary ambulance bay and new ambulatory care addition. (b) Emergency department addition and ambulance garage. (c) Emergency department internal renovation.
- Phase 5 – Construction of transitional care tower, modifications to loading bays, development of a second access to the loading area from John Sutherland Drive.

The current and future capacity of the hospital is summarized in **Table 1**.

The existing site plan and the proposed Part 4 phasing plans are included in **Appendix A**.

Figure 1: An aerial view of the subject site and its vicinity



Source: Background Aerial Snapshotted from Google Earth

Table 1: Existing and Forecasted Capacities of the Hospital

Independent Variable	Current Capacity	Gross Capacity after Part 4 Expansion
No of beds	287 beds	444 beds
No of full-time employees (FTE)	1337 FTE	2066 FTE
GFA	637,444 ft ²	1,023,388 ft ²

1.3 Screening Form

The City's *Revised TIA Guidelines* identify three triggers to satisfy the requirements for the need of a TIA report, including trip generation, location, and safety. The minimum criteria for each trigger are outlined in the City's TIA Screening form, which is included in **Appendix B**. The trigger results are as follows:

- Trip Generation Trigger – The development is anticipated to generate over 60 peak hour person trips; further assessment is **required** based on this trigger.
- Location Triggers – The development does not propose a new connection to a designated Rapid Transit or Transit Priority (RTTP) corridor or a Crosstown Bikeway, and is not located within a Hub, Protected Major Transit Station Area (PMTSA), or Design Priority Area (DPA); further assessment is **not required** based on this trigger.
- Safety Triggers – The subject site has frontage to a street with a posted speed limit of 80 kmph (Richmond Road); further assessment is **required** based on this trigger.

2.0 SCOPING

2.1 Existing Conditions

2.1.1 Roadways

All roadways within the study area fall under the jurisdiction of the City of Ottawa except the HWY416 ON-Ramp and HWY416 which fall under the jurisdiction of MTO.

Richmond Road is an arterial roadway that generally runs on an east-west alignment between Baseline Road and Island Park Drive. In the study area it has a four-lane cross section with a posted speed limit of 80 kmph and transitioning to 60kmph as approaching the Richmond Road/Holly Acres Road/Nanaimo Drive intersection. It is also classified as a full load truck route. Schedule C16 of the City of Ottawa's *Official Plan* identifies a Right-of-Way (ROW) protection of 49.5 m between Holly Acres Road and Baseline Road subject to the Baseline Road Rapid Transit Corridor (Bayshore Station to Heron Station) Planning and Environmental Assessment Study. South of the Richmond Road/John Sutherland Drive intersection, the ROW protection is met with some additional protections required to the north of the intersection.

Robertson Road is an arterial roadway that generally runs on an east-west alignment between Baseline Road and Eagleson Road. In the study area it has a four-lane undivided urban cross section with a posted speed limit of 80 kmph. It has paved asphalt sidewalks on both sides of the road. It is also classified as a full load truck route.

Baseline Road is an arterial roadway that generally runs on an east-west alignment between Richmond Road/Robertson Road and Prince of Wales Drive. In the study area it has a four-lane divided urban cross section with a posted speed limit of 70 kmph. It has a sidewalk on the south side and a multiuse pathway on the northside of the roadway between Cedarview Road and John Sutherland Drive which transitions to a sidewalk east of John Sutherland Drive. Baseline Road is classified as a full load truck route. Schedule C16 of the City of Ottawa's *Official Plan* identifies a Right-of-Way (ROW) protection of 36.3 m between Richmond Road and Greenbank Road.

Cedarview Road is an arterial roadway that generally runs on a north-south alignment between Baseline Road and ends in a dead-end south of Cobble Hill Drive. In the study area, it has a two-lane rural cross section with a posted speed limit of 60 kmph. It has a paved asphalt, bi-directional, multi-use pathway on the east side of the road. Cedarview Road is classified as a truck route with seasonal load restrictions.

Valley Stream Drive is a local roadway that generally runs on an east-west alignment between Baseline Road and Gladecrest Court. In the study area, it has a two-lane urban cross section with a speed limit of 40 kmph. It has a sidewalk on the north side of the roadway.

John Sutherland Drive is a private roadway that generally runs on a north-south alignment between Baseline Road and Richmond Road within the QCH campus. In the study area, it has a two-lane urban cross section with a posted speed limit of 50 kmph. It has a sidewalk on one side of the road.

Holly Acres Road is an arterial roadway that runs on a north-east curvilinear alignment between Carling Avenue and Richmond Road. In the study area, it has a four-lane urban cross section with a posted speed limit of 60kmph. It has paved asphalt sidewalk on both the sides of the road, transitioning to concrete sidewalks north of Aero Drive. It is classified as a truck route with seasonal load restrictions.

Nanaimo Drive runs on an east-west alignment between Richmond Road and Brian Crescent and is classified as a collector roadway between Richmond Road and Queensline Drive, and a local roadway between Queensline Drive and Brian Crescent. In the study area it has a two-lane undivided urban cross section with a posted speed limit of 40kmph. No sidewalks are provided on either side of the road. Parking is generally allowed on both the sides of the road with prohibition between April 01 and Nov 30.

Sandcastle Drive is a collector roadway that runs on a north-south alignment between Baseline Road and Valley Stream Drive. In the study area, it has a two-lane undivided urban cross section with a posted speed limit of 40kmph. A sidewalk is provided on the west side for the entire length and on the east side for approximately 120m south of Baseline Road. Parking is allowed only on the east side of the road.

HWY416 is classified as a freeway within the MTO's Highway Corridor Management Manual. It is further classified as a Fully Controlled-Access Highway (1A).

2.1.2 Study Intersections

Richmond Road/Holly Acres Road/Nanaimo Drive

- Signalized four-legged intersection.
- Northbound Approach (Richmond Road): one left turn lane, one through lane, one through/right lane, and one bicycle lane.
- Southbound Approach (Richmond Road): one left turn lane, two through lanes, one pocket bicycle lane, and one right turn lane.
- Westbound Approach (Nanaimo Drive): one through/left lane, and one right turn lane.
- Eastbound Approach (Holly Acres Road): two left turn lanes, one through lane, one pocket bicycle lane, and one channelized right turn lane.
- Standard crosswalk on all approaches except the southbound approach. Pedestrian crossing on southbound approach is prohibited by signage.



Richmond Road/John Sutherland Drive

- Signalized four-legged intersection.
- Northbound Approach (Richmond Road): one left turn lane, two through lanes, one bicycle lane, and one right turn lane.
- Southbound Approach (Richmond Road): one left turn lane, one through lane, one through/right lane, and one bicycle lane.
- Westbound Approach (John Sutherland Drive): one shared all movement lane.
- Eastbound Approach (Shouldice Farms Access): one shared all movement lane.
- Standard crosswalk on all approaches.



Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp

- Signalized four-legged intersection.
- Northbound Approach (Robertson Road): one left turn lane, two through lanes, and one channelized right turn lane.
- Southbound Approach (Richmond Road): two left turn lanes, two through lanes, one bicycle lane, and one channelized right turn lane.
- Eastbound Approach (HWY416 ON-Ramp): N/A.
- Westbound Approach (Baseline Road): two left turn lanes, one bicycle lane, one through lane, and one channelized right turn lane.
- Standard crosswalk on all approaches except the northbound approach.

Baseline Road/Cedarview Road

- Signalized three-legged intersection.
- Northbound Approach (Cedarview Road): one left turn lane, and one right turn lane.
- Eastbound Approach (Baseline Road): two through lanes, one bicycle lane, and one channelized right turn lane.
- Westbound Approach (Baseline Road): one left turn lane, two through lanes, and one bicycle lane.
- Ladder crosswalks on all three approaches.
- A bicycle crossride on the westbound approach.
- A two-stage turn queue box for eastbound cyclists turning left.



Baseline Road/John Sutherland Drive/Valley Stream Drive

- Signalized four-legged intersection.
- Northbound Approach (Valley Stream Drive): one left turn lane, and one through/right turn lane.
- Southbound Approach (John Sutherland Drive): one shared through/left turn lane, and one channelized right turn lane.
- Eastbound Approach (Baseline Road): one left turn lane, two through lanes, one bicycle lane, and one right turn lane.
- Westbound Approach (Baseline Road): one left turn lane, two through lanes, one bicycle lane, and one channelized right turn lane.
- Standard crosswalk on all approaches.



Baseline Road/Sandcastle Drive

- Signalized three-legged intersection.
- Northbound Approach (Sandcastle Drive): one left turn lane, and one right turn lane.
- Eastbound Approach (Baseline Road): one through lane, one through/right lane, and one bicycle lane.
- Westbound Approach (Baseline Road): one left turn lane, two through lanes, and one bicycle lane.
- Standard crosswalk on all approaches.



John Sutherland Drive/QCH West Access Road

- Unsignalized three-legged intersection.
- Stop control is provided on the southbound approach.
- Southbound Approach (John Sutherland Drive): one shared all movement lane.
- Eastbound Approach (West Ring Road): one shared all movement lane.
- Westbound Approach (John Sutherland Drive): one through lane, and one channelized right turn lane.
- Ladder crosswalk on southbound approach.
-



John Sutherland Drive/ Irving Greenberg Cancer Center Access

- Unsignalized three-legged intersection.
- Stop control is provided on all approaches.
- Northbound Approach (Irving Greenberg Cancer Center Access): one shared all movement lane.
- Eastbound Approach (John Sutherland Drive): one shared all movement lane.
- Westbound Approach (John Sutherland Drive): one shared all movement lane.
- Ladder crosswalk on eastbound approach.



John Sutherland Drive/North QCH Access

- Unsignalized three-legged intersection.
- Stop control is provided on all approaches.
- Northbound Approach (North QCH Access): one shared all movement lane.
- Eastbound Approach (John Sutherland Drive): one shared all movement lane.
- Westbound Approach (John Sutherland Drive): one shared all movement lane.
- Ladder crosswalks on westbound and northbound approaches.



John Sutherland Drive/Temporary Parking Lot TL2 Access/Private Hydro Access

- Unsignalized four-legged intersection.
- Stop control is provided on the northbound and southbound approaches.
- Northbound Approach (Private Hydro Access): one shared all movement lane.
- Southbound Approach (Temporary Parking Lot TL2 Access): one shared all movement lane.
- Eastbound Approach (John Sutherland Drive): one shared all movement lane.
- Westbound Approach (John Sutherland Drive): one shared all movement lane.



2.1.3 Driveways

A review of existing adjacent driveways along the boundary roads within approximately 200m from the development driveways are provided as follows:

John Sutherland Drive (North Side)

- One driveway to QCH Temporary Parking Lot TL2.
- One driveway to QCH snow dump area.

John Sutherland Drive (South Side)

- One private driveway to a private property (3460 Richmond Road) located on John Sutherland Drive, approximately 17m east of Richmond/John Sutherland Drive intersection.
- One driveway to hydro building.
- One driveway to North QCH Access.
- One driveway to QCH Irving Greenberg Cancer Center.
- Two driveways to QCH Emergency department entrance and ambulance garage.

Richmond Road (East Side)

- One commercial driveway to Académie de la Capitale at 3448 Richmond Road.
- Two commercial driveways to Tubman Funeral Homes at 3440 Richmond Road.
- One commercial driveway to Valleystream Pickleball Club and Soccer Field at 3412 Richmond Road.

Richmond Road (West Side)

- One private driveway to Shouldice Farms access (signalized) at 3451 Richmond Road.

Baseline Road (North Side)

- N/A

Baseline Road (South Side)

- One public driveway to Brucelands Park parking lot at 2960 Baseline Road.

2.1.4 Pedestrian and Cycling Facilities

Sidewalks

- John Sutherland Drive has a sidewalk on one side.
- Baseline road has an off-road multi-use pathway along the north side of it between Richmond Road and John Sutherland Drive; it transitions into a concrete sidewalk at John Sutherland Drive. On the south side, it has a concrete sidewalk.
- Richmond road does not have sidewalks but has paved shoulders on both the sides.
- Robertson Road has paved asphalt sidewalks on both the sides of the road.
- Cedarview Road has a paved shoulder on the west side. On the east side, it has a paved asphalt, bi-directional, multi-use pathway.

- Holly Acres Road has paved asphalt sidewalk on both sides of the road, transitioning to concrete sidewalks north of Aero Drive.
- Sandcastle Drive has sidewalk only on the west side of the road. On the east side, sidewalk is provided only along the frontage of commercial/residential development at 2940-2946 Baseline Road.

Cycling Facilities


- John Sutherland Drive does not have any cycling facilities (mixed traffic).
- Baseline Road has on-road cycling lanes on both the sides of the road. In addition to this, it has an off-road multi-use pathway along the north side of it between Richmond Road and John Sutherland Drive.
- Richmond Road has on-road cycling lanes on both the sides of the road.
- Robertson Road does not have any cycling facilities (mixed traffic).
- Cedarview Road has a paved asphalt, bi-directional, multi-use pathway on the east side of the road.
- Holly Acres Road does not have any cycling facilities (mixed traffic).
- Nanaimo Drive does not have any cycling facilities (mixed traffic).
- Sandcastle Drive does not have any cycling facilities (mixed traffic).

The City's *2023 Transportation Master Plan - Part 1* identifies Richmond Road, Robertson Road, the northern part of Cedarview Road, and the western portion of the NCC lands/QCH campus connecting Cedarview Road at Baseline Road to Richmond Road at John Sutherland Drive as a cross-town bikeway.

2.1.5 Transit

There are several OC Transpo bus stops within the vicinity of the subject site. The closest bus stops (including within 400 m radius) are shown in **Figure 2**. The location of the bus stops and the including the routes they service are summarized in **Table 2**. The routes that serve the study area are summarized in **Table 3**. Detailed route information and an excerpt from the OC Transpo Map are included in **Appendix C**.

Figure 2: OC Transpo Bus Stop Locations



Source: Background Aerial Snapshotted from GeoOttawa

Table 2: OC Transpo Transit Stops

Road	Side	Stop No.	Location	Routes Serviced
Robertson Road	West	5296	South of Baseline Road	57, 68, 646, 688
	East	5295	South of Baseline Road	57, 68, 646, 688
Richmond Road	East	0951	North of Baseline Road	658, 660
	East	1142	South of John Sutherland Drive	658, 660, 661, 669
	West	1143	North of John Sutherland Drive	88, 658, 660, 661, 669
Baseline Road	North	1391	West of Cedarview Road	57, 646, 658, 660, 661, 688
	North	0946	West of John Sutherland Drive	57, 646
	North	0945	East of John Sutherland Drive	68, 88, 646, 688
	North	4049	East of John Sutherland Drive	68, 88, 646, 688
	South	2310	East of Robertson Road	57, 646, 658, 660, 661, 669, 688
	South	0941	East of Valley Stream Drive	57, 646, 688
	South	0943	West of Valley Stream Drive	88, 646, 688

Road	Side	Stop No.	Location	Routes Serviced
	South	1698	West of Valley Stream Drive	68, 88, 646, 688
John Sutherland Drive	East	0947	Across from QCH Emergency Center	57, 68, 88
	East	0728	Across from QCH Irving Greenberg Cancer Center	57, 68, 88
	West	0950	In front of QCH Emergency Center	57, 68, 88
	West	0727	In front of QCH Irving Greenberg Cancer Center	57, 68, 88
	West	0949	East of Richmond Road	57, 68, 88

Table 3: OC Transpo Route Information

Route Details	Frequency
Route 57 - Rapid Bayshore/Crystal Bay ↔ Tunney's Pasture	Weekday: 15 mins headway. Every alternate bus extends to/from Carling Campus during off-peak hours, and every bus during peak hours. Weekend: 30 mins headway. Every alternate bus is from/to Carling Campus i.e., 1-hour headways.
Route 68 – Frequent Baseline ↔ Terry Fox	Weekday: 10-30 mins headway depending on peak/off-peak hours. Weekend: 15-30 mins headway depending on peak/off-peak hours.
88 – Frequent Hurdman ↔ Bayshore	Weekday: 15-25 mins or less headway depending on peak/off-peak hours. Some buses start/end at Baseline during off-peak hours. Weekend: 15-30 mins headway depending on peak/off-peak hours. Every alternate bus starts/ends at Baseline.
646 – School Route Canterbury H.S. ↔ Terry Fox	Weekday: Two consecutive buses in the morning to school at 7:37 and two consecutive buses in the afternoon at 15:34 from school. Weekend: Not Serviced.
658 – School Route Grandview ↔ Bell H.S.	Weekday: Two consecutive buses in the morning to school at 8:18 and three consecutive buses in the afternoon at 15:33 from school. Weekend: Not Serviced.
660 – School Route Bell H.S. ↔ innovation	Weekday: One bus in the morning at 8:07 to school and one bus in the afternoon at 15:36 from school. Weekend:

Route Details	Frequency
	Not Serviced.
661 – School Route Bell H.S. ↔ Terry Fox	Weekday: One bus in the morning at 8:14 to school and one bus in the afternoon at 15:33 from school. Weekend: Not Serviced.
669 – School Route Bell H.S. ↔ Bayshore	Weekday: Three consecutive buses in the morning at 8:28 to school and four consecutive buses in the afternoon at 15:24/15:33 from school. Weekend: Not Serviced.
688 – School Route Merivale H.S. ↔ Terry Fox	Weekday: Two buses in the morning at 7:00 and 7:05 to school and three consecutive buses in the afternoon at 14:30 from school. Weekend: Not Serviced.

*Data in the table is from OC Transpo Website accessed on April 21, 2025.

The peak period boarding/alighting/average load at departure data for transit at the nearby QCH transit stops was obtained from OC Transpo. The data provided by OC Transpo is summarized in **Table 4**. Assuming that all the transit trips listed in the table are QCH related, the peak period transit data was converted to peak hour data using the factors provided in table 4 of the *TRANS Trip Generation Manual – Summary Report* prepared by WSP. The factors for converting peak period transit trip rate to peak hour rates are given as 0.55 and 0.47 during the AM and PM peaks respectively. This peak period transit data converted to peak hour transit data is summarized in **Table 5**.

2.1.6 Area Traffic Management

Within the study area, there are no Area Traffic Management (ATM) studies that are in progress and/or completed recently.

The following ATM measures were identified at the Richmond Road/Holly Acres Road/Nanaimo Drive intersection:

- Northbound U-turn is prohibited
- Westbound through vehicular movement onto Nanaimo Drive is prohibited between 7:00 AM and 9:00 AM on weekdays. Bicycles are permitted.
- Traffic calmed neighborhood signage posted on entrance to Nanaimo Drive; flex posts, painted lane narrowing, 40KM/HR MAX pavement markings, and speed display devices are installed. Posted speed limit is 40kmph.

Table 4: OC Transpo Peak Period Transit Data at Nearby Stops

Stop	Location	Route	Direction	AM (6:00-9:00)			PM (15:00-18:00)			24-hr		
				Boardings	Alightings	Avg Load at Departure	Boardings	Alightings	Avg Load at Departure	Boardings	Alightings	Avg Load at Departure
0727	QCH/Irving Greenberg	57	WB	0	3	13	0	0	11	0	6	9
		58	EB	0	1	14	0	0	8	0	1	7
0728	QCH/Irving Greenberg	57	EB	0	0	7	4	0	18	5	0	10
		58	WB	0	0	6	2	0	10	2	0	8
0950	QCH/ Emergency	57	WB	1	16	11	0	4	10	3	28	8
		58	EB	0	5	13	3	1	9	5	6	7
0947	QCH/ Emergency	57	EB	2	0	7	22	1	17	41	1	10
		58	WB	0	5	6	5	0	9	14	5	7
0946	Baseline/ QCH	57	WB	0	3	11	1	3	10	2	9	8
		88	WB	1	21	28	3	11	25	10	79	21
0941	Baseline/ Valley Stream	57	EB	2	0	7	9	0	15	17	1	9
		88	EB	21	5	22	14	4	38	68	13	22
Total				27	59	145	63	24	180	167	149	126

Table 5: OC Transpo Peak Period Data converted to Peak Hour Volume

Stop	Location	Route	Direction	AM Peak Hour		PM Peak Hour	
				Conversion Factor = 0.55		Conversion Factor = 0.47	
				Boardings	Alightings	Boardings	Alightings
0727	QCH/Irving Greenberg	57	WB	0	2	0	0
		58	EB	0	1	0	0
0728	QCH/Irving Greenberg	57	EB	0	0	2	0
		58	WB	0	0	1	0
0950	QCH/ Emergency	57	WB	1	9	0	2
		58	EB	0	3	1	1
0947	QCH/ Emergency	57	EB	1	0	10	1
		58	WB	0	3	2	0
0946	Baseline/ QCH	57	WB	0	2	1	1
		88	WB	1	12	1	5
0941	Baseline/ Valley Stream	57	EB	1	0	4	0
		88	EB	12	3	7	2
Total				16	35	29	12

2.1.7 Existing Traffic Volumes


Weekday traffic counts commissioned by Novatech, as well as counts obtained from the City of Ottawa were used to determine the existing pedestrian, cyclist and vehicular traffic volumes at the study area intersections. The traffic counts were completed on the following dates:

• Richmond Road & Holly Acres Road & Nanaimo Drive	May 01, 2025
• Richmond Road & John Sutherland Drive	Mar 05, 2025
• Richmond Road/Robertson Road & Baseline Road & HWY416 ON-Ramp	Feb 13, 2024
• Baseline Road & Cedarview Road	Mar 05, 2025
• Baseline Road & Stream Valley Drive & John Sutherland Drive	Nov 06, 2024
• Baseline Road & Sandcastle Drive	Feb 03, 2022
• Baseline Road & Sandcastle Drive	Jan 12, 2017
• John Sutherland Drive & QCH West Access Road	Nov 06, 2024
• John Sutherland Drive & QCH Irving Greenberg Cancer Center	Nov 06, 2024
• John Sutherland Drive & QCH North Access	Nov 06, 2024
• John Sutherland Drive & Parking Lot TL2 & Private Access	Nov 06, 2024

The traffic count data at Baseline Road/Sandcastle Drive conducted by the City of Ottawa on February 03, 2022, was found to have significantly lower traffic volumes when compared with the traffic volumes at Baseline Road/John Sutherland Drive/Valley Stream Drive intersection. These two intersections are located beside each other, and no other road links exist between them except the Sioux Crescent on westbound movement which is a local road serving the Qualicum neighbourhood. Therefore, another traffic count was obtained from the city which was conducted on January 12, 2017 (pre-COVID) and was found to be reliable. For the purposes of this report, the through volumes at Baseline Road/Sandcastle Drive intersection were projected from the Baseline Road/John Sutherland Drive/Valley Stream Drive intersection. The traffic to/from Sandcastle Drive has been assumed from the 2017 count as it is a collector road serving the Bruce Farm neighborhood only. Comparing the google aerial imagery, only the development at 2940-2946 Baseline Road (Phase 1) occurred after 2017 traffic counts. The traffic generated from this development was added to the to/from Sandcastle Drive 2017 traffic counts to capture the traffic from this development (excerpts from the respective TIA is included in **Appendix G**).

Traffic count data is included in **Appendix D**. Traffic volumes within the study area are shown in **Figure 3**. Existing Signal Timing Plans for the study area intersections were also obtained from the City of Ottawa and are included in **Appendix E**.

Figure 3: Existing Traffic Volumes



2.1.8 Collision History

Historical collision data from 2018-2022 was obtained from the City's Public Works and Service Department for the study area intersections. Copies of the collision summary reports are included in **Appendix F**.

The collision data has been evaluated to determine if there are any identifiable collision patterns. The number of collisions at each intersection and segment from January 1, 2018, to December 31, 2022, is summarized in **Table 6** below.

Table 6: Collision History

Intersection/ Street Segment	Impact Types						Total
	Approach	Angle	Rear End	Sideswipe	Turning Movement	SMV ⁽¹⁾ / Other	
Intersection							
Richmond Road at Holly Acres Road/Nanaimo Drive	1	5	35	8	19	5	73
Richmond Road at John Sutherland Drive	0	2	11	2	5	0	20
Richmond Road/Robertson Road at Baseline Road/HWY416 IC75AR3	0	0	30	8	2	5	45
Baseline Road at Cedarview Road	0	0	5	2	6	3	16
Baseline Road at John Sutherland Drive/Valley Stream Drive	0	2	4	1	7	1	15
Baseline Road at Sioux Crescent	0	3	0	0	0	0	3
Baseline Road at Sandcastle Drive	0	1	4	1	3	0	9
Street Segment							
Richmond Road b/w John Sutherland Drive & Holly Acres Road	0	0	3	1	0	3	7
Richmond Road b/w HWY416 IC75A & John Sutherland Drive	0	0	3	0	0	2	5
Baseline Road b/w Richmond Road/Robertson	0	0	1	2	0	2	5

Intersection/ Street Segment	Impact Types						Total
	Approach	Angle	Rear End	Sideswipe	Turning Movement	SMV ⁽¹⁾ / Other	
Road & Cedarview Road							
Baseline Road b/w Cedarview Road & John Sutherland Drive	0	0	0	1	0	0	1
Baseline Road b/w Sioux Cr & Sandcastle Drive	0	0	1	0	0	1	2

1. SMV = Single Motor Vehicle

Richmond Road & Holly Acres/Nanaimo Drive

Fifteen of the Seventy-three collisions caused injuries, but none caused fatalities. One collision involved a cyclist and none involved a pedestrian.

Of the seventy-three collisions, fifty-eight occurred during clear conditions, nine in rain conditions, five in snow conditions, and one in freezing rain conditions. Additionally, fifty-one occurred in daylight conditions, one in dawn, five in dusk, and sixteen in dark conditions.

Of the rear-end collisions:

- four of the vehicles were heading northbound;
- fourteen of the vehicles were heading southbound;
- eleven of the vehicles were heading eastbound; and,
- six of the vehicles were heading westbound.

The southbound approach has a downgrade, and the high number of collisions may be attributable to the downgrade.

Of the turning-movement collisions:

- two involved northbound left turning vehicles;
- one involved southbound left turning vehicle;
- seven involved eastbound left turning vehicles; and,
- five involved westbound left turning vehicles.

One of the turning movement collisions involved a northbound left turning vehicle and a southbound traveling cyclist. This collision occurred in clear daylight conditions and resulted in non-fatal injuries.

Of the sideswipe collisions:

- two involved southbound vehicles;
- five involved eastbound vehicles; and,
- one involved westbound vehicle.

Richmond Road & John Sutherland Drive

Three of the twenty collisions caused injuries, but none caused fatalities. None of the collisions involved a cyclist or a pedestrian.

Of the twenty collisions, fourteen occurred during clear conditions, five in rain conditions, and one in snow conditions. Additionally, fifteen occurred in daylight conditions, two in dawn, and three in dark conditions.

Of the rear-end collisions:

- four of the vehicles were heading northbound;
- one of the vehicles was heading southbound;
- one of the vehicles was heading eastbound; and,
- five of the vehicles were heading westbound.

Richmond Road/Robertson Road & Baseline Road/HWY416 ON-Ramp

Eight of the forty-five collisions caused injuries, but none caused fatalities. One collision involved a cyclist and none involved a pedestrian.

Of the forty-five collisions, thirty-seven occurred during clear conditions, five in rain conditions, two in snow conditions, and one in fog, mist, smoke, dust conditions. Additionally, twenty-six occurred in daylight conditions, one in dawn, three in dusk, and seven in dark conditions.

The collision involving the cyclist was intersection related sideswipe collision while heading westbound. The car involved was changing lanes when it collided with the cyclist and caused a non-fatal injury. This collision may be attributable to improper lane change and failure to check blind spots.

Of the rear-end collisions:

- thirteen of the vehicles were heading northbound;
- two of the vehicles were heading southbound;
- six of the vehicles were heading eastbound; and,
- nine of the vehicles were heading westbound.

As there are clear sight lines on the northbound approach to the intersection, the rear-end collision pattern on this approach is likely attributable to high traffic volumes.

Of the sideswipe collisions:

- two involved northbound vehicles;
- three involved southbound vehicles; and,
- three involved westbound vehicles.

Baseline Road & Cedarview Road

Five of the sixteen collisions caused injuries, but none caused fatalities. One collision involved a cyclist, and one involved a pedestrian.

Of the sixteen collisions, thirteen occurred during clear conditions, and one in snow conditions. Additionally, thirteen occurred in daylight conditions, two in dusk, and one in dark condition.

The collision involving the cyclist occurred at the intersection and was described as a turning movement collision. The cyclist was heading northbound, and the vehicle was making a northbound left turn maneuver. This collision may be attributable to vehicle making northbound left maneuver failed to see the cyclist in its blind spot; or the cyclist suddenly entered the intersection while failing to dismount and walk the bicycle to cross the intersection.

Of the turning-movement collisions:

- one involved northbound left turning vehicles; and,
- five involved westbound left turning vehicles

Baseline Road & John Sutherland Drive/Valley Stream Drive

Five of the fifteen collisions caused injuries, but none caused fatalities. None of the collisions involved a cyclist or a pedestrian.

Of the fifteen collisions, eleven occurred during clear conditions, two in rain conditions, one in snow conditions, and one in fog, mist, smoke, dust conditions. Additionally, eleven occurred in daylight conditions, one in dawn, and three in dark condition.

Of the turning-movement collisions:

- six involved eastbound left turning vehicles; and,
- one involved westbound left turning vehicle.

Baseline Road & Sioux Crescent

None of the three collisions caused injuries/fatalities. And none of the collisions involved a cyclist or a pedestrian.

Baseline Road & Sandcastle Drive

Four of the nine collisions caused injuries, but none caused fatalities. None of the collisions involved a cyclist or a pedestrian.

Richmond Road between Holly Acres Road & John Sutherland Drive

None of the seven collisions caused injuries/fatalities. None of the collisions involved a cyclist or a pedestrian.

Richmond Road between John Sutherland Drive & Baseline Road/HWY416 ON-Ramp

None of the five collisions caused injuries/fatalities. None of the collisions involved a cyclist or a pedestrian.

Baseline Road between Richmond/Roberson Road & Cedarview Road

One of the five collisions caused injuries, but none caused fatalities. None of the collisions involved a cyclist or a pedestrian.

Baseline Road between Cedarview Road & John Sutherland Drive

The only collision did not cause injuries/fatalities. And it did not involve a cyclist or a pedestrian.

Baseline Road between Sioux Crescent & Sandcastle Drive

None of the two collisions caused injuries/fatalities. And none of the collisions involved a cyclist or a pedestrian.

2.2 Planned Conditions

2.2.1 Transportation Projects

The City's 2013 *Transportation Master Plan (TMP)*, and the recently approved *2025 TMP Capital Infrastructure Plan (CIP)* identify the following planned transportation projects that influence the study area.

Baseline Transitway – Median Bus Rapid Transit

The 2013 TMP affordable network plan identifies an at-grade Bus Rapid Transit (BRT) project from Baseline Station to Heron Station, while the network concept plan identifies it from Bayshore Station to St. Laurent Station. The Baseline Road Bus Rapid Transit (BRBRT) Environmental Project Report (EPR) was prepared by Parsons in July 2017. Based on the EPR, it is understood that the BRBRT project will be implemented in 3 phases, with phase 1 being Greenbank/Baseline intersection interim transit priority measures, phase 2 being Algonquin Station to Heron Station BRT, and phase 3 being Algonquin Station to Bayshore BRT. Relevant excerpts of the functional design within the study area are included in **Figure 4** to **Figure 7**.

Within the recently approved *2025 TMP CIP*, needs based network identifies the project extents from Bayshore Station to St. Laurent Station via Heron Station. Priority Transit Network identifies the extents from Algonquin College to Billings Bridge. Based on the CIP, there is no timeframe available for implementation of the BRBRT through the study area.

Robertson Road/Richmond Road – Transit Priority Project

The 2013 TMP affordable and network concept identify transit signal priority and queue jump lanes between Eagleson Road and Holly Acres Road.

The recently approved *2025 TMP CIP* Needs Based Network, and the Priority Network identifies Robertson Road from Mill Hill Road to Baseline Road and Richmond Road from Holly Acres Road to Carling Avenue as Transit Priority Corridors.

Active Transportation Projects

The recently approved TMP CIP identifies the implementation of a new sidewalk along Nanaimo Drive from Richmond Road to the Nanaimo Park. This project is scheduled for implementation as part of the first phase.

The TMP CIP also identifies the implementation of separated cycling facilities and/or bike lanes on Richmond Road from Carling Avenue to Holly Acres Road. The proposed cycling facilities will be implemented through two separate projects, which are both identified for implementation as part of the first phase.

Figure 4: Baseline Transitway Functional Design STA 18+925 to 19+520




Figure 5: Baseline Transitway Functional Design STA 19+520 to 30+100




Figure 6: Baseline Transitway Functional Design STA 19+920 to 30+600





Figure 7: Baseline Transitway Functional Design STA 30+600 to 31+260



2.2.2 Other Area Developments

In the vicinity of the subject site, the following developments were identified that are under construction, approved, or in the approval process. Relevant excerpts from the respective TIAs are included in **Appendix G**.

42 Northside Road

The proposed development will consist of five-storey apartment building, with a total of 51 dwellings. A TIA was prepared by Stantec in May 2022, in support of Site Plan Control application. Per the TIA, the anticipated buildout year was 2023.

1987 Robertson Road & 295 Moodie Drive

The proposed development will consist of eight high-rise buildings and one mid-rise building, with a total of 1,925 dwellings and approximately 41,657 ft² GFA of commercial space. A TIA was prepared by CGH in September 2021, in support of Official Plan Amendment and Zoning By-Law Amendment applications. Per the TIA, the development will be built in five phases, with an ultimate buildout year 2029.

2940-2946 Baseline Road

A TIA was prepared by Parsons in July 2024 for the remaining phases of the proposed residential development. At the time of the report Tower 1 was built and occupied, and Tower 2 was under construction. The report studied the impacts of Towers 4, 5, and 6.

2165 Robertson Road

The proposed development will consist of a single-storey warehouse and a single-storey building with three restaurant units. In total, the development will include approximately 11,757 ft² GFA of warehouse space and 6,017 ft² GFA of restaurant space. A TIA and a subsequent addendum were prepared by Parsons in December 2018 and December 2020, respectively, in support of a Site Plan Control application. The TIA had originally anticipated a buildout year of 2019.

1826 Robertson Road

The proposed mixed-use development is expected to generate 150 and 141 vehicle trips during the AM and PM peak hours, respectively. The site was anticipated to be completed in 2024.

2.3 Study Area and Time Periods

The study area for this report includes the boundary roadways Baseline Road and Richmond Road, as well as the following intersections:

- Richmond Road and Holly Acres Road and Nanaimo Drive
- Richmond Road and John Sutherland Drive
- Richmond Road/Robertson Road and Baseline Road/HWY416 ON-Ramp
- Baseline Road and Cedarview Road
- Baseline Road and John Sutherland Drive/Valley Stream Drive
- Baseline Road and Sandcastle Drive
- John Sutherland Drive and Main QCH Access
- John Sutherland Drive and Irving Greenberg Cancer Center Access
- John Sutherland Drive and North QCH Access
- John Sutherland Drive and TL2 Parking Lot Access/Private Access

The selected time periods for the analysis are the weekday AM and PM peak hours, as they represent the 'worst case' combination of site generated traffic and adjacent street traffic. Analysis has been completed for the Part 4 expansion ultimate buildout year 2030 and 2035 horizon year.

2.4 Development Generated Travel Demand

2.4.1 Trip Generation

The trip generation rates from the *ITE Trip Generation Manual 11th Edition* were first considered and were compared with the QCH's local trip generation rate based on the turning movement counts (TMC) commissioned by Novatech at the Richmond Road/John Sutherland Drive and Baseline Road/John Sutherland Drive/Valley Stream Drive intersections. These two intersections encompass the QCH campus and are assumed to represent the traffic generated by the hospital, since all the other intersections on John Sutherland Drive lead to QCH related land use.

Concerns regarding cut-through traffic were raised by the QCH. The concern was that the traffic utilizes John Sutherland Drive to cut-through between Richmond Road and Baseline Road. To estimate the percentage of cut-through traffic on John Sutherland Drive, the difference between the AM and PM peak period traffic volumes entering/exiting the QCH parking lots and the traffic entering/exiting the boundary intersections of QCH i.e., John Sutherland Drive/Richmond Road and John Sutherland Drive/Baseline Road/Valley Stream Drive was determined. This is shown in **Figure 8**. It is assumed that the cut-through traffic would only use John Sutherland Drive, and the traffic on the west ring road are destined to/from either the parking garage, the James Beach parking lot, or the front public parking lot.

From **Figure 8**, 2,084 vehicles arrived/departed QCH during the AM period (7am-10am) and 1,808 vehicles arrived/departed QCH during the PM period (3pm-6pm); and 1,966 vehicles arrived/departed parking lots during the AM period and 1,582 vehicles arrived/departed parking lots during the PM period. Detailed estimation of cut-through traffic is shown in **Table 7**.

Figure 8: Estimation of Cut-through Traffic on John Sutherland Drive




Table 7: Estimation of Cut-through Traffic

Traffic Direction	AM Peak Period		PM Peak Period	
	Total Volume	Cut-through Volume	Total Volume	Cut-through Volume
Traffic Entering from Richmond Road and Exiting on Baseline Road				
Total IN from Richmond Road	764 veh.	764 – 760 = 4 veh.	249 veh.	249 – 207 = 42 veh.
Total into Parking Lots	760 veh.		207 veh.	
Total OUT from Parking Lots	346 veh.	372 – 346 = 26 veh.	453 veh.	480 – 453 = 27 veh.
Total OUT onto Baseline Road	372 veh.		480 veh.	
Total IN/OUT Volume Cutting through from Richmond Road to Baseline Road	4 + 26 = 30 veh.		42 + 27 = 69 veh.	
Traffic Entering from Baseline Road and Exiting on Richmond Road				
Total IN from Baseline Road	668 veh.	668 – 594 = 74 veh.	319 veh.	319 – 224 = 95 veh.
Total into Parking Lots	594 veh.		224 veh.	
Total OUT from Parking Lots	266 veh.	280 – 266 = 14 veh.	698 veh.	760 – 698 = 62 veh.
Total OUT onto Richmond Road	280 veh.		760 veh.	
Total IN/OUT Volume Cutting through from Baseline Road to Richmond Road	74 + 14 = 88 veh.		95 + 62 = 157 veh.	
Total Two-way Cut-through Traffic Volume				
	(30 + 88)/2 = 59 veh.		(69 + 157)/2 = 113 veh.	

Based on **Table 7**, it is estimated that 59 and 113 vehicles may have cut through the QCH campus during the AM and PM peak periods respectively. Since the calculations consider the traffic both in/out of John Sutherland Drive and in/out of the parking lots, this equates to a cut through rate of 3% during the AM period and 6% during the PM period. For the purposes of this report, an averaged cut-through rate of 5% is assumed for both the AM and PM peak hours.

Table 8 summarizes the TMCs at the QCH encompassing intersections.

Table 8: Vehicles Trips Generated by QCH under Existing Conditions

Intersections	Movement	AM Peak Hour of Adjacent Street	PM Peak Hour of Adjacent Street
Richmond Road/John Sutherland Drive & Baseline Road/John Sutherland Drive/Valley Stream Drive	Vehicles into QCH	588 vehicles	200 vehicles
	Vehicles out from QCH	276 vehicles	552 vehicles
	Total Two-Way	864 vehicles	752 vehicles
<i>Accounting for estimated cut-through traffic at rate of 5%</i>			
Total Two-Way		821 vehicles	714 vehicles

The ITE trip generation manual for land use code 610 – Hospital, uses three independent variables for defining trip generation rates, viz., number of beds, number of employees, and GFA

of the hospital. The QCH local trip generation rates were also defined based on these three variables to keep the approach consistent and to rationalize the comparison of ITE and QCH local trip rates. The trip generation rates obtained from the *ITE Vehicle Trip Generation Manual 11th Edition* are summarized in **Table 9**, and the QCH local trip generation rates are summarized in **Table 10**.

Table 9: Vehicle Trip Generation Rates from ITE Trip Generation Manual 11th Edition

Independent Variable	Value	AM Peak ITE Avg Rate	PM Peak ITE Avg Rate
No of Beds	287 beds	1.79	1.69
No of Employees	1337 employees	0.28	0.28
GFA	637,444 ft ²	0.82	0.86

Table 10: QCH Local Vehicle Trip Generation Rates

Independent Variable	Value	AM Peak QCH Local Rate	PM Peak QCH Local Rate
No of Beds	287 beds	2.86	2.49
No of Full-Time Employees	1337 employees	0.61	0.53
GFA	637,444 ft ²	1.29 per 1000 ft ²	1.12 per 1000 ft ²

Comparing the trip generation rates in **Table 9** and **Table 10**, it is evident that the QCH local trip generation rates are considerably higher than the ITE trip generation rates. This may be because the ITE rates are based on the surveys for US hospitals, which operate differently than the medical system in Canada. The US has many private hospitals and public hospitals whereas Canada relies only on limited number of public hospitals. Hence, for the purposes of this report, QCH local trip generation rates were used as they are more representative of the traffic generated by this site.

As mentioned earlier in section 2.1.5, the peak period boarding/alighting/average load at departure data for transit at the nearby QCH transit stops was obtained from OC Transpo. This data was used to understand the existing transit modal share for the trips generated due to QCH. The data provided by OC Transpo is summarized in **Table 4** and the peak period transit data converted to peak hour transit data is summarized in **Table 5**.

The transit ridership analysis within the BRBRT EAS report was carried out by Parsons with the data obtained from OC Transpo. It was concluded in the report that the transit ridership is higher within the eastern segment of the study area, i.e., east of Woodroffe Avenue, and that the passenger volumes were generally lower towards the western end of the corridor. It must be noted that the QCH falls at the very end of the western corridor. Table 2-3 of the report summarizes the transit passenger volumes on Baseline Road and is included in **Appendix H**. This is consistent with the low transit ridership as seen in **Table 4** and **Table 5**.

From **Table 5**, the total peak hour transit trips generated by QCH are 51 and 41, during the AM and PM peak hours respectively.

Table 12 of the *TRANS Trip Generation Manual – Summary Report* lists out the employment generator mode share by district during the AM peak period. For Bayshore/Cedarview district, the modal shares are given as:

- Auto Driver: 77%
 - Auto Passenger: 6%
 - Walking: 4%
- Transit: 10%
Cycling: 3%

Since the available transit data is evidence of lower transit trip rate in the case of QCH, and people receiving medical care are more often dropped off/picked up, the existing modal shares for QCH have been assumed as below for the purposes of this report:

- Auto Driver: 80%
 - Auto Passenger: 10%
- Transit: 5%
Cycling and Walking: 5%

From **Table 10**, the vehicle trip generation rates can be converted to person trip generation rates based on the assumed 80% auto modal share for QCH. Hence, the QCH local person trip generation rates are derived and are summarized in the **Table 11**.

Table 11: QCH Person Trip Generation Rates

Independent Variable	Value	AM Peak QCH Local Rate	PM Peak QCH Local Rate
No of Beds	287 beds	3.58	3.11
No of Full-Time Employees	1337 employees	0.77	0.67
GFA	637,444 ft ²	1.62 per 1000 ft ²	1.40 per 1000 ft ²

From **Table 11**, it can be observed that the trip generation rates vary significantly based on the independent variable used. An average of all the three variables was considered to reduce the dependency on any one of the variables. The net person trips generated by the QCH Part 4 expansion thus can be estimated and is summarized in **Table 12**. The directional distribution is based on the existing QCH pattern, which is 68% in and 32% out during the AM peak and 27% in and 73% out during the PM peak.

Table 12: Net Person Trips Generated by Proposed QCH Expansion

Land Use	Independent Variable	Value	AM Peak			PM Peak		
			IN	OUT	TOTAL	IN	OUT	TOTAL
Existing Person Trips								
Total Existing			698	329	1027	241	652	893
QCH Part 4 Expansion								
Hospital	No of Beds	444 beds	1081	509	1590	373	1008	1381
	No of Employees	2066 employees	1082	509	1591	374	1010	1384
	GFA	1,023,388 ft²	1127	531	1658	387	1046	1433
Part 4 Expansion Average			1097	516	1613	378	1021	1399
Net New Person Trips Added by Part 4 Expansion			399	187	586	137	369	506

To reduce the number of trips generated by auto driver mode, a shift towards active modes of transport and increase in transit modal share is being targeted as part of the expansion. This is planned to be achieved through implementation of Transportation Demand Management (TDM) measures and a reduced parking ratio as the QCH campus develops. The proposed shift in modal

shares will assist in reducing the parking demand to achieve the proposed parking supply. Detailed parking demand calculations are provided in the section 4.2 of the report.

As mentioned in section 2.1.5 that the transit service in the west end of the Baseline corridor is limited, it is anticipated that the increase in transit modal shift can be achieved through the years. Also, it may be noted that early implementation of Baseline BRT phase 3 (Algonquin to Bayshore stretch), or improved transit service is desirable to provide better transit services at the west end of Baseline corridor. It is acknowledged that the recently launched New Ways to Bus initiative by OC Transpo has resulted in route 88 Bayshore↔Hurdman (frequent service) providing service to QCH via John Sutherland Drive, which earlier used Baseline Road as its route. Route 88 also provides connectivity to LRT Line 1 and Line 2. New OC Transpo route, route 68 Terry Fox↔Baseline (frequent service) has been implemented as part of New Ways to Bus initiative. It provides connectivity to locations west of QCH, and route 88 provides connectivity to locations east of QCH. With now improved east-west transit connectivity, it is anticipated that the target transit modal shares can be achieved overtime.

The cycling facilities (MUP, paved shoulder, bike lane etc.) surrounding QCH are advantageous and are anticipated to promote the shift towards active modes of transportation.

The target modal shares for Part 4 expansion are as follows:

- Auto Driver: 65%
- Auto Passenger: 15%
- Transit: 10%
- Cycling and Walking: 10%

The net new trips added to the network based on the assumed target modal shares for QCH Part 4 expansion are summarized in **Table 13**.

Table 13: Part 4 Expansion Net New Person Trips Based on Assumed QCH Modal Shares

		Net New Person Trips Added					
Modal Split	Modal Share	AM Peak			PM Peak		
		IN	OUT	TOTAL	IN	OUT	TOTAL
Existing							
Auto Driver	80%	559	263	822	193	521	714
Auto Passenger	10%	70	33	103	24	65	89
Transit	5%	35	16	51	12	33	45
Cycling and Walking	5%	35	16	51	12	33	45
Adjustment of Existing Trips due to Shift in Modal Shares towards Non-auto Modes							
Auto Driver	65%	454	214	668	157	423	580
Auto Passenger	15%	105	49	154	36	98	134
Transit	10%	70	33	103	24	65	89
Cycling and Walking	10%	70	33	103	24	65	89
Person Trips Added by QCH Part 4 Expansion							
Auto Driver	65%	259	122	381	89	240	329
Auto Passenger	15%	60	28	88	21	55	76
Transit	10%	40	19	59	14	37	51

Modal Split	Modal Share	Net New Person Trips Added					
		AM Peak			PM Peak		
		IN	OUT	TOTAL	IN	OUT	TOTAL
Cycling and Walking	10%	40	19	59	14	37	51
Net New Trips Added by QCH Part 4 Expansion							
Auto Driver	65%	154	73	227	53	142	195
Auto Passenger	15%	95	44	139	33	88	121
Transit	10%	75	36	111	26	69	95
Cycling and Walking	10%	75	36	111	26	69	95

2.4.2 Trip Distribution

The number of patient visits in 2024 to QCH from postal code areas for the Ottawa and surrounding regions was provided by QCH. This data was analyzed and was assigned a to/from direction based on the relative location of QCH to the Forward Sortation Area (FSA) segment of the postal code, i.e., the first three characters of the postal code. As per this method, the trip distribution was found to be:

- to/from north: 5%
- to/from south: 15%
- to/from east: 40%
- to/from west: 40%

The travel pattern based on the 2011 TRANS OD-Survey for Bayshore/Cedarview district was determined as:

- to/from north: 5%
- to/from south: 15%
- to/from east: 50%
- to/from west: 30%

The to/from north and south distribution is same in both the cases, however the to/from east and west trips vary by 10%. This may be because the patient visits by postal code data was available for areas outside of the areas that are considered in the TRANS OD-Survey. Since the hospital experiences trips both for visits by the patients and its employees, a blended trip distribution was used for the purposes of this report. The trip distribution derived is as follows:


- to/from north: 5%
- to/from south: 15%
- to/from east: 45%
- to/from west: 35%

2.4.3 Trip Assignment

Based on the existing traffic patterns of QCH, 65% of the traffic is assigned through the Richmond/John Sutherland Drive intersection, and the remaining 35% is assigned through the Baseline/John Sutherland Drive/Valley Stream Drive intersection. All new trips have been routed

through the QCH campus and assigned to the proposed parking garage addition. The trips assignment for Part 4 expansion is shown in **Figure 9**.

Figure 9: Trip Assignment



2.5 Exemptions Review

As per the city's 2023 Revisions to the TIA Guidelines, **Table 14** summarizes the exemptions applicable to the subject site.

Table 14: TIA Exemptions

Module	Element	Exemption Criteria	Status
Design Review Component			
4.1 Development Design	4.1.1 Design for Sustainable Modes.	Required for all.	Not Exempt
	4.1.2 Circulation and Access	Required for site plan and zoning by-law applications.	Not Exempt
	4.1.3 New Street Networks	Required for plans of subdivision.	Exempt
4.2 Parking	<i>All elements</i>	Required for site plan and zoning by-law applications.	Not Exempt
4.3 Boundary Street Design	<i>All elements</i>	Required for all.	Not Exempt
Network Impact Component			
4.5 Transportation Demand Management	<i>All Elements</i>	Required for all.	Not Exempt
4.6 Neighbourhood Traffic Calming	<i>All elements</i>	Required if all the below criteria are met: 1. Access is provided to a collector or local roadway. 2. Application is for zoning by-law amendment or draft plan of subdivision. 3. Proposed development generates more than 75 vehicle trips. 4. Site trip infiltration is expected, and site-generated traffic will increase peak hour volumes by 50%+ along the route between the site and an arterial road. 5. The subject street segment is adjacent to two or more of the following significant sensitive land uses: ○ School (within 250m walking distance) ○ Park ○ Retirement/older adult facility ○ Licensed childcare centre ○ Community centre	Exempt

Module	Element	Exemption Criteria	Status
		<ul style="list-style-type: none"> 50+% of adjacent properties along the route(s) are occupied by residential lands and at least ten dwellings are occupied 	
4.7 Transit	4.7.1 Transit Route Capacity	Required when the proposed development generates more than 75 transit trips.	Not Exempt
	4.7.2 Transit Priority Requirements	Required when the proposed development generates more than 75 vehicle trips.	Not Exempt
4.8 Network Concept	<i>All elements</i>	Required when the proposed development generates >200 person trips during the peak hour in excess of the equivalent volume permitted by the established zoning.	Exempt
4.9 Intersection Design	<i>All elements</i>	Required when the proposed development generates more than 75 vehicle trips.	Not Exempt

3.0 FORECASTING

3.1 Background Traffic

3.1.1 Other Area Developments

As discussed in section 2.2.2, there are multiple development applications for sites in proximity of the subject site that are under construction, approved, or in approval process. Traffic generated by these developments have been accounted for as background traffic. Relevant excerpts from respective transportation studies of each development listed below are included in **Appendix G**.

42 Northside Road

The proposed development will consist of five-storey apartment building, with a total of 51 dwellings. A TIA was prepared by Stantec in May 2022, in support of Site Plan Control application. Per the TIA, the anticipated buildout year was 2023. The site generated traffic has been added to the background traffic at all relevant intersections within the study area for this TIA.

1987 Robertson Road & 295 Moodie Drive

The proposed development will consist of eight high-rise buildings and one mid-rise building, with a total of 1,925 dwellings and approximately 41,657 ft² GFA of commercial space. A TIA was prepared by CGH in September 2021, in support of Official Plan Amendment and Zoning By-Law Amendment applications. Per the TIA, the development will be built in five phases, with an ultimate buildout year 2029. The site generated traffic has been added to the background traffic at all relevant intersections within the study area for this TIA.

2940-2946 Baseline Road

A TIA was prepared by Parsons in July 2024 for the remaining phases of the proposed residential development. At the time of the report Tower 1 was built and occupied, and Tower 2 was under construction. The report studied the impacts of Towers 4, 5, and 6. Traffic from towers 2, 4, 5, and 6 has been added to the background traffic conditions at all relevant intersections within the

study area for this TIA, as stated within the TIA report Tower 3 was altered to be included within Tower 4.

2165 Robertson Road

The proposed development will consist of a single-storey warehouse and a single-storey building with three restaurant units. In total, the development will include approximately 11,757 ft² GFA of warehouse space and 6,017 GFA of restaurant space. A TIA and a subsequent addendum were prepared by Parsons in December 2018 and December 2020, respectively, in support of a Site Plan Control application. The TIA had originally anticipated a buildout year of 2019. The site generated traffic has been added to the background traffic at all relevant intersections within the study area for this TIA.

1826 Robertson Road

The proposed mixed-use development is expected to generate 150 and 141 vehicle trips during the AM and PM peak hours, respectively. The site was anticipated to be completed in 2024, and the site generated traffic has been added to the background traffic at all relevant intersections within the study area for this TIA.

3.1.2 Background Growth Rate

A rate of background growth has been established through a review of snapshots of the City's Strategic Long-Range Model (comparing 2022 and 2046 AM peak volumes). The snapshots are included in **Appendix I**. The snapshots suggest negligible growth along Robertson Road/Richmond Road and Baseline Road; and suggest a growth of 5% along Cedarview Road. However, comparing two traffic counts at the Baseline Road/Cedarview Road intersection dated January 15, 2019, and March 05, 2025, it suggests that the traffic declined in 2025.

From other recent traffic reports within the study area, growth rates between 0.5% and 1% were used in most of the previous reports. To ensure a conservative analysis and to be consistent with previous studies in the vicinity of the subject site, a background growth rate of 0.5% per annum was applied to Holly Acres Road, Richmond Road, Robertson Road, and Baseline Road, and 2% was applied to Cedarview Road.

3.1.3 Future Traffic Conditions

3.1.3.1 Background Traffic Redistribution due to Site Modifications

Within the Part 4 phasing plans, the proposed site modifications include the construction of the west ring road, reduction of number of parking spaces in parking lots TL2 and 2A, the relocation of access to lot TL2 from the Hydro Access/John Sutherland Drive intersection to Truck Access/John Sutherland Drive intersection and a new secondary access from the snow dump area, the removal of access to the parking garage from the existing loading area to the new west ring road, and realignment of John Sutherland Drive and reconfiguration of the John Sutherland Drive/West Ring Road intersection. These modifications will affect the traffic flow within QCH campus.

Temporary parking lot is reduced to 48 parking spaces from the current 186 parking spaces, equivalent to a reduction of 74%. Similarly, Lot2A is reduced to 113 parking spaces from the current 122 parking spaces, equivalent to a reduction of 7%. These parking space reductions and new access to the parking garage have been accounted for and is shown in **Figure 12**.

The figures listed below present the following future traffic conditions:

- Part 4 expansion:
 - Background traffic volumes in 2030 are shown in **Figure 10**,
 - Background traffic volumes in 2035 are shown in **Figure 11**,
 - Site redistributed traffic volumes are shown in **Figure 12**,
 - Site generated traffic volumes are shown in **Figure 13**,
 - Total traffic volumes in 2030 are shown in **Figure 14**,
 - Total traffic volumes in 2035 are shown in **Figure 15**,

Figure 10: Background 2030 Traffic Volumes




Figure 11: Background 2035 Traffic Volumes




Figure 12: Site Redistributed Traffic Volumes




Figure 13: Net Site Generated Traffic Volumes




Figure 14: Total 2030 Traffic Volumes





Figure 15: Total 2035 Traffic Volumes



3.2 Demand Rationalization

A review of the existing and background intersection operations has been conducted to determine if and when traffic volumes exceed capacity within the study area. Intersection parameters in the analysis are consistent with the City's 2017 TIA guidelines (saturation flow rate: 1800 vphpl, existing conditions PHF: 0.9, future conditions PHF: 1.0).

Per the City's 2024 TMP Part 1, the city-wide target vehicular level of service (Auto LOS) is an Auto LOS E, which equates to a maximum v/c ratio of 1.0 for signalized intersections or delay of 50 seconds at unsignalized intersections.

3.2.1 Existing Conditions

Intersection capacity analysis has been completed for the existing traffic volumes (See **Figure 3**) and is summarized in **Table 15**. Detailed Synchro 11 analysis reports for existing conditions are included in **Appendix J**.

Table 15: Existing Conditions Intersection Operations

Intersection	AM Peak			PM Peak		
	Max V/C or Delay	LOS	Mvmt	Max V/C or Delay	LOS	Mvmt
Richmond Road / Holly Acres Road / Nanaimo Drive	0.75	C	EBL	0.88	D	NBL
Richmond Road / John Sutherland Drive	0.71	C	SBL	0.97	E	WB
Richmond Road / Robertson Road/Baseline Road / HWY416 On-ramp	0.65	B	WBL	0.87	D	WBL
Baseline Road / Cedarview Road	0.55	A	EBT	0.67	B	NBL
Baseline Road / Valley Stream Drive / John Sutherland Drive	0.56	A	EBT	0.73	C	SB
Baseline Road / Sandcastle Drive	0.53	A	EB	0.48	A	WBT
John Sutherland Drive / West Ring Road (South)	11 sec	B	SB	13 sec	B	SB
John Sutherland Drive / QCH Irving Greenberg Cancer Center	8 sec	A	WB	8 sec	A	EB
John Sutherland Drive / West Ring Road (North)	10 sec	A	EB	10 sec	A	NB

Intersection	AM Peak			PM Peak		
	Max V/C or Delay	LOS	Mvmt	Max V/C or Delay	LOS	Mvmt
John Sutherland Drive / QCH Lot TL2	11 sec	B	SB	12 sec	B	SB

The following summarizes the results from **Table 15** based on the synchro analysis, for the existing traffic conditions:

Richmond Road/Holly Acres Road/Nanaimo Drive

All movements operate with a LOS C or better during the AM peak and a LOS D or better during the PM peak. During the AM and PM peaks, the 95th percentile queue length of the westbound through/left turn movement is approximately 25m and 50m respectively, exceeding the available storage length of 20m. The 95th percentile queue length of the northbound left turn movement is approximately 35m and 65m respectively, exceeding the available storage length of 25m.

Richmond Road/John Sutherland Drive

All movements operate with a LOS C or better during the AM peak hour and a LOS E or better during the PM peak hour.

The 95th percentile queue length for the southbound left turn movement is approximately 80m during the AM peak hour, exceeding the available storage length of 45m.

Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp

All movements operate with a LOS B or better during the AM peak and a LOS D or better during the PM peak hour.

Baseline Road/Cedarview Road

All movements operate with a LOS A during the AM peak and a LOS B or better during the PM peak hour. The 95th percentile queue length for the northbound left turn movement is approximately 40m and 45m under the AM and PM peaks respectively, exceeding the available storage of 25m potentially blocking the adjacent northbound right turn lane.

Baseline Road/John Sutherland Drive/Valley Stream Drive

All movements operate with a LOS A during the AM peak and a LOS C or better during the PM peak hour.

Baseline Road/Sandcastle Drive

All movements operate with a LOS A during the AM and PM peaks.

All QCH accesses on John Sutherland Drive

All accesses operate with a LOS B or better during the AM and PM peak hours.

3.2.2 2030 Background Traffic Operations

Intersection capacity analysis has been conducted for the 2030 background traffic volumes (See **Figure 10**) and summarized in **Table 16**. Detailed Synchro 11 analysis reports for background conditions are included in **Appendix K**.

Table 16: 2030 Background Traffic Operations

Intersection	AM Peak			PM Peak		
	Max V/C or Delay	LOS	Mvmt	Max V/C or Delay	LOS	Mvmt
Richmond Road / Holly Acres Road / Nanaimo Drive	0.73	C	EBL	0.80	C	EBL
Richmond Road / John Sutherland Drive	0.63	B	SBL	0.92	E	WB
Richmond Road / Robertson Road/Baseline Road / HWY416 On-ramp	0.65	B	WBL	0.84	D	WBL
Baseline Road / Cedarview Road	0.52	A	EBT	0.67	B	NBL
Baseline Road / Valley Stream Drive / John Sutherland Drive	0.52	A	EBT	0.69	B	SB
Baseline Road / Sandcastle Drive	0.53	A	EB	0.47	A	WBT
John Sutherland Drive / West Ring Road (South)	11 sec	B	SB	12 sec	B	SB
John Sutherland Drive / QCH Irving Greenberg Cancer Center	8 sec	A	WB	8 sec	A	EB
John Sutherland Drive / West Ring Road (North)	9 sec	A	EB	10 sec	B	NB
John Sutherland Drive / QCH Lot TL2	11 sec	B	SB	11 sec	B	SB

The intersection operations within the study area are anticipated to be generally consistent with the existing conditions. It is noteworthy that due to the change in peak hour factor associated with future conditions, operations and queues for some movements may have improved slightly compared to the existing conditions analysis. The following summarizes the results from **Table 16** based on the synchro analysis, for the background 2030 traffic conditions:

Richmond Road/Holly Acres Road/Nanaimo Drive

All movements operate with a LOS C or better during the AM peak and PM peak. During the AM and PM peaks, the 95th percentile queue length of the westbound through/left movement is approximately 25m and 45m respectively exceeding the available storage of 20m. The 95th percentile queue length of the northbound left turn movement is 35m and 55m respectively, exceeding the available storage length of 25m.

Richmond Road/John Sutherland Drive

All movements operate with a LOS C or better during the AM peak hour and a LOS E or better during the PM peak hour. The 95th percentile queue length for the southbound left turn movement is approximately 50m, exceeding the available storage length of 45m.

Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp

Similar to the existing conditions, all movements operate with a LOS B or better during the AM peak and a LOS D or better during the PM peak hour.

Baseline Road/Cedarview Road

Similar to the existing conditions, all movements operate with a LOS A during the AM peak and a LOS B or better during the PM peak hour. The 95th percentile queue length for the northbound left turn movement is approximately 40m and 45m under the AM and PM peaks respectively, exceeding the available storage of 25m and potentially blocking the adjacent northbound right turn lane.

Baseline Road/John Sutherland Drive/Valley Stream Drive

All movements operate with a LOS A during the AM peak and a LOS B or better during the PM peak hour.

Baseline Road/Sandcastle Drive

All movements operate with a LOS A during the AM and PM peaks.

All QCH accesses on John Sutherland Drive

All accesses operate with a LOS B or better during the AM and PM peak hours.

3.2.3 2035 Background Traffic Operations

Intersection capacity analysis has been conducted for the 2035 background traffic volumes (See **Figure 11**) and summarized in **Table 17**. Detailed Synchro 11 analysis reports for background conditions are included in **Appendix K**.

Table 17: 2035 Background Traffic Operations

Intersection	AM Peak			PM Peak		
	Max V/C or Delay	LOS	Mvmt	Max V/C or Delay	LOS	Mvmt
Richmond Road / Holly Acres Road / Nanaimo Drive	0.74	C	EBL	0.83	C	NBL
Richmond Road / John Sutherland Drive	0.64	B	SBL	0.92	E	WB
Richmond Road / Robertson Road/Baseline Road / HWY416 On-ramp	0.65	B	WBL	0.85	D	WBL
Baseline Road / Cedarview Road	0.54	A	EBT	0.69	B	NBL

Intersection	AM Peak			PM Peak		
	Max V/C or Delay	LOS	Mvmt	Max V/C or Delay	LOS	Mvmt
Baseline Road / Valley Stream Drive / John Sutherland Drive	0.53	A	EBT	0.69	B	SB
Baseline Road / Sandcastle Drive	0.54	A	EB	0.48	A	WBT
John Sutherland Drive / West Ring Road (South)	11 sec	B	SB	12 sec	B	SB
John Sutherland Drive / QCH Irving Greenberg Cancer Center	8 sec	A	WB	8 sec	A	EB
John Sutherland Drive / West Ring Road (North)	9 sec	A	EB	10 sec	B	NB
John Sutherland Drive / QCH Lot TL2	11 sec	B	SB	11 sec	B	SB

Based on the foregoing, the intersection operations within the study area are anticipated to be generally consistent with the 2030 background traffic conditions.

4.0 ANALYSIS

4.1 Development Design

4.1.1 Design for Sustainable Modes

Under the existing campus conditions, a sidewalk network is provided along the periphery of the campus buildings. As part of Part 4 expansion, pedestrian facilities near the main entrance at the south end of the building will remain unchanged. Minor modifications to the south parking lots are proposed to increase the parking supply. The existing pathways north/west of the existing parking garage will be reconfigured to accommodate the new parking garage and west ring road. The pathway on the west side of the new west ring will continue to function as part of the City's Crosstown Bikeway network. Two new pedestrian crossings are proposed on the west ring road to provide connectivity to the western pathway networks.

John Sutherland Drive east of the hospital will be realigned further east to allow for the hospital expansion. As part of this, sidewalks will be provided on both sides of the road from the West Ring Road to the Emergency Department, where the sidewalk on the west side of the road continues to the Irving Greenberg Cancer Centre. A new off-road pedestrian pathway is proposed on the east side of John Sutherland Drive along its entire stretch. Three accesses to this pathway are proposed: one each at the extremes of John Sutherland Drive, and one to the east of Irving Greenberg Cancer Center. Three new pedestrian crossings are proposed along John Sutherland Drive to provide connectivity to the bus stops, pathways, and parking north/east of the road. It is

recommended that all new pedestrian crossings be designed in accordance with Ontario Traffic Manual (OTM) Book 15 requirements for a PXO Type D.

Transit will be maintained on John Sutherland Drive as part of this development. The existing bus stops and shelters near the Irving Greenberg Cancer Centre (Stops #0727 and #0728) will be maintained as part of the site plan. The existing bus stops and shelters near the emergency centre (#0947 and #0950) will be relocated to the realigned roadway. The southbound bus stop (#0950) will be relocated to the intersection of John Sutherland Drive/West Ring Road.

A total of 105 bicycle parking spaces will be provided on-site. 78 spaces will be provided within the new parking garage, 4 spaces will be provided in the landscaped area in front of parking lot TL2, 5 spaces will be provided at the entrance of Irving Greenberg Cancer Center, 14 spaces will be provided within the visitors parking lot, and 4 spaces will be provided in the middle of the new proposed pathway on the east side of John Sutherland Drive.

The Part 4 expansion of the QCH campus has been assessed using the Transportation Demand Management (TDM) – Supportive Development Design and Infrastructure Checklist. A copy of the TDM checklist is included in **Appendix L**. In addition to the required measures, the proposed development also meets the following 'basic' or 'better' measures on the checklist:

- Locate building entrances in order to minimize walking distances to sidewalks and transit stops/stations.
- Locate building doors and windows to ensure visibility of pedestrians from the building, for their security and comfort;
- Provide safe, direct and attractive walking routes from building entrances to nearby transit stops;
- Ensure that walking routes to transit stops are secure, visible, lighted, shaded and wind-protected wherever possible;
- Provide wayfinding signage for site access (where required, e.g. when multiple buildings or entrances exist) and egress (where warranted, such as when directions to reach transit stops/stations, trails or other common destinations are not obvious);
- Provide shower and change facilities for the use of active commuters;
- Provide shelters, lighting and benches at any on-site transit stops;
- Provide a designated area for carpool drivers (plus taxis and ride-hailing services) to drop off or pick up without using fire lanes or other no-stopping zones.

4.1.2 Circulation and Access

Material Management/Garbage Collection/Gas Delivery



All hospital related material delivery/pickup, and garbage collection activities will take place from the material management facility's loading/unloading docks located beside Irving Greenberg Cancer Center. Propane gas delivery will occur within parking lot TL2 as the propane storage tanks are located beside this parking lot. Diesel delivery will take place at the diesel storage tanks located between the two parking garages. Turning Movements for a WB-20 Tractor Semitrailer entering/exiting and maneuvering within the material management facility are shown from **Figure 16** to **Figure 22**. Turning movement for a 7000 WD Standard Tanker (fuel delivery truck) at the diesel storage tanks is shown in **Figure 23**. Turning Movements for a WB-20 Tractor Semitrailer entering/exiting parking lot TL2 are shown from **Figure 24** to **Figure 26**.

M:\2023\123089\CAD\Civil\Figures\Traffic\123089-TM-Ultimate.dwg, Fig23_16, Nov 19, 2025 - 1:25pm, rhiller



Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com




WB-20 - Tractor & Semi-Trailer	
Overall Length	22.700m
Overall Width	2.600m
Overall Body Height	3.730m
Min Body Ground Clearance	0.435m
Track Width	2.600m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	14.300m

QUEENSWAY CARLETON HOSPITAL - ULTIMATE TURNING MOVEMENTS (WB-20)

SCALE 1 : 750


DATE NOV 2025 JOB 123089 FIGURE 16

M:\2023\123089\CAD\Civil\Figures\Traffic\123089-TM-Ultimate.dwg, Fig24_17, Nov 19, 2025 - 1:25pm, rhiller



Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com



WB-20 - Tractor & Semi-Trailer

Overall Length	22.700m
Overall Width	2.600m
Overall Body Height	3.730m
Min Body Ground Clearance	0.435m
Track Width	2.600m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	14.300m

QUEENSWAY CARLETON HOSPITAL - ULTIMATE TURNING MOVEMENTS (WB-20)

SCALE 1 : 750

DATE NOV 2025

JOB 123089



FIGURE FIGURE 17

M:\2023\123089\CAD\Civil\Figures\Traffic\123089-TM-Ultimate.dwg, Fig25_18, Nov 19, 2025 - 1:25pm, rhiller



Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com



WB-20 - Tractor & Semi-Trailer

Overall Length	22.700m
Overall Width	2.600m
Overall Body Height	3.730m
Min Body Ground Clearance	0.435m
Track Width	2.600m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	14.300m

QUEENSWAY CARLETON HOSPITAL - ULTIMATE TURNING MOVEMENTS (WB-20)

SCALE 1 : 750


DATE NOV 2025 JOB 123089 FIGURE FIGURE 18

M:\2023\123089\CAD\Civil\Figures\Traffic\123089-TM-Ultimate.dwg, Fig26_19, Nov 19, 2025 - 1:25pm, rhiller



Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com




WB-20 - Tractor & Semi-Trailer

Overall Length	22.700m
Overall Width	2.600m
Overall Body Height	3.730m
Min Body Ground Clearance	0.435m
Track Width	2.600m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	14.300m

QUEENSWAY CARLETON HOSPITAL - ULTIMATE TURNING MOVEMENTS (WB-20)

SCALE 1 : 750

DATE NOV 2025 JOB 123089 FIGURE 19




M:\2023\123089\CAD\Civil\Figures\Traffic\123089-TM-Ultimate.dwg, Fig28_21, Nov 19, 2025 - 1:25pm, rhiller



Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com



WB-20 - Tractor & Semi-Trailer


Overall Length	22.700m
Overall Width	2.600m
Overall Body Height	3.730m
Min Body Ground Clearance	0.435m
Track Width	2.600m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	14.300m

QUEENSWAY CARLETON HOSPITAL - ULTIMATE TURNING MOVEMENTS (WB-20)

SCALE 1 : 750


DATE NOV 2025 JOB 123089 FIGURE 21

M:\2023\123089\CAD\Civil\Figures\Traffic\123089-TM-Ultimate.dwg, Fig29_22, Nov 19, 2025 - 1:25pm, rhiller



Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com



WB-20 - Tractor & Semi-Trailer

Overall Length	22.700m
Overall Width	2.600m
Overall Body Height	3.730m
Min Body Ground Clearance	0.435m
Track Width	2.600m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	14.300m

QUEENSWAY CARLETON HOSPITAL - ULTIMATE

TURNING MOVEMENTS (WB-20) - ULTIMATE LOADING

SCALE 1 : 750

DATE NOV 2025

JOB 123089


FIGURE FIGURE 22

M:\2023\123089\CAD\Civil\Figures\Traffic\123089-TM-Ultimate.dwg, Fig30_23, Nov 19, 2025 - 1:25pm, rhiller



Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com



7000 WD STANDARD TANKER

Overall Length	12.014m
Overall Width	2.743m
Overall Body Height	2.704m
Min Body Ground Clearance	0.470m
Track Width	2.743m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	16.154m

QUEENSWAY CARLETON HOSPITAL - ULTIMATE

TURNING MOVEMENTS (FUEL DELIVERY TRUCK)

SCALE 1 : 500




DATE NOV 2025

JOB 123089


FIGURE FIGURE 23

M:\2023\123089\CAD\Civil\Figures\Traffic\123089-TM-Ultimate.dwg, Fig31_24, Nov 19, 2025 - 1:25pm, rhiller



Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com



WB-20 - Tractor & Semi-Trailer

Overall Length	22.700m
Overall Width	2.600m
Overall Body Height	3.730m
Min Body Ground Clearance	0.435m
Track Width	2.600m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	14.300m

QUEENSWAY CARLETON HOSPITAL - ULTIMATE TURNING MOVEMENTS (WB-20)


SCALE 1 : 750

DATE NOV 2025

JOB 123089


FIGURE FIGURE 24

M:\2023\123089\CAD\Civil\Figures\Traffic\123089-TM-Ultimate.dwg, Fig32_25 Nov 19, 2025 - 1:25pm, rhiller



Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com



WB-20 - Tractor & Semi-Trailer

Overall Length	22.700m
Overall Width	2.600m
Overall Body Height	3.730m
Min Body Ground Clearance	0.435m
Track Width	2.600m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	14.300m


QUEENSWAY CARLETON HOSPITAL - ULTIMATE TURNING MOVEMENTS (WB-20)

SCALE 1 : 750

DATE NOV 2025

JOB 123089

FIGURE 25




Fire Routes

John Sutherland Drive between Richmond Road and Main QCH Access/John Sutherland Drive intersection is designated as a fire route. Whole of QCH west ring road, and ambulance/police bay in front of the emergency department are also designated as fire routes. All three of these fire routes meet the minimum clear width requirement of 6.0m for a fire route.

Ambulance Garage and Ambulance/Police Bay


Ambulance garage is located beside the emergency department off John Sutherland Drive. In front of the emergency department, an ambulance bay and parking for ambulance/police is also provided. Turning movements in the ambulance bay are shown in **Figure 27**.

M:\2023\123089\CAD\CIVIL\FIGURES\TRAFFIC\123089-TM-AMBULANCEGARAGE.DWG 11/19/2025 1:38 PM - RHILLIER



Engineers, Planners & Landscape Architects
Suite 200, 240 Michael Cowpland Drive
Ottawa, Ontario, Canada K2M 1P6

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com



Horton 553 Type III - Ford E Ambulance

Overall Length	6.82m
Overall Width	2.445m
Overall Body Height	2.394m
Min Body Ground Clearance	0.386m
Track Width	2.445m
Lock-to-lock time	5.00s
Curb to Curb Turning Radius	8.352m

QUEENSWAY CARLETON HOSPITAL - ULT- OPT2

TURNING MOVEMENTS - AMBULANCE GARAGE

SCALE 1 : 300

DATE NOV 2025 JOB 123089 FIGURE 27

4.2 Parking

4.2.1 Existing Parking Supply

The existing estimated parking supply for staff, visitors, and patients is approximately 1320 parking spaces. A summary of the existing parking supply is provided in **Table 18**.

Table 18: Existing Campus Parking Supply

Parking Lot	Users	Type of Facility	Number of Spaces
Existing Parking Garage	Staff	Parking Garage – 7 Levels	582
James Beach Parking Lot	Staff	Surface Lot	47
West Layby	Staff/Visitor	Surface	4
Maternity	Staff/Visitor	Surface	7
West Surface Parking Lot	Visitors	Surface Lot	93
Visitors Parking Lot 6	Visitors	Surface Lot	273
Main Entrance	Staff/Visitor	Surface	7
Short Term Parking	Staff/Visitor	Surface	14
Irving Greenberg Lot 2A	Staff	Surface Lot	82
Irving Greenberg Lot 2B	Staff	Surface Lot	38
Temporary Lot TL2	Staff	Surface Lot	163
Total Existing Number of Parking Spaces			1310

Derivation of Existing Parking Ratio

Currently QCH has a supply of approximately 1310 parking spaces including those for employees and visitors. Based on the existing aggregate auto modal share of 80% (estimated in section 2.4.1), it has been assumed that under existing conditions the employee trips auto modal share is 80%, planned patient visits auto modal share is 80%, and unplanned (emergency) patient visits auto modal share is 95%. Based on the information provided by the QCH, approximately 1945 staff and patients are expected to drive to the hospital over the course of a day. The ratio of existing parking supply to the anticipated visits is approximately 0.68 spaces per visitor.

While the above parking demand has been calculated based on the current parking supply, QCH staff have advised that there is a wait list for parking and the current parking demands are not met based on the current parking supply.

4.2.2 Part 4 Expansion Parking

The proposed parking supply for staff, visitors and patients for Part 4 expansion is 1760 parking spaces. A summary of the proposed parking supply is provided in **Table 19**.

Table 19: Part 4 Expansion Parking Supply

Parking Lot	Users	Type of Facility	Number of Spaces
New Parking Garage	Staff	Parking Garage	553
Existing Parking Garage	Staff	Parking Garage	582
James Beach Parking Lot	Staff	Surface Lot	27
West Layby	Staff/Visitor	Surface	4
Maternity	Staff/Visitor	Surface	7
West Surface Parking Lot	Visitors	Surface Lot	102
Visitors Parking Lot 6	Visitors	Surface Lot	301

Parking Lot	Users	Type of Facility	Number of Spaces
Main Entrance	Staff/Visitor	Surface	7
Short Term Parking	Staff/Visitor	Surface	18
Irving Greenberg Lot 2A	Staff	Surface Lot	62
Irving Greenberg Lot 2B	Staff	Surface Lot	51
Temporary Lot TL2	Staff	Surface Lot	46
Total Proposed Number of Parking Spaces			1760

The subject site is located in Area C of Schedule 1 and Schedule 1A of the City of Ottawa Zoning By-Law (ZBL). Section 101, 102, and 111 of the ZBL sets out the minimum required vehicle, visitor vehicle, and bicycle parking space rates respectively for various land uses. Section 112 of the Traffic and Parking By-law sets out the required rates of accessible parking spaces from the total number of parking spaces provided. The minimum number of required parking spaces as per the city's ZBL requirements are summarized in **Table 20**.

Table 20: Part 4 Expansion Minimum Required Parking Spaces

Land Use	Parking Space Rate	Gross GFA (m ²)	Min. Spaces Required	Spaces Provided
Part 4 Expansion				
<i>Minimum Vehicle Parking</i>				
Hospital	Min. required by-law rate = 1.4 per 100 m ² of GFA	95,076 m ²	1331 spaces	1760 spaces
<i>Minimum Bicycle Parking</i>				
Hospital	1 per 1000 m ² of GFA	95,076 m ²	95	105
<i>Minimum Accessible Parking</i>				
Hospital	11 + 1% of total parking spaces	95,076 m ²	31	74

Based on the foregoing, the proposed vehicle and bicycle parking for the Part 4 expansion adhere to the requirements of the City's ZBL.

To understand the future parking demand for the Part 4 expansion, a review of planned employee and patient visits has been completed using data from QCH. Detailed parking calculations are included in **Appendix M**. Based on the data provided, it is estimated that approximately 2,835 staff and patients will drive to visit the hospital over the course of a day if the existing modal shares are maintained. Applying the existing parking ratio of 0.68 spaces per visitor to the proposed visitors results in a parking demand for approximately 1,930 parking spaces.

Assuming the proposed modal shares in section 2.4.1 are met, it is estimated that approximately 2,360 staff and patients will drive to visit the hospital over the course of a day. Applying the existing parking ratio of 0.68 spaces per visitor to the proposed visitors results in a parking demand for approximately 1,600 parking spaces.

However, as noted previously the existing parking supply falls short of the current parking demand for the site. While QCH has committed to providing Transportation Demand Management (TDM) measures within the development to help shift modal shares, the effectiveness of measures is not known, and measures may take time to alter employee and visitor travel behaviors. Additionally, there are no major transit improvements proposed by the city to assist in shifting modal shares.

As such, the proposed parking supply will be roughly midway between the anticipated parking demand based on the existing and proposed modal shares.

4.3 Boundary Streets

A review of the study area boundary streets Baseline Road, and Richmond Road was conducted for existing conditions based on the city's complete street principles. The *MMLOS Guidelines*, produced by IBI Group in October 2015, were used to evaluate the levels of service for each alternative mode of transportation on the boundary streets.

Baseline Road and Richmond Road have been evaluated based on the targets for an arterial road under other designated land uses, as listed in the Exhibit 22 of the *MMLOS Guidelines*. A detailed MMLOS analysis is included in **Appendix N**. A summary of the segment MMLOS analysis for Baseline Road and Richmond Road is provided in **Table 21**.

Table 21: Segment MMLOS Summary

Segment	PLOS		BLOS		TLOS		TkLOS	
	Actual	Target	Actual	Target	Actual	Target	Actual	Target
Richmond Road	F	D	E	B	D	D	A	D
Baseline Road	F		E	C	D		A	

Richmond Road between John Sutherland Drive and Holly Acres Road/Nanaimo Drive

Richmond Road does not achieve the target PLOS and BLOS. It achieves the target TLOS and TkLOS. The stretch of Richmond Road between John Sutherland Drive and Baseline Road has a bridge that passes over HWY416 and limits the width of the roadway and hence has not been evaluated for PLOS.

Per Exhibit 4 of the MMLOS guidelines, Richmond Road can achieve the target PLOS D by providing a sidewalk of minimum 2.0m width and a boulevard of width >2.0m if the existing operating speed of 90kmph is to be maintained.

Per Exhibit 11 of the MMLOS guidelines, Richmond Road can only achieve the target BLOS B through the implementation of a separated cycling facility.

As Richmond Road is a rural arterial roadway, the above pedestrian and cycling improvements are identified for the city's consideration as part of future roadway projects.

Baseline Road between Cedarview Road and John Sutherland Drive/Valley Stream Drive

Baseline Road does not achieve the target PLOS and BLOS. It achieves the target TLOS and TkLOS.

Per Exhibit 4 of the MMLOS guidelines, Baseline Road can achieve the target PLOS D by providing a sidewalk of minimum 2.0m width and a boulevard of width >2.0m on the south side of the road if the existing operating speed of 80kmph is to be maintained. It is noted that the subject site frontage meets the target PLOS D.

Per Exhibit 11 of the MMLOS guidelines, Baseline Road can only achieve the target BLOS C through the implementation of a separated cycling facility. It is noteworthy that the city's Baseline

BRT project will provide new sidewalks and cycle tracks along the corridor, achieving the target PLOS and BLOS.

4.4 Transportation Demand Management

4.4.1 Context for TDM

Comparison of Modal Shares

The existing modal shares of the QCH were estimated based on the data collected locally. This is described in detail in section 2.4.1. The existing modal shares are as follows:

- Auto Driver: 80%
- Auto Passenger: 10%
- Transit: 5%
- Cycling and Walking: 5%

Table 12 of the *TRANS Trip Generation Manual – Summary Report* lists out the employment generator mode share by district during the AM peak period. For Bayshore/Cedarview district, the modal shares are given as:

- Auto Driver: 77%
- Auto Passenger: 6%
- Walking: 4%
- Transit: 10%
- Cycling: 3%

As stated in section 2.4.1, as part of the expansion, a shift in modals shares towards non-auto modal share is being targeted. The target modal shares for the expansion are as follows:

Part 4 Expansion:

- Auto Driver: 60%
- Auto Passenger: 15%
- Transit: 15%
- Cycling and Walking: 10%

Development Operation

The QCH campus currently employs around 1337 full-time employees and observes an estimated 789 planned visits and 255 unplanned (emergency) visits daily. With the proposed QCH expansion, these numbers are anticipated to increase as follows:

- Part 4 Expansion:
 - Number of full-time employees: 2066 employees;
 - Number of daily planned visits: 1118 visits;
 - Number of daily unplanned visits: 303 visits;

4.4.2 Need and Opportunity

As stated in the above section, a shift in non-auto modal shares is being targeted as part of the expansion. To achieve the proposed target modal shares, a focus on the measures tailored to improve transit, walking and cycling are required.

The improved east-west transit connectivity with the recently implemented OC Transpo routes 68 and 88 are anticipated to promote transit usage and help achieve the target transit modal share. The active transportation infrastructure (MUP, crosstown bikeway etc.) are anticipated to promote the target active modal shares.

4.4.3 TDM Program

Discussions were held with QCH to understand the existing TDM program and develop a planned program to assist in shifting modal shares. While the City of Ottawa TDM measures checklist for non-residential developments was used as a basis for the TDM discussions, additional hospital specific measures were discussed. A copy of the city's TDM checklist summarizing the existing and planned TDM program is included in **Appendix L**. A comprehensive list, including hospital specific measures is summarized below.

TDM measures that are currently in place within the QCH hospital include:

- Provide opportunities for staff to work from home, if they have the ability.
- Partnerships with rural hospitals, to allow doctors to travel to rural areas to provide health care services typically provided at QCH. This would reduce the number of patients visiting from rural areas outside the city.
- Provide safe, secure, convenient, and comfortable bike parking to encourage cycling.
- Provide a dynamic parking policy that prioritizes rural patients, carpoolers, pick up/drop off patients/employees.
- Charge for long-term parking (daily, weekly, monthly). To reduce the incentive to drive, increase daily parking rates for employees.
- Charge for short-term parking (hourly).
- Provide a multi-modal travel information package for new staff.
- Provide patients with information on specialized mobility incentives that are available to them (i.e. Para Transpo, Taxi Reimbursements, etc.)
- Provide clinics during evenings and weekends to shift trips outside the weekday peak periods.
- Explore opportunities for some employees to work outside peak periods.

In addition to the above measures that are currently in place, the following TDM measures will be implemented within the QCH hospital:

- Provide virtual care to reduce the number of patients who need to come to the QCH campus.
- Provide full- or part-time staff who will be dedicated to collecting data, managing incentives, and evaluating impacts of TDM measures. This staff will liaise with various leadership groups to develop a TDM strategy.
- Develop a TDM platform to track multimodal commute data, provide rewards and incentives, and serving as a resource/communications hub. This is overseen by the Transportation Coordinator.
- Build a high quality, secure, indoor bike parking facility that meets the needs of cyclists and sets a cycling culture/foundation for employees
- Purchase or lease a fleet of bikes and e-bikes that can be rented out to employees at minimal cost.
- Provide real-time transit display screens near main building entrances.
- Incentivize employees to use sustainable modes by introducing cycling challenges, etc.

The proposed TDM program will assist in achieving a higher auto passenger, transit, and cycling modal share for the hospital. The implementation of a TDM coordinator will allow the hospital to track TDM programs for effectiveness and develop an improved program over time.

4.5 Neighborhood Traffic Calming

This element is exempt from the analysis as the minimum criteria for neighbourhood traffic calming is not met.

4.6 Transit

4.6.1 Transit Capacity

Based on the trip generation estimates in section 2.4.1, the proposed development is anticipated to generate the following number of additional transit trips:

- Part 4 Expansion: 75 IN and 36 OUT in the AM peak, and 26 IN and 69 OUT in the PM peak.

All site-generated transit trips are anticipated to arrive or depart the study area via OC Transpo Routes 57, 68, and 88. All trips will utilize the stops on John Sutherland Drive (stops #0950, #0727, #0947, and #0728). The transit trip distribution is anticipated to follow the travel pattern based on the 2011 TRANS OD-Survey for Bayshore/Cedarview district determined as:

- 35% will travel to/from the east via Route 57.
- 10% will travel to/from the west via Route 57.
- 10% will travel to/from the east via Route 68.
- 10% will travel to/from the west via Route 68.
- 35% will travel to/from the east via Route 88.

Peak period transit utilization data dated April 1, 2025, was obtained from OC Transpo and is included in **Appendix C**. This peak period data was converted to peak hour data in section 2.1.5. The data obtained reflects the routes and the stops they had served prior to the recent implementation (April 27, 2025) of OC Transpo initiative “New Ways to Bus”. The changes are as follows:

- Route 57: Remains unchanged.
- Route 58: Has changed to run between Crystal Bay and Bayshore Station and is not serving QCH anymore.
- Route 68: This is a new route implemented to run between Terry Fox and Baseline Stations. Runs on John Sutherland Drive to directly serve QCH campus.
- Route 88: Changed to run between Bayshore and Hurdman Stations. Service west of QCH has been removed and replaced with route 68. Has been changed to run from QCH on John Sutherland Drive, Richmond Road, and Holly Acres Road. Previously, it had served stops #0946 and #0941 at Baseline Road/John Sutherland Drive, which are interpreted as QCH related stops.

As transit data for the new routes is not available, the specific bus loads departing QCH have not been reviewed. However, based on the anticipated transit distribution, the additional transit usage is summarized in **Table 22**.

Table 22: Part 4 Expansion Addition Transit Usage

Route	Direction	AM Peak		PM Peak	
		IN	OUT	IN	OUT
57	EB	8	13	3	24
	WB	26	4	9	7
68	EB	8	4	3	7
	WB	8	4	3	7
88	EB	0	13	0	24
	WB	26	0	9	0

4.6.2 Transit Priority

Within the study area, the delays that the transit buses experience will be that of what the auto drivers will experience since all buses are in mixed traffic lanes.

The delays prior to Part 4 expansion along the transit movements within the study are summarized in **Table 23** based on the control delays obtained from Synchro Analysis. The target TLOS within the study area as mentioned in section 4.8.1 is TLOS D based on the 2017 MMLOS guidelines.

Table 23: Transit Delays – 2030 Background Traffic Conditions

Intersection	Transit Mvmt	AM Peak Hour		PM Peak Hour	
		Delay (sec.)	LOS	Delay (sec.)	LOS
Richmond Road/Holly Acres Road/Nanaimo Drive	EBL	46	F	53	F
	EBR	8	B	10	B
	NBL	19	C	35	E
	SBR	0	B	0	B
Richmond Road/John Sutherland Drive	WBL	28	D	66	F
	WBR	28	D	66	F
	NBR	0	B	1	B
	SBL	16	C	11	C
Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp	WBL	44	F	54	F
	NBT	18	C	21	D
	NBR	4	B	4	B
	SBT	7	B	11	C
Baseline Road/Cedarview Road	EBT	21	D	11	C
	WBT	10	B	5	B
Baseline Road/John Sutherland Drive/Valley Stream Drive	EBL	10	B	10	B
	WBR	7	B	0	B
	SBL	24	D	40	E
	SBR	24	D	40	E
Baseline Road/Sandcastle Drive	EBT	2	B	5	B
	WBT	6	B	7	B

Based on the foregoing, the eastbound left turn movement at the Richmond Road/Holly Acres Road/Nanaimo Drive intersection and the westbound left turn movement at the Baseline Road/Richmond Road/Robertson Road intersection are not anticipated to meet the target TLOS D during the AM and PM peak hours. As identified in section 2.2.1, the City's recently approved

2025 TMP CIP includes the Robertson Road and Richmond Road Transit Priority project. Consideration should be given by the city to implementing left turn queue jump lanes at the aforementioned intersections as part of this project.

The westbound left and right turn movements at the Richmond Road/John Sutherland Drive intersection are not anticipated to meet the target TLOS D during the PM peak hour. To provide additional capacity and improved transit operations, consideration should be given to widening the John Sutherland Drive approach to this intersection to provide two outbound lanes. A further review of intersection operations will be provided in the following sections.

4.7 Network Concept

This module is exempt as no changes to the Transportation Master Plan concepts for auto or transit networks are required to accommodate the development-generated travel demands.

4.8 Intersection Design

4.8.1 Existing Intersection MMLOS Review

A review of the signalized study area intersections was conducted for existing conditions based on the City's complete street principles. The *MMLOS Guidelines*, produced by IBI Group in October 2015, were used to evaluate the levels of service for each alternative mode of transportation at the intersections.

The MMLOS at these intersections have been evaluated based on the targets for an arterial road under other designated land uses, as listed in the Exhibit 22 of the *MMLOS Guidelines*. A detailed MMLOS analysis is included in **Appendix N**. A summary of the intersection MMLOS results for Baseline Road and Richmond Road is provided in **Table 24**.

Table 24: Intersection MMLOS Summary

Intersection	PLOS		BLOS		TLOS		TKLOS	
	Actual	Target	Actual	Target	Actual	Target	Actual	Target
Richmond Road/Holly Acres Road/Nanaimo Drive	F	D	F	B	E	D	E	D
Richmond Road/John Sutherland Drive	F		F		F		E	
Richmond Road/Robertson Road/Baseline Road/HWY419 ON-Ramp	F		F		F		C	
Baseline Road/Cedarview Road	F		D	C	C		C	
Baseline Road/John Sutherland Drive/Valley Stream Drive	F		F		F		E	
Baseline Road/Sandcastle Drive	F		F		B		E	

Richmond Road/Holly Acres Road/Nanaimo Drive

This intersection does not meet the target PLOS, BLOS, and TLOS.

None of the approaches meet the target PLOS D. The south, east, and west approaches have a width equivalent of ten plus lanes, seven lanes, and ten plus lanes crossed respectively. There is

limited opportunity to improve the PLOS on these approaches without reducing the number of travel lanes crossed and restricting turning movements. All the approaches do not meet the city's vehicle/pedestrian conflict threshold for zebra-striped crosswalk (greater than 400,000 vehicle/pedestrian conflicts over an eight-hour period).

None of the approaches meet the target BLOS B. The north, south and west approaches achieve a BLOS F based on the left turn characteristics and the high posted speed limit of 60kmph. The implementation of two-stage left turn facilities is required to meet the target BLOS B.

The south and west approaches do not meet the target TLOS D. The north approach meets the target TLOS. As identified in section 4.6.2, consideration should be given by the city to implementing an eastbound right left turn queue jump lane at this intersection as part of the Robertson Road and Richmond Road Transit Priority project.

Richmond Road/John Sutherland Drive

This intersection does not meet the target PLOS, BLOS, TLOS, and TkLOS.

The west approach meets the target PLOS D. The north, south, and east approaches have a width equivalent of eight lanes, eight lanes, and seven lanes crossed respectively. There is limited opportunity to improve the PLOS on north, south and east approaches without reducing the number of travel lanes crossed and restricting turning movements. All the approaches do not meet the city's vehicle/pedestrian conflict threshold for zebra-striped crosswalk (greater than 400,000 vehicle/pedestrian conflicts over an eight-hour period).

None of the approaches meet the target BLOS B. The north and south approaches achieve a BLOS F based on the left turn characteristics and the high posted speed limit of 80kmph. The implementation of two-stage left turn facilities is required to meet the target BLOS B.

The east approach does not meet the target TLOS D. The north and south approaches meet the target TLOS. As identified in section 4.6.2, to provide additional capacity and improved transit operations, consideration should be given to widening the John Sutherland Drive approach to this intersection to provide two outbound lanes. A further review of intersection operations will be provided in the following sections.

The north and south approaches do not meet the target TkLOS D. There is only one receiving lane when departing from the north and south approaches. Since both these receiving approaches are private roads, no improvement measures are identified.

Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp

This intersection does not meet the target PLOS, BLOS, and TLOS.

The west approach meets the target PLOS D. The south approach does not have a pedestrian crossing. The north and east approaches have a width equivalent of 9 and 10+ lanes crossed respectively. There is limited opportunity to improve the level of service without reducing the number of travel lanes crossed. All the approaches do not meet the city's vehicle/pedestrian conflict threshold for zebra-striped crosswalk (greater than 400,000 vehicle/pedestrian conflicts over an eight-hour period).

None of the approaches except the west approach meet the target BLOS B. The north approach achieves a BLOS F based on the left turn characteristics and the high posted speed limit of

80kmph. The south approach has its right-turn lane longer than 50m thereby achieving it a BLOS F. The east approach has a right-turn lane introduced to the right of bike lane >50m thereby achieving a BLOS D. There is limited opportunity to improve BLOS at this intersection without implementing a fully protected intersection design.

The east approach does not meet the target TLOS D. The north and south approaches meet the target TLOS. As identified in section 4.6.2, consideration should be given by the city to implementing a westbound left turn queue jump lane at this intersection as part of the Robertson Road and Richmond Road Transit Priority project.

Baseline Road/Cedarview Road

This intersection does not meet the target PLOS, and BLOS.

The south, east, and west approaches have a width equivalent of six lanes, eight lanes, and eight lanes crossed respectively. There is limited opportunity to improve the PLOS on these three approaches without reducing the number of travel lanes crossed and restricting turning movements. A pedestrian phase is provided along with a crosswalk and crossride connecting the north-south MUP.

All the approaches achieve the target BLOS C except the west approach. The introduction of right-turn lane to the right side of the bicycle lane >50m long achieves a BLOS D. As the bike lane remains to the left of the right turn lane from Robertson Road to Cedarview Road and there is limited opportunity to transition the bike lane to a cycle track on the intersection approach due to high traffic volumes and the bridge over HWY416, no recommendations have been identified.

Baseline Road/John Sutherland Drive/Valley Stream Drive

This intersection does not meet the target PLOS, BLOS, TLOS, and TkLOS.

The north, south, east, and west approaches have a width equivalent of eight lanes, seven lanes, seven lanes, and ten plus lanes crossed respectively. There is limited opportunity to improve the PLOS on all approaches without reducing the number of travel lanes crossed and restricting turning movements. The east and west approaches meet the city's vehicle/pedestrian conflict threshold for zebra-striped crosswalk (greater than 400,000 vehicle/pedestrian conflicts over an eight-hour period).

None of the approaches except south approach meet the target BLOS B. The north approach achieves a BLOS E based on the length of right turn lane. The east and west approaches achieve a BLOS F based on the left turn characteristics. The implementation of two-stage left turn facilities is required to meet the target BLOS B.

The north approach does not meet the target TLOS D. The east and west approaches meet the target TLOS. Since John Sutherland Drive is a private road, no improvement measures are identified on the east approach.

The west approach does not meet the target TkLOS D. There is only one receiving lane when departing from the west approach. Since the receiving approach is a local road, and truck traffic is not anticipated to be frequent, no improvement measures are identified.

Baseline Road/Sandcastle Drive

This intersection does not meet the target PLOS and BLOS.

The south, east, and west approaches have a width equivalent of five lanes, eight lanes, and seven lanes crossed respectively. There is limited opportunity to improve the PLOS on all approaches without reducing the number of travel lanes crossed and restricting turning movements. None of the approaches meet the city's vehicle/pedestrian conflict threshold for zebra-striped crosswalk (greater than 400,000 vehicle/pedestrian conflicts over an eight-hour period).

The south and west approaches do not meet the target BLOS B. The south approach achieves a BLOS D based on the length of right turn lane and number of lanes crossed for left turn. The west approach achieves a BLOS F based on the left turn characteristics.

4.8.2 2030 Total Intersection Operations

Intersection capacity analysis has been conducted for the 2030 total traffic conditions. The results of the analysis are summarised in **Table 25** for the weekday AM and PM peak hours. Detailed reports are included in **Appendix O**.

Table 25: 2030 Total Intersection Operations

Intersection	AM Peak			PM Peak		
	Max V/C or Delay	LOS	Mvmt	Max V/C or Delay	LOS	Mvmt
Richmond Road /Holly Acres Road / Nanaimo Drive	0.73	C	EBL	0.83	D	NBL
Richmond Road/John Sutherland Drive	0.82	D	SBL	1.11	F	WBT
Richmond Road/Robertson Road/Baseline Road/HWY416 On-ramp	0.65	B	WBL	0.84	D	WBL
Baseline Road /Cedarview Road	0.53	A	EBT	0.67	B	NBL
Baseline Road /Valley Stream Drive / John Sutherland Drive	0.58	A	SB	0.77	C	SB
Baseline Road /Sandcastle Drive	0.54	A	EBT	0.34	A	EBT
John Sutherland Drive / West Ring Road (South)	11 sec.	B	EB	12 sec.	B	EB
John Sutherland Drive / QCH Irving Greenberg Cancer Center	11 sec.	B	NB	11 sec.	B	NB
John Sutherland Drive / West Ring Road (North)	17 sec.	C	NB	18 sec.	C	NB

Intersection	AM Peak			PM Peak		
	Max V/C or Delay	LOS	Mvmt	Max V/C or Delay	LOS	Mvmt
John Sutherland Drive / QCH Lot TL2	9 sec.	A	SBR	9 sec.	A	SBR

The following summarizes the results from **Table 25** based on the synchro analysis, for the total 2030 traffic conditions:

Richmond Road/Holly Acres Road/Nanaimo Drive

Operations at this intersection are generally consistent with the 2030 background traffic conditions. All movements operate with a LOS C or better during the AM peak and a LOS D or better during the PM peak.

During the AM and PM peaks, the 95th percentile queue length of the westbound through/left movement is approximately 25m and 45m respectively exceeding the available storage of 20m. The 95th percentile queue length of the northbound left movement is approximately 35m and 60m respectively exceeding the available storage length of 25m.

Richmond Road/John Sutherland Drive

This intersection is anticipated to operate with a LOS D during the AM peak hour. However, the 95th percentile southbound left turn queues are anticipated to increase from approximately 55m to 95m, exceeding the existing storage of 45m.

The westbound approach is anticipated to operate with a LOS F during the PM peak hour.

To improve operations at this intersection, consideration has been given to a permitted and protected southbound left turn phase and widening of the westbound approach to two outbound lanes. Mitigated intersection operations are presented in **Table 26**.

Table 26: Mitigated Intersection Operations at Richmond Road & John Sutherland Drive

Turn Type	Mvmt	2030 Total AM Peak		2030 Total PM Peak	
		v/c	LOS	v/c	LOS
Permitted	WBL	0.48	A	0.74	C
Permitted	WBT/R	0.21	A	0.53	A
Protected + Permitted	SBL	0.59	A	0.23	A

The aforementioned mitigation measures are anticipated to yield a LOS A during the AM peak hour and a LOS C during the PM peak hour. The 95th percentile southbound left turn queues are anticipated to reduce to approximately 30m during the AM peak hour and will be accommodated within the existing storage length.

Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp

Operations at this intersection are generally consistent with the 2030 background traffic conditions. All movements operate with a LOS B or better during the AM peak and a LOS D or better during the PM peak hour.

Baseline Road/Cedarview Road

Operations at this intersection are generally consistent with the 2030 background traffic conditions. All movements operate with a LOS A during the AM peak and a LOS B or better during the PM peak hour. The 95th percentile queue length for the northbound left turn movement is approximately 40m and 45m under the AM and PM peaks respectively, exceeding the available storage of 25m potentially blocking the adjacent northbound right turn lane.

Baseline Road/John Sutherland Drive/Valley Stream Drive

Operations at this intersection are generally consistent with the 2030 background traffic conditions. All movements operate with a LOS A during the AM peak and a LOS C or better during the PM peak hour.

Baseline Road/Sandcastle Drive

Operations at this intersection are generally consistent with the 2030 background traffic conditions. All movements operate with a LOS A during the AM and PM peaks.

All QCH accesses on John Sutherland Drive

All accesses operate with a LOS C or better during the AM and PM peak hours.

4.8.3 2035 Total Intersection Operations

Intersection capacity analysis has been conducted for the 2035 total traffic conditions. The results of the analysis are summarised in **Table 27** for the weekday AM and PM peak hours. Detailed reports are included in **Appendix O**.

Table 27: 2035 Total Intersection Operations

Intersection	AM Peak			PM Peak		
	Max V/C or Delay	LOS	Mvmt	Max V/C or Delay	LOS	Mvmt
Richmond Road /Holly Acres Road / Nanaimo Drive	0.74	C	EBL	0.87	D	NBL
Richmond Road/John Sutherland Drive	0.84	D	SBL	1.11	F	WBT
Richmond Road/Robertson Road/Baseline Road/HWY416 On-ramp	0.65	B	WBL	0.85	D	WBL
Baseline Road /Cedarview Road	0.55	A	EBT	0.69	B	NBL
Baseline Road /Valley Stream Drive / John Sutherland Drive	0.58	A	SB	0.77	C	SB
Baseline Road /Sandcastle Drive	0.55	A	EBT	0.49	A	WBT
John Sutherland Drive / West Ring Road (South)	11 sec.	B	EB	12 sec.	B	EB

Intersection	AM Peak			PM Peak		
	Max V/C or Delay	LOS	Mvmt	Max V/C or Delay	LOS	Mvmt
John Sutherland Drive / QCH Irving Greenberg Cancer Center	11 sec.	B	NB	11 sec.	B	NB
John Sutherland Drive / West Ring Road (North)	17 sec.	C	NB	18 sec.	C	NB
John Sutherland Drive / QCH Lot TL2	9 sec.	A	SBR	9 sec.	A	SBR

Based on the foregoing, the intersection operations within the study area are anticipated to be generally consistent with the 2030 total traffic conditions.

As identified above, a permitted and protected southbound left turn phase and widening of the westbound approach to two outbound lanes is anticipated to improve operations at the Richmond Road/John Sutherland Drive intersection. Mitigated intersection operations are presented in **Table 28**.

Table 28: Mitigated Intersection Operations at Richmond Road & John Sutherland Drive

Turn Type	Mvmt	2035 Total AM Peak		2035 Total PM Peak	
		v/c	LOS	v/c	LOS
Permitted	WBL	0.48	A	0.74	C
Permitted	WBT/R	0.22	A	0.53	A
Protected + Permitted	SBL	0.60	A	0.24	A

Based on the foregoing, mitigation measures are recommended for implementation as part of Part 4 expansion. A function design of the proposed roadway modifications is included in **Appendix P**.

4.8.4 Total 2035 Operations with Mainstreet Protected Left Turns at Richmond Road/John Sutherland Drive and Baseline Road/John Sutherland Drive

Per the request of the city, a scenario where fully protected left-turn movements are provided at northbound and southbound movements on Richmond Road at John Sutherland Drive and eastbound and westbound movements on Baseline Road at John Sutherland Drive intersections have been analysed. For the purposes of this assessment, it is assumed that the recommended two outbound lanes on John Sutherland Drive have been implemented. The results from the analysis are summarized in **Table 29**. Synchro Analysis Reports are included in **Appendix Q**.

Table 29: Analysis Results for Protected Mainstreet Left Turns at QCH intersections

Intersection	TOTAL 2035 AM Peak			TOTAL 2035 PM Peak		
	Max v/c	LOS	Mvmt	Max v/c	LOS	Mvmt
Richmond Road/John Sutherland Drive	0.72	C	SBL	0.58	A	SBL
Baseline Road/Valley Stream Drive/John Sutherland Drive	0.62	B	EBL	0.77	C	SBT

The following summarizes the results from **Table 29** based on the synchro analysis:

Richmond Road/John Sutherland Drive

All movements are anticipated to operate with LOS C or better during the AM and PM peaks.

During the AM peak, the 95th percentile queue length for the southbound left movement is anticipated to increase to approximately 70m from 30m, exceeding the available storage length of approximately 45m. The LOS is anticipated to decrease to LOS C from LOS A.

Based on the collision records presented in section 2.1.8, three turning movement collisions involving southbound left turning vehicles occurred over a five-year period. The previously proposed protected and permitted phasing will provide additional capacity for this movement and may reduce the number of southbound left turn collisions at this intersection going forward. As such, it is recommended that the city monitor this intersection following the QCH development to confirm if a fully protected phase is warranted based on the future collision patterns.

Baseline Road/John Sutherland Drive/Valley Stream Drive

All movements are anticipated to operate with LOS B or better during the AM peak and LOS C or better during the PM peak.

During the AM peak, the 95th percentile queue length for the eastbound left movement is anticipated to increase to approximately 55m from 30m, exceeding the available storage length of approximately 35m. The LOS is anticipated to decrease to LOS B from LOS A.

Based on the collision records presented in section 2.1.8, six turning movement collisions involving eastbound left turning vehicles occurred over a five-year period. Should fully protected eastbound and westbound left turn phases be desired by the city to address an existing or future collision pattern, an additional 20m of storage is recommended for the eastbound left turn lane. There is sufficient space within the existing grass median to extend the eastbound left turn lane to accommodate the protected phasing. This is identified for the City's consideration.

5.0 CONCLUSIONS AND RECOMMENDATIONS

The conclusions and recommendations of this TIA can be summarized as follows:

Trip Generation

- Based on the target modals shares, it is anticipated that the Part 4 expansion will generate 588 net new person trips (227 vehicle trips) during the AM peak and 506 net new person trips (195 vehicle trips) during the PM peak.

Existing Traffic Operations

- All study area intersections operate within acceptable Level of Service (LOS) during the AM and PM peaks.
- At Richmond Road/Holly Acres Road/Nanaimo Drive intersection, during the AM and PM peaks, the 95th percentile queue length of the westbound through/left turn movement exceeds the available storage length of 20m. The 95th percentile queue length of the northbound left turn movement exceeds the available storage length of 25m.
- At Richmond Road/John Sutherland Drive intersection, the 95th percentile queue length for the southbound left turn movement exceeds the available storage length of 45m during the AM peak hour.
- At Baseline Road/Cedarview Road, the 95th percentile queue length for the northbound left turn movement exceeds the available storage of 25m potentially blocking the adjacent northbound right turn lane during the AM and PM peak hours.

Background Traffic Operations

- Under the 2030 and 2035 background traffic operations, the intersection operations within the study area are anticipated to be generally consistent with the existing conditions.

Development Design

- Under the existing campus conditions, a sidewalk network is provided along the periphery of the campus buildings. As part of Part 4 expansion, pedestrian facilities near the main entrance at the south end of the building will remain unchanged.
- The existing pathways north/west of the existing parking garage will be reconfigured to accommodate the new parking garage and west ring road. The pathway on the west side of the new west ring will continue to function as part of the City's Crosstown Bikeway network. Two new uncontrolled pedestrian crossings are proposed on the west ring road to provide connectivity to the western pathway networks.
- John Sutherland Drive east of the hospital will be realigned further east to allow for the hospital expansion. As part of this, sidewalks will be provided on both sides of the road from the West Ring Road to the Emergency Department, where the sidewalk on the west side of the road continues to the Irving Greenberg Cancer Centre.
- A new off-road pedestrian pathway is proposed on the east side of John Sutherland Drive along its entire stretch. Three accesses to this pathway are proposed: one each at the extremes of John Sutherland Drive, and one to the east of Irving Greenberg Cancer Center.
- Three new uncontrolled pedestrian crossings are proposed along John Sutherland Drive to provide connectivity to the bus stops, pathways, and parking north/east of the road. It is recommended that all new uncontrolled pedestrian crossings be designed in accordance with Ontario Traffic Manual (OTM) Book 15 requirements for a PXO Type D.
- Minor modifications to the south parking lots are proposed to increase the parking supply.

- Transit will be maintained on John Sutherland Drive as part of this development. The existing bus stops and shelters near the Irving Greenberg Cancer Centre (Stops #0727 and #0728) will be maintained as part of the site plan. The existing bus stops and shelters near the emergency center (#0947 and #0950) will be relocated to the realigned roadway. The southbound bus stop (#0950) will be relocated to the intersection of John Sutherland Drive/West Ring Road.
- A total of 105 bicycle parking spaces will be provided on-site. 78 spaces will be provided within the new parking garage, 4 spaces will be provided in the landscaped area in front of parking lot TL2, 5 spaces will be provided at the entrance of Irving Greenberg Cancer Center, 14 spaces will be provided within the visitors parking lot, and 4 spaces will be provided in the middle of the new proposed pathway on the east side of John Sutherland Drive.
- All required TDM-supportive design and infrastructure measures in the TDM checklist are met.

Circulation and Access

- All hospital related material delivery/pickup, and garbage collection activities will take place from the material management facility's loading/unloading docks located beside Irving Greenberg Cancer Center.
- Propane gas delivery will occur within parking lot TL2 as the propane storage tanks are located beside this parking lot.
- Diesel delivery will take place at the diesel storage tanks located between the two parking garages
- John Sutherland Drive between Richmond Road and Main QCH Access/John Sutherland Drive intersection is designated as a fire route. Whole of QCH west ring road, and ambulance/police bay in front of the emergency department are also designated as fire routes. All three of these fire routes meet the minimum clear width requirement of 6.0m for a fire route.
- Ambulance garage is located beside the emergency department off John Sutherland Drive. In front of the emergency department, an ambulance bay and parking for ambulance/police is also provided.

Parking

- The ratio of existing parking supply to the anticipated visits is approximately 0.68 spaces per visitor. While this parking demand has been calculated based on the current parking supply, QCH staff have advised that there is a waitlist for parking, and the current demands are not met based on the current parking supply.
- Based on the proposed site plan, Part 4 expansion will have a supply of 1760 parking spaces.
- While QCH has committed to providing TDM measures within the development to help shift modal shares, the effectiveness of measures is not known, and measures may take

time to alter employee and visitor travel behaviors. Additionally, there are no major transit improvements proposed by the city to assist in shifting modal shares. As such, the proposed parking supply will meet the maximum parking demand while the modal shares from the development shift over time. As such, the proposed parking supply will be roughly midway between the anticipated parking demand based on the existing and proposed modal shares.

- The proposed number of vehicle, bicycle, and accessible parking spaces adhere to the minimum requirements of the Zoning By-law (ZBL).

Boundary Streets

- The results of the segment MMLOS can be summarised as follows:
 - None of the boundary streets meet the target pedestrian LOS D;
 - None of the boundary streets meet the target bicycle LOS B or C;
 - Both the boundary streets meet the target transit LOS D;
 - Both the boundary streets meet the target truck LOS D.
- Richmond Road can achieve the target PLOS D by providing a sidewalk of minimum 2.0m width and a boulevard of width >2.0m if the existing operating speed of 90kmph is to be maintained.
- Richmond Road can only achieve the target BLOS B through the implementation of a separated cycling facility.
- Baseline Road can achieve the target PLOS D by providing a sidewalk of minimum 2.0m width and a boulevard of width >2.0m on the south side of the road if the existing operating speed of 80kmph is to be maintained. It is noted that the subject site frontage meets the target PLOS D.
- Baseline Road can only achieve the target BLOS C through the implementation of a separated cycling facility. It is noteworthy that the city's Baseline BRT project will provide new sidewalks and cycle tracks along the corridor, achieving the target PLOS and BLOS.

Transportation Demand Management

- TDM measures that are currently in place within the QCH hospital include:
 - Provide opportunities for staff to work from home, if they have the ability.
 - Partnerships with rural hospitals, to allow doctors to travel to rural areas to provide health care services typically provided at QCH. This would reduce the number of patients visiting from rural areas outside the city.
 - Provide safe, secure, convenient, and comfortable bike parking to encourage cycling.
 - Provide a dynamic parking policy that prioritizes rural patients, carpoolers, pick up/drop off patients/employees.
 - Charge for long-term parking (daily, weekly, monthly). To reduce the incentive to drive, increase daily parking rates for employees.
 - Charge for short-term parking (hourly).
 - Provide a multi-modal travel information package for new staff.
 - Provide patients with information on specialized mobility incentives that are available to them (i.e. Para Transpo, Taxi Reimbursements, etc.)

- Provide clinics during evenings and weekends to shift trips outside the weekday peak periods.
 - Explore opportunities for some employees to work outside peak periods.
- In addition to the above measures that are currently in place, the following TDM measures will be implemented within the QCH hospital:
 - Provide virtual care to reduce the number of patients who need to come to the QCH campus
 - Provide full- or part-time staff who will be dedicated to collecting data, managing incentives, and evaluating impacts of TDM measures. This staff will liaise with various leadership groups to develop a TDM strategy.
 - Develop a TDM platform to track multimodal commute data, provide rewards and incentives, and serving as a resource/communications hub. This is overseen by the Transportation Coordinator.
 - Build a high quality, secure, indoor bike parking facility that meets the needs of cyclists and sets a cycling culture/foundation for employees
 - Purchase or lease a fleet of bikes and e-bikes that can be rented out to employees at minimal cost.
 - Provide real-time transit display screens near main building entrances.
 - Incentivize employees to use sustainable modes by introducing cycling challenges, etc.
- The proposed TDM program will assist in achieving a higher auto passenger, transit, and cycling modal share for the hospital. The implementation of a TDM coordinator will allow the hospital to track TDM programs for effectiveness and develop an improved program over time.

Transit

- The proposed Part 4 expansion is anticipated to generate the following number of additional transit trips: 75 IN and 36 OUT in the AM peak, and 26 IN and 69 OUT in the PM peak.
- Peak period transit utilization data dated April 1, 2025, was obtained from OC Transpo. The data obtained reflects the routes and the stops they had served prior to the recent implementation (April 27, 2025) of OC Transpo initiative "New Ways to Bus". As transit data for the new routes is not available, the specific bus loads departing QCH have not been reviewed. However, based on the anticipated transit distribution, the additional transit usage has been calculated.

Transit Priority

- The eastbound left turn movement at the Richmond Road/Holly Acres Road/Nanaimo Drive intersection and the westbound left turn movement at the Baseline Road/Richmond Road/Robertson Road intersection are not anticipated to meet the target TLOS D during the AM and PM peak hours. The City's recently approved 2025 TMP CIP includes the Robertson Road and Richmond Road Transit Priority project. Consideration should be given by the city to implementing left turn queue jump lanes at the aforementioned intersections as part of this project.

- The westbound left and right turn movements at the Richmond Road/John Sutherland Drive intersection are not anticipated to meet the target TLOS D during the PM peak hour. To provide additional capacity and improved transit operations, consideration have been given to widening the John Sutherland Drive approach to this intersection to provide two outbound lanes.

Intersection MMLOS

- The results of the intersection MMLOS analysis can be summarized as follows:
 - No study area intersections meet the target PLOS;
 - No study area intersections meet the target BLOS;
 - No study area intersections meet the target TLOS, except for the Baseline Road/Cedarview Road intersection and Baseline Road/Sandcastle Drive intersection;
 - All the study area intersections meet the target TkLOS except for the Richmond Road/John Sutherland Drive, and Baseline Road/John Sutherland Drive/Valley Stream Drive.
- At all the study area intersections, there is limited opportunity to improve the PLOS without reducing the number of travel lanes crossed and restricting turning movements.
- At Richmond Road/Holly Acres Road/Nanaimo Drive, Richmond Road/John Sutherland Drive, Baseline Road/John Sutherland Drive/Valley Stream Drive intersections, the target BLOS can be achieved by implementation of two-stage left turn facilities.
- At Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp intersection, there is limited opportunity to improve BLOS without implementing a fully protected intersection.
- At Baseline Road/Cedarview Road intersection, as the bike lane remains to the left of the right turn lane from Robertson Road to Cedarview Road and there is limited opportunity to transition the bike lane to a cycle track on the intersection approach due to high traffic volumes, and the bridge over Highway 416. As such, no recommendations have been identified to improve the BLOS.
- To improve TLOS at Richmond Road/Holly Acres Road/Nanaimo Drive, consideration should be given by the city to implement an eastbound left turn queue jump lane as part of the Robertson Road and Richmond Road Transit Priority Project.
- To improve TLOS at Richmond Road/John Sutherland Drive, consideration has been given to widen the John Sutherland Drive approach to provide two outbound lanes.
- To improve TLOS at Richmond Road/Robertson Road/Baseline Road/HWY416 ON-Ramp, consideration should be given by the city to implement a westbound left turn queue jump lane as part of the Robertson Road and Richmond Road Transit Priority Project.

Total Traffic Operations

- All study area intersections except for the Richmond Road/John Sutherland intersection operate within acceptable LOS during the AM and PM peaks.

- At Richmond Road/Holly Acres Road/Nanaimo Drive intersection, during the AM and PM peaks, the 95th percentile queue length of the westbound through/left turn movement exceeds the available storage length of 20m. The 95th percentile queue length of the northbound left turn movement exceeds the available storage length of 25m.
- At Richmond Road/John Sutherland Drive intersection, the 95th percentile queue length for the southbound left turn movement is anticipated to exceed the available storage length of 45m during the AM peak. The westbound approach is anticipated to operate with a LOS F during the PM peak hour.
- The proposed implementation of a permitted and protected southbound left turn phase and widening of the westbound approach to two outbound lanes is anticipated to yield a LOS A during the AM peak hour and a LOS C during the PM peak hour. The 95th percentile southbound left turn queues are anticipated to reduce during the AM peak hour and will be accommodated within the existing storage length.
- At Baseline Road/Cedarview Road, the 95th percentile queue length for the northbound left turn movement exceeds the available storage of 25m potentially blocking the adjacent northbound right turn lane during the AM and PM peak hours.
- At Baseline Road/John Sutherland Drive/Valley Stream Drive intersection, the 95th percentile queue length for the eastbound left movement is anticipated to exceed the available storage length of approximately 35m during the AM peak hour. The LOS is anticipated to decrease to LOS B from LOS A.

The proposed development is recommended from transportation perspective.

NOVATECH

Prepared by:



Mohammed Talha, M. Eng.
Engineering Intern | Transportation

Reviewed by:



Brad Byvelds, P. Eng.
Senior Project Manager | Transportation

Appendix A: Existing Site Plan & Part 4 Phasing Plans

Drawing No.

A030

Drawing No.

A030



GROSS FLOOR AREA

	EXISTING	PHASE 2	PHASE 3	PHASE 4	PHASE 5	TOTAL
LEVEL 1	13,323.6	1584.4	-	-	2127.9	17,035.9
LEVEL 2	15,363.9	-	-	6164.1	-	24,280.6
LEVEL 3	9001.0	-	-	-	2713.8	11,714.8
LEVEL 4	4996.1	-	-	-	-	4996.1
LEVEL 5	-	-	2149.9	-	2728.2	4878.2
LEVEL 6	-	-	2149.9	-	2728.2	4878.2
LEVEL 7	-	-	2149.9	-	2728.2	4878.2
TOTAL	42,684.5	1584.4	6449.8	6164.1	15,779.0	72,661.9 m ²

SITE LEGEND

- PROPERTY LINE
- SETBACK LINE
- ARMOUR STONE RETAINING WALL
- FIRE ROUTE
- MATERIALS ACCESS ROUTE
- CHAIN-LINK FENCE
- CONTRACTOR'S STAGING AREA

- EXISTING BUILDING
- NEW BUILDING ADDITION
- INTERIOR RENOVATION
- P PUBLIC ENTRANCE
- E EXIT
- S STAFF ENTRANCE
- F-S FIREFIGHTER/ STAFF ENTRANCE
- CONCRETE CURB
- PAINTED PARKING LINES
- PAVING
- NEW SIDEWALK/PEDESTRIAN PATHS
- GRAVEL
- CAST IRON TACTILE WALKING SURFACE INDICATOR
- PEDESTRIAN TRAIL/BIKE PATH
- EXISTING TREES
- NEW TREES
- BENCH
- EXISTING FIRE HYDRANT
- NEW FIRE HYDRANT
- BIKE RACK

PARKING LEGEND

- 3400mm x 5200mm TYPE A ACCESSIBLE PARKING SPACE C/W 1.5m WIDE AISLE
- 2400mm x 5200mm TYPE B ACCESSIBLE PARKING SPACE C/W 1.5m WIDE AISLE
- 2600mm x 5200mm STANDARD PARKING SPACE
- 1800mm x 600mm STANDARD BICYCLE PARKING

PARKING SUMMARY

VEHICULAR PARKING COUNT			
PHASE	STANDARD	ACCESSIBLE	
EXISTING CONDITIONS	1248	43	
PHASE 0a & 0b	+590	+15	
PHASE 2 EXPANSION	-182	-2	
PHASE 3 EXPANSION	+48	0	
PHASE 4 EXPANSION	+12	+2	
PHASE 5 EXPANSION	-17	0	
TOTAL:	1695	58	

BICYCLE PARKING COUNT		
PHASE	COUNT	
EXISTING	14	
PHASE 0a & 0b	78	
PHASE 2 EXPANSION	9	
PHASE 3 EXPANSION	-8	
PHASE 4 EXPANSION	12	
PHASE 5 EXPANSION	0	
TOTAL:	105	

ACCESSIBLE PARKING COUNT

PHASES	TYPE A	TYPE B
EXISTING	30	8
PHASE 0a & 0b	20	18
PHASE 2	2	2
PHASE 3	-	-
PHASE 4	1 (TEMP.)	-
PHASE 5	1	1
TOTAL:	53	29

LOT COVERAGE

PHASE	FOOTPRINT (m ²)		LOT COVERAGE
EXISTING	26,247.8 m ²		13.0 %
	Proposed	Total	
PHASE 1	+2736.3 m ²	28,984.1 m ²	14.4%
PHASE 2	+2361.3 m ²	31,345.4 m ²	15.5 %
PHASE 3	-	31,345.4 m ²	15.5 %
PHASE 4	+6155.7 m ²	37,501.1 m ²	18.6 %
PHASE 5	+1106.6 m ²	38,607.7 m ²	19.1 %

NOTES:

- SURVEY INFORMATION TAKEN FROM SURVEYS AND TOPOGRAPHICAL PLAN DRAWING NO. 161611160-111-QCH Rev12-TOPG 30x36-1 110624 PREPARED BY STANTEC GEOMATICS LTD. DATED NOVEMBER 5, 2014
- REFER TO CIVIL DRAWINGS FOR FINISHED GRADING, SITE SERVICES, CURBS, CONCRETE AND EXTENT OF ASPHALT PAVING
- REFER TO LANDSCAPE DRAWINGS FOR LANDSCAPE AND SIDEWALK LAYOUT AND DETAILS
- REFER TO ELECTRICAL DRAWINGS FOR SITE LIGHTING AND POWER DISTRIBUTION
- ALL DIMENSIONS ARE IN MILLIMETRES

SITE AREA:

CALCULATED PARCEL AREA : 318391.65 m² (3427135.89 ft²) (31.84 ha)

OWNER
Queensway Carleton Hospital
3045 BASELINE ROAD, OTTAWA, ON, K2H 8P4 613-721-2000

ARCHITECTS
PARKIN
PARKIN ARCHITECTS LIMITED
200 LAURIER ST. W, SUITE 300 OTTAWA, CANADA, K1P 6M7 613-799-7700


CIVIL ENG.
NOVATECH
NOVATECH ENGINEERING CONSULTANTS
240 MICHAEL COMPLAND DR., OTTAWA, ON, K2M 1P6 613-254-9643

SURVEYOR
STANTEC
STANTEC GEOMATICS LTD.
1331 CLYDE AVENUE, OTTAWA, ON, K2C 3G4 613-722-4420

LANDSCAPE ARCHITECTS
CSW
CORIUS SUNDERLAND WRIGHT
319 MCRAE AVENUE, OTTAWA, ON, K1Z 0B9 613-729-4536

MECH./ELEC. ENG.
VR ENGINEERING
VANDERWESTEN & RUTHERFORD ASSOCIATES INC.
1130 MORRISON DRIVE, OTTAWA, ON, K2H 9N6 613-969-2100

Key Plan



2	Stage 2.1 Submission Block Schematic	2025-03-28
NO.	ISSUED	DATE

Issues

All measurements are to be checked and verified on site by the contractor before proceeding with work

Do not scale drawings

PROJECT NO:	9915-96
DRAWN BY:	Author
CHECKED BY:	Checker
SCALE:	

DATE:	2025-05-29
PREVIOUS REVISION:	No
CURRENT REVISION:	2

PROJECT NAME:

QUEENSWAY CARLETON HOSPITAL PART 4 EXPANSION


PROJECT ADDRESS:
3045 BASELINE ROAD, OTTAWA, ON, K2H 8P4 613-721-2000
PROPERTY IDENTIFICATION NO. 04698-0083 (L1)

Sheet Title:

**Site Plan - Phase 2
Support Services
2b-2d - Generator room,
M.M., EVS & F.S.**





















Drawing No.





A032b



	EXISTING	PHASE 2	PHASE 3	PHASE 4	PHASE 5	TOTAL
LEVEL 1	13,323.6	1584.4	-	-	2127.9	17,035.9
LEVEL 2	15,363.9	-	-	6164.1	2752.6	24,280.6
LEVEL 3	9,001.0	-	-	-	2713.8	11,714.8
LEVEL 4	4,996.1	-	-	-	-	4,996.1
LEVEL 5	-	-	2149.9 ¹⁴	-	2728.2	4878.2
LEVEL 6	-	-	2149.9	-	2728.2	4878.2
LEVEL 7	-	-	2149.9	-	2728.2	4878.2
TOTAL	42,684.5	1584.4	6449.8	6164.1	15,779.0	72,661.9 m²

- ## SITE LEGEND
- | | |
|--|-----------------------------|
| | PROPERTY LINE |
| | SETBACK LINE |
| | ARMOUR STONE RETAINING WALL |
| | FIRE ROUTE |
| | MATERIALS ACCESS ROUTE |
| | CHAIN-LINK FENCE |
| | CONTRACTOR'S STAGING AREA |

- | | |
|---|---|
|  | EXISTING BUILDING |
|  | NEW BUILDING ADDITION |
|  | INTERIOR RENOVATION |
|  | P PUBLIC ENTRANCE |
|  | E EXIT |
|  | S STAFF ENTRANCE |
|  | F-S FIREFIGHTER/ STAFF ENTRANCE |
|  | CONCRETE CURB |
|  | PAINTED PARKING LINES |
|  | PAVING |
|  | NEW SIDEWALK/PEDESTRIAN PATHS |
|  | GRAVEL |
|  | CAST IRON TACTILE WALKING SURFACE INDICATOR |
|  | PEDESTRIAN TRAIL/BIKE PATH |
|  | EXISTING TREES |
|  | NEW TREES |
|  | BENCH |
|  | EXISTING FIRE HYDRANT |
|  | NEW FIRE HYDRANT |
|  | BIKE RACK |

- ## PARKING LEGEND
- | | |
|---|--|
|  | <p>3400mm x 5200mm TYPE A
ACCESSIBLE PARKING SPACE C/W 1.5m
WIDE AISLE</p> |
|  | <p>2400mm x 5200mm TYPE B
ACCESSIBLE PARKING SPACE C/W 1.5m
WIDE AISLE</p> |
|  | <p>2600mm x 5200mm STANDARD
PARKING SPACE</p> |
|  | <p>1800mm x 6000mm STANDARD BICYCLE
PARKING</p> |

VEHICULAR PARKING COUNT		
PHASE	STANDARD	ACCESSIBLE
EXISTING CONDITIONS	1248	43
PHASE 0a & 0b	+590	+15
PHASE 2 EXPANSION	+182	-2
PHASE 3 EXPANSION	+48	0
PHASE 4 EXPANSION	+12	+2
PHASE 5 EXPANSION	-17	0
TOTAL:	1695	58

BICYCLE PARKING COUNT	
PHASE	COUNT
EXISTING	14
PHASE 0a & 0b	78
PHASE 2 EXPANSION	9
PHASE 3 EXPANSION	-8
PHASE 4 EXPANSION	12
PHASE 5 EXPANSION	0
TOTAL:	105








ACCESSIBLE PARKING COUNT





















PHASES	TYPE A	TYPE B
EXISTING	30	8
PHASE 0a & 0b	20	18
PHASE 2	2	2
PHASE 3	-	-
PHASE 4	1 (TEMP.)	-
PHASE 5	1	1
TOTAL:	53	29

LOT COVERAGE				
PHASE		FOOTPRINT (m ²)		LOT COVERAGE
EXISTING		26,247.8 m ²		13.0 %
		Proposed	Total	
PHASE 1		+2736.3 m ²	28,984.1 m ²	14.4%
PHASE 2		+2361.3 m ²	31,345.4 m ²	15.5 %
PHASE 3		-	31,345.4 m ²	15.5 %
PHASE 4		+6155.7 m ²	37,501.1 m ²	18.6 %
PHASE 5		+1106.6 m ²	38,607.7 m ²	19.1 %

- NOTES:**
1. SURVEY INFORMATION TAKEN FROM SURVEYS AND TOPOGRAPHICAL PLAN DRAWING NO. 1516111665-111-QCR-Rev12-TOPO 3036-1 1110624 PREPARED BY STANTEC GEOMATICS INC., DATED NOVEMBER 5, 2014
 2. REFER TO CIVIL DRAWINGS FOR FINISHED GRADING, SITE SERVICES, CURBS, AND CEMENTS AND EXTENT OF ASPHALT PAVING.
 3. REFER TO LANDSCAPE DRAWINGS FOR LANDSCAPE AND SIDEWALK LAYOUTS AND DETAILS.
 4. REFER TO ELECTRICAL DRAWINGS FOR SITE LIGHTING AND POWER DISTRIBUTION.
 5. ALL DIMENSIONS ARE IN MILLIMETRES
- SITE AREA:**
- CALCULATED PARCEL AREA: 313591.65 m² (3427135.89 ft²) (31.84 ha)**

SITE LEGEND

	PROPERTY LINE
	SETBACK LINE
	ARMOUR STONE RETAINING WALL
	FIRE ROUTE
	MATERIALS ACCESS ROUTE
	CHAIN-LINK FENCE
	CONTRACTOR'S STAGING AREA

- | | |
|---|---|
|  | EXISTING BUILDING |
|  | NEW BUILDING ADDITION |
|  | INTERIOR RENOVATION |
|  | P PUBLIC ENTRANCE |
|  | E EXIT |
|  | S STAFF ENTRANCE |
|  | F-S FIREFIGHTER/ STAFF ENTRANCE |
|  | CONCRETE CURB |
|  | PAINTED PARKING LINES |
|  | PAVING |
|  | NEW SIDEWALK/PEDESTRIAN PATHS |
|  | GRAVEL |
|  | CAST IRON TACTILE WALKING SURFACE INDICATOR |
|  | PEDESTRIAN TRAIL/BIKE PATH |
|  | EXISTING TREES |
|  | NEW TREES |
|  | BENCH |
|  | EXISTING FIRE HYDRANT |
|  | NEW FIRE HYDRANT |
|  | BIKE RACK |

1500 3400
1500 5200
1500 3400
1500 5200
1500 2600
1500 5200
1500 1800
1500 6000

3400mm x 5200mm TYPE A
ACCESSIBLE PARKING SPACE C/W 1.5m
WIDE AISLE

2400mm x 5200mm TYPE B
ACCESSIBLE PARKING SPACE C/W 1.5m
WIDE AISLE

2600mm x 5200mm STANDARD
PARKING SPACE

1800mm x 6000mm STANDARD BICYCLE
PARKING

VEHICULAR PARKING COUNT		
PHASE	STANDARD	ACCESSIBLE
EXISTING CONDITIONS	1248	43
PHASE 0a & 0b	+590	+15
PHASE 2 EXPANSION	-182	-2
PHASE 3 EXPANSION	+48	0
PHASE 4 EXPANSION	+12	+2
PHASE 5 EXPANSION	-17	0
TOTAL:	1695	58

BICYCLE PARKING COUNT	
PHASE	COUNT
EXISTING	14
PHASE 0a & 0b	78
PHASE 2 EXPANSION	9
PHASE 3 EXPANSION	-8
PHASE 4 EXPANSION	-12
PHASE 5 EXPANSION	105
TOTAL:	105

PHASES	TYPE A	TYPE B
EXISTING	30	8
PHASE 0a & 0b	20	18
PHASE 2	2	2
PHASE 3	-	-
PHASE 4	1 (TEMP.)	-
PHASE 5	1	1
TOTAL:	53	29

PHASE	FOOTPRINT (m ²)		LOT COVERAGE
EXISTING	26,247.8 m ²		13.0 %
	Proposed	Total	
PHASE 1	+2736.3 m ²	28,984.1 m ²	14.4%
PHASE 2	+2361.3 m ²	31,345.4 m ²	15.5 %
PHASE 3	-	31,345.4 m ²	15.5 %
PHASE 4	+6155.7 m ²	37,501.1 m ²	18.6 %
PHASE 5	+1106.6 m ²	38,607.7 m ²	19.1 %

1. SURVEY INFORMATION TAKEN FROM SURVEYS AND TOPOGRAPHICAL PLAN DRAWING NO. 15161-150-111-GQA-Rw12-TOP-353616 11110624 PREPARED BY STATTEC GEOMATICS LTD. DATED NOVEMBER 5, 2024
2. REFER TO CIVIL DRAWINGS FOR FINISHED GRADE, SITE SERVICES, CURBS, CONCRETE AND EXTENT OF ASPHALT PAVING.
3. REFER TO LANDSCAPE DRAWINGS FOR LANDSCAPE AND SIDEWALK LAYOUT AND DETAILS
4. REFER TO ELECTRICAL DRAWINGS FOR SITE LIGHTING AND POWER DISTRIBUTION.
5. ALL DIMENSIONS ARE IN MILLIMETRES

SITE AREA:
CALCULATED PARCEL AREA : 318391.65 m² (3427135.89 ft²) (31.84 ha)

TRUE NORTH

PROJECT NORTH

PROJECT NO:	9915-96
DRAWN BY:	Author
CHECKED BY:	Checker
SCALE:	

DATE:	2025-10-01
PREVIOUS REVISION:	No
CURRENT REVISION:	2

QUEENSWAY CARLETON
HOSPITAL PART 4
EXPANSION


PROJECT ADDRESS:
3045 BASELINE ROAD, OTTAWA, ON, K2H 8P4 613-721-2000
PROPERTY IDENTIFICATION NO. 04698-0083 (LT)

Sheet Title:

**Site Plan - Phase 4
Emergency Dept.
Expansion - 4a
Ambulatory Care &
Temporary Entrance**

Drawing No.

Temporary Entrance
Drawing No. **A034a**



GROSS FLOOR AREA

	EXISTING	PHASE 2	PHASE 3	PHASE 4	PHASE 5	TOTAL
LEVEL 1	13,323.6	1584.4	-	-	2127.9	17,035.9
LEVEL 2	15,363.9	-	-	6164.1	2752.6	24280.6
LEVEL 3	9001.0	-	-	-	2713.8	11,714.8
LEVEL 4	4996.1	-	-	-	-	4996.1
LEVEL 5	-	-	2149.9	-	2728.2	4878.2
LEVEL 6	-	-	2149.9	-	2728.2	4878.2
LEVEL 7	-	-	-	-	2728.2	4878.2
TOTAL	42,684.5	1584.4	6449.8	6164.1	15,779.0	72,661.9 m ²

SITE LEGEND

- PROPERTY LINE
- SETBACK LINE
- ARMOUR STONE RETAINING WALL
- FIRE ROUTE
- MATERIALS ACCESS ROUTE
- CHAIN-LINK FENCE
- CONTRACTOR'S STAGING AREA

- EXISTING BUILDING
- NEW BUILDING ADDITION
- INTERIOR RENOVATION
- P PUBLIC ENTRANCE
- E EXIT
- S STAFF ENTRANCE
- F-S FIREFIGHTER/ STAFF ENTRANCE
- CONCRETE CURB
- PAINTED PARKING LINES
- PAVING
- NEW SIDEWALK/PEDESTRIAN PATHS
- GRAVEL
- CAST IRON TACTILE WALKING SURFACE INDICATOR
- PEDESTRIAN TRAIL/BIKE PATH
- EXISTING TREES
- NEW TREES
- BENCH
- EXISTING FIRE HYDRANT
- NEW FIRE HYDRANT
- BIKE RACK

PARKING LEGEND

- 3400mm x 5200mm TYPE A ACCESSIBLE PARKING SPACE C/W 1.5m WIDE AISLE
- 2400mm x 5200mm TYPE B ACCESSIBLE PARKING SPACE C/W 1.5m WIDE AISLE
- 2600mm x 5200mm STANDARD PARKING SPACE
- 1800mm x 600mm STANDARD BICYCLE PARKING

PARKING SUMMARY

VEHICULAR PARKING COUNT			
PHASE	STANDARD	ACCESSIBLE	
EXISTING CONDITIONS	1248	43	
PHASE 0a & 0b	+590	+15	
PHASE 2 EXPANSION	-182	-2	
PHASE 3 EXPANSION	+48	0	
PHASE 4 EXPANSION	+12	+2	
PHASE 5 EXPANSION	-17	0	
TOTAL:	1695	58	

BICYCLE PARKING COUNT		
PHASE	COUNT	
EXISTING	14	
PHASE 0a & 0b	78	
PHASE 2 EXPANSION	9	
PHASE 3 EXPANSION	-8	
PHASE 4 EXPANSION	12	
PHASE 5 EXPANSION	0	
TOTAL:	105	

ACCESSIBLE PARKING COUNT

PHASES	TYPE A	TYPE B
EXISTING	30	8
PHASE 0a & 0b	20	18
PHASE 2	2	2
PHASE 3	-	-
PHASE 4	1 (TEMP.)	-
PHASE 5	1	1
TOTAL:	53	29

LOT COVERAGE

PHASE	FOOTPRINT (m ²)		LOT COVERAGE
EXISTING	26,247.8 m ²		13.0 %
	Proposed	Total	
PHASE 1	+2736.3 m ²	28,984.1 m ²	14.4%
PHASE 2	+2361.3 m ²	31,345.4 m ²	15.5 %
PHASE 3	-	31,345.4 m ²	15.5 %
PHASE 4	+6155.7 m ²	37,501.1 m ²	18.6 %
PHASE 5	+1106.6 m ²	38,607.7 m ²	19.1 %

NOTES:

- SURVEY INFORMATION TAKEN FROM SURVEYS AND TOPOGRAPHICAL PLAN DRAWING NO. 161611560-111-QCH Rev12-TOP0 30X36-1 110624 PREPARED BY STANTEC GEOMATICS LTD. DATED NOVEMBER 5, 2024
- REFER TO CIVIL DRAWINGS FOR FINISHED GRADING, SITE SERVICES, CURBS, CONCRETE AND EXISTING OR ASPHALT PAVING
- REFER TO LANDSCAPE DRAWINGS FOR LANDSCAPE AND SIDEWALK LAYOUT AND DETAILS
- REFER TO ELECTRICAL DRAWINGS FOR SITE LIGHTING AND POWER DISTRIBUTION
- ALL DIMENSIONS ARE IN MILLIMETRES

SITE AREA:

CALCULATED PARCEL AREA : 318391.65 m² (3427135.89 ft²) (31.84 ha)

OWNER



3045 BASELINE ROAD, OTTAWA, ON, K2H 8P4 613-721-2000

ARCHITECTS

PARKIN
PARKIN ARCHITECTS LIMITED
200 LAURIER ST W, SUITE 300 OTTAWA, CANADA, K1P 0M7 613-799-7700

CIVIL ENG.

NOVATECH
NOVATECH ENGINEERING CONSULTANTS
240 MICHAEL COMPLAND DR., OTTAWA, ON, K2M 1P6 613-254-9643

SURVEYOR

STANTEC
STANTEC GEOMATICS LTD.
1331 CLYDE AVENUE, OTTAWA, ON, K2C 3G4 613-722-4420

LANDSCAPE ARCHITECTS

CSW
CORIUS SUNDERLAND WRIGHT
319 MCRAE AVENUE, OTTAWA, ON, K1Z 0B9 613-729-4536

MECH./ELEC. ENG.

VR ENGINEERING
VANDERWESTEN & RUTHERFORD ASSOCIATES INC.
1130 MORRISON DRIVE, OTTAWA, ON, K2H 9N6 613-563-2100

Key Plan



NO.	DESCRIPTION	DATE
1	Issued for Costing	2025-02-28
2	Stage 2.1 Submission Block Schematic	2025-03-28
3	Functional program submission	2024-09-30
4	ISSUED	2024-09-30

Issues

All measurements are to be checked and verified on site by the contractor before proceeding with work

Do not scale drawings

PROJECT NO:	9915-96
DRAWN BY:	DJ
CHECKED BY:	
SCALE:	

DATE:	2024-07-16
PREVIOUS REVISION:	No
CURRENT REVISION:	2

PROJECT NAME:

QUEENSWAY CARLETON HOSPITAL PART 4 EXPANSION

PROJECT ADDRESS:
3045 BASELINE ROAD, OTTAWA, ON, K2H 8P4 613-721-2000
PROPERTY IDENTIFICATION NO. 04698-0083 (LT)

Sheet Title:

**Site Plan - Phase 4
Emergency Dept.
Expansion - 4b & 4c
Emergency Services**

Drawing No.

A034b

RICHMOND ROAD

PART 4 PLAN 4R - 1238

GROSS FLOOR AREA

	EXISTING	PHASE 2	PHASE 3	PHASE 4	PHASE 5	TOTAL
LEVEL 1	13,323.6	1584.4	-	6164.1	2127.9	17,035.9
LEVEL 2	15,363.9	-	-	2752.6	24280.6	24,280.6
LEVEL 3	9001.0	-	-	-	2713.8	11,714.8
LEVEL 4	4996.1	-	-	-	4996.1	4996.1
LEVEL 5	-	-	2149.9	-	2728.2	4878.2
LEVEL 6	-	-	2149.9	-	2728.2	4878.2
LEVEL 7	-	-	2149.9	-	2728.2	4878.2
TOTAL	42,684.5	1584.4	6449.8	6164.1	15,779.0	72,661.9 m ²

SITE LEGEND

- PROPERTY LINE
- SETBACK LINE
- ARMOUR STONE RETAINING WALL
- FIRE ROUTE
- MATERIALS ACCESS ROUTE
- CHAIN-LINK FENCE
- CONTRACTOR'S STAGING AREA
- EXISTING BUILDING
- NEW BUILDING ADDITION
- INTERIOR RENOVATION
- P PUBLIC ENTRANCE
- E EXIT
- S STAFF ENTRANCE
- F-S FIREFIGHTER/ STAFF ENTRANCE
- CONCRETE CURB
- PAINTED PARKING LINES
- PAVING
- NEW SIDEWALK/PEDESTRIAN PATHS
- GRAVEL
- CAST IRON TACTILE WALKING SURFACE INDICATOR
- PEDESTRIAN TRAIL/BIKE PATH
- EXISTING TREES
- NEW TREES
- BENCH
- EXISTING FIRE HYDRANT
- NEW FIRE HYDRANT
- BIKE RACK

PARKING LEGEND

- 3400mm x 5200mm TYPE A ACCESSIBLE PARKING SPACE C/W 1.5m WIDE AISLE
- 2400mm x 5200mm TYPE B ACCESSIBLE PARKING SPACE C/W 1.5m WIDE AISLE
- 2600mm x 5200mm STANDARD PARKING SPACE
- 1800mm x 600mm STANDARD BICYCLE PARKING

PARKING SUMMARY

VEHICULAR PARKING COUNT			
PHASE	STANDARD	ACCESSIBLE	
EXISTING CONDITIONS	1248	43	
PHASE 0a & 0b	+590	+15	
PHASE 2 EXPANSION	-182	-2	
PHASE 3 EXPANSION	+48	0	
PHASE 4 EXPANSION	+12	+2	
PHASE 5 EXPANSION	-17	0	
TOTAL:	1695	58	
BICYCLE PARKING COUNT			
PHASE	COUNT		
EXISTING	14		
PHASE 0a & 0b	78		
PHASE 2 EXPANSION	9		
PHASE 3 EXPANSION	-8		
PHASE 4 EXPANSION	12		
PHASE 5 EXPANSION	0		
TOTAL:	105		

ACCESSIBLE PARKING COUNT

PHASES	TYPE A	TYPE B
EXISTING	30	8
PHASE 0a & 0b	20	18
PHASE 2	2	2
PHASE 3	-	-
PHASE 4	1 (TEMP.)	-
PHASE 5	1	1
TOTAL:	53	29

LOT COVERAGE

PHASE	FOOTPRINT (m ²)		LOT COVERAGE
EXISTING	26,247.8 m ²		13.0 %
	Proposed	Total	
PHASE 1	+2736.3 m ²	28,984.1 m ²	14.4%
PHASE 2	+2361.3 m ²	31,345.4 m ²	15.5 %
PHASE 3	-	31,345.4 m ²	15.5 %
PHASE 4	+6155.7 m ²	37,501.1 m ²	18.6 %
PHASE 5	+1106.6 m ²	38,607.7 m ²	19.1 %

NOTES:

- SURVEY INFORMATION TAKEN FROM SURVEYS AND TOPOGRAPHICAL PLAN DRAWING NO. 161611560-111-QCH Rev12-TOPG 30x36-1 110624 PREPARED BY STANTEC GEOMATICS LTD. DATED NOVEMBER 5, 2024
- REFER TO CIVIL DRAWINGS FOR FINISHED GRADING, SITE SERVICES, CURBS, CONCRETE AND EXISTING ASPHALT PAVING
- REFER TO LANDSCAPE DRAWINGS FOR LANDSCAPE AND SIDEWALK LAYOUT AND DETAILS
- REFER TO ELECTRICAL DRAWINGS FOR SITE LIGHTING AND POWER DISTRIBUTION
- ALL DIMENSIONS ARE IN MILLIMETRES

SITE AREA:

CALCULATED PARCEL AREA : 318391.65 m² (3427135.89 ft²) (31.84 ha)

OWNER
Queensway Carleton Hospital
3045 BASELINE ROAD, OTTAWA, ON, K2H 8P4 613-721-2000

ARCHITECTS
PARKIN
PARKIN ARCHITECTS LIMITED
200 LAURIER ST. W. SUITE 300 OTTAWA, CANADA, K1P 0M7 613-799-7700

CIVIL ENG.
NOVATECH
NOVATECH ENGINEERING CONSULTANTS
240 MICHAEL COMPLAND DR., OTTAWA, ON, K2M 1P6 613-254-9643

SURVEYOR
STANTEC
STANTEC GEOMATICS LTD.
1331 CLYDE AVENUE, OTTAWA, ON, K2C 3G4 613-722-4420

LANDSCAPE ARCHITECTS
CSW
CORIUS SUNDERSLAND WRIGHT
319 MCRAE AVENUE, OTTAWA, ON, K2C 0B9 613-729-4536

MECH./ELEC. ENG.
VR ENGINEERING
VANDERWESTEN & RUTHERFORD ASSOCIATES INC.
1130 MORRISON DRIVE, OTTAWA, ON, K2H 9N6 613-563-2100



NO.	ISSUES	DATE
2	Stage 2.1 Submission Block Schematic	2025-03-28
	ISSUED	

All measurements are to be checked and verified on site by the contractor before proceeding with work

Do not scale drawings

PROJECT NO:	9915-96
DRAWN BY:	Author
CHECKED BY:	Checker
SCALE:	

DATE:	2025-05-29
PREVIOUS REVISION:	No
CURRENT REVISION:	2

PROJECT NAME:

QUEENSWAY CARLETON HOSPITAL PART 4 EXPANSION

PROJECT ADDRESS:
3045 BASELINE ROAD, OTTAWA, ON, K2H 8P4 613-721-2000
PROPERTY IDENTIFICATION NO. 04698-0083 (L7)

Sheet Title:

Site Plan - Phase 5 ICU and Transitional Care Inpatient Tower



GROSS FLOOR AREA

	EXISTING	PHASE 2	PHASE 3	PHASE 4	PHASE 5	TOTAL
LEVEL 1	13,323.6	1584.4	-	-	2127.9	17,035.9
LEVEL 2	15,363.9	-	-	6164.1	2752.6	24,280.6
LEVEL 3	9001.0	-	-	-	2713.8	11,714.8
LEVEL 4	4996.1	-	-	-	-	4996.1
LEVEL 5	-	-	2149.9	-	2728.2	4878.2
LEVEL 6	-	-	2149.9	-	2728.2	4878.2
LEVEL 7	-	-	2149.9	-	2728.2	4878.2
TOTAL	42,684.5	1584.4	6449.8	6164.1	15,779.0	72,661.9 m ²

SITE LEGEND

- PROPERTY LINE
- SETBACK LINE
- ARMOUR STONE RETAINING WALL
- FIRE ROUTE
- MATERIALS ACCESS ROUTE
- CHAIN-LINK FENCE
- CONTRACTOR'S STAGING AREA
- EXISTING BUILDING
- NEW BUILDING ADDITION
- INTERIOR RENOVATION
- PUBLIC ENTRANCE
- EXIT
- STAFF ENTRANCE
- F-S FIREFIGHTER/ STAFF ENTRANCE
- CONCRETE CURB
- PAINTED PARKING LINES
- PAVING
- NEW SIDEWALK/PEDESTRIAN PATHS
- GRAVEL
- CAST IRON TACTILE WALKING SURFACE INDICATOR
- PEDESTRIAN TRAIL/BIKE PATH
- EXISTING TREES
- NEW TREES
- BENCH
- EXISTING FIRE HYDRANT
- NEW FIRE HYDRANT
- BIKE RACK

PARKING LEGEND

- 3400mm x 5200mm TYPE A ACCESSIBLE PARKING SPACE C/W 1.5m WIDE AISLE
- 2400mm x 5200mm TYPE B ACCESSIBLE PARKING SPACE C/W 1.5m WIDE AISLE
- 2600mm x 5200mm STANDARD PARKING SPACE
- 1800mm x 600mm STANDARD BICYCLE PARKING

PARKING SUMMARY

VEHICULAR PARKING COUNT			
PHASE	STANDARD	ACCESSIBLE	
EXISTING CONDITIONS	1248	43	
PHASE 0a & 0b	+590	+15	
PHASE 2 EXPANSION	-182	-2	
PHASE 3 EXPANSION	+48	0	
PHASE 4 EXPANSION	+12	+2	
PHASE 5 EXPANSION	-17	0	
TOTAL:	1695	58	
BICYCLE PARKING COUNT			
PHASE	COUNT		
EXISTING	14		
PHASE 0a & 0b	78		
PHASE 2 EXPANSION	9		
PHASE 3 EXPANSION	-8		
PHASE 4 EXPANSION	12		
PHASE 5 EXPANSION	0		
TOTAL:	105		

ACCESSIBLE PARKING COUNT

PHASES	TYPE A	TYPE B
EXISTING	30	8
PHASE 0a & 0b	20	18
PHASE 2	2	2
PHASE 3	-	-
PHASE 4	1 (TEMP.)	-
PHASE 5	1	1
TOTAL:	53	29

LOT COVERAGE

PHASE	FOOTPRINT (m ²)		LOT COVERAGE
EXISTING	26,247.8 m ²		13.0 %
	Proposed	Total	
PHASE 1	+2736.3 m ²	28,984.1 m ²	14.4 %
PHASE 2	+2361.3 m ²	31,345.4 m ²	15.5 %
PHASE 3	-	31,345.4 m ²	15.5 %
PHASE 4	+6155.7 m ²	37,501.1 m ²	18.6 %
PHASE 5	+1106.6 m ²	38,607.7 m ²	19.1 %

NOTES:

- SURVEY INFORMATION TAKEN FROM SURVEYS AND TOPOGRAPHICAL PLAN DRAWING NO. 161611560-111-QCH Rev12-TOP0 30x36-1 110624 PREPARED BY STANTEC GEOMATICS LTD. DATED NOVEMBER 5, 2024
- REFER TO CIVIL DRAWINGS FOR FINISHED GRADING, SITE SERVICES, CURBS, CONCRETE AND EXISTENT OR ASPHALT PAVING
- REFER TO LANDSCAPE DRAWINGS FOR LANDSCAPE AND SIDEWALK LAYOUT AND DETAILS
- REFER TO ELECTRICAL DRAWINGS FOR SITE LIGHTING AND POWER DISTRIBUTION
- ALL DIMENSIONS ARE IN MILLIMETRES

SITE AREA:

CALCULATED PARCEL AREA : 318391.65 m² (3427135.89 ft²) (31.84 ha)

OWNER



3045 BASELINE ROAD, OTTAWA, ON, K2H 8P4 613-721-2000

ARCHITECTS

PARKIN
PARKIN ARCHITECTS LIMITED
200 LAURIER ST W, SUITE 300 OTTAWA, CANADA, K1P 0M7 613-799-7700

CIVIL ENG.

NOVATECH
NOVATECH ENGINEERING CONSULTANTS
240 MICHAEL COMPLAN DR., OTTAWA, ON, K2M 1P6 613-254-9643

SURVEYOR

STANTEC
STANTEC GEOMATICS LTD.
1331 CLYDE AVENUE, OTTAWA, ON, K2C 3G4 613-722-4420

LANDSCAPE ARCHITECTS

CSW
CORIUS SUNDERLAND WRIGHT
319 MCRAE AVENUE, OTTAWA, ON, K1Z 0B9 613-729-4536

MECH./ELEC. ENG.

VR ENGINEERING
VANDERWESTEN & RUTHERFORD ASSOCIATES INC.
1130 MORRISON DRIVE, OTTAWA, ON, K2H 9N6 613-969-2100

Key Plan



2	Stage 2.1 Submission Block Schematic	2025-09-28
NO.	ISSUED	DATE

Issues

All measurements are to be checked and verified on site by the contractor before proceeding with work

Do not scale drawings

PROJECT NO:	9915-96
DRAWN BY:	Author
CHECKED BY:	Checker
SCALE:	

DATE:	2025-07-18
PREVIOUS REVISION:	No
CURRENT REVISION:	2

PROJECT NAME:

**QUEENSWAY CARLETON
HOSPITAL PART 4
EXPANSION**

PROJECT ADDRESS:
3045 BASELINE ROAD, OTTAWA, ON, K2H 8P4 613-721-2000
PROPERTY IDENTIFICATION NO. 04698-0083 (L7)

Sheet Title:

**Site Plan - Part 4
Complete**

Drawing No.

A037

Appendix B: TIA Screening Form

City of Ottawa 2017 TIA Guidelines TIA Screening

1. Description of Proposed Development

Municipal Address	3045 Baseline Road
Description of Location	Northeast corner of Richmond Rd & Baseline Rd
Land Use Classification	Hospital
Development Size (units)	
Development Size square metre (m ²)	35,866
Number of Accesses and Locations	Makes use of existing
Phase of Development	Multiple Sub-phases
Buildout Year	2035

If available, please attach a sketch of the development or site plan to this form.

2. Trip Generation Trigger

Considering the Development's Land Use type and Size (as filled out in the previous section), please refer to the Trip Generation Trigger checks below.

Table notes:

1. Table 2, Table 3 & Table 4 TRANS Trip Generation Manual
2. Institute of Transportation Engineers (ITE) Trip Generation Manual 11.1 Ed.

Land Use Type	Minimum Development Size
Single-family homes	60 units
Multi-Use Family (Low-Rise) ¹	90 units
Multi-Use Family (High-Rise) ¹	150 units
Office ²	1,400 m ²
Industrial ²	7,000 m ²
Fast-food restaurant or coffee shop ²	110 m ²
Destination retail ²	1,800 m ²
Gas station or convenience market ²	90 m ²

If the proposed development size is equal to or greater than the sizes identified above, the Trip Generation Trigger is satisfied.

3. Location Triggers

	Yes	No
Does the development propose a new driveway to a boundary street that is designated as part of the Transit Priority Network, Rapid Transit network or Cross-Town Bikeways?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Is the development in a Hub, a Protected Major Transit Station Area (PMTSA), or a Design Priority Area (DPA)? ²	<input type="checkbox"/>	<input checked="" type="checkbox"/>

If any of the above questions were answered with 'Yes,' the Location Trigger is satisfied.

4. Safety Triggers

	Yes	No
Are posted speed limits on a boundary street are 80 kilometers per hour (km/h) or greater?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Are there any horizontal/vertical curvatures on a boundary street limits sight lines at a proposed driveway?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Is the proposed driveway within the area of influence of an adjacent traffic signal or roundabout (i.e. within 300 metre [m] of intersection in rural conditions, or within 150 m of intersection in urban/ suburban conditions)?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Is the proposed driveway within auxiliary lanes of an intersection?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Does the proposed driveway make use of an existing median break that serves an existing site?	<input type="checkbox"/>	<input checked="" type="checkbox"/>

² Hubs are identified in Schedules B1 to B8 of the City of Ottawa Official Plan. PMTSAs are identified in Schedule C1 of the Official Plan. DPAs are identified in Schedule C7A and C7B of the Official. See Chapter 4 for a list of City of Ottawa Planning and Engineering documents that support the completion of TIA.

Transportation Impact Assessment Guidelines

	Yes	No
Is there is a documented history of traffic operations or safety concerns on the boundary streets within 500 m of the development?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Does the development include a drive-thru facility?	<input type="checkbox"/>	<input checked="" type="checkbox"/>

If any of the above questions were answered with 'Yes,' the Safety Trigger is satisfied.

5. Summary

Results of Screening	Yes	No
Does the development satisfy the Trip Generation Trigger?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Does the development satisfy the Location Trigger?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Does the development satisfy the Safety Trigger?	<input checked="" type="checkbox"/>	<input type="checkbox"/>

If none of the triggers are satisfied, the TIA Study is complete. If one or more of the triggers is satisfied, the TIA Study must continue into the next stage (Screening and Scoping).

Appendix C: OC Transpo Maps



Rapid

BAYSHORE CRYSTAL BAY TUNNEY'S PASTURE

7 days a week / 7 jours par semaine

All day and limited overnight service


Service toute la journée et limité la nuit



**TUNNEY'S
PASTURE**



BAYSHORE



2022.06



Transitway & Station



Timepoint | Heures de passage



When O-Train Line 1 is not running overnight,
Route 57 will be extended downtown to Rideau
Station. / Lorsque la Ligne 1 de l'O-Train ne
circule pas la nuit, le circuit 57 sera prolongée
au centre-ville jusqu'à la station Rideau.

2022.06



Schedule / Horaire613-560-1000

Text / Texto*560560

plus your four digit bus stop number / plus votre numéro d'arrêt à quatre chiffres

*Standard message rates may apply / Les tarifs réguliers de messagerie texte peuvent s'appliquer

Customer Service

Service à la clientèle 613-560-5000

Lost and Found / Objets perdus..... 613-563-4011

Security / Sécurité 613-741-2478

Effective June 26, 2022

En vigueur 26 juin 2022



INFO 613-560-5000
octranspo.com



BASELINE TERRY FOX


Fréquent

7 days a week / 7 jours par semaine

All day service

Service toute la journée

BASELINE



TERRY FOX



Transitway & Station



Some trips / Quelques trajets



Park & Ride / Parc relais



Shopping Centre / Centre commercial

04.2025

2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.

Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.



Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com




HURDMAN BAYSHORE

Fréquent

7 days a week / 7 jours par semaine

All day service

Service toute la journée



2025.04

This route starts on April 27, 2025 when the New Ways to Bus network comes into effect.


Ce circuit sera mis en service le 27 avril 2025, lorsque le réseau L'autobus réinventé entrera en vigueur.


Customer Service /
Service à la clientèle **613-560-5000**

Security / Sécurité **613-741-2478**



octranspo.com





Last modified: Sept. 2021

Appendix D: Traffic Count Data


Survey Date: Thursday, May 01, 2025

WO No: 42876

Start Time: 07:00

Device: Miovision

AM Period Peak Hour Diagram




Survey Date: Thursday, May 01, 2025

WO No: 42876

Start Time: 07:00

Device: Miovision

PM Period Peak Hour Diagram





Richmond Road & John Sutherland Drive

TURNING MOVEMENT COUNT PEAK HOUR SUMMARIES

Date:
Survey Hours:
Surveyor(s):

Wednesday, March 05, 2025
07:00-10:00, 11:30-13:30, 15:00-18:00
Joshua Morris & Bob Cameron



Turning Movement Count - Study Results

BASELINE RD/HWY 416 RICHMOND IC75AR53 @ RICHMOND RD


Survey Date: Tuesday, February 13, 2024

WO No: 42074

Start Time: 07:00

Device: Miovision

AM Period Peak Hour Diagram



Turning Movement Count - Study Results

BASELINE RD/HWY 416 RICHMOND IC75AR53 @ RICHMOND RD


Survey Date: Tuesday, February 13, 2024

WO No: 42074

Start Time: 07:00

Device: Miovision



PM Period Peak Hour Diagram



TURNING MOVEMENT COUNT PEAK HOUR SUMMARIES

Date:
Survey Hours:
Surveyor(s):

Wednesday, March 05, 2025
07:00-10:00, 11:30-13:30, 15:00-18:00
Joshua Morris and Bob Cameron





Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram


BASELINE RD @ CEDARVIEW RD

Survey Date: Tuesday, January 15, 2019

Start Time: 07:00

WO No: 38256

Device: Miovision





Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram


BASELINE RD @ CEDARVIEW RD

Survey Date: Tuesday, January 15, 2019

Start Time: 07:00

WO No: 38256

Device: Miovision





Turning Movement Count Summary, AM and PM Peak Hour Flow Diagrams All Vehicles Except Bicycles



Baseline Road & John Sutherland Drive/Valley Stream Drive (Loc 01)

Nepean, ON

All Vehicles


(Except Bicycles & Electric Scooters)

Wednesday, November 06, 2024

0700-1000, 1130-1330 & 1500-1800


8 Hour Survey

City of Ottawa Ward 8



AM Peak Hour Flow Diagram

PM Peak Hour Flow Diagram





Turning Movement Count Heavy Vehicle Summary (FHWA Class 4-13) Flow Diagram



Baseline Road & John Sutherland Drive/Valley Stream Drive (Loc 01)

Nepean, ON

Heavy Vehicles

(Construction Vehicles, Heavy Trucks, Buses & School Buses).
Heavy vehicle totals ARE included in the all vehicles summary and flow diagrams.

John Sutherland Dr.

Baseline Rd.

Wednesday, November 06, 2024

0700-1000, 1130-1330 & 1500-1800

8 Hour Survey

City of Ottawa Ward 8

Baseline Rd.

189

369

180 (B)

(A) 50 107 57

26 0 24 0

Total Heavy Vehicles

425

Approaching Intersection

(A+B+C+D)

(D) 186

353

Heavy Vehicles Comprise

3.06%

of Total Traffic

167

All Pedestrian Crossings

46

42 65

Total

192

Baseline Rd.

Eastbound

Baseline Rd.

Westbound

Valley Stream Dr.

Northbound

John Sutherland Dr.

Southbound

Time Period	LT	ST	RT	UT	EB Tot	LT	ST	RT	UT	WB Tot	LT	ST	RT	UT	NB Tot	LT	ST	RT	UT	SB Tot	GR Tot
0700-0800	5	37	3	0	45	1	13	3	0	17	0	0	1	0	1	5	0	4	0	9	72
0800-0900	2	24	1	0	27	0	18	3	0	21	1	0	0	0	1	2	0	6	0	8	57
0900-1000	7	15	0	1	23	0	21	2	0	23	1	0	1	0	2	5	0	3	0	8	56
1130-1230	1	12	1	0	14	0	21	4	0	25	1	0	1	0	2	2	0	2	0	4	45
1230-1330	3	15	2	0	20	3	23	4	0	30	2	0	0	0	2	2	0	3	0	5	57
1500-1600	4	20	1	0	25	0	27	2	0	29	1	0	0	0	1	2	0	2	0	4	59
1600-1700	4	12	0	0	16	0	17	4	0	21	0	0	0	0	0	4	0	4	0	8	45
1700-1800	5	5	0	0	10	0	16	4	0	20	0	0	0	0	0	2	0	2	0	4	34
Totals	31	140	8	1	180	4	156	26	0	186	6	0	3	0	9	24	0	26	0	50	425

Comments:

OC Transpo and Para Transpo buses, private buses and school buses comprise 51.29% of the heavy vehicle traffic. Many pedestrians crossing Baseline Road do so on red with some having to stop on the narrow median before completing their crossing.



Turning Movement Count Bicycle Summary Flow Diagram



Baseline Road & John Sutherland Drive/Valley Stream Drive (Loc 01)

Nepean, ON

Bicycles

(Including electric bicycles and electric scooters)

Note:

Bicycle volumes are **NOT** included in vehicle totals.

Wednesday, November 06, 2024

0700-1000, 1130-1330 & 1500-1800

8 Hour Survey

City of Ottawa Ward ► 8

Baseline Rd.

John Sutherland Dr.

Baseline Rd.

16

36

20

(A)

2 2 5 0

Total Bicycle Volume

49

Approaching Intersection
(A+B+C+D)

(D)

16

35

Bicycles
comprise
0.35%
of total traffic

19

Includes all bicycles
travelling on sidewalks.

Valley Stream Dr.

9

13

4

(C)

All Pedestrian Crossings

46

42

Total

192

39

Baseline Rd.
Eastbound

Baseline Rd.
Westbound

Valley Stream Dr.
Northbound

John Sutherland Dr.
Southbound

Time Period	LT	ST	RT	UT	EB Tot	LT	ST	RT	UT	WB Tot	LT	ST	RT	UT	NB Tot	LT	ST	RT	UT	SB Tot	GR Tot
0700-0800	0	1	0	0	1	0	4	2	0	6	2	0	0	0	2	0	0	0	0	0	9
0800-0900	0	2	0	0	2	0	0	0	0	0	1	1	0	0	2	0	1	0	0	1	5
0900-1000	0	2	0	0	2	0	1	1	0	2	0	0	0	0	0	0	0	0	0	0	4
1130-1230	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
1230-1330	0	0	1	0	1	0	1	1	0	2	0	0	0	0	0	1	1	0	0	2	5
1500-1600	0	2	2	0	4	1	1	0	0	2	0	0	0	0	0	3	0	0	0	3	9
1600-1700	0	4	1	0	5	0	3	0	0	3	0	0	0	0	0	1	0	2	0	3	11
1700-1800	0	2	2	0	4	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	5
Totals	0	14	6	0	20	1	11	4	0	16	3	1	0	0	4	5	2	2	0	9	49

Comments:

OC Transpo and Para Transpo buses, private buses and school buses comprise 51.29% of the heavy vehicle traffic. Many pedestrians crossing Baseline Road do so on red with some having to stop on the narrow median before completing their crossing.

Turning Movement Count - Study Results

BASELINE RD @ SANDCASTLE DR


Survey Date: Thursday, February 03, 2022

WO No: 40081

Start Time: 07:00

Device: Miovision

AM Period Peak Hour Diagram



Turning Movement Count - Study Results

BASELINE RD @ SANDCASTLE DR


Survey Date: Thursday, February 03, 2022

WO No: 40081

Start Time: 07:00

Device: Miovision

PM Period Peak Hour Diagram




Survey Date: Thursday, January 12, 2017

WO No: 36634

Start Time: 07:00

Device: Miovision

AM Period Peak Hour Diagram




Survey Date: Thursday, January 12, 2017

WO No: 36634

Start Time: 07:00

Device: Miovision

PM Period Peak Hour Diagram





Turning Movement Count Summary, AM and PM Peak Hour Flow Diagrams All Vehicles Except Bicycles



John Sutherland Drive & E Qwy Carleton Hospital Access (Loc 05)

Nepean, ON

All Vehicles

(Except Bicycles & Electric Scooters)

Wednesday, November 06, 2024

0700-1000, 1130-1330 & 1500-1800



8 Hour Survey

City of Ottawa Ward 8


E Qwy Carl. Hosp Access

John Sutherland Dr.


John Sutherland Dr.



All Pedestrian Crossings



AM Peak Hour Flow Diagram




Pedestrian Crossings During AM Peak Hour	
9	0
0	0
N/A	

Total AM Peak Hour
vehicle volume, all
approaches.
(A + B + D)

Summary - AM Peak Hr.	
Peak Hr.	0700-0800
Volume	508
PHF	0.81

PM Peak Hour Flow Diagram



Pedestrian Crossings During PM Peak Hour	
17	0
0	0
N/A	

Total PM Peak Hour
vehicle volume, all
approaches.
(A + B + D)

Summary - PM Peak Hr.	
Peak Hr.	1515-1615
Volume	473
PHF	0.90



Turning Movement Count

Heavy Vehicle Summary (FHWA Class 4-13)

Flow Diagram



John Sutherland Drive & E Qwy Carleton Hospital Access (Loc 05)

Nepean, ON

Heavy Vehicles

(Construction Vehicles, Heavy Trucks, Buses & School Buses).

Heavy vehicle totals **ARE** included in the all vehicles summary and flow diagrams.

Wednesday, November 06, 2024

0700-1000, 1130-1330 & 1500-1800



8 Hour Survey

City of Ottawa Ward ► 8


John Sutherland Dr.

E Qwy Carl. Hosp Access

John Sutherland Dr.



All Pedestrian Crossings



Total

116

E Qwy Carl. Hosp Access

John Sutherland Dr.

N/A

John Sutherland Dr.

Eastbound

Westbound

Northbound

Southbound

Time Period	LT	ST	RT	UT	EB Tot	LT	ST	RT	UT	WB Tot	LT	ST	RT	UT	NB Tot	LT	ST	RT	UT	SB Tot	GR Tot
0700-0800	0	0		0	0		0	8	0	8						9		0	0	9	17
0800-0900	1	2		0	3		0	5	0	5						6		4	0	10	18
0900-1000	0	2		0	2		1	7	0	8						7		0	0	7	17
1130-1230	0	1		0	1		1	5	0	6						5		1	0	6	13
1230-1330	0	0		0	0		0	7	0	7						4		1	0	5	12
1500-1600	0	1		0	1		0	6	0	6						5		1	0	6	13
1600-1700	0	1		0	1		0	8	0	8						6		0	0	6	15
1700-1800	0	0		0	0		0	9	0	9						4		0	0	4	13
Totals	1	7		0	8		2	55	0	57						46		7	0	53	118

Comments:

OC Transpo and Para Transpo buses comprise 70.34% of the heavy vehicle traffic.



Turning Movement Count Bicycle Summary Flow Diagram



John Sutherland Drive & E Qwy Carleton Hospital Access (Loc 05)

Nepean, ON

Bicycles

(Including electric bicycles and electric scooters)

Note:

Bicycle volumes are **NOT** included in vehicle totals.

Wednesday, November 06, 2024

0700-1000, 1130-1330 & 1500-1800


8 Hour Survey

City of Ottawa Ward ► 8

E Qwy Carl. Hosp Access

John Sutherland Dr.

John Sutherland Dr.



E Qwy Carl. Hosp Access

John Sutherland Dr.

N/A

John Sutherland Dr.

Eastbound

Westbound

Northbound

Southbound

Time Period	LT	ST	RT	UT	EB Tot	LT	ST	RT	UT	WB Tot	LT	ST	RT	UT	NB Tot	LT	ST	RT	UT	SB Tot	GR Tot
0700-0800	0	0		0	0		0	2	0	2						0		0	0	0	2
0800-0900	0	1		0	1		0	0	0	0						0		0	0	0	1
0900-1000	0	0		0	0		0	1	0	1						0		0	0	0	1
1130-1230	0	0		0	0		0	0	0	0						0		0	0	0	0
1230-1330	0	0		0	0		0	1	0	1						2		1	0	3	4
1500-1600	0	0		0	0		0	0	0	0						3		1	0	4	4
1600-1700	0	1		0	1		0	0	0	0						1		0	0	1	2
1700-1800	0	0		0	0		0	0	0	0						0		0	0	0	0
Totals	0	2		0	2		0	4	0	4						6		2	0	8	14

Comments:

OC Transpo and Para Transpo buses comprise 70.34% of the heavy vehicle traffic.



Turning Movement Count Summary, AM and PM Peak Hour Flow Diagrams All Vehicles Except Bicycles



John Sutherland Drive & N Irving Greenberg Fam Cancer Ctr. (Loc 04)

Nepean, ON

All Vehicles

(Except Bicycles & Electric Scooters)

Total vehicle volume,
all approaches.
(B + C + D)

Wednesday, November 06, 2024


0700-1000, 1130-1330 & 1500-1800

8 Hour Survey

City of Ottawa Ward 8


John Sutherland Dr.

John Sutherland Dr.



AM Peak Hour Flow Diagram

PM Peak Hour Flow Diagram







Turning Movement Count Bicycle Summary Flow Diagram



John Sutherland Drive & N Irving Greenberg Fam Cancer Ctr. (Loc 04)

Nepean, ON

Bicycles

(Including electric bicycles and electric scooters)

Note:

Bicycle volumes are **NOT** included in vehicle totals.

Total bicycle volume,
all approaches.
(B + C + D)

Bicycles
comprise
0.43%
of total traffic

Wednesday, November 06, 2024


0700-1000, 1130-1330 & 1500-1800

8 Hour Survey

City of Ottawa Ward ► 8

John Sutherland Dr.

John Sutherland Dr.



John Sutherland Dr.

John Sutherland Dr.

N Irving Greenberg Fam Cancer Ctr

N/A

Eastbound

Westbound

Northbound

Southbound

Time Period	LT	ST	RT	UT	EB Tot	LT	ST	RT	UT	WB Tot	LT	ST	RT	UT	NB Tot	LT	ST	RT	UT	SB Tot	GR Tot
0700-0800		0	0	0	0	0	0		0	0	0		0	0	0						0
0800-0900		0	0	0	0	0	0		0	0	0		0	0	0						0
0900-1000		0	0	0	0	1	0		0	1	0		0	0	0						1
1130-1230		0	2	0	2	0	0		0	0	2		0	0	2						4
1230-1330		2	0	0	2	0	1		0	1	0		0	0	0						3
1500-1600		0	0	0	0	0	0		0	0	0		0	0	0						0
1600-1700		1	0	0	1	0	0		0	0	0		0	0	0						1
1700-1800		0	0	0	0	0	0		0	0	0		0	0	0						0
Totals		3	2	0	5	1	1		0	2	2		0	0	2						9

Comments:

OC Transpo and Para Transpo buses comprise 65.81% of the heavy vehicle traffic.



Turning Movement Count

Heavy Vehicle Summary (FHWA Class 4 to 13)

Flow Diagram



John Sutherland Drive & N Qwy Carleton Hospital Access (Loc 03)

Nepean, ON

Heavy Vehicles

(Construction Vehicles, Heavy Trucks, Buses & School Buses).

Heavy vehicle totals ARE included in the all vehicles summary and flow diagrams.

Total heavy vehicle volume, all approaches.
(B + C + D)

Heavy Vehicles
Comprise

5.14%
of Total Traffic

Wednesday, November 06, 2024


0700-1000, 1130-1330 & 1500-1800

8 Hour Survey

City of Ottawa Ward ► 8

John Sutherland Dr.

John Sutherland Dr.



John Sutherland Dr.

John Sutherland Dr.

N Qwy Carl. Hosp. Access

N/A

Eastbound

Westbound

Northbound

Southbound

Time Period	LT	ST	RT	UT	EB Tot	LT	ST	RT	UT	WB Tot	LT	ST	RT	UT	NB Tot	LT	ST	RT	UT	SB Tot	GR Tot
0700-0800		9	2	0	11	1	4		0	5	2		1	0	3						19
0800-0900		10	1	0	11	1	6		0	7	1		0	0	1						19
0900-1000		8	1	0	9	2	7		0	9	2		2	0	4						22
1130-1230		9	3	0	12	1	6		0	7	4		0	0	4						23
1230-1330		6	0	0	6	2	8		0	10	2		0	0	2						18
1500-1600		6	0	0	6	0	7		0	7	0		0	0	0						13
1600-1700		4	1	0	5	0	9		0	9	1		0	0	1						15
1700-1800		6	1	0	7	1	8		0	9	2		0	0	2						18
Totals		58	9	0	67	8	55		0	63	14		3	0	17						147

Comments:

OC Transpo and Para Transpo buses comprise 61.90% of the heavy vehicle traffic.



Turning Movement Count Bicycle Summary Flow Diagram



John Sutherland Drive & N Qwy Carleton Hospital Access (Loc 03)

Nepean, ON

Bicycles

(Including electric bicycles and electric scooters)

Note:

Bicycle volumes are **NOT** included in vehicle totals.

Total bicycle volume, all approaches.
(B + C + D)

Bicycles comprise
0.42%
of total traffic

Wednesday, November 06, 2024


0700-1000, 1130-1330 & 1500-1800

8 Hour Survey

City of Ottawa Ward ► 8

John Sutherland Dr.

John Sutherland Dr.



John Sutherland Dr.

John Sutherland Dr.

N Qwy Carl. Hosp. Access

N/A

Eastbound

Westbound

Northbound

Southbound

Time Period	LT	ST	RT	UT	EB Tot	LT	ST	RT	UT	WB Tot	LT	ST	RT	UT	NB Tot	LT	ST	RT	UT	SB Tot	GR Tot
0700-0800		0	1	0	1	0	0		0	0	0		0	0	0						1
0800-0900		0	0	0	0	0	0		0	0	0		0	0	0						0
0900-1000		0	0	0	0	0	0		0	0	0		0	0	0						0
1130-1230		0	1	0	1	0	2		0	2	0		2	0	2						5
1230-1330		2	0	0	2	0	1		0	1	0		0	0	0						3
1500-1600		0	0	0	0	0	0		0	0			1	0	1						1
1600-1700		0	0	0	0	0	0		0	0	2		0	0	2						2
1700-1800		0	0	0	0	0	0		0	0	0		0	0	0						0
Totals		2	2	0	4	0	3		0	3	2		3	0	5						12

Comments:

OC Transpo and Para Transpo buses comprise 61.90% of the heavy vehicle traffic.



Turning Movement Count Summary, AM and PM Peak Hour Flow Diagrams All Vehicles Except Bicycles



John Sutherland Drive & N Pkg Lot/Private Access (Loc 02)

Nepean, ON

All Vehicles

(Except Bicycles & Electric Scooters)

Wednesday, November 06, 2024

0700-1000, 1130-1330 & 1500-1800

8 Hour Survey

City of Ottawa Ward 8


John Sutherland Dr.

John Sutherland Dr.

1299

2639

1340 (B)



Private Access

(A) 156 313 157

106 0 49 1

Total Volume
2757


Approaching Intersection
(A+B+C+D)

(D) 1249

2539



1290

All Pedestrian Crossings



AM Peak Hour Flow Diagram

PM Peak Hour Flow Diagram





Turning Movement Count Heavy Vehicle Summary (FHWA Class 4-13) Flow Diagram



John Sutherland Drive & N Pkg Lot/Private Access (Loc 02)

Nepean, ON

Heavy Vehicles

(Construction Vehicles, Heavy Trucks, Buses & School Buses).
Heavy vehicle totals ARE included in the all vehicles summary and flow diagrams.

North Pkg Lot

John Sutherland Dr.

Wednesday, November 06, 2024

0700-1000, 1130-1330 & 1500-1800

8 Hour Survey

City of Ottawa Ward 8

John Sutherland Dr.

68

135

67

(B)

(A)

0

0

0

0

Total Heavy Vehicles

135

Approaching Intersection

(A+B+C+D)

(D)

68

135

Heavy Vehicles
Comprise
4.90%
of Total Traffic

67

All Pedestrian Crossings


14

8

14

Total

98



Private Access



John Sutherland Dr.

Eastbound

John Sutherland Dr.

Westbound

Private Access

Northbound

North Pkg Lot

Southbound

Time Period	LT	ST	RT	UT	EB Tot	LT	ST	RT	UT	WB Tot	LT	ST	RT	UT	NB Tot	LT	ST	RT	UT	SB Tot	GR Tot
0700-0800	0	11	0	0	11	0	6	0	0	6	0	0	0	0	0	0	0	0	0	0	17
0800-0900	0	11	0	0	11	0	7	0	0	7	0	0	0	0	0	0	0	0	0	0	18
0900-1000	0	9	0	0	9	0	9	0	0	9	0	0	0	0	0	0	0	0	0	0	18
1130-1230	0	11	0	0	11	0	10	0	0	10	0	0	0	0	0	0	0	0	0	0	21
1230-1330	0	6	0	0	6	0	10	0	0	10	0	0	0	0	0	0	0	0	0	0	16
1500-1600	0	6	0	0	6	0	7	0	0	7	0	0	0	0	0	0	0	0	0	0	13
1600-1700	0	6	0	0	6	0	10	0	0	10	0	0	0	0	0	0	0	0	0	0	16
1700-1800	0	7	0	0	7	0	9	0	0	9	0	0	0	0	0	0	0	0	0	0	16
Totals	0	67	0	0	67	0	68	0	0	68	0	0	0	0	0	0	0	0	0	0	135

Comments:

OC Transpo and Para Transpo buses comprise 67.41% of the heavy vehicle traffic.



Turning Movement Count Bicycle Summary Flow Diagram



John Sutherland Drive & N Pkg Lot/Private Access (Loc 02)

Nepean, ON

Bicycles

(Including electric bicycles and electric scooters)

Note:

Bicycle volumes are **NOT** included in vehicle totals.

John Sutherland Dr.

North Pkg Lot

Wednesday, November 06, 2024

0700-1000, 1130-1330 & 1500-1800

8 Hour Survey

City of Ottawa Ward ► 8

John Sutherland Dr.

Total Bicycle Volume

9

Approaching Intersection
(A+B+C+D)

Bicycles
comprise
0.33%
of total traffic

Includes all bicycles
travelling on sidewalks.

Private Access

All Pedestrian Crossings



Total
98

John Sutherland Dr.
Eastbound

John Sutherland Dr.
Westbound

Private Access
Northbound

North Pkg Lot
Southbound

Time Period	LT	ST	RT	UT	EB Tot	LT	ST	RT	UT	WB Tot	LT	ST	RT	UT	NB Tot	LT	ST	RT	UT	SB Tot	GR Tot
0700-0800	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
0800-0900	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
0900-1000	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1130-1230	0	1	0	0	1	0	2	0	0	2	0	0	0	0	0	0	0	0	0	0	3
1230-1330	0	2	0	0	2	0	1	0	0	1	0	0	0	0	0	0	0	0	0	0	3
1500-1600	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
1600-1700	0	0	0	0	0	0	1	0	0	1	1	0	0	0	1	0	0	0	0	0	2
1700-1800	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Totals	0	4	0	0	4	0	4	0	0	4	1	0	0	0	1	0	0	0	0	0	9

Comments:

OC Transpo and Para Transpo buses comprise 67.41% of the heavy vehicle traffic.

Appendix E: Signal Timing Plans

Traffic Signal Timing

City of Ottawa, Public Works Department

Traffic Signal Operations Unit


Intersection:	Main: Richmond	Side: Holly Acres / Nanaimo
Controller:	MS 3200	TSD: 5643
Author:	Kymen Kwan	Date: 07-Jul-2025

Existing Timing Plans†


	Plan					Ped Minimum Time		
	AM Peak 1	Off Peak 2	PM Peak 3	Night 4	AM Bylaw 47	Walk	DW	A+R
Cycle	100	100	110	90	110			
Offset	49	X	X	X	49			
NB Thru	42	42	47	32	33	7	17	3.7+2.6
SB Thru	42	42	47	32	33	7	17	3.7+2.6
WB Thru/Left	17	17	17	17	20	-	-	3.0+3.7
EB Left (fp)	29	29	29	29	45	-	-	3.7+2.9
EB Thru	29	29	29	29	-	-	-	3.7+2.9
EB Ped/Bike	29	29	29	29	45	7	15	3.7+2.9
NB Left	12	12	17	12	12	-	-	3.7+2.3
SB Left	12	12	17	12	12	-	-	3.7+2.3

Phasing Sequence‡

Plan: 1, 2, 3, 4



Plan: 47



- Notes:** 1) The NB U-Turn movement is prohibited
2) The EB Thru movement is prohibited weekdays 7:00-9:00 with bicycles excepted

Schedule

Weekday		Saturday		Sunday	
Time	Plan	Time	Plan	Time	Plan
0:15	4	0:15	4	0:15	4
6:30	1	9:00	2	9:00	2
7:00	47	22:00	4	19:00	4
9:00	1				
9:30	2				
15:00	3				
18:30	2				
21:30	4				

Notes

†: Time for each direction includes amber and all red intervals
‡: Start of first phase should be used as reference point for offset
Asterisk (*) Indicates actuated phase
(fp): Fully Protected Left Turn
◀.....▶ Pedestrian signal

Cost is \$63.94 (\$56.58 + HST)

Traffic Signal Timing

City of Ottawa, Public Works Department

Traffic Signal Operations Unit


Intersection:	<i>Main:</i> Richmond	<i>Side:</i> John Sutherland / Hospital
Controller:	MS 3200	TSD: 5662
Author:	Kymen Kwan	Date: 29-Oct-2024

Existing Timing Plans[†]

	Plan				Ped Minimum Time		
	AM Peak 1	Off Peak 2	PM Peak 3	Night 4	Walk	DW	A+R
Cycle	100	80	120	80			
Offset	92	X	82	X			
NB Thru	62	42	82	42	7	16	4.6+1.8
SB Thru	62	42	82	42	7	16	4.6+1.8
EB Thru	38	38	38	38	7	24	3.3+3.3
WB Thru	38	38	38	38	7	24	3.3+3.3

Phasing Sequence[‡]

Plan: All



Notes: 1) The SB U-Turn is prohibited

Schedule

Weekday

Time	Plan
0:15	4
6:30	1
9:30	2
15:00	3
18:30	2
21:30	4

Saturday

Time	Plan
0:15	4
9:00	3
18:00	2
22:00	4

Sunday

Time	Plan
0:15	4
9:00	2
19:00	4

Notes

†: Time for each direction includes amber and all red intervals

‡: Start of first phase should be used as reference point for offset

Asterisk (*) Indicates actuated phase

(fp): Fully Protected Left Turn

◀.....▶ Pedestrian signal

Cost is \$62.38 (\$55.20 + HST)

Traffic Signal Timing

City of Ottawa, Public Works Department

Traffic Signal Operations Unit


Intersection:	<i>Main:</i> Richmond/Robertson	<i>Side:</i> Baseline
Controller:	ATC 3	TSD: 5638
Author:	Kymen Kwan	Date: 29-Oct-2024

Existing Timing Plans†

	Plan				Ped Minimum Time		
	AM Peak 1	Off Peak 2	PM Peak 3	Night 4	Walk	DW	A+R
Cycle	100	100	120	90			
Offset	93	93	108	X			
NB Thru	44	44	51	31	7	17	4.6+2.0
SB Thru	44	44	51	31	7	17	4.6+2.0
WB Thru	37	37	37	37	11	19	4.2+2.6
NB Left (fp)	19	19	32	22	-	-	4.6+2.0
SB Left (fp)	19	19	32	22	-	-	4.6+2.0

Phasing Sequence‡

Plan: All



Schedule

Weekday		Saturday		Sunday	
Time	Plan	Time	Plan	Time	Plan
0:15	4	0:15	4	0:15	4
6:30	1	9:00	3	9:00	2
9:30	2	18:00	2	19:00	4
15:00	3	22:00	4		
18:30	2				
21:30	4				

Notes

†: Time for each direction includes amber and all red intervals

‡: Start of first phase should be used as reference point for offset

Asterisk (*) Indicates actuated phase

(fp): Fully Protected Left Turn

◀.....▶ Pedestrian signal

Cost is \$62.38 (\$55.20 + HST)

Traffic Signal Timing

City of Ottawa, Public Works Department

Traffic Signal Operations Unit


Intersection:	Main: Baseline	Side: Cedarview
Controller:	ATC 3	TSD: 5572
Author:	Kymen Kwan	Date: 30-Oct-2024

Existing Timing Plans[†]

	Plan					Ped Minimum Time		
	AM Peak 1	Off Peak 2	PM Peak 3	Night 4	Weekend 5	Walk	DW	A+R
Cycle	130	105	130	105	105			
Offset	X	22	11	X	22			
EB Thru	34	28	49	28	28	7	14	4.2+1.9
WB Thru	34	39	64	28	39	-	-	4.2+1.9
NS Bike	36	36	36	36	36	7	23	3.7+2.5
NB Thru	45	30	30	30	30	-	-	3.7+2.5
NB Right	60	41	45	41	41	-	-	3.7+2.5
WB Left	15	11	15	11	11	-	-	4.2+1.9

Phasing Sequence[‡]

Plan: All



Notes: 1) If the NS pedestrian phase is not actuated, the NS Bike phase will receive a maximum green time of 15s

Schedule

Weekday

Time	Plan
0:15	4
6:30	1
9:30	2
15:00	3
18:45	2
21:30	4

Saturday

Time	Plan
0:15	4
8:30	5
22:30	4

Sunday

Time	Plan
0:15	4
8:30	5
22:30	4

Notes

†: Time for each direction includes amber and all red intervals
‡: Start of first phase should be used as reference point for offset
Asterisk (*) Indicates actuated phase
(fp): Fully Protected Left Turn
◀.....▶ Pedestrian signal

Cost is \$62.38 (\$55.20 + HST)

Traffic Signal Timing

City of Ottawa, Public Works Department

Traffic Signal Operations Unit


Intersection:	<i>Main:</i> Baseline	<i>Side:</i> Valley Stream / John Sutherland
Controller:	ATC 3	TSD: 5708
Author:	Kymen Kwan	Date: 29-Oct-2024

Existing Timing Plans[†]

	Plan					Ped Minimum Time		
	AM Peak 1	Off Peak 2	PM Peak 3	Night 4	Weekend 5	Walk	DW	A+R
Cycle	85	75	100	70	75			
Offset	37	25	77	X	25			
EB Thru	47	37	62	32	37	7	19	4.2+2.0
WB Thru	47	37	62	32	37	7	19	4.2+2.0
NB Thru	38	38	38	38	38	7	24	3.3+3.2
SB Thru	38	38	38	38	38	7	24	3.3+3.2

Phasing Sequence[‡]

Plan: All



Schedule

Weekday		Saturday		Sunday	
Time	Plan	Time	Plan	Time	Plan
0:15	4	0:15	4	0:15	4
6:30	1	8:30	5	12:00	2
9:30	2	22:30	4	22:30	4
15:00	3				
18:45	2				
21:30	4				

Notes

†: Time for each direction includes amber and all red intervals

‡: Start of first phase should be used as reference point for offset

Asterisk (*) Indicates actuated phase

(fp): Fully Protected Left Turn

◀.....▶ Pedestrian signal

Cost is \$62.38 (\$55.20 + HST)

Traffic Signal Timing

City of Ottawa, Public Works Department

Traffic Signal Operations Unit


Intersection:	Main: Baseline	Side: Sandcastle
Controller:	MS 3200	TSD: 5944
Author:	Kymen Kwan	Date: 07-Jul-2025

Existing Timing Plans[†]

	Plan					Ped Minimum Time		
	AM Peak 1	Off Peak 2	PM Peak 3	Night 4	Weekend 5	Walk	DW	A+R
Cycle	85	75	100	65	75			
Offset	55	59	62	X	59			
EB Thru	47	37	62	27	37	7	11	4.2+1.7
WB Thru	47	37	62	27	37	-	-	4.2+1.7
NB Thru	38	38	38	38	38	7	24	3.0+3.5

Phasing Sequence[‡]

Plan: All



Notes: 1) The EB U-Turn movement is prohibited

Schedule

Weekday

Time	Plan
0:15	4
6:30	1
9:30	2
15:00	3
18:45	2
21:30	4

Weekend

Time	Plan
0:15	4
8:30	5
22:30	4

Notes

†: Time for each direction includes amber and all red intervals

‡: Start of first phase should be used as reference point for offset

Asterisk (*) Indicates actuated phase

(fp): Fully Protected Left Turn

◀.....▶ Pedestrian signal

Cost is \$63.94 (\$56.58 + HST)

Appendix F: Collision Data

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: BASELINE RD @ 180 E OF CEDARVIEW RD

Traffic Control: MPS

Total Collisions: 1

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2020-Mar-11, Wed,09:27	Clear	Sideswipe	P.D. only	Ice	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Truck and trailer	Other motor vehicle	

Location: BASELINE RD @ CEDARVIEW RD

Traffic Control: Traffic signal

Total Collisions: 16

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Feb-02, Fri,16:55	Clear	Rear end	P.D. only	Dry	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2018-Mar-19, Mon,11:16	Clear	SMV other	P.D. only	Dry	West	Turning left	Pick-up truck	Pole (utility, power)	0
2018-Mar-25, Sun,18:55	Clear	Rear end	Non-fatal injury	Dry	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Passenger van	Other motor vehicle	
2018-Mar-31, Sat,16:34	Clear	Turning movement	P.D. only	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2018-May-15, Tue,15:27	Clear	Turning movement	Non-fatal injury	Dry	North	Going ahead	Bicycle	Other motor vehicle	0
					North	Turning left	Passenger van	Cyclist	
2018-Jun-14, Thu,17:12	Clear	Turning movement	Non-fatal injury	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2018-Jul-11, Wed,17:30	Clear	Rear end	P.D. only	Dry	East	Turning right	Automobile, station wagon	Other motor vehicle	0
					East	Turning right	Automobile, station wagon	Other motor vehicle	
2019-Apr-09, Tue,13:35	Snow	Sideswipe	P.D. only	Loose snow	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Dec-15, Sun,10:07	Clear	Turning movement	P.D. only	Slush	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Pick-up truck	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: BASELINE RD @ CEDARVIEW RD

Traffic Control: Traffic signal

Total Collisions: 16

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2020-Mar-03, Tue,07:17	Clear	Rear end	P.D. only	Ice	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2021-Oct-21, Thu,15:19	Clear	Sideswipe	P.D. only	Dry	West	Other	Automobile, station wagon	Other motor vehicle	0
					West	Other	Automobile, station wagon	Other motor vehicle	
2021-Dec-18, Sat,15:50	Snow	Other	P.D. only	Loose snow	East	Reversing	Pick-up truck	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2022-Jan-10, Mon,19:47	Clear	SMV other	Non-fatal injury	Dry	West	Turning left	Automobile, station wagon	Pedestrian	1
2022-Jan-29, Sat,16:19	Clear	Rear end	P.D. only	Wet	East	Turning right	Pick-up truck	Other motor vehicle	0
					East	Turning right	Pick-up truck	Other motor vehicle	
2022-Feb-03, Thu,16:36	Clear	Turning movement	P.D. only	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Pick-up truck	Other motor vehicle	
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-Feb-08, Tue,16:55	Snow	Turning movement	Non-fatal injury	Wet	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Pick-up truck	Other motor vehicle	

Location: BASELINE RD @ JOHN SUTHERLAND DR/VALLEY STREAM DR

Traffic Control: Traffic signal

Total Collisions: 15

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Jan-15, Mon,17:43	Clear	Rear end	P.D. only	Wet	East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	
2018-Jan-30, Tue,13:30	Clear	Sideswipe	P.D. only	Dry	West	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Apr-02, Tue,14:37	Clear	Turning movement	Non-fatal injury	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: BASELINE RD @ JOHN SUTHERLAND DR/VALLEY STREAM DR

Traffic Control: Traffic signal

Total Collisions: 15

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2019-Oct-01, Tue,07:45	Fog, mist, smoke, dust	Rear end	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Dec-11, Wed,17:50	Snow	Rear end	P.D. only	Loose snow	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	
2020-Jan-30, Thu,08:50	Clear	Turning movement	P.D. only	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2020-Feb-24, Mon,17:54	Clear	Turning movement	Non-fatal injury	Wet	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2020-Mar-10, Tue,11:28	Rain	Angle	Non-fatal injury	Wet	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					South	Turning left	Automobile, station wagon	Other motor vehicle	
2020-Jul-23, Thu,09:57	Clear	Turning movement	Non-fatal injury	Dry	East	Turning left	Pick-up truck	Other motor vehicle	0
					West	Going ahead	Pick-up truck	Other motor vehicle	
2020-Oct-13, Tue,07:21	Rain	Turning movement	P.D. only	Wet	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2021-Feb-05, Fri,12:42	Clear	Turning movement	P.D. only	Wet	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2021-Apr-08, Thu,16:32	Clear	SMV other	Non-fatal injury	Dry	East	Turning right	Automobile, station wagon	Ran off road	0
2022-Jun-08, Wed,15:29	Clear	Rear end	P.D. only	Dry	East	Going ahead	Pick-up truck	Other motor vehicle	0
					East	Slowing or stopping	Pick-up truck	Other motor vehicle	
2022-Aug-11, Thu,11:18	Clear	Turning movement	P.D. only	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Municipal transit bus	Other motor vehicle	
2022-Dec-14, Wed,10:20	Clear	Angle	P.D. only	Dry	South	Turning left	Municipal transit bus	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: BASELINE RD @ SANDCASTLE DR

Traffic Control: Traffic signal

Total Collisions: 9

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-May-30, Wed,22:02	Clear	Angle	P.D. only	Dry	East	Going ahead	Unknown	Other motor vehicle	0
					North	Turning left	Automobile, station wagon	Other motor vehicle	
2018-Jun-18, Mon,11:58	Rain	Sideswipe	P.D. only	Wet	East	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Nov-11, Mon,13:40	Clear	Rear end	Non-fatal injury	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2020-Feb-25, Tue,07:57	Clear	Rear end	P.D. only	Wet	East	Slowing or stopping	Passenger van	Other motor vehicle	0
					East	Slowing or stopping	School bus	Other motor vehicle	
2020-Oct-30, Fri,12:33	Clear	Rear end	Non-fatal injury	Dry	North	Going ahead	Pick-up truck	Other motor vehicle	0
					North	Stopped	Passenger van	Other motor vehicle	
2021-Feb-18, Thu,13:29	Clear	Turning movement	Non-fatal injury	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2021-Sep-27, Mon,16:50	Clear	Rear end	P.D. only	Dry	East	Going ahead	Unknown	Other motor vehicle	0
					East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2022-Feb-25, Fri,20:49	Clear	Turning movement	Non-fatal injury	Loose snow	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-Oct-18, Tue,08:30	Clear	Turning movement	P.D. only	Dry	East	Turning right	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	

Location: BASELINE RD @ SIOUX CRES

Traffic Control: Stop sign

Total Collisions: 3

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2019-Jan-29, Tue,15:59	Snow	Angle	P.D. only	Slush	West	Turning right	Automobile, station wagon	Other motor vehicle	0
					South	Going ahead	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: BASELINE RD @ SIOUX CRES

Traffic Control: Stop sign

Total Collisions: 3

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2022-Jan-17, Mon,20:26	Snow	Angle	P.D. only	Ice	West	Turning right	Pick-up truck	Other motor vehicle	0
					South	Stopped	Pick-up truck	Other motor vehicle	
2022-Dec-23, Fri,18:30	Freezing Rain	Angle	P.D. only	Ice	South	Stopped	Pick-up truck	Other motor vehicle	0
					West	Turning right	Automobile, station wagon	Other motor vehicle	

Location: BASELINE RD btwn CEDARVIEW RD & JOHN SUTHERLAND DR/VALLEY STREAM DR

Traffic Control: No control

Total Collisions: 1

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2021-Jun-21, Mon,09:16	Clear	Sideswipe	P.D. only	Dry	West	Unknown	Unknown	Other motor vehicle	0
					West	Going ahead	Passenger van	Other motor vehicle	

Location: BASELINE RD btwn RICHMOND RD/ROBERTSON RD & CEDARVIEW RD

Traffic Control: No control

Total Collisions: 5

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2019-Aug-28, Wed,00:37	Clear	SMV other	Non-fatal injury	Dry	West	Going ahead	Automobile, station wagon	Ran off road	0
2020-Dec-16, Wed,03:56	Clear	SMV other	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Curb	0
2021-Aug-03, Tue,14:00	Clear	Sideswipe	P.D. only	Dry	East	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-Mar-14, Mon,12:30	Clear	Rear end	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	
					North	Stopped	Automobile, station wagon	Other motor vehicle	
2022-Oct-07, Fri,13:45	Clear	Sideswipe	P.D. only	Dry	East	Changing lanes	Unknown	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: BASELINE RD btwn SIOUX CRES & SANDCASTLE DR

Traffic Control: No control

Total Collisions: 2

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Mar-30, Fri,00:40	Rain	SMV other	P.D. only	Wet	West	Going ahead	Automobile, station wagon	Ran off road	0
2021-Dec-17, Fri,14:29	Clear	Rear end	P.D. only	Dry	West	Going ahead	Passenger van	Other motor vehicle	0
					West	Stopped	Municipal transit bus	Other motor vehicle	

Location: BASELINE RD/HWY 416 RICHMOND IC75AR53 @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 45

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Jan-03, Wed,13:20	Clear	Rear end	P.D. only	Packed snow	South	Going ahead	Automobile, station wagon	Other motor vehicle	0
					South	Stopped	Automobile, station wagon	Other motor vehicle	
2018-Jun-01, Fri,17:33	Clear	Sideswipe	P.D. only	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Turning left	Automobile, station wagon	Other motor vehicle	
2018-Jul-14, Sat,17:15	Clear	Sideswipe	P.D. only	Dry	South	Overtaking	Automobile, station wagon	Other motor vehicle	0
					South	Stopped	Automobile, station wagon	Other motor vehicle	
2018-Jul-21, Sat,22:30	Clear	Rear end	P.D. only	Dry	East	Unknown	Unknown	Other motor vehicle	0
					East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2018-Oct-11, Thu,07:13	Rain	Rear end	P.D. only	Wet	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2018-Oct-12, Fri,09:13	Clear	Rear end	P.D. only	Dry	North	Turning right	Automobile, station wagon	Other motor vehicle	0
					North	Turning right	Automobile, station wagon	Other motor vehicle	
2018-Oct-27, Sat,14:14	Clear	Rear end	P.D. only	Dry	North	Merging	Automobile, station wagon	Other motor vehicle	0
					North	Merging	Automobile, station wagon	Other motor vehicle	
2019-Mar-09, Sat,14:14	Clear	Rear end	Non-fatal injury	Dry	North	Turning right	Unknown	Other motor vehicle	0
					North	Turning right	Pick-up truck	Other motor vehicle	
					North	Stopped	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: BASELINE RD/HWY 416 RICHMOND IC75AR53 @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 45

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2019-Apr-30, Tue,12:00	Clear	Rear end	P.D. only	Dry	South	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					South	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Aug-20, Tue,16:48	Clear	Sideswipe	Non-fatal injury	Dry	West	Changing lanes	Automobile, station wagon	Cyclist	0
					West	Going ahead	Bicycle	Other motor vehicle	
2019-Sep-22, Sun,15:30	Clear	Sideswipe	P.D. only	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Turning left	Automobile, station wagon	Other motor vehicle	
2019-Oct-02, Wed,16:03	Clear	Rear end	P.D. only	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Turning left	Automobile, station wagon	Other motor vehicle	
2019-Nov-05, Tue,07:10	Clear	Rear end	P.D. only	Wet	East	Slowing or stopping	Pick-up truck	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Nov-18, Mon,16:30	Clear	Rear end	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Nov-29, Fri,08:11	Clear	Rear end	Non-fatal injury	Dry	North	Turning right	Automobile, station wagon	Other motor vehicle	0
					North	Turning right	Automobile, station wagon	Other motor vehicle	
2019-Dec-06, Fri,14:41	Clear	Rear end	P.D. only	Wet	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2020-Jan-18, Sat,18:30	Snow	SMV other	P.D. only	Packed snow	West	Turning left	Automobile, station wagon	Skidding/sliding	0
2020-Feb-25, Tue,16:10	Clear	Sideswipe	P.D. only	Dry	South	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					South	Going ahead	Automobile, station wagon	Other motor vehicle	
2020-Jun-24, Wed,08:44	Clear	Rear end	Non-fatal injury	Dry	North	Going ahead	Passenger van	Other motor vehicle	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	
2020-Jul-27, Mon,12:15	Clear	Other	P.D. only	Dry	South	Reversing	Unknown	Other motor vehicle	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: BASELINE RD/HWY 416 RICHMOND IC75AR53 @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 45

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2020-Aug-17, Mon,11:30	Clear	Sideswipe	P.D. only	Dry	North	Changing lanes	Pick-up truck	Other motor vehicle	0
					North	Going ahead	Pick-up truck	Other motor vehicle	
2020-Nov-05, Thu,19:00	Clear	Rear end	Non-fatal injury	Dry	West	Turning right	Automobile, station wagon	Other motor vehicle	0
					West	Turning right	Automobile, station wagon	Other motor vehicle	
2021-Mar-04, Thu,15:12	Clear	Rear end	P.D. only	Dry	North	Unknown	Unknown	Other motor vehicle	0
					North	Stopped	Pick-up truck	Other motor vehicle	
2021-Mar-31, Wed,11:35	Rain	Rear end	P.D. only	Wet	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Slowing or stopping	Pick-up truck	Other motor vehicle	
2021-Jun-15, Tue,08:27	Clear	Rear end	P.D. only	Dry	North	Turning right	Pick-up truck	Other motor vehicle	0
					North	Turning right	Automobile, station wagon	Other motor vehicle	
2021-Jun-18, Fri,17:21	Rain	Rear end	P.D. only	Wet	West	Unknown	Unknown	Other motor vehicle	0
					West	Stopped	Passenger van	Other motor vehicle	
2021-Jul-27, Tue,10:00	Rain	Rear end	P.D. only	Wet	North	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					North	Stopped	Pick-up truck	Other motor vehicle	
2021-Sep-14, Tue,20:01	Clear	Rear end	P.D. only	Dry	North	Slowing or stopping	Pick-up truck	Other motor vehicle	0
					North	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2021-Sep-16, Thu,15:19	Clear	Rear end	Non-fatal injury	Dry	West	Turning right	Automobile, station wagon	Other motor vehicle	0
					West	Turning right	Pick-up truck	Other motor vehicle	
2021-Sep-24, Fri,08:25	Clear	Rear end	P.D. only	Dry	North	Turning right	Pick-up truck	Other motor vehicle	0
					North	Turning right	Unknown	Other motor vehicle	
2021-Sep-28, Tue,01:49	Clear	SMV other	P.D. only	Dry	North	Turning right	Pick-up truck	Pole (sign, parking meter)	0
2021-Nov-24, Wed,05:39	Clear	SMV other	P.D. only	Dry	West	Going ahead	Pick-up truck	Ran off road	0
2021-Dec-09, Thu,20:37	Clear	Turning movement	Non-fatal injury	Dry	East	Going ahead	Passenger van	Other motor vehicle	0
					West	Turning left	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: BASELINE RD/HWY 416 RICHMOND IC75AR53 @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 45

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2022-Jan-02, Sun,11:29	Clear	Rear end	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	
					North	Stopped	Pick-up truck	Other motor vehicle	
2022-Jan-19, Wed,10:30	Clear	Rear end	P.D. only	Packed snow	West	Unknown	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2022-Jan-24, Mon,14:30	Clear	Sideswipe	P.D. only	Packed snow	South	Going ahead	Automobile, station wagon	Other motor vehicle	0
					South	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-Feb-01, Tue,17:50	Clear	Rear end	P.D. only	Slush	North	Unknown	Unknown	Other motor vehicle	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	
2022-Apr-25, Mon,14:15	Clear	Sideswipe	P.D. only	Dry	North	Changing lanes	Pick-up truck	Other motor vehicle	0
					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-May-15, Sun,00:31	Clear	SMV other	Non-fatal injury	Dry	North	Turning right	Automobile, station wagon	Curb	0
2022-Jul-27, Wed,15:24	Clear	Rear end	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	
2022-Aug-31, Wed,18:25	Rain	Turning movement	P.D. only	Wet	West	Turning right	Pick-up truck	Other motor vehicle	0
					West	Going ahead	Pick-up truck	Other motor vehicle	
2022-Nov-04, Fri,16:59	Clear	Rear end	P.D. only	Dry	West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					West	Parked	Passenger van	Unattended vehicle	
2022-Dec-09, Fri,15:30	Clear	Rear end	P.D. only	Dry	West	Stopped	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-Dec-11, Sun,11:00	Snow	Rear end	P.D. only	Slush	North	Stopped	Automobile, station wagon	Other motor vehicle	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: BASELINE RD/HWY 416 RICHMOND IC75AR53 @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 45

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2022-Dec-31, Sat,15:30	Fog, mist, smoke, dust	Rear end	P.D. only	Wet	East	Stopped	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	

Location: JOHN SUTHERLAND DR @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 20

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Mar-05, Mon,12:30	Clear	Rear end	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	
2018-May-01, Tue,18:04	Clear	Rear end	P.D. only	Dry	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2018-Aug-04, Sat,13:26	Clear	Turning movement	P.D. only	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2018-Oct-22, Mon,06:45	Clear	Turning movement	P.D. only	Dry	South	Turning left	Automobile, station wagon	Other motor vehicle	0
					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2018-Nov-12, Mon,06:56	Snow	Angle	P.D. only	Ice	East	Turning right	Automobile, station wagon	Other motor vehicle	0
					North	Turning right	Municipal transit bus	Other motor vehicle	
2019-Jun-07, Fri,14:07	Clear	Rear end	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Jun-14, Fri,12:41	Rain	Rear end	Non-fatal injury	Wet	West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Pick-up truck	Other motor vehicle	
2019-Aug-13, Tue,11:10	Clear	Rear end	P.D. only	Dry	West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Oct-10, Thu,10:13	Clear	Turning movement	P.D. only	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: JOHN SUTHERLAND DR @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 20

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2019-Oct-19, Sat,15:28	Clear	Rear end	P.D. only	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Turning left	Automobile, station wagon	Other motor vehicle	
2019-Dec-19, Thu,15:12	Clear	Sideswipe	P.D. only	Dry	North	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					North	Going ahead	Pick-up truck	Other motor vehicle	
2020-Sep-20, Sun,17:33	Clear	Sideswipe	P.D. only	Dry	East	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2020-Oct-21, Wed,14:06	Rain	Rear end	P.D. only	Wet	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2021-Jun-29, Tue,14:00	Rain	Rear end	P.D. only	Wet	North	Slowing or stopping	Automobile, station wagon	Skidding/sliding	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	
2021-Jul-12, Mon,18:50	Clear	Angle	P.D. only	Dry	West	Turning right	Pick-up truck	Other motor vehicle	0
					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2021-Jul-27, Tue,11:33	Rain	Rear end	P.D. only	Wet	South	Going ahead	Automobile, station wagon	Other motor vehicle	0
					South	Stopped	Pick-up truck	Other motor vehicle	
2021-Oct-14, Thu,18:20	Clear	Turning movement	Non-fatal injury	Dry	South	Turning left	Automobile, station wagon	Other motor vehicle	0
					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-Jul-29, Fri,22:30	Clear	Turning movement	P.D. only	Dry	South	Turning left	Automobile, station wagon	Other motor vehicle	0
					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-Aug-25, Thu,11:50	Clear	Rear end	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Other motor vehicle	0
					North	Slowing or stopping	Pick-up truck	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: JOHN SUTHERLAND DR @ RICHMOND RD

Traffic Control: Traffic signal

Total Collisions: 20

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2022-Dec-30, Fri,18:39	Rain	Rear end	Non-fatal injury	Wet	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	
					East	Stopped	Automobile, station wagon	Other motor vehicle	
					East	Stopped	Automobile, station wagon	Other motor vehicle	

Location: KIRKWOOD AVE btwn LYMAN ST & MULVIHILL AVE

Traffic Control: No control

Total Collisions: 3

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Mar-04, Sun,17:01	Clear	Angle	P.D. only	Dry	East	Turning right	Automobile, station wagon	Other motor vehicle	0
					South	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Dec-28, Sat,11:50	Clear	Angle	P.D. only	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					North	Going ahead	Passenger van	Other motor vehicle	
2022-Sep-01, Thu,15:45	Clear	Angle	P.D. only	Dry	North	Merging	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	

Location: KIRKWOOD AVE btwn RICHMOND RD & LYMAN ST

Traffic Control: No control

Total Collisions: 3

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2021-Jul-16, Fri,13:00	Clear	Sideswipe	P.D. only	Dry	South	Unknown	Unknown	Other motor vehicle	0
					South	Going ahead	Truck - open	Other motor vehicle	
2021-Aug-16, Mon,07:25	Clear	Sideswipe	P.D. only	Dry	North	Changing lanes	Delivery van	Other motor vehicle	0
					North	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-Jan-07, Fri,20:10	Clear	Sideswipe	P.D. only	Loose snow	North	Unknown	Unknown	Other motor vehicle	0
					North	Going ahead	Pick-up truck	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: KIRKWOOD AVE btwn WILBER AVE & RICHMOND RD

Traffic Control: No control

Total Collisions: 1

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2021-Apr-27, Tue,15:58	Clear	Sideswipe	P.D. only	Dry	South	Pulling away from shoulder or curb	Delivery van	Other motor vehicle	0
					South	Going ahead	Truck - open	Other motor vehicle	

Location: RICHMOND RD @ HOLLY ACRES RD/NANAIMO DR

Traffic Control: Traffic signal

Total Collisions: 73

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Jan-24, Wed,10:31	Clear	Turning movement	P.D. only	Wet	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2018-Jan-28, Sun,12:40	Clear	Rear end	P.D. only	Dry	North	Going ahead	Automobile, station wagon	Skidding/sliding	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	
2018-Mar-01, Thu,08:54	Clear	Rear end	P.D. only	Dry	South	Stopped	Automobile, station wagon	Other motor vehicle	0
					South	Going ahead	Automobile, station wagon	Other motor vehicle	
2018-Apr-13, Fri,17:31	Clear	Turning movement	Non-fatal injury	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Turning left	Automobile, station wagon	Other motor vehicle	
2018-May-06, Sun,12:40	Clear	Rear end	P.D. only	Dry	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2018-May-09, Wed,17:24	Clear	Rear end	P.D. only	Dry	North	Turning right	Automobile, station wagon	Other motor vehicle	0
					North	Turning right	Automobile, station wagon	Other motor vehicle	
2018-May-25, Fri,15:30	Clear	Turning movement	Non-fatal injury	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
					North	Stopped	Automobile, station wagon	Other motor vehicle	
2018-Jul-23, Mon,14:34	Clear	Turning movement	P.D. only	Dry	East	Turning left	Pick-up truck	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: RICHMOND RD @ HOLLY ACRES RD/NANAIMO DR

Traffic Control: Traffic signal

Total Collisions: 73

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Sep-17, Mon,07:46	Clear	Rear end	P.D. only	Dry	South	Turning right	Pick-up truck	Other motor vehicle	0
					South	Turning right	Automobile, station wagon	Other motor vehicle	
2018-Oct-20, Sat,08:50	Clear	Rear end	P.D. only	Wet	South	Turning right	Automobile, station wagon	Other motor vehicle	0
					South	Turning right	Automobile, station wagon	Other motor vehicle	
2018-Nov-10, Sat,09:33	Clear	SMV other	P.D. only	Dry	East	Slowing or stopping	Automobile, station wagon	Pole (utility, power)	0
2018-Nov-20, Tue,15:32	Clear	Rear end	P.D. only	Wet	South	Turning right	Automobile, station wagon	Other motor vehicle	0
					South	Turning right	Automobile, station wagon	Other motor vehicle	
2019-Feb-04, Mon,08:43	Freezing Rain	Sideswipe	P.D. only	Loose snow	South	Going ahead	Truck - tractor	Other motor vehicle	0
					South	Stopped	Automobile, station wagon	Other motor vehicle	
					South	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Feb-09, Sat,17:37	Clear	Turning movement	Non-fatal injury	Dry	East	Turning left	Pick-up truck	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Mar-05, Tue,07:45	Clear	Rear end	P.D. only	Loose snow	South	Turning right	Automobile, station wagon	Other motor vehicle	0
					South	Turning right	Automobile, station wagon	Other motor vehicle	
2019-Mar-25, Mon,20:20	Clear	Turning movement	Non-fatal injury	Dry	West	Making "U" turn	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Apr-20, Sat,20:46	Clear	Sideswipe	P.D. only	Dry	East	Turning left	Pick-up truck	Other motor vehicle	0
					East	Turning left	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Passenger van	Other motor vehicle	
2019-May-20, Mon,13:39	Clear	SMV other	P.D. only	Dry	East	Turning right	Pick-up truck	Pole (utility, power)	0
2019-Jun-11, Tue,16:30	Clear	Rear end	Non-fatal injury	Dry	South	Turning right	Pick-up truck	Other motor vehicle	0
					South	Turning right	Passenger van	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: RICHMOND RD @ HOLLY ACRES RD/NANAIMO DR

Traffic Control: Traffic signal

Total Collisions: 73

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2019-Jun-27, Thu,19:15	Clear	Turning movement	Non-fatal injury	Dry	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Turning left	Passenger van	Other motor vehicle	
					South	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Jul-27, Sat,22:19	Clear	Turning movement	Non-fatal injury	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Aug-27, Tue,13:09	Clear	Turning movement	P.D. only	Dry	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Turning left	Automobile, station wagon	Other motor vehicle	
2019-Oct-16, Wed,12:42	Rain	Rear end	P.D. only	Wet	East	Going ahead	Truck - closed	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	
					East	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Oct-23, Wed,16:00	Clear	Rear end	P.D. only	Dry	South	Turning right	Motorcycle	Other motor vehicle	0
					South	Turning right	Automobile, station wagon	Other motor vehicle	
2019-Oct-24, Thu,06:45	Clear	Rear end	P.D. only	Dry	South	Changing lanes	Pick-up truck	Other motor vehicle	0
					South	Stopped	Automobile, station wagon	Other motor vehicle	
					South	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Nov-03, Sun,23:51	Clear	Rear end	P.D. only	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Turning left	Automobile, station wagon	Other motor vehicle	
2019-Nov-08, Fri,15:05	Clear	Other	P.D. only	Dry	North	Reversing	Automobile, station wagon	Other motor vehicle	0
					South	Stopped	Automobile, station wagon	Other motor vehicle	
2019-Nov-11, Mon,16:50	Snow	Rear end	P.D. only	Loose snow	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Turning left	Automobile, station wagon	Other motor vehicle	
2019-Dec-08, Sun,19:10	Clear	Sideswipe	P.D. only	Dry	East	Turning left	Passenger van	Other motor vehicle	0
					East	Turning left	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: RICHMOND RD @ HOLLY ACRES RD/NANAIMO DR

Traffic Control: Traffic signal

Total Collisions: 73

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2019-Dec-09, Mon,19:53	Rain	Rear end	P.D. only	Wet	East	Stopped	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Dec-12, Thu,17:00	Clear	Turning movement	P.D. only	Dry	North	Turning left	Automobile, station wagon	Other motor vehicle	0
					South	Going ahead	Automobile, station wagon	Other motor vehicle	
2020-Jan-06, Mon,09:30	Snow	Sideswipe	P.D. only	Loose snow	West	Changing lanes	Ambulance	Other motor vehicle	0
					West	Stopped	School bus	Other motor vehicle	
2020-Jan-21, Tue,11:30	Clear	Turning movement	P.D. only	Loose snow	West	Turning left	Pick-up truck	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2020-Jan-21, Tue,14:10	Clear	Rear end	P.D. only	Dry	North	Unknown	Unknown	Other motor vehicle	0
					North	Stopped	Pick-up truck	Other motor vehicle	
2020-Jan-24, Fri,17:15	Clear	Sideswipe	P.D. only	Wet	East	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Pick-up truck	Other motor vehicle	
2020-Feb-05, Wed,17:02	Clear	Rear end	P.D. only	Dry	South	Turning right	Automobile, station wagon	Other motor vehicle	0
					South	Turning right	Automobile, station wagon	Other motor vehicle	
2020-Feb-27, Thu,12:24	Snow	Rear end	Non-fatal injury	Loose snow	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	
2020-Jun-12, Fri,17:26	Clear	Sideswipe	P.D. only	Dry	East	Overtaking	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2020-Aug-10, Mon,10:00	Clear	Angle	P.D. only	Dry	West	Going ahead	Pick-up truck	Other motor vehicle	0
					South	Going ahead	Automobile, station wagon	Other motor vehicle	
2020-Aug-14, Fri,14:40	Clear	Rear end	Non-fatal injury	Dry	South	Turning right	Automobile, station wagon	Other motor vehicle	0
					South	Turning right	Automobile, station wagon	Other motor vehicle	
2020-Aug-21, Fri,13:23	Clear	Rear end	P.D. only	Dry	East	Turning left	Pick-up truck	Other motor vehicle	0
					East	Turning left	Automobile, station wagon	Other motor vehicle	



Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: RICHMOND RD @ HOLLY ACRES RD/NANAIMO DR

Traffic Control: Traffic signal

Total Collisions: 73

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2020-Sep-08, Tue,16:00	Rain	Rear end	P.D. only	Wet	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Turning left	Automobile, station wagon	Other motor vehicle	
2020-Sep-27, Sun,10:35	Clear	Turning movement	P.D. only	Dry	East	Turning left	Municipal transit bus	Other motor vehicle	0
					West	Going ahead	Pick-up truck	Other motor vehicle	
2020-Dec-18, Fri,14:00	Clear	Sideswipe	P.D. only	Dry	South	Turning left	Pick-up truck	Other motor vehicle	0
					South	Turning left	Automobile, station wagon	Other motor vehicle	
2021-Feb-23, Tue,18:20	Clear	Turning movement	P.D. only	Wet	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2021-Mar-10, Wed,14:15	Clear	Rear end	P.D. only	Dry	West	Going ahead	Pick-up truck	Other motor vehicle	0
					West	Stopped	Pick-up truck	Other motor vehicle	
2021-Mar-12, Fri,07:42	Clear	Turning movement	Non-fatal injury	Dry	South	Turning left	Pick-up truck	Other motor vehicle	0
					North	Going ahead	Pick-up truck	Other motor vehicle	
2021-Mar-30, Tue,08:19	Clear	Angle	Non-fatal injury	Dry	South	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Turning left	Automobile, station wagon	Other motor vehicle	
2021-Apr-20, Tue,16:15	Clear	Turning movement	P.D. only	Dry	West	Turning left	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2021-Jun-17, Thu,17:00	Clear	Turning movement	Non-fatal injury	Dry	North	Turning left	Automobile, station wagon	Cyclist	0
					South	Going ahead	Bicycle	Other motor vehicle	
2021-Jun-30, Wed,19:14	Clear	Rear end	P.D. only	Dry	South	Turning right	Automobile, station wagon	Other motor vehicle	0
					South	Turning right	Pick-up truck	Other motor vehicle	
2021-Jul-28, Wed,17:09	Clear	Rear end	P.D. only	Dry	South	Turning right	Passenger van	Other motor vehicle	0
					South	Turning right	Automobile, station wagon	Other motor vehicle	
2021-Sep-11, Sat,16:01	Clear	Angle	Non-fatal injury	Dry	North	Going ahead	Motorcycle	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: RICHMOND RD @ HOLLY ACRES RD/NANAIMO DR

Traffic Control: Traffic signal

Total Collisions: 73

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2021-Sep-23, Thu,08:50	Rain	Rear end	P.D. only	Wet	West	Slowing or stopping	Pick-up truck	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2021-Sep-23, Thu,14:37	Clear	Turning movement	P.D. only	Dry	East	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Pick-up truck	Other motor vehicle	
2021-Oct-26, Tue,18:42	Rain	Rear end	P.D. only	Wet	East	Turning right	Automobile, station wagon	Other motor vehicle	0
					East	Turning right	Pick-up truck	Other motor vehicle	
2021-Oct-28, Thu,16:03	Clear	Rear end	Non-fatal injury	Dry	South	Going ahead	Pick-up truck	Other motor vehicle	0
					South	Stopped	Pick-up truck	Other motor vehicle	
2021-Oct-30, Sat,19:12	Rain	SMV other	P.D. only	Wet	West	Going ahead	Pick-up truck	Skidding/sliding	0
2021-Nov-24, Wed,09:05	Clear	Rear end	P.D. only	Dry	West	Going ahead	Pick-up truck	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2021-Dec-15, Wed,14:38	Snow	Other	P.D. only	Wet	South	Turning left	Pick-up truck	Other motor vehicle	0
					North	Turning left	Pick-up truck	Other motor vehicle	
					West	Stopped	Pick-up truck	Other motor vehicle	
2022-May-15, Sun,15:45	Rain	Rear end	P.D. only	Wet	West	Unknown	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Pick-up truck	Other motor vehicle	
2022-May-28, Sat,10:45	Clear	Rear end	P.D. only	Dry	East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Passenger van	Other motor vehicle	
2022-Jun-12, Sun,08:24	Rain	Angle	Non-fatal injury	Wet	South	Going ahead	Pick-up truck	Other motor vehicle	0
					West	Going ahead	Pick-up truck	Other motor vehicle	
2022-Aug-25, Thu,13:10	Clear	Sideswipe	P.D. only	Dry	East	Overtaking	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	



Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: RICHMOND RD @ HOLLY ACRES RD/NANAIMO DR

Traffic Control: Traffic signal

Total Collisions: 73

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2022-Oct-18, Tue,18:30	Clear	Turning movement	P.D. only	Wet	East	Turning left	Unknown	Other motor vehicle	0
					East	Turning left	Pick-up truck	Other motor vehicle	
2022-Nov-16, Wed,06:33	Snow	Rear end	P.D. only	Loose snow	East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Pick-up truck	Other motor vehicle	
					East	Stopped	Municipal transit bus	Other motor vehicle	
2022-Nov-18, Fri,18:10	Clear	Rear end	P.D. only	Dry	East	Stopped	Automobile, station wagon	Other motor vehicle	0
					East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2022-Nov-19, Sat,15:40	Clear	Rear end	P.D. only	Wet	West	Stopped	Automobile, station wagon	Other motor vehicle	0
					West	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2022-Dec-07, Wed,18:30	Rain	Rear end	P.D. only	Wet	North	Slowing or stopping	Pick-up truck	Other motor vehicle	0
					North	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
2022-Dec-12, Mon,16:40	Clear	Turning movement	P.D. only	Loose snow	East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					East	Turning right	Automobile, station wagon	Other motor vehicle	
2022-Dec-13, Tue,06:35	Clear	Rear end	P.D. only	Dry	South	Stopped	Automobile, station wagon	Other motor vehicle	0
					South	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-Dec-19, Mon,17:30	Clear	Approaching	P.D. only	Other	South	Going ahead	Pick-up truck	Other motor vehicle	0
					North	Stopped	Automobile, station wagon	Other motor vehicle	
					East	Turning left	Automobile, station wagon	Other motor vehicle	
2022-Dec-20, Tue,05:30	Clear	Angle	P.D. only	Dry	South	Merging	Automobile, station wagon	Other motor vehicle	0
					West	Merging	Pick-up truck	Other motor vehicle	

Location: RICHMOND RD btwn BASELINE RD/HWY416 IC75A RAMP53 & HWY416 IC75A RAMP63

Traffic Control: No control

Total Collisions: 1

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
---------------	-------------	-------------	----------------	----------------	----------	-------------------	--------------	-------------	---------

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: RICHMOND RD btwn BASELINE RD/HWY416 IC75A RAMP53 & HWY416 IC75A RAMP63

Traffic Control: No control

Total Collisions: 1

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2020-Jan-20, Mon,14:30	Clear	Sideswipe	P.D. only	Slush	East	Merging	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Passenger van	Other motor vehicle	

Location: RICHMOND RD btwn CLIFTON RD & KIRKWOOD AVE

Traffic Control: No control

Total Collisions: 4

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Oct-29, Mon,12:17	Clear	Sideswipe	P.D. only	Dry	East	Pulling onto shoulder or toward curb	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Municipal transit bus	Other motor vehicle	
2019-May-04, Sat,09:52	Clear	Sideswipe	P.D. only	Dry	East	Pulling away from shoulder or curb	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Nov-05, Tue,17:05	Clear	Sideswipe	P.D. only	Dry	West	Changing lanes	Passenger van	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2020-Aug-20, Thu,16:40	Clear	Sideswipe	P.D. only	Dry	East	Pulling away from shoulder or curb	Pick-up truck	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	

Location: RICHMOND RD btwn HWY416 IC75A RAMP63 & JOHN SUTHERLAND DR

Traffic Control: No control

Total Collisions: 5

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Jan-17, Wed,23:12	Clear	SMV other	P.D. only	Wet	West	Going ahead	Automobile, station wagon	Pole (utility, power)	0
2018-Jan-20, Sat,18:03	Clear	Rear end	P.D. only	Dry	West	Turning right	Automobile, station wagon	Other motor vehicle	0
					West	Turning right	Automobile, station wagon	Other motor vehicle	
2019-May-18, Sat,18:37	Clear	Rear end	P.D. only	Dry	East	Merging	Passenger van	Other motor vehicle	0
					East	Merging	Automobile, station wagon	Other motor vehicle	

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: RICHMOND RD btwn HWY416 IC75A RAMP63 & JOHN SUTHERLAND DR

Traffic Control: No control

Total Collisions: 5

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2020-Jan-15, Wed,16:00	Snow	Other	P.D. only	Wet	West	Going ahead	Pick-up truck	Debris falling off vehicle	0
					West	Unknown	Unknown	Other	
2022-Nov-04, Fri,02:15	Clear	Rear end	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
					East	Unknown	Unknown	Other motor vehicle	

Location: RICHMOND RD btwn JOHN SUTHERLAND DR & HOLLY ACRES RD

Traffic Control: No control

Total Collisions: 7

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
2018-Sep-10, Mon,20:02	Rain	SMV other	P.D. only	Wet	West	Going ahead	Automobile, station wagon	Animal - wild	0
2019-Apr-02, Tue,07:15	Clear	Rear end	P.D. only	Dry	East	Changing lanes	Pick-up truck	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2019-Oct-08, Tue,07:56	Clear	Rear end	P.D. only	Dry	East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	0
					East	Stopped	Automobile, station wagon	Other motor vehicle	
2020-Jan-29, Wed,23:58	Clear	SMV other	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Skidding/sliding	0
2021-Nov-04, Thu,12:06	Clear	Rear end	P.D. only	Dry	West	Going ahead	Automobile, station wagon	Other motor vehicle	0
					West	Stopped	Automobile, station wagon	Other motor vehicle	
2022-Mar-08, Tue,06:06	Snow	SMV other	P.D. only	Packed snow	South	Going ahead	Automobile, station wagon	Pole (utility, power)	0
2022-Apr-28, Thu,15:00	Clear	Sideswipe	P.D. only	Dry	South	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					South	Going ahead	Unknown	Other motor vehicle	

Location: RICHMOND RD btwn KIRKWOOD AVE & HILSON AVE

Traffic Control: No control

Total Collisions: 3

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuvre	Vehicle type	First Event	No. Ped
---------------	-------------	-------------	----------------	----------------	----------	-------------------	--------------	-------------	---------

Transportation Services - Traffic Services

Collision Details Report - Public Version

From: January 1, 2018 **To:** December 31, 2022

Location: RICHMOND RD btwn KIRKWOOD AVE & HILSON AVE

Traffic Control: No control

Total Collisions: 3

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuver	Vehicle type	First Event	No. Ped
2018-Apr-19, Thu,10:06	Clear	Sideswipe	Non-fatal injury	Dry	West	Changing lanes	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2020-Feb-13, Thu,18:10	Clear	Angle	P.D. only	Wet	North	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Going ahead	Automobile, station wagon	Other motor vehicle	
2022-Feb-11, Fri,10:50	Clear	SMV unattended vehicle	P.D. only	Dry	East	Unknown	Unknown	Unattended vehicle	0

Location: RICHMOND RD btwn MCRAE AVE & CLIFTON RD

Traffic Control: No control

Total Collisions: 4

Date/Day/Time	Environment	Impact Type	Classification	Surface Cond'n	Veh. Dir	Vehicle Manoeuver	Vehicle type	First Event	No. Ped
2018-Mar-25, Sun,14:26	Clear	Rear end	P.D. only	Dry	East	Going ahead	Automobile, station wagon	Other motor vehicle	0
					East	Slowing or stopping	Automobile, station wagon	Other motor vehicle	
					East	Stopped	Automobile, station wagon	Other motor vehicle	
2019-May-16, Thu,19:44	Clear	Sideswipe	Non-fatal injury	Dry	East	Stopped	Automobile, station wagon	Cyclist	0
					East	Going ahead	Bicycle	Other motor vehicle	
2019-Aug-07, Wed,20:23	Clear	Angle	P.D. only	Dry	South	Turning left	Automobile, station wagon	Other motor vehicle	0
					West	Going ahead	Automobile, station wagon	Other motor vehicle	
2021-Oct-02, Sat,10:30	Rain	SMV other	P.D. only	Wet	South	Turning left	Pick-up truck	Fire Hydrant	0

Appendix G: Other Background Development Excerpts

42 NORTHSIDE ROAD TRANSPORTATION IMPACT ASSESSMENT

Forecasting and Strategy Report
26 January 2022

1.3 LOCATION TRIGGERS

	Yes	No
Does the development propose a new driveway to a boundary street that is designated as part of the City's Transit Priority, Rapid Transit or Spine Bicycle Networks?		x
Is the development in a Design Priority Area (DPA) or Transit-oriented Development (TOD) zone? *		x

*DPA and TOD are identified in the City of Ottawa Official Plan (DPA in Section 2.5.1 and Schedules A and B; TOD in Annex 6). See Chapter 4 for a list of City of Ottawa Planning and Engineering documents that support the completion of TIA).

If any of the above questions were answered with 'Yes,' the Location Trigger is satisfied.

1.4 SAFETY TRIGGERS

	Yes	No
Are posted speed limits on a boundary street 80 km/hr or greater?		x
Are there any horizontal/vertical curvatures on a boundary street limits sight lines at a proposed driveway?		x
Is the proposed driveway within the area of influence of an adjacent traffic signal or roundabout (i.e. within 300 m of intersection in rural conditions, or within 150 m of intersection in urban/ suburban conditions)?	✓	
Is the proposed driveway within auxiliary lanes of an intersection?		x
Does the proposed driveway make use of an existing median break that serves an existing site?		x
Is there a documented history of traffic operations or safety concerns on the boundary streets within 500 m of the development?		x
Does the development include a drive-thru facility?		x

If any of the above questions were answered with 'Yes,' the Safety Trigger is satisfied.

1.5 SUMMARY

	Yes	No
Does the development satisfy the Trip Generation Trigger?		x
Does the development satisfy the Location Trigger?		x
Does the development satisfy the Safety Trigger?	✓	


If none of the triggers are satisfied, the TIA Study is complete. If one or more of the triggers is satisfied, the TIA Study must continue into the next stage (Screening and Scoping).



42 NORTHSIDE ROAD TRANSPORTATION IMPACT ASSESSMENT

Forecasting and Strategy Report
26 January 2022

Figure 10 - Site Trips



1 Screening

This study has been prepared according to the City of Ottawa's 2017 Transportation Impact Assessment (TIA) Guidelines. Accordingly, a Step 1 Screening Form has been prepared and is included as Appendix A, along with the Certification Form for the TIA Study PM. As shown in the Screening Form, a TIA is required including the Design Review component and the Network Impact Component. This report is part of an Official Plan amendment/zoning by-law amendment.


2 Existing and Planned Conditions

2.1 Proposed Development

The existing site, zoned primarily as Business Park Industrial Zone (IP2 with minor portions as IP[1530], IPS)) and with minor portions of the site area zoned as Agricultural (AG), General Mixed Use (GM18 F(1.0) H(34)), and Arterial Mainstreet (AM) currently consists of a warehouse and industrial yard, and includes an electrical utility transmission corridor and decommissioned rail corridor. The proposed development includes eight high-rise buildings on six-storey podiums and one six-storey building comprising a total of 1,925 units and 41,657 ft² of commercial space, all to be built-out in five phases by 2029. The site is proposed as accessing Moodie Drive via a new east leg of the intersection with Timm Drive, and proposes 1,778 vehicle parking spaces. A MUP is also proposed along the eastern channel of the site connecting to the pedestrian facilities on Robertson Road.


Figure 1 illustrates the study area context. Figure 2 illustrates the proposed concept plan.

Figure 1: Area Context Plan



Source: <http://maps.ottawa.ca/geoOttawa/> Accessed: March 12, 2021

Figure 12: New and Pass-By Site Generation Auto Volumes



TIA Final Report

Parsons has been retained by Brigil to prepare a Transportation Impact Assessment (TIA) in support of a Zoning By-Law Amendment (ZBLA) and a Site Plan Application (SPA) for a residential development located at 2946 Baseline Road in Bayshore/Cedarview district. **The previous submission on May 30, 2023 focused on Phases/Towers 4, 5 and 6 as Phases/Towers 1, 2 and 3 were already approved. At this time, Tower 1 has been constructed and fully occupied, while Tower 2 is under construction. The previously approved Tower 3 is now being integrated with Tower 4 as part of a new vision for the development site. Therefore, the new development proposal will contain a total of five phases/towers, and this application is being provided in support of Phases 3-5. For the purpose of this report, “Phase 3-4” will be referred to as “Phase 4”.**

The following document has been prepared for three additional phases/towers, which follows the new TIA process, as outlined in the City Transportation Impact Assessment (TIA) Guidelines (2017). The following report represents Step 5 – TIA Final Report.

1. Screening Form

The screening form confirmed the need for a TIA Report based on the following:

- The Trip Generation trigger. Phases 4 to 5 consist of three mixed-use buildings with approximately 890 residential apartment units and 2,180 m² (23,480 ft²) of commercial space.
- The Location trigger has also been triggered, given that the development is located within a transit priority corridor and spine cycling route.
- The Safety trigger given that the proposed driveway is within the influence of an adjacent traffic signal at Sandcastle/Baseline.

The Screening Form and responses to City of Ottawa comments have been provided in **Appendix A**.

2. Scoping Report


2.1. Existing and Planned Conditions

2.1.1. PROPOSED DEVELOPMENT

The subject site is located at the municipal addresses of 2946 and 2940 Baseline Road on the southeast corner of the Sandcastle/Baseline intersection. The previous Phases 1-3 was approved under a separate development application, “2940 Baseline Road Community Transportation Study” by Delcan, submitted on October 21, 2011, and supported by an updated Memo TIA by Parsons submitted to the City on June 16, 2021. Since then, Phases 1 and 2 have been constructed, and the previous Phase 3 tower has been integrated within the current development proposal. Therefore, this TIA is being provided in support of Phases 4, 5 and 6 (note that Phase 3 has been incorporated into Phase 4).

The existing site has a small shopping plaza and surface parking which will be redeveloped to a high-density residential mixed used site. The proposed study area includes the intersections of Cedarview/Baseline, Valley Stream/Baseline, Sandcastle/Baseline, Monterey/Baseline, Morrison/Baseline, and roadway segments adjacent to site or between intersections as shown in **Figure 1**. More details regarding the study area can be found in **Section 2.1.2**.

Figure 10: Other Area Developments



1 – 2940 Baseline Road (Phase 1 and 2)

A TIA was prepared by Delcan and submitted on October 21, 2011 in support of three residential Phases within this greater development. **Phase 1 has been built and is occupied;** Phase 2 is almost complete its construction. **An on-site traffic count and vehicle trip generation associated with Phase 1 was conducted on June 20th, 2024. It was observed that approximately 32 and 24 vehicles two-way were generated by Phase 1 for the AM and PM peak hours.** It is forecasted that Phase 2 will generate approximately 35 and 26 new two-way vehicle trips based on proportionate development size compared to Phase 1, which will be added to background conditions.

2 – 2940 Baseline Road (Phase 3)

Phase 3 has since been redesigned and incorporated as part of this packaged submission. Formerly the greater site proposed 6 towers, which have now been reduced to 5 towers, with tower 3 and 4 becoming one. The Site Plans refer to this combined tower as Tower 3-4, but for the purpose of this report, it is being referred to as Phase 4.


3 – 2785 Baseline Road

The site envisions a mixture of residential, commercial, and medical land uses. The latest ZBLA according to the City's Development Application tool proposes 66 units in Building D, 80 units in Building E, 81 units and medical uses in Building F, which is an increase of approximately 31 units from the original proposal. A TIA from Castleglenn date June 18th, 2019 was found. The majority of the development has already been built. No further TIA's were found. For this TIA, the projected volumes from the Castleglenn TIA will be layered on to future background conditions.

4 – 1300 McWaters Road

Proposed 25-storey 235-unit residential development. The TIA by GHD Limited projects 36 two-way trips in the AM peak and 37 two-way trips in the PM peak. Although this development is located further than 1km away, for completeness, trips forecasted on Baseline Road will be layered on to future background conditions.

Figure 13: Site Generated Traffic Percent Distribution



3.1.4. TRIP ASSIGNMENT

The site, including Phases 1 through 6 will all share three accesses to the surrounding network. The three accesses include a RIRO to Baseline Road approximately 70m east of Sandcastle Drive and two full movement accesses to Sandcastle Drive located approximately 40m and 170m south of Baseline Road. The 'new' site-generated vehicle trips provided in **Table 11**, were assigned to the study area network as shown in **Figure 14**.

Figure 14: 'New' Site-Generated Traffic Phase 4-6





Figure 15: Other Area Development Background Volumes



3.3. Demand Rationalization

The following **Table 13** provides a summary of the existing traffic operations at the study area intersection based on the Synchro (V11) traffic analysis software. The subject intersections were assessed in terms of the volume-to-capacity (v/c) ratio and the corresponding Level of Service (LoS) for the critical movement(s). The Synchro model outputs of existing conditions are provided within **Appendix F** and the volumes used were obtained from **Figure 6**.

Table 13: Existing Intersection Performance

Intersection	Weekday AM Peak (PM Peak)					
	Critical Movement			Intersection		
	LoS	max. v/c or avg. delay (s)	Movement	Delay (s)	LoS	v/c
Cedarview/Baseline	B(B)	0.66(0.61)	NBL(NBL)	13.2(11.4)	A(A)	0.54(0.40)
Valley Stream/Baseline	A(A)	0.59(0.52)	EBT(SBT)	10.0(10.4)	A(A)	0.56(0.44)
Sandcastle/Baseline	B(A)	0.64(0.51)	EBT(NBL)	9.1(7.3)	B(A)	0.62(0.45)
Monterey/Baseline	A(A)	0.59(0.43)	EBT(WBT)	10.5(8.7)	A(A)	0.57(0.42)
Morrison/Baseline	A(B)	0.54(0.61)	EBT(SBL)	6.8(11.0)	A(A)	0.53(0.52)

Note: Analysis of signalized intersections assumes a PHF of 0.9 and a saturation flow rate of 1800 veh/h/lane. U = Unsignalized.

As seen in **Table 13** all intersections operate overall at very good LoS 'B' or better with critical movements operating at LoS 'B' or better during the existing conditions. The Synchro analysis confirms that the overall network is expected to operate well, with ample capacity remaining.

Although a 1% annual growth rate is proposed for future horizon years based on historical traffic counts, it is anticipated to gradually taper as city wide initiatives aimed at reducing auto-usage take place. Some of the more relevant initiatives for this study area include the Baseline BRT corridor which would provide improved transit connectivity from the site to Baseline Station on Woodroffe Road. Baseline Station, along with nearby Bayshore Station will both become LRT stations as part of the Stage 2 LRT expansion which will add 44kms of new rail and 24 new LRT stations by 2026.

Given the city-wide initiatives to promote alternate modes of transportation, including advancements to the greater transit network such as LRT Stage 2 and the transit network adjacent to the site with the Baseline BRT

TIA Screening and Scoping Report

1. SCREENING FORM

The Screening Form, in conjunction with the Scoping Report for the subject development, was submitted to the City of Ottawa staff for review and confirmation of the need for a Transportation Impact Assessment (TIA). Trip Generation triggers were met based on the type and size of the development. The Location triggers were met based on the site's location in the Robertson Arterial Mainstreet Design Priority Area (DPA) and fronting a designated Cycling Spine Route. The Safety trigger was met based on the proposed drive through facility and also on the site's proposed driveway location, which is within close proximity to Robertson/Fitzgerald signalized intersection. The Screening Form is provided as Appendix A.

2. SCOPING REPORT

2.1. EXISTING AND PLANNED CONDITIONS

2.1.1. PROPOSED DEVELOPMENT


Based on the Site Plan provided by Lawrence Architect Incorporated, it is our understanding that the proponent is proposing a retail/warehouse complex at the rear of the site with drive-thru restaurant at the front of the site located at 2165 Robertson Road. The expected date of occupancy is 2019. The proposed single-phase development will consist of a 1,092 m² of Warehouse (ITE 150), a 232 m² of Fast-Food Restaurant with drive-thru (ITE 934) and 74 surface parking spaces. Of these spaces, 39 are for the warehouse and 35 are for the restaurant. . Access to the site is proposed via two one-way driveways on Robertson Road. The restaurant building has been located forward on the site with the parking and drive through at the rear of the building. The site is currently occupied by warehousing and parking, which has one 8.0m wide two-way driveway connection to Robertson Road. It is zoned as AM – Arterial Mainstreet Zone. The local context of the site is provided as Figure 1 and the proposed Site Plan is provided as Figure 2.

Figure 1: Local Context



and 175m west of Fitzgerald Road, respectively. Given these driveway configurations, 'new' and 'pass-by' site-generated vehicle trips are assigned to the study area network and illustrated as Figure 8.

Figure 8: 'New', 'Pass-by' and Multi-Purpose Site-Generated Traffic



3.2. BACKGROUND NETWORK TRAVEL DEMANDS

3.2.1. TRANSPORTATION NETWORK PLANS

Refer to section 2.1.3 Planned Conditions – Planned Study Area Transportation Network Changes.

3.2.2. BACKGROUND GROWTH

According to the City of Ottawa intersection traffic growth rates, background growth at the Robertson/Moodie signalized intersection has ranged between 0.2% to 2% per annum. To be conservative and considering ongoing development at Stittsville and Kanata South, a 2% per annum background growth on Robertson Road will be used. To account for the traffic generated by the previously identified area developments, the corresponding volumes have been added to the study area intersections as per corresponding traffic studies or existing intersection vehicle movement proportions. Other area development-generated traffic is included in Appendix E. The resultant 2019 and 2024 background traffic volumes are depicted as Figure 9 and Figure 10 respectively.

Figure 9: 2019 Background Traffic Volumes




Figure 2: Current Proposed Building A

Within the original 2018 Traffic Impact Study for the whole site estimated a two-way total peak hour traffic generation of approximately 95 veh/h during weekday morning, 90 veh/h during weekday afternoon, and 110 during Saturday peak hours, excluding pass-by reductions. With regard to the previous Buildings A, it's 2,500 ft² drive-through restaurant, was estimated to generate two-way traffic of approximately 80 veh/h during the weekday morning, 65 during the weekday evening and 110 veh/h during the Saturday peak hours, excluding pass-by reductions. These volumes comprised, on average, approximately 80% of the overall site's total vehicular traffic generation for morning, afternoon and Saturday peaks.

The current Site Plan modifications reduces the drive through by ~(-)520 ft² and adds ~4,040 ft² of Fast Casual Restaurant. The following Table 1, Table 2, and Table 3 summarize the peak hour traffic generation comparisons between the Building A's new floor area plus added land uses, and includes the estimated net difference. As shown in Table 3, the estimated net difference in two-way traffic flow is a decrease of approximately 15 veh/h during the morning peak hour, an increase of approximately 30 veh/h during the afternoon peak hour and an increase of 85 veh/h during the Saturday peak hour. These additional volumes equate to approximately one more vehicle entering/leaving the site every 45 seconds during the Saturday peak hour, and for less frequently during the weekday peak hours.

Land Use	Data Source	Area (ft²)	AM Peak (Person Trips/hr)			PM Peak (Person Trips/hr)			SAT Peak (Person Trips/hr)		
			In	Out	Total	In	Out	Total	In	Out	Total
Drive-through (Fast-Food) ₁	934	2,500	39	39	78	33	31	64	54	53	107
Updated Drive-through (Fast-Food) ₂	934	0	0	0	0	0	0	0	0	0	0
Fast Casual Restaurant ₂	930	0	0	0	0	0	0	0	0	0	0
Total Vehicle Trips			39	39	78	33	31	64	54	53	107


- 1.) Accounts for Drive-through (fast food) in the original TIA
- 2.) Accounts for the updated Site Plan's Fast-Food Restaurant
- 3.) Accounts for the updated Site Plan that includes Fast Casual Restaurant (Note that this type of restaurant is closed weekday morning peak hours and that the Saturday ITE study sample study size is small for the Saturday Peak Hour of Generator rates).

The updated total site generated traffic volumes including pass-by trips and the multi-purpose trip reduction is summarized in Table 4 and the subsequent network distribution is displayed in Figure 4.

Table 4: Updated Total Site Vehicle Trip Generation

Land Use	AM Peak (veh/h)			PM Peak (veh/h)			SAT Peak (veh/h)		
	In	Out	Total	In	Out	Total	In	Out	Total
Fast-Food w/Drive-Through Trip Generation	32	30	62	26	24	50	42	42	84
Fast Casual Restaurant Trip Generation	0	0	0	24	21	45	59	49	108
Retail/Warehousing Trip Generation	16	6	22	6	17	23	0	1	1
Fast-Food w/ Drive-Through Pass-by (50%)	-16	-16	-32	-13	-13	-26	-21	-21	-42
Fast Casual Restaurant Pass-by (50%)	0	0	0	-11	-11	-22	-27	-27	-54
Retail/Warehousing Pass-by (0%)	0	0	0	0	0	0	0	0	0
Multi-purpose Trips (10%)	-3	-2	-5	-3	-4	-7	-6	-4	-10
Total 'New' Auto Trips	29	18	47	29	34	63	47	40	87

Figure 4: 'New', 'Pass-by' and Multi-Purpose Site-Generated Traffic



As displayed in Figure 4, each of projected turning movements are approximately 60 veh/h or less during the peak hours, which on averages equates to 1 vehicle every minute. The site provides ~45m of throat length, ~90m of internal drive-through queueing space, and that there is a shared center right-turn/left-turn lane on Robertson Road for eastbound left turning vehicles to wait for breaks in oncoming traffic to enter. As described within the foregoing, the impacts of the increase in traffic volumes produced by the additional restaurant floor area when compared to the original TIA, are anticipated to be minor.

1.0 SCREENING

1.1 Introduction

This Transportation Impact Assessment (TIA) has been prepared in support of a Site Plan Control application for the property located at 1826 Robertson Road. The site is currently occupied by a shopping centre (referred to as 'Lynwood Centre').

The subject site is surrounded by the following:

- Robertson Road and Northside Road, followed by a shopping centre to the north;
- A retirement residence, followed by Eaton Street to the south;
- Larkspur Drive, followed by commercial and residential uses to the east;
- Lynhar Road, Virgil Road, and Ellery Crescent, followed by commercial and residential uses to the west.

A view of the subject site is provided in **Figure 1**.

1.2 Proposed Development

The proposed development is a single-storey retail pad, and will include 2,370 ft² (220 m²) gross floor area (GFA) of drive-through restaurant space and 6,135 ft² (570 m²) GFA of retail space at the northwest corner of the subject site. No changes to the existing Lynwood Centre building or its accesses are proposed. At full buildout, a total of 208 parking spaces will be provided on the entire site. Access to the proposed development will be provided via the existing Lynwood Centre accesses to Lynhar Road and Larkspur Drive. It is anticipated that the development will be constructed in a single phase, with full occupancy in 2024.

The proposed development is located within the Outer Urban Transect, and is designated as 'Corridor – Mainstreet' (Robertson Road) in Schedule B3 of the City of Ottawa's Official Plan. The existing zoning for the subject site is 'Arterial Mainstreet' (AM). The proposed drive-through restaurant and retail uses are permitted under the existing AM zoning.

A copy of the site plan is included in **Appendix A**.

1.3 Screening

The City's *2023 Revised TIA Guidelines* identify three triggers for completing a TIA report, including trip generation, location, and safety. The criteria for each trigger are outlined in the City's TIA Screening Form (included in **Appendix B**). The trigger results are as follows:

- Trip Generation Trigger – The development is anticipated to generate over 60 peak hour person trips; further assessment is **required** based on this trigger.
- Location Triggers – The development is located within a Design Priority Area; further assessment is **required** based on this trigger.
- Safety Triggers – The proposed development includes a drive-through facility; further assessment is **required** based on this trigger.

Figure 10: Net Additional Site-Generated Primary Traffic





Figure 11: Net Additional Site-Generated Pass-By Traffic



Appendix H: BRBRT EAS Excerpts

1.3 STUDY OVERVIEW

The BRBRT corridor is a component of the City of Ottawa's planned Rapid Transit Network, as identified and supported by the policies and objectives of the City's Transportation Master Plan (TMP) and Official Plan (OP). Based on these documents, the City of Ottawa initiated a Planning and Environmental Assessment Study to develop and evaluate alternative designs and to assess the impacts of transit infrastructure required to support implementation of this facility.

The study area boundary for the BRBRT study encompasses the Baseline-Heron Road corridor between Richmond Road in the west and Data Centre Road in the east. Initially the study only extended to Prince of Wales Drive in the east, but was extended in 2014 to include section of Heron Road to Data Centre Road providing a connection to the Southeast Transitway at Heron Station. Further in the west, the study area boundary extends north from the Baseline Road/Richmond Road intersection to north of Highway 417 to provide for a connection to Bayshore Station. Figure 1-3 highlights the study area.

The study will ultimately recommend and assess a preferred alignment and design for transit infrastructure between Bayshore Station and Data Centre Road. Within the study area, a range of alternative corridor alignments and designs will be examined, including on-street bus lanes (e.g. median or curbside) and transit priority measures. To ensure that all options are being considered, the study area also includes additional area around Bayshore Station and the Baseline Road/Richmond Road intersection in the west and Baseline Station/Centrepointe Town Centre/Algonquin College in the central part of the study area.

Some tasks will require examination of a broader area beyond the study area boundaries to address environmental impacts, operational issues (transit and other modes), co-ordinate with other on-going studies and projects, and to study possible future network connections.

Figure 1-3: Overview of Baseline Road Rapid Transit Corridor Study Area




Analysis of peak load points also reflected the greater volumes of traffic towards the eastern end of the study area on Baseline Road. In the weekday morning peak hour, the peak load points were located at Lexington Street in the eastbound direction (~380 passengers), and at Clyde Avenue (~440 passengers) in the westbound direction. In the weekday afternoon peak hour, the peak load points were located at Pender St. in the eastbound direction (~370 passengers), and at Prince of Wales Dr. (~360 passengers) in the westbound direction. In comparison, passenger volumes between Valley Stream Drive and Sioux Crescent, in the western end of the study area, was in the range of 120-230 passengers per direction during the peak hours. All-day passenger volumes on Baseline Road are displayed in Table 2-3, by screenlines.

Table 2-3: Baseline Road Passenger Volume by (Screenline (OC Transpo, April/May 2012): Baseline Road Passenger

Screenline Description		Screenline #		AM Peak Hour		PM Peak Hour		24 Hour Total		
<i>Eastbound</i>	<i>Westbound</i>	<i>EB</i>	<i>WB</i>	<i>EB</i>	<i>WB</i>	<i>EB</i>	<i>WB</i>	<i>EB</i>	<i>WB</i>	<i>Total</i>
Valley Stream Dr.	Sioux Cres.	SL09	SL16	173	153	123	232	1738	1737	3475
Sandcastle Dr.	Monterey Dr.	SL10	SL17	194	163	178	299	1974	2039	4013
Cobden Rd.	Cobden Rd.	SL11	SL18	305	168	210	312	2445	2360	4805
Deerfield Dr.	Cordova St.	SL12	SL19	296	435	365	350	3256	3165	6421
Pender St.	Clyde Ave.	SL13	SL20	318	437	370	348	3372	3267	6639
Farlane Blvd.	Zena St.	SL14	SL21	356	405	342	351	3330	3232	6562
Lexington St.	Prince of Wales	SL15	SL22	380	423	353	357	3442	3183	6625

Figure 3-1: Baseline Road Rapid Transit Corridor Study Area



Appendix I: Long Range Model Snapshots

TRANS Regional Model



Version 1.01 - Assigned December 09, 2024

AM Peak Hour Total Traffic Volume
Queensway Carleton Hospital
2022 Model

User Initials: AJ
Plot Prepared: April 04, 2025
EMME Scenario: 22002



Legend



The TRANS model is continuously refined & maintained, and all information is provided in good faith. However, model outputs are provided "as is", and no warranty or guarantee is provided as to the accuracy, reliability or reasonableness of the results. In using this data, you agree to accept any and all risks arising from any incorrect, incomplete, or misleading information.

Recipients are required to use caution and professional judgement in using and interpreting model outputs. In particular, caution should be used when focusing on a geographically limited area (such as a single road or intersection), as the model is primarily designed to simulate regional-scale phenomena and has been calibrated at a regional level.

As general good practice, it is recommended that the user confirm the network coding within the area of interest, and compare base year forecasts against traffic count data to assess the extent to which the model may be over- or under-estimating the travel demand.

TRANS Regional Model

Version 1.01 - Assigned December 09, 2024

AM Peak Hour Total Traffic Volume

Prince of Wales Drive

2046 Model


User Initials: AJ

Plot Prepared: April 04, 2025


EMME Scenario: 46001

Legend

AM Peak Hour Total Traffic Volume



Distance (m)


























The TRANS model is continuously refined & maintained, and all information is provided in good faith. However, model outputs are provided "as is", and no warranty or guarantee is provided as to the accuracy, reliability or reasonableness of the results. In using this data, you agree to accept any and all risks arising from any incorrect, incomplete, or misleading information.

Recipients are required to use caution and professional judgement in using and interpreting model outputs. In particular, caution should be used when focusing on a geographically limited area (such as a single road or intersection), as the model is primarily designed to simulate regional-scale phenomena and has been calibrated at a regional level.













As general good practice, it is recommended that the user confirm the network coding within the area of interest, and compare base year forecasts against traffic count data to assess the extent to which the model may be over- or under-estimating the travel demand.

Appendix J: Synchro Analysis Reports for Existing Conditions

Richmond Rd/Holly Acres Rd/Nanaimo Dr
Existing AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	515	8	374	21	37	91	147	829	22	26	385	17
Future Volume (vph)	515	8	374	21	37	91	147	829	22	26	385	17
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		34.0	17.0		0.0	25.0		0.0	143.0		100.0
Storage Lanes	2		1	1		1	1		0	1		1
Taper Length (m)	2.5			24.0			100.0			40.0		
Lane Util. Factor	0.97	1.00	1.00	1.00	1.00	1.00	1.00	0.95	0.95	1.00	0.95	1.00
Ped Bike Factor			0.97		0.99	0.98	1.00	1.00				0.98
Frt			0.850			0.850		0.996				0.850
Flt Protected	0.950				0.982		0.950			0.950		
Satd. Flow (prot)	3195	1784	1473	0	1734	1517	1572	3375	0	1544	3357	943
Flt Permitted	0.950				0.982		0.379			0.197		
Satd. Flow (perm)	3195	1784	1431	0	1724	1487	626	3375	0	320	3357	929
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			416			158		2				162
Link Speed (k/h)		60			40			60			60	
Link Distance (m)		86.1			158.8			660.2			233.5	
Travel Time (s)		5.2			14.3			39.6			14.0	
Confl. Peds. (#/hr)			11	11			2		1	1		2
Confl. Bikes (#/hr)			1			4						1
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	5%	2%	5%	5%	2%	2%	10%	2%	2%	12%	3%	64%
Adj. Flow (vph)	572	9	416	23	41	101	163	921	24	29	428	19
Shared Lane Traffic (%)												
Lane Group Flow (vph)	572	9	416	0	64	101	163	945	0	29	428	19
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	1
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	2.0	10.0	2.0	2.0	10.0	2.0	2.0	10.0		2.0	10.0	2.0
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	2.0	0.6	2.0	2.0	0.6	2.0	2.0	0.6		2.0	0.6	2.0
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		9.4			9.4			9.4			9.4	
Detector 2 Size(m)		0.6			0.6			0.6			0.6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Richmond Rd/Holly Acres Rd/Nanaimo Dr
Existing AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Split	NA	Perm	Split	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	4	4		3	3		5	2		1	6	
Permitted Phases			4			3	2			6		6
Detector Phase	4	4	4	3	3	3	5	2		1	6	6
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	5.0	10.0		5.0	10.0	10.0
Minimum Split (s)	28.6	28.6	28.6	16.7	16.7	16.7	11.0	30.3		11.0	30.3	30.3
Total Split (s)	45.0	45.0	45.0	20.0	20.0	20.0	12.0	33.0		12.0	33.0	33.0
Total Split (%)	40.9%	40.9%	40.9%	18.2%	18.2%	18.2%	10.9%	30.0%		10.9%	30.0%	30.0%
Yellow Time (s)	3.7	3.7	3.7	3.0	3.0	3.0	3.7	3.7		3.7	3.7	3.7
All-Red Time (s)	2.9	2.9	2.9	3.7	3.7	3.7	2.3	2.6		2.3	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.6	6.6	6.6		6.7	6.7	6.0	6.3		6.0	6.3	6.3
Lead/Lag	Lag	Lag	Lag	Lead	Lead	Lead	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None	None	None	C-Max		None	C-Max	C-Max
Act Effct Green (s)	26.4	26.4	26.4		10.8	10.8	52.8	45.2		43.0	36.0	36.0
Actuated g/C Ratio	0.24	0.24	0.24		0.10	0.10	0.48	0.41		0.39	0.33	0.33
v/c Ratio	0.75	0.02	0.63		0.38	0.35	0.41	0.68		0.15	0.39	0.05
Control Delay	44.7	28.9	7.7		52.9	4.8	21.5	32.5		19.7	31.7	0.2
Queue Delay	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	44.7	28.9	7.7		52.9	4.8	21.5	32.5		19.7	31.7	0.2
LOS	D	C	A		D	A	C	C		B	C	A
Approach Delay		29.1			23.5			30.9			29.7	
Approach LOS		C			C			C			C	
Queue Length 50th (m)	53.9	1.4	0.0		12.2	0.0	17.7	84.3		2.9	34.4	0.0
Queue Length 95th (m)	65.5	4.6	21.3		23.8	3.2	35.3	#143.1		8.8	53.3	0.0
Internal Link Dist (m)		62.1			134.8			636.2			209.5	
Turn Bay Length (m)			34.0				25.0			143.0		100.0
Base Capacity (vph)	1115	622	770		209	318	397	1387		201	1098	413
Starvation Cap Reductn	0	0	0		0	0	0	0		0	0	0
Spillback Cap Reductn	0	0	0		0	0	0	0		0	0	0
Storage Cap Reductn	0	0	0		0	0	0	0		0	0	0
Reduced v/c Ratio	0.51	0.01	0.54		0.31	0.32	0.41	0.68		0.14	0.39	0.05

Intersection Summary

Area Type: Other

Cycle Length: 110

Actuated Cycle Length: 110

Offset: 49 (45%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.75

Intersection Signal Delay: 29.6

Intersection LOS: C

Intersection Capacity Utilization 70.2%

ICU Level of Service C


Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.
























Queue shown is maximum after two cycles.

Richmond Rd/Holly Acres Rd/Nanaimo Dr
Existing AM Peak













Splits and Phases: 22: Richmond Road & Holly Acres Road/Nanaimo Drive



Richmond Rd/Holly Acres Rd/Nanaimo Dr
Existing PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	485	50	325	37	71	52	244	776	33	27	729	22
Future Volume (vph)	485	50	325	37	71	52	244	776	33	27	729	22
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		34.0	17.0		0.0	25.0		0.0	143.0		100.0
Storage Lanes	2		1	1		1	1		0	1		1
Taper Length (m)	2.5			24.0			100.0			40.0		
Lane Util. Factor	0.97	1.00	1.00	1.00	1.00	1.00	1.00	0.95	0.95	1.00	0.95	1.00
Ped Bike Factor			0.96		0.99	0.98	1.00	1.00				0.97
Frt			0.850			0.850		0.994				0.850
Flt Protected	0.950				0.983		0.950			0.950		
Satd. Flow (prot)	3257	1784	1473	0	1748	1517	1631	3365	0	1662	3357	1097
Flt Permitted	0.950				0.983		0.199			0.253		
Satd. Flow (perm)	3257	1784	1415	0	1736	1484	340	3365	0	443	3357	1063
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			331			158			4			162
Link Speed (k/h)		60			40			60			50	
Link Distance (m)		86.1			158.8			660.2			233.5	
Travel Time (s)		5.2			14.3			39.6			16.8	
Confl. Peds. (#/hr)			15	15			13					13
Confl. Bikes (#/hr)			5			4			4			2
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	3%	2%	5%	3%	2%	2%	6%	2%	3%	4%	3%	41%
Adj. Flow (vph)	539	56	361	41	79	58	271	862	37	30	810	24
Shared Lane Traffic (%)												
Lane Group Flow (vph)	539	56	361	0	120	58	271	899	0	30	810	24
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	97		97	97		97	97		97	97		97
Number of Detectors	1	2	1	1	2	1	1	2		1	2	1
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	2.0	10.0	2.0	2.0	10.0	2.0	2.0	10.0		2.0	10.0	2.0
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	2.0	0.6	2.0	2.0	0.6	2.0	2.0	0.6		2.0	0.6	2.0
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		9.4			9.4			9.4			9.4	
Detector 2 Size(m)		0.6			0.6			0.6			0.6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Richmond Rd/Holly Acres Rd/Nanaimo Dr
Existing PM Peak





















												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Split	NA	Perm	Split	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	4	4		3	3		5	2		1	6	
Permitted Phases			4			3	2			6		6
Detector Phase	4	4	4	3	3	3	5	2		1	6	6
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	5.0	10.0		5.0	10.0	10.0
Minimum Split (s)	28.6	28.6	28.6	16.7	16.7	16.7	11.0	30.3		11.0	30.3	30.3
Total Split (s)	29.0	29.0	29.0	17.0	17.0	17.0	17.0	47.0		17.0	47.0	47.0
Total Split (%)	26.4%	26.4%	26.4%	15.5%	15.5%	15.5%	15.5%	42.7%		15.5%	42.7%	42.7%
Yellow Time (s)	3.7	3.7	3.7	3.0	3.0	3.0	3.7	3.7		3.7	3.7	3.7
All-Red Time (s)	2.9	2.9	2.9	3.7	3.7	3.7	2.3	2.6		2.3	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.6	6.6	6.6		6.7	6.7	6.0	6.3		6.0	6.3	6.3
Lead/Lag	Lag	Lag	Lag	Lead	Lead	Lead	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None	None	None	Max		None	Max	Max
Act Effct Green (s)	21.3	21.3	21.3		10.2	10.2	56.8	50.0		47.5	40.7	40.7
Actuated g/C Ratio	0.20	0.20	0.20		0.09	0.09	0.52	0.46		0.44	0.37	0.37
v/c Ratio	0.85	0.16	0.66		0.73	0.21	0.88	0.58		0.11	0.65	0.05
Control Delay	55.6	37.5	12.6		74.3	1.6	47.0	25.0		14.0	31.3	0.2
Queue Delay	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	55.6	37.5	12.6		74.3	1.6	47.0	25.0		14.0	31.3	0.2
LOS	E	D	B		E	A	D	C		B	C	A
Approach Delay		38.3			50.6			30.1			29.8	
Approach LOS		D			D			C			C	
Queue Length 50th (m)	52.8	9.2	4.9		23.5	0.0	29.1	73.3		2.7	69.2	0.0
Queue Length 95th (m)	#74.2	19.2	31.7		#49.1	0.0	#67.4	95.1		6.9	88.4	0.0
Internal Link Dist (m)		62.1			134.8			636.2			209.5	
Turn Bay Length (m)			34.0				25.0			143.0		100.0
Base Capacity (vph)	670	367	553		165	283	308	1547		335	1255	499
Starvation Cap Reductn	0	0	0		0	0	0	0		0	0	0
Spillback Cap Reductn	0	0	0		0	0	0	0		0	0	0
Storage Cap Reductn	0	0	0		0	0	0	0		0	0	0
Reduced v/c Ratio	0.80	0.15	0.65		0.73	0.20	0.88	0.58		0.09	0.65	0.05
Intersection Summary												
Area Type: Other												
Cycle Length: 110												
Actuated Cycle Length: 108.9												
Natural Cycle: 90												
Control Type: Semi Act-Uncoord												
Maximum v/c Ratio: 0.88												
Intersection Signal Delay: 33.6						Intersection LOS: C						
Intersection Capacity Utilization 72.6%						ICU Level of Service C						
Analysis Period (min) 15												
# 95th percentile volume exceeds capacity, queue may be longer.												
Queue shown is maximum after two cycles.												

Richmond Rd/Holly Acres Rd/Nanaimo Dr
Existing PM Peak













Splits and Phases: 22: Richmond Road & Holly Acres Road/Nanaimo Drive

 Ø1	 Ø2	 Ø3	 Ø4
17 s	47 s	17 s	29 s
 Ø5	 Ø6		
17 s	47 s		


Richmond Rd/John Sutherland Dr
Existing AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	51	0	80	0	861	88	242	517	0
Future Volume (vph)	0	0	0	51	0	80	0	861	88	242	517	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	0		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Frt					0.918				0.850			
Flt Protected					0.981					0.950		
Satd. Flow (prot)	0	1784	0	0	1579	0	1784	3390	1517	1679	3390	0
Flt Permitted					0.872					0.286		
Satd. Flow (perm)	0	1784	0	0	1403	0	1784	3390	1517	505	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					82				95			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			660.2	
Travel Time (s)		7.0			8.7			16.2			29.7	
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	2%	2%	2%	2%	2%	5%	2%	2%	2%	3%	2%	2%
Adj. Flow (vph)	0	0	0	57	0	89	0	957	98	269	574	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	146	0	0	957	98	269	574	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		0.0			0.0			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type				Perm	NA		Perm	NA	Perm	Perm	NA	
Protected Phases		4			8			2			6	





















Richmond Rd/John Sutherland Dr
Existing AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	6	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	10.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	29.4	29.4	
Total Split (s)	38.0	38.0		38.0	38.0		62.0	62.0	62.0	62.0	62.0	
Total Split (%)	38.0%	38.0%		38.0%	38.0%		62.0%	62.0%	62.0%	62.0%	62.0%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0			0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6			6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	C-Max	C-Max	
Act Effct Green (s)					12.0		75.0	75.0	75.0	75.0	75.0	
Actuated g/C Ratio					0.12		0.75	0.75	0.75	0.75	0.75	
v/c Ratio					0.61		0.38	0.08	0.71	0.23		
Control Delay					30.3		1.3	0.2	21.1	4.3		
Queue Delay					0.0		0.0	0.0	0.0	0.0		
Total Delay					30.3		1.3	0.2	21.1	4.3		
LOS					C		A	A	C	A		
Approach Delay					30.3		1.2			9.6		
Approach LOS					C		A			A		
Queue Length 50th (m)					10.9		2.7	0.0	19.2	12.1		
Queue Length 95th (m)					27.2		9.8	0.1	#78.9	22.8		
Internal Link Dist (m)		73.1			97.2		335.3			636.2		
Turn Bay Length (m)								35.0	40.0			
Base Capacity (vph)					496		2542	1161	378	2542		
Starvation Cap Reductn					0		0	0	0	0		
Spillback Cap Reductn					0		0	0	0	0		
Storage Cap Reductn					0		0	0	0	0		
Reduced v/c Ratio					0.29		0.38	0.08	0.71	0.23		
Intersection Summary												
Area Type:	Other											
Cycle Length: 100												
Actuated Cycle Length: 100												
Offset: 92 (92%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green												
Natural Cycle: 110												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.71												
Intersection Signal Delay: 6.7							Intersection LOS: A					
Intersection Capacity Utilization 63.8%							ICU Level of Service B					
Analysis Period (min) 15												
# 95th percentile volume exceeds capacity, queue may be longer.												
Queue shown is maximum after two cycles.												













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/John Sutherland Dr
Existing PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	137	0	224	4	703	27	79	864	0
Future Volume (vph)	0	0	0	137	0	224	4	703	27	79	864	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	0		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Ped Bike Factor							1.00		0.98	1.00		
Frt					0.916				0.850			
Flt Protected					0.981		0.950			0.950		
Satd. Flow (prot)	0	1784	0	0	1594	0	1695	3390	1517	1647	3390	0
Flt Permitted					0.875		0.256			0.325		
Satd. Flow (perm)	0	1784	0	0	1421	0	456	3390	1482	563	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					67				33			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			660.2	
Travel Time (s)		7.0			8.7			16.2			29.7	
Confl. Peds. (#/hr)							2		1	1		2
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	2%	2%	2%	2%	2%	3%	2%	2%	2%	5%	2%	2%
Adj. Flow (vph)	0	0	0	152	0	249	4	781	30	88	960	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	401	0	4	781	30	88	960	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		0.0			0.0			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	

Richmond Rd/John Sutherland Dr
Existing PM Peak











												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Turn Type				Perm	NA		Perm	NA	Perm	Perm	NA	
Protected Phases		4			8			2			6	
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	6	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	10.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	29.4	29.4	
Total Split (s)	38.0	38.0		38.0	38.0		82.0	82.0	82.0	82.0	82.0	
Total Split (%)	31.7%	31.7%		31.7%	31.7%		68.3%	68.3%	68.3%	68.3%	68.3%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0			0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6			6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	C-Max	C-Max	
Act Effct Green (s)					30.8		76.2	76.2	76.2	76.2	76.2	
Actuated g/C Ratio					0.26		0.64	0.64	0.64	0.64	0.64	
v/c Ratio					0.97		0.01	0.36	0.03	0.25	0.45	
Control Delay					74.1		6.0	6.0	0.9	11.9	12.1	
Queue Delay					0.0		0.0	0.0	0.0	0.0	0.0	
Total Delay					74.1		6.0	6.0	0.9	11.9	12.1	
LOS					E		A	A	A	B	B	
Approach Delay					74.1			5.8			12.0	
Approach LOS					E			A			B	
Queue Length 50th (m)					73.7		0.1	14.9	0.0	7.8	52.6	
Queue Length 95th (m)					#130.2		m0.5	23.7	0.3	16.1	65.3	
Internal Link Dist (m)		73.1			97.2			335.3			636.2	
Turn Bay Length (m)							40.0		35.0	40.0		
Base Capacity (vph)					421		289	2152	952	357	2152	
Starvation Cap Reductn					0		0	0	0	0	0	
Spillback Cap Reductn					0		0	0	0	0	0	
Storage Cap Reductn					0		0	0	0	0	0	
Reduced v/c Ratio					0.95		0.01	0.36	0.03	0.25	0.45	
Intersection Summary												
Area Type:	Other											
Cycle Length: 120												
Actuated Cycle Length: 120												
Offset: 82 (68%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.97												
Intersection Signal Delay: 20.8							Intersection LOS: C					
Intersection Capacity Utilization 72.3%							ICU Level of Service C					
Analysis Period (min) 15												
# 95th percentile volume exceeds capacity, queue may be longer.												
Queue shown is maximum after two cycles.												
m Volume for 95th percentile queue is metered by upstream signal.												

Richmond Rd/John Sutherland Dr
Existing PM Peak













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/Robertson Rd/Baseline Rd
Existing AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	324	21	153	12	808	628	165	305	66
Future Volume (vph)	0	0	0	324	21	153	12	808	628	165	305	66
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	250.0		60.0	45.0		100.0	80.0		125.0
Storage Lanes	0		0	1		1	1		1	2		1
Taper Length (m)	7.6			50.0			75.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	0.95	1.00	0.97	0.95	1.00
Frt						0.850			0.850			0.850
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	0	0	3225	1784	1473	1601	3390	1488	3195	3357	1502
Flt Permitted				0.950			0.950			0.950		
Satd. Flow (perm)	0	0	0	3225	1784	1473	1601	3390	1488	3195	3357	1502
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)						170			698			113
Link Speed (k/h)		70			70			80			80	
Link Distance (m)		130.4			357.2			405.5			359.3	
Travel Time (s)		6.7			18.4			18.2			16.2	
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	2%	2%	2%	4%	2%	5%	8%	2%	4%	5%	3%	3%
Adj. Flow (vph)	0	0	0	360	23	170	13	898	698	183	339	73
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	360	23	170	13	898	698	183	339	73
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors				1	2	1	1	2	1	1	2	1
Detector Template				Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Leading Detector (m)				6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5	6.1
Trailing Detector (m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)				6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8	6.1
Detector 1 Type				Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)					28.7			28.7			28.7	
Detector 2 Size(m)					1.8			1.8			1.8	
Detector 2 Type					Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)					0.0			0.0			0.0	
Turn Type				Perm	NA	Perm	Prot	NA	Perm	Prot	NA	Perm
Protected Phases					8		5	2		1	6	

Richmond Rd/Robertson Rd/Baseline Rd
Existing AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases				8		8			2			6
Detector Phase				8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)				10.0	10.0	10.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)				36.8	36.8	36.8	11.6	30.6	30.6	11.6	30.6	30.6
Total Split (s)				37.0	37.0	37.0	19.0	44.0	44.0	19.0	44.0	44.0
Total Split (%)				37.0%	37.0%	37.0%	19.0%	44.0%	44.0%	19.0%	44.0%	44.0%
Yellow Time (s)				4.2	4.2	4.2	4.6	4.6	4.6	4.6	4.6	4.6
All-Red Time (s)				2.6	2.6	2.6	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)				6.8	6.8	6.8	6.6	6.6	6.6	6.6	6.6	6.6
Lead/Lag							Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode				None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effect Green (s)				17.2	17.2	17.2	6.4	51.8	51.8	11.0	66.5	66.5
Actuated g/C Ratio				0.17	0.17	0.17	0.06	0.52	0.52	0.11	0.66	0.66
v/c Ratio				0.65	0.08	0.43	0.13	0.51	0.63	0.52	0.15	0.07
Control Delay				43.9	33.1	8.9	46.3	18.2	4.3	52.0	7.0	0.5
Queue Delay				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay				43.9	33.1	8.9	46.3	18.2	4.3	52.0	7.0	0.5
LOS				D	C	A	D	B	A	D	A	A
Approach Delay					32.7			12.4			20.0	
Approach LOS					C			B			C	
Queue Length 50th (m)				31.1	3.5	0.0	2.3	53.1	0.0	17.4	9.1	0.0
Queue Length 95th (m)				41.5	9.1	14.8	7.6	81.7	19.5	27.0	17.7	1.1
Internal Link Dist (m)		106.4			333.2			381.5			335.3	
Turn Bay Length (m)				250.0		60.0	45.0		100.0	80.0		125.0
Base Capacity (vph)				973	538	563	198	1756	1107	407	2233	1037
Starvation Cap Reductn				0	0	0	0	0	0	0	0	0
Spillback Cap Reductn				0	0	0	0	0	0	0	0	0
Storage Cap Reductn				0	0	0	0	0	0	0	0	0
Reduced v/c Ratio				0.37	0.04	0.30	0.07	0.51	0.63	0.45	0.15	0.07

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 93 (93%), Referenced to phase 2:NBT and 6:SBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.65

Intersection Signal Delay: 18.1


Intersection LOS: B

Intersection Capacity Utilization 57.0%











ICU Level of Service B

Analysis Period (min) 15













Splits and Phases: 3: Robertson Road/Richmond Road & HWY 416 On-Ramp/Baseline Road



Richmond Rd/Robertson Rd/Baseline Rd
Existing PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	622	105	172	55	556	487	194	599	234
Future Volume (vph)	0	0	0	622	105	172	55	556	487	194	599	234
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	250.0		60.0	45.0		100.0	80.0		125.0
Storage Lanes	0		0	1		1	1		1	2		1
Taper Length (m)	7.6			50.0			75.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	0.95	1.00	0.97	0.95	1.00
Ped Bike Factor							1.00		0.99	1.00		0.98
Frt						0.850			0.850			0.850
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	0	0	3288	1767	1517	1647	3390	1517	3288	3390	1502
Flt Permitted				0.950			0.950			0.950		
Satd. Flow (perm)	0	0	0	3288	1767	1517	1643	3390	1495	3286	3390	1465
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)						191			541			260
Link Speed (k/h)		70			70			80			80	
Link Distance (m)		130.4			357.2			405.5			359.3	
Travel Time (s)		6.7			18.4			18.2			16.2	
Confl. Peds. (#/hr)							2		1	1		2
Confl. Bikes (#/hr)									1			
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	2%	2%	2%	2%	3%	2%	5%	2%	2%	2%	2%	3%
Adj. Flow (vph)	0	0	0	691	117	191	61	618	541	216	666	260
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	691	117	191	61	618	541	216	666	260
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors				1	2	1	1	2	1	1	2	1
Detector Template				Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Leading Detector (m)				6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5	6.1
Trailing Detector (m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)				6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8	6.1
Detector 1 Type				Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)					28.7			28.7			28.7	
Detector 2 Size(m)					1.8			1.8			1.8	
Detector 2 Type					Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Richmond Rd/Robertson Rd/Baseline Rd
Existing PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)					0.0			0.0			0.0	
Turn Type				Perm	NA	Perm	Prot	NA	Perm	Prot	NA	Perm
Protected Phases					8		5	2		1	6	
Permitted Phases				8		8			2			6
Detector Phase				8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)				10.0	10.0	10.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)				36.8	36.8	36.8	11.6	30.6	30.6	11.6	30.6	30.6
Total Split (s)				37.0	37.0	37.0	32.0	51.0	51.0	32.0	51.0	51.0
Total Split (%)				30.8%	30.8%	30.8%	26.7%	42.5%	42.5%	26.7%	42.5%	42.5%
Yellow Time (s)				4.2	4.2	4.2	4.6	4.6	4.6	4.6	4.6	4.6
All-Red Time (s)				2.6	2.6	2.6	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)				6.8	6.8	6.8	6.6	6.6	6.6	6.6	6.6	6.6
Lead/Lag							Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode				None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effct Green (s)				29.0	29.0	29.0	9.8	57.8	57.8	13.2	63.7	63.7
Actuated g/C Ratio				0.24	0.24	0.24	0.08	0.48	0.48	0.11	0.53	0.53
v/c Ratio				0.87	0.27	0.37	0.46	0.38	0.54	0.60	0.37	0.29
Control Delay				56.3	38.5	7.2	62.4	21.3	3.9	72.3	11.5	0.9
Queue Delay				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay				56.3	38.5	7.2	62.4	21.3	3.9	72.3	11.5	0.9
LOS				E	D	A	E	C	A	E	B	A
Approach Delay					44.8			15.6			20.6	
Approach LOS					D			B			C	
Queue Length 50th (m)				73.4	20.4	0.0	12.8	44.4	0.0	24.7	23.4	0.0
Queue Length 95th (m)				#95.2	35.3	16.1	24.7	61.1	17.8	m34.5	m29.8	m1.7
Internal Link Dist (m)		106.4			333.2			381.5			335.3	
Turn Bay Length (m)				250.0		60.0	45.0		100.0	80.0		125.0
Base Capacity (vph)				827	444	524	348	1632	1000	695	1799	899
Starvation Cap Reductn				0	0	0	0	0	0	0	0	0
Spillback Cap Reductn				0	0	0	0	0	0	0	0	0
Storage Cap Reductn				0	0	0	0	0	0	0	0	0
Reduced v/c Ratio				0.84	0.26	0.36	0.18	0.38	0.54	0.31	0.37	0.29

Intersection Summary

Area Type: Other

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 108 (90%), Referenced to phase 2:NBT and 6:SBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.87

Intersection Signal Delay: 26.0

Intersection LOS: C

Intersection Capacity Utilization 61.2%

ICU Level of Service B

Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Richmond Rd/Robertson Rd/Baseline Rd
Existing PM Peak

m Volume for 95th percentile queue is metered by upstream signal.

Splits and Phases: 3: Robertson Road/Richmond Road & HWY 416 On-Ramp/Baseline Road



Baseline Rd/Cedarview Rd
Existing AM Peak

							Ø7
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑	↑	↓	↑↑	↓	↑	
Traffic Volume (vph)	718	83	87	419	110	333	
Future Volume (vph)	718	83	87	419	110	333	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	45.0		20.0	0.0	
Storage Lanes		1	1		1	1	
Taper Length (m)			80.0		35.0		
Lane Util. Factor	0.95	1.00	1.00	0.95	1.00	1.00	
Ped Bike Factor		0.98			1.00		
Frt		0.850				0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3390	1517	1695	3325	1695	1517	
Flt Permitted			0.218		0.950		
Satd. Flow (perm)	3390	1482	389	3325	1693	1517	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)		85				370	
Link Speed (k/h)	70			70	60		
Link Distance (m)	357.2			373.9	442.3		
Travel Time (s)	18.4			19.2	26.5		
Confl. Peds. (#/hr)		1	1		1		
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	
Heavy Vehicles (%)	2%	2%	2%	4%	2%	2%	
Adj. Flow (vph)	798	92	97	466	122	370	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	798	92	97	466	122	370	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	4.9			4.9	4.9		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2	1	1	2	1	1	
Detector Template	Thru	Right	Left	Thru	Left	Right	
Leading Detector (m)	30.5	6.1	6.1	30.5	6.1	6.1	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	1.8	6.1	6.1	1.8	6.1	6.1	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)	28.7			28.7			
Detector 2 Size(m)	1.8			1.8			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Cedarview Rd
Existing AM Peak

	→	↘	↙	←	↖	↗	
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA	Perm	pm+pt	NA	Prot	pm+ov	
Protected Phases	2		1	6	8	1	7
Permitted Phases		2	6			8	
Detector Phase	2	2	1	6	8	1	
Switch Phase							
Minimum Initial (s)	10.0	10.0	5.0	10.0	5.0	5.0	5.0
Minimum Split (s)	27.1	27.1	11.1	27.1	11.2	11.1	34.2
Total Split (s)	34.0	34.0	15.0	49.0	45.0	15.0	36.0
Total Split (%)	26.2%	26.2%	11.5%	37.7%	34.6%	11.5%	28%
Yellow Time (s)	4.2	4.2	4.2	4.2	3.7	4.2	3.7
All-Red Time (s)	1.9	1.9	1.9	1.9	2.5	1.9	2.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.1	6.1	6.1	6.1	6.2	6.1	
Lead/Lag	Lag	Lag	Lead		Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	Max	Max	None	Max	None	None	None
Act Effct Green (s)	31.1	31.1	44.7	44.7	10.7	24.4	
Actuated g/C Ratio	0.43	0.43	0.61	0.61	0.15	0.33	
v/c Ratio	0.55	0.14	0.26	0.23	0.49	0.49	
Control Delay	21.3	7.1	12.2	9.9	38.0	5.2	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	21.3	7.1	12.2	9.9	38.0	5.2	
LOS	C	A	B	A	D	A	
Approach Delay	19.8			10.3	13.3		
Approach LOS	B			B	B		
Queue Length 50th (m)	31.3	0.4	3.3	9.0	12.6	0.0	
Queue Length 95th (m)	#109.2	12.2	21.6	43.9	37.6	19.2	
Internal Link Dist (m)	333.2			349.9	418.3		
Turn Bay Length (m)			45.0		20.0		
Base Capacity (vph)	1445	680	404	2039	940	786	
Starvation Cap Reductn	0	0	0	0	0	0	
Spillback Cap Reductn	0	0	0	0	0	0	
Storage Cap Reductn	0	0	0	0	0	0	
Reduced v/c Ratio	0.55	0.14	0.24	0.23	0.13	0.47	
Intersection Summary							
Area Type:	Other						
Cycle Length: 130							
Actuated Cycle Length: 72.9							
Natural Cycle: 85							
Control Type: Semi Act-Uncoord							
Maximum v/c Ratio: 0.55							
Intersection Signal Delay: 15.4				Intersection LOS: B			
Intersection Capacity Utilization 52.9%				ICU Level of Service A			
Analysis Period (min) 15							
# 95th percentile volume exceeds capacity, queue may be longer.							
Queue shown is maximum after two cycles.							

Baseline Rd/Cedarview Rd
Existing AM Peak

Splits and Phases: 6: Cedarview Road & Baseline Road



Baseline Rd/Cedarview Rd
Existing PM Peak

							Ø7
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑	↑	↓	↑↑	↓	↑	
Traffic Volume (vph)	528	148	221	793	118	125	
Future Volume (vph)	528	148	221	793	118	125	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	45.0		20.0	0.0	
Storage Lanes		1	1		1	1	
Taper Length (m)			80.0		35.0		
Lane Util. Factor	0.95	1.00	1.00	0.95	1.00	1.00	
Ped Bike Factor		0.96	0.99				
Frt		0.850				0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3357	1517	1662	3390	1601	1517	
Flt Permitted			0.384		0.950		
Satd. Flow (perm)	3357	1454	668	3390	1601	1517	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)		164				139	
Link Speed (k/h)	70			70	50		
Link Distance (m)	357.2			373.9	442.3		
Travel Time (s)	18.4			19.2	31.8		
Confl. Peds. (#/hr)		7	7				
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	
Heavy Vehicles (%)	3%	2%	4%	2%	8%	2%	
Adj. Flow (vph)	587	164	246	881	131	139	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	587	164	246	881	131	139	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	4.9			4.9	4.9		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2	1	1	2	1	1	
Detector Template	Thru	Right	Left	Thru	Left	Right	
Leading Detector (m)	30.5	6.1	6.1	30.5	6.1	6.1	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	1.8	6.1	6.1	1.8	6.1	6.1	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)	28.7			28.7			
Detector 2 Size(m)	1.8			1.8			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Cedarview Rd
Existing PM Peak



Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA	Perm	pm+pt	NA	Prot	pm+ov	
Protected Phases	2		1	6	8	1	7
Permitted Phases		2	6			8	
Detector Phase	2	2	1	6	8	1	
Switch Phase							
Minimum Initial (s)	10.0	10.0	5.0	10.0	5.0	5.0	5.0
Minimum Split (s)	27.1	27.1	11.1	27.1	11.2	11.1	34.2
Total Split (s)	49.0	49.0	15.0	64.0	30.0	15.0	36.0
Total Split (%)	37.7%	37.7%	11.5%	49.2%	23.1%	11.5%	28%
Yellow Time (s)	4.2	4.2	4.2	4.2	3.7	4.2	3.7
All-Red Time (s)	1.9	1.9	1.9	1.9	2.5	1.9	2.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.1	6.1	6.1	6.1	6.2	6.1	
Lead/Lag	Lag	Lag	Lead		Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	C-Max	C-Max	None	C-Max	None	None	None
Act Effect Green (s)	83.5	83.5	101.8	101.8	15.9	34.3	
Actuated g/C Ratio	0.64	0.64	0.78	0.78	0.12	0.26	
v/c Ratio	0.27	0.17	0.40	0.33	0.67	0.28	
Control Delay	11.3	2.1	6.0	4.9	70.5	6.5	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	11.3	2.1	6.0	4.9	70.5	6.5	
LOS	B	A	A	A	E	A	
Approach Delay	9.3			5.1	37.5		
Approach LOS	A			A	D		
Queue Length 50th (m)	29.4	0.0	12.5	27.1	30.0	0.0	
Queue Length 95th (m)	46.4	8.7	23.9	42.4	47.2	12.9	
Internal Link Dist (m)	333.2			349.9	418.3		
Turn Bay Length (m)			45.0		20.0		
Base Capacity (vph)	2157	992	615	2653	293	502	
Starvation Cap Reductn	0	0	0	0	0	0	
Spillback Cap Reductn	0	0	0	0	0	0	
Storage Cap Reductn	0	0	0	0	0	0	
Reduced v/c Ratio	0.27	0.17	0.40	0.33	0.45	0.28	

Intersection Summary

Area Type: Other

Cycle Length: 130

Actuated Cycle Length: 130

Offset: 11 (8%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 85

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.67

Intersection Signal Delay: 10.7


Intersection LOS: B

Intersection Capacity Utilization 52.7%






















ICU Level of Service A

Analysis Period (min) 15













Splits and Phases: 6: Cedarview Road & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
Existing AM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	138	1124	19	8	482	118	30	2	14	72	6	67
Future Volume (vph)	138	1124	19	8	482	118	30	2	14	72	6	67
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		0.99			0.99	
Frt			0.850			0.850		0.958			0.938	
Flt Protected	0.950			0.950				0.969			0.976	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1642	0	0	1579	0
Flt Permitted	0.453			0.183				0.747			0.816	
Satd. Flow (perm)	784	3357	1461	317	3357	1446	0	1265	0	0	1317	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			45			131		16			57	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			376.3			325.9			172.9	
Travel Time (s)		19.2			19.4			29.3			12.4	
Confl. Peds. (#/hr)	2		4	4		2	2		6	6		2
Confl. Bikes (#/hr)			1			6			2			
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	153	1249	21	9	536	131	33	2	16	80	7	74
Shared Lane Traffic (%)												
Lane Group Flow (vph)	153	1249	21	9	536	131	0	51	0	0	161	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Existing AM Peak






















												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Perm	NA	Perm	Perm	NA	Perm	Perm	NA		Perm	NA	
Protected Phases		2			6			8			4	
Permitted Phases	2		2	6		6	8			4		
Detector Phase	2	2	2	6	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	32.2	32.2	32.2	32.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	47.0	47.0	47.0	47.0	47.0	47.0	38.0	38.0		38.0	38.0	
Total Split (%)	55.3%	55.3%	55.3%	55.3%	55.3%	55.3%	44.7%	44.7%		44.7%	44.7%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Max	C-Max	C-Max	C-Max	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	56.6	56.6	56.6	56.6	56.6	56.6		15.7			15.7	
Actuated g/C Ratio	0.67	0.67	0.67	0.67	0.67	0.67		0.18			0.18	
v/c Ratio	0.29	0.56	0.02	0.04	0.24	0.13		0.21			0.56	
Control Delay	10.2	10.5	1.4	17.8	11.6	7.3		20.9			25.9	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	10.2	10.5	1.4	17.8	11.6	7.3		20.9			25.9	
LOS	B	B	A	B	B	A		C			C	
Approach Delay		10.3			10.9			20.9			25.9	
Approach LOS		B			B			C			C	
Queue Length 50th (m)	7.0	38.7	0.0	0.4	11.9	0.0		4.7			14.7	
Queue Length 95th (m)	28.1	100.1	1.3	m4.6	50.2	20.4		9.9			23.8	
Internal Link Dist (m)		349.9			352.3			301.9			148.9	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	522	2236	988	211	2236	1006		478			523	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.29	0.56	0.02	0.04	0.24	0.13		0.11			0.31	
Intersection Summary												
Area Type:	Other											
Cycle Length: 85												
Actuated Cycle Length: 85												
Offset: 37 (44%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green												
Natural Cycle: 75												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.56												
Intersection Signal Delay: 11.8							Intersection LOS: B					
Intersection Capacity Utilization 68.4%							ICU Level of Service C					
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Existing AM Peak













Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
Existing PM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	34	665	57	14	1122	56	38	4	12	94	5	92
Future Volume (vph)	34	665	57	14	1122	56	38	4	12	94	5	92
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		1.00			0.99	
Frt			0.850			0.850		0.970			0.935	
Flt Protected	0.950			0.950				0.966			0.976	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1661	0	0	1572	0
Flt Permitted	0.184			0.357				0.658			0.814	
Satd. Flow (perm)	319	3357	1456	617	3357	1446	0	1131	0	0	1306	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			63			38		13			49	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			376.3			325.9			172.9	
Travel Time (s)		19.2			19.4			29.3			12.4	
Confl. Peds. (#/hr)	3		4	4		3			9	9		
Confl. Bikes (#/hr)			5			3						3
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	38	739	63	16	1247	62	42	4	13	104	6	102
Shared Lane Traffic (%)												
Lane Group Flow (vph)	38	739	63	16	1247	62	0	59	0	0	212	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Existing PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Perm	NA	Perm	Perm	NA	Perm	Perm	NA		Perm	NA	
Protected Phases		2			6			8			4	
Permitted Phases	2		2	6		6	8			4		
Detector Phase	2	2	2	6	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	32.2	32.2	32.2	32.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	62.0	62.0	62.0	62.0	62.0	62.0	38.0	38.0		38.0	38.0	
Total Split (%)	62.0%	62.0%	62.0%	62.0%	62.0%	62.0%	38.0%	38.0%		38.0%	38.0%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Max	C-Max	C-Max	C-Max	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	68.1	68.1	68.1	68.1	68.1	68.1		19.2			19.2	
Actuated g/C Ratio	0.68	0.68	0.68	0.68	0.68	0.68		0.19			0.19	
v/c Ratio	0.18	0.32	0.06	0.04	0.55	0.06		0.26			0.73	
Control Delay	10.8	8.1	2.5	3.0	5.4	0.6		28.0			42.5	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	10.8	8.1	2.5	3.0	5.4	0.6		28.0			42.5	
LOS	B	A	A	A	A	A		C			D	
Approach Delay		7.8			5.2			28.0			42.5	
Approach LOS		A			A			C			D	
Queue Length 50th (m)	2.1	24.2	0.0	0.3	55.2	0.2		7.1			28.0	
Queue Length 95th (m)	9.1	47.8	4.9	m0.5	12.0	0.0		14.8			43.2	
Internal Link Dist (m)		349.9			352.3			301.9			148.9	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	217	2286	1011	419	2286	996		365			444	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.18	0.32	0.06	0.04	0.55	0.06		0.16			0.48	
Intersection Summary												
Area Type:	Other											
Cycle Length: 100												
Actuated Cycle Length: 100												
Offset: 77 (77%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green												
Natural Cycle: 75												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.73												
Intersection Signal Delay: 9.9							Intersection LOS: A					
Intersection Capacity Utilization 58.6%							ICU Level of Service B					
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Existing PM Peak







Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/Sandcastle Dr
Existing AM Peak

							Ø7
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑		↵	↑↑	↵	↵	
Traffic Volume (vph)	1191	19	39	587	21	97	
Future Volume (vph)	1191	19	39	587	21	97	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	146.0		37.0	0.0	
Storage Lanes		0	1		1	1	
Taper Length (m)			26.0		75.0		
Lane Util. Factor	0.95	0.95	1.00	0.95	1.00	1.00	
Ped Bike Factor	1.00				1.00		
Frt	0.998					0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3349	0	1695	3357	1695	1488	
Flt Permitted			0.170		0.950		
Satd. Flow (perm)	3349	0	303	3357	1693	1488	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)	3					98	
Link Speed (k/h)	50			70	50		
Link Distance (m)	376.3			243.7	303.8		
Travel Time (s)	27.1			12.5	21.9		
Confl. Peds. (#/hr)		5	5		1		
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	
Heavy Vehicles (%)	3%	2%	2%	3%	2%	4%	
Adj. Flow (vph)	1323	21	43	652	23	108	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	1344	0	43	652	23	108	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	1.6			1.6	1.6		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2		1	2	1	1	
Detector Template	Thru		Left	Thru	Left	Right	
Leading Detector (m)	10.0		2.0	10.0	2.0	2.0	
Trailing Detector (m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Size(m)	0.6		2.0	0.6	2.0	2.0	
Detector 1 Type	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0		0.0	0.0	0.0	0.0	
Detector 2 Position(m)	9.4			9.4			
Detector 2 Size(m)	0.6			0.6			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Sandcastle Dr
Existing AM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA		Perm	NA	Perm	Perm	
Protected Phases	2			6			7
Permitted Phases			6		8	8	
Detector Phase	2		6	6	8	8	
Switch Phase							
Minimum Initial (s)	10.0		10.0	10.0	5.0	5.0	1.0
Minimum Split (s)	23.9		15.9	15.9	32.5	32.5	5.0
Total Split (s)	47.0		47.0	47.0	33.0	33.0	5.0
Total Split (%)	55.3%		55.3%	55.3%	38.8%	38.8%	6%
Yellow Time (s)	4.2		4.2	4.2	3.0	3.0	2.0
All-Red Time (s)	1.7		1.7	1.7	3.5	3.5	0.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.9		5.9	5.9	6.5	6.5	
Lead/Lag					Lag	Lag	Lead
Lead-Lag Optimize?							
Recall Mode	C-Max		C-Max	C-Max	None	None	None
Act Effct Green (s)	64.8		64.8	64.8	10.4	10.4	
Actuated g/C Ratio	0.76		0.76	0.76	0.12	0.12	
v/c Ratio	0.53		0.19	0.25	0.11	0.40	
Control Delay	4.0		10.4	5.9	30.0	12.2	
Queue Delay	0.0		0.0	0.0	0.0	0.0	
Total Delay	4.0		10.4	5.9	30.0	12.2	
LOS	A		B	A	C	B	
Approach Delay	4.0			6.1	15.3		
Approach LOS	A			A	B		
Queue Length 50th (m)	14.0		1.3	10.7	3.3	1.4	
Queue Length 95th (m)	29.9		11.2	42.4	7.2	11.0	
Internal Link Dist (m)	352.3			219.7	279.8		
Turn Bay Length (m)			146.0		37.0		
Base Capacity (vph)	2552		231	2557	527	531	
Starvation Cap Reductn	0		0	0	0	0	
Spillback Cap Reductn	0		0	0	0	0	
Storage Cap Reductn	0		0	0	0	0	
Reduced v/c Ratio	0.53		0.19	0.25	0.04	0.20	

Intersection Summary

Area Type: Other

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 55 (65%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.53

Intersection Signal Delay: 5.4

Intersection LOS: A

Intersection Capacity Utilization 52.1%


ICU Level of Service A

Analysis Period (min) 15

Splits and Phases: 26: Sandcastle Road & Baseline Road



Baseline Rd/Sandcastle Dr
Existing PM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑		↵	↑↑	↵	↵	
Traffic Volume (vph)	738	33	112	1149	43	78	
Future Volume (vph)	738	33	112	1149	43	78	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	146.0		37.0	0.0	
Storage Lanes		0	1		1	1	
Taper Length (m)			26.0		75.0		
Lane Util. Factor	0.95	0.95	1.00	0.95	1.00	1.00	
Ped Bike Factor					0.99	0.98	
Frt	0.994					0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3339	0	1695	3357	1695	1488	
Flt Permitted			0.319		0.950		
Satd. Flow (perm)	3339	0	569	3357	1674	1461	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)	7					87	
Link Speed (k/h)	70			70	50		
Link Distance (m)	376.3			243.7	303.8		
Travel Time (s)	19.4			12.5	21.9		
Confl. Peds. (#/hr)					11	5	
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	
Heavy Vehicles (%)	3%	2%	2%	3%	2%	4%	
Adj. Flow (vph)	820	37	124	1277	48	87	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	857	0	124	1277	48	87	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	1.6			1.6	1.6		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		97	97		97	97	
Number of Detectors	2		1	2	1	1	
Detector Template	Thru		Left	Thru	Left	Right	
Leading Detector (m)	10.0		2.0	10.0	2.0	2.0	
Trailing Detector (m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Size(m)	0.6		2.0	0.6	2.0	2.0	
Detector 1 Type	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0		0.0	0.0	0.0	0.0	
Detector 2 Position(m)	9.4			9.4			
Detector 2 Size(m)	0.6			0.6			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Sandcastle Dr

Existing PM Peak



Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA		Perm	NA	Perm	Perm	
Protected Phases	2			6			7
Permitted Phases			6		8	8	
Detector Phase	2		6	6	8	8	
Switch Phase							
Minimum Initial (s)	10.0		10.0	10.0	5.0	5.0	1.0
Minimum Split (s)	23.9		15.9	15.9	32.5	32.5	5.0
Total Split (s)	62.0		62.0	62.0	33.0	33.0	5.0
Total Split (%)	62.0%		62.0%	62.0%	33.0%	33.0%	5%
Yellow Time (s)	4.2		4.2	4.2	3.0	3.0	2.0
All-Red Time (s)	1.7		1.7	1.7	3.5	3.5	0.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.9		5.9	5.9	6.5	6.5	
Lead/Lag					Lag	Lag	Lead
Lead-Lag Optimize?							
Recall Mode	C-Max		C-Max	C-Max	None	None	None
Act Effct Green (s)	78.9		78.9	78.9	11.2	11.2	
Actuated g/C Ratio	0.79		0.79	0.79	0.11	0.11	
v/c Ratio	0.32		0.28	0.48	0.26	0.36	
Control Delay	4.3		8.3	7.0	40.6	11.7	
Queue Delay	0.0		0.0	0.0	0.0	0.0	
Total Delay	4.3		8.3	7.0	40.6	11.7	
LOS	A		A	A	D	B	
Approach Delay	4.3			7.1	22.0		
Approach LOS	A			A	C		
Queue Length 50th (m)	14.7		4.5	30.8	8.3	0.0	
Queue Length 95th (m)	36.9		24.4	99.7	14.7	10.3	
Internal Link Dist (m)	352.3			219.7	279.8		
Turn Bay Length (m)			146.0		37.0		
Base Capacity (vph)	2637		449	2650	443	451	
Starvation Cap Reductn	0		0	0	0	0	
Spillback Cap Reductn	0		0	0	0	0	
Storage Cap Reductn	0		0	0	0	0	
Reduced v/c Ratio	0.32		0.28	0.48	0.11	0.19	

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 62 (62%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.48

Intersection Signal Delay: 7.0

Intersection LOS: A

Intersection Capacity Utilization 53.1%


ICU Level of Service A




Analysis Period (min) 15

Splits and Phases: 26: Sandcastle Road & Baseline Road







John Sutherland Dr/QCH West Ring Road (South)
Existing AM Peak












Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	26	86	151	143	39	63
Future Volume (Veh/h)	26	86	151	143	39	63
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Hourly flow rate (vph)	29	96	168	159	43	70
Pedestrians					9	
Lane Width (m)					3.7	
Walking Speed (m/s)					1.0	
Percent Blockage					1	
Right turn flare (veh)						
Median type		None	None			
Median storage veh						
Upstream signal (m)			173			
pX, platoon unblocked						
vC, conflicting volume	177				410	256
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	177				410	256
tC, single (s)	4.1				6.5	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.6	3.3
p0 queue free %	98				92	91
cM capacity (veh/h)	1386				561	775
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	125	327	113			
Volume Left	29	0	43			
Volume Right	0	159	70			
cSH	1386	1700	677			
Volume to Capacity	0.02	0.19	0.17			
Queue Length 95th (m)	0.4	0.0	4.2			
Control Delay (s)	1.9	0.0	11.4			
Lane LOS	A		B			
Approach Delay (s)	1.9	0.0	11.4			
Approach LOS			B			
Intersection Summary						
Average Delay			2.7			
Intersection Capacity Utilization			40.7%		ICU Level of Service	
Analysis Period (min)			15		A	

John Sutherland Dr/QCH West Ring Road (South)
Existing PM Peak












Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	70	129	68	57	97	52
Future Volume (Veh/h)	70	129	68	57	97	52
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Hourly flow rate (vph)	78	143	76	63	108	58
Pedestrians					17	
Lane Width (m)					3.7	
Walking Speed (m/s)					1.0	
Percent Blockage					2	
Right turn flare (veh)						
Median type		None	None			
Median storage veh)						
Upstream signal (m)			173			
pX, platoon unblocked						
vC, conflicting volume	93				424	124
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	93				424	124
tC, single (s)	4.1				6.5	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.6	3.3
p0 queue free %	95				80	94
cM capacity (veh/h)	1475				529	910
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	221	139	166			
Volume Left	78	0	108			
Volume Right	0	63	58			
cSH	1475	1700	620			
Volume to Capacity	0.05	0.08	0.27			
Queue Length 95th (m)	1.2	0.0	7.5			
Control Delay (s)	3.0	0.0	12.9			
Lane LOS	A		B			
Approach Delay (s)	3.0	0.0	12.9			
Approach LOS			B			
Intersection Summary						
Average Delay			5.3			
Intersection Capacity Utilization			40.7%	ICU Level of Service		A
Analysis Period (min)			15			










John Sutherland Dr/QCH Irving Greenberg Cancer Center
Existing AM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	124	41	15	121	13	2
Future Volume (vph)	124	41	15	121	13	2
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Hourly flow rate (vph)	138	46	17	134	14	2
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	184	151	16			
Volume Left (vph)	0	17	14			
Volume Right (vph)	46	0	2			
Hadj (s)	-0.04	0.16	0.13			
Departure Headway (s)	4.1	4.3	4.8			
Degree Utilization, x	0.21	0.18	0.02			
Capacity (veh/h)	875	830	702			
Control Delay (s)	8.1	8.2	7.9			
Approach Delay (s)	8.1	8.2	7.9			
Approach LOS	A	A	A			
Intersection Summary						
Delay			8.1			
Level of Service			A			
Intersection Capacity Utilization			30.3%	ICU Level of Service	A	
Analysis Period (min)			15			











John Sutherland Dr/QCH Irving Greenberg Cancer Center
Existing PM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	129	18	18	94	47	26
Future Volume (vph)	129	18	18	94	47	26
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Hourly flow rate (vph)	143	20	20	104	52	29
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	163	124	81			
Volume Left (vph)	0	20	52			
Volume Right (vph)	20	0	29			
Hadj (s)	0.05	0.17	-0.05			
Departure Headway (s)	4.3	4.4	4.5			
Degree Utilization, x	0.19	0.15	0.10			
Capacity (veh/h)	820	781	751			
Control Delay (s)	8.3	8.2	8.0			
Approach Delay (s)	8.3	8.2	8.0			
Approach LOS	A	A	A			
Intersection Summary						
Delay			8.2			
Level of Service			A			
Intersection Capacity Utilization			31.5%	ICU Level of Service	A	
Analysis Period (min)			15			

















John Sutherland Dr/QCH West Ring Road (North)
Existing AM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	124	190	61	85	77	25
Future Volume (vph)	124	190	61	85	77	25
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Hourly flow rate (vph)	138	211	68	94	86	28
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	349	162	114			
Volume Left (vph)	0	68	86			
Volume Right (vph)	211	0	28			
Hadj (s)	-0.30	0.20	0.05			
Departure Headway (s)	4.1	4.8	5.1			
Degree Utilization, x	0.40	0.21	0.16			
Capacity (veh/h)	852	721	651			
Control Delay (s)	9.8	9.1	9.0			
Approach Delay (s)	9.8	9.1	9.0			
Approach LOS	A	A	A			
Intersection Summary						
Delay			9.5			
Level of Service			A			
Intersection Capacity Utilization			51.6%	ICU Level of Service	A	
Analysis Period (min)			15			

















John Sutherland Dr/QCH West Ring Road (North)
Existing PM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	87	35	8	133	191	48
Future Volume (vph)	87	35	8	133	191	48
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90
Hourly flow rate (vph)	97	39	9	148	212	53
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	136	157	265			
Volume Left (vph)	0	9	212			
Volume Right (vph)	39	0	53			
Hadj (s)	-0.08	0.14	0.09			
Departure Headway (s)	4.7	4.9	4.7			
Degree Utilization, x	0.18	0.21	0.35			
Capacity (veh/h)	713	690	729			
Control Delay (s)	8.7	9.2	10.2			
Approach Delay (s)	8.7	9.2	10.2			
Approach LOS	A	A	B			
Intersection Summary						
Delay			9.6			
Level of Service			A			
Intersection Capacity Utilization			35.9%	ICU Level of Service	A	
Analysis Period (min)			15			

John Sutherland Dr/QCH Lot TL2
Existing AM Peak
























												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	83	300	1	1	117	45	0	0	1	4	0	11
Future Volume (Veh/h)	83	300	1	1	117	45	0	0	1	4	0	11
Sign Control		Free			Free			Stop			Stop	
Grade		0%			0%			0%			0%	
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Hourly flow rate (vph)	92	333	1	1	130	50	0	0	1	4	0	12
Pedestrians		5			7			2			4	
Lane Width (m)		3.7			3.7			3.7			3.7	
Walking Speed (m/s)		1.0			1.0			1.0			1.0	
Percent Blockage		1			1			0			0	
Right turn flare (veh)												
Median type		None			None							
Median storage (veh)												
Upstream signal (m)		121										
pX, platoon unblocked				0.97			0.97	0.97	0.97	0.97	0.97	
vC, conflicting volume	184			336			694	706	342	686	681	164
vC1, stage 1 conf vol												
vC2, stage 2 conf vol												
vCu, unblocked vol	184			297			667	679	304	659	654	164
tC, single (s)	4.1			4.1			7.1	6.5	6.2	7.1	6.5	6.2
tC, 2 stage (s)												
tF (s)	2.2			2.2			3.5	4.0	3.3	3.5	4.0	3.3
p0 queue free %	93			100			100	100	100	99	100	99
cM capacity (veh/h)	1385			1221			333	335	706	340	347	872
Direction, Lane #	EB 1	WB 1	NB 1	SB 1								
Volume Total	426	181	1	16								
Volume Left	92	1	0	4								
Volume Right	1	50	1	12								
cSH	1385	1221	706	627								
Volume to Capacity	0.07	0.00	0.00	0.03								
Queue Length 95th (m)	1.5	0.0	0.0	0.5								
Control Delay (s)	2.2	0.1	10.1	10.9								
Lane LOS	A	A	B	B								
Approach Delay (s)	2.2	0.1	10.1	10.9								
Approach LOS			B	B								
Intersection Summary												
Average Delay			1.8									
Intersection Capacity Utilization			48.1%	ICU Level of Service					A			
Analysis Period (min)			15									

John Sutherland Dr/QCH Lot TL2
Existing PM Peak













												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	1	119	0	3	307	2	0	0	1	14	0	73
Future Volume (Veh/h)	1	119	0	3	307	2	0	0	1	14	0	73
Sign Control		Free			Free			Stop			Stop	
Grade		0%			0%			0%			0%	
Peak Hour Factor	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90	0.90
Hourly flow rate (vph)	1	132	0	3	341	2	0	0	1	16	0	81
Pedestrians		3			6			9			5	
Lane Width (m)		3.7			3.7			3.7			3.7	
Walking Speed (m/s)		1.0			1.0			1.0			1.0	
Percent Blockage		0			1			1			1	
Right turn flare (veh)												
Median type		None			None							
Median storage (veh)												
Upstream signal (m)		121										
pX, platoon unblocked												
vC, conflicting volume	348			141			575	497	147	494	496	350
vC1, stage 1 conf vol												
vC2, stage 2 conf vol												
vCu, unblocked vol	348			141			575	497	147	494	496	350
tC, single (s)	4.1			4.1			7.1	6.5	6.2	7.1	6.5	6.2
tC, 2 stage (s)												
tF (s)	2.2			2.2			3.5	4.0	3.3	3.5	4.0	3.3
p0 queue free %	100			100			100	100	100	97	100	88
cM capacity (veh/h)	1205			1429			369	466	886	473	467	688
Direction, Lane #	EB 1	WB 1	NB 1	SB 1								
Volume Total	133	346	1	97								
Volume Left	1	3	0	16								
Volume Right	0	2	1	81								
cSH	1205	1429	886	640								
Volume to Capacity	0.00	0.00	0.00	0.15								
Queue Length 95th (m)	0.0	0.0	0.0	3.7								
Control Delay (s)	0.1	0.1	9.1	11.6								
Lane LOS	A	A	A	B								
Approach Delay (s)	0.1	0.1	9.1	11.6								
Approach LOS			A	B								
Intersection Summary												
Average Delay			2.0									
Intersection Capacity Utilization			38.5%	ICU Level of Service					A			
Analysis Period (min)			15									

Appendix K: Synchro Analysis Reports for Background Conditions

Holly Acres Rd/Richmond Rd/Nanaimo Dr
2030 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	528	8	383	21	37	91	151	916	22	26	428	17
Future Volume (vph)	528	8	383	21	37	91	151	916	22	26	428	17
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		34.0	17.0		0.0	25.0		0.0	143.0		100.0
Storage Lanes	2		1	1		1	1		0	1		1
Taper Length (m)	2.5			24.0			100.0			40.0		
Lane Util. Factor	0.97	1.00	1.00	1.00	1.00	1.00	1.00	0.95	0.95	1.00	0.95	1.00
Ped Bike Factor			0.97		0.99	0.98	1.00	1.00				0.98
Frt			0.850			0.850		0.996				0.850
Flt Protected	0.950				0.982		0.950			0.950		
Satd. Flow (prot)	3195	1784	1473	0	1734	1517	1572	3375	0	1544	3357	943
Flt Permitted	0.950				0.982		0.397			0.220		
Satd. Flow (perm)	3195	1784	1431	0	1723	1487	656	3375	0	358	3357	929
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			383			158		2				162
Link Speed (k/h)		60			40			60			60	
Link Distance (m)		88.7			195.5			655.9			232.4	
Travel Time (s)		5.3			17.6			39.4			13.9	
Confl. Peds. (#/hr)			11	11			2		1	1		2
Confl. Bikes (#/hr)			1			4						1
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	2%	5%	5%	2%	2%	10%	2%	2%	12%	3%	64%
Adj. Flow (vph)	528	8	383	21	37	91	151	916	22	26	428	17
Shared Lane Traffic (%)												
Lane Group Flow (vph)	528	8	383	0	58	91	151	938	0	26	428	17
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	1
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	2.0	10.0	2.0	2.0	10.0	2.0	2.0	10.0		2.0	10.0	2.0
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	2.0	0.6	2.0	2.0	0.6	2.0	2.0	0.6		2.0	0.6	2.0
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		9.4			9.4			9.4			9.4	
Detector 2 Size(m)		0.6			0.6			0.6			0.6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Holly Acres Rd/Richmond Rd/Nanaimo Dr
2030 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Split	NA	Perm	Split	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	4	4		3	3		5	2		1	6	
Permitted Phases			4			3	2			6		6
Detector Phase	4	4	4	3	3	3	5	2		1	6	6
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	5.0	10.0		5.0	10.0	10.0
Minimum Split (s)	28.6	28.6	28.6	16.7	16.7	16.7	11.0	30.3		11.0	30.3	30.3
Total Split (s)	45.0	45.0	45.0	20.0	20.0	20.0	12.0	33.0		12.0	33.0	33.0
Total Split (%)	40.9%	40.9%	40.9%	18.2%	18.2%	18.2%	10.9%	30.0%		10.9%	30.0%	30.0%
Yellow Time (s)	3.7	3.7	3.7	3.0	3.0	3.0	3.7	3.7		3.7	3.7	3.7
All-Red Time (s)	2.9	2.9	2.9	3.7	3.7	3.7	2.3	2.6		2.3	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.6	6.6	6.6		6.7	6.7	6.0	6.3		6.0	6.3	6.3
Lead/Lag	Lag	Lag	Lag	Lead	Lead	Lead	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None	None	None	C-Max		None	C-Max	C-Max
Act Effct Green (s)	24.8	24.8	24.8		10.6	10.6	58.3	50.4		48.4	41.5	41.5
Actuated g/C Ratio	0.23	0.23	0.23		0.10	0.10	0.53	0.46		0.44	0.38	0.38
v/c Ratio	0.73	0.02	0.62		0.35	0.32	0.35	0.61		0.11	0.34	0.04
Control Delay	45.5	30.0	8.0		52.3	3.2	18.5	28.7		18.1	28.7	0.2
Queue Delay	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	45.5	30.0	8.0		52.3	3.2	18.5	28.7		18.1	28.7	0.2
LOS	D	C	A		D	A	B	C		B	C	A
Approach Delay		29.8			22.3			27.3			27.1	
Approach LOS		C			C			C			C	
Queue Length 50th (m)	50.4	1.3	0.0		11.0	0.0	15.6	80.2		2.5	32.7	0.0
Queue Length 95th (m)	61.4	4.6	20.8		22.3	0.9	31.7	#133.0		7.8	53.3	0.0
Internal Link Dist (m)		64.7			171.5			631.9			208.4	
Turn Bay Length (m)			34.0				25.0			143.0		100.0
Base Capacity (vph)	1115	622	748		209	318	437	1548		230	1267	451
Starvation Cap Reductn	0	0	0		0	0	0	0		0	0	0
Spillback Cap Reductn	0	0	0		0	0	0	0		0	0	0
Storage Cap Reductn	0	0	0		0	0	0	0		0	0	0
Reduced v/c Ratio	0.47	0.01	0.51		0.28	0.29	0.35	0.61		0.11	0.34	0.04

Intersection Summary

Area Type: Other

Cycle Length: 110

Actuated Cycle Length: 110

Offset: 49 (45%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.73

Intersection Signal Delay: 27.8

Intersection LOS: C

Intersection Capacity Utilization 70.8%

ICU Level of Service C


Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.
























Queue shown is maximum after two cycles.

Holly Acres Rd/Richmond Rd/Nanaimo Dr
2030 BG AM Peak













Splits and Phases: 22: Richmond Road & Holly Acres Road/Nanaimo Drive



Holly Acres Rd/Richmond Rd/Nanaimo Dr
2030 BG PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	497	50	333	37	71	52	250	859	33	27	798	23
Future Volume (vph)	497	50	333	37	71	52	250	859	33	27	798	23
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		34.0	17.0		0.0	25.0		0.0	143.0		100.0
Storage Lanes	2		1	1		1	1		0	1		1
Taper Length (m)	2.5			24.0			100.0			40.0		
Lane Util. Factor	0.97	1.00	1.00	1.00	1.00	1.00	1.00	0.95	0.95	1.00	0.95	1.00
Ped Bike Factor			0.96		0.99	0.98	1.00	1.00				0.97
Frt			0.850			0.850		0.994				0.850
Flt Protected	0.950				0.983		0.950			0.950		
Satd. Flow (prot)	3257	1784	1473	0	1748	1517	1631	3366	0	1662	3357	1097
Flt Permitted	0.950				0.983		0.206			0.259		
Satd. Flow (perm)	3257	1784	1415	0	1736	1484	352	3366	0	453	3357	1063
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			333			158			4			162
Link Speed (k/h)		60			40			60			60	
Link Distance (m)		88.7			195.5			655.9			232.4	
Travel Time (s)		5.3			17.6			39.4			13.9	
Confl. Peds. (#/hr)			15	15			13					13
Confl. Bikes (#/hr)			5			4			4			2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	3%	2%	5%	3%	2%	2%	6%	2%	3%	4%	3%	41%
Adj. Flow (vph)	497	50	333	37	71	52	250	859	33	27	798	23
Shared Lane Traffic (%)												
Lane Group Flow (vph)	497	50	333	0	108	52	250	892	0	27	798	23
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	97		97	97		97	97		97	97		97
Number of Detectors	1	2	1	1	2	1	1	2		1	2	1
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	2.0	10.0	2.0	2.0	10.0	2.0	2.0	10.0		2.0	10.0	2.0
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	2.0	0.6	2.0	2.0	0.6	2.0	2.0	0.6		2.0	0.6	2.0
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		9.4			9.4			9.4			9.4	
Detector 2 Size(m)		0.6			0.6			0.6			0.6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Holly Acres Rd/Richmond Rd/Nanaimo Dr
2030 BG PM Peak





















												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Split	NA	Perm	Split	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	4	4		3	3		5	2		1	6	
Permitted Phases			4			3	2			6		6
Detector Phase	4	4	4	3	3	3	5	2		1	6	6
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	5.0	10.0		5.0	10.0	10.0
Minimum Split (s)	28.6	28.6	28.6	16.7	16.7	16.7	11.0	30.3		11.0	30.3	30.3
Total Split (s)	29.0	29.0	29.0	17.0	17.0	17.0	17.0	47.0		17.0	47.0	47.0
Total Split (%)	26.4%	26.4%	26.4%	15.5%	15.5%	15.5%	15.5%	42.7%		15.5%	42.7%	42.7%
Yellow Time (s)	3.7	3.7	3.7	3.0	3.0	3.0	3.7	3.7		3.7	3.7	3.7
All-Red Time (s)	2.9	2.9	2.9	3.7	3.7	3.7	2.3	2.6		2.3	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.6	6.6	6.6		6.7	6.7	6.0	6.3		6.0	6.3	6.3
Lead/Lag	Lag	Lag	Lag	Lead	Lead	Lead	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None	None	None	Max		None	Max	Max
Act Effct Green (s)	20.6	20.6	20.6		10.2	10.2	56.9	50.1		47.4	40.7	40.7
Actuated g/C Ratio	0.19	0.19	0.19		0.09	0.09	0.53	0.46		0.44	0.38	0.38
v/c Ratio	0.80	0.15	0.62		0.65	0.18	0.79	0.57		0.10	0.63	0.05
Control Delay	52.6	37.4	9.7		67.2	1.4	35.3	24.5		13.8	30.7	0.2
Queue Delay	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	52.6	37.4	9.7		67.2	1.4	35.3	24.5		13.8	30.7	0.2
LOS	D	D	A		E	A	D	C		B	C	A
Approach Delay		35.5			45.9			26.9			29.3	
Approach LOS		D			D			C			C	
Queue Length 50th (m)	47.9	8.2	0.0		21.0	0.0	26.4	72.4		2.5	67.8	0.0
Queue Length 95th (m)	64.6	17.7	22.9		#42.6	0.0	#55.2	94.0		6.3	86.8	0.0
Internal Link Dist (m)		64.7			171.5			631.9			208.4	
Turn Bay Length (m)			34.0				25.0			143.0		100.0
Base Capacity (vph)	675	369	557		166	284	315	1562		341	1264	501
Starvation Cap Reductn	0	0	0		0	0	0	0		0	0	0
Spillback Cap Reductn	0	0	0		0	0	0	0		0	0	0
Storage Cap Reductn	0	0	0		0	0	0	0		0	0	0
Reduced v/c Ratio	0.74	0.14	0.60		0.65	0.18	0.79	0.57		0.08	0.63	0.05
Intersection Summary												
Area Type: Other												
Cycle Length: 110												
Actuated Cycle Length: 108.2												
Natural Cycle: 90												
Control Type: Semi Act-Uncoord												
Maximum v/c Ratio: 0.80												
Intersection Signal Delay: 31.1 Intersection LOS: C												
Intersection Capacity Utilization 75.3% ICU Level of Service D												
Analysis Period (min) 15												
# 95th percentile volume exceeds capacity, queue may be longer.												
Queue shown is maximum after two cycles.												

Holly Acres Rd/Richmond Rd/Nanaimo Dr
2030 BG PM Peak


Splits and Phases: 22: Richmond Road & Holly Acres Road/Nanaimo Drive

 Ø1	 Ø2	 Ø3	 Ø4
17 s	47 s	17 s	29 s
 Ø5	 Ø6		
17 s	47 s		

Richmond Rd/John Sutherland Dr
2030 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	51	0	80	0	949	88	242	563	0
Future Volume (vph)	0	0	0	51	0	80	0	949	88	242	563	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	0		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Frt					0.918				0.850			
Flt Protected					0.981					0.950		
Satd. Flow (prot)	0	1784	0	0	1579	0	1784	3390	1517	1679	3390	0
Flt Permitted					0.872					0.289		
Satd. Flow (perm)	0	1784	0	0	1403	0	1784	3390	1517	511	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					80				86			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	5%	2%	2%	2%	3%	2%	2%
Adj. Flow (vph)	0	0	0	51	0	80	0	949	88	242	563	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	131	0	0	949	88	242	563	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		0.0			0.0			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type				Perm	NA		Perm	NA	Perm	Perm	NA	
Protected Phases		4			8			2			6	

Richmond Rd/John Sutherland Dr
2030 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	6	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	10.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	29.4	29.4	
Total Split (s)	38.0	38.0		38.0	38.0		62.0	62.0	62.0	62.0	62.0	
Total Split (%)	38.0%	38.0%		38.0%	38.0%		62.0%	62.0%	62.0%	62.0%	62.0%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0			0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6			6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	C-Max	C-Max	
Act Effect Green (s)					11.5			75.5	75.5	75.5	75.5	
Actuated g/C Ratio					0.12			0.76	0.76	0.76	0.76	
v/c Ratio					0.56			0.37	0.08	0.63	0.22	
Control Delay					27.8			1.2	0.2	15.5	4.0	
Queue Delay					0.0			0.0	0.0	0.0	0.0	
Total Delay					27.8			1.2	0.2	15.5	4.0	
LOS					C			A	A	B	A	
Approach Delay					27.8			1.1			7.5	
Approach LOS					C			A			A	
Queue Length 50th (m)					8.7			2.7	0.0	15.2	11.7	
Queue Length 95th (m)					24.2			9.6	0.1	52.0	21.1	
Internal Link Dist (m)		73.1			97.2			335.3			631.9	
Turn Bay Length (m)									35.0	40.0		
Base Capacity (vph)					495			2559	1166	385	2559	
Starvation Cap Reductn					0			0	0	0	0	
Spillback Cap Reductn					0			0	0	0	0	
Storage Cap Reductn					0			0	0	0	0	
Reduced v/c Ratio					0.26			0.37	0.08	0.63	0.22	

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 92 (92%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 100

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.63

Intersection Signal Delay: 5.5


Intersection LOS: A

Intersection Capacity Utilization 66.3%


ICU Level of Service C

Analysis Period (min) 15













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/John Sutherland Dr
2030 BG PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕		↗	↕	↗	↗	↕	↕
Traffic Volume (vph)	0	0	0	137	0	224	4	785	27	79	937	0
Future Volume (vph)	0	0	0	137	0	224	4	785	27	79	937	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	0		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Ped Bike Factor							1.00		0.98	1.00		
Frt					0.916				0.850			
Flt Protected					0.981		0.950			0.950		
Satd. Flow (prot)	0	1784	0	0	1594	0	1695	3390	1517	1647	3390	0
Flt Permitted					0.875		0.268			0.327		
Satd. Flow (perm)	0	1784	0	0	1421	0	478	3390	1482	566	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					66				33			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Confl. Peds. (#/hr)							2		1	1		2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	3%	2%	2%	2%	5%	2%	2%
Adj. Flow (vph)	0	0	0	137	0	224	4	785	27	79	937	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	361	0	4	785	27	79	937	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		0.0			0.0			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	

Richmond Rd/John Sutherland Dr
2030 BG PM Peak











												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Turn Type				Perm	NA		Perm	NA	Perm	Perm	NA	
Protected Phases		4			8			2			6	
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	6	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	10.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	29.4	29.4	
Total Split (s)	38.0	38.0		38.0	38.0		82.0	82.0	82.0	82.0	82.0	
Total Split (%)	31.7%	31.7%		31.7%	31.7%		68.3%	68.3%	68.3%	68.3%	68.3%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0			0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6			6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	C-Max	C-Max	
Act Effct Green (s)				28.9			78.1	78.1	78.1	78.1	78.1	
Actuated g/C Ratio				0.24			0.65	0.65	0.65	0.65	0.65	
v/c Ratio				0.92			0.01	0.36	0.03	0.21	0.42	
Control Delay				65.8			5.5	5.6	0.6	11.1	11.2	
Queue Delay				0.0			0.0	0.0	0.0	0.0	0.0	
Total Delay				65.8			5.5	5.6	0.6	11.1	11.2	
LOS				E			A	A	A	B	B	
Approach Delay				65.8				5.4			11.2	
Approach LOS				E				A			B	
Queue Length 50th (m)				62.5			0.1	14.6	0.0	6.9	50.8	
Queue Length 95th (m)				#110.4			m0.5	23.1	0.3	14.3	63.3	
Internal Link Dist (m)		73.1		97.2				335.3			631.9	
Turn Bay Length (m)							40.0		35.0	40.0		
Base Capacity (vph)				420			311	2207	976	368	2207	
Starvation Cap Reductn				0			0	0	0	0	0	
Spillback Cap Reductn				0			0	0	0	0	0	
Storage Cap Reductn				0			0	0	0	0	0	
Reduced v/c Ratio				0.86			0.01	0.36	0.03	0.21	0.42	
Intersection Summary												
Area Type:	Other											
Cycle Length: 120												
Actuated Cycle Length: 120												
Offset: 82 (68%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.92												
Intersection Signal Delay: 18.1							Intersection LOS: B					
Intersection Capacity Utilization 74.4%							ICU Level of Service D					
Analysis Period (min) 15												
# 95th percentile volume exceeds capacity, queue may be longer.												
Queue shown is maximum after two cycles.												
m Volume for 95th percentile queue is metered by upstream signal.												

Richmond Rd/John Sutherland Dr
2030 BG PM Peak













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/Robertson Rd/Baseline Rd
2030 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	356	24	168	12	883	660	173	342	68
Future Volume (vph)	0	0	0	356	24	168	12	883	660	173	342	68
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	250.0		60.0	45.0		100.0	80.0		125.0
Storage Lanes	0		0	1		1	1		1	2		1
Taper Length (m)	7.6			50.0			75.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	0.95	1.00	0.97	0.95	1.00
Frt						0.850			0.850			0.850
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	0	0	3225	1784	1473	1601	3390	1488	3195	3357	1502
Flt Permitted				0.950			0.950			0.950		
Satd. Flow (perm)	0	0	0	3225	1784	1473	1601	3390	1488	3195	3357	1502
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)						168			660			113
Link Speed (k/h)		70			70			80			80	
Link Distance (m)		130.4			357.2			405.5			359.3	
Travel Time (s)		6.7			18.4			18.2			16.2	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	4%	2%	5%	8%	2%	4%	5%	3%	3%
Adj. Flow (vph)	0	0	0	356	24	168	12	883	660	173	342	68
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	356	24	168	12	883	660	173	342	68
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors				1	2	1	1	2	1	1	2	1
Detector Template				Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Leading Detector (m)				6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5	6.1
Trailing Detector (m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)				6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8	6.1
Detector 1 Type				Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)					28.7			28.7			28.7	
Detector 2 Size(m)					1.8			1.8			1.8	
Detector 2 Type					Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)					0.0			0.0			0.0	
Turn Type				Perm	NA	Perm	Prot	NA	Perm	Prot	NA	Perm
Protected Phases					8		5	2		1	6	

Richmond Rd/Robertson Rd/Baseline Rd
2030 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases				8		8			2			6
Detector Phase				8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)				10.0	10.0	10.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)				36.8	36.8	36.8	11.6	30.6	30.6	11.6	30.6	30.6
Total Split (s)				37.0	37.0	37.0	19.0	44.0	44.0	19.0	44.0	44.0
Total Split (%)				37.0%	37.0%	37.0%	19.0%	44.0%	44.0%	19.0%	44.0%	44.0%
Yellow Time (s)				4.2	4.2	4.2	4.6	4.6	4.6	4.6	4.6	4.6
All-Red Time (s)				2.6	2.6	2.6	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)				6.8	6.8	6.8	6.6	6.6	6.6	6.6	6.6	6.6
Lead/Lag							Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode				None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effect Green (s)				17.1	17.1	17.1	6.4	52.2	52.2	10.7	66.7	66.7
Actuated g/C Ratio				0.17	0.17	0.17	0.06	0.52	0.52	0.11	0.67	0.67
v/c Ratio				0.65	0.08	0.43	0.12	0.50	0.60	0.51	0.15	0.07
Control Delay				43.9	33.3	9.0	46.2	17.8	4.1	51.8	7.0	0.3
Queue Delay				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay				43.9	33.3	9.0	46.2	17.8	4.1	51.8	7.0	0.3
LOS				D	C	A	D	B	A	D	A	A
Approach Delay					32.7			12.2			19.5	
Approach LOS					C			B			B	
Queue Length 50th (m)				30.7	3.6	0.0	2.1	51.3	0.0	16.4	9.3	0.0
Queue Length 95th (m)				41.1	9.4	14.6	7.1	79.2	18.6	25.8	18.0	0.8
Internal Link Dist (m)		106.4			333.2			381.5			335.3	
Turn Bay Length (m)				250.0		60.0	45.0		100.0	80.0		125.0
Base Capacity (vph)				973	538	562	198	1770	1092	405	2237	1038
Starvation Cap Reductn				0	0	0	0	0	0	0	0	0
Spillback Cap Reductn				0	0	0	0	0	0	0	0	0
Storage Cap Reductn				0	0	0	0	0	0	0	0	0
Reduced v/c Ratio				0.37	0.04	0.30	0.06	0.50	0.60	0.43	0.15	0.07

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 93 (93%), Referenced to phase 2:NBT and 6:SBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.65

Intersection Signal Delay: 18.0


Intersection LOS: B

Intersection Capacity Utilization 59.3%






















ICU Level of Service B

Analysis Period (min) 15













Splits and Phases: 3: Robertson Road/Richmond Road & HWY 416 On-Ramp/Baseline Road



Richmond Rd/Robertson Rd/Baseline Rd
2030 BG PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	653	112	180	56	630	521	208	656	240
Future Volume (vph)	0	0	0	653	112	180	56	630	521	208	656	240
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	250.0		60.0	45.0		100.0	80.0		125.0
Storage Lanes	0		0	1		1	1		1	2		1
Taper Length (m)	7.6			50.0			75.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	0.95	1.00	0.97	0.95	1.00
Ped Bike Factor							1.00		0.99	1.00		0.98
Frt						0.850			0.850			0.850
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	0	0	3288	1767	1517	1647	3390	1517	3288	3390	1502
Flt Permitted				0.950			0.950			0.950		
Satd. Flow (perm)	0	0	0	3288	1767	1517	1643	3390	1495	3286	3390	1465
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)						180			521			240
Link Speed (k/h)		70			70			80			80	
Link Distance (m)		130.4			357.2			405.5			359.3	
Travel Time (s)		6.7			18.4			18.2			16.2	
Confl. Peds. (#/hr)							2		1	1		2
Confl. Bikes (#/hr)									1			
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	3%	2%	5%	2%	2%	2%	2%	3%
Adj. Flow (vph)	0	0	0	653	112	180	56	630	521	208	656	240
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	653	112	180	56	630	521	208	656	240
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors				1	2	1	1	2	1	1	2	1
Detector Template				Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Leading Detector (m)				6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5	6.1
Trailing Detector (m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)				6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8	6.1
Detector 1 Type				Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)					28.7			28.7			28.7	
Detector 2 Size(m)					1.8			1.8			1.8	
Detector 2 Type					Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Richmond Rd/Robertson Rd/Baseline Rd
2030 BG PM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)					0.0			0.0			0.0	
Turn Type				Perm	NA	Perm	Prot	NA	Perm	Prot	NA	Perm
Protected Phases					8		5	2		1	6	
Permitted Phases				8		8			2			6
Detector Phase				8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)				10.0	10.0	10.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)				36.8	36.8	36.8	11.6	30.6	30.6	11.6	30.6	30.6
Total Split (s)				37.0	37.0	37.0	32.0	51.0	51.0	32.0	51.0	51.0
Total Split (%)				30.8%	30.8%	30.8%	26.7%	42.5%	42.5%	26.7%	42.5%	42.5%
Yellow Time (s)				4.2	4.2	4.2	4.6	4.6	4.6	4.6	4.6	4.6
All-Red Time (s)				2.6	2.6	2.6	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)				6.8	6.8	6.8	6.6	6.6	6.6	6.6	6.6	6.6
Lead/Lag							Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode				None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effct Green (s)				28.4	28.4	28.4	9.5	58.7	58.7	12.9	64.6	64.6
Actuated g/C Ratio				0.24	0.24	0.24	0.08	0.49	0.49	0.11	0.54	0.54
v/c Ratio				0.84	0.27	0.36	0.43	0.38	0.52	0.59	0.36	0.27
Control Delay				54.2	38.6	7.3	62.1	20.9	3.8	72.9	11.1	0.8
Queue Delay				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay				54.2	38.6	7.3	62.1	20.9	3.8	72.9	11.1	0.8
LOS				D	D	A	E	C	A	E	B	A
Approach Delay					43.5			15.4			20.5	
Approach LOS					D			B			C	
Queue Length 50th (m)				68.4	19.5	0.0	11.8	45.2	0.0	24.1	22.4	0.0
Queue Length 95th (m)				88.0	33.9	15.8	23.3	62.0	17.2	m34.1	m27.4	m1.9
Internal Link Dist (m)		106.4			333.2			381.5			335.3	
Turn Bay Length (m)				250.0		60.0	45.0		100.0	80.0		125.0
Base Capacity (vph)				827	444	516	348	1658	997	695	1825	899
Starvation Cap Reductn				0	0	0	0	0	0	0	0	0
Spillback Cap Reductn				0	0	0	0	0	0	0	0	0
Storage Cap Reductn				0	0	0	0	0	0	0	0	0
Reduced v/c Ratio				0.79	0.25	0.35	0.16	0.38	0.52	0.30	0.36	0.27
Intersection Summary												
Area Type: Other												
Cycle Length: 120												
Actuated Cycle Length: 120												
Offset: 108 (90%), Referenced to phase 2:NBT and 6:SBT, Start of Green												
Natural Cycle: 80												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.84												
Intersection Signal Delay: 25.3 Intersection LOS: C												
Intersection Capacity Utilization 62.6% ICU Level of Service B												
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Richmond Rd/Robertson Rd/Baseline Rd
2030 BG PM Peak


Splits and Phases: 3: Robertson Road/Richmond Road & HWY 416 On-Ramp/Baseline Road



Baseline Rd/Cedarview Rd
2030 BG AM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑	↑	↓	↑↑	↓	↑	
Traffic Volume (vph)	756	91	98	466	121	367	
Future Volume (vph)	756	91	98	466	121	367	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	45.0		20.0	0.0	
Storage Lanes		1	1		1	1	
Taper Length (m)			80.0		35.0		
Lane Util. Factor	0.95	1.00	1.00	0.95	1.00	1.00	
Ped Bike Factor		0.98			1.00		
Frt		0.850				0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3390	1517	1695	3325	1695	1517	
Flt Permitted			0.236		0.950		
Satd. Flow (perm)	3390	1482	421	3325	1693	1517	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)		89				367	
Link Speed (k/h)	70			70	50		
Link Distance (m)	357.2			373.9	442.3		
Travel Time (s)	18.4			19.2	31.8		
Confl. Peds. (#/hr)		1	1		1		
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	2%	2%	2%	4%	2%	2%	
Adj. Flow (vph)	756	91	98	466	121	367	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	756	91	98	466	121	367	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	4.9			4.9	4.9		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2	1	1	2	1	1	
Detector Template	Thru	Right	Left	Thru	Left	Right	
Leading Detector (m)	30.5	6.1	6.1	30.5	6.1	6.1	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	1.8	6.1	6.1	1.8	6.1	6.1	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)	28.7			28.7			
Detector 2 Size(m)	1.8			1.8			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Cedarview Rd
2030 BG AM Peak



Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA	Perm	pm+pt	NA	Prot	pm+ov	
Protected Phases	2		1	6	8	1	7
Permitted Phases		2	6			8	
Detector Phase	2	2	1	6	8	1	
Switch Phase							
Minimum Initial (s)	10.0	10.0	5.0	10.0	5.0	5.0	5.0
Minimum Split (s)	27.1	27.1	11.1	27.1	36.2	11.1	34.2
Total Split (s)	34.0	34.0	15.0	49.0	45.0	15.0	36.0
Total Split (%)	26.2%	26.2%	11.5%	37.7%	34.6%	11.5%	28%
Yellow Time (s)	4.2	4.2	4.2	4.2	3.7	4.2	3.7
All-Red Time (s)	1.9	1.9	1.9	1.9	2.5	1.9	2.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.1	6.1	6.1	6.1	6.2	6.1	
Lead/Lag	Lag	Lag	Lead		Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	Max	Max	None	Max	None	None	None
Act Effect Green (s)	31.1	31.1	44.7	44.7	10.7	24.4	
Actuated g/C Ratio	0.43	0.43	0.61	0.61	0.15	0.33	
v/c Ratio	0.52	0.13	0.25	0.23	0.49	0.49	
Control Delay	20.8	6.6	12.0	9.8	38.0	5.2	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	20.8	6.6	12.0	9.8	38.0	5.2	
LOS	C	A	B	A	D	A	
Approach Delay	19.3			10.2	13.3		
Approach LOS	B			B	B		
Queue Length 50th (m)	29.2	0.1	3.3	9.0	12.5	0.0	
Queue Length 95th (m)	#99.8	11.2	21.9	43.8	37.4	18.9	
Internal Link Dist (m)	333.2			349.9	418.3		
Turn Bay Length (m)			45.0		20.0		
Base Capacity (vph)	1444	682	420	2040	940	783	
Starvation Cap Reductn	0	0	0	0	0	0	
Spillback Cap Reductn	0	0	0	0	0	0	
Storage Cap Reductn	0	0	0	0	0	0	
Reduced v/c Ratio	0.52	0.13	0.23	0.23	0.13	0.47	

Intersection Summary

Area Type: Other

Cycle Length: 130

Actuated Cycle Length: 72.9

Natural Cycle: 110

Control Type: Semi Act-Uncoord

Maximum v/c Ratio: 0.52

Intersection Signal Delay: 15.1

Intersection LOS: B

Intersection Capacity Utilization 56.2%

ICU Level of Service B

Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.


Queue shown is maximum after two cycles.

Baseline Rd/Cedarview Rd
2030 BG AM Peak

Splits and Phases: 6: Cedarview Road & Baseline Road



Baseline Rd/Cedarview Rd
2030 BG PM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑	↑	↓	↑↑	↓	↑	
Traffic Volume (vph)	572	163	245	836	130	140	
Future Volume (vph)	572	163	245	836	130	140	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	45.0		20.0	0.0	
Storage Lanes		1	1		1	1	
Taper Length (m)			80.0		35.0		
Lane Util. Factor	0.95	1.00	1.00	0.95	1.00	1.00	
Ped Bike Factor		0.96	0.99				
Frt		0.850				0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3357	1517	1662	3390	1601	1517	
Flt Permitted			0.392		0.950		
Satd. Flow (perm)	3357	1454	682	3390	1601	1517	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)		163				140	
Link Speed (k/h)	70			70	50		
Link Distance (m)	357.2			373.9	442.3		
Travel Time (s)	18.4			19.2	31.8		
Confl. Peds. (#/hr)		7	7				
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	4%	2%	8%	2%	
Adj. Flow (vph)	572	163	245	836	130	140	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	572	163	245	836	130	140	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	4.9			4.9	4.9		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2	1	1	2	1	1	
Detector Template	Thru	Right	Left	Thru	Left	Right	
Leading Detector (m)	30.5	6.1	6.1	30.5	6.1	6.1	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	1.8	6.1	6.1	1.8	6.1	6.1	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)	28.7			28.7			
Detector 2 Size(m)	1.8			1.8			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Cedarview Rd
2030 BG PM Peak



Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA	Perm	pm+pt	NA	Prot	pm+ov	
Protected Phases	2		1	6	8	1	7
Permitted Phases		2	6			8	
Detector Phase	2	2	1	6	8	1	
Switch Phase							
Minimum Initial (s)	10.0	10.0	5.0	10.0	5.0	5.0	5.0
Minimum Split (s)	27.1	27.1	11.1	27.1	11.2	11.1	34.2
Total Split (s)	49.0	49.0	15.0	64.0	30.0	15.0	36.0
Total Split (%)	37.7%	37.7%	11.5%	49.2%	23.1%	11.5%	28%
Yellow Time (s)	4.2	4.2	4.2	4.2	3.7	4.2	3.7
All-Red Time (s)	1.9	1.9	1.9	1.9	2.5	1.9	2.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.1	6.1	6.1	6.1	6.2	6.1	
Lead/Lag	Lag	Lag	Lead		Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	C-Max	C-Max	None	C-Max	None	None	None
Act Effect Green (s)	84.1	84.1	101.9	101.9	15.8	33.7	
Actuated g/C Ratio	0.65	0.65	0.78	0.78	0.12	0.26	
v/c Ratio	0.26	0.16	0.39	0.31	0.67	0.28	
Control Delay	11.0	2.1	5.9	4.7	70.5	6.5	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	11.0	2.1	5.9	4.7	70.5	6.5	
LOS	B	A	A	A	E	A	
Approach Delay	9.0			5.0	37.3		
Approach LOS	A			A	D		
Queue Length 50th (m)	28.1	0.0	12.4	25.1	29.8	0.0	
Queue Length 95th (m)	44.5	8.5	23.7	39.6	46.9	13.0	
Internal Link Dist (m)	333.2			349.9	418.3		
Turn Bay Length (m)			45.0		20.0		
Base Capacity (vph)	2171	997	623	2656	293	497	
Starvation Cap Reductn	0	0	0	0	0	0	
Spillback Cap Reductn	0	0	0	0	0	0	
Storage Cap Reductn	0	0	0	0	0	0	
Reduced v/c Ratio	0.26	0.16	0.39	0.31	0.44	0.28	

Intersection Summary

Area Type: Other

Cycle Length: 130

Actuated Cycle Length: 130

Offset: 15 (12%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 85

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.67

Intersection Signal Delay: 10.6


Intersection LOS: B

Intersection Capacity Utilization 54.8%





















ICU Level of Service A

Analysis Period (min) 15













Splits and Phases: 6: Cedarview Road & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
2030 BG AM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	138	1173	19	8	533	118	30	2	14	72	6	67
Future Volume (vph)	138	1173	19	8	533	118	30	2	14	72	6	67
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		0.99			0.99	
Frt			0.850			0.850		0.959			0.938	
Flt Protected	0.950			0.950				0.968			0.976	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1642	0	0	1579	0
Flt Permitted	0.454			0.206				0.767			0.819	
Satd. Flow (perm)	786	3357	1461	357	3357	1446	0	1300	0	0	1322	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			45			118		14			58	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			378.0			325.9			172.9	
Travel Time (s)		19.2			19.4			29.3			12.4	
Confl. Peds. (#/hr)	2		4	4		2	2		6	6		2
Confl. Bikes (#/hr)			1			6			2			
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	138	1173	19	8	533	118	30	2	14	72	6	67
Shared Lane Traffic (%)												
Lane Group Flow (vph)	138	1173	19	8	533	118	0	46	0	0	145	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	2.0	10.0	6.1	6.1	10.0	2.0	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	2.0	0.6	6.1	6.1	0.6	2.0	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		9.4			9.4			28.7			28.7	
Detector 2 Size(m)		0.6			0.6			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
2030 BG AM Peak






















												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Perm	NA	Perm	Perm	NA	Perm	Perm	NA		Perm	NA	
Protected Phases		2			6			8			4	
Permitted Phases	2		2	6		6	8			4		
Detector Phase	2	2	2	6	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	32.2	32.2	32.2	32.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	47.0	47.0	47.0	47.0	47.0	47.0	38.0	38.0		38.0	38.0	
Total Split (%)	55.3%	55.3%	55.3%	55.3%	55.3%	55.3%	44.7%	44.7%		44.7%	44.7%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Max	C-Max	C-Max	C-Max	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	57.1	57.1	57.1	57.1	57.1	57.1		15.2			15.2	
Actuated g/C Ratio	0.67	0.67	0.67	0.67	0.67	0.67		0.18			0.18	
v/c Ratio	0.26	0.52	0.02	0.03	0.24	0.12		0.19			0.51	
Control Delay	9.6	9.7	1.1	16.4	10.7	6.7		21.2			23.8	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	9.6	9.7	1.1	16.4	10.7	6.7		21.2			23.8	
LOS	A	A	A	B	B	A		C			C	
Approach Delay		9.6			10.1			21.2			23.8	
Approach LOS		A			B			C			C	
Queue Length 50th (m)	5.8	32.8	0.0	0.2	10.3	0.0		4.3			12.3	
Queue Length 95th (m)	25.0	91.1	1.0	m3.9	47.5	17.0		9.4			20.8	
Internal Link Dist (m)		349.9			354.0			301.9			148.9	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	528	2256	996	239	2256	1010		490			526	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.26	0.52	0.02	0.03	0.24	0.12		0.09			0.28	
Intersection Summary												
Area Type:	Other											
Cycle Length: 85												
Actuated Cycle Length: 85												
Offset: 37 (44%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.52												
Intersection Signal Delay: 10.9						Intersection LOS: B						
Intersection Capacity Utilization 69.8%						ICU Level of Service C						
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
2030 BG AM Peak













Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
2030 BG PM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	34	715	57	14	1175	56	38	4	12	94	5	92
Future Volume (vph)	34	715	57	14	1175	56	38	4	12	94	5	92
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		1.00			0.99	
Frt			0.850			0.850		0.970			0.935	
Flt Protected	0.950			0.950				0.966			0.976	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1661	0	0	1572	0
Flt Permitted	0.206			0.369				0.677			0.816	
Satd. Flow (perm)	357	3357	1456	638	3357	1446	0	1164	0	0	1309	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			57			38		12			49	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			378.0			325.9			172.9	
Travel Time (s)		19.2			19.4			29.3			12.4	
Confl. Peds. (#/hr)	3		4	4		3			9	9		
Confl. Bikes (#/hr)			5			3						3
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	34	715	57	14	1175	56	38	4	12	94	5	92
Shared Lane Traffic (%)												
Lane Group Flow (vph)	34	715	57	14	1175	56	0	54	0	0	191	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	2.0	10.0	6.1	6.1	10.0	2.0	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	2.0	0.6	6.1	6.1	0.6	2.0	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		9.4			9.4			28.7			28.7	
Detector 2 Size(m)		0.6			0.6			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
2030 BG PM Peak












												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Perm	NA	Perm	Perm	NA	Perm	Perm	NA		Perm	NA	
Protected Phases		2			6			8			4	
Permitted Phases	2		2	6		6	8			4		
Detector Phase	2	2	2	6	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	32.2	32.2	32.2	32.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	62.0	62.0	62.0	62.0	62.0	62.0	38.0	38.0		38.0	38.0	
Total Split (%)	62.0%	62.0%	62.0%	62.0%	62.0%	62.0%	38.0%	38.0%		38.0%	38.0%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Max	C-Max	C-Max	C-Max	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	69.1	69.1	69.1	69.1	69.1	69.1		18.2			18.2	
Actuated g/C Ratio	0.69	0.69	0.69	0.69	0.69	0.69		0.18			0.18	
v/c Ratio	0.14	0.31	0.06	0.03	0.51	0.06		0.24			0.69	
Control Delay	9.5	7.6	2.6	3.0	4.6	0.4		28.3			39.7	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	9.5	7.6	2.6	3.0	4.6	0.4		28.3			39.7	
LOS	A	A	A	A	A	A		C			D	
Approach Delay		7.3			4.4			28.3			39.7	
Approach LOS		A			A			C			D	
Queue Length 50th (m)	1.7	21.6	0.0	0.3	32.8	0.3		6.6			24.4	
Queue Length 95th (m)	7.9	46.1	4.8	m0.6	13.8	0.0		13.7			38.0	
Internal Link Dist (m)		349.9			354.0			301.9			148.9	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	246	2320	1024	441	2320	1011		374			445	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.14	0.31	0.06	0.03	0.51	0.06		0.14			0.43	
Intersection Summary												
Area Type:	Other											
Cycle Length: 100												
Actuated Cycle Length: 100												
Offset: 77 (77%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.69												
Intersection Signal Delay: 8.9							Intersection LOS: A					
Intersection Capacity Utilization 58.6%							ICU Level of Service B					
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
2030 BG PM Peak

Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/Sandcastle Dr
2030 BG AM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations							
Traffic Volume (vph)	1236	25	94	602	60	129	
Future Volume (vph)	1236	25	94	602	60	129	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	146.0		37.0	0.0	
Storage Lanes		0	1		1	1	
Taper Length (m)			26.0		75.0		
Lane Util. Factor	0.95	0.95	1.00	0.95	1.00	1.00	
Ped Bike Factor	1.00				1.00		
Frt	0.997					0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3346	0	1695	3357	1695	1488	
Flt Permitted			0.185		0.950		
Satd. Flow (perm)	3346	0	330	3357	1693	1488	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)	3					106	
Link Speed (k/h)	70			70	50		
Link Distance (m)	378.0			246.3	226.0		
Travel Time (s)	19.4			12.7	16.3		
Confl. Peds. (#/hr)		5	5		1		
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	2%	3%	2%	4%	
Adj. Flow (vph)	1236	25	94	602	60	129	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	1261	0	94	602	60	129	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	1.6			1.6	1.6		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2		1	2	1	1	
Detector Template	Thru		Left	Thru	Left	Right	
Leading Detector (m)	10.0		2.0	10.0	2.0	2.0	
Trailing Detector (m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Size(m)	0.6		2.0	0.6	2.0	2.0	
Detector 1 Type	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0		0.0	0.0	0.0	0.0	
Detector 2 Position(m)	9.4			9.4			
Detector 2 Size(m)	0.6			0.6			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Sandcastle Dr
2030 BG AM Peak

	→	↘	↙	←	↖	↗	
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA		Perm	NA	Perm	Perm	
Protected Phases	2			6			7
Permitted Phases			6		8	8	
Detector Phase	2		6	6	8	8	
Switch Phase							
Minimum Initial (s)	10.0		10.0	10.0	5.0	5.0	1.0
Minimum Split (s)	23.9		15.9	15.9	32.5	32.5	5.0
Total Split (s)	47.0		47.0	47.0	33.0	33.0	5.0
Total Split (%)	55.3%		55.3%	55.3%	38.8%	38.8%	6%
Yellow Time (s)	4.2		4.2	4.2	3.0	3.0	2.0
All-Red Time (s)	1.7		1.7	1.7	3.5	3.5	0.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.9		5.9	5.9	6.5	6.5	
Lead/Lag					Lag	Lag	Lead
Lead-Lag Optimize?							
Recall Mode	C-Max		C-Max	C-Max	None	None	None
Act Effct Green (s)	60.3		60.3	60.3	11.3	11.3	
Actuated g/C Ratio	0.71		0.71	0.71	0.13	0.13	
v/c Ratio	0.53		0.40	0.25	0.27	0.44	
Control Delay	2.2		16.7	6.3	32.9	13.6	
Queue Delay	0.0		0.0	0.0	0.0	0.0	
Total Delay	2.2		16.7	6.3	32.9	13.6	
LOS	A		B	A	C	B	
Approach Delay	2.2			7.7	19.7		
Approach LOS	A			A	B		
Queue Length 50th (m)	6.3		3.8	11.1	8.6	3.2	
Queue Length 95th (m)	9.2		#30.7	38.8	14.4	13.5	
Internal Link Dist (m)	354.0			222.3	202.0		
Turn Bay Length (m)			146.0		37.0		
Base Capacity (vph)	2373		234	2379	527	536	
Starvation Cap Reductn	0		0	0	0	0	
Spillback Cap Reductn	0		0	0	0	0	
Storage Cap Reductn	0		0	0	0	0	
Reduced v/c Ratio	0.53		0.40	0.25	0.11	0.24	

Intersection Summary

Area Type: Other

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 55 (65%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.53

Intersection Signal Delay: 5.5

Intersection LOS: A

Intersection Capacity Utilization 64.7%

ICU Level of Service C


Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Baseline Rd/Sandcastle Dr
2030 BG AM Peak

Splits and Phases: 5: Sandcastle Dr & Baseline Road



Baseline Rd/Sandcastle Dr
2030 BG PM Peak

							Ø7
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑		↵	↑↑	↵	↵	
Traffic Volume (vph)	775	43	193	1178	68	107	
Future Volume (vph)	775	43	193	1178	68	107	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	146.0		37.0	0.0	
Storage Lanes		0	1		1	1	
Taper Length (m)			26.0		75.0		
Lane Util. Factor	0.95	0.95	1.00	0.95	1.00	1.00	
Ped Bike Factor					0.99	0.98	
Frt	0.992					0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3332	0	1695	3357	1695	1488	
Flt Permitted			0.331		0.950		
Satd. Flow (perm)	3332	0	591	3357	1674	1461	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)	9					107	
Link Speed (k/h)	70			70	50		
Link Distance (m)	378.0			246.3	226.0		
Travel Time (s)	19.4			12.7	16.3		
Confl. Peds. (#/hr)					11	5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	2%	3%	2%	4%	
Adj. Flow (vph)	775	43	193	1178	68	107	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	818	0	193	1178	68	107	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	1.6			1.6	1.6		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		97	97		97	97	
Number of Detectors	2		1	2	1	1	
Detector Template	Thru		Left	Thru	Left	Right	
Leading Detector (m)	10.0		2.0	10.0	2.0	2.0	
Trailing Detector (m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Size(m)	0.6		2.0	0.6	2.0	2.0	
Detector 1 Type	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0		0.0	0.0	0.0	0.0	
Detector 2 Position(m)	9.4			9.4			
Detector 2 Size(m)	0.6			0.6			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Sandcastle Dr
2030 BG PM Peak

	→	↘	↙	←	↖	↗	
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA		Perm	NA	Perm	Perm	
Protected Phases	2			6			7
Permitted Phases			6		8	8	
Detector Phase	2		6	6	8	8	
Switch Phase							
Minimum Initial (s)	10.0		10.0	10.0	5.0	5.0	1.0
Minimum Split (s)	23.9		15.9	15.9	32.5	32.5	5.0
Total Split (s)	62.0		62.0	62.0	33.0	33.0	5.0
Total Split (%)	62.0%		62.0%	62.0%	33.0%	33.0%	5%
Yellow Time (s)	4.2		4.2	4.2	3.0	3.0	2.0
All-Red Time (s)	1.7		1.7	1.7	3.5	3.5	0.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.9		5.9	5.9	6.5	6.5	
Lead/Lag					Lag	Lag	Lead
Lead-Lag Optimize?							
Recall Mode	C-Max		C-Max	C-Max	None	None	None
Act Effect Green (s)	74.6		74.6	74.6	12.0	12.0	
Actuated g/C Ratio	0.75		0.75	0.75	0.12	0.12	
v/c Ratio	0.33		0.44	0.47	0.34	0.40	
Control Delay	4.8		11.5	7.3	42.1	11.2	
Queue Delay	0.0		0.0	0.0	0.0	0.0	
Total Delay	4.8		11.5	7.3	42.1	11.2	
LOS	A		B	A	D	B	
Approach Delay	4.8			7.9	23.2		
Approach LOS	A			A	C		
Queue Length 50th (m)	15.1		8.8	29.3	11.7	0.0	
Queue Length 95th (m)	35.3		43.5	88.2	19.3	11.3	
Internal Link Dist (m)	354.0			222.3	202.0		
Turn Bay Length (m)			146.0		37.0		
Base Capacity (vph)	2487		441	2504	443	465	
Starvation Cap Reductn	0		0	0	0	0	
Spillback Cap Reductn	0		0	0	0	0	
Storage Cap Reductn	0		0	0	0	0	
Reduced v/c Ratio	0.33		0.44	0.47	0.15	0.23	

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 62 (62%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.47

Intersection Signal Delay: 7.9

Intersection LOS: A

Intersection Capacity Utilization 57.4%


ICU Level of Service B




Analysis Period (min) 15

Splits and Phases: 5: Sandcastle Dr & Baseline Road







John Sutherland Dr/QCH West Ring Road (North)
2030 BG AM Peak













Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	26	86	151	143	39	63
Future Volume (Veh/h)	26	86	151	143	39	63
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	26	86	151	143	39	63
Pedestrians					9	
Lane Width (m)					3.7	
Walking Speed (m/s)					1.0	
Percent Blockage					1	
Right turn flare (veh)						
Median type		None	None			
Median storage veh						
Upstream signal (m)			173			
pX, platoon unblocked						
vC, conflicting volume	160				370	232
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	160				370	232
tC, single (s)	4.1				6.5	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.6	3.3
p0 queue free %	98				93	92
cM capacity (veh/h)	1406				595	800
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	112	294	102			
Volume Left	26	0	39			
Volume Right	0	143	63			
cSH	1406	1700	707			
Volume to Capacity	0.02	0.17	0.14			
Queue Length 95th (m)	0.4	0.0	3.5			
Control Delay (s)	1.9	0.0	11.0			
Lane LOS	A		B			
Approach Delay (s)	1.9	0.0	11.0			
Approach LOS			B			
Intersection Summary						
Average Delay			2.6			
Intersection Capacity Utilization			40.7%	ICU Level of Service	A	
Analysis Period (min)			15			

John Sutherland Dr/QCH West Ring Road (North)
2030 BG PM Peak












Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	70	129	68	57	97	52
Future Volume (Veh/h)	70	129	68	57	97	52
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	70	129	68	57	97	52
Pedestrians					17	
Lane Width (m)					3.7	
Walking Speed (m/s)					1.0	
Percent Blockage					2	
Right turn flare (veh)						
Median type		None	None			
Median storage veh						
Upstream signal (m)			173			
pX, platoon unblocked						
vC, conflicting volume	85				382	114
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	85				382	114
tC, single (s)	4.1				6.5	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.6	3.3
p0 queue free %	95				83	94
cM capacity (veh/h)	1485				563	923
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	199	125	149			
Volume Left	70	0	97			
Volume Right	0	57	52			
cSH	1485	1700	651			
Volume to Capacity	0.05	0.07	0.23			
Queue Length 95th (m)	1.0	0.0	6.1			
Control Delay (s)	2.9	0.0	12.2			
Lane LOS	A		B			
Approach Delay (s)	2.9	0.0	12.2			
Approach LOS			B			
Intersection Summary						
Average Delay			5.1			
Intersection Capacity Utilization			40.7%	ICU Level of Service	A	
Analysis Period (min)			15			











John Sutherland Dr/QCH Irving Greenberg Cancer Center
2030 BG AM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	124	41	15	121	13	2
Future Volume (vph)	124	41	15	121	13	2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	124	41	15	121	13	2
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	165	136	15			
Volume Left (vph)	0	15	13			
Volume Right (vph)	41	0	2			
Hadj (s)	-0.04	0.16	0.13			
Departure Headway (s)	4.0	4.3	4.7			
Degree Utilization, x	0.18	0.16	0.02			
Capacity (veh/h)	879	835	717			
Control Delay (s)	7.9	8.1	7.8			
Approach Delay (s)	7.9	8.1	7.8			
Approach LOS	A	A	A			
Intersection Summary						
Delay			8.0			
Level of Service			A			
Intersection Capacity Utilization			30.3%	ICU Level of Service	A	
Analysis Period (min)			15			











John Sutherland Dr/QCH Irving Greenberg Cancer Center
2030 BG PM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	129	18	18	94	47	26
Future Volume (vph)	129	18	18	94	47	26
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	129	18	18	94	47	26
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	147	112	73			
Volume Left (vph)	0	18	47			
Volume Right (vph)	18	0	26			
Hadj (s)	0.05	0.17	-0.05			
Departure Headway (s)	4.2	4.4	4.4			
Degree Utilization, x	0.17	0.14	0.09			
Capacity (veh/h)	828	800	764			
Control Delay (s)	8.1	8.1	7.9			
Approach Delay (s)	8.1	8.1	7.9			
Approach LOS	A	A	A			
Intersection Summary						
Delay			8.1			
Level of Service			A			
Intersection Capacity Utilization			31.5%	ICU Level of Service	A	
Analysis Period (min)			15			

















John Sutherland Dr/QCH West Ring Road (North)
2030 BG AM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations					 	
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	124	190	61	85	77	25
Future Volume (vph)	124	190	61	85	77	25
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	124	190	61	85	77	25
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	314	146	102			
Volume Left (vph)	0	61	77			
Volume Right (vph)	190	0	25			
Hadj (s)	-0.30	0.20	0.05			
Departure Headway (s)	4.0	4.7	4.9			
Degree Utilization, x	0.35	0.19	0.14			
Capacity (veh/h)	866	735	669			
Control Delay (s)	9.2	8.8	8.8			
Approach Delay (s)	9.2	8.8	8.8			
Approach LOS	A	A	A			
Intersection Summary						
Delay			9.0			
Level of Service			A			
Intersection Capacity Utilization			51.6%	ICU Level of Service	A	
Analysis Period (min)			15			

















John Sutherland Dr/QCH West Ring Road (North)
2030 BG PM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	87	35	8	133	191	48
Future Volume (vph)	87	35	8	133	191	48
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	87	35	8	133	191	48
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	122	141	239			
Volume Left (vph)	0	8	191			
Volume Right (vph)	35	0	48			
Hadj (s)	-0.08	0.14	0.09			
Departure Headway (s)	4.6	4.8	4.6			
Degree Utilization, x	0.16	0.19	0.31			
Capacity (veh/h)	731	706	743			
Control Delay (s)	8.4	8.9	9.7			
Approach Delay (s)	8.4	8.9	9.7			
Approach LOS	A	A	A			
Intersection Summary						
Delay			9.2			
Level of Service			A			
Intersection Capacity Utilization			35.9%	ICU Level of Service	A	
Analysis Period (min)			15			
























John Sutherland Dr/QCH Lot TL2
2030 BG AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	83	300	1	1	117	45	0	0	1	4	0	11
Future Volume (Veh/h)	83	300	1	1	117	45	0	0	1	4	0	11
Sign Control		Free			Free			Stop			Stop	
Grade		0%			0%			0%			0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	83	300	1	1	117	45	0	0	1	4	0	11
Pedestrians		5			7			2			4	
Lane Width (m)		3.7			3.7			3.7			3.7	
Walking Speed (m/s)		1.0			1.0			1.0			1.0	
Percent Blockage		1			1			0			0	
Right turn flare (veh)												
Median type		None			None							
Median storage (veh)												
Upstream signal (m)		121										
pX, platoon unblocked				0.98			0.98	0.98	0.98	0.98	0.98	
vC, conflicting volume	166			303			626	636	310	620	614	148
vC1, stage 1 conf vol												
vC2, stage 2 conf vol												
vCu, unblocked vol	166			274			605	616	281	599	593	148
tC, single (s)	4.1			4.1			7.1	6.5	6.2	7.1	6.5	6.2
tC, 2 stage (s)												
tF (s)	2.2			2.2			3.5	4.0	3.3	3.5	4.0	3.3
p0 queue free %	94			100			100	100	100	99	100	99
cM capacity (veh/h)	1406			1256			373	371	733	379	382	890
Direction, Lane #	EB 1	WB 1	NB 1	SB 1								
Volume Total	384	163	1	15								
Volume Left	83	1	0	4								
Volume Right	1	45	1	11								
cSH	1406	1256	733	654								
Volume to Capacity	0.06	0.00	0.00	0.02								
Queue Length 95th (m)	1.3	0.0	0.0	0.5								
Control Delay (s)	2.1	0.1	9.9	10.6								
Lane LOS	A	A	A	B								
Approach Delay (s)	2.1	0.1	9.9	10.6								
Approach LOS			A	B								
Intersection Summary												
Average Delay			1.8									
Intersection Capacity Utilization			48.1%	ICU Level of Service					A			
Analysis Period (min)			15									













John Sutherland Dr/QCH Lot TL2
2030 BG PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	1	119	0	3	307	2	0	0	1	14	0	73
Future Volume (Veh/h)	1	119	0	3	307	2	0	0	1	14	0	73
Sign Control		Free			Free			Stop			Stop	
Grade		0%			0%			0%			0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	1	119	0	3	307	2	0	0	1	14	0	73
Pedestrians		3			6			9			5	
Lane Width (m)		3.7			3.7			3.7			3.7	
Walking Speed (m/s)		1.0			1.0			1.0			1.0	
Percent Blockage		0			1			1			1	
Right turn flare (veh)												
Median type		None			None							
Median storage (veh)												
Upstream signal (m)		121										
pX, platoon unblocked												
vC, conflicting volume	314			128			520	450	134	447	449	316
vC1, stage 1 conf vol												
vC2, stage 2 conf vol												
vCu, unblocked vol	314			128			520	450	134	447	449	316
tC, single (s)	4.1			4.1			7.1	6.5	6.2	7.1	6.5	6.2
tC, 2 stage (s)												
tF (s)	2.2			2.2			3.5	4.0	3.3	3.5	4.0	3.3
p0 queue free %	100			100			100	100	100	97	100	90
cM capacity (veh/h)	1240			1444			409	496	901	509	496	719
Direction, Lane #	EB 1	WB 1	NB 1	SB 1								
Volume Total	120	312	1	87								
Volume Left	1	3	0	14								
Volume Right	0	2	1	73								
cSH	1240	1444	901	674								
Volume to Capacity	0.00	0.00	0.00	0.13								
Queue Length 95th (m)	0.0	0.0	0.0	3.1								
Control Delay (s)	0.1	0.1	9.0	11.1								
Lane LOS	A	A	A	B								
Approach Delay (s)	0.1	0.1	9.0	11.1								
Approach LOS			A	B								
Intersection Summary												
Average Delay			2.0									
Intersection Capacity Utilization			38.5%	ICU Level of Service					A			
Analysis Period (min)			15									

Holly Acres Rd/Richmond Rd/Nanaimo Dr
2035 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	541	8	393	21	37	91	154	936	22	26	437	18
Future Volume (vph)	541	8	393	21	37	91	154	936	22	26	437	18
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		34.0	17.0		0.0	25.0		0.0	143.0		100.0
Storage Lanes	2		1	1		1	1		0	1		1
Taper Length (m)	2.5			24.0			100.0			40.0		
Lane Util. Factor	0.97	1.00	1.00	1.00	1.00	1.00	1.00	0.95	0.95	1.00	0.95	1.00
Ped Bike Factor			0.97		0.99	0.98	1.00	1.00				0.98
Frt			0.850			0.850		0.997				0.850
Flt Protected	0.950				0.982		0.950			0.950		
Satd. Flow (prot)	3195	1784	1473	0	1734	1517	1572	3378	0	1544	3357	943
Flt Permitted	0.950				0.982		0.389			0.209		
Satd. Flow (perm)	3195	1784	1431	0	1723	1487	643	3378	0	340	3357	929
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			393			158			2			162
Link Speed (k/h)		60			40			60			60	
Link Distance (m)		88.7			195.5			655.9			232.4	
Travel Time (s)		5.3			17.6			39.4			13.9	
Confl. Peds. (#/hr)			11	11			2		1	1		2
Confl. Bikes (#/hr)			1			4						1
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	2%	5%	5%	2%	2%	10%	2%	2%	12%	3%	64%
Adj. Flow (vph)	541	8	393	21	37	91	154	936	22	26	437	18
Shared Lane Traffic (%)												
Lane Group Flow (vph)	541	8	393	0	58	91	154	958	0	26	437	18
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	97		97	97		97	97		97	97		97
Number of Detectors	1	2	1	1	2	1	1	2		1	2	1
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	2.0	10.0	2.0	2.0	10.0	2.0	2.0	10.0		2.0	10.0	2.0
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	2.0	0.6	2.0	2.0	0.6	2.0	2.0	0.6		2.0	0.6	2.0
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		9.4			9.4			9.4			9.4	
Detector 2 Size(m)		0.6			0.6			0.6			0.6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Holly Acres Rd/Richmond Rd/Nanaimo Dr
2035 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Split	NA	Perm	Split	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	4	4		3	3		5	2		1	6	
Permitted Phases			4			3	2			6		6
Detector Phase	4	4	4	3	3	3	5	2		1	6	6
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	5.0	10.0		5.0	10.0	10.0
Minimum Split (s)	28.6	28.6	28.6	16.7	16.7	16.7	11.0	30.3		11.0	30.3	30.3
Total Split (s)	45.0	45.0	45.0	20.0	20.0	20.0	12.0	33.0		12.0	33.0	33.0
Total Split (%)	40.9%	40.9%	40.9%	18.2%	18.2%	18.2%	10.9%	30.0%		10.9%	30.0%	30.0%
Yellow Time (s)	3.7	3.7	3.7	3.0	3.0	3.0	3.7	3.7		3.7	3.7	3.7
All-Red Time (s)	2.9	2.9	2.9	3.7	3.7	3.7	2.3	2.6		2.3	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.6	6.6	6.6		6.7	6.7	6.0	6.3		6.0	6.3	6.3
Lead/Lag	Lag	Lag	Lag	Lead	Lead	Lead	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None	None	None	C-Max		None	C-Max	C-Max
Act Effct Green (s)	25.2	25.2	25.2		10.6	10.6	57.8	50.0		47.9	41.0	41.0
Actuated g/C Ratio	0.23	0.23	0.23		0.10	0.10	0.53	0.45		0.44	0.37	0.37
v/c Ratio	0.74	0.02	0.62		0.35	0.32	0.36	0.62		0.12	0.35	0.04
Control Delay	45.3	29.6	7.9		52.3	3.2	19.0	29.4		18.5	29.2	0.2
Queue Delay	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	45.3	29.6	7.9		52.3	3.2	19.0	29.4		18.5	29.2	0.2
LOS	D	C	A		D	A	B	C		B	C	A
Approach Delay		29.6			22.3			27.9			27.5	
Approach LOS		C			C			C			C	
Queue Length 50th (m)	51.5	1.2	0.0		11.0	0.0	16.1	83.3		2.5	33.9	0.0
Queue Length 95th (m)	62.6	4.6	21.2		22.3	0.9	32.6	#139.3		7.9	54.4	0.0
Internal Link Dist (m)		64.7			171.5			631.9			208.4	
Turn Bay Length (m)			34.0				25.0			143.0		100.0
Base Capacity (vph)	1115	622	755		209	318	429	1536		222	1252	448
Starvation Cap Reductn	0	0	0		0	0	0	0		0	0	0
Spillback Cap Reductn	0	0	0		0	0	0	0		0	0	0
Storage Cap Reductn	0	0	0		0	0	0	0		0	0	0
Reduced v/c Ratio	0.49	0.01	0.52		0.28	0.29	0.36	0.62		0.12	0.35	0.04

Intersection Summary

Area Type: Other

Cycle Length: 110

Actuated Cycle Length: 110

Offset: 71.5 (65%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.74

Intersection Signal Delay: 28.1

Intersection LOS: C

Intersection Capacity Utilization 71.5%

ICU Level of Service C


Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.
























Queue shown is maximum after two cycles.

Holly Acres Rd/Richmond Rd/Nanaimo Dr
2035 BG AM Peak













Splits and Phases: 22: Richmond Road & Holly Acres Road/Nanaimo Drive



Holly Acres Rd/Richmond Rd/Nanaimo Dr
2035 BG PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	509	50	341	37	71	52	256	879	33	27	816	23
Future Volume (vph)	509	50	341	37	71	52	256	879	33	27	816	23
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		34.0	17.0		0.0	25.0		0.0	143.0		100.0
Storage Lanes	2		1	1		1	1		0	1		1
Taper Length (m)	2.5			24.0			100.0			40.0		
Lane Util. Factor	0.97	1.00	1.00	1.00	1.00	1.00	1.00	0.95	0.95	1.00	0.95	1.00
Ped Bike Factor			0.96		0.99	0.98	1.00	1.00				0.97
Frt			0.850			0.850		0.995				0.850
Flt Protected	0.950				0.983		0.950			0.950		
Satd. Flow (prot)	3257	1784	1473	0	1748	1517	1631	3369	0	1662	3357	1097
Flt Permitted	0.950				0.983		0.198			0.249		
Satd. Flow (perm)	3257	1784	1415	0	1736	1484	339	3369	0	436	3357	1063
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			337			158			4			162
Link Speed (k/h)		60			40			60			60	
Link Distance (m)		88.7			195.5			655.9			232.4	
Travel Time (s)		5.3			17.6			39.4			13.9	
Confl. Peds. (#/hr)			15	15			13					13
Confl. Bikes (#/hr)			5			4			4			2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	3%	2%	5%	3%	2%	2%	6%	2%	3%	4%	3%	41%
Adj. Flow (vph)	509	50	341	37	71	52	256	879	33	27	816	23
Shared Lane Traffic (%)												
Lane Group Flow (vph)	509	50	341	0	108	52	256	912	0	27	816	23
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	97		97	97		97	97		97	97		97
Number of Detectors	1	2	1	1	2	1	1	2		1	2	1
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	2.0	10.0	2.0	2.0	10.0	2.0	2.0	10.0		2.0	10.0	2.0
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	2.0	0.6	2.0	2.0	0.6	2.0	2.0	0.6		2.0	0.6	2.0
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		9.4			9.4			9.4			9.4	
Detector 2 Size(m)		0.6			0.6			0.6			0.6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Holly Acres Rd/Richmond Rd/Nanaimo Dr
2035 BG PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Split	NA	Perm	Split	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	4	4		3	3		5	2		1	6	
Permitted Phases			4			3	2			6		6
Detector Phase	4	4	4	3	3	3	5	2		1	6	6
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	5.0	10.0		5.0	10.0	10.0
Minimum Split (s)	28.6	28.6	28.6	16.7	16.7	16.7	11.0	30.3		11.0	30.3	30.3
Total Split (s)	29.0	29.0	29.0	17.0	17.0	17.0	17.0	47.0		17.0	47.0	47.0
Total Split (%)	26.4%	26.4%	26.4%	15.5%	15.5%	15.5%	15.5%	42.7%		15.5%	42.7%	42.7%
Yellow Time (s)	3.7	3.7	3.7	3.0	3.0	3.0	3.7	3.7		3.7	3.7	3.7
All-Red Time (s)	2.9	2.9	2.9	3.7	3.7	3.7	2.3	2.6		2.3	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.6	6.6	6.6		6.7	6.7	6.0	6.3		6.0	6.3	6.3
Lead/Lag	Lag	Lag	Lag	Lead	Lead	Lead	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None	None	None	Max		None	Max	Max
Act Effct Green (s)	20.8	20.8	20.8		10.2	10.2	56.9	50.1		47.4	40.7	40.7
Actuated g/C Ratio	0.19	0.19	0.19		0.09	0.09	0.52	0.46		0.44	0.38	0.38
v/c Ratio	0.82	0.15	0.63		0.65	0.18	0.83	0.58		0.10	0.65	0.05
Control Delay	53.4	37.4	10.0		67.4	1.4	39.5	24.8		13.9	31.1	0.2
Queue Delay	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	53.4	37.4	10.0		67.4	1.4	39.5	24.8		13.9	31.1	0.2
LOS	D	D	B		E	A	D	C		B	C	A
Approach Delay		36.1			46.0			28.1			29.7	
Approach LOS		D			D			C			C	
Queue Length 50th (m)	49.3	8.2	0.6		21.0	0.0	27.2	74.6		2.5	69.8	0.0
Queue Length 95th (m)	66.2	17.7	24.1		#42.6	0.0	#60.3	96.5		6.3	89.3	0.0
Internal Link Dist (m)		64.7			171.5			631.9			208.4	
Turn Bay Length (m)			34.0				25.0			143.0		100.0
Base Capacity (vph)	673	369	559		166	284	309	1559		333	1261	500
Starvation Cap Reductn	0	0	0		0	0	0	0		0	0	0
Spillback Cap Reductn	0	0	0		0	0	0	0		0	0	0
Storage Cap Reductn	0	0	0		0	0	0	0		0	0	0
Reduced v/c Ratio	0.76	0.14	0.61		0.65	0.18	0.83	0.58		0.08	0.65	0.05

Intersection Summary

Area Type: Other

Cycle Length: 110

Actuated Cycle Length: 108.4

Natural Cycle: 90

Control Type: Semi Act-Uncoord

Maximum v/c Ratio: 0.83

Intersection Signal Delay: 31.8

Intersection LOS: C

Intersection Capacity Utilization 76.5%

ICU Level of Service D

Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.










Queue shown is maximum after two cycles.

Holly Acres Rd/Richmond Rd/Nanaimo Dr
 2035 BG PM Peak













Splits and Phases: 22: Richmond Road & Holly Acres Road/Nanaimo Drive

 Ø1 17 s	 Ø2 47 s	 Ø3 17 s	 Ø4 29 s
 Ø5 17 s	 Ø6 47 s		


Richmond Rd/John Sutherland Dr
2035 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	51	0	80	0	970	88	242	576	0
Future Volume (vph)	0	0	0	51	0	80	0	970	88	242	576	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	0		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Frt					0.918				0.850			
Flt Protected					0.981					0.950		
Satd. Flow (prot)	0	1784	0	0	1579	0	1784	3390	1517	1679	3390	0
Flt Permitted					0.872					0.282		
Satd. Flow (perm)	0	1784	0	0	1403	0	1784	3390	1517	498	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					80				84			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	5%	2%	2%	2%	3%	2%	2%
Adj. Flow (vph)	0	0	0	51	0	80	0	970	88	242	576	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	131	0	0	970	88	242	576	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		0.0			0.0			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type				Perm	NA		Perm	NA	Perm	Perm	NA	
Protected Phases		4			8			2			6	


Richmond Rd/John Sutherland Dr
2035 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	6	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	10.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	29.4	29.4	
Total Split (s)	38.0	38.0		38.0	38.0		62.0	62.0	62.0	62.0	62.0	
Total Split (%)	38.0%	38.0%		38.0%	38.0%		62.0%	62.0%	62.0%	62.0%	62.0%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0			0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6			6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	C-Max	C-Max	
Act Effct Green (s)					11.5		75.5	75.5	75.5	75.5	75.5	
Actuated g/C Ratio					0.12		0.76	0.76	0.76	0.76	0.76	
v/c Ratio					0.56		0.38	0.08	0.64	0.23		
Control Delay					27.8		1.2	0.2	16.7	4.0		
Queue Delay					0.0		0.0	0.0	0.0	0.0		
Total Delay					27.8		1.2	0.2	16.7	4.0		
LOS					C		A	A	B	A		
Approach Delay					27.8		1.1			7.8		
Approach LOS					C		A			A		
Queue Length 50th (m)					8.7		2.8	0.0	15.6	12.1		
Queue Length 95th (m)					24.2		9.7	0.1	#55.8	21.7		
Internal Link Dist (m)		73.1			97.2		335.3			631.9		
Turn Bay Length (m)								35.0	40.0			
Base Capacity (vph)					495		2559	1165	376	2559		
Starvation Cap Reductn					0		0	0	0	0		
Spillback Cap Reductn					0		0	0	0	0		
Storage Cap Reductn					0		0	0	0	0		
Reduced v/c Ratio					0.26		0.38	0.08	0.64	0.23		
Intersection Summary												
Area Type:	Other											
Cycle Length: 100												
Actuated Cycle Length: 100												
Offset: 92 (92%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green												
Natural Cycle: 100												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.64												
Intersection Signal Delay: 5.6							Intersection LOS: A					
Intersection Capacity Utilization 67.0%							ICU Level of Service C					
Analysis Period (min) 15												
# 95th percentile volume exceeds capacity, queue may be longer.												
Queue shown is maximum after two cycles.												













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/John Sutherland Dr
2035 BG PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕		↗	↕	↗	↗	↕	↕
Traffic Volume (vph)	0	0	0	137	0	224	4	802	27	79	958	0
Future Volume (vph)	0	0	0	137	0	224	4	802	27	79	958	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	0		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Ped Bike Factor							1.00		0.98	1.00		
Frt					0.916				0.850			
Flt Protected					0.981		0.950			0.950		
Satd. Flow (prot)	0	1784	0	0	1594	0	1695	3390	1517	1647	3390	0
Flt Permitted					0.875		0.261			0.320		
Satd. Flow (perm)	0	1784	0	0	1421	0	465	3390	1482	554	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					66				33			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Confl. Peds. (#/hr)							2		1	1		2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	3%	2%	2%	2%	5%	2%	2%
Adj. Flow (vph)	0	0	0	137	0	224	4	802	27	79	958	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	361	0	4	802	27	79	958	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		0.0			0.0			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	

Richmond Rd/John Sutherland Dr
2035 BG PM Peak











												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Turn Type				Perm	NA		Perm	NA	Perm	Perm	NA	
Protected Phases		4			8			2			6	
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	6	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	10.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	29.4	29.4	
Total Split (s)	38.0	38.0		38.0	38.0		82.0	82.0	82.0	82.0	82.0	
Total Split (%)	31.7%	31.7%		31.7%	31.7%		68.3%	68.3%	68.3%	68.3%	68.3%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0			0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6			6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	C-Max	C-Max	
Act Effct Green (s)				28.9			78.1	78.1	78.1	78.1	78.1	
Actuated g/C Ratio				0.24			0.65	0.65	0.65	0.65	0.65	
v/c Ratio				0.92			0.01	0.36	0.03	0.22	0.43	
Control Delay				65.8			5.5	5.6	0.6	11.2	11.3	
Queue Delay				0.0			0.0	0.0	0.0	0.0	0.0	
Total Delay				65.8			5.5	5.6	0.6	11.2	11.3	
LOS				E			A	A	A	B	B	
Approach Delay				65.8			5.5				11.3	
Approach LOS				E			A				B	
Queue Length 50th (m)				62.5			0.1	14.9	0.0	6.9	52.5	
Queue Length 95th (m)				#110.4			m0.4	23.6	0.3	14.4	65.2	
Internal Link Dist (m)		73.1		97.2				335.3			631.9	
Turn Bay Length (m)							40.0		35.0	40.0		
Base Capacity (vph)				420			302	2207	976	360	2207	
Starvation Cap Reductn				0			0	0	0	0	0	
Spillback Cap Reductn				0			0	0	0	0	0	
Storage Cap Reductn				0			0	0	0	0	0	
Reduced v/c Ratio				0.86			0.01	0.36	0.03	0.22	0.43	
Intersection Summary												
Area Type:	Other											
Cycle Length: 120												
Actuated Cycle Length: 120												
Offset: 82 (68%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.92												
Intersection Signal Delay: 18.0							Intersection LOS: B					
Intersection Capacity Utilization 75.0%							ICU Level of Service D					
Analysis Period (min) 15												
# 95th percentile volume exceeds capacity, queue may be longer.												
Queue shown is maximum after two cycles.												
m Volume for 95th percentile queue is metered by upstream signal.												

Richmond Rd/John Sutherland Dr
2035 BG PM Peak













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/Robertson Rd/Baseline Rd
2035 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	364	24	172	13	903	675	177	349	69
Future Volume (vph)	0	0	0	364	24	172	13	903	675	177	349	69
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	250.0		60.0	45.0		100.0	80.0		125.0
Storage Lanes	0		0	1		1	1		1	2		1
Taper Length (m)	7.6			50.0			75.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	0.95	1.00	0.97	0.95	1.00
Frt						0.850			0.850			0.850
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	0	0	3225	1784	1473	1601	3390	1488	3195	3357	1502
Flt Permitted				0.950			0.950			0.950		
Satd. Flow (perm)	0	0	0	3225	1784	1473	1601	3390	1488	3195	3357	1502
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)						172			675			113
Link Speed (k/h)		70			70			80			80	
Link Distance (m)		130.4			357.2			405.5			359.3	
Travel Time (s)		6.7			18.4			18.2			16.2	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	4%	2%	5%	8%	2%	4%	5%	3%	3%
Adj. Flow (vph)	0	0	0	364	24	172	13	903	675	177	349	69
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	364	24	172	13	903	675	177	349	69
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors				1	2	1	1	2	1	1	2	1
Detector Template				Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Leading Detector (m)				6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5	6.1
Trailing Detector (m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)				6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8	6.1
Detector 1 Type				Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)					28.7			28.7			28.7	
Detector 2 Size(m)					1.8			1.8			1.8	
Detector 2 Type					Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)					0.0			0.0			0.0	
Turn Type				Perm	NA	Perm	Prot	NA	Perm	Prot	NA	Perm
Protected Phases					8		5	2		1	6	

Richmond Rd/Robertson Rd/Baseline Rd
2035 BG AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases				8		8			2			6
Detector Phase				8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)				10.0	10.0	10.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)				36.8	36.8	36.8	11.6	30.6	30.6	11.6	30.6	30.6
Total Split (s)				37.0	37.0	37.0	19.0	44.0	44.0	19.0	44.0	44.0
Total Split (%)				37.0%	37.0%	37.0%	19.0%	44.0%	44.0%	19.0%	44.0%	44.0%
Yellow Time (s)				4.2	4.2	4.2	4.6	4.6	4.6	4.6	4.6	4.6
All-Red Time (s)				2.6	2.6	2.6	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)				6.8	6.8	6.8	6.6	6.6	6.6	6.6	6.6	6.6
Lead/Lag							Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode				None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effect Green (s)				17.3	17.3	17.3	6.4	51.9	51.9	10.8	66.4	66.4
Actuated g/C Ratio				0.17	0.17	0.17	0.06	0.52	0.52	0.11	0.66	0.66
v/c Ratio				0.65	0.08	0.43	0.13	0.51	0.62	0.51	0.16	0.07
Control Delay				43.8	33.1	8.8	46.4	18.2	4.2	52.0	7.1	0.4
Queue Delay				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay				43.8	33.1	8.8	46.4	18.2	4.2	52.0	7.1	0.4
LOS				D	C	A	D	B	A	D	A	A
Approach Delay					32.6			12.5			19.7	
Approach LOS					C			B			B	
Queue Length 50th (m)				31.4	3.6	0.0	2.3	53.2	0.0	16.9	9.5	0.0
Queue Length 95th (m)				41.9	9.4	14.7	7.6	82.2	18.9	26.3	18.2	0.9
Internal Link Dist (m)		106.4			333.2			381.5			335.3	
Turn Bay Length (m)				250.0		60.0	45.0		100.0	80.0		125.0
Base Capacity (vph)				973	538	564	198	1758	1097	406	2229	1035
Starvation Cap Reductn				0	0	0	0	0	0	0	0	0
Spillback Cap Reductn				0	0	0	0	0	0	0	0	0
Storage Cap Reductn				0	0	0	0	0	0	0	0	0
Reduced v/c Ratio				0.37	0.04	0.30	0.07	0.51	0.62	0.44	0.16	0.07

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 93 (93%), Referenced to phase 2:NBT and 6:SBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.65

Intersection Signal Delay: 18.2


Intersection LOS: B

Intersection Capacity Utilization 60.4%






















ICU Level of Service B

Analysis Period (min) 15













Splits and Phases: 3: Robertson Road/Richmond Road & HWY 416 On-Ramp/Baseline Road



Richmond Rd/Robertson Rd/Baseline Rd
2035 BG PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	668	114	185	58	644	533	213	671	246
Future Volume (vph)	0	0	0	668	114	185	58	644	533	213	671	246
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	250.0		60.0	45.0		100.0	80.0		125.0
Storage Lanes	0		0	1		1	1		1	2		1
Taper Length (m)	7.6			50.0			75.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	0.95	1.00	0.97	0.95	1.00
Ped Bike Factor							1.00		0.99	1.00		0.98
Frt						0.850			0.850			0.850
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	0	0	3288	1767	1517	1647	3390	1517	3288	3390	1502
Flt Permitted				0.950			0.950			0.950		
Satd. Flow (perm)	0	0	0	3288	1767	1517	1643	3390	1495	3286	3390	1465
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)						185			533			246
Link Speed (k/h)		70			70			80			80	
Link Distance (m)		130.4			357.2			405.5			359.3	
Travel Time (s)		6.7			18.4			18.2			16.2	
Confl. Peds. (#/hr)							2		1	1		2
Confl. Bikes (#/hr)									1			
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	3%	2%	5%	2%	2%	2%	2%	3%
Adj. Flow (vph)	0	0	0	668	114	185	58	644	533	213	671	246
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	668	114	185	58	644	533	213	671	246
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors				1	2	1	1	2	1	1	2	1
Detector Template				Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Leading Detector (m)				6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5	6.1
Trailing Detector (m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)				6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8	6.1
Detector 1 Type				Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)					28.7			28.7			28.7	
Detector 2 Size(m)					1.8			1.8			1.8	
Detector 2 Type					Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Richmond Rd/Robertson Rd/Baseline Rd
2035 BG PM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)					0.0			0.0			0.0	
Turn Type				Perm	NA	Perm	Prot	NA	Perm	Prot	NA	Perm
Protected Phases					8		5	2		1	6	
Permitted Phases				8		8			2			6
Detector Phase				8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)				10.0	10.0	10.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)				36.8	36.8	36.8	11.6	30.6	30.6	11.6	30.6	30.6
Total Split (s)				37.0	37.0	37.0	32.0	51.0	51.0	32.0	51.0	51.0
Total Split (%)				30.8%	30.8%	30.8%	26.7%	42.5%	42.5%	26.7%	42.5%	42.5%
Yellow Time (s)				4.2	4.2	4.2	4.6	4.6	4.6	4.6	4.6	4.6
All-Red Time (s)				2.6	2.6	2.6	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)				6.8	6.8	6.8	6.6	6.6	6.6	6.6	6.6	6.6
Lead/Lag							Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode				None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effct Green (s)				28.6	28.6	28.6	9.6	58.3	58.3	13.1	64.3	64.3
Actuated g/C Ratio				0.24	0.24	0.24	0.08	0.49	0.49	0.11	0.54	0.54
v/c Ratio				0.85	0.27	0.37	0.44	0.39	0.53	0.59	0.37	0.27
Control Delay				55.0	38.6	7.3	62.3	21.3	3.9	73.1	11.2	0.9
Queue Delay				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay				55.0	38.6	7.3	62.3	21.3	3.9	73.1	11.2	0.9
LOS				E	D	A	E	C	A	E	B	A
Approach Delay					44.0			15.7			20.6	
Approach LOS					D			B			C	
Queue Length 50th (m)				70.4	19.9	0.0	12.2	46.6	0.0	24.7	22.8	0.0
Queue Length 95th (m)				90.5	34.5	16.0	24.0	63.8	17.5	m34.9	m27.9	m1.9
Internal Link Dist (m)		106.4			333.2			381.5			335.3	
Turn Bay Length (m)				250.0		60.0	45.0		100.0	80.0		125.0
Base Capacity (vph)				827	444	520	348	1646	1000	695	1815	898
Starvation Cap Reductn				0	0	0	0	0	0	0	0	0
Spillback Cap Reductn				0	0	0	0	0	0	0	0	0
Storage Cap Reductn				0	0	0	0	0	0	0	0	0
Reduced v/c Ratio				0.81	0.26	0.36	0.17	0.39	0.53	0.31	0.37	0.27
Intersection Summary												
Area Type: Other												
Cycle Length: 120												
Actuated Cycle Length: 120												
Offset: 108 (90%), Referenced to phase 2:NBT and 6:SBT, Start of Green												
Natural Cycle: 80												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.85												
Intersection Signal Delay: 25.6 Intersection LOS: C												
Intersection Capacity Utilization 63.2% ICU Level of Service B												
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Richmond Rd/Robertson Rd/Baseline Rd
2035 BG PM Peak

Splits and Phases: 3: Robertson Road/Richmond Road & HWY 416 On-Ramp/Baseline Road



Baseline Rd/Cedarview Rd
2035 BG AM Peak

							Ø7
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑	↑	↓	↑↑	↓	↑	
Traffic Volume (vph)	774	100	106	477	132	401	
Future Volume (vph)	774	100	106	477	132	401	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	45.0		20.0	0.0	
Storage Lanes		1	1		1	1	
Taper Length (m)			80.0		35.0		
Lane Util. Factor	0.95	1.00	1.00	0.95	1.00	1.00	
Ped Bike Factor		0.98			1.00		
Frt		0.850				0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3390	1517	1695	3325	1695	1517	
Flt Permitted			0.226		0.950		
Satd. Flow (perm)	3390	1482	403	3325	1693	1517	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)		95				401	
Link Speed (k/h)	70			70	50		
Link Distance (m)	357.2			373.9	442.3		
Travel Time (s)	18.4			19.2	31.8		
Confl. Peds. (#/hr)		1	1		1		
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	2%	2%	2%	4%	2%	2%	
Adj. Flow (vph)	774	100	106	477	132	401	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	774	100	106	477	132	401	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	4.9			4.9	4.9		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2	1	1	2	1	1	
Detector Template	Thru	Right	Left	Thru	Left	Right	
Leading Detector (m)	30.5	6.1	6.1	30.5	6.1	6.1	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	1.8	6.1	6.1	1.8	6.1	6.1	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)	28.7			28.7			
Detector 2 Size(m)	1.8			1.8			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Cedarview Rd
2035 BG AM Peak


	→	↘	↙	←	↖	↗	
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA	Perm	pm+pt	NA	Prot	pm+ov	
Protected Phases	2		1	6	8	1	7
Permitted Phases		2	6			8	
Detector Phase	2	2	1	6	8	1	
Switch Phase							
Minimum Initial (s)	10.0	10.0	5.0	10.0	5.0	5.0	5.0
Minimum Split (s)	27.1	27.1	11.1	27.1	36.2	11.1	34.2
Total Split (s)	34.0	34.0	15.0	49.0	45.0	15.0	36.0
Total Split (%)	26.2%	26.2%	11.5%	37.7%	34.6%	11.5%	28%
Yellow Time (s)	4.2	4.2	4.2	4.2	3.7	4.2	3.7
All-Red Time (s)	1.9	1.9	1.9	1.9	2.5	1.9	2.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.1	6.1	6.1	6.1	6.2	6.1	
Lead/Lag	Lag	Lag	Lead		Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	Max	Max	None	Max	None	None	None
Act Effct Green (s)	30.9	30.9	44.8	44.8	11.2	25.1	
Actuated g/C Ratio	0.42	0.42	0.61	0.61	0.15	0.34	
v/c Ratio	0.54	0.15	0.28	0.24	0.51	0.51	
Control Delay	21.5	6.8	12.5	10.1	38.3	5.2	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	21.5	6.8	12.5	10.1	38.3	5.2	
LOS	C	A	B	B	D	A	
Approach Delay	19.8			10.5	13.4		
Approach LOS	B			B	B		
Queue Length 50th (m)	30.6	0.3	3.7	9.4	13.7	0.0	
Queue Length 95th (m)	#105.2	12.3	23.7	45.6	40.4	19.6	
Internal Link Dist (m)	333.2			349.9	418.3		
Turn Bay Length (m)			45.0		20.0		
Base Capacity (vph)	1426	678	409	2027	934	810	
Starvation Cap Reductn	0	0	0	0	0	0	
Spillback Cap Reductn	0	0	0	0	0	0	
Storage Cap Reductn	0	0	0	0	0	0	
Reduced v/c Ratio	0.54	0.15	0.26	0.24	0.14	0.50	
Intersection Summary							
Area Type:	Other						
Cycle Length: 130							
Actuated Cycle Length: 73.4							
Natural Cycle: 110							
Control Type: Semi Act-Uncoord							
Maximum v/c Ratio: 0.54							
Intersection Signal Delay: 15.4				Intersection LOS: B			
Intersection Capacity Utilization 59.0%				ICU Level of Service B			
Analysis Period (min) 15							
# 95th percentile volume exceeds capacity, queue may be longer.							
Queue shown is maximum after two cycles.							

Baseline Rd/Cedarview Rd
2035 BG AM Peak


Splits and Phases: 6: Cedarview Road & Baseline Road



Baseline Rd/Cedarview Rd
2035 BG PM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑	↑	↓	↑↑	↓	↓	
Traffic Volume (vph)	585	178	267	856	142	152	
Future Volume (vph)	585	178	267	856	142	152	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	45.0		20.0	0.0	
Storage Lanes		1	1		1	1	
Taper Length (m)			80.0		35.0		
Lane Util. Factor	0.95	1.00	1.00	0.95	1.00	1.00	
Ped Bike Factor		0.96	0.99				
Frt		0.850				0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3357	1517	1662	3390	1601	1517	
Flt Permitted			0.381		0.950		
Satd. Flow (perm)	3357	1454	663	3390	1601	1517	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)		178				152	
Link Speed (k/h)	70			70	50		
Link Distance (m)	357.2			373.9	442.3		
Travel Time (s)	18.4			19.2	31.8		
Confl. Peds. (#/hr)		7	7				
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	4%	2%	8%	2%	
Adj. Flow (vph)	585	178	267	856	142	152	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	585	178	267	856	142	152	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	4.9			4.9	4.9		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2	1	1	2	1	1	
Detector Template	Thru	Right	Left	Thru	Left	Right	
Leading Detector (m)	30.5	6.1	6.1	30.5	6.1	6.1	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	1.8	6.1	6.1	1.8	6.1	6.1	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)	28.7			28.7			
Detector 2 Size(m)	1.8			1.8			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Cedarview Rd
2035 BG PM Peak



Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA	Perm	pm+pt	NA	Prot	pm+ov	
Protected Phases	2		1	6	8	1	7
Permitted Phases		2	6			8	
Detector Phase	2	2	1	6	8	1	
Switch Phase							
Minimum Initial (s)	10.0	10.0	5.0	10.0	5.0	5.0	5.0
Minimum Split (s)	27.1	27.1	11.1	27.1	11.2	11.1	34.2
Total Split (s)	49.0	49.0	15.0	64.0	30.0	15.0	36.0
Total Split (%)	37.7%	37.7%	11.5%	49.2%	23.1%	11.5%	28%
Yellow Time (s)	4.2	4.2	4.2	4.2	3.7	4.2	3.7
All-Red Time (s)	1.9	1.9	1.9	1.9	2.5	1.9	2.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.1	6.1	6.1	6.1	6.2	6.1	
Lead/Lag	Lag	Lag	Lead		Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	C-Max	C-Max	None	C-Max	None	None	None
Act Effect Green (s)	80.7	80.7	100.9	100.9	16.8	37.1	
Actuated g/C Ratio	0.62	0.62	0.78	0.78	0.13	0.29	
v/c Ratio	0.28	0.18	0.43	0.33	0.69	0.28	
Control Delay	12.6	2.3	6.6	5.1	70.5	5.8	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	12.6	2.3	6.6	5.1	70.5	5.8	
LOS	B	A	A	A	E	A	
Approach Delay	10.2			5.4	37.1		
Approach LOS	B			A	D		
Queue Length 50th (m)	31.5	0.0	14.3	27.1	32.5	0.0	
Queue Length 95th (m)	48.8	9.4	27.0	42.5	50.3	12.9	
Internal Link Dist (m)	333.2			349.9	418.3		
Turn Bay Length (m)			45.0		20.0		
Base Capacity (vph)	2084	970	623	2631	293	541	
Starvation Cap Reductn	0	0	0	0	0	0	
Spillback Cap Reductn	0	0	0	0	0	0	
Storage Cap Reductn	0	0	0	0	0	0	
Reduced v/c Ratio	0.28	0.18	0.43	0.33	0.48	0.28	

Intersection Summary

Area Type: Other

Cycle Length: 130

Actuated Cycle Length: 130

Offset: 15 (12%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 85

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.69

Intersection Signal Delay: 11.4


Intersection LOS: B

Intersection Capacity Utilization 56.8%






















ICU Level of Service B

Analysis Period (min) 15













Splits and Phases: 6: Cedarview Road & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
2035 BG AM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	138	1201	19	8	545	118	30	2	14	72	6	67
Future Volume (vph)	138	1201	19	8	545	118	30	2	14	72	6	67
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		0.99			0.99	
Frt			0.850			0.850		0.959			0.938	
Flt Protected	0.950			0.950				0.968			0.976	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1642	0	0	1579	0
Flt Permitted	0.449			0.198				0.767			0.819	
Satd. Flow (perm)	777	3357	1461	343	3357	1446	0	1300	0	0	1322	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			45			118		14			58	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			378.0			325.9			172.9	
Travel Time (s)		19.2			19.4			29.3			12.4	
Confl. Peds. (#/hr)	2		4	4		2	2		6	6		2
Confl. Bikes (#/hr)			1			6			2			
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	138	1201	19	8	545	118	30	2	14	72	6	67
Shared Lane Traffic (%)												
Lane Group Flow (vph)	138	1201	19	8	545	118	0	46	0	0	145	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	2.0	10.0	6.1	6.1	10.0	2.0	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	2.0	0.6	6.1	6.1	0.6	2.0	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		9.4			9.4			28.7			28.7	
Detector 2 Size(m)		0.6			0.6			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
2035 BG AM Peak






















												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Perm	NA	Perm	Perm	NA	Perm	Perm	NA		Perm	NA	
Protected Phases		2			6			8			4	
Permitted Phases	2		2	6		6	8			4		
Detector Phase	2	2	2	6	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	32.2	32.2	32.2	32.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	47.0	47.0	47.0	47.0	47.0	47.0	38.0	38.0		38.0	38.0	
Total Split (%)	55.3%	55.3%	55.3%	55.3%	55.3%	55.3%	44.7%	44.7%		44.7%	44.7%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Max	C-Max	C-Max	C-Max	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	57.1	57.1	57.1	57.1	57.1	57.1		15.2			15.2	
Actuated g/C Ratio	0.67	0.67	0.67	0.67	0.67	0.67		0.18			0.18	
v/c Ratio	0.26	0.53	0.02	0.03	0.24	0.12		0.19			0.51	
Control Delay	9.6	9.9	1.1	16.5	10.8	6.8		21.2			23.8	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	9.6	9.9	1.1	16.5	10.8	6.8		21.2			23.8	
LOS	A	A	A	B	B	A		C			C	
Approach Delay		9.7			10.1			21.2			23.8	
Approach LOS		A			B			C			C	
Queue Length 50th (m)	5.8	34.1	0.0	0.2	10.6	0.0		4.3			12.3	
Queue Length 95th (m)	25.2	94.4	1.0	m3.8	49.2	17.2		9.4			20.8	
Internal Link Dist (m)		349.9			354.0			301.9			148.9	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	522	2256	996	230	2256	1010		490			526	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.26	0.53	0.02	0.03	0.24	0.12		0.09			0.28	
Intersection Summary												
Area Type:	Other											
Cycle Length: 85												
Actuated Cycle Length: 85												
Offset: 37 (44%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.53												
Intersection Signal Delay: 11.0							Intersection LOS: B					
Intersection Capacity Utilization 70.6%							ICU Level of Service C					
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
2035 BG AM Peak













Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
2035 BG PM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	34	731	57	14	1203	56	38	4	12	94	5	92
Future Volume (vph)	34	731	57	14	1203	56	38	4	12	94	5	92
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		1.00			0.99	
Frt			0.850			0.850		0.970			0.935	
Flt Protected	0.950			0.950				0.966			0.976	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1661	0	0	1572	0
Flt Permitted	0.198			0.362				0.677			0.816	
Satd. Flow (perm)	343	3357	1456	626	3357	1446	0	1164	0	0	1309	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			57			38		12			49	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			378.0			325.9			172.9	
Travel Time (s)		19.2			19.4			29.3			12.4	
Confl. Peds. (#/hr)	3		4	4		3			9	9		
Confl. Bikes (#/hr)			5			3						3
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	34	731	57	14	1203	56	38	4	12	94	5	92
Shared Lane Traffic (%)												
Lane Group Flow (vph)	34	731	57	14	1203	56	0	54	0	0	191	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	2.0	10.0	6.1	6.1	10.0	2.0	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	2.0	0.6	6.1	6.1	0.6	2.0	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		9.4			9.4			28.7			28.7	
Detector 2 Size(m)		0.6			0.6			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
2035 BG PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Perm	NA	Perm	Perm	NA	Perm	Perm	NA		Perm	NA	
Protected Phases		2			6			8			4	
Permitted Phases	2		2	6		6	8			4		
Detector Phase	2	2	2	6	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	32.2	32.2	32.2	32.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	62.0	62.0	62.0	62.0	62.0	62.0	38.0	38.0		38.0	38.0	
Total Split (%)	62.0%	62.0%	62.0%	62.0%	62.0%	62.0%	38.0%	38.0%		38.0%	38.0%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Max	C-Max	C-Max	C-Max	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	69.1	69.1	69.1	69.1	69.1	69.1		18.2			18.2	
Actuated g/C Ratio	0.69	0.69	0.69	0.69	0.69	0.69		0.18			0.18	
v/c Ratio	0.14	0.32	0.06	0.03	0.52	0.06		0.24			0.69	
Control Delay	9.7	7.6	2.6	3.0	4.7	0.4		28.3			39.7	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	9.7	7.6	2.6	3.0	4.7	0.4		28.3			39.7	
LOS	A	A	A	A	A	A		C			D	
Approach Delay		7.3			4.5			28.3			39.7	
Approach LOS		A			A			C			D	
Queue Length 50th (m)	1.7	22.3	0.0	0.3	34.6	0.3		6.6			24.4	
Queue Length 95th (m)	8.0	47.3	4.8	m0.6	14.0	m0.0		13.7			38.0	
Internal Link Dist (m)		349.9			354.0			301.9			148.9	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	237	2320	1024	432	2320	1011		374			445	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.14	0.32	0.06	0.03	0.52	0.06		0.14			0.43	
Intersection Summary												
Area Type:	Other											
Cycle Length: 100												
Actuated Cycle Length: 100												
Offset: 77 (77%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.69												
Intersection Signal Delay: 8.9							Intersection LOS: A					
Intersection Capacity Utilization 58.6%							ICU Level of Service B					
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
2035 BG PM Peak







Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/Sandcastle Dr
2035 BG AM Peak

Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑		↵	↑↑	↵	↶	
Traffic Volume (vph)	1266	25	94	616	60	129	
Future Volume (vph)	1266	25	94	616	60	129	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	146.0		37.0	0.0	
Storage Lanes		0	1		1	1	
Taper Length (m)			26.0		75.0		
Lane Util. Factor	0.95	0.95	1.00	0.95	1.00	1.00	
Ped Bike Factor	1.00				1.00		
Frt	0.997					0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3346	0	1695	3357	1695	1488	
Flt Permitted			0.178		0.950		
Satd. Flow (perm)	3346	0	318	3357	1693	1488	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)	3					103	
Link Speed (k/h)	70			70	50		
Link Distance (m)	378.0			246.3	226.0		
Travel Time (s)	19.4			12.7	16.3		
Confl. Peds. (#/hr)		5	5		1		
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	2%	3%	2%	4%	
Adj. Flow (vph)	1266	25	94	616	60	129	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	1291	0	94	616	60	129	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	1.6			1.6	1.6		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		97	97		97	97	
Number of Detectors	2		1	2	1	1	
Detector Template	Thru		Left	Thru	Left	Right	
Leading Detector (m)	10.0		2.0	10.0	2.0	2.0	
Trailing Detector (m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Size(m)	0.6		2.0	0.6	2.0	2.0	
Detector 1 Type	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0		0.0	0.0	0.0	0.0	
Detector 2 Position(m)	9.4			9.4			
Detector 2 Size(m)	0.6			0.6			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Sandcastle Dr
2035 BG AM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA		Perm	NA	Prot	Perm	
Protected Phases	2			6	8		7
Permitted Phases			6			8	
Detector Phase	2		6	6	8	8	
Switch Phase							
Minimum Initial (s)	10.0		10.0	10.0	5.0	5.0	1.0
Minimum Split (s)	23.9		15.9	15.9	32.5	32.5	5.0
Total Split (s)	47.0		47.0	47.0	33.0	33.0	5.0
Total Split (%)	55.3%		55.3%	55.3%	38.8%	38.8%	6%
Yellow Time (s)	4.2		4.2	4.2	3.0	3.0	2.0
All-Red Time (s)	1.7		1.7	1.7	3.5	3.5	0.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.9		5.9	5.9	6.5	6.5	
Lead/Lag					Lag	Lag	Lead
Lead-Lag Optimize?							
Recall Mode	C-Max		C-Max	C-Max	None	None	None
Act Effct Green (s)	60.3		60.3	60.3	11.3	11.3	
Actuated g/C Ratio	0.71		0.71	0.71	0.13	0.13	
v/c Ratio	0.54		0.42	0.26	0.27	0.45	
Control Delay	2.3		17.7	6.4	32.9	14.2	
Queue Delay	0.0		0.0	0.0	0.0	0.0	
Total Delay	2.3		17.7	6.4	32.9	14.2	
LOS	A		B	A	C	B	
Approach Delay	2.3			7.9	20.1		
Approach LOS	A			A	C		
Queue Length 50th (m)	6.4		3.9	11.4	8.6	3.6	
Queue Length 95th (m)	9.3		#31.6	39.8	14.4	13.8	
Internal Link Dist (m)	354.0			222.3	202.0		
Turn Bay Length (m)			146.0		37.0		
Base Capacity (vph)	2373		225	2379	528	534	
Starvation Cap Reductn	0		0	0	0	0	
Spillback Cap Reductn	0		0	0	0	0	
Storage Cap Reductn	0		0	0	0	0	
Reduced v/c Ratio	0.54		0.42	0.26	0.11	0.24	

Intersection Summary

Area Type: Other

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 55 (65%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.54

Intersection Signal Delay: 5.6

Intersection LOS: A

Intersection Capacity Utilization 65.5%

ICU Level of Service C


Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.


Queue shown is maximum after two cycles.

Baseline Rd/Sandcastle Dr
2035 BG AM Peak

Splits and Phases: 5: Sandcastle Dr & Baseline Road



Baseline Rd/Sandcastle Dr
2035 BG PM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑		↵	↑↑	↵	↵	
Traffic Volume (vph)	794	43	193	1206	68	107	
Future Volume (vph)	794	43	193	1206	68	107	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	146.0		37.0	0.0	
Storage Lanes		0	1		1	1	
Taper Length (m)			26.0		75.0		
Lane Util. Factor	0.95	0.95	1.00	0.95	1.00	1.00	
Ped Bike Factor					0.99	0.98	
Frt	0.992					0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3332	0	1695	3357	1695	1488	
Flt Permitted			0.324		0.950		
Satd. Flow (perm)	3332	0	578	3357	1674	1461	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)	9					107	
Link Speed (k/h)	70			70	50		
Link Distance (m)	378.0			246.3	226.0		
Travel Time (s)	19.4			12.7	16.3		
Confl. Peds. (#/hr)					11	5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	2%	3%	2%	4%	
Adj. Flow (vph)	794	43	193	1206	68	107	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	837	0	193	1206	68	107	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	1.6			1.6	1.6		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		97	97		97	97	
Number of Detectors	2		1	2	1	1	
Detector Template	Thru		Left	Thru	Left	Right	
Leading Detector (m)	10.0		2.0	10.0	2.0	2.0	
Trailing Detector (m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Size(m)	0.6		2.0	0.6	2.0	2.0	
Detector 1 Type	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0		0.0	0.0	0.0	0.0	
Detector 2 Position(m)	9.4			9.4			
Detector 2 Size(m)	0.6			0.6			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Sandcastle Dr
2035 BG PM Peak

	→	↘	↙	←	↖	↗	
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA		Perm	NA	Perm	Perm	
Protected Phases	2			6			7
Permitted Phases			6		8	8	
Detector Phase	2		6	6	8	8	
Switch Phase							
Minimum Initial (s)	10.0		10.0	10.0	5.0	5.0	1.0
Minimum Split (s)	23.9		15.9	15.9	32.5	32.5	5.0
Total Split (s)	62.0		62.0	62.0	33.0	33.0	5.0
Total Split (%)	62.0%		62.0%	62.0%	33.0%	33.0%	5%
Yellow Time (s)	4.2		4.2	4.2	3.0	3.0	2.0
All-Red Time (s)	1.7		1.7	1.7	3.5	3.5	0.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.9		5.9	5.9	6.5	6.5	
Lead/Lag					Lag	Lag	Lead
Lead-Lag Optimize?							
Recall Mode	C-Max		C-Max	C-Max	None	None	None
Act Effct Green (s)	74.6		74.6	74.6	12.0	12.0	
Actuated g/C Ratio	0.75		0.75	0.75	0.12	0.12	
v/c Ratio	0.34		0.45	0.48	0.34	0.40	
Control Delay	4.9		11.9	7.4	42.1	11.2	
Queue Delay	0.0		0.0	0.0	0.0	0.0	
Total Delay	4.9		11.9	7.4	42.1	11.2	
LOS	A		B	A	D	B	
Approach Delay	4.9			8.0	23.2		
Approach LOS	A			A	C		
Queue Length 50th (m)	15.7		8.9	30.5	11.7	0.0	
Queue Length 95th (m)	36.3		44.5	91.3	19.3	11.3	
Internal Link Dist (m)	354.0			222.3	202.0		
Turn Bay Length (m)			146.0		37.0		
Base Capacity (vph)	2487		431	2504	443	465	
Starvation Cap Reductn	0		0	0	0	0	
Spillback Cap Reductn	0		0	0	0	0	
Storage Cap Reductn	0		0	0	0	0	
Reduced v/c Ratio	0.34		0.45	0.48	0.15	0.23	

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 62 (62%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.48

Intersection Signal Delay: 8.0


Intersection LOS: A

Intersection Capacity Utilization 58.0%


ICU Level of Service B




Analysis Period (min) 15

Splits and Phases: 5: Sandcastle Dr & Baseline Road







John Sutherland Dr/QCH West Ring Road (North)
2035 BG AM Peak













Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	26	86	151	143	39	63
Future Volume (Veh/h)	26	86	151	143	39	63
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	26	86	151	143	39	63
Pedestrians					9	
Lane Width (m)					3.7	
Walking Speed (m/s)					1.0	
Percent Blockage					1	
Right turn flare (veh)						
Median type		None	None			
Median storage veh						
Upstream signal (m)			173			
pX, platoon unblocked						
vC, conflicting volume	160				370	232
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	160				370	232
tC, single (s)	4.1				6.5	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.6	3.3
p0 queue free %	98				93	92
cM capacity (veh/h)	1406				595	800
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	112	294	102			
Volume Left	26	0	39			
Volume Right	0	143	63			
cSH	1406	1700	707			
Volume to Capacity	0.02	0.17	0.14			
Queue Length 95th (m)	0.4	0.0	3.5			
Control Delay (s)	1.9	0.0	11.0			
Lane LOS	A		B			
Approach Delay (s)	1.9	0.0	11.0			
Approach LOS			B			
Intersection Summary						
Average Delay			2.6			
Intersection Capacity Utilization			40.7%	ICU Level of Service		A
Analysis Period (min)			15			

John Sutherland Dr/QCH West Ring Road (North)
2035 BG PM Peak












Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations						
Traffic Volume (veh/h)	70	129	68	57	97	52
Future Volume (Veh/h)	70	129	68	57	97	52
Sign Control		Free	Free		Stop	
Grade		0%	0%		0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	70	129	68	57	97	52
Pedestrians					17	
Lane Width (m)					3.7	
Walking Speed (m/s)					1.0	
Percent Blockage					2	
Right turn flare (veh)						
Median type		None	None			
Median storage veh						
Upstream signal (m)			173			
pX, platoon unblocked						
vC, conflicting volume	85				382	114
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	85				382	114
tC, single (s)	4.1				6.5	6.2
tC, 2 stage (s)						
tF (s)	2.2				3.6	3.3
p0 queue free %	95				83	94
cM capacity (veh/h)	1485				563	923
Direction, Lane #	EB 1	WB 1	SB 1			
Volume Total	199	125	149			
Volume Left	70	0	97			
Volume Right	0	57	52			
cSH	1485	1700	651			
Volume to Capacity	0.05	0.07	0.23			
Queue Length 95th (m)	1.0	0.0	6.1			
Control Delay (s)	2.9	0.0	12.2			
Lane LOS	A		B			
Approach Delay (s)	2.9	0.0	12.2			
Approach LOS			B			
Intersection Summary						
Average Delay			5.1			
Intersection Capacity Utilization			40.7%	ICU Level of Service	A	
Analysis Period (min)			15			










John Sutherland Dr/QCH Irving Greenberg Cancer Center
2035 BG AM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	124	41	15	121	13	2
Future Volume (vph)	124	41	15	121	13	2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	124	41	15	121	13	2
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	165	136	15			
Volume Left (vph)	0	15	13			
Volume Right (vph)	41	0	2			
Hadj (s)	-0.04	0.16	0.13			
Departure Headway (s)	4.0	4.3	4.7			
Degree Utilization, x	0.18	0.16	0.02			
Capacity (veh/h)	879	835	717			
Control Delay (s)	7.9	8.1	7.8			
Approach Delay (s)	7.9	8.1	7.8			
Approach LOS	A	A	A			
Intersection Summary						
Delay			8.0			
Level of Service			A			
Intersection Capacity Utilization			30.3%	ICU Level of Service	A	
Analysis Period (min)			15			











John Sutherland Dr/QCH Irving Greenberg Cancer Center
2035 BG PM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	129	18	18	94	47	26
Future Volume (vph)	129	18	18	94	47	26
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	129	18	18	94	47	26
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	147	112	73			
Volume Left (vph)	0	18	47			
Volume Right (vph)	18	0	26			
Hadj (s)	0.05	0.17	-0.05			
Departure Headway (s)	4.2	4.4	4.4			
Degree Utilization, x	0.17	0.14	0.09			
Capacity (veh/h)	828	800	764			
Control Delay (s)	8.1	8.1	7.9			
Approach Delay (s)	8.1	8.1	7.9			
Approach LOS	A	A	A			
Intersection Summary						
Delay			8.1			
Level of Service			A			
Intersection Capacity Utilization			31.5%	ICU Level of Service	A	
Analysis Period (min)			15			

















John Sutherland Dr/QCH West Ring Road (North)
2035 BG AM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	124	190	61	85	77	25
Future Volume (vph)	124	190	61	85	77	25
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	124	190	61	85	77	25
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	314	146	102			
Volume Left (vph)	0	61	77			
Volume Right (vph)	190	0	25			
Hadj (s)	-0.30	0.20	0.05			
Departure Headway (s)	4.0	4.7	4.9			
Degree Utilization, x	0.35	0.19	0.14			
Capacity (veh/h)	866	735	669			
Control Delay (s)	9.2	8.8	8.8			
Approach Delay (s)	9.2	8.8	8.8			
Approach LOS	A	A	A			
Intersection Summary						
Delay			9.0			
Level of Service			A			
Intersection Capacity Utilization			51.6%	ICU Level of Service	A	
Analysis Period (min)			15			

















John Sutherland Dr/QCH West Ring Road (North)
2035 BG PM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Sign Control	Stop			Stop	Stop	
Traffic Volume (vph)	87	35	8	133	191	48
Future Volume (vph)	87	35	8	133	191	48
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	87	35	8	133	191	48
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total (vph)	122	141	239			
Volume Left (vph)	0	8	191			
Volume Right (vph)	35	0	48			
Hadj (s)	-0.08	0.14	0.09			
Departure Headway (s)	4.6	4.8	4.6			
Degree Utilization, x	0.16	0.19	0.31			
Capacity (veh/h)	731	706	743			
Control Delay (s)	8.4	8.9	9.7			
Approach Delay (s)	8.4	8.9	9.7			
Approach LOS	A	A	A			
Intersection Summary						
Delay			9.2			
Level of Service			A			
Intersection Capacity Utilization			35.9%	ICU Level of Service	A	
Analysis Period (min)			15			

John Sutherland Dr/QCH Lot TL2
2035 BG AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	83	300	1	1	117	45	0	0	1	4	0	11
Future Volume (Veh/h)	83	300	1	1	117	45	0	0	1	4	0	11
Sign Control		Free			Free			Stop			Stop	
Grade		0%			0%			0%			0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	83	300	1	1	117	45	0	0	1	4	0	11
Pedestrians		5			7			2			4	
Lane Width (m)		3.7			3.7			3.7			3.7	
Walking Speed (m/s)		1.0			1.0			1.0			1.0	
Percent Blockage		1			1			0			0	
Right turn flare (veh)												
Median type		None			None							
Median storage (veh)												
Upstream signal (m)		121										
pX, platoon unblocked				0.98			0.98	0.98	0.98	0.98	0.98	
vC, conflicting volume	166			303			626	636	310	620	614	148
vC1, stage 1 conf vol												
vC2, stage 2 conf vol												
vCu, unblocked vol	166			274			605	616	281	599	593	148
tC, single (s)	4.1			4.1			7.1	6.5	6.2	7.1	6.5	6.2
tC, 2 stage (s)												
tF (s)	2.2			2.2			3.5	4.0	3.3	3.5	4.0	3.3
p0 queue free %	94			100			100	100	100	99	100	99
cM capacity (veh/h)	1406			1256			373	371	733	379	382	890
Direction, Lane #	EB 1	WB 1	NB 1	SB 1								
Volume Total	384	163	1	15								
Volume Left	83	1	0	4								
Volume Right	1	45	1	11								
cSH	1406	1256	733	654								
Volume to Capacity	0.06	0.00	0.00	0.02								
Queue Length 95th (m)	1.3	0.0	0.0	0.5								
Control Delay (s)	2.1	0.1	9.9	10.6								
Lane LOS	A	A	A	B								
Approach Delay (s)	2.1	0.1	9.9	10.6								
Approach LOS			A	B								
Intersection Summary												
Average Delay			1.8									
Intersection Capacity Utilization			48.1%	ICU Level of Service					A			
Analysis Period (min)			15									

John Sutherland Dr/QCH Lot TL2
2035 BG PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	1	119	0	3	307	2	0	0	1	14	0	73
Future Volume (Veh/h)	1	119	0	3	307	2	0	0	1	14	0	73
Sign Control		Free			Free			Stop			Stop	
Grade		0%			0%			0%			0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	1	119	0	3	307	2	0	0	1	14	0	73
Pedestrians		3			6			9			5	
Lane Width (m)		3.7			3.7			3.7			3.7	
Walking Speed (m/s)		1.0			1.0			1.0			1.0	
Percent Blockage		0			1			1			1	
Right turn flare (veh)												
Median type		None			None							
Median storage (veh)												
Upstream signal (m)		121										
pX, platoon unblocked												
vC, conflicting volume	314			128			520	450	134	447	449	316
vC1, stage 1 conf vol												
vC2, stage 2 conf vol												
vCu, unblocked vol	314			128			520	450	134	447	449	316
tC, single (s)	4.1			4.1			7.1	6.5	6.2	7.1	6.5	6.2
tC, 2 stage (s)												
tF (s)	2.2			2.2			3.5	4.0	3.3	3.5	4.0	3.3
p0 queue free %	100			100			100	100	100	97	100	90
cM capacity (veh/h)	1240			1444			409	496	901	509	496	719
Direction, Lane #	EB 1	WB 1	NB 1	SB 1								
Volume Total	120	312	1	87								
Volume Left	1	3	0	14								
Volume Right	0	2	1	73								
cSH	1240	1444	901	674								
Volume to Capacity	0.00	0.00	0.00	0.13								
Queue Length 95th (m)	0.0	0.0	0.0	3.1								
Control Delay (s)	0.1	0.1	9.0	11.1								
Lane LOS	A	A	A	B								
Approach Delay (s)	0.1	0.1	9.0	11.1								
Approach LOS			A	B								
Intersection Summary												
Average Delay			2.0									
Intersection Capacity Utilization			38.5%	ICU Level of Service						A		
Analysis Period (min)			15									

Appendix L: TDM Checklists

TDM Measures Checklist:

Non-Residential Developments (office, institutional, retail or industrial)

Legend	
BASIC	The measure is generally feasible and effective, and in most cases would benefit the development and its users
BETTER	The measure could maximize support for users of sustainable modes, and optimize development performance
★	The measure is one of the most dependably effective tools to encourage the use of sustainable modes

TDM measures: <i>Non-residential developments</i>		Check if proposed & add descriptions
1. TDM PROGRAM MANAGEMENT		
1.1 Program coordinator		
BASIC ★	1.1.1 Designate an internal coordinator, or contract with an external coordinator	<input checked="" type="checkbox"/>
1.2 Travel surveys		
BETTER	1.2.1 Conduct periodic surveys to identify travel-related behaviours, attitudes, challenges and solutions, and to track progress	<input checked="" type="checkbox"/>
2. WALKING AND CYCLING		
2.1 Information on walking/cycling routes & destinations		
BASIC	2.1.1 Display local area maps with walking/cycling access routes and key destinations at major entrances	<input type="checkbox"/>
2.2 Bicycle skills training		
<i>Commuter travel</i>		
BETTER ★	2.2.1 Offer on-site cycling courses for commuters, or subsidize off-site courses	<input type="checkbox"/>
2.3 Valet bike parking		
<i>Visitor travel</i>		
BETTER	2.3.1 Offer secure valet bike parking during public events when demand exceeds fixed supply (e.g. for festivals, concerts, games)	<input type="checkbox"/>

TDM measures: <i>Non-residential developments</i>		Check if proposed & add descriptions
3. TRANSIT		
3.1 Transit information		
BASIC	3.1.1 Display relevant transit schedules and route maps at entrances	<input type="checkbox"/>
BASIC	3.1.2 Provide online links to OC Transpo and STO information	<input type="checkbox"/>
BETTER	3.1.3 Provide real-time arrival information display at entrances	<input checked="" type="checkbox"/>
3.2 Transit fare incentives		
<i>Commuter travel</i>		
BETTER	3.2.1 Offer preloaded PRESTO cards to encourage commuters to use transit	<input type="checkbox"/>
BETTER ★	3.2.2 Subsidize or reimburse monthly transit pass purchases by employees	<input type="checkbox"/>
<i>Visitor travel</i>		
BETTER	3.2.3 Arrange inclusion of same-day transit fare in price of tickets (e.g. for festivals, concerts, games)	<input type="checkbox"/>
3.3 Enhanced public transit service		
<i>Commuter travel</i>		
BETTER	3.3.1 Contract with OC Transpo to provide enhanced transit services (e.g. for shift changes, weekends)	<input type="checkbox"/>
<i>Visitor travel</i>		
BETTER	3.3.2 Contract with OC Transpo to provide enhanced transit services (e.g. for festivals, concerts, games)	<input type="checkbox"/>
3.4 Private transit service		
<i>Commuter travel</i>		
BETTER	3.4.1 Provide shuttle service when OC Transpo cannot offer sufficient quality or capacity to serve demand (e.g. for shift changes, weekends)	<input type="checkbox"/>
<i>Visitor travel</i>		
BETTER	3.4.2 Provide shuttle service when OC Transpo cannot offer sufficient quality or capacity to serve demand (e.g. for festivals, concerts, games)	<input type="checkbox"/>

TDM measures: <i>Non-residential developments</i>			Check if proposed & add descriptions
4. RIDESHARING			
4.1 Ridematching service			
<i>Commuter travel</i>			
BASIC	★	4.1.1 Provide a dedicated ridematching portal at OttawaRideMatch.com	<input type="checkbox"/>
4.2 Carpool parking price incentives			
<i>Commuter travel</i>			
BETTER		4.2.1 Provide discounts on parking costs for registered carpools	<input checked="" type="checkbox"/>
4.3 Vanpool service			
<i>Commuter travel</i>			
BETTER		4.3.1 Provide a vanpooling service for long-distance commuters	<input type="checkbox"/>
5. CARSHARING & BIKESHARING			
5.1 Bikeshare stations & memberships			
BETTER		5.1.1 Contract with provider to install on-site bikeshare station for use by commuters and visitors	<input checked="" type="checkbox"/>
<i>Commuter travel</i>			
BETTER		5.1.2 Provide employees with bikeshare memberships for local business travel	<input type="checkbox"/>
5.2 Carshare vehicles & memberships			
<i>Commuter travel</i>			
BETTER		5.2.1 Contract with provider to install on-site carshare vehicles and promote their use by tenants	<input type="checkbox"/>
BETTER		5.2.2 Provide employees with carshare memberships for local business travel	<input type="checkbox"/>
6. PARKING			
6.1 Priced parking			
<i>Commuter travel</i>			
BASIC	★	6.1.1 Charge for long-term parking (daily, weekly, monthly)	<input checked="" type="checkbox"/>
BASIC		6.1.2 Unbundle parking cost from lease rates at multi-tenant sites	<input type="checkbox"/>
<i>Visitor travel</i>			
BETTER		6.1.3 Charge for short-term parking (hourly)	<input checked="" type="checkbox"/>



TDM measures: <i>Non-residential developments</i>			Check if proposed & add descriptions
7. TDM MARKETING & COMMUNICATIONS			
7.1 Multimodal travel information			
<i>Commuter travel</i>			
BASIC	★	7.1.1 Provide a multimodal travel option information package to new/relocating employees and students	<input checked="" type="checkbox"/>
<i>Visitor travel</i>			
BETTER	★	7.1.2 Include multimodal travel option information in invitations or advertising that attract visitors or customers (e.g. for festivals, concerts, games)	<input checked="" type="checkbox"/>
7.2 Personalized trip planning			
<i>Commuter travel</i>			
BETTER	★	7.2.1 Offer personalized trip planning to new/relocating employees	<input type="checkbox"/>
7.3 Promotions			
<i>Commuter travel</i>			
BETTER		7.3.1 Deliver promotions and incentives to maintain awareness, build understanding, and encourage trial of sustainable modes	<input checked="" type="checkbox"/>
8. OTHER INCENTIVES & AMENITIES			
8.1 Emergency ride home			
<i>Commuter travel</i>			
BETTER	★	8.1.1 Provide emergency ride home service to non-driving commuters	<input type="checkbox"/>
8.2 Alternative work arrangements			
<i>Commuter travel</i>			
BASIC	★	8.2.1 Encourage flexible work hours	<input checked="" type="checkbox"/>
BETTER		8.2.2 Encourage compressed workweeks	<input type="checkbox"/>
BETTER	★	8.2.3 Encourage telework	<input checked="" type="checkbox"/>
8.3 Local business travel options			
<i>Commuter travel</i>			
BASIC	★	8.3.1 Provide local business travel options that minimize the need for employees to bring a personal car to work	<input type="checkbox"/>
8.4 Commuter incentives			
<i>Commuter travel</i>			
BETTER		8.4.1 Offer employees a taxable, mode-neutral commuting allowance	<input type="checkbox"/>
8.5 On-site amenities			
<i>Commuter travel</i>			
BETTER		8.5.1 Provide on-site amenities/services to minimize mid-day or mid-commute errands	<input type="checkbox"/>

TDM-Supportive Development Design and Infrastructure Checklist: *Non-Residential Developments (office, institutional, retail or industrial)*

Legend	
REQUIRED	The Official Plan or Zoning By-law provides related guidance that must be followed
BASIC	The measure is generally feasible and effective, and in most cases would benefit the development and its users
BETTER	The measure could maximize support for users of sustainable modes, and optimize development performance

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
1. WALKING & CYCLING: ROUTES		
1.1 Building location & access points		
BASIC	1.1.1 Locate building close to the street, and do not locate parking areas between the street and building entrances	<input type="checkbox"/>
BASIC	1.1.2 Locate building entrances in order to minimize walking distances to sidewalks and transit stops/stations	<input checked="" type="checkbox"/>
BASIC	1.1.3 Locate building doors and windows to ensure visibility of pedestrians from the building, for their security and comfort	<input checked="" type="checkbox"/>
1.2 Facilities for walking & cycling		
REQUIRED	1.2.1 Provide convenient, direct access to stations or major stops along rapid transit routes within 600 metres; minimize walking distances from buildings to rapid transit; provide pedestrian-friendly, weather-protected (where possible) environment between rapid transit accesses and building entrances; ensure quality linkages from sidewalks through building entrances to integrated stops/stations (<i>see Official Plan policy 4.3.3</i>)	<input checked="" type="checkbox"/>
REQUIRED	1.2.2 Provide safe, direct and attractive pedestrian access from public sidewalks to building entrances through such measures as: reducing distances between public sidewalks and major building entrances; providing walkways from public streets to major building entrances; within a site, providing walkways along the front of adjoining buildings, between adjacent buildings, and connecting areas where people may congregate, such as courtyards and transit stops; and providing weather protection through canopies, colonnades, and other design elements wherever possible (<i>see Official Plan policy 4.3.12</i>)	<input checked="" type="checkbox"/>

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
REQUIRED	1.2.3 Provide sidewalks of smooth, well-drained walking surfaces of contrasting materials or treatments to differentiate pedestrian areas from vehicle areas, and provide marked pedestrian crosswalks at intersection sidewalks (<i>see Official Plan policy 4.3.10</i>)	<input checked="" type="checkbox"/>
REQUIRED	1.2.4 Make sidewalks and open space areas easily accessible through features such as gradual grade transition, depressed curbs at street corners and convenient access to extra-wide parking spaces and ramps (<i>see Official Plan policy 4.3.10</i>)	<input checked="" type="checkbox"/>
REQUIRED	1.2.5 Include adequately spaced inter-block/street cycling and pedestrian connections to facilitate travel by active transportation. Provide links to the existing or planned network of public sidewalks, multi-use pathways and on-road cycle routes. Where public sidewalks and multi-use pathways intersect with roads, consider providing traffic control devices to give priority to cyclists and pedestrians (<i>see Official Plan policy 4.3.11</i>)	<input checked="" type="checkbox"/>
BASIC	1.2.6 Provide safe, direct and attractive walking routes from building entrances to nearby transit stops	<input checked="" type="checkbox"/>
BASIC	1.2.7 Ensure that walking routes to transit stops are secure, visible, lighted, shaded and wind-protected wherever possible	<input checked="" type="checkbox"/>
BASIC	1.2.8 Design roads used for access or circulation by cyclists using a target operating speed of no more than 30 km/h, or provide a separated cycling facility	<input type="checkbox"/>
1.3 Amenities for walking & cycling		
BASIC	1.3.1 Provide lighting, landscaping and benches along walking and cycling routes between building entrances and streets, sidewalks and trails	<input type="checkbox"/>
BASIC	1.3.2 Provide wayfinding signage for site access (where required, e.g. when multiple buildings or entrances exist) and egress (where warranted, such as when directions to reach transit stops/stations, trails or other common destinations are not obvious)	<input checked="" type="checkbox"/>

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
2. WALKING & CYCLING: END-OF-TRIP FACILITIES		
2.1 Bicycle parking		
REQUIRED	2.1.1 Provide bicycle parking in highly visible and lighted areas, sheltered from the weather wherever possible (<i>see Official Plan policy 4.3.6</i>)	<input checked="" type="checkbox"/>  Check on site plans
REQUIRED	2.1.2 Provide the number of bicycle parking spaces specified for various land uses in different parts of Ottawa; provide convenient access to main entrances or well-used areas (<i>see Zoning By-law Section 111</i>)	<input checked="" type="checkbox"/>
REQUIRED	2.1.3 Ensure that bicycle parking spaces and access aisles meet minimum dimensions; that no more than 50% of spaces are vertical spaces; and that parking racks are securely anchored (<i>see Zoning By-law Section 111</i>)	<input checked="" type="checkbox"/>
BASIC	2.1.4 Provide bicycle parking spaces equivalent to the expected number of commuter cyclists (assuming the cycling mode share target is met), plus the expected peak number of customer/visitor cyclists	<input type="checkbox"/>
BETTER	2.1.5 Provide bicycle parking spaces equivalent to the expected number of commuter and customer/visitor cyclists, plus an additional buffer (e.g. 25 percent extra) to encourage other cyclists and ensure adequate capacity in peak cycling season	<input type="checkbox"/>  Check on site plans
2.2 Secure bicycle parking		
REQUIRED	2.2.1 Where more than 50 bicycle parking spaces are provided for a single office building, locate at least 25% of spaces within a building/structure, a secure area (e.g. supervised parking lot or enclosure) or bicycle lockers (<i>see Zoning By-law Section 111</i>)	<input checked="" type="checkbox"/>
BETTER	2.2.2 Provide secure bicycle parking spaces equivalent to the expected number of commuter cyclists (assuming the cycling mode share target is met)	<input type="checkbox"/>
2.3 Shower & change facilities		
BASIC	2.3.1 Provide shower and change facilities for the use of active commuters	<input checked="" type="checkbox"/>
BETTER	2.3.2 In addition to shower and change facilities, provide dedicated lockers, grooming stations, drying racks and laundry facilities for the use of active commuters	<input type="checkbox"/>
2.4 Bicycle repair station		
BETTER	2.4.1 Provide a permanent bike repair station, with commonly used tools and an air pump, adjacent to the main bicycle parking area (or secure bicycle parking area, if provided)	<input type="checkbox"/>

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
3. TRANSIT		
3.1 Customer amenities		
BASIC	3.1.1 Provide shelters, lighting and benches at any on-site transit stops	<input checked="" type="checkbox"/>
BASIC	3.1.2 Where the site abuts an off-site transit stop and insufficient space exists for a transit shelter in the public right-of-way, protect land for a shelter and/or install a shelter	<input type="checkbox"/>
BETTER	3.1.3 Provide a secure and comfortable interior waiting area by integrating any on-site transit stops into the building	<input type="checkbox"/>
4. RIDESHARING		
4.1 Pick-up & drop-off facilities		
BASIC	4.1.1 Provide a designated area for carpool drivers (plus taxis and ride-hailing services) to drop off or pick up passengers without using fire lanes or other no-stopping zones	<input checked="" type="checkbox"/>
4.2 Carpool parking		
BASIC	4.2.1 Provide signed parking spaces for carpools in a priority location close to a major building entrance, sufficient in number to accommodate the mode share target for carpools	<input type="checkbox"/>
BETTER	4.2.2 At large developments, provide spaces for carpools in a separate, access-controlled parking area to simplify enforcement	<input type="checkbox"/>
5. CARSHARING & BIKESHARING		
5.1 Carshare parking spaces		
BETTER	5.1.1 Provide carshare parking spaces in permitted non-residential zones, occupying either required or provided parking spaces (<i>see Zoning By-law Section 94</i>)	<input type="checkbox"/>
5.2 Bikeshare station location		
BETTER	5.2.1 Provide a designated bikeshare station area near a major building entrance, preferably lighted and sheltered with a direct walkway connection	<input type="checkbox"/>

TDM-supportive design & infrastructure measures: <i>Non-residential developments</i>		Check if completed & add descriptions, explanations or plan/drawing references
6. PARKING		
6.1 Number of parking spaces		
REQUIRED	6.1.1 Do not provide more parking than permitted by zoning, nor less than required by zoning, unless a variance is being applied for	<input checked="" type="checkbox"/>
BASIC	6.1.2 Provide parking for long-term and short-term users that is consistent with mode share targets, considering the potential for visitors to use off-site public parking	<input type="checkbox"/>
BASIC	6.1.3 Where a site features more than one use, provide shared parking and reduce the cumulative number of parking spaces accordingly (<i>see Zoning By-law Section 104</i>)	<input type="checkbox"/>
BETTER	6.1.4 Reduce the minimum number of parking spaces required by zoning by one space for each 13 square metres of gross floor area provided as shower rooms, change rooms, locker rooms and other facilities for cyclists in conjunction with bicycle parking (<i>see Zoning By-law Section 111</i>)	<input type="checkbox"/>
6.2 Separate long-term & short-term parking areas		
BETTER	6.2.1 Separate short-term and long-term parking areas using signage or physical barriers, to permit access controls and simplify enforcement (i.e. to discourage employees from parking in visitor spaces, and vice versa)	<input type="checkbox"/>
7. OTHER		
7.1 On-site amenities to minimize off-site trips		
BETTER	7.1.1 Provide on-site amenities to minimize mid-day or mid-commute errands	<input type="checkbox"/>

Appendix M: Detailed Parking Calculations

Part 4 Expansion Parking Calculations - If Existing Modal Shares Persist

Existing Modal Shares		
Employees	Planned	Emerg
80%	80%	95%

Part 4 Modal Shares		
Employees	Planned	Emerg
80%	80%	95%

Hospital Stats			Notes	
	Existing	Part 4		
GFA ft ²	637,444	1,023,388		
No of Beds	287	444		
Full Time Employees	1337	2066		
Total Visitors - Annual	331,331	450,934		
Planned	250,264	354,856		
Emerg	81,067	96,078		
%growth from existing	-	136		
Total Visitors - Daily	1044	1421	1.15	Daily = (Annual/365) + 15% for daily variation
Planned	789	1118		
Emerg	255	303		
Approx. Total Parking	1320	1760		
Approx. Emp Parking	912	1321		
Approx. Visitor Parking	408	439		

Estimated Auto Drivers				
	Employees	Planned	Emerg	Total
Existing	1070	631	242	1943
Part 4	1653	894	288	2835

Parking/D river Ratio
0.68
0.62

If existing ratio is maintained, how much is the demand
1321.24
1927.8

Part 4 Expansion Parking Calculations - If Target Modal Shares are Met

Existing Modal Shares		
Employees	Planned	Emerg
80%	80%	95%

Part 4 Modal Shares		
Employees	Planned	Emerg
65%	65%	95%

Hospital Stats			Notes	
	Existing	Part 4		
GFA ft ²	637,444	1,023,388		
No of Beds	287	444		
Full Time Employees	1337	2066		
Total Visitors - Annual	331,331	450,934		
Planned	250,264	354,856		
Emerg	81,067	96,078		
%growth from existing	-	136		
Total Visitors - Daily	1044	1421	1.15	Daily = (Annual/365) + 15% for daily variation
Planned	789	1118		
Emerg	255	303		
Approx. Total Parking	1320	1760		
Approx. Emp Parking	912	1321		
Approx. Visitor Parking	408	439		

Estimated Auto Drivers				
	Employees	Planned	Emerg	Total
Existing	1070	631	242	1943
Part 4	1343	727	288	2358

Parking/D river Ratio
0.68
0.75

If existing ratio is maintained, how much is the demand
1321.24
1603.44

Appendix N: Detailed MMLoS Analysis

1.0 SEGMENT MMLOS

1.1.1 Pedestrian Level of Service (PLOS)

Exhibit 4 of the MMLOS guidelines has been used to evaluate the segment PLOS of Richmond Road, and Baseline Road. Target PLOS are based on the targets for an Arterial Road under other designated land uses, as listed in the Exhibit 22 of the MMLOS guidelines. The results of the segment PLOS analysis are summarized in **Table 1**.

Table 1: Segment PLOS

Sidewalk Width (m)	Boulevard Width (m)	Avg. Daily Curb Lane Traffic Volume	Presence of On-Street Parking	Operating Speed ¹	Segment PLOS	Target PLOS
Baseline Road (North Curb) (MUP)						
> 2.0	>2.0	> 3000	No	80 km/h	D	D
Baseline Road (South Curb)						
2.0	0.0	> 3000	No	80 km/h	F	D
Richmond Road (East Curb)						
1.8 (paved shoulder)	0.0	> 3000	No	90 km/h	F → F ²	D
Richmond Road (West Curb)						
1.8 (paved shoulder)	0.0	> 3000	No	90 km/h	F → F ²	D

1. Operating Speed = Posted Speed + 10 kmph.

2. Downgraded by one level in case of a paved shoulder.

1.1.2 Bicycle Level of Service (BLOS)

Exhibit 11 of the MMLOS guidelines has been used to evaluate the segment BLOS of Richmond Road and Baseline Road. Target BLOS are based on the targets for an Arterial Road under other designated land uses, as listed in the Exhibit 22 of the MMLOS guidelines. The results of the segment BLOS analysis are summarized in **Table 2**.

Table 2: Segment BLOS

Road Class	Route Type	Type of Bikeway	No. of Travel Lanes in each direction	Operating Speed	Bike Lane Width	Bike Lane Blockage	Segment BLOS	Target BLOS
Richmond Road								
Arterial Road	Cross-town Bikeway	Bike Lanes	2	90 km/h	>1.8m	Rare	E	B
Baseline Road								
Arterial Road	Local Route	Bike Lanes	2	80 km/h	1.6m	Rare	E	C

1.1.3 Transit Level of Service (TLOS)

Exhibit 15 of the MMLOS guidelines has been used to evaluate the segment TLOS of Richmond Road and Baseline Road. Target TLOS are based on the targets for an Arterial Road under other

designated land uses, as listed in the Exhibit 22 of the MMLOS guidelines. The results of the segment TLOS analysis are summarized in **Table 3**.

Table 3: Segment TLOS

Facility Type	Congestion	Frictions	Incident Potential	Segment TLOS	Target BLOS
Richmond Road					
Mixed Traffic	Yes	Low	Medium	D	D
Baseline Road					
Mixed Traffic	Yes	Low	Medium	D	D

1.1.4 Truck Level of Service (TkLOS)

Exhibit 20 of the MMLOS guidelines has been used to evaluate the segment TkLOS of Richmond Road and Baseline Road. Target TLOS are based on the targets for an Arterial Road under other designated land uses, as listed in the Exhibit 22 of the MMLOS guidelines. The results of the segment TkLOS analysis are summarized in **Table 4**.

Table 4: Segment TkLOS

Curb Lane Width	Number of Travel Lanes per Direction	Segment TkLOS	Target TkLOS
Richmond Road			
≤ 3.5m	2	A	D
Baseline Road			
≤ 3.5m	2	A	D

2.0 INTERSECTION MMLOS

2.1.1 Pedestrian Level of Service (PLOS)

Exhibit 5 of the MMLOS guidelines has been used to evaluate the intersection PLOS at Baseline Road/John Sutherland Drive/Valley Stream Drive, Baseline Road/Cedarview Road, Baseline Road/Richmond Road/Robertson Road, and Richmond Road/John Sutherland Drive. Target PLOS are based on the targets for an Arterial Road under other designated land uses, as listed in the Exhibit 22 of the MMLOS guidelines. The results of the intersection PLOS analysis are shown in **Figure 1 to Figure 6**.

Figure 1: Baseline Road/Sandcastle Drive PLOS

Criteria	North Approach	South Approach	East Approach	West Approach				
Baseline Road/Sandcastle Drive								
PETS I SCORE								
CROSSING DISTANCE CONDITIONS								
Median > 2.4m in Width	N/A	No	72	No	23	No	23	
Lanes Crossed (3.5m Lane Width)		5		8		8		
SIGNAL PHASING AND TIMING								
Left Turn Conflict	N/A	Permissive	-8	No Left Turn/Prohibited	0	Permissive	-8	
Right Turn Conflict		Permissive or Yield	-5	Permissive or Yield	-5	No Right Turn/Prohibited	0	
Right Turn on Red		RTOR Allowed	-3	N/A	0	RTOR Allowed	-3	
Leading Pedestrian Interval		No	-2	Yes	0	Yes	0	
CORNER RADIUS								
Parallel Radius	N/A	> 5m to 10m	-5	> 5m to 10m	-5	No Right Turn	0	
Parallel Right Turn Channel		No Right Turn Channel	-4	No Right Turn Channel	-4	No Right Turn	0	
Perpendicular Radius		N/A	0	N/A	0	N/A	0	
Perpendicular Right Turn Channel		N/A	0	N/A	0	N/A	0	
CROSSING TREATMENT								
Treatment	N/A	N/A	Standard	-7	Standard	-7	Standard	-7
PETS I SCORE			38	2	5			
LOS			E	F	F			
DELAY SCORE								
Cycle Length	N/A		100		100		100	
Pedestrian Walk Time			45.1		7.5		7.5	
DELAY SCORE		15.1	42.8	42.8				
LOS		B	E	E				
OVERALL		N/A	E	F	F			

Figure 2: Baseline Road/John Sutherland Drive/Valley Stream Drive PLOS

Criteria	North Approach		South Approach		East Approach		West Approach	
Baseline Road/John Sutherland Drive/Valley Stream Drive								
PETSI SCORE								
CROSSING DISTANCE CONDITIONS								
Median > 2.4m in Width	No	23	No	39	No	6	No	-10
Lanes Crossed (3.5m Lane Width)	8		7		9		10 +	
SIGNAL PHASING AND TIMING								
Left Turn Conflict	Permissive	-8	Permissive	-8	Permissive	-8	Permissive	-8
Right Turn Conflict	Permissive or Yield	-5	Permissive or Yield	-5	Permissive or Yield	-5	Permissive or Yield	-5
Right Turn on Red	N/A	0	RTOR Allowed	-3	N/A	0	RTOR Allowed	-3
Leading Pedestrian Interval	No	-2	No	-2	No	-2	No	-2
CORNER RADIUS								
Parallel Radius	> 15m to 25m	-8	> 10m to 15m	-6	N/A	0	> 15m to 25m	-8
Parallel Right Turn Channel	Conventional without Receiving	0	No Right Turn Channel	-4		0	Conventional with Receiving	-3
Perpendicular Radius	> 15m to 25m	-8	N/A	0	> 15m to 25m	-8	N/A	0
Perpendicular Right Turn Channel	Conventional with Receiving	-3	N/A	0	Conventional without Receiving	0	N/A	0
CROSSING TREATMENT								
Treatment	Standard	-7	Standard	-7	Standard	-7	Standard	-7
PETSI SCORE		-18	4		-24		-46	
LOS		F	F		F		F	
DELAY SCORE								
Cycle Length	85		85		100		100	
Pedestrian Walk Time	21.8		21.8		7.5		7.5	
DELAY SCORE		23.5	23.5		42.8		42.8	
LOS		C	C		E		E	
OVERALL		F	F		F		F	

Figure 3: Baseline Road/Cedarview Road PLOS

Criteria	North Approach		South Approach		East Approach		West Approach		
Baseline Road/Cedarview Road									
PETSİ SCORE									
CROSSİNG DISTANCE CONDITIONS									
Median > 2.4m in Width	N/A	FALSE	No	55	No	23	No	23	
Lanes Crossed (3.5m Lane Width)			6		8		8		
SİGNAL PHASİNG AND TIMİNG									
Left Turn Conflict	N/A	N/A	Perm + Prot	-8	No Left Turn/Prohibited	0	Protected	0	
Right Turn Conflict			Permissive or Yield	-5	Perm + Prot	-5	No Right Turn/Prohibited	0	
Right Turn on Red			RTOR Allowed	-3	N/A	0	N/A	0	
Leading Pedestrian Interval			No	-2	Yes	0	Yes	0	
CORNİER RADİUS									
Parallel Radius	N/A	N/A	> 25m	-9	N/A	0	No Right Turn	0	
Parallel Right Turn Channel			onventional without Receivir	0	N/A	0	No Right Turn	0	
Perpendicular Radius			N/A	0	N/A	0	> 25m	-9	
Perpendicular Right Turn Channel			N/A	0	N/A	0	onventional without Receivir	0	
CROSSİNG TREATMENT									
Treatment	N/A	N/A	Zebra Stripe	-4	Zebra Stripe	-4	Zebra Stripe	-4	
PETSİ SCORE				24		14		10	
LOS				F		F		F	
DELAY SCORE									
Cycle Length	N/A			130		130		130	
Pedestrian Walk Time				13.9		6.8		6.8	
DELAY SCORE				51.8		58.4		58.4	
LOS				E		E		E	
OVERALL		N/A		F		F		F	

Figure 4: Baseline Road/Richmond Road/Robertson Road/HWY416 ON-Ramp PLOS

Criteria	North Approach		South Approach		East Approach		West Approach	
Baseline Road/Richmond Road/Robertson Road/HWY416 ON-Ramp								
PETSİ SCORE								
CROSSING DISTANCE CONDITIONS								
Median > 2.4m in Width	No	6	N/A	No	-10	No	105	
Lanes Crossed (3.5m Lane Width)	9			10 +		3		
SIGNAL PHASING AND TIMING								
Left Turn Conflict	No Left Turn/Prohibited	0	N/A	Protected	0	Protected	0	
Right Turn Conflict	Permissive or Yield	-5		Permissive or Yield	-5	No Right Turn/Prohibited	0	
Right Turn on Red	N/A	0		N/A	0	N/A	0	
Leading Pedestrian Interval	No	-2		No	-2	No	-2	
CORNER RADIUS								
Parallel Radius	> 25m	-9	N/A	> 25m	-9	No Right Turn	0	
Parallel Right Turn Channel	Conventional with Receiving	-3		Conventional with Receiving	-3	No Right Turn	0	
Perpendicular Radius	N/A	0		N/A	0	N/A	0	
Perpendicular Right Turn Channel	N/A	0		N/A	0	N/A	0	
CROSSING TREATMENT								
Treatment	Standard	-7	N/A	Standard	-7	Standard	-7	
PETSİ SCORE		-20		-36	96			
LOS		F		F	A			
DELAY SCORE								
Cycle Length		120	N/A		120		120	
Pedestrian Walk Time		11.2			27.4		27.4	
DELAY SCORE		49.3			35.7		35.7	
LOS		E			D		D	
OVERALL		F		N/A	F		D	

Figure 5: Richmond Road/John Sutherland Drive PLOS

Criteria	North Approach		South Approach		East Approach		West Approach	
Richmond Road/John Sutherland Drive								
PETSI SCORE								
CROSSING DISTANCE CONDITIONS								
Median > 2.4m in Width	No	23	No	23	No	39	No	88
Lanes Crossed (3.5m Lane Width)	8		8		7		4	
SIGNAL PHASING AND TIMING								
Left Turn Conflict	Permissive	-8	Permissive	-8	Permissive	-8	Permissive	-8
Right Turn Conflict	Permissive or Yield	-5	Permissive or Yield	-5	Permissive or Yield	-5	Permissive or Yield	-5
Right Turn on Red	RTOR Allowed	-3	RTOR Allowed	-3	RTOR Allowed	-3	RTOR Allowed	-3
Leading Pedestrian Interval	No	-2	No	-2	No	-2	No	-2
CORNER RADIUS								
Parallel Radius	> 10m to 15m	-6	> 10m to 15m	-6	> 10m to 15m	-6	> 5m to 10m	-5
Parallel Right Turn Channel	No Right Turn Channel	-4	No Right Turn Channel	-4	No Right Turn Channel	-4	No Right Turn Channel	-4
Perpendicular Radius	N/A	0	N/A	0	N/A	0	N/A	0
Perpendicular Right Turn Channel	N/A	0	N/A	0	N/A	0	N/A	0
CROSSING TREATMENT								
Treatment	Standard	-7	Standard	-7	Standard	-7	Standard	-7
PETSI SCORE		-12	PETSI SCORE		-12	PETSI SCORE		54
LOS		F	LOS		F	LOS		D
DELAY SCORE								
Cycle Length		120		120		100		100
Pedestrian Walk Time		7.4		7.4		39.6		39.6
DELAY SCORE		52.8	DELAY SCORE		52.8	DELAY SCORE		18.2
LOS		E	LOS		E	LOS		B
OVERALL		F	OVERALL		F	OVERALL		D

Figure 6: Richmond Rd/Holly Acres Rd/Nanaimo Drive PLOS

Criteria	North Approach		South Approach		East Approach		West Approach	
Richmond Road/Holly Acres Road/Nanaimo Drive								
PETSI SCORE								
CROSSING DISTANCE CONDITIONS								
Median > 2.4m in Width	N/A	N/A	No	-10	No	39	No	-10
Lanes Crossed (3.5m Lane Width)			10 +		7		10 +	
SIGNAL PHASING AND TIMING								
Left Turn Conflict	N/A	N/A	Protected	0	Perm + Prot	-8	Perm + Prot	-8
Right Turn Conflict			Permissive or Yield	-5	Permissive or Yield	-5	Permissive or Yield	-5
Right Turn on Red			RTOR Allowed	-3	RTOR Allowed	-3	N/A	0
Leading Pedestrian Interval			No	-2	No	-2	No	-2
CORNER RADIUS								
Parallel Radius	N/A	N/A	> 15m to 25m	-8	> 10m to 15m	-6	> 10m to 15m	-6
Parallel Right Turn Channel			onventional without Receiver	0	No Right Turn Channel	-4	No Right Turn Channel	-4
Perpendicular Radius			N/A	0	N/A	0	> 15m to 25m	-8
Perpendicular Right Turn Channel			N/A	0	N/A	0	onventional without Receiver	0
CROSSING TREATMENT								
Treatment	N/A	N/A	Standard	-7	Standard	-7	Standard	-7
PETSI SCORE				-35		4		-50
LOS				F		F		F
DELAY SCORE								
Cycle Length		N/A		110		110		110
Pedestrian Walk Time				7.4		9.7		9.7
DELAY SCORE				47.8		45.7		45.7
LOS				E		E		E
OVERALL		N/A		F		F		F

2.1.2 Bicycle Level of Service (BLOS)

Exhibit 12 of the MMLOS guidelines has been used to evaluate the intersection BLOS at Baseline Road/John Sutherland Drive/Valley Stream Drive, Baseline Road/Cedarview Road, Baseline Road/Richmond Road/Robertson Road, and Richmond Road/John Sutherland Drive. Target BLOS are based on the targets for an Arterial Road under other designated land uses, as listed in the Exhibit 22 of the MMLOS guidelines. The results of the intersection BLOS analysis are summarized in **Table 5**.

Table 5: Intersection BLOS

Approach	Bikeway Facility Type	Criteria	Travel Lanes and/or Speed	BLOS
Baseline Road/Sandcastle Drive				
North Approach	-	Right Turn Lane Characteristics	-	-
		Left Turn Accommodation	-	-
South Approach	Mixed Traffic	Right Turn Lane Characteristics	Right-turn Lane 25 to 50m long, turning speed ≤25kmph	D
		Left Turn Accommodation	1 lane crossed, 50kmph	D
East Approach	Bike Lane	Right Turn Lane Characteristics	No impact on LTS	A
		Left Turn Accommodation	2 or more lanes crossed, ≥50kmph	F
West Approach	Bike Lane	Right Turn Lane Characteristics	No impact on LTS	A
		Left Turn Accommodation	-	-
Baseline Road/John Sutherland Drive/Valley Stream Drive				
North Approach	Mixed Traffic	Right Turn Lane Characteristics	Right-turn Lane 25 to 50m long, turning speed >25kmph	E
		Left Turn Accommodation	No lanes crossed, ≤50kmph	B
South Approach	Mixed Traffic	Right Turn Lane Characteristics	Right-turn Lane 25 to 50m long, turning speed ≤25kmph	D
		Left Turn Accommodation	1 lane crossed, 50kmph	D
East Approach	Bike Lane	Right Turn Lane Characteristics	Right-turn Lane introduced to the right of the bike lane >50m long, turning speed ≤30kmph	D
		Left Turn Accommodation	Two or more lanes crossed, >60kmph	F
West Approach	Bike Lane	Right Turn Lane Characteristics	Right-turn Lane introduced to the right of the bike lane >50m long, turning speed ≤25kmph	B
		Left Turn Accommodation	Two or more lanes crossed, >60kmph	F
Baseline Road/Cedarview Road				
North Approach	MUP	Right Turn Lane Characteristics	No impact on LTS	A
		Left Turn Accommodation	Crossride	A
South Approach	Mixed Traffic	Right Turn Lane Characteristics	No impact on LTS	A
		Left Turn Accommodation	Crossride	A

Approach	Bikeway Facility Type	Criteria	Travel Lanes and/or Speed	BLOS
East Approach	Mixed Traffic	Right Turn Lane Characteristics	No impact on LTS	A
		Left Turn Accommodation	Two-stage left-turn, ≤50kmph	A
West Approach	Mixed Traffic	Right Turn Lane Characteristics	Right-turn Lane introduced to the right of the bike lane >50m long, turning speed ≤30kmph	D
		Left Turn Accommodation	Two-stage left-turn, ≤50kmph	A
Baseline Road/Richmond Road/Robertson Road/HWY416 ON-Ramp				
North Approach	Bike Lane	Right Turn Lane Characteristics	Right-turn Lane introduced to the right of the bike lane >50m long, turning speed ≤30kmph	D
		Left Turn Accommodation	2 or more lanes crossed, ≥50kmph	F
South Approach	Mixed Traffic	Right Turn Lane Characteristics	Right-turn Lane longer than 50m	F
		Left Turn Accommodation	-	-
East Approach	Bike Lane	Right Turn Lane Characteristics	Right-turn Lane introduced to the right of the bike lane >50m long, turning speed ≤30kmph	D
		Left Turn Accommodation	No lane crossed, ≤50kmph	B
West Approach	-	Right Turn Lane Characteristics	-	-
		Left Turn Accommodation	-	-
Richmond Road/John Sutherland Drive				
North Approach	Bike Lane	Right Turn Lane Characteristics	No impact to LTS	A
		Left Turn Accommodation	2 or more lanes crossed, ≥50kmph	F
South Approach	Bike Lane	Right Turn Lane Characteristics	Right-turn Lane introduced to the right of the bike lane >50m long, turning speed ≤30kmph	D
		Left Turn Accommodation	2 or more lanes crossed, ≥50kmph	F
East Approach	Mixed Traffic	Right Turn Lane Characteristics	No impact to LTS	A
		Left Turn Accommodation	No lane crossed, ≤50kmph	B
West Approach	Mixed Traffic	Right Turn Lane Characteristics	No impact to LTS	A
		Left Turn Accommodation	No lane crossed, ≤50kmph	B

Approach	Bikeway Facility Type	Criteria	Travel Lanes and/or Speed	BLOS
Richmond Road/Holly Acres Road/Nanaimo Drive				
North Approach	Pocket Bike Lane	Right Turn Lane Characteristics	Right-turn Lane introduced to the right of the bike lane >50m long, turning speed ≤30kmph	D
		Left Turn Accommodation	2 or more lanes crossed, ≥50kmph	F
South Approach	Bike Lane	Right Turn Lane Characteristics	No impact to LTS	A
		Left Turn Accommodation	2 or more lanes crossed, ≥50kmph	F
East Approach	Mixed Traffic	Right Turn Lane Characteristics	No impact to LTS	A
		Left Turn Accommodation	1 lane crossed, 50kmph	D
West Approach	Pocket Bike Lane	Right Turn Lane Characteristics	Right-turn Lane introduced to the right of the bike lane >50m long, turning speed ≤30kmph	D
		Left Turn Accommodation	2 or more lanes crossed, ≥50kmph	F

2.1.3 Transit Level of Service (TLOS)

Exhibit 16 of the MMLOS guidelines has been used to evaluate the intersection TLOS at Baseline Road/John Sutherland Drive/Valley Stream Drive, Baseline Road/Cedarview Road, Baseline Road/Richmond Road/Robertson Road, and Richmond Road/John Sutherland Drive. Target TLOS are based on the targets for an Arterial Road under other designated land uses, as listed in the Exhibit 22 of the MMLOS guidelines. The results of the intersection TLOS analysis are summarized in **Table 6**.

Table 6: Intersection TLOS

Approach	Facility Type	Delay ¹		TLOS
		AM Peak (TLOS)	PM Peak (TLOS)	
Baseline Road/Sandcastle Drive				
North Approach	-	-	-	-
South Approach	No Transit Route	-	-	-
East Approach	Mixed Traffic (No TSP)	6 sec. (B)	7 sec. (B)	B
West Approach	Mixed Traffic (No TSP)	4 sec. (B)	4 sec. (B)	B
Baseline Road/John Sutherland Drive/Valley Stream Drive				
North Approach	Mixed Traffic (No TSP)	26 sec. (D)	43 sec. (F)	F
South Approach	No Transit Route	-	-	-
East Approach	Mixed Traffic (No TSP)	6 sec. (B)	10 sec. (B)	B
West Approach	Mixed Traffic (No TSP)	10 sec. (B)	8 sec. (B)	B
Baseline Road/Cedarview Road				
North Approach	N/A	-	-	-
South Approach	No Transit Route	-	-	-
East Approach	Mixed Traffic (No TSP)	10 sec. (B)	5 sec. (B)	B
West Approach	Mixed Traffic (No TSP)	20 sec. (C)	9 sec. (B)	C
Baseline Road/Richmond Road/Robertson Road/HWY416 ON-Ramp				
North Approach	Mixed Traffic (No TSP)	20 sec. (C)	21 sec. (D)	D
South Approach	Mixed Traffic (No TSP)	13 sec. (C)	16 sec. (C)	C
East Approach	Mixed Traffic (No TSP)	33 sec. (E)	45 sec. (F)	F
West Approach	N/A	-	-	-
Richmond Road/John Sutherland Drive				
North Approach	Mixed Traffic (No TSP)	10 sec. (B)	12 sec (C)	C
South Approach	Mixed Traffic (No TSP)	1 sec. (B)	6 sec. (B)	B
East Approach	Mixed Traffic (No TSP)	30 sec. (D)	74 sec. (F)	F
West Approach	No Transit Route	-	-	-

Approach	Facility Type	Delay ¹		TLOS
		AM Peak (TLOS)	PM Peak (TLOS)	
Richmond Road/Holly Acres Road/Nanaimo Drive				
North Approach	Mixed Traffic (No TSP)	30 sec. (D)	30 sec. (D)	D
South Approach	Mixed Traffic (No TSP)	31 sec. (E)	30 sec. (D)	E
East Approach	No Transit Route	-	-	-
West Approach	Mixed Traffic (No TSP)	29 sec. (D)	38 sec. (E)	E

1. Delay based on the approach delay in Synchro analysis of existing conditions (mixed traffic).

2.1.4 Truck Level of Service (TkLOS)

Exhibit 21 of the MMLOS guidelines has been used to evaluate the intersection PLOS at Baseline Road/John Sutherland Drive/Valley Stream Drive, Baseline Road/Cedarview Road, Baseline Road/Richmond Road/Robertson Road, and Richmond Road/John Sutherland Drive. Target TLOS are based on the targets for an Arterial Road under other designated land uses, as listed in the Exhibit 22 of the MMLOS guidelines. The results of the segment TkLOS analysis are summarized in **Table 7**.





























Table 7: Intersection TkLOS

Approach	Effective Corner Radius	Number of Receiving Lanes on Departure from Intersection	TkLOS
Baseline Road/Sandcastle Drive			
North Approach	N/A	-	-
South Approach	<10m	More than one	D
East Approach	N/A	-	-
West Approach	<10m	One	F
Baseline Road/John Sutherland Drive/Valley Stream Drive			
North Approach	>15m	More than one	A
South Approach	>15m	More than one	A
East Approach	>15m	One	C
West Approach	10-15m	One	E
Baseline Road/Cedarview Road			
North Approach	N/A	-	-
South Approach	10-15m	More than one	B
East Approach	N/A	-	-
West Approach	>15m	One	C
Baseline Road/Richmond Road/Robertson Road			
North Approach	>15m	One	C
South Approach	>15m	More than one	A
East Approach	>15m	More than one	A
West Approach	N/A	-	-
Richmond Road/John Sutherland Drive			
North Approach	10-15m	One	E
South Approach	10-15m	One	E
East Approach	>15m	More than one	A













Approach	Effective Corner Radius	Number of Receiving Lanes on Departure from Intersection	TkLOS
West Approach	>15m	More than one	A
Richmond Road/Holly Acres Road/Nanaimo Drive			
North Approach	10-15m	More than one	B
South Approach	10-15m	One	F
East Approach	10-15m	Two	B
West Approach	>15m	Two	A

Appendix O: Synchro Analysis Reports for Total Conditions

Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2030 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	 				 		 	 		 	 	
Traffic Volume (vph)	528	8	391	21	37	91	155	938	22	26	474	17
Future Volume (vph)	528	8	391	21	37	91	155	938	22	26	474	17
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		34.0	17.0		0.0	25.0		0.0	143.0		100.0
Storage Lanes	2		1	1		1	1		0	1		1
Taper Length (m)	2.5			24.0			100.0			40.0		
Lane Util. Factor	0.97	1.00	1.00	1.00	1.00	1.00	1.00	0.95	0.95	1.00	0.95	1.00
Ped Bike Factor			0.97		0.99	0.98	1.00	1.00				0.98
Frt			0.850			0.850		0.997				0.850
Flt Protected	0.950				0.982		0.950			0.950		
Satd. Flow (prot)	3195	1784	1473	0	1734	1517	1572	3378	0	1544	3357	943
Flt Permitted	0.950				0.982		0.365			0.212		
Satd. Flow (perm)	3195	1784	1431	0	1723	1487	603	3378	0	345	3357	929
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			391			158			2			162
Link Speed (k/h)		60			40			60			60	
Link Distance (m)		88.7			195.5			655.9			232.4	
Travel Time (s)		5.3			17.6			39.4			13.9	
Confl. Peds. (#/hr)			11	11			2		1	1		2
Confl. Bikes (#/hr)			1			4						1
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	2%	5%	5%	2%	2%	10%	2%	2%	12%	3%	64%
Adj. Flow (vph)	528	8	391	21	37	91	155	938	22	26	474	17
Shared Lane Traffic (%)												
Lane Group Flow (vph)	528	8	391	0	58	91	155	960	0	26	474	17
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	1
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	2.0	10.0	2.0	2.0	10.0	2.0	2.0	10.0		2.0	10.0	2.0
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	2.0	0.6	2.0	2.0	0.6	2.0	2.0	0.6		2.0	0.6	2.0
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		9.4			9.4			9.4			9.4	
Detector 2 Size(m)		0.6			0.6			0.6			0.6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2030 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Split	NA	Perm	Split	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	4	4		3	3		5	2		1	6	
Permitted Phases			4			3	2			6		6
Detector Phase	4	4	4	3	3	3	5	2		1	6	6
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	5.0	10.0		5.0	10.0	10.0
Minimum Split (s)	28.6	28.6	28.6	16.7	16.7	16.7	11.0	30.3		11.0	30.3	30.3
Total Split (s)	45.0	45.0	45.0	20.0	20.0	20.0	12.0	33.0		12.0	33.0	33.0
Total Split (%)	40.9%	40.9%	40.9%	18.2%	18.2%	18.2%	10.9%	30.0%		10.9%	30.0%	30.0%
Yellow Time (s)	3.7	3.7	3.7	3.0	3.0	3.0	3.7	3.7		3.7	3.7	3.7
All-Red Time (s)	2.9	2.9	2.9	3.7	3.7	3.7	2.3	2.6		2.3	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.6	6.6	6.6		6.7	6.7	6.0	6.3		6.0	6.3	6.3
Lead/Lag	Lag	Lag	Lag	Lead	Lead	Lead	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None	None	None	C-Max		None	C-Max	C-Max
Act Effct Green (s)	24.8	24.8	24.8		10.6	10.6	58.4	50.4		48.0	41.1	41.1
Actuated g/C Ratio	0.23	0.23	0.23		0.10	0.10	0.53	0.46		0.44	0.37	0.37
v/c Ratio	0.73	0.02	0.63		0.35	0.32	0.37	0.62		0.12	0.38	0.04
Control Delay	45.5	30.0	8.1		52.3	3.2	18.9	29.0		18.2	29.5	0.2
Queue Delay	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	45.5	30.0	8.1		52.3	3.2	18.9	29.0		18.2	29.5	0.2
LOS	D	C	A		D	A	B	C		B	C	A
Approach Delay		29.6			22.3			27.6			28.0	
Approach LOS		C			C			C			C	
Queue Length 50th (m)	50.4	1.3	0.0		11.0	0.0	16.0	82.8		2.5	37.2	0.0
Queue Length 95th (m)	61.4	4.6	21.1		22.3	0.9	32.5	#138.2		7.8	59.1	0.0
Internal Link Dist (m)		64.7			171.5			631.9			208.4	
Turn Bay Length (m)			34.0				25.0			143.0		100.0
Base Capacity (vph)	1115	622	754		209	318	418	1550		224	1255	448
Starvation Cap Reductn	0	0	0		0	0	0	0		0	0	0
Spillback Cap Reductn	0	0	0		0	0	0	0		0	0	0
Storage Cap Reductn	0	0	0		0	0	0	0		0	0	0
Reduced v/c Ratio	0.47	0.01	0.52		0.28	0.29	0.37	0.62		0.12	0.38	0.04

Intersection Summary

Area Type: Other

Cycle Length: 110

Actuated Cycle Length: 110

Offset: 49 (45%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.73

Intersection Signal Delay: 28.1

Intersection LOS: C

Intersection Capacity Utilization 71.4%

ICU Level of Service C


Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.
























Queue shown is maximum after two cycles.

Holly Acres Rd/Richmond Rd/Nanaimo Dr Total2030 AM Peak













Splits and Phases: 22: Richmond Road & Holly Acres Road/Nanaimo Drive



Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2030 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	497	50	336	37	71	52	257	902	33	27	814	23
Future Volume (vph)	497	50	336	37	71	52	257	902	33	27	814	23
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		34.0	17.0		0.0	25.0		0.0	143.0		100.0
Storage Lanes	2		1	1		1	1		0	1		1
Taper Length (m)	2.5			24.0			100.0			40.0		
Lane Util. Factor	0.97	1.00	1.00	1.00	1.00	1.00	1.00	0.95	0.95	1.00	0.95	1.00
Ped Bike Factor			0.96		0.99	0.98	1.00	1.00				0.97
Frt			0.850			0.850		0.995				0.850
Flt Protected	0.950				0.983		0.950			0.950		
Satd. Flow (prot)	3257	1784	1473	0	1748	1517	1631	3369	0	1662	3357	1097
Flt Permitted	0.950				0.983		0.199			0.238		
Satd. Flow (perm)	3257	1784	1415	0	1736	1484	340	3369	0	416	3357	1063
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			336			158		4				162
Link Speed (k/h)		60			40			60			60	
Link Distance (m)		88.7			195.5			655.9			232.4	
Travel Time (s)		5.3			17.6			39.4			13.9	
Confl. Peds. (#/hr)			15	15			13					13
Confl. Bikes (#/hr)			5			4			4			2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	3%	2%	5%	3%	2%	2%	6%	2%	3%	4%	3%	41%
Adj. Flow (vph)	497	50	336	37	71	52	257	902	33	27	814	23
Shared Lane Traffic (%)												
Lane Group Flow (vph)	497	50	336	0	108	52	257	935	0	27	814	23
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	97		97	97		97	97		97	97		97
Number of Detectors	1	2	1	1	2	1	1	2		1	2	1
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	2.0	10.0	2.0	2.0	10.0	2.0	2.0	10.0		2.0	10.0	2.0
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	2.0	0.6	2.0	2.0	0.6	2.0	2.0	0.6		2.0	0.6	2.0
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		9.4			9.4			9.4			9.4	
Detector 2 Size(m)		0.6			0.6			0.6			0.6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2030 PM Peak





















												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Split	NA	Perm	Split	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	4	4		3	3		5	2		1	6	
Permitted Phases			4			3	2			6		6
Detector Phase	4	4	4	3	3	3	5	2		1	6	6
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	5.0	10.0		5.0	10.0	10.0
Minimum Split (s)	28.6	28.6	28.6	16.7	16.7	16.7	11.0	30.3		11.0	30.3	30.3
Total Split (s)	29.0	29.0	29.0	17.0	17.0	17.0	17.0	47.0		17.0	47.0	47.0
Total Split (%)	26.4%	26.4%	26.4%	15.5%	15.5%	15.5%	15.5%	42.7%		15.5%	42.7%	42.7%
Yellow Time (s)	3.7	3.7	3.7	3.0	3.0	3.0	3.7	3.7		3.7	3.7	3.7
All-Red Time (s)	2.9	2.9	2.9	3.7	3.7	3.7	2.3	2.6		2.3	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.6	6.6	6.6		6.7	6.7	6.0	6.3		6.0	6.3	6.3
Lead/Lag	Lag	Lag	Lag	Lead	Lead	Lead	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None	None	None	Max		None	Max	Max
Act Effct Green (s)	20.6	20.6	20.6		10.2	10.2	56.9	50.1		47.4	40.7	40.7
Actuated g/C Ratio	0.19	0.19	0.19		0.09	0.09	0.53	0.46		0.44	0.38	0.38
v/c Ratio	0.80	0.15	0.62		0.65	0.18	0.83	0.60		0.11	0.64	0.05
Control Delay	52.6	37.4	9.7		67.2	1.4	39.5	25.1		13.9	31.0	0.2
Queue Delay	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	52.6	37.4	9.7		67.2	1.4	39.5	25.1		13.9	31.0	0.2
LOS	D	D	A		E	A	D	C		B	C	A
Approach Delay		35.4			45.9			28.2			29.6	
Approach LOS		D			D			C			C	
Queue Length 50th (m)	47.9	8.2	0.0		21.0	0.0	27.3	77.3		2.5	69.6	0.0
Queue Length 95th (m)	64.6	17.7	22.8		#42.6	0.0	#60.6	99.8		6.3	88.9	0.0
Internal Link Dist (m)		64.7			171.5			631.9			208.4	
Turn Bay Length (m)			34.0				25.0			143.0		100.0
Base Capacity (vph)	675	369	559		166	284	310	1563		327	1264	501
Starvation Cap Reductn	0	0	0		0	0	0	0		0	0	0
Spillback Cap Reductn	0	0	0		0	0	0	0		0	0	0
Storage Cap Reductn	0	0	0		0	0	0	0		0	0	0
Reduced v/c Ratio	0.74	0.14	0.60		0.65	0.18	0.83	0.60		0.08	0.64	0.05
Intersection Summary												
Area Type: Other												
Cycle Length: 110												
Actuated Cycle Length: 108.2												
Natural Cycle: 90												
Control Type: Semi Act-Uncoord												
Maximum v/c Ratio: 0.83												
Intersection Signal Delay: 31.6												
Intersection LOS: C												
Intersection Capacity Utilization 76.2%												
ICU Level of Service D												
Analysis Period (min) 15												
# 95th percentile volume exceeds capacity, queue may be longer.												
Queue shown is maximum after two cycles.												

Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2030 PM Peak













Splits and Phases: 22: Richmond Road & Holly Acres Road/Nanaimo Drive

 Ø1	 Ø2	 Ø3	 Ø4
17 s	47 s	17 s	29 s
 Ø5	 Ø6		
17 s	47 s		


Richmond Rd/John Sutherland Dr
Total2030 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	77	0	106	0	949	134	296	563	0
Future Volume (vph)	0	0	0	77	0	106	0	949	134	296	563	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	0		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Frt					0.922				0.850			
Flt Protected					0.979					0.950		
Satd. Flow (prot)	0	1784	0	0	1584	0	1784	3390	1517	1679	3390	0
Flt Permitted					0.863					0.284		
Satd. Flow (perm)	0	1784	0	0	1396	0	1784	3390	1517	502	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					72				131			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	5%	2%	2%	2%	3%	2%	2%
Adj. Flow (vph)	0	0	0	77	0	106	0	949	134	296	563	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	183	0	0	949	134	296	563	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		0.0			0.0			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type				Perm	NA		Perm	NA	Perm	Perm	NA	
Protected Phases		4			8			2			6	


Richmond Rd/John Sutherland Dr
Total2030 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	6	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	10.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	29.4	29.4	
Total Split (s)	38.0	38.0		38.0	38.0		62.0	62.0	62.0	62.0	62.0	
Total Split (%)	38.0%	38.0%		38.0%	38.0%		62.0%	62.0%	62.0%	62.0%	62.0%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0			0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6			6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	C-Max	C-Max	
Act Effct Green (s)				14.5			72.5	72.5	72.5	72.5	72.5	
Actuated g/C Ratio				0.14			0.72	0.72	0.72	0.72	0.72	
v/c Ratio				0.70			0.39	0.12	0.82	0.23		
Control Delay				37.7			1.5	0.2	32.3	5.3		
Queue Delay				0.0			0.0	0.0	0.0	0.0		
Total Delay				37.7			1.5	0.2	32.3	5.3		
LOS				D			A	A	C	A		
Approach Delay				37.7			1.3				14.6	
Approach LOS				D			A				B	
Queue Length 50th (m)				19.0			3.2	0.0	29.0	14.3		
Queue Length 95th (m)				36.7			10.1	0.1	#95.1	26.5		
Internal Link Dist (m)		73.1		97.2			335.3				631.9	
Turn Bay Length (m)								35.0	40.0			
Base Capacity (vph)				487			2457	1135	363	2457		
Starvation Cap Reductn				0			0	0	0	0		
Spillback Cap Reductn				0			0	0	0	0		
Storage Cap Reductn				0			0	0	0	0		
Reduced v/c Ratio				0.38			0.39	0.12	0.82	0.23		
Intersection Summary												
Area Type:	Other											
Cycle Length: 100												
Actuated Cycle Length: 100												
Offset: 92 (92%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green												
Natural Cycle: 120												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.82												
Intersection Signal Delay: 9.8							Intersection LOS: A					
Intersection Capacity Utilization 72.5%							ICU Level of Service C					
Analysis Period (min) 15												
# 95th percentile volume exceeds capacity, queue may be longer.												
Queue shown is maximum after two cycles.												












Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/John Sutherland Dr
Total2030 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕		↗	↕	↗	↗	↕	↕
Traffic Volume (vph)	0	0	0	187	0	274	4	785	43	98	937	0
Future Volume (vph)	0	0	0	187	0	274	4	785	43	98	937	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	0		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Ped Bike Factor							1.00		0.98	1.00		
Frt					0.920				0.850			
Flt Protected					0.980		0.950			0.950		
Satd. Flow (prot)	0	1784	0	0	1599	0	1695	3390	1517	1647	3390	0
Flt Permitted					0.868		0.263			0.323		
Satd. Flow (perm)	0	1784	0	0	1417	0	469	3390	1482	559	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					60				43			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Confl. Peds. (#/hr)							2		1	1		2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	3%	2%	2%	2%	5%	2%	2%
Adj. Flow (vph)	0	0	0	187	0	274	4	785	43	98	937	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	461	0	4	785	43	98	937	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		0.0			0.0			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	

Richmond Rd/John Sutherland Dr
Total2030 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Turn Type				Perm	NA		Perm	NA	Perm	Perm	NA	
Protected Phases		4			8			2			6	
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	6	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	10.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	29.4	29.4	
Total Split (s)	38.0	38.0		38.0	38.0		82.0	82.0	82.0	82.0	82.0	
Total Split (%)	31.7%	31.7%		31.7%	31.7%		68.3%	68.3%	68.3%	68.3%	68.3%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0			0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6			6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	C-Max	C-Max	
Act Effct Green (s)					31.4		75.6	75.6	75.6	75.6	75.6	
Actuated g/C Ratio					0.26		0.63	0.63	0.63	0.63	0.63	
v/c Ratio					1.11		0.01	0.37	0.05	0.28	0.44	
Control Delay					114.1		5.5	5.9	0.8	12.5	12.1	
Queue Delay					0.0		0.0	0.0	0.0	0.0	0.0	
Total Delay					114.1		5.5	5.9	0.8	12.5	12.1	
LOS					F		A	A	A	B	B	
Approach Delay					114.1			5.6			12.2	
Approach LOS					F			A			B	
Queue Length 50th (m)					~104.4		0.1	14.5	0.0	8.9	50.8	
Queue Length 95th (m)					#163.2		m0.4	22.8	0.4	18.0	63.3	
Internal Link Dist (m)		73.1			97.2			335.3			631.9	
Turn Bay Length (m)							40.0		35.0	40.0		
Base Capacity (vph)					415		295	2135	949	352	2135	
Starvation Cap Reductn					0		0	0	0	0	0	
Spillback Cap Reductn					0		0	0	0	0	0	
Storage Cap Reductn					0		0	0	0	0	0	
Reduced v/c Ratio					1.11		0.01	0.37	0.05	0.28	0.44	
Intersection Summary												
Area Type:	Other											
Cycle Length: 120												
Actuated Cycle Length: 120												
Offset: 82 (68%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 1.11												
Intersection Signal Delay: 30.0							Intersection LOS: C					
Intersection Capacity Utilization 80.5%							ICU Level of Service D					
Analysis Period (min) 15												
~ Volume exceeds capacity, queue is theoretically infinite.												
Queue shown is maximum after two cycles.												
# 95th percentile volume exceeds capacity, queue may be longer.												

Richmond Rd/John Sutherland Dr

Total2030 PM Peak











Queue shown is maximum after two cycles.

m Volume for 95th percentile queue is metered by upstream signal.













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/Robertson Rd/Baseline Rd
Total2030 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	356	24	168	12	929	660	173	364	72
Future Volume (vph)	0	0	0	356	24	168	12	929	660	173	364	72
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	250.0		60.0	45.0		100.0	80.0		125.0
Storage Lanes	0		0	1		1	1		1	2		1
Taper Length (m)	7.6			50.0			75.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	0.95	1.00	0.97	0.95	1.00
Frt						0.850			0.850			0.850
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	0	0	3225	1784	1473	1601	3390	1488	3195	3357	1502
Flt Permitted				0.950			0.950			0.950		
Satd. Flow (perm)	0	0	0	3225	1784	1473	1601	3390	1488	3195	3357	1502
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)						168			660			113
Link Speed (k/h)		70			70			80			80	
Link Distance (m)		130.4			357.2			405.5			359.3	
Travel Time (s)		6.7			18.4			18.2			16.2	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	4%	2%	5%	8%	2%	4%	5%	3%	3%
Adj. Flow (vph)	0	0	0	356	24	168	12	929	660	173	364	72
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	356	24	168	12	929	660	173	364	72
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors				1	2	1	1	2	1	1	2	1
Detector Template				Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Leading Detector (m)				6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5	6.1
Trailing Detector (m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)				6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8	6.1
Detector 1 Type				Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)					28.7			28.7			28.7	
Detector 2 Size(m)					1.8			1.8			1.8	
Detector 2 Type					Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)					0.0			0.0			0.0	
Turn Type				Perm	NA	Perm	Prot	NA	Perm	Prot	NA	Perm
Protected Phases					8		5	2		1	6	

Richmond Rd/Robertson Rd/Baseline Rd
Total2030 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases				8		8			2			6
Detector Phase				8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)				10.0	10.0	10.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)				36.8	36.8	36.8	11.6	30.6	30.6	11.6	30.6	30.6
Total Split (s)				37.0	37.0	37.0	19.0	44.0	44.0	19.0	44.0	44.0
Total Split (%)				37.0%	37.0%	37.0%	19.0%	44.0%	44.0%	19.0%	44.0%	44.0%
Yellow Time (s)				4.2	4.2	4.2	4.6	4.6	4.6	4.6	4.6	4.6
All-Red Time (s)				2.6	2.6	2.6	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)				6.8	6.8	6.8	6.6	6.6	6.6	6.6	6.6	6.6
Lead/Lag							Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode				None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effect Green (s)				17.1	17.1	17.1	6.4	52.2	52.2	10.7	66.7	66.7
Actuated g/C Ratio				0.17	0.17	0.17	0.06	0.52	0.52	0.11	0.67	0.67
v/c Ratio				0.65	0.08	0.43	0.12	0.52	0.60	0.51	0.16	0.07
Control Delay				43.9	33.3	9.0	46.2	18.2	4.1	51.8	6.8	0.3
Queue Delay				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay				43.9	33.3	9.0	46.2	18.2	4.1	51.8	6.8	0.3
LOS				D	C	A	D	B	A	D	A	A
Approach Delay					32.7			12.6			18.8	
Approach LOS					C			B			B	
Queue Length 50th (m)				30.7	3.6	0.0	2.1	55.1	0.0	16.4	9.4	0.0
Queue Length 95th (m)				41.1	9.4	14.6	7.1	84.5	18.6	25.7	18.5	0.8
Internal Link Dist (m)		106.4			333.2			381.5			335.3	
Turn Bay Length (m)				250.0		60.0	45.0		100.0	80.0		125.0
Base Capacity (vph)				973	538	562	198	1770	1092	405	2237	1038
Starvation Cap Reductn				0	0	0	0	0	0	0	0	0
Spillback Cap Reductn				0	0	0	0	0	0	0	0	0
Storage Cap Reductn				0	0	0	0	0	0	0	0	0
Reduced v/c Ratio				0.37	0.04	0.30	0.06	0.52	0.60	0.43	0.16	0.07

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 93 (93%), Referenced to phase 2:NBT and 6:SBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.65

Intersection Signal Delay: 18.0


Intersection LOS: B

Intersection Capacity Utilization 59.7%


ICU Level of Service B

Analysis Period (min) 15













Splits and Phases: 3: Robertson Road/Richmond Road & HWY 416 On-Ramp/Baseline Road



Richmond Rd/Robertson Rd/Baseline Rd
Total2030 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations				↰	↑	↱	↰	↑↑	↱	↰	↑↑	↱
Traffic Volume (vph)	0	0	0	653	112	180	56	646	521	208	699	247
Future Volume (vph)	0	0	0	653	112	180	56	646	521	208	699	247
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	250.0		60.0	45.0		100.0	80.0		125.0
Storage Lanes	0		0	1		1	1		1	2		1
Taper Length (m)	7.6			50.0			75.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	0.95	1.00	0.97	0.95	1.00
Ped Bike Factor							1.00		0.99	1.00		0.98
Frt						0.850			0.850			0.850
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	0	0	3288	1767	1517	1647	3390	1517	3288	3390	1502
Flt Permitted				0.950			0.950			0.950		
Satd. Flow (perm)	0	0	0	3288	1767	1517	1644	3390	1495	3286	3390	1465
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)						180			521			247
Link Speed (k/h)		70			70			80			80	
Link Distance (m)		130.4			357.2			405.5			359.3	
Travel Time (s)		6.7			18.4			18.2			16.2	
Confl. Peds. (#/hr)							2		1	1		2
Confl. Bikes (#/hr)									1			
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	3%	2%	5%	2%	2%	2%	2%	3%
Adj. Flow (vph)	0	0	0	653	112	180	56	646	521	208	699	247
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	653	112	180	56	646	521	208	699	247
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors				1	2	1	1	2	1	1	2	1
Detector Template				Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Leading Detector (m)				6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5	6.1
Trailing Detector (m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)				6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8	6.1
Detector 1 Type				Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)					28.7			28.7			28.7	
Detector 2 Size(m)					1.8			1.8			1.8	
Detector 2 Type					Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Richmond Rd/Robertson Rd/Baseline Rd
Total2030 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)					0.0			0.0			0.0	
Turn Type				Perm	NA	Perm	Prot	NA	Perm	Prot	NA	Perm
Protected Phases					8		5	2		1	6	
Permitted Phases				8		8			2			6
Detector Phase				8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)				10.0	10.0	10.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)				36.8	36.8	36.8	11.6	30.6	30.6	11.6	30.6	30.6
Total Split (s)				37.0	37.0	37.0	32.0	51.0	51.0	32.0	51.0	51.0
Total Split (%)				30.8%	30.8%	30.8%	26.7%	42.5%	42.5%	26.7%	42.5%	42.5%
Yellow Time (s)				4.2	4.2	4.2	4.6	4.6	4.6	4.6	4.6	4.6
All-Red Time (s)				2.6	2.6	2.6	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)				6.8	6.8	6.8	6.6	6.6	6.6	6.6	6.6	6.6
Lead/Lag							Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode				None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effct Green (s)				28.4	28.4	28.4	9.5	58.7	58.7	12.9	64.6	64.6
Actuated g/C Ratio				0.24	0.24	0.24	0.08	0.49	0.49	0.11	0.54	0.54
v/c Ratio				0.84	0.27	0.36	0.43	0.39	0.52	0.59	0.38	0.27
Control Delay				54.2	38.6	7.3	62.1	21.0	3.8	70.4	11.6	0.8
Queue Delay				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay				54.2	38.6	7.3	62.1	21.0	3.8	70.4	11.6	0.8
LOS				D	D	A	E	C	A	E	B	A
Approach Delay					43.5			15.6			19.9	
Approach LOS					D			B			B	
Queue Length 50th (m)				68.4	19.5	0.0	11.8	46.6	0.0	23.5	26.5	0.0
Queue Length 95th (m)				88.0	33.9	15.8	23.3	63.7	17.2	m32.3	m34.0	m1.2
Internal Link Dist (m)		106.4			333.2			381.5			335.3	
Turn Bay Length (m)				250.0		60.0	45.0		100.0	80.0		125.0
Base Capacity (vph)				827	444	516	348	1658	997	695	1825	902
Starvation Cap Reductn				0	0	0	0	0	0	0	0	0
Spillback Cap Reductn				0	0	0	0	0	0	0	0	0
Storage Cap Reductn				0	0	0	0	0	0	0	0	0
Reduced v/c Ratio				0.79	0.25	0.35	0.16	0.39	0.52	0.30	0.38	0.27

Intersection Summary

Area Type: Other

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 108 (90%), Referenced to phase 2:NBT and 6:SBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.84

Intersection Signal Delay: 25.0

Intersection LOS: C

Intersection Capacity Utilization 62.6%

ICU Level of Service B

Analysis Period (min) 15

m Volume for 95th percentile queue is metered by upstream signal.

Richmond Rd/Robertson Rd/Baseline Rd
Total2030 PM Peak

Splits and Phases: 3: Robertson Road/Richmond Road & HWY 416 On-Ramp/Baseline Road



Baseline Rd/Cedarview Rd
Total2030 AM Peak

							Ø7
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑	↑	↵	↑↑	↵	↑	
Traffic Volume (vph)	756	91	105	466	121	390	
Future Volume (vph)	756	91	105	466	121	390	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	45.0		20.0	0.0	
Storage Lanes		1	1		1	1	
Taper Length (m)			80.0		35.0		
Lane Util. Factor	0.95	1.00	1.00	0.95	1.00	1.00	
Ped Bike Factor		0.98			1.00		
Frt		0.850				0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3390	1517	1695	3325	1695	1517	
Flt Permitted			0.235		0.950		
Satd. Flow (perm)	3390	1482	419	3325	1693	1517	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)		89				390	
Link Speed (k/h)	70			70	50		
Link Distance (m)	357.2			373.9	442.3		
Travel Time (s)	18.4			19.2	31.8		
Confl. Peds. (#/hr)		1	1		1		
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	2%	2%	2%	4%	2%	2%	
Adj. Flow (vph)	756	91	105	466	121	390	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	756	91	105	466	121	390	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	4.9			4.9	4.9		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2	1	1	2	1	1	
Detector Template	Thru	Right	Left	Thru	Left	Right	
Leading Detector (m)	30.5	6.1	6.1	30.5	6.1	6.1	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	1.8	6.1	6.1	1.8	6.1	6.1	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)	28.7			28.7			
Detector 2 Size(m)	1.8			1.8			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Cedarview Rd
Total2030 AM Peak

	→	↘	↙	←	↖	↗	
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA	Perm	pm+pt	NA	Prot	pm+ov	
Protected Phases	2		1	6	8	1	7
Permitted Phases		2	6			8	
Detector Phase	2	2	1	6	8	1	
Switch Phase							
Minimum Initial (s)	10.0	10.0	5.0	10.0	5.0	5.0	5.0
Minimum Split (s)	27.1	27.1	11.1	27.1	36.2	11.1	34.2
Total Split (s)	34.0	34.0	15.0	49.0	45.0	15.0	36.0
Total Split (%)	26.2%	26.2%	11.5%	37.7%	34.6%	11.5%	28%
Yellow Time (s)	4.2	4.2	4.2	4.2	3.7	4.2	3.7
All-Red Time (s)	1.9	1.9	1.9	1.9	2.5	1.9	2.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.1	6.1	6.1	6.1	6.2	6.1	
Lead/Lag	Lag	Lag	Lead		Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	Max	Max	None	Max	None	None	None
Act Effct Green (s)	30.9	30.9	44.7	44.7	10.7	24.6	
Actuated g/C Ratio	0.42	0.42	0.61	0.61	0.15	0.34	
v/c Ratio	0.53	0.13	0.27	0.23	0.49	0.51	
Control Delay	20.9	6.6	12.1	9.8	38.0	5.2	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	20.9	6.6	12.1	9.8	38.0	5.2	
LOS	C	A	B	A	D	A	
Approach Delay	19.4			10.3	13.0		
Approach LOS	B			B	B		
Queue Length 50th (m)	29.3	0.1	3.5	9.0	12.5	0.0	
Queue Length 95th (m)	#99.8	11.2	23.1	43.8	37.4	19.6	
Internal Link Dist (m)	333.2			349.9	418.3		
Turn Bay Length (m)			45.0		20.0		
Base Capacity (vph)	1437	679	419	2040	940	798	
Starvation Cap Reductn	0	0	0	0	0	0	
Spillback Cap Reductn	0	0	0	0	0	0	
Storage Cap Reductn	0	0	0	0	0	0	
Reduced v/c Ratio	0.53	0.13	0.25	0.23	0.13	0.49	
Intersection Summary							
Area Type:	Other						
Cycle Length: 130							
Actuated Cycle Length: 72.9							
Natural Cycle: 110							
Control Type: Semi Act-Uncoord							
Maximum v/c Ratio: 0.53							
Intersection Signal Delay: 15.0				Intersection LOS: B			
Intersection Capacity Utilization 57.7%				ICU Level of Service B			
Analysis Period (min) 15							
# 95th percentile volume exceeds capacity, queue may be longer.							
Queue shown is maximum after two cycles.							

Baseline Rd/Cedarview Rd
Total2030 AM Peak


Splits and Phases: 6: Cedarview Road & Baseline Road



Baseline Rd/Cedarview Rd
Total2030 PM Peak

							Ø7
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑	↑	↓	↑↑	↓	↑	
Traffic Volume (vph)	572	163	259	836	130	148	
Future Volume (vph)	572	163	259	836	130	148	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	45.0		20.0	0.0	
Storage Lanes		1	1		1	1	
Taper Length (m)			80.0		35.0		
Lane Util. Factor	0.95	1.00	1.00	0.95	1.00	1.00	
Ped Bike Factor		0.96	0.99				
Frt		0.850				0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3357	1517	1662	3390	1601	1517	
Flt Permitted			0.391		0.950		
Satd. Flow (perm)	3357	1454	680	3390	1601	1517	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)		163				148	
Link Speed (k/h)	70			70	50		
Link Distance (m)	357.2			373.9	442.3		
Travel Time (s)	18.4			19.2	31.8		
Confl. Peds. (#/hr)		7	7				
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	4%	2%	8%	2%	
Adj. Flow (vph)	572	163	259	836	130	148	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	572	163	259	836	130	148	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	4.9			4.9	4.9		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2	1	1	2	1	1	
Detector Template	Thru	Right	Left	Thru	Left	Right	
Leading Detector (m)	30.5	6.1	6.1	30.5	6.1	6.1	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	1.8	6.1	6.1	1.8	6.1	6.1	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)	28.7			28.7			
Detector 2 Size(m)	1.8			1.8			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Cedarview Rd
Total2030 PM Peak



Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA	Perm	pm+pt	NA	Prot	pm+ov	
Protected Phases	2		1	6	8	1	7
Permitted Phases		2	6			8	
Detector Phase	2	2	1	6	8	1	
Switch Phase							
Minimum Initial (s)	10.0	10.0	5.0	10.0	5.0	5.0	5.0
Minimum Split (s)	27.1	27.1	11.1	27.1	11.2	11.1	34.2
Total Split (s)	49.0	49.0	15.0	64.0	30.0	15.0	36.0
Total Split (%)	37.7%	37.7%	11.5%	49.2%	23.1%	11.5%	28%
Yellow Time (s)	4.2	4.2	4.2	4.2	3.7	4.2	3.7
All-Red Time (s)	1.9	1.9	1.9	1.9	2.5	1.9	2.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.1	6.1	6.1	6.1	6.2	6.1	
Lead/Lag	Lag	Lag	Lead		Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	C-Max	C-Max	None	C-Max	None	None	None
Act Effect Green (s)	83.0	83.0	101.9	101.9	15.8	34.8	
Actuated g/C Ratio	0.64	0.64	0.78	0.78	0.12	0.27	
v/c Ratio	0.27	0.17	0.41	0.31	0.67	0.29	
Control Delay	11.5	2.2	6.1	4.7	70.5	6.3	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	11.5	2.2	6.1	4.7	70.5	6.3	
LOS	B	A	A	A	E	A	
Approach Delay	9.4			5.1	36.3		
Approach LOS	A			A	D		
Queue Length 50th (m)	29.0	0.0	13.2	25.1	29.8	0.0	
Queue Length 95th (m)	45.5	8.7	25.0	39.6	46.9	13.1	
Internal Link Dist (m)	333.2			349.9	418.3		
Turn Bay Length (m)			45.0		20.0		
Base Capacity (vph)	2142	986	629	2656	293	514	
Starvation Cap Reductn	0	0	0	0	0	0	
Spillback Cap Reductn	0	0	0	0	0	0	
Storage Cap Reductn	0	0	0	0	0	0	
Reduced v/c Ratio	0.27	0.17	0.41	0.31	0.44	0.29	

Intersection Summary

Area Type: Other

Cycle Length: 130

Actuated Cycle Length: 130

Offset: 15 (12%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 85

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.67

Intersection Signal Delay: 10.7


Intersection LOS: B

Intersection Capacity Utilization 55.6%






















ICU Level of Service B

Analysis Period (min) 15













Splits and Phases: 6: Cedarview Road & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2030 AM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	161	1173	19	8	533	149	30	2	14	87	6	74
Future Volume (vph)	161	1173	19	8	533	149	30	2	14	87	6	74
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		0.99			0.99	
Frt			0.850			0.850		0.959			0.940	
Flt Protected	0.950			0.950				0.968			0.975	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1642	0	0	1581	0
Flt Permitted	0.454			0.204				0.756			0.812	
Satd. Flow (perm)	786	3357	1461	353	3357	1446	0	1282	0	0	1313	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			45			149		14			54	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			378.0			325.9			150.3	
Travel Time (s)		19.2			19.4			29.3			10.8	
Confl. Peds. (#/hr)	2		4	4		2	2		6	6		2
Confl. Bikes (#/hr)			1			6			2			
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	161	1173	19	8	533	149	30	2	14	87	6	74
Shared Lane Traffic (%)												
Lane Group Flow (vph)	161	1173	19	8	533	149	0	46	0	0	167	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	2.0	10.0	6.1	6.1	10.0	2.0	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	2.0	0.6	6.1	6.1	0.6	2.0	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		9.4			9.4			28.7			28.7	
Detector 2 Size(m)		0.6			0.6			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2030 AM Peak





















												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Perm	NA	Perm	Perm	NA	Perm	Perm	NA		Perm	NA	
Protected Phases		2			6			8			4	
Permitted Phases	2		2	6		6	8			4		
Detector Phase	2	2	2	6	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	32.2	32.2	32.2	32.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	47.0	47.0	47.0	47.0	47.0	47.0	38.0	38.0		38.0	38.0	
Total Split (%)	55.3%	55.3%	55.3%	55.3%	55.3%	55.3%	44.7%	44.7%		44.7%	44.7%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Max	C-Max	C-Max	C-Max	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	56.3	56.3	56.3	56.3	56.3	56.3		16.0			16.0	
Actuated g/C Ratio	0.66	0.66	0.66	0.66	0.66	0.66		0.19			0.19	
v/c Ratio	0.31	0.53	0.02	0.03	0.24	0.15		0.18			0.58	
Control Delay	10.5	10.2	1.1	16.6	11.1	6.5		20.5			27.2	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	10.5	10.2	1.1	16.6	11.1	6.5		20.5			27.2	
LOS	B	B	A	B	B	A		C			C	
Approach Delay		10.1			10.2			20.5			27.2	
Approach LOS		B			B			C			C	
Queue Length 50th (m)	7.7	36.2	0.0	0.3	11.4	0.0		4.2			15.9	
Queue Length 95th (m)	29.7	91.1	1.0	m3.7	48.2	20.2		9.4			25.3	
Internal Link Dist (m)		349.9			354.0			301.9			126.3	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	521	2225	983	233	2225	1008		483			520	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.31	0.53	0.02	0.03	0.24	0.15		0.10			0.32	
Intersection Summary												
Area Type:	Other											
Cycle Length: 85												
Actuated Cycle Length: 85												
Offset: 37 (44%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.58												
Intersection Signal Delay: 11.6						Intersection LOS: B						
Intersection Capacity Utilization 70.5%						ICU Level of Service C						
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2030 AM Peak













Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2030 PM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	42	715	57	14	1175	67	38	4	12	122	5	106
Future Volume (vph)	42	715	57	14	1175	67	38	4	12	122	5	106
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		1.00			0.99	
Frt			0.850			0.850		0.970			0.939	
Flt Protected	0.950			0.950				0.966			0.974	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1661	0	0	1576	0
Flt Permitted	0.200			0.365				0.682			0.807	
Satd. Flow (perm)	346	3357	1456	631	3357	1446	0	1172	0	0	1300	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			57			40		12			44	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			378.0			325.9			150.3	
Travel Time (s)		19.2			19.4			29.3			10.8	
Confl. Peds. (#/hr)	3		4	4		3			9	9		
Confl. Bikes (#/hr)			5			3						3
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	42	715	57	14	1175	67	38	4	12	122	5	106
Shared Lane Traffic (%)												
Lane Group Flow (vph)	42	715	57	14	1175	67	0	54	0	0	233	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	2.0	10.0	6.1	6.1	10.0	2.0	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	2.0	0.6	6.1	6.1	0.6	2.0	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		9.4			9.4			28.7			28.7	
Detector 2 Size(m)		0.6			0.6			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2030 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Perm	NA	Perm	Perm	NA	Perm	Perm	NA		Perm	NA	
Protected Phases		2			6			8			4	
Permitted Phases	2		2	6		6	8			4		
Detector Phase	2	2	2	6	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	32.2	32.2	32.2	32.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	62.0	62.0	62.0	62.0	62.0	62.0	38.0	38.0		38.0	38.0	
Total Split (%)	62.0%	62.0%	62.0%	62.0%	62.0%	62.0%	38.0%	38.0%		38.0%	38.0%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Max	C-Max	C-Max	C-Max	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	66.6	66.6	66.6	66.6	66.6	66.6		20.7			20.7	
Actuated g/C Ratio	0.67	0.67	0.67	0.67	0.67	0.67		0.21			0.21	
v/c Ratio	0.18	0.32	0.06	0.03	0.53	0.07		0.22			0.77	
Control Delay	11.2	8.6	2.7	3.5	6.0	0.8		26.1			45.8	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	11.2	8.6	2.7	3.5	6.0	0.8		26.1			45.8	
LOS	B	A	A	A	A	A		C			D	
Approach Delay		8.3			5.7			26.1			45.8	
Approach LOS		A			A			C			D	
Queue Length 50th (m)	2.5	25.2	0.0	0.3	55.9	0.2		6.2			32.3	
Queue Length 95th (m)	9.6	46.1	4.8	m0.6	13.7	0.0		13.7			49.7	
Internal Link Dist (m)		349.9			354.0			301.9			126.3	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	230	2237	989	420	2237	977		377			439	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.18	0.32	0.06	0.03	0.53	0.07		0.14			0.53	
Intersection Summary												
Area Type:	Other											
Cycle Length: 100												
Actuated Cycle Length: 100												
Offset: 77 (77%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.77												
Intersection Signal Delay: 11.0							Intersection LOS: B					
Intersection Capacity Utilization 62.5%							ICU Level of Service B					
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2030 PM Peak

Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/Sandcastle Dr
Total2030 AM Peak

Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑		↵	↑↑	↵	↶	
Traffic Volume (vph)	1251	25	94	633	60	129	
Future Volume (vph)	1251	25	94	633	60	129	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	146.0		37.0	0.0	
Storage Lanes		0	1		1	1	
Taper Length (m)			26.0		75.0		
Lane Util. Factor	0.95	0.95	1.00	0.95	1.00	1.00	
Ped Bike Factor	1.00				1.00		
Frt	0.997					0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3346	0	1695	3357	1695	1488	
Flt Permitted			0.181		0.950		
Satd. Flow (perm)	3346	0	323	3357	1693	1488	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)	3					104	
Link Speed (k/h)	70			70	50		
Link Distance (m)	378.0			246.3	226.0		
Travel Time (s)	19.4			12.7	16.3		
Confl. Peds. (#/hr)		5	5		1		
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	2%	3%	2%	4%	
Adj. Flow (vph)	1251	25	94	633	60	129	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	1276	0	94	633	60	129	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	1.6			1.6	1.6		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2		1	2	1	1	
Detector Template	Thru		Left	Thru	Left	Right	
Leading Detector (m)	10.0		2.0	10.0	2.0	2.0	
Trailing Detector (m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Size(m)	0.6		2.0	0.6	2.0	2.0	
Detector 1 Type	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0		0.0	0.0	0.0	0.0	
Detector 2 Position(m)	9.4			9.4			
Detector 2 Size(m)	0.6			0.6			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Sandcastle Dr
Total2030 AM Peak

	→	↘	↙	←	↖	↗	
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA		Perm	NA	Perm	Perm	
Protected Phases	2			6			7
Permitted Phases			6		8	8	
Detector Phase	2		6	6	8	8	
Switch Phase							
Minimum Initial (s)	10.0		10.0	10.0	5.0	5.0	1.0
Minimum Split (s)	23.9		15.9	15.9	32.5	32.5	5.0
Total Split (s)	47.0		47.0	47.0	33.0	33.0	5.0
Total Split (%)	55.3%		55.3%	55.3%	38.8%	38.8%	6%
Yellow Time (s)	4.2		4.2	4.2	3.0	3.0	2.0
All-Red Time (s)	1.7		1.7	1.7	3.5	3.5	0.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.9		5.9	5.9	6.5	6.5	
Lead/Lag					Lag	Lag	Lead
Lead-Lag Optimize?							
Recall Mode	C-Max		C-Max	C-Max	None	None	None
Act Effct Green (s)	60.3		60.3	60.3	11.3	11.3	
Actuated g/C Ratio	0.71		0.71	0.71	0.13	0.13	
v/c Ratio	0.54		0.41	0.27	0.27	0.45	
Control Delay	2.5		17.3	6.4	32.9	14.0	
Queue Delay	0.0		0.0	0.0	0.0	0.0	
Total Delay	2.5		17.3	6.4	32.9	14.0	
LOS	A		B	A	C	B	
Approach Delay	2.5			7.8	20.0		
Approach LOS	A			A	B		
Queue Length 50th (m)	7.6		3.8	11.8	8.6	3.5	
Queue Length 95th (m)	10.7		#31.2	41.0	14.4	13.7	
Internal Link Dist (m)	354.0			222.3	202.0		
Turn Bay Length (m)			146.0		37.0		
Base Capacity (vph)	2373		228	2379	527	535	
Starvation Cap Reductn	0		0	0	0	0	
Spillback Cap Reductn	0		0	0	0	0	
Storage Cap Reductn	0		0	0	0	0	
Reduced v/c Ratio	0.54		0.41	0.27	0.11	0.24	

Intersection Summary

Area Type: Other

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 55 (65%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.54

Intersection Signal Delay: 5.8

Intersection LOS: A

Intersection Capacity Utilization 65.1%

ICU Level of Service C


Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.


Queue shown is maximum after two cycles.

Baseline Rd/Sandcastle Dr
Total2030 AM Peak

Splits and Phases: 5: Sandcastle Dr & Baseline Road



Baseline Rd/Sandcastle Dr
Total2030 PM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑		↵	↑↑	↵	↵	
Traffic Volume (vph)	803	43	193	1189	68	107	
Future Volume (vph)	803	43	193	1189	68	107	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	146.0		37.0	0.0	
Storage Lanes		0	1		1	1	
Taper Length (m)			26.0		75.0		
Lane Util. Factor	0.95	0.95	1.00	0.95	1.00	1.00	
Ped Bike Factor					0.99	0.98	
Frt	0.992					0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3332	0	1695	3357	1695	1488	
Flt Permitted			0.320		0.950		
Satd. Flow (perm)	3332	0	571	3357	1674	1461	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)	9					107	
Link Speed (k/h)	70			70	50		
Link Distance (m)	378.0			246.3	226.0		
Travel Time (s)	19.4			12.7	16.3		
Confl. Peds. (#/hr)					11	5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	2%	3%	2%	4%	
Adj. Flow (vph)	803	43	193	1189	68	107	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	846	0	193	1189	68	107	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	1.6			1.6	1.6		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		97	97		97	97	
Number of Detectors	2		1	2	1	1	
Detector Template	Thru		Left	Thru	Left	Right	
Leading Detector (m)	10.0		2.0	10.0	2.0	2.0	
Trailing Detector (m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Size(m)	0.6		2.0	0.6	2.0	2.0	
Detector 1 Type	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0		0.0	0.0	0.0	0.0	
Detector 2 Position(m)	9.4			9.4			
Detector 2 Size(m)	0.6			0.6			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Sandcastle Dr
Total2030 PM Peak

	→	↘	↙	←	↖	↗	
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA		Perm	NA	Perm	Perm	
Protected Phases	2			6			7
Permitted Phases			6		8	8	
Detector Phase	2		6	6	8	8	
Switch Phase							
Minimum Initial (s)	10.0		10.0	10.0	5.0	5.0	1.0
Minimum Split (s)	23.9		15.9	15.9	32.5	32.5	5.0
Total Split (s)	62.0		62.0	62.0	33.0	33.0	5.0
Total Split (%)	62.0%		62.0%	62.0%	33.0%	33.0%	5%
Yellow Time (s)	4.2		4.2	4.2	3.0	3.0	2.0
All-Red Time (s)	1.7		1.7	1.7	3.5	3.5	0.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.9		5.9	5.9	6.5	6.5	
Lead/Lag					Lag	Lag	Lead
Lead-Lag Optimize?							
Recall Mode	C-Max		C-Max	C-Max	None	None	None
Act Effect Green (s)	74.6		74.6	74.6	12.0	12.0	
Actuated g/C Ratio	0.75		0.75	0.75	0.12	0.12	
v/c Ratio	0.34		0.45	0.47	0.34	0.40	
Control Delay	4.7		12.1	7.3	42.1	11.2	
Queue Delay	0.0		0.0	0.0	0.0	0.0	
Total Delay	4.7		12.1	7.3	42.1	11.2	
LOS	A		B	A	D	B	
Approach Delay	4.7			8.0	23.2		
Approach LOS	A			A	C		
Queue Length 50th (m)	15.1		9.0	29.8	11.7	0.0	
Queue Length 95th (m)	35.6		45.1	89.3	19.3	11.3	
Internal Link Dist (m)	354.0			222.3	202.0		
Turn Bay Length (m)			146.0		37.0		
Base Capacity (vph)	2487		426	2504	443	465	
Starvation Cap Reductn	0		0	0	0	0	
Spillback Cap Reductn	0		0	0	0	0	
Storage Cap Reductn	0		0	0	0	0	
Reduced v/c Ratio	0.34		0.45	0.47	0.15	0.23	

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 62 (62%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.47

Intersection Signal Delay: 7.9

Intersection LOS: A

Intersection Capacity Utilization 58.3%

ICU Level of Service B










Analysis Period (min) 15

Splits and Phases: 5: Sandcastle Dr & Baseline Road












John Sutherland Dr/QCH West Ring Road (South)

Total2030 AM Peak










						
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	26	99	196	152	48	63
Future Volume (Veh/h)	26	99	196	152	48	63
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	26	99	196	152	48	63
Pedestrians					9	
Lane Width (m)					3.7	
Walking Speed (m/s)					1.0	
Percent Blockage					1	
Right turn flare (veh)						
Median type				None	None	
Median storage (veh)						
Upstream signal (m)				150		
pX, platoon unblocked						
vC, conflicting volume	632	80	111			
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	632	80	111			
tC, single (s)	6.4	6.2	4.1			
tC, 2 stage (s)						
tF (s)	3.5	3.3	2.2			
p0 queue free %	93	90	87			
cM capacity (veh/h)	382	981	1479			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	125	348	111			
Volume Left	26	196	0			
Volume Right	99	0	63			
cSH	739	1479	1700			
Volume to Capacity	0.17	0.13	0.07			
Queue Length 95th (m)	4.2	3.2	0.0			
Control Delay (s)	10.9	4.9	0.0			
Lane LOS	B	A				
Approach Delay (s)	10.9	4.9	0.0			
Approach LOS	B					
Intersection Summary						
Average Delay		5.2				
Intersection Capacity Utilization		41.2%		ICU Level of Service		A
Analysis Period (min)		15				

John Sutherland Dr/QCH West Ring Road (South)










Total2030 PM Peak

						
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	70	155	79	65	113	52
Future Volume (Veh/h)	70	155	79	65	113	52
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	70	155	79	65	113	52
Pedestrians					17	
Lane Width (m)					3.7	
Walking Speed (m/s)					1.0	
Percent Blockage					2	
Right turn flare (veh)						
Median type				None	None	
Median storage (veh)						
Upstream signal (m)				150		
pX, platoon unblocked						
vC, conflicting volume	379	139	165			
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	379	139	165			
tC, single (s)	6.4	6.2	4.1			
tC, 2 stage (s)						
tF (s)	3.5	3.3	2.2			
p0 queue free %	88	83	94			
cM capacity (veh/h)	578	909	1413			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	225	144	165			
Volume Left	70	79	0			
Volume Right	155	0	52			
cSH	772	1413	1700			
Volume to Capacity	0.29	0.06	0.10			
Queue Length 95th (m)	8.5	1.2	0.0			
Control Delay (s)	11.6	4.4	0.0			
Lane LOS	B	A				
Approach Delay (s)	11.6	4.4	0.0			
Approach LOS	B					
Intersection Summary						
Average Delay		6.1				
Intersection Capacity Utilization		42.0%		ICU Level of Service		A
Analysis Period (min)		15				

John Sutherland Dr/QCH Irving Greenberg Cancer Center
Total2030 AM Peak










						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Volume (veh/h)	130	38	14	120	12	2
Future Volume (Veh/h)	130	38	14	120	12	2
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	130	38	14	120	12	2
Pedestrians	38			1	4	
Lane Width (m)	3.7			3.7	3.7	
Walking Speed (m/s)	1.0			1.0	1.0	
Percent Blockage	4			0	0	
Right turn flare (veh)						
Median type	None			None		
Median storage (veh)						
Upstream signal (m)	262					
pX, platoon unblocked						
vC, conflicting volume			172		339	154
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			172		339	154
tC, single (s)			4.1		6.4	6.2
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			99		98	100
cM capacity (veh/h)			1399		622	887
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total	168	134	14			
Volume Left	0	14	12			
Volume Right	38	0	2			
cSH	1700	1399	650			
Volume to Capacity	0.10	0.01	0.02			
Queue Length 95th (m)	0.0	0.2	0.5			
Control Delay (s)	0.0	0.9	10.7			
Lane LOS		A	B			
Approach Delay (s)	0.0	0.9	10.7			
Approach LOS			B			
Intersection Summary						
Average Delay			0.8			
Intersection Capacity Utilization			29.4%	ICU Level of Service		A
Analysis Period (min)			15			

John Sutherland Dr/QCH Irving Greenberg Cancer Center
Total2030 PM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Volume (veh/h)	142	17	17	103	44	24
Future Volume (Veh/h)	142	17	17	103	44	24
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	142	17	17	103	44	24
Pedestrians	32			4	8	
Lane Width (m)	3.7			3.7	3.7	
Walking Speed (m/s)	1.0			1.0	1.0	
Percent Blockage	3			0	1	
Right turn flare (veh)						
Median type	None			None		
Median storage veh						
Upstream signal (m)	262					
pX, platoon unblocked						
vC, conflicting volume			167		328	162
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			167		328	162
tC, single (s)			4.1		6.4	6.2
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			99		93	97
cM capacity (veh/h)			1399		632	871
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total	159	120	68			
Volume Left	0	17	44			
Volume Right	17	0	24			
cSH	1700	1399	700			
Volume to Capacity	0.09	0.01	0.10			
Queue Length 95th (m)	0.0	0.3	2.3			
Control Delay (s)	0.0	1.2	10.7			
Lane LOS		A	B			
Approach Delay (s)	0.0	1.2	10.7			
Approach LOS			B			
Intersection Summary						
Average Delay		2.5				
Intersection Capacity Utilization		32.2%	ICU Level of Service	A		
Analysis Period (min)		15				










John Sutherland Dr/QCH West Ring Road (North)

Total2030 AM Peak

















						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Volume (veh/h)	129	355	106	43	137	39
Future Volume (Veh/h)	129	355	106	43	137	39
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	129	355	106	43	137	39
Pedestrians	5			7	2	
Lane Width (m)	3.7			3.7	3.7	
Walking Speed (m/s)	1.0			1.0	1.0	
Percent Blockage	1			1	0	
Right turn flare (veh)						
Median type	None			None		
Median storage veh						
Upstream signal (m)	121					
pX, platoon unblocked			0.95		0.95	0.95
vC, conflicting volume			486		568	316
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			436		523	258
tC, single (s)			4.1		6.4	6.2
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			90		69	95
cM capacity (veh/h)			1069		439	738
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total	484	149	176			
Volume Left	0	106	137			
Volume Right	355	0	39			
cSH	1700	1069	482			
Volume to Capacity	0.28	0.10	0.37			
Queue Length 95th (m)	0.0	2.3	11.6			
Control Delay (s)	0.0	6.5	16.7			
Lane LOS		A	C			
Approach Delay (s)	0.0	6.5	16.7			
Approach LOS			C			
Intersection Summary						
Average Delay		4.8				
Intersection Capacity Utilization		60.2%	ICU Level of Service	B		
Analysis Period (min)		15				

John Sutherland Dr/QCH West Ring Road (North)

















Total2030 PM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Volume (veh/h)	83	71	22	133	347	77
Future Volume (Veh/h)	83	71	22	133	347	77
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	83	71	22	133	347	77
Pedestrians	3			6	9	
Lane Width (m)	3.7			3.7	3.7	
Walking Speed (m/s)	1.0			1.0	1.0	
Percent Blockage	0			1	1	
Right turn flare (veh)						
Median type	None			None		
Median storage veh						
Upstream signal (m)	121					
pX, platoon unblocked			1.00		1.00	1.00
vC, conflicting volume			163		308	134
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			162		307	133
tC, single (s)			4.1		6.4	6.2
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			98		48	91
cM capacity (veh/h)			1403		666	902
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total	154	155	424			
Volume Left	0	22	347			
Volume Right	71	0	77			
cSH	1700	1403	699			
Volume to Capacity	0.09	0.02	0.61			
Queue Length 95th (m)	0.0	0.3	28.9			
Control Delay (s)	0.0	1.2	17.8			
Lane LOS		A	C			
Approach Delay (s)	0.0	1.2	17.8			
Approach LOS			C			
Intersection Summary						
Average Delay		10.5				
Intersection Capacity Utilization		54.6%	ICU Level of Service	A		
Analysis Period (min)		15				



























John Sutherland Dr/QCH Lot TL2
Total2030 AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	22	155	0	0	144	0	0	0	0	0	0	3
Future Volume (Veh/h)	22	155	0	0	144	0	0	0	0	0	0	3
Sign Control		Free			Free			Stop			Stop	
Grade		0%			0%			0%			0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	22	155	0	0	144	0	0	0	0	0	0	3
Pedestrians		3			89			18				
Lane Width (m)		3.7			3.7			3.7				
Walking Speed (m/s)		1.0			1.0			1.0				
Percent Blockage		0			9			2				
Right turn flare (veh)												
Median type		None			None							
Median storage (veh)												
Upstream signal (m)		169										
pX, platoon unblocked												
vC, conflicting volume	144			173			367	361	262	432	361	147
vC1, stage 1 conf vol												
vC2, stage 2 conf vol												
vCu, unblocked vol	144			173			367	361	262	432	361	147
tC, single (s)	4.1			4.1			7.1	6.5	6.2	7.1	6.5	6.2
tC, 2 stage (s)												
tF (s)	2.2			2.2			3.5	4.0	3.3	3.5	4.0	3.3
p0 queue free %	98			100			100	100	100	100	100	100
cM capacity (veh/h)	1438			1360			558	547	693	473	547	897
Direction, Lane #	EB 1	WB 1	NB 1	SB 1								
Volume Total	177	144	0	3								
Volume Left	22	0	0	0								
Volume Right	0	0	0	3								
cSH	1438	1360	1700	897								
Volume to Capacity	0.02	0.00	0.00	0.00								
Queue Length 95th (m)	0.3	0.0	0.0	0.1								
Control Delay (s)	1.0	0.0	0.0	9.0								
Lane LOS	A		A	A								
Approach Delay (s)	1.0	0.0	0.0	9.0								
Approach LOS			A	A								
Intersection Summary												
Average Delay			0.7									
Intersection Capacity Utilization			42.3%	ICU Level of Service				A				
Analysis Period (min)			15									













John Sutherland Dr/QCH Lot TL2
Total2030 PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	0	148	0	0	147	0	0	0	0	0	0	19
Future Volume (Veh/h)	0	148	0	0	147	0	0	0	0	0	0	19
Sign Control		Free			Free			Stop			Stop	
Grade		0%			0%			0%			0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	0	148	0	0	147	0	0	0	0	0	0	19
Pedestrians		2			41			22				
Lane Width (m)		3.7			3.7			3.7				
Walking Speed (m/s)		1.0			1.0			1.0				
Percent Blockage		0			4			2				
Right turn flare (veh)												
Median type		None			None							
Median storage (veh)												
Upstream signal (m)		169										
pX, platoon unblocked												
vC, conflicting volume	147			170			338	317	211	336	317	149
vC1, stage 1 conf vol												
vC2, stage 2 conf vol												
vCu, unblocked vol	147			170			338	317	211	336	317	149
tC, single (s)	4.1			4.1			7.1	6.5	6.2	7.1	6.5	6.2
tC, 2 stage (s)												
tF (s)	2.2			2.2			3.5	4.0	3.3	3.5	4.0	3.3
p0 queue free %	100			100			100	100	100	100	100	98
cM capacity (veh/h)	1435			1358			576	586	776	581	586	896
Direction, Lane #	EB 1	WB 1	NB 1	SB 1								
Volume Total	148	147	0	19								
Volume Left	0	0	0	0								
Volume Right	0	0	0	19								
cSH	1435	1358	1700	896								
Volume to Capacity	0.00	0.00	0.00	0.02								
Queue Length 95th (m)	0.0	0.0	0.0	0.5								
Control Delay (s)	0.0	0.0	0.0	9.1								
Lane LOS			A	A								
Approach Delay (s)	0.0	0.0	0.0	9.1								
Approach LOS			A	A								
Intersection Summary												
Average Delay			0.6									
Intersection Capacity Utilization			28.3%		ICU Level of Service				A			
Analysis Period (min)			15									

Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2035 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	 				 			 			 	
Traffic Volume (vph)	541	8	401	21	37	91	158	958	22	26	483	18
Future Volume (vph)	541	8	401	21	37	91	158	958	22	26	483	18
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		34.0	17.0		0.0	25.0		0.0	143.0		100.0
Storage Lanes	2		1	1		1	1		0	1		1
Taper Length (m)	2.5			24.0			100.0			40.0		
Lane Util. Factor	0.97	1.00	1.00	1.00	1.00	1.00	1.00	0.95	0.95	1.00	0.95	1.00
Ped Bike Factor			0.97		0.99	0.98	1.00	1.00				0.98
Frt			0.850			0.850		0.997				0.850
Flt Protected	0.950				0.982		0.950			0.950		
Satd. Flow (prot)	3195	1784	1473	0	1734	1517	1572	3378	0	1544	3357	943
Flt Permitted	0.950				0.982		0.357			0.201		
Satd. Flow (perm)	3195	1784	1431	0	1723	1487	590	3378	0	327	3357	929
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			401			158			2			162
Link Speed (k/h)		60			40			60			60	
Link Distance (m)		88.7			195.5			655.9			232.4	
Travel Time (s)		5.3			17.6			39.4			13.9	
Confl. Peds. (#/hr)			11	11			2		1	1		2
Confl. Bikes (#/hr)			1			4						1
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	2%	5%	5%	2%	2%	10%	2%	2%	12%	3%	64%
Adj. Flow (vph)	541	8	401	21	37	91	158	958	22	26	483	18
Shared Lane Traffic (%)												
Lane Group Flow (vph)	541	8	401	0	58	91	158	980	0	26	483	18
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	97		97	97		97	97		97	97		97
Number of Detectors	1	2	1	1	2	1	1	2		1	2	1
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	2.0	10.0	2.0	2.0	10.0	2.0	2.0	10.0		2.0	10.0	2.0
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	2.0	0.6	2.0	2.0	0.6	2.0	2.0	0.6		2.0	0.6	2.0
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		9.4			9.4			9.4			9.4	
Detector 2 Size(m)		0.6			0.6			0.6			0.6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2035 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Split	NA	Perm	Split	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	4	4		3	3		5	2		1	6	
Permitted Phases			4			3	2			6		6
Detector Phase	4	4	4	3	3	3	5	2		1	6	6
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	5.0	10.0		5.0	10.0	10.0
Minimum Split (s)	28.6	28.6	28.6	16.7	16.7	16.7	11.0	30.3		11.0	30.3	30.3
Total Split (s)	45.0	45.0	45.0	20.0	20.0	20.0	12.0	33.0		12.0	33.0	33.0
Total Split (%)	40.9%	40.9%	40.9%	18.2%	18.2%	18.2%	10.9%	30.0%		10.9%	30.0%	30.0%
Yellow Time (s)	3.7	3.7	3.7	3.0	3.0	3.0	3.7	3.7		3.7	3.7	3.7
All-Red Time (s)	2.9	2.9	2.9	3.7	3.7	3.7	2.3	2.6		2.3	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.6	6.6	6.6		6.7	6.7	6.0	6.3		6.0	6.3	6.3
Lead/Lag	Lag	Lag	Lag	Lead	Lead	Lead	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None	None	None	C-Max		None	C-Max	C-Max
Act Effct Green (s)	25.2	25.2	25.2		10.6	10.6	57.9	50.0		47.5	40.6	40.6
Actuated g/C Ratio	0.23	0.23	0.23		0.10	0.10	0.53	0.45		0.43	0.37	0.37
v/c Ratio	0.74	0.02	0.63		0.35	0.32	0.38	0.64		0.12	0.39	0.04
Control Delay	45.3	29.6	8.0		52.3	3.2	19.4	29.7		18.6	30.0	0.2
Queue Delay	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	45.3	29.6	8.0		52.3	3.2	19.4	29.7		18.6	30.0	0.2
LOS	D	C	A		D	A	B	C		B	C	A
Approach Delay		29.4			22.3			28.3			28.4	
Approach LOS		C			C			C			C	
Queue Length 50th (m)	51.5	1.2	0.0		11.0	0.0	16.5	86.0		2.5	38.4	0.0
Queue Length 95th (m)	62.6	4.6	21.2		22.3	0.9	33.2	#144.6		7.9	60.2	0.0
Internal Link Dist (m)		64.7			171.5			631.9			208.4	
Turn Bay Length (m)			34.0				25.0			143.0		100.0
Base Capacity (vph)	1115	622	760		209	318	411	1536		215	1238	445
Starvation Cap Reductn	0	0	0		0	0	0	0		0	0	0
Spillback Cap Reductn	0	0	0		0	0	0	0		0	0	0
Storage Cap Reductn	0	0	0		0	0	0	0		0	0	0
Reduced v/c Ratio	0.49	0.01	0.53		0.28	0.29	0.38	0.64		0.12	0.39	0.04

Intersection Summary

Area Type: Other

Cycle Length: 110

Actuated Cycle Length: 110

Offset: 71.5 (65%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.74

Intersection Signal Delay: 28.4

Intersection LOS: C

Intersection Capacity Utilization 72.0%

ICU Level of Service C


Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.
























Queue shown is maximum after two cycles.

Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2035 AM Peak













Splits and Phases: 22: Richmond Road & Holly Acres Road/Nanaimo Drive



Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2035 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	509	50	344	37	71	52	263	922	33	27	832	23
Future Volume (vph)	509	50	344	37	71	52	263	922	33	27	832	23
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		34.0	17.0		0.0	25.0		0.0	143.0		100.0
Storage Lanes	2		1	1		1	1		0	1		1
Taper Length (m)	2.5			24.0			100.0			40.0		
Lane Util. Factor	0.97	1.00	1.00	1.00	1.00	1.00	1.00	0.95	0.95	1.00	0.95	1.00
Ped Bike Factor			0.96		0.99	0.98	1.00	1.00				0.97
Frt			0.850			0.850		0.995				0.850
Flt Protected	0.950				0.983		0.950			0.950		
Satd. Flow (prot)	3257	1784	1473	0	1748	1517	1631	3369	0	1662	3357	1097
Flt Permitted	0.950				0.983		0.191			0.228		
Satd. Flow (perm)	3257	1784	1415	0	1736	1484	327	3369	0	399	3357	1063
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			335			158		4				162
Link Speed (k/h)		60			40			60			60	
Link Distance (m)		88.7			195.5			655.9			232.4	
Travel Time (s)		5.3			17.6			39.4			13.9	
Confl. Peds. (#/hr)			15	15			13					13
Confl. Bikes (#/hr)			5			4			4			2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	3%	2%	5%	3%	2%	2%	6%	2%	3%	4%	3%	41%
Adj. Flow (vph)	509	50	344	37	71	52	263	922	33	27	832	23
Shared Lane Traffic (%)												
Lane Group Flow (vph)	509	50	344	0	108	52	263	955	0	27	832	23
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			3.7			3.7	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			1.6			1.6			1.6	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	97		97	97		97	97		97	97		97
Number of Detectors	1	2	1	1	2	1	1	2		1	2	1
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	Right
Leading Detector (m)	2.0	10.0	2.0	2.0	10.0	2.0	2.0	10.0		2.0	10.0	2.0
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Size(m)	2.0	0.6	2.0	2.0	0.6	2.0	2.0	0.6		2.0	0.6	2.0
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0
Detector 2 Position(m)		9.4			9.4			9.4			9.4	
Detector 2 Size(m)		0.6			0.6			0.6			0.6	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2035 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Split	NA	Perm	Split	NA	Perm	pm+pt	NA		pm+pt	NA	Perm
Protected Phases	4	4		3	3		5	2		1	6	
Permitted Phases			4			3	2			6		6
Detector Phase	4	4	4	3	3	3	5	2		1	6	6
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	5.0	10.0		5.0	10.0	10.0
Minimum Split (s)	28.6	28.6	28.6	16.7	16.7	16.7	11.0	30.3		11.0	30.3	30.3
Total Split (s)	29.0	29.0	29.0	17.0	17.0	17.0	17.0	47.0		17.0	47.0	47.0
Total Split (%)	26.4%	26.4%	26.4%	15.5%	15.5%	15.5%	15.5%	42.7%		15.5%	42.7%	42.7%
Yellow Time (s)	3.7	3.7	3.7	3.0	3.0	3.0	3.7	3.7		3.7	3.7	3.7
All-Red Time (s)	2.9	2.9	2.9	3.7	3.7	3.7	2.3	2.6		2.3	2.6	2.6
Lost Time Adjust (s)	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Lost Time (s)	6.6	6.6	6.6		6.7	6.7	6.0	6.3		6.0	6.3	6.3
Lead/Lag	Lag	Lag	Lag	Lead	Lead	Lead	Lead	Lag		Lead	Lag	Lag
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None	None	None	Max		None	Max	Max
Act Effct Green (s)	20.8	20.8	20.8		10.2	10.2	56.9	50.1		47.4	40.7	40.7
Actuated g/C Ratio	0.19	0.19	0.19		0.09	0.09	0.52	0.46		0.44	0.38	0.38
v/c Ratio	0.82	0.15	0.64		0.65	0.18	0.87	0.61		0.11	0.66	0.05
Control Delay	53.4	37.4	10.6		67.4	1.4	44.8	25.5		14.0	31.4	0.2
Queue Delay	0.0	0.0	0.0		0.0	0.0	0.0	0.0		0.0	0.0	0.0
Total Delay	53.4	37.4	10.6		67.4	1.4	44.8	25.5		14.0	31.4	0.2
LOS	D	D	B		E	A	D	C		B	C	A
Approach Delay		36.2			46.0			29.6			30.1	
Approach LOS		D			D			C			C	
Queue Length 50th (m)	49.3	8.2	1.5		21.0	0.0	28.1	79.6		2.5	71.6	0.0
Queue Length 95th (m)	66.2	17.7	25.4		#42.6	0.0	#65.8	102.5		6.3	91.4	0.0
Internal Link Dist (m)		64.7			171.5			631.9			208.4	
Turn Bay Length (m)			34.0				25.0			143.0		100.0
Base Capacity (vph)	673	369	558		166	284	304	1559		319	1261	500
Starvation Cap Reductn	0	0	0		0	0	0	0		0	0	0
Spillback Cap Reductn	0	0	0		0	0	0	0		0	0	0
Storage Cap Reductn	0	0	0		0	0	0	0		0	0	0
Reduced v/c Ratio	0.76	0.14	0.62		0.65	0.18	0.87	0.61		0.08	0.66	0.05

Intersection Summary

Area Type: Other

Cycle Length: 110

Actuated Cycle Length: 108.4

Natural Cycle: 90

Control Type: Semi Act-Uncoord

Maximum v/c Ratio: 0.87

Intersection Signal Delay: 32.5

Intersection LOS: C

Intersection Capacity Utilization 77.4%

ICU Level of Service D

Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.









Queue shown is maximum after two cycles.

Holly Acres Rd/Richmond Rd/Nanaimo Dr
Total2035 PM Peak













Splits and Phases: 22: Richmond Road & Holly Acres Road/Nanaimo Drive

 Ø1	 Ø2	 Ø3	 Ø4
17 s	47 s	17 s	29 s
 Ø5	 Ø6		
17 s	47 s		


Richmond Rd/John Sutherland Dr
Total2035 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	77	0	106	0	970	134	296	576	0
Future Volume (vph)	0	0	0	77	0	106	0	970	134	296	576	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	0		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Frt					0.922				0.850			
Flt Protected					0.979					0.950		
Satd. Flow (prot)	0	1784	0	0	1584	0	1784	3390	1517	1679	3390	0
Flt Permitted					0.863					0.277		
Satd. Flow (perm)	0	1784	0	0	1396	0	1784	3390	1517	489	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					72				128			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	5%	2%	2%	2%	3%	2%	2%
Adj. Flow (vph)	0	0	0	77	0	106	0	970	134	296	576	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	183	0	0	970	134	296	576	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		0.0			0.0			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type				Perm	NA		Perm	NA	Perm	Perm	NA	
Protected Phases		4			8			2			6	


Richmond Rd/John Sutherland Dr
Total2035 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	6	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	10.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	29.4	29.4	
Total Split (s)	38.0	38.0		38.0	38.0		62.0	62.0	62.0	62.0	62.0	
Total Split (%)	38.0%	38.0%		38.0%	38.0%		62.0%	62.0%	62.0%	62.0%	62.0%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0			0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6			6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	C-Max	C-Max	
Act Effct Green (s)					14.5		72.5	72.5	72.5	72.5	72.5	
Actuated g/C Ratio					0.14		0.72	0.72	0.72	0.72	0.72	
v/c Ratio					0.70		0.39	0.12	0.84	0.23		
Control Delay					37.7		1.5	0.2	35.3	5.3		
Queue Delay					0.0		0.0	0.0	0.0	0.0		
Total Delay					37.7		1.5	0.2	35.3	5.3		
LOS					D		A	A	D	A		
Approach Delay					37.7		1.3				15.5	
Approach LOS					D		A				B	
Queue Length 50th (m)					19.0		3.3	0.0	30.3	14.7		
Queue Length 95th (m)					36.7		10.2	0.1	#96.7	27.3		
Internal Link Dist (m)		73.1			97.2		335.3				631.9	
Turn Bay Length (m)									35.0	40.0		
Base Capacity (vph)					487		2457	1134	354	2457		
Starvation Cap Reductn					0		0	0	0	0		
Spillback Cap Reductn					0		0	0	0	0		
Storage Cap Reductn					0		0	0	0	0		
Reduced v/c Ratio					0.38		0.39	0.12	0.84	0.23		
Intersection Summary												
Area Type:	Other											
Cycle Length: 100												
Actuated Cycle Length: 100												
Offset: 92 (92%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green												
Natural Cycle: 120												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.84												
Intersection Signal Delay: 10.1							Intersection LOS: B					
Intersection Capacity Utilization 73.2%							ICU Level of Service D					
Analysis Period (min) 15												
# 95th percentile volume exceeds capacity, queue may be longer.												
Queue shown is maximum after two cycles.												













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/John Sutherland Dr
Total2035 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕			↕		↗	↕	↗	↗	↕	↕
Traffic Volume (vph)	0	0	0	187	0	274	4	802	43	98	958	0
Future Volume (vph)	0	0	0	187	0	274	4	802	43	98	958	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	0		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Ped Bike Factor							1.00		0.98	1.00		
Frt					0.920				0.850			
Flt Protected					0.980		0.950			0.950		
Satd. Flow (prot)	0	1784	0	0	1599	0	1695	3390	1517	1647	3390	0
Flt Permitted					0.868		0.256			0.315		
Satd. Flow (perm)	0	1784	0	0	1417	0	456	3390	1482	546	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					60				43			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Confl. Peds. (#/hr)							2		1	1		2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	3%	2%	2%	2%	5%	2%	2%
Adj. Flow (vph)	0	0	0	187	0	274	4	802	43	98	958	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	0	461	0	4	802	43	98	958	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		0.0			0.0			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	

Richmond Rd/John Sutherland Dr
Total2035 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Turn Type				Perm	NA		Perm	NA	Perm	Perm	NA	
Protected Phases		4			8			2				6
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	6		6
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	10.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	29.4	29.4	
Total Split (s)	38.0	38.0		38.0	38.0		82.0	82.0	82.0	82.0	82.0	
Total Split (%)	31.7%	31.7%		31.7%	31.7%		68.3%	68.3%	68.3%	68.3%	68.3%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0			0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6			6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	C-Max	C-Max	
Act Effct Green (s)					31.4		75.6	75.6	75.6	75.6	75.6	
Actuated g/C Ratio					0.26		0.63	0.63	0.63	0.63	0.63	
v/c Ratio					1.11		0.01	0.38	0.05	0.29	0.45	
Control Delay					114.1		5.5	5.9	0.8	12.7	12.3	
Queue Delay					0.0		0.0	0.0	0.0	0.0	0.0	
Total Delay					114.1		5.5	5.9	0.8	12.7	12.3	
LOS					F		A	A	A	B	B	
Approach Delay					114.1			5.6			12.3	
Approach LOS					F			A			B	
Queue Length 50th (m)					~104.4		0.1	14.8	0.0	8.9	52.5	
Queue Length 95th (m)					#163.2		m0.4	23.3	0.4	18.1	65.2	
Internal Link Dist (m)		73.1			97.2			335.3			631.9	
Turn Bay Length (m)							40.0		35.0	40.0		
Base Capacity (vph)					415		287	2135	949	343	2135	
Starvation Cap Reductn					0		0	0	0	0	0	
Spillback Cap Reductn					0		0	0	0	0	0	
Storage Cap Reductn					0		0	0	0	0	0	
Reduced v/c Ratio					1.11		0.01	0.38	0.05	0.29	0.45	
Intersection Summary												
Area Type:	Other											
Cycle Length: 120												
Actuated Cycle Length: 120												
Offset: 82 (68%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 1.11												
Intersection Signal Delay: 29.7							Intersection LOS: C					
Intersection Capacity Utilization 81.2%							ICU Level of Service D					
Analysis Period (min) 15												
~ Volume exceeds capacity, queue is theoretically infinite.												
Queue shown is maximum after two cycles.												
# 95th percentile volume exceeds capacity, queue may be longer.												

Richmond Rd/John Sutherland Dr
Total2035 PM Peak











Queue shown is maximum after two cycles.

m Volume for 95th percentile queue is metered by upstream signal.













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/Robertson Rd/Baseline Rd
Total2035 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	364	24	172	13	949	675	177	371	73
Future Volume (vph)	0	0	0	364	24	172	13	949	675	177	371	73
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	250.0		60.0	45.0		100.0	80.0		125.0
Storage Lanes	0		0	1		1	1		1	2		1
Taper Length (m)	7.6			50.0			75.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	0.95	1.00	0.97	0.95	1.00
Frt						0.850			0.850			0.850
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	0	0	3225	1784	1473	1601	3390	1488	3195	3357	1502
Flt Permitted				0.950			0.950			0.950		
Satd. Flow (perm)	0	0	0	3225	1784	1473	1601	3390	1488	3195	3357	1502
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)						172			675			113
Link Speed (k/h)		70			70			80			80	
Link Distance (m)		130.4			357.2			405.5			359.3	
Travel Time (s)		6.7			18.4			18.2			16.2	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	4%	2%	5%	8%	2%	4%	5%	3%	3%
Adj. Flow (vph)	0	0	0	364	24	172	13	949	675	177	371	73
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	364	24	172	13	949	675	177	371	73
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors				1	2	1	1	2	1	1	2	1
Detector Template				Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Leading Detector (m)				6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5	6.1
Trailing Detector (m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)				6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8	6.1
Detector 1 Type				Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)					28.7			28.7			28.7	
Detector 2 Size(m)					1.8			1.8			1.8	
Detector 2 Type					Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)					0.0			0.0			0.0	
Turn Type				Perm	NA	Perm	Prot	NA	Perm	Prot	NA	Perm
Protected Phases					8		5	2		1	6	

Richmond Rd/Robertson Rd/Baseline Rd
Total2035 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases				8		8			2			6
Detector Phase				8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)				10.0	10.0	10.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)				36.8	36.8	36.8	11.6	30.6	30.6	11.6	30.6	30.6
Total Split (s)				37.0	37.0	37.0	19.0	44.0	44.0	19.0	44.0	44.0
Total Split (%)				37.0%	37.0%	37.0%	19.0%	44.0%	44.0%	19.0%	44.0%	44.0%
Yellow Time (s)				4.2	4.2	4.2	4.6	4.6	4.6	4.6	4.6	4.6
All-Red Time (s)				2.6	2.6	2.6	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)				6.8	6.8	6.8	6.6	6.6	6.6	6.6	6.6	6.6
Lead/Lag							Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode				None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effect Green (s)				17.3	17.3	17.3	6.4	51.9	51.9	10.8	66.4	66.4
Actuated g/C Ratio				0.17	0.17	0.17	0.06	0.52	0.52	0.11	0.66	0.66
v/c Ratio				0.65	0.08	0.43	0.13	0.54	0.62	0.51	0.17	0.07
Control Delay				43.8	33.1	8.8	46.4	18.7	4.2	51.9	6.9	0.4
Queue Delay				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay				43.8	33.1	8.8	46.4	18.7	4.2	51.9	6.9	0.4
LOS				D	C	A	D	B	A	D	A	A
Approach Delay					32.6			12.9			18.9	
Approach LOS					C			B			B	
Queue Length 50th (m)				31.4	3.6	0.0	2.3	57.0	0.0	16.8	9.7	0.0
Queue Length 95th (m)				41.9	9.4	14.7	7.6	87.7	18.9	26.1	19.0	0.9
Internal Link Dist (m)		106.4			333.2			381.5			335.3	
Turn Bay Length (m)				250.0		60.0	45.0		100.0	80.0		125.0
Base Capacity (vph)				973	538	564	198	1758	1097	406	2229	1035
Starvation Cap Reductn				0	0	0	0	0	0	0	0	0
Spillback Cap Reductn				0	0	0	0	0	0	0	0	0
Storage Cap Reductn				0	0	0	0	0	0	0	0	0
Reduced v/c Ratio				0.37	0.04	0.30	0.07	0.54	0.62	0.44	0.17	0.07

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 93 (93%), Referenced to phase 2:NBT and 6:SBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.65

Intersection Signal Delay: 18.2

Intersection LOS: B

Intersection Capacity Utilization 60.6%


ICU Level of Service B

Analysis Period (min) 15













Splits and Phases: 3: Robertson Road/Richmond Road & HWY 416 On-Ramp/Baseline Road



Richmond Rd/Robertson Rd/Baseline Rd
Total2035 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	668	114	185	58	660	533	213	714	253
Future Volume (vph)	0	0	0	668	114	185	58	660	533	213	714	253
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	250.0		60.0	45.0		100.0	80.0		125.0
Storage Lanes	0		0	1		1	1		1	2		1
Taper Length (m)	7.6			50.0			75.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	0.97	1.00	1.00	1.00	0.95	1.00	0.97	0.95	1.00
Ped Bike Factor							1.00		0.99	1.00		0.98
Frt						0.850			0.850			0.850
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	0	0	3288	1767	1517	1647	3390	1517	3288	3390	1502
Flt Permitted				0.950			0.950			0.950		
Satd. Flow (perm)	0	0	0	3288	1767	1517	1644	3390	1495	3287	3390	1465
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)						185			533			253
Link Speed (k/h)		70			70			80			80	
Link Distance (m)		130.4			357.2			405.5			359.3	
Travel Time (s)		6.7			18.4			18.2			16.2	
Confl. Peds. (#/hr)							2		1	1		2
Confl. Bikes (#/hr)									1			
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	3%	2%	5%	2%	2%	2%	2%	3%
Adj. Flow (vph)	0	0	0	668	114	185	58	660	533	213	714	253
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	668	114	185	58	660	533	213	714	253
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		7.4			7.4			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors				1	2	1	1	2	1	1	2	1
Detector Template				Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Leading Detector (m)				6.1	30.5	6.1	6.1	30.5	6.1	6.1	30.5	6.1
Trailing Detector (m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Position(m)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Size(m)				6.1	1.8	6.1	6.1	1.8	6.1	6.1	1.8	6.1
Detector 1 Type				Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex
Detector 1 Channel												
Detector 1 Extend (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Queue (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 1 Delay (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Detector 2 Position(m)					28.7			28.7			28.7	
Detector 2 Size(m)					1.8			1.8			1.8	
Detector 2 Type					Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Richmond Rd/Robertson Rd/Baseline Rd
Total2035 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)					0.0			0.0			0.0	
Turn Type				Perm	NA	Perm	Prot	NA	Perm	Prot	NA	Perm
Protected Phases					8		5	2		1	6	
Permitted Phases				8		8			2			6
Detector Phase				8	8	8	5	2	2	1	6	6
Switch Phase												
Minimum Initial (s)				10.0	10.0	10.0	5.0	10.0	10.0	5.0	10.0	10.0
Minimum Split (s)				36.8	36.8	36.8	11.6	30.6	30.6	11.6	30.6	30.6
Total Split (s)				37.0	37.0	37.0	32.0	51.0	51.0	32.0	51.0	51.0
Total Split (%)				30.8%	30.8%	30.8%	26.7%	42.5%	42.5%	26.7%	42.5%	42.5%
Yellow Time (s)				4.2	4.2	4.2	4.6	4.6	4.6	4.6	4.6	4.6
All-Red Time (s)				2.6	2.6	2.6	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)				6.8	6.8	6.8	6.6	6.6	6.6	6.6	6.6	6.6
Lead/Lag							Lead	Lag	Lag	Lead	Lag	Lag
Lead-Lag Optimize?							Yes	Yes	Yes	Yes	Yes	Yes
Recall Mode				None	None	None	None	C-Max	C-Max	None	C-Max	C-Max
Act Effct Green (s)				28.6	28.6	28.6	9.6	58.3	58.3	13.1	64.3	64.3
Actuated g/C Ratio				0.24	0.24	0.24	0.08	0.49	0.49	0.11	0.54	0.54
v/c Ratio				0.85	0.27	0.37	0.44	0.40	0.53	0.59	0.39	0.28
Control Delay				55.0	38.6	7.3	62.3	21.4	3.9	70.5	11.8	0.8
Queue Delay				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay				55.0	38.6	7.3	62.3	21.4	3.9	70.5	11.8	0.8
LOS				E	D	A	E	C	A	E	B	A
Approach Delay					44.0			15.8			20.0	
Approach LOS					D			B			C	
Queue Length 50th (m)				70.4	19.9	0.0	12.2	48.1	0.0	24.1	26.9	0.0
Queue Length 95th (m)				90.5	34.5	16.0	24.0	65.6	17.5	m33.0	m35.5	m1.2
Internal Link Dist (m)		106.4			333.2			381.5			335.3	
Turn Bay Length (m)				250.0		60.0	45.0		100.0	80.0		125.0
Base Capacity (vph)				827	444	520	348	1646	1000	695	1815	902
Starvation Cap Reductn				0	0	0	0	0	0	0	0	0
Spillback Cap Reductn				0	0	0	0	0	0	0	0	0
Storage Cap Reductn				0	0	0	0	0	0	0	0	0
Reduced v/c Ratio				0.81	0.26	0.36	0.17	0.40	0.53	0.31	0.39	0.28

Intersection Summary

Area Type: Other

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 108 (90%), Referenced to phase 2:NBT and 6:SBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.85

Intersection Signal Delay: 25.3

Intersection LOS: C

Intersection Capacity Utilization 63.2%

ICU Level of Service B

Analysis Period (min) 15

m Volume for 95th percentile queue is metered by upstream signal.

Richmond Rd/Robertson Rd/Baseline Rd
Total2035 PM Peak

Splits and Phases: 3: Robertson Road/Richmond Road & HWY 416 On-Ramp/Baseline Road



Baseline Rd/Cedarview Rd
Total2035 AM Peak

Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑	↑	↓	↑↑	↓	↑	
Traffic Volume (vph)	774	100	113	477	132	424	
Future Volume (vph)	774	100	113	477	132	424	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	45.0		20.0	0.0	
Storage Lanes		1	1		1	1	
Taper Length (m)			80.0		35.0		
Lane Util. Factor	0.95	1.00	1.00	0.95	1.00	1.00	
Ped Bike Factor		0.98			1.00		
Frt		0.850				0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3390	1517	1695	3325	1695	1517	
Flt Permitted			0.224		0.950		
Satd. Flow (perm)	3390	1482	400	3325	1693	1517	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)		95				424	
Link Speed (k/h)	70			70	50		
Link Distance (m)	357.2			373.9	442.3		
Travel Time (s)	18.4			19.2	31.8		
Confl. Peds. (#/hr)		1	1		1		
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	2%	2%	2%	4%	2%	2%	
Adj. Flow (vph)	774	100	113	477	132	424	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	774	100	113	477	132	424	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	4.9			4.9	4.9		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2	1	1	2	1	1	
Detector Template	Thru	Right	Left	Thru	Left	Right	
Leading Detector (m)	30.5	6.1	6.1	30.5	6.1	6.1	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	1.8	6.1	6.1	1.8	6.1	6.1	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)	28.7			28.7			
Detector 2 Size(m)	1.8			1.8			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Cedarview Rd
Total2035 AM Peak

	→	↘	↙	←	↖	↗	
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA	Perm	pm+pt	NA	Prot	pm+ov	
Protected Phases	2		1	6	8	1	7
Permitted Phases		2	6			8	
Detector Phase	2	2	1	6	8	1	
Switch Phase							
Minimum Initial (s)	10.0	10.0	5.0	10.0	5.0	5.0	5.0
Minimum Split (s)	27.1	27.1	11.1	27.1	36.2	11.1	34.2
Total Split (s)	34.0	34.0	15.0	49.0	45.0	15.0	36.0
Total Split (%)	26.2%	26.2%	11.5%	37.7%	34.6%	11.5%	28%
Yellow Time (s)	4.2	4.2	4.2	4.2	3.7	4.2	3.7
All-Red Time (s)	1.9	1.9	1.9	1.9	2.5	1.9	2.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.1	6.1	6.1	6.1	6.2	6.1	
Lead/Lag	Lag	Lag	Lead		Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	Max	Max	None	Max	None	None	None
Act Effect Green (s)	30.6	30.6	44.8	44.8	11.2	25.4	
Actuated g/C Ratio	0.42	0.42	0.61	0.61	0.15	0.35	
v/c Ratio	0.55	0.15	0.30	0.24	0.51	0.53	
Control Delay	21.7	6.8	12.6	10.1	38.3	5.2	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	21.7	6.8	12.6	10.1	38.3	5.2	
LOS	C	A	B	B	D	A	
Approach Delay	20.0			10.6	13.1		
Approach LOS	C			B	B		
Queue Length 50th (m)	31.1	0.3	3.9	9.4	13.7	0.0	
Queue Length 95th (m)	#105.2	12.3	24.9	45.6	40.4	20.4	
Internal Link Dist (m)	333.2			349.9	418.3		
Turn Bay Length (m)			45.0		20.0		
Base Capacity (vph)	1413	673	407	2027	934	824	
Starvation Cap Reductn	0	0	0	0	0	0	
Spillback Cap Reductn	0	0	0	0	0	0	
Storage Cap Reductn	0	0	0	0	0	0	
Reduced v/c Ratio	0.55	0.15	0.28	0.24	0.14	0.51	

Intersection Summary

Area Type: Other

Cycle Length: 130

Actuated Cycle Length: 73.4

Natural Cycle: 110

Control Type: Semi Act-Uncoord

Maximum v/c Ratio: 0.55

Intersection Signal Delay: 15.3

Intersection LOS: B

Intersection Capacity Utilization 60.5%

ICU Level of Service B

Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Baseline Rd/Cedarview Rd
Total2035 AM Peak

Splits and Phases: 6: Cedarview Road & Baseline Road



Baseline Rd/Cedarview Rd
Total2035 PM Peak

							Ø7
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑	↑	↵	↑↑	↵	↑	
Traffic Volume (vph)	585	178	281	856	142	160	
Future Volume (vph)	585	178	281	856	142	160	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	45.0		20.0	0.0	
Storage Lanes		1	1		1	1	
Taper Length (m)			80.0		35.0		
Lane Util. Factor	0.95	1.00	1.00	0.95	1.00	1.00	
Ped Bike Factor		0.96	0.99				
Frt		0.850				0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3357	1517	1662	3390	1601	1517	
Flt Permitted			0.378		0.950		
Satd. Flow (perm)	3357	1454	658	3390	1601	1517	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)		178				160	
Link Speed (k/h)	70			70	50		
Link Distance (m)	357.2			373.9	442.3		
Travel Time (s)	18.4			19.2	31.8		
Confl. Peds. (#/hr)		7	7				
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	4%	2%	8%	2%	
Adj. Flow (vph)	585	178	281	856	142	160	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	585	178	281	856	142	160	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	4.9			4.9	4.9		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		14	24		24	14	
Number of Detectors	2	1	1	2	1	1	
Detector Template	Thru	Right	Left	Thru	Left	Right	
Leading Detector (m)	30.5	6.1	6.1	30.5	6.1	6.1	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	1.8	6.1	6.1	1.8	6.1	6.1	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)	28.7			28.7			
Detector 2 Size(m)	1.8			1.8			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Cedarview Rd
Total2035 PM Peak



Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA	Perm	pm+pt	NA	Prot	pm+ov	
Protected Phases	2		1	6	8	1	7
Permitted Phases		2	6			8	
Detector Phase	2	2	1	6	8	1	
Switch Phase							
Minimum Initial (s)	10.0	10.0	5.0	10.0	5.0	5.0	5.0
Minimum Split (s)	27.1	27.1	11.1	27.1	11.2	11.1	34.2
Total Split (s)	49.0	49.0	15.0	64.0	30.0	15.0	36.0
Total Split (%)	37.7%	37.7%	11.5%	49.2%	23.1%	11.5%	28%
Yellow Time (s)	4.2	4.2	4.2	4.2	3.7	4.2	3.7
All-Red Time (s)	1.9	1.9	1.9	1.9	2.5	1.9	2.5
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.1	6.1	6.1	6.1	6.2	6.1	
Lead/Lag	Lag	Lag	Lead		Lag	Lead	Lead
Lead-Lag Optimize?	Yes	Yes	Yes		Yes	Yes	Yes
Recall Mode	C-Max	C-Max	None	C-Max	None	None	None
Act Effect Green (s)	79.0	79.0	100.9	100.9	16.8	38.8	
Actuated g/C Ratio	0.61	0.61	0.78	0.78	0.13	0.30	
v/c Ratio	0.29	0.19	0.44	0.33	0.69	0.28	
Control Delay	13.3	2.4	6.7	5.1	70.5	5.6	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	13.3	2.4	6.7	5.1	70.5	5.6	
LOS	B	A	A	A	E	A	
Approach Delay	10.8			5.5	36.1		
Approach LOS	B			A	D		
Queue Length 50th (m)	32.5	0.0	15.2	27.1	32.5	0.0	
Queue Length 95th (m)	49.7	9.5	28.5	42.5	50.3	13.0	
Internal Link Dist (m)	333.2			349.9	418.3		
Turn Bay Length (m)			45.0		20.0		
Base Capacity (vph)	2040	953	632	2631	293	564	
Starvation Cap Reductn	0	0	0	0	0	0	
Spillback Cap Reductn	0	0	0	0	0	0	
Storage Cap Reductn	0	0	0	0	0	0	
Reduced v/c Ratio	0.29	0.19	0.44	0.33	0.48	0.28	

Intersection Summary

Area Type: Other

Cycle Length: 130

Actuated Cycle Length: 130

Offset: 15 (12%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 85

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.69

Intersection Signal Delay: 11.5


Intersection LOS: B

Intersection Capacity Utilization 57.6%






















ICU Level of Service B

Analysis Period (min) 15













Splits and Phases: 6: Cedarview Road & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 AM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	161	1201	19	8	545	149	30	2	14	87	6	74
Future Volume (vph)	161	1201	19	8	545	149	30	2	14	87	6	74
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		0.99			0.99	
Frt			0.850			0.850		0.959			0.940	
Flt Protected	0.950			0.950				0.968			0.975	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1642	0	0	1581	0
Flt Permitted	0.449			0.196				0.756			0.812	
Satd. Flow (perm)	777	3357	1461	339	3357	1446	0	1282	0	0	1313	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			45			149		14			54	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			378.0			325.9			150.3	
Travel Time (s)		19.2			19.4			29.3			10.8	
Confl. Peds. (#/hr)	2		4	4		2	2		6	6		2
Confl. Bikes (#/hr)			1			6			2			
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	161	1201	19	8	545	149	30	2	14	87	6	74
Shared Lane Traffic (%)												
Lane Group Flow (vph)	161	1201	19	8	545	149	0	46	0	0	167	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	2.0	10.0	6.1	6.1	10.0	2.0	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	2.0	0.6	6.1	6.1	0.6	2.0	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		9.4			9.4			28.7			28.7	
Detector 2 Size(m)		0.6			0.6			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 AM Peak





















												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Perm	NA	Perm	Perm	NA	Perm	Perm	NA		Perm	NA	
Protected Phases		2			6			8			4	
Permitted Phases	2		2	6		6	8			4		
Detector Phase	2	2	2	6	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	32.2	32.2	32.2	32.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	47.0	47.0	47.0	47.0	47.0	47.0	38.0	38.0		38.0	38.0	
Total Split (%)	55.3%	55.3%	55.3%	55.3%	55.3%	55.3%	44.7%	44.7%		44.7%	44.7%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Max	C-Max	C-Max	C-Max	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	56.3	56.3	56.3	56.3	56.3	56.3		16.0			16.0	
Actuated g/C Ratio	0.66	0.66	0.66	0.66	0.66	0.66		0.19			0.19	
v/c Ratio	0.31	0.54	0.02	0.04	0.24	0.15		0.18			0.58	
Control Delay	10.6	10.3	1.1	16.6	11.2	6.6		20.5			27.2	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	10.6	10.3	1.1	16.6	11.2	6.6		20.5			27.2	
LOS	B	B	A	B	B	A		C			C	
Approach Delay		10.2			10.3			20.5			27.2	
Approach LOS		B			B			C			C	
Queue Length 50th (m)	7.8	37.5	0.0	0.3	11.8	0.0		4.2			15.9	
Queue Length 95th (m)	29.8	94.4	1.0	m3.7	49.8	20.4		9.4			25.3	
Internal Link Dist (m)		349.9			354.0			301.9			126.3	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	514	2225	983	224	2225	1008		483			520	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.31	0.54	0.02	0.04	0.24	0.15		0.10			0.32	
Intersection Summary												
Area Type:	Other											
Cycle Length: 85												
Actuated Cycle Length: 85												
Offset: 37 (44%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.58												
Intersection Signal Delay: 11.7						Intersection LOS: B						
Intersection Capacity Utilization 71.4%						ICU Level of Service C						
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 AM Peak













Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 PM Peak


												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	42	731	57	14	1203	67	38	4	12	122	5	106
Future Volume (vph)	42	731	57	14	1203	67	38	4	12	122	5	106
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		1.00			0.99	
Frt			0.850			0.850		0.970			0.939	
Flt Protected	0.950			0.950				0.966			0.974	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1661	0	0	1576	0
Flt Permitted	0.192			0.358				0.682			0.807	
Satd. Flow (perm)	333	3357	1456	619	3357	1446	0	1172	0	0	1300	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			57			39		12			44	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			378.0			325.9			150.3	
Travel Time (s)		19.2			19.4			29.3			10.8	
Confl. Peds. (#/hr)	3		4	4		3			9	9		
Confl. Bikes (#/hr)			5			3						3
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	42	731	57	14	1203	67	38	4	12	122	5	106
Shared Lane Traffic (%)												
Lane Group Flow (vph)	42	731	57	14	1203	67	0	54	0	0	233	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	2.0	10.0	6.1	6.1	10.0	2.0	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	2.0	0.6	6.1	6.1	0.6	2.0	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		9.4			9.4			28.7			28.7	
Detector 2 Size(m)		0.6			0.6			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 PM Peak












												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Perm	NA	Perm	Perm	NA	Perm	Perm	NA		Perm	NA	
Protected Phases		2			6			8			4	
Permitted Phases	2		2	6		6	8			4		
Detector Phase	2	2	2	6	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0	10.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	32.2	32.2	32.2	32.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	62.0	62.0	62.0	62.0	62.0	62.0	38.0	38.0		38.0	38.0	
Total Split (%)	62.0%	62.0%	62.0%	62.0%	62.0%	62.0%	38.0%	38.0%		38.0%	38.0%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	C-Max	C-Max	C-Max	C-Max	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	66.6	66.6	66.6	66.6	66.6	66.6		20.7			20.7	
Actuated g/C Ratio	0.67	0.67	0.67	0.67	0.67	0.67		0.21			0.21	
v/c Ratio	0.19	0.33	0.06	0.03	0.54	0.07		0.22			0.77	
Control Delay	11.5	8.6	2.7	3.5	6.0	0.8		26.1			45.8	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	11.5	8.6	2.7	3.5	6.0	0.8		26.1			45.8	
LOS	B	A	A	A	A	A		C			D	
Approach Delay		8.4			5.7			26.1			45.8	
Approach LOS		A			A			C			D	
Queue Length 50th (m)	2.5	25.9	0.0	0.3	57.7	0.2		6.2			32.3	
Queue Length 95th (m)	9.7	47.3	4.8	m0.6	13.8	0.0		13.7			49.7	
Internal Link Dist (m)		349.9			354.0			301.9			126.3	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	221	2237	989	412	2237	976		377			439	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.19	0.33	0.06	0.03	0.54	0.07		0.14			0.53	
Intersection Summary												
Area Type:	Other											
Cycle Length: 100												
Actuated Cycle Length: 100												
Offset: 77 (77%), Referenced to phase 2:EBTL and 6:WBTL, Start of Green												
Natural Cycle: 70												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.77												
Intersection Signal Delay: 11.0							Intersection LOS: B					
Intersection Capacity Utilization 62.5%							ICU Level of Service B					
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 PM Peak

Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/Sandcastle Dr
Total2035 AM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations							
Traffic Volume (vph)	1281	25	94	647	60	129	
Future Volume (vph)	1281	25	94	647	60	129	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	146.0		37.0	0.0	
Storage Lanes		0	1		1	1	
Taper Length (m)			26.0		75.0		
Lane Util. Factor	0.95	0.95	1.00	0.95	1.00	1.00	
Ped Bike Factor	1.00				1.00		
Frt	0.997					0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3346	0	1695	3357	1695	1488	
Flt Permitted			0.174		0.950		
Satd. Flow (perm)	3346	0	310	3357	1693	1488	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)	3					102	
Link Speed (k/h)	70			70	50		
Link Distance (m)	378.0			246.3	226.0		
Travel Time (s)	19.4			12.7	16.3		
Confl. Peds. (#/hr)		5	5		1		
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	2%	3%	2%	4%	
Adj. Flow (vph)	1281	25	94	647	60	129	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	1306	0	94	647	60	129	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	1.6			1.6	1.6		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		97	97		97	97	
Number of Detectors	2		1	2	1	1	
Detector Template	Thru		Left	Thru	Left	Right	
Leading Detector (m)	10.0		2.0	10.0	2.0	2.0	
Trailing Detector (m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Size(m)	0.6		2.0	0.6	2.0	2.0	
Detector 1 Type	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0		0.0	0.0	0.0	0.0	
Detector 2 Position(m)	9.4			9.4			
Detector 2 Size(m)	0.6			0.6			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Sandcastle Dr
Total2035 AM Peak

	→	↘	↙	←	↖	↗	
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA		Perm	NA	Prot	Perm	
Protected Phases	2			6	8		7
Permitted Phases			6			8	
Detector Phase	2		6	6	8	8	
Switch Phase							
Minimum Initial (s)	10.0		10.0	10.0	5.0	5.0	1.0
Minimum Split (s)	23.9		15.9	15.9	32.5	32.5	5.0
Total Split (s)	47.0		47.0	47.0	33.0	33.0	5.0
Total Split (%)	55.3%		55.3%	55.3%	38.8%	38.8%	6%
Yellow Time (s)	4.2		4.2	4.2	3.0	3.0	2.0
All-Red Time (s)	1.7		1.7	1.7	3.5	3.5	0.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.9		5.9	5.9	6.5	6.5	
Lead/Lag					Lag	Lag	Lead
Lead-Lag Optimize?							
Recall Mode	C-Max		C-Max	C-Max	None	None	None
Act Effct Green (s)	60.3		60.3	60.3	11.3	11.3	
Actuated g/C Ratio	0.71		0.71	0.71	0.13	0.13	
v/c Ratio	0.55		0.43	0.27	0.27	0.45	
Control Delay	2.5		18.5	6.4	32.9	14.3	
Queue Delay	0.0		0.0	0.0	0.0	0.0	
Total Delay	2.5		18.5	6.4	32.9	14.3	
LOS	A		B	A	C	B	
Approach Delay	2.5			8.0	20.2		
Approach LOS	A			A	C		
Queue Length 50th (m)	7.6		3.9	12.1	8.6	3.8	
Queue Length 95th (m)	10.9		#32.2	42.0	14.4	13.9	
Internal Link Dist (m)	354.0			222.3	202.0		
Turn Bay Length (m)			146.0		37.0		
Base Capacity (vph)	2373		219	2379	528	534	
Starvation Cap Reductn	0		0	0	0	0	
Spillback Cap Reductn	0		0	0	0	0	
Storage Cap Reductn	0		0	0	0	0	
Reduced v/c Ratio	0.55		0.43	0.27	0.11	0.24	

Intersection Summary

Area Type: Other

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 55 (65%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.55

Intersection Signal Delay: 5.8

Intersection LOS: A

Intersection Capacity Utilization 66.0%

ICU Level of Service C


Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.

Baseline Rd/Sandcastle Dr
Total2035 AM Peak







Splits and Phases: 5: Sandcastle Dr & Baseline Road



Baseline Rd/Sandcastle Dr
Total2035 PM Peak

							Ø7
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Lane Configurations	↑↑		↵	↑↑	↵	↵	
Traffic Volume (vph)	822	43	193	1217	68	107	
Future Volume (vph)	822	43	193	1217	68	107	
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	
Storage Length (m)		0.0	146.0		37.0	0.0	
Storage Lanes		0	1		1	1	
Taper Length (m)			26.0		75.0		
Lane Util. Factor	0.95	0.95	1.00	0.95	1.00	1.00	
Ped Bike Factor					0.99	0.98	
Frt	0.993					0.850	
Flt Protected			0.950		0.950		
Satd. Flow (prot)	3335	0	1695	3357	1695	1488	
Flt Permitted			0.313		0.950		
Satd. Flow (perm)	3335	0	558	3357	1674	1461	
Right Turn on Red		Yes				Yes	
Satd. Flow (RTOR)	9					107	
Link Speed (k/h)	70			70	50		
Link Distance (m)	378.0			246.3	226.0		
Travel Time (s)	19.4			12.7	16.3		
Confl. Peds. (#/hr)					11	5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	
Heavy Vehicles (%)	3%	2%	2%	3%	2%	4%	
Adj. Flow (vph)	822	43	193	1217	68	107	
Shared Lane Traffic (%)							
Lane Group Flow (vph)	865	0	193	1217	68	107	
Enter Blocked Intersection	No	No	No	No	No	No	
Lane Alignment	Left	Right	Left	Left	Left	Right	
Median Width(m)	3.7			3.7	3.7		
Link Offset(m)	0.0			0.0	0.0		
Crosswalk Width(m)	1.6			1.6	1.6		
Two way Left Turn Lane							
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	
Turning Speed (k/h)		97	97		97	97	
Number of Detectors	2		1	2	1	1	
Detector Template	Thru		Left	Thru	Left	Right	
Leading Detector (m)	10.0		2.0	10.0	2.0	2.0	
Trailing Detector (m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Size(m)	0.6		2.0	0.6	2.0	2.0	
Detector 1 Type	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel							
Detector 1 Extend (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0		0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0		0.0	0.0	0.0	0.0	
Detector 2 Position(m)	9.4			9.4			
Detector 2 Size(m)	0.6			0.6			
Detector 2 Type	Cl+Ex			Cl+Ex			
Detector 2 Channel							
Detector 2 Extend (s)	0.0			0.0			

Baseline Rd/Sandcastle Dr
Total2035 PM Peak

							
Lane Group	EBT	EBR	WBL	WBT	NBL	NBR	Ø7
Turn Type	NA		Perm	NA	Perm	Perm	
Protected Phases	2			6			7
Permitted Phases			6		8	8	
Detector Phase	2		6	6	8	8	
Switch Phase							
Minimum Initial (s)	10.0		10.0	10.0	5.0	5.0	1.0
Minimum Split (s)	23.9		15.9	15.9	32.5	32.5	5.0
Total Split (s)	62.0		62.0	62.0	33.0	33.0	5.0
Total Split (%)	62.0%		62.0%	62.0%	33.0%	33.0%	5%
Yellow Time (s)	4.2		4.2	4.2	3.0	3.0	2.0
All-Red Time (s)	1.7		1.7	1.7	3.5	3.5	0.0
Lost Time Adjust (s)	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	5.9		5.9	5.9	6.5	6.5	
Lead/Lag					Lag	Lag	Lead
Lead-Lag Optimize?							
Recall Mode	C-Max		C-Max	C-Max	None	None	None
Act Effct Green (s)	74.6		74.6	74.6	12.0	12.0	
Actuated g/C Ratio	0.75		0.75	0.75	0.12	0.12	
v/c Ratio	0.35		0.46	0.49	0.34	0.40	
Control Delay	4.7		12.5	7.4	42.1	11.2	
Queue Delay	0.0		0.0	0.0	0.0	0.0	
Total Delay	4.7		12.5	7.4	42.1	11.2	
LOS	A		B	A	D	B	
Approach Delay	4.7			8.1	23.2		
Approach LOS	A			A	C		
Queue Length 50th (m)	15.6		9.1	30.9	11.7	0.0	
Queue Length 95th (m)	36.5		46.2	92.5	19.3	11.3	
Internal Link Dist (m)	354.0			222.3	202.0		
Turn Bay Length (m)			146.0		37.0		
Base Capacity (vph)	2489		416	2504	443	465	
Starvation Cap Reductn	0		0	0	0	0	
Spillback Cap Reductn	0		0	0	0	0	
Storage Cap Reductn	0		0	0	0	0	
Reduced v/c Ratio	0.35		0.46	0.49	0.15	0.23	

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 62 (62%), Referenced to phase 2:EBT and 6:WBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.49

Intersection Signal Delay: 8.0

Intersection LOS: A

Intersection Capacity Utilization 58.8%

ICU Level of Service B










Analysis Period (min) 15

Splits and Phases: 5: Sandcastle Dr & Baseline Road












John Sutherland Dr/QCH West Ring Road (South)

Total2035 AM Peak










						
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	26	99	196	152	48	63
Future Volume (Veh/h)	26	99	196	152	48	63
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	26	99	196	152	48	63
Pedestrians					9	
Lane Width (m)					3.7	
Walking Speed (m/s)					1.0	
Percent Blockage					1	
Right turn flare (veh)						
Median type				None	None	
Median storage veh						
Upstream signal (m)				150		
pX, platoon unblocked						
vC, conflicting volume	632	80	111			
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	632	80	111			
tC, single (s)	6.4	6.2	4.1			
tC, 2 stage (s)						
tF (s)	3.5	3.3	2.2			
p0 queue free %	93	90	87			
cM capacity (veh/h)	382	981	1479			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	125	348	111			
Volume Left	26	196	0			
Volume Right	99	0	63			
cSH	739	1479	1700			
Volume to Capacity	0.17	0.13	0.07			
Queue Length 95th (m)	4.2	3.2	0.0			
Control Delay (s)	10.9	4.9	0.0			
Lane LOS	B	A				
Approach Delay (s)	10.9	4.9	0.0			
Approach LOS	B					
Intersection Summary						
Average Delay		5.2				
Intersection Capacity Utilization		41.2%	ICU Level of Service	A		
Analysis Period (min)		15				

John Sutherland Dr/QCH West Ring Road (South)











Total 2035 PM Peak

						
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Volume (veh/h)	70	155	79	65	113	52
Future Volume (Veh/h)	70	155	79	65	113	52
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	70	155	79	65	113	52
Pedestrians					17	
Lane Width (m)					3.7	
Walking Speed (m/s)					1.0	
Percent Blockage					2	
Right turn flare (veh)						
Median type				None	None	
Median storage veh						
Upstream signal (m)				150		
pX, platoon unblocked						
vC, conflicting volume	379	139	165			
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	379	139	165			
tC, single (s)	6.4	6.2	4.1			
tC, 2 stage (s)						
tF (s)	3.5	3.3	2.2			
p0 queue free %	88	83	94			
cM capacity (veh/h)	578	909	1413			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	225	144	165			
Volume Left	70	79	0			
Volume Right	155	0	52			
cSH	772	1413	1700			
Volume to Capacity	0.29	0.06	0.10			
Queue Length 95th (m)	8.5	1.2	0.0			
Control Delay (s)	11.6	4.4	0.0			
Lane LOS	B	A				
Approach Delay (s)	11.6	4.4	0.0			
Approach LOS	B					
Intersection Summary						
Average Delay		6.1				
Intersection Capacity Utilization		42.0%	ICU Level of Service	A		
Analysis Period (min)		15				

John Sutherland Dr/QCH Irving Greenberg Cancer Center
Total2035 AM Peak










						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Volume (veh/h)	130	38	14	120	12	2
Future Volume (Veh/h)	130	38	14	120	12	2
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	130	38	14	120	12	2
Pedestrians	38			1	4	
Lane Width (m)	3.7			3.7	3.7	
Walking Speed (m/s)	1.0			1.0	1.0	
Percent Blockage	4			0	0	
Right turn flare (veh)						
Median type	None			None		
Median storage veh						
Upstream signal (m)	262					
pX, platoon unblocked						
vC, conflicting volume			172		339	154
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			172		339	154
tC, single (s)			4.1		6.4	6.2
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			99		98	100
cM capacity (veh/h)			1399		622	887
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total	168	134	14			
Volume Left	0	14	12			
Volume Right	38	0	2			
cSH	1700	1399	650			
Volume to Capacity	0.10	0.01	0.02			
Queue Length 95th (m)	0.0	0.2	0.5			
Control Delay (s)	0.0	0.9	10.7			
Lane LOS		A	B			
Approach Delay (s)	0.0	0.9	10.7			
Approach LOS			B			
Intersection Summary						
Average Delay		0.8				
Intersection Capacity Utilization		29.4%	ICU Level of Service	A		
Analysis Period (min)		15				

John Sutherland Dr/QCH Irving Greenberg Cancer Center
Total2035 PM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Volume (veh/h)	142	17	17	103	44	24
Future Volume (Veh/h)	142	17	17	103	44	24
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	142	17	17	103	44	24
Pedestrians	32			4	8	
Lane Width (m)	3.7			3.7	3.7	
Walking Speed (m/s)	1.0			1.0	1.0	
Percent Blockage	3			0	1	
Right turn flare (veh)						
Median type	None			None		
Median storage (veh)						
Upstream signal (m)	262					
pX, platoon unblocked						
vC, conflicting volume			167		328	162
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			167		328	162
tC, single (s)			4.1		6.4	6.2
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			99		93	97
cM capacity (veh/h)			1399		632	871
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total	159	120	68			
Volume Left	0	17	44			
Volume Right	17	0	24			
cSH	1700	1399	700			
Volume to Capacity	0.09	0.01	0.10			
Queue Length 95th (m)	0.0	0.3	2.3			
Control Delay (s)	0.0	1.2	10.7			
Lane LOS		A	B			
Approach Delay (s)	0.0	1.2	10.7			
Approach LOS			B			
Intersection Summary						
Average Delay			2.5			
Intersection Capacity Utilization			32.2%	ICU Level of Service		A
Analysis Period (min)			15			










John Sutherland Dr/QCH West Ring Road (North)

Total 2035 AM Peak

















						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Volume (veh/h)	129	355	106	43	137	39
Future Volume (Veh/h)	129	355	106	43	137	39
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	129	355	106	43	137	39
Pedestrians	5			7	2	
Lane Width (m)	3.7			3.7	3.7	
Walking Speed (m/s)	1.0			1.0	1.0	
Percent Blockage	1			1	0	
Right turn flare (veh)						
Median type	None			None		
Median storage veh						
Upstream signal (m)	121					
pX, platoon unblocked			0.95		0.95	0.95
vC, conflicting volume			486		568	316
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			436		523	258
tC, single (s)			4.1		6.4	6.2
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			90		69	95
cM capacity (veh/h)			1069		439	738
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total	484	149	176			
Volume Left	0	106	137			
Volume Right	355	0	39			
cSH	1700	1069	482			
Volume to Capacity	0.28	0.10	0.37			
Queue Length 95th (m)	0.0	2.3	11.6			
Control Delay (s)	0.0	6.5	16.7			
Lane LOS		A	C			
Approach Delay (s)	0.0	6.5	16.7			
Approach LOS			C			
Intersection Summary						
Average Delay		4.8				
Intersection Capacity Utilization		60.2%	ICU Level of Service	B		
Analysis Period (min)		15				

John Sutherland Dr/QCH West Ring Road (North)

















Total 2035 PM Peak

						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Volume (veh/h)	83	71	22	133	347	77
Future Volume (Veh/h)	83	71	22	133	347	77
Sign Control	Free			Free	Stop	
Grade	0%			0%	0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	83	71	22	133	347	77
Pedestrians	3			6	9	
Lane Width (m)	3.7			3.7	3.7	
Walking Speed (m/s)	1.0			1.0	1.0	
Percent Blockage	0			1	1	
Right turn flare (veh)						
Median type	None			None		
Median storage veh						
Upstream signal (m)	121					
pX, platoon unblocked			1.00		1.00	1.00
vC, conflicting volume			163		308	134
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol			162		307	133
tC, single (s)			4.1		6.4	6.2
tC, 2 stage (s)						
tF (s)			2.2		3.5	3.3
p0 queue free %			98		48	91
cM capacity (veh/h)			1403		666	902
Direction, Lane #	EB 1	WB 1	NB 1			
Volume Total	154	155	424			
Volume Left	0	22	347			
Volume Right	71	0	77			
cSH	1700	1403	699			
Volume to Capacity	0.09	0.02	0.61			
Queue Length 95th (m)	0.0	0.3	28.9			
Control Delay (s)	0.0	1.2	17.8			
Lane LOS		A	C			
Approach Delay (s)	0.0	1.2	17.8			
Approach LOS			C			
Intersection Summary						
Average Delay		10.5				
Intersection Capacity Utilization		54.6%	ICU Level of Service	A		
Analysis Period (min)		15				






















John Sutherland Dr/QCH Lot TL2
Total2035 AM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	22	155	0	0	144	0	0	0	0	0	0	3
Future Volume (Veh/h)	22	155	0	0	144	0	0	0	0	0	0	3
Sign Control		Free			Free			Stop			Stop	
Grade		0%			0%			0%			0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	22	155	0	0	144	0	0	0	0	0	0	3
Pedestrians		3			89			18				
Lane Width (m)		3.7			3.7			3.7				
Walking Speed (m/s)		1.0			1.0			1.0				
Percent Blockage		0			9			2				
Right turn flare (veh)												
Median type		None			None							
Median storage (veh)												
Upstream signal (m)		169										
pX, platoon unblocked												
vC, conflicting volume	144			173			367	361	262	432	361	147
vC1, stage 1 conf vol												
vC2, stage 2 conf vol												
vCu, unblocked vol	144			173			367	361	262	432	361	147
tC, single (s)	4.1			4.1			7.1	6.5	6.2	7.1	6.5	6.2
tC, 2 stage (s)												
tF (s)	2.2			2.2			3.5	4.0	3.3	3.5	4.0	3.3
p0 queue free %	98			100			100	100	100	100	100	100
cM capacity (veh/h)	1438			1360			558	547	693	473	547	897
Direction, Lane #	EB 1	WB 1	NB 1	SB 1								
Volume Total	177	144	0	3								
Volume Left	22	0	0	0								
Volume Right	0	0	0	3								
cSH	1438	1360	1700	897								
Volume to Capacity	0.02	0.00	0.00	0.00								
Queue Length 95th (m)	0.3	0.0	0.0	0.1								
Control Delay (s)	1.0	0.0	0.0	9.0								
Lane LOS	A		A	A								
Approach Delay (s)	1.0	0.0	0.0	9.0								
Approach LOS			A	A								
Intersection Summary												
Average Delay			0.7									
Intersection Capacity Utilization			42.3%	ICU Level of Service					A			
Analysis Period (min)			15									













John Sutherland Dr/QCH Lot TL2
Total2035 PM Peak

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	0	148	0	0	147	0	0	0	0	0	0	19
Future Volume (Veh/h)	0	148	0	0	147	0	0	0	0	0	0	19
Sign Control		Free			Free			Stop			Stop	
Grade		0%			0%			0%			0%	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Hourly flow rate (vph)	0	148	0	0	147	0	0	0	0	0	0	19
Pedestrians		2			41			22				
Lane Width (m)		3.7			3.7			3.7				
Walking Speed (m/s)		1.0			1.0			1.0				
Percent Blockage		0			4			2				
Right turn flare (veh)												
Median type		None			None							
Median storage (veh)												
Upstream signal (m)		169										
pX, platoon unblocked												
vC, conflicting volume	147			170			338	317	211	336	317	149
vC1, stage 1 conf vol												
vC2, stage 2 conf vol												
vCu, unblocked vol	147			170			338	317	211	336	317	149
tC, single (s)	4.1			4.1			7.1	6.5	6.2	7.1	6.5	6.2
tC, 2 stage (s)												
tF (s)	2.2			2.2			3.5	4.0	3.3	3.5	4.0	3.3
p0 queue free %	100			100			100	100	100	100	100	98
cM capacity (veh/h)	1435			1358			576	586	776	581	586	896
Direction, Lane #	EB 1	WB 1	NB 1	SB 1								
Volume Total	148	147	0	19								
Volume Left	0	0	0	0								
Volume Right	0	0	0	19								
cSH	1435	1358	1700	896								
Volume to Capacity	0.00	0.00	0.00	0.02								
Queue Length 95th (m)	0.0	0.0	0.0	0.5								
Control Delay (s)	0.0	0.0	0.0	9.1								
Lane LOS			A	A								
Approach Delay (s)	0.0	0.0	0.0	9.1								
Approach LOS			A	A								
Intersection Summary												
Average Delay			0.6									
Intersection Capacity Utilization			28.3%		ICU Level of Service				A			
Analysis Period (min)			15									

Richmond Rd/John Sutherland Dr
Total2030 AM Peak - Mitigated

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	77	0	106	0	949	134	296	563	0
Future Volume (vph)	0	0	0	77	0	106	0	949	134	296	563	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	1		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Frt					0.850				0.850			
Flt Protected				0.950						0.950		
Satd. Flow (prot)	0	1784	0	1695	1473	0	1784	3390	1517	1679	3390	0
Flt Permitted				0.757						0.203		
Satd. Flow (perm)	0	1784	0	1351	1473	0	1784	3390	1517	359	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					380				109			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	5%	2%	2%	2%	3%	2%	2%
Adj. Flow (vph)	0	0	0	77	0	106	0	949	134	296	563	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	77	106	0	0	949	134	296	563	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type				Perm	NA		Perm	NA	Perm	pm+pt	NA	
Protected Phases		4			8			2		1	6	

Richmond Rd/John Sutherland Dr
Total2030 AM Peak - Mitigated

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	1	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	5.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	11.4	29.4	
Total Split (s)	37.6	37.6		37.6	37.6		39.4	39.4	39.4	23.0	62.4	
Total Split (%)	37.6%	37.6%		37.6%	37.6%		39.4%	39.4%	39.4%	23.0%	62.4%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6		6.6	6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag							Lag	Lag	Lag	Lead		
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	None	C-Max	
Act Effct Green (s)				12.0	12.0			51.0	51.0	75.0	75.0	
Actuated g/C Ratio				0.12	0.12			0.51	0.51	0.75	0.75	
v/c Ratio				0.48	0.21			0.55	0.16	0.59	0.22	
Control Delay				50.4	0.9			5.9	0.5	10.6	4.2	
Queue Delay				0.0	0.0			0.0	0.0	0.0	0.0	
Total Delay				50.4	0.9			5.9	0.5	10.6	4.2	
LOS				D	A			A	A	B	A	
Approach Delay					21.7			5.2			6.4	
Approach LOS					C			A			A	
Queue Length 50th (m)				13.2	0.0			7.9	0.1	12.6	12.4	
Queue Length 95th (m)				25.2	0.0			20.6	0.1	32.2	21.3	
Internal Link Dist (m)		73.1			97.2			335.3			631.9	
Turn Bay Length (m)									35.0	40.0		
Base Capacity (vph)				418	718			1729	827	522	2541	
Starvation Cap Reductn				0	0			0	0	0	0	
Spillback Cap Reductn				0	0			0	0	0	0	
Storage Cap Reductn				0	0			0	0	0	0	
Reduced v/c Ratio				0.18	0.15			0.55	0.16	0.57	0.22	

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 12 (12%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.59

Intersection Signal Delay: 7.1


Intersection LOS: A

Intersection Capacity Utilization 69.5%


ICU Level of Service C

Analysis Period (min) 15













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/John Sutherland Dr
Total2030 PM Peak - Mitigated

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕		↗	↖		↗	↕	↖	↗	↕	↖
Traffic Volume (vph)	0	0	0	187	0	274	4	785	43	98	937	0
Future Volume (vph)	0	0	0	187	0	274	4	785	43	98	937	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	1		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Ped Bike Factor							1.00		0.98	1.00		
Frt					0.850				0.850			
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	1784	0	1695	1502	0	1695	3390	1517	1647	3390	0
Flt Permitted				0.757			0.305			0.286		
Satd. Flow (perm)	0	1784	0	1351	1502	0	543	3390	1482	495	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					291				91			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Confl. Peds. (#/hr)							2		1	1		2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	3%	2%	2%	2%	5%	2%	2%
Adj. Flow (vph)	0	0	0	187	0	274	4	785	43	98	937	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	187	274	0	4	785	43	98	937	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	

Richmond Rd/John Sutherland Dr
Total2030 PM Peak - Mitigated

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Turn Type				Perm	NA		Perm	NA	Perm	pm+pt	NA	
Protected Phases		4			8			2		1	6	
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	1	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	5.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	11.4	29.4	
Total Split (s)	44.0	44.0		44.0	44.0		57.0	57.0	57.0	19.0	76.0	
Total Split (%)	36.7%	36.7%		36.7%	36.7%		47.5%	47.5%	47.5%	15.8%	63.3%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6		6.6	6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag							Lag	Lag	Lag	Lead		
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	None	C-Max	
Act Effect Green (s)				22.5	22.5		70.1	70.1	70.1	84.5	84.5	
Actuated g/C Ratio				0.19	0.19		0.58	0.58	0.58	0.70	0.70	
v/c Ratio				0.74	0.53		0.01	0.40	0.05	0.23	0.39	
Control Delay				62.4	7.2		5.0	4.2	0.1	8.2	8.6	
Queue Delay				0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Total Delay				62.4	7.2		5.0	4.2	0.1	8.2	8.6	
LOS				E	A		A	A	A	A	A	
Approach Delay					29.6			4.0			8.6	
Approach LOS					C			A			A	
Queue Length 50th (m)				38.8	0.0		0.1	8.2	0.0	5.9	38.6	
Queue Length 95th (m)				56.1	15.3		m0.3	17.2	0.3	14.2	64.3	
Internal Link Dist (m)		73.1			97.2			335.3			631.9	
Turn Bay Length (m)							40.0		35.0	40.0		
Base Capacity (vph)				421	668		317	1981	904	469	2387	
Starvation Cap Reductn				0	0		0	0	0	0	0	
Spillback Cap Reductn				0	0		0	0	0	0	0	
Storage Cap Reductn				0	0		0	0	0	0	0	
Reduced v/c Ratio				0.44	0.41		0.01	0.40	0.05	0.21	0.39	

Intersection Summary

Area Type: Other

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 118 (98%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.74

Intersection Signal Delay: 11.1

Intersection LOS: B

Intersection Capacity Utilization 69.7%

ICU Level of Service C

Analysis Period (min) 15


m Volume for 95th percentile queue is metered by upstream signal.

Richmond Rd/John Sutherland Dr
Total2030 PM Peak - Mitigated













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/John Sutherland Dr
Total2035 AM Peak - Mitigated

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕		↖	↗		↖	↕	↗	↖	↕	↗
Traffic Volume (vph)	0	0	0	77	0	106	0	970	134	296	576	0
Future Volume (vph)	0	0	0	77	0	106	0	970	134	296	576	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	1		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Frt					0.850				0.850			
Flt Protected				0.950						0.950		
Satd. Flow (prot)	0	1784	0	1695	1473	0	1784	3390	1517	1679	3390	0
Flt Permitted				0.757						0.194		
Satd. Flow (perm)	0	1784	0	1351	1473	0	1784	3390	1517	343	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					359				109			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	5%	2%	2%	2%	3%	2%	2%
Adj. Flow (vph)	0	0	0	77	0	106	0	970	134	296	576	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	77	106	0	0	970	134	296	576	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type				Perm	NA		Perm	NA	Perm	pm+pt	NA	
Protected Phases		4			8			2		1	6	

Richmond Rd/John Sutherland Dr
Total2035 AM Peak - Mitigated

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	1	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	5.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	11.4	29.4	
Total Split (s)	37.6	37.6		37.6	37.6		40.4	40.4	40.4	22.0	62.4	
Total Split (%)	37.6%	37.6%		37.6%	37.6%		40.4%	40.4%	40.4%	22.0%	62.4%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6		6.6	6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag							Lag	Lag	Lag	Lead		
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	None	C-Max	
Act Effct Green (s)				12.0	12.0			50.6	50.6	75.0	75.0	
Actuated g/C Ratio				0.12	0.12			0.51	0.51	0.75	0.75	
v/c Ratio				0.48	0.22			0.57	0.16	0.60	0.23	
Control Delay				50.4	1.0			6.0	0.4	11.2	4.2	
Queue Delay				0.0	0.0			0.0	0.0	0.0	0.0	
Total Delay				50.4	1.0			6.0	0.4	11.2	4.2	
LOS				D	A			A	A	B	A	
Approach Delay					21.8			5.3			6.6	
Approach LOS					C			A			A	
Queue Length 50th (m)				13.2	0.0			8.2	0.1	12.6	12.8	
Queue Length 95th (m)				25.2	0.0			14.9	0.1	34.1	22.0	
Internal Link Dist (m)		73.1			97.2			335.3			631.9	
Turn Bay Length (m)									35.0	40.0		
Base Capacity (vph)				418	704			1714	820	510	2541	
Starvation Cap Reductn				0	0			0	0	0	0	
Spillback Cap Reductn				0	0			0	0	0	0	
Storage Cap Reductn				0	0			0	0	0	0	
Reduced v/c Ratio				0.18	0.15			0.57	0.16	0.58	0.23	

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 11 (11%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.60

Intersection Signal Delay: 7.2


Intersection LOS: A

Intersection Capacity Utilization 70.1%


ICU Level of Service C

Analysis Period (min) 15













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/John Sutherland Dr
Total2035 PM Peak - Mitigated

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕		↗	↖		↗	↕	↖	↗	↕	↖
Traffic Volume (vph)	0	0	0	187	0	274	4	802	43	98	958	0
Future Volume (vph)	0	0	0	187	0	274	4	802	43	98	958	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	1		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Ped Bike Factor							1.00		0.98	1.00		
Frt					0.850				0.850			
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	1784	0	1695	1502	0	1695	3390	1517	1647	3390	0
Flt Permitted				0.757			0.299			0.279		
Satd. Flow (perm)	0	1784	0	1351	1502	0	533	3390	1482	483	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					287				91			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Confl. Peds. (#/hr)							2		1	1		2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	3%	2%	2%	2%	5%	2%	2%
Adj. Flow (vph)	0	0	0	187	0	274	4	802	43	98	958	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	187	274	0	4	802	43	98	958	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	

Richmond Rd/John Sutherland Dr
Total2035 PM Peak - Mitigated

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Turn Type				Perm	NA		Perm	NA	Perm	pm+pt	NA	
Protected Phases		4			8			2		1	6	
Permitted Phases	4			8			2		2	6		
Detector Phase	4	4		8	8		2	2	2	1	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		10.0	10.0	10.0	5.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		29.4	29.4	29.4	11.4	29.4	
Total Split (s)	44.0	44.0		44.0	44.0		57.0	57.0	57.0	19.0	76.0	
Total Split (%)	36.7%	36.7%		36.7%	36.7%		47.5%	47.5%	47.5%	15.8%	63.3%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6		6.6	6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag							Lag	Lag	Lag	Lead		
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		C-Max	C-Max	C-Max	None	C-Max	
Act Effect Green (s)				22.5	22.5		70.1	70.1	70.1	84.5	84.5	
Actuated g/C Ratio				0.19	0.19		0.58	0.58	0.58	0.70	0.70	
v/c Ratio				0.74	0.53		0.01	0.40	0.05	0.24	0.40	
Control Delay				62.4	7.5		5.0	4.2	0.1	8.2	8.7	
Queue Delay				0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Total Delay				62.4	7.5		5.0	4.2	0.1	8.2	8.7	
LOS				E	A		A	A	A	A	A	
Approach Delay					29.8			4.0			8.7	
Approach LOS					C			A			A	
Queue Length 50th (m)				38.8	0.0		0.1	8.3	0.0	5.9	39.8	
Queue Length 95th (m)				56.1	16.0		m0.3	17.4	0.2	14.2	66.1	
Internal Link Dist (m)		73.1			97.2			335.3			631.9	
Turn Bay Length (m)							40.0		35.0	40.0		
Base Capacity (vph)				421	665		311	1981	904	462	2387	
Starvation Cap Reductn				0	0		0	0	0	0	0	
Spillback Cap Reductn				0	0		0	0	0	0	0	
Storage Cap Reductn				0	0		0	0	0	0	0	
Reduced v/c Ratio				0.44	0.41		0.01	0.40	0.05	0.21	0.40	

Intersection Summary

Area Type: Other

Cycle Length: 120

Actuated Cycle Length: 120

Offset: 118 (98%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.74

Intersection Signal Delay: 11.1

Intersection LOS: B

Intersection Capacity Utilization 70.4%

ICU Level of Service C

Analysis Period (min) 15



m Volume for 95th percentile queue is metered by upstream signal.

Richmond Rd/John Sutherland Dr
Total2035 PM Peak - Mitigated

Splits and Phases: 11: Richmond Road & John Sutherland Drive



Appendix P: Functional Design of Proposed Roadway Modifications



Rb-16 NO U-TURN
Rb-25 ISLAND WARNING
Wa-33L OBJECT MARKER

WAY FINDER (HOSPITAL,
BUS STOP)

EDR/417
EAST SIGNS

RICHMOND ROAD

JOHN SUTHERLAND DRIVE

MAXIMUM
80
km/h

-Rb-3 (80km/h,

NOTE:
THE POSITION OF ALL POLE LINES, CONDUITS,
WATERMAINS, SEWERS AND OTHER
UNDERGROUND AND OVERGROUND UTILITIES AND
STRUCTURES IS NOT NECESSARILY SHOWN ON
THE CONTRACT DRAWINGS, AND WHERE SHOWN,
THE ACCURACY OF THE POSITION OF SUCH
UTILITIES AND STRUCTURES IS NOT GUARANTEED.
BEFORE STARTING WORK, DETERMINE THE EXACT
LOCATION OF ALL SUCH UTILITIES AND
STRUCTURES AND ASSUME ALL LIABILITY FOR
DAMAGE TO THEM.

1.	WIP		Nov ??/25	BJ
No.	REVISION		DATE	BY

SCALE

0 5 10 15 20

DESIGN

--	--

ABBO

--	--

FOR REVIEW ONLY

NOVATECH

Telephone (613) 254-9643
Facsimile (613) 254-5867
Website www.novatech-eng.com

LOCATION
CITY of OTTAWA
JOHN SUTHERLAND DRIVE & RICHMOND ROAD






















FUNCTIONAL DESIGN

REV # 1













123089-ED

Appendix Q: Synchro Analysis Reports for Protected Left Turn Movements Scenario

Richmond Rd/John Sutherland Dr
Total2035 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	0	0	0	77	0	106	0	970	134	296	576	0
Future Volume (vph)	0	0	0	77	0	106	0	970	134	296	576	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	1		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Frt					0.850				0.850			
Flt Protected				0.950						0.950		
Satd. Flow (prot)	0	1784	0	1695	1473	0	1784	3390	1517	1679	3390	0
Flt Permitted				0.757						0.950		
Satd. Flow (perm)	0	1784	0	1351	1473	0	1784	3390	1517	1679	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					319				179			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	5%	2%	2%	2%	3%	2%	2%
Adj. Flow (vph)	0	0	0	77	0	106	0	970	134	296	576	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	77	106	0	0	970	134	296	576	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type				Perm	NA		Prot	NA	Perm	Prot	NA	
Protected Phases		4			8		5	2		1	6	

Richmond Rd/John Sutherland Dr
Total2035 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Permitted Phases	4			8					2			
Detector Phase	4	4		8	8		5	2	2	1	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0		10.0	10.0		5.0	10.0	10.0	5.0	10.0	
Minimum Split (s)	37.6	37.6		37.6	37.6		11.4	29.4	29.4	11.4	29.4	
Total Split (s)	37.6	37.6		37.6	37.6		11.4	37.4	37.4	25.0	51.0	
Total Split (%)	37.6%	37.6%		37.6%	37.6%		11.4%	37.4%	37.4%	25.0%	51.0%	
Yellow Time (s)	3.3	3.3		3.3	3.3		4.6	4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3		3.3	3.3		1.8	1.8	1.8	1.8	1.8	
Lost Time Adjust (s)		0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Total Lost Time (s)		6.6		6.6	6.6		6.4	6.4	6.4	6.4	6.4	
Lead/Lag							Lead	Lag	Lag	Lead	Lag	
Lead-Lag Optimize?												
Recall Mode	None	None		None	None		None	C-Max	C-Max	None	C-Max	
Act Effect Green (s)				12.0	12.0			43.9	43.9	24.7	75.0	
Actuated g/C Ratio				0.12	0.12			0.44	0.44	0.25	0.75	
v/c Ratio				0.48	0.23			0.65	0.17	0.72	0.23	
Control Delay				50.4	1.2			11.5	0.7	44.4	4.2	
Queue Delay				0.0	0.0			0.0	0.0	0.0	0.0	
Total Delay				50.4	1.2			11.5	0.7	44.4	4.2	
LOS				D	A			B	A	D	A	
Approach Delay					21.9			10.2			17.9	
Approach LOS					C			B			B	
Queue Length 50th (m)				13.2	0.0			69.1	0.0	48.0	12.8	
Queue Length 95th (m)				25.2	0.0			88.4	0.2	70.8	22.0	
Internal Link Dist (m)		73.1			97.2			335.3			631.9	
Turn Bay Length (m)									35.0	40.0		
Base Capacity (vph)				418	676			1488	766	413	2541	
Starvation Cap Reductn				0	0			0	0	0	0	
Spillback Cap Reductn				0	0			0	0	0	0	
Storage Cap Reductn				0	0			0	0	0	0	
Reduced v/c Ratio				0.18	0.16			0.65	0.17	0.72	0.23	

Intersection Summary

Area Type: Other

Cycle Length: 100

Actuated Cycle Length: 100

Offset: 13 (13%), Referenced to phase 2:NBT and 6:SBT, Start of Green

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.72

Intersection Signal Delay: 14.3


Intersection LOS: B

Intersection Capacity Utilization 70.1%


ICU Level of Service C

Analysis Period (min) 15













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Richmond Rd/John Sutherland Dr
Total2035 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↕		↖	↗		↖	↕	↗	↖	↕	
Traffic Volume (vph)	0	0	0	187	0	274	4	802	43	98	958	0
Future Volume (vph)	0	0	0	187	0	274	4	802	43	98	958	0
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	0.0		0.0	0.0		0.0	40.0		35.0	40.0		0.0
Storage Lanes	0		0	1		0	1		1	1		0
Taper Length (m)	2.5			7.6			45.0			100.0		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	0.95	1.00	1.00	0.95	0.95
Ped Bike Factor							1.00		0.98	1.00		
Frt					0.850				0.850			
Flt Protected				0.950			0.950			0.950		
Satd. Flow (prot)	0	1784	0	1695	1502	0	1695	3390	1517	1647	3390	0
Flt Permitted				0.757			0.950			0.950		
Satd. Flow (perm)	0	1784	0	1351	1502	0	1693	3390	1482	1645	3390	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)					267				149			
Link Speed (k/h)		50			50			80			80	
Link Distance (m)		97.1			121.2			359.3			655.9	
Travel Time (s)		7.0			8.7			16.2			29.5	
Confl. Peds. (#/hr)							2		1	1		2
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	2%	2%	2%	2%	2%	3%	2%	2%	2%	5%	2%	2%
Adj. Flow (vph)	0	0	0	187	0	274	4	802	43	98	958	0
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	0	0	187	274	0	4	802	43	98	958	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			7.4			7.4	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		1.6			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2		1	2		1	2	1	1	2	
Detector Template	Left	Thru		Left	Thru		Left	Thru	Right	Left	Thru	
Leading Detector (m)	6.1	30.5		6.1	30.5		6.1	30.5	6.1	6.1	30.5	
Trailing Detector (m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Position(m)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Size(m)	6.1	1.8		6.1	1.8		6.1	1.8	6.1	6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Queue (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 1 Delay (s)	0.0	0.0		0.0	0.0		0.0	0.0	0.0	0.0	0.0	
Detector 2 Position(m)		28.7			28.7			28.7			28.7	
Detector 2 Size(m)		1.8			1.8			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	

Richmond Rd/John Sutherland Dr
Total2035 PM Peak






















												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Turn Type				Perm	NA		Prot		NA	Perm	Prot	NA
Protected Phases	4			8		5		2	1			6
Permitted Phases	4				8			2				
Detector Phase	4	4	8		8	5		2	2	1	6	
Switch Phase												
Minimum Initial (s)	10.0	10.0	10.0		10.0	5.0		10.0	10.0	5.0	10.0	
Minimum Split (s)	37.6	37.6	37.6		37.6	11.4		29.4	29.4	11.4	29.4	
Total Split (s)	42.0	42.0	42.0		42.0	12.0		54.0	54.0	24.0	66.0	
Total Split (%)	35.0%	35.0%	35.0%		35.0%	10.0%		45.0%	45.0%	20.0%	55.0%	
Yellow Time (s)	3.3	3.3	3.3		3.3	4.6		4.6	4.6	4.6	4.6	
All-Red Time (s)	3.3	3.3	3.3		3.3	1.8		1.8	1.8	1.8	1.8	
Lost Time Adjust (s)	0.0		0.0		0.0	0.0		0.0	0.0	0.0	0.0	
Total Lost Time (s)	6.6		6.6		6.6	6.4		6.4	6.4	6.4	6.4	
Lead/Lag							Lead	Lag	Lag	Lead	Lag	
Lead-Lag Optimize?												
Recall Mode	None	None	None		None	None		C-Max	C-Max	None	C-Max	
Act Effct Green (s)				22.4	22.4	5.9		65.8	65.8	12.4	82.0	
Actuated g/C Ratio				0.19	0.19	0.05		0.55	0.55	0.10	0.68	
v/c Ratio				0.74	0.55	0.05		0.43	0.05	0.58	0.41	
Control Delay				62.7	9.3	73.5		6.2	0.1	64.0	10.8	
Queue Delay				0.0	0.0	0.0		0.0	0.0	0.0	0.0	
Total Delay				62.7	9.3	73.5		6.2	0.1	64.0	10.8	
LOS				E	A	E		A	A	E	B	
Approach Delay					31.0	6.2				15.8		
Approach LOS					C	A				B		
Queue Length 50th (m)				38.8	1.3	0.9		9.9	0.0	20.6	39.6	
Queue Length 95th (m)				56.2	20.3	m2.2		28.0	0.2	35.1	88.1	
Internal Link Dist (m)	73.1				97.2	335.3			631.9			
Turn Bay Length (m)							40.0	35.0		40.0		
Base Capacity (vph)				398	631	84		1858	879	241	2315	
Starvation Cap Reductn				0	0	0		0	0	0	0	
Spillback Cap Reductn				0	0	0		0	0	0	0	
Storage Cap Reductn				0	0	0		0	0	0	0	
Reduced v/c Ratio				0.47	0.43	0.05		0.43	0.05	0.41	0.41	
Intersection Summary												
Area Type: Other												
Cycle Length: 120												
Actuated Cycle Length: 120												
Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green												
Natural Cycle: 80												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.74												
Intersection Signal Delay: 15.3					Intersection LOS: B							
Intersection Capacity Utilization 66.2%					ICU Level of Service C							
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Richmond Rd/John Sutherland Dr
Total2035 PM Peak













Splits and Phases: 11: Richmond Road & John Sutherland Drive



Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	161	1201	19	8	545	149	30	2	14	87	6	74
Future Volume (vph)	161	1201	19	8	545	149	30	2	14	87	6	74
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		0.99			0.99	
Frt			0.850			0.850		0.959			0.940	
Flt Protected	0.950			0.950				0.968			0.975	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1642	0	0	1581	0
Flt Permitted	0.950			0.950				0.756			0.812	
Satd. Flow (perm)	1644	3357	1461	1645	3357	1442	0	1282	0	0	1313	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			124			145		14			53	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			378.0			325.9			150.3	
Travel Time (s)		19.2			19.4			29.3			10.8	
Confl. Peds. (#/hr)	2		4	4		2	2		6	6		2
Confl. Bikes (#/hr)			1			6			2			
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	161	1201	19	8	545	149	30	2	14	87	6	74
Shared Lane Traffic (%)												
Lane Group Flow (vph)	161	1201	19	8	545	149	0	46	0	0	167	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	2.0	10.0	6.1	6.1	10.0	2.0	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	2.0	0.6	6.1	6.1	0.6	2.0	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		9.4			9.4			28.7			28.7	
Detector 2 Size(m)		0.6			0.6			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 AM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Prot	NA	Perm	Prot	NA	Perm	Perm	NA		Perm	NA	
Protected Phases	5	2		1	6			8			4	
Permitted Phases			2			6	8			4		
Detector Phase	5	2	2	1	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	5.0	10.0	10.0	5.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	11.2	32.2	32.2	11.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	15.1	36.3	36.3	11.2	32.4	32.4	37.5	37.5		37.5	37.5	
Total Split (%)	17.8%	42.7%	42.7%	13.2%	38.1%	38.1%	44.1%	44.1%		44.1%	44.1%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag						
Lead-Lag Optimize?												
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	13.4	54.1	54.1	5.6	36.7	36.7		16.0			16.0	
Actuated g/C Ratio	0.16	0.64	0.64	0.07	0.43	0.43		0.19			0.19	
v/c Ratio	0.62	0.56	0.02	0.07	0.38	0.21		0.18			0.58	
Control Delay	47.1	13.9	0.1	33.0	22.6	10.9		20.5			27.5	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	47.1	13.9	0.1	33.0	22.6	10.9		20.5			27.5	
LOS	D	B	A	C	C	B		C			C	
Approach Delay		17.6			20.2			20.5			27.5	
Approach LOS		B			C			C			C	
Queue Length 50th (m)	22.0	37.7	0.0	1.1	24.7	0.0		4.2			16.0	
Queue Length 95th (m)	#57.0	#136.1	0.0	m4.5	61.4	26.4		9.4			25.4	
Internal Link Dist (m)		349.9			354.0			301.9			126.3	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	259	2135	974	108	1451	705		476			512	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.62	0.56	0.02	0.07	0.38	0.21		0.10			0.33	

Intersection Summary

Area Type: Other

Cycle Length: 85

Actuated Cycle Length: 85

Offset: 41 (48%), Referenced to phase 2:EBT and 6:WBT, Start of Green

Natural Cycle: 85

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.62

Intersection Signal Delay: 19.2

Intersection LOS: B

Intersection Capacity Utilization 67.2%

ICU Level of Service C

Analysis Period (min) 15

95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.






















Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 AM Peak

m Volume for 95th percentile queue is metered by upstream signal.













Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road



Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	42	731	57	14	1203	67	38	4	12	122	5	106
Future Volume (vph)	42	731	57	14	1203	67	38	4	12	122	5	106
Ideal Flow (vphpl)	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800	1800
Storage Length (m)	35.0		115.0	35.0		25.0	0.0		0.0	0.0		0.0
Storage Lanes	1		1	1		1	0		0	0		0
Taper Length (m)	30.0			25.0			7.6			7.6		
Lane Util. Factor	1.00	0.95	1.00	1.00	0.95	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Ped Bike Factor	1.00		0.97	1.00		0.97		1.00			0.99	
Frt			0.850			0.850		0.970			0.939	
Flt Protected	0.950			0.950				0.966			0.974	
Satd. Flow (prot)	1647	3357	1502	1647	3357	1488	0	1661	0	0	1576	0
Flt Permitted	0.950			0.950				0.681			0.807	
Satd. Flow (perm)	1645	3357	1454	1642	3357	1446	0	1171	0	0	1300	0
Right Turn on Red			Yes			Yes			Yes			Yes
Satd. Flow (RTOR)			106			106		12			44	
Link Speed (k/h)		70			70			40			50	
Link Distance (m)		373.9			378.0			325.9			150.3	
Travel Time (s)		19.2			19.4			29.3			10.8	
Confl. Peds. (#/hr)	3		4	4		3			9	9		
Confl. Bikes (#/hr)			5			3						3
Peak Hour Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Heavy Vehicles (%)	5%	3%	3%	5%	3%	4%	2%	2%	3%	5%	2%	5%
Adj. Flow (vph)	42	731	57	14	1203	67	38	4	12	122	5	106
Shared Lane Traffic (%)												
Lane Group Flow (vph)	42	731	57	14	1203	67	0	54	0	0	233	0
Enter Blocked Intersection	No	No	No	No	No	No	No	No	No	No	No	No
Lane Alignment	Left	Left	Right	Left	Left	Right	Left	Left	Right	Left	Left	Right
Median Width(m)		3.7			3.7			0.0			0.0	
Link Offset(m)		0.0			0.0			0.0			0.0	
Crosswalk Width(m)		4.9			4.9			4.9			4.9	
Two way Left Turn Lane												
Headway Factor	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06	1.06
Turning Speed (k/h)	24		14	24		14	24		14	24		14
Number of Detectors	1	2	1	1	2	1	1	2		1	2	
Detector Template	Left	Thru	Right	Left	Thru	Right	Left	Thru		Left	Thru	
Leading Detector (m)	2.0	10.0	6.1	6.1	10.0	2.0	6.1	30.5		6.1	30.5	
Trailing Detector (m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Position(m)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Size(m)	2.0	0.6	6.1	6.1	0.6	2.0	6.1	1.8		6.1	1.8	
Detector 1 Type	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex	Cl+Ex		Cl+Ex	Cl+Ex	
Detector 1 Channel												
Detector 1 Extend (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Queue (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 1 Delay (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		0.0	0.0	
Detector 2 Position(m)		9.4			9.4			28.7			28.7	
Detector 2 Size(m)		0.6			0.6			1.8			1.8	
Detector 2 Type		Cl+Ex			Cl+Ex			Cl+Ex			Cl+Ex	
Detector 2 Channel												

Baseline Rd/John Sutherland Dr/Valley Stream Dr
Total2035 PM Peak

												
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Detector 2 Extend (s)		0.0			0.0			0.0			0.0	
Turn Type	Prot	NA	Perm	Prot	NA	Perm	Perm	NA		Perm	NA	
Protected Phases	5	2		1	6			8			4	
Permitted Phases			2			6	8			4		
Detector Phase	5	2	2	1	6	6	8	8		4	4	
Switch Phase												
Minimum Initial (s)	5.0	10.0	10.0	5.0	10.0	10.0	10.0	10.0		10.0	10.0	
Minimum Split (s)	11.2	32.2	32.2	11.2	32.2	32.2	37.5	37.5		37.5	37.5	
Total Split (s)	12.0	51.3	51.3	11.2	50.5	50.5	37.5	37.5		37.5	37.5	
Total Split (%)	12.0%	51.3%	51.3%	11.2%	50.5%	50.5%	37.5%	37.5%		37.5%	37.5%	
Yellow Time (s)	4.2	4.2	4.2	4.2	4.2	4.2	3.3	3.3		3.3	3.3	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	3.2	3.2		3.2	3.2	
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Lost Time (s)	6.2	6.2	6.2	6.2	6.2	6.2		6.5			6.5	
Lead/Lag	Lead	Lag	Lag	Lead	Lag	Lag						
Lead-Lag Optimize?												
Recall Mode	None	C-Max	C-Max	None	C-Max	C-Max	None	None		None	None	
Act Effct Green (s)	7.0	64.4	64.4	5.9	58.4	58.4		20.6			20.6	
Actuated g/C Ratio	0.07	0.64	0.64	0.06	0.58	0.58		0.21			0.21	
v/c Ratio	0.37	0.34	0.06	0.15	0.61	0.08		0.22			0.77	
Control Delay	53.6	10.6	0.6	58.7	12.8	0.4		26.2			45.9	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0		0.0			0.0	
Total Delay	53.6	10.6	0.6	58.7	12.8	0.4		26.2			45.9	
LOS	D	B	A	E	B	A		C			D	
Approach Delay		12.1			12.6			26.2			45.9	
Approach LOS		B			B			C			D	
Queue Length 50th (m)	7.2	25.9	0.0	2.6	82.6	0.0		6.2			32.3	
Queue Length 95th (m)	17.3	61.3	1.2	m5.6	37.5	0.6		13.7			49.7	
Internal Link Dist (m)		349.9			354.0			301.9			126.3	
Turn Bay Length (m)	35.0		115.0	35.0		25.0						
Base Capacity (vph)	116	2162	974	96	1960	888		371			433	
Starvation Cap Reductn	0	0	0	0	0	0		0			0	
Spillback Cap Reductn	0	0	0	0	0	0		0			0	
Storage Cap Reductn	0	0	0	0	0	0		0			0	
Reduced v/c Ratio	0.36	0.34	0.06	0.15	0.61	0.08		0.15			0.54	
Intersection Summary												
Area Type: Other												
Cycle Length: 100												
Actuated Cycle Length: 100												
Offset: 71 (71%), Referenced to phase 2:EBT and 6:WBT, Start of Green												
Natural Cycle: 85												
Control Type: Actuated-Coordinated												
Maximum v/c Ratio: 0.77												
Intersection Signal Delay: 16.0						Intersection LOS: B						
Intersection Capacity Utilization 62.5%						ICU Level of Service B						
Analysis Period (min) 15												
m Volume for 95th percentile queue is metered by upstream signal.												

Baseline Rd/John Sutherland Dr/Valley Stream Dr Total2035 PM Peak

Splits and Phases: 8: Valley Stream Drive/John Sutherland Drive & Baseline Road

 Ø1 11.2 s	 Ø2 (R) 51.3 s	 Ø4 37.5 s
 Ø5 12 s	 Ø6 (R) 50.5 s	 Ø8 37.5 s