

REPORT ON

**HYDROGEOLOGICAL INVESTIGATION
PROPOSED RESIDENTIAL DEVELOPMENT
HEMPHILL STREET, RICHMOND
OTTAWA, ONTARIO**

Submitted to:

Schouten Construction Ltd.
2740 Harbison Road
Richmond, Ontario
K0A 2Z0

DISTRIBUTION

1 PDF copy – Schouten Construction Ltd.
1 copy – Schouten Construction Ltd.
4 copies – Holzman Consultants Inc.
1 copy – Morey Associates Ltd.

May 2018

File No. 017630



TABLE OF CONTENTS

TABLE OF CONTENTS	I
TABLE OF CONTENTS (CONTINUED)	II
1.0 INTRODUCTION	1
1.1 SITE BACKGROUND	2
2.0 PROCEDURES	2
2.1 GENERAL.....	2
2.2 TEST WELL CONSTRUCTION	3
2.3 WELL WATER QUALITY TESTING	3
2.3.1 TEST WELLS.....	3
2.3.2 NEIGHBOURING WELLS	4
2.4 WELL WATER QUANTITY TESTING.....	5
3.0 GROUNDWATER SUPPLY INVESTIGATION	5
3.1 SUPPLY AQUIFER	5
3.2 WATER QUALITY	6
3.2.4 NEIGHBOURING WELLS	9
3.3 WATER QUANTITY	11
3.3.1 TEST WELL TW1	12
3.3.2 TEST WELL TW2	13
3.3.3 TEST WELL TW3	13
3.3.4 SUMMARY OF TEST WELL YIELDS	14
3.3.5 SUMMARY OF TRANSMISSIVITY ANALYSIS	14
4.0 IMPACT ASSESSMENT	15
4.1 HYDROGEOLOGICAL SENSITIVITY	15
4.2 INTERFERENCE EFFECTS	15
4.3 DEVELOPMENT IMPACTS AND NEIGHBOURING LAND USES.....	18
4.4 POST DEVELOPMENT MONITORING PROGRAM	18
5.0 CONCLUSIONS AND RECOMMENDATIONS	19
5.1 SUMMARY AND CONCLUSIONS	19
5.2 RECOMMENDATIONS	20
6.0 LIMITATIONS AND USE OF REPORT	23
7.0 SIGNATURES	24
8.0 REFERENCES	25



TABLE OF CONTENTS (Continued)

LIST OF TABLES (within text of report)

TABLE 2.1: SUMMARY OF WELL SURVEY FORM DISTRIBUTION.....	4
TABLE 3.1: SUMMARY OF TEST WELL CONSTRUCTION DETAILS.....	5
TABLE 3.2: PUMPING TEST WELL WATER SAMPLES LABORATORY TESTING RESULTS.....	6
TABLE 3.3: SUMMARY OF NEIGHBOURING WELL CONSTRUCTION DETAILS	9
TABLE 3.4: CLASSIFICATION OF TRANSMISSIVITY VALUES.....	14

LIST OF TABLES (following text of report)

TABLE I:	RESULTS OF THE FIELD WATER QUALITY TESTING MEASUREMENTS FOR TEST WELLS
TABLE II:	LANGELIER SATURATION INDEX CALCULATIONS
TABLE III:	SUMMARY OF PUMPING TEST RESULTS AND WELL PARAMETERS
TABLE IV:	ESTIMATE OF STORATIVITY BY COOPER-JACOB METHOD
TABLE V:	MUTUAL WELL INTERFERENCE AT CENTRAL WELL 20 YEAR ASSESSMENT
TABLE VI:	MUTUAL WELL INTERFERENCE AT CENTRAL WELL PEAK WATER DEMAND ASSESSMENT

LIST OF FIGURES

FIGURE 1:	KEY PLAN
FIGURE 2:	AERIAL PHOTOGRAPH
FIGURE 3:	SITE SKETCH PLAN
FIGURE 4:	SURFICIAL GEOLOGY
FIGURE 5:	BEDROCK GEOLOGY
FIGURE 6:	STRATIGRAPHIC CROSS-SECTION SKETCH

APPENDICES

APPENDIX A:	MOECC WELL RECORDS FOR TEST WELLS
APPENDIX B:	MOECC WELL RECORDS & SURVEY QUESTIONNAIRE FOR NEIGHBOURING WELLS
APPENDIX C:	RESULTS OF LABORATORY TESTING OF TEST WELL WATER SAMPLES
APPENDIX D:	RESULTS OF LABORATORY TESTING OF NEIGHBOURING WELL WATER SAMPLES
APPENDIX E:	PUMPING TEST DATA FOR TEST WELL TW1
APPENDIX F:	PUMPING TEST DATA FOR TEST WELL TW2
APPENDIX G:	PUMPING TEST DATA FOR TEST WELL TW3
APPENDIX H:	TEST PIT LOGS FROM PREVIOUS MOREY ASSOCIATES LTD. GEOTECHNICAL INVESTIGATION
APPENDIX I:	CURRICULA VITAE



1.0 INTRODUCTION

Morey Associates Ltd. was retained by Schouten Construction Ltd. to undertake a hydrogeological investigation at the site of the proposed residential subdivision located on the north side of Hemphill Street, Village of Richmond, within Part Lot 25, Concession 4, Geographic Township of Goulbourn, City of Ottawa, Ontario (see Key Plan, Figure 1).

The subject site for this assessment consists of about a 0.8 hectare 'L' shaped property. The proposed site development plan drawing prepared by H. A. Ken Shipman Surveying Ltd., Ref. No. GLB-467 for File 16-10896, indicates that the site will be subdivided into 7 lots for single family dwelling construction, with lot sizes of some 0.08 to 0.14 hectares (see Site Sketch Plan, Figure 3). The proposed dwellings will be serviced by individual on-site private wells. The dwellings will be serviced by a municipal sanitary sewer and accordingly a septic system impact assessment is not required.

For the purpose of this report Hemphill Street is considered to exist at the south side of the proposed subdivision (see Key Plan, Figure 1).

This investigation was carried out in general accordance with the Ministry of the Environment and Climate Change (MOECC) Procedure D-5-5 Technical Guideline for Private Wells: Water Supply Assessment (August 1996) and the applicable sections of the City of Ottawa Official Plan (2003) requiring that information be provided indicating the following:

- Sufficient quantity of groundwater exists on site to service the development.
- Water wells can be constructed on the proposed lots that will not be impacted by identified potential sources of groundwater contamination in the area.
- The quality of the groundwater meets or exceeds the Ontario Drinking Water Standards, Objectives and Guidelines.

The City of Ottawa provided us with a copy of a Hydrogeological Study Report previously carried out by Golder Associates Ltd. for a proposed residential development consisting of some 51 lots on the east side of Shea Road immediately opposite the site for this present report. That Golder Associates Ltd. Report is titled "Hydrogeological Study, Proposed Development, Part of Lot 26,



Concession 4, Geographic Township of Goulbourn, City of Ottawa (Richmond Village), Ontario”, dated September 2017, Report Number 14118381-1000, Rev. 2, hereinafter collectively referred to as the “GAL report”. The GAL report has not been relied upon for the conclusions presented in this present report, however the GAL report has been reviewed as one of several information sources with regards to the geological/hydrogeological setting in the general area of the present site.

1.1 SITE BACKGROUND

The site is bordered on the north and west by vacant agricultural fields, on the south by Hemphill Street with existing residential development beyond, and on the east by an existing single family dwelling with Shea Road and vacant agricultural fields beyond. The ground cover at the site consists of cultivated lands with some young to mature trees along the south property boundary. A tributary to Jock River exists some 130 metres east of the subject site. The regional groundwater flow is generally from southwest to northeast (MVC and RVCA, 2011).

A review of the surficial geology map for the site area indicates that the site is underlain by marine deposited clay, silt, and silty clay. The bedrock geology map indicates that the bedrock underlying the site consists of dolostone and sandstone of the Beekmantown Group (specifically the Oxford formation). The Oxford formation in the general area of the site is generally known (based on preparation and review of hydrogeological investigations carried out by the undersigned in the Ottawa area over the past some 30 years) as an adequate source of groundwater from a quality and quantity point of view for domestic use with localized occurrences of elevated iron, hardness, sodium, total dissolved solids and hydrogen sulphide.

2.0 PROCEDURES

2.1 GENERAL

The objectives of this investigation were:

- to investigate the potential quantity and quality of groundwater that would be expected from water supply wells drilled at the site to service the proposed residential development.



The test wells installed for this investigation will be used as water supply wells for the proposed development and constitute about 43 percent (3 out of 7) of the total number of water supply wells which will be required for the proposed 7 lot development.

2.2 TEST WELL CONSTRUCTION

To determine the quantity and quality of groundwater available for domestic water supply, three test wells, numbered TW1, TW2 and TW3 were pump tested and sampled. The approximate locations of the test wells are shown on the attached Site Sketch Plan, Figure 3. The test wells, TW1, TW2 and TW3 were drilled by Air Rock Drilling Co. Ltd., of Richmond, Ontario, on January 29, January 30 and February 6, 2018, respectively, for the purposes of this investigation. The water well records for the test wells are provided in Appendix A.

The water well records for the test wells supplied by the well driller indicate that nominal 16 centimetre inside diameter steel casings were installed through the overburden and were set well into the bedrock and grouted in place using cement slurry and bentonite. The well casings are indicated to extend some 15.8 to 16.5 metres (52 to 54 feet) below the ground surface at the test wells. The wells were drilled to final depths using a 15 centimetre diameter bit and completed as an open hole in the bedrock. TW1, TW2 and TW3 were drilled into the bedrock to final depths of some 48.8, 42.7 and 54.9 metres, respectively, below the existing ground surface.

The ground surface elevation at each test well location was surveyed using total station survey equipment in reference to a site benchmark, the Geodetic elevation of which was supplied by H. A. Ken Shipman Surveying Ltd. (see Site Sketch Plan, Figure 3). The ground surface elevations at TW1, TW2 and TW3 were 94.0, 94.0 and 93.7 metres and the stick-up of the well casing at each well is about 0.75, 1.2 and 0.75 metres, respectively.

2.3 WELL WATER QUALITY TESTING

2.3.1 TEST WELLS

Groundwater samples were collected from the test wells at about hours 3 and 6 of the pumping tests to characterize groundwater quality. The groundwater samples from the test wells were collected and prepared/preserved in the field using appropriate techniques and submitted to



Eurofins Environment Testing laboratory in Ottawa, Ontario for the chemical, physical and bacteriological analyses listed in the Ministry of the Environment and Climate Control (MOECC) guideline entitled Procedure D-5-5, Technical Guideline for Private Wells: Water Supply Assessment, August 1996. The temperature, conductivity, pH, total dissolved solids (TDS), turbidity and residual chlorine levels of the groundwater were measured at periodic intervals during the pumping tests.

2.3.2 NEIGHBOURING WELLS

An attempt was made to identify the MOECC well records associated with the 15 closest existing dwellings to the site located adjacent to the site, north of the site and south of Hemphill Street (see Appendix B). An attempt was also made to contact the residents of those 15 dwellings in order to carry out a well survey and/or collect samples of their well water. A well survey form was hand delivered to the residents of the 15 dwellings listed in the following table:

Table 2.1: Summary of Well Survey Form Distribution

Civic Address	*Survey Form Returned	Consented to Sampling for Laboratory Testing	Water Sample Obtained
3244 Shea Road	NO	NO	NO
3290 Shea Road	NO	NO	NO
4 Hemphill Street	NO	NO	NO
6 Hemphill Street	NO	NO	NO
39 Gamble Drive	YES	YES	YES
40 Gamble Drive	NO	NO	NO
41 Gamble Drive	NO	NO	NO
42 Gamble Drive	NO	NO	NO
43 Gamble Drive	NO	NO	NO
44 Gamble Drive	YES	YES	YES
22 Mary Hill Crescent	NO	NO	NO
24 Mary Hill Crescent	NO	NO	NO
26 Mary Hill Crescent	YES	YES	NO**
28 Mary Hill Crescent	NO	NO	NO
30 Mary Hill Crescent	NO	NO	NO

*At time of preparation of this report

**Several unsuccessful attempts to schedule a time for sampling were made between the time consent to sample was granted and time of preparation of this report. It is considered that the property owner became disinterested in a water sample being obtained from their well.

The completed well survey forms and consent to obtain a well water sample from the dwelling occupants from 39 Gamble Drive, 44 Gamble Drive and 26 Mary Hill Crescent had been provided to our office as of the date of this report. The completed well surveys are provided in Appendix B.



In addition to the above, the MOECC well records and the results of well surveys, conducted as part of the above mentioned GAL report, for the water wells associated with the dwellings located at 2 Hemphill Street and 3310, 3316 and 3326 Shea Road are provided in Appendix B.

2.4 WELL WATER QUANTITY TESTING

Pumping tests were conducted on TW1, TW2 and TW3 on January 7, January 12 and January 6, 2015, respectively. The testing consisted of six hour duration constant discharge rate pumping tests. During the pumping tests, water level measurements were made on a regular basis to monitor the drawdown of the water level in the wells in response to pumping. After the pumping period, the pump was shut off and the recovery of the water level in the test wells was monitored for a period of time. Water levels at adjacent test wells were monitored periodically during pumping tests to determine the potential interference effects between the wells. During the pump tests, the pump discharge outlet was located an adequate distance from the test wells to ensure the discharge did not interfere with the natural recharge to the wells in view of the relatively impermeable nature and thickness of the overburden (silty clay) at the site.

3.0 GROUNDWATER SUPPLY INVESTIGATION

3.1 SUPPLY AQUIFER

As mentioned above, the bedrock geology map for the site area indicates that dolomite of the Oxford formation underlies the site. The MOECC well records for the test wells indicate grey limestone was encountered during drilling. A review of the MOECC water well records for the test wells, attached in Appendix A, indicate that the test wells encountered water during drilling in the bedrock at depths of some 40.8 to 53.0 metres below the existing ground surface.

Table 3.1: Summary of Test Well Construction Details

Test Well	Total Depth of Well (m BGS)	Depth to Surface of Bedrock (m BGS)	Overburden Material Type	Bedrock Type	Depth of Well Casing (m BGS)	Depth Water Found (m BGS)
TW1	48.8	14.0	Clay	Limestone	15.8	46.9
TW2	42.7	14.3	Clay	Limestone	16.2	40.8
TW3	54.9	14.6	Clay	Limestone	16.5	33.8, 53.0

Note: m BGS = Metres Below Ground Surface



3.2 WATER QUALITY

The laboratory testing results of the chemical, physical and bacteriological analyses of water samples obtained from the test wells during the pumping tests are provided in the attached Appendix C and are summarized in the table below.

Table 3.2: Pumping Test Well Water Samples Laboratory Testing Results

Parameter	MRL	Units	¹ Guideline	TW1			TW2			TW3	
				3 hr	6 hr	Sample obtained 03/15/18	3 hr	6 hr	Sample obtained 03/15/18	3 hr	6 hr
Hardness as CaCO ₃	1	mg/L	OG-100, ⁴ 500	113	113	-	117	117	-	120	123
Ion Balance	0.01			0.91	0.93	-	0.94	0.99	-	0.93	0.97
TDS (COND - CALC)	1	mg/L	AO-500	555	552	-	491	493	-	530	536
Alkalinity as CaCO ₃	5	mg/L	OG-30 - 500	241	228	-	243	232	-	234	223
Cl	1	mg/L	AO-250	101	104	-	80	80	-	100	100
Colour	2	TCU	AO-5, ² T-7	4	3	-	20	14	3	<2	3
Conductivity	5	uS/cm		854	849	-	756	759	-	815	825
DOC	0.5	mg/L	AO-5, ² T-10.0	1.3	<0.5	-	1.5	<0.5	-	<0.5	<0.5
F	0.10	mg/L	MAC-1.5	1.20	1.22	-	1.20	1.18	-	0.95	1.05
N-NO ₂	0.10	mg/L	MAC-1.0	<0.10	<0.10	-	<0.10	<0.10	-	<0.10	<0.10
N-NO ₃	0.10	mg/L	MAC-10.0	<0.10	<0.10	-	<0.10	<0.10	-	0.24	0.15
pH	1.00		OG-6.5 - 8.5	8.47	8.45	-	8.24	8.22	-	8.24	8.25
SO ₄	1	mg/L	AO-500	36	36	-	33	32	-	45	41
Ca	1	mg/L		22	22	-	22	22	-	25	26
Fe	0.03	mg/L	AO-0.3, ² T-5.0	0.13	0.11	-	0.41	0.39	-	0.12	0.09
K	1	mg/L		8	8	-	7	7	-	7	7
Mg	1	mg/L		14	14	-	15	15	-	14	14
Mn	0.01	mg/L	AO-0.05, ² T-1.0	<0.01	<0.01	-	0.05	0.04	-	<0.01	<0.01
Na	2	mg/L	AO-200, A-20	120	120	-	112	116	-	123	123
TKN	0.1	mg/L		0.5	0.5	-	0.4	0.4	-	0.2	0.3
Phenols	0.001	mg/L		<0.001	<0.001	-	<0.001	<0.001	-	<0.001	<0.001
N-NH ₃	0.01	mg/L		0.49	0.49	-	0.34	0.35	-	0.22	0.23
S ₂ -	0.02	mg/L	AO-0.05	<0.02	<0.02	-	<0.02	<0.02	-	<0.02	<0.02
Tannin & Lignin	0.1	mg/L		<0.1	<0.1	-	0.1	0.1	-	<0.1	<0.01
Turbidity	0.1	NTU	AO-5.0	1.1	1.2	-	9.1	10.6	-	2.5	2.3
Heterotrophic Plate Count	0	ct/1mL		202	361	-	4	1	-	24	18
E.Coli	0	ct/100mL	MAC-0	0	0	-	0	0	-	0	0
Faecal Coliforms	0	ct/100mL		0	0	-	0	0	-	0	0
Total Coliforms	0	ct/100mL	MAC-0	0	4	0	0	0	-	0	0
⁵ Organic Nitrogen		mg/L	OG-0.15	0.01	0.01	-	0.06	0.05	-	0	0.07

¹ Guideline = Ontario Drinking Water Standards Objectives and Guidelines

² MOECC Maximum Concentration Considered Reasonably Treatable (See MOECC Guideline 'D-5-5 Private Wells: Water Supply Assessment')

³ Table 2, Appendix, MOECC Guideline 'D-5-5 Private Wells: Water Supply Assessment' document

⁴ "Hardness in excess of 500mg/L in drinking water is unacceptable for most domestic purposes" - Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines, Revised June 2006, Province of Ontario.

⁵ Organic Nitrogen = | Total Kjeldahl Nitrogen - N-NH₃ | and should not exceed 0.15 mg/L

MRL = Method Reporting Limit

AO = MOECC Aesthetic Objective

OG = MOECC Operational Guideline

MAC = MOECC Maximum Acceptable Concentration

T = MOECC Treatability Limit (See Note 2)

A = MOECC Advisory Limit (See Note 3)

Bold Italic = AO, OG or MAC Guideline Exceedence



The results of the chemical, physical and bacteriological analyses of water samples obtained from the test wells are provided in the attached Appendix C and in Table I. The water quality as determined from the results of the analyses is relatively favourable. The water meets all the Ontario Drinking Water Standards, Objectives and Guidelines (ODWSOG) health and aesthetic parameters tested for at the test wells except for the following:

- hardness at all of the wells
- TDS at TW1 and TW3
- Iron at TW2

The water samples obtained from all of the test wells is considered to be hard by water treatment standards with a hardness level above the ODWSOG operational guideline of 100 milligrams per litre. The hardness at the test wells ranges from about 113 to 123 milligrams per litre. However, based on the Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines, Revised June 2006, the hardness levels of the water samples are less than what is considered unacceptable (greater than 500 milligrams per litre) for most domestic purposes and is considered treatable. Water with hardness above 80 to 100 milligrams per litre as CaCO_3 is often softened for domestic use. Water softening by conventional sodium ion exchange may introduce relatively high concentrations of sodium into the drinking water, which may contribute a significant percentage to the daily sodium intake for a consumer on a sodium restricted diet. Where ion exchange water softeners are used, a separate unsoftened water supply could be used for drinking and culinary purposes.

The levels of TDS measured at the laboratory for test wells TW1 and TW3 ranged from about 530 to 555 milligrams per litre and is above the ODWSOG aesthetic objective of 500 milligrams per litre. The in-situ measurements of TDS during the pumping tests, between hours 3 and 6, ranged from some 378 to 400 milligrams per litre for test well TW1 and from some 382 to 445 milligrams per litre for test well TW3, for an average TDS level of both laboratory measurement and in-situ measurements of about 381 milligrams per litre for test well TW1 and 473 milligrams per litre for test well TW3. TDS may result in corrosion or encrusting of plumbing/plumbing fixtures. Langelier Saturation Index (LSI) calculations (using the American Water Works Association spreadsheet) were carried out using the 3 hour and 6 hour water sample testing results for all of the test wells and gave LSI values ranging between 0.07 to 0.33 (see Table II). These LSI values are within the range (-0.5 to 0.5) considered to indicate an unlikely occurrence of encrusting/scale or corrosion on plumbing/plumbing fixtures.



The laboratory measured levels of iron for the water samples for test well TW2 ranged from 0.39 to 0.41 milligrams per litre and are above the ODWSOG aesthetic objective of 0.3 milligrams per litre. The above indicated iron levels are well within the MOECC maximum concentration considered reasonably treatable of 5.0 milligrams per litre. The levels of iron for the water samples are considered treatable using a water softener or manganese greensand filter.

The Total Coliform count at test well TW1 was 0 ct/100mL for the 3 hour sample and 4 ct/100mL for the 6 hour sample. On March 15, 2018 chlorination of test well TW1 was carried out and the well sampled after pumping and field testing confirmed that the free chlorine level for the well water was 0 milligrams per litre. The water sample was delivered to Eurofins Environment Testing for total coliform testing and gave a total coliform count of 0 ct/100mL. The total coliform count for the hour 6 sample at test well TW1 is considered typical of recently drilled wells.

The level of turbidity measured at the laboratory for test well TW2 was 9.1 NTU and 10.6 NTU for the 3 and 6 hour samples, respectively, which exceeds the ODWSOG aesthetic objective of 5 NTU. However, it is expected that the laboratory turbidity level reflects the precipitation of iron from the water sample during the time between when the water was sampled and then tested in the laboratory. Additional development of test well TW2 was carried out on March 15, 2018. Field measurements for turbidity were carried out at that time and gave values ranging from 12 NTU decreasing with time to 0.8 NTU.

The level of colour measured for the water samples at test well TW2 were 20 TCU and 14 TCU for the 3 and 6 hour samples, respectively, and are above the ODWSOG aesthetic objective of 5 TCU and the MOECC maximum concentration considered reasonably treatable of 7 TCU. As mentioned above the levels of iron measured for the water sample were above the ODWSOG aesthetic objective (but well within treatability limits) and as indicated in the Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines, Revised June 2006, "Sometimes colour may be contributed to by iron and manganese compounds produced by processes occurring in natural sediments or in aquifers". As mentioned above additional development of test well TW2 was carried out on March 15, 2018. At that time a water sample was obtained from the well and delivered to Eurofins Environmental laboratory for colour testing. The results of that testing gave a value of 3 TCU which meets the ODWSOG aesthetic objective.



It is pointed out that the levels of sodium for the water samples for all three test wells were measured above 20 milligrams per litre (112 to 123 milligrams per litre) and accordingly may be of interest to persons on a sodium restricted diet. According to the MOECC, the local Medical Office of Health should be notified where sodium levels are above 20 milligrams per litre in order that this information may be relayed to local physicians. The sodium levels are well within the ODWSOG aesthetic objective of 200 milligrams per litre.

3.2.4 NEIGHBOURING WELLS

The following table provides available well construction information for the 15 residential water wells indicated in the above mentioned Table 2.1 (with the exception of 3244 and 3290 Shea Road and 28 Mary Hill Crescent for which the well records could not be located) as well as for the 4 previously mentioned water wells located at 2 Hemphill Street, 3310, 3316 and 3326 Shea Road (see report section 2.3.2).

Table 3.3: Summary of Neighbouring Well Construction Details

Well ID	Likely Well Location	Year of Well Construction	Total Depth of Well (m BGS)	Depth to Surface of Bedrock (m BGS)	Static Water Level (assumed m BGS)	Available Drawdown (m)
1509756	4 Hemphill St	1968	26.2	13.1	3.4	22.8
1528767	6 Hemphill St	1995	14.3	14.0	2.4	11.9
1509810	***39 Gamble Dr	1968	15.5	13.7	1.2	14.3
1509758	40 Gamble Dr	1968	15.2	13.7	1.8	13.4
1509748	41 Gamble Dr	1968	15.2	13.7	3.0	12.2
1509757	42 Gamble Dr	1968	14.3	13.7	1.5	12.8
1509791	43 Gamble Dr	1968	15.2	13.7	1.2	14.0
1509766	***44 Gamble Dr	1968	16.2	14.3	2.1	14.1
1531497	22 Mary Hill Cres	2000	73.2	14.9	4.1	69.1
1531410	24 Mary Hill Cres	2000	71.6	15.8	3.8	67.8
1531128	**26 Mary Hill Cres	2000	68.6	15.5	3.4	65.2
1530215	30 Mary Hill Cres	1998	22.9	15.8	4.5	18.4
1509773	**2 Hemphill St	1968	18.0	14.0	7.6	10.4
1509747	***3310 Shea Rd	1968	14.6	12.5	3.0	11.6
1509751	**3316 Shea Rd	1968	15.8	12.8	4.6	11.2
1509753	**3326 Shea Rd	1968	15.2	12.2	4.6	10.6

Note: m BGS = Metres Below Ground Surface

**Well survey results available as of the date of this present report

***Well survey and water sample testing results available as of the date of this present report

As indicated in the above Table 3.3, the results of seven well surveys for the wells located at 39 and 44 Gamble Drive, 26 Mary Hill Crescent, 2 Hemphill Street, and 3310, 3316 and 3326 Shea Road are available and provided in the attached Appendix B. Further, the results of laboratory testing of



water samples obtained from the wells located at 39 and 44 Gamble Drive and 3310 Shea Road are available and provided in the attached Appendix D.

The above mentioned seven residential wells are indicated to have been constructed in 1968 (some 50 years old), except for the well located at 26 Mary Hill Crescent which is indicated to have been constructed in 2000 (some 18 years old). No well grouting details are indicated on the well records for the above mentioned wells constructed in 1968. The well record for the well at 26 Mary Hill Crescent indicates that the annular space around the well casing from a depth of some 15.8 metres up to the ground surface was grouted/sealed with 1 bag of cement and 1 bag of QuickGrout (bentonite).

The well surveys for the above noted seven residential wells indicate that the groundwater is used for drinking water. Water treatment systems (water softeners) are used at all of the above mentioned locations, except for 39 and 44 Gamble Drive. The owner at 26 Mary Hill Crescent indicated that a filter and a water softener was used. The interviewees all indicated that their water was acceptable to excellent with regards to water quality and the interviewees did not indicate any problems with regards to water quantity.

The well water samples obtained from 39 Gamble Drive, 44 Gamble Drive and 3310 Shea Road were tested for the MOECC “subdivision package” list of bacteriological parameters. The results of that testing indicate all three water samples are of acceptable bacteriological quality.

The well water samples obtained from 44 Gamble Drive and 3310 Shea Road were also tested for the MOECC “subdivision package” list of chemical and physical parameters. The results of that testing indicated the two water samples meet all the ODWSOG health and aesthetic parameters tested for except for hardness, TDS, colour and sulphide for the sample obtained from 44 Gamble Drive and hardness, TDS and iron for the sample obtained from 3310 Shea Road.

The level of hardness measured for the above two samples (117 milligrams per litre) is less than what is considered unacceptable (greater than 500 milligrams per litre) for most domestic purposes and is considered treatable. The levels of TDS measured for the above two samples (515 and 536 milligrams per litre) is slightly above the aesthetic objective of 500 milligrams per litre and the interviewees at 44 Gamble Drive and 3310 Shea Road did not indicate any issues with encrusting/scale or corrosion on plumbing/plumbing fixtures.



The level of colour measured for the water sample obtained from 44 Gamble Drive was 6 TCU and is slightly above the ODWSOG aesthetic objective of 5 TCU, however is within the MOECC maximum concentration considered reasonably treatable of 7 TCU.

The level of iron measured for the water sample obtained from 3310 Shea Road was 0.31 milligrams per litre and is slightly above the ODWSOG aesthetic objective of 0.3 milligrams per litre, however is well within the MOECC maximum concentration considered reasonably treatable of 5.0 milligrams per litre.

The level of sulphide measured for the water sample obtained from 44 Gamble Drive was 0.06 milligrams per litre and is slightly above the ODWSOG aesthetic objective of 0.05 milligrams per litre. The interviewee at 44 Gamble Drive indicated that their water was acceptable to excellent with regards to quality and specifically did not indicate a poor odour or sulphur smell.

It is pointed out that the levels of sodium for the above two samples were measured above 20 milligrams per litre (124 and 134 milligrams per litre) and accordingly may be of interest to persons on a sodium restricted diet. According to the MOECC, the local Medical Office of Health should be notified where sodium levels are above 20 milligrams per litre in order that this information may be relayed to local physicians. The sodium levels are well within the ODWSOG aesthetic objective of 200 milligrams per litre.

The water quality at the sampled neighbouring wells is indicated to be comparable to the water quality at the test wells constructed for this investigation, with the exception of the slightly elevated level of sulphide measured for the water sample obtained from 44 Gamble Drive. Based on the results of the neighbouring well surveys and laboratory testing of neighbouring well water samples carried out for this investigation, the water quality and quantity in the water supply aquifer is indicated to be acceptable for typical domestic use.

3.3 WATER QUANTITY

The drawdown and recovery data and plots for TW1, TW2 and TW3 are shown in Appendices E, F and G, respectively. The drawdown and recovery data provided were measured with reference to the top of the well casing at each test well location.



The pumping test data for the test wells were analyzed using the method of Cooper and Jacob (1946). Although the assumptions on which these equations are based are not strictly met, this method provides a reasonable estimate of the aquifer transmissivity. The analysis of the data obtained during the pumping tests is summarized in the attached Table III. The water levels in adjacent wells were monitored during the pumping tests for the three test wells. The drawdown in the observation wells was plotted as a function of time during pumping (see attached Appendices E, F and G) and a resulting storativity estimate was calculated (see attached Table IV).

The following sections discuss the results of the analysis of the data obtained during the pumping tests with respect to test well yields.

3.3.1 TEST WELL TW1

The six hour duration pumping test was carried out at a discharge rate of 36 litres per minute (8 l/gpm). The static water level prior to testing was about 3.28 metres below the top of the well casing and the water level after six hours of pumping was about 15.17 metres below the top of the well casing for a total drawdown at the end of pumping of 11.89 metres. The available drawdown in the well is about 45 metres. The specific capacity of the well at this pumping rate is approximately 4.4 cubic metres per day per metre of drawdown.

Based on the pumping test drawdown data the transmissivity of the aquifer is estimated to be 34.2 m²/day. Based on the pumping test recovery data the aquifer transmissivity is estimated to be 95.9 m²/day. The average transmissivity of the bedrock aquifer in the area of TW1 is estimated to be 65.1 m²/day. At the end of pumping, 120 minutes was required for 100 percent recovery of the total drawdown in the static water level created during pumping.

Based on the data obtained during the pumping test, it can be concluded that the well is capable of sustaining a short term yield of at least 36 litres per minute (8 l/gpm) and that during the course of the six hour pumping period about 27 percent of the available drawdown in the test well was utilized.



3.3.2 TEST WELL TW2

The six hour duration pumping test was carried out at a discharge rate of 68 litres per minute (15 l/gpm). The static water level prior to testing was about 2.51 metres below the top of the well casing and the water level after six hours of pumping was about 10.78 metres below the top of the well casing for a total drawdown at the end of pumping of 8.27 metres. The available drawdown in the well is about 40 metres. The specific capacity of the well at this pumping rate is approximately 11.9 cubic metres per day per metre of drawdown.

Based on the pumping test drawdown data the transmissivity of the aquifer is estimated to be 74.9 m²/day. Based on the pumping test recovery data the aquifer transmissivity is estimated to be 112.3 m²/day. The average transmissivity of the bedrock aquifer in the area of TW2 is estimated to be 93.6 m²/day. At the end of pumping, 50 minutes was required for 100 percent recovery of the total drawdown in the static water level created during pumping.

Based on the data obtained during the pumping test, it can be concluded that the well is capable of sustaining a short term yield of at least 68 litres per minute (15 l/gpm) and that during the course of the six hour pumping period about 21 percent of the available drawdown in the test well was utilized.

3.3.3 TEST WELL TW3

The six hour duration pumping test was carried out at a discharge rate of 46 litres per minute (10 l/gpm). The static water level prior to testing was about 2.14 metres below the top of the well casing and the water level after six hours of pumping was about 13.62 metres below the top of the well casing for a total drawdown at the end of pumping of 11.48 metres. The available drawdown in the well is about 52 metres. The specific capacity of the well at this pumping rate is approximately 5.7 cubic metres per day per metre of drawdown.

Based on the pumping test drawdown data the transmissivity of the aquifer is estimated to be 54.5 m²/day. Based on the pumping test recovery data the aquifer transmissivity is estimated to be 38.7 m²/day. The average transmissivity of the bedrock aquifer in the area of TW3 is estimated to be 46.6 m²/day. At the end of pumping, 70 minutes was required for 100 percent recovery of the total drawdown in the static water level created during pumping.



Based on the data obtained during the pumping test, it can be concluded that the well is capable of sustaining a short term yield of at least 46 litres per minute (10 lpm) and that during the course of the six hour pumping period about 22 percent of the available drawdown in the test well was utilized.

3.3.4 SUMMARY OF TEST WELL YIELDS

The MOECC Guideline D-5-5 Section 4.3.2 for water quantity requirement indicates that the per-person requirement shall be 450 litres per day and relates that quantity to an equivalent peak per person demand rate of 3.75 litres per minute. The MOECC guideline indicates that for a single family dwelling the likely number of persons per well (per dwelling) is considered to be the number of bedrooms in the dwelling plus one. The MOECC guidelines further requires that regardless of the demand rate determined using the above mentioned calculation, the demand rate (minimum pumping rate of a well servicing a single family dwelling) shall not be less than 13.7 litres per minute.

The results of the pumping tests indicate that all of the test wells are capable of more than meeting MOECC minimum demand rate of 13.7 litres per minute and that TW1, TW2 and TW3 are capable of meeting the MOECC demand rate for an eight, seventeen and eleven bedroom single family dwelling, respectively, (a typical single family dwelling is considered to be a four bedroom dwelling).

3.3.5 SUMMARY OF TRANSMISSIVITY ANALYSIS

The above mentioned transmissivity values based on the pumping test drawdown and recovery data are summarized in Table 3.4 and classified regarding magnitude, designation and groundwater supply potential based on Krasny (1993).

Table 3.4: Classification of Transmissivity Values

¹ Magnitude (m ² /day)	¹ Class	¹ Designation	¹ Groundwater Supply Potential	Transmissivity Values from Pumping Tests (m ² /day)					
				TW1		TW2		TW3	
				Pump.	Rec.	Pump.	Rec.	Pump.	Rec.
>1000	I	Very High	Regional Importance						
100 - 1000	II	High	Lesser Regional Importance				112.3		
10 - 100	III	Intermediate	Local Water Supply	34.2	95.9	74.9		54.5	38.7
1 - 10	IV	Low	Private Consumption						
0.1 - 1	V	Very Low	Limited Consumption						
<0.1	VI	Imperceptible	Very difficult to Utilize for Water Supply						

¹Krasny (1993) "Classification of Transmissivity Magnitude and Variation", Vol.31, No.2 - Ground Water



Based on the above, all of the test wells are indicated to be capable of providing an adequate quantity of water for local water supply.

4.0 IMPACT ASSESSMENT

4.1 HYDROGEOLOGICAL SENSITIVITY

No karstic areas, areas of fractured bedrock exposed at the surface, areas of thin soil cover or areas of highly permeable soils were identified for the site. Accordingly, the site is not considered hydrogeologically sensitive.

4.2 INTERFERENCE EFFECTS

During the pumping of TW1, periodic water level measurements were made at TW2 and TW3 located some 62 and 100 metres, respectively, from TW1. During the pumping of TW2, periodic water level measurements were made at TW1 and TW3 located some 62 and 40 metres, respectively, from TW2. During the pumping of TW3, periodic water level measurements were made at TW1 and TW2 located some 100 and 40 metres, respectively, from TW3. The graphs of observation wells drawdown versus time during the pumping tests at TW1, TW2 and TW3 are shown in the attached Appendices E, F and G.

In order to estimate the maximum interference between future wells at the site, calculations were carried out to predict the cumulative twenty year drawdown due to the proposed 7 domestic wells at a central well in the proposed subdivision (central well being TW2, located at Lot 4 – see attached Figure 3). The cumulative drawdown at the wells was calculated for a twenty year pumping rate of 2250 litres per day, which allows for a four bedroom household in accordance with Section 4.3.2 of MOECC Procedure D-5-5. The previously mentioned nineteen neighbouring dwellings discussed in section 2.3.2 of this report were also included in the cumulative twenty year drawdown calculation. The calculation was carried out using the following Cooper-Jacob formula:

$$s = \frac{2.3Q}{4\pi T} \log\left(\frac{2.25Tt}{r^2 S}\right)$$



Where, Q = 20 year pumping rate, 2250L/day
 T = lowest transmissivity, 34.2 m²/day
 t = duration, 20 years
 S = lowest storativity estimate, 4.5 x 10⁻⁵
 s = expected drawdown due to the 26 domestic wells

The results of the calculations indicate that the cumulative twenty year drawdown at the centrally located well (TW2), including the interference from the other six wells in the proposed residential development and from the other nineteen neighbouring wells, is about 2.0 metres (see attached Table V). It is pointed out that it is considered, in Morey Associates Ltd. professional opinion, that the actual cumulative twenty year drawdown at the centrally located well could be more accurately estimated by the use of the average transmissivity value determined from the pumping tests, the average estimated storativity value and the use of a more likely daily pumping rate given today's more efficient plumbing. However, for the purpose of this present report and for an exceedingly conservative approach the cumulative twenty year drawdown at the centrally located well was estimated using the lowest transmissivity value determined during the pumping tests, the lowest estimated storativity value and a daily pumping rate of 2250 litres.

In addition to the above twenty year drawdown calculation, and in order to estimate the maximum interference between future wells at the site during daily peak water usage, calculations were carried out to predict the cumulative drawdown at the centrally located well due to simultaneous peak demand use of the proposed seven domestic wells. A simultaneous peak demand pumping rate at each well of 2250 litres over a two hour period was used in the calculation and is equivalent to the peak demand rate indicated in Section 4.3.2 of MOECC Procedure D-5-5. The calculation was carried out using the following Cooper-Jacob formula:

$$s = \frac{2.3Q}{4\pi T} \log\left(\frac{2.25Tt}{r^2 S}\right)$$

Where, Q = peak demand pumping rate, 2250L/2hr
 T = lowest transmissivity, 34.2 m²/day
 t = duration, 2 hours
 S = lowest storativity estimate, 4.5 x 10⁻⁵
 s = expected drawdown due to the 7 subject site proposed domestic wells



The results of the calculations indicate that the cumulative peak demand drawdown at the centrally located well (TW2), including the interference from the other six wells in the proposed residential development is about 2.5 metres (see attached Table VI). It is pointed out that it is considered, in Morey Associates Ltd. professional opinion, that the actual cumulative peak demand drawdown at the centrally located well could be more accurately estimated by the use of the average transmissivity value determined from the pumping tests, the average estimated storativity value and the use of a more likely peak demand water usage pumping rate given today's more efficient plumbing and that the actual two hour peak demand is divided up into two separate one hour periods (a morning hour and an evening hour), allowing for well recovery in between the two peak demand periods. However, for the purpose of this present report and for an exceedingly conservative approach the cumulative peak demand drawdown at the centrally located well was estimated using the lowest transmissivity value determined during the pumping tests, the lowest estimated storativity value and a peak demand pumping rate of 2250 litres over a two hour period.

Based on the above mentioned exceedingly conservative 20 year drawdown calculation, the expected drawdown was found to be about 2.0 metres at the centrally located well. Applying this drawdown value to all sixteen existing neighbouring wells indicated on Table 3.3 for which available drawdown information is known (which is also a conservative approach as the drawdown at the site boundaries would be less than estimated at a central lot) would result in the reduction of available drawdown at those existing wells of between about 3% to 19%.

Based on the above mentioned exceedingly conservative peak demand drawdown calculation, the expected drawdown was found to be about 2.5 metres at the centrally located well. Applying this drawdown value to all sixteen existing neighbouring wells indicated on Table 3.3 for which available drawdown information is known (which is also a conservative approach as the drawdown at the site boundaries would be less than estimated at a central lot) would result in the reduction of available drawdown at those existing wells of between about 4% to 25%.

The above estimated drawdown values provide a fair assurance of adequate water supply for the proposed residential development. Further, as indicated above it is considered that the above estimated drawdown values are exceedingly conservative and the actual cumulative drawdown values should be much less and interference with existing neighbouring wells should not result in significant reduction of available well drawdown for the proposed residential development as well as the nearby neighbouring wells.



4.3 DEVELOPMENT IMPACTS AND NEIGHBOURING LAND USES

The land use south of the site is currently residential, the land use west and north of the site is currently agricultural fields, the land use east of the site is currently vacant fields and it is understood that plans are being prepared for a proposed residential development east of the site. The results of the water quality testing at the test wells indicate that there is no significant impact on the groundwater at the site due to the surrounding existing land use. The proposed residential development east of the site is not considered a significant potential for interference on water quality for the site. Further, a Phase One Environmental Site Assessment (Phase I ESA) for the proposed residential development east of the subject site was carried out by Golder Associates Limited in 2015. The GAL report indicates that the Phase I ESA did not identify any areas of potential environmental concern within the Phase I ESA study area. The subject site is within the study area of that Phase I ESA and based on observations carried out by members of our engineering staff during the fieldwork for this present report, no significant changes in use since 2015 or areas of potential environmental concern were identified within or in close proximity to the subject site.

Based on the above, potential adverse impacts to the water quality of the proposed residential development from possible sources of groundwater contamination due to the above described neighbouring land use is not anticipated.

4.4 POST DEVELOPMENT MONITORING PROGRAM

The results of this investigation indicate acceptable existing and expected impact on the groundwater quality at this site due to existing neighbouring land uses and the proposed development. The local hydrogeological conditions and existing water quantity and quality, all indicate that the impact of the proposed development will not significantly impact the overall groundwater quality and quantity at the site. Accordingly, based on the findings of this current investigation no post development monitoring program is considered to be required.



5.0 CONCLUSIONS AND RECOMMENDATIONS

5.1 SUMMARY AND CONCLUSIONS

Based on the groundwater supply investigation and impact assessment carried out for the proposed residential subdivision, the following summary and conclusions are provided by Morey Associates Ltd. and are based on our professional opinion and our interpretation of the relevant sections of the guideline MOECC Procedure D-5-5 and applicable sections of the City of Ottawa Official Plan:

- 1) There is a sufficient groundwater supply of acceptable drinking water quality in the bedrock aquifer system to satisfy the water requirements of the proposed residential subdivision. It is indicated that most wells will have to be drilled to depths of about 43 to 55 metres and that individual well yields of 36 to 68 litres per minute (8 to 15 Imperial gallons per minute) will be typical. However, because it is impossible to predict with certainty the depth at which water-producing fractures will be encountered during drilling, it may be necessary to drill to depths greater than 55 metres on some lots to produce a sufficient water supply. It is pointed out that water bearing zones were encountered in the bedrock between about 33 and 53 metres depth at the test wells and that water quality from water bearing zones below 53 metres depth have not been evaluated as part of this present investigation.
- 2) The groundwater quality in the bedrock aquifer system at the three test wells at the site meets all the ODWSOG concentrations for all health related chemical, physical and bacteriological parameters tested, except for hardness at all of the test wells, TDS at two of the test wells and iron at one of the test wells. The levels of hardness measured at the three test wells are well within the acceptable range that is considered treatable. Based on the results of LSI calculations the levels of TDS measured at the test wells are considered unlikely to result in encrusting/scale or corrosion on plumbing/plumbing fixtures. The levels of iron measured at TW2 are well within the MOECC maximum concentration considered reasonably treatable. Water softeners are indicated to be adequate to lower hardness to acceptable levels. Water softeners or manganese greensand filters are indicated to be adequate to lower iron to acceptable levels.



- 3) Interviewees from seven neighbouring residences all indicated that their water was acceptable to excellent with regards to water quality and the interviewees did not indicate any problems with regards to water quantity.
- 4) Mutual well interference calculations indicate a sufficient groundwater supply for the proposed residential subdivision and interference with existing neighbouring wells should not result in significant reduction of available well drawdown for the proposed residential development as well as the nearby neighbouring wells.
- 5) It is considered that the type of existing surrounding land use adjacent to the subject property should not significantly impact the subject site from a water supply or water quality point of view.
- 6) It is understood that test wells TW1, TW2 and TW3 are planned to be used as domestic supply wells for the proposed dwellings located at Lot 1, Lot 4 and Lot 6, respectively. As such, it is considered that provided the three test wells are used as domestic supply wells they do not require decommissioning in accordance with O.Reg 903.
- 7) It is considered that with regards to proposed domestic supply wells the proposed residential subdivision meets the above mentioned applicable sections of the City of Ottawa Official Plan.

5.2 RECOMMENDATIONS

Morey Associates Ltd. provides the following recommendations regarding groundwater supply wells at the site:

- 1) Future wells drilled on the site should be constructed with steel casing through the overburden materials and set well into the bedrock. The steel casings for the test wells for this investigation are indicated by the well driller on the MOECC Well Records to be set 1.8 metres into the bedrock. As such, for future wells drilled on the site, setting the steel casing 1.8 metres into the bedrock should be considered a minimum. The steel casing placed in the boreholes should be pressure grouted into place for the full length of the casing. The material used to seal the annular space could consist of either a cement grout or a commercially available bentonite grout product. Cement grout mixtures should be allowed



to set for a minimum two day period for normal cement or twelve hours for a high early strength cement prior to advancing the well further into bedrock. If a bentonite grout product is used, drilling need only be suspended for a few hours depending on the product used. Bentonite grout has the additional advantage of remaining flexible when set and therefore should not crack or shrink thereby ensuring as well as possible that surface water or shallow groundwater will not migrate along the annular space and into the well bore.

Once the casing has been sealed, the well should be advanced uncased in the bedrock until a water supply of sufficient quantity and quality is encountered. The completed well should then be developed to maximize the yield. The well casings should be completed at least 400 millimetres above the highest point on the finished ground surface within three metres radially from the well after surface drainage is directed away from the well. The casing should be fitted with a pitless adapter to facilitate below ground plumbing and electrical connections. Surface grading should be completed to direct surface water away from the well in order to ensure that water will not collect or pond in the vicinity of the well.

In addition to the above, future wells drilled on the site are to be constructed in accordance with O.Reg 903.

- 2) Future wells drilled on the site should be constructed by licensed well drillers in accordance with O.Reg 903.
- 3) The well casing installation for future wells drilled on the site should be inspected by qualified professional engineering or geoscientist consulting firms to ensure that the well casings are constructed in accordance with the requirements.
- 4) The existing test wells (understood to be used as domestic supply wells for the proposed subdivision) and future wells drilled at the site shall be located a minimum 15 metres from a source of contamination which includes sanitary/storm sewer mains and service laterals. Further, the existing test wells and futures wells drilled at the site shall be made "accessible" for future well maintenance, in accordance with O.Reg 903. It is understood that D.B. Gray Engineering Inc. (consulting civil engineers for the proposed subdivision) have taken into consideration the above 15 metre separation distance and well accessibility in their



preparation of the proposed subdivision site plan. Future homeowners at the site should be made aware of the above requirements, particularly the well accessibility requirement.

- 5) In order to encourage domestic supply well education and best management practices future homeowners at the site should be made aware of and refer to the MOECC publication titled "Water Supply Wells: Requirements and Best Management Practices", revised April 2015.
- 6) Future homeowners at the site should be made aware that the use of water softeners for treatment of hardness and the use of water softeners or manganese greensand filters for treatment of iron may be desired based on the results of the water quality testing carried out for this investigation.
- 7) Future homeowners at the site should be made aware that the use of conventional sodium ion exchange water softeners may introduce relatively high concentrations of sodium into the drinking water, which may contribute a significant percentage to the daily sodium intake for a consumer on a sodium restricted diet. Where ion exchange water softeners are used, a separate unsoftened water supply could be used for drinking and culinary purposes.
- 8) Future homeowners at the site should be made aware that the levels of sodium for the water samples for all three test wells at the site were measured above 20 milligrams per litre (112 to 123 milligrams per litre) and accordingly may be of interest to persons on a sodium restricted diet. According to the MOECC, the local Medical Office of Health should be notified where sodium levels are above 20 milligrams per litre in order that this information may be relayed to local physicians. The sodium levels are well within the ODWSOG aesthetic objective of 200 milligrams per litre.



6.0 LIMITATIONS AND USE OF REPORT

This report was prepared for the exclusive use of Schouten Construction Ltd. This report may not be relied upon by any other person or entity without the express written consent of Schouten Construction Ltd. and Morey Associates Ltd.

This report documents work that was carried out with generally accepted professional standards at the time and location in which the services were provided and in a manner consistent with a level of care and skill normally exercised by other professional engineering and geoscientist firms practicing under similar conditions and subject to the time limits and financial and physical constraints applicable to the services.

Any third party use of this report, including reliance of this report and/or decisions made based on this report, is the sole responsibility of the third party. Morey Associates Ltd. accepts no responsibility for damages, whether direct or indirect, suffered by any third party as a result of any third party use of this report.

The conclusions provided herein represent an opinion of Morey Associates Ltd. as of the time of preparation of this report. It is recognized that the passage of time affects the information provided in this report. This report should not be construed as legal advice. If new information is discovered during future work, including excavations, borings or other studies, Morey Associates Ltd. should be requested to re-evaluate the conclusions presented in this report and provide amendments as required.



7.0 SIGNATURES

We trust that this report is sufficient for your present requirements. If you have any questions concerning this report, please do not hesitate to contact our office.

Yours truly,

Morey Associates Ltd.

D.G. Morey, B.A.Sc (Civil Eng.), P.Eng.
Director/Civil Engineer



C.R. Morey, M.Sc. (Eng.), P. Eng.
Senior Consulting Engineer





8.0 REFERENCES

Internet source: Mississippi-Rideau Source Protection Region website: *Assessment Report, Rideau Valley Source Protection Area*, dated 2011

Golder Associates Limited: Hydrogeological Study, Proposed Development, Part of Lot 26, Concession 4, Geographic Township of Goulbourn, City of Ottawa (Richmond Village), Ontario, report No. 1418381-1000, Rev.2, dated 2017 [*provided to Morey Associates Ltd. by the City of Ottawa*]

Map 1492A – Surficial Geology Map – Kemptville Ontario: Energy, Mines and Resources, Ottawa, Geological Survey of Canada, published 1982

Map 2544 – Bedrock Geology of Ontario Map – Southern Sheet: Province of Ontario, Ministry of Northern Development and Mines, dated 1991

Morey Associates Ltd.: Geotechnical Investigation, Proposed Residential Development, Hemphill Street, Richmond, Ottawa, Ontario, File No. 017600, dated 2018

Internet Source: Ontario Ministry of the Environment and Climate Change: On line map-based water well records search website.

Kransy: Classification of Transmissivity Magnitude and Variation, Vol.31, No.2 - Ground Water, dated 1993

Internet Source: American Water Works Associations website: website search results for LSI calculation

Internet Source: City of Ottawa website: Official Plan, dated 2003, amended 2017 and partly under appeal

Ontario Ministry of the Environment and Climate Change: Procedure D-5-5: Technical Guideline for Private Wells: Water Supply Assessment, August 1996

Province of Ontario: Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines, revised June 2006



TABLE I
RESULTS OF THE FIELD WATER QUALITY MEASUREMENTS
FOR TEST WELLS

Test Well	Hours Since Pumping Started	Temp. (°C)	Conductivity (uS/cm)	pH (pH units)	TDS (ppm)	Turbidity (NTU)	Free Chlorine (mg/L)	Sample
TW1	1	8.7	771	8.4	391	17	-	-
	2	9.1	795	8.4	400	5.3	-	-
	3	9.5	774	8.3	389	2.0	0.00	3hr sample
	4	10.1	760	8.2	378	2.2	-	-
	5	11.1	778	8.2	386	1.2	-	-
	6	11.2	796	8.2	396	0.9	0.00	6hr sample
TW2	1	9.5	667	8.2	335	29	-	-
	2	8.0	588	8.2	289	26	-	-
	3	7.7	639	8.2	318	24	0.00	3hr sample
	4	10.3	721	8.1	351	17	-	-
	5	10.5	728	8.2	361	13	-	-
	6	10.9	659	8.0	280	11	0.00	6hr sample
TW3	1	9.6	893	8.4	445	11.0	-	-
	2	11.0	778	8.3	390	4.3	-	-
	3	10.6	769	8.4	383	3.7	0.00	3hr sample
	4	10.9	777	8.4	387	2.3	-	-
	5	11.1	781	8.4	389	1.3	-	-
	6	10.6	767	8.4	382	0.9	0.00	6hr sample
TW1 (Pumping for additional sampling and laboratory testing, 03/15/18)	1	-	-	-	-	-	0.03	-
	2	-	-	-	-	-	0.00	-
	2.75	-	-	-	-	-	0.00	Sample
TW2 (Additional pumping for in-situ turbidity testing and additional sampling and laboratory testing, 03/15/18)	0.75	-	-	-	-	12	-	-
	1.75	-	-	-	-	7.8	-	-
	2.75	-	-	-	-	3.6	-	-
	3.75	-	-	-	-	1.4	-	-
	5	-	-	-	-	1.1	-	-
	6	-	-	-	-	0.8	-	Sample



TABLE II
LANGELIER SATURATION INDEX CALCULATIONS

Sample	pH	TDS (mg/L)	Temp. (°C)	Ca (mg/L)	Ca as CaCO ₃ (mg/L)	Alkalinity as CaCO ₃ (mg/L)	A	B	C	D	pHs	Langelier Saturation Index (pH - pHs)	*Comment
TW1 - 3hr	8.47	555	9.5	22	55	241	0.1744293	2.3926379	1.3403627	2.3820170	8.1447	0.33	Acceptable
TW1 - 6hr	8.45	552	11.2	22	55	228	0.1741939	2.3584522	1.3403627	2.3579348	8.1343	0.32	Acceptable
TW2 - 3hr	8.24	491	7.7	22	55	243	0.1691081	2.4290595	1.3403627	2.3856063	8.1722	0.07	Acceptable
TW2 - 6hr	8.22	493	10.9	22	55	232.0	0.1692847	2.3644701	1.3403627	2.3654880	8.1279	0.09	Acceptable
TW3 - 3hr	8.24	530	10.6	25	62.5	234	0.1724276	2.3704943	1.3958800	2.3692159	8.0778	0.16	Acceptable
TW3 - 6hr	8.25	536	10.6	26	65	223	0.1729165	2.3704943	1.4129134	2.3483049	8.0822	0.17	Acceptable

*An acceptable range is considered a value between -0.5 and 0.5

Notes:

$$\text{Ca as CaCO}_3 = \text{Ca} / 0.4$$

$$A = (\text{Log}_{10}[\text{TDS}] - 1) / 10$$

$$B = -13.12[(\text{Log}_{10}(\text{Temp.} + 273))] + 34.55$$

$$C = \text{Log}_{10}[\text{Ca as CaCO}_3] - 0.4$$

$$D = \text{Log}_{10}[\text{alkalinity as CaCO}_3]$$

$$\text{pHs} = (9.3 + A + B) - (C + D)$$

$$\text{Langelier Saturation Index} = \text{pH} - \text{pHs}$$



TABLE III
SUMMARY OF PUMPING TEST RESULTS AND WELL PARAMETERS

Well	Tp (m ² /day)	Tr (m ² /day)	Tav (m ² /day)	Q (m ³ /day)	SC (m ³ /day/m)	ho m	hf m	Td m	TD m	CS m	AD m
TW1	34.2	95.9	65.1	52.4	4.4	3.28	15.17	11.89	48.77	0.75	45
TW2	74.9	112.3	93.6	98.2	11.9	2.51	10.78	8.27	42.67	1.20	40
TW3	54.5	38.7	46.6	65.5	5.7	2.14	13.63	11.49	54.86	0.75	52

Well	% Available Drawdown Used
TW1	27%
TW2	21%
TW3	22%

Overall Average Transmissivity

T 68.4 m²/day

- Note:
- Tp: Transmissivity as calculated from pumping data (m²/day)
 - Tr: Transmissivity as calculated from recovery data (m²/day)
 - Tav: Average transmissivity (average of pumping and recovery) (m²/day)
 - Q: Test pumping rate (m³/day)
 - SC: Specific Capacity (m³/day/m)
 - ho: Static water level (below top of casing) at beginning of pumping test (metres)
 - hf: Water level (below top of casing) at end of 6 hour pumping test (metres)
 - Td: Total drawdown (metres)
 - TD: Total depth of well (below ground surface) (metres)
 - CS: Casing stickup above ground surface, as measured at time of pumping test (metres)
 - AD: Approximate available drawdown (metres)



TABLE IV
ESTIMATE OF STORATIVITY BY COOPER-JACOB METHOD

$$S = \frac{2.25 T t_0}{r^2}$$

(A curve of drawdown versus time was generated for an observation well as an adjacent well was pumped)

Pumping Well	Observation Well	r (m)	Q (m³/day)	t₀ (s)	T (m²/s)	S
TW1	TW2	61	52.4	36	3.7E-03	8.1E-05
	TW3	100		684	3.7E-03	5.7E-04
TW2	TW1	61	98.2	82	5.2E-03	2.6E-04
	TW3	40		88	3.5E-03	4.3E-04
TW3	TW1	100	98.2	29	6.9E-03	4.5E-05
	TW2	40		73	6.9E-03	7.1E-04
Average Storativity						3.5E-04



TABLE V
MUTUAL WELL INTERFERENCE AT CENTRAL WELL
20 YEAR ASSESSMENT

Centre Lot:	Lot 4	Calculated by Cooper-Jacob Method using:
S =	4.5E-05	Lowest Transmissivity value determined from pumping tests (conservative)
T =	34.2 m ² /day	Lowest Storativity value calculated from pumping tests (conservative)
T =	4.0E-04 m ² /s	Flow/pump rate (Q) using section 4.3.2 of MOECC Procedure D-5-5 for a
Q =	2250 L/day	four bedroom dwelling, [4 + 1] * 450 L/day = 2250 L/d
Q =	2.6E-05 m ³ /s	
Duration =	20 years	
Duration =	6.3E+08 seconds	

Lot	Distance (m)	20 year Drawdown (m)
1	62	0.08
2	44	0.08
3	28	0.09
4	0	0.13
5	20	0.09
6	40	0.08
7	60	0.08
3244 Shea	235	0.06
3290 Shea	87	0.07
4 Hemphill	79	0.07
6 Hemphill	61	0.08
39 Gamble	119	0.07
40 Gamble	97	0.07
41 Gamble	89	0.07
42 Gamble	70	0.08
43 Gamble	58	0.08
44 Gamble	59	0.08
22 Mary Hill	153	0.07
24 Mary Hill	135	0.07
26 Mary Hill	126	0.07
28 Mary Hill	124	0.07
30 Mary Hill	134	0.07
2 Hemphill	99	0.07
3310 Shea	145	0.07
3316 Shea	162	0.07
3326 Shea	211	0.06
Cumulative aquifer drawdown at Lot 4 =		1.97





TABLE VI
MUTUAL WELL INTERFERENCE AT CENTRAL WELL
PEAK WATER DEMAND ASSESSMENT

Centre Lot:	Lot 4	Calculated by Cooper-Jacob Method using:
S =	4.5E-05	Lowest Transmissivity value determined from pumping tests (conservative)
T =	34.2 m ² /day	Lowest Storativity value calculated from pumping tests (conservative)
T =	4.0E-04 m ² /s	Flow/pump rate (Q) = 2250 L over a continuous 2 hour period simultaneously
Q =	2250 L/2hr	at all wells (conservative)
Q =	3.1E-04 m ³ /s	
Duration =	0.0002282 years	
Duration =	7.2E+03 seconds	

Lot	Distance (m)	Peak Drawdown (m)
1	62	0.22
2	44	0.27
3	28	0.32
4	0	0.84
5	20	0.36
6	40	0.28
7	60	0.23
Cumulative aquifer drawdown at Lot 4 =		2.52

KEY PLAN



FIGURE 1



APPROXIMATE SCALE



NOT TO SCALE




- NOTES:**
1. All dimensions are in metres. Do not scale drawing.
 2. This drawing is to be read in conjunction with the accompanying report.
 3. Site benchmark = Existing nail in utility pole, located as shown on drawing. Geodetic elevation 94.21m as per H.A.Ken Shipman Surveying Ltd. drawing Ref. No. GLB.-478 for File No. 16-10896D.
 4. Lot numbers shown on subject site have been arbitrarily selected.
 5. Any changes made to this plan must be verified and approved by Morey Associates Ltd.

- LEGEND**
- APPROXIMATE MOREY ASSOCIATES LTD. TEST WELL
 - APPROXIMATE MOREY ASSOCIATES LTD. TEST PIT
 - APPROXIMATE EXISTING SPOT ELEVATION
 - NEIGHBOURING WELL WATER SAMPLE LABORATORY TESTING INFORMATION OBTAINED
 - NEIGHBOURING WATER WELL SYSTEM SURVEY QUESTIONNAIRE INFORMATION OBTAINED
 - APPROXIMATE CROSS-SECTION LOCATION (See Figure 6)

REFERENCE:
 Base plan information referenced from D. B. Gray Engineering Inc., Site Servicing Plan, Drawing C-1, dated Feb-XX-12 for Job No. 17037, Proposed 7-lot Residential Development Hemphill Street Richmond Ontario, Revision 01 dated Nov 29-17.

DRAWING	SITE SKETCH PLAN - FIGURE 3
LOCATION	HEMPHILL STREET, RICHMOND OTTAWA, ONTARIO


PROJECT	PROPOSED RESIDENTIAL DEVELOPMENT HYDROGEOLOGICAL INVESTIGATION			
CLIENT	SCHOUTEN CONSTRUCTION LTD.			
DATE	DRAWING No.	DRAWN BY	APPROX. SCALE	FILE NO.
May 2018	1 of 1	DGM	1:1000	017630



MOREY ASSOCIATES LTD.
CONSULTING ENGINEERS


2672 HWY.43, PO BOX 184
KEMPTVILLE, ONTARIO
K0G 1J0

T:613.215.0605
F:613.258.0605
info@moreyassociates.com




NOT TO SCALE

3 OFFSHORE MARINE DEPOSITS: massive blue-grey clay, silty clay and silt; calcareous and fossiliferous; locally overlain by thin sands




NOT TO SCALE





NOTES:

1. All dimensions are in metres. Do not scale drawing.
2. This drawing is to be read in conjunction with the accompanying report.
3. See Site Sketch Plan, Figure 3 for cross-section location.
4. About a 0.3m thickness of topsoil was encountered from the surface at each of the test pits. For clarity purposes that topsoil layer is not shown on this cross-section drawing. For detailed soil stratigraphy and or groundwater conditions at test pits, refer to Record of Test Pit Logs.
5. Any changes made to this plan must be verified and approved by Morey Associates Ltd.



LEGEND

-  SILTY CLAY or CLAY (as indicated by well driller)
-  GREY LIMESTONE (as indicated by well driller)
- WF** Water Found (as indicated by well driller)

DRAWING
STRATIGRAPHIC CROSS-SECTION A-A' - FIGURE 6
LOCATION
HEMPHILL STREET, RICHMOND OTTAWA, ONTARIO

PROJECT	PROPOSED RESIDENTIAL DEVELOPMENT HYDROGEOLOGICAL INVESTIGATION			
CLIENT	SCHOUTEN CONSTRUCTION LTD.			
DATE	DRAWING No.	DRAWN BY	APPROX. SCALE	FILE NO.
May 2018	1 of 1	DGM	1:600	017630



2672 HWY.43, PO BOX 184
KEMPTVILLE, ONTARIO
K0G 1J0

T:613.215.0605
F:613.258.0605
info@moreyassociates.com



APPENDIX A

MOECC WELL RECORDS FOR TEST WELLS



Measurements recorded in: Metric Imperial

TW1

Well Owner's Information

First Name: 1230381 Last Name / Organization: Ontario Inc E-mail Address: Adrian Schoups Well Constructed by Well Owner

Mailing Address (Street, Number/Name): 2740 Horbison Road Municipality: Richmond Ont Postal Code: K0A 2Z0 Telephone No. (inc. area code):

Well Location

Address of Well Location (Street Number/Name): (NO CIVIC) HEMPHILL STREET Township: GOULBOURN Lot: 4 Concession: 4

County/District/Municipality: OTTAWA-CARLETON City/Town/Village: RICHMOND Province: Ontario Postal Code:

UTM Coordinates: Zone: 18 Easting: 434309 Northing: 5006032 Municipal Plan and Sublot Number: PART # 4 Other:

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)
				From To
	Clay			0' 46'
	Grey limestone			46' 160'
TW #1 of 3				

Annular Space

Depth Set at (m/ft)	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
From To		
50' 42'	Neat Cement Slurry	12.48
42' 0'	Bestonik Grout	29.40

Method of Construction

Cable Tool Diamond Public Commercial Not used

Rotary (Conventional) Jetting Domestic Municipal Dewatering

Rotary (Reverse) Driving Livestock Test Hole Monitoring

Boring Digging Irrigation Cooling & Air Conditioning

Air percussion Other, specify: Surge

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)	Status of Well
			From To	
6 1/4"	Steel	.188"	0' 52'	<input checked="" type="checkbox"/> Water Supply
6"	Open hole		52' 160'	<input type="checkbox"/> Replacement Well

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	Status of Well
			From To	
				<input type="checkbox"/> Test Hole
				<input type="checkbox"/> Recharge Well
				<input type="checkbox"/> Dewatering Well
				<input type="checkbox"/> Observation and/or Monitoring Hole
				<input type="checkbox"/> Alteration (Construction)
				<input type="checkbox"/> Abandoned, Insufficient Supply
				<input type="checkbox"/> Abandoned, Poor Water Quality
				<input type="checkbox"/> Abandoned, other, specify
				<input type="checkbox"/> Other, specify

Water Details

Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft)	Diameter (cm/in)
	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	From To	
154 (m/ft)		0' 52'	93/4"
		52' 160'	6"

Well Contractor and Well Technician Information

Business Name of Well Contractor: AIR ROCK DRILLING CO LTD 1119 Business Address (Street Number/Name): Richmond Municipality: Richmond Province: ONT Postal Code: K0A 2Z0 Business E-mail Address:

Results of Well Yield Testing

After test of well yield, water was: Clear and sand free Other, specify

If pumping discontinued, give reason:

Pump Intake set at (m/ft): 140'

Pumping rate (l/min / GPM): 10

Duration of pumping: 1 hrs + 0 min

Final water level end of pumping (m/ft): 129.7'

If flowing give rate (l/min / GPM):


Time (min)	Draw Down		Recovery	
	Water Level (m/ft)	Time (min)	Water Level (m/ft)	Time (min)
Static Level	10.2"		129.7"	
1	21.4	1	97.3	
2	27.2	2	90.2	
3	33.	3	85.	
4	37.4	4	80.7	
5	41.3	5	76.	
10	56.6	10	53.7	
15	72.5	15	40.4	
20	86.4	20	25.1	
25	94.8	25	16.1	
30	107.6	30	10.2	
40	115.4	40	10.2	
50	121.6	50	10.2	
60	129.7	60	10.2	

Recommended pump depth (m/ft): 140'

Recommended pump rate (l/min / GPM): 10

Well production (l/min / GPM): 10

Disinfected? Yes No



Well Contractor and Well Technician Information

Business Name of Well Contractor: AIR ROCK DRILLING CO LTD 1119 Business Address (Street Number/Name): Richmond Municipality: Richmond Province: ONT Postal Code: K0A 2Z0 Business E-mail Address:

Bus. Telephone No. (inc. area code): 61388382170 Name of Well Technician (Last Name, First Name): HANNA JEREMY Well Technician's Licence No.: 113632 Signature of Technician and/or Contractor: [Signature] Date Submitted: 20180208

Comments: 1/2 HR - 10 GPM @ 140 FT

Well owner's information package delivered: Yes No Date Package Delivered: 20180201 Date Work Completed: 20180129

Ministry Use Only: Audit No.: Z237032 Received:

TW2



Ministry of the Environment and Climate Change

Well Tag #: A 240714 (OW)

Well Record

Regulation 903 Ontario Water Resources Act

Measurements recorded in: Metric Imperial

Page _____ of _____

A 240714

Well Owner's Information

First Name: 1230381 Ontario Inc. Last Name / Organization: (Adrian Schenck) E-mail Address: [] Well Constructed by Well Owner

Mailing Address (Street Number/Name): 2740 Herbison Road Municipality: Richmond Province: Ont Postal Code: K0A2Z0 Telephone No. (inc. area code):

Well Location

Address of Well Location (Street Number/Name): (NOCIVIC) HEMPHILL STREET Township: GOULBOURN P/L25 Lot: 4 Concession: 4

County/District/Municipality: OTTAWA-CARLETON City/Town/Village: RICHMOND Province: Ontario Postal Code:

UTM Coordinates Zone, Easting, Northing: NAD 83 1843437 15006052 Municipal Plan and Sublot Number: PART # 6 Other:

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m)
				From To
	Clay			0' 47'
	Grey limestone			47' 140'
* Broken Rock - Do NOT Set Pump Below 100 FT *				
TW # 2 OF 3				

Annular Space

Depth Set at (m)	Type of Sealant Used (Material and Type)	Volume Placed (m³)
From To		
53' 43'	Neat Cement Slurry	10.92
43' 0'	Bentonite Slurry	8.40

Method of Construction

Cable Tool Diamond Public Commercial Not used

Rotary (Conventional) Jetting Domestic Municipal Dewatering

Rotary (Reverse) Driving Livestock Test Hole Monitoring

Boring Digging Irrigation Cooling & Air Conditioning

Air percussion Other, specify

Construction Record - Casing

Inside Diameter (cm)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm)	Depth (m)
			From To
6 1/4"	Steel	.188"	+2' 53'
6"	Open Hole		53' 140'

Status of Well:

Water Supply Replacement Well Test Hole Recharge Well Dewatering Well Observation and/or Monitoring Hole Alteration (Construction) Abandoned, Insufficient Supply Abandoned, Poor Water Quality Abandoned, other, specify Other, specify

Construction Record - Screen

Outside Diameter (cm)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m)
			From To

Water Details

Water found at Depth (m)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify	Depth (m)	Diameter (cm)
		From To	
134'		0' 53'	9 3/4"
		53' 140'	6"

Well Contractor and Well Technician Information

Business Name of Well Contractor: AIR ROCK DRILLING CO LTD Well Contractor's Licence No.: 1119

Business Address (Street Number/Name): RR# 1 Municipality: RICHMOND

Province: ONT Postal Code: K0A2Z0 Business E-mail Address:

Bus Telephone No. (inc. area code): 6138382170 Name of Well Technician (Last Name, First Name): HANNA JEREMY

Well Technician's Licence No.: 13632 Signature of Technician and/or Contractor: [Signature] Date Submitted: 20180202

Results of Well Yield Testing

After test of well yield, water was: Clear and sand free Other, specify

If pumping discontinued, give reason: Pump intake set at (m): 100'

Pumping rate (l/min @ PM): 20

Duration of pumping: 1 hrs 0 min

Final water level end of pumping (m): 51.4'

If flowing give rate (l/min / GPM): X


Static Level	Draw Down		Recovery	
	Time (min)	Water Level (m)	Time (min)	Water Level (m)
9.6"			51.4"	
1	18.8		1	37.7
2	26.		2	28.8
3	32		3	21.9
4	35.8		4	20.4
5	38.6		5	18.6
10	46.8		10	11.3
15	47.6		15	9.6
20	50.2		20	9.6
25	50.6		25	
30	50.9		30	
40	51.2		40	
50	51.3		50	
60	51.4		60	

Recommended pump depth (m): 100'

Recommended pump rate (l/min @ PM): 20

Well production (l/min @ PM): 20

Disinfect? Yes No



Comments: 1/2HP-10GPM @ 100 FT

Well owner's information package delivered: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Date Package Delivered: 20180206	Ministry Use Only Audit No.: 2237047
	Date Work Completed: 20180130	Received:

TW3



Ministry of the Environment

Well Tag #: A 240721

Well Record

Regulation 903 Ontario Water Resources Act

Measurements recorded in: Metric Imperial

Page 1 of 1

Well Owner's Information

First Name: 1230381 (Last Name / Organization) Ontario Inc E-mail Address: (Adrian Schonten) Well Constructed by Well Owner

Mailing Address (Street Number/Name): 2740 Harrison Road Municipality: Richmond Ont Province: Ont Postal Code: K0A 2Z0 Telephone No. (inc. area code):

Well Location

Address of Well Location (Street Number/Name): (No Civic) Hemphill Street Township: Goulbourn Lot: P/L25 Concession: 4

County/District/Municipality: QUANA CARLETON City/Town/Village: Richmond Province: Ontario Postal Code:

UTM Coordinates Zone: 18 Easting: 43855006065 Northing: Municipal Plan and Sublot Number: PART # 8/9 Other:

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m)
				From To
	Clay			0' 48'
	Grey limestone			48' 180'
TW#3 OF 3				

Annular Space			Volume Placed (m³)
Depth Set at (m)	Type of Sealant Used (Material and Type)		
From To			
54' 44'	Neat Cement Slurry		10.92
44' 0'	Bestonite Grout		16.80

Method of Construction

Cable Tool Diamond Rotary (Conventional) Jetting Rotary (Reverse) Driving Boring Air percussion Other, specify

Well Use

Public Commercial Not used Domestic Municipal Dewatering Livestock Test Hole Monitoring Irrigation Cooling & Air Conditioning Industrial Other, specify

Construction Record - Casing			Status of Well	
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm)	Depth (m)	From To
6 1/4"	Steel	.188"	2' 54'	
5 7/8"	Open hole		54' 180'	

Water Supply Replacement Well Test Hole Recharge Well Dewatering Well Observation and/or Monitoring Hole Alteration (Construction) Abandoned, Insufficient Supply Abandoned, Poor Water Quality Abandoned, other, specify Other, specify

Construction Record - Screen		
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No. Depth (m)
		From To

Water Details		Hole Diameter	
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify <u></u>	Depth (m)	Diameter (cm/in)
		From To	
111 (m/ft)		0' 54'	9 3/4"
174 (m/ft)		54' 180'	5 7/8"

Well Contractor and Well Technician Information

Business Name of Well Contractor: Air Rock Drilling Co Ltd Well Contractor's Licence No.: 1119


Business Address (Street Number/Name): Rt#1 Municipality: Richmond

Province: Ont Postal Code: K0A 2Z0 Business E-mail Address:

Bus. Telephone No. (inc. area code): 613882210 Name of Well Technician (Last Name, First Name): HANNA JEREMY

Well Technician's Licence No.: T3632 Signature of Technician and/or Contractor: [Signature] Date Submitted: 20180208

Results of Well Yield Testing				
After test of well yield, water was: <input type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify <u></u>	Draw Down		Recovery	
	Time (min)	Water Level (m/ft)	Time (min)	Water Level (m/ft)
<input checked="" type="checkbox"/> If pumping discontinued, give reason: <u>X</u>	Static Level	8' 4"		104.7
	1	16.1	1	81.4
	2	24.3	2	62.2
	3	32.5	3	55.1
	4	40.7	4	46.4
	5	47.8	5	38.7
Pump intake set at (m/ft): <u>160'</u>				
Pumping rate (l/min / GPM): <u>15</u>				
Duration of pumping: <u>1</u> hrs + <u>0</u> min				
Final water level end of pumping (m/ft): <u>104' 7"</u>				
If flowing give rate (l/min / GPM): <u>X</u>				
Recommended pump depth (m/ft): <u>140'</u>				
Recommended pump rate (l/min / GPM): <u>15</u>				
Well production (l/min / GPM): <u>15</u>				
Disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No				
10	63.8	10	23.9	
15	70.8	15	12.3	
20	76.4	20	8.4	
25	81.7	25	8.4	
30	93.4	30		
40	98.6	40		
50	101.4	50		
60	104.7	60		



Comments: 1/2HP-10GPM @ 140 FT

Well owner's information package delivered: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Date Package Delivered: <u>20180207</u>	Ministry Use Only
Date Work Completed: <u>20180206</u>	Audit No. <u>202848</u>	Received



APPENDIX B

MOECC WELL RECORDS AND SURVEY QUESTIONNAIRE FOR NEIGHBOURING WELLS

65

A 18 434 4.0 SCODED

14 5005810

4 0304



1509756

B

The Ontario Water Resources Commission Act LIKELY 4 HEMPHILL STREET

WATER WELL RECORD

County or District Carleton Township Richmond
 Con. 14 Lot 4 Date completed 14 Aug 1968
 (day month year)
 Owner Julia Construction Ltd. Address Richmond Ont.
 (print in block letters)

Casing and Screen Record

Inside diameter of casing 5"
 Total length of casing 47'
 Type of screen
 Length of screen
 Depth to top of screen
 Diameter of finished hole 5"

Pumping Test

Static level 11'
 Test-pumping rate 10 G.P.M.
 Pumping level 50
 Duration of test pumping 1 hr
 Water clear or cloudy at end of test clear
 Recommended pumping rate 5 G.P.M.
 with pump setting of 60 feet below ground surface

Well Log

Overburden and Bedrock Record

Overburden and Bedrock Record	From ft.	To ft.
<u>clay</u>	<u>0</u>	<u>43</u>
<u>limestone</u>	<u>43</u>	<u>86</u>

Water Record

Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
<u>85</u>	<u>fresh</u>

For what purpose(s) is the water to be used?

new house

Is well on upland, in valley, or on hillside?

Drilling or Boring Firm Capital Well Drilling

Address 14 Ashford Dr

Licence Number 2857

Name of Driller or Borer H. Mainis

Address


Date Aug 14 1968

Thatcher Kavanagh
(Signature of Licensed Drilling or Boring Contractor)

Form 7 15M-60-4138 Lot 45

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.





Ministry
of the
Environment
Ontario

The Ontario Water Resources Act

WATER WELL RECORD

LIKELY 6 HEMPHILL STREET

1528767

15704

CON

1. PRINT ONLY IN SPACES PROVIDED

2. CHECK CORRECT BOX WHERE APPLICABLE

11

Hemphill St. Richmond

04

COUNTY OR DISTRICT <i>Ont</i>	TOWNSHIP <i>Wain (Richmond)</i>	CITY/TOWN/VILLAGE <i>Richmond</i>	CON. BLOCK/TRACT/SURVEY ETC. <i>Con 4</i>	LOT <i>25</i>
ADDRESS <i>639 Richmond KOA 220</i>			DATE COMPLETED DAY <i>5</i> MO <i>9</i> YR <i>95</i>	

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)					
GENERAL COLOUR	MOST COMMON MATERIAL	OTHER MATERIALS	GENERAL DESCRIPTION	DEPTH - FEET	
				FROM	TO
<i>grey</i>	<i>clay</i>			<i>0</i>	<i>46</i>
<i>grey</i>	<i>broken rock</i>			<i>46</i>	<i>47</i>

31	32
----	----

41 WATER RECORD	
WATER FOUND AT - FEET	KIND OF WATER
<i>47</i>	<i>Not tested</i>
10-13	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERALS 6 <input type="checkbox"/> GAS
15-18	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERALS 6 <input type="checkbox"/> GAS
20-23	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERALS 6 <input type="checkbox"/> GAS
25-28	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERALS 6 <input type="checkbox"/> GAS
30-33	1 <input type="checkbox"/> FRESH 3 <input type="checkbox"/> SULPHUR 2 <input type="checkbox"/> SALTY 4 <input type="checkbox"/> MINERALS 6 <input type="checkbox"/> GAS

51 CASING & OPEN HOLE RECORD			
INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH - FEET
<i>6 1/2</i>	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE 5 <input type="checkbox"/> PLASTIC	<i>1/8</i>	<i>0 46</i>
<i>6</i>	1 <input type="checkbox"/> STEEL 2 <input type="checkbox"/> GALVANIZED 3 <input type="checkbox"/> CONCRETE 4 <input type="checkbox"/> OPEN HOLE 5 <input type="checkbox"/> PLASTIC		<i>46 47</i>

SIZES OF OPENING (SLOT NO.)	31-33 DIAMETER	34-38 LENGTH	39-40
MATERIAL AND TYPE	DEPTH TO TOP OF SCREEN		

61 PLUGGING & SEALING RECORD	
DEPTH SET AT - FEET	MATERIAL AND TYPE (CEMENT GROUT LEAD PACKER ETC.)
<i>10-13</i>	<i>14-17</i>
<i>18-21</i>	<i>22-25</i>
<i>26-29</i>	<i>30-33</i>

71 PUMPING TEST	
PUMPING TEST METHOD	PUMPING RATE
1 <input checked="" type="checkbox"/> <i>Flow</i> 2 <input type="checkbox"/> BAILER	<i>15</i> GPM
15-16 DURATION OF PUMPING	17-18
<i>1</i> HOURS	<i>0</i> MINS
STATIC LEVEL	WATER LEVEL END OF PUMPING
<i>8</i> FEET	<i>30</i> FEET
WATER LEVELS DURING	
15 MINUTES	30 MINUTES
<i>8</i> FEET	<i>8</i> FEET
45 MINUTES	60 MINUTES
<i>8</i> FEET	<i>8</i> FEET
IF FLOWING, GIVE RATE	PUMP INTAKE SET AT
	<i>30</i> FEET
RECOMMENDED PUMP TYPE	RECOMMENDED PUMP SETTING
<input checked="" type="checkbox"/> SHALLOW <input type="checkbox"/> DEEP	<i>30</i> FEET
RECOMMENDED PUMPING RATE	RECOMMENDED PUMPING RATE
<i>10</i> GPM	<i>10</i> GPM

LOCATION OF WELL	
IN DIAGRAM BELOW SHOW DISTANCES OF WELL FROM ROAD AND LOT LINE - INDICATE NORTH BY ARROW.	
DRILLERS REMARKS	
137565	

FINAL STATUS OF WELL	
1 <input checked="" type="checkbox"/> WATER SUPPLY	5 <input type="checkbox"/> ABANDONED, INSUFFICIENT SUPPLY
2 <input type="checkbox"/> OBSERVATION WELL	6 <input type="checkbox"/> ABANDONED, POOR QUALITY
3 <input type="checkbox"/> TEST HOLE	7 <input type="checkbox"/> UNFINISHED
4 <input type="checkbox"/> RECHARGE WELL	8 <input type="checkbox"/> DEWATERING
WATER USE	
1 <input checked="" type="checkbox"/> DOMESTIC	5 <input type="checkbox"/> COMMERCIAL
2 <input type="checkbox"/> STOCK	6 <input type="checkbox"/> MUNICIPAL
3 <input type="checkbox"/> IRRIGATION	7 <input type="checkbox"/> PUBLIC SUPPLY
4 <input type="checkbox"/> INDUSTRIAL	8 <input type="checkbox"/> COOLING OR AIR CONDITIONING
9 <input type="checkbox"/> NOT USED	
METHOD OF CONSTRUCTION	
1 <input type="checkbox"/> CABLE TOOL	6 <input type="checkbox"/> BORING
2 <input type="checkbox"/> ROTARY (CONVENTIONAL)	7 <input type="checkbox"/> DIAMOND
3 <input type="checkbox"/> ROTARY (REVERSE)	8 <input type="checkbox"/> JETTING
4 <input type="checkbox"/> ROTARY (AIR)	9 <input type="checkbox"/> DRIVING
5 <input checked="" type="checkbox"/> AIR PERCUSSION	10 <input type="checkbox"/> DIGGING
11 <input type="checkbox"/> OTHER	

CONTRACTOR	NAME OF WELL CONTRACTOR	WELL CONTRACTOR'S LICENSE NUMBER
	<i>Henry Manis Well Drilling</i>	<i>3644</i>
	ADDRESS	
	<i>Box 326 Richmond Ont</i>	
	NAME OF WELL TECHNICIAN	WELL TECHNICIAN'S LICENSE NUMBER
	<i>Manis</i>	<i>7-0064</i>
	SIGNATURE OF TECHNICIAN/CONTRACTOR	SUBMISSION DATE
	<i>Manis</i>	DAY <i>7</i> MO <i>9</i> YR <i>95</i>

OFFICE USE ONLY	DATA SOURCE	CONTRACTOR	DATE RECEIVED
		3644	OCT 10 1995
	DATE OF INSPECTION	INSPECTOR	
	REMARKS		

PARK LOTS 1, 2, 3
 NORTH PART OF P.L.O. CODED



1509810 WATER RESOURCES
LIKELY 39 GAMBLE DRIVE

B

The Ontario Water Resources Commission Act

APR 2 1969

4 KPO 305 **WATER WELL RECORD**

County or District 25 CARLETON Township, Village, Town or City RICHMOND

Con. DELLA ST. IV Lot PARCEL 31 Date completed 2 7 68
 (day month year)



Address 10 Cedar View Rd. BELLS CORNERS

Casing and Screen Record

Pumping Test

Inside diameter of casing 5"
 Total length of casing 45'
 Type of screen -
 Length of screen -
 Depth to top of screen -
 Diameter of finished hole 5"

Static level 4'
 Test-pumping rate 10 G.P.M.
 Pumping level 15'
 Duration of test pumping 2 hrs.
 Water clear or cloudy at end of test clear
 Recommended pumping rate 8 G.P.M.
 with pump setting of 25 feet below ground surface

Well Log

Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
<u>Blue clay</u>	<u>0</u>	<u>43</u>		
<u>Gravel</u>	<u>43</u>	<u>45</u>		
<u>limestone</u>	<u>45</u>	<u>51</u>	<u>50</u>	<u>Fresh</u>

For what purpose(s) is the water to be used?

HOUSE

Is well on upland, in valley, or on hillside? upland

Drilling or Boring Firm McLean Water Supply Ltd.

Address 1532 RAYEN AVE
OTTAWA 3, ONT

Licence Number 2879

Name of Driller or Borer H. SALLY

Address


Date JULY 21 1968

(Signature of Licensed Drilling or Boring Contractor)

[Signature]
 Lot 21

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



Am

B



18 434 380 CODED

1509758

WATER RESOURCES DIVISION

The Ontario Water Resources Commission Act

LIKELY 40 GAMBLE DRIVE

14 501015700

14 10305

WATER WELL RECORD

County or District Carleton Township, Village, Town or City Richmond
 Con. 14 Lot 14 Date completed 16 Aug 1968
 (day month year)
 Owner Julia Construction Ltd Address Richmond Ont.
 (print in block letters)

Casing and Screen Record

Pumping Test

Inside diameter of casing 5"
 Total length of casing 46'
 Type of screen
 Length of screen
 Depth to top of screen
 Diameter of finished hole 5"

Static level 6'
 Test-pumping rate 10 G.P.M.
 Pumping level 10'
 Duration of test pumping 1 hr
 Water clear or cloudy at end of test
 Recommended pumping rate 5 G.P.M.
 with pump setting of 30' feet below ground surface

Well Log


Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
<u>clay</u>	<u>0'</u>	<u>45'</u>	<u>49'</u>	<u>fresh</u>
<u>limestone</u>	<u>45'</u>	<u>50'</u>		

For what purpose(s) is the water to be used? new house
 Is well on upland, in valley, or on hillside?
 Drilling or Boring Firm Capital Well Drilling
 Address 14 Ashford Dr
Ottawa 6
 Licence Number 2857
 Name of Driller or Borer H mains
 Address
 Date Aug 16, 1968
Shated Lavanagh
 (Signature of Licensed Drilling or Boring Contractor)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



Lot 26

CODED



1509748

WATER RESOURCES DIVISION
OCT 17 1968
ONTARIO WATER RESOURCES COMMISSION

B

118 434 385
14 500574
14 0305

The Ontario Water Resources Commission Act

LIKELY 41 GAMBLE DRIVE

WATER WELL RECORD

County or District 251 Carleton Township, Village, Town or City Richmond
Con. TV Lot 1 Date completed 24 Sept 1968
(day) (month) (year)
Owner Julia Construction Ltd Address Richmond Int.
(print in block letters)

Casing and Screen Record

Pumping Test

Inside diameter of casing 5"
Total length of casing 46
Type of screen
Length of screen
Depth to top of screen
Diameter of finished hole 5"

Static level 10'
Test-pumping rate 10 G.P.M.
Pumping level 10'
Duration of test pumping 1 hr
Water clear or cloudy at end of test
Recommended pumping rate 5 G.P.M.
with pump setting of 30 feet below ground surface

Well Log


Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
<u>clay</u>	<u>0</u>	<u>45</u>	<u>49</u>	<u>fresh</u>
<u>limestone</u>	<u>45</u>	<u>50</u>		

For what purpose(s) is the water to be used? new house
Is well on upland, in valley, or on hillside?
Drilling or Boring Firm Capital Water Supply Ltd
Address 14 Ashford Dr
Ottawa 6
Licence Number 2857
Name of Driller or Borer M. Kavanagh
Address
Date Sept 24 1968
Halter Kavanagh
(Signature of Licensed Drilling or Boring Contractor)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



Form 7 5M 60-20912

Lot 22

OWRC COPY

715
CODED 18 4134360 CODED



1509757

B

14 51005720

4 0305

The Ontario Water Resources Commission Act **LIKELY 42 GAMBLE DRIVE**

WATER WELL RECORD

County or District Carleton Township, Village, Town or City Richmond
 Con. 14 Lot 14 Date completed 14 Aug 1968
 (day month year)
 Owner Julia Construction Ltd Address Richmond Ont.
 (print in block letters)

Casing and Screen Record

Inside diameter of casing 5"
 Total length of casing 46'
 Type of screen
 Length of screen
 Depth to top of screen
 Diameter of finished hole 5"

Pumping Test

Static level 5'
 Test-pumping rate 10 G.P.M.
 Pumping level 8'
 Duration of test pumping 1 hr
 Water clear or cloudy at end of test cloudy
 Recommended pumping rate 5 G.P.M.
 with pump setting of 30 feet below ground surface

Well Log


Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
<u>clay</u>	<u>0</u>	<u>45</u>	<u>47'</u>	<u>fresh</u>
<u>limestone</u>	<u>45</u>	<u>47</u>		

For what purpose(s) is the water to be used? new house
 Is well on upland, in valley or on hillside?
 Drilling or Boring Firm Capital Well Drilling
 Address 14 Ashford Dr
 Licence Number 2857
 Name of Driller or Borer A Mains
 Address
 Date Aug 14 1968
Halter Lavanagh
 (Signature of Licensed Drilling or Boring Contractor)
Lot 25

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.





PARK 180 STS #134 3.60
NORTH PERTH 05.76.5
10 30.5

CODE

1509791

WATER RECORD

APR 28 1968

The Ontario Water Resources Commission Act

WATER WELL RECORD

LIKELY 43 GAMBLE DRIVE

County or District

CARLETON

Township, Village, Town or City

RICHMOND, ONT.

Con. DELLA ST

Lot PARCEL 23

Date completed

27

6

1968

(day)

month

year

Address 10 CEDARVIEW RD. BELLS

CORNERS, ONT

Casing and Screen Record

Pumping Test

Inside diameter of casing 5"

Total length of casing 45'

Type of screen —

Length of screen —

Depth to top of screen —

Diameter of finished hole 5"

Static level 4'

Test-pumping rate 8 G.P.M.

Pumping level 15'

Duration of test pumping 1 1/2 hrs.

Water clear or cloudy at end of test Clear

Recommended pumping rate 8 G.P.M.

with pump setting of 25' feet below ground surface

Well Log

Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
Blue clay	0	42		
Coarse Gravel	42	45		
limestone	45	50	48'	Fresh

For what purpose(s) is the water to be used?

HOUSE

Is well on upland, in valley, or on hillside? Upland

Drilling or Boring Firm McLean Water

Supply Ltd.

Address 1532 RAVEN AVE.

OTTAWA, ONT

Licence Number 2879

Name of Driller or Borer H. SALLY

Address

Date JULY 2, 1968

(Signature of Licensed Drilling or Boring Contractor)

Form 7 15M-60-4138

OWRC COPY

lot 23

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



ESME ST. - 34' to well

DELLA ST.

47

18 434 340 CODED



1509766

LIKELY 44 GAMBLE DRIVE

B

4 510 057 40

4 0305

The Ontario Water Resources Commission Act

25T

WATER WELL RECORD

County or District

Carleton

Township, Village, Town or City

Richmond

Con.

14

Lot

Date completed

27

Aug

1968

Owner

Julia Constr. Ltd
(print in block letters)

Address

Richmond Ont.

Casing and Screen Record

Pumping Test

Inside diameter of casing 5"

Total length of casing 48'

Type of screen

Length of screen

Depth to top of screen

Diameter of finished hole 5"

Static level 7'

Test-pumping rate 10 G.P.M.

Pumping level 10

Duration of test pumping 4 8hr

Water clear or cloudy at end of test

Recommended pumping rate 5 G.P.M.

with pump setting of 30' feet below ground surface

Well Log

Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
clay	0	47'	52	fresh
limestone	47'	53'		

For what purpose(s) is the water to be used?

new house

Is well on upland, in valley, or on hillside?

Drilling or Boring Firm

Capital Hald
Drilling

Address

14 Ashford Dr
Altamont 6

Licence Number

2857

Name of Driller or Borer

H. Mainis

Address

Date

Aug 28, 1968

Walter Lavanagh
(Signature of Licensed Drilling or Boring Contractor)


Form 7 15M-60-4138

Lot 24

OWRC COPY

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.





Print only in spaces provided. Mark correct box with a checkmark, where applicable.

11

1531410

Municipality 15003 Con. CON. 04

County or District: Ottawa Carleton; Township/Borough/City/Town/Village: Gaitherburn; Con block tract survey, etc.: 4; Lot: 25; Owner's surname: Cedarstone Homes; First Name: ; Address: P.O. Box 1297 Richmond, Ontario K9A 2Z0; Date completed: 23 day 9 month 00 year

Zone, Easting, Northing, RC, Elevation, RC, Basin Code, ii, iii, iv

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions). Table with columns: General colour, Most common material, Other materials, General description, Depth - feet (From, To). Rows: Brown Clay (0-12), Gray Clay (12-52), Gray Limestone (52-160), Gray & White Sandstone (160-235).

31, 32


41 WATER RECORD. Water found at - feet: 231. Kind of water: Fresh, Salty, Sulphur, Minerals, Gas. NOT TESTED.

51 CASING & OPEN HOLE RECORD. Inside diam inches: 6 1/4, 6 1/16. Material: Steel, Galvanized, Concrete, Open hole, Plastic. Wall thickness inches: .188. Depth - feet: 0-55, 55-235.

SCREEN. Sizes of opening (Slot No.), Diameter inches, Length feet. Material and type, Depth at top of screen feet.

61 PLUGGING & SEALING RECORD. Annular space, Abandonment. Depth set at - feet: 54. Material and type: Grouted - Cement (5).

71 PUMPING TEST. Pumping test method: Pump. Pumping rate: 15 GPM. Duration of pumping: 1 Hour. Static level: 12.6 ft. Water level during pumping: 75 ft. Pump intake set at: 230 feet. Water at end of test: 75 feet. Recommended pump type: Deep. Recommended pump setting: 100 feet. Recommended pump rate: 5 GPM.



FINAL STATUS OF WELL: Water supply, Observation well, Test hole, Recharge well, Abandoned, insufficient supply, Abandoned, poor quality, Abandoned (Other), Dewatering, Unfinished, Replacement well. WATER USE: Domestic, Stock, Irrigation, Industrial, Commercial, Municipal, Public supply, Cooling & air conditioning, Not use, Other. METHOD OF CONSTRUCTION: Cable tool, Rotary (conventional), Rotary (reverse), Rotary (air), Air percussion, Boring, Diamond, Jetting, Driving, Digging, Other.

Name of Well Contractor: Capital Water Supply Ltd.; Well Contractor's Licence No.: 1558; Address: P.O. Box 490 Stittsville, Ontario K2S 1A6; Name of Well Technician: S. Miller; Well Technician's Licence No.: T0097; Signature of Technician/Contractor: S. Miller; Submission date: day 25 mo 9 yr 00.

MINISTRY USE ONLY. Data source: 1558; Date received: OCT 18 2000; Date of inspection; Inspector; Remarks: CSS.ES0.

Print only in spaces provided.
Mark correct box with a checkmark, where applicable.

11

1531128

Municipality
15003

Con.
CON

04

County or District Ottawa Carleton		Township/Borough/City/Town/Village Goulbourn		Con block tract survey, etc. 4		Lot 25	
Owner's surname Cedarstone Homes		First Name		Address P.O. Box 1297 Richmond, Ontario K0A 2Z0		Date completed 18 May 5 month 00 year	

21

Zone Easting Northing RC Elevation RC Basin Code

LOG OF OVERBURDEN AND BEDROCK MATERIALS (see instructions)					
General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
Brown	Clay			0	12
Gray	Clay			12	49
Gray	Clay	Stones		49	51
Gray	Limestone			51	170
Gray & White	Sandstone			170	225

31

32


41 WATER RECORD			
Water found at - feet	Kind of water		
0-1	<input type="checkbox"/> Fresh	<input type="checkbox"/> Sulphur	<input type="checkbox"/> Minerals
2	<input type="checkbox"/> Salty	<input type="checkbox"/> Gas	
15-18	<input type="checkbox"/> Fresh	<input type="checkbox"/> Sulphur	<input type="checkbox"/> Minerals
2	<input type="checkbox"/> Salty	<input type="checkbox"/> Gas	
20-23	<input type="checkbox"/> Fresh	<input type="checkbox"/> Sulphur	<input type="checkbox"/> Minerals
2	<input type="checkbox"/> Salty	<input type="checkbox"/> Gas	
25-28	<input type="checkbox"/> Fresh	<input type="checkbox"/> Sulphur	<input type="checkbox"/> Minerals
2	<input type="checkbox"/> Salty	<input type="checkbox"/> Gas	
30-33	<input type="checkbox"/> Fresh	<input type="checkbox"/> Sulphur	<input type="checkbox"/> Minerals
2	<input type="checkbox"/> Salty	<input type="checkbox"/> Gas	

51 CASING & OPEN HOLE RECORD				
Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4	<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic	.188	0	53.5
5 7/8	<input type="checkbox"/> Steel <input checked="" type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic		53.5	225
4 25	<input type="checkbox"/> Steel <input checked="" type="checkbox"/> Galvanized <input type="checkbox"/> Concrete <input type="checkbox"/> Open hole <input type="checkbox"/> Plastic			27.30

SCREEN	Sizes of opening (Slot No.)		Diameter	Length
			inches	feet
	Material and type		Depth at top of screen feet	

51 PLUGGING & SEALING RECORD			
<input checked="" type="checkbox"/> Annular space <input type="checkbox"/> Abandonment			
Depth set at - feet		Material and type (Cement grout, bentonite, etc.)	
From	To		
52	0	Grouted-Cement (1)	
		-QuickGrout (1)	

71 PUMPING TEST			
Pumping test method <input checked="" type="checkbox"/> Pump <input type="checkbox"/> Bailor	Pumping rate GPM	Duration of pumping Hours Mins	
Static level 11'0"	Water level end of pumping 125 feet	Water levels during 15 minutes: 220 feet 30 minutes: 150 feet 45 minutes: 150 feet 60 minutes: 125 feet	Pumping <input checked="" type="checkbox"/> Recovery <input type="checkbox"/>
If flowing give rate	Pump intake set at	Water at end of test <input type="checkbox"/> Clear <input checked="" type="checkbox"/> Cloudy	
Recommended pump type <input type="checkbox"/> Shallow <input checked="" type="checkbox"/> Deep	Recommended pump setting 150 feet	Recommended pump rate 5 GPM	



FINAL STATUS OF WELL			
<input checked="" type="checkbox"/> Water supply	<input type="checkbox"/> Abandoned, insufficient supply	<input type="checkbox"/> Unfinished	
<input checked="" type="checkbox"/> Observation well	<input type="checkbox"/> Abandoned, poor quality	<input type="checkbox"/> Replacement well	
<input type="checkbox"/> Test hole	<input type="checkbox"/> Abandoned (Other)		
<input type="checkbox"/> Recharge well	<input type="checkbox"/> Dewatering		

WATER USE			
<input checked="" type="checkbox"/> Domestic	<input type="checkbox"/> Commercial	<input type="checkbox"/> Not use	
<input type="checkbox"/> Stock	<input type="checkbox"/> Municipal	<input type="checkbox"/> Other	
<input type="checkbox"/> Irrigation	<input type="checkbox"/> Public supply		
<input type="checkbox"/> Industrial	<input type="checkbox"/> Cooling & air conditioning		

METHOD OF CONSTRUCTION			
<input type="checkbox"/> Cable tool	<input checked="" type="checkbox"/> Air percussion	<input type="checkbox"/> Driving	
<input type="checkbox"/> Rotary (conventional)	<input type="checkbox"/> Boring	<input type="checkbox"/> Digging	
<input type="checkbox"/> Rotary (reverse)	<input type="checkbox"/> Diamond	<input type="checkbox"/> Other	
<input checked="" type="checkbox"/> Rotary (air)	<input type="checkbox"/> Jetting		

Name of Well Contractor Capital Water Supply Ltd.	Well Contractor's Licence No. 1558
Address P.O. Box 490 Stittsville, Ontario K2B 1A6	
Name of Well Technician S. Miller	Well Technician's Licence No. T0097
Signature of Technician/Contractor	Submission date day 23 mo 5 yr 00

MINISTRY USE ONLY	Data source 1558	Contractor 1558	Date received JUN 20 2000
	Date of inspection	Inspector	
	Remarks CSS.ES0		

Print only in spaces provided. Mark correct box with a checkmark, where applicable.

11

1530215

Municipality 15003 Con. 04

County or District Ottawa Carleton	Township/Borough/City/Town/Village Goulbourn	Con block tract survey, etc. 4	Lot 25
Owner's surname Cedarstone Homes	First name Goulbourn	Address P.O. Box 1297 Richmond, Ontario K0A 2Z7	
Date completed 8 day 9 month 98		Easting 21	

General colour	Most common material	Other materials	General description	Depth - feet	
				From	To
Brown	Clay	Stones	Packed	0	12
Gray	Clay		Loose	12	51
Gray	Sandy Clay	Stones		51	52
Gray	Limestone		Medium	52	75

31 32


Water found at - feet	Kind of water
10-13	1 <input type="checkbox"/> Fresh 3 <input type="checkbox"/> Sulphur 14 2 <input type="checkbox"/> Salty 4 <input type="checkbox"/> Minerals 6 <input type="checkbox"/> Gas
15-18	NOT TESTED
20-23	1 <input type="checkbox"/> Fresh 3 <input type="checkbox"/> Sulphur 24 2 <input type="checkbox"/> Salty 4 <input type="checkbox"/> Minerals 6 <input type="checkbox"/> Gas
25-28	1 <input type="checkbox"/> Fresh 3 <input type="checkbox"/> Sulphur 29 2 <input type="checkbox"/> Salty 4 <input type="checkbox"/> Minerals 6 <input type="checkbox"/> Gas
30-33	1 <input type="checkbox"/> Fresh 3 <input type="checkbox"/> Sulphur 34 2 <input type="checkbox"/> Salty 4 <input type="checkbox"/> Minerals 6 <input type="checkbox"/> Gas

Inside diam inches	Material	Wall thickness inches	Depth - feet	
			From	To
6 1/4	1 <input type="checkbox"/> Steel 12 2 <input type="checkbox"/> Galvanized 5 3 <input type="checkbox"/> Concrete 4 4 <input type="checkbox"/> Open hole 5 5 <input type="checkbox"/> Plastic	.188	0	53.5
6	1 <input type="checkbox"/> Steel 19 2 <input type="checkbox"/> Galvanized 2 3 <input type="checkbox"/> Concrete 3 4 <input type="checkbox"/> Open hole 4 5 <input type="checkbox"/> Plastic		53.5	75
6	1 <input type="checkbox"/> Steel 26 2 <input type="checkbox"/> Galvanized 2 3 <input type="checkbox"/> Concrete 3 4 <input type="checkbox"/> Open hole 4 5 <input type="checkbox"/> Plastic			27-30

Sizes of opening (Slot No.)	Diameter inches	Length feet
Material and type	Depth at top of screen feet	

Depth set at - feet		Material and type (Cement grout, bentonite, etc.)
From	To	
52	0	Grouted Cement (8)

Pumping test method 1 <input checked="" type="checkbox"/> Pump 2 <input type="checkbox"/> Bailor	Pumping rate 12 GPM	Duration of pumping Hours: _____ Mins: _____
Static level 14.10 feet	Water level during 15 minutes 15.2 feet	Water levels during 30 minutes 15 feet
Water level end of pumping 60 feet	45 minutes 14.1 feet	60 minutes 14.10 feet
Recommended pump type 1 <input type="checkbox"/> Shallow 2 <input checked="" type="checkbox"/> Deep	Recommended pump setting 60 feet	Recommended pump rate 5 GPM



1 <input type="checkbox"/> Water supply	5 <input type="checkbox"/> Abandoned, insufficient supply	9 <input type="checkbox"/> Unfinished
2 <input checked="" type="checkbox"/> Observation well	6 <input type="checkbox"/> Abandoned, poor quality	10 <input type="checkbox"/> Replacement well
3 <input type="checkbox"/> Test hole	7 <input type="checkbox"/> Abandoned (Other)	
4 <input type="checkbox"/> Recharge well	8 <input type="checkbox"/> Dewatering	

1 <input type="checkbox"/> Domestic	5 <input type="checkbox"/> Commercial	9 <input type="checkbox"/> Not used
2 <input checked="" type="checkbox"/> Stock	6 <input type="checkbox"/> Municipal	10 <input type="checkbox"/> Other
3 <input type="checkbox"/> Irrigation	7 <input type="checkbox"/> Public supply	
4 <input type="checkbox"/> Industrial	8 <input type="checkbox"/> Cooling & air conditioning	

1 <input type="checkbox"/> Cable tool	5 <input type="checkbox"/> Air percussion	9 <input type="checkbox"/> Driving
2 <input type="checkbox"/> Rotary (conventional)	6 <input checked="" type="checkbox"/> Boring	10 <input type="checkbox"/> Digging
3 <input type="checkbox"/> Rotary (reverse)	7 <input type="checkbox"/> Diamond	11 <input type="checkbox"/> Other
4 <input type="checkbox"/> Rotary (air)	8 <input type="checkbox"/> Jetting	

Name of Well Contractor Capital Water Supply Ltd.	Well Contractor's Licence No. 1558
Address P.O. Box 490 Stittsville, Ontario K2S 1A6	
Name of Well Technician S. Miller	Well Technician's Licence No. T0097
Signature of Technician/Contractor <i>S. Miller</i>	Submission date day 10 mo 9 yr 98

MINISTRY USE ONLY	Data source 1558	Contractor 1558	Date received OCT 15 1998
	Date of inspection	Inspector	
	Remarks CSS. ES9		

CODED



1509773

B

181 4344400000

14 5005830

4 0304

The Ontario Water Resources Commission Act

LIKELY 2 HEMPHILL STREET

WATER WELL RECORD

County or District Carleton Township, Village, Town or City Richmond
 Con. 4 Lot 14 Date completed 24 Oct 1968
 (day month year)
 Owner Julia Constr. Ltd Address Richmond Ont.
 (print in block letters)

Casing and Screen Record

Pumping Test

Inside diameter of casing 5"
 Total length of casing 46'
 Type of screen
 Length of screen
 Depth to top of screen
 Diameter of finished hole 5"

Static level 25
 Test-pumping rate 10 G.P.M.
 Pumping level 25
 Duration of test pumping 1 hr
 Water clear or cloudy at end of test
 Recommended pumping rate 5 G.P.M.
 with pump setting of 35 feet below ground surface

Well Log


Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
<u>clay</u>	<u>0'</u>	<u>44'</u>	<u>58</u>	<u>fresh</u>
<u>hardpan</u>	<u>44'</u>	<u>46'</u>		
<u>limestone</u>	<u>46'</u>	<u>59'</u>		

For what purpose(s) is the water to be used? new house
 Is well on upland, in valley, or on hillside?
 Drilling or Boring Firm Capital Water Supply Ltd.
 Address 14 Ashford Dr
Ottawa 6
 Licence Number 2857
 Name of Driller or Borer M Kavanagh
 Address
 Date Oct 24 1968
Walter Kavanagh
 (Signature of Licensed Drilling or Boring Contractor)

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



Lot 44

CODED



1509747

WATER RESOURCES DIVISION

DATE 15 1968

LIKELY 3310 SHEA ROAD

ONTARIO WATER RESOURCES ACT

B

The Ontario Water Resources Commission Act

WATER WELL RECORD

County or District

251 Carleton

Township, Village, Town or City

Richmond

Con.

14 Lot

Date completed

24

Sept

1968

Owner

Julia Construction Ltd

Address

Richmond Ont.

Casing and Screen Record

Pumping Test

Inside diameter of casing 5"

Total length of casing 42'

Type of screen

Length of screen

Depth to top of screen

Diameter of finished hole 5"

Static level 10

Test-pumping rate 10 G.P.M.

Pumping level 12

Duration of test pumping 1 hr

Water clear or cloudy at end of test

Recommended pumping rate 5 G.P.M.

with pump setting of 30 feet below ground surface

Well Log

Water Record

Overburden and Bedrock Record

From ft.

To ft.

Depth(s) at which water(s) found

Kind of water (fresh, salty, sulphur)

clay
limestone

0'

41'

47

fresh

41'

48'

For what purpose(s) is the water to be used?

new house

Is well on upland, in valley or on hillside?

Drilling or Boring Firm

Capital Water Supply Ltd.

Address

14 Ashford Dr
Ottawa 6

Licence Number

2857

Name of Driller or Borer

M Kavanagh

Address

Date 24 Sept 1968


Malter Kavanagh

(Signature of Licensed Drilling or Boring Contractor)

lot 46

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



CODED



1509751

WATER RESOURCES DIVISION

OCT 15 1968

The Ontario Water Resources Commission Act

LIKELY 3316 SHEA ROAD

WATER WELL RECORD

County or District 251 Carleton Township, Village, Town or City Richmond
 Con. 11 Lot 47 Date completed 25 Sept 1968
 (day month year)
 Owner Julia Constr. Ltd. Address Richmond Int.
 (print in block letters)

Casing and Screen Record

Pumping Test

Inside diameter of casing 5"
 Total length of casing 44'
 Type of screen
 Length of screen
 Depth to top of screen
 Diameter of finished hole

Static level 15
 Test-pumping rate 10 G.P.M.
 Pumping level 16
 Duration of test pumping 1 hr
 Water clear or cloudy at end of test
 Recommended pumping rate 5 G.P.M.
 with pump setting of 30 feet below ground surface

Well Log


Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
<u>clay</u>	<u>0'</u>	<u>40'</u>	<u>51</u>	<u>fresh</u>
<u>gravel</u>	<u>40'</u>	<u>42'</u>		
<u>limestone</u>	<u>42</u>	<u>52</u>		

For what purpose(s) is the water to be used? new house
 Is well on upland, in valley, or on hillside?
 Drilling or Boring Firm Capital Water Supply Ltd.
 Address 14 Ashford Dr
Ottawa 6
 Licence Number 2857
 Name of Driller or Borer B Acres
 Address
 Date Sept 25 1968
Walter Kavanagh
 (Signature of Licensed Drilling or Boring Contractor)
Lot 47

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



Form 7 5M 60-20912

OWRC COPY

CSS.S3



1509753

WATER RESOURCES COMMISSION
0001 7 1968
ONTARIO WATER RESOURCES COMMISSION

B

18 434 525 CODED
14 50105720
4 9304

The Ontario Water Resources Commission Act

LIKELY 3326 SHEA ROAD

WATER WELL RECORD

County or District Carleton Township, Village, Town or City Richmond
Con. 14 Lot 10 Date completed 24 Sept 1968
(day) (month) (year)
Owner Julia Construction Ltd Address Richmond Ont.
(print in block letters)

Casing and Screen Record

Pumping Test

Inside diameter of casing 5"
Total length of casing 42'
Type of screen
Length of screen
Depth to top of screen
Diameter of finished hole 5"

Static level 15'
Test-pumping rate 10 G.P.M.
Pumping level 17'
Duration of test pumping 1 hr
Water clear or cloudy at end of test
Recommended pumping rate 5 G.P.M.
with pump setting of 30 feet below ground surface

Well Log


Water Record

Overburden and Bedrock Record	From ft.	To ft.	Depth(s) at which water(s) found	Kind of water (fresh, salty, sulphur)
<u>clay</u>	<u>0</u>	<u>40</u>	<u>49</u>	<u>fresh</u>
<u>limestone</u>	<u>40</u>	<u>50</u>		

For what purpose(s) is the water to be used?
new house
Is well on upland, in valley, or on hillside?
Drilling or Boring Firm Capital Water Supply Ltd.
Address 14 Ashford Dr Ottawa 6
Licence Number 2857
Name of Driller or Borer B Acres
Address
Date Sept 24 1968
Thelma Lavanagh
(Signature of Licensed Drilling or Boring Contractor)
Lot 49

Location of Well

In diagram below show distances of well from road and lot line. Indicate north by arrow.



WATER WELL SYSTEM SURVEY QUESTIONNAIRE

Our File No.: 017630

SECTION A: PROPERTY INFORMATION	
Address of Property:	26 MARY HILL CRES
* Name of Property Owner:	[REDACTED]
* Telephone Number (Home):	[REDACTED]
Number of Occupants:	2
Number of Bedrooms:	3
How Long at Present Address:	3 YRS

*This information will NOT be included in any reporting

SECTION B: WELL CONSTRUCTION DETAILS	
Date or year well constructed:	2001 ?
Do you have a copy of the MOE Well Record?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
Well record number (if known):	
Type of well:	<input checked="" type="checkbox"/> Drilled <input type="checkbox"/> Dug
Well casing diameter (inches):	
Location of well (e.g. front yard, back yard, etc.):	FRONT
Present well depth: 200ft	Original well depth: <input type="checkbox"/> Same as present
Is the well accessible?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
Is it vented and how?	?

SECTION C: WATER SUPPLY	
Do you have a water treatment system?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
If yes, what kind of treatment?:	
Chlorination:	<input type="checkbox"/> YES <input type="checkbox"/> NO
Softener:	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
Filter:	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
Other:	

SECTION D: WATER QUALITY & QUANTITY	
Do you drink the water?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
If no, since when and why?	
Have you ever run out of water?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
Has your well ever been deepened or a new well constructed?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
If yes, why?	
Have you ever experienced any problems with your well?	NO
What was the cause of the problem?	<input type="checkbox"/> Drought <input type="checkbox"/> Pump Failure
<input type="checkbox"/> Increased Usage	<input type="checkbox"/> Interference <input type="checkbox"/> Other (Please Specify)

SECTION D CONTINUED: WATER QUALITY & QUANTITY			
Quality: Taste	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Odour	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Colour	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Hardness	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Iron	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Sulphur Smell	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Has your water quality been tested previously?		<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO
If yes, for what?	<input checked="" type="checkbox"/> Bacteriological	<input type="checkbox"/> Chemical analysis	<input type="checkbox"/> Other
Does your well supply enough water for your use?		<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO
If no, is this the case?:	<input type="checkbox"/> Some of the time	<input type="checkbox"/> Seasonally	<input type="checkbox"/> Other
Do you use your well for?:	<input checked="" type="checkbox"/> Lawn watering	<input type="checkbox"/> Pool filling	<input checked="" type="checkbox"/> Gardening
Number of persons using water from your well?		2	

SECTION E: WATER SAMPLING		
Would you be interested in having a water sample collected?	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO

Please return this questionnaire in the included pre-addressed, stamped envelope.

WATER WELL SYSTEM SURVEY QUESTIONNAIRE

Our File No.: 017630

SECTION A: PROPERTY INFORMATION	
Address of Property:	44 GAMBLES DR
* Name of Property Owner:	[REDACTED]
* Telephone Number (Home):	[REDACTED]
Number of Occupants:	2
Number of Bedrooms:	4
How Long at Present Address:	35 YRS

*This information will NOT be included in any reporting

SECTION B: WELL CONSTRUCTION DETAILS	
Date or year well constructed:	OVER 47 APPROX (YRS)
Do you have a copy of the MOE Well Record?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
Well record number (if known):	
Type of well:	<input checked="" type="checkbox"/> Drilled <input type="checkbox"/> Dug
Well casing diameter (inches):	NOT SURE
Location of well (e.g. front yard, back yard, etc.):	FRONT YARD
Present well depth: 34 FT	Original well depth: YES <input type="checkbox"/> Same as present
Is the well accessible?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
Is it vented and how?	YES TOP

SECTION C: WATER SUPPLY	
Do you have a water treatment system?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
If yes, what kind of treatment?:	
Chlorination:	<input type="checkbox"/> YES <input type="checkbox"/> NO
Softener:	<input type="checkbox"/> YES <input type="checkbox"/> NO
Filter:	<input type="checkbox"/> YES <input type="checkbox"/> NO
Other:	

SECTION D: WATER QUALITY & QUANTITY	
Do you drink the water?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
If no, since when and why?	
Have you ever run out of water?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
Has your well ever been deepened or a new well constructed?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
If yes, why?	
Have you ever experienced any problems with your well?	NO
What was the cause of the problem?	<input type="checkbox"/> Drought <input type="checkbox"/> Pump Failure
<input type="checkbox"/> Increased Usage	<input type="checkbox"/> Interference <input type="checkbox"/> Other (Please Specify)

SECTION D CONTINUED: WATER QUALITY & QUANTITY			
Quality: Taste	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Odour	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Colour	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Hardness	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Iron	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Sulphur Smell	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Has your water quality been tested previously?	<input type="checkbox"/> YES		<input checked="" type="checkbox"/> NO
If yes, for what?	<input type="checkbox"/> Bacteriological	<input type="checkbox"/> Chemical analysis	<input type="checkbox"/> Other
Does your well supply enough water for your use?	<input checked="" type="checkbox"/> YES		<input type="checkbox"/> NO
If no, is this the case?:	<input type="checkbox"/> Some of the time	<input type="checkbox"/> Seasonally	<input type="checkbox"/> Other
Do you use your well for?:	<input checked="" type="checkbox"/> Lawn watering	<input checked="" type="checkbox"/> Pool filling	<input checked="" type="checkbox"/> Gardening
Number of persons using water from your well?	UP TO 5 PEOPLE		

SECTION E: WATER SAMPLING	
Would you be interested in having a water sample collected?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO

Please return this questionnaire in the included pre-addressed, stamped envelope.

WATER WELL SYSTEM SURVEY QUESTIONNAIRE

Our File No.: 017630

SECTION A: PROPERTY INFORMATION	
Address of Property:	39 GAMBLE DR., RICHMOND, ON.
* Name of Property Owner:	[REDACTED]
* Telephone Number (Home):	[REDACTED]
Number of Occupants:	2
Number of Bedrooms:	4
How Long at Present Address:	31

*This information will NOT be included in any reporting

SECTION B: WELL CONSTRUCTION DETAILS	
Date or year well constructed:	JULY 2, 1968
Do you have a copy of the MOE Well Record?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
Well record number (if known):	1509810
Type of well:	<input checked="" type="checkbox"/> Drilled <input type="checkbox"/> Dug
Well casing diameter (inches):	5"
Location of well (e.g. front yard, back yard, etc.):	FRONT YARD
Present well depth:	51' <input checked="" type="checkbox"/> Same as present
Original well depth:	51' <input type="checkbox"/> Different
Is the well accessible?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
Is it vented and how?	IN HOUSE

SECTION C: WATER SUPPLY	
Do you have a water treatment system?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
If yes, what kind of treatment?:	
Chlorination:	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
Softener:	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
Filter:	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
Other:	

SECTION D: WATER QUALITY & QUANTITY	
Do you drink the water?	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
If no, since when and why?	
Have you ever run out of water?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
Has your well ever been deepened or a new well constructed?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
If yes, why?	
Have you ever experienced any problems with your well?	No
What was the cause of the problem?	<input type="checkbox"/> Drought <input checked="" type="checkbox"/> Pump Failure
<input type="checkbox"/> Increased Usage	<input type="checkbox"/> Interference <input type="checkbox"/> Other (Please Specify)

SECTION D CONTINUED: WATER QUALITY & QUANTITY

Quality: Taste	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Odour	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Colour	<input checked="" type="checkbox"/> Excellent	<input type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Hardness	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Iron	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Sulphur Smell	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Acceptable	<input type="checkbox"/> Poor
Has your water quality been tested previously?	<input checked="" type="checkbox"/> YES		<input type="checkbox"/> NO
If yes, for what?	<input checked="" type="checkbox"/> Bacteriological	<input type="checkbox"/> Chemical analysis	<input type="checkbox"/> Other
Does your well supply enough water for your use?	<input checked="" type="checkbox"/> YES		<input type="checkbox"/> NO
If no, is this the case?:	<input type="checkbox"/> Some of the time	<input type="checkbox"/> Seasonally	<input type="checkbox"/> Other
Do you use your well for?:	<input checked="" type="checkbox"/> Lawn watering	<input checked="" type="checkbox"/> Pool filling	<input checked="" type="checkbox"/> Gardening
Number of persons using water from your well?	2		

SECTION E: WATER SAMPLING

Would you be interested in having a water sample collected?	<input checked="" type="checkbox"/> YES	<input type="checkbox"/> NO
---	---	-----------------------------

Please return this questionnaire in the included pre-addressed, stamped envelope.



WATER WELL SYSTEM SURVEY QUESTIONNAIRE

TYPE OF DWELLING: Residential Commercial Institutional Other

I. OWNER/OCCUPANT INFORMATION AND GENERAL QUESTIONS:

OWNER/OCCUPANT:

Name: [REDACTED] Telephone No. (business)
 Address: *2 Hemphill Street* Telephone No. (home) [REDACTED]
 Number of Bedrooms *3* Number of Occupants *2*

GENERAL QUESTIONS

How long have you owned/occupied this dwelling? *43 years*

Is well water used for drinking water supply? Yes No

If no, why not?.....

If no, how long has it been since well water was used for drinking?.....

If no, what is the origin of drinking water?.....

II. WATER WELL

A. WELL CONSTRUCTION DETAILS:

Date or year constructed *1968* Contractor

Well record number (if known)

Type of well: Drilled Dug Well diameter (inches) *8 inch (?)*

Location of well (e.g. front yard, back yard, etc.) *Front yard*

Present well depth *30 ft* Original well depth Same as present

Is the well accessible? Yes No *By digging*

Is well vented and how? ~~At the top~~ *Yes - 1 inch plastic hose runs parallel with supply line*

* Water Well Survey Questionnaire from Golder Associates Ltd.
 Hydrogeological Study, dated September 2017, Report No. 1418381-
 1000, Rev.2, provided to us by the City of Ottawa



B. WATER QUANTITY

Does your well supply enough water for your use? Yes No

If no, is this the case: all the time some of the time seasonally other

Use: Domestic: No Yes No. of persons using water from well

Lawn Watering: No Yes Other Uses

Have you ever experienced any problems with your well? *once*

What was the cause of the problem? Drought Pump Failure Plugging

Increased Usage Interference Other (Please Specify) *90° elbow of well head broke (rusted)*

Did you ever have your well deepened or cleaned, or a new well constructed? *No*

If so, why?

C. WATER QUALITY

Water Treatment equipment in use (if any) *softener*

Has your well recently been chlorinated and, if so, when? *No*

How would you describe quality of your water? Poor Good Excellent

Has your water quality previously been tested? No Yes

If yes, for what and how often? (bacteriological, chemical analyses, etc.)

Probably once a year

D. WATER SAMPLING INFORMATION

Would you be interested in having a water sample collected? No Yes

Please return this questionnaire in the included pre-addressed, stamped envelope.

* *Water Well Survey Questionnaire from Golder Associates Ltd. Hydrogeological Study, dated September 2017, Report No. 1418381-1000, Rev.2, provided to us by the City of Ottawa*

*** WATER WELL SYSTEM SURVEY QUESTIONNAIRE**

TYPE OF DWELLING: Residential Commercial Institutional Other

I. OWNER/OCCUPANT INFORMATION AND GENERAL QUESTIONS:

OWNER/OCCUPANT:

Name: [redacted] Telephone No. (business) [redacted]
Address: 331 P. Shea Rd Telephone No. (home) [redacted]
Number of Bedrooms 3 Number of Occupants 4

GENERAL QUESTIONS

How long have you owned/occupied this dwelling? 32 years.
Is well water used for drinking water supply? Yes No
If no, why not?
If no, how long has it been since well water was used for drinking?
If no, what is the origin of drinking water?

II. WATER WELL

A. WELL CONSTRUCTION DETAILS:

Date or year constructed Late 60's Contractor don't know
Well record number (if known)
Type of well: Drilled Dug Well diameter (inches) 6"
Location of well (e.g. front yard, back yard, etc.) Front yard
Present well depth 45 ft Original well depth Same as present
Is the well accessible? Yes No
Is well vented and how? yes 1" plastic pipe

* Water Well Survey Questionnaire from Golder Associates Ltd.
Hydrogeological Study, dated September 2017, Report No. 1418381-
1000, Rev.2, provided to us by the City of Ottawa



B. WATER QUANTITY

Does your well supply enough water for your use? Yes No

If no, is this is the case: all the time some of the time seasonally other

Use: Domestic: No Yes No. of persons using water from well4.....

 Lawn Watering: No Yes Other Uses

Have you ever experienced any problems with your well?No.....

What was the cause of the problem? Drought Pump Failure Plugging

Increased Usage Interference Other (Please Specify)

Did you ever have your well deepened or cleaned, or a new well constructed?No.....

If so, why?

C. WATER QUALITY

Water Treatment equipment in use (if any).....Softener.....

Has your well recently been chlorinated and, if so, when?No.....

How would you describe quality of your water? Poor Good Excellent

Has your water quality previously been tested? No Yes

If yes, for what and how often? (bacteriological, chemical analyses, etc.)

.....E Coli..... every sample of months.....

D. WATER SAMPLING INFORMATION

Would you be interested in having a water sample collected? No Yes

Please return this questionnaire in the included pre- addressed, stamped envelope.

* Water Well Survey Questionnaire from Golder Associates Ltd.
 Hydrogeological Study, dated September 2017, Report No. 1418381-
 1000, Rev.2, provided to us by the City of Ottawa

*** WATER WELL SYSTEM SURVEY QUESTIONNAIRE**

TYPE OF DWELLING: Residential Commercial Institutional Other

I. OWNER/OCCUPANT INFORMATION AND GENERAL QUESTIONS:

OWNER/OCCUPANT:

Name: [REDACTED] Telephone No. (business) [REDACTED]
 Address: 3316 SHEAR Telephone No. (home) [REDACTED]
 Number of Bedrooms 3 Number of Occupants 2

GENERAL QUESTIONS

How long have you owned/occupied this dwelling? 44 years

Is well water used for drinking water supply? Yes No

If no, why not?

If no, how long has it been since well water was used for drinking?

If no, what is the origin of drinking water?

II. WATER WELL

A. WELL CONSTRUCTION DETAILS:

Date or year constructed Approx 1967-68 Contractor N/A

Well record number (if known) unknown

Type of well: Drilled Dug Well diameter (inches) unknown

Location of well (e.g. front yard, back yard, etc.) FRONT YARD

Present well depth Approx 40ft Original well depth Same as present

Is the well accessible? Yes No

Is well vented and how? Vented thru basement wall

* Water Well Survey Questionnaire from Golder Associates Ltd.
 Hydrogeological Study, dated September 2017, Report No. 1418381-
 1000, Rev.2, provided to us by the City of Ottawa

B. WATER QUANTITY

Does your well supply enough water for your use? Yes No

If no, is this the case: all the time some of the time seasonally other

Use: Domestic: No Yes No. of persons using water from well3.....

Lawn Watering: No Yes Other Uses

Have you ever experienced any problems with your well?No.....

What was the cause of the problem? Drought Pump Failure Plugging

Increased Usage Interference Other (Please Specify)

Did you ever have your well deepened or cleaned, or a new well constructed?

If so, why?Foot Valve ~~replaced~~ replaced.....

C. WATER QUALITY

Water Treatment equipment in use (if any).....WATER SOFTENER.....

Has your well recently been chlorinated and, if so, when?No.....

How would you describe quality of your water? Poor Good Excellent

Has your water quality previously been tested? No Yes

If yes, for what and how often? (bacteriological, chemical analyses, etc.)

.....Bacteriological.....

D. WATER SAMPLING INFORMATION

Would you be interested in having a water sample collected? No Yes

Please return this questionnaire in the included pre- addressed, stamped envelope.

* Water Well Survey Questionnaire from Golder Associates Ltd. Hydrogeological Study, dated September 2017, Report No. 1418381-1000, Rev.2, provided to us by the City of Ottawa

*** WATER WELL SYSTEM SURVEY QUESTIONNAIRE**

TYPE OF DWELLING: Residential Commercial Institutional Other

I. OWNER/OCCUPANT INFORMATION AND GENERAL QUESTIONS:

OWNER/OCCUPANT:

Name: [redacted] Telephone No. (business)

Address: 3326 Shea Rd Telephone No. (home) [redacted]

Number of Bedrooms 3 Number of Occupants 3

GENERAL QUESTIONS

How long have you owned/occupied this dwelling? 1 1/2 years

Is well water used for drinking water supply? Yes No

If no, why not? It is drinkable, but we have a filter system

If no, how long has it been since well water was used for drinking?

If no, what is the origin of drinking water?

II. WATER WELL

A. WELL CONSTRUCTION DETAILS:

Date or year constructed..... Contractor

Well record number (if known)

Type of well: Drilled Dug Well diameter (inches)

Location of well (e.g. front yard, back yard, etc.) front yard

Present well depth Original well depth Same as present

Is the well accessible? Yes No

Is well vented and how? No

*** Water Well Survey Questionnaire from Golder Associates Ltd. Hydrogeological Study, dated September 2017, Report No. 1418381-1000, Rev.2, provided to us by the City of Ottawa**



B. WATER QUANTITY

Does your well supply enough water for your use? Yes No

If no, is this is the case: all the time some of the time seasonally other

Use: Domestic: No Yes No. of persons using water from well ...3.....

Lawn Watering: No Yes Other Uses

Have you ever experienced any problems with your well? ..no.....

What was the cause of the problem? Drought Pump Failure Plugging

Increased Usage Interference Other (Please Specify)

Did you ever have your well deepened or cleaned, or a new well constructed?

If so, why? ..N.A.....

C. WATER QUALITY

Water Treatment equipment in use (if any) ..Water Softener.....

Has your well recently been chlorinated and, if so, when? ..na.....

How would you describe quality of your water? Poor Good Excellent

Has your water quality previously been tested? No Yes

If yes, for what and how often? (bacteriological, chemical analyses, etc.) ..When...we...bought the house, test came back good.....

D. WATER SAMPLING INFORMATION

Would you be interested in having a water sample collected? No Yes

Please return this questionnaire in the included pre- addressed, stamped envelope.

* Water Well Survey Questionnaire from Golder Associates Ltd. Hydrogeological Study, dated September 2017, Report No. 1418381-1000, Rev.2, provided to us by the City of Ottawa



APPENDIX C

RESULTS OF LABORATORY TESTING OF TEST WELL WATER SAMPLES

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802379
Date Submitted: 2018-02-17
Date Reported: 2018-02-20
Project: 017630
COC #: 192756

Page 1 of 2

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Dragana Dzeletovic, Team Leader

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802379
 Date Submitted: 2018-02-17
 Date Reported: 2018-02-20
 Project: 017630
 COC #: 192756

Lab I.D. 1345671
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-16
 Sample I.D. TWI 3hr

Group	Analyte	MRL	Units	Guideline	
Others	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Heterotrophic Plate Count	0	ct/1mL		202
	Total Coliforms	0	ct/100mL	MAC 0	0

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802377
Date Submitted: 2018-02-17
Date Reported: 2018-02-27
Project: 017630
COC #: 192756

Page 1 of 6

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins(Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802377
 Date Submitted: 2018-02-17
 Date Reported: 2018-02-27
 Project: 017630
 COC #: 192756

Lab I.D. 1345669
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-16
 Sample I.D. TWI 3hr

Group	Analyte	MRL	Units	Guideline	
Calculations	Hardness as CaCO3	1	mg/L	OG 100	113*
	Ion Balance	0.01			0.91
	TDS (COND - CALC)	1	mg/L	AO 500	555*
General Chemistry	Alkalinity as CaCO3	10	mg/L	OG 500	241
	Cl	1	mg/L	AO 250	101
	Colour	2	TCU	AO 5	4
	Conductivity	5	uS/cm		854
	F	0.10	mg/L	MAC 1.5	1.20
	N-NO2	0.10	mg/L	MAC 1.0	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10
	pH	1.00		6.5-8.5	8.47
	SO4	1	mg/L	AO 500	36
	Turbidity	0.1	NTU	AO 5.0	1.1
	Metals	Ca	1	mg/L	
Fe		0.03	mg/L	AO 0.3	0.13
K		1	mg/L		8
Mg		1	mg/L		14
Mn		0.01	mg/L	AO 0.05	<0.01
Na		2	mg/L	AO 200	120
Nutrients	Total Kjeldahl Nitrogen	0.1	mg/L		0.5
Phenols	Phenols	0.001	mg/L		<0.001
Subcontract	DOC	0.5	mg/L	AO 5	1.3
	N-NH3	0.01	mg/L		0.49
	S2-	0.02	mg/L	AO 0.05	<0.02
	Tannin & Lignin	0.1	mg/L		<0.1

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802377
 Date Submitted: 2018-02-17
 Date Reported: 2018-02-27
 Project: 017630
 COC #: 192756

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 340887 Analysis/Extraction Date 2018-02-20 Analyst C_F			
Method C SM2130B			
Turbidity	0.1 NTU	101	70-130
Run No 340888 Analysis/Extraction Date 2018-02-21 Analyst H_F			
Method SM 4110			
Chloride	<1 mg/L	110	90-110
SO4	<1 mg/L	111	90-110
Run No 340893 Analysis/Extraction Date 2018-02-20 Analyst SKH			
Method EPA 200.8			
Iron	<0.03 mg/L	96	91-109
Manganese	<0.01 mg/L	100	92.9-107
Run No 340924 Analysis/Extraction Date 2018-02-23 Analyst R_E			
Method C SM2120C			
Colour	<2 TCU	98	90-110
Run No 340947 Analysis/Extraction Date 2018-02-21 Analyst H_F			
Method M SM3120B-3500C			
Calcium	<1 mg/L	92	90-110
Potassium	<1 mg/L	107	87-113

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802377
 Date Submitted: 2018-02-17
 Date Reported: 2018-02-27
 Project: 017630
 COC #: 192756

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Magnesium	<1 mg/L	92	76-124
Sodium	<2 mg/L	104	82-118
Run No 341060 Analysis/Extraction Date 2018-02-22 Analyst R_E			
Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	100	80-120
N-NO3	<0.10 mg/L	93	80-120
Run No 341062 Analysis/Extraction Date 2018-02-23 Analyst H_D			
Method SM 2320B			
Alkalinity (CaCO3)	<10 mg/L	102	90-110
Method SM 2510B			
Conductivity	<5 uS/cm	102	90-110
Method SM 4500-H+B			
pH		145	90-110
Run No 341108 Analysis/Extraction Date 2018-02-23 Analyst H_D			
Method SM 4500-FC			
F	<0.10 mg/L	101	90-110
Run No 341152 Analysis/Extraction Date 2018-02-23 Analyst AET			
Method SUBCONTRACT P-INORG			
DOC	<0.5 mg/L	90	

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802377
 Date Submitted: 2018-02-17
 Date Reported: 2018-02-27
 Project: 017630
 COC #: 192756

QC Summary

Analyte	Blank	QC % Rec	QC Limits
N-NH3	<0.01 mg/L	104	
Phenols	<0.001 mg/L	92	69-132
S2-	<0.02 mg/L	104	
Tannin & Lignin	<0.1 mg/L	90	
Total Kjeldahl Nitrogen	<0.1 mg/L	91	81-126
Run No 341162 Analysis/Extraction Date 2018-02-26 Analyst AET			
Method C Ion Balance			
Ion Balance			
Method C SM2340B			
Hardness as CaCO3			
Method C SM2540			
TDS (COND - CALC)			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802377
Date Submitted: 2018-02-17
Date Reported: 2018-02-27
Project: 017630
COC #: 192756

Sample Comment Summary

Sample ID: 1345669 TWI 3hr Holding time for turbidity analysis was exceeded.
--

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802380
Date Submitted: 2018-02-17
Date Reported: 2018-02-20
Project: 017630
COC #: 192755

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Dragana Dzeletovic, Team Leader

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802380
 Date Submitted: 2018-02-17
 Date Reported: 2018-02-20
 Project: 017630
 COC #: 192755

Lab I.D. 1345672
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-16
 Sample I.D. TWI 6hr

Group	Analyte	MRL	Units	Guideline	
Others	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Heterotrophic Plate Count	0	ct/1mL		361
	Total Coliforms	0	ct/100mL	MAC 0	4*

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802378
Date Submitted: 2018-02-17
Date Reported: 2018-02-27
Project: 017630
COC #: 192755

Page 1 of 6

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins(Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802378
 Date Submitted: 2018-02-17
 Date Reported: 2018-02-27
 Project: 017630
 COC #: 192755

Lab I.D. 1345670
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-16
 Sample I.D. Tw1 6hr

Group	Analyte	MRL	Units	Guideline	
Calculations	Hardness as CaCO3	1	mg/L	OG 100	113*
	Ion Balance	0.01			0.93
	TDS (COND - CALC)	1	mg/L	AO 500	552*
General Chemistry	Alkalinity as CaCO3	10	mg/L	OG 500	228
	Cl	1	mg/L	AO 250	104
	Colour	2	TCU	AO 5	3
	Conductivity	5	uS/cm		849
	F	0.10	mg/L	MAC 1.5	1.22
	N-NO2	0.10	mg/L	MAC 1.0	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10
	pH	1.00		6.5-8.5	8.45
	SO4	1	mg/L	AO 500	36
	Turbidity	0.1	NTU	AO 5.0	1.2
	Metals	Ca	1	mg/L	
Fe		0.03	mg/L	AO 0.3	0.11
K		1	mg/L		8
Mg		1	mg/L		14
Mn		0.01	mg/L	AO 0.05	<0.01
Na		2	mg/L	AO 200	120
Nutrients	Total Kjeldahl Nitrogen	0.1	mg/L		0.5
Phenols	Phenols	0.001	mg/L		<0.001
Subcontract	DOC	0.5	mg/L	AO 5	<0.5
	N-NH3	0.01	mg/L		0.49
	S2-	0.02	mg/L	AO 0.05	<0.02
	Tannin & Lignin	0.1	mg/L		<0.1

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802378
 Date Submitted: 2018-02-17
 Date Reported: 2018-02-27
 Project: 017630
 COC #: 192755

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 340887 Analysis/Extraction Date 2018-02-20 Analyst C_F			
Method C SM2130B			
Turbidity	0.1 NTU	101	70-130
Run No 340888 Analysis/Extraction Date 2018-02-21 Analyst H_F			
Method SM 4110			
Chloride	<1 mg/L	110	90-110
SO4	<1 mg/L	111	90-110
Run No 340893 Analysis/Extraction Date 2018-02-20 Analyst SKH			
Method EPA 200.8			
Iron	<0.03 mg/L	96	91-109
Manganese	<0.01 mg/L	100	92.9-107
Run No 340924 Analysis/Extraction Date 2018-02-23 Analyst R_E			
Method C SM2120C			
Colour	<2 TCU	98	90-110
Run No 340947 Analysis/Extraction Date 2018-02-21 Analyst H_F			
Method M SM3120B-3500C			
Calcium	<1 mg/L	92	90-110
Potassium	<1 mg/L	107	87-113

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802378
 Date Submitted: 2018-02-17
 Date Reported: 2018-02-27
 Project: 017630
 COC #: 192755

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Magnesium	<1 mg/L	92	76-124
Sodium	<2 mg/L	104	82-118
Run No 341060 Analysis/Extraction Date 2018-02-22 Analyst R_E			
Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	100	80-120
N-NO3	<0.10 mg/L	93	80-120
Run No 341062 Analysis/Extraction Date 2018-02-23 Analyst H_D			
Method SM 2320B			
Alkalinity (CaCO3)	<10 mg/L	102	90-110
Method SM 2510B			
Conductivity	<5 uS/cm	102	90-110
Method SM 4500-H+B			
pH		145	90-110
Run No 341108 Analysis/Extraction Date 2018-02-23 Analyst H_D			
Method SM 4500-FC			
F	<0.10 mg/L	101	90-110
Run No 341153 Analysis/Extraction Date 2018-02-23 Analyst AET			
Method SUBCONTRACT P-INORG			
DOC	<0.5 mg/L	90	

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802378
 Date Submitted: 2018-02-17
 Date Reported: 2018-02-27
 Project: 017630
 COC #: 192755

QC Summary

Analyte	Blank	QC % Rec	QC Limits
N-NH3	<0.01 mg/L	104	
Phenols	<0.001 mg/L	92	69-132
S2-	<0.02 mg/L	104	
Tannin & Lignin	<0.1 mg/L	90	
Total Kjeldahl Nitrogen	<0.1 mg/L	91	81-126
Run No 341162 Analysis/Extraction Date 2018-02-26 Analyst AET			
Method C Ion Balance			
Ion Balance			
Method C SM2340B			
Hardness as CaCO3			
Method C SM2540			
TDS (COND - CALC)			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802378
Date Submitted: 2018-02-17
Date Reported: 2018-02-27
Project: 017630
COC #: 192755

Sample Comment Summary

Sample ID: 1345670 Tw1 6hr Holding time for turbidity analysis was exceeded.
--

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802616
Date Submitted: 2018-02-23
Date Reported: 2018-02-25
Project: 017630
COC #: 192915

Page 1 of 2

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Dragana Dzeletovic, Team Leader

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802616
 Date Submitted: 2018-02-23
 Date Reported: 2018-02-25
 Project: 017630
 COC #: 192915

Lab I.D.	1346273
Sample Matrix	Water
Sample Type	-
Sampling Date	2018-02-22
Sample I.D.	TW2 3hr

Group	Analyte	MRL	Units	Guideline	
Microbiology	Heterotrophic Plate Count	0	ct/1mL		4
Others	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Total Coliforms	0	ct/100mL	MAC 0	0

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802607
Date Submitted: 2018-02-23
Date Reported: 2018-03-02
Project: 017630
COC #: 192915

Page 1 of 5

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins(Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802607
 Date Submitted: 2018-02-23
 Date Reported: 2018-03-02
 Project: 017630
 COC #: 192915

Lab I.D. 1346241
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-22
 Sample I.D. TW2 3hr

Group	Analyte	MRL	Units	Guideline	
Calculations	Hardness as CaCO3	1	mg/L	OG 100	117*
	Ion Balance	0.01			0.94
	TDS (COND - CALC)	1	mg/L	AO 500	491
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	243
	Cl	1	mg/L	AO 250	80
	Colour	2	TCU	AO 5	20*
	Conductivity	5	uS/cm		756
	F	0.10	mg/L	MAC 1.5	1.20
	N-NO2	0.10	mg/L	MAC 1.0	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10
	pH	1.00		6.5-8.5	8.24
	SO4	1	mg/L	AO 500	33
	Turbidity	0.1	NTU	AO 5.0	9.1*
	Metals	Ca	1	mg/L	
Fe		0.03	mg/L	AO 0.3	0.41*
K		1	mg/L		7
Mg		1	mg/L		15
Mn		0.01	mg/L	AO 0.05	0.05
Na		2	mg/L	AO 200	112
Nutrients	Total Kjeldahl Nitrogen	0.1	mg/L		0.4
Phenols	Phenols	0.001	mg/L		<0.001
Subcontract	DOC	0.5	mg/L	AO 5	1.5
	N-NH3	0.01	mg/L		0.34
	S2-	0.02	mg/L	AO 0.05	<0.02
	Tannin & Lignin	0.1	mg/L		0.1

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802607
 Date Submitted: 2018-02-23
 Date Reported: 2018-03-02
 Project: 017630
 COC #: 192915

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 341078 Analysis/Extraction Date 2018-02-23 Analyst SKH			
Method EPA 200.8			
Manganese	<0.01 mg/L	100	92.9-107
Run No 341092 Analysis/Extraction Date 2018-02-23 Analyst C_F			
Method C SM2130B			
Turbidity	<0.1 NTU	99	70-130
Run No 341096 Analysis/Extraction Date 2018-02-26 Analyst R_E			
Method C SM2120C			
Colour	<2 TCU	90	90-110
Run No 341108 Analysis/Extraction Date 2018-02-23 Analyst H_D			
Method SM 2320B			
Alkalinity (CaCO3)	<5 mg/L	101	90-110
Method SM 2510B			
Conductivity	<5 uS/cm	100	90-110
Method SM 4500-FC			
F	<0.10 mg/L	101	90-110
Method SM 4500-H+B			
pH		100	90-110

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802607
 Date Submitted: 2018-02-23
 Date Reported: 2018-03-02
 Project: 017630
 COC #: 192915

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 341175 Analysis/Extraction Date 2018-02-26 Analyst SKH			
Method EPA 200.8			
Iron	<0.03 mg/L	95	91-109
Run No 341182 Analysis/Extraction Date 2018-02-27 Analyst H_F			
Method M SM3120B-3500C			
Calcium	<1 mg/L	97	90-110
Potassium	<1 mg/L	102	87-113
Magnesium	<1 mg/L	96	76-124
Sodium	<2 mg/L	99	82-118
Run No 341251 Analysis/Extraction Date 2018-02-28 Analyst H_F			
Method SM 4110			
Chloride	<1 mg/L	104	90-110
SO4	<1 mg/L	105	90-110
Run No 341353 Analysis/Extraction Date 2018-03-01 Analyst AET			
Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	100	80-120
N-NO3	<0.10 mg/L	90	80-120
Run No 341372 Analysis/Extraction Date 2018-03-01 Analyst AET			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802607
 Date Submitted: 2018-02-23
 Date Reported: 2018-03-02
 Project: 017630
 COC #: 192915

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Method C Ion Balance			
Ion Balance			
Method C SM2340B			
Hardness as CaCO3			
Method C SM2540			
TDS (COND - CALC)			
Run No 341392	Analysis/Extraction Date 2018-03-01	Analyst AET	
Method SUBCONTRACT P-INORG			
DOC	<0.5 mg/L	95	
N-NH3	<0.01 mg/L	108	
Phenols	<0.001 mg/L	84	69-132
S2-	<0.02 mg/L	102	
Tannin & Lignin	<0.1 mg/L	100	
Total Kjeldahl Nitrogen	<0.1 mg/L	97	81-126

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802618
Date Submitted: 2018-02-23
Date Reported: 2018-02-25
Project: 017630
COC #: 192916

Page 1 of 2

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Dragana Dzeletovic, Team Leader

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802618
 Date Submitted: 2018-02-23
 Date Reported: 2018-02-25
 Project: 017630
 COC #: 192916

Lab I.D.	1346275
Sample Matrix	Water
Sample Type	-
Sampling Date	2018-02-22
Sample I.D.	TW2 6hr

Group	Analyte	MRL	Units	Guideline	
Microbiology	Heterotrophic Plate Count	0	ct/1mL		1
Others	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Total Coliforms	0	ct/100mL	MAC 0	0

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802609
Date Submitted: 2018-02-23
Date Reported: 2018-03-02
Project: 017630
COC #: 192916

Page 1 of 5

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins(Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802609
 Date Submitted: 2018-02-23
 Date Reported: 2018-03-02
 Project: 017630
 COC #: 192916

Lab I.D.	1346242
Sample Matrix	Water
Sample Type	
Sampling Date	2018-02-22
Sample I.D.	TW2 6hr

Group	Analyte	MRL	Units	Guideline	
Calculations	Hardness as CaCO3	1	mg/L	OG 100	117*
	Ion Balance	0.01			0.99
	TDS (COND - CALC)	1	mg/L	AO 500	493
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	232
	Cl	1	mg/L	AO 250	80
	Colour	2	TCU	AO 5	14*
	Conductivity	5	uS/cm		759
	F	0.10	mg/L	MAC 1.5	1.18
	N-NO2	0.10	mg/L	MAC 1.0	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10
	pH	1.00		6.5-8.5	8.22
	SO4	1	mg/L	AO 500	32
	Turbidity	0.1	NTU	AO 5.0	10.6*
	Metals	Ca	1	mg/L	
Fe		0.03	mg/L	AO 0.3	0.39*
K		1	mg/L		7
Mg		1	mg/L		15
Mn		0.01	mg/L	AO 0.05	0.04
Na		2	mg/L	AO 200	116
Nutrients	Total Kjeldahl Nitrogen	0.1	mg/L		0.4
Phenols	Phenols	0.001	mg/L		<0.001
Subcontract	DOC	0.5	mg/L	AO 5	<0.5
	N-NH3	0.01	mg/L		0.35
	S2-	0.02	mg/L	AO 0.05	<0.02
	Tannin & Lignin	0.1	mg/L		0.1

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802609
 Date Submitted: 2018-02-23
 Date Reported: 2018-03-02
 Project: 017630
 COC #: 192916

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 341078 Analysis/Extraction Date 2018-02-23 Analyst SKH			
Method EPA 200.8			
Iron	<0.03 mg/L	94	91-109
Manganese	<0.01 mg/L	100	92.9-107
Run No 341092 Analysis/Extraction Date 2018-02-23 Analyst C_F			
Method C SM2130B			
Turbidity	<0.1 NTU	99	70-130
Run No 341096 Analysis/Extraction Date 2018-02-26 Analyst R_E			
Method C SM2120C			
Colour	<2 TCU	90	90-110
Run No 341108 Analysis/Extraction Date 2018-02-23 Analyst H_D			
Method SM 2320B			
Alkalinity (CaCO3)	<5 mg/L	101	90-110
Method SM 2510B			
Conductivity	<5 uS/cm	100	90-110
Method SM 4500-FC			
F	<0.10 mg/L	101	90-110
Method SM 4500-H+B			
pH		100	90-110

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802609
 Date Submitted: 2018-02-23
 Date Reported: 2018-03-02
 Project: 017630
 COC #: 192916

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 341182 Analysis/Extraction Date 2018-02-27 Analyst H_F			
Method M SM3120B-3500C			
Calcium	<1 mg/L	97	90-110
Potassium	<1 mg/L	102	87-113
Magnesium	<1 mg/L	96	76-124
Sodium	<2 mg/L	99	82-118
Run No 341251 Analysis/Extraction Date 2018-02-28 Analyst H_F			
Method SM 4110			
Chloride	<1 mg/L	104	90-110
SO4	<1 mg/L	105	90-110
Run No 341353 Analysis/Extraction Date 2018-03-01 Analyst AET			
Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	100	80-120
N-NO3	<0.10 mg/L	90	80-120
Run No 341372 Analysis/Extraction Date 2018-03-01 Analyst AET			
Method C Ion Balance			
Ion Balance			
Method C SM2340B			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802609
 Date Submitted: 2018-02-23
 Date Reported: 2018-03-02
 Project: 017630
 COC #: 192916

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Hardness as CaCO3			
Method C SM2540			
TDS (COND - CALC)			
Run No 341389 Analysis/Extraction Date 2018-03-01 Analyst AET			
Method SUBCONTRACT P-INORG			
DOC	<0.5 mg/L	102	
N-NH3	<0.01 mg/L	108	
Phenols	<0.001 mg/L	84	69-132
S2-	<0.02 mg/L	102	
Tannin & Lignin	<0.1 mg/L	100	
Total Kjeldahl Nitrogen	<0.1 mg/L	97	81-126

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802939
Date Submitted: 2018-03-01
Date Reported: 2018-03-04
Project: 017630
COC #: 192757

Page 1 of 2

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Dragana Dzeletovic, Team Leader

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802939
 Date Submitted: 2018-03-01
 Date Reported: 2018-03-04
 Project: 017630
 COC #: 192757

Lab I.D. 1347081
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-28
 Sample I.D. TW3 3Hr

Group	Analyte	MRL	Units	Guideline	
Microbiology	Heterotrophic Plate Count	0	ct/1mL		24
Others	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Total Coliforms	0	ct/100mL	MAC 0	0

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802929
Date Submitted: 2018-03-01
Date Reported: 2018-03-07
Project: 017630
COC #: 192757

Page 1 of 5

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins(Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802929
 Date Submitted: 2018-03-01
 Date Reported: 2018-03-07
 Project: 017630
 COC #: 192757

Lab I.D. 1347060
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-28
 Sample I.D. TW3 3Hr

Group	Analyte	MRL	Units	Guideline	
Calculations	Hardness as CaCO3	1	mg/L	OG 100	120*
	Ion Balance	0.01			0.93
	TDS (COND - CALC)	1	mg/L	AO 500	530*
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	234
	Cl	1	mg/L	AO 250	100
	Colour	2	TCU	AO 5	<2
	Conductivity	5	uS/cm		815
	F	0.10	mg/L	MAC 1.5	0.95
	N-NO2	0.10	mg/L	MAC 1.0	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	0.24
	pH	1.00		6.5-8.5	8.24
	SO4	1	mg/L	AO 500	45
	Turbidity	0.1	NTU	AO 5.0	2.5
	Metals	Ca	1	mg/L	
Fe		0.03	mg/L	AO 0.3	0.12
K		1	mg/L		7
Mg		1	mg/L		14
Mn		0.01	mg/L	AO 0.05	<0.01
Na		2	mg/L	AO 200	123
Nutrients	Total Kjeldahl Nitrogen	0.1	mg/L		0.2
Phenols	Phenols	0.001	mg/L		<0.001
Subcontract	DOC	0.5	mg/L	AO 5	<0.5
	N-NH3	0.01	mg/L		0.22
	S2-	0.02	mg/L	AO 0.05	<0.02
	Tannin & Lignin	0.1	mg/L		<0.1

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802929
 Date Submitted: 2018-03-01
 Date Reported: 2018-03-07
 Project: 017630
 COC #: 192757

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 341345 Analysis/Extraction Date 2018-03-01 Analyst C_F			
Method C SM2130B			
Turbidity	<0.1 NTU	99	70-130
Run No 341355 Analysis/Extraction Date 2018-03-01 Analyst AET			
Method C SM2120C			
Colour	<2 TCU	105	90-110
Run No 341401 Analysis/Extraction Date 2018-03-02 Analyst H_F			
Method M SM3120B-3500C			
Calcium	<1 mg/L	99	90-110
Potassium	<1 mg/L	107	87-113
Magnesium	<1 mg/L	97	76-124
Sodium	<2 mg/L	97	82-118
Run No 341414 Analysis/Extraction Date 2018-03-01 Analyst AET			
Method EPA 200.8			
Iron	<0.03 mg/L	97	91-109
Manganese	<0.01 mg/L	103	92.9-107
Run No 341456 Analysis/Extraction Date 2018-03-05 Analyst H_F			
Method SM 4110			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802929
 Date Submitted: 2018-03-01
 Date Reported: 2018-03-07
 Project: 017630
 COC #: 192757

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Chloride	<1 mg/L	102	90-110
SO4	<1 mg/L	105	90-110
Run No 341457 Analysis/Extraction Date 2018-03-02 Analyst AET			
Method SM 2320B			
Alkalinity (CaCO3)	<5 mg/L	102	90-110
Method SM 2510B			
Conductivity	<5 uS/cm	101	90-110
Method SM 4500-FC			
F	<0.10 mg/L	103	90-110
Method SM 4500-H+B			
pH		100	90-110
Run No 341496 Analysis/Extraction Date 2018-03-05 Analyst AET			
Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	100	80-120
N-NO3	<0.10 mg/L	87	80-120
Run No 341647 Analysis/Extraction Date 2018-03-06 Analyst SDC			
Method SUBCONTRACT P-INORG			
DOC	<0.5 mg/L	100	
N-NH3	<0.01 mg/L	101	

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802929
 Date Submitted: 2018-03-01
 Date Reported: 2018-03-07
 Project: 017630
 COC #: 192757

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Phenols	<0.001 mg/L	108	69-132
S2-	<0.02 mg/L	104	
Tannin & Lignin			
Total Kjeldahl Nitrogen	<0.1 mg/L	94	81-126
Run No 341656 Analysis/Extraction Date 2018-03-07 Analyst AET			
Method C Ion Balance			
Ion Balance			
Method C SM2340B			
Hardness as CaCO3			
Method C SM2540			
TDS (COND - CALC)			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802938
Date Submitted: 2018-03-01
Date Reported: 2018-03-04
Project: 017630
COC #: 192917

Page 1 of 2

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Dragana Dzeletovic, Team Leader

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802938
 Date Submitted: 2018-03-01
 Date Reported: 2018-03-04
 Project: 017630
 COC #: 192917

Lab I.D. 1347080
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-28
 Sample I.D. TW3 6Hr

Group	Analyte	MRL	Units	Guideline	
Microbiology	Heterotrophic Plate Count	0	ct/1mL		18
Others	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Total Coliforms	0	ct/100mL	MAC 0	0

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802930
Date Submitted: 2018-03-01
Date Reported: 2018-03-07
Project: 017630
COC #: 192917

Page 1 of 5

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins(Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802930
 Date Submitted: 2018-03-01
 Date Reported: 2018-03-07
 Project: 017630
 COC #: 192917

Lab I.D. 1347061
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-28
 Sample I.D. TW 3 6Hr

Group	Analyte	MRL	Units	Guideline	
Calculations	Hardness as CaCO3	1	mg/L	OG 100	123*
	Ion Balance	0.01			0.97
	TDS (COND - CALC)	1	mg/L	AO 500	536*
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	223
	Cl	1	mg/L	AO 250	100
	Colour	2	TCU	AO 5	3
	Conductivity	5	uS/cm		825
	F	0.10	mg/L	MAC 1.5	1.05
	N-NO2	0.10	mg/L	MAC 1.0	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	0.15
	pH	1.00		6.5-8.5	8.25
	SO4	1	mg/L	AO 500	41
	Turbidity	0.1	NTU	AO 5.0	2.3
	Metals	Ca	1	mg/L	
Fe		0.03	mg/L	AO 0.3	0.09
K		1	mg/L		7
Mg		1	mg/L		14
Mn		0.01	mg/L	AO 0.05	<0.01
Na		2	mg/L	AO 200	123
Nutrients	Total Kjeldahl Nitrogen	0.1	mg/L		0.3
Phenols	Phenols	0.001	mg/L		<0.001
Subcontract	DOC	0.5	mg/L	AO 5	<0.5
	N-NH3	0.01	mg/L		0.23
	S2-	0.02	mg/L	AO 0.05	<0.02
	Tannin & Lignin	0.1	mg/L		<0.1

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802930
 Date Submitted: 2018-03-01
 Date Reported: 2018-03-07
 Project: 017630
 COC #: 192917

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 341345 Analysis/Extraction Date 2018-03-01 Analyst C_F			
Method C SM2130B			
Turbidity	<0.1 NTU	99	70-130
Run No 341355 Analysis/Extraction Date 2018-03-01 Analyst AET			
Method C SM2120C			
Colour	<2 TCU	105	90-110
Run No 341401 Analysis/Extraction Date 2018-03-02 Analyst H_F			
Method M SM3120B-3500C			
Calcium	<1 mg/L	99	90-110
Potassium	<1 mg/L	107	87-113
Magnesium	<1 mg/L	97	76-124
Sodium	<2 mg/L	97	82-118
Run No 341414 Analysis/Extraction Date 2018-03-01 Analyst AET			
Method EPA 200.8			
Iron	<0.03 mg/L	97	91-109
Manganese	<0.01 mg/L	103	92.9-107
Run No 341456 Analysis/Extraction Date 2018-03-05 Analyst H_F			
Method SM 4110			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802930
 Date Submitted: 2018-03-01
 Date Reported: 2018-03-07
 Project: 017630
 COC #: 192917

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Chloride	<1 mg/L	102	90-110
SO4	<1 mg/L	105	90-110
Run No 341457 Analysis/Extraction Date 2018-03-02 Analyst AET			
Method SM 2320B			
Alkalinity (CaCO3)	<5 mg/L	102	90-110
Method SM 2510B			
Conductivity	<5 uS/cm	101	90-110
Method SM 4500-FC			
F	<0.10 mg/L	103	90-110
Method SM 4500-H+B			
pH		100	90-110
Run No 341496 Analysis/Extraction Date 2018-03-05 Analyst AET			
Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	103	80-120
N-NO3	<0.10 mg/L	93	80-120
Run No 341636 Analysis/Extraction Date 2018-03-07 Analyst AET			
Method C Ion Balance			
Ion Balance			
Method C SM2340B			

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802930
 Date Submitted: 2018-03-01
 Date Reported: 2018-03-07
 Project: 017630
 COC #: 192917

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Hardness as CaCO3			
Method C SM2540			
TDS (COND - CALC)			
Run No 341648 Analysis/Extraction Date 2018-03-06 Analyst SDC			
Method SUBCONTRACT P-INORG			
DOC	<0.5 mg/L	100	
N-NH3	<0.01 mg/L	101	
Phenols	<0.001 mg/L	108	69-132
S2-	<0.02 mg/L	104	
Tannin & Lignin			
Total Kjeldahl Nitrogen	<0.1 mg/L	94	81-126

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1803745
Date Submitted: 2018-03-15
Date Reported: 2018-03-19
Project: 017630
COC #: 192918

Page 1 of 2

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Krista Quantrill, Microbiology Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1803745
 Date Submitted: 2018-03-15
 Date Reported: 2018-03-19
 Project: 017630
 COC #: 192918

Lab I.D.	1349267
Sample Matrix	Water
Sample Type	
Sampling Date	2018-03-15
Sample I.D.	TW1

Group	Analyte	MRL	Units	Guideline	
Others	Total Coliforms	0	ct/100mL	MAC 0	0

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1803746
Date Submitted: 2018-03-15
Date Reported: 2018-03-19
Project: 017630
COC #: 194176

Page 1 of 3

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins(Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1803746
 Date Submitted: 2018-03-15
 Date Reported: 2018-03-19
 Project: 017630
 COC #: 194176

Lab I.D.	1349268
Sample Matrix	Water
Sample Type	
Sampling Date	2018-03-15
Sample I.D.	TW2

Group	Analyte	MRL	Units	Guideline	
General Chemistry	Colour	2	TCU	AO 5	3

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1803746
 Date Submitted: 2018-03-15
 Date Reported: 2018-03-19
 Project: 017630
 COC #: 194176

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 342108 Analysis/Extraction Date 2018-03-16 Analyst A_V			
Method C SM2120C			
Colour	<2 TCU	75	90-110

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



APPENDIX D

RESULTS OF LABORATORY TESTING OF NEIGHBOURING WELL WATER SAMPLES

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802063
Date Submitted: 2018-02-13
Date Reported: 2018-02-15
Project: 017630
COC #: 190259

Page 1 of 2

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Krista Quantrill, Microbiology Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802063
 Date Submitted: 2018-02-13
 Date Reported: 2018-02-15
 Project: 017630
 COC #: 190259

Lab I.D. 1344809
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-12
 Sample I.D. 44 Gamble Dr.

Group	Analyte	MRL	Units	Guideline	
Microbiology	Heterotrophic Plate Count	0	ct/1mL		0
Others	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Total Coliforms	0	ct/100mL	MAC 0	0

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1802076
Date Submitted: 2018-02-13
Date Reported: 2018-02-21
Project: 017630
COC #: 190259

Page 1 of 5

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Addrine Thomas, Inorganics Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins(Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802076
 Date Submitted: 2018-02-13
 Date Reported: 2018-02-21
 Project: 017630
 COC #: 190259

Lab I.D. 1344862
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-02-12
 Sample I.D. 44 Gamble Dr

Group	Analyte	MRL	Units	Guideline	
Calculations	Hardness as CaCO3	1	mg/L	OG 100	117*
	Ion Balance	0.01			1.01
	TDS (COND - CALC)	1	mg/L	AO 500	515*
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG 500	232
	Cl	1	mg/L	AO 250	91
	Colour	2	TCU	AO 5	6*
	Conductivity	5	uS/cm		792
	F	0.10	mg/L	MAC 1.5	1.15
	N-NO2	0.10	mg/L	MAC 1.0	<0.10
	N-NO3	0.10	mg/L	MAC 10.0	<0.10
	pH	1.00		6.5-8.5	8.19
	SO4	1	mg/L	AO 500	30
	Turbidity	0.1	NTU	AO 5.0	0.4
	Metals	Ca	1	mg/L	
Fe		0.03	mg/L	AO 0.3	0.14
K		1	mg/L		7
Mg		1	mg/L		17
Mn		0.01	mg/L	AO 0.05	<0.01
Na		2	mg/L	AO 200	124
Nutrients	Total Kjeldahl Nitrogen	0.1	mg/L		0.6
Phenols	Phenols	0.001	mg/L		<0.001
Subcontract	DOC	0.5	mg/L	AO 5	1.4
	N-NH3	0.02	mg/L		0.51
	S2-	0.02	mg/L	AO 0.05	0.06*
	Tannin & Lignin	0.1	mg/L		0.2

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Certificate of Analysis

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802076
 Date Submitted: 2018-02-13
 Date Reported: 2018-02-21
 Project: 017630
 COC #: 190259

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 340672 Analysis/Extraction Date 2000-00-18 Analyst C_F			
Method C SM2130B			
Turbidity	<0.1 NTU	100	70-130
Run No 340694 Analysis/Extraction Date 2018-02-14 Analyst H_F			
Method SM 4110			
Chloride	<1 mg/L	110	90-110
SO4	<1 mg/L	111	90-110
Run No 340696 Analysis/Extraction Date 2018-02-13 Analyst R_E			
Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	103	80-120
N-NO3	<0.10 mg/L	87	80-120
Run No 340745 Analysis/Extraction Date 2018-02-14 Analyst SKH			
Method EPA 200.8			
Iron	<0.03 mg/L	93	91-109
Manganese	<0.01 mg/L	97	92.9-107
Run No 340748 Analysis/Extraction Date 2018-02-15 Analyst H_F			
Method M SM3120B-3500C			
Calcium	<1 mg/L	97	90-110

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802076
 Date Submitted: 2018-02-13
 Date Reported: 2018-02-21
 Project: 017630
 COC #: 190259

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Potassium	<1 mg/L	97	87-113
Magnesium	<1 mg/L	97	76-124
Sodium	<2 mg/L	97	82-118
Run No 340833 Analysis/Extraction Date 2018-02-16 Analyst H_D			
Method SM 2320B			
Alkalinity (CaCO3)	<5 mg/L	96	90-110
Method SM 2510B			
Conductivity	5 uS/cm	101	90-110
Method SM 4500-FC			
F	<0.10 mg/L	94	90-110
Method SM 4500-H+B			
pH		100	90-110
Run No 340922 Analysis/Extraction Date 2018-02-15 Analyst AET			
Method SUBCONTRACT P-INORG			
DOC	<0.5 mg/L	105	
N-NH3	<0.01 mg/L	98	
Phenols	<0.001 mg/L	124	69-132
S2-	<0.02 mg/L	104	
Tannin & Lignin	<0.1 mg/L	100	

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1802076
 Date Submitted: 2018-02-13
 Date Reported: 2018-02-21
 Project: 017630
 COC #: 190259

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Total Kjeldahl Nitrogen	<0.1 mg/L	92	81-126
Run No 340924 Analysis/Extraction Date 2018-02-21 Analyst R_E			
Method C SM2120C			
Colour	<2 TCU	98	90-110
Run No 340938 Analysis/Extraction Date 2018-02-21 Analyst AET			
Method C Ion Balance			
Ion Balance			
Method C SM2340B			
Hardness as CaCO3			
Method C SM2540			
TDS (COND - CALC)			

Guideline = ODWSOG

*** = Guideline Exceedence**

Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Morey Associates
2672 Highway 43
Kemptville, ON
K0G 1J0
Attention: Mr. Dan Morey
PO#:
Invoice to: Morey Associates

Report Number: 1804402
Date Submitted: 2018-03-28
Date Reported: 2018-04-02
Project: 017630
COC #: 194197

Page 1 of 2

Dear Dan Morey:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

APPROVAL: _____

Krista Quantrill, Microbiology Supervisor

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Eurofins Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Eurofins (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Eurofins recommends consulting the official provincial or federal guideline as required.

Client: Morey Associates
 2672 Highway 43
 Kemptville, ON
 K0G 1J0
 Attention: Mr. Dan Morey
 PO#:
 Invoice to: Morey Associates

Report Number: 1804402
 Date Submitted: 2018-03-28
 Date Reported: 2018-04-02
 Project: 017630
 COC #: 194197

Lab I.D. 1350999
 Sample Matrix Water
 Sample Type
 Sampling Date 2018-03-27
 Sample I.D. 39 Gamble Dr.

Group	Analyte	MRL	Units	Guideline	
Microbiology	Heterotrophic Plate Count	0	ct/1mL		1
Others	Escherichia Coli	0	ct/100mL	MAC 0	0
	Faecal Coliforms	0	ct/100mL		0
	Total Coliforms	0	ct/100mL	MAC 0	0

Guideline = ODWSOG

* = Guideline Exceedence

Results relate only to the parameters tested on the samples submitted.

Analytical Method: AMBCOLM1

additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Golder Associates Ltd. (Ottawa)
 1931 Robertson Road
 Ottawa, ON
 K2H 5B7
 Attention: Ms. Caitlin Cooke
 PO#:
 Invoice to: Golder Associates Ltd. (Ottawa)

Report Number: 1521146
 Date Submitted: 2015-10-23
 Date Reported: 2015-10-25
 Project: 1418381
 COC #: 180449

Page 1 of 2

Dear Caitlin Cooke:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:

Dragana
 Dzeletovic
 2015.10.25
 13:47:27
 -04'00'

APPROVAL:

Dragana Dzeletovic
 Team Leader, Microbiology

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Exova Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Exova (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Exova (Mississauga) is accredited for specific parameters by SCC, Standards Council of Canada (to ISO 17025)

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Exova recommends consulting the official provincial or federal guideline as required.

*** Water well sample laboratory testing results from Golder Associates Ltd. Hydrogeological Study, dated September 2017, report No. 1418381-1000, Rev.2, provided to us by the City of Ottawa**

Client: Golder Associates Ltd. (Ottawa)
 1931 Robertson Road
 Ottawa, ON
 K2H 5B7
Attention: Ms. Caitlin Cooke
PO#:
Invoice to: Golder Associates Ltd. (Ottawa)

Report Number: 1521146
Date Submitted: 2015-10-23
Date Reported: 2015-10-25
Project: 1418381
COC #: 180449

*** Water well sample laboratory testing results from Golder Associates Ltd. Hydrogeological Study, dated September 2017, report No. 1418381-1000 Rev.2, provided to us by the City of Ottawa**

Group	Analyte	MRL	Units	Guideline
Microbiology	Escherichia Coli	0	ct/100mL	MAC-0
	Total Coliforms	0	ct/100mL	MAC-0
				1209515 Water - 2015-10-23 3310 Shea

Guideline = ODWSOG * = **Guideline Exceedence**
 All analysis completed in Ottawa, Ontario (unless otherwise indicated by ** which indicates analysis was completed in Mississauga, Ontario).
 Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STG Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Golder Associates Ltd.
1931 Robertson Road
Ottawa, ON
K2H 5B7
Attention: Ms. Caitlin Cooke
PO#:
Invoice to: Golder Associates Ltd. (Ottawa)

Report Number: 1521181
Date Submitted: 2015-10-23
Date Reported: 2015-11-02
Project: 1418381
COC #: 180449

Page 1 of 7

Dear Caitlin Cooke:

Please find attached the analytical results for your samples. If you have any questions regarding this report, please do not hesitate to call (613-727-5692).

Report Comments:


Shyla Monette
2015.11.02
13:42:24 -05'00'

APPROVAL:

Shyla Monette
Team Leader, Inorganics

All analysis is completed in Ottawa, Ontario (unless otherwise indicated).

Exova Ottawa is accredited by CALA, Canadian Association for Laboratory Accreditation to ISO/IEC 17025 for tests which appear on our CALA scope of accreditation. It can be found at <http://www.cala.ca/scopes/2602.pdf>.

Exova (Ottawa) is certified and accredited for specific parameters by OMAFRA, Ontario Ministry of Agriculture, Food and Rural Affairs (for farm soils). Licensed by Ontario MOE for specific tests in drinking water.

Exova (Mississauga) is accredited for specific parameters by SCC, Standards Council of Canada (to ISO 17025)

Please note: Field data, where presented on the report, has been provided by the client and is presented for informational purposes only. Guideline values listed on this report are provided for ease of use (informational purposes) only. Exova recommends consulting the official provincial or federal guideline as required.

*** Water well sample laboratory testing results from Golder Associates Ltd. Hydrogeological Study, dated September 2017, report No. 1418381-1000, Rev.2, provided to us by the City of Ottawa**

Client: Golder Associates Ltd.
1931 Robertson Road
Ottawa, ON
K2H 5B7
Attention: Ms. Caitlin Cooke
PO#:
Invoice to: Golder Associates Ltd. (Ottawa)

Report Number: 1521181
Date Submitted: 2015-10-23
Date Reported: 2015-11-02
Project: 1418381
COC #: 180449

*** Water well sample laboratory testing results from Golder Associates Ltd. Hydrogeological Study, dated September 2017, report No. 1418381-1000, Rev.2, provided to us by the City of Ottawa**

Group	Analyte	MRL	Units	Guideline	1209571 Water 2015-10-23 3310 Shea
Calculations	Hardness as CaCO3	1	mg/L	OG-100	117*
	TDS (COND - CALC)	1	mg/L	AO-500	536*
General Chemistry	Alkalinity as CaCO3	5	mg/L	OG-500	238
	Cl	1	mg/L	AO-250	100
	Colour	2	TCU	AO-5	3
	Conductivity	5	uS/cm		825
	F	0.10	mg/L	MAC-1.5	1.11
	N-NO2	0.10	mg/L	MAC-1.0	<0.10
	N-NO3	0.10	mg/L	MAC-10.0	<0.10
	pH	1.00		6.5-8.5	8.33
	SO4	1	mg/L	AO-500	38
	Hg	0.0001	mg/L	MAC-0.001	<0.0001
Mercury Metals	Ag	0.0001	mg/L		<0.0001
	Al	0.01	mg/L	OG-0.1	<0.01
	As	0.001	mg/L	IMAC-0.025	<0.001
	B	0.01	mg/L	IMAC-5.0	0.52
	Ba	0.01	mg/L	MAC-1.0	0.08
	Be	0.0005	mg/L		<0.0005
	Ca	1	mg/L		19
	Cd	0.0001	mg/L	MAC-0.005	<0.0001
	Cr	0.001	mg/L	MAC-0.05	<0.001
	Cu	0.001	mg/L	AO-1.0	0.001
	Fe	0.03	mg/L	AO-0.3	0.31*
	K	1	mg/L		6
	Mg	1	mg/L		17
	Mn	0.01	mg/L	AO-0.05	<0.01

Guideline = ODWSOG
All analysis completed in Ottawa, Ontario (unless otherwise indicated by ** which indicates analysis was completed in Mississauga, Ontario).
Results relate only to the parameters tested on the samples submitted.
Methods references and/or additional QA/QC information available on request.

*** = Guideline Exceedance**
MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWGO = Provincial Water Quality Guideline, IPWGO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



Client: Golder Associates Ltd.
 1931 Robertson Road
 Ottawa, ON
 K2H 5B7
Attention: Ms. Caitlin Cooke
PO#:
Invoice to: Golder Associates Ltd. (Ottawa)

Report Number: 1521181
Date Submitted: 2015-10-23
Date Reported: 2015-11-02
Project: 1418381
COC #: 180449

*** Water well sample laboratory testing results from Golder Associates Ltd. Hydrogeological Study, dated September 2017, report No. 1418381-1000 Rev.2, provided to us by the City of Ottawa**

Group	Analyte	MRL	Units	Guideline	1209571 Water 2015-10-23 3310 Shea
Metals	Mo	0.005	mg/L		<0.005
	Na	2	mg/L	AO-200	134
	Ni	0.005	mg/L		<0.005
	Pb	0.001	mg/L	MAC-0.010	<0.001
	Sb	0.0005	mg/L	IMAC-0.006	<0.0005
	Se	0.001	mg/L	MAC-0.01	<0.001
	Sr	0.001	mg/L		2.86
	Tl	0.0001	mg/L		<0.0001
	U	0.001	mg/L	MAC-0.02	<0.001
	Zn	0.01	mg/L	AO-5.0	<0.01
Nutrients	Organic Nitrogen	0.08	mg/L	OG-0.15	<0.08
	Total Kjeldahl Nitrogen	0.1	mg/L		0.4
Phenols Subcontract	Phenols	0.001	mg/L		<0.001
	DOC	0.5	mg/L	AO-5	1.3
	N-NH3	0.01	mg/L		0.41
	PO4 as P	0.2	mg/L		<0.2
	Tannin & Lignin	0.1	mg/L		<0.1

Guideline = ODWSOG
 All analysis completed in Ottawa, Ontario (unless otherwise indicated by ** which indicates analysis was completed in Mississauga, Ontario).
 Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

*** = Guideline Exceedence**
 MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Golder Associates Ltd.
 1931 Robertson Road
 Ottawa, ON
 K2H 5B7
 Attention: Ms. Caitlin Cooke
 PO#:
 Invoice to: Golder Associates Ltd. (Ottawa)

Report Number: 1521181
 Date Submitted: 2015-10-23
 Date Reported: 2015-11-02
 Project: 1418381
 COC #: 180449

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Run No 297423	Analysis/Extraction Date 2015-10-27	Analyst SKH	
Method M SM3120B-3500C			
Calcium	<1 mg/L	103	90-110
Potassium	<1 mg/L	99	87-113
Magnesium	<1 mg/L	102	76-124
Sodium	<2 mg/L	99	82-118
Run No 297446	Analysis/Extraction Date 2015-10-27	Analyst AET	
Method C SM4500-H+B			
Alkalinity (CaCO3)	<5 mg/L	101	90-110
Conductivity	<5 uS/cm	101	90-110
F	<0.10 mg/L	98	90-110
pH	5.64	100	90-110
Run No 297487	Analysis/Extraction Date 2015-10-28	Analyst NP	
Method SM 4110C			
Chloride	<1 mg/L	102	90-112
SO4	<1 mg/L	104	90-110
Run No 297496	Analysis/Extraction Date 2015-10-28	Analyst K A	
Method EPA 200.8			

Guideline = ODWSOG
 All analysis completed in Ottawa, Ontario (unless otherwise indicated by ** which indicates analysis was completed in Mississauga, Ontario).
 Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.
 146 Colonnade Rd. Unit 8, Ottawa, ON K2E 7Y1

*** = Guideline Exceedence**
 MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

*** Water well sample laboratory testing results from Golder Associates Ltd. Hydrogeological Study, dated September 2017, report No. 1418381-1000 Rev.2, provided to us by the City of Ottawa**

Client: Golder Associates Ltd.
 1931 Robertson Road
 Ottawa, ON
 K2H 5B7
Attention: Ms. Caitlin Cooke
PO#:
Invoice to: Golder Associates Ltd. (Ottawa)

Report Number: 1521181
Date Submitted: 2015-10-23
Date Reported: 2015-11-02
Project: 1418381
COC #: 180449

*** Water well sample laboratory testing results from Golder Associates Ltd. Hydrogeological Study, dated September 2017, report No. 1418381-1000 Rev.2, provided to us by the City of Ottawa**

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Silver	<0.0001 mg/L	98	94-106
Aluminum	<0.01 mg/L	98	89-111
Arsenic	<0.001 mg/L	97	93-106
Boron (total)	<0.01 mg/L	101	88-112
Barium	<0.01 mg/L	103	91-109
Beryllium	<0.0005 mg/L	96	93-107
Cadmium	<0.0001 mg/L	96	93-107
Chromium Total	<0.001 mg/L	97	94-106
Copper	<0.001 mg/L	97	93-106
Iron	<0.03 mg/L	97	92-107
Manganese	<0.01 mg/L	99	94-106
Molybdenum	<0.005 mg/L	100	94-106
Nickel	<0.005 mg/L	97	94-106
Lead	<0.001 mg/L	100	70-130
Antimony	<0.0005 mg/L	108	80-120
Selenium	<0.001 mg/L	102	91-108
Strontium	<0.001 mg/L	103	89-110
Thallium	<0.0001 mg/L	97	95-105

Guideline = ODWSOG
 All analysis completed in Ottawa, Ontario (unless otherwise indicated by **, which indicates analysis was completed in Mississauga, Ontario).
 Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

Client: Golder Associates Ltd.
 1931 Robertson Road
 Ottawa, ON
 K2H 5B7
Attention: Ms. Caitlin Cooke
PO#:
Invoice to: Golder Associates Ltd. (Ottawa)

Report Number: 1521181
Date Submitted: 2015-10-23
Date Reported: 2015-11-02
Project: 1418381
COC #: 180449

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Uranium	<0.001 mg/L	99	94-106
Zinc	<0.01 mg/L	101	94-106
Run No 297545	Analysis/Extraction Date 2015-10-29	Analyst AET	
Method C SM2120C			
Colour	<2 TCU	104	90-110
Run No 297568	Analysis/Extraction Date 2015-10-28	Analyst JDT	
Method M SM3112B-3500B			
Mercury	<0.0001 mg/L	95	76-123
Run No 297648	Analysis/Extraction Date 2015-10-29	Analyst NP	
Method C SM4500-NO3-F			
N-NO2	<0.10 mg/L	107	80-120
N-NO3	<0.10 mg/L	95	80-120
Run No 297749	Analysis/Extraction Date 2015-10-28	Analyst SDC	
Method SUBCONTRACT P			
DOC	<0.5 mg/L	109	
N-NH3	<0.01 mg/L	96	
Phenols	<0.001 mg/L	112	
PO4 as P	<0.2 mg/L	118	
Tannin & Lignin	<0.1 mg/L	90	

Guideline = ODWSOG

All analysis completed in Ottawa, Ontario (unless otherwise indicated by ** which indicates analysis was completed in Mississauga, Ontario). Results relate only to the parameters tested on the samples submitted. Methods references and/or additional QA/QC information available on request.

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range

*** Water well sample laboratory testing results from Golder Associates Ltd. Hydrogeological Study, dated September 2017, report No. 1418381-1000 Rev.2, provided to us by the City of Ottawa**

Client: Golder Associates Ltd.
 1931 Robertson Road
 Ottawa, ON
 K2H 5B7
Attention: Ms. Caitlin Cooke
PO#:
Invoice to: Golder Associates Ltd. (Ottawa)

Report Number: 1521181
Date Submitted: 2015-10-23
Date Reported: 2015-11-02
Project: 1418381
COC #: 180449

*** Water well sample laboratory testing results from Golder Associates Ltd. Hydrogeological Study, dated September 2017, report No. 1418381-1000 Rev.2, provided to us by the City of Ottawa**

QC Summary

Analyte	Blank	QC % Rec	QC Limits
Total Kjeldahl Nitrogen	<0.1 mg/L	98	
Run No 297785	Analysis/Extraction Date 2015-11-02	Analyst SCM	
Method C SM2340B			
Hardness as CaCO3			
Method C SM2540			
TDS (COND - CALC)			
Run No 297787	Analysis/Extraction Date 2015-11-02	Analyst SCM	
Method C SM4500-Norg-C			
Organic Nitrogen			

Guideline = ODWSOG * = **Guideline Exceedence**
 All analysis completed in Ottawa, Ontario (unless otherwise indicated by ** which indicates analysis was completed in Mississauga, Ontario).
 Results relate only to the parameters tested on the samples submitted.
 Methods references and/or additional QA/QC information available on request.
 146 Colonnade Rd. Unit 8, Ottawa, ON K2E 7Y1

MRL = Method Reporting Limit, AO = Aesthetic Objective, OG = Operational Guideline, MAC = Maximum Acceptable Concentration, IMAC = Interim Maximum Acceptable Concentration, STD = Standard, PWQO = Provincial Water Quality Guideline, IPWQO = Interim Provincial Water Quality Objective, TDR = Typical Desired Range



APPENDIX E

PUMPING TEST DATA FOR TEST WELL TW1




DRAWDOWN DATA TW1

File: 017630
Pump Test Date: Feb.16/18
Pump Rate: 8 l/gpm

Time of Day	Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
8:40	0	3.28	0.00
8:41	1	5.41	2.13
8:42	2	6.33	3.05
8:44	4	7.20	3.92
8:46	6	8.22	4.94
8:48	8	9.47	6.19
8:50	10	10.15	6.87
8:52	12	10.80	7.52
8:54	14	11.25	7.97
8:56	16	11.67	8.39
8:58	18	12.10	8.82
9:00	20	12.41	9.13
9:05	25	13.00	9.72
9:10	30	13.43	10.15
9:15	35	13.90	10.62
9:20	40	14.06	10.78
9:25	45	14.24	10.96
9:30	50	14.39	11.11
9:35	55	14.53	11.25
9:40	60	14.58	11.30
9:50	70	14.68	11.40
10:00	80	14.76	11.48
10:10	90	14.83	11.55
10:20	100	14.90	11.62
10:40	120	14.98	11.70
11:00	140	15.01	11.73
11:20	160	15.04	11.76
11:40	180	15.06	11.78
12:00	200	15.08	11.80
12:20	220	15.09	11.81
12:40	240	15.11	11.83
13:40	300	15.13	11.85
14:40	360	15.17	11.89



TW1 WELL DRAWDOWN VS. TIME





RECOVERY DATA TW1

File: 017630

Pump Test Date: Feb.16/18

Recovery Time t' (minutes)	t / t' (ratio)	Depth (metres)	h-ho (metres)
0		15.17	11.89
1	361	13.06	9.78
2	181	11.86	8.58
4	91	9.70	6.42
6	61	7.97	4.69
8	46	6.81	3.53
10	37	5.64	2.36
12	31	4.98	1.70
14	27	4.24	0.96
16	24	3.84	0.56
18	21	3.55	0.27
20	19	3.38	0.10
25	15	3.35	0.07
30	13	3.33	0.05
35	11	3.33	0.05
40	10	3.32	0.04
45	9	3.32	0.04
50	8	3.32	0.04
55	8	3.31	0.03
60	7	3.31	0.03
70	6	3.31	0.03
80	6	3.30	0.02
90	5	3.30	0.02
100	5	3.30	0.02
120	4	3.29	0.01

99.9%


RECOVERY AFTER

120

MINUTES



TW1 RECOVERY DATA






OBSERVATION WELLS DRAWDOWN DURING TW1 PUMPING TEST

Approximate Time of Day	Time Lapsed (minutes)	TW2	
		Depth (m)	h-ho (m)
8:20	0	2.82	
8:55	35	2.87	0.05
9:12	52	2.88	0.06
9:54	94	2.89	0.07
10:23	123	2.89	0.07
10:49	149	2.90	0.08
11:27	187	2.90	0.08
12:03	223	2.90	0.08
13:04	284	2.90	0.08
14:24	364	2.90	0.08

Approximate Time of Day	Time Lapsed (minutes)	TW3	
		Depth (m)	h-ho (m)
8:24	0	2.59	
8:59	35	2.60	0.01
9:14	50	2.61	0.02
9:56	92	2.62	0.03
10:25	121	2.62	0.03
10:51	147	2.63	0.04
11:29	185	2.63	0.04
12:05	221	2.63	0.04
13:06	282	2.63	0.04
14:26	362	2.63	0.04



DRAWDOWN VS. TIME IN OBSERVATION WELLS (TW2 & TW3) DURING PUMPING TEST OF TW1





APPENDIX F

PUMPING TEST DATA FOR TEST WELL TW2



DRAWDOWN DATA TW2

File: 017630


Pump Test Date: Feb.22/18

Pump Rate: 15 l/gpm

Time of Day	Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
9:10	0	2.51	0.00
9:11	1	4.42	1.91
9:12	2	5.78	3.27
9:14	4	7.11	4.60
9:16	6	8.01	5.50
9:18	8	8.75	6.24
9:20	10	9.11	6.60
9:22	12	9.38	6.87
9:24	14	9.60	7.09
9:26	16	9.75	7.24
9:28	18	9.84	7.33
9:30	20	9.91	7.40
9:35	25	9.98	7.47
9:40	30	10.05	7.54
9:45	35	10.16	7.65
9:50	40	10.21	7.70
9:55	45	10.25	7.74
10:00	50	10.29	7.78
10:05	55	10.33	7.82
10:10	60	10.38	7.87
10:20	70	10.45	7.94
10:30	80	10.52	8.01
10:40	90	10.64	8.13
10:50	100	10.68	8.17
11:10	120	10.70	8.19
11:30	140	10.71	8.20
11:50	160	10.72	8.21
12:10	180	10.72	8.21
12:30	200	10.72	8.21
12:50	220	10.73	8.22
13:10	240	10.73	8.22
14:10	300	10.75	8.24
15:10	360	10.78	8.27



TW2 WELL DRAWDOWN VS. TIME





RECOVERY DATA TW2

File: 017630

Pump Test Date: Feb.22/18

Recovery Time t' (minutes)	t / t' (ratio)	Depth (metres)	h-ho (metres)
0		10.78	8.27
1	361	7.92	5.41
2	181	4.78	2.27
4	91	3.67	1.16
6	61	3.29	0.78
8	46	2.99	0.48
10	37	2.76	0.25
12	31	2.67	0.16
14	27	2.60	0.09
16	24	2.57	0.06
18	21	2.55	0.04
20	19	2.54	0.03
25	15	2.53	0.02
30	13	2.53	0.02
35	11	2.52	0.01
40	10	2.52	0.01
45	9	2.52	0.01
50	8	2.51	0.00

100%


RECOVERY AFTER

50

MINUTES



TW2 RECOVERY DATA




**OBSERVATION WELLS DRAWDOWN
DURING TW2 PUMPING TEST**

Approximate Time of Day	Time Lapsed (minutes)	TW1	
		Depth (m)	h-ho (m)
9:00	0	2.96	
9:32	32	3.01	0.05
10:34	94	3.03	0.07
10:57	117	3.05	0.09
11:38	158	3.05	0.09
12:10	190	3.05	0.09
12:35	215	3.05	0.09
13:15	255	3.05	0.09
13:40	280	3.05	0.09
14:41	341	3.05	0.09

Approximate Time of Day	Time Lapsed (minutes)	TW3	
		Depth (m)	h-ho (m)
9:05	0	2.26	
9:37	32	2.32	0.06
10:32	87	2.37	0.11
10:52	107	2.37	0.11
11:32	147	2.38	0.12
12:12	187	2.38	0.12
12:33	208	2.38	0.12
13:12	247	2.38	0.12
13:42	277	2.38	0.12
14:43	338	2.38	0.12



DRAWDOWN VS. TIME IN OBSERVATION WELLS (TW1 & TW3) DURING PUMPING TEST OF TW2





APPENDIX G

PUMPING TEST DATA FOR TEST WELL TW3



DRAWDOWN DATA TW3

File: 017630


Pump Test Date: Feb.28/18

Pump Rate: 10 l/gpm

Time of Day	Time Lapsed (minutes)	Depth (metres)	h-ho (metres)
9:00	0	2.14	0.00
9:01	1	4.33	2.19
9:02	2	5.90	3.76
9:04	4	7.50	5.36
9:06	6	8.84	6.70
9:08	8	9.80	7.66
9:10	10	10.65	8.51
9:12	12	11.20	9.06
9:14	14	11.67	9.53
9:16	16	12.06	9.92
9:18	18	12.33	10.19
9:20	20	12.60	10.46
9:25	25	13.04	10.90
9:30	30	13.33	11.19
9:35	35	13.40	11.26
9:40	40	13.40	11.26
9:45	45	13.41	11.27
9:50	50	13.44	11.30
9:55	55	13.46	11.32
10:00	60	13.48	11.34
10:10	70	13.49	11.35
10:20	80	13.51	11.37
10:30	90	13.53	11.39
10:40	100	13.53	11.39
11:00	120	13.54	11.40
11:20	140	13.56	11.42
11:40	160	13.58	11.44
12:00	180	13.59	11.45
12:20	200	13.60	11.46
12:40	220	13.61	11.47
13:00	240	13.61	11.47
14:00	300	13.62	11.48
15:00	360	13.62	11.48



TW3 WELL DRAWDOWN VS. TIME





RECOVERY DATA TW3

File: 017630

Pump Test Date: Feb.28/18

Recovery Time t' (minutes)	t / t' (ratio)	Depth (metres)	h-ho (metres)
0		13.62	11.48
1	361	10.90	8.76
2	181	9.41	7.27
4	91	6.85	4.71
6	61	5.36	3.22
8	46	4.43	2.29
10	37	3.49	1.35
12	31	2.93	0.79
14	27	2.61	0.47
16	24	2.44	0.30
18	21	2.40	0.26
20	19	2.36	0.22
25	15	2.31	0.17
30	13	2.27	0.13
35	11	2.23	0.09
40	10	2.20	0.06
45	9	2.18	0.04
50	8	2.16	0.02
55	8	2.16	0.02
60	7	2.15	0.01
70	6	2.14	0.00

100%


RECOVERY AFTER

70

MINUTES



TW3 RECOVERY DATA




**OBSERVATION WELLS DRAWDOWN
DURING TW3 PUMPING TEST**

Approximate Time of Day	Time Lapsed (minutes)	TW1	
		Depth (m)	h-ho (m)
8:50	0	2.80	
9:28	38	2.84	0.04
10:13	83	2.84	0.04
11:04	134	2.84	0.04
12:04	194	2.85	0.05
12:53	243	2.84	0.04
13:12	262	2.85	0.05
13:54	304	2.85	0.05
14:21	331	2.86	0.06
14:51	361	2.86	0.06

Approximate Time of Day	Time Lapsed (minutes)	TW2	
		Depth (m)	h-ho (m)
8:55	0	2.39	
9:26	31	2.43	0.04
10:12	77	2.43	0.04
11:02	127	2.43	0.04
12:02	187	2.44	0.05
12:51	236	2.45	0.06
13:14	259	2.45	0.06
13:52	297	2.45	0.06
14:25	330	2.45	0.06
14:55	360	2.45	0.06



DRAWDOWN VS. TIME IN OBSERVATION WELLS (TW1 & TW2) DURING PUMPING TEST OF TW3





APPENDIX H

TEST PIT LOGS FROM PREVIOUS MOREY ASSOCIATES LTD. GEOTECHNICAL INVESTIGATION

TABLE I

RECORD OF TEST PITS
 PROPOSED RESIDENTIAL DEVELOPMENT
 HEMPHILL STREET
 OTTAWA, ONTARIO

TEST PIT NUMBER/ ELEVATION	DEPTH (METRES)	DESCRIPTION
TP1 ELEV. 93.5m	0.00 – 0.30	TOPSOIL
	0.30 – 3.35	Stiff to very stiff, grey brown SILTY CLAY
	3.35	End of test pit
	<u>Depth (m)</u>	<u>Strength, Cu (kPa)</u>
	0.3	>130
	0.6	>130
	0.9	>130
	1.2	>130
	1.5	>130
	1.8	>130
	2.1	120
	2.4	105
	2.7	89
	3.0	65
	3.3	62

Groundwater flow observed in test pit at about 2.3 metres below existing ground surface, November 22, 2017.
 Water measured in standpipe at about 1.1 metres below existing ground surface, December 6, 2017.

TABLE I (CONTINUED)

TEST PIT NUMBER/ ELEVATION	DEPTH (METRES)	DESCRIPTION																												
TP2 ELEV. 93.7m	0.00 – 0.30	TOPSOIL																												
	0.30 – 4.00	Stiff to very stiff, grey brown SILTY CLAY																												
	4.00	End of test pit																												
		<table border="1"> <thead> <tr> <th>Depth (m)</th> <th>Strength, Cu (kPa)</th> </tr> </thead> <tbody> <tr><td>0.3</td><td>>130</td></tr> <tr><td>0.6</td><td>>130</td></tr> <tr><td>0.9</td><td>>130</td></tr> <tr><td>1.2</td><td>>130</td></tr> <tr><td>1.5</td><td>>130</td></tr> <tr><td>1.8</td><td>>130</td></tr> <tr><td>2.1</td><td>120</td></tr> <tr><td>2.4</td><td>110</td></tr> <tr><td>2.7</td><td>90</td></tr> <tr><td>3.0</td><td>71</td></tr> <tr><td>3.3</td><td>67</td></tr> <tr><td>3.6</td><td>78</td></tr> <tr><td>3.9</td><td>84</td></tr> </tbody> </table>	Depth (m)	Strength, Cu (kPa)	0.3	>130	0.6	>130	0.9	>130	1.2	>130	1.5	>130	1.8	>130	2.1	120	2.4	110	2.7	90	3.0	71	3.3	67	3.6	78	3.9	84
Depth (m)	Strength, Cu (kPa)																													
0.3	>130																													
0.6	>130																													
0.9	>130																													
1.2	>130																													
1.5	>130																													
1.8	>130																													
2.1	120																													
2.4	110																													
2.7	90																													
3.0	71																													
3.3	67																													
3.6	78																													
3.9	84																													

Groundwater seepage observed in test pit at about 1.8 metres below existing ground surface, November 22, 2017. Water measured in standpipe at about 1.2 metres below existing ground surface, December 6, 2017.

TABLE I (CONTINUED)

TEST PIT NUMBER/ ELEVATION	DEPTH (METRES)	DESCRIPTION																										
TP3 ELEV. 93.8m	0.00 – 0.30	TOPSOIL																										
	0.30 – 4.00	Stiff to very stiff, grey brown SILTY CLAY																										
	4.00	End of test pit																										
		<table border="1"> <thead> <tr> <th><u>Depth (m)</u></th> <th><u>Strength, Cu (kPa)</u></th> </tr> </thead> <tbody> <tr><td>0.3</td><td>>130</td></tr> <tr><td>0.6</td><td>>130</td></tr> <tr><td>0.9</td><td>>130</td></tr> <tr><td>1.2</td><td>>130</td></tr> <tr><td>1.5</td><td>>130</td></tr> <tr><td>1.8</td><td>110</td></tr> <tr><td>2.1</td><td>95</td></tr> <tr><td>2.4</td><td>83</td></tr> <tr><td>2.7</td><td>67</td></tr> <tr><td>3.0</td><td>72</td></tr> <tr><td>3.3</td><td>80</td></tr> <tr><td>3.6</td><td>92</td></tr> </tbody> </table>	<u>Depth (m)</u>	<u>Strength, Cu (kPa)</u>	0.3	>130	0.6	>130	0.9	>130	1.2	>130	1.5	>130	1.8	110	2.1	95	2.4	83	2.7	67	3.0	72	3.3	80	3.6	92
<u>Depth (m)</u>	<u>Strength, Cu (kPa)</u>																											
0.3	>130																											
0.6	>130																											
0.9	>130																											
1.2	>130																											
1.5	>130																											
1.8	110																											
2.1	95																											
2.4	83																											
2.7	67																											
3.0	72																											
3.3	80																											
3.6	92																											

Groundwater flow observed in test pit at about 2.1 metres below existing ground surface, November 22, 2017.
 Water measured in standpipe at about 1.2 metres below existing ground surface, December 6, 2017.

TABLE I (CONTINUED)

TEST PIT NUMBER/ ELEVATION	DEPTH (METRES)	DESCRIPTION																										
TP4 ELEV. 93.7m	0.00 – 0.30	TOPSOIL																										
	0.30 – 4.00	Stiff to very stiff, grey brown SILTY CLAY																										
	4.00	End of test pit																										
		<table border="1"> <thead> <tr> <th><u>Depth (m)</u></th> <th><u>Strength, Cu (kPa)</u></th> </tr> </thead> <tbody> <tr><td>0.3</td><td>>130</td></tr> <tr><td>0.6</td><td>>130</td></tr> <tr><td>0.9</td><td>>130</td></tr> <tr><td>1.2</td><td>>130</td></tr> <tr><td>1.5</td><td>>130</td></tr> <tr><td>1.8</td><td>125</td></tr> <tr><td>2.1</td><td>100</td></tr> <tr><td>2.4</td><td>96</td></tr> <tr><td>2.7</td><td>90</td></tr> <tr><td>3.0</td><td>74</td></tr> <tr><td>3.3</td><td>80</td></tr> <tr><td>3.6</td><td>96</td></tr> </tbody> </table>	<u>Depth (m)</u>	<u>Strength, Cu (kPa)</u>	0.3	>130	0.6	>130	0.9	>130	1.2	>130	1.5	>130	1.8	125	2.1	100	2.4	96	2.7	90	3.0	74	3.3	80	3.6	96
<u>Depth (m)</u>	<u>Strength, Cu (kPa)</u>																											
0.3	>130																											
0.6	>130																											
0.9	>130																											
1.2	>130																											
1.5	>130																											
1.8	125																											
2.1	100																											
2.4	96																											
2.7	90																											
3.0	74																											
3.3	80																											
3.6	96																											

Groundwater flow observed in test pit at about 2.1 metres below existing ground surface, November 22, 2017.
 Water measured in standpipe at about 1.2 metres below existing ground surface, December 6, 2017.



APPENDIX I

CURRICULA VITAE

D.G. MOREY, P.Eng.

LANGUAGE: English

EDUCATION: Bachelor of Applied Science, Civil Engineering
University of Ottawa, 2009

PROFESSIONAL AFFILIATIONS: Registered Professional Engineer Ontario

EXPERIENCE:

2012 – Present **Morey Associates Ltd.**
Director/Senior Engineer

Responsible for the managerial and technical aspects of the operation of the firm carrying out geotechnical and hydrogeological investigations, environmental site assessments, and construction inspection and testing.

2010 – 2012 **Levac Robichaud Leclerc Associates Ltd.**
Junior Engineer

Analysis, preparation and field work for geotechnical investigations, hydrogeological impact assessments and environmental assessments. Also carry out quality control testing (i.e. compaction, subgrade, concrete testing)

2009 – 2010 **Kollaard Associates Inc.**
Junior Engineer

Analysis and preparation of geotechnical and slope stability evaluation reports. Responsible for field work and drafting (using AutoCAD) for geotechnical investigations, slope stability evaluations, environmental site assessments, hydrogeological investigations, site grading plans, roadway designs, and structural designs. Also carry out quality control testing (i.e. compaction, subgrade, concrete testing).

2005 – 2008 (Summers) **Kollaard Associates Inc.**
Civil Engineering Student

Responsible for field work and drafting for geotechnical investigations, site grading plans, septic system designs, roadway designs, and structural designs.

2004 **Morey Houle Chevrier Engineering Ltd.**
Technician

Carried out surveying and drafting for site grading plans and septic system designs. Also carried out well grouting inspections and well pump tests.

C.R. MOREY, P.Eng

LANGUAGE: English

EDUCATION: B.Sc., Geological Engineering, Queen's University, Kingston, Ontario, 1973.
M.Sc.(Eng.), Civil Engineering, Queen's University, Kingston, Ontario, 1977.
Graduate courses in Civil and Geotechnical Engineering, Windsor and Carleton Universities, 1980 and 1982.

PROFESSIONAL AFFILIATIONS: Registered Professional Engineer Ontario
Designated Consulting Engineer

EXPERIENCE:

2012 – PRESENT **Morey Associates (Kemptonville, Ontario)**
Senior Engineer

Responsible for supervision of all technical aspects of projects carried out by the firm.

2010 - 2012 **Levac Robichaud Leclerc Associates Ltd. (Rockland & Kemptonville, Ontario)**
Director of Geotechnical Department

Responsible for senior level supervision of geotechnical investigations, hydrogeological impact assessments and environmental site assessments and providing QA/QC for the related project letters, memos, reports and drawings.

2005 – 2010 **Kollaard Associates Inc. (Kemptonville, Ontario)**
Principal

Responsible for mentoring of professional staff, project letter and report reviews, senior level project supervision, business development, and assisting in office administration.

1994 – 2005 **Morey Houle Chevrier Engineering Ltd. (Kemptonville, Ontario)**
President

Responsible for the managerial and technical aspects of the operation of the firm carrying out geotechnical and hydrogeological investigations, environmental site assessments, and construction inspection and testing. Geotechnical and hydrogeological expert witness for Ontario Municipal Board hearings and Ontario Court Provincial Division trials.

1980 - 1994

**Golder Associates Ltd. (Windsor & Ottawa, Ontario)
Geotechnical Engineer then Associate**

Responsible for subsurface investigations and design of roadways, retaining walls, airport runways, residential and commercial developments, buried services, septic systems, wharves, building foundations, dams, municipal drains, stormwater management facilities, building flood proofing.

PUBLICATIONS:

Co-author of two papers regarding retrogressive landslides in sensitive marine deposited silty clay of the Ottawa Valley area, published by the Geological Survey of Canada.