



Geotechnical
Engineering

Environmental
Engineering

Hydrogeology

Geological
Engineering

Materials Testing

Building Science

Archaeological
Services

Phase II – Environmental Site Assessment

Trail's Edge: Phase 4 (South)
Southern Parcel (Commercial Zone)
Part of 2284 Mer Bleue Road
Ottawa, Ontario

Prepared For

Richcraft Group of Companies

Paterson Group Inc.

Consulting Engineers
154 Colonnade Road South
Ottawa (Nepean), Ontario
Canada K2E 7J5

Tel: (613) 226-7381
Fax: (613) 226-6344
www.patersongroup.ca

January 8, 2021

Report: PE4999-1

TABLE OF CONTENTS

| | PAGE |
|---|-------------|
| EXECUTIVE SUMMARY..... | iii |
| 1.0 INTRODUCTION..... | 1 |
| 1.1 Subject Site Information..... | 1 |
| 1.2 Property Ownership..... | 2 |
| 1.3 Current and Proposed Future Uses..... | 2 |
| 1.4 Applicable Site Condition Standard..... | 2 |
| 2.0 BACKGROUND INFORMATION..... | 3 |
| 2.1 Physical Setting..... | 3 |
| 3.0 SCOPE OF INVESTIGATION..... | 3 |
| 3.1 Overview of Site Investigation..... | 3 |
| 3.2 Media Investigated..... | 3 |
| 3.3 Phase I ESA Conceptual Site Model..... | 4 |
| 4.0 INVESTIGATION METHOD..... | 6 |
| 4.1 Subsurface Investigation..... | 6 |
| 4.2 Soil Sampling..... | 6 |
| 4.3 Field Screening Measurements..... | 7 |
| 4.4 Groundwater Monitoring Well Installation..... | 7 |
| 4.5 Field Measurement of Water Quality Parameters..... | 8 |
| 4.6 Groundwater Sampling..... | 8 |
| 4.7 Residue Management..... | 8 |
| 4.8 Analytical Testing..... | 8 |
| 4.9 Elevation Surveying..... | 10 |
| 4.10 Quality Assurance and Quality Control Measures..... | 10 |
| 5.0 REVIEW AND EVALUATION..... | 10 |
| 5.1 Geology..... | 10 |
| 5.2 Groundwater Elevations, Flow Direction, and Hydraulic Gradient..... | 11 |
| 5.3 Fine/Coarse Soil Texture..... | 11 |
| 5.4 Field Screening..... | 11 |
| 5.5 Soil Quality..... | 12 |
| 5.6 Groundwater Quality..... | 17 |
| 5.7 Quality Assurance and Quality Control Results..... | 19 |
| 5.8 Phase II Conceptual Site Model..... | 19 |
| 6.0 CONCLUSION..... | 24 |
| 7.0 STATEMENT OF LIMITATIONS..... | 26 |

List of Figures

Figure 1 – Key Plan

Drawing PE4999-3 – Test Hole Location Plan

Drawing PE4999-4 – Analytical Testing Plan – Soil (PAHs)

Drawing PE4999-4A – Cross Section A-A' – Soil (PAHs)

Drawing PE4999-5 – Analytical Testing Plan – Soil (BTEX, PHCs, Metals)

Drawing PE4999-5A – Cross Section A-A' – Soil (BTEX, PHCs, Metals)

Drawing PE4999-6 – Analytical Testing Plan – Groundwater

Drawing PE4999-6A – Cross Section A-A' – Groundwater

List of Appendices

- Appendix 1 Sampling and Analysis Plan
 - Soil Profile and Test Data Sheets
 - Symbols and Terms
 - Laboratory Certificates of Analysis

EXECUTIVE SUMMARY

Assessment

A Phase II ESA was conducted for a parcel of land (part of 2284 Mer Bleue Road) situated within the proposed Trail's Edge: Phase 4 (South) residential subdivision development, in the City of Ottawa, Ontario. The purpose of the Phase II ESA was to address the potentially contaminating activities (PCAs) that were identified during the Phase I ESA and were considered to result in areas of potential environmental concern (APECs) on the subject site.

The subsurface investigation for this assessment was conducted on September 29, October 19, and November 6, 2020. The field program consisted of drilling three (3) boreholes (BH4-20, BH5-20, and BH6-20), all of which were instrumented with groundwater monitoring wells, as well as excavating five (5) test pits (TP10-TP14). The boreholes were advanced to depths ranging from approximately 4.42 m to 5.94 m below ground surface and terminated within a layer of saturated native silty clay. The test pits were advanced to depths ranging from approximately 1.28 m to 2.61 m below ground surface and terminated within the underlying native soils.

Site soils generally consist of fill material (brown silty sand with crushed stone), underlain by stiff brown silty clay over top of soft grey silty clay. Bedrock was not encountered in any of the borehole or test pit locations.

Three (3) soil samples, recovered from BH4-20, BH5-20, and BH6-20, were submitted for laboratory analysis of: BTEX and PHCs (F₁-F₄). An additional five (5) soil samples, recovered from test pits TP10-TP14, were submitted for laboratory analysis of either: PHCs (F₂-F₄), PAHs, and/or metals. According to the analytical test results, the concentration of benzo[a]pyrene in soil sample TP14-G1 is in excess of the MECP Table 2 commercial standards.

Three (3) groundwater samples were recovered from the monitoring wells installed in BH4-20, BH5-20, and BH6-20 and submitted for laboratory analysis of VOCs and PHCs (F₁-F₄). According to the analytical test results, all detected parameter concentrations in the groundwater samples analyzed are in compliance with the selected MECP Table 2 commercial standards.

Recommendations

PAH impacted soil/fill material was identified within the vicinity of TP14, located in the southwestern portion of the Phase II study area, requiring some remedial work. It is our understanding that the subject site is to be developed for commercial purposes in conjunction with the neighbouring residential subdivision. Therefore, it is our recommendation that an environmental site remediation program be completed in conjunction with site redevelopment. This will require the segregation of clean soils from impacted soils, the latter of which will require disposal at an approved waste disposal facility.

While in compliance with the site-specific standards, it should be noted that the concentration of PHCs and PAHs within the vicinity of TP12 are in excess of the MECP Table 1 standards. These exceedances are not considered to pose an environmental concern to the subject site, however, if the soil is ever to be removed from the property, it should be classified as contaminated and disposed of at an approved waste disposal site.

Prior to off-site disposal at a licenced landfill site, a leachate analysis of a representative sample of this soil must be conducted in accordance with Ontario Regulation 347/558.

If the groundwater monitoring wells installed in BH4-20, BH5-20, and BH6-20 are not going to be used in the future, or will be destroyed during future redevelopment activities, then they must be decommissioned according to Ontario Regulation Reg. 903 (Ontario Water Resources Act). The monitoring wells will be registered with the MECP under this regulation. Further information can be provided upon request in this regard.

1.0 INTRODUCTION

At the request of Richcraft Group of Companies (Richcraft), Paterson Group (Paterson) conducted a Phase II – Environmental Site Assessment (Phase II ESA) for a parcel of land situated within the proposed Trail's Edge: Phase 4 (South) residential subdivision development, in the City of Ottawa, Ontario. The purpose of this Phase II ESA has been to address the areas of potential environmental concern (APECs) identified on the subject site as a result the findings of the Phase I ESA Update, conducted by Paterson in September 2020.

1.1 Subject Site Information

| | |
|-------------------------|--|
| Address: | Part of 2284 Mer Bleue Road, Ottawa, ON |
| Legal Description: | Block 198, Part of Lots 1, 2, and 3, Concession 3 (Ottawa Front), Part 1 of Registered Plan 4R-30034, Formerly the Geographic Township of Gloucester, in the City of Ottawa. |
| Location: | The subject site is located on the west side of Mer Bleue Road, south of Brian Coburn Boulevard, in the City of Ottawa, Ontario. Refer to Figure 1 – Key Plan for the site location. |
| Latitude and Longitude: | 45° 26' 39" N, 75° 29' 54" W |

Site Description

| | |
|----------------|--|
| Configuration: | Rectangular |
| Site Area: | 8,750 m ² (approximate) |
| Zoning: | DR – Development Reserve Zone. |
| Current Use: | The subject site is currently occupied with an abandoned metal workshop building and storage shed. |
| Services: | The subject site is located within a municipally serviced area. |

1.2 Property Ownership

The subject property is currently owned by Richcraft. Paterson was retained to complete this Phase II ESA by Mr. Patrick Gaudreault of Richcraft, whose offices are located at 2280 St. Laurent Boulevard, Suite 201, Ottawa, Ontario. Mr. Gaudreault can be contacted by telephone at 613-739-1111.

1.3 Current and Proposed Future Uses

The subject site is currently occupied by an abandoned metal workshop building and a storage shed.

It is our understanding that the property is to be redeveloped for commercial purposes as part of the development of the subdivision.

1.4 Applicable Site Condition Standard

The site condition standards for the subject properties were obtained from Table 2 of the document entitled, "*Soil, Ground Water and Sediment Standards for Use Under Part XV.1 of the Environmental Protection Act*", prepared by the Ministry of the Environment, Conservation and Parks (MECP), and dated April 15, 2011. The selected MECP standards are based on the following considerations:

- Coarse-grained soil conditions;
- Potable groundwater conditions;
- Commercial land use.

The commercial standards were selected based on the future land use of the subject sites. Grain size analysis was not conducted as part of this assessment. The coarse-grained soil standards were chosen as a conservative approach.

The MECP Table 1 standards for Full Depth Background Site Conditions were also selected for additional consideration in order to assess the on-site soil conditions prior to future off-site disposal.

2.0 BACKGROUND INFORMATION

2.1 Physical Setting

The subject site is located on the west side of Mer Bleue Road, south of Brian Coburn Boulevard, in the City of Ottawa, Ontario. The subject site is currently occupied with an abandoned metal workshop building and storage shed. The remainder of the subject site consists primarily of vacant grassland, apart from some gravel surfaced areas in the vicinity of the metal workshop building.

The subject site is at-grade with the adjacent roads as well as the neighbouring properties. The site topography is relatively flat, whereas the regional topography slopes very gently down towards the south, in the general direction of Mer Bleue Bog. Water drainage on the subject site occurs primarily via infiltration throughout the properties, as well as via surface run-off towards drainage ditches present along the adjacent roads.

3.0 SCOPE OF INVESTIGATION

3.1 Overview of Site Investigation

The subsurface investigation for this assessment was conducted on September 29, October 19, and November 6, 2020. The field program consisted of drilling three (3) boreholes (BH4-20, BH5-20, and BH6-20), all of which were instrumented with groundwater monitoring wells, as well as excavating five (5) test pits (TP10-TP14). The boreholes were advanced to depths ranging from approximately 4.42 m to 5.94 m below ground surface and terminated within a layer of saturated native silty clay. The test pits were advanced to depths ranging from approximately 1.28 m to 2.61 m below ground surface and terminated within the underlying native soils.

3.2 Media Investigated

During the subsurface investigation, soil and groundwater samples were obtained and submitted for laboratory analysis. The rationale for sampling and analyzing these media is based on the contaminants of potential concern identified in the Phase I ESA.

The contaminants of potential concern for the soil and groundwater on the subject site include the following:

- Benzene, Toluene, Ethylbenzene, and Xylenes (BTEX);
- Petroleum Hydrocarbons, fractions 1 - 4 (PHCs F₁-F₄);
- Volatile Organic Compounds (VOCs);
- Polycyclic Aromatic Hydrocarbons (PAHs);
- Metals (including Mercury and Hexavalent Chromium).

3.3 Phase I ESA Conceptual Site Model

Existing Buildings and Structures

The subject site is currently occupied with a two (2) storey, slab-on-grade style metal workshop building (currently abandoned) as well as a storage shed.

Water Bodies and Areas of Natural and Scientific Interest

No areas of natural and scientific interest are known to exist within the Phase I study area. The nearest named water body with respect to the subject site is Mer Bleue Bog, located approximately 2.25 km to the south.

Geological and Hydrogeological Setting

Based on the available mapping information, the bedrock within the area of the subject sites consist of interbedded limestone and shale of the Lindsay Formation, whereas the surficial geology consists of offshore marine deposits (clay and silt) with an overburden ranging from approximately 15 m to 50 m in thickness. Based on the regional topography, the groundwater is interpreted to be moving in a southerly direction towards Mer Bleue Bog.

Neighbouring Land Use

The neighbouring lands within the Phase I study area consist of a combination of residential and commercial properties or vacant land.

Drinking Water Wells

Based on the available MECP water well records, it is likely that some of the residential properties adjacent to Mer Bleue Road may still utilize private drinking water wells.

Potentially Contaminating Activities and Areas of Potential Environmental Concern

Based on the findings of the Phase I ESA Update, two (2) potentially contaminating activities (PCAs), resulting in areas of potential environmental concern (APECs), were identified as pertaining to the subject sites:

- The presence and historical operation of an on-site metal workshop building, located within the central portion of the Phase II study area;
- The presence of fill material of unknown quality, located within the vicinity of the on-site metal workshop building;

Other off-site PCAs were identified within the Phase I study area but were deemed not to be of concern based on their separation distances as well as their down-gradient or cross-gradient orientations.

Contaminants of Potential Concern

The contaminants of potential concern (CPCs) associated with the aforementioned APECs are considered to be:

- Benzene, Toluene, Ethylbenzene, and Xylenes (BTEX);
- Petroleum Hydrocarbons, fractions 1 - 4 (PHCs F₁-F₄);
- Volatile Organic Compounds (VOCs);
- Polycyclic Aromatic Hydrocarbons (PAHs);
- Metals (including Mercury and Hexavalent Chromium).

These CPCs have the potential to be present in the soil matrix and/or the groundwater situated beneath the subject sites.

Assessment of Uncertainty and/or Absence of Information

The information available for review as part of the preparation of the Phase I ESA is considered to be sufficient to conclude that there are PCAs and APECs associated with the subject site.

The presence of these PCAs were confirmed by a variety of independent sources, and as such, the conclusions of this report are not affected by uncertainty which may be present with respect to the individual sources.

4.0 INVESTIGATION METHOD

4.1 Subsurface Investigation

The subsurface investigation for this assessment was conducted on September 29, October 19, and November 6, 2020. The field program consisted of drilling three (3) boreholes (BH4-20, BH5-20, and BH6-20), all of which were instrumented with groundwater monitoring wells, as well as excavating five (5) test pits (TP10-TP14). The boreholes were advanced to depths ranging from approximately 4.42 m to 5.94 m below ground surface and terminated within a layer of saturated native silty clay. The test pits were advanced to depths ranging from approximately 1.28 m to 2.61 m below ground surface and terminated within the underlying native soils.

Under the full-time supervision of Paterson personnel, the boreholes were drilled using a track-mounted drill rig provided by George Downing Estate Drilling of Hawkesbury, Ontario; whereas the test pits were excavated using a backhoe provided by Quast Excavating of Ottawa, Ontario.

The locations of the boreholes and test pits are illustrated on Drawing PE4999-3 – Test Hole Location Plan, appended to this report.

4.2 Soil Sampling

Soil sampling protocols were followed using the MECP document entitled, *“Guidance on Sampling and Analytical Methods for Use at Contaminated Sites in Ontario”*, dated May 1996. The samples were recovered using a stainless-steel split spoon while wearing protective gloves (changed after each sample), and immediately placed into plastic bags. If significant contamination was encountered, the samples were instead placed into glass jars. Sampling equipment was routinely washed in soapy water and rinsed with methylhydrate after each split spoon to prevent any cross contamination of the samples. The samples were also stored in coolers to reduce analyte volatilization during transportation.

Twenty-two (22) soil samples were obtained from the boreholes by means of auger and split spoon sampling, with samples taken at approximate 0.76 m intervals. The depths at which auger and split spoon samples were obtained from the boreholes are shown as **“AU”** and **“SS”**, respectively, on the Soil Profile and Test Data Sheets, appended to this report.

Twelve (12) soil samples were obtained from the test pits by means of grab sampling. The depths at which grab samples were obtained from the test pits are shown as "G", on the Soil Profile and Test Data Sheets, appended to this report.

Site soils generally consist of fill material (brown silty sand), underlain by stiff brown silty clay over top of soft grey silty clay. Bedrock was not encountered in any of the boreholes or test pits at the time of the field program.

4.3 Field Screening Measurements

All soil samples collected were subjected to a preliminary screening procedure, which included visual screening for colour and evidence of metals, as well as soil vapour screening with a Photo Ionization Detector.

The recovered soil samples were placed immediately into airtight plastic bags with nominal headspace. All lumps of soil inside the bags were broken by hand, and the soil was allowed to come to room temperature prior to conducting the vapour survey, ensuring consistency of readings between samples. To measure the soil vapours, the analyser probe was inserted into the nominal headspace above the sample. The sample was then agitated and manipulated gently by hand as the measurement was taken. The peak reading registered within the first 15 seconds was recorded as the vapour measurement. The parts per million (ppm) scale was used to measure concentrations of organic vapours.

Samples with the highest vapour readings for a given borehole were generally selected as candidates for laboratory analysis. The results of the vapour survey are presented on the Soil Profile and Test Data Sheets, appended to this report.

4.4 Groundwater Monitoring Well Installation

Three (3) groundwater monitoring wells were installed on the subject sites as part of this assessment. These monitoring wells were constructed using 50 mm diameter Schedule 40 threaded PVC risers and screens. A sand pack consisting of silica sand was placed around the screen and a bentonite seal was placed above the screen to minimize cross-contamination.

A summary of the monitoring well construction details are listed below in Table 1 as well as on the Soil Profile and Test Data Sheets provided in Appendix 1.

Upon completion, the groundwater monitoring wells were developed using a dedicated inertial lift pump, with a minimum of three (3) well volumes being removed from the wells at the time of installation. The wells were developed until the appearance of the water was noted to be stabilized. In addition, the ground surface elevations of each borehole were subsequently surveyed with respect to a known geodetic elevation.

| Table 1 Monitoring Well Construction Details | | | | | | |
|---|---|----------------------------|----------------------------------|--------------------------|-------------------------------|--------------------|
| Well ID | Ground Surface Elevation (m ASL) | Total Depth (m BGS) | Screened Interval (m BGS) | Sand Pack (m BGS) | Bentonite Seal (m BGS) | Casing Type |
| BH4-20 | 88.24 | 5.94 | 2.94-5.94 | 2.44-5.94 | 0.10-2.44 | Stick-Up |
| BH5-20 | 87.81 | 5.94 | 2.94-5.94 | 2.44-5.94 | 0.10-2.44 | Flushmount |
| BH6-20 | 87.81 | 4.42 | 1.42-4.42 | 0.74-1.42 | 0.43-0.74 | Stick-Up |

4.5 Field Measurement of Water Quality Parameters

Groundwater sampling was conducted at BH4-20, BH5-20, and BH6-20 on October 2, and November 12, 2020. No water quality parameters were measured in the field at that time.

4.6 Groundwater Sampling

Groundwater sampling protocols were followed using the MECP document entitled, *“Guidance on Sampling and Analytical Methods for Use at Contaminated Sites in Ontario”*, dated May 1996. Standing water was purged from each monitoring well prior to the recovery of the groundwater samples using dedicated sampling equipment. The samples were then stored in coolers to reduce possible analyte volatilization during their transportation. Further details of our standard operating procedure for groundwater sampling are provided in the Sampling and Analysis Plan, appended to this report.

4.7 Residue Management

Soil cuttings, purge water, and equipment cleaning fluids were retained on-site.

4.8 Analytical Testing

The following soil and groundwater samples were submitted for laboratory analysis:

| Table 2 | | | | | | | |
|--|-----------------------------------|---------------------|-------------------------------------|-------------------------------------|------|---------------------|--|
| Testing Parameters for Submitted Soil Samples | | | | | | | |
| Sample ID | Sample Depth & Stratigraphic Unit | Parameters Analyzed | | | | | Rationale |
| | | BTEX | PHCs F ₁ -F ₄ | PHCs F ₂ -F ₄ | PAHs | Metals ¹ | |
| BH4-20-SS5 | 3.05 – 3.66 m Grey Silty Clay | X | X | | | | To assess for potential impacts resulting from a former metal workshop. |
| BH5-20-SS4 | 2.29 – 2.90 m Grey Silty Clay | X | X | | | | |
| BH6-20-SS3 | 1.52 – 2.13 m Grey Silty Clay | X | X | | | | |
| TP10-G1 | 0.10 – 0.30 m Fill Material | | | X | X | X | To assess for potential impacts resulting from the presence of fill material of unknown quality. |
| TP11-G1 | 0.30 – 0.50 m Fill Material | | | X | X | X | |
| TP12-G1 | 0.10 – 0.20 m Fill Material | | | X | X | X | |
| TP13-G1 | 0.10 – 0.20 m Fill Material | | | X | X | X | |
| TP14-G1 | 0.10 – 0.20 m Fill Material | | | X | X | X | |

1 – Including Mercury and Hexavalent Chromium

| Table 3 | | | | |
|---|--|---------------------|-------------------------------------|---|
| Testing Parameters for Submitted Groundwater Samples | | | | |
| Sample ID | Screened Interval & Stratigraphic Unit | Parameters Analyzed | | Rationale |
| | | VOCs | PHCs F ₁ -F ₄ | |
| BH4-20-GW1 | 2.94 – 5.94 m Grey Silty Clay | X | X | To assess for potential impacts resulting from a former metal workshop. |
| BH5-20-GW1 | 2.94 – 5.94 m Grey Silty Clay | X | X | |
| BH6-20-GW1 | 1.42 – 4.42 m Grey Silty Clay | X | X | |
| DUP1 | 2.94 – 5.94 m Grey Silty Clay | X | | |

1 – Including Mercury and Hexavalent Chromium

Paracel Laboratories (Paracel), of Ottawa, Ontario, performed the laboratory analysis on the samples submitted for analytical testing. Paracel is a member of the Standards Council of Canada/Canadian Association for Laboratory Accreditation (SCC/CALA) and is accredited and certified by the SCC/CALA for specific tests registered with the association.

4.9 Elevation Surveying

The ground surface elevations at each borehole and test pit location were surveyed using a GPS device by Paterson personnel and referenced to a geodetic datum.

4.10 Quality Assurance and Quality Control Measures

A summary of the quality assurance and quality control (QA/QC) measures, undertaken as part of this assessment, is provided in the Sampling and Analysis Plan in Appendix 1.

5.0 REVIEW AND EVALUATION

5.1 Geology

Generally, the subsurface profile encountered at the borehole locations consists of fill material, underlain by stiff brown silty clay over top of soft grey silty clay. The surficial fill material was observed to consist of brown silty sand with crushed stone and was noted to extend to depths ranging from approximately 0.23 m to 1.07 m below ground surface. No unusual visual or olfactory observations, as well as any deleterious substances, were identified within the fill material encountered on-site.

The subsurface profile encountered at the test pit locations consists of fill material underlain by native brown silty clay. The fill material was observed to consist of brown silty clay / silty sand, organics, as well as trace brick and asphalt, and was noted to extend to depths ranging from approximately 0.2 m to 0.8 m below ground surface.

Bedrock was not encountered in any of the boreholes or test pits.

Site geology details are provided in the Soil Profile and Test Data Sheets in Appendix 1.

5.2 Groundwater Elevations, Flow Direction, and Hydraulic Gradient

Groundwater levels were measured using an electronic water level meter at the monitoring wells installed in BH4-20, BH5-20, and BH6-20 on November 12, 2020. The groundwater levels are summarized below in Table 4.

| Borehole Location | Ground Surface Elevation (m) | Water Level Depth (m below grade) | Water Level Elevation (m ASL) | Date of Measurement |
|--------------------------|-------------------------------------|--|--------------------------------------|----------------------------|
| BH4-20 | 88.24 | 1.04 | 87.20 | November 12, 2020 |
| BH5-20 | 87.81 | 0.37 | 87.44 | |
| BH6-20 | 87.81 | 0.46 | 87.35 | |

The groundwater at the subject site was encountered within the native grey silty clay, at depths ranging from approximately 0.37 m to 1.04 m below the existing ground surface. No unusual visual or olfactory observations were noted in the groundwater samples recovered from the boreholes.

Using the groundwater elevations recorded during the November 12, 2020 sampling event, groundwater contour mapping was completed as part of this assessment. According to the mapped contour data, illustrated on Drawing PE4999-3 – Test Hole Location Plan in the appendix, the groundwater flow within the Phase II study area is interpreted to be in a northerly direction. A horizontal hydraulic gradient of approximately 0.007 m/m was also calculated as part of this assessment.

It should be noted that groundwater levels are expected to fluctuate throughout the year with seasonal variations.

5.3 Fine/Coarse Soil Texture

Grain size analysis was not completed as part of this investigation. Coarse grained soil standards were chosen as a conservative approach.

5.4 Field Screening

Field screening of the soil samples collected during the drilling program resulted in organic vapour readings ranging from 0.1 ppm to 8.2 ppm. The organic vapour readings obtained from the field screening indicate that there is a negligible potential for the presence of volatile substances. Field screening results of each individual soil sample are provided on the Soil Profile and Test Data Sheets appended to this report.

5.5 Soil Quality

Three (3) soil samples, recovered from BH4-20, BH5-20, and BH6-20, were submitted for laboratory analysis of: BTEX and PHCs (F₁-F₄).

Five (5) soil samples, recovered from test pits TP10-TP14, were submitted for laboratory analysis of either: PHCs (F₂-F₄), PAHs, and/or metals.

The results of the analytical testing are presented below in Tables 5 to 8, as well as on the laboratory certificates of analysis included in Appendix 1.

| Table 5 Analytical Test Results – Soil (Boreholes) (BTEX & PHCs F₁-F₄) | | | | | | |
|--|---------------|---------------------|------------|--------------|--|--|
| Parameter | MDL (µg/g) | Soil Samples (µg/g) | | | MECP Table 1 Background Soil Standards (µg/g) | MECP Table 2 Commercial Soil Standards (µg/g) |
| | | Sept. 29, 2020 | | Nov. 6, 2020 | | |
| | | BH4-20-SS5 | BH5-20-SS4 | BH6-20-SS3 | | |
| Benzene | 0.05 | nd | nd | nd | 0.02 | 0.21 |
| Ethylbenzene | 0.05 | nd | nd | nd | 0.05 | 1.1 |
| Toluene | 0.05 | nd | nd | nd | 0.2 | 2.3 |
| Xylenes | 0.05 | nd | nd | nd | 0.05 | 3.1 |
| PHCs F ₁ | 7 | nd | nd | nd | 25 | 55 |
| PHCs F ₂ | 4 | nd | nd | nd | 10 | 98 |
| PHCs F ₃ | 8 | nd | nd | nd | 240 | 300 |
| PHCs F ₄ | 6 | nd | nd | nd | 120 | 2,800 |
| <i>Notes:</i> <ul style="list-style-type: none"> <input type="checkbox"/> MDL – Method Detection Limit <input type="checkbox"/> nd – not detected above the MDL <input type="checkbox"/> <u>Underlined</u> – Value exceeds MECP Table 1 standards <input type="checkbox"/> <u>Bold and Underlined</u> – value exceeds selected MECP standards | | | | | | |

No BTEX or PHC parameters were detected in the soil samples analyzed. The results are in compliance with the selected MECP Table 2 commercial standards as well as the MECP Table 1 standards.

| Table 6 Analytical Test Results – Soil (Test Pits) (PHCs F ₂ -F ₄) | | | | | | | | |
|---|---------------|---------------------|-------------|-------------|-------------|-------------|--|--|
| Parameter | MDL (µg/g) | Soil Samples (µg/g) | | | | | MECP Table 1 Background Soil Standards (µg/g) | MECP Table 2 Commercial Soil Standards (µg/g) |
| | | Oct. 19, 2020 | | | | | | |
| | | TP10- G1 | TP11- G1 | TP12- G1 | TP13- G1 | TP14- G1 | | |
| PHCs F ₂ | 4 | nd | nd | nd | nd | nd | 10 | 98 |
| PHCs F ₃ | 8 | nd | nd | 40 | nd | 60 | 240 | 300 |
| PHCs F ₄ | 6 | nd | nd | <u>122</u> | nd | <u>188</u> | 120 | 2,800 |
| PHCs F _{4G} | 50 | nt | nt | nt | nt | <u>722</u> | 120 | 2,800 |

Notes:

- MDL – Method Detection Limit
- nd – not detected above the MDL
- nt – not tested for this parameter
- Underlined – Value exceeds MECP Table 1 standards
- Bold and Underlined** – value exceeds selected MECP standards

All detected PHC parameter concentrations in the soil samples analyzed are in compliance with the selected MECP Table 2 commercial standards.

The concentration of PHC F₄ in sample TP12-G1, as well as the concentrations of PHC F₄ and F_{4G} in sample TP14-G1 are in excess of the MECP Table 1 standards. These exceedances are not considered to pose an environmental concern to the subject site, however, if the soil is ever to be removed from the property, it should be classified as contaminated and disposed of at an approved waste disposal site.

| Table 7 Analytical Test Results – Soil (Test Pits) PAHs | | | | | | | | |
|---|---------------|---------------------|-------------|-------------|-------------|-------------|--|--|
| Parameter | MDL (µg/g) | Soil Samples (µg/g) | | | | | MECP Table 1 Background Soil Standards (µg/g) | MECP Table 2 Commercial Soil Standards (µg/g) |
| | | October 19, 2020 | | | | | | |
| | | TP10 -G1 | TP11 -G1 | TP12 -G1 | TP13 -G1 | TP14 -G1 | | |
| Acenaphthene | 0.02 | nd | nd | nd | nd | nd | 0.072 | 7.9 |
| Acenaphthylene | 0.02 | nd | nd | nd | 0.02 | 0.04 | 0.093 | 0.15 |
| Anthracene | 0.02 | nd | nd | nd | 0.07 | 0.09 | 0.16 | 0.67 |
| Benzo[a]anthracene | 0.02 | nd | nd | 0.05 | 0.16 | 0.36 | 0.36 | 0.5 |
| Benzo[a]pyrene | 0.02 | nd | nd | 0.18 | 0.16 | 0.41 | 0.3 | 0.3 |
| Benzo[b]fluoranthene | 0.02 | nd | nd | <u>0.50</u> | 0.18 | 0.79 | 0.47 | 0.78 |
| Benzo[g,h,i]perylene | 0.02 | nd | nd | 0.22 | 0.10 | 0.34 | 0.68 | 6.6 |
| Benzo[k]fluoranthene | 0.02 | nd | nd | 0.14 | 0.09 | 0.44 | 0.48 | 0.78 |
| Chrysene | 0.02 | nd | nd | 0.06 | 0.16 | 0.42 | 2.8 | 7 |
| Dibenzo[a,h]anthracene | 0.02 | nd | nd | 0.04 | 0.03 | 0.08 | 0.1 | 0.1 |
| Fluoranthene | 0.02 | nd | nd | 0.11 | 0.35 | 0.84 | 0.56 | 0.69 |
| Fluorene | 0.02 | nd | nd | nd | nd | nd | 0.12 | 62 |
| Indeno[1,2,3-cd]pyrene | 0.02 | nd | nd | 0.13 | 0.09 | <u>0.29</u> | 0.23 | 0.38 |
| 1-Methylnaphthalene | 0.02 | nd | nd | nd | nd | nd | 0.59 | 0.99 |
| 2-Methylnaphthalene | 0.02 | nd | nd | nd | nd | nd | 0.59 | 0.99 |
| Methylnaphthalene (1&2) | 0.04 | nd | nd | nd | nd | nd | 0.59 | 0.99 |
| Naphthalene | 0.01 | nd | nd | nd | nd | nd | 0.09 | 0.6 |
| Phenanthrene | 0.02 | nd | nd | 0.06 | 0.17 | 0.29 | 0.69 | 6.2 |
| Pyrene | 0.02 | nd | nd | 0.16 | 0.27 | 0.67 | 1 | 78 |

Notes:

- MDL – Method Detection Limit
- nd – not detected above the MDL
- Underlined – Value exceeds MECP Table 1 standards
- Underlined** – value exceeds selected MECP standards

The concentrations of benzo[a]pyrene, benzo[b]fluoranthene, and fluoranthene detected in soil sample TP14-G1 is in excess of the selected MECP Table 2 commercial standards. All remaining PAH parameter concentrations detected in the soil samples analyzed are in compliance with the selected MECP Table 2 commercial standards.

The concentration of benzo[b]fluoranthene detected in soil sample TP12-G1, as well as the concentration of indeno[1,2,3-cd]pyrene detected in soil sample TP14-G1 are in excess of the MECP Table 1 standards. These exceedances are not considered to pose an environmental concern to the subject site, however, if these soils are ever to be removed from the property, they should be classified as contaminated and disposed of at an approved waste disposal site.

| Table 8 Analytical Test Results – Soil (Test Pits) Metals | | | | | | | | |
|--|---------------|---------------------|-------------|-------------|-------------|-------------|--|--|
| Parameter | MDL (µg/g) | Soil Samples (µg/g) | | | | | MECP Table 1 Background Soil Standards (µg/g) | MECP Table 2 Commercial Soil Standards (µg/g) |
| | | October 19, 2020 | | | | | | |
| | | TP10- G1 | TP11- G1 | TP12- G1 | TP13- G1 | TP14- G1 | | |
| Antimony | 1.0 | nd | nd | nd | nd | nd | 1.3 | 7.5 |
| Arsenic | 1.0 | 1.8 | 3.3 | 4.4 | 3.0 | 3.1 | 18 | 18 |
| Barium | 1.0 | 55.3 | 167 | 157 | 116 | 138 | 220 | 390 |
| Beryllium | 0.5 | nd | 0.6 | 0.6 | nd | nd | 2.5 | 4 |
| Boron | 5.0 | nd | nd | 6.2 | 6.2 | 5.4 | 36 | 120 |
| Cadmium | 0.5 | nd | nd | nd | nd | nd | 1.2 | 1.2 |
| Chromium | 5.0 | 15.4 | 69.2 | 69.1 | 48.2 | 53.5 | 70 | 160 |
| Chromium (VI) | 0.2 | nd | nd | nd | nd | nd | 0.66 | 8 |
| Cobalt | 1.0 | 3.6 | 13.7 | 12.0 | 9.0 | 10.9 | 21 | 22 |
| Copper | 5.0 | 5.4 | 26.8 | 22.8 | 17.2 | 23.3 | 92 | 140 |
| Lead | 1.0 | 4.0 | 7.8 | 12.8 | 11.6 | 15.1 | 120 | 120 |
| Mercury | 0.05 | nd | nd | nd | nd | nd | 0.27 | 0.27 |
| Molybdenum | 1.0 | nd | nd | 1.2 | nd | nd | 2 | 6.9 |
| Nickel | 5.0 | 9.3 | 38.5 | 35.5 | 25.0 | 31.1 | 82 | 100 |
| Selenium | 1.0 | nd | nd | nd | nd | nd | 1.5 | 2.4 |
| Silver | 0.3 | nd | nd | nd | nd | nd | 0.5 | 20 |
| Thallium | 1.0 | nd | nd | nd | nd | nd | 1 | 1 |
| Uranium | 1.0 | nd | nd | 2.4 | 1.3 | nd | 2.5 | 23 |
| Vanadium | 10.0 | 15.9 | 54.5 | 56.1 | 39.6 | 51.3 | 86 | 86 |
| Zinc | 20.0 | nd | 65.9 | 84.1 | 53.7 | 65.1 | 290 | 340 |

Notes:

- MDL – Method Detection Limit
- nd – not detected above the MDL
- Underlined – Value exceeds MECP Table 1 standards
- Bold and Underlined** – value exceeds selected MECP standards

All detected metal concentrations in the soil samples analysed are in compliance with the selected MECP Table 2 commercial standards as well as the MECP Table 1 standards.

| Table 9 Maximum Concentrations – Soil | | | |
|---|-------------------------------------|-------------------|-------------------------------|
| Parameter | Maximum Concentration (µg/g) | Sample ID | Depth Interval (m BGS) |
| PHCs F ₃ | 60 | TP14-G1 | 0.1 – 0.2 m |
| PHCs F ₄ | 188 | TP14-G1 | 0.1 – 0.2 m |
| PHCs F _{4G} | <u>722</u> | TP14-G1 | 0.1 – 0.2 m |
| Acenaphthylene | 0.04 | TP14-G1 | 0.1 – 0.2 m |
| Anthracene | 0.09 | TP14-G1 | 0.1 – 0.2 m |
| Benzo[a]anthracene | 0.36 | TP14-G1 | 0.1 – 0.2 m |
| Benzo[a]pyrene | 0.41 | TP14-G1 | 0.1 – 0.2 m |
| Benzo[b]fluoranthene | 0.79 | TP14-G1 | 0.1 – 0.2 m |
| Benzo[g,h,i]perylene | 0.34 | TP14-G1 | 0.1 – 0.2 m |
| Benzo[k]fluoranthene | 0.44 | TP14-G1 | 0.1 – 0.2 m |
| Chrysene | 0.42 | TP14-G1 | 0.1 – 0.2 m |
| Dibenzo[a,h]anthracene | 0.08 | TP14-G1 | 0.1 – 0.2 m |
| Fluoranthene | 0.84 | TP14-G1 | 0.1 – 0.2 m |
| Indeno[1,2,3-cd]pyrene | <u>0.29</u> | TP14-G1 | 0.1 – 0.2 m |
| Phenanthrene | 0.29 | TP14-G1 | 0.1 – 0.2 m |
| Pyrene | 0.67 | TP14-G1 | 0.1 – 0.2 m |
| Arsenic | 4.4 | TP12-G1 | 0.1 – 0.2 m |
| Barium | 167 | TP11-G1 | 0.3 – 0.5 m |
| Beryllium | 0.6 | TP11-G1 / TP12-G1 | 0.3 – 0.5 m / 0.1 – 0.2 m |
| Boron | 6.2 | TP12-G1 / TP13-G1 | 0.1 – 0.2 m / 0.1 – 0.2 m |
| Chromium | 69.2 | TP11-G1 | 0.3 – 0.5 m |
| Cobalt | 13.7 | TP11-G1 | 0.3 – 0.5 m |
| Copper | 26.8 | TP11-G1 | 0.3 – 0.5 m |
| Lead | 15.1 | TP14-G1 | 0.1 – 0.2 m |
| Molybdenum | 1.2 | TP12-G1 | 0.1 – 0.2 m |
| Nickel | 38.5 | TP11-G1 | 0.3 – 0.5 m |
| Uranium | 2.4 | TP12-G1 | 0.1 – 0.2 m |
| Vanadium | 56.1 | TP12-G1 | 0.1 – 0.2 m |
| Zinc | 84.1 | TP12-G1 | 0.1 – 0.2 m |
| <i>Notes:</i> | | | |
| <input type="checkbox"/> <u>Underlined</u> – Value exceeds MECP Table 1 standards <input type="checkbox"/> <u>Bold and Underlined</u> – value exceeds selected MECP standards | | | |

All other parameter concentrations analyzed were below the laboratory detection limits. The laboratory certificates of analysis are provided in Appendix 1.

5.6 Groundwater Quality

Groundwater samples were recovered from the monitoring wells installed in BH4-20, BH5-20, and BH6-20 and submitted for laboratory analysis of: PHCs (F₁-F₄) and VOCs. The results of the analytical testing are presented below in Tables 10 and 11, as well as on the laboratory certificates of analysis included in Appendix 1.

| Table 10 Analytical Test Results – Groundwater PHCs (F₁-F₄) | | | | | |
|--|---------------|----------------------------|------------|---------------|--|
| Parameter | MDL (µg/L) | Groundwater Samples (µg/L) | | | MECP Table 2 Commercial Groundwater Standards (µg/L) |
| | | Oct. 2, 2020 | | Nov. 12, 2020 | |
| | | BH4-20-GW1 | BH5-20-GW1 | BH6-20-GW1 | |
| PHC F ₁ | 25 | nd | nd | nd | 750 |
| PHC F ₂ | 100 | nd | nd | nd | 150 |
| PHC F ₃ | 100 | nd | nd | nd | 500 |
| PHC F ₄ | 100 | nd | nd | nd | 500 |

Notes:

- MDL – Method Detection Limit
- nd – not detected above the MDL
- value exceeds selected MECP standards

No PHC parameters were detected in the groundwater samples analyzed. The results are in compliance with the selected MECP Table 2 commercial standards.

| Table 11 | | | | | |
|--|---------------|----------------------------|------------|----------------------|--|
| Analytical Test Results – Groundwater | | | | | |
| VOCs | | | | | |
| Parameter | MDL (µg/L) | Groundwater Samples (ug/L) | | | MECP Table 2 Residential Groundwater Standards (µg/L) |
| | | October 2, 2020 | | November 12, 2020 | |
| | | BH4-20-GW1 | BH5-20-GW1 | BH6-20-GW1 | |
| Acetone | 5.0 | nd | nd | nd | 2,700 |
| Benzene | 0.5 | nd | nd | nd | 5 |
| Bromodichloromethane | 0.5 | nd | nd | nd | 16 |
| Bromoform | 0.5 | nd | nd | nd | 25 |
| Bromomethane | 0.5 | nd | nd | nd | 0.89 |
| Carbon Tetrachloride | 0.2 | nd | nd | nd | 0.79 |
| Chlorobenzene | 0.5 | nd | nd | nd | 30 |
| Chloroform | 0.5 | nd | nd | nd | 2.4 |
| Dibromochloromethane | 0.5 | nd | nd | nd | 25 |
| Dichlorodifluoromethane | 1.0 | nd | nd | nd | 590 |
| 1,2-Dichlorobenzene | 0.5 | nd | nd | nd | 3 |
| 1,3-Dichlorobenzene | 0.5 | nd | nd | nd | 59 |
| 1,4-Dichlorobenzene | 0.5 | nd | nd | nd | 1 |
| 1,1-Dichloroethane | 0.5 | nd | nd | nd | 5 |
| 1,2-Dichloroethane | 0.5 | nd | nd | nd | 1.6 |
| 1,1-Dichloroethylene | 0.5 | nd | nd | nd | 1.6 |
| cis-1,2-Dichloroethylene | 0.5 | nd | nd | nd | 1.6 |
| trans-1,2-Dichloroethylene | 0.5 | nd | nd | nd | 1.6 |
| 1,2-Dichloropropane | 0.5 | nd | nd | nd | 5 |
| 1,3-Dichloropropene | 0.5 | nd | nd | nd | 0.5 |
| Ethylbenzene | 0.5 | nd | nd | nd | 2.4 |
| Ethylene Dibromide | 0.2 | nd | nd | nd | 0.2 |
| Hexane | 1.0 | nd | nd | nd | 51 |
| Methyl Ethyl Ketone | 5.0 | nd | nd | nd | 1,800 |
| Methyl Isobutyl Ketone | 5.0 | nd | nd | nd | 640 |
| Methyl tert-butyl ether | 2.0 | nd | nd | nd | 15 |
| Methylene Chloride | 5.0 | nd | nd | nd | 20 |
| Styrene | 0.5 | nd | nd | nd | 5.4 |
| 1,1,1,2-Tetrachloroethane | 0.5 | nd | nd | nd | 1.1 |
| 1,1,2,2-Tetrachloroethane | 0.5 | nd | nd | nd | 1 |
| Tetrachloroethylene | 0.5 | nd | nd | nd | 1.6 |
| Toluene | 0.5 | nd | nd | nd | 24 |
| 1,1,1-Trichloroethane | 0.5 | nd | nd | nd | 200 |
| 1,1,2-Trichloroethane | 0.5 | nd | nd | nd | 4.7 |
| Trichloroethylene | 0.5 | nd | nd | nd | 1.6 |
| Trichlorofluoromethane | 1.0 | nd | nd | nd | 150 |
| Vinyl Chloride | 0.5 | nd | nd | nd | 0.5 |
| Xylenes | 0.5 | nd | nd | nd | 300 |

Notes:

- MDL – Method Detection Limit
- nd – not detected above the MDL
- Bold and Underlined** – value exceeds selected MECP standards

No VOC parameters were detected in the groundwater samples analyzed. The results are in compliance with the selected MECP Table 2 commercial standards.

5.7 Quality Assurance and Quality Control Results

All samples submitted as part of this Phase II ESA were handled in accordance with the analytical protocols with respect to holding time, preservation method, storage requirement, and container type. As per Subsection 47(3) of O.Reg. 153/04, as amended by the Environmental Protection Act, the certificates of analysis have been received for each sample submitted for laboratory analysis and have been appended to this report.

As per the Sampling and Analysis Plan, a duplicate groundwater sample was obtained from the monitoring well installed in BH4-20 and analyzed for VOC parameters. No parameter concentrations were detected in both the original or the duplicate samples, and as such, the RPD results are considered to be acceptable. As a result, the quality of the field data collected during this Phase II ESA is considered to be sufficient to meet the overall objectives of this assessment.

5.8 Phase II Conceptual Site Model

The following section has been prepared in accordance with the requirements of O.Reg. 153/04 amended by the Environmental Protection Act. Conclusions and recommendations are discussed in a subsequent section.

Site Description

Potentially Contaminating Activity and Areas of Potential Environmental Concern

As described in the Phase I ESA Update report, as well as in Section 2.2 of this report, the following PCAs, as described by Table 2 of O.Reg. 153/04, are considered to result in APECs on the subject sites:

- Item 30: "Importation of Fill Material of Unknown Quality"*

This PCA was identified as a result of the presence of fill material located within the vicinity of the on-site metal workshop.

- Item 34: "Metal Fabrication"*

This PCA was identified as a result of the historical operation of an on-site metal workshop.

Contaminants of Potential Concern

The contaminants of potential concern (CPCs) associated with the aforementioned APECs are considered to be:

- Benzene, Toluene, Ethylbenzene, and Xylenes (BTEX);
- Petroleum Hydrocarbons, fractions 1 - 4 (PHCs F₁-F₄);
- Volatile Organic Compounds (VOCs);
- Polycyclic Aromatic Hydrocarbons (PAHs);
- Metals (including Mercury and Hexavalent Chromium).

These CPCs have the potential to be present in the soil matrix and/or the groundwater situated beneath the subject sites.

Subsurface Structures and Utilities

Underground service locates were completed prior to the subsurface investigation. No underground utilities were identified on the subject site.

Physical Setting

Site Stratigraphy

The stratigraphy of the subject sites generally consists of:

- Crushed stone (engineered fill); encountered at ground surface and extending to depths of approximately 0.10 m to 0.80 m below ground surface;
- Fill material consisting of brown silty sand; encountered at ground surface and extending to depths of approximately 0.38 m to 1.07 m below ground surface;
- Stiff native brown silty clay; encountered at depths ranging from approximately 0.23 m to 1.07 m below ground surface;
- Soft native grey silty clay; encountered at a depths ranging from approximately 1.98 m to 3.05 m below ground surface.

The site stratigraphy, from ground surface to the deepest aquifer or aquitard investigated, is provided in the Soil Profile and Test Data Sheets in Appendix 1.

Hydrogeological Characteristics

The groundwater beneath the subject site was typically encountered within the native grey silty clay, at depths ranging from approximately 0.37 m to 1.04 m below the existing ground surface. Based on the measured groundwater levels, the groundwater flow direction in the vicinity of the boreholes is interpreted to be in a northerly direction.

Approximate Depth to Bedrock

Bedrock was not encountered in any of the boreholes. According to the available mapping information, the bedrock is interpreted to lie at a depth of approximately 15 m to 50 m below ground level.

Approximate Depth to Water Table

The depth to the water table is approximately 0.37 m to 1.04 m below the existing ground surface.

Sections 41 and 43.1 of Ontario Regulation 153/04

Section 41 of the Regulation does not apply to the subject site, as there are no bodies of water or areas of natural significance located on or within 30 m of the subject site. The subject site is therefore not considered to be environmentally sensitive.

Section 43.1 of the Regulation does not apply to the subject site, since the bedrock is not situated at a depth of less than 2 m below ground surface, and thus is not considered to be a shallow soil property.

Existing Buildings and Structures

The subject site is currently occupied with a two (2) storey, slab-on-grade style metal workshop building (currently abandoned) as well as a storage shed.

Fill Placement

Fill material, consisting of brown silty sand and silty clay was encountered within the test pit locations on the western portion of the study area. Engineered fill consisting of crushed stone was encountered within the borehole locations adjacent to the metal workshop building.

Proposed Buildings and Other Structures

It is our understanding that the land is to be redeveloped for commercial purposes as part of the development of the surrounding subdivision.

Water Bodies and Areas of Natural and Scientific Interest

No areas of natural and scientific interest are known to exist within the Phase I study area. The nearest named water body with respect to the subject site is Mer Bleue Bog, located approximately 2.25 km to the south.

Environmental Condition

Areas Where Contaminants are Present

According to the analytical test results, PAH impacted fill material was identified in TP14, located in the southwestern portion of the Phase II study area.

Types of Contaminants

According to the analytical test results, the concentration of PAHs detected in fill sample TP14-G1 is in excess of the MECP Table 2 commercial standards.

Contaminated Media

As noted above, the fill within the vicinity of TP14-G1 is in excess of the MECP Table 2 commercial standards.

According to the analytical test results, the groundwater beneath the subject site is not contaminated.

What Is Known About Areas Where Contaminants Are Present

TP14 is located within the southwestern portion of the Phase II study area. The PAH contaminants identified in this location are the result of poor-quality fill material placed in this area.

Distribution and Migration of Contaminants

As noted above, PAH impacted soil/fill material was identified within the southwestern portion of the subject site, in the vicinity of TP14. Based on their low mobility, it is anticipated that the PAH contaminants are contained within the soil/fill in this area of the subject site.

Discharge of Contaminants

The PAH impacted fill in the vicinity of TP14 is considered to have resulted from the importation and placement of poor-quality fill material.

Potential for Vapour Intrusion

Based on the non-volatile nature of the contaminants, as well as the slab-on-grade nature of the proposed commercial developments, there is no risk for any future vapour intrusion on the subject site.

Climatic and Meteorological Conditions

In general, climatic and meteorological conditions have the potential to affect contaminant distribution. Two (2) ways by which climatic and meteorological conditions may affect contaminant distribution include the downward leaching of contaminants via the infiltration of precipitation, and the migration of contaminants via groundwater levels and/or flow, which may fluctuate seasonally.

The downward migration of PAH contaminants in the vicinity of TP14 is not suspected to have occurred based on the nature of the contaminants as well as their low concentration. In addition, any fluctuations in the groundwater level and groundwater flow are not considered to have affected any contaminant distribution at this location due to the depth of the water table well below the shallow fill material.

6.0 CONCLUSION

Assessment

A Phase II ESA was conducted for a parcel of land (part of 2284 Mer Bleue Road) situated within the proposed Trail's Edge: Phase 4 (South) residential subdivision development, in the City of Ottawa, Ontario. The purpose of the Phase II ESA was to address the potentially contaminating activities (PCAs) that were identified during the Phase I ESA and were considered to result in areas of potential environmental concern (APECs) on the subject site.

The subsurface investigation for this assessment was conducted on September 29, October 19, and November 6, 2020. The field program consisted of drilling three (3) boreholes (BH4-20, BH5-20, and BH6-20), all of which were instrumented with groundwater monitoring wells, as well as excavating five (5) test pits (TP10-TP14). The boreholes were advanced to depths ranging from approximately 4.42 m to 5.94 m below ground surface and terminated within a layer of saturated native silty clay. The test pits were advanced to depths ranging from approximately 1.28 m to 2.61 m below ground surface and terminated within the underlying native soils.

Site soils generally consist of fill material (brown silty sand with crushed stone), underlain by stiff brown silty clay over top of soft grey silty clay. Bedrock was not encountered in any of the borehole or test pit locations.

Three (3) soil samples, recovered from BH4-20, BH5-20, and BH6-20, were submitted for laboratory analysis of: BTEX and PHCs (F₁-F₄). An additional five (5) soil samples, recovered from test pits TP10-TP14, were submitted for laboratory analysis of either: PHCs (F₂-F₄), PAHs, and/or metals. According to the analytical test results, the concentration of benzo[a]pyrene in soil sample TP14-G1 is in excess of the MECP Table 2 commercial standards.

Three (3) groundwater samples were recovered from the monitoring wells installed in BH4-20, BH5-20, and BH6-20 and submitted for laboratory analysis of VOCs and PHCs (F₁-F₄). According to the analytical test results, all detected parameter concentrations in the groundwater samples analyzed are in compliance with the selected MECP Table 2 commercial standards.

Recommendations

PAH impacted soil/fill material was identified within the vicinity of TP14, located in the southwestern portion of the Phase II study area, requiring some remedial work. It is our understanding that the subject site is to be developed for commercial purposes in conjunction with the neighbouring residential subdivision. Therefore, it is our recommendation that an environmental site remediation program be completed in conjunction with site redevelopment. This will require the segregation of clean soils from impacted fill, the latter of which will require disposal at an approved waste disposal facility.

While in compliance with the site-specific standards, it should be noted that the concentration of PHCs and PAHs within the vicinity of TP12 are in excess of the MECP Table 1 standards. These exceedances are not considered to pose an environmental concern to the subject site, however, if the soil is ever to be removed from the property, it should be classified as contaminated and disposed of at an approved waste disposal site.

Prior to off-site disposal at a licenced landfill site, a leachate analysis of a representative sample of this soil must be conducted in accordance with Ontario Regulation 347/558.

If the groundwater monitoring wells installed in BH4-20, BH5-20, and BH6-20 are not going to be used in the future, or will be destroyed during future redevelopment activities, then they must be decommissioned according to Ontario Regulation Reg. 903 (Ontario Water Resources Act). The monitoring wells will be registered with the MECP under this regulation. Further information can be provided upon request in this regard.

7.0 STATEMENT OF LIMITATIONS

This Phase II – Environmental Site Assessment report has been prepared in general accordance with O.Reg. 153/04, as amended, and meets the requirements of CSA Z769-00. The conclusions presented herein are based on information gathered from a limited sampling and testing program. The test results represent conditions at specific test locations at the time of the field program.

The client should be aware that any information pertaining to soils and all test hole logs are furnished as a matter of general information only and test hole descriptions or logs are not to be interpreted as descriptive of conditions at locations other than those of the test holes themselves.

Should any conditions be encountered at the subject site and/or historical information that differ from our findings, we request that we be notified immediately in order to allow for a reassessment.

This report was prepared for the sole use of Richcraft Group of Companies. Permission and notification from the Richcraft Group of Companies and Paterson Group will be required prior to the release of this report to any other party.

Paterson Group Inc.



Nick Sullivan, B.Sc.



Mark S. D'Arcy, P.Eng., QP_{ESA}



Report Distribution:

- Richcraft Group of Companies
- Paterson Group Inc.

FIGURES

FIGURE 1 - KEY PLAN

DRAWING PE4999-3 – TEST HOLE LOCATION PLAN

**DRAWING PE4999-4 – ANALYTICAL TESTING PLAN – SOIL
(PAHS)**

**DRAWING PE4999-4A – CROSS SECTION A-A' – SOIL
(PAHS)**

**DRAWING PE4999-5 – ANALYTICAL TESTING PLAN – SOIL
(BTEX, PHCS, METALS)**

**DRAWING PE4999-5A – CROSS SECTION A-A' – SOIL
(BTEX, PHCS, METALS)**

**DRAWING PE4999-6 – ANALYTICAL TESTING PLAN –
GROUNDWATER**

DRAWING PE4999-6A – CROSS SECTION A-A' – GROUNDWATER






FIGURE 1
KEY PLAN



- LEGEND:**
- - - PROPERTY BOUNDARY
 - - - PHASE II STUDY AREA BOUNDARY
 - BOREHOLE WITH MONITORING WELL LOCATION
 - TEST PIT LOCATION
 - 87.81 GROUND SURFACE ELEVATION (m)
 - (87.35) GROUNDWATER SURFACE ELEVATION (m) (NOVEMBER 14, 2020)
 - 87.25 GROUNDWATER CONTOURS (m)
 - APPROX. GROUNDWATER FLOW DIRECTION (HORIZONTAL HYDRAULIC GRADIENT)
 - A**—**A'** CROSS SECTION
- GROUND SURFACE ELEVATIONS AT TEST HOLE LOCATIONS ARE REFERENCED TO A GEODETIC DATUM.

patersongroup
consulting engineers

154 Colonnade Road South
Ottawa, Ontario K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344

| NO. | REVISIONS | DATE | INITIAL |
|-----|-----------|------|---------|
| | | | |
| | | | |
| | | | |



RICHCRAFT HOMES LTD.
PHASE II - ENVIRONMENTAL SITE ASSESSMENT
TRAIL'S EDGE - PHASE 4 (SOUTH)
SOUTHERN PARCEL (COMMERCIAL ZONE)

OTTAWA, ONTARIO

TEST HOLE LOCATION PLAN

| | | | |
|--------------|--------|---------------|-----------------|
| Scale: | 1:1000 | Date: | 12/2020 |
| Drawn by: | YA | Report No.: | PE4999-1 |
| Checked by: | NS | Dwg. No.: | PE4999-3 |
| Approved by: | MSD | Revision No.: | |

p:\autocad\drawings\environmental\pe4999\pe4999-phase ii.dwg



TP13-G1 0.10-0.20m October 19, 2020
PAHs comply with MECP Table 2 Standards

TP10-G1 0.10-0.30m October 19, 2020
PAHs comply with MECP Table 2 Standards

TP12-G1 0.10-0.20m October 19, 2020
PAHs comply with MECP Table 2 Standards

| TP14-G1 | 0.10-0.20m | October 19, 2020 |
|---|---------------|------------------|
| Parameter | Result (µg/g) | Standard (µg/g) |
| Benzo[a]pyrene | 0.41 | 0.3 |
| Benzo[b]fluoranthene | 0.79 | 0.78 |
| Fluoranthene | 0.84 | 0.69 |
| Remaining PAHs comply with MECP Table 2 Standards | | |

TP11-G1 0.30-0.50m October 19, 2020
PAHs comply with MECP Table 2 Standards

SOIL RESULT COMPLIES WITH MECP TABLE 2 STANDARDS
SOIL RESULT EXCEEDS MECP TABLE 2 STANDARDS

- LEGEND:**
- PROPERTY BOUNDARY
 - PHASE II STUDY AREA BOUNDARY
 - BOREHOLE WITH MONITORING WELL LOCATION
 - TEST PIT LOCATION
 - 87.81 GROUND SURFACE ELEVATION (m)
 - (87.35) GROUNDWATER SURFACE ELEVATION (m) (NOVEMBER 14, 2020)
 - CROSS SECTION
- GROUND SURFACE ELEVATIONS AT TEST HOLE LOCATIONS ARE REFERENCED TO A GEODETIC DATUM.

patersongroup
consulting engineers

154 Colonnade Road South
Ottawa, Ontario K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344

| NO. | REVISIONS | DATE | INITIAL |
|-----|-----------|------|---------|
| | | | |


OTTAWA, ONTARIO

RICH CRAFT HOMES LTD.
PHASE II - ENVIRONMENTAL SITE ASSESSMENT
TRAIL'S EDGE - PHASE 4 (SOUTH)
SOUTHERN PARCEL (COMMERCIAL ZONE)

Title: **ANALYTICAL TESTING PLAN - SOIL (PAHs)**

| | | | |
|--------------|--------|---------------|-----------------|
| Scale: | 1:1000 | Date: | 12/2020 |
| Drawn by: | YA | Report No.: | PE4999-1 |
| Checked by: | NS | Dwg. No.: | PE4999-4 |
| Approved by: | MSD | Revision No.: | |

p:\autocad\drawings\environmental\pe4999\pe4999-phase ii.dwg



SOIL RESULT COMPLIES WITH MECP TABLE 2 STANDARDS

SOIL RESULT EXCEEDS MECP TABLE 2 STANDARDS



patersongroup
consulting engineers

154 Colonnade Road South
Ottawa, Ontario K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344

| NO. | REVISIONS | DATE | INITIAL |
|-----|-----------|------|---------|
| | | | |
| | | | |
| | | | |

OTTAWA, ONTARIO
 RICHCRAFT HOMES LTD.
 PHASE II - ENVIRONMENTAL SITE ASSESSMENT
 TRAIL'S EDGE - PHASE 4 (SOUTH)
 SOUTHERN PARCEL (COMMERCIAL ZONE)
CROSS SECTION A-A' - SOIL (PAHs)

| | | | |
|--------------|----------|---------------|------------------|
| Scale: | AS SHOWN | Date: | 12/2020 |
| Drawn by: | YA | Report No.: | PE4999-1 |
| Checked by: | NS | Dwg. No.: | PE4999-4A |
| Approved by: | MSD | Revision No.: | |



TP13-G1 0.10-0.20m October 19, 2020
 PHCs and Metals comply with MECP Table 2 Standards

TP10-G1 0.10-0.30m October 19, 2020
 PHCs and Metals comply with MECP Table 2 Standards

TP12-G1 0.10-0.20m October 19, 2020
 PHCs and Metals comply with MECP Table 2 Standards

BH6-20-SS3 1.52-2.13m November 6, 2020
 BTEX and PHCs comply with MECP Table 2 Standards

TP14-G1 0.10-0.20m October 19, 2020
 PHCs and Metals comply with MECP Table 2 Standards

BH4-20-SS5 3.05-3.66m September 29, 2020
 BTEX and PHCs comply with MECP Table 2 Standards

BH5-20-SS4 2.29-2.90m September 29, 2020
 BTEX and PHCs comply with MECP Table 2 Standards

TP11-G1 0.30-0.50m October 19, 2020
 PHCs and Metals comply with MECP Table 2 Standards

- LEGEND:**
- - - PROPERTY BOUNDARY
 - - - PHASE II STUDY AREA BOUNDARY
 - BOREHOLE WITH MONITORING WELL LOCATION
 - TEST PIT LOCATION
 - 87.81 GROUND SURFACE ELEVATION (m)
 - (87.35) GROUNDWATER SURFACE ELEVATION (m) (NOVEMBER 14, 2020)
 - CROSS SECTION
- GROUND SURFACE ELEVATIONS AT TEST HOLE LOCATIONS ARE REFERENCED TO A GEODETIC DATUM.

SOIL RESULT COMPLIES WITH MECP TABLE 2 STANDARDS

SOIL RESULT EXCEEDS MECP TABLE 2 STANDARDS

patersongroup
 consulting engineers

154 Colonnade Road South
 Ottawa, Ontario K2E 7J5
 Tel: (613) 226-7381 Fax: (613) 226-6344

| NO. | REVISIONS | DATE | INITIAL |
|-----|-----------|------|---------|
| | | | |
| | | | |
| | | | |

RICHCRAFT HOMES LTD.
PHASE II - ENVIRONMENTAL SITE ASSESSMENT
TRAIL'S EDGE - PHASE 4 (SOUTH)
SOUTHERN PARCEL (COMMERCIAL ZONE)

OTTAWA, ONTARIO

Title: **ANALYTICAL TESTING PLAN - SOIL (BTEX, PHCs, METALS)**


| | | | |
|--------------|--------|---------------|-----------------|
| Scale: | 1:1000 | Date: | 12/2020 |
| Drawn by: | YA | Report No.: | PE4999-1 |
| Checked by: | NS | Dwg. No.: | PE4999-5 |
| Approved by: | MSD | Revision No.: | |

p:\autocad\drawings\environmental\pe4999\pe4999-phase ii.dwg

TP14-G1 0.10-0.20m October 19, 2020
 PHCs and Metals comply with MECP Table 2 Standards

BH6-20-SS3 1.52-2.13m November 6, 2020
 BTEX and PHCs comply with MECP Table 2 Standards

BH4-20-SS5 3.05-3.66m September 29, 2020
 BTEX and PHCs comply with MECP Table 2 Standards



SOIL RESULT COMPLIES WITH MECP TABLE 2 STANDARDS

SOIL RESULT EXCEEDS MECP TABLE 2 STANDARDS

patersongroup
 consulting engineers

154 Colonnade Road South
 Ottawa, Ontario K2E 7J5
 Tel: (613) 226-7381 Fax: (613) 226-6344



| NO. | REVISIONS | DATE | INITIAL |
|-----|-----------|------|---------|
| | | | |
| | | | |
| | | | |

OTTAWA, ONTARIO
 Title: **CROSS SECTION A-A' - SOIL (BTEX, PHCs, METALS)**

RICH CRAFT HOMES LTD.
 PHASE II - ENVIRONMENTAL SITE ASSESSMENT
 TRAIL'S EDGE - PHASE 4 (SOUTH)
 SOUTHERN PARCEL (COMMERCIAL ZONE)

| | | | |
|--------------|----------|---------------|------------------|
| Scale: | AS SHOWN | Date: | 12/2020 |
| Drawn by: | YA | Report No.: | PE4999-1 |
| Checked by: | NS | Dwg. No.: | PE4999-5A |
| Approved by: | MSD | Revision No.: | |

p:\autocad drawings\environmental\pe4999\pe4999-phase ii.dwg



BH6-20-GW1 1.42-4.42m November 12, 2020
 PHCs and VOCs comply with MECP Table 2 Standards

BH4-20-GW1 2.94-5.94m October 2, 2020
 PHCs and VOCs comply with MECP Table 2 Standards

BH5-20-GW1 2.94-5.94m October 2, 2020
 PHCs and VOCs comply with MECP Table 2 Standards

- LEGEND:**
- - - PROPERTY BOUNDARY
 - - - PHASE II STUDY AREA BOUNDARY
 - BOREHOLE WITH MONITORING WELL LOCATION
 - TEST PIT LOCATION
 - 87.81 GROUND SURFACE ELEVATION (m)
 - (87.35) GROUNDWATER SURFACE ELEVATION (m) (NOVEMBER 14, 2020)
 - CROSS SECTION
- GROUND SURFACE ELEVATIONS AT TEST HOLE LOCATIONS ARE REFERENCED TO A GEODETIC DATUM.

GROUNDWATER RESULT COMPLIES WITH MECP TABLE 2 STANDARDS

GROUNDWATER RESULT EXCEEDS MECP TABLE 2 STANDARDS

patersongroup
 consulting engineers

154 Colonnade Road South
 Ottawa, Ontario K2E 7J5
 Tel: (613) 226-7381 Fax: (613) 226-6344


| NO. | REVISIONS | DATE | INITIAL |
|-----|-----------|------|---------|
| | | | |
| | | | |
| | | | |

RICHCRAFT HOMES LTD.
 PHASE II - ENVIRONMENTAL SITE ASSESSMENT
 TRAIL'S EDGE - PHASE 4 (SOUTH)
 SOUTHERN PARCEL (COMMERCIAL ZONE) ONTARIO

OTTAWA,
 Title: **ANALYTICAL TESTING PLAN - GROUNDWATER (PHCs, VOCs)**

| | | | |
|--------------|--------|---------------|-----------------|
| Scale: | 1:1000 | Date: | 12/2020 |
| Drawn by: | YA | Report No.: | PE4999-1 |
| Checked by: | NS | Dwg. No.: | PE4999-6 |
| Approved by: | MSD | Revision No.: | |

p:\autocad\drawings\environmental\pe4999\pe4999-phase ii.dwg



GROUNDWATER RESULT COMPLIES WITH MECP TABLE 2 STANDARDS

GROUNDWATER RESULT EXCEEDS MECP TABLE 2 STANDARDS

patersongroup
consulting engineers

154 Colonnade Road South
Ottawa, Ontario K2E 7J5
Tel: (613) 226-7381 Fax: (613) 226-6344

| NO. | REVISIONS | DATE | INITIAL |
|-----|-----------|------|---------|
| | | | |
| | | | |
| | | | |

OTTAWA, ONTARIO

RICH CRAFT HOMES LTD.
PHASE II - ENVIRONMENTAL SITE ASSESSMENT
TRAIL'S EDGE - PHASE 4 (SOUTH)
SOUTHERN PARCEL (COMMERCIAL ZONE)

Title:
CROSS SECTION A-A' - GROUNDWATER (PHCs, VOCs)

| | | | |
|--------------|----------|---------------|------------------|
| Scale: | AS SHOWN | Date: | 12/2020 |
| Drawn by: | YA | Report No.: | PE4999-1 |
| Checked by: | NS | Dwg. No.: | PE4999-6A |
| Approved by: | MSD | Revision No.: | |

p:\autocad\drawings\environmental\pe4999\pe4999-phase ii.dwg

APPENDIX 1

SAMPLING AND ANALYSIS PLAN

SOIL PROFILE AND TEST DATA SHEETS

SYMBOLS AND TERMS

LABORATORY CERTIFICATES OF ANALYSIS



Geotechnical
Engineering

Environmental
Engineering

Hydrogeology

Geological
Engineering

Materials Testing

Building Science

Archaeological
Services

Sampling & Analysis Plan

Phase II – Environmental Site Assessment
Trail's Edge: Phase 4 (South)
Southern Parcel (Commercial Zone)
Part of 2284 Mer Bleue Road
Ottawa, Ontario

Prepared For

Richcraft Group of Companies

Paterson Group Inc.

Consulting Engineers
154 Colonnade Road South
Ottawa (Nepean), Ontario
Canada K2E 7J5

Tel: (613) 226-7381
Fax: (613) 226-6344
www.patersongroup.ca

September 21, 2020

Report: PE4999-1-SAP

TABLE OF CONTENTS

1.0 SAMPLING PROGRAM 1
2.0 ANALYTICAL TESTING PROGRAM..... 2
3.0 STANDARD OPERATING PROCEDURES 3
 3.1 Environmental Drilling Procedure 3
 3.2 Monitoring Well Installation Procedure 6
 3.3 Monitoring Well Sampling Procedure 7
4.0 QUALITY ASSURANCE/QUALITY CONTROL (QA/QC) 8
5.0 DATA QUALITY OBJECTIVES 9
6.0 PHYSICAL IMPEDIMENTS..... 10

1.0 SAMPLING PROGRAM

Paterson Group Inc. (Paterson) was commissioned by Richcraft Group of Companies to conduct a Phase II – Environmental Site Assessment (Phase II ESA) for a portion of land within the proposed Trail's Edge: Phase 4 (South) subdivision development, in the City of Ottawa, Ontario.

This Phase II ESA was completed in conjunction with the Phase II ESA work carried out on another portion of the Trail's Edge: Phase 4 (South) development.

Based on the findings of the Phase I ESA, the following subsurface investigation program was developed.

| Borehole/ Test Pit | Location & Rationale | Proposed Depth & Rationale |
|-----------------------|---|--|
| BH4-20 | Northern portion of Phase II study area; to assess for potential impacts resulting from a former metal workshop as well as the presence of fill material of unknown quality. | 4-7 m; to intercept the groundwater table for the purpose of installing a groundwater monitoring well. |
| BH5-20 | South-central portion of Phase II study area; to assess for potential impacts resulting from a former metal workshop as well as the presence of fill material of unknown quality. | 4-7 m; to intercept the groundwater table for the purpose of installing a groundwater monitoring well. |
| BH6-20 | Central portion of Phase II study area; to assess for potential impacts resulting from a former metal workshop as well as the presence of fill material of unknown quality. | 4-7 m; to intercept the groundwater table for the purpose of installing a groundwater monitoring well. |
| TP10-TP14 | Throughout the Phase II study area; to assess for potential impacts resulting from the presence of fill material of unknown quality. | 0-0.5 m; for general coverage purposes. |

Borehole and grab sample locations are shown on Drawing PE4999-3 – Test Hole Location Plan, appended to the main report.

At each borehole, split-spoon samples of the overburden soils will be obtained at 0.76 m (2'6") intervals until practical refusal to augering. All soil samples will be retained, and samples will be selected for submission following a preliminary screening analysis.

Following the borehole drilling, groundwater monitoring wells will be installed in all boreholes (BH4-20 to BH6-20) for the collection of groundwater samples.

2.0 ANALYTICAL TESTING PROGRAM

The analytical testing program for soil at the subject site is based on the following general considerations:

- At least one sample from each borehole should be submitted, in order to delineate the horizontal extent of contamination across the site.
- At least one sample from each stratigraphic unit should be submitted, in order to delineate the vertical extent of contamination at the site.
- In boreholes where there is visual or olfactory evidence of contamination, or where organic vapour meter or photoionization detector readings indicate the presence of contamination, the 'worst-case' sample from each borehole should be submitted for comparison with MECP site condition standards.
- In boreholes with evidence of contamination as described above, a sample should be submitted from the stratigraphic unit below the 'worst-case' sample to determine whether the contaminant(s) have migrated downward.
- Parameters analyzed should be consistent with the Contaminants of Potential Concern identified in the Phase I ESA.

The analytical testing program for soil at the subject site is based on the following general considerations:

- Groundwater monitoring wells should be installed in all boreholes with visual or olfactory evidence of soil contamination, in stratigraphic units where soil contamination was encountered, where those stratigraphic units are at or below the water table (i.e. a water sample can be obtained).
- Groundwater monitoring well screens should straddle the water table at sites where the contaminants of concern are suspected to be LNAPLs.
- At least one groundwater monitoring well should be installed in a stratigraphic unit below the suspected contamination, where said stratigraphic unit is water-bearing.
- Parameters analyzed should be consistent with the Contaminants of Concern identified in the Phase I ESA and with the contaminants identified in the soil samples.

3.0 STANDARD OPERATING PROCEDURES

3.1 Environmental Drilling Procedure

Purpose

The purpose of environmental boreholes is to identify and/or delineate contamination within the soil and/or to install groundwater monitoring wells in order to identify contamination within the groundwater.

Equipment

The following is a list of equipment that is in addition to regular drilling equipment stated in the geotechnical drilling SOP:

- Glass soil sample jars
- two buckets
- cleaning brush (toilet brush works well)
- dish detergent
- methyl hydrate
- water (if not available on site - water jugs available in trailer)
- latex or nitrile gloves (depending on suspected contaminant)
- RKI Eagle organic vapour meter or MiniRae photoionization detector (depending on contamination suspected)

Determining Borehole Locations

If conditions on site are not as suspected, and planned borehole locations cannot be drilled, **call the office to discuss**. Alternative borehole locations will be determined in conversation with the field technician and supervising engineer.

After drilling is completed a plan with the borehole locations must be provided. Distances and orientations of boreholes with respect to site features (buildings, roadways, etc.) must be provided. Distances should be measured using a measuring tape or wheel rather than paced off. Ground surface elevations at each borehole should be surveyed relative to a geodetic benchmark, if one is available, or a temporary site benchmark which can be tied in at a later date if necessary.

Drilling Procedure

The actual drilling procedure for environmental boreholes is the same as geotechnical boreholes (see SOP for drilling and sampling) with a few exceptions as follows:

- Continuous split spoon samples (every 0.6 m or 2') or semi-continuous (every 0.76 m or 2'6") are required.
- Make sure samples are well sealed in plastic bags with no holes prior to screening and are kept cool but unfrozen.
- If sampling for VOCs, BTEX, or PHCs F₁, a soil core from each soil sample, which may be analyzed, must be taken and placed in the laboratory-provided methanol vial.
- Note all and any odours or discolouration of samples.
- Split spoon samplers must be washed between samples.
- If obvious contamination is encountered, continue sampling until vertical extent of contamination is delineated.
- As a general rule, environmental boreholes should be deep enough to intercept the groundwater table (unless this is impossible/impractical - call project manager to discuss).
- If at all possible, soil samples should be submitted to a preliminary screening procedure on site, either using a RKI Eagle, PID, etc. depending on type of suspected contamination.

Spoon Washing Procedure

All sampling equipment (spilt spoons, etc.) must be washed between samples in order to prevent cross contamination of soil samples.

- Obtain two buckets of water (preferably hot if available)
- Add a small amount of dish soap to one bucket
- Scrub spoons with brush in soapy water, inside and out, including tip
- Rinse in clean water
- Apply a small amount of methyl hydrate to the inside of the spoon. (A spray bottle or water bottle with a small hole in the cap works well)
- Allow to dry (takes seconds)
- Rinse with distilled water, a spray bottle works well.

The methyl hydrate eliminates any soap residue that may be on the spoon and is especially important when dealing with suspected VOCs.

Screening Procedure

The RKI Eagle is used to screen most soil samples, particularly where petroleum hydrocarbon contamination is suspected. The MiniRae is used when VOCs are suspected, however it also can be useful for detecting petroleum. These tools are for screening purposes only and cannot be used in place of laboratory testing. Vapour results obtained from the RKI Eagle and the PID are relative and must be interpreted.

Screening equipment should be calibrated on an approximately monthly basis, more frequently if heavily used.

- Samples should be brought to room temperature; this is specifically important in colder weather. Soil must not be frozen.
- Turn instrument on and allow to come to zero - calibrate if necessary
- If using RKI Eagle, ensure instrument is in methane elimination mode unless otherwise directed.
- Ensure measurement units are ppm (parts per million) initially. RKI Eagle will automatically switch to %LEL (lower explosive limit) if higher concentrations are encountered.
- Break up large lumps of soil in the sample bag, taking care not to puncture bag.
- Insert probe into soil bag, creating a seal with your hand around the opening.
- Gently manipulate soil in bag while observing instrument readings.
- Record the highest value obtained in the first 15 to 25 seconds
- Make sure to indicate scale (ppm or LEL); also note which instrument was used (RKI Eagle 1 or 2, or MiniRae).
- Jar samples and refrigerate as per Sampling and Analysis Plan.

3.2 Monitoring Well Installation Procedure

Equipment

- 5' x 2" threaded sections of Schedule 40 PVC slotted well screen (5' x 1 ¼" if installing in cored hole in bedrock)
- 5' x 2" threaded sections of Schedule 40 PVC riser pipe (5' x 1 ¼" if installing in cored hole in bedrock)
- Threaded end-cap
- Slip-cap or J-plug
- Asphalt cold patch or concrete
- Silica Sand
- Bentonite chips (Holeplug)
- Steel flushmount casing

Procedure

- Drill borehole to required depth, using drilling and sampling procedures described above.
- If borehole is deeper than required monitoring well, backfill with bentonite chips to required depth. This should only be done on wells where contamination is not suspected, in order to prevent downward migration of contamination.
- Only one monitoring well should be installed per borehole.
- Monitoring wells should not be screened across more than one stratigraphic unit to prevent potential migration of contaminants between units.
- Where LNAPLs are the suspected contaminants of concern, monitoring wells should be screened straddling the water table in order to capture any free product floating on top of the water table.
- Thread the end cap onto a section of screen. Thread second section of screen if required. Thread risers onto screen. Lower into borehole to required depth. Ensure slip-cap or J-plug is inserted to prevent backfill materials entering well.
- As drillers remove augers, backfill borehole annulus with silica sand until the level of sand is approximately 0.3 m above the top of the screen.
- Backfill with holeplug until at least 0.3 m of holeplug is present above the top of the silica sand.
- Backfill remainder of borehole with holeplug or with auger cuttings (if contamination is not suspected).
- Install flushmount casing. Seal space between flushmount and borehole annulus with concrete, cold patch, or holeplug to match surrounding ground surface.

3.3 Monitoring Well Sampling Procedure

Equipment

- Water level metre or interface probe on hydrocarbon/LNAPL sites
- Spray bottles containing water and methanol to clean water level tape or interface probe
- Peristaltic pump
- Polyethylene tubing for peristaltic pump
- Flexible tubing for peristaltic pump
- Latex or nitrile gloves (depending on suspected contaminant)
- Allen keys and/or 9/16" socket wrench to remove well caps
- Graduated bucket with volume measurements
- pH/Temperature/Conductivity combo pen
- Laboratory-supplied sample bottles

Sampling Procedure

- Locate well and use socket wrench or Allan key to open metal flush mount protector cap. Remove plastic well cap.
- Measure water level, with respect to existing ground surface, using water level meter or interface probe. If using interface probe on suspected NAPL site, measure the thickness of free product.
- Measure total depth of well.
- Clean water level tape or interface probe using methanol and water. Change gloves between wells.
- Calculate volume of standing water within well and record.
- Insert polyethylene tubing into well and attach to peristaltic pump. Turn on peristaltic pump and purge into graduated bucket. Purge at least three well volumes of water from the well. Measure and record field chemistry. Continue to purge, measuring field chemistry after every well volume purged, until appearance or field chemistry stabilizes.
- Note appearance of purge water, including colour, opacity (clear, cloudy, silty), sheen, presence of LNAPL, and odour. Note any other unusual features (particulate matter, effervescence (bubbling) of dissolved gas, etc.).
- Fill required sample bottles. If sampling for metals, attach 75-micron filter to discharge tube and filter metals sample. If sampling for VOCs, use low flow rate to ensure continuous stream of non-turbulent flow into sample bottles. Ensure no headspace is present in VOC vials.
- Replace well cap and flushmount casing cap.

4.0 QUALITY ASSURANCE/QUALITY CONTROL (QA/QC)

The QA/QC program for this Phase II ESA is as follows:

- All non-dedicated sampling equipment (split spoons) will be decontaminated according to the SOPs listed above.
- All groundwater sampling equipment is dedicated (polyethylene and flexible peristaltic tubing is replaced for each well).
- Where groundwater samples are to be analyzed for VOCs, one laboratory-provided trip blank will be submitted for analysis with every laboratory submission.
- Approximately one (1) field duplicate will be submitted for every ten (10) samples submitted for laboratory analysis. A minimum of one (1) field duplicate per project will be submitted. Field duplicates will be submitted for soil and groundwater samples
- Where combo pens are used to measure field chemistry, they will be calibrated on an approximately monthly basis, according to frequency of use.

5.0 DATA QUALITY OBJECTIVES

The purpose of setting data quality objectives (DQOs) is to ensure that the level of uncertainty in data collected during the Phase II ESA is low enough that decision-making is not affected, and that the overall objectives of the investigation are met.

The quality of data is assessed by comparing field duplicates with original samples. If the relative percent difference (RPD) between the duplicate and the sample is within 20%, the data are considered to be of sufficient quality so as not to affect decision-making. The RPD is calculated as follows:

$$RPD = \left| \frac{x_1 - x_2}{(x_1 + x_2)/2} \right| \times 100\%$$

Where x_1 is the concentration of a given parameter in an original sample and x_2 is the concentration of that same parameter in the field duplicate sample.

For the purpose of calculating the RPD, it is desirable to select field duplicates from samples for which parameters are present in concentrations above laboratory detection limits, i.e. samples which are expected to be contaminated. If parameters are below laboratory detection limits for selected samples or duplicates, the RPD may be calculated using a concentration equal to one half the laboratory detection limit.

It is also important to consider data quality in the overall context of the project. For example, if the DQOs are not met for a given sample, yet the concentrations of contaminants in both the sample and the duplicate exceed the MOE site remediation standards by a large margin, the decision-making usefulness of the sample may not be considered to be impaired. The proximity of other samples which meet the DQOs must also be considered in developing the Phase II Conceptual Site Model; often there are enough data available to produce a reliable Phase II Conceptual Site Model even if DQOs are not met for certain individual samples.

These considerations are discussed in the body of the report.

6.0 PHYSICAL IMPEDIMENTS

Physical impediments to the Sampling and Analysis plan may include:

- The location of underground utilities
- Poor recovery of split-spoon soil samples
- Insufficient groundwater volume for groundwater samples
- Breakage of sampling containers following sampling or while in transit to the laboratory
- Elevated detection limits due to matrix interference (generally related to soil colour or presence of organic material)
- Elevated detection limits due to high concentrations of certain parameters, necessitating dilution of samples in laboratory
- Drill rig breakdowns
- Winter conditions
- Other site-specific impediments

Site-specific impediments to the Sampling and Analysis plan are discussed in the body of the Phase II ESA report.

DATUM Geodetic


REMARKS

BORINGS BY Track-Mount Power Auger

DATE September 29, 2020

FILE NO. **PE4999**

HOLE NO. **BH 4-20**



DATUM Geodetic

FILE NO. **PE4999**

REMARKS

HOLE NO. **BH 5-20**

BORINGS BY Track-Mount Power Auger

DATE September 29, 2020

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE | | | | DEPTH (m) | ELEV. (m) | Photo Ionization Detector | | | | Monitoring Well Construction | |
|---|-------------|--------|--------|------------|----------------|-----------|-----------|----------------------------------|-----|-----|-----|------------------------------|--|
| | | TYPE | NUMBER | RECOVERY % | N VALUE or RQD | | | ● Volatile Organic Rgd. (ppm) | | | | | |
| GROUND SURFACE | | | | | | | | ○ Lower Explosive Limit % | | | | | |
| | | | | | | | | 20 | 40 | 60 | 80 | | |
| FILL: Crushed stone with sand and clay | 0.23 | AU | 1 | | | 0 | 87.81 | | | | | | |
| Stiff, brown SILTY CLAY - firm to soft and grey by 2.3m depth | | SS | 2 | 92 | 9 | 1 | 86.81 | | | | | | |
| | | SS | 3 | 100 | 6 | 2 | 85.81 | | | | | | |
| | | SS | 4 | 100 | 2 | 3 | 84.81 | | | | | | |
| | | SS | 5 | 100 | W | 4 | 83.81 | | | | | | |
| | | SS | 6 | 100 | W | 5 | 82.81 | | | | | | |
| | | SS | 7 | 100 | W | | | | | | | | |
| | | SS | 8 | 100 | W | | | | | | | | |
| | | 5.94 | | | | | | | | | | | |
| End of Borehole (GWL @ 0.37m - Nov. 12, 2020) | | | | | | | | | | | | | |
| | | | | | | | | 100 | 200 | 300 | 400 | 500 | |
| | | | | | | | | RKI Eagle Rgd. (ppm) | | | | | |
| | | | | | | | | ▲ Full Gas Resp. △ Methane Elim. | | | | | |

DATUM Geodetic


REMARKS

BORINGS BY CME-55 Low Clearance Drill

DATE November 6, 2020

FILE NO. **PE4999**

HOLE NO. **BH 6-20**



SOIL PROFILE AND TEST DATA

Phase II - Environmental Site Assessment
Trail's Edge: Phase 4 (South)
Ottawa, Ontario

DATUM Geodetic

FILE NO. **PE4999**

REMARKS

HOLE NO. **TP10**

BORINGS BY Backhoe

DATE October 19, 2020

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE | | | | DEPTH (m) | ELEV. (m) | Photo Ionization Detector | | | | Monitoring Well Construction |
|--|-------------|--------|--------|------------|----------------|-----------|-----------|---|----|----|----|------------------------------|
| | | TYPE | NUMBER | RECOVERY % | N VALUE or RQD | | | <input checked="" type="radio"/> Volatile Organic Rdg. (ppm) <input type="radio"/> Lower Explosive Limit % | | | | |
| GROUND SURFACE | | | | | | 0 | 87.55 | 20 | 40 | 60 | 80 | |
| FILL: Crushed stone | 0.10 | | | | | | | | | | | |
| FILL: Brown silty sand, some crushed stone, trace clay, topsoil, organics | 0.48 | G | 1 | | | | | | | | | |
| FILL: Brown silty clay, trace sand and gravel | 0.82 | G | 2 | | | | | | | | | |
| Brown SILTY CLAY | | | | | | 1 | 86.55 | | | | | |
| End of Test Pit | 1.85 | | | | | | | | | | | |

100 200 300 400 500

RKI Eagle Rdg. (ppm)

▲ Full Gas Resp. △ Methane Elim.

SOIL PROFILE AND TEST DATA

Phase II - Environmental Site Assessment
Trail's Edge: Phase 4 (South)
Ottawa, Ontario

DATUM Geodetic




REMARKS

BORINGS BY Backhoe

DATE October 19, 2020

FILE NO. **PE4999**

HOLE NO. **TP11**

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE | | | | DEPTH (m) | ELEV. (m) | Photo Ionization Detector | | | | Monitoring Well Construction | |
|---|--|--------|--------|------------|----------------|-----------|-----------|-------------------------------|---------------------------|----|----|------------------------------|----|
| | | TYPE | NUMBER | RECOVERY % | N VALUE or RQD | | | ● Volatile Organic Rdg. (ppm) | ○ Lower Explosive Limit % | 20 | 40 | | 60 |
| GROUND SURFACE | | | | | | 0 | 87.73 | | | | | | |
| FILL: Brown silty clay, some sand, trace gravel, cobbles and boulders |  | G | 1 | | | | | ● | | | | | |
| | 0.64 | | | | | | | | | | | | |
| TOPSOIL |  | G | 2 | | | | | ● | | | | | |
| | 0.91 | | | | | | | | | | | | |
| Brown SILTY CLAY |  | G | 3 | | | 1 | 86.73 | ● | | | | | |
| | 1.82 | | | | | | | | | | | | |
| End of Test Pit | | | | | | | | | | | | | |

100 200 300 400 500
RKI Eagle Rdg. (ppm)
▲ Full Gas Resp. △ Methane Elim.

SOIL PROFILE AND TEST DATA

Phase II - Environmental Site Assessment
Trail's Edge: Phase 4 (South)
Ottawa, Ontario

DATUM Geodetic



REMARKS

BORINGS BY Backhoe

DATE October 19, 2020

FILE NO. **PE4999**

HOLE NO. **TP13**

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE | | | | DEPTH (m) | ELEV. (m) | Photo Ionization Detector | | | | Monitoring Well Construction |
|---|--|--------|--------|------------|----------------|-----------|-----------|-------------------------------|---------------------------|----|----|------------------------------|
| | | TYPE | NUMBER | RECOVERY % | N VALUE or RQD | | | ● Volatile Organic Rdg. (ppm) | ○ Lower Explosive Limit % | | | |
| GROUND SURFACE | | | | | | 0 | 87.64 | 20 | 40 | 60 | 80 | |
| FILL: Brown silty clay, some sand and gravel, trace cobbles, topsoil |  | G | 1 | | | | | | | | | |
| | 0.41 | | | | | | | | | | | |
| Light reddish brown SILTY CLAY - brown by 0.8m depth |  | | | | | 1 | 86.64 | | | | | |
| | 1.81 | G | 2 | | | | | | | | | |
| End of Test Pit | | | | | | | | | | | | |

100 200 300 400 500
RKI Eagle Rdg. (ppm)
▲ Full Gas Resp. △ Methane Elim.

SOIL PROFILE AND TEST DATA

Phase II - Environmental Site Assessment
Trail's Edge: Phase 4 (South)
Ottawa, Ontario

DATUM Geodetic

REMARKS

BORINGS BY Backhoe

DATE October 19, 2020

FILE NO. **PE4999**

HOLE NO. **TP14**

| SOIL DESCRIPTION | STRATA PLOT | SAMPLE | | | | DEPTH (m) | ELEV. (m) | Photo Ionization Detector | | | | Monitoring Well Construction | |
|---|----------------------------|--------|--------|------------|----------------|-----------|-----------|-------------------------------|---------------------------|----|----|------------------------------|----|
| | | TYPE | NUMBER | RECOVERY % | N VALUE or RQD | | | ● Volatile Organic Rdg. (ppm) | ○ Lower Explosive Limit % | 20 | 40 | | 60 |
| GROUND SURFACE | | | | | | 0 | 87.44 | | | | | | |
| FILL: Brown/black silty sand, some clay and gravel, trace cobbles | [Cross-hatched pattern] | G | 1 | | | | | ● | | | | | |
| | | | | | | | | | | | | | |
| | 0.54 | | | | | | | | | | | | |
| Brown SILTY CLAY | [Diagonal hatched pattern] | G | 2 | | | | | ● | | | | | |
| | | | | | | | | | | | | | |
| | 1.42 | | | | | 1 | 86.44 | | | | | | |
| End of Test Pit | | | | | | | | | | | | | |

100 200 300 400 500
RKI Eagle Rdg. (ppm)
 ▲ Full Gas Resp. △ Methane Elim.

SYMBOLS AND TERMS

SOIL DESCRIPTION

Behavioural properties, such as structure and strength, take precedence over particle gradation in describing soils. Terminology describing soil structure are as follows:

| | | |
|------------------|---|--|
| Desiccated | - | having visible signs of weathering by oxidation of clay minerals, shrinkage cracks, etc. |
| Fissured | - | having cracks, and hence a blocky structure. |
| Varved | - | composed of regular alternating layers of silt and clay. |
| Stratified | - | composed of alternating layers of different soil types, e.g. silt and sand or silt and clay. |
| Well-Graded | - | Having wide range in grain sizes and substantial amounts of all intermediate particle sizes (see Grain Size Distribution). |
| Uniformly-Graded | - | Predominantly of one grain size (see Grain Size Distribution). |

The standard terminology to describe the relative strength of cohesionless soils is the compactness condition, usually inferred from the results of the Standard Penetration Test (SPT) 'N' value. The SPT N value is the number of blows of a 63.5 kg hammer, falling 760 mm, required to drive a 51 mm O.D. split spoon sampler 300 mm into the soil after an initial penetration of 150 mm. An SPT N value of "P" denotes that the split-spoon sampler was pushed 300 mm into the soil without the use of a falling hammer.

| Compactness Condition | 'N' Value | Relative Density % |
|-----------------------|-----------|--------------------|
| Very Loose | <4 | <15 |
| Loose | 4-10 | 15-35 |
| Compact | 10-30 | 35-65 |
| Dense | 30-50 | 65-85 |
| Very Dense | >50 | >85 |

The standard terminology to describe the strength of cohesive soils is the consistency, which is based on the undisturbed undrained shear strength as measured by the in situ or laboratory shear vane tests, unconfined compression tests, or occasionally by the Standard Penetration Test (SPT). Note that the typical correlations of undrained shear strength to SPT N value (tabulated below) tend to underestimate the consistency for sensitive silty clays, so Paterson reviews the applicable split spoon samples in the laboratory to provide a more representative consistency value based on tactile examination.

| Consistency | Undrained Shear Strength (kPa) | 'N' Value |
|-------------|--------------------------------|-----------|
| Very Soft | <12 | <2 |
| Soft | 12-25 | 2-4 |
| Firm | 25-50 | 4-8 |
| Stiff | 50-100 | 8-15 |
| Very Stiff | 100-200 | 15-30 |
| Hard | >200 | >30 |

SYMBOLS AND TERMS (continued)

SOIL DESCRIPTION (continued)

Cohesive soils can also be classified according to their “sensitivity”. The sensitivity, S_t , is the ratio between the undisturbed undrained shear strength and the remoulded undrained shear strength of the soil. The classes of sensitivity may be defined as follows:

| | |
|---------------------|----------------|
| Low Sensitivity: | $S_t < 2$ |
| Medium Sensitivity: | $2 < S_t < 4$ |
| Sensitive: | $4 < S_t < 8$ |
| Extra Sensitive: | $8 < S_t < 16$ |
| Quick Clay: | $S_t > 16$ |

ROCK DESCRIPTION

The structural description of the bedrock mass is based on the Rock Quality Designation (RQD).

The RQD classification is based on a modified core recovery percentage in which all pieces of sound core over 100 mm long are counted as recovery. The smaller pieces are considered to be a result of closely-spaced discontinuities (resulting from shearing, jointing, faulting, or weathering) in the rock mass and are not counted. RQD is ideally determined from NQ or larger size core. However, it can be used on smaller core sizes, such as BQ, if the bulk of the fractures caused by drilling stresses (called “mechanical breaks”) are easily distinguishable from the normal in situ fractures.

| RQD % | ROCK QUALITY |
|--------|--|
| 90-100 | Excellent, intact, very sound |
| 75-90 | Good, massive, moderately jointed or sound |
| 50-75 | Fair, blocky and seamy, fractured |
| 25-50 | Poor, shattered and very seamy or blocky, severely fractured |
| 0-25 | Very poor, crushed, very severely fractured |

SAMPLE TYPES

| | | |
|----|---|---|
| SS | - | Split spoon sample (obtained in conjunction with the performing of the Standard Penetration Test (SPT)) |
| TW | - | Thin wall tube or Shelby tube, generally recovered using a piston sampler |
| G | - | "Grab" sample from test pit or surface materials |
| AU | - | Auger sample or bulk sample |
| WS | - | Wash sample |
| RC | - | Rock core sample (Core bit size BQ, NQ, HQ, etc.). Rock core samples are obtained with the use of standard diamond drilling bits. |

SYMBOLS AND TERMS (continued)

PLASTICITY LIMITS AND GRAIN SIZE DISTRIBUTION

| | | |
|-----------------|---|---|
| WC% | - | Natural water content or water content of sample, % |
| LL | - | Liquid Limit, % (water content above which soil behaves as a liquid) |
| PL | - | Plastic Limit, % (water content above which soil behaves plastically) |
| PI | - | Plasticity Index, % (difference between LL and PL) |
| D _{xx} | - | Grain size at which xx% of the soil, by weight, is of finer grain sizes These grain size descriptions are not used below 0.075 mm grain size |
| D ₁₀ | - | Grain size at which 10% of the soil is finer (effective grain size) |
| D ₆₀ | - | Grain size at which 60% of the soil is finer |
| C _c | - | Concavity coefficient = $(D_{30})^2 / (D_{10} \times D_{60})$ |
| C _u | - | Uniformity coefficient = D_{60} / D_{10} |

C_c and C_u are used to assess the grading of sands and gravels:

Well-graded gravels have: $1 < C_c < 3$ and $C_u > 4$

Well-graded sands have: $1 < C_c < 3$ and $C_u > 6$

Sands and gravels not meeting the above requirements are poorly-graded or uniformly-graded.

C_c and C_u are not applicable for the description of soils with more than 10% silt and clay (more than 10% finer than 0.075 mm or the #200 sieve)

CONSOLIDATION TEST

| | | |
|-----------------|---|---|
| p' _o | - | Present effective overburden pressure at sample depth |
| p' _c | - | Preconsolidation pressure of (maximum past pressure on) sample |
| C _{cr} | - | Recompression index (in effect at pressures below p' _c) |
| C _c | - | Compression index (in effect at pressures above p' _c) |
| OC Ratio | | Overconsolidation ratio = p'_c / p'_o |
| Void Ratio | | Initial sample void ratio = volume of voids / volume of solids |
| W _o | - | Initial water content (at start of consolidation test) |

PERMEABILITY TEST

| | | |
|---|---|--|
| k | - | Coefficient of permeability or hydraulic conductivity is a measure of the ability of water to flow through the sample. The value of k is measured at a specified unit weight for (remoulded) cohesionless soil samples, because its value will vary with the unit weight or density of the sample during the test. |
|---|---|--|

SYMBOLS AND TERMS (continued)


STRATA PLOT



Topsoil




Asphalt




Fill




Peat




Sand




Silty Sand




Silt



Sandy Silt



Clay




Silty Clay




Clayey Silty Sand



Glacial Till




Shale




Bedrock

MONITORING WELL AND PIEZOMETER CONSTRUCTION

MONITORING WELL CONSTRUCTION



PIEZOMETER CONSTRUCTION



Certificate of Analysis

Paterson Group Consulting Engineers

154 Colonnade Road South
Nepean, ON K2E 7J5
Attn: Nick Sullivan

Client PO: 30902
Project: PE4999
Custody: 128222

Report Date: 5-Oct-2020
Order Date: 30-Sep-2020

Order #: 2040420

This Certificate of Analysis contains analytical data applicable to the following samples as submitted:

| Parcel ID | Client ID |
|------------|------------|
| 2040420-01 | BH2-20-AU1 |
| 2040420-02 | BH2-20-SS5 |
| 2040420-03 | BH4-20-SS5 |
| 2040420-04 | BH5-20-SS4 |

Approved By:



Dale Robertson, BSc
Laboratory Director

Certificate of Analysis

Report Date: 05-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 30-Sep-2020

Client PO: 30902

Project Description: PE4999

Analysis Summary Table

| Analysis | Method Reference/Description | Extraction Date | Analysis Date |
|---------------------------------|---------------------------------------|-----------------|---------------|
| BTEX by P&T GC-MS | EPA 8260 - P&T GC-MS | 1-Oct-20 | 1-Oct-20 |
| Chromium, hexavalent - soil | MOE E3056 - Extraction, colourimetric | 1-Oct-20 | 3-Oct-20 |
| Mercury by CVAA | EPA 7471B - CVAA, digestion | 5-Oct-20 | 5-Oct-20 |
| PHC F1 | CWS Tier 1 - P&T GC-FID | 1-Oct-20 | 1-Oct-20 |
| PHCs F2 to F4 | CWS Tier 1 - GC-FID, extraction | 1-Oct-20 | 5-Oct-20 |
| REG 153: Metals by ICP/MS, soil | EPA 6020 - Digestion - ICP-MS | 2-Oct-20 | 2-Oct-20 |
| REG 153: PAHs by GC-MS | EPA 8270 - GC-MS, extraction | 1-Oct-20 | 4-Oct-20 |
| Solids, % | Gravimetric, calculation | 1-Oct-20 | 2-Oct-20 |

Certificate of Analysis

Report Date: 05-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 30-Sep-2020

Client PO: 30902

Project Description: PE4999

| | | | | |
|---------------------|-----------------|-----------------|-----------------|-----------------|
| Client ID: | BH2-20-AU1 | BH2-20-SS5 | BH4-20-SS5 | BH5-20-SS4 |
| Sample Date: | 29-Sep-20 09:00 | 29-Sep-20 09:00 | 29-Sep-20 12:00 | 29-Sep-20 12:00 |
| Sample ID: | 2040420-01 | 2040420-02 | 2040420-03 | 2040420-04 |
| MDL/Units | Soil | Soil | Soil | Soil |

Physical Characteristics

| | | | | | |
|----------|--------------|------|------|------|------|
| % Solids | 0.1 % by Wt. | 94.6 | 59.7 | 59.9 | 60.9 |
|----------|--------------|------|------|------|------|

Metals

| | | | | | |
|---------------|---------------|------|---|---|---|
| Antimony | 1.0 ug/g dry | <1.0 | - | - | - |
| Arsenic | 1.0 ug/g dry | 4.2 | - | - | - |
| Barium | 1.0 ug/g dry | 101 | - | - | - |
| Beryllium | 0.5 ug/g dry | <0.5 | - | - | - |
| Boron | 5.0 ug/g dry | 5.3 | - | - | - |
| Cadmium | 0.5 ug/g dry | <0.5 | - | - | - |
| Chromium | 5.0 ug/g dry | 27.6 | - | - | - |
| Chromium (VI) | 0.2 ug/g dry | <0.2 | - | - | - |
| Cobalt | 1.0 ug/g dry | 6.7 | - | - | - |
| Copper | 5.0 ug/g dry | 17.9 | - | - | - |
| Lead | 1.0 ug/g dry | 38.2 | - | - | - |
| Mercury | 0.1 ug/g dry | 0.1 | - | - | - |
| Molybdenum | 1.0 ug/g dry | <1.0 | - | - | - |
| Nickel | 5.0 ug/g dry | 17.4 | - | - | - |
| Selenium | 1.0 ug/g dry | <1.0 | - | - | - |
| Silver | 0.3 ug/g dry | <0.3 | - | - | - |
| Thallium | 1.0 ug/g dry | <1.0 | - | - | - |
| Uranium | 1.0 ug/g dry | <1.0 | - | - | - |
| Vanadium | 10.0 ug/g dry | 31.3 | - | - | - |
| Zinc | 20.0 ug/g dry | 72.2 | - | - | - |

Volatiles

| | | | | | |
|----------------|---------------|---|-------|-------|-------|
| Benzene | 0.02 ug/g dry | - | <0.02 | <0.02 | <0.02 |
| Ethylbenzene | 0.05 ug/g dry | - | <0.05 | <0.05 | <0.05 |
| Toluene | 0.05 ug/g dry | - | <0.05 | <0.05 | <0.05 |
| m,p-Xylenes | 0.05 ug/g dry | - | <0.05 | <0.05 | <0.05 |
| o-Xylene | 0.05 ug/g dry | - | <0.05 | <0.05 | <0.05 |
| Xylenes, total | 0.05 ug/g dry | - | <0.05 | <0.05 | <0.05 |
| Toluene-d8 | Surrogate | - | 114% | 114% | 114% |

Hydrocarbons

| | | | | | |
|-------------------|------------|---|----|----|----|
| F1 PHCs (C6-C10) | 7 ug/g dry | - | <7 | <7 | <7 |
| F2 PHCs (C10-C16) | 4 ug/g dry | - | <4 | <4 | <4 |
| F3 PHCs (C16-C34) | 8 ug/g dry | - | <8 | <8 | <8 |
| F4 PHCs (C34-C50) | 6 ug/g dry | - | <6 | <6 | <6 |

Certificate of Analysis

Report Date: 05-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 30-Sep-2020

Client PO: 30902

Project Description: PE4999

| | Client ID: | BH2-20-AU1 | BH2-20-SS5 | BH4-20-SS5 | BH5-20-SS4 |
|--|--------------|-----------------|-----------------|-----------------|-----------------|
| | Sample Date: | 29-Sep-20 09:00 | 29-Sep-20 09:00 | 29-Sep-20 12:00 | 29-Sep-20 12:00 |
| | Sample ID: | 2040420-01 | 2040420-02 | 2040420-03 | 2040420-04 |
| | MDL/Units | Soil | Soil | Soil | Soil |

Semi-Volatiles

| | MDL/Units | BH2-20-AU1 | BH2-20-SS5 | BH4-20-SS5 | BH5-20-SS4 |
|--------------------------|---------------|------------|------------|------------|------------|
| Acenaphthene | 0.02 ug/g dry | 0.08 | - | - | - |
| Acenaphthylene | 0.02 ug/g dry | 0.15 | - | - | - |
| Anthracene | 0.02 ug/g dry | 0.27 | - | - | - |
| Benzo [a] anthracene | 0.02 ug/g dry | 0.72 | - | - | - |
| Benzo [a] pyrene | 0.02 ug/g dry | 0.92 | - | - | - |
| Benzo [b] fluoranthene | 0.02 ug/g dry | 0.59 | - | - | - |
| Benzo [g,h,i] perylene | 0.02 ug/g dry | 0.62 | - | - | - |
| Benzo [k] fluoranthene | 0.02 ug/g dry | 0.57 | - | - | - |
| Chrysene | 0.02 ug/g dry | 0.68 | - | - | - |
| Dibenzo [a,h] anthracene | 0.02 ug/g dry | 0.16 | - | - | - |
| Fluoranthene | 0.02 ug/g dry | 1.37 | - | - | - |
| Fluorene | 0.02 ug/g dry | 0.10 | - | - | - |
| Indeno [1,2,3-cd] pyrene | 0.02 ug/g dry | 0.57 | - | - | - |
| 1-Methylnaphthalene | 0.02 ug/g dry | 0.03 | - | - | - |
| 2-Methylnaphthalene | 0.02 ug/g dry | 0.05 | - | - | - |
| Methylnaphthalene (1&2) | 0.04 ug/g dry | 0.08 | - | - | - |
| Naphthalene | 0.01 ug/g dry | 0.11 | - | - | - |
| Phenanthrene | 0.02 ug/g dry | 0.94 | - | - | - |
| Pyrene | 0.02 ug/g dry | 1.26 | - | - | - |
| 2-Fluorobiphenyl | Surrogate | 112% | - | - | - |
| Terphenyl-d14 | Surrogate | 86.5% | - | - | - |

Certificate of Analysis

Report Date: 05-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 30-Sep-2020

Client PO: 30902

Project Description: PE4999

Method Quality Control: Blank

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|-----------------------------|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | ND | 7 | ug/g | | | | | | |
| F2 PHCs (C10-C16) | ND | 4 | ug/g | | | | | | |
| F3 PHCs (C16-C34) | ND | 8 | ug/g | | | | | | |
| F4 PHCs (C34-C50) | ND | 6 | ug/g | | | | | | |
| Metals | | | | | | | | | |
| Antimony | ND | 1.0 | ug/g | | | | | | |
| Arsenic | ND | 1.0 | ug/g | | | | | | |
| Barium | ND | 1.0 | ug/g | | | | | | |
| Beryllium | ND | 0.5 | ug/g | | | | | | |
| Boron | ND | 5.0 | ug/g | | | | | | |
| Cadmium | ND | 0.5 | ug/g | | | | | | |
| Chromium (VI) | ND | 0.2 | ug/g | | | | | | |
| Chromium | ND | 5.0 | ug/g | | | | | | |
| Cobalt | ND | 1.0 | ug/g | | | | | | |
| Copper | ND | 5.0 | ug/g | | | | | | |
| Lead | ND | 1.0 | ug/g | | | | | | |
| Mercury | ND | 0.1 | ug/g | | | | | | |
| Molybdenum | ND | 1.0 | ug/g | | | | | | |
| Nickel | ND | 5.0 | ug/g | | | | | | |
| Selenium | ND | 1.0 | ug/g | | | | | | |
| Silver | ND | 0.3 | ug/g | | | | | | |
| Thallium | ND | 1.0 | ug/g | | | | | | |
| Uranium | ND | 1.0 | ug/g | | | | | | |
| Vanadium | ND | 10.0 | ug/g | | | | | | |
| Zinc | ND | 20.0 | ug/g | | | | | | |
| Semi-Volatiles | | | | | | | | | |
| Acenaphthene | ND | 0.02 | ug/g | | | | | | |
| Acenaphthylene | ND | 0.02 | ug/g | | | | | | |
| Anthracene | ND | 0.02 | ug/g | | | | | | |
| Benzo [a] anthracene | ND | 0.02 | ug/g | | | | | | |
| Benzo [a] pyrene | ND | 0.02 | ug/g | | | | | | |
| Benzo [b] fluoranthene | ND | 0.02 | ug/g | | | | | | |
| Benzo [g,h,i] perylene | ND | 0.02 | ug/g | | | | | | |
| Benzo [k] fluoranthene | ND | 0.02 | ug/g | | | | | | |
| Chrysene | ND | 0.02 | ug/g | | | | | | |
| Dibenzo [a,h] anthracene | ND | 0.02 | ug/g | | | | | | |
| Fluoranthene | ND | 0.02 | ug/g | | | | | | |
| Fluorene | ND | 0.02 | ug/g | | | | | | |
| Indeno [1,2,3-cd] pyrene | ND | 0.02 | ug/g | | | | | | |
| 1-Methylnaphthalene | ND | 0.02 | ug/g | | | | | | |
| 2-Methylnaphthalene | ND | 0.02 | ug/g | | | | | | |
| Methylnaphthalene (1&2) | ND | 0.04 | ug/g | | | | | | |
| Naphthalene | ND | 0.01 | ug/g | | | | | | |
| Phenanthrene | ND | 0.02 | ug/g | | | | | | |
| Pyrene | ND | 0.02 | ug/g | | | | | | |
| Surrogate: 2-Fluorobiphenyl | 1.18 | | ug/g | | 88.1 | 50-140 | | | |
| Surrogate: Terphenyl-d14 | 1.16 | | ug/g | | 87.3 | 50-140 | | | |
| Volatiles | | | | | | | | | |
| Benzene | ND | 0.02 | ug/g | | | | | | |
| Ethylbenzene | ND | 0.05 | ug/g | | | | | | |
| Toluene | ND | 0.05 | ug/g | | | | | | |
| m,p-Xylenes | ND | 0.05 | ug/g | | | | | | |
| o-Xylene | ND | 0.05 | ug/g | | | | | | |
| Xylenes, total | ND | 0.05 | ug/g | | | | | | |
| Surrogate: Toluene-d8 | 9.09 | | ug/g | | 114 | 50-140 | | | |

Certificate of Analysis

Report Date: 05-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 30-Sep-2020

Client PO: 30902

Project Description: PE4999

Method Quality Control: Duplicate

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|---------------------------------|--------|-----------------|----------|---------------|------|------------|------|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | ND | 7 | ug/g dry | ND | | | NC | 40 | |
| F2 PHCs (C10-C16) | ND | 4 | ug/g dry | ND | | | NC | 30 | |
| F3 PHCs (C16-C34) | ND | 8 | ug/g dry | ND | | | NC | 30 | |
| F4 PHCs (C34-C50) | ND | 6 | ug/g dry | ND | | | NC | 30 | |
| Metals | | | | | | | | | |
| Antimony | ND | 1.0 | ug/g dry | ND | | | NC | 30 | |
| Arsenic | 1.9 | 1.0 | ug/g dry | 2.1 | | | 9.2 | 30 | |
| Barium | 45.7 | 1.0 | ug/g dry | 46.7 | | | 2.3 | 30 | |
| Beryllium | ND | 0.5 | ug/g dry | ND | | | NC | 30 | |
| Boron | 6.0 | 5.0 | ug/g dry | 5.7 | | | 5.4 | 30 | |
| Cadmium | ND | 0.5 | ug/g dry | ND | | | NC | 30 | |
| Chromium (VI) | ND | 0.2 | ug/g dry | ND | | | NC | 35 | |
| Chromium | 16.4 | 5.0 | ug/g dry | 16.4 | | | 0.3 | 30 | |
| Cobalt | 4.9 | 1.0 | ug/g dry | 4.7 | | | 3.9 | 30 | |
| Copper | 9.2 | 5.0 | ug/g dry | 9.4 | | | 1.5 | 30 | |
| Lead | 4.3 | 1.0 | ug/g dry | 4.5 | | | 2.8 | 30 | |
| Mercury | ND | 0.1 | ug/g dry | ND | | | NC | 30 | |
| Molybdenum | ND | 1.0 | ug/g dry | ND | | | NC | 30 | |
| Nickel | 9.3 | 5.0 | ug/g dry | 9.3 | | | 0.2 | 30 | |
| Selenium | ND | 1.0 | ug/g dry | ND | | | NC | 30 | |
| Silver | ND | 0.3 | ug/g dry | ND | | | NC | 30 | |
| Thallium | ND | 1.0 | ug/g dry | ND | | | NC | 30 | |
| Uranium | ND | 1.0 | ug/g dry | ND | | | NC | 30 | |
| Vanadium | 26.4 | 10.0 | ug/g dry | 26.4 | | | 0.1 | 30 | |
| Zinc | 24.1 | 20.0 | ug/g dry | 23.8 | | | 1.6 | 30 | |
| Physical Characteristics | | | | | | | | | |
| % Solids | 96.9 | 0.1 | % by Wt. | 95.9 | | | 1.0 | 25 | |
| Semi-Volatiles | | | | | | | | | |
| Acenaphthene | 0.094 | 0.02 | ug/g dry | 0.083 | | | 12.8 | 40 | |
| Acenaphthylene | 0.124 | 0.02 | ug/g dry | 0.146 | | | 17.0 | 40 | |
| Anthracene | 0.296 | 0.02 | ug/g dry | 0.273 | | | 7.9 | 40 | |
| Benzo [a] anthracene | 0.663 | 0.02 | ug/g dry | 0.720 | | | 8.2 | 40 | |
| Benzo [a] pyrene | 0.835 | 0.02 | ug/g dry | 0.921 | | | 9.8 | 40 | |
| Benzo [b] fluoranthene | 0.951 | 0.02 | ug/g dry | 0.589 | | | 47.1 | 40 | QR-04 |
| Benzo [g,h,i] perylene | 0.562 | 0.02 | ug/g dry | 0.623 | | | 10.2 | 40 | |
| Benzo [k] fluoranthene | 0.509 | 0.02 | ug/g dry | 0.571 | | | 11.5 | 40 | |
| Chrysene | 0.637 | 0.02 | ug/g dry | 0.679 | | | 6.4 | 40 | |
| Dibenzo [a,h] anthracene | 0.141 | 0.02 | ug/g dry | 0.157 | | | 10.5 | 40 | |
| Fluoranthene | 1.36 | 0.02 | ug/g dry | 1.37 | | | 0.9 | 40 | |
| Fluorene | 0.112 | 0.02 | ug/g dry | 0.098 | | | 12.6 | 40 | |
| Indeno [1,2,3-cd] pyrene | 0.513 | 0.02 | ug/g dry | 0.572 | | | 10.8 | 40 | |
| 1-Methylnaphthalene | 0.036 | 0.02 | ug/g dry | 0.032 | | | 12.1 | 40 | |
| 2-Methylnaphthalene | 0.054 | 0.02 | ug/g dry | 0.047 | | | 13.7 | 40 | |
| Naphthalene | 0.128 | 0.01 | ug/g dry | 0.107 | | | 17.6 | 40 | |
| Phenanthrene | 1.04 | 0.02 | ug/g dry | 0.943 | | | 9.7 | 40 | |
| Pyrene | 1.22 | 0.02 | ug/g dry | 1.26 | | | 3.5 | 40 | |
| Surrogate: 2-Fluorobiphenyl | 1.53 | | ug/g dry | | 109 | 50-140 | | | |
| Surrogate: Terphenyl-d14 | 1.17 | | ug/g dry | | 82.8 | 50-140 | | | |
| Volatiles | | | | | | | | | |
| Benzene | ND | 0.02 | ug/g dry | ND | | | NC | 50 | |
| Ethylbenzene | ND | 0.05 | ug/g dry | ND | | | NC | 50 | |
| Toluene | ND | 0.05 | ug/g dry | ND | | | NC | 50 | |
| m,p-Xylenes | ND | 0.05 | ug/g dry | ND | | | NC | 50 | |
| o-Xylene | ND | 0.05 | ug/g dry | ND | | | NC | 50 | |
| Surrogate: Toluene-d8 | 15.4 | | ug/g dry | | 115 | 50-140 | | | |

Certificate of Analysis

Report Date: 05-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 30-Sep-2020

Client PO: 30902

Project Description: PE4999

Method Quality Control: Spike

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|-----------------------------|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | 181 | 7 | ug/g | ND | 90.7 | 80-120 | | | |
| F2 PHCs (C10-C16) | 144 | 4 | ug/g | ND | 107 | 60-140 | | | |
| F3 PHCs (C16-C34) | 359 | 8 | ug/g | ND | 109 | 60-140 | | | |
| F4 PHCs (C34-C50) | 229 | 6 | ug/g | ND | 111 | 60-140 | | | |
| Metals | | | | | | | | | |
| Antimony | 44.8 | 1.0 | ug/g | ND | 89.2 | 70-130 | | | |
| Arsenic | 53.1 | 1.0 | ug/g | ND | 105 | 70-130 | | | |
| Barium | 68.5 | 1.0 | ug/g | 18.7 | 99.7 | 70-130 | | | |
| Beryllium | 48.7 | 0.5 | ug/g | ND | 97.1 | 70-130 | | | |
| Boron | 43.9 | 5.0 | ug/g | ND | 83.3 | 70-130 | | | |
| Cadmium | 49.3 | 0.5 | ug/g | ND | 98.6 | 70-130 | | | |
| Chromium (VI) | 0.1 | 0.2 | ug/g | ND | 60.5 | 70-130 | | | QM-05 |
| Chromium | 58.7 | 5.0 | ug/g | 6.6 | 104 | 70-130 | | | |
| Cobalt | 52.0 | 1.0 | ug/g | 1.9 | 100 | 70-130 | | | |
| Copper | 52.2 | 5.0 | ug/g | ND | 96.9 | 70-130 | | | |
| Lead | 50.4 | 1.0 | ug/g | 1.8 | 97.3 | 70-130 | | | |
| Mercury | 1.53 | 0.1 | ug/g | ND | 102 | 70-130 | | | |
| Molybdenum | 49.5 | 1.0 | ug/g | ND | 98.8 | 70-130 | | | |
| Nickel | 52.5 | 5.0 | ug/g | ND | 97.6 | 70-130 | | | |
| Selenium | 48.4 | 1.0 | ug/g | ND | 96.7 | 70-130 | | | |
| Silver | 42.6 | 0.3 | ug/g | ND | 85.3 | 70-130 | | | |
| Thallium | 49.3 | 1.0 | ug/g | ND | 98.5 | 70-130 | | | |
| Uranium | 52.0 | 1.0 | ug/g | ND | 104 | 70-130 | | | |
| Vanadium | 62.2 | 10.0 | ug/g | 10.6 | 103 | 70-130 | | | |
| Zinc | 55.8 | 20.0 | ug/g | ND | 92.6 | 70-130 | | | |
| Semi-Volatiles | | | | | | | | | |
| Acenaphthene | 0.123 | 0.02 | ug/g | ND | 74.0 | 50-140 | | | |
| Acenaphthylene | 0.107 | 0.02 | ug/g | ND | 64.3 | 50-140 | | | |
| Anthracene | 0.116 | 0.02 | ug/g | ND | 69.7 | 50-140 | | | |
| Benzo [a] anthracene | 0.095 | 0.02 | ug/g | ND | 57.3 | 50-140 | | | |
| Benzo [a] pyrene | 0.093 | 0.02 | ug/g | ND | 56.0 | 50-140 | | | |
| Benzo [b] fluoranthene | 0.144 | 0.02 | ug/g | ND | 86.2 | 50-140 | | | |
| Benzo [g,h,i] perylene | 0.112 | 0.02 | ug/g | ND | 67.0 | 50-140 | | | |
| Benzo [k] fluoranthene | 0.130 | 0.02 | ug/g | ND | 78.2 | 50-140 | | | |
| Chrysene | 0.124 | 0.02 | ug/g | ND | 74.6 | 50-140 | | | |
| Dibenzo [a,h] anthracene | 0.108 | 0.02 | ug/g | ND | 64.6 | 50-140 | | | |
| Fluoranthene | 0.113 | 0.02 | ug/g | ND | 67.8 | 50-140 | | | |
| Fluorene | 0.113 | 0.02 | ug/g | ND | 67.6 | 50-140 | | | |
| Indeno [1,2,3-cd] pyrene | 0.111 | 0.02 | ug/g | ND | 66.3 | 50-140 | | | |
| 1-Methylnaphthalene | 0.135 | 0.02 | ug/g | ND | 81.0 | 50-140 | | | |
| 2-Methylnaphthalene | 0.149 | 0.02 | ug/g | ND | 89.5 | 50-140 | | | |
| Naphthalene | 0.129 | 0.01 | ug/g | ND | 77.5 | 50-140 | | | |
| Phenanthrene | 0.121 | 0.02 | ug/g | ND | 72.4 | 50-140 | | | |
| Pyrene | 0.114 | 0.02 | ug/g | ND | 68.2 | 50-140 | | | |
| Surrogate: 2-Fluorobiphenyl | 0.960 | | ug/g | | 72.0 | 50-140 | | | |
| Surrogate: Terphenyl-d14 | 0.962 | | ug/g | | 72.2 | 50-140 | | | |
| Volatiles | | | | | | | | | |
| Benzene | 3.93 | 0.02 | ug/g | ND | 98.3 | 60-130 | | | |

Certificate of Analysis

Report Date: 05-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 30-Sep-2020

Client PO: 30902

Project Description: PE4999

Method Quality Control: Spike

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|-----------------------|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Ethylbenzene | 3.97 | 0.05 | ug/g | ND | 99.2 | 60-130 | | | |
| Toluene | 3.88 | 0.05 | ug/g | ND | 97.0 | 60-130 | | | |
| m,p-Xylenes | 8.28 | 0.05 | ug/g | ND | 104 | 60-130 | | | |
| o-Xylene | 4.06 | 0.05 | ug/g | ND | 101 | 60-130 | | | |
| Surrogate: Toluene-d8 | 7.89 | | ug/g | | 98.6 | 50-140 | | | |

Certificate of Analysis

Report Date: 05-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 30-Sep-2020

Client PO: 30902

Project Description: PE4999

Qualifier Notes:

QC Qualifiers :

QM-05 : The spike recovery was outside acceptance limits for the matrix spike due to matrix interference.

QR-04 : Duplicate results exceeds RPD limits due to non-homogeneous matrix.

Sample Data Revisions

None

Work Order Revisions / Comments:

None

Other Report Notes:

n/a: not applicable

ND: Not Detected

MDL: Method Detection Limit

Source Result: Data used as source for matrix and duplicate samples

%REC: Percent recovery.

RPD: Relative percent difference.

NC: Not Calculated

Soil results are reported on a dry weight basis when the units are denoted with 'dry'.

Where %Solids is reported, moisture loss includes the loss of volatile hydrocarbons.

CCME PHC additional information:

- The method for the analysis of PHCs complies with the Reference Method for the CWS PHC and is validated for use in the laboratory. All prescribed quality criteria identified in the method has been met.
- F1 range corrected for BTEX.
- F2 to F3 ranges corrected for appropriate PAHs where available.
- The gravimetric heavy hydrocarbons (F4G) are not to be added to C6 to C50 hydrocarbons.
- In the case where F4 and F4G are both reported, the greater of the two results is to be used for comparison to CWS PHC criteria.
- When reported, data for F4G has been processed using a silica gel cleanup.



ent Blvd.
1G 4J8

llabs.com

Paracel Order Number
(Lab Use Only)

2040420

Chain Of Custody
(Lab Use Only)

Nº 128222

| | | |
|--------------------------------------|---|--|
| Client Name: Paterson Group | Project Ref: PE4999 | Page <u>1</u> of <u>1</u> |
| Contact Name: Nick Sullivan | Quote #: | Turnaround Time <input type="checkbox"/> 1 day <input type="checkbox"/> 3 day <input type="checkbox"/> 2 day <input checked="" type="checkbox"/> Regular |
| Address: 154 Colonnade Rd. S. | PO #: 30902 | |
| Telephone: 613-226-7381 | E-mail: nsullivan@patersongroup.ca | |
| Date Required: _____ | | |

| Regulation 153/04 | | Other Regulation | | Matrix Type: S (Soil/Sed.) GW (Ground Water) SW (Surface Water) SS (Storm/Sanitary Sewer) P (Paint) A (Air) O (Other) | | Required Analysis | | | | | | | | | | | | | | | | | | | |
|---|--|--|----------------------------------|---|--------|-------------------|-----------------|--------------|------|------|-----------------|------|------|---------------|----|------|---------|--|--|--|--|--|--|------------------------------------|-------------------------------------|
| <input type="checkbox"/> Table 1 | <input checked="" type="checkbox"/> Res/Park | <input type="checkbox"/> Med/Fine | <input type="checkbox"/> REG 558 | <input type="checkbox"/> PWQO | Matrix | Air Volume | # of Containers | Sample Taken | Date | Time | PHCs F1-F4+BTEX | VOCs | PAHs | Metals by ICP | Hg | CrVI | B (HWS) | | | | | | | | |
| <input type="checkbox"/> Table 2 | <input type="checkbox"/> Ind/Comm | <input checked="" type="checkbox"/> Coarse | <input type="checkbox"/> CCME | <input type="checkbox"/> MISA | | | | | | | | | | | | | | | | | | | | <input type="checkbox"/> SU - Sani | <input type="checkbox"/> SU - Storm |
| <input checked="" type="checkbox"/> Table 3 | <input type="checkbox"/> Agri/Other | | Mun: _____ | <input type="checkbox"/> Other: _____ | | | | | | | | | | | | | | | | | | | | | |
| For RSC: <input type="checkbox"/> Yes <input type="checkbox"/> No | | | | | | | | | | | | | | | | | | | | | | | | | |
| Sample ID/Location Name | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | BH2-20-AU1 | S | 1 | Sept. 29/20 | AM | | | | | | | | X | X | X | X | | | | | | | | | |
| 2 | BH2-20-SS5 | S | 2 | ↓ | ↓ | | | | | | X | | | | | | | | | | | | | | |
| 3 | BH4-20-SS5 | S | 2 | ↓ | PM | | | | | | X | | | | | | | | | | | | | | |
| 4 | BH5-20-SS4 | S | 2 | ↓ | ↓ | | | | | | X | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | | | | |

Comments: _____ Method of Delivery: **PARACEL COURIER**

| | | | |
|---|---|--------------------------------------|---|
| Relinquished By (Sign): <i>N. Sullivan</i> | Received By Driver/Depot: <i>A. Deane</i> | Received at Site: <i>[Signature]</i> | Verified By: <i>[Signature]</i> |
| Relinquished By (Print): Nick Sullivan | Date/Time: 30/09/20 3:21 | Date/Time: 9-30-20/16 | Date/Time: 9-30-20/16/20 |
| Date/Time: Sept. 30, 2020 | Temperature: _____ °C 17.1 | Temperature: 15.0 °C | pH Verified: <input type="checkbox"/> By: _____ |

Certificate of Analysis

Paterson Group Consulting Engineers

154 Colonnade Road South
Nepean, ON K2E 7J5
Attn: Mark D'Arcy

Client PO: 31209
Project: PE4999
Custody: 52670

Report Date: 13-Nov-2020
Order Date: 10-Nov-2020

Order #: 2046234

This Certificate of Analysis contains analytical data applicable to the following samples as submitted:

| Paracel ID | Client ID |
|------------|------------|
| 2046234-01 | BH6-20-SS3 |

Approved By:



Mark Foto, M.Sc.
Lab Supervisor

Certificate of Analysis

Report Date: 13-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 10-Nov-2020

Client PO: 31209

Project Description: PE4999

Analysis Summary Table

| Analysis | Method Reference/Description | Extraction Date | Analysis Date |
|-------------------|---------------------------------|-----------------|---------------|
| BTEX by P&T GC-MS | EPA 8260 - P&T GC-MS | 12-Nov-20 | 13-Nov-20 |
| PHC F1 | CWS Tier 1 - P&T GC-FID | 12-Nov-20 | 13-Nov-20 |
| PHCs F2 to F4 | CWS Tier 1 - GC-FID, extraction | 11-Nov-20 | 13-Nov-20 |
| Solids, % | Gravimetric, calculation | 11-Nov-20 | 12-Nov-20 |

Certificate of Analysis

Report Date: 13-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 10-Nov-2020

Client PO: 31209

Project Description: PE4999

| | | | | |
|---------------------|-----------------|---|---|---|
| Client ID: | BH6-20-SS3 | - | - | - |
| Sample Date: | 06-Nov-20 09:00 | - | - | - |
| Sample ID: | 2046234-01 | - | - | - |
| MDL/Units | Soil | - | - | - |

Physical Characteristics

| | | | | | |
|----------|--------------|------|---|---|---|
| % Solids | 0.1 % by Wt. | 67.7 | - | - | - |
|----------|--------------|------|---|---|---|

Volatiles

| | | | | | |
|----------------|---------------|-------|---|---|---|
| Benzene | 0.02 ug/g dry | <0.02 | - | - | - |
| Ethylbenzene | 0.05 ug/g dry | <0.05 | - | - | - |
| Toluene | 0.05 ug/g dry | <0.05 | - | - | - |
| m,p-Xylenes | 0.05 ug/g dry | <0.05 | - | - | - |
| o-Xylene | 0.05 ug/g dry | <0.05 | - | - | - |
| Xylenes, total | 0.05 ug/g dry | <0.05 | - | - | - |
| Toluene-d8 | Surrogate | 119% | - | - | - |

Hydrocarbons

| | | | | | |
|-------------------|------------|----|---|---|---|
| F1 PHCs (C6-C10) | 7 ug/g dry | <7 | - | - | - |
| F2 PHCs (C10-C16) | 4 ug/g dry | <4 | - | - | - |
| F3 PHCs (C16-C34) | 8 ug/g dry | <8 | - | - | - |
| F4 PHCs (C34-C50) | 6 ug/g dry | <6 | - | - | - |

Certificate of Analysis

Report Date: 13-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 10-Nov-2020

Client PO: 31209

Project Description: PE4999

Method Quality Control: Blank

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|-----------------------|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | ND | 7 | ug/g | | | | | | |
| F2 PHCs (C10-C16) | ND | 4 | ug/g | | | | | | |
| F3 PHCs (C16-C34) | ND | 8 | ug/g | | | | | | |
| F4 PHCs (C34-C50) | ND | 6 | ug/g | | | | | | |
| Volatiles | | | | | | | | | |
| Benzene | ND | 0.02 | ug/g | | | | | | |
| Ethylbenzene | ND | 0.05 | ug/g | | | | | | |
| Toluene | ND | 0.05 | ug/g | | | | | | |
| m,p-Xylenes | ND | 0.05 | ug/g | | | | | | |
| o-Xylene | ND | 0.05 | ug/g | | | | | | |
| Xylenes, total | ND | 0.05 | ug/g | | | | | | |
| Surrogate: Toluene-d8 | 9.47 | | ug/g | | 118 | 50-140 | | | |

Certificate of Analysis

Report Date: 13-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 10-Nov-2020

Client PO: 31209

Project Description: PE4999

Method Quality Control: Duplicate

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|---------------------------------|--------|-----------------|----------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | ND | 7 | ug/g dry | ND | | | NC | 40 | |
| F2 PHCs (C10-C16) | ND | 4 | ug/g dry | ND | | | NC | 30 | |
| F3 PHCs (C16-C34) | ND | 8 | ug/g dry | ND | | | NC | 30 | |
| F4 PHCs (C34-C50) | ND | 6 | ug/g dry | ND | | | NC | 30 | |
| Physical Characteristics | | | | | | | | | |
| % Solids | 91.5 | 0.1 | % by Wt. | 91.2 | | | 0.3 | 25 | |
| Volatiles | | | | | | | | | |
| Benzene | ND | 0.02 | ug/g dry | ND | | | NC | 50 | |
| Ethylbenzene | ND | 0.05 | ug/g dry | ND | | | NC | 50 | |
| Toluene | ND | 0.05 | ug/g dry | ND | | | NC | 50 | |
| m,p-Xylenes | ND | 0.05 | ug/g dry | ND | | | NC | 50 | |
| o-Xylene | ND | 0.05 | ug/g dry | ND | | | NC | 50 | |
| Surrogate: Toluene-d8 | 10.9 | | ug/g dry | | 119 | 50-140 | | | |

Certificate of Analysis

Report Date: 13-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 10-Nov-2020

Client PO: 31209

Project Description: PE4999

Method Quality Control: Spike

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|-----------------------|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | 163 | 7 | ug/g | ND | 81.5 | 80-120 | | | |
| F2 PHCs (C10-C16) | 93 | 4 | ug/g | ND | 91.3 | 60-140 | | | |
| F3 PHCs (C16-C34) | 226 | 8 | ug/g | ND | 90.6 | 60-140 | | | |
| F4 PHCs (C34-C50) | 140 | 6 | ug/g | ND | 88.9 | 60-140 | | | |
| Volatiles | | | | | | | | | |
| Benzene | 3.55 | 0.02 | ug/g | ND | 88.7 | 60-130 | | | |
| Ethylbenzene | 3.97 | 0.05 | ug/g | ND | 99.3 | 60-130 | | | |
| Toluene | 4.21 | 0.05 | ug/g | ND | 105 | 60-130 | | | |
| m,p-Xylenes | 8.32 | 0.05 | ug/g | ND | 104 | 60-130 | | | |
| o-Xylene | 3.89 | 0.05 | ug/g | ND | 97.2 | 60-130 | | | |
| Surrogate: Toluene-d8 | 8.32 | | ug/g | | 104 | 50-140 | | | |

Certificate of Analysis

Report Date: 13-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 10-Nov-2020

Client PO: 31209

Project Description: PE4999

Qualifier Notes:

None

Sample Data Revisions

None

Work Order Revisions / Comments:

None

Other Report Notes:

n/a: not applicable

ND: Not Detected

MDL: Method Detection Limit

Source Result: Data used as source for matrix and duplicate samples

%REC: Percent recovery.

RPD: Relative percent difference.

NC: Not Calculated

Soil results are reported on a dry weight basis when the units are denoted with 'dry'.

Where %Solids is reported, moisture loss includes the loss of volatile hydrocarbons.

CCME PHC additional information:

- The method for the analysis of PHCs complies with the Reference Method for the CWS PHC and is validated for use in the laboratory. All prescribed quality criteria identified in the method has been met.
- F1 range corrected for BTEX.
- F2 to F3 ranges corrected for appropriate PAHs where available.
- The gravimetric heavy hydrocarbons (F4G) are not to be added to C6 to C50 hydrocarbons.
- In the case where F4 and F4G are both reported, the greater of the two results is to be used for comparison to CWS PHC criteria.
- When reported, data for F4G has been processed using a silica gel cleanup.

Certificate of Analysis

Paterson Group Consulting Engineers

154 Colonnade Road South
Nepean, ON K2E 7J5
Attn: Nick Sullivan

Client PO: 31420
Project: PE4999
Custody: 55010/11

Report Date: 26-Oct-2020
Order Date: 20-Oct-2020

Order #: 2043350

This Certificate of Analysis contains analytical data applicable to the following samples as submitted:

| Parcel ID | Client ID |
|------------|-----------|
| 2043350-01 | TP1-G2 |
| 2043350-02 | TP2-G1 |
| 2043350-03 | TP4-G2 |
| 2043350-04 | TP5-G2 |
| 2043350-05 | TP7-G1 |
| 2043350-06 | TP8-G2 |
| 2043350-07 | TP10-G1 |
| 2043350-08 | TP11-G1 |
| 2043350-09 | TP12-G1 |
| 2043350-10 | TP13-G1 |
| 2043350-11 | TP14-G1 |

Approved By:



Dale Robertson, BSc
Laboratory Director

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

Analysis Summary Table

| Analysis | Method Reference/Description | Extraction Date | Analysis Date |
|---------------------------------|---------------------------------------|-----------------|---------------|
| Chromium, hexavalent - soil | MOE E3056 - Extraction, colourimetric | 21-Oct-20 | 23-Oct-20 |
| Mercury by CVAA | EPA 7471B - CVAA, digestion | 23-Oct-20 | 23-Oct-20 |
| PHC F4G (gravimetric) | CWS Tier 1 - Extraction Gravimetric | 26-Oct-20 | 26-Oct-20 |
| PHCs F2 to F4 | CWS Tier 1 - GC-FID, extraction | 21-Oct-20 | 22-Oct-20 |
| REG 153: Metals by ICP/MS, soil | EPA 6020 - Digestion - ICP-MS | 23-Oct-20 | 23-Oct-20 |
| REG 153: PAHs by GC-MS | EPA 8270 - GC-MS, extraction | 21-Oct-20 | 23-Oct-20 |
| Solids, % | Gravimetric, calculation | 21-Oct-20 | 22-Oct-20 |

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

| | | | | |
|---------------------|-----------------|-----------------|-----------------|-----------------|
| Client ID: | TP1-G2 | TP2-G1 | TP4-G2 | TP5-G2 |
| Sample Date: | 19-Oct-20 09:00 | 19-Oct-20 09:00 | 19-Oct-20 09:00 | 19-Oct-20 09:00 |
| Sample ID: | 2043350-01 | 2043350-02 | 2043350-03 | 2043350-04 |
| MDL/Units | Soil | Soil | Soil | Soil |

Physical Characteristics

| | | | | | |
|----------|--------------|------|------|------|------|
| % Solids | 0.1 % by Wt. | 77.8 | 85.9 | 69.1 | 75.6 |
|----------|--------------|------|------|------|------|

Metals

| | | | | | |
|---------------|---------------|------|------|------|------|
| Antimony | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | <1.0 |
| Arsenic | 1.0 ug/g dry | 3.5 | 2.6 | 4.1 | 3.9 |
| Barium | 1.0 ug/g dry | 152 | 45.2 | 300 | 149 |
| Beryllium | 0.5 ug/g dry | 0.6 | <0.5 | 0.8 | 0.6 |
| Boron | 5.0 ug/g dry | <5.0 | <5.0 | 5.9 | <5.0 |
| Cadmium | 0.5 ug/g dry | <0.5 | <0.5 | <0.5 | <0.5 |
| Chromium | 5.0 ug/g dry | 70.0 | 19.5 | 118 | 66.8 |
| Chromium (VI) | 0.2 ug/g dry | <0.2 | <0.2 | <0.2 | <0.2 |
| Cobalt | 1.0 ug/g dry | 13.3 | 5.1 | 22.3 | 11.9 |
| Copper | 5.0 ug/g dry | 23.5 | 11.3 | 50.5 | 22.3 |
| Lead | 1.0 ug/g dry | 10.8 | 8.2 | 7.7 | 13.9 |
| Mercury | 0.1 ug/g dry | <0.1 | <0.1 | <0.1 | <0.1 |
| Molybdenum | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | <1.0 |
| Nickel | 5.0 ug/g dry | 34.2 | 12.7 | 62.6 | 31.7 |
| Selenium | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | <1.0 |
| Silver | 0.3 ug/g dry | <0.3 | <0.3 | <0.3 | <0.3 |
| Thallium | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | <1.0 |
| Uranium | 1.0 ug/g dry | 1.7 | <1.0 | <1.0 | 2.2 |
| Vanadium | 10.0 ug/g dry | 59.9 | 23.2 | 104 | 57.2 |
| Zinc | 20.0 ug/g dry | 77.4 | 33.3 | 118 | 84.2 |

Hydrocarbons

| | | | | | |
|-------------------|------------|----|----|----|----|
| F2 PHCs (C10-C16) | 4 ug/g dry | <4 | <4 | <4 | <4 |
| F3 PHCs (C16-C34) | 8 ug/g dry | <8 | <8 | <8 | <8 |
| F4 PHCs (C34-C50) | 6 ug/g dry | <6 | <6 | <6 | <6 |

Semi-Volatiles

| | | | | | |
|------------------------|---------------|-------|-------|-------|-------|
| Acenaphthene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Acenaphthylene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Anthracene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Benzo [a] anthracene | 0.02 ug/g dry | <0.02 | 0.05 | <0.02 | <0.02 |
| Benzo [a] pyrene | 0.02 ug/g dry | <0.02 | 0.07 | <0.02 | <0.02 |
| Benzo [b] fluoranthene | 0.02 ug/g dry | <0.02 | 0.09 | <0.02 | <0.02 |
| Benzo [g,h,i] perylene | 0.02 ug/g dry | <0.02 | 0.05 | <0.02 | <0.02 |
| Benzo [k] fluoranthene | 0.02 ug/g dry | <0.02 | 0.04 | <0.02 | <0.02 |

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

| | Client ID: | TP1-G2 | TP2-G1 | TP4-G2 | TP5-G2 |
|--------------------------|---------------|-----------------|-----------------|-----------------|-----------------|
| | Sample Date: | 19-Oct-20 09:00 | 19-Oct-20 09:00 | 19-Oct-20 09:00 | 19-Oct-20 09:00 |
| | Sample ID: | 2043350-01 | 2043350-02 | 2043350-03 | 2043350-04 |
| | MDL/Units | Soil | Soil | Soil | Soil |
| Chrysene | 0.02 ug/g dry | <0.02 | 0.07 | <0.02 | <0.02 |
| Dibenzo [a,h] anthracene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Fluoranthene | 0.02 ug/g dry | <0.02 | 0.13 | <0.02 | 0.03 |
| Fluorene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Indeno [1,2,3-cd] pyrene | 0.02 ug/g dry | <0.02 | 0.05 | <0.02 | <0.02 |
| 1-Methylnaphthalene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| 2-Methylnaphthalene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Methylnaphthalene (1&2) | 0.04 ug/g dry | <0.04 | <0.04 | <0.04 | <0.04 |
| Naphthalene | 0.01 ug/g dry | <0.01 | <0.01 | <0.01 | <0.01 |
| Phenanthrene | 0.02 ug/g dry | <0.02 | 0.04 | <0.02 | <0.02 |
| Pyrene | 0.02 ug/g dry | <0.02 | 0.11 | <0.02 | 0.02 |
| 2-Fluorobiphenyl | Surrogate | 70.4% | 84.9% | 68.2% | 72.3% |
| Terphenyl-d14 | Surrogate | 104% | 132% | 101% | 110% |

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

| Client ID: | TP7-G1 | TP8-G2 | TP10-G1 | TP11-G1 |
|--------------|-----------------|-----------------|-----------------|-----------------|
| Sample Date: | 19-Oct-20 09:00 | 19-Oct-20 09:00 | 19-Oct-20 09:00 | 19-Oct-20 09:00 |
| Sample ID: | 2043350-05 | 2043350-06 | 2043350-07 | 2043350-08 |
| MDL/Units | Soil | Soil | Soil | Soil |

Physical Characteristics

| | | | | | |
|----------|--------------|------|------|------|------|
| % Solids | 0.1 % by Wt. | 72.6 | 78.8 | 93.2 | 76.5 |
|----------|--------------|------|------|------|------|

Metals

| | | | | | |
|---------------|---------------|------|------|-------|------|
| Antimony | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | <1.0 |
| Arsenic | 1.0 ug/g dry | 3.2 | 2.9 | 1.8 | 3.3 |
| Barium | 1.0 ug/g dry | 209 | 106 | 55.3 | 167 |
| Beryllium | 0.5 ug/g dry | 0.7 | <0.5 | <0.5 | 0.6 |
| Boron | 5.0 ug/g dry | 5.6 | <5.0 | <5.0 | <5.0 |
| Cadmium | 0.5 ug/g dry | <0.5 | <0.5 | <0.5 | <0.5 |
| Chromium | 5.0 ug/g dry | 102 | 41.8 | 15.4 | 69.2 |
| Chromium (VI) | 0.2 ug/g dry | <0.2 | <0.2 | <0.2 | <0.2 |
| Cobalt | 1.0 ug/g dry | 18.0 | 8.6 | 3.6 | 13.7 |
| Copper | 5.0 ug/g dry | 31.5 | 16.5 | 5.4 | 26.8 |
| Lead | 1.0 ug/g dry | 13.7 | 23.9 | 4.0 | 7.8 |
| Mercury | 0.1 ug/g dry | <0.1 | <0.1 | <0.1 | <0.1 |
| Molybdenum | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | <1.0 |
| Nickel | 5.0 ug/g dry | 50.5 | 21.0 | 9.3 | 38.5 |
| Selenium | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | <1.0 |
| Silver | 0.3 ug/g dry | <0.3 | <0.3 | <0.3 | <0.3 |
| Thallium | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | <1.0 |
| Uranium | 1.0 ug/g dry | 1.8 | 1.2 | <1.0 | <1.0 |
| Vanadium | 10.0 ug/g dry | 78.6 | 39.0 | 15.9 | 54.5 |
| Zinc | 20.0 ug/g dry | 98.2 | 78.3 | <20.0 | 65.9 |

Hydrocarbons

| | | | | | |
|-------------------|------------|----|----|----|----|
| F2 PHCs (C10-C16) | 4 ug/g dry | <4 | <4 | <4 | <4 |
| F3 PHCs (C16-C34) | 8 ug/g dry | <8 | <8 | <8 | <8 |
| F4 PHCs (C34-C50) | 6 ug/g dry | <6 | <6 | <6 | <6 |

Semi-Volatiles

| | | | | | |
|------------------------|---------------|-------|-------|-------|-------|
| Acenaphthene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Acenaphthylene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Anthracene | 0.02 ug/g dry | <0.02 | 0.02 | <0.02 | <0.02 |
| Benzo [a] anthracene | 0.02 ug/g dry | <0.02 | 0.06 | <0.02 | <0.02 |
| Benzo [a] pyrene | 0.02 ug/g dry | <0.02 | 0.08 | <0.02 | <0.02 |
| Benzo [b] fluoranthene | 0.02 ug/g dry | <0.02 | 0.10 | <0.02 | <0.02 |
| Benzo [g,h,i] perylene | 0.02 ug/g dry | <0.02 | 0.06 | <0.02 | <0.02 |
| Benzo [k] fluoranthene | 0.02 ug/g dry | <0.02 | 0.05 | <0.02 | <0.02 |

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

| | Client ID: | TP7-G1 | TP8-G2 | TP10-G1 | TP11-G1 |
|--------------------------|---------------|-----------------|-----------------|-----------------|-----------------|
| | Sample Date: | 19-Oct-20 09:00 | 19-Oct-20 09:00 | 19-Oct-20 09:00 | 19-Oct-20 09:00 |
| | Sample ID: | 2043350-05 | 2043350-06 | 2043350-07 | 2043350-08 |
| | MDL/Units | Soil | Soil | Soil | Soil |
| Chrysene | 0.02 ug/g dry | <0.02 | 0.08 | <0.02 | <0.02 |
| Dibenzo [a,h] anthracene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Fluoranthene | 0.02 ug/g dry | <0.02 | 0.14 | <0.02 | <0.02 |
| Fluorene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Indeno [1,2,3-cd] pyrene | 0.02 ug/g dry | <0.02 | 0.05 | <0.02 | <0.02 |
| 1-Methylnaphthalene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| 2-Methylnaphthalene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | <0.02 |
| Methylnaphthalene (1&2) | 0.04 ug/g dry | <0.04 | <0.04 | <0.04 | <0.04 |
| Naphthalene | 0.01 ug/g dry | <0.01 | <0.01 | <0.01 | <0.01 |
| Phenanthrene | 0.02 ug/g dry | <0.02 | 0.05 | <0.02 | <0.02 |
| Pyrene | 0.02 ug/g dry | <0.02 | 0.12 | <0.02 | <0.02 |
| 2-Fluorobiphenyl | Surrogate | 61.8% | 75.2% | 76.5% | 66.0% |
| Terphenyl-d14 | Surrogate | 83.5% | 118% | 102% | 70.6% |

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

| | | | | |
|---------------------|-----------------|-----------------|-----------------|---|
| Client ID: | TP12-G1 | TP13-G1 | TP14-G1 | - |
| Sample Date: | 19-Oct-20 09:00 | 19-Oct-20 09:00 | 19-Oct-20 09:00 | - |
| Sample ID: | 2043350-09 | 2043350-10 | 2043350-11 | - |
| MDL/Units | Soil | Soil | Soil | - |

Physical Characteristics

| | | | | | |
|----------|--------------|------|------|------|---|
| % Solids | 0.1 % by Wt. | 81.0 | 80.8 | 87.2 | - |
|----------|--------------|------|------|------|---|

Metals

| | | | | | |
|---------------|---------------|------|------|------|---|
| Antimony | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | - |
| Arsenic | 1.0 ug/g dry | 4.4 | 3.0 | 3.1 | - |
| Barium | 1.0 ug/g dry | 157 | 116 | 138 | - |
| Beryllium | 0.5 ug/g dry | 0.6 | <0.5 | <0.5 | - |
| Boron | 5.0 ug/g dry | 6.2 | 6.2 | 5.4 | - |
| Cadmium | 0.5 ug/g dry | <0.5 | <0.5 | <0.5 | - |
| Chromium | 5.0 ug/g dry | 69.1 | 48.2 | 53.5 | - |
| Chromium (VI) | 0.2 ug/g dry | <0.2 | <0.2 | <0.2 | - |
| Cobalt | 1.0 ug/g dry | 12.0 | 9.0 | 10.9 | - |
| Copper | 5.0 ug/g dry | 22.8 | 17.2 | 23.3 | - |
| Lead | 1.0 ug/g dry | 12.8 | 11.6 | 15.1 | - |
| Mercury | 0.1 ug/g dry | <0.1 | <0.1 | <0.1 | - |
| Molybdenum | 1.0 ug/g dry | 1.2 | <1.0 | <1.0 | - |
| Nickel | 5.0 ug/g dry | 35.5 | 25.0 | 31.1 | - |
| Selenium | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | - |
| Silver | 0.3 ug/g dry | <0.3 | <0.3 | <0.3 | - |
| Thallium | 1.0 ug/g dry | <1.0 | <1.0 | <1.0 | - |
| Uranium | 1.0 ug/g dry | 2.4 | 1.3 | <1.0 | - |
| Vanadium | 10.0 ug/g dry | 56.1 | 39.6 | 51.3 | - |
| Zinc | 20.0 ug/g dry | 84.2 | 53.7 | 65.1 | - |

Hydrocarbons

| | | | | | |
|------------------------|-------------|-----|----|---------|---|
| F2 PHCs (C10-C16) | 4 ug/g dry | <4 | <4 | <4 | - |
| F3 PHCs (C16-C34) | 8 ug/g dry | 40 | <8 | 60 | - |
| F4 PHCs (C34-C50) | 6 ug/g dry | 122 | <6 | 188 [1] | - |
| F4G PHCs (gravimetric) | 50 ug/g dry | - | - | 722 | - |

Semi-Volatiles

| | | | | | |
|------------------------|---------------|-------|-------|-------|---|
| Acenaphthene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | - |
| Acenaphthylene | 0.02 ug/g dry | <0.02 | 0.02 | 0.04 | - |
| Anthracene | 0.02 ug/g dry | <0.02 | 0.07 | 0.09 | - |
| Benzo [a] anthracene | 0.02 ug/g dry | 0.05 | 0.16 | 0.36 | - |
| Benzo [a] pyrene | 0.02 ug/g dry | 0.18 | 0.16 | 0.41 | - |
| Benzo [b] fluoranthene | 0.02 ug/g dry | 0.50 | 0.18 | 0.79 | - |
| Benzo [g,h,i] perylene | 0.02 ug/g dry | 0.22 | 0.10 | 0.34 | - |

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

| | Client ID: | TP12-G1 | TP13-G1 | TP14-G1 | - |
|--------------------------|---------------|-----------------|-----------------|-----------------|---|
| | Sample Date: | 19-Oct-20 09:00 | 19-Oct-20 09:00 | 19-Oct-20 09:00 | - |
| | Sample ID: | 2043350-09 | 2043350-10 | 2043350-11 | - |
| | MDL/Units | Soil | Soil | Soil | - |
| Benzo [k] fluoranthene | 0.02 ug/g dry | 0.14 | 0.09 | 0.44 | - |
| Chrysene | 0.02 ug/g dry | 0.06 | 0.16 | 0.42 | - |
| Dibenzo [a,h] anthracene | 0.02 ug/g dry | 0.04 | 0.03 | 0.08 | - |
| Fluoranthene | 0.02 ug/g dry | 0.11 | 0.35 | 0.84 | - |
| Fluorene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | - |
| Indeno [1,2,3-cd] pyrene | 0.02 ug/g dry | 0.13 | 0.09 | 0.29 | - |
| 1-Methylnaphthalene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | - |
| 2-Methylnaphthalene | 0.02 ug/g dry | <0.02 | <0.02 | <0.02 | - |
| Methylnaphthalene (1&2) | 0.04 ug/g dry | <0.04 | <0.04 | <0.04 | - |
| Naphthalene | 0.01 ug/g dry | <0.01 | <0.01 | <0.01 | - |
| Phenanthrene | 0.02 ug/g dry | 0.06 | 0.17 | 0.29 | - |
| Pyrene | 0.02 ug/g dry | 0.16 | 0.27 | 0.67 | - |
| 2-Fluorobiphenyl | Surrogate | 103% | 71.1% | 107% | - |
| Terphenyl-d14 | Surrogate | 107% | 112% | 110% | - |

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

Method Quality Control: Blank

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|-----------------------------|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F2 PHCs (C10-C16) | ND | 4 | ug/g | | | | | | |
| F3 PHCs (C16-C34) | ND | 8 | ug/g | | | | | | |
| F4 PHCs (C34-C50) | ND | 6 | ug/g | | | | | | |
| F4G PHCs (gravimetric) | ND | 50 | ug/g | | | | | | |
| Metals | | | | | | | | | |
| Antimony | ND | 1.0 | ug/g | | | | | | |
| Arsenic | ND | 1.0 | ug/g | | | | | | |
| Barium | ND | 1.0 | ug/g | | | | | | |
| Beryllium | ND | 0.5 | ug/g | | | | | | |
| Boron | ND | 5.0 | ug/g | | | | | | |
| Cadmium | ND | 0.5 | ug/g | | | | | | |
| Chromium (VI) | ND | 0.2 | ug/g | | | | | | |
| Chromium | ND | 5.0 | ug/g | | | | | | |
| Cobalt | ND | 1.0 | ug/g | | | | | | |
| Copper | ND | 5.0 | ug/g | | | | | | |
| Lead | ND | 1.0 | ug/g | | | | | | |
| Mercury | ND | 0.1 | ug/g | | | | | | |
| Molybdenum | ND | 1.0 | ug/g | | | | | | |
| Nickel | ND | 5.0 | ug/g | | | | | | |
| Selenium | ND | 1.0 | ug/g | | | | | | |
| Silver | ND | 0.3 | ug/g | | | | | | |
| Thallium | ND | 1.0 | ug/g | | | | | | |
| Uranium | ND | 1.0 | ug/g | | | | | | |
| Vanadium | ND | 10.0 | ug/g | | | | | | |
| Zinc | ND | 20.0 | ug/g | | | | | | |
| Semi-Volatiles | | | | | | | | | |
| Acenaphthene | ND | 0.02 | ug/g | | | | | | |
| Acenaphthylene | ND | 0.02 | ug/g | | | | | | |
| Anthracene | ND | 0.02 | ug/g | | | | | | |
| Benzo [a] anthracene | ND | 0.02 | ug/g | | | | | | |
| Benzo [a] pyrene | ND | 0.02 | ug/g | | | | | | |
| Benzo [b] fluoranthene | ND | 0.02 | ug/g | | | | | | |
| Benzo [g,h,i] perylene | ND | 0.02 | ug/g | | | | | | |
| Benzo [k] fluoranthene | ND | 0.02 | ug/g | | | | | | |
| Chrysene | ND | 0.02 | ug/g | | | | | | |
| Dibenzo [a,h] anthracene | ND | 0.02 | ug/g | | | | | | |
| Fluoranthene | ND | 0.02 | ug/g | | | | | | |
| Fluorene | ND | 0.02 | ug/g | | | | | | |
| Indeno [1,2,3-cd] pyrene | ND | 0.02 | ug/g | | | | | | |
| 1-Methylnaphthalene | ND | 0.02 | ug/g | | | | | | |
| 2-Methylnaphthalene | ND | 0.02 | ug/g | | | | | | |
| Methylnaphthalene (1&2) | ND | 0.04 | ug/g | | | | | | |
| Naphthalene | ND | 0.01 | ug/g | | | | | | |
| Phenanthrene | ND | 0.02 | ug/g | | | | | | |
| Pyrene | ND | 0.02 | ug/g | | | | | | |
| Surrogate: 2-Fluorobiphenyl | 0.869 | | ug/g | | 65.1 | 50-140 | | | |
| Surrogate: Terphenyl-d14 | 1.59 | | ug/g | | 119 | 50-140 | | | |

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

Method Quality Control: Duplicate

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|---------------------------------|--------|-----------------|----------|---------------|------|------------|------|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F2 PHCs (C10-C16) | ND | 4 | ug/g dry | ND | | | NC | 30 | |
| F3 PHCs (C16-C34) | ND | 8 | ug/g dry | ND | | | NC | 30 | |
| F4 PHCs (C34-C50) | ND | 6 | ug/g dry | ND | | | NC | 30 | |
| Metals | | | | | | | | | |
| Antimony | ND | 1.0 | ug/g dry | ND | | | NC | 30 | |
| Arsenic | 3.8 | 1.0 | ug/g dry | 3.5 | | | 6.2 | 30 | |
| Barium | 170 | 1.0 | ug/g dry | 152 | | | 11.0 | 30 | |
| Beryllium | 0.7 | 0.5 | ug/g dry | 0.6 | | | 18.8 | 30 | |
| Boron | 6.1 | 5.0 | ug/g dry | ND | | | NC | 30 | |
| Cadmium | ND | 0.5 | ug/g dry | ND | | | NC | 30 | |
| Chromium (VI) | ND | 0.2 | ug/g dry | ND | | | NC | 35 | |
| Chromium | 77.6 | 5.0 | ug/g dry | 70.0 | | | 10.3 | 30 | |
| Cobalt | 14.6 | 1.0 | ug/g dry | 13.3 | | | 8.7 | 30 | |
| Copper | 26.2 | 5.0 | ug/g dry | 23.5 | | | 10.8 | 30 | |
| Lead | 12.2 | 1.0 | ug/g dry | 10.8 | | | 11.6 | 30 | |
| Mercury | ND | 0.1 | ug/g dry | ND | | | NC | 30 | |
| Molybdenum | ND | 1.0 | ug/g dry | ND | | | NC | 30 | |
| Nickel | 37.7 | 5.0 | ug/g dry | 34.2 | | | 9.9 | 30 | |
| Selenium | ND | 1.0 | ug/g dry | ND | | | NC | 30 | |
| Silver | ND | 0.3 | ug/g dry | ND | | | NC | 30 | |
| Thallium | ND | 1.0 | ug/g dry | ND | | | NC | 30 | |
| Uranium | 2.0 | 1.0 | ug/g dry | 1.7 | | | 16.0 | 30 | |
| Vanadium | 66.5 | 10.0 | ug/g dry | 59.9 | | | 10.5 | 30 | |
| Zinc | 86.0 | 20.0 | ug/g dry | 77.4 | | | 10.4 | 30 | |
| Physical Characteristics | | | | | | | | | |
| % Solids | 84.7 | 0.1 | % by Wt. | 84.6 | | | 0.0 | 25 | |
| Semi-Volatiles | | | | | | | | | |
| Acenaphthene | ND | 0.02 | ug/g dry | ND | | | NC | 40 | |
| Acenaphthylene | ND | 0.02 | ug/g dry | ND | | | NC | 40 | |
| Anthracene | 0.023 | 0.02 | ug/g dry | ND | | | NC | 40 | |
| Benzo [a] anthracene | 0.036 | 0.02 | ug/g dry | 0.028 | | | 22.8 | 40 | |
| Benzo [a] pyrene | 0.037 | 0.02 | ug/g dry | 0.028 | | | 27.5 | 40 | |
| Benzo [b] fluoranthene | 0.046 | 0.02 | ug/g dry | 0.036 | | | 25.6 | 40 | |
| Benzo [g,h,i] perylene | 0.028 | 0.02 | ug/g dry | ND | | | NC | 40 | |
| Benzo [k] fluoranthene | 0.020 | 0.02 | ug/g dry | ND | | | NC | 40 | |
| Chrysene | 0.044 | 0.02 | ug/g dry | 0.030 | | | 37.0 | 40 | |
| Dibenzo [a,h] anthracene | ND | 0.02 | ug/g dry | ND | | | NC | 40 | |
| Fluoranthene | 0.097 | 0.02 | ug/g dry | 0.079 | | | 21.3 | 40 | |
| Fluorene | ND | 0.02 | ug/g dry | ND | | | NC | 40 | |
| Indeno [1,2,3-cd] pyrene | 0.023 | 0.02 | ug/g dry | ND | | | NC | 40 | |
| 1-Methylnaphthalene | ND | 0.02 | ug/g dry | ND | | | NC | 40 | |
| 2-Methylnaphthalene | ND | 0.02 | ug/g dry | ND | | | NC | 40 | |
| Naphthalene | 0.021 | 0.01 | ug/g dry | 0.013 | | | NC | 40 | |
| Phenanthrene | 0.091 | 0.02 | ug/g dry | 0.059 | | | NC | 40 | |
| Pyrene | 0.078 | 0.02 | ug/g dry | 0.062 | | | 22.4 | 40 | |
| Surrogate: 2-Fluorobiphenyl | 0.852 | | ug/g dry | | 55.6 | 50-140 | | | |
| Surrogate: Terphenyl-d14 | 1.47 | | ug/g dry | | 95.7 | 50-140 | | | |

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

Method Quality Control: Spike

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|-----------------------------|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F2 PHCs (C10-C16) | 110 | 4 | ug/g | ND | 107 | 60-140 | | | |
| F3 PHCs (C16-C34) | 280 | 8 | ug/g | ND | 111 | 60-140 | | | |
| F4 PHCs (C34-C50) | 175 | 6 | ug/g | ND | 109 | 60-140 | | | |
| F4G PHCs (gravimetric) | 980 | 50 | ug/g | ND | 98.0 | 80-120 | | | |
| Metals | | | | | | | | | |
| Antimony | 40.3 | 1.0 | ug/g | ND | 80.3 | 70-130 | | | |
| Arsenic | 47.6 | 1.0 | ug/g | 1.4 | 92.3 | 70-130 | | | |
| Barium | 109 | 1.0 | ug/g | 60.9 | 95.3 | 70-130 | | | |
| Beryllium | 43.0 | 0.5 | ug/g | ND | 85.5 | 70-130 | | | |
| Boron | 38.0 | 5.0 | ug/g | ND | 72.1 | 70-130 | | | |
| Cadmium | 42.6 | 0.5 | ug/g | ND | 85.0 | 70-130 | | | |
| Chromium (VI) | 4.1 | 0.2 | ug/g | ND | 81.5 | 70-130 | | | |
| Chromium | 75.7 | 5.0 | ug/g | 28.0 | 95.4 | 70-130 | | | |
| Cobalt | 50.3 | 1.0 | ug/g | 5.3 | 89.9 | 70-130 | | | |
| Copper | 53.2 | 5.0 | ug/g | 9.4 | 87.6 | 70-130 | | | |
| Lead | 46.0 | 1.0 | ug/g | 4.3 | 83.3 | 70-130 | | | |
| Mercury | 1.66 | 0.1 | ug/g | ND | 111 | 70-130 | | | |
| Molybdenum | 42.4 | 1.0 | ug/g | ND | 84.1 | 70-130 | | | |
| Nickel | 57.6 | 5.0 | ug/g | 13.7 | 87.9 | 70-130 | | | |
| Selenium | 44.1 | 1.0 | ug/g | ND | 87.8 | 70-130 | | | |
| Silver | 36.5 | 0.3 | ug/g | ND | 73.0 | 70-130 | | | |
| Thallium | 44.7 | 1.0 | ug/g | ND | 89.3 | 70-130 | | | |
| Uranium | 46.0 | 1.0 | ug/g | ND | 90.6 | 70-130 | | | |
| Vanadium | 71.3 | 10.0 | ug/g | 23.9 | 94.7 | 70-130 | | | |
| Zinc | 74.7 | 20.0 | ug/g | 31.0 | 87.5 | 70-130 | | | |
| Semi-Volatiles | | | | | | | | | |
| Acenaphthene | 0.201 | 0.02 | ug/g | ND | 105 | 50-140 | | | |
| Acenaphthylene | 0.154 | 0.02 | ug/g | ND | 80.6 | 50-140 | | | |
| Anthracene | 0.265 | 0.02 | ug/g | ND | 138 | 50-140 | | | |
| Benzo [a] anthracene | 0.275 | 0.02 | ug/g | 0.028 | 128 | 50-140 | | | |
| Benzo [a] pyrene | 0.294 | 0.02 | ug/g | 0.028 | 139 | 50-140 | | | |
| Benzo [b] fluoranthene | 0.294 | 0.02 | ug/g | 0.036 | 135 | 50-140 | | | |
| Benzo [g,h,i] perylene | 0.218 | 0.02 | ug/g | ND | 114 | 50-140 | | | |
| Benzo [k] fluoranthene | 0.265 | 0.02 | ug/g | ND | 139 | 50-140 | | | |
| Chrysene | 0.292 | 0.02 | ug/g | 0.030 | 136 | 50-140 | | | |
| Dibenzo [a,h] anthracene | 0.175 | 0.02 | ug/g | ND | 91.3 | 50-140 | | | |
| Fluoranthene | 0.112 | 0.02 | ug/g | ND | 67.1 | 50-140 | | | |
| Fluorene | 0.213 | 0.02 | ug/g | ND | 111 | 50-140 | | | |
| Indeno [1,2,3-cd] pyrene | 0.220 | 0.02 | ug/g | ND | 115 | 50-140 | | | |
| 1-Methylnaphthalene | 0.120 | 0.02 | ug/g | ND | 62.7 | 50-140 | | | |
| 2-Methylnaphthalene | 0.136 | 0.02 | ug/g | ND | 71.2 | 50-140 | | | |
| Naphthalene | 0.181 | 0.01 | ug/g | 0.013 | 87.6 | 50-140 | | | |
| Phenanthrene | 0.109 | 0.02 | ug/g | ND | 65.2 | 50-140 | | | |
| Pyrene | 0.108 | 0.02 | ug/g | ND | 65.0 | 50-140 | | | |
| Surrogate: 2-Fluorobiphenyl | 0.829 | | ug/g | | 54.1 | 50-140 | | | |
| Surrogate: Terphenyl-d14 | 1.66 | | ug/g | | 108 | 50-140 | | | |

Certificate of Analysis

Report Date: 26-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 20-Oct-2020

Client PO: 31420

Project Description: PE4999

Qualifier Notes:

Sample Qualifiers :

1 : GC-FID signal did not return to baseline by C50

QC Qualifiers :

Sample Data Revisions

None

Work Order Revisions / Comments:

None

Other Report Notes:

n/a: not applicable
ND: Not Detected
MDL: Method Detection Limit
Source Result: Data used as source for matrix and duplicate samples
%REC: Percent recovery.
RPD: Relative percent difference.
NC: Not Calculated

Soil results are reported on a dry weight basis when the units are denoted with 'dry'.
Where %Solids is reported, moisture loss includes the loss of volatile hydrocarbons.

CCME PHC additional information:

- The method for the analysis of PHCs complies with the Reference Method for the CWS PHC and is validated for use in the laboratory. All prescribed quality criteria identified in the method has been met.
- F1 range corrected for BTEX.
- F2 to F3 ranges corrected for appropriate PAHs where available.
- The gravimetric heavy hydrocarbons (F4G) are not to be added to C6 to C50 hydrocarbons.
- In the case where F4 and F4G are both reported, the greater of the two results is to be used for comparison to CWS PHC criteria.
- When reported, data for F4G has been processed using a silica gel cleanup.



| | |
|--|--|
| Parcel Order Number (Lab Use Only) 2043350 | Chain Of Custody (Lab Use Only) No 55010 |
|--|--|

| | | |
|--------------------------------------|---|--|
| Client Name: Paterson Group | Project Ref: PE1999 | Page 1 of 2 |
| Contact Name: Nick Sullivan | Quote #: | Turnaround Time <input type="checkbox"/> 1 day <input type="checkbox"/> 3 day <input type="checkbox"/> 2 day <input checked="" type="checkbox"/> Regular |
| Address: 154 Colonnade Rd. S. | PO #: 31420 | |
| Telephone: 613-226-7381 | E-mail: nsullivan@patersongroup.ca | |

| Regulation 153/04 | | Other Regulation | | Matrix Type: S (Soil/Sed.) GW (Ground Water) SW (Surface Water) SS (Storm/Sanitary Sewer) P (Paint) A (Air) O (Other) | | Required Analysis | | | | | | | | |
|---|--|--|------------------------------------|---|--------|-------------------|-----------------|--------------|------|------------|------|--------------|---------|-------------|
| <input type="checkbox"/> Table 1 | <input checked="" type="checkbox"/> Res/Park | <input type="checkbox"/> Med/Fine | <input type="checkbox"/> REG 558 | <input type="checkbox"/> PWQO | Matrix | Air Volume | # of Containers | Sample Taken | | PHC F2-F21 | PAHs | Metals (ICP) | Mercury | Chromium VI |
| <input type="checkbox"/> Table 2 | <input type="checkbox"/> Ind/Comm | <input checked="" type="checkbox"/> Coarse | <input type="checkbox"/> CCME | <input type="checkbox"/> MISA | | | | Date | Time | | | | | |
| <input checked="" type="checkbox"/> Table 3 | <input type="checkbox"/> Agri/Other | | <input type="checkbox"/> SU - Sani | <input type="checkbox"/> SU - Storm | | | | | | | | | | |
| For RSC: <input type="checkbox"/> Yes <input type="checkbox"/> No | | Mun: _____ | | Other: _____ | | | | | | | | | | |
| Sample ID/Location Name | | | | | | | | | | | | | | |
| 1 | TP1-G2 | | | S | | 1 | Oct. 19.20 | AM | X | X | X | X | X | |
| 2 | TP2-G1 | | | | | 1 | | | | | | | | |
| 3 | TP4-G2 | | | | | 1 | | | | | | | | |
| 4 | TP5-G2 | | | | | 1 | | | | | | | | |
| 5 | TP7-G1 | | | | | 1 | | | | | | | | |
| 6 | TP8-G2 | | | | | 1 | | | | | | | | |
| 7 | TP10-G1 | | | | | 1 | | | | | | | | |
| 8 | TP11-G1 | | | | | 1 | | | | | | | | |
| 9 | TP12-G1 | | | | | 1 | | | | | | | | |
| 10 | TP13-G1 | | | | | 1 | | | | | | | | |

| | |
|-----------|---|
| Comments: | Method of Delivery: PARACEL CURIEL |
|-----------|---|

| | | | |
|---|--|--|---|
| Relinquished By (Sign): N. Sullivan | Received By Driver/Depot: A. Drouse | Received at Lab: Juneppann Dohmai | Verified By: Sam |
| Relinquished By (Print): Nick Sullivan | Date/Time: 20/10/20 3:25 | Date/Time: Oct 20, 2020 04:50 | Date/Time: Oct 21, 2020 13:30 |
| Date/Time: Oct. 20.20 | Temperature: °C PA | Temperature: 10.1 °C | pH Verified: <input type="checkbox"/> By: _____ |



2043350

No 55011

| | | |
|--------------------------------------|---|--|
| Client Name: <i>Paterson Group</i> | Project Ref: <i>PE4999</i> | Page <i>2</i> of <i>2</i> |
| Contact Name: <i>Nick Sullivan</i> | Quote #: | Turnaround Time <input type="checkbox"/> 1 day <input type="checkbox"/> 3 day <input type="checkbox"/> 2 day <input checked="" type="checkbox"/> Regular |
| Address: <i>154 Colonnade Rd. S.</i> | PO #: <i>31420</i> | |
| Telephone: <i>613-226-7381</i> | E-mail: <i>nsullivan@patersongroup.ca</i> | |
| Date Required: _____ | | |

| Regulation 153/04 | | Other Regulation | | Matrix Type: S (Soil/Sed.) GW (Ground Water) SW (Surface Water) SS (Storm/Sanitary Sewer) P (Paint) A (Air) O (Other) | | Required Analysis | | | | | | | | | | | | | | | | |
|---|--|--|------------------------------------|---|----------|--------------------|-----------------|--------------|----------|------------|----------|--------------|---------|-------------|--|--|--|--|--|--|--|--|
| <input type="checkbox"/> Table 1 | <input checked="" type="checkbox"/> Res/Park | <input type="checkbox"/> Med/Fine | <input type="checkbox"/> REG 558 | <input type="checkbox"/> PWQO | Matrix | Air Volume | # of Containers | Sample Taken | | PHCs F2-F4 | PAHs | Metals (ICP) | Mercury | Chromium VI | | | | | | | | |
| <input type="checkbox"/> Table 2 | <input type="checkbox"/> Ind/Comm | <input checked="" type="checkbox"/> Coarse | <input type="checkbox"/> CCME | <input type="checkbox"/> MISA | | | | Date | Time | | | | | | | | | | | | | |
| <input checked="" type="checkbox"/> Table 3 | <input type="checkbox"/> Agri/Other | | <input type="checkbox"/> SU - Sani | <input type="checkbox"/> SU - Storm | | | | | | | | | | | | | | | | | | |
| For RSC: <input type="checkbox"/> Yes <input type="checkbox"/> No | | Mun: _____ | Other: _____ | | | | | | | | | | | | | | | | | | | |
| Sample ID/Location Name | | | | | | | | | | | | | | | | | | | | | | |
| 1 | <i>JP14-G1</i> | | <i>S</i> | | <i>1</i> | <i>Oct. 19. 20</i> | <i>AM</i> | <i>X</i> | <i>X</i> | <i>X</i> | <i>X</i> | <i>X</i> | | | | | | | | | | |
| 2 | | | | | | | | | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | | | | | | | |

| | | | |
|---|--|--|---|
| Comments: | | Method of Delivery: <i>PARACEL COURIER</i> | |
| Relinquished By (Sign): <i>N. Sullivan</i> | Received By Driver/Depot: <i>A. TROUPE</i> | Received at Lab: <i>Suneparm Colmar</i> | Verified By: <i>STAM</i> |
| Relinquished By (Print): <i>Nick Sullivan</i> | Date/Time: <i>20/10/20 3:25</i> | Date/Time: <i>Oct 20, 2020 04:50</i> | Date/Time: <i>Oct 21, 2020 13:30</i> |
| Date/Time: <i>Oct. 20. 20</i> | Temperature: _____ °C <i>PH</i> | Temperature: <i>10.1</i> °C | pH Verified: <input type="checkbox"/> By: _____ |

Certificate of Analysis

Paterson Group Consulting Engineers

154 Colonnade Road South
Nepean, ON K2E 7J5
Attn: Nick Sullivan

Client PO: 31397
Project: PE4999
Custody: 116611

Report Date: 8-Oct-2020
Order Date: 5-Oct-2020

Order #: 2041094

This Certificate of Analysis contains analytical data applicable to the following samples as submitted:

| Parcel ID | Client ID |
|------------|-----------|
| 2041094-01 | BH2-GW1 |
| 2041094-02 | BH4-GW1 |
| 2041094-03 | BH5-GW1 |
| 2041094-04 | DUP1 |

Approved By:



Dale Robertson, BSc
Laboratory Director

Certificate of Analysis

Report Date: 08-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 5-Oct-2020

Client PO: 31397

Project Description: PE4999

Analysis Summary Table

| Analysis | Method Reference/Description | Extraction Date | Analysis Date |
|----------------------------|---------------------------------|-----------------|---------------|
| BTEX by P&T GC-MS | EPA 624 - P&T GC-MS | 6-Oct-20 | 6-Oct-20 |
| PHC F1 | CWS Tier 1 - P&T GC-FID | 6-Oct-20 | 6-Oct-20 |
| PHCs F2 to F4 | CWS Tier 1 - GC-FID, extraction | 7-Oct-20 | 7-Oct-20 |
| REG 153: VOCs by P&T GC/MS | EPA 624 - P&T GC-MS | 6-Oct-20 | 6-Oct-20 |

Certificate of Analysis

Report Date: 08-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 5-Oct-2020

Client PO: 31397

Project Description: PE4999

| Client ID: | BH2-GW1 | BH4-GW1 | BH5-GW1 | DUP1 |
|--------------|-----------------|-----------------|-----------------|-----------------|
| Sample Date: | 02-Oct-20 12:00 | 02-Oct-20 12:00 | 02-Oct-20 12:00 | 02-Oct-20 12:00 |
| Sample ID: | 2041094-01 | 2041094-02 | 2041094-03 | 2041094-04 |
| MDL/Units | Water | Water | Water | Water |

| Volatiles | | | | | |
|--|-----------|---------|---------|---------|------|
| Compound | MDL/Units | BH2-GW1 | BH4-GW1 | BH5-GW1 | DUP1 |
| Acetone | 5.0 ug/L | - | <5.0 | <5.0 | <5.0 |
| Benzene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Bromodichloromethane | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Bromoform | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Bromomethane | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Carbon Tetrachloride | 0.2 ug/L | - | <0.2 | <0.2 | <0.2 |
| Chlorobenzene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Chloroform | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Dibromochloromethane | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Dichlorodifluoromethane | 1.0 ug/L | - | <1.0 | <1.0 | <1.0 |
| 1,2-Dichlorobenzene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 1,3-Dichlorobenzene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 1,4-Dichlorobenzene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 1,1-Dichloroethane | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 1,2-Dichloroethane | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 1,1-Dichloroethylene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| cis-1,2-Dichloroethylene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| trans-1,2-Dichloroethylene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 1,2-Dichloropropane | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| cis-1,3-Dichloropropylene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| trans-1,3-Dichloropropylene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 1,3-Dichloropropene, total | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Ethylbenzene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Ethylene dibromide (dibromoethane, 1,2-) | 0.2 ug/L | - | <0.2 | <0.2 | <0.2 |
| Hexane | 1.0 ug/L | - | <1.0 | <1.0 | <1.0 |
| Methyl Ethyl Ketone (2-Butanone) | 5.0 ug/L | - | <5.0 | <5.0 | <5.0 |
| Methyl Isobutyl Ketone | 5.0 ug/L | - | <5.0 | <5.0 | <5.0 |
| Methyl tert-butyl ether | 2.0 ug/L | - | <2.0 | <2.0 | <2.0 |
| Methylene Chloride | 5.0 ug/L | - | <5.0 | <5.0 | <5.0 |
| Styrene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 1,1,1,2-Tetrachloroethane | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 1,1,2,2-Tetrachloroethane | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Tetrachloroethylene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Toluene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 1,1,1-Trichloroethane | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |

Certificate of Analysis

Report Date: 08-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 5-Oct-2020

Client PO: 31397

Project Description: PE4999

| | Client ID: | BH2-GW1 | BH4-GW1 | BH5-GW1 | DUP1 |
|------------------------|--------------|-----------------|-----------------|-----------------|-----------------|
| | Sample Date: | 02-Oct-20 12:00 | 02-Oct-20 12:00 | 02-Oct-20 12:00 | 02-Oct-20 12:00 |
| | Sample ID: | 2041094-01 | 2041094-02 | 2041094-03 | 2041094-04 |
| | MDL/Units | Water | Water | Water | Water |
| 1,1,2-Trichloroethane | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Trichloroethylene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Trichlorofluoromethane | 1.0 ug/L | - | <1.0 | <1.0 | <1.0 |
| Vinyl chloride | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| m,p-Xylenes | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| o-Xylene | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| Xylenes, total | 0.5 ug/L | - | <0.5 | <0.5 | <0.5 |
| 4-Bromofluorobenzene | Surrogate | - | 97.0% | 97.0% | 96.3% |
| Dibromofluoromethane | Surrogate | - | 98.1% | 98.2% | 79.0% |
| Toluene-d8 | Surrogate | - | 104% | 105% | 106% |
| Benzene | 0.5 ug/L | <0.5 | - | - | - |
| Ethylbenzene | 0.5 ug/L | <0.5 | - | - | - |
| Toluene | 0.5 ug/L | <0.5 | - | - | - |
| m,p-Xylenes | 0.5 ug/L | <0.5 | - | - | - |
| o-Xylene | 0.5 ug/L | <0.5 | - | - | - |
| Xylenes, total | 0.5 ug/L | <0.5 | - | - | - |
| Toluene-d8 | Surrogate | 105% | - | - | - |

Hydrocarbons

| | | | | | |
|-------------------|----------|------|------|------|---|
| F1 PHCs (C6-C10) | 25 ug/L | <25 | <25 | <25 | - |
| F2 PHCs (C10-C16) | 100 ug/L | <100 | <100 | <100 | - |
| F3 PHCs (C16-C34) | 100 ug/L | <100 | <100 | <100 | - |
| F4 PHCs (C34-C50) | 100 ug/L | <100 | <100 | <100 | - |

Certificate of Analysis

Report Date: 08-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 5-Oct-2020

Client PO: 31397

Project Description: PE4999

Method Quality Control: Blank

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|---|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | ND | 25 | ug/L | | | | | | |
| F2 PHCs (C10-C16) | ND | 100 | ug/L | | | | | | |
| F3 PHCs (C16-C34) | ND | 100 | ug/L | | | | | | |
| F4 PHCs (C34-C50) | ND | 100 | ug/L | | | | | | |
| Volatiles | | | | | | | | | |
| Acetone | ND | 5.0 | ug/L | | | | | | |
| Benzene | ND | 0.5 | ug/L | | | | | | |
| Bromodichloromethane | ND | 0.5 | ug/L | | | | | | |
| Bromoform | ND | 0.5 | ug/L | | | | | | |
| Bromomethane | ND | 0.5 | ug/L | | | | | | |
| Carbon Tetrachloride | ND | 0.2 | ug/L | | | | | | |
| Chlorobenzene | ND | 0.5 | ug/L | | | | | | |
| Chloroform | ND | 0.5 | ug/L | | | | | | |
| Dibromochloromethane | ND | 0.5 | ug/L | | | | | | |
| Dichlorodifluoromethane | ND | 1.0 | ug/L | | | | | | |
| 1,2-Dichlorobenzene | ND | 0.5 | ug/L | | | | | | |
| 1,3-Dichlorobenzene | ND | 0.5 | ug/L | | | | | | |
| 1,4-Dichlorobenzene | ND | 0.5 | ug/L | | | | | | |
| 1,1-Dichloroethane | ND | 0.5 | ug/L | | | | | | |
| 1,2-Dichloroethane | ND | 0.5 | ug/L | | | | | | |
| 1,1-Dichloroethylene | ND | 0.5 | ug/L | | | | | | |
| cis-1,2-Dichloroethylene | ND | 0.5 | ug/L | | | | | | |
| trans-1,2-Dichloroethylene | ND | 0.5 | ug/L | | | | | | |
| 1,2-Dichloropropane | ND | 0.5 | ug/L | | | | | | |
| cis-1,3-Dichloropropylene | ND | 0.5 | ug/L | | | | | | |
| trans-1,3-Dichloropropylene | ND | 0.5 | ug/L | | | | | | |
| 1,3-Dichloropropene, total | ND | 0.5 | ug/L | | | | | | |
| Ethylbenzene | ND | 0.5 | ug/L | | | | | | |
| Ethylene dibromide (dibromoethane, 1,2- | ND | 0.2 | ug/L | | | | | | |
| Hexane | ND | 1.0 | ug/L | | | | | | |
| Methyl Ethyl Ketone (2-Butanone) | ND | 5.0 | ug/L | | | | | | |
| Methyl Isobutyl Ketone | ND | 5.0 | ug/L | | | | | | |
| Methyl tert-butyl ether | ND | 2.0 | ug/L | | | | | | |
| Methylene Chloride | ND | 5.0 | ug/L | | | | | | |
| Styrene | ND | 0.5 | ug/L | | | | | | |
| 1,1,1,2-Tetrachloroethane | ND | 0.5 | ug/L | | | | | | |
| 1,1,2,2-Tetrachloroethane | ND | 0.5 | ug/L | | | | | | |
| Tetrachloroethylene | ND | 0.5 | ug/L | | | | | | |
| Toluene | ND | 0.5 | ug/L | | | | | | |
| 1,1,1-Trichloroethane | ND | 0.5 | ug/L | | | | | | |
| 1,1,2-Trichloroethane | ND | 0.5 | ug/L | | | | | | |
| Trichloroethylene | ND | 0.5 | ug/L | | | | | | |
| Trichlorofluoromethane | ND | 1.0 | ug/L | | | | | | |
| Vinyl chloride | ND | 0.5 | ug/L | | | | | | |
| m,p-Xylenes | ND | 0.5 | ug/L | | | | | | |
| o-Xylene | ND | 0.5 | ug/L | | | | | | |
| Xylenes, total | ND | 0.5 | ug/L | | | | | | |
| Surrogate: 4-Bromofluorobenzene | 77.9 | | ug/L | | 97.4 | 50-140 | | | |
| Surrogate: Dibromofluoromethane | 76.5 | | ug/L | | 95.6 | 50-140 | | | |
| Surrogate: Toluene-d8 | 84.3 | | ug/L | | 105 | 50-140 | | | |
| Benzene | ND | 0.5 | ug/L | | | | | | |
| Ethylbenzene | ND | 0.5 | ug/L | | | | | | |
| Toluene | ND | 0.5 | ug/L | | | | | | |
| m,p-Xylenes | ND | 0.5 | ug/L | | | | | | |
| o-Xylene | ND | 0.5 | ug/L | | | | | | |
| Xylenes, total | ND | 0.5 | ug/L | | | | | | |
| Surrogate: Toluene-d8 | 84.3 | | ug/L | | 105 | 50-140 | | | |

Certificate of Analysis

Report Date: 08-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 5-Oct-2020

Client PO: 31397

Project Description: PE4999

Method Quality Control: Duplicate

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|---|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | ND | 25 | ug/L | ND | | | NC | 30 | |
| Volatiles | | | | | | | | | |
| Acetone | ND | 5.0 | ug/L | ND | | | NC | 30 | |
| Benzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Bromodichloromethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Bromoform | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Bromomethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Carbon Tetrachloride | ND | 0.2 | ug/L | ND | | | NC | 30 | |
| Chlorobenzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Chloroform | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Dibromochloromethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Dichlorodifluoromethane | ND | 1.0 | ug/L | ND | | | NC | 30 | |
| 1,2-Dichlorobenzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,3-Dichlorobenzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,4-Dichlorobenzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1-Dichloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,2-Dichloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1-Dichloroethylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| cis-1,2-Dichloroethylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| trans-1,2-Dichloroethylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,2-Dichloropropane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| cis-1,3-Dichloropropylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| trans-1,3-Dichloropropylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Ethylbenzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Ethylene dibromide (dibromoethane, 1,2- | ND | 0.2 | ug/L | ND | | | NC | 30 | |
| Hexane | ND | 1.0 | ug/L | ND | | | NC | 30 | |
| Methyl Ethyl Ketone (2-Butanone) | ND | 5.0 | ug/L | ND | | | NC | 30 | |
| Methyl Isobutyl Ketone | ND | 5.0 | ug/L | ND | | | NC | 30 | |
| Methyl tert-butyl ether | ND | 2.0 | ug/L | ND | | | NC | 30 | |
| Methylene Chloride | ND | 5.0 | ug/L | ND | | | NC | 30 | |
| Styrene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1,1,2-Tetrachloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1,2,2-Tetrachloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Tetrachloroethylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Toluene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1,1-Trichloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1,2-Trichloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Trichloroethylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Trichlorofluoromethane | ND | 1.0 | ug/L | ND | | | NC | 30 | |
| Vinyl chloride | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| m,p-Xylenes | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| o-Xylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Surrogate: 4-Bromofluorobenzene | 78.2 | | ug/L | | 97.7 | 50-140 | | | |
| Surrogate: Dibromofluoromethane | 77.6 | | ug/L | | 97.0 | 50-140 | | | |
| Surrogate: Toluene-d8 | 83.6 | | ug/L | | 104 | 50-140 | | | |
| Benzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Ethylbenzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Toluene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| m,p-Xylenes | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| o-Xylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Surrogate: Toluene-d8 | 83.6 | | ug/L | | 104 | 50-140 | | | |

Certificate of Analysis

Report Date: 08-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 5-Oct-2020

Client PO: 31397

Project Description: PE4999

Method Quality Control: Spike

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|---|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | 1740 | 25 | ug/L | ND | 86.8 | 68-117 | | | |
| F2 PHCs (C10-C16) | 1840 | 100 | ug/L | ND | 115 | 60-140 | | | |
| F3 PHCs (C16-C34) | 4590 | 100 | ug/L | ND | 117 | 60-140 | | | |
| F4 PHCs (C34-C50) | 2840 | 100 | ug/L | ND | 115 | 60-140 | | | |
| Volatiles | | | | | | | | | |
| Acetone | 96.6 | 5.0 | ug/L | ND | 96.6 | 50-140 | | | |
| Benzene | 40.3 | 0.5 | ug/L | ND | 101 | 60-130 | | | |
| Bromodichloromethane | 41.9 | 0.5 | ug/L | ND | 105 | 60-130 | | | |
| Bromoform | 42.4 | 0.5 | ug/L | ND | 106 | 60-130 | | | |
| Bromomethane | 47.4 | 0.5 | ug/L | ND | 119 | 50-140 | | | |
| Carbon Tetrachloride | 41.7 | 0.2 | ug/L | ND | 104 | 60-130 | | | |
| Chlorobenzene | 41.3 | 0.5 | ug/L | ND | 103 | 60-130 | | | |
| Chloroform | 41.6 | 0.5 | ug/L | ND | 104 | 60-130 | | | |
| Dibromochloromethane | 43.5 | 0.5 | ug/L | ND | 109 | 60-130 | | | |
| Dichlorodifluoromethane | 44.2 | 1.0 | ug/L | ND | 110 | 50-140 | | | |
| 1,2-Dichlorobenzene | 41.9 | 0.5 | ug/L | ND | 105 | 60-130 | | | |
| 1,3-Dichlorobenzene | 42.4 | 0.5 | ug/L | ND | 106 | 60-130 | | | |
| 1,4-Dichlorobenzene | 41.9 | 0.5 | ug/L | ND | 105 | 60-130 | | | |
| 1,1-Dichloroethane | 42.4 | 0.5 | ug/L | ND | 106 | 60-130 | | | |
| 1,2-Dichloroethane | 40.4 | 0.5 | ug/L | ND | 101 | 60-130 | | | |
| 1,1-Dichloroethylene | 40.7 | 0.5 | ug/L | ND | 102 | 60-130 | | | |
| cis-1,2-Dichloroethylene | 41.5 | 0.5 | ug/L | ND | 104 | 60-130 | | | |
| trans-1,2-Dichloroethylene | 42.4 | 0.5 | ug/L | ND | 106 | 60-130 | | | |
| 1,2-Dichloropropane | 41.7 | 0.5 | ug/L | ND | 104 | 60-130 | | | |
| cis-1,3-Dichloropropylene | 39.5 | 0.5 | ug/L | ND | 98.8 | 60-130 | | | |
| trans-1,3-Dichloropropylene | 39.2 | 0.5 | ug/L | ND | 98.0 | 60-130 | | | |
| Ethylbenzene | 40.2 | 0.5 | ug/L | ND | 101 | 60-130 | | | |
| Ethylene dibromide (dibromoethane, 1,2- | 39.0 | 0.2 | ug/L | ND | 97.5 | 60-130 | | | |
| Methyl Ethyl Ketone (2-Butanone) | 86.2 | 5.0 | ug/L | ND | 86.2 | 50-140 | | | |
| Methyl Isobutyl Ketone | 89.7 | 5.0 | ug/L | ND | 89.7 | 50-140 | | | |
| Methyl tert-butyl ether | 87.2 | 2.0 | ug/L | ND | 87.2 | 50-140 | | | |
| Methylene Chloride | 37.0 | 5.0 | ug/L | ND | 92.6 | 60-130 | | | |
| Styrene | 38.6 | 0.5 | ug/L | ND | 96.6 | 60-130 | | | |
| 1,1,1,2-Tetrachloroethane | 40.2 | 0.5 | ug/L | ND | 101 | 60-130 | | | |
| 1,1,2,2-Tetrachloroethane | 39.8 | 0.5 | ug/L | ND | 99.4 | 60-130 | | | |
| Tetrachloroethylene | 40.6 | 0.5 | ug/L | ND | 102 | 60-130 | | | |
| Toluene | 40.8 | 0.5 | ug/L | ND | 102 | 60-130 | | | |
| 1,1,1-Trichloroethane | 41.7 | 0.5 | ug/L | ND | 104 | 60-130 | | | |
| 1,1,2-Trichloroethane | 40.2 | 0.5 | ug/L | ND | 100 | 60-130 | | | |
| Trichloroethylene | 42.7 | 0.5 | ug/L | ND | 107 | 60-130 | | | |
| Trichlorofluoromethane | 43.3 | 1.0 | ug/L | ND | 108 | 60-130 | | | |
| Vinyl chloride | 46.8 | 0.5 | ug/L | ND | 117 | 50-140 | | | |
| m,p-Xylenes | 81.0 | 0.5 | ug/L | ND | 101 | 60-130 | | | |
| o-Xylene | 40.0 | 0.5 | ug/L | ND | 100 | 60-130 | | | |
| Surrogate: 4-Bromofluorobenzene | 83.9 | | ug/L | | 105 | 50-140 | | | |
| Surrogate: Dibromofluoromethane | 84.2 | | ug/L | | 105 | 50-140 | | | |
| Surrogate: Toluene-d8 | 81.2 | | ug/L | | 102 | 50-140 | | | |
| Benzene | 40.3 | 0.5 | ug/L | ND | 101 | 60-130 | | | |

Certificate of Analysis

Report Date: 08-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 5-Oct-2020

Client PO: 31397

Project Description: PE4999

Method Quality Control: Spike

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|-----------------------|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Ethylbenzene | 40.2 | 0.5 | ug/L | ND | 101 | 60-130 | | | |
| Toluene | 40.8 | 0.5 | ug/L | ND | 102 | 60-130 | | | |
| m,p-Xylenes | 81.0 | 0.5 | ug/L | ND | 101 | 60-130 | | | |
| o-Xylene | 40.0 | 0.5 | ug/L | ND | 100 | 60-130 | | | |
| Surrogate: Toluene-d8 | 81.2 | | ug/L | | 102 | 50-140 | | | |

Certificate of Analysis

Report Date: 08-Oct-2020

Client: Paterson Group Consulting Engineers

Order Date: 5-Oct-2020

Client PO: 31397

Project Description: PE4999

Qualifier Notes:

None

Sample Data Revisions

None

Work Order Revisions / Comments:

None

Other Report Notes:

n/a: not applicable
ND: Not Detected
MDL: Method Detection Limit
Source Result: Data used as source for matrix and duplicate samples
%REC: Percent recovery.
RPD: Relative percent difference.
NC: Not Calculated

CCME PHC additional information:

- The method for the analysis of PHCs complies with the Reference Method for the CWS PHC and is validated for use in the laboratory. All prescribed quality criteria identified in the method has been met.
- F1 range corrected for BTEX.
- F2 to F3 ranges corrected for appropriate PAHs where available.
- The gravimetric heavy hydrocarbons (F4G) are not to be added to C6 to C50 hydrocarbons.
- In the case where F4 and F4G are both reported, the greater of the two results is to be used for comparison to CWS PHC criteria.
- When reported, data for F4G has been processed using a silica gel cleanup.



Head Office
300-2319 St. Laurent Blvd.
Ottawa, Ontario K1G 4J8
p: 1-800-749-1947
e: parcel@paracellabs.com

Chain of Custody
(Lab Use Only)
No 116611

Page 1 of 1

| | | |
|--------------------------------------|--|--|
| Client Name: <u>Paterson Group</u> | Project Reference: <u>PE4999</u> | Turnaround Time: <input type="checkbox"/> 1 Day <input type="checkbox"/> 3 Day <input type="checkbox"/> 2 Day <input checked="" type="checkbox"/> Regular Date Required: _____ |
| Contact Name: <u>Nick Sullivan</u> | Quote # | |
| Address: <u>154 Colonnade Rd. S.</u> | PO # <u>31397</u> | |
| Telephone: <u>613-226-7381</u> | Email Address: <u>nsullivan@patersongroup.ca</u> | |

Criteria: O. Reg. 153/04 (As Amended) Table 3 RSC Filing O. Reg. 558/00 PWQO CCME SUB (Storm) SUB (Sanitary) Municipality: _____ Other: _____

Matrix Type: S (Soil/Sed.) GW (Ground Water) SW (Surface Water) SS (Storm/Sanitary Sewer) P (Paint) A (Air) O (Other) Required Analyses

| Parcel Order Number: <u>2041094</u> | | Matrix | Air Volume | # of Containers | Sample Taken | | PHCs F1-F4+BTEX | VOCs | PAHs | Metals by ICP | Hg | CrVI | B (HWS) | PHCs F1-F4 |
|--|---------|--------|------------|-----------------|--------------|------|-----------------|------|------|---------------|----|------|---------|------------|
| Sample ID/Location Name | | | | | Date | Time | | | | | | | | |
| 1 | BH2-GWI | GW | | 3 | Oct. 2.20 | PM | X | | | | | | | |
| 2 | BH4-GWI | ↓ | | 3 | ↓ | ↓ | | X | | | | | | X |
| 3 | BH5-GWI | ↓ | | 3 | ↓ | ↓ | | X | | | | | | X |
| 4 | DUP 1 | ↓ | | 2 | ↓ | ↓ | | X | | | | | | |
| 5 | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | |

Comments: _____ Method of Delivery: PARACEL COURIER

| | | | |
|---|--|------------------------------------|---------------------------------|
| Relinquished By (Sign): <u>N. Sullivan</u> | Received by Driver/Depot: <u>A. J. LOUIE</u> | Received at Lab: <u>Paracel</u> | Verified By: <u>[Signature]</u> |
| Relinquished By (Print): <u>Nick Sullivan</u> | Date/Time: <u>05/10/20 3:04</u> | Date/Time: <u>5 Oct 2020 15:57</u> | Date/Time: <u>10-5-20/6:17</u> |
| Date/Time: <u>October 5, 2020</u> | Temperature: <u>14°C</u> | Temperature: <u>17.7°C</u> | pH Verified [] By: _____ |

Certificate of Analysis

Paterson Group Consulting Engineers

154 Colonnade Road South
Nepean, ON K2E 7J5
Attn: Mark D'Arcy

Client PO: 31218
Project: PE4999
Custody: 54893

Report Date: 18-Nov-2020
Order Date: 12-Nov-2020

Order #: 2046443

This Certificate of Analysis contains analytical data applicable to the following samples as submitted:

| Paracel ID | Client ID |
|------------|------------|
| 2046443-01 | BH6-20-GW1 |

Approved By:



Dale Robertson, BSc
Laboratory Director

Certificate of Analysis

Report Date: 18-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 12-Nov-2020

Client PO: 31218

Project Description: PE4999

Analysis Summary Table

| Analysis | Method Reference/Description | Extraction Date | Analysis Date |
|----------------------------|---------------------------------|-----------------|---------------|
| PHC F1 | CWS Tier 1 - P&T GC-FID | 13-Nov-20 | 14-Nov-20 |
| PHCs F2 to F4 | CWS Tier 1 - GC-FID, extraction | 17-Nov-20 | 18-Nov-20 |
| REG 153: VOCs by P&T GC/MS | EPA 624 - P&T GC-MS | 13-Nov-20 | 14-Nov-20 |

Certificate of Analysis

Report Date: 18-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 12-Nov-2020

Client PO: 31218

Project Description: PE4999

| | | | | |
|---------------------|-----------------|---|---|---|
| Client ID: | BH6-20-GW1 | - | - | - |
| Sample Date: | 12-Nov-20 09:00 | - | - | - |
| Sample ID: | 2046443-01 | - | - | - |
| MDL/Units | Water | - | - | - |

| Volatiles | | | | | |
|--|----------|------|---|---|---|
| Acetone | 5.0 ug/L | <5.0 | - | - | - |
| Benzene | 0.5 ug/L | <0.5 | - | - | - |
| Bromodichloromethane | 0.5 ug/L | <0.5 | - | - | - |
| Bromoform | 0.5 ug/L | <0.5 | - | - | - |
| Bromomethane | 0.5 ug/L | <0.5 | - | - | - |
| Carbon Tetrachloride | 0.2 ug/L | <0.2 | - | - | - |
| Chlorobenzene | 0.5 ug/L | <0.5 | - | - | - |
| Chloroform | 0.5 ug/L | <0.5 | - | - | - |
| Dibromochloromethane | 0.5 ug/L | <0.5 | - | - | - |
| Dichlorodifluoromethane | 1.0 ug/L | <1.0 | - | - | - |
| 1,2-Dichlorobenzene | 0.5 ug/L | <0.5 | - | - | - |
| 1,3-Dichlorobenzene | 0.5 ug/L | <0.5 | - | - | - |
| 1,4-Dichlorobenzene | 0.5 ug/L | <0.5 | - | - | - |
| 1,1-Dichloroethane | 0.5 ug/L | <0.5 | - | - | - |
| 1,2-Dichloroethane | 0.5 ug/L | <0.5 | - | - | - |
| 1,1-Dichloroethylene | 0.5 ug/L | <0.5 | - | - | - |
| cis-1,2-Dichloroethylene | 0.5 ug/L | <0.5 | - | - | - |
| trans-1,2-Dichloroethylene | 0.5 ug/L | <0.5 | - | - | - |
| 1,2-Dichloropropane | 0.5 ug/L | <0.5 | - | - | - |
| cis-1,3-Dichloropropylene | 0.5 ug/L | <0.5 | - | - | - |
| trans-1,3-Dichloropropylene | 0.5 ug/L | <0.5 | - | - | - |
| 1,3-Dichloropropene, total | 0.5 ug/L | <0.5 | - | - | - |
| Ethylbenzene | 0.5 ug/L | <0.5 | - | - | - |
| Ethylene dibromide (dibromoethane, 1,2-) | 0.2 ug/L | <0.2 | - | - | - |
| Hexane | 1.0 ug/L | <1.0 | - | - | - |
| Methyl Ethyl Ketone (2-Butanone) | 5.0 ug/L | <5.0 | - | - | - |
| Methyl Isobutyl Ketone | 5.0 ug/L | <5.0 | - | - | - |
| Methyl tert-butyl ether | 2.0 ug/L | <2.0 | - | - | - |
| Methylene Chloride | 5.0 ug/L | <5.0 | - | - | - |
| Styrene | 0.5 ug/L | <0.5 | - | - | - |
| 1,1,1,2-Tetrachloroethane | 0.5 ug/L | <0.5 | - | - | - |
| 1,1,2,2-Tetrachloroethane | 0.5 ug/L | <0.5 | - | - | - |
| Tetrachloroethylene | 0.5 ug/L | <0.5 | - | - | - |
| Toluene | 0.5 ug/L | <0.5 | - | - | - |
| 1,1,1-Trichloroethane | 0.5 ug/L | <0.5 | - | - | - |

Certificate of Analysis

Report Date: 18-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 12-Nov-2020

Client PO: 31218

Project Description: PE4999

| | Client ID: | BH6-20-GW1 | - | - | - |
|------------------------|--------------|-----------------|---|---|---|
| | Sample Date: | 12-Nov-20 09:00 | - | - | - |
| | Sample ID: | 2046443-01 | - | - | - |
| | MDL/Units | Water | - | - | - |
| 1,1,2-Trichloroethane | 0.5 ug/L | <0.5 | - | - | - |
| Trichloroethylene | 0.5 ug/L | <0.5 | - | - | - |
| Trichlorofluoromethane | 1.0 ug/L | <1.0 | - | - | - |
| Vinyl chloride | 0.5 ug/L | <0.5 | - | - | - |
| m,p-Xylenes | 0.5 ug/L | <0.5 | - | - | - |
| o-Xylene | 0.5 ug/L | <0.5 | - | - | - |
| Xylenes, total | 0.5 ug/L | <0.5 | - | - | - |
| 4-Bromofluorobenzene | Surrogate | 116% | - | - | - |
| Dibromofluoromethane | Surrogate | 102% | - | - | - |
| Toluene-d8 | Surrogate | 115% | - | - | - |

Hydrocarbons

| | | | | | |
|-------------------|----------|------|---|---|---|
| F1 PHCs (C6-C10) | 25 ug/L | <25 | - | - | - |
| F2 PHCs (C10-C16) | 100 ug/L | <100 | - | - | - |
| F3 PHCs (C16-C34) | 100 ug/L | <100 | - | - | - |
| F4 PHCs (C34-C50) | 100 ug/L | <100 | - | - | - |

Certificate of Analysis

Report Date: 18-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 12-Nov-2020

Client PO: 31218

Project Description: PE4999

Method Quality Control: Blank

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|---|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | ND | 25 | ug/L | | | | | | |
| F2 PHCs (C10-C16) | ND | 100 | ug/L | | | | | | |
| F3 PHCs (C16-C34) | ND | 100 | ug/L | | | | | | |
| F4 PHCs (C34-C50) | ND | 100 | ug/L | | | | | | |
| Volatiles | | | | | | | | | |
| Acetone | ND | 5.0 | ug/L | | | | | | |
| Benzene | ND | 0.5 | ug/L | | | | | | |
| Bromodichloromethane | ND | 0.5 | ug/L | | | | | | |
| Bromoform | ND | 0.5 | ug/L | | | | | | |
| Bromomethane | ND | 0.5 | ug/L | | | | | | |
| Carbon Tetrachloride | ND | 0.2 | ug/L | | | | | | |
| Chlorobenzene | ND | 0.5 | ug/L | | | | | | |
| Chloroform | ND | 0.5 | ug/L | | | | | | |
| Dibromochloromethane | ND | 0.5 | ug/L | | | | | | |
| Dichlorodifluoromethane | ND | 1.0 | ug/L | | | | | | |
| 1,2-Dichlorobenzene | ND | 0.5 | ug/L | | | | | | |
| 1,3-Dichlorobenzene | ND | 0.5 | ug/L | | | | | | |
| 1,4-Dichlorobenzene | ND | 0.5 | ug/L | | | | | | |
| 1,1-Dichloroethane | ND | 0.5 | ug/L | | | | | | |
| 1,2-Dichloroethane | ND | 0.5 | ug/L | | | | | | |
| 1,1-Dichloroethylene | ND | 0.5 | ug/L | | | | | | |
| cis-1,2-Dichloroethylene | ND | 0.5 | ug/L | | | | | | |
| trans-1,2-Dichloroethylene | ND | 0.5 | ug/L | | | | | | |
| 1,2-Dichloropropane | ND | 0.5 | ug/L | | | | | | |
| cis-1,3-Dichloropropylene | ND | 0.5 | ug/L | | | | | | |
| trans-1,3-Dichloropropylene | ND | 0.5 | ug/L | | | | | | |
| 1,3-Dichloropropene, total | ND | 0.5 | ug/L | | | | | | |
| Ethylbenzene | ND | 0.5 | ug/L | | | | | | |
| Ethylene dibromide (dibromoethane, 1,2- | ND | 0.2 | ug/L | | | | | | |
| Hexane | ND | 1.0 | ug/L | | | | | | |
| Methyl Ethyl Ketone (2-Butanone) | ND | 5.0 | ug/L | | | | | | |
| Methyl Isobutyl Ketone | ND | 5.0 | ug/L | | | | | | |
| Methyl tert-butyl ether | ND | 2.0 | ug/L | | | | | | |
| Methylene Chloride | ND | 5.0 | ug/L | | | | | | |
| Styrene | ND | 0.5 | ug/L | | | | | | |
| 1,1,1,2-Tetrachloroethane | ND | 0.5 | ug/L | | | | | | |
| 1,1,2,2-Tetrachloroethane | ND | 0.5 | ug/L | | | | | | |
| Tetrachloroethylene | ND | 0.5 | ug/L | | | | | | |
| Toluene | ND | 0.5 | ug/L | | | | | | |
| 1,1,1-Trichloroethane | ND | 0.5 | ug/L | | | | | | |
| 1,1,2-Trichloroethane | ND | 0.5 | ug/L | | | | | | |
| Trichloroethylene | ND | 0.5 | ug/L | | | | | | |
| Trichlorofluoromethane | ND | 1.0 | ug/L | | | | | | |
| Vinyl chloride | ND | 0.5 | ug/L | | | | | | |
| m,p-Xylenes | ND | 0.5 | ug/L | | | | | | |
| o-Xylene | ND | 0.5 | ug/L | | | | | | |
| Xylenes, total | ND | 0.5 | ug/L | | | | | | |
| Surrogate: 4-Bromofluorobenzene | 90.2 | | ug/L | | 113 | 50-140 | | | |
| Surrogate: Dibromofluoromethane | 78.1 | | ug/L | | 97.7 | 50-140 | | | |
| Surrogate: Toluene-d8 | 95.2 | | ug/L | | 119 | 50-140 | | | |

Certificate of Analysis

Report Date: 18-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 12-Nov-2020

Client PO: 31218

Project Description: PE4999

Method Quality Control: Duplicate

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|---|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | ND | 25 | ug/L | ND | | | NC | 30 | |
| Volatiles | | | | | | | | | |
| Acetone | ND | 5.0 | ug/L | ND | | | NC | 30 | |
| Benzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Bromodichloromethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Bromoform | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Bromomethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Carbon Tetrachloride | ND | 0.2 | ug/L | ND | | | NC | 30 | |
| Chlorobenzene | 3.03 | 0.5 | ug/L | 3.07 | | | 1.3 | 30 | |
| Chloroform | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Dibromochloromethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Dichlorodifluoromethane | ND | 1.0 | ug/L | ND | | | NC | 30 | |
| 1,2-Dichlorobenzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,3-Dichlorobenzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,4-Dichlorobenzene | 6.90 | 0.5 | ug/L | 6.81 | | | 1.3 | 30 | |
| 1,1-Dichloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,2-Dichloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1-Dichloroethylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| cis-1,2-Dichloroethylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| trans-1,2-Dichloroethylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,2-Dichloropropane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| cis-1,3-Dichloropropylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| trans-1,3-Dichloropropylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Ethylbenzene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Ethylene dibromide (dibromoethane, 1,2- | ND | 0.2 | ug/L | ND | | | NC | 30 | |
| Hexane | ND | 1.0 | ug/L | ND | | | NC | 30 | |
| Methyl Ethyl Ketone (2-Butanone) | ND | 5.0 | ug/L | ND | | | NC | 30 | |
| Methyl Isobutyl Ketone | ND | 5.0 | ug/L | ND | | | NC | 30 | |
| Methyl tert-butyl ether | ND | 2.0 | ug/L | ND | | | NC | 30 | |
| Methylene Chloride | ND | 5.0 | ug/L | ND | | | NC | 30 | |
| Styrene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1,1,2-Tetrachloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1,2,2-Tetrachloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Tetrachloroethylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Toluene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1,1-Trichloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| 1,1,2-Trichloroethane | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Trichloroethylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Trichlorofluoromethane | ND | 1.0 | ug/L | ND | | | NC | 30 | |
| Vinyl chloride | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| m,p-Xylenes | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| o-Xylene | ND | 0.5 | ug/L | ND | | | NC | 30 | |
| Surrogate: 4-Bromofluorobenzene | 94.7 | | ug/L | | 118 | 50-140 | | | |
| Surrogate: Dibromofluoromethane | 80.2 | | ug/L | | 100 | 50-140 | | | |
| Surrogate: Toluene-d8 | 93.6 | | ug/L | | 117 | 50-140 | | | |

Certificate of Analysis

Report Date: 18-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 12-Nov-2020

Client PO: 31218

Project Description: PE4999

Method Quality Control: Spike

| Analyte | Result | Reporting Limit | Units | Source Result | %REC | %REC Limit | RPD | RPD Limit | Notes |
|---|--------|-----------------|-------|---------------|------|------------|-----|-----------|-------|
| Hydrocarbons | | | | | | | | | |
| F1 PHCs (C6-C10) | 2120 | 25 | ug/L | ND | 106 | 68-117 | | | |
| F2 PHCs (C10-C16) | 1800 | 100 | ug/L | ND | 112 | 60-140 | | | |
| F3 PHCs (C16-C34) | 4220 | 100 | ug/L | ND | 108 | 60-140 | | | |
| F4 PHCs (C34-C50) | 2940 | 100 | ug/L | ND | 119 | 60-140 | | | |
| Volatiles | | | | | | | | | |
| Acetone | 110 | 5.0 | ug/L | ND | 110 | 50-140 | | | |
| Benzene | 36.6 | 0.5 | ug/L | ND | 91.4 | 60-130 | | | |
| Bromodichloromethane | 34.1 | 0.5 | ug/L | ND | 85.2 | 60-130 | | | |
| Bromoform | 37.8 | 0.5 | ug/L | ND | 94.4 | 60-130 | | | |
| Bromomethane | 40.9 | 0.5 | ug/L | ND | 102 | 50-140 | | | |
| Carbon Tetrachloride | 33.8 | 0.2 | ug/L | ND | 84.4 | 60-130 | | | |
| Chlorobenzene | 41.8 | 0.5 | ug/L | ND | 105 | 60-130 | | | |
| Chloroform | 36.4 | 0.5 | ug/L | ND | 91.1 | 60-130 | | | |
| Dibromochloromethane | 40.2 | 0.5 | ug/L | ND | 100 | 60-130 | | | |
| Dichlorodifluoromethane | 37.2 | 1.0 | ug/L | ND | 93.1 | 50-140 | | | |
| 1,2-Dichlorobenzene | 46.5 | 0.5 | ug/L | ND | 116 | 60-130 | | | |
| 1,3-Dichlorobenzene | 46.0 | 0.5 | ug/L | ND | 115 | 60-130 | | | |
| 1,4-Dichlorobenzene | 43.9 | 0.5 | ug/L | ND | 110 | 60-130 | | | |
| 1,1-Dichloroethane | 36.3 | 0.5 | ug/L | ND | 90.8 | 60-130 | | | |
| 1,2-Dichloroethane | 31.0 | 0.5 | ug/L | ND | 77.4 | 60-130 | | | |
| 1,1-Dichloroethylene | 36.1 | 0.5 | ug/L | ND | 90.3 | 60-130 | | | |
| cis-1,2-Dichloroethylene | 38.3 | 0.5 | ug/L | ND | 95.8 | 60-130 | | | |
| trans-1,2-Dichloroethylene | 38.4 | 0.5 | ug/L | ND | 96.0 | 60-130 | | | |
| 1,2-Dichloropropane | 37.2 | 0.5 | ug/L | ND | 93.0 | 60-130 | | | |
| cis-1,3-Dichloropropylene | 38.0 | 0.5 | ug/L | ND | 95.0 | 60-130 | | | |
| trans-1,3-Dichloropropylene | 34.8 | 0.5 | ug/L | ND | 86.9 | 60-130 | | | |
| Ethylbenzene | 40.6 | 0.5 | ug/L | ND | 102 | 60-130 | | | |
| Ethylene dibromide (dibromoethane, 1,2- | 40.6 | 0.2 | ug/L | ND | 102 | 60-130 | | | |
| Hexane | 50.0 | 1.0 | ug/L | ND | 125 | 60-130 | | | |
| Methyl Ethyl Ketone (2-Butanone) | 97.5 | 5.0 | ug/L | ND | 97.5 | 50-140 | | | |
| Methyl Isobutyl Ketone | 89.3 | 5.0 | ug/L | ND | 89.3 | 50-140 | | | |
| Methyl tert-butyl ether | 92.7 | 2.0 | ug/L | ND | 92.7 | 50-140 | | | |
| Methylene Chloride | 37.3 | 5.0 | ug/L | ND | 93.4 | 60-130 | | | |
| Styrene | 37.6 | 0.5 | ug/L | ND | 94.0 | 60-130 | | | |
| 1,1,1,2-Tetrachloroethane | 39.4 | 0.5 | ug/L | ND | 98.5 | 60-130 | | | |
| 1,1,2,2-Tetrachloroethane | 44.9 | 0.5 | ug/L | ND | 112 | 60-130 | | | |
| Tetrachloroethylene | 44.5 | 0.5 | ug/L | ND | 111 | 60-130 | | | |
| Toluene | 42.6 | 0.5 | ug/L | ND | 106 | 60-130 | | | |
| 1,1,1-Trichloroethane | 35.3 | 0.5 | ug/L | ND | 88.4 | 60-130 | | | |
| 1,1,2-Trichloroethane | 37.9 | 0.5 | ug/L | ND | 94.7 | 60-130 | | | |
| Trichloroethylene | 37.4 | 0.5 | ug/L | ND | 93.6 | 60-130 | | | |
| Trichlorofluoromethane | 35.6 | 1.0 | ug/L | ND | 89.0 | 60-130 | | | |
| Vinyl chloride | 33.0 | 0.5 | ug/L | ND | 82.6 | 50-140 | | | |
| m,p-Xylenes | 85.0 | 0.5 | ug/L | ND | 106 | 60-130 | | | |
| o-Xylene | 39.8 | 0.5 | ug/L | ND | 99.6 | 60-130 | | | |
| Surrogate: 4-Bromofluorobenzene | 92.5 | | ug/L | | 116 | 50-140 | | | |
| Surrogate: Dibromofluoromethane | 73.5 | | ug/L | | 91.9 | 50-140 | | | |
| Surrogate: Toluene-d8 | 83.3 | | ug/L | | 104 | 50-140 | | | |

Certificate of Analysis

Report Date: 18-Nov-2020

Client: Paterson Group Consulting Engineers

Order Date: 12-Nov-2020

Client PO: 31218

Project Description: PE4999

Qualifier Notes:

None

Sample Data Revisions

None

Work Order Revisions / Comments:

None

Other Report Notes:

n/a: not applicable
ND: Not Detected
MDL: Method Detection Limit
Source Result: Data used as source for matrix and duplicate samples
%REC: Percent recovery.
RPD: Relative percent difference.
NC: Not Calculated

CCME PHC additional information:

- The method for the analysis of PHCs complies with the Reference Method for the CWS PHC and is validated for use in the laboratory. All prescribed quality criteria identified in the method has been met.
- F1 range corrected for BTEX.
- F2 to F3 ranges corrected for appropriate PAHs where available.
- The gravimetric heavy hydrocarbons (F4G) are not to be added to C6 to C50 hydrocarbons.
- In the case where F4 and F4G are both reported, the greater of the two results is to be used for comparison to CWS PHC criteria.
- When reported, data for F4G has been processed using a silica gel cleanup.

