

3288 & 3300 Borrisokane Road, 4205, 4345 & 4375 McKenna
Casey Drive

Transportation Impact Assessment

Step 1 Screening Report

Step 2 Scoping Report

Step 3 Forecasting Report

Step 4 Strategy Report (Revision 1)

Prepared for:

Barrhaven Conservancy Development Corporation
2934 Baseline Road, Suite 302
Ottawa, ON K2H 1B2

Prepared by:



6 Plaza Court
Ottawa, ON K2G 3Z1

December 2022

PN: 2021-115

Table of Contents

| | | |
|-------|---|----|
| 1 | Screening..... | 1 |
| 2 | Existing and Planned Conditions..... | 1 |
| 2.1 | Proposed Development..... | 1 |
| 2.2 | Existing Conditions..... | 3 |
| 2.2.1 | Area Road Network..... | 3 |
| 2.2.2 | Existing Intersections..... | 3 |
| 2.2.3 | Existing Driveways..... | 4 |
| 2.2.4 | Cycling and Pedestrian Facilities..... | 4 |
| 2.2.5 | Existing Transit..... | 6 |
| 2.2.6 | Existing Area Traffic Management Measures..... | 8 |
| 2.2.7 | Existing Peak Hour Travel Demand..... | 8 |
| 2.2.8 | Collision Analysis..... | 9 |
| 2.3 | Planned Conditions..... | 12 |
| 2.3.1 | Changes to the Area Transportation Network..... | 12 |
| 2.3.2 | Other Study Area Developments..... | 13 |
| 3 | Study Area and Time Periods..... | 15 |
| 3.1 | Study Area..... | 15 |
| 3.2 | Time Periods..... | 15 |
| 3.3 | Horizon Years..... | 15 |
| 4 | Exemption Review..... | 15 |
| 5 | Development-Generated Travel Demand..... | 16 |
| 5.1 | Mode Shares..... | 16 |
| 5.2 | Trip Generation..... | 17 |
| 5.3 | Trip Distribution..... | 18 |
| 5.4 | Trip Assignment..... | 18 |
| 6 | Background Network Travel Demands..... | 19 |
| 6.1 | Transportation Network Plans..... | 19 |
| 6.2 | Background Growth..... | 19 |
| 6.3 | Other Developments..... | 21 |
| 7 | Demand Rationalization..... | 22 |
| 7.1 | 2030 Future Background Operations..... | 22 |
| 7.2 | 2035 Future Background Operations..... | 24 |
| 7.3 | Demand Rationalization Conclusions..... | 27 |
| 8 | Development Design..... | 27 |
| 8.1 | Design for Sustainable Modes..... | 27 |
| 8.2 | New Street Networks..... | 28 |
| 9 | Boundary Street Design..... | 29 |
| 10 | Access Intersections Design..... | 29 |
| 10.1 | Location and Design of Access..... | 29 |
| 10.2 | Intersection Control..... | 29 |
| 10.3 | Access Intersection Design..... | 29 |
| 11 | Transportation Demand Management..... | 29 |

11.1 Context for TDM 29

11.2 Need and Opportunity..... 29

11.3 TDM Program 29

12 Neighbourhood Traffic Management..... 30

13 Transit..... 30

13.1 Route Capacity..... 30

13.2 Transit Priority 30

14 Network Concept..... 31

15 Network Intersection Design..... 31

15.1 Network Intersection Control..... 31

15.2 Network Intersection Design..... 31

15.2.1 2030 Future Total Network Intersection Operations 31

15.2.2 2035 Future Total Network Intersection Operations 33

15.2.3 Network Intersection MMLOS..... 35

15.2.4 Recommended Design Elements..... 37

16 Summary of Improvements Indicated and Modifications Options..... 37

17 Conclusion 40

List of Figures

Figure 1: Area Context Plan1

Figure 2: Concept Plan.....2

Figure 3: Existing Driveways4

Figure 4: Study Area Pedestrian Facilities5

Figure 5: Study Area Cycling Facilities5

Figure 6: Existing Pedestrian Volumes6

Figure 7: Existing Cyclist Volumes6

Figure 8: Existing Study Area Transit Service.....7

Figure 9: Existing Study Area Transit Stops7

Figure 10: Existing Traffic Counts8

Figure 11: Study Area Collision Records – Representation of 2015-2019..... 10

Figure 12: New Site Generation Auto Volumes..... 19

Figure 13: 2030 Background Growth..... 20

Figure 14: 2035 Background Growth..... 20

Figure 15: Total Background Development Traffic..... 22

Figure 16: 2030 Future Background Volumes 23

Figure 17: 2035 Future Background Volumes 25

Figure 18: Concept Pedestrian and Cycling Network 27

Figure 19: Concept Pedestrian and Cycling Network 28

Figure 20: 2030 Future Total Volumes 32

Figure 21: 2035 Future Total Volumes 34

Table of Tables

| | |
|--|----|
| Table 1: Intersection Count Date..... | 8 |
| Table 2: Existing Intersection Operations..... | 9 |
| Table 3: Study Area Collision Summary, 2016-2020 | 10 |
| Table 4: Summary of Collision Locations, 2016-2020..... | 11 |
| Table 5: Borrisokane Road/Tartan Drive at Strandherd Drive Collision Summary..... | 11 |
| Table 6: Borrisokane Road Between Cambrian Road and Strandherd Drive Collision Summary | 12 |
| Table 7: Exemption Review | 15 |
| Table 8: TRANS Trip Generation Person Trip Rates – South Nepean | 16 |
| Table 9: Proposed Development Mode Shares | 17 |
| Table 10: Generation Person Trip Rates by Peak Period..... | 17 |
| Table 11: Total Residential Person Trip Generation by Peak Period..... | 17 |
| Table 12: Trip Generation by Mode | 17 |
| Table 13: OD Survey Distribution – South Nepean | 18 |
| Table 14: Trip Assignment..... | 18 |
| Table 15: 2030 Future Background Intersection Operations | 23 |
| Table 16: 2035 Future Background Intersection Operations | 26 |
| Table 17: Trip Generation by Transit Mode | 30 |
| Table 18: Forecasted Site-Generated Transit Ridership..... | 30 |
| Table 19: 2030 Future Total Network Intersection Operations | 32 |
| Table 20: 2035 Future Total Network Intersection Operations | 34 |
| Table 21: Study Area Intersection MMLoS Analysis | 36 |

List of Appendices

| |
|--|
| Appendix A – TIA Screening Form and Certification Form |
| Appendix B – Turning Movement Count Data |
| Appendix C – Synchro Intersection Worksheets – Existing Conditions |
| Appendix D – Collision Data |
| Appendix E – Synchro Intersection Worksheets – 2030 Future Background Conditions |
| Appendix F – Synchro Intersection Worksheets – 2035 Future Background Conditions |
| Appendix G – TDM Checklist |
| Appendix H – Justification 7 Signal Warrants |
| Appendix I – Synchro Intersection Worksheets – 2030 Future Total Conditions |
| Appendix J – Synchro Intersection Worksheets – 2035 Future Total Conditions |
| Appendix K – MMLoS Analysis |

1 Screening


This study has been prepared according to the City of Ottawa’s 2017 Transportation Impact Assessment (TIA) Guidelines. Accordingly, a Step 1 Screening Form has been prepared and is included as Appendix A, along with the Certification Form for TIA Study PM. As shown in the Screening Form, a TIA is required including the Design Review component and the Network Impact Component. This TIA will support a zoning bylaw amendment and a plan of subdivision application. The first submission was completed in October 2021 and City comments were received in the spring/summer of 2022.

2 Existing and Planned Conditions

2.1 Proposed Development


The proposed development, located at 3288 and 3300 Borrisokane Road and 4305, 4345 and 4375 McKenna Casey Drive, is zoned as Development Reserve Zone (DR). The proposed development consists of a mix of residential product types, totalling approximately 499 townhomes and 462 single detached homes. The collector roads located within the East Phase will connect the West Phase to the boundary street network on Borrisokane Road. The anticipated full build-out and occupancy horizon is 2030 with construction occurring in a single phase. The site is located within the Nepean South 10 Secondary Plan area. Figure 1 illustrates the Study Area Context. Figure 2 illustrates the proposed concept plan.

Figure 1: Area Context Plan



Source: <http://maps.ottawa.ca/geoOttawa/> Accessed: November 7, 2022

Figure 2: Concept Plan



SCALE: 1:1000
 DATE: 10/15/2011
 DRAWN BY: J. BARNES
 CHECKED BY: J. BARNES
 APPROVED BY: J. BARNES

ADDITIONAL INFORMATION AS REQUIRED UNDER SECTION 34(1) OF THE PLANNING ACT R.S.O. 2001
 CONGRESSIONAL ACT 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100



| SCHEDULE OF LAND USE | | |
|----------------------|--------|--------|
| LAND AREA | 100.00 | 100.00 |
| BLK 1-10 | 10.00 | 10.00 |
| BLK 11-20 | 10.00 | 10.00 |
| BLK 21-30 | 10.00 | 10.00 |
| BLK 31-40 | 10.00 | 10.00 |
| BLK 41-50 | 10.00 | 10.00 |
| BLK 51-60 | 10.00 | 10.00 |
| BLK 61-70 | 10.00 | 10.00 |
| BLK 71-80 | 10.00 | 10.00 |
| BLK 81-90 | 10.00 | 10.00 |
| BLK 91-100 | 10.00 | 10.00 |
| TOTAL | 100.00 | 100.00 |

DRAFT PLAN OF SUBDIVISION
 PART OF LOTS 13, 14 AND 15
 CONGRESSION 4 (RIDEAU FRONT)
 CITY OF OTTAWA

NOTES
 1. ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SPECIFIED.
 2. THE PLAN IS TO BE CONSIDERED AS A PRELIMINARY PLAN.
 3. THE PLAN IS TO BE CONSIDERED AS A PRELIMINARY PLAN.
 4. THE PLAN IS TO BE CONSIDERED AS A PRELIMINARY PLAN.
 5. THE PLAN IS TO BE CONSIDERED AS A PRELIMINARY PLAN.

LEGEND
 - - - - - PROPOSED
 - - - - - EXISTING

OWNER'S CERTIFICATE
 I, the undersigned, being the owner of the land hereinafter described, do hereby certify that the plan hereon is a true and correct copy of the original plan as filed in the office of the Registrar of Deeds.

SURVEYOR'S CERTIFICATE
 I, the undersigned, being a duly qualified and licensed Surveyor, do hereby certify that the plan hereon is a true and correct copy of the original plan as filed in the office of the Registrar of Deeds.

FOR REVIEW
 THE REGISTRAR OF DEEDS

PRELIMINARY
 THIS PLAN IS NOT TO BE USED FOR ANY PURPOSE WITHOUT THE WRITTEN CONSENT OF THE SURVEYOR.

J.D.BARNES
 SURVEYOR

2.2 Existing Conditions

2.2.1 Area Road Network

Borrisokane Road: Borrisokane Road is a City of Ottawa arterial road with a two-lane rural cross-section including gravel shoulders and an 80 km/h posted speed limit along the frontage of the site. South Cambrian Road, Borrisokane Road becomes a collector road, the cross section does not change. The City-protected right-of-way is 37.5 metres rights through the subject site.

Strandherd Drive: Strandherd Drive is a City of Ottawa arterial road with a two-lane rural cross-section including paved shoulders. The posted speed limit is 80 km/h, and the City-protected right-of-way is 44.5 metres. No sidewalks are provided along the section of Strandherd Drive within the study area.

Kennevale Drive: Kennevale Road is a City of Ottawa collector road with an urban two-lane cross-section permitting parking on both sides of the roadway. Sidewalks are provided on both sides of the road and the posted speed limit is 40 km/h. The existing right-of-way is 20.0 metres.

Dealership Way: Dealership Way is a City of Ottawa collector road with an urban two-lane cross-section permitting parking on both sides of the roadway. Sidewalks are provided on both sides of the road and the posted speed limit is 40 km/h. The existing right-of-way is 24.0 metres.

Tartan Drive: Tartan Drive is a City of Ottawa collector road with a two-lane rural cross-section including gravel shoulders and a 40 km/h posted speed limit, near Strandherd Drive. The existing right-of-way is 26.0 metres.

McKenna Casey Drive: McKenna Casey Drive is a City of Ottawa local road with a two-lane rural cross-section including gravel shoulders. The posted speed limit changed from 60 km/h to 80 km/h at approximately 70 metres west of the Strandherd Drive at McKenna Casey Drive intersection. The existing right-of-way is 20.0 metres.

2.2.2 Existing Intersections

The existing signalized area intersections within approximately one kilometre of the site have been summarized below:

Strandherd Drive at Kennevale Drive/Dealership Way

The intersection of Strandherd Drive and Kennevale Drive/Dealership Way is a signalized intersection. The northbound, southbound, and eastbound approaches consist of an auxiliary left-turn lane, a through lane, and an auxiliary right-turn lane. The westbound approach consists of an auxiliary left-turn lane and a shared through/right-turn lane. Bike pockets are provided on the north and south bound approaches. No turn restrictions were noted.

Strandherd Drive at Borrisokane Road/Tartan Drive

The intersection of Strandherd Drive at Borrisokane Road/Tartan Drive is a signalized intersection with left-turn auxiliary lanes on all approaches. Crosswalks are present on each leg of the intersection; however, these do not connect to sidewalks. West of the intersection an at grade cycling lane is provided alongside an auxiliary right-turn lane into an adjacent development. Further east and west of the intersection paved shoulders are provided. No turn restrictions were noted.


Strandherd Drive at McKenna Casey Drive

The intersection of Strandherd Drive at *McKenna Casey Drive* is an unsignalized intersection. The eastbound approach consists of a shared through/right-turn lane, the westbound approach consists of a shared through/left-turn lane, and the northbound approaches consist of a shared left-turn/right-turn lane. No turn restrictions were noted.

2.2.3 Existing Driveways

Within 200 metres of the future collector road intersections on Borrisokane Road, construction accesses are located at the future intersection locations, field accesses to the south adjacent to the Jock River, a driveway to an existing residential property, and a construction access for the Strandherd Drive widening project. None of the driveways within the area of consideration are significant traffic generators. Figure 3 illustrates the existing driveways.

Figure 3: Existing Driveways



Source: <http://maps.ottawa.ca/geoOttawa/> Accessed: November 7, 2022


2.2.4 Cycling and Pedestrian Facilities

Figure 4 illustrates the pedestrian facilities in the study area and Figure 5 illustrates the cycling facilities.

Strandherd Drive and McKenna Casey Drive is noted on the City of Ottawa’s Existing Cycling Network as a “Paved Shoulder”. No pedestrian facilities are provided along either Strandherd Drive or Borrisokane Road. Both networks are developing in the area and will include sidewalks and cycling tracks along Strandherd Drive, and future pathways are planned along the Jock River and Chapman Mills BRT corridor.


Strandherd Drive is spine route, and Borrisokane Road and McKenna Casey Drive are local routes. Major pathways are provided along rail, Strandherd Drive, Jock River and Highway 416.

Figure 4: Study Area Pedestrian Facilities



Source: <http://maps.ottawa.ca/geoOttawa/> Accessed: November 7, 2022

Figure 5: Study Area Cycling Facilities



Source: <http://maps.ottawa.ca/geoOttawa/> Accessed: November 7, 2022

Pedestrian and cyclist volumes included in study area intersection counts, presented in Section 2.2.7, have been compiled and are illustrated in Figure 6 and Figure 7, respectively. Only the intersections of Kennevale at Strandherd, and Borrisokane at Strandherd had pedestrian and cyclist volumes available.

Figure 6: Existing Pedestrian Volumes





Figure 7: Existing Cyclist Volumes




2.2.5 Existing Transit

Figure 8 illustrates the transit system map in the study area and Figure 9 illustrates nearby transit stops. All transit information is from November 7, 2022 and is included for general information purposes and context to the surrounding area.

Within the study area, the routes #170, 173 and 273 provide service within 800 metres of the proposed site. Primary stops are located on Tartan Dive north of Strandherd Drive. The frequency of these routes within proximity of the proposed site based on November 7, 2022 service levels are:


- Route #170 – 30-minute service during evenings and weekdays
- Route #173 – 1-hour service during the day (assumed reduced service from typical 30-minute service during peak hour)
- Route #273 – Peak hour service only, with trips starting at 6:00 to 8:35 AM every 20-30 minutes to downtown, returned 3:30 to 6:25 PM to Strandherd Drive and Jockvale Road

Figure 8: Existing Study Area Transit Service



Source: <http://www.octranspo.com/> Accessed: November 7, 2022

Figure 9: Existing Study Area Transit Stops



Source: <http://maps.ottawa.ca/geoOttawa/> Accessed: November 7, 2022

2.2.6 Existing Area Traffic Management Measures

There are no existing area traffic management measures within the Study Area.

2.2.7 Existing Peak Hour Travel Demand

Existing turning movement counts were acquired from the City of Ottawa for the existing Study Area intersection. The intersections were also balanced, and the adjacent developments completed, such as Minto Harmony and Caivan Conservancy Phase 1, have been included to account for additional volumes along Strandherd Drive. Table 1 summarizes the intersection count dates.

Table 1: Intersection Count Date

| Intersection | Count Date |
|--------------------------------------|------------------|
| Kennevale Drive at Strandherd Drive | January 18, 2018 |
| Borrisokane Road at Strandherd Drive | January 18, 2018 |

Figure 10 illustrates the existing traffic counts and Table 2 summarizes the existing intersection operations. The level of service for signalized intersections is based on volume to capacity ratio (v/c) calculations for individual lane movements and HCM 2000 v/c calculations for the overall intersection, and average delay for unsignalized intersections. Detailed turning movement count data is included in Appendix B and the Synchro worksheets are provided in Appendix C.

Figure 10: Existing Traffic Counts




Table 2: Existing Intersection Operations

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|---|----------------|--------------|-------------|-------------|-----------------------|--------------|-------------|-------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Strandherd Drive & Dealership Way/Kennevale Drive <i>Signalized</i> | EBL | A | 0.06 | 43.5 | 5.5 | A | 0.17 | 42.9 | 14.6 |
| | EBT | A | 0.01 | 41.5 | 2.7 | A | 0.03 | 39.0 | 6.0 |
| | EBR | A | 0.03 | 0.1 | 0.0 | A | 0.07 | 0.5 | 0.0 |
| | WBL | B | 0.66 | 66.8 | 41.2 | C | 0.74 | 70.0 | 50.3 |
| | WBT/R | A | 0.42 | 12.7 | 16.4 | A | 0.32 | 12.3 | 14.7 |
| | NBL | A | 0.05 | 10.1 | 5.8 | A | 0.11 | 15.1 | 5.1 |
| | NBT | F | 1.10 | 80.9 | #447.0 | D | 0.82 | 26.9 | #275.3 |
| | NBR | A | 0.10 | 2.7 | 7.5 | A | 0.16 | 4.8 | 14.5 |
| | SBL | A | 0.41 | 20.6 | 13.8 | A | 0.29 | 8.2 | 11.1 |
| | SBT | A | 0.57 | 9.1 | 108.2 | E | 0.96 | 33.6 | #377.2 |
| | SBR | A | 0.02 | 0.9 | 1.3 | A | 0.01 | 0.5 | 0.7 |
| Overall | F | 1.03 | 49.5 | - | E | 0.98 | 29.8 | - | |
| Strandherd Drive & Borrisokane Road/Tartan Drive <i>Signalized</i> | EBL | E | 0.92 | 99.9 | #46.0 | A | 0.47 | 18.8 | 34.3 |
| | EBT | B | 0.63 | 20.8 | 102.4 | D | 0.85 | 25.9 | #230.3 |
| | EBR | A | 0.20 | 2.8 | 9.0 | A | 0.38 | 2.4 | 12.8 |
| | WBL | A | 0.06 | 12.6 | 4.9 | A | 0.15 | 12.6 | 7.5 |
| | WBT/R | E | 0.97 | 47.3 | #228.5 | C | 0.71 | 18.4 | #154.0 |
| | NBL | E | 0.96 | 69.3 | #120.8 | C | 0.77 | 47.7 | 52.2 |
| | NBT/R | A | 0.14 | 15.1 | 16.3 | A | 0.19 | 14.4 | 13.9 |
| | SBL | A | 0.18 | 22.8 | 20.0 | A | 0.21 | 25.4 | 16.1 |
| | SBT/R | A | 0.26 | 6.9 | 15.9 | A | 0.34 | 11.8 | 19.8 |
| | Overall | E | 0.96 | 38.8 | - | D | 0.82 | 20.4 | - |

Notes: Saturation flow rate of 1800 veh/h/lane
Queue is measured in metres
Peak Hour Factor = 0.90

Delay = average vehicle delay in seconds
m = metered queue
= volume for the 95th %ile cycle exceeds capacity

During both the AM and PM peak hours, the study area intersections are subject to queuing issues generally and capacity issues on various movements.

At the intersection of Strandherd Drive & Dealership Way/Kennevale Drive, the northbound through movement during AM peak hour is over theoretical capacity and may subject to high delays and extended queues. Extended queues may be exhibited on the northbound through and southbound through movements during PM peak hour.

The intersection of Strandherd Drive & Borrisokane Road/Tartan Drive may subject to extended queues on the westbound shared through/right-turn movement, northbound shared through/right-turn movement, and both extended queues and high delay on the eastbound left-turn movement during the AM peak hour. It may also be subject to extended queues on the eastbound through movement and westbound shared through/right-turn movement during PM peak hour.

2.2.8 Collision Analysis

Collision data have been acquired from the City of Ottawa open data website (data.ottawa.ca) for five years prior to the commencement of this TIA for the surrounding study area road network. Table 3 summarizes the collisions types and conditions in the study area, Figure 11 illustrates the intersections and segments analyzed, and Table 4 summarizes the total collisions for each of these locations. Collision data are included in Appendix D.

Table 3: Study Area Collision Summary, 2016-2020

| | | Number | % |
|-------------------------------|----------------------|-----------|-------------|
| Total Collisions | | 74 | 100% |
| Classification | Fatality | 0 | 0% |
| | Non-Fatal Injury | 16 | 22% |
| | Property Damage Only | 58 | 78% |
| Initial Impact Type | Angled | 4 | 5% |
| | Rear end | 37 | 50% |
| | Sideswipe | 4 | 5% |
| | Turning Movement | 7 | 9% |
| | SMV Other | 21 | 28% |
| | Other | 1 | 1% |
| Road Surface Condition | Dry | 47 | 64% |
| | Wet | 16 | 22% |
| | Loose Snow | 4 | 5% |
| | Packed Snow | 2 | 3% |
| | Ice | 5 | 7% |
| Pedestrian Involved | | 0 | 0% |
| Cyclists Involved | | 0 | 0% |

Figure 11: Study Area Collision Records – Representation of 2015-2019




Table 4: Summary of Collision Locations, 2016-2020

| | Number | % |
|--|-----------|-------------|
| Intersections / Segments | 74 | 100% |
| Borriskane Rd/Tartan Dr @ Strandherd Dr | 47 | 64% |
| Strandherd Dr Btwn Cedarview Rd & Mckenna Casey Dr | 4 | 5% |
| Borriskane Rd Btwn Cambrian Rd & Strandherd Dr | 23 | 31% |

Within the study area, the intersection of Borriskane Road/Tartan Drive at Strandherd Drive and Borriskane Road Between Cambrian Road & Strandherd Drive are noted to have experienced higher collisions than other locations. Table 5 and Table 6 summarize the collision types and conditions for these locations.

Table 5: Borriskane Road/Tartan Drive at Strandherd Drive Collision Summary

| | | Number | % |
|-------------------------------|----------------------|-----------|-------------|
| Total Collisions | | 47 | 100% |
| Classification | Fatality | 0 | 0% |
| | Non-Fatal Injury | 9 | 19% |
| | Property Damage Only | 38 | 81% |
| Initial Impact Type | Angle | 4 | 9% |
| | Rear end | 31 | 66% |
| | Sideswipe | 3 | 6% |
| | Turning Movement | 7 | 15% |
| | SMV Other | 2 | 4% |
| Road Surface Condition | Dry | 29 | 62% |
| | Wet | 13 | 28% |
| | Loose Snow | 1 | 2% |
| | Packed Snow | 2 | 4% |
| | Ice | 2 | 4% |
| Pedestrian Involved | | 0 | 0% |
| Cyclists Involved | | 0 | 0% |

The Strandherd Drive and Borriskane Road intersection had a total of 47 collisions during the 2016-2020 time period, with 38 involving property damage only and the remaining nine having non-fatal injuries. The collision types are most represented by rear end with 31 collisions, turning movement with seven collisions, angle with four collisions, sideswipe with three collisions, and the remaining SMV Other two collisions. The rear end collisions are typical of congested conditions. Weather conditions do not influence collisions at this location. No further collision review is required as part of this study.

Table 6: Borrisokane Road Between Cambrian Road and Strandherd Drive Collision Summary

| | | Number | % |
|-------------------------------|-----------------------------|-----------|-------------|
| Total Collisions | | 23 | 100% |
| Classification | Fatality | 0 | 0% |
| | Non-Fatal Injury | 5 | 22% |
| | Property Damage Only | 18 | 78% |
| Initial Impact Type | Rear end | 3 | 13% |
| | SMV Other | 19 | 83% |
| | Other | 1 | 4% |
| Road Surface Condition | Dry | 15 | 65% |
| | Wet | 2 | 9% |
| | Loose Snow | 3 | 13% |
| | Ice | 3 | 13% |
| Pedestrian Involved | | 0 | 0% |
| Cyclists Involved | | 0 | 0% |

The segment of Borrisokane Road between Cambrian Road and Strandherd Drive had a total of 23 collisions during the 2016-2020 time period, with 18 property damage only and five non-fatal injuries. The collision types are most represented by SMV Other with 19 collisions, rear end with three collisions, and a single collision for other. The rural nature of the roadway may be the cause of these collisions, from running off the road or animal strikes. Weather conditions do not influence collisions at this location. No further collision review is required as part of this study.

2.3 Planned Conditions

2.3.1 Changes to the Area Transportation Network

Strandherd Drive Widening (Maravista Drive to Jockvale Road)

The widening of Strandherd Drive from two to four lanes is currently underway. It is anticipated that this will be completed by 2022 and include the reconstruction of the Borrisokane Road at Strandherd Drive intersection. The McKenna Casey Drive connection to Strandherd Drive will be removed and it will end to the west of the CN rail line and Gregory Casey stormwater pond.

Chapman Mills Drive Extension

While beyond the study area, the environmental assessment study was completed in 2016 for the Chapman Mills Drive Extensions and Bus Rapid Transit corridor between Strandherd Drive and Longfields Drive, with the BRT corridor continuing separately to Borrisokane Road. As part of the development in the area, Chapman Mills Drive has been completed on the north-south section from Strandherd to Canoe Street, with an interim road east to the Kennedy-Burnett Stormwater Pond. The roadway is included within the Affordable Network for 2031 and the BRT portion is anticipated to be constructed post 2031. It is understood that the design will be initiated for 2023 with construction subsequent to this in an interim configuration.

Greenbank Road Re-Alignment

While not within the study area, Greenbank Road is planned to be re-aligned from near the existing Jockvale Road intersection with a new bridge crossing to the north of the existing Jock River crossing, and loop around Mattamy's Half Moon Bay North development and connect to Cambrian Road approximately 1.1km to the west of the existing alignment. The construction for Greenbank Road has been delayed as to advance the Strandherd Drive widening, likely to beyond 2031.

Barnsdale Road Highway 416 Interchange

A new interchange at Barnsdale Road to Highway 416 is currently being planned by the City with the Ministry of Transportation Ontario to support the existing and future growth within Barrhaven, specifically south of the Jock River and adjacent to the Fallowfield Drive interchange. The interchange is anticipated to be completed post 2031.

2.3.2 Other Study Area Developments

3195 Jockvale Road

The development is proposed to be a mix of 210 stacked townhome units and approximately 200,000 sq. ft. of retail space, located between the Barrhaven Towncentre and the On The Green golf range. The development will extend Jockvale Road south of the Barrhaven Towncentre and include a new signalized intersection on Greenbank Road. It is estimated that the development will be constructed by 2026.

Harmony Phase 5 – 3232 Jockvale Road

This development is proposed to include a total of 310 apartment units and 602 townhome units and is located on the west side of Greenbank Road, north of the future Chapman Mills Drive corridor. It is estimated that the development will be constructed by 2025.

3201 Greenbank Road

Recently constructed, approximately 11,000 ft² of retail and an 8,000 ft² restaurant space will be incorporated into the existing retail development of the Loblaws and Home Sense.

3288 Greenbank Road

The development is proposed to be a mix of 310 apartment units and 602 townhome units, located between the future Chapman Mills Drive alignment on the north and the Claridge development (3370 Greenbank Road) to the south. It is estimated that the development will be constructed by 2025.

3370 Greenbank Road

This development is proposed to include 177 townhomes in Phase 1, 70 townhomes in Phase 2 and 720 condo units in Phase 3. Originally proposed to be completed by 2020, the plan of subdivision application is currently pending, and the Official Plan and Zoning By-Law Amendment have been adopted.

Riversbend – 3311 Greenbank Road

A residential subdivision is under construction south of St Joseph High School, in conjunction with the City of Ottawa. A total of 144 townhome units (25 within City lands), and 64 mid-rise units (City) will ultimately be constructed within the proposed lands.

Half Moon Bay South Phase 5

The Mattamy Development of Half Moon Bay South Phase 5 is located east of Re-Aligned Greenbank Road and south of Dundonald Drive and is expected to be built-out during 2020. The development will consist of 164 single detached home units and 97 townhouse units. (CGH 2019)

Half Moon Bay West

The Mattamy Development of Half Moon Bay West is located north of Cambrian Road and east of Borrisokane Road and is expected to be built-out during 2024. This development will include 552 single family homes and 464 townhomes. (Stantec 2016)

Half Moon Bay North Phase 9- 2444 Watercolours Way

North of the proposed development is the Half Moon Bay North Phase 9 development which is expected to be built-out during 2019. This development will consist of 60 stacked townhouses. (Stantec 2018)

Quinn's Pointe 2- 3882 Barnsdale and 3960 Greenbank Road

The Minto Development of Quinn's Pointe 2 is located west of Greenbank Road and north of Barnsdale Road. This development will include 536 single-family dwelling units, 493 townhomes, 100 apartment units, and two elementary schools, anticipated over 2 phases of construction for the horizon year of 2024. (Stantec 2018)

The Meadows Phase 5-6

Phase 5-6 (termed Phase 4 during the file circulation) of the Meadows Tamarack Development was expected to be built out during 2019 and is located south of Cambrian Road on the east side of Re-Aligned Greenbank Road. Phase 4 will have 136 townhouse units and 50 single family units. (IBI 2018)

The Meadows Phase 7-8

Phases 7-8 (termed Phase 5 during the file circulation) of the Meadows Tamarack Development is located south of Cambrian Road on the west side of Re-Aligned Greenbank Road. The concept plan considers a total of 221 townhouses and 125 single family units. The full build-out and occupancy of Phase 7 is now assumed to be 2023 and Phase 8 by 2025. (IBI, 2018)

3387 Borrisokane Road

North of Cambrian Road is the Glenview Development of 3387 Borrisokane Road which is expected to be built-out during 2022. The development is expected to have 179 single family units and 109 townhouses. (Stantec 2016)

Citi-Gate Development

North of the proposed development is the Citi Gate Corporate Campus. This development will include 32,516 square metres allocated towards a shopping centre, 165,600 square metres allocated towards business parks and 105,000 square metres allocated towards car dealerships. The full build-out year is 2029. (Novatech 2012)

The new phase of CitiGate has not been incorporated as it will address the issues north of Kennevale Drive to the Highway 416 interchange as part of its scope.

4401 Fallowfield Road Development

This development will not have shared accesses or traffic cross-over but will impact the Study Area intersections. The site trips generated by this site will be accounted for in the traffic projections using the 3285 Borrisokane Road TIS for Phase 1 of the Conservancy Development documenting the 4401 Fallowfield Road traffic volumes.

Harmony Development – 4025 Strandherd Drive

The Minto Communities development of 4025 Strandherd Drive has been constructed and the traffic for this site has been included within the existing conditions.

Conservancy Phase 1 – 3285 Borrisokane Road

On the south side of the Chapman Mills Drive corridor is 3285 Borrisokane Road which is expected to be built-out during 2020. This development will include 125 single family homes and 75 townhouses. (Parsons 2018)

The Ridge/Brazeau – 3809 Borrisokane Road

The proposed development includes 590 residential units, split between townhouse units and detached home units. The site is located on the west side of Re-Aligned Greenbank Road. (CGH 2019)

Drummond Subdivision – 3713 Borrisokane Road

Located west of Re-Aligned Greenbank Road is the proposed residential development of 3713 Borrisokane Road. The development will include approximately 123 detached homes and 439 townhouses and is expected to be built-out during 2024. (CGH 2020)

ABIC Manufacturing – 3713 Borrisokane Road

A light industrial parcel will be developed at 3713 Borrisokane Road along Borrisokane Road and include approximately 3,250 square metres of general office space and 9,385 square metres of industrial buildings and is expected to be built-out during 2022. (CGH 2020)

Conservancy East – 3285, 3288 & 3305 Borrisokane Road

The proposed residential development includes approximately 1,300 units. The anticipated full build-out and occupancy horizon is 2029. An update to Phase 5, on the west side of Borrisokane Road, is planned and will be accounted for in the unit counts and forecasted traffic used within this study. (CGH 2021 & 2022).

3 Study Area and Time Periods

3.1 Study Area

The study area will include the intersection will include:

- Strandherd Drive
 - Dealership Way/Kennevale Drive
 - Tartan Road/Borrisokane Road
- Borrisokane Road
 - Conservancy Way
 - New Collector

No boundary roads are located adjacent to the development. No screenlines are present near the proposed site and any screenline analysis would need extend across Barrhaven to capture each of the north/south or east-west corridors. Therefore, no screenline analysis is included within this TIA study

3.2 Time Periods

As the proposed development is composed entirely of residential units the AM and PM peak hours will be examined.

3.3 Horizon Years

The anticipated build-out year is 2030. As a result, the full build-out plus five years horizon year is 2035.

4 Exemption Review

Table 7 summarizes the exemptions for this TIA.

Table 7: Exemption Review

| Module | Element | Explanation | Exempt/Required |
|--------------------------------|------------------------------|--|-----------------|
| Design Review Component | | | |
| 4.1 Development Design | 4.1.2 Circulation and Access | Only required for site plans | Exempt |
| | 4.2.3 New Street Networks | Only required for plans of subdivision | Required |

| Module | Element | Explanation | Exempt/Required |
|---|-------------------------------|--|-----------------|
| 4.2 Parking | 4.2.1 Parking Supply | Only required for site plans | Exempt |
| | 4.2.2 Spillover Parking | Only required for site plans where parking supply is 15% below unconstrained demand | Exempt |
| rk Impact Component | | | |
| 4.5 Transportation Demand Management | All Elements | Not required for site plans expected to have fewer than 60 employees and/or students on location at any given time | Required |
| 4.6 Neighbourhood Traffic Management | 4.6.1 Adjacent Neighbourhoods | Only required when the development relies on local or collector streets for access and total volumes exceed ATM capacity thresholds | Required |
| 4.8 Network Concept | | Only required when proposed development generates more than 200 person-trips during the peak hour in excess of equivalent volume permitted by established zoning | Required |

5 Development-Generated Travel Demand

5.1 Mode Shares

Examining the mode shares recommended in the TRANS Trip Generation Manual (2020) for the subject district, derived from the most recent National Capital Region Origin-Destination survey (OD Survey), the existing average district mode shares by land use for South Nepean have been summarized in Table 8.

Table 8: TRANS Trip Generation Person Trip Rates – South Nepean

| Travel Mode | Single Detached | | Multi-Unit (Low-Rise) | |
|-----------------------|-----------------|-------------|-----------------------|-------------|
| | AM | PM | AM | PM |
| Auto Driver | 51% | 53% | 49% | 49% |
| Auto Passenger | 14% | 19% | 13% | 13% |
| Transit | 25% | 18% | 26% | 24% |
| Cycling | 1% | 1% | 2% | 2% |
| Walking | 9% | 10% | 9% | 12% |
| Total | 100% | 100% | 100% | 100% |

The widening of Strandherd Drive and the construction of Chapman Mills Drive are scheduled to be constructed within the Study Area by the future horizons of this TIA. The BRT lanes within Chapman Mills Drive are not included in the Affordable Network (2031) and no bus facilities are proposed along Strandherd Drive. Beyond the 2031 horizon, the Chapman Mills BRT is assumed to be in place and the terminus station located on the southwest corner of the Strandherd Drive and Borrisokane Road intersection. As transit will be located in proximity to the proposed subdivision, an increase in transit trips is proposed for the development as a whole. The modified mode share targets are proposed for the development and are summarized in Table 9.

Table 9: Proposed Development Mode Shares

| Travel Mode | Single-Detached | | Multi-Unit (Low-Rise) | |
|----------------|-----------------|-------------|-----------------------|-------------|
| | AM | PM | AM | PM |
| Auto Driver | 41% | 43% | 39% | 39% |
| Auto Passenger | 14% | 19% | 13% | 13% |
| Transit | 35% | 28% | 36% | 34% |
| Cycling | 1% | 1% | 2% | 2% |
| Walking | 9% | 10% | 9% | 12% |
| Total | 100% | 100% | 100% | 100% |

5.2 Trip Generation

This TIA has been prepared using the vehicle and person trip rates for the residential dwellings using the TRANS Trip Generation Manual (2020). Table 10 summarizes the person trip rates for the proposed residential land uses for each peak period.

Table 10: Generation Person Trip Rates by Peak Period

| Land Use | Land Use Code | Peak Period | Person Trip Rates |
|-----------------------|---------------|-------------|-------------------|
| Single-Detached | 210 (TRANS) | AM | 2.05 |
| | | PM | 2.48 |
| Multi-Unit (Low-Rise) | 220 (TRANS) | AM | 1.35 |
| | | PM | 1.58 |

Using the above person trip rates, the total person trip generation has been estimated. Table 11 summarizes the total person trip generation for the residential land uses.

Table 11: Total Residential Person Trip Generation by Peak Period

| Land Use | Units | AM Peak Period | | | PM Peak Period | | |
|-----------------------|-------|----------------|-----|-------|----------------|-----|-------|
| | | In | Out | Total | In | Out | Total |
| Single-Detached | 462 | 284 | 663 | 947 | 711 | 435 | 1146 |
| Multi-Unit (Low-Rise) | 499 | 202 | 472 | 674 | 441 | 347 | 788 |

Using the above mode share targets for a BRT area, the person trip rates, the person trips by mode have been projected. Table 12 summarizes the trip generation by mode and peak hour using the residential peak hour adjustment factor.

Table 12: Trip Generation by Mode

| Travel Mode | | AM Peak Hour | | | | PM Peak Hour | | | |
|-----------------------|----------------|--------------|------------|------------|------------|--------------|------------|------------|------------|
| | | Mode Share | In | Out | Total | Mode Share | In | Out | Total |
| Single-Detached | Auto Driver | 41% | 56 | 131 | 187 | 43% | 135 | 82 | 217 |
| | Auto Passenger | 14% | 19 | 45 | 64 | 19% | 59 | 37 | 96 |
| | Transit | 35% | 54 | 128 | 182 | 28% | 94 | 57 | 151 |
| | Cycling | 1% | 2 | 4 | 6 | 1% | 3 | 2 | 5 |
| | Walking | 9% | 15 | 35 | 50 | 10% | 37 | 23 | 60 |
| | Total | 100% | 146 | 343 | 489 | 100% | 328 | 201 | 529 |
| Multi-Unit (Low-Rise) | Auto Driver | 39% | 38 | 88 | 126 | 39% | 76 | 59 | 135 |
| | Auto Passenger | 13% | 12 | 29 | 41 | 13% | 25 | 20 | 45 |
| | Transit | 36% | 40 | 94 | 134 | 34% | 71 | 55 | 126 |
| | Cycling | 2% | 2 | 5 | 7 | 2% | 4 | 3 | 7 |
| | Walking | 9% | 10 | 24 | 34 | 12% | 28 | 22 | 50 |
| | Total | 100% | 102 | 240 | 342 | 100% | 204 | 159 | 363 |

| Travel Mode | | AM Peak Hour | | | | PM Peak Hour | | | |
|--------------|----------------|--------------|------------|------------|------------|--------------|------------|------------|------------|
| | | Mode Share | In | Out | Total | Mode Share | In | Out | Total |
| Total | Auto Driver | - | 94 | 219 | 313 | - | 211 | 141 | 352 |
| | Auto Passenger | - | 31 | 74 | 105 | - | 84 | 57 | 141 |
| | Transit | - | 94 | 222 | 316 | - | 165 | 112 | 277 |
| | Cycling | - | 4 | 9 | 13 | - | 7 | 5 | 12 |
| | Walking | - | 25 | 59 | 84 | - | 65 | 45 | 110 |
| | Total | - | 248 | 583 | 831 | - | 532 | 360 | 892 |

As shown above, a total of 313 AM and 352 PM new peak hour two-way vehicle trips are projected as a result of the proposed development.

5.3 Trip Distribution

To understand the travel patterns of the subject development the OD Survey has been reviewed to determine the travel for the residential component patterns were applied based on the build-out of South Nepean. Table 13 below summarizes the distributions.

Table 13: OD Survey Distribution – South Nepean

| To/From | Residential % of Trips |
|--------------|------------------------|
| North | 80% |
| South | 5% |
| East | 10% |
| West | 5% |
| Total | 100% |


5.4 Trip Assignment

Using the distribution outlined above, turning movement splits, and access to major transportation infrastructure, the trips generated by the site have been assigned to the study area road network. Table 14 summarizes the proportional assignment to the study area roadways. Figure 12 illustrates the new site generated volumes.

Table 14: Trip Assignment

| To/From | Via |
|--------------|--|
| North | 27% Strandherd (E), 53% Strandherd (N) |
| South | 5% Borrisokane (S) |
| East | 10% Strandherd (E) |
| West | 5% Strandherd (N) |
| Total | 100% |

Figure 12: New Site Generation Auto Volumes



6 Background Network Travel Demands

6.1 Transportation Network Plans

The study area transportation network plans were discussed in Section 2.3.1.

For the future horizons, the Strandherd Drive widening and Chapman Mills Drive extension have been assumed in all horizons and is assumed within the traffic model and background development volumes/assignment. As Re-Aligned Greenbank Road has an undetermined construction date, it has not been explicitly included in the analysis. Should it be completed, it will have minimal impact on the study area intersections as it occurs south of Chapman Mills Drive.

6.2 Background Growth

A large amount of background traffic has been accounted for through the other developments that have been documented in Section 2.3.2. This is particularly important for volumes along Borriskane Road, where most of the developments being built or planned must travel to access Barrhaven or the Highway 416 interchange. This growth around results in over 11% annual growth along Borriskane Road, or 320% of the existing volumes. Therefore, a nominal amount of additional background growth has been accounted for along Strandherd Drive, Borriskane Road and Cambrian Road. To account for background growth along this corridor a 1.5%/annum

background growth rate has been applied for the primary intersection movements. The 2030 and 2035 background growth are illustrated in Figure 13 and Figure 14, respectively

Figure 13: 2030 Background Growth





Figure 14: 2035 Background Growth



6.3 Other Developments


As detailed in Section 2.3.2, the following developments have been included in the background traffic forecast:

- 3195 Jockvale Road
- Harmony Phase 5 – 3232 Jockvale Road
- 3201 Greenbank Road
- 3288 Greenbank Road
- 3370 Greenbank Road
- Riversbend – 3311 Greenbank Road
- Half Moon Bay South Phase 5
- Half Moon Bay West
- Half Moon Bay North Phase 9
- Quinn’s Pointe 2
- The Meadows Phase 5/6
- The Meadows Phase 7/8
- 3387 Borrisokane Road
- Citi-Gate Development
- 4401 Fallowfield Road Development
- Harmony Development – 4025 Strandherd Drive
- Conservancy Phase 1 – 3285 Borrisokane Road
- The Ridge/Brazeau – 3809 Borrisokane Road
- Drummond Subdivision – 3713 Borrisokane Road
- ABIC Manufacturing – 3713 Borrisokane Road
- Conservancy East – Phases 2-5 (per 2022 update)

A review of the TRANS Trip Generation Manual (2020) has illustrated that the prior methodologies for trip generation over estimated trips within the Ottawa context. Specifically for Barrhaven South and within Barrhaven/Nepean, these trips could be between 49% to 89% of the previously generated auto volumes. As such, an overall reduction in forecasted trips has been applied to the subject developments.

Figure 15 illustrates the total background development volumes for the study area, adjusted for the changes in the transportation network and trip generation adjustment.

Figure 15: Total Background Development Traffic



7 Demand Rationalization

7.1 2030 Future Background Operations

The study area intersections have been modified to include the following improvements previously noted in Section 2.3.1 and the new intersections along Borrisokane Road have been included as proposed in the East Phase of Conservancy. All signalized intersections optimized for new lane arrangements, as approximations of future signal coordination and sequencing.

Figure 16 illustrates the 2030 background volumes and Table 15 summarizes the 2030 background intersection operations. The level of service for signalized intersections is based on v/c calculations for individual lane movements and HCM 2000 v/c calculations for the overall intersection, and average delay for unsignalized intersections. The synchro worksheets for the 2030 future background horizon are provided in Appendix E.

Figure 16: 2030 Future Background Volumes




Table 15: 2030 Future Background Intersection Operations

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|---|-------|--------------|-------------|--------------|-----------------------|--------------|-------------|--------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Strandherd Drive & Dealership Way/Kennevale Drive Signalized | EBL | A | 0.58 | 60.0 | 28.6 | D | 0.90 | 72.9 | #101.1 |
| | EBT | A | 0.08 | 35.6 | 9.1 | A | 0.21 | 34.0 | 29.9 |
| | EBR | A | 0.16 | 37.4 | 17.6 | A | 0.49 | 41.0 | 56.8 |
| | WBL | A | 0.39 | 43.8 | 33.2 | A | 0.43 | 40.3 | 41.3 |
| | WBT/R | C | 0.79 | 64.3 | 70.2 | A | 0.31 | 36.2 | 36.4 |
| | NBL | B | 0.66 | 66.9 | m15.9 | A | 0.43 | 72.2 | m7.4 |
| | NBT/R | F | 1.47 | 230.0 | m#255.5 | F | 1.22 | 120.0 | m#248.8 |
| | SBL | A | 0.50 | 69.4 | #32.4 | C | 0.71 | 87.3 | #55.1 |
| | SBT | C | 0.78 | 28.9 | #174.4 | F | 1.49 | 247.3 | #497.9 |
| SBR | A | 0.42 | 21.5 | 73.9 | A | 0.14 | 16.4 | 23.8 | |
| Overall | | F | 1.28 | 142.0 | - | F | 1.31 | 166.2 | - |

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|--|--|--------------|--------------|-------------|-----------------------|--------------|--------------|-------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Strandherd Drive & Borrisokane Road/Tartan Drive <i>Signalized</i> | EBL | E | 0.95 | 126.1 | m#56.0 | F | 1.58 | 305.9 | m#72.1 |
| | EBT | B | 0.67 | 21.2 | 58.5 | F | 1.11 | 69.4 | m48.3 |
| | EBR | F | 1.05 | 75.6 | #191.6 | F | 1.63 | 306.3 | m#210.7 |
| | WBL | B | 0.69 | 92.5 | #42.7 | F | 1.03 | 148.6 | #67.2 |
| | WBT | F | 1.47 | 247.8 | #310.1 | D | 0.87 | 42.7 | 148.5 |
| | WBR | A | 0.11 | 28.2 | 17.4 | A | 0.12 | 24.5 | 19.1 |
| | NBL | F | 2.06 | 509.9 | #233.1 | F | 1.83 | 415.6 | #161.4 |
| | NBT | A | 0.10 | 31.9 | 17.7 | A | 0.09 | 38.2 | 14.9 |
| | NBR | A | 0.26 | 34.4 | 35.7 | A | 0.35 | 43.4 | 38.1 |
| | SBL | A | 0.54 | 68.3 | 30.3 | B | 0.67 | 94.2 | #31.7 |
| | SBT/R | D | 0.86 | 72.2 | #92.0 | D | 0.85 | 84.5 | #74.4 |
| Overall | F | 1.38 | 222.8 | - | F | 1.59 | 171.9 | - | |
| Borrisokane Road & Conservancy Way <i>Signalized</i> | EBL | A | 0.25 | 34.7 | 13.7 | A | 0.16 | 32.5 | 9.9 |
| | EBT | A | 0.01 | 28.0 | 2.3 | A | 0.01 | 28.0 | 1.8 |
| | WBL | A | 0.06 | 29.6 | 5.3 | A | 0.04 | 29.0 | 4.0 |
| | WBT | A | 0.23 | 33.8 | 14.1 | A | 0.15 | 32.0 | 10.3 |
| | NBL | A | 0.01 | 40.0 | 1.7 | A | 0.03 | 40.7 | 3.2 |
| | NBT/R | A | 0.39 | 11.2 | 102.6 | A | 0.26 | 11.4 | 61.2 |
| | SBL | A | 0.20 | 44.0 | 10.9 | A | 0.37 | 42.4 | 20.4 |
| | SBT | A | 0.16 | 7.5 | 39.1 | A | 0.38 | 10.6 | 79.4 |
| | SBR | A | 0.02 | 8.8 | 5.9 | A | 0.04 | 11.5 | 11.6 |
| | Overall | A | 0.44 | 13.9 | - | A | 0.45 | 14.1 | - |
| | Borrisokane Road & New Collector <i>Signalized</i> | EBL | A | 0.21 | 35.2 | 14.6 | A | 0.14 | 33.0 |
| EBR | | A | 0.01 | 30.0 | 2.0 | A | 0.00 | 29.0 | 1.3 |
| NBL | | A | 0.00 | 6.0 | 0.7 | A | 0.00 | 3.5 | m0.3 |
| NBT | | A | 0.42 | 6.8 | 89.0 | A | 0.26 | 2.9 | 17.6 |
| SBT | | A | 0.18 | 4.9 | 32.1 | A | 0.42 | 5.8 | 81.5 |
| SBR | | A | 0.02 | 5.3 | 4.1 | A | 0.04 | 4.2 | 6.3 |
| Overall | | A | 0.44 | 7.7 | - | A | 0.42 | 5.5 | - |

Notes: Saturation flow rate of 1800 veh/h/lane
Queue is measured in metres
Peak Hour Factor = 1.00

Delay = average vehicle delay in seconds
m = metered queue
= volume for the 95th %ile cycle exceeds capacity

The 2030 future background operations summarized above identify significant capacity constraints along Strandherd Drive. High delays and extended queueing are noted for the entire corridor, both along the mainline of Strandherd Drive and on turning movements from that side streets. The volumes illustrated in Figure 16 outline an unconstrained demand for 2-3 lanes in each direction between Borrisokane Road and Greenbank Road, and 4 lanes from Borrisokane Road to Kennevale Road. As this is not a feasible option for Strandherd Drive and accepted City arterial road policies, alternative solutions for Barrhaven will need to be examined by the City.

A number of solutions have been presented in previous TIA studies and will continue to be reviewed as part of the City’s new Transportation Master Plan. No mitigation will be proposed as part of this TIA as it is beyond the scope of a specific TIA development and requires a regional solution.

7.2 2035 Future Background Operations

Figure 17 illustrates the 2035 background volumes and Table 16 summarizes the 2035 background intersection operations. The level of service for signalized intersections is based on v/c calculations for individual lane movements and HCM 2000 v/c calculations for the overall intersection, and average delay for unsignalized intersections. The synchro worksheets for the 2035 future background horizon are provided in Appendix F.

Figure 17: 2035 Future Background Volumes




Table 16: 2035 Future Background Intersection Operations

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|---|----------|--------------|--------------|----------|-----------------------|--------------|--------------|----------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Strandherd Drive & Dealership Way/Kennevale Drive <i>Signalized</i> | EBL | A | 0.58 | 60.0 | 28.6 | E | 0.93 | 79.9 | #108.3 |
| | EBT | A | 0.08 | 35.6 | 9.1 | A | 0.22 | 35.6 | 31.1 |
| | EBR | A | 0.16 | 37.4 | 17.6 | A | 0.51 | 42.9 | 59.0 |
| | WBL | A | 0.39 | 43.8 | 33.2 | A | 0.45 | 42.3 | 42.9 |
| | WBT/R | C | 0.79 | 64.3 | 70.2 | A | 0.32 | 37.8 | 37.9 |
| | NBL | B | 0.66 | 66.8 | m15.5 | A | 0.46 | 74.3 | m6.9 |
| | NBT/R | F | 1.52 | 255.1 | m#258.6 | F | 1.22 | 117.5 | m#218.2 |
| | SBL | A | 0.50 | 69.4 | #32.4 | D | 0.85 | 113.1 | #55.1 |
| | SBT | D | 0.82 | 30.5 | #196.3 | F | 1.51 | 257.6 | #511.7 |
| | SBR | A | 0.42 | 21.4 | 73.5 | A | 0.14 | 15.1 | 22.4 |
| Overall | F | 1.32 | 156.7 | - | F | 1.35 | 171.8 | - | |
| Strandherd Drive & Borrisokane Road/Tartan Drive <i>Signalized</i> | EBL | E | 0.95 | 124.1 | m#52.9 | F | 1.33 | 200.4 | m#83.8 |
| | EBT | C | 0.71 | 22.3 | 66.6 | F | 1.27 | 147.3 | m94.2 |
| | EBR | F | 1.08 | 83.6 | m#192.1 | F | 1.85 | 404.9 | m#232.0 |
| | WBL | B | 0.69 | 92.5 | #42.7 | B | 0.64 | 70.2 | #73.8 |
| | WBT | F | 1.53 | 273.0 | #326.4 | E | 0.97 | 57.1 | #179.0 |
| | WBR | A | 0.11 | 28.2 | 17.4 | A | 0.12 | 26.3 | 19.9 |
| | NBL | F | 2.12 | 536.9 | #241.1 | F | 2.34 | 635.7 | #175.2 |
| | NBT | A | 0.10 | 31.9 | 17.7 | A | 0.09 | 39.1 | 14.5 |
| | NBR | A | 0.26 | 34.4 | 35.7 | A | 0.39 | 45.8 | 37.0 |
| | SBL | A | 0.54 | 68.3 | 30.3 | A | 0.48 | 67.2 | 24.4 |
| | SBT/R | D | 0.86 | 72.2 | #92.0 | C | 0.72 | 64.5 | 57.2 |
| Overall | F | 1.42 | 238.5 | - | F | 1.66 | 237.2 | - | |
| Borrisokane Road & Conservancy Way <i>Signalized</i> | EBL | A | 0.25 | 34.7 | 13.7 | A | 0.16 | 32.5 | 9.9 |
| | EBT | A | 0.01 | 28.0 | 2.3 | A | 0.01 | 28.0 | 1.8 |
| | WBL | A | 0.06 | 29.6 | 5.3 | A | 0.04 | 29.0 | 4.0 |
| | WBT | A | 0.23 | 33.8 | 14.1 | A | 0.15 | 32.0 | 10.3 |
| | NBL | A | 0.01 | 40.0 | 1.7 | A | 0.03 | 40.3 | 3.2 |
| | NBT/R | A | 0.33 | 10.6 | 83.3 | A | 0.22 | 11.1 | 51.1 |
| | SBL | A | 0.19 | 43.2 | 12.1 | A | 0.37 | 43.4 | 20.6 |
| | SBT | A | 0.14 | 6.4 | 21.0 | A | 0.32 | 9.7 | 61.6 |
| | SBR | A | 0.02 | 8.2 | 4.4 | A | 0.04 | 11.1 | 10.4 |
| Overall | A | 0.38 | 13.9 | - | A | 0.39 | 14.1 | - | |
| Borrisokane Road & New Collector/BRT <i>Signalized</i> | EBL | A | 0.26 | 35.8 | 14.5 | A | 0.17 | 33.7 | 10.7 |
| | EBT | A | 0.02 | 29.2 | 2.9 | A | 0.02 | 29.5 | 2.9 |
| | EBR | A | 0.01 | 29.0 | 1.9 | A | 0.00 | 28.0 | 1.3 |
| | WB | A | 0.02 | 29.5 | 2.9 | A | 0.02 | 29.5 | 2.9 |
| | NBL | A | 0.00 | 5.0 | m0.1 | A | 0.00 | 4.5 | m0.4 |
| | NBT | A | 0.37 | 4.3 | 32.7 | A | 0.23 | 3.9 | 21.0 |
| | SBL/T | A | 0.16 | 4.9 | 27.7 | A | 0.37 | 6.4 | 74.0 |
| | SBR | A | 0.02 | 5.5 | 4.1 | A | 0.04 | 5.2 | 7.1 |
| Overall | A | 0.39 | 6.6 | - | A | 0.38 | 6.6 | - | |

Notes: Saturation flow rate of 1800 veh/h/lane
Queue is measured in metres
Peak Hour Factor = 1.00

Delay = average vehicle delay in seconds
m = metered queue
= volume for the 95th %ile cycle exceeds capacity

The 2035 background operations are expected to be similar to the 2030 background operations at most study area intersections. The Strandherd Drive intersections at Kennevale Drive and at Borrisokane Road will continue

to have significant capacity constraints, delay, and queuing concerns for many of the movements and will see incremental decrease in operations due to the background growth.

7.3 Demand Rationalization Conclusions

Through the TIA process, the City requires transportation demand measures be considered for each development to ease the burden on the road network. These measures will be included in this development, such as transit ridership, active mode connectivity and supporting programs within the community.


To address the systemic issues noted in the existing and background conditions, the deferral of planned infrastructure, such as the Re-Aligned Greenbank Road corridor being shifted to beyond 2031, will need to be reassessed and additional regional TDM programs or infrastructure will be needed from the City of Ottawa. The minimum needs have been highlighted above with the Chapman Mills BRT corridor, new Barnsdale Road Interchange (which the planning appears to be underway) and transit corridor to Barrhaven South.

8 Development Design

8.1 Design for Sustainable Modes

The proposed development is a residential subdivision, and the auto parking and bicycle parking will be located at each of the individual units. Figure 18 illustrates the conceptual pedestrian and cycling network. The plan incorporates the adjacent developments and planned routes on geoOttawa. Street 1 and 2 will include cycle tracks.

Figure 18: Concept Pedestrian and Cycling Network



The active mode network will also connect to Borriskane Road and the future park and ride at the corner of Strandherd Drive and Borriskane Road through the East Phase of Conservancy. The park and ride is approximately a 1.35km walking distance from the western limits of the subdivision, and similarly, the maximum walking distance from the western limits of the subdivision to the Street 1 at Street 2 intersection is approximately 670m if a local route stop is placed at this location. OC Transpo will need to indicate the preferred transit stop locations should local service be extended into the subdivision.

8.2 New Street Networks

The new streets proposed as part of the plan of subdivision include 14.75 window streets, 16.5 and 18.0 metre local roads and 24.0 metre collector roads. Figure 19 illustrates the conceptual traffic calming elements to be incorporated into the future geometric road design with limited applications within the internal local road intersections. Vertical measures will be explored on the future local roadways, although due to site servicing constraints, cost implications for future City maintenance of underground infrastructure and locations of street elements, such as driveways, fire hydrants, etc., the feasibility of implementation may be restricted.

Figure 19: Concept Pedestrian and Cycling Network



Within the subdivision, no turn lanes are proposed for the intersections and will be controlled by minor stop control.

Once the internal road network is finalized, including input from all disciplines involved in plan of subdivision approvals, include urban planning and parks, a geometric road design drawing will be prepared to outline the above traffic calming measures. The City should endeavour to confirm all input from the various departments is discussed holistically to reduce competing design commentary when preparing the geometric road design.

9 Boundary Street Design

No roadways are located at the boundary of the proposed subdivision. All MMLOS analysis is included in Section 15.2.3.

10 Access Intersections Design

10.1 Location and Design of Access

The residential accesses will connect via new collector roads to Borrisokane Road. The intersections along Borrisokane Road have been proposed as signalized during the East Phase TIA and this assumption has been maintained. The signalization of these intersections is based on the BRT corridor requirements at the northern intersection and need for interconnectivity of active modes across Borrisokane Road. Operational sensitivity was conducted in the East Phase TIA, noting high delays with a minor-stop control may lead to unsafe turning movements as residents attempt to exit the community.

10.2 Intersection Control

No changes in the area intersection control. Future control under construction, proposed as City DC upgrades or within adjacent development applications also remain the same.

10.3 Access Intersection Design

The subdivision will use the adjacent development to access Borrisokane Road. Section 15 includes the analysis of the network intersection operations.

Similar to Section 9, the network intersection MMLOS analysis is provided in Section 15.2.3.

11 Transportation Demand Management

11.1 Context for TDM

The mode shares used within the TIA represent this area of the City and typical mode shares for BRT areas. The modal shares are likely to be achieved.

Total bedrooms within the development are subject to the final unit count and product styles selected by purchasers. No age restrictions are noted.

11.2 Need and Opportunity

The subject site has been assumed to rely on a higher transit modal share than typically found within Nepean, requiring increase transit service and rapid adoption of transit ridership. These assumptions have been carried through the analysis. The opportunity for the City to extend transit infrastructure elsewhere within Barrhaven and Barrhaven South exists and will help encourage this modal shift to greater areas of Barrhaven than the localized targets for this development. The development can provide the internal connectivity to transit and adjacent non-auto infrastructure, although this will be underutilized until other City infrastructure is constructed to support the development potential in Barrhaven.

11.3 TDM Program

The “suite of post occupancy TDM measures” has been summarized in the TDM checklists for the residential land uses. The checklist is provided in Appendix G. The key TDM measures recommended include:

- Enhanced connectivity of pedestrians and cyclists to the adjacent network
- Posting of pedestrian and cycling wayfinding signage within the community

- Organize community cycling course for new residents
- Early service agreement with OC Transpo to support higher adoption of transit ridership
- Inclusion of a 6-month Presto card for first time new townhome purchase, with a set time frame for this offer (e.g., 6-months) from the initial offering of the site
- Conduct semi-annual community surveys for 2 years to collect travel pattern and behaviour data (in conjunction with City TDM coordinator)

12 Neighbourhood Traffic Management

The proposed development will connect to the arterial road network at Borrisokane Road through the collector roads proposed as part of the East Phase of Conservancy. The two collector roads were forecasted to convey between 110-120 two-way vehicle trips as part of the East Phase and an additional 300-360 vehicles trips from the West Phase. The total 410-480 vehicle trips are within the capacity range of two minor collector roads. While noted to be low, these volumes meet the threshold of 300 two-way vehicles during a peak hour outlined within the City of Ottawa TIA Guidelines. No change to the adjacent neighbourhood roadways is required to support the West Phase of Conservancy.

13 Transit

13.1 Route Capacity

In Section 5.1 the trip generation by mode was estimated, including an estimate of the number of transit trips that will be generated by the proposed development. Table 17 summarizes the transit trip generation.

Table 17: Trip Generation by Transit Mode

| Travel Mode | Mode Share | AM Peak Hour | | | PM Peak Hour | | |
|-------------|------------|--------------|-----|-------|--------------|-----|-------|
| | | In | Out | Total | In | Out | Total |
| Transit | Varies | 94 | 222 | 316 | 165 | 112 | 277 |

The proposed development is anticipated to generate an additional 316 AM and 277 PM peak hour two-way transit trips. From the trip distribution found in section 5.3, these values can be further broken down. Table 18 summarizes forecasted site-generated transit ridership trips by direction and the equivalent bus loads.

Table 18: Forecasted Site-Generated Transit Ridership

| Direction | AM Peak Hour | | PM Peak Hour | | Service Type | Approximate Equivalent Peak Hour/Direction Bus Loads |
|-----------|--------------|-----|--------------|-----|--------------|--|
| | In | Out | In | Out | | |
| North | 75 | 178 | 132 | 90 | Bus/BRT | Three to Four standard buses |
| South | 5 | 11 | 8 | 5 | Bus/BRT | One-fifth of a standard bus |
| East | 9 | 22 | 17 | 12 | Bus/BRT | One-third of a standard bus |
| West | 5 | 11 | 8 | 5 | Bus/BRT | One-fifth of a standard bus |

13.2 Transit Priority

A transit signal will need to be incorporated into the signalized intersection of the New Collector and BRT once the BRT is extended to Borrisokane Road. The corridor improvements are currently being reviewed as part of the Conservancy East subdivision phases/draft conditions. It is anticipated that the closely spaced intersection at Conservancy Way will require balancing of the design requirements, and tie-ins with the newly upgraded intersection at Strandherd Drive.

14 Network Concept

The existing and background volumes forecasted along Strandherd Drive and accessing Strandherd Drive from the south, are exceeding the existing lane capacities and will continue to do so once the widening is completed. Extensive infrastructure projects have been planned for Barrhaven, and overall, a minimum number of these projects have been implemented and many continue to be pushed farther into the future. As identified previously, the following projects are required to support Barrhaven as a whole, and additional projects that would begin to bring the transportation network to the level of other suburban areas of Ottawa are also listed and support the growth potential of Barrhaven:

- Currently required projects:
 - Barnsdale-Highway 417 interchange (interim)
 - Chapman Mills BRT extension to Borrisokane Road
 - Re-Aligned Greenbank Road BRT Corridor, Towncentre to Kilbirnie Drive
- Barrhaven supportive projects:
 - Re-Aligned Greenbank Road, to Cambrian Road and Barnsdale Road
 - LRT extension to the Towncentre

15 Network Intersection Design

15.1 Network Intersection Control

The study area intersections are all assumed to be signalized, through the Strandherd Drive widening, extension of Chapman Mills Drive and the BRT corridor, and development related improvements along Borrisokane Road. These changes have been noted in Section 7.1.

Updated signal warrants for the Borrisokane Road intersections are provided in Appendix H. Based on the East Phase of Conservancy, signalized intersections of Borrisokane Road at Conservancy Way and Borrisokane Road at New Collector intersections have been proposed. Although both intersections do not meet signal warrant at all study horizons, both intersections are required to be signalized.

15.2 Network Intersection Design

15.2.1 2030 Future Total Network Intersection Operations

Figure 20 illustrates the 2030 future total volumes, and the 2030 future total network intersection operations are summarized below in Table 19. The level of service for signalized intersections is based on v/c calculations for individual lane movements and HCM 2000 v/c calculations for the overall intersection, and average delay for unsignalized intersections. The synchro worksheets have been provided in Appendix I.

Figure 20: 2030 Future Total Volumes




Table 19: 2030 Future Total Network Intersection Operations

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|---|-------|--------------|-------------|--------------|-----------------------|--------------|-------------|--------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Strandherd Drive & Dealership Way/Kennevale Drive Signalized | EBL | A | 0.58 | 60.0 | 28.6 | D | 0.90 | 72.9 | #101.1 |
| | EBT | A | 0.08 | 35.6 | 9.1 | A | 0.21 | 34.0 | 29.9 |
| | EBR | A | 0.16 | 37.4 | 17.6 | A | 0.49 | 41.0 | 56.8 |
| | WBL | A | 0.39 | 43.8 | 33.2 | A | 0.43 | 40.3 | 41.3 |
| | WBT/R | C | 0.79 | 64.3 | 70.2 | A | 0.31 | 36.2 | 36.4 |
| | NBL | B | 0.66 | 66.8 | m15.4 | A | 0.43 | 72.0 | m7.3 |
| | NBT/R | F | 1.54 | 260.2 | m#256.5 | F | 1.28 | 144.4 | m#248.0 |
| | SBL | A | 0.50 | 69.4 | #32.4 | C | 0.71 | 87.3 | #55.1 |
| | SBT | D | 0.81 | 30.4 | #197.1 | F | 1.56 | 277.9 | #528.2 |
| SBR | A | 0.42 | 21.5 | 73.9 | A | 0.14 | 16.4 | 23.8 | |
| Overall | | F | 1.33 | 159.9 | - | F | 1.35 | 190.1 | - |

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|--|----------|--------------|--------------|----------|-----------------------|--------------|--------------|----------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Strandherd Drive & Borrisokane Road/Tartan Drive <i>Signalized</i> | EBL | E | 0.95 | 124.2 | m#52.8 | F | 1.58 | 305.9 | m#67.6 |
| | EBT | B | 0.69 | 22.1 | 58.1 | F | 1.11 | 69.2 | m41.6 |
| | EBR | F | 1.20 | 129.3 | m#217.1 | F | 1.82 | 391.5 | m#237.7 |
| | WBL | E | 0.92 | 125.0 | #64.9 | F | 1.73 | 397.8 | #113.7 |
| | WBT | F | 1.47 | 247.8 | #310.1 | D | 0.87 | 42.7 | 148.5 |
| | WBR | A | 0.11 | 28.2 | 17.4 | A | 0.12 | 24.5 | 19.1 |
| | NBL | F | 2.31 | 620.8 | #265.6 | F | 2.05 | 509.2 | #182.8 |
| | NBT | A | 0.10 | 31.9 | 17.7 | A | 0.09 | 38.2 | 14.9 |
| | NBR | A | 0.44 | 38.3 | 59.3 | A | 0.52 | 48.2 | 55.3 |
| | SBL | A | 0.54 | 68.3 | 30.3 | B | 0.67 | 94.2 | #31.7 |
| | SBT/R | D | 0.86 | 72.2 | #92.0 | D | 0.85 | 84.5 | #74.4 |
| Overall | F | 1.43 | 257.7 | - | F | 1.74 | 216.1 | - | |
| Borrisokane Road & Conservancy Way <i>Signalized</i> | EBL | B | 0.64 | 44.6 | 36.8 | A | 0.47 | 39.7 | 24.7 |
| | EBT | A | 0.04 | 25.8 | 4.8 | A | 0.03 | 27.0 | 3.4 |
| | WBL | A | 0.05 | 26.2 | 5.3 | A | 0.04 | 27.4 | 4.0 |
| | WBT | A | 0.18 | 29.2 | 14.1 | A | 0.13 | 30.2 | 10.3 |
| | NBL | A | 0.04 | 40.8 | 3.9 | A | 0.09 | 41.9 | 6.1 |
| | NBT/R | A | 0.48 | 15.1 | 103.4 | A | 0.29 | 13.0 | 62.0 |
| | SBL | A | 0.20 | 44.0 | 10.9 | A | 0.37 | 40.5 | m17.4 |
| | SBT | A | 0.20 | 9.8 | 39.8 | A | 0.42 | 12.6 | 85.6 |
| | SBR | A | 0.07 | 9.8 | 13.8 | A | 0.14 | 11.6 | 30.3 |
| Overall | A | 0.55 | 19.5 | - | A | 0.52 | 16.9 | - | |
| Borrisokane Road & New Collector <i>Signalized</i> | EBL | A | 0.57 | 42.7 | 38.3 | A | 0.41 | 38.7 | 26.2 |
| | EBR | A | 0.03 | 28.5 | 3.7 | A | 0.02 | 29.0 | 3.0 |
| | NBL | A | 0.00 | 6.7 | 1.3 | A | 0.01 | 5.2 | m1.2 |
| | NBT | A | 0.59 | 11.3 | 115.9 | A | 0.32 | 5.5 | 34.1 |
| | SBT | A | 0.26 | 7.0 | 37.9 | A | 0.53 | 7.9 | 104.9 |
| | SBR | A | 0.07 | 6.2 | 9.6 | A | 0.13 | 4.6 | 16.9 |
| Overall | A | 0.59 | 14.0 | - | A | 0.54 | 9.1 | - | |

Notes: Saturation flow rate of 1800 veh/h/lane
 Queue is measured in metres
 Peak Hour Factor = 1.00

Delay = average vehicle delay in seconds
 m = metered queue
 # = volume for the 95th %ile cycle exceeds capacity

The study area network intersections operate with similar capacity constraints, delays, and queuing as the 2030 future background conditions.

As noted in the background conditions, a commitment from the City is required to advance new infrastructure within Barrhaven and continue to look for continual mode shifting to further reduce the auto dependency currently observed.

15.2.2 2035 Future Total Network Intersection Operations

Figure 21 illustrates the 2035 future total volumes, and the 2035 future total network intersection operations are summarized below in Table 20. The level of service for signalized intersections is based on v/c calculations for individual lane movements and HCM 2000 v/c calculations for the overall intersection, and average delay for unsignalized intersections. The synchro worksheets have been provided in Appendix J.

Figure 21: 2035 Future Total Volumes




Table 20: 2035 Future Total Network Intersection Operations

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|---|-------|--------------|-------------|--------------|-----------------------|--------------|-------------|--------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Strandherd Drive & Dealership Way/Kennevale Drive Signalized | EBL | A | 0.58 | 60.0 | 28.6 | E | 0.93 | 79.9 | #108.3 |
| | EBT | A | 0.08 | 35.6 | 9.1 | A | 0.22 | 35.6 | 31.1 |
| | EBR | A | 0.16 | 37.4 | 17.6 | A | 0.51 | 42.9 | 59.0 |
| | WBL | A | 0.39 | 43.8 | 33.2 | A | 0.45 | 42.3 | 42.9 |
| | WBT/R | C | 0.79 | 64.3 | 70.2 | A | 0.32 | 37.8 | 37.9 |
| | NBL | B | 0.66 | 66.7 | m15.0 | A | 0.46 | 73.8 | m6.7 |
| | NBT/R | F | 1.59 | 284.8 | m#259.8 | F | 1.27 | 140.0 | m#218.6 |
| | SBL | A | 0.50 | 69.4 | #32.4 | D | 0.85 | 113.1 | #55.1 |
| | SBT | D | 0.85 | 32.4 | #210.5 | F | 1.58 | 287.6 | #542.2 |
| SBR | A | 0.42 | 21.4 | 73.5 | A | 0.14 | 15.1 | 22.4 | |
| Overall | | F | 1.37 | 174.5 | - | F | 1.39 | 194.9 | - |

| Intersection | Lane | AM Peak Hour | | | | PM Peak Hour | | | |
|--|----------------|--------------|--------------|-------------|-----------------------|--------------|--------------|-------------|-----------------------|
| | | LOS | V/C | Delay | Q (95 th) | LOS | V/C | Delay | Q (95 th) |
| Strandherd Drive & Borrisokane Road/Tartan Drive <i>Signalized</i> | EBL | E | 0.95 | 122.1 | m#50.2 | F | 1.33 | 200.5 | m#78.7 |
| | EBT | C | 0.73 | 22.9 | m64.6 | F | 1.27 | 147.2 | m84.5 |
| | EBR | F | 1.23 | 139.8 | m#211.8 | F | 2.06 | 497.9 | m#257.7 |
| | WBL | E | 0.92 | 125.0 | #64.9 | F | 1.08 | 142.3 | #120.2 |
| | WBT | F | 1.53 | 273.0 | #326.4 | E | 0.97 | 57.1 | #179.0 |
| | WBR | A | 0.11 | 28.2 | 17.4 | A | 0.12 | 26.3 | 19.9 |
| | NBL | F | 2.37 | 648.0 | #273.3 | F | 2.61 | 754.0 | #196.5 |
| | NBT | A | 0.10 | 31.9 | 17.7 | A | 0.09 | 39.1 | 14.5 |
| | NBR | A | 0.44 | 38.3 | 59.3 | A | 0.58 | 52.3 | 53.8 |
| | SBL | A | 0.54 | 68.3 | 30.3 | A | 0.48 | 67.2 | 24.4 |
| | SBT/R | D | 0.86 | 72.2 | #92.0 | C | 0.72 | 64.5 | 57.2 |
| Overall | F | 1.47 | 273.4 | - | F | 1.81 | 280.4 | - | |
| Borrisokane Road & Conservancy Way <i>Signalized</i> | EBL | B | 0.64 | 44.6 | 36.8 | A | 0.47 | 39.7 | 24.7 |
| | EBT | A | 0.04 | 25.8 | 4.8 | A | 0.03 | 27.0 | 3.4 |
| | WBL | A | 0.05 | 26.2 | 5.3 | A | 0.04 | 27.4 | 4.0 |
| | WBT | A | 0.18 | 29.2 | 14.1 | A | 0.13 | 30.2 | 10.3 |
| | NBL | A | 0.04 | 40.8 | 3.8 | A | 0.09 | 41.7 | 6.0 |
| | NBT/R | A | 0.41 | 14.1 | 83.8 | A | 0.25 | 12.6 | 52.0 |
| | SBL | A | 0.19 | 43.2 | 11.8 | A | 0.37 | 41.0 | m19.2 |
| | SBT | A | 0.17 | 8.4 | 21.8 | A | 0.35 | 11.8 | 68.7 |
| | SBR | A | 0.07 | 8.8 | 9.7 | A | 0.14 | 11.5 | 28.3 |
| | Overall | A | 0.49 | 19.5 | - | A | 0.46 | 17.0 | - |
| Borrisokane Road & New Collector/BRT <i>Signalized</i> | EBL | B | 0.65 | 46.4 | 39.2 | A | 0.49 | 41.5 | 26.7 |
| | EBT | A | 0.01 | 26.5 | 2.9 | A | 0.01 | 28.0 | 2.9 |
| | EBR | A | 0.02 | 26.8 | 3.6 | A | 0.02 | 28.0 | 2.9 |
| | WB | A | 0.01 | 26.5 | 2.9 | A | 0.02 | 28.0 | 2.9 |
| | NBL | A | 0.00 | 7.0 | m0.6 | A | 0.01 | 6.8 | m1.6 |
| | NBT | A | 0.54 | 9.7 | 56.6 | A | 0.30 | 6.9 | 37.5 |
| | SBL/T | A | 0.23 | 7.5 | 33.4 | A | 0.48 | 8.9 | 96.0 |
| | SBR | A | 0.07 | 6.8 | 9.7 | A | 0.13 | 6.0 | 19.1 |
| Overall | A | 0.56 | 14.2 | - | A | 0.52 | 10.7 | - | |

Notes: Saturation flow rate of 1800 veh/h/lane
Queue is measured in metres
Peak Hour Factor = 1.00

Delay = average vehicle delay in seconds
m = metered queue
= volume for the 95th %ile cycle exceeds capacity

The operations noted are similar to the 2030 future total conditions with a slight decrease in network operations due to background growth. The need for the City to provide wider Barrhaven improvements continues to be the major constraint to decrease the impact on Strandherd Drive.

15.2.3 Network Intersection MMLOS

Table 21 summarizes the MMLOS analysis for the network intersections. The existing and future conditions for both intersections will be the same and are considered in one row. The intersection analysis is based on the policy area of employment area (Kennevale), developing community (existing Borrisokane) and within 600m of a rapid transit station. The MMLOS worksheets has been provided in Appendix K.

Table 21: Study Area Intersection MMLOS Analysis

| Intersection | Pedestrian LOS | | Bicycle LOS | | Transit LOS | | Truck LOS | | Auto LOS | |
|--|----------------|--------|-------------|--------|-------------|--------|-----------|--------|----------|--------|
| | PLOS | Target | BLOS | Target | TLOS | Target | TrLOS | Target | ALOS | Target |
| Strandherd Drive & Kennevale Drive/Dealership Way (existing) | F | C | E | C | F | D | E | B | E | D |
| Strandherd Drive & Kennevale Drive/Dealership Way (future) | F | C | E | C | F | D | E | B | F | D |
| Strandherd Drive & Borrisokane Road/Tartan Drive (existing) | F | C | F | C | E | D | E | D | E | D |
| Strandherd Drive & Borrisokane Road/Tartan Drive (future) | F | A | A | C | F | A | E | D | F | E |
| Borrisokane Road & Conservancy Way | E | A | A | B | E | A | - | N/A | A | E |
| Borrisokane Road & New Collector/BRT | D | A | A | B | D | A | - | N/A | A | E |

The MMLOS targets for the pedestrian and transit LOS are currently not met and will continue to not meet the targets at the network intersections. The pedestrian level of service would require a maximum of four lanes at a crossing to meet a LOS C or two lanes to achieve a level of service A. This is a limitation of the MMLOS framework. For example, the protected intersections proposed for the Strandherd Drive widening will be comfortable for pedestrians but still result in a level of service F. Due to the traffic congestion in Barrhaven, the intersection delays cannot be reduced to increase the transit level of service. It is assumed that the BRT will pre-empt the signal timing to allow transit to proceed and would operate closer to the targets. It is noted that transit LOS A requires zero seconds average delay for the approach, which is not achievable. A LOS B with less than 10 seconds delay may be a more realistic target for the Chapman Mills Drive corridor.

The bicycle LOS will not meet targets along Strandherd Drive due to the side street geometry having mixed use operations and lacking separated crossings for left turns. The incorporation of bike boxes or protected crossings at the intersections would improve the operations and meet the targets. It is assumed that the City conducted a MMLOS assessment of the Strandherd Drive widening and is providing a balanced solution weighing the trade-offs on all the intersections.

The truck LOS will not be met on Borrisokane Road from Strandherd Drive due to a single receiving lane, as typical of the MMLOS framework but is not considered a cause for mitigation.

The auto level of service will not be met along Strandherd Drive as the area congestion will have high-capacity constraints. The signal timing will require a corridor study along the widened Strandherd Drive to balance the demands of the mainline, turning movements at Borrisokane Road, and side street operations.

Overall, the study area network intersections highlight limitations in the MMLOS framework that require no mitigation as part of this plan of subdivision, illustrate that transit services along Strandherd Drive will result in poor service times, and high congestion is anticipated and reflected in the capacity constraints. The auto level of service will require investment in Barrhaven, beyond the transit and interchange options already assumed to be

in place, to mitigate the demands on the network, and BRT corridors and park and rides will be required to remove the need for transit to operate on Strandherd Drive.

15.2.4 Recommended Design Elements

No study area intersection design elements are proposed as part of this study.

16 Summary of Improvements Indicated and Modifications Options

The following summarizes the analysis and results presented in this TIA report:

Proposed Site and Screening

- The proposed development consists of a mix of residential product types, totalling approximately 499 townhomes and 462 single detached homes
- The anticipated full build-out and occupancy horizon is 2030 with construction occurring in a single phase
- The trip generation trigger was met for the TIA Screening

Existing Conditions

- Borrisokane Road and Strandherd Drive are arterial roads, and Kennevale Road and Dealership Way are collector roads within the study area
- None of the driveways within the area of consideration are significant traffic generators
- Sidewalks and cycling tracks will be along Strandherd Drive, and future pathways are planned along the Jock River and Chapman Mills BRT corridor
- Strandherd Drive is spine route, and Borrisokane Road and McKenna Casey Drive are local routes. Major pathways are provided along rail, Strandherd Drive, Jock River and Highway 416
- At the intersection of Strandherd Drive & Dealership Way/Kennevale Drive, the northbound through movement during AM peak hour is over theoretical capacity and may subject to high delays and extended queues
- The study area intersections are subject to queuing issues generally on various movements
- The high volumes roadways have produced a high number of collisions at the study area intersections, primarily at Strandherd Drive and Borrisokane Road intersection, which has 64% of the collisions (47 of 74) within the study area
- The collisions are predominantly rear end collisions due to the congestion along Strandherd Drive, and no further collision review is required as part of this study

Development Generated Travel Demand

- The proposed development is forecasted produce 831 two-way people trips during the AM peak hour and 892 two-way people trips during the PM peak hour
- Of the forecasted people trips, 313 two-way trips will be vehicle trips during the AM peak hour and 352 two-way trips will be vehicle trips during the PM peak hour
- Of the forecasted trips, 80% are anticipated to travel north, 5% to the south, 10 % to the east, and 5 % to the west

Background and Total Conditions

- A 1.5%/annum background growth rate has been applied for the primary intersection movements
- Significant capacity constraints are noted along Strandherd Drive, and high delays and extended queueing are noted for the entire corridor, both along the mainline of Strandherd Drive and on turning movements from that side streets

- Alternative solutions for Barrhaven will need to be examined by the City
- No mitigation will be proposed as part of this TIA as it is beyond the scope of a specific TIA development and requires a regional solution

Development Design

- The plan of subdivision includes Street 1 and Street 2 as 24.0 metre collector roads, with the remaining roadways set at 16.5 or 18.0 metres for the local roads and 14.75 metres for window streets
- Sidewalks will be provided in primary corridors to bisect the community and connect to adjacent open space, and cycletracks will be provided along Street 1 and Street 2
- Traffic calming elements are conceptually identified throughout the community with intersection narrowings at intersections and speed humps on longer uninterrupted stretches of the road network
- It is noted that this traffic calming measure are conceptual and will need to be implemented in conjunction with other subdivision elements, such as lotting, driveway locations, utilities, etc.

Boundary Street Design

- No roadways are located at the boundary of the proposed subdivision

Access Intersections Design

- The residential accesses will connect via new collector roads to Borrisokane Road
- The intersections along Borrisokane Road have been proposed as signalized during the East Phase TIA and this assumption has been maintained
- Operational sensitivity was conducted in the East Phase TIA, noting high delays with a minor-stop control may lead to unsafe turning movements as residents attempt to exit the community

TDM

- Supportive TDM measures to be included within the proposed development should include:
 - Enhanced connectivity of pedestrians and cyclists to the adjacent network
 - Posting of pedestrian and cycling wayfinding signage within the community
 - Organize community cycling course for new residents
 - Early service agreement with OC Transpo to support higher adoption of transit ridership
 - Inclusion of a 6-month Presto card for first time new townhome purchase, with a set time frame for this offer (e.g., 6-months) from the initial offering of the site
 - Conduct semi-annual community surveys for 2 years to collect travel pattern and behaviour data (in conjunction with City TDM coordinator)

NTM

- The proposed development will connect to the arterial road network at Borrisokane Road through the collector roads proposed as part of the East Phase of Conservancy
- No change to the adjacent neighbourhood roadways is required to support the West Phase of Conservancy

Transit

- The forecasted transit trips will include 316 two-way trips during the AM peak and 277 two-way trips during the PM peak

- Peak hour increases in transit ridership resulting from the site equate to three to four double standard buses load northerly of the site, One-fifth of a standard bus load southerly and westerly of the site, and One-third of a standard bus load easterly of the site
- A transit signal will need to be incorporated into the signalized intersection of the New Collector and BRT once the BRT is extended to Borrisokane Road

Network Concept

- The existing and background volumes forecasted along Strandherd Drive and accessing Strandherd Drive from the south, are exceeding the existing lane capacities and will continue to do so once the widening is completed
- A minimum number of these projects have been implemented and many continue to be pushed farther into the future

Network Intersection Design

- The study area network intersections operate with similar capacity constraints, delays, and queuing as the future background conditions
- As noted in the background conditions, the need for the City to provide wider Barrhaven improvements continues to be the major constraint to decrease the impact on Strandherd Drive
- The MMLOS targets for the pedestrian and transit LOS are currently not met and will continue to not meet the targets at the network intersections
- The pedestrian level of service would require a maximum of four lanes at a crossing to meet a LOS C or two lanes to achieve a level of service A, and this is a limitation of the MMLOS framework
- BRT is assumed to pre-empt the signal timing to allow transit to proceed and would operate closer to the transit targets
- It is assumed that the City conducted a MMLOS assessment of the Strandherd Drive widening and is providing a balanced solution weighing the trade-offs on all the intersections
- Overall, the study area network intersections highlight limitations in the MMLOS framework that require no mitigation as part of this plan of subdivision

17 Conclusion

It is recommended that, from a transportation perspective, the proposed development applications proceed.

Prepared By:

Reviewed By:



Andrew Harte, P.Eng.
Senior Transportation Engineer

A handwritten signature in blue ink, appearing to read "Chris Gordon".

Christopher Gordon, P.Eng.
Senior Transportation Engineer

Appendix A

TIA Screening Form and PM Certification Form

City of Ottawa 2017 TIA Guidelines
Step 1 - Screening Form

Date: 30-Sep-21
Project Number: 2021-115
Project Reference: Caivan Conservancy West

| 1.1 Description of Proposed Development | |
|---|---|
| Municipal Address | 3288 & 3300 Borrisokane, 4205, 4345 & 4375 McKenna Casey. |
| Description of Location | Vacant farm fields |
| Land Use Classification | Development Reserve (DR) |
| Development Size | 1036 residential units total; 702 townhomes and 334 single detached homes |
| Accesses | Two new intersections with Borrisokane, part of previous East Phase |
| Phase of Development | TBD - Zoning and Draft Plan only |
| Buildout Year | TBD |
| TIA Requirement | Full TIA Required |

| 1.2 Trip Generation Trigger | |
|-----------------------------|-------------------------|
| Land Use Type | Townhomes or apartments |
| Development Size | 1036 Units |
| Trip Generation Trigger | Yes |

| 1.3 Location Triggers | |
|--|-------------------------------------|
| Does the development propose a new driveway to a boundary street that is designated as part of the City's Transit Priority, Rapid Transit or Spine Bicycle Networks? | No Access through previous phase |
| Is the development in a Design Priority Area (DPA) or Transit-oriented Development (TOD) zone? | No Located within 800 metres of BRT |
| Location Trigger | No |

| 1.4. Safety Triggers | |
|---|----|
| Are posted speed limits on a boundary street 80 km/hr or greater? | No |
| Are there any horizontal/vertical curvatures on a boundary street limits sight lines at a proposed driveway? | No |
| Is the proposed driveway within the area of influence of an adjacent traffic signal or roundabout (i.e. within 300 m of intersection in rural conditions, or within 150 m of intersection in urban/ suburban conditions)? | No |
| Is the proposed driveway within auxiliary lanes of an intersection? | No |
| Does the proposed driveway make use of an existing median break that serves an existing site? | No |
| Is there is a documented history of traffic operations or safety concerns on the boundary streets within 500 m of the development? | No |
| Does the development include a drive-thru facility? | No |
| Safety Trigger | No |



TIA Plan Reports

On 14 June 2017, the Council of the City of Ottawa adopted new Transportation Impact Assessment (TIA) Guidelines. In adopting the guidelines, Council established a requirement for those preparing and delivering transportation impact assessments and reports to sign a letter of certification.

Individuals submitting TIA reports will be responsible for all aspects of development-related transportation assessment and reporting, and undertaking such work, in accordance and compliance with the City of Ottawa's Official Plan, the Transportation Master Plan and the Transportation Impact Assessment (2017) Guidelines.

By submitting the attached TIA report (and any associated documents) and signing this document, the individual acknowledges that s/he meets the four criteria listed below.

CERTIFICATION

1. I have reviewed and have a sound understanding of the objectives, needs and requirements of the City of Ottawa's Official Plan, Transportation Master Plan and the Transportation Impact Assessment (2017) Guidelines;
2. I have a sound knowledge of industry standard practice with respect to the preparation of transportation impact assessment reports, including multi modal level of service review;
3. I have substantial experience (more than 5 years) in undertaking and delivering transportation impact studies (analysis, reporting and geometric design) with strong background knowledge in transportation planning, engineering or traffic operations; and
4. I am either a licensed¹ or registered² professional in good standing, whose field of expertise [check appropriate field(s)] is either transportation engineering or transportation planning .

1,2 License of registration body that oversees the profession is required to have a code of conduct and ethics guidelines that will ensure appropriate conduct and representation for transportation planning and/or transportation engineering works.


City Of Ottawa
Infrastructure Services and Community
Sustainability
Planning and Growth Management
110 Laurier Avenue West, 4th fl.
Ottawa, ON K1P 1J1
Tel. : 613-580-2424
Fax: 613-560-6006

Ville d'Ottawa
Services d'infrastructure et Viabilité des
collectivités
Urbanisme et Gestion de la croissance
110, avenue Laurier Ouest
Ottawa (Ontario) K1P 1J1
Tél. : 613-580-2424
Télécopieur: 613-560-6006

Dated at Ottawa this 20 day of September, 2018.
(City)

Name: Andrew Harte
(Please Print)

Professional Title: Professional Engineer



Signature of Individual certifier that s/he meets the above four criteria

| |
|--|
| Office Contact Information (Please Print) |
| Address: 6 Plaza Court |
| City / Postal Code: Ottawa / K2H 7W1 |
| Telephone / Extension: (613) 697-3797 |
| E-Mail Address: Andrew.Harte@CGHTransportation.com |



Appendix B

Turning Movement Counts



Transportation Services - Traffic Services

Turning Movement Count - Study Results

KENNEVALE DR @ STRANDHERD DR


Survey Date: Thursday, January 18, 2018

WO No: 37427

Start Time: 07:00

Device: Miovision

Full Study Diagram



Transportation Services - Traffic Services

Turning Movement Count - Study Results

KENNEVALE DR @ STRANDHERD DR


Survey Date: Thursday, January 18, 2018

WO No: 37427

Start Time: 07:00

Device: Miovision

Full Study Peak Hour Diagram






Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram

KENNEVALE DR @ STRANDHERD DR

Survey Date: Thursday, January 18, 2018
Start Time: 07:00

WO No: 37427
Device: Miovision



Comments




Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram

KENNEVALE DR @ STRANDHERD DR

Survey Date: Thursday, January 18, 2018
Start Time: 07:00

WO No: 37427
Device: Miovision



Comments




Transportation Services - Traffic Services

Turning Movement Count - Peak Hour Diagram

KENNEVALE DR @ STRANDHERD DR

Survey Date: Thursday, January 18, 2018
Start Time: 07:00

WO No: 37427
Device: Miovision



Comments



Transportation Services - Traffic Services

Turning Movement Count - Study Results

KENNEVALE DR @ STRANDHERD DR

Survey Date: Thursday, January 18, 2018
Start Time: 07:00

WO No: 37427
Device: Miovision

Full Study Summary (8 HR Standard)

Survey Date: Thursday, January 18, 2018

Total Observed U-Turns

| | | | |
|-------------|----|-------------|---|
| Northbound: | 10 | Southbound: | 4 |
| Eastbound: | 0 | Westbound: | 0 |

AADT Factor
1.39

| Period | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Grand Total | | |
|---|------------|-------|------|--------|------------|-------|-----|--------|-----------|-----|----|--------|-----------|------|----|--------|-------------|---------|-------|
| | LT | ST | RT | NB TOT | LT | ST | RT | SB TOT | LT | ST | RT | EB TOT | LT | ST | RT | WB TOT | | STR TOT | |
| 07:00-08:00 | 14 | 945 | 57 | 1016 | 35 | 466 | 19 | 520 | 1536 | 4 | 1 | 6 | 11 | 80 | 3 | 100 | 183 | 194 | 1730 |
| 08:00-09:00 | 23 | 1039 | 93 | 1155 | 53 | 477 | 23 | 553 | 1708 | 8 | 2 | 8 | 18 | 96 | 2 | 105 | 203 | 221 | 1929 |
| 09:00-10:00 | 28 | 696 | 65 | 789 | 47 | 448 | 14 | 509 | 1298 | 17 | 4 | 10 | 31 | 52 | 1 | 56 | 109 | 140 | 1438 |
| 11:30-12:30 | 14 | 603 | 57 | 674 | 69 | 589 | 21 | 679 | 1353 | 22 | 5 | 15 | 42 | 61 | 5 | 60 | 126 | 168 | 1521 |
| 12:30-13:30 | 16 | 567 | 60 | 643 | 60 | 683 | 18 | 761 | 1404 | 23 | 0 | 6 | 29 | 60 | 1 | 63 | 124 | 153 | 1557 |
| 15:00-16:00 | 20 | 670 | 100 | 790 | 83 | 866 | 23 | 972 | 1762 | 25 | 7 | 20 | 52 | 111 | 5 | 74 | 190 | 242 | 2004 |
| 16:00-17:00 | 11 | 749 | 132 | 892 | 72 | 983 | 13 | 1068 | 1960 | 29 | 8 | 20 | 57 | 128 | 5 | 80 | 213 | 270 | 2230 |
| 17:00-18:00 | 12 | 718 | 98 | 828 | 70 | 989 | 11 | 1070 | 1898 | 17 | 3 | 17 | 37 | 106 | 5 | 71 | 182 | 219 | 2117 |
| Sub Total | 138 | 5987 | 662 | 6787 | 489 | 5501 | 142 | 6132 | 12919 | 145 | 30 | 102 | 277 | 694 | 27 | 609 | 1330 | 1607 | 14526 |
| U Turns | | | | 10 | | | | 4 | 14 | | | | 0 | | | | 0 | 0 | 14 |
| Total | 138 | 5987 | 662 | 6797 | 489 | 5501 | 142 | 6136 | 12933 | 145 | 30 | 102 | 277 | 694 | 27 | 609 | 1330 | 1607 | 14540 |
| EQ 12Hr | 192 | 8322 | 920 | 9448 | 680 | 7646 | 197 | 8529 | 17977 | 202 | 42 | 142 | 385 | 965 | 38 | 847 | 1849 | 2234 | 20211 |
| Note: These values are calculated by multiplying the totals by the appropriate expansion factor. | | | | | | | | | | | | | | | | | | | |
| 1.39 | | | | | | | | | | | | | | | | | | | |
| AVG 12Hr | 192 | 8322 | 920 | 9448 | 680 | 7646 | 197 | 8529 | 17977 | 202 | 42 | 142 | 385 | 965 | 38 | 847 | 1849 | 2234 | 20211 |
| Note: These volumes are calculated by multiplying the Equivalent 12 hr. totals by the AADT factor. | | | | | | | | | | | | | | | | | | | |
| 1 | | | | | | | | | | | | | | | | | | | |
| AVG 24Hr | 251 | 10902 | 1205 | 12377 | 890 | 10017 | 259 | 11173 | 23550 | 264 | 55 | 186 | 504 | 1264 | 49 | 1109 | 2422 | 2926 | 26476 |
| Note: These volumes are calculated by multiplying the Average Daily 12 hr. totals by 12 to 24 expansion factor. | | | | | | | | | | | | | | | | | | | |
| 1.31 | | | | | | | | | | | | | | | | | | | |
| Note: U-Turns provided for approach totals. Refer to 'U-Turn' Report for specific breakdown. | | | | | | | | | | | | | | | | | | | |



Transportation Services - Traffic Services

Turning Movement Count - Study Results

KENNEVALE DR @ STRANDHERD DR

Survey Date: Thursday, January 18, 2018

WO No: 37427

Start Time: 07:00

Device: Miovision

Full Study 15 Minute Increments

Table with columns: Time Period, Northbound (LT, ST, RT, N TOT, STR TOT), Southbound (LT, ST, RT, S TOT, STR TOT), Eastbound (LT, ST, RT, E TOT), Westbound (LT, ST, RT, W TOT, STR TOT), Grand Total. Rows show 15-minute intervals from 07:00 to 18:00.

Note: U-Turns are included in Totals.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

KENNEVALE DR @ STRANDHERD DR

Survey Date: Thursday, January 18, 2018

WO No: 37427

Start Time: 07:00

Device: Miovision

Full Study Cyclist Volume

Table with columns: Time Period, Northbound, Southbound, Street Total, Eastbound, Westbound, Street Total, Grand Total. Rows show 15-minute intervals from 07:00 to 18:00.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

KENNEVALE DR @ STRANDHERD DR

Survey Date: Thursday, January 18, 2018

WO No: 37427

Start Time: 07:00

Device: Miovision

Full Study Pedestrian Volume

Table with columns: Time Period, NB Approach, SB Approach, Total, EB Approach, WB Approach, Grand Total. Rows show pedestrian volume for various time intervals from 07:00 to 17:45.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

KENNEVALE DR @ STRANDHERD DR

Survey Date: Thursday, January 18, 2018

WO No: 37427

Start Time: 07:00

Device: Miovision

Full Study Heavy Vehicles

Table with columns: Time Period, Northbound (LT, ST, RT, N TOT), Southbound (LT, ST, RT, S TOT, STR TOT), Eastbound (LT, ST, RT, E TOT), Westbound (LT, ST, RT, W TOT, STR TOT), Grand Total. Rows show heavy vehicle volume for various time intervals from 07:00 to 17:45.



Transportation Services - Traffic Services

Turning Movement Count - Study Results

KENNEVALE DR @ STRANDHERD DR

Survey Date: Thursday, January 18, 2018

WO No: 37427

Start Time: 07:00

Device: Miovision

Full Study 15 Minute U-Turn Total

| Time Period | Northbound U-Turn Total | Southbound U-Turn Total | Eastbound U-Turn Total | Westbound U-Turn Total | Total |
|-------------|-------------------------|-------------------------|------------------------|------------------------|-------|
| 07:00 07:15 | 0 | 0 | 0 | 0 | 0 |
| 07:15 07:30 | 0 | 0 | 0 | 0 | 0 |
| 07:30 07:45 | 1 | 0 | 0 | 0 | 1 |
| 07:45 08:00 | 0 | 0 | 0 | 0 | 0 |
| 08:00 08:15 | 0 | 0 | 0 | 0 | 0 |
| 08:15 08:30 | 0 | 0 | 0 | 0 | 0 |
| 08:30 08:45 | 0 | 0 | 0 | 0 | 0 |
| 08:45 09:00 | 0 | 0 | 0 | 0 | 0 |
| 09:00 09:15 | 1 | 0 | 0 | 0 | 1 |
| 09:15 09:30 | 2 | 0 | 0 | 0 | 2 |
| 09:30 09:45 | 1 | 0 | 0 | 0 | 1 |
| 09:45 10:00 | 0 | 0 | 0 | 0 | 0 |
| 11:30 11:45 | 1 | 0 | 0 | 0 | 1 |
| 11:45 12:00 | 0 | 0 | 0 | 0 | 0 |
| 12:00 12:15 | 0 | 0 | 0 | 0 | 0 |
| 12:15 12:30 | 1 | 0 | 0 | 0 | 1 |
| 12:30 12:45 | 0 | 0 | 0 | 0 | 0 |
| 12:45 13:00 | 0 | 1 | 0 | 0 | 1 |
| 13:00 13:15 | 0 | 0 | 0 | 0 | 0 |
| 13:15 13:30 | 0 | 0 | 0 | 0 | 0 |
| 15:00 15:15 | 1 | 1 | 0 | 0 | 2 |
| 15:15 15:30 | 2 | 0 | 0 | 0 | 2 |
| 15:30 15:45 | 0 | 0 | 0 | 0 | 0 |
| 15:45 16:00 | 0 | 0 | 0 | 0 | 0 |
| 16:00 16:15 | 0 | 0 | 0 | 0 | 0 |
| 16:15 16:30 | 0 | 0 | 0 | 0 | 0 |
| 16:30 16:45 | 0 | 0 | 0 | 0 | 0 |
| 16:45 17:00 | 0 | 0 | 0 | 0 | 0 |
| 17:00 17:15 | 0 | 0 | 0 | 0 | 0 |
| 17:15 17:30 | 0 | 2 | 0 | 0 | 2 |
| 17:30 17:45 | 0 | 0 | 0 | 0 | 0 |
| 17:45 18:00 | 0 | 0 | 0 | 0 | 0 |
| Total | 10 | 4 | 0 | 0 | 14 |



Transportation Services - Traffic Services W.O. 37540

Turning Movement Count - 15 Minute Summary Report

STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Survey Date: Thursday, January 18, 2018

Total Observed U-Turns

Northbound: 0 Southbound: 0
Eastbound: 2 Westbound: 0

| Time Period | CEDARVIEW RD/TARTAN DR | | | | STRANDHERD DR | | | | W | STR | Grand Total | | | | | | | | |
|-------------|------------------------|-----|------------|-------|---------------|-----|-----------|-------|---------|-----|-------------|------|-------|----|------|-----|------|-------|-------|
| | Northbound | | Southbound | | Eastbound | | Westbound | | | | | | | | | | | | |
| | LT | ST | RT | N TOT | LT | ST | RT | S TOT | STR TOT | LT | ST | RT | E TOT | LT | ST | RT | TOT | TOT | |
| 07:00 07:15 | 89 | 1 | 3 | 93 | 9 | 2 | 22 | 33 | 126 | 5 | 78 | 23 | 106 | 1 | 124 | 3 | 128 | 234 | 360 |
| 07:15 07:30 | 81 | 6 | 6 | 93 | 1 | 1 | 15 | 17 | 110 | 14 | 133 | 24 | 171 | 3 | 146 | 4 | 153 | 324 | 434 |
| 07:30 07:45 | 80 | 3 | 5 | 88 | 11 | 6 | 27 | 44 | 132 | 18 | 108 | 22 | 148 | 1 | 203 | 7 | 211 | 359 | 491 |
| 07:45 08:00 | 104 | 12 | 7 | 123 | 9 | 4 | 26 | 39 | 162 | 15 | 139 | 25 | 179 | 2 | 148 | 10 | 160 | 339 | 501 |
| 08:00 08:15 | 85 | 9 | 3 | 97 | 12 | 3 | 26 | 41 | 138 | 22 | 125 | 34 | 181 | 0 | 187 | 16 | 203 | 384 | 522 |
| 08:15 08:30 | 100 | 27 | 3 | 130 | 37 | 10 | 41 | 88 | 218 | 26 | 111 | 33 | 170 | 1 | 192 | 19 | 212 | 382 | 600 |
| 08:30 08:45 | 98 | 13 | 4 | 115 | 10 | 3 | 25 | 38 | 153 | 12 | 96 | 28 | 136 | 0 | 184 | 12 | 196 | 332 | 485 |
| 08:45 09:00 | 82 | 8 | 4 | 94 | 15 | 8 | 21 | 44 | 138 | 19 | 100 | 20 | 139 | 2 | 182 | 12 | 196 | 335 | 473 |
| 09:00 09:15 | 71 | 10 | 5 | 86 | 6 | 4 | 15 | 25 | 111 | 9 | 93 | 25 | 127 | 2 | 155 | 15 | 172 | 299 | 410 |
| 09:15 09:30 | 69 | 6 | 1 | 76 | 6 | 3 | 17 | 26 | 102 | 17 | 114 | 20 | 151 | 0 | 140 | 20 | 160 | 311 | 413 |
| 09:30 09:45 | 47 | 2 | 6 | 55 | 8 | 2 | 12 | 22 | 77 | 21 | 109 | 20 | 150 | 5 | 127 | 14 | 146 | 296 | 373 |
| 09:45 10:00 | 47 | 6 | 2 | 55 | 14 | 3 | 13 | 30 | 85 | 16 | 100 | 18 | 134 | 4 | 133 | 21 | 158 | 292 | 377 |
| 11:30 11:45 | 39 | 2 | 3 | 44 | 17 | 1 | 20 | 38 | 82 | 15 | 113 | 36 | 165 | 1 | 126 | 20 | 147 | 312 | 394 |
| 11:45 12:00 | 35 | 2 | 0 | 37 | 7 | 3 | 13 | 23 | 60 | 22 | 120 | 35 | 177 | 0 | 106 | 15 | 121 | 298 | 358 |
| 12:00 12:15 | 38 | 2 | 2 | 42 | 14 | 5 | 16 | 35 | 77 | 19 | 127 | 35 | 181 | 1 | 128 | 8 | 137 | 318 | 395 |
| 12:15 12:30 | 32 | 4 | 3 | 39 | 11 | 2 | 16 | 29 | 68 | 14 | 133 | 29 | 176 | 2 | 136 | 11 | 149 | 325 | 393 |
| 12:30 12:45 | 40 | 2 | 3 | 45 | 12 | 2 | 11 | 25 | 70 | 18 | 142 | 30 | 190 | 4 | 124 | 14 | 142 | 332 | 402 |
| 12:45 13:00 | 38 | 0 | 5 | 43 | 13 | 2 | 17 | 32 | 75 | 18 | 162 | 43 | 223 | 0 | 112 | 18 | 130 | 353 | 428 |
| 13:00 13:15 | 29 | 2 | 1 | 32 | 17 | 2 | 11 | 30 | 62 | 21 | 129 | 37 | 187 | 4 | 129 | 12 | 145 | 332 | 394 |
| 13:15 13:30 | 35 | 4 | 3 | 42 | 14 | 1 | 14 | 29 | 71 | 16 | 124 | 42 | 182 | 2 | 113 | 7 | 122 | 304 | 375 |
| 15:00 15:15 | 33 | 5 | 1 | 39 | 13 | 7 | 17 | 37 | 76 | 39 | 141 | 57 | 237 | 2 | 149 | 25 | 176 | 413 | 489 |
| 15:15 15:30 | 48 | 11 | 2 | 61 | 28 | 17 | 30 | 75 | 136 | 21 | 167 | 66 | 254 | 4 | 160 | 20 | 184 | 438 | 574 |
| 15:30 15:45 | 36 | 6 | 2 | 44 | 22 | 5 | 32 | 59 | 103 | 25 | 173 | 71 | 269 | 2 | 145 | 15 | 162 | 431 | 534 |
| 15:45 16:00 | 54 | 3 | 3 | 60 | 15 | 7 | 14 | 36 | 96 | 32 | 168 | 76 | 276 | 2 | 136 | 19 | 157 | 433 | 529 |
| 16:00 16:15 | 48 | 9 | 5 | 62 | 11 | 14 | 25 | 50 | 112 | 26 | 184 | 79 | 289 | 8 | 169 | 13 | 190 | 479 | 591 |
| 16:15 16:30 | 47 | 9 | 7 | 63 | 14 | 13 | 21 | 48 | 111 | 36 | 197 | 93 | 327 | 3 | 174 | 19 | 196 | 523 | 634 |
| 16:30 16:45 | 53 | 5 | 5 | 63 | 13 | 13 | 23 | 49 | 112 | 32 | 170 | 87 | 289 | 3 | 144 | 15 | 162 | 451 | 563 |
| 16:45 17:00 | 50 | 11 | 7 | 68 | 14 | 9 | 20 | 43 | 111 | 22 | 173 | 99 | 294 | 3 | 161 | 18 | 182 | 476 | 587 |
| 17:00 17:15 | 38 | 6 | 3 | 47 | 21 | 11 | 18 | 50 | 97 | 28 | 169 | 87 | 284 | 4 | 156 | 15 | 175 | 459 | 556 |
| 17:15 17:30 | 41 | 11 | 6 | 58 | 17 | 7 | 11 | 35 | 93 | 22 | 180 | 100 | 302 | 5 | 145 | 9 | 159 | 461 | 554 |
| 17:30 17:45 | 46 | 3 | 2 | 51 | 19 | 9 | 14 | 42 | 93 | 28 | 182 | 92 | 302 | 1 | 148 | 16 | 165 | 467 | 560 |
| 17:45 18:00 | 45 | 4 | 1 | 50 | 10 | 8 | 12 | 30 | 80 | 24 | 180 | 87 | 291 | 3 | 162 | 19 | 184 | 475 | 555 |
| TOTAL: | 1778 | 204 | 113 | 2095 | 440 | 187 | 615 | 1242 | 3337 | 672 | 4440 | 1573 | 6687 | 75 | 4744 | 461 | 5280 | 11967 | 15304 |

Note: U-Turns are included in Totals.

Comment:



Transportation Services - Traffic Services
Turning Movement Count - Cyclist Volume Report

Work Order
37540

STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Count Date: Thursday, January 18, 2018

Start Time: 07:00

| Time Period | CEDARVIEW RD/TARTAN DR | | | STRANDHERD DR | | | Grand Total |
|-------------|------------------------|------------|--------------|---------------|-----------|--------------|-------------|
| | Northbound | Southbound | Street Total | Eastbound | Westbound | Street Total | |
| 07:00 08:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 08:00 09:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 09:00 10:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11:30 12:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12:30 13:30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15:00 16:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16:00 17:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17:00 18:00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Total | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Comment:

Note: These volumes consists of bicycles only (no mopeds or motorcycles) and ARE NOT included in the Turning Movement Count Summary.




Transportation Services - Traffic Services
Turning Movement Count - Full Study Diagram

STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Survey Date: Thursday, January 18, 2018

WO#: 37540

Device: Miovision





Transportation Services - Traffic Services

W.O. 37540

Turning Movement Count - Heavy Vehicle Report

STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Survey Date: Thursday, January 18, 2018

Table with columns for Time Period, Northbound (LT, ST, RT, N TOT), Southbound (LT, ST, RT, S TOT), Eastbound (LT, ST, RT, E TOT), Westbound (LT, ST, RT, W TOT), STR TOT, and Grand Total. Includes sub-totals for U-Turns and Total.

Heavy Vehicles include Buses, Single-Unit Trucks and Articulated Trucks. Further, they ARE included in the Turning Movement Count Summary.



Transportation Services - Traffic Services

Work Order 37540

Turning Movement Count - Pedestrian Volume Report

STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Count Date: Thursday, January 18, 2018

Start Time: 07:00

Table with columns for Time Period, NB Approach (E or W Crossing), SB Approach (E or W Crossing), Total, EB Approach (N or S Crossing), WB Approach (N or S Crossing), Total, and Grand Total. Shows pedestrian volume data for various time intervals.

Comment:



Transportation Services - Traffic Services

Work Order
37540

Turning Movement Count - Full Study Summary Report

STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Survey Date: Thursday, January 18, 2018

Total Observed U-Turns
Northbound: 0 Southbound: 0
Eastbound: 2 Westbound: 0

AADT Factor
1.00

Full Study

| Period | CEDARVIEW RD/TARTAN DR | | | | | | | | STRANDHERD DR | | | | | | | | WB TOT | STR TOT | Grand Total | | | |
|---|------------------------|------------|------------|-------------|------------|------------|-------------|-------------|---------------|-------------|-------------|-------------|--------------|------------|-------------|------------|-------------|--------------|--------------|--------|-------------|--|
| | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | | | | | | |
| | LT | ST | RT | NB TOT | LT | ST | RT | SB TOT | STR TOT | LT | ST | RT | EB TOT | LT | ST | RT | | | | WB TOT | | |
| 07:00 08:00 | 354 | 22 | 21 | 397 | 30 | 13 | 90 | 133 | 530 | 52 | 458 | 94 | 604 | 7 | 621 | 24 | 652 | 1256 | 1786 | | | |
| 08:00 09:00 | 365 | 57 | 14 | 436 | 74 | 24 | 113 | 211 | 647 | 79 | 432 | 115 | 626 | 3 | 745 | 59 | 807 | 1433 | 2080 | | | |
| 09:00 10:00 | 234 | 24 | 14 | 272 | 34 | 12 | 57 | 103 | 375 | 63 | 416 | 83 | 562 | 11 | 555 | 70 | 636 | 1198 | 1573 | | | |
| 11:30 12:30 | 144 | 10 | 8 | 162 | 49 | 11 | 65 | 125 | 287 | 70 | 493 | 135 | 698 | 4 | 496 | 54 | 554 | 1252 | 1539 | | | |
| 12:30 13:30 | 142 | 8 | 12 | 162 | 56 | 7 | 53 | 116 | 278 | 73 | 557 | 152 | 782 | 10 | 478 | 51 | 539 | 1321 | 1599 | | | |
| 15:00 16:00 | 171 | 25 | 8 | 204 | 78 | 36 | 93 | 207 | 411 | 117 | 649 | 270 | 1036 | 10 | 590 | 79 | 679 | 1715 | 2126 | | | |
| 16:00 17:00 | 198 | 34 | 24 | 256 | 52 | 49 | 89 | 190 | 446 | 116 | 724 | 358 | 1198 | 17 | 648 | 65 | 730 | 1928 | 2374 | | | |
| 17:00 18:00 | 170 | 24 | 12 | 206 | 67 | 35 | 55 | 157 | 363 | 102 | 711 | 366 | 1179 | 13 | 611 | 59 | 683 | 1862 | 2225 | | | |
| Sub Total | 1778 | 204 | 113 | 2095 | 440 | 187 | 615 | 1242 | 3337 | 672 | 4440 | 1573 | 6685 | 75 | 4744 | 461 | 5280 | 11965 | 15302 | | | |
| U Turns | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 2 | 0 | 0 | 2 | 2 | 2 | 2 | | | |
| Total | 1778 | 204 | 113 | 2095 | 440 | 187 | 615 | 1242 | 3337 | 672 | 4440 | 1573 | 6687 | 75 | 4744 | 461 | 5280 | 11967 | 15304 | | | |
| EQ 12Hr | 2471 | 284 | 157 | 2912 | 612 | 260 | 855 | 1726 | 4638 | 934 | 6172 | 2186 | 9295 | 104 | 6594 | 641 | 7339 | 16634 | 21272 | | | |
| Note: These values are calculated by multiplying the totals by the appropriate expansion factor. | | | | | | | | | | | | | | | | | | | | | 1.39 | |
| AVG 12Hr | 2471 | 284 | 157 | 2912 | 612 | 260 | 855 | 1726 | 4638 | 934 | 6172 | 2186 | 9295 | 104 | 6594 | 641 | 7339 | 16634 | 21272 | | 1.00 | |
| Note: These volumes are calculated by multiplying the Equivalent 12 hr. totals by the AADT factor. | | | | | | | | | | | | | | | | | | | | | | |
| AVG 24Hr | 3238 | 371 | 206 | 3815 | 801 | 341 | 1120 | 2262 | 6077 | 1224 | 8085 | 2864 | 12176 | 137 | 8638 | 839 | 9614 | 21790 | 27867 | | 1.31 | |
| Note: These volumes are calculated by multiplying the Average Daily 12 hr. totals by 12 to 24 expansion factor. | | | | | | | | | | | | | | | | | | | | | | |

Comments:

Note: U-Turns provided for approach totals. Refer to 'U-Turn' Report for specific breakdown.



Transportation Services - Traffic Services

Turning Movement Count - Full Study Peak Hour Diagram


STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Survey Date: Thursday, January 18, 2018

WO No: 37540

Start Time: 07:00

Device: Miovision



Comments




Transportation Services - Traffic Services

Turning Movement Count - Full Study Peak Hour Diagram

STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Survey Date: Thursday, January 18, 2018
Start Time: 07:00

WO No: 37540
Device: Miovision




Transportation Services - Traffic Services

Turning Movement Count - Full Study Peak Hour Diagram

STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Survey Date: Thursday, January 18, 2018
Start Time: 07:00

WO No: 37540
Device: Miovision





Transportation Services - Traffic Services

Turning Movement Count - Full Study Peak Hour Diagram


STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Survey Date: Thursday, January 18, 2018

Start Time: 07:00

WO No: 37540

Device: Miovision



Transportation Services - Traffic Services

Work Order
37540

Turning Movement Count - 15 Min U-Turn Total Report

STRANDHERD DR @ CEDARVIEW RD/TARTAN DR

Survey Date: Thursday, January 18, 2018

| Time Period | Northbound U-Turn Total | Southbound U-Turn Total | Eastbound U-Turn Total | Westbound U-Turn Total | Total |
|--------------|-------------------------|-------------------------|------------------------|------------------------|----------|
| 07:00 07:15 | 0 | 0 | 0 | 0 | 0 |
| 07:15 07:30 | 0 | 0 | 0 | 0 | 0 |
| 07:30 07:45 | 0 | 0 | 0 | 0 | 0 |
| 07:45 08:00 | 0 | 0 | 0 | 0 | 0 |
| 08:00 08:15 | 0 | 0 | 0 | 0 | 0 |
| 08:15 08:30 | 0 | 0 | 0 | 0 | 0 |
| 08:30 08:45 | 0 | 0 | 0 | 0 | 0 |
| 08:45 09:00 | 0 | 0 | 0 | 0 | 0 |
| 09:00 09:15 | 0 | 0 | 0 | 0 | 0 |
| 09:15 09:30 | 0 | 0 | 0 | 0 | 0 |
| 09:30 09:45 | 0 | 0 | 0 | 0 | 0 |
| 09:45 10:00 | 0 | 0 | 0 | 0 | 0 |
| 11:30 11:45 | 0 | 0 | 1 | 0 | 1 |
| 11:45 12:00 | 0 | 0 | 0 | 0 | 0 |
| 12:00 12:15 | 0 | 0 | 0 | 0 | 0 |
| 12:15 12:30 | 0 | 0 | 0 | 0 | 0 |
| 12:30 12:45 | 0 | 0 | 0 | 0 | 0 |
| 12:45 13:00 | 0 | 0 | 0 | 0 | 0 |
| 13:00 13:15 | 0 | 0 | 0 | 0 | 0 |
| 13:15 13:30 | 0 | 0 | 0 | 0 | 0 |
| 15:00 15:15 | 0 | 0 | 0 | 0 | 0 |
| 15:15 15:30 | 0 | 0 | 0 | 0 | 0 |
| 15:30 15:45 | 0 | 0 | 0 | 0 | 0 |
| 15:45 16:00 | 0 | 0 | 0 | 0 | 0 |
| 16:00 16:15 | 0 | 0 | 0 | 0 | 0 |
| 16:15 16:30 | 0 | 0 | 1 | 0 | 1 |
| 16:30 16:45 | 0 | 0 | 0 | 0 | 0 |
| 16:45 17:00 | 0 | 0 | 0 | 0 | 0 |
| 17:00 17:15 | 0 | 0 | 0 | 0 | 0 |
| 17:15 17:30 | 0 | 0 | 0 | 0 | 0 |
| 17:30 17:45 | 0 | 0 | 0 | 0 | 0 |
| 17:45 18:00 | 0 | 0 | 0 | 0 | 0 |
| Total | 0 | 0 | 2 | 0 | 2 |

Appendix C

Synchro Intersection Worksheets – Existing Conditions

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
Existing AM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|-----|-------|--------|-------|-------|-------|-------|
| Lane Configurations | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ |
| Traffic Volume (vph) | 6 | 2 | 7 | 100 | 3 | 109 | 19 | 1125 | 86 | 50 | 628 | 18 |
| Future Volume (vph) | 6 | 2 | 7 | 100 | 3 | 109 | 19 | 1125 | 86 | 50 | 628 | 18 |
| Satd. Flow (prot) | 1243 | 1160 | 1450 | 1589 | 1406 | 0 | 1621 | 1706 | 1409 | 1476 | 1626 | 1395 |
| Fit Permitted | 0.631 | | | 0.757 | | | 0.400 | | | 0.047 | | |
| Satd. Flow (perm) | 826 | 1160 | 1450 | 1267 | 1406 | 0 | 682 | 1706 | 1409 | 73 | 1626 | 1395 |
| Satd. Flow (RTOR) | | | 89 | | 121 | | | | 91 | | | 33 |
| Lane Group Flow (vph) | 7 | 2 | 8 | 111 | 124 | 0 | 21 | 1250 | 96 | 56 | 698 | 20 |
| Turn Type | Perm | NA | Perm | Perm | NA | | Perm | NA | Perm | pm-pt | NA | Perm |
| Protected Phases | | | 4 | | | | 8 | | | | 1 | 6 |
| Permitted Phases | 4 | | 4 | 8 | | | 2 | | 2 | 6 | | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 2 | 2 | 2 | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 10.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 32.6 | 32.6 | 32.6 | 32.6 | 32.6 | | 30.4 | 30.4 | 30.4 | 11.4 | 30.4 | 30.4 |
| Total Split (s) | 33.0 | 33.0 | 33.0 | 33.0 | 33.0 | | 75.0 | 75.0 | 75.0 | 12.0 | 87.0 | 87.0 |
| Total Split (%) | 27.5% | 27.5% | 27.5% | 27.5% | 27.5% | | 62.5% | 62.5% | 62.5% | 10.0% | 72.5% | 72.5% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 1.8 | 1.8 | 1.8 | 1.8 | 1.8 | 1.8 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | | 6.4 | 6.4 | 6.4 | 6.4 | 6.4 | 6.4 |
| Lead/Lag | | | | | | | Lag | Lag | Lag | Lead | | |
| Lead-Lag Optimize? | | | | | | | Yes | Yes | Yes | Yes | | |
| Recall Mode | None | None | None | None | None | | C-Max | C-Max | C-Max | None | C-Max | C-Max |
| Act Effct Green (s) | 16.0 | 16.0 | 16.0 | 16.0 | 16.0 | | 80.0 | 80.0 | 80.0 | 91.0 | 91.0 | 91.0 |
| Actuated g/C Ratio | 0.13 | 0.13 | 0.13 | 0.13 | 0.13 | | 0.67 | 0.67 | 0.67 | 0.76 | 0.76 | 0.76 |
| v/c Ratio | 0.06 | 0.01 | 0.03 | 0.66 | 0.42 | | 0.05 | 1.10 | 0.10 | 0.41 | 0.57 | 0.02 |
| Control Delay | 43.5 | 41.5 | 0.1 | 66.8 | 12.7 | | 10.1 | 80.9 | 2.7 | 20.6 | 9.1 | 0.9 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Delay | 43.5 | 41.5 | 0.1 | 66.8 | 12.7 | | 10.1 | 80.9 | 2.7 | 20.6 | 9.1 | 0.9 |
| LOS | D | D | A | E | B | | B | F | A | C | A | A |
| Approach Delay | | 22.9 | | | 38.2 | | | 74.3 | | | 9.7 | |
| Approach LOS | | C | | | D | | | E | | | A | |
| Queue Length 50th (m) | 1.4 | 0.4 | 0.0 | 24.9 | 0.6 | | 1.6 | ~335.6 | 0.4 | 2.8 | 58.1 | 0.0 |
| Queue Length 95th (m) | 5.5 | 2.7 | 0.0 | 41.2 | 16.4 | | 5.8 | #447.0 | 7.5 | 13.8 | 108.2 | 1.3 |
| Internal Link Dist (m) | | 172.9 | | | 177.4 | | | 1040.6 | | | 345.0 | |
| Turn Bay Length (m) | 70.0 | | 150.0 | 50.0 | | | 130.0 | | 60.0 | 180.0 | | 60.0 |
| Base Capacity (vph) | 181 | 255 | 388 | 278 | 403 | | 454 | 1137 | 969 | 136 | 1232 | 1065 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.04 | 0.01 | 0.02 | 0.40 | 0.31 | | 0.05 | 1.10 | 0.10 | 0.41 | 0.57 | 0.02 |


| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 105 (88%), Referenced to phase 2:NBT and 6:SBTL, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 130 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
Existing AM Peak Hour

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.10 | Intersection LOS: D |
| Intersection Signal Delay: 49.5 | ICU Level of Service E |
| Intersection Capacity Utilization 85.8% | |
| Analysis Period (min) 15 | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |

Splits and Phases: 1: Strandherd & Dealership/Kennevale



Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
Existing AM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|--------|-------|-------|--------|------|--------|-------|-----|-------|-------|------|
| Lane Configurations | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ |
| Traffic Volume (vph) | 81 | 482 | 141 | 15 | 703 | 52 | 336 | 49 | 27 | 69 | 23 | 120 |
| Future Volume (vph) | 81 | 482 | 141 | 15 | 703 | 52 | 336 | 49 | 27 | 69 | 23 | 120 |
| Satd. Flow (prot) | 1589 | 1642 | 1332 | 1621 | 1665 | 0 | 1605 | 1594 | 0 | 1605 | 1493 | 0 |
| Fit Permitted | 0.113 | | | 0.342 | | | 0.652 | | | 0.702 | | |
| Satd. Flow (perm) | 189 | 1642 | 1332 | 583 | 1665 | 0 | 1101 | 1594 | 0 | 1186 | 1493 | 0 |
| Satd. Flow (RTOR) | | | 157 | | 6 | | | 30 | | | 133 | |
| Lane Group Flow (vph) | 90 | 536 | 157 | 17 | 839 | 0 | 373 | 84 | 0 | 77 | 159 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | NA | Perm | NA | Perm | NA | Perm |
| Protected Phases | | 2 | | | 6 | | | 8 | | | 4 | |
| Permitted Phases | 2 | | 2 | 6 | | | 8 | | | 4 | | |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | | 8 | 8 | | 4 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 10.0 | 10.0 | | 10.0 | 10.0 | |
| Minimum Split (s) | 56.4 | 56.4 | 56.4 | 56.4 | 56.4 | | 23.8 | 23.8 | | 23.8 | 23.8 | |
| Total Split (s) | 56.4 | 56.4 | 56.4 | 56.4 | 56.4 | | 40.8 | 40.8 | | 40.8 | 40.8 | |
| Total Split (%) | 58.0% | 58.0% | 58.0% | 58.0% | 58.0% | | 42.0% | 42.0% | | 42.0% | 42.0% | |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | | 3.3 | 3.3 | | 3.3 | 3.3 | |
| All-Red Time (s) | 1.8 | 1.8 | 1.8 | 1.8 | 1.8 | | 2.5 | 2.5 | | 2.5 | 2.5 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.4 | 6.4 | 6.4 | 6.4 | 6.4 | | 5.8 | 5.8 | | 5.8 | 5.8 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | Max | Max | Max | Max | Max | | None | None | | None | None | |
| Act Effct Green (s) | 50.0 | 50.0 | 50.0 | 50.0 | 50.0 | | 33.9 | 33.9 | | 33.9 | 33.9 | |
| Actuated g/C Ratio | 0.52 | 0.52 | 0.52 | 0.52 | 0.52 | | 0.35 | 0.35 | | 0.35 | 0.35 | |
| v/c Ratio | 0.92 | 0.63 | 0.20 | 0.06 | 0.97 | | 0.96 | 0.14 | | 0.18 | 0.26 | |
| Control Delay | 99.9 | 20.8 | 2.8 | 12.6 | 47.3 | | 69.3 | 15.1 | | 22.8 | 6.9 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | |
| Total Delay | 99.9 | 20.8 | 2.8 | 12.6 | 47.3 | | 69.3 | 15.1 | | 22.8 | 6.9 | |
| LOS | F | C | A | B | D | | E | B | | C | A | |
| Approach Delay | | 26.3 | | | 46.6 | | | 59.3 | | | 12.1 | |
| Approach LOS | | C | | | D | | | E | | | B | |
| Queue Length 50th (m) | 14.8 | 68.3 | 0.0 | 1.5 | 144.1 | | 66.1 | 6.6 | | 9.7 | 3.1 | |
| Queue Length 95th (m) | #46.0 | 102.4 | 9.0 | 4.9 | #228.5 | | #120.8 | 16.3 | | 20.0 | 15.9 | |
| Internal Link Dist (m) | | 1040.6 | | | 357.0 | | | 275.6 | | | 103.1 | |
| Turn Bay Length (m) | 140.0 | | 175.0 | 150.0 | | | 70.0 | | | 38.0 | | |
| Base Capacity (vph) | 98 | 854 | 768 | 302 | 869 | | 400 | 599 | | 432 | 628 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | |
| Reduced v/c Ratio | 0.92 | 0.63 | 0.20 | 0.06 | 0.97 | | 0.93 | 0.14 | | 0.18 | 0.25 | |


| Intersection Summary | |
|------------------------|------------------------|
| Cycle Length: | 97.2 |
| Actuated Cycle Length: | 96.2 |
| Natural Cycle: | 95 |
| Control Type: | Actuated-Uncoordinated |
| Maximum v/c Ratio: | 0.97 |

Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
Existing AM Peak Hour

| | |
|---|------------------------|
| Intersection Signal Delay: 38.8 | Intersection LOS: D |
| Intersection Capacity Utilization 99.8% | ICU Level of Service F |
| Analysis Period (min) 15 | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |

Splits and Phases: 2: Borriskane/Tartan & Strandherd



Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
Existing PM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|-----|-------|--------|-------|-------|--------|-------|
| Lane Configurations | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ |
| Traffic Volume (vph) | 29 | 8 | 20 | 128 | 5 | 80 | 11 | 791 | 132 | 72 | 1073 | 13 |
| Future Volume (vph) | 29 | 8 | 20 | 128 | 5 | 80 | 11 | 791 | 132 | 72 | 1073 | 13 |
| Satd. Flow (prot) | 1605 | 1706 | 1450 | 1517 | 1389 | 0 | 1621 | 1689 | 1450 | 1589 | 1706 | 1450 |
| Fit Permitted | 0.695 | | | 0.752 | | | 0.104 | | | 0.161 | | |
| Satd. Flow (perm) | 1174 | 1706 | 1414 | 1195 | 1389 | 0 | 177 | 1689 | 1417 | 269 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | 89 | | 89 | | | | 100 | | | 33 |
| Lane Group Flow (vph) | 32 | 9 | 22 | 142 | 95 | 0 | 12 | 879 | 147 | 80 | 1192 | 14 |
| Turn Type | Perm | NA | Perm | Perm | NA | | Perm | NA | Perm | pm+pt | NA | Perm |
| Protected Phases | | | 4 | | | 8 | | | 2 | | 1 | 6 |
| Permitted Phases | 4 | | 4 | 8 | | | 2 | | 2 | 6 | | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 2 | 2 | 2 | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 10.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 32.6 | 32.6 | 32.6 | 32.6 | 32.6 | | 30.4 | 30.4 | 30.4 | 11.4 | 30.4 | 30.4 |
| Total Split (s) | 33.0 | 33.0 | 33.0 | 33.0 | 33.0 | | 72.0 | 72.0 | 72.0 | 15.0 | 87.0 | 87.0 |
| Total Split (%) | 27.5% | 27.5% | 27.5% | 27.5% | 27.5% | | 60.0% | 60.0% | 60.0% | 12.5% | 72.5% | 72.5% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 1.8 | 1.8 | 1.8 | 1.8 | 1.8 | 1.8 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | | 6.4 | 6.4 | 6.4 | 6.4 | 6.4 | 6.4 |
| Lead/Lag | | | | | | | Lag | Lag | Lag | Lead | | |
| Lead-Lag Optimize? | | | | | | | Yes | Yes | Yes | Yes | | |
| Recall Mode | None | None | None | None | None | | C-Max | C-Max | C-Max | None | C-Max | C-Max |
| Act Effct Green (s) | 19.2 | 19.2 | 19.2 | 19.2 | 19.2 | | 76.6 | 76.6 | 76.6 | 87.8 | 87.8 | 87.8 |
| Actuated g/C Ratio | 0.16 | 0.16 | 0.16 | 0.16 | 0.16 | | 0.64 | 0.64 | 0.64 | 0.73 | 0.73 | 0.73 |
| v/c Ratio | 0.17 | 0.03 | 0.07 | 0.74 | 0.32 | | 0.11 | 0.82 | 0.16 | 0.29 | 0.96 | 0.01 |
| Control Delay | 42.9 | 39.0 | 0.5 | 70.0 | 12.3 | | 15.1 | 26.9 | 4.8 | 8.2 | 33.6 | 0.5 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Delay | 42.9 | 39.0 | 0.5 | 70.0 | 12.3 | | 15.1 | 26.9 | 4.8 | 8.2 | 33.6 | 0.5 |
| LOS | D | D | A | E | B | | B | C | A | A | C | A |
| Approach Delay | | 27.5 | | | 46.8 | | | 23.7 | | | 31.7 | |
| Approach LOS | | C | | | D | | | C | | | C | |
| Queue Length 50th (m) | 6.5 | 1.8 | 0.0 | 31.7 | 1.2 | | 1.1 | 153.2 | 4.1 | 4.7 | 218.9 | 0.0 |
| Queue Length 95th (m) | 14.6 | 6.0 | 0.0 | 50.3 | 14.7 | | 5.1 | #275.3 | 14.5 | 11.1 | #377.2 | 0.7 |
| Internal Link Dist (m) | | 172.9 | | | 177.4 | | | 1040.6 | | | 345.0 | |
| Turn Bay Length (m) | 70.0 | | 150.0 | 50.0 | | | 130.0 | | 60.0 | 180.0 | | 60.0 |
| Base Capacity (vph) | 258 | 375 | 380 | 262 | 375 | | 113 | 1078 | 941 | 291 | 1248 | 1069 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | 0 | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.12 | 0.02 | 0.06 | 0.54 | 0.25 | | 0.11 | 0.82 | 0.16 | 0.27 | 0.96 | 0.01 |

| Intersection Summary | | | | | | | | | | | | |
|--|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 57 (48%), Referenced to phase 2:NBT and 6:SBTL, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 130 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
Existing PM Peak Hour

| | | |
|---|---------------------------------|---------------------|
| Maximum v/c Ratio: 0.96 | Intersection Signal Delay: 29.8 | Intersection LOS: C |
| Intersection Capacity Utilization 93.5% | ICU Level of Service F | |
| Analysis Period (min) 15 | | |
| # 95th percentile volume exceeds capacity, queue may be longer. | | |
| Queue shown is maximum after two cycles. | | |

Splits and Phases: 1: Strandherd & Dealership/Kennevale



Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
Existing PM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|--------|-------|-------|--------|------|-------|-------|-----|-------|-------|------|
| Lane Configurations | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ |
| Traffic Volume (vph) | 117 | 787 | 353 | 23 | 577 | 65 | 184 | 34 | 35 | 52 | 49 | 89 |
| Future Volume (vph) | 117 | 787 | 353 | 23 | 577 | 65 | 184 | 34 | 35 | 52 | 49 | 89 |
| Satd. Flow (prot) | 1605 | 1706 | 1436 | 1621 | 1664 | 0 | 1531 | 1495 | 0 | 1503 | 1493 | 0 |
| Fit Permitted | 0.274 | | | 0.171 | | | 0.659 | | | 0.707 | | |
| Satd. Flow (perm) | 463 | 1706 | 1436 | 292 | 1664 | 0 | 1062 | 1495 | 0 | 1118 | 1493 | 0 |
| Satd. Flow (RTOR) | | | 392 | | 9 | | | 39 | | | 99 | |
| Lane Group Flow (vph) | 130 | 874 | 392 | 26 | 713 | 0 | 204 | 77 | 0 | 58 | 153 | 0 |
| Turn Type | Perm | NA | Perm | Perm | NA | Perm | NA | Perm | NA | Perm | NA | Perm |
| Protected Phases | | 2 | | 6 | | 6 | 8 | | 8 | 4 | | 4 |
| Permitted Phases | 2 | | 2 | 6 | | 6 | 8 | | 8 | 4 | | 4 |
| Detector Phase | 2 | 2 | 2 | 6 | 6 | | 8 | 8 | | 4 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 10.0 | 10.0 | | 10.0 | 10.0 | |
| Minimum Split (s) | 56.4 | 56.4 | 56.4 | 56.4 | 56.4 | | 23.8 | 23.8 | | 23.8 | 23.8 | |
| Total Split (s) | 56.4 | 56.4 | 56.4 | 56.4 | 56.4 | | 40.8 | 40.8 | | 40.8 | 40.8 | |
| Total Split (%) | 58.0% | 58.0% | 58.0% | 58.0% | 58.0% | | 42.0% | 42.0% | | 42.0% | 42.0% | |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | | 3.3 | 3.3 | | 3.3 | 3.3 | |
| All-Red Time (s) | 1.8 | 1.8 | 1.8 | 1.8 | 1.8 | | 2.5 | 2.5 | | 2.5 | 2.5 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.4 | 6.4 | 6.4 | 6.4 | 6.4 | | 5.8 | 5.8 | | 5.8 | 5.8 | |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | Max | Max | Max | Max | Max | | None | None | | None | None | |
| Act Effct Green (s) | 50.3 | 50.3 | 50.3 | 50.3 | 50.3 | | 21.0 | 21.0 | | 21.0 | 21.0 | |
| Actuated g/C Ratio | 0.60 | 0.60 | 0.60 | 0.60 | 0.60 | | 0.25 | 0.25 | | 0.25 | 0.25 | |
| v/c Ratio | 0.47 | 0.85 | 0.38 | 0.15 | 0.71 | | 0.77 | 0.19 | | 0.21 | 0.34 | |
| Control Delay | 18.8 | 25.9 | 2.4 | 12.6 | 18.4 | | 47.7 | 14.4 | | 25.4 | 11.8 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | |
| Total Delay | 18.8 | 25.9 | 2.4 | 12.6 | 18.4 | | 47.7 | 14.4 | | 25.4 | 11.8 | |
| LOS | B | C | A | B | B | | D | B | | C | B | |
| Approach Delay | | 18.6 | | | 18.2 | | | 38.6 | | | 15.5 | |
| Approach LOS | | B | | | B | | | D | | | B | |
| Queue Length 50th (m) | 10.2 | 101.0 | 0.0 | 1.6 | 69.3 | | 29.6 | 4.6 | | 7.2 | 6.6 | |
| Queue Length 95th (m) | 34.3 | #230.3 | 12.8 | 7.5 | #154.0 | | 52.2 | 13.9 | | 16.1 | 19.8 | |
| Internal Link Dist (m) | | 1040.6 | | | 354.9 | | | 275.6 | | | 103.1 | |
| Turn Bay Length (m) | 140.0 | | 175.0 | 150.0 | | | 70.0 | | | 38.0 | | |
| Base Capacity (vph) | 278 | 1027 | 1020 | 175 | 1005 | | 447 | 652 | | 471 | 686 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | |
| Reduced v/c Ratio | 0.47 | 0.85 | 0.38 | 0.15 | 0.71 | | 0.46 | 0.12 | | 0.12 | 0.22 | |


| Intersection Summary | |
|------------------------|------------------------|
| Cycle Length: | 97.2 |
| Actuated Cycle Length: | 83.6 |
| Natural Cycle: | 85 |
| Control Type: | Actuated-Uncoordinated |
| Maximum v/c Ratio: | 0.85 |

Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
Existing PM Peak Hour

| | |
|---|------------------------|
| Intersection Signal Delay: 20.4 | Intersection LOS: C |
| Intersection Capacity Utilization 91.6% | ICU Level of Service F |
| Analysis Period (min) 15 | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |

Splits and Phases: 2: Borriskane/Tartan & Strandherd



Appendix D

Collision Data

| Accident Date | Accident Year | Accident Time | Location | Environment Condition | Light | Traffic Control | Traffic Control Condition | Classification Of Accident | Initial Impact Type | Road Surface Condition | # Vehicles | # Motorcycles | # Bicycles | # Pedestrians |
|---------------|---------------|---------------|---|-----------------------|---------------|---------------------|---------------------------|----------------------------|-----------------------|------------------------|------------|---------------|------------|---------------|
| 10/16/2016 | 2016 | 11:45 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 02 - Rain | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 10/17/2016 | 2016 | 20:18 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 12/2/2016 | 2016 | 13:33 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 00 - Unknown | 03 - P-D only | 01 - Dry | 01 - Dry | 2 | 0 | 0 | 0 |
| 2/6/2016 | 2016 | 17:26 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 05 - Dusk | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 05 - Turning movement | 01 - Dry | 2 | 0 | 0 | 0 |
| 5/8/2016 | 2016 | 20:00 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 02 - Non-fatal injury | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 11/15/2016 | 2016 | 12:02 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 8/4/2016 | 2016 | 13:20 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 8/2/2016 | 2016 | 20:57 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 9/19/2016 | 2016 | 22:30 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 01 - Functioning | 02 - Non-fatal injury | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 10/25/2017 | 2017 | 14:07 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 12/8/2017 | 2017 | 1:22 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 02 - Angle | 01 - Dry | 2 | 0 | 0 | 0 |
| 6/12/2017 | 2017 | 13:03 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 7/21/2017 | 2017 | 9:22 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 02 - Non-fatal injury | 05 - Turning movement | 01 - Dry | 2 | 0 | 0 | 0 |
| 8/12/2017 | 2017 | 19:16 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 02 - Rain | 05 - Dusk | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 12/12/2017 | 2017 | 15:01 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 10/11/2018 | 2018 | 16:22 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 05 - Turning movement | 01 - Dry | 2 | 0 | 0 | 0 |
| 10/17/2018 | 2018 | 7:45 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 02 - Rain | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 05 - Turning movement | 02 - Wet | 2 | 0 | 0 | 0 |
| 10/22/2018 | 2018 | 11:58 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 02 - Non-fatal injury | 05 - Turning movement | 01 - Dry | 2 | 0 | 0 | 0 |
| 12/30/2018 | 2018 | 18:56 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 07 - Dark | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 12/25/2018 | 2018 | 8:03 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 07 - SMV other | 01 - Dry | 1 | 0 | 0 | 0 |
| 4/7/2018 | 2018 | 17:29 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 4/2/2018 | 2018 | 18:22 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 05 - Dusk | 01 - Traffic signal | 00 - Unknown | 03 - P-D only | 03 - Rear end | 01 - Dry | 3 | 0 | 0 | 0 |
| 7/12/2018 | 2018 | 10:08 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 04 - Sideswipe | 01 - Dry | 2 | 0 | 0 | 0 |
| 7/5/2018 | 2018 | 11:00 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 05 - Turning movement | 01 - Dry | 2 | 0 | 0 | 0 |
| 9/21/2019 | 2019 | 19:05 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 1/21/2019 | 2019 | 15:46 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 05 - Drifting Snow | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 05 - Packed snow | 2 | 0 | 0 | 0 |
| 11/11/2019 | 2019 | 22:27 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 03 - Snow | 07 - Dark | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 02 - Angle | 05 - Packed snow | 2 | 0 | 0 | 0 |
| 11/11/2019 | 2019 | 15:35 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 03 - Snow | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 03 - Loose snow | 2 | 0 | 0 | 0 |
| 12/1/2019 | 2019 | 12:15 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 01 - Dry | 3 | 0 | 0 | 0 |
| 12/11/2019 | 2019 | 19:00 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 03 - Snow | 07 - Dark | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 12/23/2019 | 2019 | 14:11 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 3/25/2019 | 2019 | 22:10 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 04 - Freezing Rain | 07 - Dark | 01 - Traffic signal | 00 - Unknown | 03 - P-D only | 07 - SMV other | 06 - Ice | 1 | 0 | 0 | 0 |
| 4/1/2019 | 2019 | 12:10 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 02 - Non-fatal injury | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 3/22/2019 | 2019 | 19:20 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 03 - Snow | 07 - Dark | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 3/25/2019 | 2019 | 7:20 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 02 - Angle | 06 - Ice | 2 | 0 | 0 | 0 |
| 4/29/2019 | 2019 | 9:22 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 04 - Sideswipe | 01 - Dry | 2 | 0 | 0 | 0 |
| 4/28/2019 | 2019 | 17:30 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 02 - Rain | 01 - Daylight | 01 - Traffic signal | 00 - Unknown | 03 - P-D only | 02 - Wet | 02 - Wet | 2 | 0 | 0 | 0 |
| 5/17/2019 | 2019 | 12:00 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 02 - Non-fatal injury | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 7/11/2019 | 2019 | 16:38 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 02 - Rain | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 02 - Wet | 3 | 0 | 0 | 0 |
| 7/5/2019 | 2019 | 13:50 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 00 - Unknown | 02 - Non-fatal injury | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 7/9/2019 | 2019 | 10:43 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 02 - Non-fatal injury | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 7/29/2019 | 2019 | 16:50 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 02 - Rain | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 02 - Non-fatal injury | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 8/12/2019 | 2019 | 13:22 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 05 - Turning movement | 01 - Dry | 2 | 0 | 0 | 0 |
| 6/11/2020 | 2020 | 16:30 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 7/9/2020 | 2020 | 14:23 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 7/11/2020 | 2020 | 19:20 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 02 - Angle | 01 - Dry | 2 | 1 | 0 | 0 |
| 9/16/2020 | 2020 | 10:37 | BORRISOKANE RD/TARTAN DR @ STRANDHERD DR (0010634) | 01 - Clear | 01 - Daylight | 01 - Traffic signal | 01 - Functioning | 03 - P-D only | 03 - Rear end | 01 - Dry | 4 | 0 | 0 | 0 |
| 11/26/2016 | 2016 | 14:39 | STRANDHERD DR btwn CEDARVIEW RD & MCKENNA CASEY DR (_3012PQ) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 02 - Non-fatal injury | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 12/21/2017 | 2017 | 16:50 | STRANDHERD DR btwn CEDARVIEW RD & MCKENNA CASEY DR (_3012PQ) | 01 - Clear | 05 - Dusk | 10 - No control | 0 | 03 - P-D only | 04 - Sideswipe | 01 - Dry | 2 | 0 | 0 | 0 |
| 8/4/2018 | 2018 | 14:19 | STRANDHERD DR btwn CEDARVIEW RD & MCKENNA CASEY DR (_3012PQ) | 02 - Rain | 01 - Daylight | 10 - No control | 0 | 03 - P-D only | 03 - Rear end | 02 - Wet | 2 | 0 | 0 | 0 |
| 5/30/2019 | 2019 | 20:24 | STRANDHERD DR btwn CEDARVIEW RD & MCKENNA CASEY DR (_3012PQ) | 01 - Clear | 05 - Dusk | 10 - No control | 0 | 02 - Non-fatal injury | 03 - Rear end | 01 - Dry | 4 | 0 | 0 | 0 |
| 9/28/2016 | 2016 | 13:17 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 02 - Non-fatal injury | 07 - SMV other | 01 - Dry | 1 | 0 | 0 | 0 |
| 10/7/2017 | 2017 | 10:28 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 02 - Rain | 01 - Daylight | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 02 - Wet | 1 | 0 | 0 | 0 |
| 12/16/2017 | 2017 | 8:10 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 02 - Non-fatal injury | 07 - SMV other | 01 - Dry | 1 | 0 | 0 | 0 |
| 2/6/2017 | 2017 | 20:11 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 03 - Snow | 07 - Dark | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 03 - Loose snow | 1 | 0 | 0 | 0 |
| 2/10/2017 | 2017 | 22:39 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 04 - Freezing Rain | 07 - Dark | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 06 - Ice | 1 | 0 | 0 | 0 |
| 5/23/2017 | 2017 | 14:40 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 03 - P-D only | 99 - Other | 01 - Dry | 2 | 0 | 0 | 0 |
| 9/23/2017 | 2017 | 21:27 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 07 - Dark | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 01 - Dry | 1 | 0 | 0 | 0 |
| 10/8/2018 | 2018 | 13:45 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 02 - Rain | 01 - Daylight | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 02 - Wet | 1 | 0 | 0 | 0 |
| 12/1/2018 | 2018 | 22:45 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 07 - Dark | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 01 - Dry | 1 | 0 | 0 | 0 |
| 12/27/2018 | 2018 | 12:27 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 03 - P-D only | 03 - Rear end | 06 - Ice | 2 | 0 | 0 | 0 |
| 3/7/2018 | 2018 | 8:37 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 03 - Snow | 01 - Daylight | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 03 - Loose snow | 1 | 0 | 0 | 0 |
| 5/15/2018 | 2018 | 8:26 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 02 - Non-fatal injury | 07 - SMV other | 01 - Dry | 1 | 0 | 0 | 0 |
| 8/2/2018 | 2018 | 16:36 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 01 - Dry | 1 | 0 | 0 | 0 |
| 8/15/2018 | 2018 | 11:11 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 01 - Dry | 1 | 0 | 0 | 0 |
| 8/24/2018 | 2018 | 17:17 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 02 - Non-fatal injury | 07 - SMV other | 01 - Dry | 1 | 0 | 0 | 0 |
| 9/15/2018 | 2018 | 17:30 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 01 - Dry | 1 | 0 | 0 | 0 |
| 10/15/2019 | 2019 | 16:11 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 01 - Clear | 01 - Daylight | 10 - No control | 0 | 03 - P-D only | 03 - Rear end | 01 - Dry | 2 | 0 | 0 | 0 |
| 12/30/2019 | 2019 | 23:15 | BORRISOKANE RD btwn CAMBRIAN RD & STRANDHERD DR (_32A1CC) | 04 - Freezing Rain | 07 - Dark | 10 - No control | 0 | 03 - P-D only | 07 - SMV other | 06 - Ice | | | | |

Appendix E

Synchro Intersection Worksheets – 2030 Future Background Conditions

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2030 Future Background AM Peak Hour


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|------|---------------|--------|-----|-------|--------|-------|
| Lane Configurations | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ |
| Traffic Volume (vph) | 72 | 19 | 47 | 100 | 108 | 113 | 219 | 2642 | 86 | 53 | 1262 | 307 |
| Future Volume (vph) | 72 | 19 | 47 | 100 | 108 | 113 | 219 | 2642 | 86 | 53 | 1262 | 307 |
| Satd. Flow (prot) | 1243 | 1160 | 1450 | 1589 | 1353 | 0 | 3144 | 3219 | 0 | 1476 | 3090 | 1395 |
| Fit Permitted | 0.460 | | | 0.745 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 602 | 1160 | 1431 | 1245 | 1353 | 0 | 3144 | 3219 | 0 | 1476 | 3090 | 1395 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 72 | 19 | 47 | 100 | 221 | 0 | 219 | 2728 | 0 | 53 | 1262 | 307 |
| Turn Type | Perm | NA | Perm | Perm | NA | Prot | NA | Prot | NA | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | 4 | 8 | | | | | | | | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 39.9 | 39.9 | 39.9 | 32.9 | 32.9 | | 11.4 | 30.4 | | 11.4 | 39.4 | 39.4 |
| Total Split (s) | 41.0 | 41.0 | 41.0 | 41.0 | 41.0 | | 17.8 | 66.6 | | 12.4 | 61.2 | 61.2 |
| Total Split (%) | 34.2% | 34.2% | 34.2% | 34.2% | 34.2% | | 14.8% | 55.5% | | 10.3% | 51.0% | 51.0% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.6 | 3.6 | 3.6 | 3.6 | 3.6 | | 1.8 | 1.8 | | 1.8 | 1.8 | 1.8 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.9 | 6.9 | 6.9 | 6.9 | 6.9 | | 6.4 | 6.4 | | 6.4 | 6.4 | 6.4 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 24.8 | 24.8 | 24.8 | 24.8 | 24.8 | | 12.7 | 69.3 | | 8.8 | 62.8 | 62.8 |
| Actuated g/C Ratio | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | | 0.11 | 0.58 | | 0.07 | 0.52 | 0.52 |
| v/c Ratio | 0.58 | 0.08 | 0.16 | 0.39 | 0.79 | | 0.66 | 1.47 | | 0.50 | 0.78 | 0.42 |
| Control Delay | 60.0 | 35.6 | 37.4 | 43.8 | 64.3 | | 66.9 | 230.0 | | 69.4 | 28.9 | 21.5 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 60.0 | 35.6 | 37.4 | 43.8 | 64.3 | | 66.9 | 230.0 | | 69.4 | 28.9 | 21.5 |
| LOS | E | D | D | D | E | | E | F | | E | C | C |
| Approach Delay | | 49.0 | | | 57.9 | | | 217.9 | | | 28.8 | |
| Approach LOS | | D | | | E | | | F | | | C | |
| Queue Length 50th (m) | 15.2 | 3.6 | 9.0 | 20.2 | 49.1 | | 25.2 | ~485.6 | | 11.9 | 122.6 | 43.0 |
| Queue Length 95th (m) | 28.6 | 9.1 | 17.6 | 33.2 | 70.2 | | m15.9 m#255.5 | | | #32.4 | #174.4 | 73.9 |
| Internal Link Dist (m) | | 172.9 | | | 177.4 | | | 1040.6 | | | 345.0 | |
| Turn Bay Length (m) | 70.0 | | 150.0 | 50.0 | | | 130.0 | | | 180.0 | | 60.0 |
| Base Capacity (vph) | 171 | 329 | 406 | 353 | 384 | | 338 | 1858 | | 107 | 1618 | 730 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.42 | 0.06 | 0.12 | 0.28 | 0.58 | | 0.65 | 1.47 | | 0.50 | 0.78 | 0.42 |

| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 69 (58%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 125 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2030 Future Background AM Peak Hour

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.47 | Intersection LOS: F |
| Intersection Signal Delay: 142.0 | ICU Level of Service H |
| Intersection Capacity Utilization 127.9% | |
| Analysis Period (min) 15 | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2030 Future Background AM Peak Hour


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|--------|--------|--------|-------|--------|-------|--------|-------|-------|-------|-------|-----|
| Lane Configurations | ↔ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ |
| Traffic Volume (vph) | 117 | 753 | 506 | 63 | 1599 | 52 | 1029 | 49 | 114 | 69 | 23 | 230 |
| Future Volume (vph) | 117 | 753 | 506 | 63 | 1599 | 52 | 1029 | 49 | 114 | 69 | 23 | 230 |
| Satd. Flow (prot) | 1589 | 3119 | 1332 | 1621 | 3210 | 1345 | 3113 | 1673 | 1450 | 1605 | 1474 | 0 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1589 | 3119 | 1332 | 1621 | 3210 | 1345 | 3113 | 1673 | 1450 | 1605 | 1474 | 0 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 117 | 753 | 506 | 63 | 1599 | 52 | 1029 | 49 | 114 | 69 | 253 | 0 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | |
| Protected Phases | 5 | 2 | 2 | 1 | 6 | 6 | 3 | 8 | 8 | 7 | 4 | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Detector Phase | 5 | 2 | 2 | 1 | 6 | 6 | 3 | 8 | 8 | 7 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | |
| Minimum Split (s) | 11.6 | 33.6 | 33.6 | 11.6 | 33.6 | 33.6 | 11.7 | 33.7 | 33.7 | 11.7 | 33.7 | |
| Total Split (s) | 13.0 | 48.7 | 48.7 | 11.6 | 47.3 | 47.3 | 26.0 | 41.8 | 41.8 | 17.9 | 33.7 | |
| Total Split (%) | 10.8% | 40.6% | 40.6% | 9.7% | 39.4% | 39.4% | 21.7% | 34.8% | 34.8% | 14.9% | 28.1% | |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | |
| All-Red Time (s) | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 3.4 | 3.4 | 3.4 | 3.4 | 3.4 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | |
| Lead/Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 9.3 | 43.2 | 43.2 | 6.8 | 40.7 | 40.7 | 19.3 | 36.4 | 36.4 | 9.6 | 24.1 | |
| Actuated g/C Ratio | 0.08 | 0.36 | 0.36 | 0.06 | 0.34 | 0.34 | 0.16 | 0.30 | 0.30 | 0.08 | 0.20 | |
| v/c Ratio | 0.95 | 0.67 | 1.05 | 0.69 | 1.47 | 0.11 | 2.06 | 0.10 | 0.26 | 0.54 | 0.86 | |
| Control Delay | 126.1 | 21.2 | 75.6 | 92.5 | 247.8 | 28.2 | 509.9 | 31.9 | 34.4 | 68.3 | 72.2 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 126.1 | 21.2 | 75.6 | 92.5 | 247.8 | 28.2 | 509.9 | 31.9 | 34.4 | 68.3 | 72.2 | |
| LOS | F | C | E | F | F | C | F | C | C | E | E | |
| Approach Delay | | 50.1 | | | 235.4 | | | 444.8 | | | 71.4 | |
| Approach LOS | | D | | | F | | | F | | | E | |
| Queue Length 50th (m) | ~33.4 | 49.3 | ~133.0 | 14.8 | ~268.4 | 8.3 | ~194.0 | 8.3 | 20.4 | 15.5 | 55.9 | |
| Queue Length 95th (m) | m#56.0 | 58.5 | #191.6 | #42.7 | #310.1 | 17.4 | #233.1 | 17.7 | 35.7 | 30.3 | #92.0 | |
| Internal Link Dist (m) | | 1040.6 | | | 387.1 | | | 275.6 | | | 103.1 | |
| Turn Bay Length (m) | 90.0 | | 90.0 | 50.0 | | 27.5 | 160.0 | | 57.5 | 17.0 | | |
| Base Capacity (vph) | 123 | 1124 | 480 | 91 | 1088 | 456 | 500 | 512 | 444 | 149 | 331 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.95 | 0.67 | 1.05 | 0.69 | 1.47 | 0.11 | 2.06 | 0.10 | 0.26 | 0.46 | 0.76 | |

| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 120 |
| Actuated Cycle Length: | 120 |
| Offset: | 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green |
| Natural Cycle: | 125 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2030 Future Background AM Peak Hour

| | |
|---|--------|
| Maximum v/c Ratio: | 2.06 |
| Intersection Signal Delay: | 222.8 |
| Intersection LOS: | F |
| Intersection Capacity Utilization: | 122.9% |
| ICU Level of Service: | H |
| Analysis Period (min): | 15 |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2030 Future Background AM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-----|-------|-------|-----|-------|-------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 46 | 0 | 3 | 12 | 0 | 49 | 1 | 494 | 5 | 22 | 216 | 20 |
| Future Volume (vph) | 46 | 0 | 3 | 12 | 0 | 49 | 1 | 494 | 5 | 22 | 216 | 20 |
| Satd. Flow (prot) | 1621 | 1450 | 0 | 1621 | 1450 | 0 | 1621 | 1702 | 0 | 1621 | 1706 | 1450 |
| Fit Permitted | 0.725 | | | 0.756 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1237 | 1450 | 0 | 1290 | 1450 | 0 | 1621 | 1702 | 0 | 1621 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 46 | 3 | 0 | 12 | 49 | 0 | 1 | 499 | 0 | 22 | 216 | 20 |
| Turn Type | Perm | NA | | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | | | | | | | 6 |
| Detector Phase | 4 | 4 | | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 25.6 | | 11.6 | 25.6 | 25.6 |
| Total Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 44.7 | | 12.0 | 45.1 | 45.1 |
| Total Split (%) | 37.0% | 37.0% | | 37.0% | 37.0% | | 12.9% | 49.7% | | 13.3% | 50.1% | 50.1% |
| Yellow Time (s) | 3.3 | 3.3 | | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.0 | 3.0 | | 3.0 | 3.0 | | 2.0 | 2.0 | | 2.0 | 2.0 | 2.0 |
| Lost Time Adjust (s) | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.3 | 6.3 | | 6.3 | 6.3 | | 6.6 | 6.6 | | 6.6 | 6.6 | 6.6 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 13.5 | 13.5 | | 13.5 | 13.5 | | 5.4 | 67.6 | | 6.2 | 70.5 | 70.5 |
| Actuated g/C Ratio | 0.15 | 0.15 | | 0.15 | 0.15 | | 0.06 | 0.75 | | 0.07 | 0.78 | 0.78 |
| v/c Ratio | 0.25 | 0.01 | | 0.06 | 0.23 | | 0.01 | 0.39 | | 0.20 | 0.16 | 0.02 |
| Control Delay | 34.7 | 28.0 | | 29.6 | 33.8 | | 40.0 | 11.2 | | 44.0 | 7.5 | 8.8 |
| Queue Delay | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 34.7 | 28.0 | | 29.6 | 33.8 | | 40.0 | 11.2 | | 44.0 | 7.5 | 8.8 |
| LOS | C | C | | C | C | | D | B | | D | A | A |
| Approach Delay | | 34.3 | | | 33.0 | | | 11.2 | | | 10.7 | |
| Approach LOS | | C | | | C | | | B | | | B | |
| Queue Length 50th (m) | 7.4 | 0.5 | | 1.9 | 7.8 | | 0.2 | 24.9 | | 3.6 | 8.7 | 0.7 |
| Queue Length 95th (m) | 13.7 | 2.3 | | 5.3 | 14.1 | | 1.7 | 102.6 | | 10.9 | 39.1 | 5.9 |
| Internal Link Dist (m) | | 145.0 | | | 184.4 | | | 650.0 | | | 273.4 | |
| Turn Bay Length (m) | 9.3 | | | 9.3 | | | 84.0 | | | 84.5 | | 83.0 |
| Base Capacity (vph) | 371 | 435 | | 387 | 435 | | 98 | 1278 | | 111 | 1336 | 1135 |
| Starvation Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.12 | 0.01 | | 0.03 | 0.11 | | 0.01 | 0.39 | | 0.20 | 0.16 | 0.02 |


| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 90 | | | | | | | | | | | | |
| Actuated Cycle Length: 90 | | | | | | | | | | | | |
| Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 80 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2030 Future Background AM Peak Hour

| | | |
|---|---------------------------------|---------------------|
| Maximum v/c Ratio: 0.39 | Intersection Signal Delay: 13.9 | Intersection LOS: B |
| Intersection Capacity Utilization 47.9% | ICU Level of Service A | |
| Analysis Period (min) 15 | | |

Splits and Phases: 9: Borriskane & Conservancy Way



Lanes, Volumes, Timings
10: Borrisokane & New Collector

Caivan Conservancy West
2030 Future Background AM Peak Hour


| Lane Group | EBL | EBR | NBL | NBT | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|-------|
| Lane Configurations | ↖ | ↗ | ↖ | ↗ | ↗ | ↗ |
| Traffic Volume (vph) | 47 | 2 | 1 | 588 | 256 | 20 |
| Future Volume (vph) | 47 | 2 | 1 | 588 | 256 | 20 |
| Satd. Flow (prot) | 1621 | 1450 | 1621 | 1706 | 1706 | 1450 |
| Fit Permitted | 0.950 | | 0.601 | | | |
| Satd. Flow (perm) | 1621 | 1450 | 1025 | 1706 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | |
| Lane Group Flow (vph) | 47 | 2 | 1 | 588 | 256 | 20 |
| Turn Type | Perm | Perm | Perm | NA | NA | Perm |
| Protected Phases | | | | 2 | 6 | |
| Permitted Phases | 4 | 4 | 2 | | | 6 |
| Detector Phase | 4 | 4 | 2 | 2 | 6 | 6 |
| Switch Phase | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 |
| Minimum Split (s) | 30.8 | 30.8 | 31.8 | 31.8 | 31.8 | 31.8 |
| Total Split (s) | 30.8 | 30.8 | 61.0 | 61.0 | 61.0 | 61.0 |
| Total Split (%) | 33.6% | 33.6% | 66.4% | 66.4% | 66.4% | 66.4% |
| Yellow Time (s) | 4.6 | 4.6 | 3.3 | 3.3 | 3.3 | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 3.5 | 3.5 | 3.5 | 3.5 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 |
| Lead/Lag | | | | | | |
| Lead-Lag Optimize? | | | | | | |
| Recall Mode | None | None | C-Max | C-Max | C-Max | C-Max |
| Act Effct Green (s) | 12.8 | 12.8 | 74.8 | 74.8 | 74.8 | 74.8 |
| Actuated g/C Ratio | 0.14 | 0.14 | 0.81 | 0.81 | 0.81 | 0.81 |
| v/c Ratio | 0.21 | 0.01 | 0.00 | 0.42 | 0.18 | 0.02 |
| Control Delay | 35.2 | 30.0 | 6.0 | 6.8 | 4.9 | 5.3 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Delay | 35.2 | 30.0 | 6.0 | 6.8 | 4.9 | 5.3 |
| LOS | D | C | A | A | A | A |
| Approach Delay | 35.0 | | | 6.8 | 4.9 | |
| Approach LOS | C | | | A | A | |
| Queue Length 50th (m) | 7.7 | 0.3 | 0.0 | 33.0 | 11.1 | 0.7 |
| Queue Length 95th (m) | 14.6 | 2.0 | 0.7 | 89.0 | 32.1 | 4.1 |
| Internal Link Dist (m) | 113.8 | | | 273.4 | 275.6 | |
| Turn Bay Length (m) | 38.5 | | 27.5 | | | |
| Base Capacity (vph) | 423 | 379 | 835 | 1391 | 1391 | 1182 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.11 | 0.01 | 0.00 | 0.42 | 0.18 | 0.02 |

Intersection Summary
 Cycle Length: 91.8
 Actuated Cycle Length: 91.8
 Offset: 0 (0%), Referenced to phase 2:NBL and 6:SBT, Start of Green
 Natural Cycle: 65
 Control Type: Actuated-Coordinated

Lanes, Volumes, Timings
10: Borrisokane & New Collector

Caivan Conservancy West
2030 Future Background AM Peak Hour

Maximum v/c Ratio: 0.42
 Intersection Signal Delay: 7.7
 Intersection Capacity Utilization 52.3%
 Analysis Period (min) 15
 Intersection LOS: A
 ICU Level of Service A



Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2030 Future Background PM Peak Hour

| | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|--------|-------|-------|-------|-------|-----|-------|---------|-----|-------|--------|-------|
| Lane Configurations | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ |
| Traffic Volume (vph) | 275 | 96 | 188 | 128 | 26 | 92 | 66 | 1785 | 132 | 85 | 2602 | 108 |
| Future Volume (vph) | 275 | 96 | 188 | 128 | 26 | 92 | 66 | 1785 | 132 | 85 | 2602 | 108 |
| Satd. Flow (prot) | 1605 | 1706 | 1450 | 1517 | 1440 | 0 | 3144 | 3174 | 0 | 1589 | 3241 | 1450 |
| Fit Permitted | 0.681 | | | 0.695 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1150 | 1706 | 1431 | 1108 | 1440 | 0 | 3144 | 3174 | 0 | 1589 | 3241 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 275 | 96 | 188 | 128 | 118 | 0 | 66 | 1917 | 0 | 85 | 2602 | 108 |
| Turn Type | Perm | NA | Perm | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | | 8 | 5 | 2 | | 1 | | 6 |
| Permitted Phases | 4 | | 4 | 8 | | | 5 | 2 | | 1 | 6 | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 39.9 | 39.9 | 39.9 | 32.9 | 32.9 | | 11.4 | 30.4 | | 11.4 | 39.4 | 39.4 |
| Total Split (s) | 43.0 | 43.0 | 43.0 | 43.0 | 43.0 | | 11.4 | 65.0 | | 12.0 | 65.6 | 65.6 |
| Total Split (%) | 35.8% | 35.8% | 35.8% | 35.8% | 35.8% | | 9.5% | 54.2% | | 10.0% | 54.7% | 54.7% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.6 | 3.6 | 3.6 | 3.6 | 3.6 | | 1.8 | 1.8 | | 1.8 | 1.8 | 1.8 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.9 | 6.9 | 6.9 | 6.9 | 6.9 | | 6.4 | 6.4 | | 6.4 | 6.4 | 6.4 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 32.1 | 32.1 | 32.1 | 32.1 | 32.1 | | 5.8 | 59.3 | | 9.0 | 64.8 | 64.8 |
| Actuated g/C Ratio | 0.27 | 0.27 | 0.27 | 0.27 | 0.27 | | 0.05 | 0.49 | | 0.08 | 0.54 | 0.54 |
| v/c Ratio | 0.90 | 0.21 | 0.49 | 0.43 | 0.31 | | 0.43 | 1.22 | | 0.71 | 1.49 | 0.14 |
| Control Delay | 72.9 | 34.0 | 41.0 | 40.3 | 36.2 | | 72.2 | 120.0 | | 87.3 | 247.3 | 16.4 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 72.9 | 34.0 | 41.0 | 40.3 | 36.2 | | 72.2 | 120.0 | | 87.3 | 247.3 | 16.4 |
| LOS | E | C | D | D | D | | E | F | | F | F | B |
| Approach Delay | | 55.5 | | | 38.3 | | | 118.4 | | | 233.5 | |
| Approach LOS | | E | | | D | | | F | | | F | |
| Queue Length 50th (m) | 59.6 | 16.8 | 35.7 | 23.9 | 21.2 | | 7.4 | ~300.8 | | 20.0 | ~458.7 | 13.3 |
| Queue Length 95th (m) | #101.1 | 29.9 | 56.8 | 41.3 | 36.4 | | m7.4 | m#248.8 | | #55.1 | #497.9 | 23.8 |
| Internal Link Dist (m) | | 172.9 | | | 177.4 | | | 1040.6 | | | 345.0 | |
| Turn Bay Length (m) | 70.0 | | 150.0 | 50.0 | | | 130.0 | | | 180.0 | | 60.0 |
| Base Capacity (vph) | 345 | 513 | 430 | 333 | 433 | | 153 | 1567 | | 119 | 1751 | 783 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.80 | 0.19 | 0.44 | 0.38 | 0.27 | | 0.43 | 1.22 | | 0.71 | 1.49 | 0.14 |


| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 64 (53%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 125 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2030 Future Background PM Peak Hour

| | | |
|---|----------------------------------|---------------------|
| Maximum v/c Ratio: 1.49 | Intersection Signal Delay: 166.2 | Intersection LOS: F |
| Intersection Capacity Utilization 113.9% | ICU Level of Service H | |
| Analysis Period (min) 15 | | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | | |
| Queue shown is maximum after two cycles. | | |
| # 95th percentile volume exceeds capacity, queue may be longer. | | |
| Queue shown is maximum after two cycles. | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |

Splits and Phases: 1: Strandherd & Dealership/Kennevale



Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2030 Future Background PM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|--------|--------|---------|-------|-------|-------|--------|-------|-------|-------|-------|-----|
| Lane Configurations | ↔ | ↕ | ↕ | ↔ | ↕ | ↕ | ↔ | ↕ | ↕ | ↔ | ↕ | ↕ |
| Traffic Volume (vph) | 322 | 1600 | 1044 | 114 | 1075 | 65 | 693 | 34 | 107 | 52 | 49 | 122 |
| Future Volume (vph) | 322 | 1600 | 1044 | 114 | 1075 | 65 | 693 | 34 | 107 | 52 | 49 | 122 |
| Satd. Flow (prot) | 1605 | 3241 | 1436 | 1621 | 3210 | 1436 | 2969 | 1706 | 1309 | 1503 | 1472 | 0 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1605 | 3241 | 1436 | 1621 | 3210 | 1436 | 2969 | 1706 | 1309 | 1503 | 1472 | 0 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 322 | 1600 | 1044 | 114 | 1075 | 65 | 693 | 34 | 107 | 52 | 171 | 0 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Detector Phase | 5 | 2 | 2 | 1 | 6 | 6 | 3 | 8 | 8 | 7 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | |
| Minimum Split (s) | 11.6 | 33.6 | 33.6 | 11.6 | 33.6 | 33.6 | 11.7 | 31.7 | 31.7 | 11.7 | 16.7 | |
| Total Split (s) | 21.0 | 60.0 | 60.0 | 14.0 | 53.0 | 53.0 | 22.0 | 33.0 | 33.0 | 13.0 | 24.0 | |
| Total Split (%) | 17.5% | 50.0% | 50.0% | 11.7% | 44.2% | 44.2% | 18.3% | 27.5% | 27.5% | 10.8% | 20.0% | |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | |
| All-Red Time (s) | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 3.4 | 3.4 | 3.4 | 3.4 | 3.4 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | |
| Lead/Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 15.3 | 53.4 | 53.4 | 8.3 | 46.4 | 46.4 | 15.3 | 28.0 | 28.0 | 6.3 | 16.4 | |
| Actuated g/C Ratio | 0.13 | 0.44 | 0.44 | 0.07 | 0.39 | 0.39 | 0.13 | 0.23 | 0.23 | 0.05 | 0.14 | |
| v/c Ratio | 1.58 | 1.11 | 1.63 | 1.03 | 0.87 | 0.12 | 1.83 | 0.09 | 0.35 | 0.67 | 0.85 | |
| Control Delay | 305.9 | 69.4 | 306.3 | 148.6 | 42.7 | 24.5 | 415.6 | 38.2 | 43.4 | 94.2 | 84.5 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 305.9 | 69.4 | 306.3 | 148.6 | 42.7 | 24.5 | 415.6 | 38.2 | 43.4 | 94.2 | 84.5 | |
| LOS | F | E | F | F | D | C | F | D | D | F | F | |
| Approach Delay | | 178.5 | | | 51.4 | | | 352.5 | | | 86.8 | |
| Approach LOS | | F | | | D | | | F | | | F | |
| Queue Length 50th (m) | ~110.4 | ~219.2 | ~347.4 | ~31.0 | 119.8 | 9.6 | ~125.5 | 6.4 | 21.3 | 12.1 | 39.0 | |
| Queue Length 95th (m) | m#72.1 | m#48.3 | m#210.7 | #67.2 | 148.5 | 19.1 | #161.4 | 14.9 | 38.1 | #31.7 | #74.4 | |
| Internal Link Dist (m) | | 1040.6 | | | 313.4 | | | 275.6 | | | 103.1 | |
| Turn Bay Length (m) | 90.0 | | 90.0 | 50.0 | | 27.5 | 160.0 | | 57.5 | 17.0 | | |
| Base Capacity (vph) | 204 | 1442 | 639 | 111 | 1241 | 555 | 378 | 398 | 305 | 78 | 212 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 1.58 | 1.11 | 1.63 | 1.03 | 0.87 | 0.12 | 1.83 | 0.09 | 0.35 | 0.67 | 0.81 | |

| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 120 |
| Actuated Cycle Length: | 120 |
| Offset: | 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green |
| Natural Cycle: | 130 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2030 Future Background PM Peak Hour

| | |
|---|--------|
| Maximum v/c Ratio: | 1.83 |
| Intersection Signal Delay: | 171.9 |
| Intersection LOS: | F |
| Intersection Capacity Utilization: | 107.0% |
| ICU Level of Service: | G |
| Analysis Period (min): | 15 |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2030 Future Background PM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-----|-------|-------|-----|-------|--------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 30 | 0 | 2 | 8 | 0 | 32 | 3 | 304 | 12 | 49 | 509 | 42 |
| Future Volume (vph) | 30 | 0 | 2 | 8 | 0 | 32 | 3 | 304 | 12 | 49 | 509 | 42 |
| Satd. Flow (prot) | 1621 | 1450 | 0 | 1621 | 1450 | 0 | 1621 | 1696 | 0 | 1621 | 1706 | 1450 |
| Fit Permitted | 0.736 | | | 0.757 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1256 | 1450 | 0 | 1291 | 1450 | 0 | 1621 | 1696 | 0 | 1621 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 30 | 2 | 0 | 8 | 32 | 0 | 3 | 316 | 0 | 49 | 509 | 42 |
| Turn Type | Perm | NA | | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | | | | | | | 6 |
| Detector Phase | 4 | 4 | | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 25.6 | | 11.6 | 25.6 | 25.6 |
| Total Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 42.8 | | 13.9 | 45.1 | 45.1 |
| Total Split (%) | 37.0% | 37.0% | | 37.0% | 37.0% | | 12.9% | 47.6% | | 15.4% | 50.1% | 50.1% |
| Yellow Time (s) | 3.3 | 3.3 | | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.0 | 3.0 | | 3.0 | 3.0 | | 2.0 | 2.0 | | 2.0 | 2.0 | 2.0 |
| Lost Time Adjust (s) | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.3 | 6.3 | | 6.3 | 6.3 | | 6.6 | 6.6 | | 6.6 | 6.6 | 6.6 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 13.4 | 13.4 | | 13.4 | 13.4 | | 5.5 | 64.0 | | 7.4 | 70.5 | 70.5 |
| Actuated g/C Ratio | 0.15 | 0.15 | | 0.15 | 0.15 | | 0.06 | 0.71 | | 0.08 | 0.78 | 0.78 |
| v/c Ratio | 0.16 | 0.01 | | 0.04 | 0.15 | | 0.03 | 0.26 | | 0.37 | 0.38 | 0.04 |
| Control Delay | 32.5 | 28.0 | | 29.0 | 32.0 | | 40.7 | 11.4 | | 42.4 | 10.6 | 11.5 |
| Queue Delay | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 32.5 | 28.0 | | 29.0 | 32.0 | | 40.7 | 11.4 | | 42.4 | 10.6 | 11.5 |
| LOS | C | C | | C | C | | D | B | | D | B | B |
| Approach Delay | | 32.2 | | | 31.4 | | | 11.7 | | | 13.3 | |
| Approach LOS | | C | | | C | | | B | | | B | |
| Queue Length 50th (m) | 4.7 | 0.3 | | 1.3 | 5.1 | | 0.5 | 25.6 | | 8.0 | 25.7 | 1.5 |
| Queue Length 95th (m) | 9.9 | 1.8 | | 4.0 | 10.3 | | 3.2 | 61.2 | | 20.4 | 79.4 | 11.6 |
| Internal Link Dist (m) | | 154.2 | | | 129.4 | | | 1276.6 | | | 273.4 | |
| Turn Bay Length (m) | 9.3 | | | 9.3 | | | 84.0 | | | 84.5 | | 83.0 |
| Base Capacity (vph) | 376 | 435 | | 387 | 435 | | 99 | 1205 | | 141 | 1337 | 1136 |
| Starvation Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.08 | 0.00 | | 0.02 | 0.07 | | 0.03 | 0.26 | | 0.35 | 0.38 | 0.04 |


| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 90 | | | | | | | | | | | | |
| Actuated Cycle Length: 90 | | | | | | | | | | | | |
| Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 80 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2030 Future Background PM Peak Hour

| | |
|---|------------------------|
| Maximum v/c Ratio: 0.38 | Intersection LOS: B |
| Intersection Signal Delay: 14.1 | ICU Level of Service B |
| Intersection Capacity Utilization 57.1% | |
| Analysis Period (min) 15 | |

Splits and Phases: 9: Borriskane & Conservancy Way



Lanes, Volumes, Timings
10: Borrisokane & New Collector

Caivan Conservancy West
2030 Future Background PM Peak Hour

| Lane Group | EBL | EBR | NBL | NBT | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|-------|
| Lane Configurations | ↖ | ↗ | ↖ | ↖ | ↖ | ↖ |
| Traffic Volume (vph) | 31 | 1 | 2 | 364 | 599 | 43 |
| Future Volume (vph) | 31 | 1 | 2 | 364 | 599 | 43 |
| Satd. Flow (prot) | 1621 | 1450 | 1621 | 1706 | 1706 | 1450 |
| Fit Permitted | 0.950 | | 0.413 | | | |
| Satd. Flow (perm) | 1621 | 1450 | 705 | 1706 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | |
| Lane Group Flow (vph) | 31 | 1 | 2 | 364 | 599 | 43 |
| Turn Type | Perm | Perm | Perm | NA | NA | Perm |
| Protected Phases | | | | 2 | 6 | |
| Permitted Phases | 4 | 4 | 2 | | | 6 |
| Detector Phase | 4 | 4 | 2 | 2 | 6 | 6 |
| Switch Phase | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 |
| Minimum Split (s) | 28.3 | 28.3 | 23.6 | 23.6 | 23.6 | 23.6 |
| Total Split (s) | 29.0 | 29.0 | 61.0 | 61.0 | 61.0 | 61.0 |
| Total Split (%) | 32.2% | 32.2% | 67.8% | 67.8% | 67.8% | 67.8% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 |
| All-Red Time (s) | 2.0 | 2.0 | 2.3 | 2.3 | 2.3 | 2.3 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 5.3 | 5.3 | 5.6 | 5.6 | 5.6 | 5.6 |
| Lead/Lag | | | | | | |
| Lead-Lag Optimize? | | | | | | |
| Recall Mode | None | None | C-Max | C-Max | C-Max | C-Max |
| Act Effct Green (s) | 12.6 | 12.6 | 74.9 | 74.9 | 74.9 | 74.9 |
| Actuated g/C Ratio | 0.14 | 0.14 | 0.83 | 0.83 | 0.83 | 0.83 |
| v/c Ratio | 0.14 | 0.00 | 0.00 | 0.26 | 0.42 | 0.04 |
| Control Delay | 33.0 | 29.0 | 3.5 | 2.9 | 5.8 | 4.2 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Delay | 33.0 | 29.0 | 3.5 | 2.9 | 5.8 | 4.2 |
| LOS | C | C | A | A | A | A |
| Approach Delay | 32.9 | | | 2.9 | 5.7 | |
| Approach LOS | C | | | A | A | |
| Queue Length 50th (m) | 4.9 | 0.2 | 0.1 | 13.2 | 28.8 | 1.4 |
| Queue Length 95th (m) | 10.7 | 1.3 | m0.3 | 17.6 | 81.5 | 6.3 |
| Internal Link Dist (m) | 209.1 | | | 273.4 | 275.6 | |
| Turn Bay Length (m) | 38.5 | | 27.5 | | | |
| Base Capacity (vph) | 426 | 381 | 586 | 1419 | 1419 | 1206 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.07 | 0.00 | 0.00 | 0.26 | 0.42 | 0.04 |


| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 90 |
| Actuated Cycle Length: | 90 |
| Offset: | 0 (0%), Referenced to phase 2:NBL and 6:SBT, Start of Green |
| Natural Cycle: | 60 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
10: Borrisokane & New Collector

Caivan Conservancy West
2030 Future Background PM Peak Hour

| | | |
|---|--------------------------------|---------------------|
| Maximum v/c Ratio: 0.42 | Intersection Signal Delay: 5.5 | Intersection LOS: A |
| Intersection Capacity Utilization 50.7% | ICU Level of Service A | |
| Analysis Period (min) 15 | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |

Splits and Phases: 10: Borrisokane & New Collector



Appendix F

Synchro Intersection Worksheets – 2035 Future Background Conditions

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2035 Future Background AM Peak Hour


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|------|---------------|--------|-----|-------|--------|-------|
| Lane Configurations | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ |
| Traffic Volume (vph) | 72 | 19 | 47 | 100 | 108 | 113 | 219 | 2746 | 86 | 53 | 1320 | 307 |
| Future Volume (vph) | 72 | 19 | 47 | 100 | 108 | 113 | 219 | 2746 | 86 | 53 | 1320 | 307 |
| Satd. Flow (prot) | 1243 | 1160 | 1450 | 1589 | 1353 | 0 | 3144 | 3220 | 0 | 1476 | 3090 | 1395 |
| Fit Permitted | 0.460 | | | 0.745 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 602 | 1160 | 1431 | 1245 | 1353 | 0 | 3144 | 3220 | 0 | 1476 | 3090 | 1395 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 72 | 19 | 47 | 100 | 221 | 0 | 219 | 2832 | 0 | 53 | 1320 | 307 |
| Turn Type | Perm | NA | Perm | Perm | NA | Prot | NA | Prot | NA | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | 4 | 8 | | | 5 | 2 | | 1 | 6 | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 39.9 | 39.9 | 39.9 | 32.9 | 32.9 | | 11.4 | 30.4 | | 11.4 | 39.4 | 39.4 |
| Total Split (s) | 41.0 | 41.0 | 41.0 | 41.0 | 41.0 | | 17.4 | 66.6 | | 12.4 | 61.6 | 61.6 |
| Total Split (%) | 34.2% | 34.2% | 34.2% | 34.2% | 34.2% | | 14.5% | 55.5% | | 10.3% | 51.3% | 51.3% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.6 | 3.6 | 3.6 | 3.6 | 3.6 | | 1.8 | 1.8 | | 1.8 | 1.8 | 1.8 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.9 | 6.9 | 6.9 | 6.9 | 6.9 | | 6.4 | 6.4 | | 6.4 | 6.4 | 6.4 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 24.8 | 24.8 | 24.8 | 24.8 | 24.8 | | 12.7 | 69.3 | | 8.8 | 62.8 | 62.8 |
| Actuated g/C Ratio | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | | 0.11 | 0.58 | | 0.07 | 0.52 | 0.52 |
| v/c Ratio | 0.58 | 0.08 | 0.16 | 0.39 | 0.79 | | 0.66 | 1.52 | | 0.50 | 0.82 | 0.42 |
| Control Delay | 60.0 | 35.6 | 37.4 | 43.8 | 64.3 | | 66.8 | 255.1 | | 69.4 | 30.5 | 21.4 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 60.0 | 35.6 | 37.4 | 43.8 | 64.3 | | 66.8 | 255.1 | | 69.4 | 30.5 | 21.4 |
| LOS | E | D | D | D | E | | E | F | | E | C | C |
| Approach Delay | | 49.0 | | | 57.9 | | | 241.6 | | | 30.1 | |
| Approach LOS | | D | | | E | | | F | | | C | |
| Queue Length 50th (m) | 15.2 | 3.6 | 9.0 | 20.2 | 49.1 | | 25.0 | ~512.4 | | 11.9 | 132.7 | 43.1 |
| Queue Length 95th (m) | 28.6 | 9.1 | 17.6 | 33.2 | 70.2 | | m15.5 m#258.6 | | | #32.4 | #196.3 | 73.5 |
| Internal Link Dist (m) | | 172.9 | | | 177.4 | | | 1040.6 | | | 345.0 | |
| Turn Bay Length (m) | 70.0 | | 150.0 | 50.0 | | | 130.0 | | | 180.0 | | 60.0 |
| Base Capacity (vph) | 171 | 329 | 406 | 353 | 384 | | 336 | 1859 | | 107 | 1618 | 730 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.42 | 0.06 | 0.12 | 0.28 | 0.58 | | 0.65 | 1.52 | | 0.50 | 0.82 | 0.42 |

| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 69 (58%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 125 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2035 Future Background AM Peak Hour

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.52 | Intersection LOS: F |
| Intersection Signal Delay: 156.7 | ICU Level of Service H |
| Intersection Capacity Utilization 131.0% | |
| Analysis Period (min) 15 | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2035 Future Background AM Peak Hour


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|--------|--------|---------|-------|--------|-------|--------|-------|-------|-------|-------|-----|
| Lane Configurations | ↔ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ |
| Traffic Volume (vph) | 117 | 798 | 519 | 63 | 1663 | 52 | 1060 | 49 | 114 | 69 | 23 | 230 |
| Future Volume (vph) | 117 | 798 | 519 | 63 | 1663 | 52 | 1060 | 49 | 114 | 69 | 23 | 230 |
| Satd. Flow (prot) | 1589 | 3119 | 1332 | 1621 | 3210 | 1345 | 3113 | 1673 | 1450 | 1605 | 1474 | 0 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1589 | 3119 | 1332 | 1621 | 3210 | 1345 | 3113 | 1673 | 1450 | 1605 | 1474 | 0 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 117 | 798 | 519 | 63 | 1663 | 52 | 1060 | 49 | 114 | 69 | 253 | 0 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Detector Phase | 5 | 2 | 2 | 1 | 6 | 6 | 3 | 8 | 8 | 7 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | |
| Minimum Split (s) | 11.6 | 33.6 | 33.6 | 11.6 | 33.6 | 33.6 | 11.7 | 33.7 | 33.7 | 11.7 | 33.7 | |
| Total Split (s) | 13.0 | 48.7 | 48.7 | 11.6 | 47.3 | 47.3 | 26.0 | 41.8 | 41.8 | 17.9 | 33.7 | |
| Total Split (%) | 10.8% | 40.6% | 40.6% | 9.7% | 39.4% | 39.4% | 21.7% | 34.8% | 34.8% | 14.9% | 28.1% | |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | |
| All-Red Time (s) | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 3.4 | 3.4 | 3.4 | 3.4 | 3.4 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | |
| Lead/Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 9.3 | 43.2 | 43.2 | 6.8 | 40.7 | 40.7 | 19.3 | 36.4 | 36.4 | 9.6 | 24.1 | |
| Actuated g/C Ratio | 0.08 | 0.36 | 0.36 | 0.06 | 0.34 | 0.34 | 0.16 | 0.30 | 0.30 | 0.08 | 0.20 | |
| v/c Ratio | 0.95 | 0.71 | 1.08 | 0.69 | 1.53 | 0.11 | 2.12 | 0.10 | 0.26 | 0.54 | 0.86 | |
| Control Delay | 124.1 | 22.3 | 83.6 | 92.5 | 273.0 | 28.2 | 536.9 | 31.9 | 34.4 | 68.3 | 72.2 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 124.1 | 22.3 | 83.6 | 92.5 | 273.0 | 28.2 | 536.9 | 31.9 | 34.4 | 68.3 | 72.2 | |
| LOS | F | C | F | F | F | C | F | C | C | E | E | |
| Approach Delay | | 52.8 | | | 259.5 | | | 469.8 | | | 71.4 | |
| Approach LOS | | D | | | F | | | F | | | E | |
| Queue Length 50th (m) | ~33.7 | 50.8 | ~139.2 | 14.8 | ~284.6 | 8.3 | ~201.8 | 8.3 | 20.4 | 15.5 | 55.9 | |
| Queue Length 95th (m) | m#52.9 | 66.6 | m#192.1 | #42.7 | #326.4 | 17.4 | #241.1 | 17.7 | 35.7 | 30.3 | #92.0 | |
| Internal Link Dist (m) | | 1040.6 | | | 387.1 | | | 275.6 | | | 103.1 | |
| Turn Bay Length (m) | 90.0 | | 90.0 | 50.0 | | 27.5 | 160.0 | | 57.5 | 17.0 | | |
| Base Capacity (vph) | 123 | 1124 | 480 | 91 | 1088 | 456 | 500 | 512 | 444 | 149 | 331 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.95 | 0.71 | 1.08 | 0.69 | 1.53 | 0.11 | 2.12 | 0.10 | 0.26 | 0.46 | 0.76 | |

| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 120 |
| Actuated Cycle Length: | 120 |
| Offset: | 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green |
| Natural Cycle: | 125 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2035 Future Background AM Peak Hour

| | |
|---|--------|
| Maximum v/c Ratio: | 2.12 |
| Intersection Signal Delay: | 238.5 |
| Intersection LOS: | F |
| Intersection Capacity Utilization: | 125.7% |
| ICU Level of Service: | H |
| Analysis Period (min): | 15 |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2035 Future Background AM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-----|-------|-------|-----|-------|-------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 46 | 0 | 3 | 12 | 0 | 49 | 1 | 413 | 5 | 22 | 181 | 20 |
| Future Volume (vph) | 46 | 0 | 3 | 12 | 0 | 49 | 1 | 413 | 5 | 22 | 181 | 20 |
| Satd. Flow (prot) | 1621 | 1450 | 0 | 1621 | 1450 | 0 | 1621 | 1702 | 0 | 1621 | 1706 | 1450 |
| Fit Permitted | 0.725 | | | 0.756 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1237 | 1450 | 0 | 1290 | 1450 | 0 | 1621 | 1702 | 0 | 1621 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 46 | 3 | 0 | 12 | 49 | 0 | 1 | 418 | 0 | 22 | 181 | 20 |
| Turn Type | Perm | NA | | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | | | | | | | 6 |
| Detector Phase | 4 | 4 | | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 25.6 | | 11.6 | 25.6 | 25.6 |
| Total Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 12.0 | 43.7 | | 13.0 | 44.7 | 44.7 |
| Total Split (%) | 37.0% | 37.0% | | 37.0% | 37.0% | | 13.3% | 48.6% | | 14.4% | 49.7% | 49.7% |
| Yellow Time (s) | 3.3 | 3.3 | | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.0 | 3.0 | | 3.0 | 3.0 | | 2.0 | 2.0 | | 2.0 | 2.0 | 2.0 |
| Lost Time Adjust (s) | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.3 | 6.3 | | 6.3 | 6.3 | | 6.6 | 6.6 | | 6.6 | 6.6 | 6.6 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 13.5 | 13.5 | | 13.5 | 13.5 | | 5.5 | 67.4 | | 6.4 | 70.4 | 70.4 |
| Actuated g/C Ratio | 0.15 | 0.15 | | 0.15 | 0.15 | | 0.06 | 0.75 | | 0.07 | 0.78 | 0.78 |
| v/c Ratio | 0.25 | 0.01 | | 0.06 | 0.23 | | 0.01 | 0.33 | | 0.19 | 0.14 | 0.02 |
| Control Delay | 34.7 | 28.0 | | 29.6 | 33.8 | | 40.0 | 10.6 | | 43.2 | 6.4 | 8.2 |
| Queue Delay | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 34.7 | 28.0 | | 29.6 | 33.8 | | 40.0 | 10.6 | | 43.2 | 6.4 | 8.2 |
| LOS | C | C | | C | C | | D | B | | D | A | A |
| Approach Delay | | 34.3 | | | 33.0 | | | 10.7 | | | 10.2 | |
| Approach LOS | | C | | | C | | | B | | | B | |
| Queue Length 50th (m) | 7.4 | 0.5 | | 1.9 | 7.8 | | 0.2 | 19.6 | | 3.6 | 7.2 | 0.7 |
| Queue Length 95th (m) | 13.7 | 2.3 | | 5.3 | 14.1 | | 1.7 | 83.3 | | 12.1 | 21.0 | 4.4 |
| Internal Link Dist (m) | | 145.0 | | | 184.4 | | | 650.0 | | | 273.4 | |
| Turn Bay Length (m) | 9.3 | | | 9.3 | | | 84.0 | | | 84.5 | | 83.0 |
| Base Capacity (vph) | 371 | 435 | | 387 | 435 | | 99 | 1274 | | 120 | 1334 | 1134 |
| Starvation Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.12 | 0.01 | | 0.03 | 0.11 | | 0.01 | 0.33 | | 0.18 | 0.14 | 0.02 |


| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 90 |
| Actuated Cycle Length: | 90 |
| Offset: | 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green |
| Natural Cycle: | 75 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2035 Future Background AM Peak Hour

| | | |
|---|---------------------------------|---------------------|
| Maximum v/c Ratio: 0.33 | Intersection Signal Delay: 13.9 | Intersection LOS: B |
| Intersection Capacity Utilization 43.4% | ICU Level of Service A | |
| Analysis Period (min) 15 | | |

Splits and Phases: 9: Borriskane & Conservancy Way



Lanes, Volumes, Timings
10: Borrisokane & New Collector/BRT

Caivan Conservancy West
2035 Future Background AM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|-----|-------|-------|-----|-------|-------|-------|
| Lane Configurations | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ |
| Traffic Volume (vph) | 47 | 4 | 2 | 0 | 4 | 0 | 1 | 507 | 0 | 0 | 221 | 20 |
| Future Volume (vph) | 47 | 4 | 2 | 0 | 4 | 0 | 1 | 507 | 0 | 0 | 221 | 20 |
| Satd. Flow (prot) | 1621 | 1706 | 1450 | 0 | 1706 | 0 | 1621 | 1706 | 0 | 0 | 1706 | 1450 |
| Fit Permitted | 0.755 | | | | | | 0.620 | | | | | |
| Satd. Flow (perm) | 1288 | 1706 | 1450 | 0 | 1706 | 0 | 1058 | 1706 | 0 | 0 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 47 | 4 | 2 | 0 | 4 | 0 | 1 | 507 | 0 | 0 | 221 | 20 |
| Turn Type | Perm | NA | Perm | | NA | | Perm | NA | | NA | Perm | |
| Protected Phases | | 4 | | | 8 | | | 2 | | | 6 | |
| Permitted Phases | 4 | | 4 | 8 | | | 2 | | | 6 | | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 2 | 2 | | 6 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 | 10.0 | 10.0 |
| Minimum Split (s) | 31.8 | 31.8 | 31.8 | 31.8 | 31.8 | | 31.8 | 31.8 | | 31.8 | 31.8 | 31.8 |
| Total Split (s) | 33.0 | 33.0 | 33.0 | 33.0 | 33.0 | | 57.0 | 57.0 | | 57.0 | 57.0 | 57.0 |
| Total Split (%) | 36.7% | 36.7% | 36.7% | 36.7% | 36.7% | | 63.3% | 63.3% | | 63.3% | 63.3% | 63.3% |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | | 3.3 | 3.3 | | 3.3 | 3.3 | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 | 3.5 | 3.5 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | | 6.8 | 6.8 | | 6.8 | 6.8 | 6.8 |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | C-Max | C-Max | | C-Max | C-Max | C-Max |
| Act Effct Green (s) | 12.8 | 12.8 | 12.8 | | 11.0 | | 73.0 | 73.0 | | 73.0 | 73.0 | 73.0 |
| Actuated g/C Ratio | 0.14 | 0.14 | 0.14 | | 0.12 | | 0.81 | 0.81 | | 0.81 | 0.81 | 0.81 |
| v/c Ratio | 0.26 | 0.02 | 0.01 | | 0.02 | | 0.00 | 0.37 | | 0.16 | 0.02 | |
| Control Delay | 35.8 | 29.2 | 29.0 | | 29.5 | | 5.0 | 4.3 | | 4.9 | 5.5 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | |
| Total Delay | 35.8 | 29.2 | 29.0 | | 29.5 | | 5.0 | 4.3 | | 4.9 | 5.5 | |
| LOS | D | C | C | | C | | A | A | | A | A | A |
| Approach Delay | | 35.1 | | | 29.5 | | | 4.3 | | | 5.0 | |
| Approach LOS | | D | | | C | | | A | | | A | |
| Queue Length 50th (m) | 7.5 | 0.6 | 0.3 | | 0.6 | | 0.0 | 25.1 | | 9.3 | 0.7 | |
| Queue Length 95th (m) | 14.5 | 2.9 | 1.9 | | 2.9 | | m0.1 | 32.7 | | 27.7 | 4.1 | |
| Internal Link Dist (m) | | 113.8 | | | 68.5 | | | 273.4 | | | 275.6 | |
| Turn Bay Length (m) | 38.5 | | | | | | | 27.5 | | | | |
| Base Capacity (vph) | 374 | 496 | 422 | | 496 | | 858 | 1383 | | 1383 | 1176 | |
| Starvation Cap Reductn | 0 | 0 | 0 | | 0 | | 0 | 0 | | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | | 0 | | 0 | 0 | | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | | 0 | | 0 | 0 | | 0 | 0 | |
| Reduced v/c Ratio | 0.13 | 0.01 | 0.00 | | 0.01 | | 0.00 | 0.37 | | 0.16 | 0.02 | |


| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 90 | | | | | | | | | | | | |
| Actuated Cycle Length: 90 | | | | | | | | | | | | |
| Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SRTL, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 65 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
10: Borrisokane & New Collector/BRT

Caivan Conservancy West
2035 Future Background AM Peak Hour

| | | |
|---|--------------------------------|---------------------|
| Maximum v/c Ratio: 0.37 | Intersection Signal Delay: 6.6 | Intersection LOS: A |
| Intersection Capacity Utilization 57.7% | ICU Level of Service B | |
| Analysis Period (min) 15 | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |

Splits and Phases: 10: Borrisokane & New Collector/BRT



Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2035 Future Background PM Peak Hour


| | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|--------|-------|-------|-------|-------|-----|--------------|--------|-----|-------|--------|-------|
| Lane Configurations | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ |
| Traffic Volume (vph) | 275 | 96 | 188 | 128 | 26 | 92 | 66 | 1858 | 132 | 85 | 2701 | 108 |
| Future Volume (vph) | 275 | 96 | 188 | 128 | 26 | 92 | 66 | 1858 | 132 | 85 | 2701 | 108 |
| Satd. Flow (prot) | 1605 | 1706 | 1450 | 1517 | 1440 | 0 | 3144 | 3174 | 0 | 1589 | 3241 | 1450 |
| Fit Permitted | 0.681 | | | 0.695 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1150 | 1706 | 1431 | 1108 | 1440 | 0 | 3144 | 3174 | 0 | 1589 | 3241 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 275 | 96 | 188 | 128 | 118 | 0 | 66 | 1990 | 0 | 85 | 2701 | 108 |
| Turn Type | Perm | NA | Perm | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | 4 | 8 | | | 5 | 2 | | 1 | 6 | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 39.9 | 39.9 | 39.9 | 32.9 | 32.9 | | 11.4 | 30.4 | | 11.4 | 39.4 | 39.4 |
| Total Split (s) | 39.9 | 39.9 | 39.9 | 39.9 | 39.9 | | 11.4 | 68.1 | | 12.0 | 68.7 | 68.7 |
| Total Split (%) | 33.3% | 33.3% | 33.3% | 33.3% | 33.3% | | 9.5% | 56.8% | | 10.0% | 57.3% | 57.3% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.6 | 3.6 | 3.6 | 3.6 | 3.6 | | 1.8 | 1.8 | | 1.8 | 1.8 | 1.8 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.9 | 6.9 | 6.9 | 6.9 | 6.9 | | 6.4 | 6.4 | | 6.4 | 6.4 | 6.4 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 31.0 | 31.0 | 31.0 | 31.0 | 31.0 | | 5.5 | 61.7 | | 7.6 | 66.2 | 66.2 |
| Actuated g/C Ratio | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | | 0.05 | 0.51 | | 0.06 | 0.55 | 0.55 |
| v/c Ratio | 0.93 | 0.22 | 0.51 | 0.45 | 0.32 | | 0.46 | 1.22 | | 0.85 | 1.51 | 0.14 |
| Control Delay | 79.9 | 35.6 | 42.9 | 42.3 | 37.8 | | 74.3 | 117.5 | | 113.1 | 257.6 | 15.1 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 79.9 | 35.6 | 42.9 | 42.3 | 37.8 | | 74.3 | 117.5 | | 113.1 | 257.6 | 15.1 |
| LOS | E | D | D | D | D | | E | F | | F | F | B |
| Approach Delay | | 59.8 | | | 40.1 | | | 116.1 | | | 244.3 | |
| Approach LOS | | E | | | D | | | F | | | F | |
| Queue Length 50th (m) | 61.0 | 17.2 | 36.5 | 24.4 | 21.7 | | 7.4 | ~304.2 | | ~23.2 | ~473.2 | 12.6 |
| Queue Length 95th (m) | #108.3 | 31.1 | 59.0 | 42.9 | 37.9 | | m6.9 m#218.2 | | | #55.1 | #511.7 | 22.4 |
| Internal Link Dist (m) | | 172.9 | | | 177.4 | | | 1040.6 | | | 345.0 | |
| Turn Bay Length (m) | 70.0 | | 150.0 | 50.0 | | | 130.0 | | | 180.0 | | 60.0 |
| Base Capacity (vph) | 316 | 469 | 393 | 304 | 396 | | 143 | 1631 | | 100 | 1788 | 800 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.87 | 0.20 | 0.48 | 0.42 | 0.30 | | 0.46 | 1.22 | | 0.85 | 1.51 | 0.14 |

| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 64 (53%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 125 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2035 Future Background PM Peak Hour

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.51 | Intersection LOS: F |
| Intersection Signal Delay: 171.8 | ICU Level of Service H |
| Intersection Capacity Utilization 116.8% | |
| Analysis Period (min) 15 | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2035 Future Background PM Peak Hour


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|--------|--------|---------|-------|--------|-------|--------|-------|-------|-------|-------|-----|
| Lane Configurations | ↔ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ |
| Traffic Volume (vph) | 322 | 1673 | 1077 | 114 | 1128 | 65 | 710 | 34 | 107 | 52 | 49 | 122 |
| Future Volume (vph) | 322 | 1673 | 1077 | 114 | 1128 | 65 | 710 | 34 | 107 | 52 | 49 | 122 |
| Satd. Flow (prot) | 1605 | 3241 | 1436 | 1621 | 3210 | 1436 | 2969 | 1706 | 1309 | 1503 | 1472 | 0 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1605 | 3241 | 1436 | 1621 | 3210 | 1436 | 2969 | 1706 | 1309 | 1503 | 1472 | 0 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 322 | 1673 | 1077 | 114 | 1128 | 65 | 710 | 34 | 107 | 52 | 171 | 0 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | |
| Protected Phases | 5 | 2 | 2 | 1 | 6 | 6 | 3 | 8 | 8 | 7 | 4 | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Detector Phase | 5 | 2 | 2 | 1 | 6 | 6 | 3 | 8 | 8 | 7 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | |
| Minimum Split (s) | 11.6 | 33.6 | 33.6 | 11.6 | 33.6 | 33.6 | 11.7 | 34.0 | 34.0 | 11.7 | 33.7 | |
| Total Split (s) | 17.0 | 55.3 | 55.3 | 12.0 | 50.3 | 50.3 | 19.0 | 35.5 | 35.5 | 17.2 | 33.7 | |
| Total Split (%) | 14.2% | 46.1% | 46.1% | 10.0% | 41.9% | 41.9% | 15.8% | 29.6% | 29.6% | 14.3% | 28.1% | |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | |
| All-Red Time (s) | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 3.4 | 3.4 | 3.4 | 3.4 | 3.4 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | |
| Lead/Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 18.1 | 48.7 | 48.7 | 13.1 | 43.7 | 43.7 | 12.3 | 25.2 | 25.2 | 8.8 | 19.3 | |
| Actuated g/C Ratio | 0.15 | 0.41 | 0.41 | 0.11 | 0.36 | 0.36 | 0.10 | 0.21 | 0.21 | 0.07 | 0.16 | |
| v/c Ratio | 1.33 | 1.27 | 1.85 | 0.64 | 0.97 | 0.12 | 2.34 | 0.09 | 0.39 | 0.48 | 0.72 | |
| Control Delay | 200.4 | 147.3 | 404.9 | 70.2 | 57.1 | 26.3 | 635.7 | 39.1 | 45.8 | 67.2 | 64.5 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 200.4 | 147.3 | 404.9 | 70.2 | 57.1 | 26.3 | 635.7 | 39.1 | 45.8 | 67.2 | 64.5 | |
| LOS | F | F | F | E | E | C | F | D | D | E | E | |
| Approach Delay | | 243.2 | | | 56.7 | | | 537.7 | | | 65.1 | |
| Approach LOS | | F | | | E | | | F | | | E | |
| Queue Length 50th (m) | ~98.1 | ~255.0 | ~377.9 | 25.8 | 134.1 | 10.0 | ~139.0 | 6.7 | 22.3 | 11.7 | 38.2 | |
| Queue Length 95th (m) | m#83.8 | m#94.2 | m#232.0 | #73.8 | #179.0 | 19.9 | #175.2 | 14.5 | 37.0 | 24.4 | 57.2 | |
| Internal Link Dist (m) | | 1040.6 | | | 371.1 | | | 275.6 | | | 103.1 | |
| Turn Bay Length (m) | 90.0 | | 90.0 | 50.0 | | 27.5 | 160.0 | | 57.5 | 17.0 | | |
| Base Capacity (vph) | 242 | 1315 | 582 | 177 | 1168 | 522 | 304 | 415 | 318 | 131 | 331 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 1.33 | 1.27 | 1.85 | 0.64 | 0.97 | 0.12 | 2.34 | 0.08 | 0.34 | 0.40 | 0.52 | |

| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 120 |
| Actuated Cycle Length: | 120 |
| Offset: | 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green |
| Natural Cycle: | 125 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2035 Future Background PM Peak Hour

| | |
|---|--------|
| Maximum v/c Ratio: | 2.34 |
| Intersection Signal Delay: | 237.2 |
| Intersection LOS: | F |
| Intersection Capacity Utilization: | 109.7% |
| ICU Level of Service: | H |
| Analysis Period (min): | 15 |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2035 Future Background PM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-----|-------|-------|-----|-------|--------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 30 | 0 | 2 | 8 | 0 | 32 | 3 | 255 | 12 | 49 | 426 | 42 |
| Future Volume (vph) | 30 | 0 | 2 | 8 | 0 | 32 | 3 | 255 | 12 | 49 | 426 | 42 |
| Satd. Flow (prot) | 1621 | 1450 | 0 | 1621 | 1450 | 0 | 1621 | 1694 | 0 | 1621 | 1706 | 1450 |
| Fit Permitted | 0.736 | | | 0.757 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1256 | 1450 | 0 | 1291 | 1450 | 0 | 1621 | 1694 | 0 | 1621 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 30 | 2 | 0 | 8 | 32 | 0 | 3 | 267 | 0 | 49 | 426 | 42 |
| Turn Type | Perm | NA | | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | | | | | | | 6 |
| Detector Phase | 4 | 4 | | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 25.6 | | 11.6 | 25.6 | 25.6 |
| Total Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 12.0 | 42.7 | | 14.0 | 44.7 | 44.7 |
| Total Split (%) | 37.0% | 37.0% | | 37.0% | 37.0% | | 13.3% | 47.4% | | 15.6% | 49.7% | 49.7% |
| Yellow Time (s) | 3.3 | 3.3 | | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.0 | 3.0 | | 3.0 | 3.0 | | 2.0 | 2.0 | | 2.0 | 2.0 | 2.0 |
| Lost Time Adjust (s) | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.3 | 6.3 | | 6.3 | 6.3 | | 6.6 | 6.6 | | 6.6 | 6.6 | 6.6 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 13.4 | 13.4 | | 13.4 | 13.4 | | 5.6 | 63.9 | | 7.4 | 70.5 | 70.5 |
| Actuated g/C Ratio | 0.15 | 0.15 | | 0.15 | 0.15 | | 0.06 | 0.71 | | 0.08 | 0.78 | 0.78 |
| v/c Ratio | 0.16 | 0.01 | | 0.04 | 0.15 | | 0.03 | 0.22 | | 0.37 | 0.32 | 0.04 |
| Control Delay | 32.5 | 28.0 | | 29.0 | 32.0 | | 40.3 | 11.1 | | 43.4 | 9.7 | 11.1 |
| Queue Delay | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 32.5 | 28.0 | | 29.0 | 32.0 | | 40.3 | 11.1 | | 43.4 | 9.7 | 11.1 |
| LOS | C | C | | C | C | | D | B | | D | A | B |
| Approach Delay | | 32.2 | | | 31.4 | | | 11.4 | | | 13.0 | |
| Approach LOS | | C | | | C | | | B | | | B | |
| Queue Length 50th (m) | 4.7 | 0.3 | | 1.3 | 5.1 | | 0.5 | 20.9 | | 8.0 | 20.1 | 1.5 |
| Queue Length 95th (m) | 9.9 | 1.8 | | 4.0 | 10.3 | | 3.2 | 51.1 | | 20.6 | 61.6 | 10.4 |
| Internal Link Dist (m) | | 154.2 | | | 129.4 | | | 1276.6 | | | 273.4 | |
| Turn Bay Length (m) | 9.3 | | | 9.3 | | | 84.0 | | | 84.5 | | 83.0 |
| Base Capacity (vph) | 376 | 435 | | 387 | 435 | | 100 | 1203 | | 142 | 1335 | 1135 |
| Starvation Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.08 | 0.00 | | 0.02 | 0.07 | | 0.03 | 0.22 | | 0.35 | 0.32 | 0.04 |

| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 90 | | | | | | | | | | | | |
| Actuated Cycle Length: 90 | | | | | | | | | | | | |
| Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 75 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2035 Future Background PM Peak Hour

| | | |
|---|---------------------------------|---------------------|
| Maximum v/c Ratio: 0.37 | Intersection Signal Delay: 14.1 | Intersection LOS: B |
| Intersection Capacity Utilization 52.5% | ICU Level of Service A | |
| Analysis Period (min) 15 | | |

Splits and Phases: 9: Borriskane & Conservancy Way



Lanes, Volumes, Timings
10: Borrisokane & New Collector/BRT

Caivan Conservancy West
2035 Future Background PM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|------|-------|-------|-----|-------|-------|-------|
| Lane Configurations | ↖ | ↗ | ↘ | ↙ | ↘ | ↗ | ↖ | ↗ | ↘ | ↙ | ↘ | ↗ |
| Traffic Volume (vph) | 31 | 4 | 1 | 0 | 4 | 0 | 2 | 315 | 0 | 0 | 516 | 43 |
| Future Volume (vph) | 31 | 4 | 1 | 0 | 4 | 0 | 2 | 315 | 0 | 0 | 516 | 43 |
| Satd. Flow (prot) | 1621 | 1706 | 1450 | 0 | 1706 | 0 | 1621 | 1706 | 0 | 0 | 1706 | 1450 |
| Fit Permitted | 0.755 | | | | | | 0.458 | | | | | |
| Satd. Flow (perm) | 1288 | 1706 | 1450 | 0 | 1706 | 0 | 781 | 1706 | 0 | 0 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 31 | 4 | 1 | 0 | 4 | 0 | 2 | 315 | 0 | 0 | 516 | 43 |
| Turn Type | Perm | NA | Perm | NA | NA | Perm | NA | NA | NA | NA | Perm | Perm |
| Protected Phases | | 4 | | | 8 | | 2 | 2 | | | 6 | 6 |
| Permitted Phases | 4 | | 4 | 8 | | | 2 | | | 6 | | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 2 | 2 | | 6 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 | 10.0 | 10.0 |
| Minimum Split (s) | 30.8 | 30.8 | 30.8 | 30.8 | 30.8 | | 31.8 | 31.8 | | 31.8 | 31.8 | 31.8 |
| Total Split (s) | 32.0 | 32.0 | 32.0 | 32.0 | 32.0 | | 58.0 | 58.0 | | 58.0 | 58.0 | 58.0 |
| Total Split (%) | 35.6% | 35.6% | 35.6% | 35.6% | 35.6% | | 64.4% | 64.4% | | 64.4% | 64.4% | 64.4% |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | | 3.3 | 3.3 | | 3.3 | 3.3 | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 | 3.5 | 3.5 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | | 6.8 | 6.8 | | 6.8 | 6.8 | 6.8 |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | C-Max | C-Max | | C-Max | C-Max | C-Max |
| Act Effct Green (s) | 12.8 | 12.8 | 12.8 | | 11.0 | | 73.0 | 73.0 | | 73.0 | 73.0 | 73.0 |
| Actuated g/C Ratio | 0.14 | 0.14 | 0.14 | | 0.12 | | 0.81 | 0.81 | | 0.81 | 0.81 | 0.81 |
| v/c Ratio | 0.17 | 0.02 | 0.00 | | 0.02 | | 0.00 | 0.23 | | 0.37 | 0.04 | |
| Control Delay | 33.7 | 29.5 | 28.0 | | 29.5 | | 4.5 | 3.9 | | 6.4 | 5.2 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | |
| Total Delay | 33.7 | 29.5 | 28.0 | | 29.5 | | 4.5 | 3.9 | | 6.4 | 5.2 | |
| LOS | C | C | C | | C | | A | A | | A | A | A |
| Approach Delay | | 33.1 | | | 29.5 | | | 3.9 | | | 6.3 | |
| Approach LOS | | C | | | C | | | A | | | A | |
| Queue Length 50th (m) | 4.9 | 0.6 | 0.2 | | 0.6 | | 0.1 | 15.0 | | 27.1 | 1.6 | |
| Queue Length 95th (m) | 10.7 | 2.9 | 1.3 | | 2.9 | | m0.4 | 21.0 | | 74.0 | 7.1 | |
| Internal Link Dist (m) | | 209.1 | | | 112.8 | | | 273.4 | | | 275.6 | |
| Turn Bay Length (m) | 38.5 | | | | | | 27.5 | | | | | |
| Base Capacity (vph) | 360 | 477 | 406 | | 477 | | 634 | 1384 | | 1384 | 1176 | |
| Starvation Cap Reductn | 0 | 0 | 0 | | 0 | | 0 | 0 | | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | | 0 | | 0 | 0 | | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | | 0 | | 0 | 0 | | 0 | 0 | |
| Reduced v/c Ratio | 0.09 | 0.01 | 0.00 | | 0.01 | | 0.00 | 0.23 | | 0.37 | 0.04 | |


| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 90 | | | | | | | | | | | | |
| Actuated Cycle Length: 90 | | | | | | | | | | | | |
| Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 65 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
10: Borrisokane & New Collector/BRT

Caivan Conservancy West
2035 Future Background PM Peak Hour

| | | |
|---|--------------------------------|---------------------|
| Maximum v/c Ratio: 0.37 | Intersection Signal Delay: 6.6 | Intersection LOS: A |
| Intersection Capacity Utilization 58.2% | ICU Level of Service B | |
| Analysis Period (min) 15 | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |

Splits and Phases: 10: Borrisokane & New Collector/BRT



Appendix G

TDM Checklist

TDM Measures Checklist:
Residential Developments (multi-family, condominium or subdivision)

| Legend | |
|--------|--|
| BASIC | The measure is generally feasible and effective, and in most cases would benefit the development and its users |
| BETTER | The measure could maximize support for users of sustainable modes, and optimize development performance |
| ★ | The measure is one of the most dependably effective tools to encourage the use of sustainable modes |

| TDM measures: Residential developments | | Check if proposed & add descriptions |
|---|---|--|
| 1. TDM PROGRAM MANAGEMENT | | |
| 1.1 Program coordinator | | |
| BASIC | ★ 1.1.1 Designate an internal coordinator, or contract with an external coordinator | <input type="checkbox"/> Community Association may fulfill this role in future. |
| 1.2 Travel surveys | | |
| BETTER | 1.2.1 Conduct periodic surveys to identify travel-related behaviours, attitudes, challenges and solutions, and to track progress | <input checked="" type="checkbox"/> Community Association may fulfill this role in future. |
| 2. WALKING AND CYCLING | | |
| 2.1 Information on walking/cycling routes & destinations | | |
| BASIC | 2.1.1 Display local area maps with walking/cycling access routes and key destinations at major entrances (<i>multi-family, condominium</i>) | <input type="checkbox"/> N/A |
| 2.2 Bicycle skills training | | |
| BETTER | 2.2.1 Offer on-site cycling courses for residents, or subsidize off-site courses | <input checked="" type="checkbox"/> |

| TDM measures: Residential developments | | Check if proposed & add descriptions |
|---|--|--------------------------------------|
| 3. TRANSIT | | |
| 3.1 Transit information | | |
| BASIC | 3.1.1 Display relevant transit schedules and route maps at entrances (<i>multi-family, condominium</i>) | <input type="checkbox"/> N/A |
| BETTER | 3.1.2 Provide real-time arrival information display at entrances (<i>multi-family, condominium</i>) | <input type="checkbox"/> N/A |
| 3.2 Transit fare incentives | | |
| BASIC | ★ 3.2.1 Offer PRESTO cards preloaded with one monthly transit pass on residence purchase/move-in, to encourage residents to use transit | <input checked="" type="checkbox"/> |
| BETTER | 3.2.2 Offer at least one year of free monthly transit passes on residence purchase/move-in | <input type="checkbox"/> |
| 3.3 Enhanced public transit service | | |
| BETTER | ★ 3.3.1 Contract with OC Transpo to provide early transit services until regular services are warranted by occupancy levels (<i>subdivision</i>) | <input checked="" type="checkbox"/> |
| 3.4 Private transit service | | |
| BETTER | 3.4.1 Provide shuttle service for seniors homes or lifestyle communities (e.g. scheduled mall or supermarket runs) | <input type="checkbox"/> N/A |
| 4. CARSHARING & BIKESHARING | | |
| 4.1 Bikeshare stations & memberships | | |
| BETTER | 4.1.1 Contract with provider to install on-site bikeshare station (<i>multi-family</i>) | <input type="checkbox"/> |
| BETTER | 4.1.2 Provide residents with bikeshare memberships, either free or subsidized (<i>multi-family</i>) | <input type="checkbox"/> |
| 4.2 Carshare vehicles & memberships | | |
| BETTER | 4.2.1 Contract with provider to install on-site carshare vehicles and promote their use by residents | <input type="checkbox"/> |
| BETTER | 4.2.2 Provide residents with carshare memberships, either free or subsidized | <input type="checkbox"/> |
| 5. PARKING | | |
| 5.1 Priced parking | | |
| BASIC | ★ 5.1.1 Unbundle parking cost from purchase price (<i>condominium</i>) | <input type="checkbox"/> N/A |
| BASIC | ★ 5.1.2 Unbundle parking cost from monthly rent (<i>multi-family</i>) | <input type="checkbox"/> N/A |

| TDM measures: Residential developments | | Check if proposed & add descriptions |
|--|---|--------------------------------------|
| 6. TDM MARKETING & COMMUNICATIONS | | |
| 6.1 Multimodal travel information | | |
| BASIC ★ | 6.1.1 Provide a multimodal travel option information package to new residents | <input checked="" type="checkbox"/> |
| 6.2 Personalized trip planning | | |
| BETTER ★ | 6.2.1 Offer personalized trip planning to new residents | <input type="checkbox"/> |

Appendix H

Justification 7 Signal Warrants

Conservancy Way @ Borrisokane Road
FB 2030

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | Entire % | Signal |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|-----|----------|--------|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 465 | 97% | 38% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 46 | 38% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 419 | 87% | 48% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 24 | 48% | | |

- Notes
1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percentage governs justification
 3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
 4. T-intersection factor corrected, applies only to 1B
 5. Correction to 2B, as per MTO and City of Ottawa, for '2 or More Lanes' has been applied

Conservancy Way @ Borrisokane Road
FB 2035

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | Entire % | Signal |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|-----|----------|--------|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 403 | 84% | 38% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 46 | 38% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 357 | 74% | 48% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 24 | 48% | | |

- Notes
1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percentage governs justification
 3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
 4. T-intersection factor corrected, applies only to 1B
 5. Correction to 2B, as per MTO and City of Ottawa, for '2 or More Lanes' has been applied

Conservancy Way @ Borrisokane Road
FT 2030

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | Entire % | Signal |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|------|----------|--------|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 551 | 115% | 75% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 91 | 75% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 461 | 96% | 96% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 66 | 133% | | |

- Notes
1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percentage governs justification
 3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
 4. T-intersection factor corrected, applies only to 1B
 5. Correction to 2B, as per MTO and City of Ottawa, for '2 or More Lanes' has been applied

Conservancy Way @ Borrisokane Road
FT 2035

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | Entire % | Signal |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|------|----------|--------|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 489 | 102% | 75% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 91 | 75% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 399 | 83% | 83% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 66 | 133% | | |

- Notes
1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percentage governs justification
 3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
 4. T-intersection factor corrected, applies only to 1B
 5. Correction to 2B, as per MTO and City of Ottawa, for '2 or More Lanes' has been applied

New Collector @ Borrisokane
 FB 2030

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | Entire % | Signal |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|------|----------|--------|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 489 | 102% | 25% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 30 | 25% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 468 | 98% | 39% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 20 | 39% | | |

- Notes
1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percentage governs justification
 3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2 \text{ or } (AM + PM) / 4$, including amplification factors
 4. T-intersection factor corrected, applies only to 1B
 5. Correction to 2B, as per MTO and City of Ottawa, for '2 or More Lanes' has been applied

New Collector @ Borrisokane
 FB 2035

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | Entire % | Signal |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|-----|----------|--------|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 431 | 90% | 30% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 36 | 30% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 406 | 85% | 43% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 22 | 43% | | |

- Notes
1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percentage governs justification
 3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2 \text{ or } (AM + PM) / 4$, including amplification factors
 4. T-intersection factor corrected, applies only to 1B
 5. Correction to 2B, as per MTO and City of Ottawa, for '2 or More Lanes' has been applied

New Collector @ Borrisokane
FT 2030

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | Entire % | Signal |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|------|----------|--------|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 650 | 135% | 82% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 98 | 82% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 584 | 122% | 122% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 63 | 126% | | |

- Notes
1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percentage governs justification
 3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
 4. T-intersection factor corrected, applies only to 1B
 5. Correction to 2B, as per MTO and City of Ottawa, for '2 or More Lanes' has been applied

New Collector @ Borrisokane
FT 2035

Justification #7

| Justification | Description | Minimum Requirement | | Minimum Requirement | | Compliance | | Entire % | Signal |
|-----------------------------|---|---------------------|-------------|---------------------|-------------|------------|------|----------|--------|
| | | 1 Lane Highway | | 2 or More Lanes | | Sectional | | | |
| | | Free Flow | Restr. Flow | Free Flow | Restr. Flow | Numerical | % | | |
| 1. Minimum Vehicular Volume | A. Vehicle volume, all approaches (average hour) | 480 | 720 | 600 | 900 | 592 | 123% | 87% | No |
| | B. Vehicle volume, along minor streets (average hour) | 120 | 170 | 120 | 170 | 104 | 87% | | |
| 2. Delay to Cross Traffic | A. Vehicle volumes, major street (average hour) | 480 | 720 | 600 | 900 | 522 | 109% | 109% | No |
| | B. Combined vehicle and pedestrian volume crossing artery from minor streets (average hour) | 50 | 75 | 50 | 75 | 65 | 130% | | |

- Notes
1. Refer to OTM Book 12, pg 92, Mar 2012
 2. Lowest section percentage governs justification
 3. Average hourly volumes estimated from peak hour volumes, $AHV = PM/2$ or $(AM + PM) / 4$, including amplification factors
 4. T-intersection factor corrected, applies only to 1B
 5. Correction to 2B, as per MTO and City of Ottawa, for '2 or More Lanes' has been applied

Appendix I

Synchro Intersection Worksheets – 2030 Future Total Conditions

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2030 Future Total AM Peak Hour


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|------|---------------|--------|-----|--------------|-------|-------|
| Lane Configurations | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ | ↔ | ↗ | ↘ |
| Traffic Volume (vph) | 72 | 19 | 47 | 100 | 108 | 113 | 219 | 2769 | 86 | 53 | 1317 | 307 |
| Future Volume (vph) | 72 | 19 | 47 | 100 | 108 | 113 | 219 | 2769 | 86 | 53 | 1317 | 307 |
| Satd. Flow (prot) | 1243 | 1160 | 1450 | 1589 | 1353 | 0 | 3144 | 3220 | 0 | 1476 | 3090 | 1395 |
| Fit Permitted | 0.460 | | | 0.745 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 602 | 1160 | 1431 | 1245 | 1353 | 0 | 3144 | 3220 | 0 | 1476 | 3090 | 1395 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 72 | 19 | 47 | 100 | 221 | 0 | 219 | 2855 | 0 | 53 | 1317 | 307 |
| Turn Type | Perm | NA | Perm | Perm | NA | Prot | NA | Prot | NA | Perm | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | 4 | 8 | | | | | | | | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 39.9 | 39.9 | 39.9 | 32.9 | 32.9 | | 11.4 | 30.4 | | 11.4 | 39.4 | 39.4 |
| Total Split (s) | 41.0 | 41.0 | 41.0 | 41.0 | 41.0 | | 17.8 | 66.6 | | 12.4 | 61.2 | 61.2 |
| Total Split (%) | 34.2% | 34.2% | 34.2% | 34.2% | 34.2% | | 14.8% | 55.5% | | 10.3% | 51.0% | 51.0% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.6 | 3.6 | 3.6 | 3.6 | 3.6 | | 1.8 | 1.8 | | 1.8 | 1.8 | 1.8 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.9 | 6.9 | 6.9 | 6.9 | 6.9 | | 6.4 | 6.4 | | 6.4 | 6.4 | 6.4 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 24.8 | 24.8 | 24.8 | 24.8 | 24.8 | | 12.7 | 69.3 | | 8.8 | 62.8 | 62.8 |
| Actuated g/C Ratio | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | | 0.11 | 0.58 | | 0.07 | 0.52 | 0.52 |
| v/c Ratio | 0.58 | 0.08 | 0.16 | 0.39 | 0.79 | | 0.66 | 1.54 | | 0.50 | 0.81 | 0.42 |
| Control Delay | 60.0 | 35.6 | 37.4 | 43.8 | 64.3 | | 66.8 | 260.2 | | 69.4 | 30.4 | 21.5 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 60.0 | 35.6 | 37.4 | 43.8 | 64.3 | | 66.8 | 260.2 | | 69.4 | 30.4 | 21.5 |
| LOS | E | D | D | D | E | | E | F | | E | C | C |
| Approach Delay | | 49.0 | | | 57.9 | | | 246.4 | | | 30.0 | |
| Approach LOS | | D | | | E | | | F | | | C | |
| Queue Length 50th (m) | 15.2 | 3.6 | 9.0 | 20.2 | 49.1 | | 25.2 | ~519.0 | | 11.9 | 131.8 | 43.0 |
| Queue Length 95th (m) | 28.6 | 9.1 | 17.6 | 33.2 | 70.2 | | m15.4 m#256.5 | | | #32.4 #197.1 | 73.9 | |
| Internal Link Dist (m) | | 172.9 | | | 177.4 | | | 1040.6 | | | 345.0 | |
| Turn Bay Length (m) | 70.0 | | 150.0 | 50.0 | | | 130.0 | | | 180.0 | | 60.0 |
| Base Capacity (vph) | 171 | 329 | 406 | 353 | 384 | | 338 | 1859 | | 107 | 1618 | 730 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.42 | 0.06 | 0.12 | 0.28 | 0.58 | | 0.65 | 1.54 | | 0.50 | 0.81 | 0.42 |

| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 69 (58%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 125 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2030 Future Total AM Peak Hour

| | |
|---|------------------------|
| Maximum v/c Ratio: 1.54 | Intersection LOS: F |
| Intersection Signal Delay: 159.9 | ICU Level of Service H |
| Intersection Capacity Utilization 131.7% | |
| Analysis Period (min) 15 | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2030 Future Total AM Peak Hour


| | ↖ | → | ↘ | ↙ | ← | ↖ | ↙ | ↗ | ↘ | ↖ | ↙ | ↘ |
|------------------------|--------|--------------|--------|--------|--------|--------|--------|-------|-------|-------|-------|-----|
| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | ↖ | ↖↗ | ↖ | ↖ | ↖↗ | ↖ | ↖↗ | ↖ | ↖ | ↖ | ↖ | ↖ |
| Traffic Volume (vph) | 117 | 753 | 561 | 98 | 1599 | 52 | 1156 | 49 | 195 | 69 | 23 | 230 |
| Future Volume (vph) | 117 | 753 | 561 | 98 | 1599 | 52 | 1156 | 49 | 195 | 69 | 23 | 230 |
| Satd. Flow (prot) | 1589 | 3119 | 1332 | 1621 | 3210 | 1345 | 3113 | 1673 | 1450 | 1605 | 1474 | 0 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1589 | 3119 | 1332 | 1621 | 3210 | 1345 | 3113 | 1673 | 1450 | 1605 | 1474 | 0 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 117 | 753 | 561 | 98 | 1599 | 52 | 1156 | 49 | 195 | 69 | 253 | 0 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Detector Phase | 5 | 2 | 2 | 1 | 6 | 6 | 3 | 8 | 8 | 7 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | |
| Minimum Split (s) | 11.6 | 33.6 | 33.6 | 11.6 | 33.6 | 33.6 | 11.7 | 33.7 | 33.7 | 11.7 | 33.7 | |
| Total Split (s) | 13.0 | 48.7 | 48.7 | 11.6 | 47.3 | 47.3 | 26.0 | 41.8 | 41.8 | 17.9 | 33.7 | |
| Total Split (%) | 10.8% | 40.6% | 40.6% | 9.7% | 39.4% | 39.4% | 21.7% | 34.8% | 34.8% | 14.9% | 28.1% | |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | |
| All-Red Time (s) | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 3.4 | 3.4 | 3.4 | 3.4 | 3.4 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | |
| Lead/Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 9.3 | 42.1 | 42.1 | 7.9 | 40.7 | 40.7 | 19.3 | 36.4 | 36.4 | 9.6 | 24.1 | |
| Actuated g/C Ratio | 0.08 | 0.35 | 0.35 | 0.07 | 0.34 | 0.34 | 0.16 | 0.30 | 0.30 | 0.08 | 0.20 | |
| v/c Ratio | 0.95 | 0.69 | 1.20 | 0.92 | 1.47 | 0.11 | 2.31 | 0.10 | 0.44 | 0.54 | 0.86 | |
| Control Delay | 124.2 | 22.1 | 129.3 | 125.0 | 247.8 | 28.2 | 620.8 | 31.9 | 38.3 | 68.3 | 72.2 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 124.2 | 22.1 | 129.3 | 125.0 | 247.8 | 28.2 | 620.8 | 31.9 | 38.3 | 68.3 | 72.2 | |
| LOS | F | C | F | F | F | C | F | C | D | E | E | |
| Approach Delay | | 72.5 | | | 234.4 | | | 519.1 | | | 71.4 | |
| Approach LOS | | E | | | F | | | F | | | E | |
| Queue Length 50th (m) | ~33.3 | 46.4 | ~160.0 | ~28.8 | ~268.4 | 8.3 | ~225.7 | 8.3 | 37.0 | 15.5 | 55.9 | |
| Queue Length 95th (m) | m#52.8 | 58.1 m#217.1 | #64.9 | #310.1 | 17.4 | #265.6 | 17.7 | 59.3 | 30.3 | #92.0 | #92.0 | |
| Internal Link Dist (m) | | 1040.6 | | | 387.1 | | | 275.6 | | | 103.1 | |
| Turn Bay Length (m) | 90.0 | | 90.0 | 50.0 | | 27.5 | 160.0 | | 57.5 | 17.0 | | |
| Base Capacity (vph) | 123 | 1094 | 467 | 106 | 1088 | 456 | 500 | 512 | 444 | 149 | 331 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.95 | 0.69 | 1.20 | 0.92 | 1.47 | 0.11 | 2.31 | 0.10 | 0.44 | 0.46 | 0.76 | |

| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 120 |
| Actuated Cycle Length: | 120 |
| Offset: | 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green |
| Natural Cycle: | 125 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2030 Future Total AM Peak Hour

| | |
|---|--------|
| Maximum v/c Ratio: | 2.31 |
| Intersection Signal Delay: | 257.7 |
| Intersection LOS: | F |
| Intersection Capacity Utilization: | 126.8% |
| ICU Level of Service: | H |
| Analysis Period (min): | 15 |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2030 Future Total AM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-----|-------|-------|-----|-------|-------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 149 | 0 | 10 | 12 | 0 | 49 | 4 | 496 | 5 | 22 | 220 | 64 |
| Future Volume (vph) | 149 | 0 | 10 | 12 | 0 | 49 | 4 | 496 | 5 | 22 | 220 | 64 |
| Satd. Flow (prot) | 1621 | 1450 | 0 | 1621 | 1450 | 0 | 1621 | 1704 | 0 | 1621 | 1706 | 1450 |
| Fit Permitted | 0.725 | | | 0.751 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1237 | 1450 | 0 | 1281 | 1450 | 0 | 1621 | 1704 | 0 | 1621 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 149 | 10 | 0 | 12 | 49 | 0 | 4 | 501 | 0 | 22 | 220 | 64 |
| Turn Type | Perm | NA | | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | | | | | | | 6 |
| Detector Phase | 4 | 4 | | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 25.6 | | 11.6 | 25.6 | 25.6 |
| Total Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 44.7 | | 12.0 | 45.1 | 45.1 |
| Total Split (%) | 37.0% | 37.0% | | 37.0% | 37.0% | | 12.9% | 49.7% | | 13.3% | 50.1% | 50.1% |
| Yellow Time (s) | 3.3 | 3.3 | | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.0 | 3.0 | | 3.0 | 3.0 | | 2.0 | 2.0 | | 2.0 | 2.0 | 2.0 |
| Lost Time Adjust (s) | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.3 | 6.3 | | 6.3 | 6.3 | | 6.6 | 6.6 | | 6.6 | 6.6 | 6.6 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 17.1 | 17.1 | | 17.1 | 17.1 | | 5.5 | 54.8 | | 6.2 | 57.7 | 57.7 |
| Actuated g/C Ratio | 0.19 | 0.19 | | 0.19 | 0.19 | | 0.06 | 0.61 | | 0.07 | 0.64 | 0.64 |
| v/c Ratio | 0.64 | 0.04 | | 0.05 | 0.18 | | 0.04 | 0.48 | | 0.20 | 0.20 | 0.07 |
| Control Delay | 44.6 | 25.8 | | 26.2 | 29.2 | | 40.8 | 15.1 | | 44.0 | 9.8 | 9.8 |
| Queue Delay | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 44.6 | 25.8 | | 26.2 | 29.2 | | 40.8 | 15.1 | | 44.0 | 9.8 | 9.8 |
| LOS | D | C | | C | C | | D | B | | D | A | A |
| Approach Delay | | 43.4 | | | 28.6 | | | 15.3 | | | 12.2 | |
| Approach LOS | | D | | | C | | | B | | | B | |
| Queue Length 50th (m) | 24.0 | 1.4 | | 1.7 | 7.2 | | 0.7 | 34.0 | | 3.6 | 12.1 | 3.2 |
| Queue Length 95th (m) | 36.8 | 4.8 | | 5.3 | 14.1 | | 3.9 | 103.4 | | 10.9 | 39.8 | 13.8 |
| Internal Link Dist (m) | | 145.0 | | | 184.4 | | | 650.0 | | | 273.4 | |
| Turn Bay Length (m) | 9.3 | | | 9.3 | | | 84.0 | | | 84.5 | | 83.0 |
| Base Capacity (vph) | 371 | 435 | | 384 | 435 | | 100 | 1037 | | 111 | 1093 | 929 |
| Starvation Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.40 | 0.02 | | 0.03 | 0.11 | | 0.04 | 0.48 | | 0.20 | 0.20 | 0.07 |


| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 90 |
| Actuated Cycle Length: | 90 |
| Offset: | 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green |
| Natural Cycle: | 80 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2030 Future Total AM Peak Hour

| | | |
|---|---------------------------------|---------------------|
| Maximum v/c Ratio: 0.64 | Intersection Signal Delay: 19.5 | Intersection LOS: B |
| Intersection Capacity Utilization 54.0% | ICU Level of Service A | |
| Analysis Period (min) 15 | | |

Splits and Phases: 9: Borriskane & Conservancy Way



Lanes, Volumes, Timings
10: Borrisokane & New Collector

Caivan Conservancy West
2030 Future Total AM Peak Hour


| | ↖ | ↗ | ↙ | ↘ | ↕ | ↖ |
|------------------------|-------|-------|-------|-------|-------|-------|
| Lane Group | EBL | EBR | NBL | NBT | SBT | SBR |
| Lane Configurations | ↖ | ↗ | ↙ | ↘ | ↕ | ↖ |
| Traffic Volume (vph) | 152 | 6 | 3 | 691 | 300 | 65 |
| Future Volume (vph) | 152 | 6 | 3 | 691 | 300 | 65 |
| Satd. Flow (prot) | 1621 | 1450 | 1621 | 1706 | 1706 | 1450 |
| Fit Permitted | 0.950 | | 0.577 | | | |
| Satd. Flow (perm) | 1621 | 1450 | 984 | 1706 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | |
| Lane Group Flow (vph) | 152 | 6 | 3 | 691 | 300 | 65 |
| Turn Type | Perm | Perm | Perm | NA | NA | Perm |
| Protected Phases | | | | 2 | 6 | |
| Permitted Phases | 4 | 4 | 2 | | | 6 |
| Detector Phase | 4 | 4 | 2 | 2 | 6 | 6 |
| Switch Phase | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 |
| Minimum Split (s) | 30.8 | 30.8 | 31.8 | 31.8 | 31.8 | 31.8 |
| Total Split (s) | 30.8 | 30.8 | 61.0 | 61.0 | 61.0 | 61.0 |
| Total Split (%) | 33.6% | 33.6% | 66.4% | 66.4% | 66.4% | 66.4% |
| Yellow Time (s) | 4.6 | 4.6 | 3.3 | 3.3 | 3.3 | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 3.5 | 3.5 | 3.5 | 3.5 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 |
| Lead/Lag | | | | | | |
| Lead-Lag Optimize? | | | | | | |
| Recall Mode | None | None | C-Max | C-Max | C-Max | C-Max |
| Act Effct Green (s) | 15.1 | 15.1 | 63.1 | 63.1 | 63.1 | 63.1 |
| Actuated g/C Ratio | 0.16 | 0.16 | 0.69 | 0.69 | 0.69 | 0.69 |
| v/c Ratio | 0.57 | 0.03 | 0.00 | 0.59 | 0.26 | 0.07 |
| Control Delay | 42.7 | 28.5 | 6.7 | 11.3 | 7.0 | 6.2 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Delay | 42.7 | 28.5 | 6.7 | 11.3 | 7.0 | 6.2 |
| LOS | D | C | A | B | A | A |
| Approach Delay | 42.2 | | | 11.3 | 6.9 | |
| Approach LOS | D | | | B | A | |
| Queue Length 50th (m) | 25.1 | 0.9 | 0.2 | 52.2 | 16.4 | 3.1 |
| Queue Length 95th (m) | 38.3 | 3.7 | 1.3 | 115.9 | 37.9 | 9.6 |
| Internal Link Dist (m) | 113.8 | | | 273.4 | 275.6 | |
| Turn Bay Length (m) | 38.5 | | 27.5 | | | |
| Base Capacity (vph) | 423 | 379 | 675 | 1171 | 1171 | 996 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.36 | 0.02 | 0.00 | 0.59 | 0.26 | 0.07 |

| Intersection Summary | |
|------------------------|--|
| Cycle Length: | 91.8 |
| Actuated Cycle Length: | 91.8 |
| Offset: | 0 (0%), Referenced to phase 2:NBTL and 6:SBT, Start of Green |
| Natural Cycle: | 70 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
10: Borrisokane & New Collector

Caivan Conservancy West
2030 Future Total AM Peak Hour

| | |
|---|------------------------|
| Maximum v/c Ratio: 0.59 | Intersection LOS: B |
| Intersection Signal Delay: 14.0 | ICU Level of Service B |
| Intersection Capacity Utilization 58.6% | |
| Analysis Period (min) 15 | |



Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2030 Future Total PM Peak Hour


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|--------|-------|-------|-------|-------|-----|-------|---------|-----|-------|--------|-------|
| Lane Configurations | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ |
| Traffic Volume (vph) | 275 | 96 | 188 | 128 | 26 | 92 | 66 | 1867 | 132 | 85 | 2724 | 108 |
| Future Volume (vph) | 275 | 96 | 188 | 128 | 26 | 92 | 66 | 1867 | 132 | 85 | 2724 | 108 |
| Satd. Flow (prot) | 1605 | 1706 | 1450 | 1517 | 1440 | 0 | 3144 | 3174 | 0 | 1589 | 3241 | 1450 |
| Fit Permitted | 0.681 | | | 0.695 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1150 | 1706 | 1431 | 1108 | 1440 | 0 | 3144 | 3174 | 0 | 1589 | 3241 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 275 | 96 | 188 | 128 | 118 | 0 | 66 | 1999 | 0 | 85 | 2724 | 108 |
| Turn Type | Perm | NA | Perm | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | | 8 | | 5 | 2 | | 1 | 6 |
| Permitted Phases | 4 | | 4 | 8 | | | | | | | | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | | 5 | 2 | | 1 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 39.9 | 39.9 | 39.9 | 32.9 | 32.9 | | 11.4 | 30.4 | | 11.4 | 39.4 | 39.4 |
| Total Split (s) | 43.0 | 43.0 | 43.0 | 43.0 | 43.0 | | 11.4 | 65.0 | | 12.0 | 65.6 | 65.6 |
| Total Split (%) | 35.8% | 35.8% | 35.8% | 35.8% | 35.8% | | 9.5% | 54.2% | | 10.0% | 54.7% | 54.7% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.6 | 3.6 | 3.6 | 3.6 | 3.6 | | 1.8 | 1.8 | | 1.8 | 1.8 | 1.8 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.9 | 6.9 | 6.9 | 6.9 | 6.9 | | 6.4 | 6.4 | | 6.4 | 6.4 | 6.4 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 32.1 | 32.1 | 32.1 | 32.1 | 32.1 | | 5.8 | 59.3 | | 9.0 | 64.8 | 64.8 |
| Actuated g/C Ratio | 0.27 | 0.27 | 0.27 | 0.27 | 0.27 | | 0.05 | 0.49 | | 0.08 | 0.54 | 0.54 |
| v/c Ratio | 0.90 | 0.21 | 0.49 | 0.43 | 0.31 | | 0.43 | 1.28 | | 0.71 | 1.56 | 0.14 |
| Control Delay | 72.9 | 34.0 | 41.0 | 40.3 | 36.2 | | 72.0 | 144.4 | | 87.3 | 277.9 | 16.4 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 72.9 | 34.0 | 41.0 | 40.3 | 36.2 | | 72.0 | 144.4 | | 87.3 | 277.9 | 16.4 |
| LOS | E | C | D | D | D | | E | F | | F | F | B |
| Approach Delay | | 55.5 | | | 38.3 | | | 142.1 | | | 262.7 | |
| Approach LOS | | E | | | D | | | F | | | F | |
| Queue Length 50th (m) | 59.6 | 16.8 | 35.7 | 23.9 | 21.2 | | 7.4 | ~322.4 | | 20.0 | ~489.7 | 13.3 |
| Queue Length 95th (m) | #101.1 | 29.9 | 56.8 | 41.3 | 36.4 | | m7.3 | m#248.0 | | #55.1 | #528.2 | 23.8 |
| Internal Link Dist (m) | | 172.9 | | | 177.4 | | | 1040.6 | | | 345.0 | |
| Turn Bay Length (m) | 70.0 | | 150.0 | 50.0 | | | 130.0 | | | 180.0 | | 60.0 |
| Base Capacity (vph) | 345 | 513 | 430 | 333 | 433 | | 153 | 1567 | | 119 | 1751 | 783 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.80 | 0.19 | 0.44 | 0.38 | 0.27 | | 0.43 | 1.28 | | 0.71 | 1.56 | 0.14 |

| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 64 (53%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 125 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2030 Future Total PM Peak Hour

| | | |
|---|----------------------------------|---------------------|
| Maximum v/c Ratio: 1.56 | Intersection Signal Delay: 190.1 | Intersection LOS: F |
| Intersection Capacity Utilization 117.5% | ICU Level of Service H | |
| Analysis Period (min) 15 | | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | | |
| Queue shown is maximum after two cycles. | | |
| # 95th percentile volume exceeds capacity, queue may be longer. | | |
| Queue shown is maximum after two cycles. | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |



Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2030 Future Total PM Peak Hour


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|--------|--------|---------|--------|-------|-------|--------|-------|-------|-------|-------|-----|
| Lane Configurations | ↔ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ |
| Traffic Volume (vph) | 322 | 1600 | 1166 | 192 | 1075 | 65 | 775 | 34 | 159 | 52 | 49 | 122 |
| Future Volume (vph) | 322 | 1600 | 1166 | 192 | 1075 | 65 | 775 | 34 | 159 | 52 | 49 | 122 |
| Satd. Flow (prot) | 1605 | 3241 | 1436 | 1621 | 3210 | 1436 | 2969 | 1706 | 1309 | 1503 | 1472 | 0 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1605 | 3241 | 1436 | 1621 | 3210 | 1436 | 2969 | 1706 | 1309 | 1503 | 1472 | 0 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 322 | 1600 | 1166 | 192 | 1075 | 65 | 775 | 34 | 159 | 52 | 171 | 0 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Detector Phase | 5 | 2 | 2 | 1 | 6 | 6 | 3 | 8 | 8 | 7 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | |
| Minimum Split (s) | 11.6 | 33.6 | 33.6 | 11.6 | 33.6 | 33.6 | 11.7 | 31.7 | 31.7 | 11.7 | 16.7 | |
| Total Split (s) | 21.0 | 60.0 | 60.0 | 14.0 | 53.0 | 53.0 | 22.0 | 33.0 | 33.0 | 13.0 | 24.0 | |
| Total Split (%) | 17.5% | 50.0% | 50.0% | 11.7% | 44.2% | 44.2% | 18.3% | 27.5% | 27.5% | 10.8% | 20.0% | |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | |
| All-Red Time (s) | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 3.4 | 3.4 | 3.4 | 3.4 | 3.4 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | |
| Lead/Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 15.3 | 53.4 | 53.4 | 8.3 | 46.4 | 46.4 | 15.3 | 28.0 | 28.0 | 6.3 | 16.4 | |
| Actuated g/C Ratio | 0.13 | 0.44 | 0.44 | 0.07 | 0.39 | 0.39 | 0.13 | 0.23 | 0.23 | 0.05 | 0.14 | |
| v/c Ratio | 1.58 | 1.11 | 1.82 | 1.73 | 0.87 | 0.12 | 2.05 | 0.09 | 0.52 | 0.67 | 0.85 | |
| Control Delay | 305.9 | 69.2 | 391.5 | 397.8 | 42.7 | 24.5 | 509.2 | 38.2 | 48.2 | 94.2 | 84.5 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 305.9 | 69.2 | 391.5 | 397.8 | 42.7 | 24.5 | 509.2 | 38.2 | 48.2 | 94.2 | 84.5 | |
| LOS | F | E | F | F | D | C | F | D | D | F | F | |
| Approach Delay | | 215.6 | | | 93.0 | | | 416.9 | | | 86.8 | |
| Approach LOS | | F | | | F | | | F | | | F | |
| Queue Length 50th (m) | ~110.4 | ~219.2 | ~406.3 | ~68.7 | 119.8 | 9.6 | ~145.9 | 6.4 | 33.1 | 12.1 | 39.0 | |
| Queue Length 95th (m) | m#67.6 | m#41.6 | m#237.7 | #113.7 | 148.5 | 19.1 | #182.8 | 14.9 | 55.3 | #31.7 | #74.4 | |
| Internal Link Dist (m) | | 1040.6 | | | 313.4 | | | 275.6 | | | 103.1 | |
| Turn Bay Length (m) | 90.0 | | 90.0 | 50.0 | | 27.5 | 160.0 | | 57.5 | 17.0 | | |
| Base Capacity (vph) | 204 | 1442 | 639 | 111 | 1241 | 555 | 378 | 398 | 305 | 78 | 212 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 1.58 | 1.11 | 1.82 | 1.73 | 0.87 | 0.12 | 2.05 | 0.09 | 0.52 | 0.67 | 0.81 | |

| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 120 |
| Actuated Cycle Length: | 120 |
| Offset: | 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green |
| Natural Cycle: | 130 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2030 Future Total PM Peak Hour

| | |
|---|--------|
| Maximum v/c Ratio: | 2.05 |
| Intersection Signal Delay: | 216.1 |
| Intersection LOS: | F |
| Intersection Capacity Utilization: | 114.7% |
| ICU Level of Service: | H |
| Analysis Period (min): | 15 |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2030 Future Total PM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-----|-------|-------|-----|-------|--------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 96 | 0 | 6 | 8 | 0 | 32 | 9 | 308 | 12 | 49 | 512 | 141 |
| Future Volume (vph) | 96 | 0 | 6 | 8 | 0 | 32 | 9 | 308 | 12 | 49 | 512 | 141 |
| Satd. Flow (prot) | 1621 | 1450 | 0 | 1621 | 1450 | 0 | 1621 | 1696 | 0 | 1621 | 1706 | 1450 |
| Fit Permitted | 0.736 | | | 0.754 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1256 | 1450 | 0 | 1286 | 1450 | 0 | 1621 | 1696 | 0 | 1621 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 96 | 6 | 0 | 8 | 32 | 0 | 9 | 320 | 0 | 49 | 512 | 141 |
| Turn Type | Perm | NA | | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | | 6 |
| Permitted Phases | 4 | | | 8 | | | 5 | | | 1 | | 6 |
| Detector Phase | 4 | 4 | | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 25.6 | | 11.6 | 25.6 | 25.6 |
| Total Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 42.8 | | 13.9 | 45.1 | 45.1 |
| Total Split (%) | 37.0% | 37.0% | | 37.0% | 37.0% | | 12.9% | 47.6% | | 15.4% | 50.1% | 50.1% |
| Yellow Time (s) | 3.3 | 3.3 | | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.0 | 3.0 | | 3.0 | 3.0 | | 2.0 | 2.0 | | 2.0 | 2.0 | 2.0 |
| Lost Time Adjust (s) | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.3 | 6.3 | | 6.3 | 6.3 | | 6.6 | 6.6 | | 6.6 | 6.6 | 6.6 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 14.8 | 14.8 | | 14.8 | 14.8 | | 5.7 | 58.0 | | 7.4 | 64.6 | 64.6 |
| Actuated g/C Ratio | 0.16 | 0.16 | | 0.16 | 0.16 | | 0.06 | 0.64 | | 0.08 | 0.72 | 0.72 |
| v/c Ratio | 0.47 | 0.03 | | 0.04 | 0.13 | | 0.09 | 0.29 | | 0.37 | 0.42 | 0.14 |
| Control Delay | 39.7 | 27.0 | | 27.4 | 30.2 | | 41.9 | 13.0 | | 40.5 | 12.6 | 11.6 |
| Queue Delay | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 39.7 | 27.0 | | 27.4 | 30.2 | | 41.9 | 13.0 | | 40.5 | 12.6 | 11.6 |
| LOS | D | C | | C | C | | D | B | | D | B | B |
| Approach Delay | | 39.0 | | | 29.6 | | | 13.8 | | | 14.4 | |
| Approach LOS | | D | | | C | | | B | | | B | |
| Queue Length 50th (m) | 15.6 | 0.9 | | 1.2 | 4.9 | | 1.5 | 27.8 | | 8.0 | 29.2 | 6.2 |
| Queue Length 95th (m) | 24.7 | 3.4 | | 4.0 | 10.3 | | 6.1 | 62.0 | | 17.4 | 85.6 | 30.3 |
| Internal Link Dist (m) | | 154.2 | | | 129.4 | | | 1276.6 | | | 273.4 | |
| Turn Bay Length (m) | 9.3 | | | 9.3 | | | 84.0 | | | 84.5 | | 83.0 |
| Base Capacity (vph) | 376 | 435 | | 385 | 435 | | 102 | 1093 | | 141 | 1224 | 1040 |
| Starvation Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.26 | 0.01 | | 0.02 | 0.07 | | 0.09 | 0.29 | | 0.35 | 0.42 | 0.14 |

| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 90 |
| Actuated Cycle Length: | 90 |
| Offset: | 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green |
| Natural Cycle: | 80 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2030 Future Total PM Peak Hour

| | | |
|---|---------------------------------|---------------------|
| Maximum v/c Ratio: 0.47 | Intersection Signal Delay: 16.9 | Intersection LOS: B |
| Intersection Capacity Utilization 61.1% | ICU Level of Service B | |
| Analysis Period (min) 15 | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |

Splits and Phases: 9: Borriskane & Conservancy Way



Lanes, Volumes, Timings
10: Borrisokane & New Collector

Caivan Conservancy West
2030 Future Total PM Peak Hour

| Lane Group | EBL | EBR | NBL | NBT | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|-------|
| Lane Configurations | ↖ | ↗ | ↖ | ↖ | ↖ | ↖ |
| Traffic Volume (vph) | 99 | 4 | 6 | 430 | 698 | 144 |
| Future Volume (vph) | 99 | 4 | 6 | 430 | 698 | 144 |
| Satd. Flow (prot) | 1621 | 1450 | 1621 | 1706 | 1706 | 1450 |
| Fit Permitted | 0.950 | | 0.350 | | | |
| Satd. Flow (perm) | 1621 | 1450 | 597 | 1706 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | |
| Lane Group Flow (vph) | 99 | 4 | 6 | 430 | 698 | 144 |
| Turn Type | Perm | Perm | Perm | NA | NA | Perm |
| Protected Phases | | | | 2 | 6 | |
| Permitted Phases | 4 | 4 | 2 | | | 6 |
| Detector Phase | 4 | 4 | 2 | 2 | 6 | 6 |
| Switch Phase | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 |
| Minimum Split (s) | 28.3 | 28.3 | 23.6 | 23.6 | 23.6 | 23.6 |
| Total Split (s) | 29.0 | 29.0 | 61.0 | 61.0 | 61.0 | 61.0 |
| Total Split (%) | 32.2% | 32.2% | 67.8% | 67.8% | 67.8% | 67.8% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 |
| All-Red Time (s) | 2.0 | 2.0 | 2.3 | 2.3 | 2.3 | 2.3 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 5.3 | 5.3 | 5.6 | 5.6 | 5.6 | 5.6 |
| Lead/Lag | | | | | | |
| Lead-Lag Optimize? | | | | | | |
| Recall Mode | None | None | C-Max | C-Max | C-Max | C-Max |
| Act Effct Green (s) | 13.3 | 13.3 | 70.0 | 70.0 | 70.0 | 70.0 |
| Actuated g/C Ratio | 0.15 | 0.15 | 0.78 | 0.78 | 0.78 | 0.78 |
| v/c Ratio | 0.41 | 0.02 | 0.01 | 0.32 | 0.53 | 0.13 |
| Control Delay | 38.7 | 29.0 | 5.2 | 5.5 | 7.9 | 4.6 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Total Delay | 38.7 | 29.0 | 5.2 | 5.5 | 7.9 | 4.6 |
| LOS | D | C | A | A | A | A |
| Approach Delay | 38.4 | | | 5.5 | 7.3 | |
| Approach LOS | D | | | A | A | |
| Queue Length 50th (m) | 16.1 | 0.6 | 0.3 | 25.2 | 38.8 | 5.2 |
| Queue Length 95th (m) | 26.2 | 3.0 | m1.2 | 34.1 | 104.9 | 16.9 |
| Internal Link Dist (m) | 209.1 | | | 273.4 | 275.6 | |
| Turn Bay Length (m) | 38.5 | | 27.5 | | | |
| Base Capacity (vph) | 426 | 381 | 464 | 1326 | 1326 | 1127 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.23 | 0.01 | 0.01 | 0.32 | 0.53 | 0.13 |

| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 90 |
| Actuated Cycle Length: | 90 |
| Offset: | 0 (0%), Referenced to phase 2:NBL and 6:SBT, Start of Green |
| Natural Cycle: | 65 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
10: Borrisokane & New Collector

Caivan Conservancy West
2030 Future Total PM Peak Hour

| | | |
|---|--------------------------------|---------------------|
| Maximum v/c Ratio: 0.53 | Intersection Signal Delay: 9.1 | Intersection LOS: A |
| Intersection Capacity Utilization 56.2% | ICU Level of Service B | |
| Analysis Period (min) 15 | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |

Splits and Phases: 10: Borrisokane & New Collector



Appendix J

Synchro Intersection Worksheets – 2035 Future Total Conditions

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2035 Future Total AM Peak Hour


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|------|---------------|--------|-----|-------|--------|-------|
| Lane Configurations | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ | ↖ | ↗ | ↘ |
| Traffic Volume (vph) | 72 | 19 | 47 | 100 | 108 | 113 | 219 | 2873 | 86 | 53 | 1375 | 307 |
| Future Volume (vph) | 72 | 19 | 47 | 100 | 108 | 113 | 219 | 2873 | 86 | 53 | 1375 | 307 |
| Satd. Flow (prot) | 1243 | 1160 | 1450 | 1589 | 1353 | 0 | 3144 | 3223 | 0 | 1476 | 3090 | 1395 |
| Fit Permitted | 0.460 | | | 0.745 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 602 | 1160 | 1431 | 1245 | 1353 | 0 | 3144 | 3223 | 0 | 1476 | 3090 | 1395 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 72 | 19 | 47 | 100 | 221 | 0 | 219 | 2959 | 0 | 53 | 1375 | 307 |
| Turn Type | Perm | NA | Perm | Perm | NA | Prot | NA | Prot | NA | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | 4 | 8 | | | 5 | 2 | | 1 | 6 | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 39.9 | 39.9 | 39.9 | 32.9 | 32.9 | | 11.4 | 30.4 | | 11.4 | 39.4 | 39.4 |
| Total Split (s) | 41.0 | 41.0 | 41.0 | 41.0 | 41.0 | | 17.4 | 66.6 | | 12.4 | 61.6 | 61.6 |
| Total Split (%) | 34.2% | 34.2% | 34.2% | 34.2% | 34.2% | | 14.5% | 55.5% | | 10.3% | 51.3% | 51.3% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.6 | 3.6 | 3.6 | 3.6 | 3.6 | | 1.8 | 1.8 | | 1.8 | 1.8 | 1.8 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.9 | 6.9 | 6.9 | 6.9 | 6.9 | | 6.4 | 6.4 | | 6.4 | 6.4 | 6.4 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 24.8 | 24.8 | 24.8 | 24.8 | 24.8 | | 12.7 | 69.3 | | 8.8 | 62.8 | 62.8 |
| Actuated g/C Ratio | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | | 0.11 | 0.58 | | 0.07 | 0.52 | 0.52 |
| v/c Ratio | 0.58 | 0.08 | 0.16 | 0.39 | 0.79 | | 0.66 | 1.59 | | 0.50 | 0.85 | 0.42 |
| Control Delay | 60.0 | 35.6 | 37.4 | 43.8 | 64.3 | | 66.7 | 284.8 | | 69.4 | 32.4 | 21.4 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 60.0 | 35.6 | 37.4 | 43.8 | 64.3 | | 66.7 | 284.8 | | 69.4 | 32.4 | 21.4 |
| LOS | E | D | D | D | E | | E | F | | E | C | C |
| Approach Delay | | 49.0 | | | 57.9 | | | 269.8 | | | 31.6 | |
| Approach LOS | | D | | | E | | | F | | | C | |
| Queue Length 50th (m) | 15.2 | 3.6 | 9.0 | 20.2 | 49.1 | | 25.1 | ~545.5 | | 11.9 | 142.8 | 43.1 |
| Queue Length 95th (m) | 28.6 | 9.1 | 17.6 | 33.2 | 70.2 | | m15.0 m#259.8 | | | #32.4 | #210.5 | 73.5 |
| Internal Link Dist (m) | | 172.9 | | | 177.4 | | | 1040.6 | | | 345.0 | |
| Turn Bay Length (m) | 70.0 | | 150.0 | 50.0 | | | 130.0 | | | 180.0 | | 60.0 |
| Base Capacity (vph) | 171 | 329 | 406 | 353 | 384 | | 336 | 1861 | | 107 | 1618 | 730 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.42 | 0.06 | 0.12 | 0.28 | 0.58 | | 0.65 | 1.59 | | 0.50 | 0.85 | 0.42 |

| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 69 (58%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 125 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2035 Future Total AM Peak Hour

| | | |
|---|----------------------------------|---------------------|
| Maximum v/c Ratio: 1.59 | Intersection Signal Delay: 174.5 | Intersection LOS: F |
| Intersection Capacity Utilization 134.7% | ICU Level of Service H | |
| Analysis Period (min) 15 | | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | | |
| Queue shown is maximum after two cycles. | | |
| # 95th percentile volume exceeds capacity, queue may be longer. | | |
| Queue shown is maximum after two cycles. | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |



Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2035 Future Total AM Peak Hour


| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|--------|--------|---------|-------|--------|-------|--------|-------|-------|-------|-------|-----|
| Lane Configurations | ↔ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ |
| Traffic Volume (vph) | 117 | 798 | 574 | 98 | 1663 | 52 | 1187 | 49 | 195 | 69 | 23 | 230 |
| Future Volume (vph) | 117 | 798 | 574 | 98 | 1663 | 52 | 1187 | 49 | 195 | 69 | 23 | 230 |
| Satd. Flow (prot) | 1589 | 3119 | 1332 | 1621 | 3210 | 1345 | 3113 | 1673 | 1450 | 1605 | 1474 | 0 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1589 | 3119 | 1332 | 1621 | 3210 | 1345 | 3113 | 1673 | 1450 | 1605 | 1474 | 0 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 117 | 798 | 574 | 98 | 1663 | 52 | 1187 | 49 | 195 | 69 | 253 | 0 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Detector Phase | 5 | 2 | 2 | 1 | 6 | 6 | 3 | 8 | 8 | 7 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | |
| Minimum Split (s) | 11.6 | 33.6 | 33.6 | 11.6 | 33.6 | 33.6 | 11.7 | 33.7 | 33.7 | 11.7 | 33.7 | |
| Total Split (s) | 13.0 | 48.7 | 48.7 | 11.6 | 47.3 | 47.3 | 26.0 | 41.8 | 41.8 | 17.9 | 33.7 | |
| Total Split (%) | 10.8% | 40.6% | 40.6% | 9.7% | 39.4% | 39.4% | 21.7% | 34.8% | 34.8% | 14.9% | 28.1% | |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | |
| All-Red Time (s) | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 3.4 | 3.4 | 3.4 | 3.4 | 3.4 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | |
| Lead/Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 9.3 | 42.1 | 42.1 | 7.9 | 40.7 | 40.7 | 19.3 | 36.4 | 36.4 | 9.6 | 24.1 | |
| Actuated g/C Ratio | 0.08 | 0.35 | 0.35 | 0.07 | 0.34 | 0.34 | 0.16 | 0.30 | 0.30 | 0.08 | 0.20 | |
| v/c Ratio | 0.95 | 0.73 | 1.23 | 0.92 | 1.53 | 0.11 | 2.37 | 0.10 | 0.44 | 0.54 | 0.86 | |
| Control Delay | 122.1 | 22.9 | 139.8 | 125.0 | 273.0 | 28.2 | 648.0 | 31.9 | 38.3 | 68.3 | 72.2 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 122.1 | 22.9 | 139.8 | 125.0 | 273.0 | 28.2 | 648.0 | 31.9 | 38.3 | 68.3 | 72.2 | |
| LOS | F | C | F | F | F | C | F | C | D | E | E | |
| Approach Delay | | 75.8 | | | 258.0 | | | 543.8 | | | 71.4 | |
| Approach LOS | | E | | | F | | | F | | | E | |
| Queue Length 50th (m) | ~33.8 | 47.6 | ~165.3 | ~28.8 | ~284.6 | 8.3 | ~233.4 | 8.3 | 37.0 | 15.5 | 55.9 | |
| Queue Length 95th (m) | m#50.2 | m#64.6 | m#211.8 | #64.9 | #326.4 | 17.4 | #273.3 | 17.7 | 59.3 | 30.3 | #92.0 | |
| Internal Link Dist (m) | | 1040.6 | | | 387.1 | | | 275.6 | | | 103.1 | |
| Turn Bay Length (m) | 90.0 | | 90.0 | 50.0 | | 27.5 | 160.0 | | 57.5 | 17.0 | | |
| Base Capacity (vph) | 123 | 1094 | 467 | 106 | 1088 | 456 | 500 | 512 | 444 | 149 | 331 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 0.95 | 0.73 | 1.23 | 0.92 | 1.53 | 0.11 | 2.37 | 0.10 | 0.44 | 0.46 | 0.76 | |

| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 120 |
| Actuated Cycle Length: | 120 |
| Offset: | 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green |
| Natural Cycle: | 125 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2035 Future Total AM Peak Hour

| | |
|---|--------|
| Maximum v/c Ratio: | 2.37 |
| Intersection Signal Delay: | 273.4 |
| Intersection LOS: | F |
| Intersection Capacity Utilization: | 129.6% |
| ICU Level of Service: | H |
| Analysis Period (min): | 15 |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2035 Future Total AM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-----|-------|-------|-----|-------|-------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 149 | 0 | 10 | 12 | 0 | 49 | 4 | 415 | 5 | 22 | 185 | 64 |
| Future Volume (vph) | 149 | 0 | 10 | 12 | 0 | 49 | 4 | 415 | 5 | 22 | 185 | 64 |
| Satd. Flow (prot) | 1621 | 1450 | 0 | 1621 | 1450 | 0 | 1621 | 1702 | 0 | 1621 | 1706 | 1450 |
| Fit Permitted | 0.725 | | | 0.751 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1237 | 1450 | 0 | 1281 | 1450 | 0 | 1621 | 1702 | 0 | 1621 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 149 | 10 | 0 | 12 | 49 | 0 | 4 | 420 | 0 | 22 | 185 | 64 |
| Turn Type | Perm | NA | | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | | | | | | | 6 |
| Detector Phase | 4 | 4 | | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 25.6 | | 11.6 | 25.6 | 25.6 |
| Total Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 12.0 | 43.7 | | 13.0 | 44.7 | 44.7 |
| Total Split (%) | 37.0% | 37.0% | | 37.0% | 37.0% | | 13.3% | 48.6% | | 14.4% | 49.7% | 49.7% |
| Yellow Time (s) | 3.3 | 3.3 | | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.0 | 3.0 | | 3.0 | 3.0 | | 2.0 | 2.0 | | 2.0 | 2.0 | 2.0 |
| Lost Time Adjust (s) | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.3 | 6.3 | | 6.3 | 6.3 | | 6.6 | 6.6 | | 6.6 | 6.6 | 6.6 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 17.1 | 17.1 | | 17.1 | 17.1 | | 5.6 | 54.6 | | 6.4 | 57.6 | 57.6 |
| Actuated g/C Ratio | 0.19 | 0.19 | | 0.19 | 0.19 | | 0.06 | 0.61 | | 0.07 | 0.64 | 0.64 |
| v/c Ratio | 0.64 | 0.04 | | 0.05 | 0.18 | | 0.04 | 0.41 | | 0.19 | 0.17 | 0.07 |
| Control Delay | 44.6 | 25.8 | | 26.2 | 29.2 | | 40.8 | 14.1 | | 43.2 | 8.4 | 8.8 |
| Queue Delay | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 44.6 | 25.8 | | 26.2 | 29.2 | | 40.8 | 14.1 | | 43.2 | 8.4 | 8.8 |
| LOS | D | C | | C | C | | D | B | | D | A | A |
| Approach Delay | | 43.4 | | | 28.6 | | | 14.4 | | | 11.3 | |
| Approach LOS | | D | | | C | | | B | | | B | |
| Queue Length 50th (m) | 24.0 | 1.4 | | 1.7 | 7.2 | | 0.7 | 26.8 | | 3.7 | 9.8 | 3.2 |
| Queue Length 95th (m) | 36.8 | 4.8 | | 5.3 | 14.1 | | 3.8 | 83.8 | | 11.8 | 21.8 | 9.7 |
| Internal Link Dist (m) | | 145.0 | | | 184.4 | | | 650.0 | | | 273.4 | |
| Turn Bay Length (m) | 9.3 | | | 9.3 | | | 84.0 | | | 84.5 | | 83.0 |
| Base Capacity (vph) | 371 | 435 | | 384 | 435 | | 101 | 1032 | | 120 | 1092 | 928 |
| Starvation Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.40 | 0.02 | | 0.03 | 0.11 | | 0.04 | 0.41 | | 0.18 | 0.17 | 0.07 |


| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 90 | | | | | | | | | | | | |
| Actuated Cycle Length: 90 | | | | | | | | | | | | |
| Offset: 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 75 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2035 Future Total AM Peak Hour

| | | |
|---|---------------------------------|---------------------|
| Maximum v/c Ratio: 0.64 | Intersection Signal Delay: 19.5 | Intersection LOS: B |
| Intersection Capacity Utilization 49.5% | ICU Level of Service A | |
| Analysis Period (min) 15 | | |

Splits and Phases: 9: Borriskane & Conservancy Way



Lanes, Volumes, Timings
10: Borrisokane & New Collector/BRT

Caivan Conservancy West
2035 Future Total AM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|------|-------|-------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 152 | 4 | 6 | 0 | 4 | 0 | 3 | 610 | 0 | 0 | 265 | 65 |
| Future Volume (vph) | 152 | 4 | 6 | 0 | 4 | 0 | 3 | 610 | 0 | 0 | 265 | 65 |
| Satd. Flow (prot) | 1621 | 1706 | 1450 | 0 | 1706 | 0 | 1621 | 1706 | 0 | 0 | 1706 | 1450 |
| Fit Permitted | 0.755 | | | | | | 0.596 | | | | | |
| Satd. Flow (perm) | 1288 | 1706 | 1450 | 0 | 1706 | 0 | 1017 | 1706 | 0 | 0 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 152 | 4 | 6 | 0 | 4 | 0 | 3 | 610 | 0 | 0 | 265 | 65 |
| Turn Type | Perm | NA | Perm | NA | NA | Perm | NA | NA | NA | NA | Perm | Perm |
| Protected Phases | | 4 | | | 8 | | 2 | 2 | | | 6 | 6 |
| Permitted Phases | 4 | | 4 | 8 | | | 2 | | | 6 | | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 2 | 2 | | 6 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 | 10.0 | 10.0 |
| Minimum Split (s) | 31.8 | 31.8 | 31.8 | 31.8 | 31.8 | | 31.8 | 31.8 | | 31.8 | 31.8 | 31.8 |
| Total Split (s) | 33.0 | 33.0 | 33.0 | 33.0 | 33.0 | | 57.0 | 57.0 | | 57.0 | 57.0 | 57.0 |
| Total Split (%) | 36.7% | 36.7% | 36.7% | 36.7% | 36.7% | | 63.3% | 63.3% | | 63.3% | 63.3% | 63.3% |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | | 3.3 | 3.3 | | 3.3 | 3.3 | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 | 3.5 | 3.5 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | | 6.8 | 6.8 | | 6.8 | 6.8 | 6.8 |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | C-Max | C-Max | | C-Max | C-Max | C-Max |
| Act Effct Green (s) | 16.3 | 16.3 | 16.3 | 16.3 | 16.3 | | 60.1 | 60.1 | | 60.1 | 60.1 | 60.1 |
| Actuated g/C Ratio | 0.18 | 0.18 | 0.18 | 0.18 | 0.18 | | 0.67 | 0.67 | | 0.67 | 0.67 | 0.67 |
| v/c Ratio | 0.65 | 0.01 | 0.02 | 0.01 | 0.01 | | 0.00 | 0.54 | | 0.23 | 0.07 | 0.07 |
| Control Delay | 46.4 | 26.5 | 26.8 | 26.5 | 26.5 | | 7.0 | 9.7 | | 7.5 | 6.8 | 6.8 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 46.4 | 26.5 | 26.8 | 26.5 | 26.5 | | 7.0 | 9.7 | | 7.5 | 6.8 | 6.8 |
| LOS | D | C | C | C | C | | A | A | | A | A | A |
| Approach Delay | | 45.2 | | | 26.5 | | | 9.7 | | | 7.3 | |
| Approach LOS | | D | | | C | | | A | | | A | |
| Queue Length 50th (m) | 24.5 | 0.6 | 0.9 | 0.6 | 0.6 | | 0.2 | 44.4 | | 15.4 | 3.3 | 3.3 |
| Queue Length 95th (m) | 39.2 | 2.9 | 3.6 | 2.9 | 2.9 | | m0.6 | 56.6 | | 33.4 | 9.7 | 9.7 |
| Internal Link Dist (m) | | 113.8 | | | 68.5 | | | 273.4 | | | 275.6 | |
| Turn Bay Length (m) | 38.5 | | | | | | 27.5 | | | | | |
| Base Capacity (vph) | 374 | 496 | 422 | 496 | 496 | | 678 | 1138 | | 1138 | 967 | 967 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.41 | 0.01 | 0.01 | 0.01 | 0.01 | | 0.00 | 0.54 | | 0.23 | 0.07 | 0.07 |

| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 90 | | | | | | | | | | | | |
| Actuated Cycle Length: 90 | | | | | | | | | | | | |
| Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SRTL, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 65 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
10: Borrisokane & New Collector/BRT

Caivan Conservancy West
2035 Future Total AM Peak Hour

| | | |
|---|---------------------------------|---------------------|
| Maximum v/c Ratio: 0.65 | Intersection Signal Delay: 14.2 | Intersection LOS: B |
| Intersection Capacity Utilization 63.4% | ICU Level of Service B | |
| Analysis Period (min) 15 | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |

Splits and Phases: 10: Borrisokane & New Collector/BRT



Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2035 Future Total PM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|--------|-------|-------|-------|-------|-----|-------|---------|-----|-------|--------|-------|
| Lane Configurations | ↖ | → | ↗ | ↖ | → | ↗ | ↖ | → | ↗ | ↖ | → | ↗ |
| Traffic Volume (vph) | 275 | 96 | 188 | 128 | 26 | 92 | 66 | 1940 | 132 | 85 | 2823 | 108 |
| Future Volume (vph) | 275 | 96 | 188 | 128 | 26 | 92 | 66 | 1940 | 132 | 85 | 2823 | 108 |
| Satd. Flow (prot) | 1605 | 1706 | 1450 | 1517 | 1440 | 0 | 3144 | 3174 | 0 | 1589 | 3241 | 1450 |
| Fit Permitted | 0.681 | | | 0.695 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1150 | 1706 | 1431 | 1108 | 1440 | 0 | 3144 | 3174 | 0 | 1589 | 3241 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 275 | 96 | 188 | 128 | 118 | 0 | 66 | 2072 | 0 | 85 | 2823 | 108 |
| Turn Type | Perm | NA | Perm | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | 4 | 8 | | | 5 | 2 | | 1 | 6 | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 39.9 | 39.9 | 39.9 | 32.9 | 32.9 | | 11.4 | 30.4 | | 11.4 | 39.4 | 39.4 |
| Total Split (s) | 39.9 | 39.9 | 39.9 | 39.9 | 39.9 | | 11.4 | 68.1 | | 12.0 | 68.7 | 68.7 |
| Total Split (%) | 33.3% | 33.3% | 33.3% | 33.3% | 33.3% | | 9.5% | 56.8% | | 10.0% | 57.3% | 57.3% |
| Yellow Time (s) | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.6 | 3.6 | 3.6 | 3.6 | 3.6 | | 1.8 | 1.8 | | 1.8 | 1.8 | 1.8 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.9 | 6.9 | 6.9 | 6.9 | 6.9 | | 6.4 | 6.4 | | 6.4 | 6.4 | 6.4 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 31.0 | 31.0 | 31.0 | 31.0 | 31.0 | | 5.5 | 61.7 | | 7.6 | 66.2 | 66.2 |
| Actuated g/C Ratio | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | | 0.05 | 0.51 | | 0.06 | 0.55 | 0.55 |
| v/c Ratio | 0.93 | 0.22 | 0.51 | 0.45 | 0.32 | | 0.46 | 1.27 | | 0.85 | 1.58 | 0.14 |
| Control Delay | 79.9 | 35.6 | 42.9 | 42.3 | 37.8 | | 73.8 | 140.0 | | 113.1 | 287.6 | 15.1 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 79.9 | 35.6 | 42.9 | 42.3 | 37.8 | | 73.8 | 140.0 | | 113.1 | 287.6 | 15.1 |
| LOS | E | D | D | D | D | | E | F | | F | F | B |
| Approach Delay | | 59.8 | | | 40.1 | | | 137.9 | | | 272.9 | |
| Approach LOS | | E | | | D | | | F | | | F | |
| Queue Length 50th (m) | 61.0 | 17.2 | 36.5 | 24.4 | 21.7 | | 7.5 | ~325.9 | | ~23.2 | ~504.3 | 12.6 |
| Queue Length 95th (m) | #108.3 | 31.1 | 59.0 | 42.9 | 37.9 | | m6.7 | m#218.6 | | #55.1 | #542.2 | 22.4 |
| Internal Link Dist (m) | | 172.9 | | | 177.4 | | | 1040.6 | | | 345.0 | |
| Turn Bay Length (m) | 70.0 | | 150.0 | 50.0 | | | 130.0 | | | 180.0 | | 60.0 |
| Base Capacity (vph) | 316 | 469 | 393 | 304 | 396 | | 143 | 1631 | | 100 | 1788 | 800 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.87 | 0.20 | 0.48 | 0.42 | 0.30 | | 0.46 | 1.27 | | 0.85 | 1.58 | 0.14 |


| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 120 | | | | | | | | | | | | |
| Actuated Cycle Length: 120 | | | | | | | | | | | | |
| Offset: 64 (53%), Referenced to phase 2:NBT and 6:SBT, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 125 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
1: Strandherd & Dealership/Kennevale

Caivan Conservancy West
2035 Future Total PM Peak Hour

| | | |
|---|----------------------------------|---------------------|
| Maximum v/c Ratio: 1.58 | Intersection Signal Delay: 194.9 | Intersection LOS: F |
| Intersection Capacity Utilization 120.4% | ICU Level of Service H | |
| Analysis Period (min) 15 | | |
| ~ Volume exceeds capacity, queue is theoretically infinite. | | |
| Queue shown is maximum after two cycles. | | |
| # 95th percentile volume exceeds capacity, queue may be longer. | | |
| Queue shown is maximum after two cycles. | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |

Splits and Phases: 1: Strandherd & Dealership/Kennevale



Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2035 Future Total PM Peak Hour


| | ↖ | → | ↘ | ↙ | ← | ↖ | ↙ | ↑ | ↗ | ↘ | ↓ | ↙ |
|------------------------|--------|--------|---------|--------|--------|-------|--------|-------|-------|-------|-------|-----|
| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | ↖ | ↖↗ | ↖ | ↖ | ↖↗ | ↖ | ↖↗ | ↖ | ↖ | ↖ | ↖ | ↖ |
| Traffic Volume (vph) | 322 | 1673 | 1199 | 192 | 1128 | 65 | 792 | 34 | 159 | 52 | 49 | 122 |
| Future Volume (vph) | 322 | 1673 | 1199 | 192 | 1128 | 65 | 792 | 34 | 159 | 52 | 49 | 122 |
| Satd. Flow (prot) | 1605 | 3241 | 1436 | 1621 | 3210 | 1436 | 2969 | 1706 | 1309 | 1503 | 1472 | 0 |
| Fit Permitted | 0.950 | | | 0.950 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1605 | 3241 | 1436 | 1621 | 3210 | 1436 | 2969 | 1706 | 1309 | 1503 | 1472 | 0 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 322 | 1673 | 1199 | 192 | 1128 | 65 | 792 | 34 | 159 | 52 | 171 | 0 |
| Turn Type | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | Perm | Prot | NA | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Detector Phase | 5 | 2 | 2 | 1 | 6 | 6 | 3 | 8 | 8 | 7 | 4 | |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | 10.0 | 5.0 | 10.0 | |
| Minimum Split (s) | 11.6 | 33.6 | 33.6 | 11.6 | 33.6 | 33.6 | 11.7 | 34.0 | 34.0 | 11.7 | 33.7 | |
| Total Split (s) | 17.0 | 55.3 | 55.3 | 12.0 | 50.3 | 50.3 | 19.0 | 35.5 | 35.5 | 17.2 | 33.7 | |
| Total Split (%) | 14.2% | 46.1% | 46.1% | 10.0% | 41.9% | 41.9% | 15.8% | 29.6% | 29.6% | 14.3% | 28.1% | |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | 3.3 | 3.3 | 3.3 | 3.3 | 3.3 | |
| All-Red Time (s) | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 3.4 | 3.4 | 3.4 | 3.4 | 3.4 | |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Lost Time (s) | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.6 | 6.7 | 6.7 | 6.7 | 6.7 | 6.7 | |
| Lead/Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | Lag | Lead | Lag | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | C-Max | C-Max | None | C-Max | C-Max | None | None | None | None | None | |
| Act Effct Green (s) | 18.1 | 48.7 | 48.7 | 13.1 | 43.7 | 43.7 | 12.3 | 25.2 | 25.2 | 8.8 | 19.3 | |
| Actuated g/C Ratio | 0.15 | 0.41 | 0.41 | 0.11 | 0.36 | 0.36 | 0.10 | 0.21 | 0.21 | 0.07 | 0.16 | |
| v/c Ratio | 1.33 | 1.27 | 2.06 | 1.08 | 0.97 | 0.12 | 2.61 | 0.09 | 0.58 | 0.48 | 0.72 | |
| Control Delay | 200.5 | 147.2 | 497.9 | 142.3 | 57.1 | 26.3 | 754.0 | 39.1 | 52.3 | 67.2 | 64.5 | |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| Total Delay | 200.5 | 147.2 | 497.9 | 142.3 | 57.1 | 26.3 | 754.0 | 39.1 | 52.3 | 67.2 | 64.5 | |
| LOS | F | F | F | F | E | C | F | D | D | E | E | |
| Approach Delay | | 284.2 | | | 67.5 | | | 616.0 | | | 65.1 | |
| Approach LOS | | F | | | E | | | F | | | E | |
| Queue Length 50th (m) | -97.9 | -255.0 | -437.3 | -49.7 | 134.1 | 10.0 | -159.4 | 6.7 | 34.7 | 11.7 | 38.2 | |
| Queue Length 95th (m) | m#78.7 | m#84.5 | m#257.7 | #120.2 | #179.0 | 19.9 | #196.5 | 14.5 | 53.8 | 24.4 | 57.2 | |
| Internal Link Dist (m) | | 1040.6 | | | 371.1 | | | 275.6 | | | 103.1 | |
| Turn Bay Length (m) | 90.0 | | 90.0 | 50.0 | | 27.5 | 160.0 | | 57.5 | 17.0 | | |
| Base Capacity (vph) | 242 | 1315 | 582 | 177 | 1168 | 522 | 304 | 415 | 318 | 131 | 331 | |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Reduced v/c Ratio | 1.33 | 1.27 | 2.06 | 1.08 | 0.97 | 0.12 | 2.61 | 0.08 | 0.50 | 0.40 | 0.52 | |

| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 120 |
| Actuated Cycle Length: | 120 |
| Offset: | 0 (0%), Referenced to phase 2:EBT and 6:WBT, Start of Green |
| Natural Cycle: | 125 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
2: Borriskane/Tartan & Strandherd

Caivan Conservancy West
2035 Future Total PM Peak Hour

| | |
|---|--------|
| Maximum v/c Ratio: | 2.61 |
| Intersection Signal Delay: | 280.4 |
| Intersection LOS: | F |
| Intersection Capacity Utilization: | 116.8% |
| ICU Level of Service: | H |
| Analysis Period (min): | 15 |
| ~ Volume exceeds capacity, queue is theoretically infinite. | |
| Queue shown is maximum after two cycles. | |
| # 95th percentile volume exceeds capacity, queue may be longer. | |
| Queue shown is maximum after two cycles. | |
| m Volume for 95th percentile queue is metered by upstream signal. | |



Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2035 Future Total PM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-----|-------|-------|-----|-------|--------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 96 | 0 | 6 | 8 | 0 | 32 | 9 | 259 | 12 | 49 | 429 | 141 |
| Future Volume (vph) | 96 | 0 | 6 | 8 | 0 | 32 | 9 | 259 | 12 | 49 | 429 | 141 |
| Satd. Flow (prot) | 1621 | 1450 | 0 | 1621 | 1450 | 0 | 1621 | 1694 | 0 | 1621 | 1706 | 1450 |
| Fit Permitted | 0.736 | | | 0.754 | | | 0.950 | | | 0.950 | | |
| Satd. Flow (perm) | 1256 | 1450 | 0 | 1286 | 1450 | 0 | 1621 | 1694 | 0 | 1621 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 96 | 6 | 0 | 8 | 32 | 0 | 9 | 271 | 0 | 49 | 429 | 141 |
| Turn Type | Perm | NA | | Perm | NA | | Prot | NA | | Prot | NA | Perm |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | | 6 |
| Permitted Phases | 4 | | | 8 | | | | | | | | 6 |
| Detector Phase | 4 | 4 | | 8 | 8 | | 5 | 2 | | 1 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | | 10.0 | 10.0 | | 5.0 | 10.0 | | 5.0 | 10.0 | 10.0 |
| Minimum Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 11.6 | 25.6 | | 11.6 | 25.6 | 25.6 |
| Total Split (s) | 33.3 | 33.3 | | 33.3 | 33.3 | | 12.0 | 42.7 | | 14.0 | 44.7 | 44.7 |
| Total Split (%) | 37.0% | 37.0% | | 37.0% | 37.0% | | 13.3% | 47.4% | | 15.6% | 49.7% | 49.7% |
| Yellow Time (s) | 3.3 | 3.3 | | 3.3 | 3.3 | | 4.6 | 4.6 | | 4.6 | 4.6 | 4.6 |
| All-Red Time (s) | 3.0 | 3.0 | | 3.0 | 3.0 | | 2.0 | 2.0 | | 2.0 | 2.0 | 2.0 |
| Lost Time Adjust (s) | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.3 | 6.3 | | 6.3 | 6.3 | | 6.6 | 6.6 | | 6.6 | 6.6 | 6.6 |
| Lead/Lag | | | | | | | Lead | Lag | | Lead | Lag | Lag |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | | None | None | | None | C-Max | | None | C-Max | C-Max |
| Act Effct Green (s) | 14.8 | 14.8 | | 14.8 | 14.8 | | 5.8 | 58.0 | | 7.4 | 64.5 | 64.5 |
| Actuated g/C Ratio | 0.16 | 0.16 | | 0.16 | 0.16 | | 0.06 | 0.64 | | 0.08 | 0.72 | 0.72 |
| v/c Ratio | 0.47 | 0.03 | | 0.04 | 0.13 | | 0.09 | 0.25 | | 0.37 | 0.35 | 0.14 |
| Control Delay | 39.7 | 27.0 | | 27.4 | 30.2 | | 41.7 | 12.6 | | 41.0 | 11.8 | 11.5 |
| Queue Delay | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 39.7 | 27.0 | | 27.4 | 30.2 | | 41.7 | 12.6 | | 41.0 | 11.8 | 11.5 |
| LOS | D | C | | C | C | | D | B | | D | B | B |
| Approach Delay | | 39.0 | | | 29.6 | | | 13.5 | | | 14.1 | |
| Approach LOS | | D | | | C | | | B | | | B | |
| Queue Length 50th (m) | 15.6 | 0.9 | | 1.2 | 4.9 | | 1.5 | 22.7 | | 7.9 | 22.9 | 6.2 |
| Queue Length 95th (m) | 24.7 | 3.4 | | 4.0 | 10.3 | | 6.0 | 52.0 | | m19.2 | 68.7 | 28.3 |
| Internal Link Dist (m) | | 154.2 | | | 129.4 | | | 1276.6 | | | 273.4 | |
| Turn Bay Length (m) | 9.3 | | | 9.3 | | | 84.0 | | | 84.5 | | 83.0 |
| Base Capacity (vph) | 376 | 435 | | 385 | 435 | | 104 | 1091 | | 142 | 1223 | 1039 |
| Starvation Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.26 | 0.01 | | 0.02 | 0.07 | | 0.09 | 0.25 | | 0.35 | 0.35 | 0.14 |


| Intersection Summary | |
|------------------------|---|
| Cycle Length: | 90 |
| Actuated Cycle Length: | 90 |
| Offset: | 0 (0%), Referenced to phase 2:NBT and 6:SBT, Start of Green |
| Natural Cycle: | 75 |
| Control Type: | Actuated-Coordinated |

Lanes, Volumes, Timings
9: Borriskane & Conservancy Way

Caivan Conservancy West
2035 Future Total PM Peak Hour

| | |
|---|-------|
| Maximum v/c Ratio: | 0.47 |
| Intersection Signal Delay: | 17.0 |
| Intersection Capacity Utilization: | 56.5% |
| Analysis Period (min): | 15 |
| Intersection LOS: | B |
| ICU Level of Service: | B |
| m Volume for 95th percentile queue is metered by upstream signal. | |

Splits and Phases: 9: Borriskane & Conservancy Way



Lanes, Volumes, Timings
10: Borrisokane & New Collector/BRT

Caivan Conservancy West
2035 Future Total PM Peak Hour

| Lane Group | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|-------|-------|-------|-------|------|-------|-------|-----|-------|-------|-------|
| Lane Configurations | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Traffic Volume (vph) | 99 | 4 | 4 | 0 | 4 | 0 | 6 | 381 | 0 | 0 | 615 | 144 |
| Future Volume (vph) | 99 | 4 | 4 | 0 | 4 | 0 | 6 | 381 | 0 | 0 | 615 | 144 |
| Satd. Flow (prot) | 1621 | 1706 | 1450 | 0 | 1706 | 0 | 1621 | 1706 | 0 | 0 | 1706 | 1450 |
| Fit Permitted | 0.755 | | | | | | 0.388 | | | | | |
| Satd. Flow (perm) | 1288 | 1706 | 1450 | 0 | 1706 | 0 | 662 | 1706 | 0 | 0 | 1706 | 1450 |
| Satd. Flow (RTOR) | | | | | | | | | | | | |
| Lane Group Flow (vph) | 99 | 4 | 4 | 0 | 4 | 0 | 6 | 381 | 0 | 0 | 615 | 144 |
| Turn Type | Perm | NA | Perm | NA | NA | Perm | NA | NA | NA | NA | Perm | Perm |
| Protected Phases | | 4 | | | 8 | | 2 | 2 | | | 6 | 6 |
| Permitted Phases | 4 | | 4 | 8 | | | 2 | | | 6 | | 6 |
| Detector Phase | 4 | 4 | 4 | 8 | 8 | | 2 | 2 | | 6 | 6 | 6 |
| Switch Phase | | | | | | | | | | | | |
| Minimum Initial (s) | 10.0 | 10.0 | 10.0 | 5.0 | 5.0 | | 10.0 | 10.0 | | 10.0 | 10.0 | 10.0 |
| Minimum Split (s) | 30.8 | 30.8 | 30.8 | 30.8 | 30.8 | | 31.8 | 31.8 | | 31.8 | 31.8 | 31.8 |
| Total Split (s) | 32.0 | 32.0 | 32.0 | 32.0 | 32.0 | | 58.0 | 58.0 | | 58.0 | 58.0 | 58.0 |
| Total Split (%) | 35.6% | 35.6% | 35.6% | 35.6% | 35.6% | | 64.4% | 64.4% | | 64.4% | 64.4% | 64.4% |
| Yellow Time (s) | 4.6 | 4.6 | 4.6 | 4.6 | 4.6 | | 3.3 | 3.3 | | 3.3 | 3.3 | 3.3 |
| All-Red Time (s) | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | 3.5 | 3.5 | | 3.5 | 3.5 | 3.5 |
| Lost Time Adjust (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Lost Time (s) | 6.8 | 6.8 | 6.8 | 6.8 | 6.8 | | 6.8 | 6.8 | | 6.8 | 6.8 | 6.8 |
| Lead/Lag | | | | | | | | | | | | |
| Lead-Lag Optimize? | | | | | | | | | | | | |
| Recall Mode | None | None | None | None | None | | C-Max | C-Max | | C-Max | C-Max | C-Max |
| Act Effct Green (s) | 14.1 | 14.1 | 14.1 | 13.2 | 13.2 | | 67.0 | 67.0 | | 67.0 | 67.0 | 67.0 |
| Actuated g/C Ratio | 0.16 | 0.16 | 0.16 | 0.15 | 0.15 | | 0.74 | 0.74 | | 0.74 | 0.74 | 0.74 |
| v/c Ratio | 0.49 | 0.01 | 0.02 | 0.02 | 0.02 | | 0.01 | 0.30 | | 0.48 | 0.13 | 0.13 |
| Control Delay | 41.5 | 28.0 | 28.0 | 28.0 | 28.0 | | 6.8 | 6.9 | | 8.9 | 6.0 | 6.0 |
| Queue Delay | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | 0.0 | 0.0 | | 0.0 | 0.0 | 0.0 |
| Total Delay | 41.5 | 28.0 | 28.0 | 28.0 | 28.0 | | 6.8 | 6.9 | | 8.9 | 6.0 | 6.0 |
| LOS | D | C | C | C | C | | A | A | | A | A | A |
| Approach Delay | | 40.5 | | | 28.0 | | | 6.9 | | | 8.4 | |
| Approach LOS | | D | | | C | | | A | | | A | |
| Queue Length 50th (m) | 16.1 | 0.6 | 0.6 | 0.6 | 0.6 | | 0.4 | 27.1 | | 39.8 | 6.6 | 6.6 |
| Queue Length 95th (m) | 26.7 | 2.9 | 2.9 | 2.9 | 2.9 | | m1.6 | 37.5 | | 96.0 | 19.1 | 19.1 |
| Internal Link Dist (m) | | 209.1 | | | 112.8 | | | 273.4 | | | 275.6 | |
| Turn Bay Length (m) | 38.5 | | | | | | 27.5 | | | | | |
| Base Capacity (vph) | 360 | 477 | 406 | 477 | 477 | | 492 | 1269 | | 1269 | 1079 | 1079 |
| Starvation Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Spillback Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Storage Cap Reductn | 0 | 0 | 0 | 0 | 0 | | 0 | 0 | | 0 | 0 | 0 |
| Reduced v/c Ratio | 0.28 | 0.01 | 0.01 | 0.01 | 0.01 | | 0.01 | 0.30 | | 0.48 | 0.13 | 0.13 |


| Intersection Summary | | | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|--|--|
| Cycle Length: 90 | | | | | | | | | | | | |
| Actuated Cycle Length: 90 | | | | | | | | | | | | |
| Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Green | | | | | | | | | | | | |
| Natural Cycle: 65 | | | | | | | | | | | | |
| Control Type: Actuated-Coordinated | | | | | | | | | | | | |

Lanes, Volumes, Timings
10: Borrisokane & New Collector/BRT

Caivan Conservancy West
2035 Future Total PM Peak Hour

| | | |
|---|---------------------------------|---------------------|
| Maximum v/c Ratio: 0.49 | Intersection Signal Delay: 10.7 | Intersection LOS: B |
| Intersection Capacity Utilization 63.7% | ICU Level of Service B | |
| Analysis Period (min) 15 | | |
| m Volume for 95th percentile queue is metered by upstream signal. | | |

Splits and Phases: 10: Borrisokane & New Collector/BRT



Appendix K

MMLOS Analysis

Consultant Scenario Comments

| |
|--------------------|
| CGH Transportation |
| Existing/Future |
| |
| |

Project Date

| |
|------------------|
| Conservancy West |
| 7-Dec-22 |
| |
| |

| INTERSECTIONS | | Strandherd-Kennevale (Existing) | | | | Strandherd-Kennevale (Future) | | | |
|-----------------------------|--|-----------------------------------|-----------------------------------|-----------------------------|-----------------------------|-----------------------------------|-----------------------------------|-----------------------------|-----------------------------|
| Crossing Side | | NORTH | SOUTH | EAST | WEST | NORTH | SOUTH | EAST | WEST |
| Pedestrian | Lanes | 4 | 5 | 3 | 5 | 7 | 7 | 3 | 5 |
| | Median | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | Median > 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m |
| | Conflicting Left Turns | Permissive | Permissive | Permissive | Permissive | Protected | Protected | Protected | Protected |
| | Conflicting Right Turns | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control |
| | Right Turns on Red (RTor) ? | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed |
| | Ped Signal Leading Interval? | No | No | No | No | No | No | No | No |
| | Right Turn Channel | No Channel | No Channel | No Channel | No Channel | No Channel | No Channel | No Channel | No Channel |
| | Corner Radius | 10-15m | 10-15m | 5-10m | 15-25m | 10-15m | 10-15m | 15-25m | 15-25m |
| | Crosswalk Type | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings |
| | PETSI Score | 53 | 37 | 71 | 35 | 18 | 12 | 76 | 43 |
| | Ped. Exposure to Traffic LoS | D | E | C | E | F | F | B | E |
| | Cycle Length | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 |
| | Effective Walk Time | 64 | 49 | 7 | 7 | 41 | 46 | 7 | 7 |
| | Average Pedestrian Delay | 13 | 21 | 53 | 53 | 26 | 23 | 53 | 53 |
| Pedestrian Delay LoS | B | C | E | E | C | C | E | E | |
| Level of Service | D | E | E | E | F | F | E | E | |
| Approach From | | NORTH | SOUTH | EAST | WEST | NORTH | SOUTH | EAST | WEST |
| Bicycle | Bicycle Lane Arrangement on Approach | Pocket Bike Lane | Pocket Bike Lane | Mixed Traffic | Mixed Traffic | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP | Mixed Traffic | Mixed Traffic |
| | Right Turn Lane Configuration | ≤ 50 m Introduced right turn lane | > 50 m Introduced right turn lane | ≤ 50 m | ≤ 50 m | Not Applicable | Not Applicable | ≤ 50 m | ≤ 50 m |
| | Right Turning Speed | ≤ 25 km/h | ≤ 25 km/h | ≤ 25 km/h | ≤ 25 km/h | Not Applicable | Not Applicable | ≤ 25 km/h | ≤ 25 km/h |
| | Cyclist relative to RT motorists | B | D | D | D | Not Applicable | Not Applicable | D | D |
| | Separated or Mixed Traffic | Separated | Separated | Mixed Traffic | Mixed Traffic | Separated | Separated | Mixed Traffic | Mixed Traffic |
| | Left Turn Approach | 1 lane crossed | 1 lane crossed | No lane crossed | One lane crossed | 2-stage, LT box | 2-stage, LT box | No lane crossed | One lane crossed |
| | Operating Speed | ≥ 60 km/h | ≥ 60 km/h | > 40 to ≤ 50 km/h | > 50 to < 60 km/h | ≥ 60 km/h | ≥ 60 km/h | > 40 to ≤ 50 km/h | > 50 to < 60 km/h |
| | Left Turning Cyclist | E | E | B | E | A | A | B | E |
| Level of Service | E | E | D | E | A | A | D | E | |
| Level of Service | E | | | | E | | | | |
| Transit | Average Signal Delay | > 40 sec | > 40 sec | ≤ 30 sec | | > 40 sec | > 40 sec | > 40 sec | |
| | Level of Service | F | F | D | - | F | F | F | - |
| Level of Service | F | | | | F | | | | |
| Truck | Effective Corner Radius | 10 - 15 m | < 10 m | | > 15 m | 10 - 15 m | 10 - 15 m | | > 15 m |
| | Number of Receiving Lanes on Departure from Intersection | 1 | ≥ 2 | | 1 | 1 | ≥ 2 | | ≥ 2 |
| | Level of Service | E | D | - | C | E | B | - | A |
| Level of Service | E | | | | E | | | | |
| Auto | Volume to Capacity Ratio | > 1.00 | | | | > 1.00 | | | |
| | Level of Service | F | | | | F | | | |

| Strandherd-Borrisokane (Existing) | | | | Strandherd-Borrisokane (Future) | | | | New Collector/BRT-Borrisokane (Future) | | | |
|-----------------------------------|-----------------------------|-----------------------------|-----------------------------|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|--|-----------------------------------|-----------------------------------|-----------------------------------|
| NORTH | SOUTH | EAST | WEST | NORTH | SOUTH | EAST | WEST | NORTH | SOUTH | EAST | WEST |
| 4 | 3 | 3 | 4 | 3 | 4 | 5 | 6 | 5 | 4 | 4 | 5 |
| No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | Median > 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m | No Median - 2.4 m |
| Permissive | Permissive | Permissive | Permissive | Protected | Protected | Protected | Protected | Permissive | Permissive | Protected | Protected |
| Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control | Permissive or yield control |
| RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed | RTOR allowed |
| No | No | No | No | No | No | No | No | No | No | No | No |
| No Channel | No Channel | No Channel | No Channel | No Channel | No Channel | No Channel | No Channel | No Channel | No Channel | No Channel | No Channel |
| 10-15m | 10-15m | 5-10m | 15-25m | 5-10m | 5-10m | 10-15m | 10-15m | 10-15m | 10-15m | 10-15m | 10-15m |
| Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings |
| 53 | 70 | 71 | 51 | 79 | 62 | 45 | 28 | 37 | 53 | 61 | 45 |
| D | C | C | D | B | C | D | F | E | D | C | D |
| 97 | 97 | 97 | 97 | 120 | 120 | 120 | 120 | 90 | 90 | 90 | 90 |
| 24 | 24 | 40 | 40 | 7 | 9 | 21 | 22 | 32 | 32 | 8 | 8 |
| 27 | 27 | 17 | 17 | 53 | 51 | 41 | 40 | 19 | 19 | 37 | 37 |
| C | C | B | B | E | E | E | E | B | B | D | D |
| D | C | C | D | E | E | E | F | E | D | D | D |
| D | | | | F | | | | E | | | |
| NORTH | SOUTH | EAST | WEST | NORTH | SOUTH | EAST | WEST | NORTH | SOUTH | EAST | WEST |
| Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP |
| ≤ 50 m | ≤ 50 m | ≤ 50 m | > 50 m | | | | | | | | |
| ≤ 25 km/h | ≤ 25 km/h | ≤ 25 km/h | >25 km/h | | | | | | | | |
| D | D | D | F | Not Applicable | Not Applicable | Not Applicable | Not Applicable | Not Applicable | Not Applicable | Not Applicable | Not Applicable |
| Mixed Traffic | Mixed Traffic | Mixed Traffic | Mixed Traffic | Separated | Separated | Separated | Separated | Separated | Separated | Separated | Separated |
| One lane crossed | One lane crossed | One lane crossed | ≥ 2 lanes crossed | 2-stage, LT box | 2-stage, LT box | 2-stage, LT box | 2-stage, LT box | 2-stage, LT box | 2-stage, LT box | 2-stage, LT box | 2-stage, LT box |
| > 50 to < 60 km/h | > 40 to ≤ 50 km/h | ≥ 60 km/h | ≥ 60 km/h | > 40 to ≤ 50 km/h | > 50 to < 60 km/h | ≥ 60 km/h | ≥ 60 km/h | > 50 to < 60 km/h | > 50 to < 60 km/h | ≥ 60 km/h | ≥ 60 km/h |
| E | D | F | F | A | A | A | A | A | A | A | A |
| E | D | F | F | A | A | A | A | A | A | A | A |
| F | | | | A | | | | A | | | |
| ≤ 30 sec | | > 40 sec | ≤ 40 sec | > 40 sec | | > 40 sec | > 40 sec | ≤ 10 sec | ≤ 10 sec | ≤ 30 sec | ≤ 30 sec |
| D | - | F | E | F | - | F | F | B | B | D | D |
| F | | | | F | | | | D | | | |
| | 10 - 15 m | | > 15 m | | < 10 m | | 10 - 15 m | | | | |
| | 1 | | 1 | | ≥ 2 | | 1 | | | | |
| - | E | - | C | - | D | - | E | - | - | - | - |
| E | | | | E | | | | - | | | |
| | > 1.00 | | | | > 1.00 | | | | 0.0 - 0.60 | | |
| F | | | | F | | | | A | | | |

| Conservancy Way-Borrisokane (Future) | | | |
|---|-----------------------------------|-----------------------------------|-----------------------------------|
| NORTH | SOUTH | EAST | WEST |
| 4 | 4 | 3 | 3 |
| No Median - 2.4 m | No Median - 2.4 m | Median > 2.4 m | No Median - 2.4 m |
| Permissive | Permissive | No left turn / Prohib. | Permissive |
| No right turn | Permissive or yield control | No right turn | Permissive or yield control |
| RTOR allowed | RTOR prohibited | RTOR prohibited | RTOR allowed |
| No | No | No | No |
| No Right Turn | No Channel | No Right Turn | No Channel |
| 10-15m | 10-15m | 10-15m | 10-15m |
| Std transverse markings | Std transverse markings | Std transverse markings | Std transverse markings |
| 62 | 56 | 90 | 70 |
| C | D | A | C |
| 90 | 90 | 90 | 90 |
| 26 | 24 | 7 | 7 |
| 23 | 24 | 38 | 38 |
| C | C | D | D |
| C | D | D | D |
| D | | | |
| NORTH | SOUTH | EAST | WEST |
| Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP | Curb Bike Lane, Cycletrack or MUP |
| Not Applicable | Not Applicable | Not Applicable | Not Applicable |
| Separated | Separated | Separated | Separated |
| 2-stage, LT box | 2-stage, LT box | 2-stage, LT box | 2-stage, LT box |
| > 50 to < 60 km/h | > 50 to < 60 km/h | ≥ 60 km/h | ≥ 60 km/h |
| A | A | A | A |
| A | A | A | A |
| A | | | |
| ≤ 20 sec | ≤ 20 sec | ≤ 40 sec | ≤ 30 sec |
| C | C | E | D |
| E | | | |
| | | | |
| - | - | - | - |
| - | | | |
| 0.0 - 0.60 | | | |
| A | | | |